



Prepared for

Georgia Power Company
241 Ralph McGill Blvd NE
Atlanta, Georgia 30308

PILOT STUDY SUMMARY REPORT

**PILOT TEST NO. UPT000062 AND UPT000068
PLANT HAMMOND ASH POND 1 (AP-1)**

Prepared by
Geosyntec 
consultants

engineers | scientists | innovators

1255 Roberts Boulevard, Suite 200
Kennesaw, Georgia 30144

Project Number GW6581G

August 2025

CERTIFICATION STATEMENT

I hereby certify that this *Pilot Study Summary Report* was prepared by, or under the direct supervision of, a Qualified Groundwater Scientist, in accordance with the Georgia Environmental Protection Division Rules of Solid Waste Management. According to 391-3-4-.01, a Qualified Groundwater Scientist is “a professional engineer or geologist registered to practice in Georgia who has received a baccalaureate or post-graduate degree in the natural sciences or engineering and has sufficient training and experience in groundwater hydrology and related fields that enable individuals to make sound professional judgments regarding groundwater monitoring, contaminant fate and transport, and corrective action.” This report was developed in compliance with the Georgia Rules of Solid Waste Management, Chapter 391-3-4.10.



Whitney B. Law
Georgia Professional Engineer No. 36641

August 29, 2025
Date

TABLE OF CONTENTS

1.	BACKGROUND AND PURPOSE	1
2.	PRE-INJECTION ACTIVITIES	3
3.	INJECTION ACTIVITIES	5
4.	POST-INJECTION PERFORMANCE MONITORING ACTIVITIES.....	7
5.	PILOT STUDY RESULTS.....	8
	5.1 Injectate Efficacy and Dosing.....	8
	5.1.1 HGWC-8 Area	8
	5.1.2 HGWC-13 Area	9
	5.2 Radius of Influence	9
	5.2.1 HGWC-8 Area	9
	5.2.2 HGWC-13 Area	10
	5.3 Sustainable Injection Pressure and Flowrate	11
	5.3.1 HGWC-8 Area	11
	5.3.2 HGWC-13 Area	11
	5.4 Source Control and Natural Attenuation.....	11
6.	CONCLUSION.....	13
7.	REFERENCES	14

LIST OF TABLES

Table 1	Summary of Well Construction Details
Table 2	Summary of Horizontal Hydraulic Conductivity Results
Table 3	Summary of 2024 Baseline Groundwater Analytical Data
Table 4	Summary of Daily Injection Volumes
Table 5	Summary of Daily Air Sparging Activities
Table 6	Summary of Screening-Level Groundwater Analytical Data
Table 7A	Summary of 2023 Post-injection Performance Monitoring Groundwater Analytical Data
Table 7B	Summary of 2024 Post-injection Performance Monitoring Groundwater Analytical Data

LIST OF FIGURES

Figure 1	Pilot Study DPT Injection and Performance Monitoring Well Locations
Figure 2	Pilot Study Injection and Performance Monitoring Well Locations
Figure 3	HGWC-8 Area – Molybdenum Time Series
Figure 4	HGWC-13 Area – Arsenic Time Series

LIST OF APPENDICES

Appendix A	2023 and 2024 Pilot Study Post-Injection Event Report, Plant Hammond Ash Pond 1
Appendix B	Slug Test Graphical Solutions and Model Parameters
Appendix C	Baseline Groundwater Analytical Laboratory Results and Field Sampling Forms
Appendix D	Screening Level Groundwater Analytical Laboratory Results and Field Sampling Forms
Appendix E	Post-injection Performance Monitoring Groundwater Analytical Laboratory Results and Field Sampling Forms

LIST OF ACRONYMS AND ABBREVIATIONS

ACM	Assessment of Corrective Measures
AP-1	Ash Pond 1
As	Arsenic
Cascade	Cascade Drilling, Inc.
CAMP	Corrective Action Monitoring Plan
CCR	coal combustion residual
CFR	Code of Federal Regulations
CSM	conceptual site model
DPT	direct push technology
EPD	Georgia Environmental Protection Division
ft/day	feet per day
FeSO ₄	ferrous sulfate
g/L	grams per liter
gal	gallons
gpm	gallons per minute
gpd	gallons per day
GA EPD	Georgia Environmental Protection Division
Georgia Power	Georgia Power Company
Geosyntec	Geosyntec Consultants, Inc.
gpd	gallons per day
GWPS	Groundwater Protection Standard
HCO ₃	bicarbonate
IBC	intermediate bulk container
Kh	horizontal hydraulic conductivity
MgO	magnesium oxide
mg/L	milligrams per liter
Mo	molybdenum
MNA	monitored natural attenuation
NaHCO ₃	sodium bicarbonate
ORP	oxidation-reduction potential
psi	pound per square inch
PSPIER	Pilot Study Post-Injection Event Report
ROI	radius of influence
SCFM	Standard Cubic Feet per Minute

1. BACKGROUND AND PURPOSE

This *Pilot Study Summary Report* (Report) was developed by Geosyntec Consultants, Inc. (Geosyntec) as part of implementing the Assessment of Corrective Measures (ACM) process at Georgia Power Company (Georgia Power) Plant Hammond Ash Pond 1 (AP-1; Site). The *Draft Remedy Selection Report* (Geosyntec, 2022) proposed in-situ geochemical injections, coupled with monitored natural attenuation (MNA), as corrective measures to address concentrations of molybdenum (Mo) and arsenic (As) reported at statistically significant levels (SSLs) above Groundwater Protection Standards (GWPS) in detection monitoring wells HGWC-8 and HGWC-13, respectively, at Georgia Power Plant Hammond Ash Pond 1. As documented in the *Draft Remedy Selection Report*, geochemical injections and monitored natural attenuation meet the required remedy criteria set forth in the United States Environmental Protection Agency's (USEPA's) Coal Combustion Residuals (CCR) Rule, 40 Code of Federal Regulations (CFR) Parts 257 effective October 19, 2015 (CCR Rule) including subsequent revisions and Georgia Environmental Protection Division's (GA EPD's) Rule for Solid Waste Management Rule 391-3-4-.10 for CCR.

In a letter dated September 23, 2022, the GA EPD Solid Waste Management Program reviewed the *Draft Remedy Selection Report* and provided written concurrence to move forward with pilot testing to inform corrective action design. Geosyntec prepared the *HGWC-8 Pilot Study Workplan* and the *HGWC-13 Pilot Study Workplan* (Geosyntec, 2023a; 2023b; collectively referred to herein as primary Workplans) detailing the planned injections and subsequent performance monitoring. The Workplans were subsequently approved by both the EPD Underground Injection Control (UIC) Program and Solid Waste Management Program in a letter dated August 24, 2023, authorizing limited pilot test injections with a 90-day duration to inform corrective action design.

In 2024, Geosyntec submitted *HGWC-8 Supplemental Pilot Study Workplan* and the *HGWC-13 Supplemental Pilot Study Workplan* describing additional injection activities necessary to inform corrective action design (Geosyntec, 2024a; 2024b). These supplemental Workplans were subsequently approved by both the EPD UIC Program and Solid Waste Management Program in a letter dated June 21, 2024, authorizing limited pilot test injections with a 90-day duration. This comprehensive report summarizes the results of these pilot studies.

Design of in-situ geochemical injection corrective measures includes multiple assessment and design components, including pilot studies to evaluate injection delivery and the performance of injectates prior to implementing a full scale remedy. Data collected during this pilot study has been used to evaluate:

1. Injectate dosing and efficacy of treating Mo and As in groundwater to below the GWPS.
2. Radius of influence (ROI) of the injected amendment and air sparge to evaluate future injection point spacing requirements; and
3. Sustainable injection and sparging pressure and flowrate.

This comprehensive Report summarizes pilot study activities which were initiated in June 2023 and were completed in February 2025 in accordance with the Workplans. Pilot study activities, completed in two phases (June through October 2023 and April through July 2024), were previously reported in *Pilot Study Post-Injection Event Reports* (Geosyntec, 2023c; 2024c; PSPIER), and are included as **Appendix A**. The performance monitoring activities through December 2024 have been summarized in semiannual groundwater monitoring reports and below. This report summarizes the results of the pilot study.

Georgia Power anticipates receiving written authorization from GA EPD to hold a public meeting to discuss the proposed remedy of in-situ geochemical approaches, coupled with MNA. After the public meeting, Georgia Power will revise the *Draft Remedy Selection Report*, incorporating the public meeting comments.

2. PRE-INJECTION ACTIVITIES

Two temporary corrective action performance monitoring piezometers (performance monitoring wells) were installed at each pilot study area (i.e., the HGWC-8 area and the HGWC-13 area) in June 2023. Performance monitoring wells were located proximal to HGWC-8 and HGWC-13, in areas where detections of Mo and As above the GWPS were expected, based on high-resolution site characterization activities. Performance monitoring wells PT-07 and PT-08 were installed at the HGWC-13 pilot study area. Performance monitoring wells PT-09 and PT-10 were installed at the HGWC-8 pilot study area.

Twelve additional temporary injection, air sparge, and performance monitoring wells were installed in April 2024 to support supplemental pilot study activities (INW-03, AS-01, AS-02, PT-11, PT-12 in HGWC-8 area, and AS-03, AS-04, INW-04, INW-05, PT-13, PT-14, and PT-15 in HGWC-13 area). INW-03, INW-04, and INW-05 were installed as injection wells, AS-01, AS-02, AS-03, and AS-04 were installed as air sparge wells, and wells PT-11, PT-12, PT-13, PT-14, and PT-15 were installed to monitor the performance of the supplemental pilot study injections. Well installation was performed in accordance with the Workplans by Cascade Drilling, Inc. (Cascade) of Midland, North Carolina. Well locations are shown on **Figures 1 and 2**, and construction details are provided in **Table 1**. Additional details on pilot well installation is included in the PSPIERs (Geosyntec, 2023c; 2024c).

Geosyntec conducted slug testing to estimate horizontal hydraulic conductivity (K_h) at select pilot study wells following well installation and development. Hydraulic conductivities were estimated using the Bouwer-Rice analytical solution. The geometric mean hydraulic conductivities of HGWC-8 and HGWC-13 pilot study area wells were 5.49 and 3.65 feet per day (ft/d), respectively. Hydraulic conductivities estimated from slug tests are summarized in **Table 2**. Slug test graphical solutions and model parameters are included as **Appendix B**.

Two rounds of groundwater samples were collected from the performance monitoring wells (PT-07 through PT-10) in July and August 2023 to establish pre-injection baseline conditions. Two additional rounds of groundwater samples were collected from the injection wells and performance monitoring wells (INW-03 through INW-05; PT-07 through PT-15) in May 2024 to re-establish baseline prior to supplemental pilot study injection activities.

The results of the 2024 baseline sampling event are presented in **Table 3**. The baseline analytical laboratory results and field sampling and equipment calibration forms are

provided in **Appendix C**. These results were generally consistent with screening level analytical data collected during high resolution site characterization activities completed in 2022 proximal to HGWC-8 (Geosyntec, 2023d; Geosyntec, 2023e) and in 2023 proximal to HGWC-13 (Geosyntec, 2023d).

3. INJECTION ACTIVITIES

Injection activities in 2023 and 2024 were performed by Cascade with technical supervision conducted by a Qualified Groundwater Scientist from Geosyntec. Pilot study injection activities conducted from September 25 through October 17, and December 4-13, 2023 consisted of ferrous sulfate (FeSO_4) heptahydrate, and/or magnesium oxide (MgO) obtained from TerraSystems, Inc. mixed with potable water obtained from an on-site fire hydrant that was designated in the Workplans. Injectate batches consisted of up to 0.02 gram per liter (g/L) FeSO_4 , or up to 1 g/L MgO , which are below the maximum allowable injectate concentration of 0.03 g/L FeSO_4 and 5 g/L MgO set forth in the primary Workplans.

As detailed in the 2023 PSPIER (**Appendix A**), injectate was delivered using a pump and through steel rods to a steel well screen advanced using direct push technology (DPT) drilling. DPT injections were initiated at the top of injectable treatment zone and proceeded downward (i.e., top-down), utilizing both 2-ft or 5-ft long steel well screens. DPT injections occurred at four locations surrounding PT-07 and PT-09, as shown on **Figure 1**. The average injection flow rate, average daily injection volume, and total injection volume for each pilot study area are provided below.

	HGWC-8 Area	HGWC-13 Area
Average Flow Rate (gallons per minute [gpm])	3.9	2.4
Average Daily Injection Volume (gal)	1,290	840
Total Injection Volume (gal)	24,492	11,759

Based on post-injection analytical data, supplemental injection activities were performed July 9 to July 31, 2024, and September 9 to September 20, 2024, utilizing static injection at injection wells and air-spargers. Injections at wells INW-03, INW-04 and INW-05 (**Figure 2**) were initially tested using gravity-fed injection methodology. Due to low flow rates observed while implementing this method, a pressurized injection methodology was employed at INW-03 through INW-05, as detailed in the 2024 PSPIER. Injectate consisted of 0.5 to 1 g/L FeSO_4 , which was below the maximum allowable concentration of 2 g/L FeSO_4 included in the supplemental Workplans. The average injection flow rate, average daily injection volume, and total injection volume for each injection well are provided below.

	INW-03	INW-04	INW-5
	HGWC-8 Area	HGWC-13 Area	HGWC-13 Area
Average Flow Rate (gpm)	6.1	3.3	3.5
Average Daily Injection Volume (gal)	1,294	638	614
Total Injection Volume (gal)	5,175	7,650	5,530

Injection pressures, flowrates, water levels, and groundwater quality parameters in nearby performance monitoring wells were measured throughout injection activities, and the daily maximum injection volume across both pilot study areas was below the value included in the Pilot Test Notification Form (3,500 gal per day [gpd]). A summary of daily injected volumes is included in **Table 4**.

In addition to the supplemental injection of FeSO₄, air sparging activities were performed in the HGWC-13 area. Air sparging flow rates and pressures were monitored throughout the sparging activities and were below the maximum allowable values included in the supplemental Pilot Test Notification Form (25 standard cubic feet per minute [SCFM] and 15 pounds per square inch [psi], respectively). Air sparging flowrates and durations are summarized in **Table 5**.

Screening level groundwater grab samples were collected and analyzed for select total and dissolved¹ metals during supplemental injection activities to evaluate ongoing injection performance while in the field. Screening-level groundwater analytical results are summarized in **Table 6** and the associated analytical laboratory reports and field calibration forms are included in **Appendix D**.

¹ Dissolved samples were filtered in the field.

4. POST-INJECTION PERFORMANCE MONITORING ACTIVITIES

Post-injection performance monitoring was initiated following the September 2023 injection event on October 10, 2023, and October 17, 2023, in HGWC-8 and HGWC-13 area, respectively, with groundwater samples collected from all performance monitoring wells in accordance with the Workplans. The monitoring frequency was weekly² for three weeks, followed by two additional samples collected every two to four weeks, prior to December 2023 injection activities.

Post-injection performance monitoring was initiated at the HGWC-8 area and HGWC-13 on December 14 and on December 8, 2023, respectively, following December injections. Both pilot study areas were monitored in accordance with the primary Workplans through May 2024. Supplemental injections were subsequently implemented based on post-injection performance data, which indicated that injections did not treat As and Mo to below GWPS at pilot study wells.

Following July 2024 supplemental injections, additional post-injection performance monitoring was initiated on July 31, 2024, and August 1, 2024, at the HGWC-8 and HGWC-13 areas, respectively. Three samples were collected on a weekly basis, followed by two additional samples collected every 2 to 3 weeks prior to September 2024 supplemental injections. The post injection performance monitoring following the September 2024 injection activities was initiated on September 25, 2024, and continued on a weekly basis for three weeks, and on a monthly basis for five months through March 2025.

In accordance with the Workplans, groundwater quality data from each performance monitoring event was directly compared against the Mo and As GWPS and the results of the baseline characterization to evaluate the efficacy of injectates as a method of remediation. In addition, Appendix IV monitoring parameters³ were analyzed and monitored over the duration of the pilot study to evaluate potential localized mobilization of other Appendix IV parameters following injections. Post-injection performance sampling results for 2023 and 2024 injection activities are presented in **Table 7A** and **Table 7B**, respectively. Post-injection performance monitoring analytical laboratory results and field sampling and equipment calibration forms are provided in **Appendix E**.

² In accordance with the Workplans, monitoring frequency in the first month was increased from biweekly to weekly based on field observations.

³ Excluding radium.

5. PILOT STUDY RESULTS

5.1 Injectate Efficacy and Dosing

5.1.1 HGWC-8 Area

As demonstrated in **Figure 3**, the injection of 0.5 to 1.0 g/L FeSO₄ in 2024 successfully treated Mo in groundwater to below the GWPS at PT-11. Additionally, secondary mobilization of other Appendix IV constituents was not observed.

The concentration of Mo dropped to below GWPS in PT-11, the closest monitoring well to the injection well, following the first injection in July 2024 and remained below GWPS for 40 days (**Figure 3**). An additional injection of 1 g/L of FeSO₄ was completed in September 2024 following a rebound in Mo concentration above the GWPS at PT-11. Following this injection, the Mo concentration at PT-11 dropped to and remained below GWPS for about 50 days. Although a subsequent rebound in Mo above the GWPS was observed after 50 days, Mo concentrations stabilized at significantly lower level (0.13 mg/L) as compared to June 2024 baseline concentrations (0.24 mg/L). Molybdenum concentrations in other performance monitoring wells PT-09 and PT-12 also generally decreased (up to 50%) following July and September injections (**Figure 3**).

The pilot study results for HGWC-8 area align with the conceptual site model (CSM) for AP-1, which states that Mo in HGWC-8 potentially originated from AP-1 and is attenuated through adsorption onto naturally occurring amorphous and crystalline metal oxides and oxyhydroxides surfaces. The extent of Mo attenuation varies based on the groundwater chemistry and availability of sorption sites. Molybdenum can also potentially be attenuated through coprecipitation and entrained in the crystal structure of iron oxide minerals as they form (e.g. after injection of iron) under oxidizing conditions similar to groundwater conditions in HGWC-8 area. As such, the injection of FeSO₄ in HGWC-8 area reduced Mo concentrations in groundwater through multiple likely mechanisms, including (i) coprecipitation of iron oxides, and (ii) enhanced adsorption onto iron oxide surfaces by increasing the number of adsorption sites and adsorption intensity.

The injectate dosing of 1 g/L FeSO₄ was sufficient to immobilize Mo during the pilot study. However, injectate concentrations may be adjusted during implementation to meet remedial objectives, as Mo impacts vary spatially. Additionally, maintenance injections may be required during implementation.

5.1.2 HGWC-13 Area

Air sparging in the HGWC-13 pilot study area successfully reduced As concentrations to below the GWPS. Additionally, no secondary mobilization of other Appendix IV constituents was observed during the pilot study.

The concentration of As dropped below the GWPS in PT-07, PT-13, PT-14, and PT-15, and remained below the GWPS in PT-07, PT-13, and PT-15 for an extended period after air sparging was discontinued (>250 hours, **Figure 4, Tables 6, 7B**). There was a rebound in As in PT-14, PT-13, and PT-07 and concentrations were comparable to baseline levels by January 2025. However, in PT-15, the closest well to the air sparge well (AS-03), As concentrations remained five times lower than the baseline concentration (0.08 mg/L vs. 0.4 mg/L) by March 2025, seven months after air sparging ceased. This was associated with higher oxidation-reduction potential (ORP) and lower iron concentrations compared to baseline levels (**Table 7B**). Similar correlations between As, background iron and ORP levels were observed across all monitoring wells throughout the pilot study.

The groundwater in the HGWC-13 pilot study area is generally reducing and contains more than 9 mg/L of iron. Under reducing conditions, As is predominantly present as As(III), which is significantly less susceptible to adsorption onto soil surfaces than As(V). Air sparging promotes the oxidation of Fe(II) and the precipitation of iron hydroxides. Arsenic can coprecipitate with iron and become entrained within iron mineral crystals. The elevated oxidation levels in the presence of ferrous iron can also promote the co-oxidation of As through Fenton-type reactions. The oxidized species, As(V), can readily adsorb onto soil surfaces.

The pilot study results suggest that air sparging at the HGWC-13 area attenuated arsenic through multiple iron dependent mechanisms, including coprecipitation and adsorption. Although injections of FeSO₄ at concentrations up to 1 g/L were unsuccessful at treating As to below the GWPS in the absence of air sparging, FeSO₄ injections may be necessary when insufficient iron is present to attenuate As due to spatial and temporal variations in water chemistry.

5.2 Radius of Influence

Injection radius of influence (ROI) was evaluated using analytical data collected in nearby performance monitoring wells during injections, as described below.

5.2.1 HGWC-8 Area

The ROI in HGWC-8 area was estimated based on concentrations of boron (B), iron, and Mo in performance monitoring wells following the July 2024 injections. Boron concentration was used as a conservative tracer to assess groundwater dilution following

the injection of FeSO_4 . Iron served as a qualitative indicator of injectate breakthrough, and Mo was used as a qualitative indicator of the effective treatment ROI, as these constituents are redox-sensitive constituents.

The analytical results (**Table 6**) suggest that a relatively consistent injectate breakthrough occurred at PT-11 (located 3.9 ft side-gradient from injection well INW-03) after 975 gallons of injectate were injected. Boron concentration dropped by 45%, iron concentration increased from 0.34 mg/L to 3 mg/L, and Mo concentration decreased by approximately 80% and below GWPS. After 3,400 gallons of FeSO_4 were injected (2,200 gallons of 0.5 g/L and 1,200 gallons of 1 g/L), iron concentrations increased by more than two orders of magnitude compared to baseline levels. These suggest that a minimum ROI of 3.9 ft was achieved

At PT-09, located 5.7 ft downgradient from the injection well, B concentration decreased by 20% after the injection of 2,200 gallons. Molybdenum concentrations decreased by 50% after a total injection of 3,200 gallons but remained slightly above the GWPS (0.13 mg/L). This suggests that PT-09 is within the ROI of the injection well. However, given that Mo concentrations remained above the GWPS, the effective ROI of INW-03 was assumed to be 3.9 ft. There were generally limited changes in the B at PT-12 and PT-10, suggesting that the injection ROI was less than 7.8 ft.

5.2.2 HGWC-13 Area

The air sparging radius of influence in the HGWC-13 area was estimated based on changes in dissolved oxygen, ORP, As, and iron in performance monitoring wells following September 2024 air sparging activities. Air was injected into wells AS-03 and AS-04 for more than 60 hours between September 9 and September 12. Dissolved oxygen, ORP, and iron were used as indicators of changes in redox conditions in the wells. Oxygen levels were significantly higher than baseline levels (prior to sparging) in PT-13, PT-15, and PT-07. This was associated with increases in ORP and decreases in baseline iron and As concentrations. After 60 hours of air sparging, arsenic levels were barely above the GWPS (0.012 to 0.017 mg/L) in these three wells. Arsenic concentrations dropped below the GWPS after 90 cumulative hours of air sparging between September 9 and September 18 in PT-15.

A relatively limited and non-sustained response to air sparging was observed in PT-14 and PT-08, indicating no clear correlation between observed redox condition changes and well distances from air sparging wells beyond 4 ft, likely attributed to subsurface heterogeneity.

Among the five performance monitoring wells, PT-15 demonstrated the most sustained response to air sparging, reflected in generally higher ORP and lower arsenic levels compared to the other wells during the performance monitoring period. As such, the distance between AS-03 and PT-15 was assumed to represent the minimum effective sparging ROI in the HGWC-13 pilot study area.

Iron concentration was used as a qualitative indicator of the injection radius of influence in the HGWC-13 area. Following the injection of approximately 3,300 gallons of 1 g/L FeSO₄ between July 23 and 24, iron concentrations at PT-14 increased by more than one order of magnitude, indicating that a minimum ROI of 3.9 feet was achieved. Iron concentrations increased approximately 2.8 to 4.4 times in PT-08, and PT-13, but remained relatively stable at PT-15, suggesting that the injection ROI in the HGWC-13 area is less than 8.2 ft.

5.3 Sustainable Injection Pressure and Flowrate

5.3.1 HGWC-8 Area

A DPT maximum injection flow rate of 6.8 gpm was achieved with an injection pressure of 4 psi. An injection flow rate of 2–3 gpm was achieved using gravity-feed injection at INW-03, while the wellhead pressure remained below 2 psi. Under pressurized injection (<4 psi) higher flow rates (up to 10 gpm) were achieved.

5.3.2 HGWC-13 Area

A DPT maximum injection flow rate of 5 gpm was achieved with an injection pressure of 11 psi. Injection flow rates of up to 4 gpm were achieved during the gravity-fed injection of potable water at INW-04 and INW-05. Injection flow rates as high as approximately 5.0 gpm, with a maximum wellhead pressure of 6.8 psi, were achieved during pressurized injections at INW-04 and INW-05.

The maximum air sparging flow rates attained at AS-03 and AS-04 were 10 SCFM and 4 SCFM, respectively. The wellhead pressure at AS-03 and AS-04 remained below 14 psi.

5.4 Source Control and Natural Attenuation

Closure construction activities for AP-1 consist of closure by removal. Closure by removal includes excavation and removal of the CCR material from AP-1. Physical removal of the CCR will, over time, be supportive of declining concentrations of Appendix IV constituents in groundwater downgradient of AP-1 and improve overall

groundwater quality. For example, Mo concentrations at HGWC-8 have declined substantially since the initiation of closure activities in 2020. Data collected during the pilot study confirm that in-situ injections are compatible with ongoing natural attenuation at AP-1, and are expected to further enhance groundwater cleanup to below GWPS.

6. CONCLUSION

This pilot study has demonstrated that (i) the in-situ geochemical injection of FeSO_4 successfully treated Mo in groundwater to below the GWPS at HGWC-8 pilot study area, and (ii) air sparging successfully treated As in groundwater to below the GWPS at HGWC-13 pilot study area. Secondary mobilization of other Appendix IV constituents was not observed during pilot studies. Furthermore, the results of this pilot study support the proposed remedy described in the Draft Remedy Selection Report. Based on these results, the proposed remedies are capable of meeting requirements listed in §257.97. Data collected from this pilot study will be used in the design of in-situ geochemical injection corrective measures and included in the Corrective Action Monitoring Plan. Full-scale in-situ geochemical injection and MNA corrective measures are expected to treat Mo and As SSLs above the GWPS in detection monitoring wells HGWC-8 and HGWC-13, respectively, at AP-1.

Georgia Power anticipates receiving written authorization from GA EPD to hold the public meeting with the proposed remedy of in-situ geochemical approaches, coupled with MNA. After the public meeting, Georgia Power will revise the Draft Remedy Selection Report, incorporating the public meeting comments.

7. REFERENCES

- Geosyntec, 2022. *Draft Remedy Selection Report, Georgia Power Company, Plant Hammond Ash Pond 1*. August 2022.
- Geosyntec, 2023a. *HGWC-8 Pilot Study Workplan, Plant Hammond Ash Pond 1 (AP-1)*. August 2023.
- Geosyntec, 2023b. *HGWC-13 Pilot Study Workplan, Plant Hammond Ash Pond 1 (AP-1)*. August 2023.
- Geosyntec, 2023c. *Pilot Study Post-Injection Event Report (AP-1)*. November 2023.
- Geosyntec, 2023d. *HGWC-8 Pre-Design Investigation Summary Technical Memorandum, Plant Hammond Ash Pond 1 (AP-1)*. June 2023.
- Geosyntec, 2023e. *HGWC-13 Pre-Design Investigation Summary Technical Memorandum, Plant Hammond Ash Pond 1 (AP-1)*. June 2023.
- Geosyntec, 2024a. *HGWC-8 Supplemental Pilot Study Workplan, Plant Hammond Ash Pond 1 (AP-1)*. March 2024.
- Geosyntec, 2024b. *HGWC-13 Supplemental Pilot Study Workplan, Plant Hammond Ash Pond 1 (AP-1)*. March 2024.
- Geosyntec, 2024c. *Pilot Study Post-Injection Event Report (AP-1)*. August 2024.
- SiREM, 2023. *Laboratory Treatability Study to Evaluate In-Situ Remediation of Arsenic and Molybdenum at the Hammond Ash Pond 1*. June 2023.

TABLES

Table 1
Summary of Well Construction Details
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area	Well ID	Well Completion	Installation Date	Northing ⁽¹⁾	Easting ⁽¹⁾	Ground Surface Elevation ⁽¹⁾ (ft)	Top of Casing Elevation ⁽¹⁾ (ft)	Top of Screen Elevation (ft)	Bottom of Screen Elevation (ft)	Well Depth (ft bgs) ⁽²⁾
HGWC-13 Area	Temporary Sparge Wells									
	AS-03	Flush Mount	4/28/2024	1548670.10	1940933.87	591.98	591.60	545.98	543.98	48.30
	AS-04	Flush Mount	4/28/2024	1548680.80	1940930.83	591.97	591.50	544.97	542.97	49.30
	Temporary Injection Wells									
	INW-04	Flush Mount	4/28/2024	1548671.73	1940929.98	592.01	591.58	557.01	547.01	45.30
	INW-05	Flush Mount	4/28/2024	1548680.07	1940935.89	591.81	591.31	556.81	546.81	45.30
	Temporary Performance Monitoring Wells									
	PT-07 ⁽³⁾	Flush Mount	6/3/2023	1548675.24	1940933.39	592.00	591.75	554.40	544.30	48.00
	PT-08 ⁽³⁾	Flush Mount	6/3/2023	1548666.82	1940929.58	592.10	591.83	560.20	550.20	42.20
	PT-13	Flush Mount	4/28/2024	1548676.04	1940939.23	591.88	591.47	556.88	546.88	45.30
	PT-14	Flush Mount	4/28/2024	1548673.63	1940926.52	592.06	591.62	557.06	547.06	45.30
	PT-15	Flush Mount	4/28/2024	1548668.35	1940937.45	591.90	591.37	556.90	546.90	45.30
HGWC-8 Area	Temporary Sparge Wells									
	AS-01	Flush Mount	5/7/2024	1549048.28	1942388.06	577.46	577.08	548.46	546.46	31.30
	AS-02	Flush Mount	5/6/2024	1549049.08	1942400.03	577.14	576.72	547.14	545.14	32.30
	Temporary Injection Well									
	INW-03	Flush Mount	5/6/2024	1549052.75	1942388.28	577.38	577.07	560.28	550.28	27.40
	Temporary Performance Monitoring Wells									
	PT-09 ⁽³⁾	Protective Riser	6/1/2023	1549049.74	1942393.11	577.33	580.35	560.18	550.18	27.45
	PT-10 ⁽³⁾	Protective Riser	6/1/2023	1549040.34	1942413.88	577.39	580.44	560.29	550.29	27.40
	PT-11	Flush Mount	5/7/2024	1549055.61	1942390.89	577.35	576.96	560.75	550.75	26.90
	PT-12	Flush Mount	5/7/2024	1549045.43	1942391.10	577.34	576.84	560.34	550.34	27.30

Notes:

ft = feet.

ft bgs = feet below ground surface.

(1) Coordinates in North American Datum (NAD) 1983, State Plane, Georgia-West, feet. Elevations referenced to the North American Vertical Datum of 1988 (NAVD88).

Survey data from wells installed in 2024 was certified by GEL Solutions (GEL) July 1, 2024. Survey data from wells installed in 2023 certified by GEL on July 17, 2023, and August 30, 2023.

(2) Total well depth accounts for 0.3 ft sump.

(3) Well was previously constructed in accordance with the HGWC-8 and HGWC-13 Pilot Study Workplans.

Table 2
Summary of Horizontal Hydraulic Conductivity Results
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area	Well ID	Horizontal Hydraulic Conductivity ⁽¹⁾ (ft/day)	Average Horizontal Hydraulic Conductivity (ft/day)	Horizontal Hydraulic Conductivity by Pilot Study Area (ft/day)		
				Max	Min	Geometric Mean
HGWC-13 Area	INW-04	2.31	2.54	10.80	1.89	3.65
		2.77				
	INW-05	1.95	1.89			
		1.84				
	PT-07	10.25	10.80			
		11.34				
	PT-08	3.58	3.42			
		3.26				
HGWC-8 Area	INW-03	10.11	12.78	12.78	1.67	5.49
		15.44				
	PT-09	7.62	7.76			
		7.91				
	PT-10	1.63	1.67			
		1.71				

Notes:

ft/day = foot per day

(1) Pneumatic slug tests were repeated twice and horizontal hydraulic conductivities were estimated from the Bouwer-Rice model.

Table 3
Summary of 2024 Baseline Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-8 Area		
Sample Location		PT-11	PT-12	PT-12
Sample Date		05/29/2024	05/14/2024	05/29/2024
ANALYTE	UNITS			
APPENDIX III				
Boron	mg/L	1.4	1.6	1.5
Calcium	mg/L	95.7	99.7	91.0
Chloride	mg/L	39.4	50.3	48.0
Fluoride	mg/L	0.31	0.20	0.31
pH, Field	SU	7	6.58	6.82
Sulfate	mg/L	118	125	131
TDS	mg/L	474	523	488
APPENDIX IV				
Antimony	mg/L	< 0.00054	< 0.00054	< 0.00054
Arsenic	mg/L	0.0021 J	< 0.00084	0.0026 J
Barium	mg/L	0.072	0.069	0.069
Beryllium	mg/L	< 0.000094	< 0.000094	< 0.000094
Cadmium	mg/L	0.00013 J	0.00014 J	0.00011 J
Chromium	mg/L	< 0.0019	< 0.0019	< 0.0019
Cobalt	mg/L	0.0013 J	0.0044 J	0.0021 J
Lead	mg/L	< 0.00016	0.00017 J	< 0.00016
Lithium	mg/L	< 0.0016	< 0.0016	< 0.0016
Mercury	mg/L	< 0.00013	< 0.00013	< 0.00013
Molybdenum	mg/L	0.17	0.085	0.22
Selenium	mg/L	< 0.00096	< 0.00096	0.0015 J
Thallium	mg/L	< 0.00038	< 0.00038	< 0.00038
Fluoride	mg/L	0.31	0.20	0.31
Additional Parameters				
Bicarbonate Alkalinity as CaCO3	mg/L	143	129	136
Carbonate Alkalinity as CaCO3	mg/L	< 5.0	< 5.0	< 5.0
Total Alkalinity as CaCO3	mg/L	143	129	136
Iron	mg/L	0.10	0.33	0.032 J
Magnesium	mg/L	16.7	16.6	18.6
Manganese	mg/L	0.27	1.0	0.75
Potassium	mg/L	6.5	6.8	5.7
Sodium	mg/L	9.2	11.8	9.6
Sulfide	mg/L	< 0.022	< 0.022	< 0.022
Supplemental				
Oxidation Reduction Potential, Field	mV	161.94	58.81	81.45
pH, Field	SU	7	6.58	6.82
Disolved Oxygen, Field	mg/L	0.42	0.32	0.71
Specific Conductance, Field	uS/cm	708.73	685.68	678.21
Temperature, Field	deg C	19.15	18.81	19.36
Turbidity, Field	NTU	3.84	4.71	0.73

Table 3
Summary of 2024 Baseline Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-13 Area									
Sample Location		INW-04	INW-04	INW-05	INW-05	PT-07	PT-07	PT-08	PT-08	PT-13	PT-13
Sample Date		05/02/2024	05/15/2024	05/02/2024	05/15/2024	05/09/2024	05/16/2024	05/02/2024	05/16/2024	05/09/2024	05/15/2024
ANALYTE	UNITS										
APPENDIX III											
Boron	mg/L	0.61	0.59	0.54	0.51	0.55	0.50	0.83	0.73	0.54	0.52
Calcium	mg/L	110	107	108	101	98.0	96.0	98.2	89.4	94.4	99.2
Chloride	mg/L	8.0	9.9	6.0	6.9	9.2	10	15.4	16.7	9.0	9.5
Fluoride	mg/L	0.47	0.28	0.59	0.37	0.33	0.31	0.36	0.19	0.35	0.34
pH, Field	SU	6.78	6.94	6.87	7.01	6.86	6.98	6.53	6.49	6.84	6.93
Sulfate	mg/L	180	187	206	181	177	171	176	159	195	190
TDS	mg/L	482	483	526	456	463	450	477	410	472	459
APPENDIX IV											
Antimony	mg/L	< 0.00054	< 0.00054	0.00098 J	< 0.00054	0.00059 J	< 0.00054	< 0.00054	< 0.00054	< 0.00054	< 0.00054
Arsenic	mg/L	0.21	0.19	0.24	0.23	0.30	0.27	0.26	0.23	0.30	0.29
Barium	mg/L	0.042	0.043	0.032	0.033	0.037	0.034	0.045	0.041	0.036	0.033
Beryllium	mg/L	< 0.000094	< 0.000094	0.000099 J	0.00012 J	0.00010 J	< 0.000094	< 0.000094	< 0.000094	< 0.000094	< 0.000094
Cadmium	mg/L	< 0.00010	< 0.00010	< 0.00010	< 0.00010	< 0.00010	< 0.00010	< 0.00010	< 0.00010	< 0.00010	< 0.00010
Chromium	mg/L	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019
Cobalt	mg/L	0.029	0.031	0.028	0.026	0.041	0.052	0.054	0.046	0.026	0.024
Lead	mg/L	< 0.00016	< 0.00016	< 0.00016	< 0.00016	< 0.00016	< 0.00016	< 0.00016	0.0079	< 0.00016	< 0.00016
Lithium	mg/L	0.048	0.043	0.060	0.057	0.064	0.056	0.016 J	0.010 J	0.061	0.058
Mercury	mg/L	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013
Molybdenum	mg/L	0.016	0.015	0.0094 J	0.0096 J	0.010	0.0093 J	0.017	0.017	0.0095 J	0.0087 J
Selenium	mg/L	0.0016 J	< 0.00096	0.0015 J	< 0.00096	< 0.00096	< 0.00096	0.0012 J	< 0.00096	< 0.00096	< 0.00096
Thallium	mg/L	0.00048 J	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038
Fluoride	mg/L	0.47	0.28	0.59	0.37	0.33	0.31	0.36	0.19	0.35	0.34
Additional Parameters											
Bicarbonate Alkalinity as CaCO3	mg/L	128	133	109	123	117	116	108	104	106	111
Carbonate Alkalinity as CaCO3	mg/L	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0
Total Alkalinity as CaCO3	mg/L	128	133	109	123	117	116	108	104	106	111
Iron	mg/L	10.3	8.4	17.3	16.9	16.9	15.7	8.5	8.0	15.5	15.0
Magnesium	mg/L	13.5	13.1	12.6	11.8	12.5	12.1	12.0	11.5	11.4	12.0
Manganese	mg/L	4.2	4.4	3.6	3.3	3.2	3.4	3.9	3.3	3.5	3.6
Potassium	mg/L	5.4	4.8	5.2	4.7	5.6	4.9	5.3	4.8	5.0	5.0
Sodium	mg/L	6.9	7.0	6.5	6.7	6.8	7.0	7.2	7.2	6.9	7.8
Sulfide	mg/L	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022
Supplemental											
Oxidation Reduction Potential, Field	mV	-96.08	-97.42	-120.94	-124.26	-100.64	-91.91	154.38	-29.02	-103.97	-98.34
pH, Field	SU	6.78	6.94	6.87	7.01	6.86	6.98	6.53	6.49	6.84	6.93
Disolved Oxygen, Field	mg/L	0.72	0.48	0.06	0.36	0.37	2.33	1.01	0.51	0.16	1.1
Specific Conductance, Field	uS/cm	674.04	693.25	706.51	675.78	665.99	671.25	691.07	626.3	670.23	683.83
Temperature, Field	deg C	20.57	19.86	18.17	19.19	20.53	19.39	21.27	19.16	20.75	18.64
Turbidity, Field	NTU	4.11	4.92	4.15	4.97	1.06	13.8	8.6	4.1	2.27	4.82

Notes:

< = Indicates the parameter was not detected above the analytical method detection limit (MDL).

deg C = degrees Celsius

J = Indicates the parameter was estimated and detected between the MDL and the reporting limit (RL).

µS/cm = microsiemens per centimeter

mg/L = miligrams per liter

mV = millivolts

NTU = nephelometric turbidity units

SU = standard units

TDS = Total dissolved solids

(1) Appendix III/IV parameter per 40 CFR 257 Subpart D. Analysis of combined radium omitted from the pilot study monitoring program. Unless otherwise indicated, parameters are reported in units of milligrams per liter (mg/L).

(2) Metals were analyzed by EPA Method 6010D, 6020B, and 7470A, anions were analyzed by EPA Method 300.0, TDS was analyzed by SM2540C-2015.

(3) The pH value presented was recorded at the time of sample collection in the field.

Table 3
Summary of 2024 Baseline Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-13 Area				HGWC-8 Area					
Sample Location		PT-14	PT-14	PT-15	PT-15	INW-03	INW-03	PT-09	PT-09	PT-10	PT-10
Sample Date		05/02/2024	05/15/2024	05/02/2024	05/15/2024	5/14/2024	5/29/2024	05/14/2024	05/30/2024	05/15/2024	05/30/2024
ANALYTE	UNITS										
APPENDIX III											
Boron	mg/L	0.51	0.51	0.75	0.76	1.5	1.5	1.4	1.5	1.5	1.4
Calcium	mg/L	101	97.4	141	141	127	144	82.8	94.9	108	95.9
Chloride	mg/L	7.9	10.5	11.8	12.6	56.9	61.6	44.4	52.4	50.1	53.0
Fluoride	mg/L	0.43	0.26	0.55	0.35	0.20	0.13	0.37	0.33	0.22	0.17
pH, Field	SU	6.83	6.78	6.95	7.01	7.68	7.36	7.16	7.06	6.92	6.81
Sulfate	mg/L	169	175	278	271	178	187	130	133	146	124
TDS	mg/L	462	461	638	639	564	610	436	532	503	495
APPENDIX IV											
Antimony	mg/L	< 0.00054	< 0.00054	< 0.00054	< 0.00054	< 0.00054	<0.00054	< 0.00054	< 0.00054	< 0.00054	< 0.00054
Arsenic	mg/L	0.22	0.21	0.41	0.39	< 0.00084	< 0.0022 J	< 0.00084	0.0022 J	< 0.00084	0.0018 J
Barium	mg/L	0.037	0.038	0.044	0.043	0.075	0.12	0.058	0.062	0.054	0.052
Beryllium	mg/L	< 0.000094	0.00016 J	< 0.000094	< 0.000094	< 0.000094	< 0.000094	< 0.000094	< 0.000094	< 0.000094	< 0.000094
Cadmium	mg/L	< 0.00010	< 0.00010	< 0.00010	< 0.00010	< 0.0010	< 0.00010	0.00015 J	0.00010 J	< 0.00010	< 0.00010
Chromium	mg/L	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019
Cobalt	mg/L	0.021	0.020	0.052	0.059	0.00070 J	0.00087 J	0.0012 J	0.0010 J	0.0016 J	0.0014 J
Lead	mg/L	< 0.00016	0.00046 J	< 0.00016	< 0.00016	< 0.00016	< 0.00016	0.00017 J	< 0.00016	< 0.00016	< 0.00016
Lithium	mg/L	0.055	0.051	0.051	0.047	0.0050 J	0.0048 J	< 0.0016	< 0.0016	< 0.0016	< 0.0016
Mercury	mg/L	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013
Molybdenum	mg/L	0.011	0.011	0.017	0.021	0.082	0.060	0.27	0.24	0.092	0.053
Selenium	mg/L	0.0014 J	< 0.00096	< 0.00096	< 0.00096	< 0.00096	0.0016 J	< 0.00096	< 0.00096	< 0.00096	< 0.00096
Thallium	mg/L	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038	<0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038
Fluoride	mg/L	0.43	0.26	0.55	0.35	0.20	0.13	0.37	0.33	0.22	0.17
Additional Parameters											
Bicarbonate Alkalinity as CaCO3	mg/L	121	121	124	134	175	176	139	138	132	116
Carbonate Alkalinity as CaCO3	mg/L	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0
Total Alkalinity as CaCO3	mg/L	121	121	124	134	175	176	139	138	132	116
Iron	mg/L	13.7	14.9	9.7	9.2	0.11	0.14	0.42	0.24	0.24	0.21
Magnesium	mg/L	12.7	12.7	15.6	16.1	17.1	16.5	23.7	19.9	14.3	13.1
Manganese	mg/L	3.1	3.1	5.6	5.7	0.45	1.2	0.19	0.28	0.74	0.52
Potassium	mg/L	5.4	5.0	5.2	5.3	13.8	6.1	6.1	6.2	6.7	6.6
Sodium	mg/L	6.7	6.7	6.8	8.1	12.4	11.1	9.3	11.5	9.2	9.5
Sulfide	mg/L	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022
Supplemental											
Oxidation Reduction Potential, Field	mV	-116.47	-109.98	93.76	-118.35	43.0	-26.7	49.89	83.36	20.06	52.5
pH, Field	SU	6.83	6.78	6.95	7.01	7.68	7.36	7.16	7.06	6.92	6.81
Disolved Oxygen, Field	mg/L	0.05	0.05	-0.03	0.1	0.25	0.61	0.04	0.05	0.25	0.43
Specific Conductance, Field	uS/cm	636.04	671.71	868.6	863.09	835.04	864.90	681.69	703.83	707.36	664.75
Temperature, Field	deg C	19.09	18.75	21.71	20.45	18.77	20.17	17.76	19.69	20	20.16
Turbidity, Field	NTU	4.27	4.99	2.99	0.77	4.98	0.56	4.98	4.71	4.92	3.01

Table 3
Summary of 2024 Baseline Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-8 Area			
Sample Location		PT-11	PT-11	PT-12	PT-12
Sample Date		05/14/2024	05/29/2024	05/14/2024	05/29/2024
ANALYTE	UNITS				
APPENDIX III					
Boron	mg/L	1.6	1.4	1.6	1.5
Calcium	mg/L	90.9	95.7	99.7	91.0
Chloride	mg/L	41.4	39.4	50.3	48.0
Fluoride	mg/L	0.34	0.31	0.20	0.31
pH, Field	SU	6.98	7	6.58	6.82
Sulfate	mg/L	122	118	125	131
TDS	mg/L	441	474	523	488
APPENDIX IV					
Antimony	mg/L	< 0.00054	< 0.00054	< 0.00054	< 0.00054
Arsenic	mg/L	< 0.00084	0.0021 J	< 0.00084	0.0026 J
Barium	mg/L	0.057	0.072	0.069	0.069
Beryllium	mg/L	< 0.000094	< 0.000094	< 0.000094	< 0.000094
Cadmium	mg/L	0.00013 J	0.00013 J	0.00014 J	0.00011 J
Chromium	mg/L	< 0.0019	< 0.0019	< 0.0019	< 0.0019
Cobalt	mg/L	0.0016 J	0.0013 J	0.0044 J	0.0021 J
Lead	mg/L	< 0.00016	< 0.00016	0.00017 J	< 0.00016
Lithium	mg/L	< 0.0016	< 0.0016	< 0.0016	< 0.0016
Mercury	mg/L	< 0.00013	< 0.00013	< 0.00013	< 0.00013
Molybdenum	mg/L	0.24	0.17	0.085	0.22
Selenium	mg/L	< 0.00096	< 0.00096	< 0.00096	0.0015 J
Thallium	mg/L	< 0.00038	< 0.00038	< 0.00038	< 0.00038
Fluoride	mg/L	0.34	0.31	0.20	0.31
Additional Parameters					
Bicarbonate Alkalinity as CaCO3	mg/L	125	143	129	136
Carbonate Alkalinity as CaCO3	mg/L	< 5.0	< 5.0	< 5.0	< 5.0
Total Alkalinity as CaCO3	mg/L	125	143	129	136
Iron	mg/L	< 0.025	0.10	0.33	0.032 J
Magnesium	mg/L	16.2	16.7	16.6	18.6
Manganese	mg/L	0.28	0.27	1.0	0.75
Potassium	mg/L	6.0	6.5	6.8	5.7
Sodium	mg/L	8.8	9.2	11.8	9.6
Sulfide	mg/L	< 0.022	< 0.022	< 0.022	< 0.022
Supplemental					
Oxidation Reduction Potential, Field	mV	28.65	161.94	58.81	81.45
pH, Field	SU	6.98	7	6.58	6.82
Disolved Oxygen, Field	mg/L	0.07	0.42	0.32	0.71
Specific Conductance, Field	uS/cm	676.01	708.73	685.68	678.21
Temperature, Field	deg C	18.11	19.15	18.81	19.36
Turbidity, Field	NTU	1.43	3.84	4.71	0.73

Table 4
Summary of Daily Injection Volumes
Plant Hammond AP-1, Floyd County, Georgia

HGWC-13 Area		HGWC-8 Area	
Date	Daily Injection Volume (gal)	Date	Daily Injection Volume (gal)
10/4/2023	238	9/25/2023	492
10/9/2023	580	9/26/2023	1500
10/10/2023	1050	9/27/2023	2200
10/11/2023	1575	9/28/2023	2250
10/12/2023	1975	9/29/2023	2350
10/13/2023	1575	9/30/2023	2000
10/14/2023	1625	10/1/2023	2250
12/4/2023	16	10/2/2023	2300
12/4/2023	1630	10/3/2023	250
12/6/2023	25	10/15/2023	735
12/6/2023	350	10/16/2023	1540
12/7/2023	700	10/16/2023	540
12/8/2023	350	10/17/2023	585
12/8/2023	70	12/9/2023	200
7/9/2024	480*	12/10/2023	1150
7/10/2024	950	12/11/2023	760
7/12/2024	950	12/12/2023	640
7/14/2024	1800*	12/12/2023	185
7/16/2024	1800*	12/13/2023	2565
7/23/2024	1500*	7/11/2024	975
7/24/2024	1800*	7/13/2024	1200
7/29/2024	900*	7/15/2024	1200
7/31/2024	300	9/17/2024	1800
9/18/2024	700*	--	--
9/19/2024	1200*	--	--
9/20/2024	800*	--	--
TOTAL:	24,939	TOTAL:	29,667

Notes:

gal = gallons

* Injection volumes represent total volume injected simultaneously between two injection wells, INW-04 and INW-

Table 5
Summary of Daily Air Sparging Activities
Plant Hammond AP-1, Floyd County, Georgia

Well-ID	Date	Flow Rate (SCFM)	Duration (hours)
AS-03	7/26/2024	<1.0	2.5
AS-03	7/27/2024	<1.0	3
AS-04	7/27/2024	1.2	1
AS-03	7/28/2024	1.7	3
AS-03	7/30/2024	1.8	3
AS-03	9/9/2024	1-8	11.25
AS-04	9/9/2024	2-4	8
AS-03	9/10/2024	10	19
AS-04	9/10/2024	4	19
AS-03	9/11/2024	10	19
AS-04	9/11/2024	4	19
AS-03	9/12/2024	10	12
AS-04	9/12/2024	4	12
AS-03	9/16/2024	6	12
AS-04	9/16/2024	3	12
AS-03	9/17/2024	6	20
AS-04	9/17/2024	3	20
AS-03	9/18/2024	6-10	8
AS-04	9/18/2024	3-4	8
AS-03	9/19/2024	6-10	15
AS-04	9/19/2024	3-4	15
AS-03	9/20/2024	10	9
AS-04	9/20/2024	10	9
TOTAL:			260

Notes:

SCFM = standard cubic feet per minute.

Table 6
Summary of Screening-Level Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

	Parameter ^(1,2) :			Total Iron	Dissolved Iron	Total Boron	Dissolved Boron	Total Molybdenum	Dissolved Molybdenum	Total Arsenic	Dissolved Arsenic
Area	Well ID	Sample Date	Sample Time								
HGWC-8	PT-09	5/31/2024 ⁽³⁾	11:52 AM	0.24	--	1.5	--	0.24	--	0.0022 J	--
		7/11/2024	6:00 PM	0.56	0.02	1.5	1.4	0.43	0.42	--	--
		7/13/2024	8:45 AM	0.36	< 0.018	1.4	1.5	0.34	0.33	--	--
		7/13/2024	4:38 PM	0.66	0.3	1.1	1.2	0.29	0.29	--	--
		7/15/2024	8:22 AM	0.38	0.031	1.2	1.3	0.3	0.27	--	--
		7/15/2024	4:02 PM	6.3	3.8	1.0	1.0	0.13	0.12	--	--
		7/17/2024	1:42 PM	0.78	0.46	1.0	1.0	0.25	0.24	--	--
	PT-10	5/30/2024 ⁽³⁾	2:40 PM	0.21	--	1.4	--	0.053	--	0.0018 J	
		7/11/2024	6:00 PM	0.37	< 0.018	1.6	1.7	0.16	0.15	--	--
		7/13/2024	8:50 AM	0.19	< 0.018	1.6	1.7	0.16	0.17	--	--
		7/13/2024	4:40 PM	0.12	< 0.018	1.6	1.7	0.18	0.16	--	--
		7/15/2024	5:19 PM	0.14	--	1.7	--	0.16	--	--	--
		7/17/2024	1:44 PM	0.10	--	1.7	--	0.17	--	--	--
	PT-11	5/29/2024 ⁽³⁾	4:43 PM	0.10	--	1.4	--	0.17	--	0.0021 J	--
		7/11/2024	8:00 PM	3.2	2.4	0.69	0.72	0.046	0.047	--	--
		7/13/2024	5:56 PM	11	9	0.57	0.6	0.024	0.022	--	--
		7/15/2024	8:46 AM	2.4	1.6	0.85	0.87	0.043	0.04	--	--
		7/15/2024	4:15 PM	44	37	0.49	0.51	0.0086	0.0069	--	--
		7/17/2024	9:22 AM	13	12	0.8	0.82	0.0087	0.0081	--	--
		7/24/2024	10:05 AM	4.9	3.6	1.2	1.2	0.045	0.037	--	--
	PT-12	5/29/2024 ⁽³⁾	12:08 PM	0.032 J	--	1.5	--	0.22	--	0.0026 J	--
		7/11/2024	8:15 PM	0.1	< 0.018	1.5	1.6	0.31	0.3	--	--
		7/13/2024	5:54 PM	0.22	0.024	1.2	1.3	0.23	0.23	--	--
		7/15/2024	5:20 PM	0.49	--	1.2	--	0.14	--	--	--
		7/17/2024	12:04 PM	0.6	< 0.018	1.2	1.3	0.23	0.23	--	--
HGWC-13 Area	PT-07	5/16/2024 ⁽³⁾	12:16 PM	15.7	--	0.50	--	0.0093 J	--	0.27	--
		7/10/2024	7:40 PM	41	14	0.54	0.49	--	--	0.32	0.23
		7/12/2024	6:12 PM	17	12	0.52	0.52	--	--	0.24	0.16
		7/18/2024	2:00 PM	21	16	0.58	0.59	--	--	0.28	0.26
		7/26/2024	8:10 PM	140	0.19	0.7	0.58	--	--	0.64	0.052
		7/27/2024	5:00 PM	190	0.6	0.71	0.56	--	--	0.29	0.025
		7/28/2024	5:00 PM	31	0.46	0.63	0.56	--	--	0.097	0.026
		7/29/2024	9:05 AM	26	6.4	0.6	0.54	--	--	0.13	0.055
		7/29/2024	6:43 PM	23	12	0.56	0.54	--	--	0.13	0.088
		7/30/2024	8:55 AM	31	12	0.62	0.57	--	--	0.18	0.091
		7/30/2024	6:00 PM	160	1.4	0.76	0.59	--	--	0.39	0.045
		7/31/2024	9:40 AM	110	2.8	0.61	0.51	--	--	0.44	0.03
		9/10/2024	10:45 AM	6.9	< 0.018	0.6	--	--	--	0.16	0.016
		9/10/2024	12:35 PM	1	< 0.018	0.6	--	--	--	0.055	0.032
		9/11/2024	9:50 AM	1.9	< 0.018	0.63	--	--	--	0.071	0.0065
		9/11/2024	10:45 AM	6.6	< 0.018	0.65	--	--	--	0.035	0.019
		9/12/2024	10:50 AM	1.8	< 0.018	0.61	--	--	--	0.022	0.01
		9/13/2024	8:45 AM	0.46	< 0.018	0.68	--	--	--	0.017	0.13
		9/13/2024	8:45 AM	0.04	0.46		--	--	--	0.017	0.013
		9/21/2024	11:45 AM	0.13	< 0.018	0.46	--	--	--	0.0092	0.0073
	PT-08	5/16/2024 ⁽³⁾	10:37 AM	8.0	--	0.73	--	0.017	--	0.23	--
		7/10/2024	9:00 PM	22	9.1	0.74	0.69	--	--	0.33	0.26
		7/16/2024	7:55 AM	7.3	7.4	0.8	0.76	--	--	0.25	0.28
		7/16/2024	6:45 PM	22	9.9	0.76	0.65	--	--	0.34	0.30
		7/18/2024	8:47 PM	8.8	7.5	0.72	0.75	--	--	0.29	0.26
		7/24/2024	9:00 AM	21	11	0.7	0.71	--	--	0.3	0.26

Table 6
Summary of Screening-Level Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

	Parameter ^(1,2) :			Total Iron	Dissolved Iron	Total Boron	Dissolved Boron	Total Molybdenum	Dissolved Molybdenum	Total Arsenic	Dissolved Arsenic
Area	Well ID	Sample Date	Sample Time								
HGWC-13 Area	PT-08	7/24/2024	8:00 PM	23	9.3	0.63	0.63	--	--	0.31	0.25
		7/25/2024	4:50 PM	17	--	0.67	--	--	--	0.35	--
		7/28/2024	4:30 PM	26	7.7	0.75	0.66	--	--	0.42	0.17
		7/30/2024	5:50 PM	25	7.7	0.78	0.7	--	--	0.34	0.12
		7/31/2024	10:00 AM	34	13	0.65	0.61	--	--	0.43	0.16
		9/13/2024	10:50 AM	1.1	0.21	0.72	--	--	--	0.066	0.022
		9/21/2024	11:45 AM	0.46	0.056	0.64	--	--	--	0.02	0.0055
	PT-13	5/15/2024 ⁽³⁾	6:45 PM	15	--	0.52	--	0.0087 J	--	0.29	--
		7/10/2024	8:12 PM	80	11	0.56	0.56	--	--	0.29	0.23
		7/12/2024	7:14 PM	24	13	0.58	0.59	--	--	0.3	0.23
		7/14/2024	8:30 AM	27	15	0.61	0.57	--	--	0.3	0.29
		7/14/2024	5:00 PM	28	20	0.45	0.43	--	--	0.27	0.23
		7/18/2024	11:47 AM	18	15	0.53	0.56	--	--	0.29	0.27
		7/24/2024	8:00 PM	66	51	0.39	0.39	--	--	0.2	0.15
		7/25/2024	3:20 PM	38	--	0.55	--	--	--	0.3	--
		7/26/2024	8:20 PM	42	16	0.54	0.5	--	--	0.26	0.18
		7/27/2024	5:00 PM	30	12	0.6	0.5	--	--	0.26	0.083
		7/28/2024	4:20 PM	23	13	0.59	0.51	--	--	0.19	0.11
		7/30/2024	6:10 PM	24	13	0.57	0.56	--	--	0.17	0.076
		7/31/2024	9:50 AM	36	23	0.56	0.54	--	--	0.22	0.13
		9/10/2024	12:45 PM	15	1.2	0.72	--	--	--	0.059	0.038
		9/13/2024	4:15 PM	2.6	1.6	0.65	--	--	--	0.012	0.0071
		9/21/2024	4:00 PM	1.7	0.74	0.5	0.54	--	--	0.0078	0.0028 J
	PT-14	5/15/2024 ⁽³⁾	6:27 PM	15	--	0.51	--	0.011	--	0.21	--
		7/12/2024	6:47 PM	53	10	0.46	0.44	--	--	0.17	0.079
		7/14/2024	8:30 AM	48	14	0.68	0.66	--	--	0.20	0.18
		7/14/2024	5:15 PM	73	19	0.32	0.28	--	--	0.14	0.035
		7/16/2024	7:45 AM	63	13	0.62	0.64	--	--	0.24	0.15
		7/16/2024	6:00 PM	34	20	0.62	0.40	--	--	0.08	0.024
		7/18/2024	4:32 PM	18	14	0.64	0.66	--	--	0.21	0.2
		7/24/2024	9:00 AM	87	24	0.68	0.61	--	--	0.21	0.051
		7/24/2024	8:00 PM	250	71	0.53	0.37	--	--	0.21	0.0043
		7/25/2024	2:40 PM	130	28	0.60	0.58	--	--	0.20	0.056
		7/26/2024	10:10 AM	40	18	0.63	0.57	--	--	0.16	0.14
		7/26/2024	8:00 PM	38	18	0.62	0.57	--	--	0.16	0.15
		7/27/2024	5:00 PM	62	2.3	0.67	0.57	--	--	0.26	0.019
		7/28/2024	3:30 PM	22	15	0.65	0.59	--	--	0.13	0.12
		7/29/2024	9:05 AM	52	16	0.62	0.57	--	--	0.20	0.13
		7/29/2024	12:00 PM	64	22	0.46	0.5	--	--	0.04	0.019
		7/29/2024	1:00 PM	120	53	0.46	0.36	--	--	0.093	0.022
		7/29/2024	3:00 PM	160	75	0.36	0.31	--	--	0.098	0.02
		7/29/2024	6:33 PM	110	70	0.43	0.38	--	--	0.095	0.012
		7/30/2024	9:05 AM	25	19	0.63	0.58	--	--	0.053	0.034
		7/30/2024	5:40 PM	32	17	0.63	0.59	--	--	0.11	0.054
		7/31/2024	9:10 AM	34	18	0.61	0.56	--	--	0.18	0.11
		7/31/2024	3:40 PM	17	4.3	0.31	0.32	--	--	0.051	0.014
		9/12/2024	11:45 AM	6.5	4.4	0.74	--	--	--	0.043	0.037
		9/13/2024	9:30 AM	11	7.6	0.71	--	--	--	0.084	0.067
		9/20/2024	10:05 AM	1.8	1.5	0.58	--	--	--	0.0078	0.0067
		9/21/2024	3:45 AM	3.3	2.8	0.58	--	--	--	0.0087	0.0078

Table 6
Summary of Screening-Level Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

	Parameter ^(1,2) :			Total Iron	Dissolved Iron	Total Boron	Dissolved Boron	Total Molybdenum	Dissolved Molybdenum	Total Arsenic	Dissolved Arsenic
Area	Well ID	Sample Date	Sample Time								
HWC-13 Area	PT-15	5/15/2024 ⁽³⁾	4:10 PM	9.2	--	0.76	--	0.021	--	0.39	--
		7/14/2024	5:30 PM	14	8.2	0.69	0.69	--	--	0.42	0.38
		7/18/2024	6:13 PM	9.4	7.7	0.7	0.72	--	--	0.42	0.41
		7/24/2024	8:00 PM	13	12	0.65	0.64	--	--	0.33	0.36
		7/25/2024	4:40 PM	18	--	0.69	--	--	--	0.48	--
		9/13/2024	11:30 AM	0.29	0.16	0.73	--	--	--	0.014	0.013
		9/13/2024	11:30 AM	0.29	0.16	0.73	--	--	--	0.014	0.013
		9/18/2024	9:55 AM	0.35	0.021	0.68	--	--	--	0.0079	0.0056
		9/21/2024	10:15 AM	0.031 J	0.09 J	0.63	--	--	--	0.0062	0.0052

Notes:
< = Indicates the parameter was not detected above the analytical method detection limit (MDL).
-- = indicates sample was not collected on this date or sample was not analyzed for that parameter.
J = Indicates the parameter was estimated and detected between the MDL and the reporting limit (RL).
(1) Parameters are reported in units of milligrams per liter (mg/L).
(2) Metals were analyzed by EPA Method 6010D, 6020B.
(3) Data was collected from a baseline sampling event that occurred pre-injection activities.
(4) Screening-Level refers to data collected during injection and air sparging activities.

Table 7A
Summary of 2023 Post-injection Performance Monitoring Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-13 Area							
Sample Location		PT-07	PT-07	PT-07	PT-07	PT-07	PT-07	PT-07	PT-07
Sample Date		10/17/2023	10/24/2023	10/31/2023	11/07/2023	11/21/2023	12/08/2023	12/14/2023	12/20/2023
ANALYTE ^(1, 2, 3)	UNITS								
APPENDIX III									
Boron	mg/L	1.1	1.1	1.1	1.1	1.0	NA	1.0	1.0
Calcium	mg/L	151	NA	144	NA	121	NA	116	NA
Chloride	mg/L	15.3	15.7	16.5	NA	17.6	NA	19.4	NA
Fluoride	mg/L	0.35	0.38	0.36	NA	0.36	NA	0.38	NA
pH, Field	SU	6.89	6.83	6.75	6.89	6.89	7.2	7.17	7.13
Sulfate	mg/L	306	299	291	287	248	179	279	280
TDS	mg/L	677	NA	630	NA	566	NA	596	NA
APPENDIX IV									
Antimony	mg/L	< 0.0012	NA	< 0.00054	NA	< 0.00054	NA	< 0.00054	NA
Arsenic	mg/L	0.23	0.31	0.34	0.33	0.34	0.18	0.19	0.24
Barium	mg/L	0.092	NA	0.073	NA	0.058	NA	0.065	NA
Beryllium	mg/L	0.00014 J	NA	0.00023 J	NA	0.00014 J	NA	0.000097 J	NA
Cadmium	mg/L	< 0.00011	NA	< 0.00010	NA	< 0.00010	NA	< 0.00010	NA
Chromium	mg/L	< 0.0011	NA	< 0.0019	NA	< 0.0019	NA	< 0.0019	NA
Cobalt	mg/L	0.068	NA	0.081	NA	0.085	NA	0.025	NA
Lead	mg/L	0.00029 J	NA	< 0.00016	NA	< 0.00016	NA	< 0.00016	NA
Lithium	mg/L	0.062	NA	0.065	NA	0.060	NA	0.061	NA
Mercury	mg/L	< 0.00013	NA	< 0.00013	NA	< 0.00013	NA	< 0.00013	NA
Molybdenum	mg/L	0.011	NA	0.014	NA	0.015	NA	0.012	NA
Selenium	mg/L	< 0.0014	NA	< 0.00096	NA	< 0.00096	NA	< 0.00096	NA
Thallium	mg/L	0.00026 J	NA	< 0.00038	NA	< 0.00038	NA	< 0.00038	NA
Fluoride	mg/L	0.35	0.38	0.36	NA	0.36	NA	0.38	NA
Additional Parameters									
Bicarbonate Alkalinity as CaCO3	mg/L	120	NA	138	NA	138	NA	132	NA
Carbonate Alkalinity as CaCO3	mg/L	< 5.0	NA	< 5.0	NA	< 5.0	NA	< 5.0	NA
Total Alkalinity as CaCO3	mg/L	120	NA	138	NA	138	NA	132	NA
Iron	mg/L	18.1	18.5	20.0	4.0	17.7	28.4	10.5	13.4
Magnesium	mg/L	17.9	NA	17.9	NA	15.1	NA	35.6	NA
Manganese	mg/L	5.9	NA	5.1	NA	4.5	NA	3.3	NA
Potassium	mg/L	5.5	NA	6.9	NA	6.4	NA	6.2	NA
Sodium	mg/L	6.8	NA	7.6	NA	7.0	NA	7.4	NA
Sulfide	mg/L	< 0.022	NA	< 0.022	NA	< 0.022	NA	< 0.022	NA
Supplemental									
Oxidation Reduction Potential, Field	mV	-104.41	-103.83	-84.01	-111.48	-78.21	-126.5	34.42	-120.45
pH, Field	SU	6.89	6.83	6.75	6.89	6.89	7.2	7.17	7.13
Dissolved Oxygen, Field	mg/L	0.27	0.27	0.7	0.3	2.36	2.34	0.2	0.43
Specific Conductance, Field	uS/cm	835.69	857.51	793.71	974.44	745.93	621.06	854.78	817.25
Temperature, Field	deg C	20.71	19.83	19.32	20.67	19.18	19.41	18.33	18.29
Turbidity, Field	NTU	3.22	2.78	4.39	4.27	4.17	634	4.63	2.51
Total Iron (Field)	mg/L	NA	NA	NA	NA	NA	NA	NA	NA
Ferrous Iron (Field)	mg/L	NA	NA	NA	NA	NA	NA	NA	NA

Notes:
< = Indicates the parameter was not detected above the analytical method detection limit (MDL).
deg C = degrees Celsius
J = Indicates the parameter was estimated and detected between the MDL and the reporting limit (RL).
µS/cm = microsiemens per centimeter
mg/L = milligrams per liter.
mV = millivolts
NA = not applicable.
NTU = nephelometric turbidity units
SU = standard units
TDS = Total dissolved solids
(1) Appendix III/IV parameter per 40 CFR 257 Subpart D. Analysis of combined radium omitted from the pilot study monitoring program. Unless otherwise indicated, parameters are reported in units of milligrams per liter (mg/L).
(2) Metals were analyzed by EPA Method 6010D, 6020B, and 7470A, anions were analyzed by EPA Method 300.0, TDS was analyzed by SM2540C-2015.
(3) The pH value presented was recorded at the time of sample collection in the field.

Table 7A
Summary of 2023 Post-injection Performance Monitoring Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-13 Area							
Sample Location		PT-07	PT-07	PT-07	PT-07	PT-07	PT-08	PT-08	PT-08
Sample Date		12/27/2023	01/03/2024	01/16/2024	02/15/2024	03/13/2024	10/17/2023	10/24/2023	10/31/2023
ANALYTE ^(1, 2, 3)	UNITS								
APPENDIX III									
Boron	mg/L	1.2	1.2	1.1	0.86	0.79	0.51	1.1	1.1
Calcium	mg/L	138	NA	162	190	203	88.0	NA	115
Chloride	mg/L	17.7	NA	23.6	15.4	13.6	10.8	17.6	21.3
Fluoride	mg/L	0.34	NA	0.39	0.29	0.35	0.30	0.30	0.24
pH, Field	SU	7.21	7.02	6.91	6.84	6.82	6.79	6.75	6.54
Sulfate	mg/L	276	302	374	452	488	146	238	210
TDS	mg/L	661	NA	743	876	932	378	NA	484
APPENDIX IV									
Antimony	mg/L	< 0.00054	NA	< 0.00054	0.00069 J	0.00078 J	0.00062 J	NA	0.00079 J
Arsenic	mg/L	0.28	0.31	0.31	0.30	0.36	0.19	0.28	0.17
Barium	mg/L	0.074	NA	0.080	0.064	0.068	0.039	NA	0.051
Beryllium	mg/L	0.00011 J	NA	0.00011 J	< 0.000094	0.00011 J	< 0.000094	NA	0.00017 J
Cadmium	mg/L	< 0.00010	NA	< 0.00010	< 0.00010	< 0.00010	< 0.00010	NA	< 0.00010
Chromium	mg/L	< 0.0019	NA	< 0.0019	< 0.0019	< 0.0019	< 0.0019	NA	< 0.0019
Cobalt	mg/L	0.052	NA	0.072	0.084	0.12	0.018	NA	0.026
Lead	mg/L	< 0.00016	NA	< 0.00016	< 0.00016	< 0.00016	< 0.00016	NA	0.00019 J
Lithium	mg/L	0.079	NA	0.080	0.069	0.071	0.022 J	NA	0.013 J
Mercury	mg/L	< 0.00013	NA	< 0.00013	< 0.00013	< 0.00013	< 0.00013	NA	< 0.00013
Molybdenum	mg/L	0.011	NA	0.010	0.011	0.013	0.020	NA	0.024
Selenium	mg/L	< 0.00096	NA	< 0.00096	< 0.00096	< 0.00096	< 0.00096	NA	< 0.00096
Thallium	mg/L	< 0.00038	NA	< 0.00038	< 0.00038	< 0.00038	< 0.00038	NA	< 0.00038
Fluoride	mg/L	0.34	NA	0.39	0.29	0.35	0.30	0.30	0.24
Additional Parameters									
Bicarbonate Alkalinity as CaCO3	mg/L	137	NA	131	89.6	98.7	106	NA	126
Carbonate Alkalinity as CaCO3	mg/L	< 5.0	NA	< 5.0	< 5.0	< 5.0	< 5.0	NA	< 5.0
Total Alkalinity as CaCO3	mg/L	137	NA	131	89.6	98.7	106	NA	126
Iron	mg/L	15.8	20.9	22.8	24.5	25.3	6.5	8.0	5.8
Magnesium	mg/L	24.4	NA	23.7	26.4	24.9	10.6	NA	14.7
Manganese	mg/L	4.3	NA	5.0	5.8	5.7	2.9	NA	2.4
Potassium	mg/L	6.8	NA	7.1	7.1	6.3	4.6	NA	6.0
Sodium	mg/L	7.8	NA	7.4	7.5	6.9	4.8	NA	8.5
Sulfide	mg/L	< 0.022	NA	< 0.022	< 0.022	< 0.022	< 0.022	NA	< 0.022
Supplemental									
Oxidation Reduction Potential, Field	mV	52.94	-119.69	-124.45	-105.61	-97.33	-62.49	-75.66	-46.3
pH, Field	SU	7.21	7.02	6.91	6.84	6.82	6.79	6.75	6.54
Dissolved Oxygen, Field	mg/L	0.25	0.1	0.35	1.38	1.12	0.17	0.23	1.31
Specific Conductance, Field	uS/cm	804.84	839.53	952.88	1151.58	1182.15	504.85	736.95	747.41
Temperature, Field	deg C	17.01	17.83	17.31	19.11	18.39	19.28	20.57	19.22
Turbidity, Field	NTU	1.82	4.73	1.36	2.97	0	4.97	4.87	4.57
Total Iron (Field)	mg/L	NA	NA	NA	NA	NA	NA	NA	NA
Ferrous Iron (Field)	mg/L	NA	NA	NA	NA	NA	NA	NA	NA

Table 7A
Summary of 2023 Post-injection Performance Monitoring Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-13 Area							
Sample Location		PT-08	PT-08	PT-08	PT-08	PT-08	PT-08	PT-08	PT-08
Sample Date		11/07/2023	11/21/2023	12/08/2023	12/14/2023	12/20/2023	12/27/2023	01/03/2024	01/16/2024
ANALYTE ^(1, 2, 3)	UNITS								
APPENDIX III									
Boron	mg/L	1.0	1.1	NA	1.0	0.90	1.1	1.2	0.95
Calcium	mg/L	NA	125	NA	108	NA	105	NA	100
Chloride	mg/L	NA	18.9	NA	18.0	NA	18.9	NA	18.9
Fluoride	mg/L	NA	0.32	NA	0.28	NA	0.24	NA	0.27
pH, Field	SU	6.73	6.83	7.41	6.78	6.84	6.87	6.76	6.63
Sulfate	mg/L	273	247	217	193	191	180	205	196
TDS	mg/L	NA	545	NA	471	NA	469	NA	494
APPENDIX IV									
Antimony	mg/L	NA	< 0.00054	NA	< 0.00054	NA	< 0.00054	NA	0.00061 J
Arsenic	mg/L	0.24	0.28	0.39	0.22	0.22	0.19	0.28	0.21
Barium	mg/L	NA	0.051	NA	0.040	NA	0.047	NA	0.048
Beryllium	mg/L	NA	< 0.000094	NA	< 0.000094	NA	< 0.000094	NA	0.00010 J
Cadmium	mg/L	NA	< 0.00010	NA	< 0.00010	NA	< 0.00010	NA	< 0.00010
Chromium	mg/L	NA	< 0.0019	NA	< 0.0019	NA	< 0.0019	NA	< 0.0019
Cobalt	mg/L	NA	0.028	NA	0.026	NA	0.031	NA	0.035
Lead	mg/L	NA	< 0.00016	NA	< 0.00016	NA	< 0.00016	NA	< 0.00016
Lithium	mg/L	NA	0.026 J	NA	0.017 J	NA	0.015 J	NA	0.018 J
Mercury	mg/L	NA	< 0.00013	NA	< 0.00013	NA	< 0.00013	NA	< 0.00013
Molybdenum	mg/L	NA	0.032	NA	0.031	NA	0.035	NA	0.028
Selenium	mg/L	NA	< 0.00096	NA	< 0.00096	NA	< 0.00096	NA	< 0.00096
Thallium	mg/L	NA	< 0.00038	NA	< 0.00038	NA	< 0.00038	NA	< 0.00038
Fluoride	mg/L	NA	0.32	NA	0.28	NA	0.24	NA	0.27
Additional Parameters									
Bicarbonate Alkalinity as CaCO3	mg/L	NA	144	NA	141	NA	122	NA	116
Carbonate Alkalinity as CaCO3	mg/L	NA	< 5.0	NA	< 5.0	NA	< 5.0	NA	< 5.0
Total Alkalinity as CaCO3	mg/L	NA	144	NA	141	NA	122	NA	116
Iron	mg/L	5.7	6.7	37.9	5.0	4.8	4.9	5.9	6.9
Magnesium	mg/L	NA	14.4	NA	12.8	NA	11.8	NA	13.5
Manganese	mg/L	NA	3.5	NA	2.9	NA	2.3	NA	2.7
Potassium	mg/L	NA	5.9	NA	5.2	NA	5.3	NA	5.9
Sodium	mg/L	NA	7.0	NA	6.4	NA	7.1	NA	7.3
Sulfide	mg/L	NA	< 0.022	NA	< 0.022	NA	< 0.022	NA	< 0.022
Supplemental									
Oxidation Reduction Potential, Field	mV	-44.49	-50.51	-118.2	59.72	-62.31	77.65	-20.99	-27.71
pH, Field	SU	6.73	6.83	7.41	6.78	6.84	6.87	6.76	6.63
Dissolved Oxygen, Field	mg/L	0.99	1.33	3.61	1.35	0.21	0.59	0.71	0.33
Specific Conductance, Field	uS/cm	914.11	749.39	763.31	688.68	631.07	606.55	662.72	600.76
Temperature, Field	deg C	20.78	18.99	16.75	17.76	17.84	17.61	17.09	8.69
Turbidity, Field	NTU	4.81	4.12	194	4.43	3.51	0.56	3.17	1.55
Total Iron (Field)	mg/L	NA	NA	NA	NA	NA	NA	NA	NA
Ferrous Iron (Field)	mg/L	NA	NA	NA	NA	NA	NA	NA	NA

Table 7A
Summary of 2023 Post-injection Performance Monitoring Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-13 Area		HGWC-8 Area					
Sample Location		PT-08	PT-08	PT-09	PT-09	PT-09	PT-09	PT-09	PT-09
Sample Date		02/15/2024	03/13/2024	10/10/2023	10/17/2023	10/24/2023	10/31/2023	11/14/2023	12/14/2023
ANALYTE ^(1, 2, 3)	UNITS								
APPENDIX III									
Boron	mg/L	0.88	0.79	0.61	0.23	0.50	0.71	1.2	0.19
Calcium	mg/L	109	86.6	11.0	NA	56.2	NA	111	13.3
Chloride	mg/L	15.4	16.3	13.0	NA	14.2	NA	38.5	7.4
Fluoride	mg/L	0.15	0.16	0.38	NA	0.46	NA	0.35	0.43
pH, Field	SU	6.36	6.31	9.4	7.8	7.25	7.04	6.98	10.81
Sulfate	mg/L	251	175	71.6	25.2	69.3	107	179	24.9
TDS	mg/L	516	409	257	NA	246	NA	491	136
APPENDIX IV									
Antimony	mg/L	< 0.00054	0.0011 J	0.0017 J	NA	< 0.00054	NA	< 0.00054	< 0.00054
Arsenic	mg/L	0.19	0.16	< 0.0037	NA	< 0.00084	NA	< 0.00084	< 0.00084
Barium	mg/L	0.055	0.047	0.063	NA	0.079	NA	0.10	0.010
Beryllium	mg/L	< 0.000094	0.00012 J	< 0.000054	NA	< 0.000094	NA	< 0.000094	< 0.000094
Cadmium	mg/L	< 0.00010	< 0.00010	< 0.00011	NA	< 0.00010	NA	0.00011 J	0.00013 J
Chromium	mg/L	< 0.0019	< 0.0019	< 0.0011	NA	< 0.0019	NA	< 0.0019	< 0.0019
Cobalt	mg/L	0.033	0.034	0.00063 J	NA	0.00054 J	NA	0.0013 J	< 0.00032
Lead	mg/L	< 0.00016	< 0.00016	< 0.00012	NA	< 0.00016	NA	< 0.00016	< 0.00016
Lithium	mg/L	0.026 J	0.0092 J	0.0012 J	NA	< 0.0016	NA	< 0.0016	< 0.0016
Mercury	mg/L	< 0.00013	< 0.00013	< 0.00013	NA	< 0.00013	NA	< 0.00013	< 0.00013
Molybdenum	mg/L	0.0096 J	0.017	0.20	0.27	0.25	0.22	0.20	0.55
Selenium	mg/L	< 0.00096	< 0.00096	< 0.0014	NA	< 0.00096	NA	< 0.00096	< 0.00096
Thallium	mg/L	< 0.00038	< 0.00038	< 0.00018	NA	< 0.00038	NA	< 0.00038	< 0.00038
Fluoride	mg/L	0.15	0.16	0.38	NA	0.46	NA	0.35	0.43
Additional Parameters									
Bicarbonate Alkalinity as CaCO3	mg/L	69.0	83.0	112	NA	115	NA	133	14.7
Carbonate Alkalinity as CaCO3	mg/L	< 5.0	< 5.0	< 5.0	NA	< 5.0	NA	< 5.0	103
Total Alkalinity as CaCO3	mg/L	69.0	83.0	112	NA	115	NA	133	118
Iron	mg/L	10.6	6.5	0.089	0.040	0.40	0.067	< 0.025	0.061
Magnesium	mg/L	14.8	11.2	1.9	NA	13.7	NA	18.9	27.7
Manganese	mg/L	2.9	2.2	0.030 J	NA	0.076	NA	0.23	0.014 J
Potassium	mg/L	5.9	5.1	0.69	NA	3.8	NA	4.9	1.6
Sodium	mg/L	7.1	6.7	0.69 J	NA	4.1	NA	6.9	2.2
Sulfide	mg/L	< 0.022	< 0.022	< 0.022	NA	< 0.022	NA	< 0.022	< 0.022
Supplemental									
Oxidation Reduction Potential, Field	mV	33.23	17.62	-5.31	32.24	42.7	20.14	-12.94	-65.74
pH, Field	SU	6.36	6.31	9.4	7.8	7.25	7.04	6.98	10.81
Dissolved Oxygen, Field	mg/L	0.18	0.95	2.79	6.07	1.99	0.31	0.06	6.91
Specific Conductance, Field	uS/cm	753.81	581.66	345.12	252.68	367.85	528.08	813.75	282.14
Temperature, Field	deg C	16.85	18.96	22.18	21.47	21.31	20.06	19.07	18.03
Turbidity, Field	NTU	4.89	0.04	4.93	4.32	4.91	4.77	64.1	2.51
Total Iron (Field)	mg/L	NA	NA	NA	NA	NA	NA	NA	NA
Ferrous Iron (Field)	mg/L	NA	NA	NA	NA	NA	NA	NA	NA

Table 7A
Summary of 2023 Post-injection Performance Monitoring Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-8 Area							
Sample Location		PT-09	PT-09	PT-09	PT-09	PT-09	PT-09	PT-10	PT-10
Sample Date		12/20/2023	12/27/2023	01/03/2024	01/16/2024	02/15/2024	03/13/2024	10/10/2023	10/17/2023
ANALYTE ^(1, 2, 3)	UNITS								
APPENDIX III									
Boron	mg/L	0.44	0.99	1.2	1.0	1.6	1.8	1.7	1.3
Calcium	mg/L	NA	57.6	NA	55.5	111	82.7	125	NA
Chloride	mg/L	NA	30.4	NA	30.8	48.0	57.2	46.1	NA
Fluoride	mg/L	NA	0.39	NA	0.45	0.37	0.40	0.30	NA
pH, Field	SU	9.55	9.14	8.48	7.77	7.23	7.19	9.72	7.11
Sulfate	mg/L	97.1	147	173	128	132	139	184	122
TDS	mg/L	NA	401	NA	368	477	460	597	NA
APPENDIX IV									
Antimony	mg/L	NA	< 0.00054	NA	< 0.00054	< 0.00054	< 0.00054	< 0.0012	NA
Arsenic	mg/L	NA	0.0010 J	NA	< 0.00084	< 0.00084	0.0011 J	< 0.0037	NA
Barium	mg/L	NA	0.060	NA	0.043	0.051	0.064	0.076	NA
Beryllium	mg/L	NA	< 0.000094	NA	< 0.000094	< 0.000094	< 0.000094	< 0.000054	NA
Cadmium	mg/L	NA	0.00015 J	NA	0.00014 J	0.00014 J	0.00024 J	< 0.00011	NA
Chromium	mg/L	NA	< 0.0019	NA	< 0.0019	< 0.0019	< 0.0019	< 0.0011	NA
Cobalt	mg/L	NA	0.00051 J	NA	0.00058 J	0.00071 J	0.00085 J	0.0022 J	NA
Lead	mg/L	NA	< 0.00016	NA	< 0.00016	< 0.00016	< 0.00016	< 0.00012	NA
Lithium	mg/L	NA	< 0.0016	NA	< 0.0016	< 0.0016	< 0.0016	< 0.0073	NA
Mercury	mg/L	NA	< 0.00013	NA	< 0.00013	< 0.00013	< 0.00013	< 0.00013	NA
Molybdenum	mg/L	0.54	0.56	0.51	0.50	0.38	0.26	0.18	0.21
Selenium	mg/L	NA	< 0.00096	NA	< 0.00096	< 0.00096	< 0.00096	< 0.0014	NA
Thallium	mg/L	NA	< 0.00038	NA	< 0.00038	< 0.00038	< 0.00038	< 0.00018	NA
Fluoride	mg/L	NA	0.39	NA	0.45	0.37	0.40	0.30	NA
Additional Parameters									
Bicarbonate Alkalinity as CaCO3	mg/L	NA	86.2	NA	111	129	148	166	NA
Carbonate Alkalinity as CaCO3	mg/L	NA	< 5.0	NA	< 5.0	< 5.0	< 5.0	< 5.0	NA
Total Alkalinity as CaCO3	mg/L	NA	90.4	NA	111	129	148	166	NA
Iron	mg/L	0.24	0.27	0.071	0.11	10.7	0.28	1.6	0.84
Magnesium	mg/L	NA	34.1	NA	26.1	14.9	33.6	16.7	NA
Manganese	mg/L	NA	0.042	NA	0.15	3.0	0.20	1.6	NA
Potassium	mg/L	NA	4.0	NA	5.0	6.0	6.7	6.1	NA
Sodium	mg/L	NA	6.9	NA	9.9	7.2	11.6	8.4	NA
Sulfide	mg/L	NA	< 0.022	NA	< 0.022	< 0.022	< 0.022	< 0.022	NA
Supplemental									
Oxidation Reduction Potential, Field	mV	169.18	-6.94	-63.05	-0.49	-6.65	10.59	-278.56	-50.33
pH, Field	SU	9.55	9.14	8.48	7.77	7.23	7.19	9.72	7.11
Dissolved Oxygen, Field	mg/L	0.94	1.51	0.12	0.27	0.08	0.25	0.39	0.29
Specific Conductance, Field	uS/cm	403.87	533.31	617.95	511.03	678.76	731.33	898.8	568.18
Temperature, Field	deg C	17.65	18.78	16.43	14.23	18.42	17.39	21.48	20.31
Turbidity, Field	NTU	4.95	4.97	2.52	3.62	4.68	4.43	2.95	4.42
Total Iron (Field)	mg/L	NA	NA	NA	NA	NA	NA	NA	NA
Ferrous Iron (Field)	mg/L	NA	NA	NA	NA	NA	NA	NA	NA

Table 7A
Summary of 2023 Post-injection Performance Monitoring Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-8 Area									
Sample Location		PT-10	PT-10	PT-10	PT-10	PT-10	PT-10	PT-10	PT-10	PT-10	PT-10
Sample Date		10/24/2023	10/31/2023	11/14/2023	12/14/2023	12/20/2023	12/27/2023	01/03/2024	01/16/2024	02/15/2024	03/13/2024
ANALYTE ^(1, 2, 3)	UNITS										
APPENDIX III											
Boron	mg/L	1.3	1.1	1.3	1.6	1.3	1.6	1.7	2.1	2.0	1.6
Calcium	mg/L	90.6	NA	119	137	NA	109	NA	120	112	114
Chloride	mg/L	31.7	NA	43.3	46.9	NA	37.3	NA	55.2	60.3	93.5
Fluoride	mg/L	0.34	NA	0.35	0.33	NA	0.32	NA	0.27	0.18	0.20
pH, Field	SU	7.13	7.11	7.16	7.09	6.66	6.99	6.97	7.05	6.68	6.84
Sulfate	mg/L	102	108	184	206	165	157	170	163	139	37.6
TDS	mg/L	402	NA	516	569	NA	488	NA	512	518	507
APPENDIX IV											
Antimony	mg/L	< 0.00054	NA	< 0.00054	< 0.00054	NA	< 0.00054	NA	< 0.00054	< 0.00054	< 0.00054
Arsenic	mg/L	0.00085 J	NA	< 0.00084	< 0.00084	NA	< 0.00084	NA	< 0.00084	< 0.00084	0.0011 J
Barium	mg/L	0.056	NA	0.061	0.063	NA	0.055	NA	0.062	0.055	0.061
Beryllium	mg/L	< 0.000094	NA	< 0.000094	< 0.000094	NA	< 0.000094	NA	< 0.000094	< 0.000094	< 0.000094
Cadmium	mg/L	< 0.00010	NA	< 0.00010	< 0.00010	NA	< 0.00010	NA	< 0.00010	< 0.00010	< 0.00010
Chromium	mg/L	< 0.0019	NA	< 0.0019	< 0.0019	NA	< 0.0019	NA	< 0.0019	< 0.0019	< 0.0019
Cobalt	mg/L	0.0016 J	NA	0.0024 J	0.0027 J	NA	0.0023 J	NA	0.0020 J	0.0018 J	0.0014 J
Lead	mg/L	< 0.00016	NA	< 0.00016	< 0.00016	NA	< 0.00016	NA	< 0.00016	< 0.00016	< 0.00016
Lithium	mg/L	0.0016 J	NA	0.0022 J	0.0026 J	NA	0.0021 J	NA	< 0.0016	< 0.0016	< 0.0016
Mercury	mg/L	< 0.00013	NA	< 0.00013	< 0.00013	NA	< 0.00013	NA	< 0.00013	< 0.00013	< 0.00013
Molybdenum	mg/L	0.22	0.19	0.19	0.21	0.20	0.22	0.24	0.097	0.065	0.074
Selenium	mg/L	< 0.00096	NA	< 0.00096	< 0.00096	NA	< 0.00096	NA	< 0.00096	< 0.00096	< 0.00096
Thallium	mg/L	< 0.00038	NA	< 0.00038	< 0.00038	NA	< 0.00038	NA	< 0.00038	< 0.00038	< 0.00038
Fluoride	mg/L	0.34	NA	0.35	0.33	NA	0.32	NA	0.27	0.18	0.20
Additional Parameters											
Bicarbonate Alkalinity as CaCO3	mg/L	141	NA	136	141	NA	135	NA	158	139	135
Carbonate Alkalinity as CaCO3	mg/L	< 5.0	NA	< 5.0	< 5.0	NA	< 5.0	NA	< 5.0	< 5.0	< 5.0
Total Alkalinity as CaCO3	mg/L	141	NA	136	141	NA	135	NA	158	139	135
Iron	mg/L	0.91	0.66	0.56	0.71	0.78	0.51	0.46	0.30	0.32	0.61
Magnesium	mg/L	12.1	NA	15.3	18.9	NA	13.9	NA	16.1	15.3	14.4
Manganese	mg/L	0.95	NA	0.82	0.59	NA	0.47	NA	0.63	0.67	0.64
Potassium	mg/L	7.0	NA	6.6	7.5	NA	6.5	NA	8.0	7.2	6.6
Sodium	mg/L	7.3	NA	7.1	8.9	NA	7.7	NA	9.3	9.5	8.7
Sulfide	mg/L	< 0.022	NA	< 0.022	< 0.022	NA	< 0.022	NA	< 0.022	< 0.022	< 0.022
Supplemental											
Oxidation Reduction Potential, Field	mV	-80.61	-57.17	-50.86	-129.48	-10.29	-79.65	-40.46	-24.07	-3.45	-22.57
pH, Field	SU	7.13	7.11	7.16	7.09	6.66	6.99	6.97	7.05	6.68	6.84
Dissolved Oxygen, Field	mg/L	0.13	0.15	2.86	0.09	0.22	0.85	0.66	0.41	0.06	0.07
Specific Conductance, Field	uS/cm	548.18	483.92	713.27	711.29	708.31	627.32	648.52	731.31	731.35	739.98
Temperature, Field	deg C	21.19	19.84	20.6	19.15	16.12	18.65	16.78	17.09	18.42	18.52
Turbidity, Field	NTU	1.43	3.88	4.45	4.94	4.81	4.74	4.1	3.57	2.66	4.39
Total Iron (Field)	mg/L	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Ferrous Iron (Field)	mg/L	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA

Table 7B
Summary of 2024 Post-injection Performance Monitoring Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-13 Area										
Sample Location		PT-07	PT-07	PT-07	PT-07	PT-07	PT-07	PT-07	PT-07	PT-07	PT-07	PT-07
Sample Date		08/01/2024	08/09/2024	08/14/2024	08/20/2024	09/04/2024	09/24/2024	10/01/2024	10/08/2024	10/15/2024	11/04/2024	12/02/2024
ANALYTE	UNITS											
APPENDIX III												
Boron	mg/L	0.57	0.54	0.55	0.57	0.56	0.54	0.61	0.54	0.56	0.67	0.72
Calcium	mg/L	123	NA	127	NA	117	128	NA	108	NA	121	129
Chloride	mg/L	16.7	NA	18.6	NA	17.4	17.5	NA	18.6	NA	16.5	16.5
Fluoride	mg/L	0.22	NA	0.29	NA	0.37	0.26	NA	0.30	NA	0.29	0.35
pH, Field	SU	6.72	6.93	7.04	6.84	6.89	6.61	6.94	6.72	6.75	6.76	6.87
Sulfate	mg/L	223	NA	231	NA	221	249	NA	238	NA	194	192
TDS	mg/L	578	NA	574	NA	561	559	NA	548	NA	542	528
APPENDIX IV												
Antimony	mg/L	< 0.00054	NA	< 0.00054	NA	0.0014 J	0.00056 J	NA	< 0.00054	NA	< 0.00054	< 0.00038
Arsenic	mg/L	0.11	0.21	0.24	0.26	0.30	0.016	0.0062	0.025	0.044	0.11	0.15
Barium	mg/L	0.049	NA	0.047	NA	0.050	0.056	NA	0.051	NA	0.051	0.047
Beryllium	mg/L	0.00019 J	NA	0.00010 J	NA	< 0.000094	0.00012 J	NA	0.00014 J	NA	< 0.000094	0.000071 J
Cadmium	mg/L	< 0.00010	NA	< 0.00010	NA	< 0.00010	0.00015 J	NA	0.00016 J	NA	< 0.00010	0.00012 J
Chromium	mg/L	< 0.0019	NA	< 0.0019	NA	< 0.0019	< 0.0019	NA	< 0.0019	NA	< 0.0019	0.00032 J
Cobalt	mg/L	0.056	NA	0.059	NA	0.12	0.031	NA	0.033	NA	0.042	0.048
Lead	mg/L	< 0.00016	NA	< 0.00016	NA	< 0.00016	< 0.00016	NA	< 0.00016	NA	0.00019 J	< 0.000076
Lithium	mg/L	0.056	NA	0.058	NA	0.053	0.048	NA	0.051	NA	0.051	0.050
Mercury	mg/L	< 0.00013	NA	< 0.00013	NA	< 0.00013	< 0.00013	NA	0.00018 J	NA	< 0.00013	< 0.00013
Molybdenum	mg/L	0.0047 J	NA	0.0079 J	NA	0.010	0.0054 J	NA	0.0045 J	NA	0.0088 J	0.011
Selenium	mg/L	< 0.00096	NA	< 0.00096	NA	< 0.00096	0.0011 J	NA	< 0.00096	NA	< 0.00096	0.00097 J
Thallium	mg/L	0.00050 J	NA	< 0.00038	NA	< 0.00038	0.00067 J	NA	< 0.00038	NA	< 0.00038	0.00024 J
Fluoride	mg/L	0.22	NA	0.29	NA	0.37	0.26	NA	0.30	NA	0.29	0.35
Additional Parameters												
Bicarbonate Alkalinity as CaCO3	mg/L	119	NA	134	NA	143	136	NA	149	NA	152	150
Carbonate Alkalinity as CaCO3	mg/L	< 5.0	NA	< 5.0	NA	< 5.0	< 1.9	NA	< 1.9	NA	< 5.0	< 5.0
Total Alkalinity as CaCO3	mg/L	119	NA	134	NA	143	136	NA	149	NA	152	150
Iron	mg/L	13.2	18.3	18.4	17.9	15.6	0.54	0.23	3.2	4.3	6.6	7.7
Magnesium	mg/L	17.8	NA	18.7	NA	16.4	18.7	NA	17.0	NA	17.9	17.7
Manganese	mg/L	4.2	NA	4.3	NA	4.4	2.4	NA	2.8	NA	3.1	3.4
Potassium	mg/L	5.7	NA	5.7	NA	5.8	5.9	NA	5.6	NA	5.9	6.0
Sodium	mg/L	8.6	NA	9.5	NA	9.8	10.2	NA	10.5	NA	9.8	8.5
Sulfide	mg/L	< 0.022	NA	< 0.022	NA	< 0.022	< 0.011 H	NA	< 0.011	NA	< 0.022	< 0.022
Supplemental												
Oxidation Reduction Potential, Field	mV	-56.66	-85.29	-94.38	-91.63	-83.52	18.71	591.7	-20.46	-59.53	-79.29	-57.67
pH, Field	SU	6.72	6.93	7.04	6.84	6.89	6.61	6.94	6.72	6.75	6.76	6.87
Dissolved Oxygen, Field	mg/L	0.14	0.06	0.3	0.13	0.14	0.28	0.19	0.54	0.09	1.46	0.46
Specific Conductance, Field	uS/cm	777.88	772.04	708.53	790.53	752.53	716.65	754.99	729.91	747.98	756.66	760.18
Temperature, Field	deg C	18.01	20.75	20.27	21.73	20.23	22.16	21.1	20.76	19.49	19.98	18.82
Turbidity, Field	NTU	4.94	2.62	3.35	5	1.66	0.54	4.92	4.4	1.12	0.44	1.93
Total Iron (Field)	mg/L	NA	NA	NA	NA	5.5	NA	NA	NA	1.0	5.0	9.2
Ferrous Iron (Field)	mg/L	NA	NA	NA	NA	2.0	NA	NA	NA	0.50	4.5	6.5

Notes:

< = Indicates the parameter was not detected above the analytical method detection limit (MDL).
deg C = degrees Celsius
J = Indicates the parameter was estimated and detected between the MDL and the reporting limit (RL).
H = Indicates sample was received or analysis requested beyond the recognized method holding time.
µS/cm = microsiemens per centimeter
mg/L = miligrams per liter.

mV = millivolts
NA = not applicable.
ND = nondetectable.
NTU = nephelometric turbidity units
SU = standard units
TDS = Total dissolved solids

(1) Appendix III/IV parameter per 40 CFR 257 Subpart D. Analysis of combined radium omitted from the pilot study monitoring program. Unless otherwise indicated, parameters are reported in units of milligrams per liter (mg/L).

(2) Metals were analyzed by EPA Method 6010D, 6020B, and 7470A, anions were analyzed by EPA Method 300.0, TDS was analyzed by SM2540C-2015.

(3) The pH value presented was recorded at the time of sample collection in the field.

Table 7B
Summary of 2024 Post-injection Performance Monitoring Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-13 Area									
Sample Location		PT-07	PT-07	PT-07	PT-07	PT-08	PT-08	PT-08	PT-08	PT-08	PT-08
Sample Date		01/06/2025	02/04/2025	03/05/2025	4/03/2025	08/01/2024	08/08/2024	08/14/2024	08/20/2024	09/05/2024	09/24/2024
ANALYTE	UNITS										
APPENDIX III											
Boron	mg/L	0.83 J	0.74	0.77	0.80	0.63	0.55	0.62	0.63	0.70	0.61
Calcium	mg/L	113	121	121	116	85.2	NA	99.1	NA	94.4	112
Chloride	mg/L	18.1	19.3	17.0	16.6	14.0	NA	17.0	NA	19.3	17.1
Fluoride	mg/L	0.38	0.40	0.34	0.34	0.16	NA	< 0.050	NA	0.16	0.25
pH, Field	SU	6.86	6.88	6.94	6.92	6.48	6.48	6.58	6.4	6.48	6.5
Sulfate	mg/L	181	157	159	159	176	NA	203	NA	193	239
TDS	mg/L	529	520	484	512	443	NA	474	NA	466	490
APPENDIX IV											
Antimony	mg/L	< 0.00050	< 0.00050	< 0.00050	< 0.00050	< 0.00054	NA	< 0.00054	NA	0.0013 J	0.0012 J
Arsenic	mg/L	0.18	0.15	0.18	0.23	0.26	0.32	0.29	0.29	0.23	0.021
Barium	mg/L	0.047	0.047	0.049	0.044	0.044	NA	0.048	NA	0.048	0.050
Beryllium	mg/L	< 0.00015	< 0.00015	< 0.00015	< 0.00015	0.000098 J	NA	< 0.000094	NA	< 0.000094	0.00013 J
Cadmium	mg/L	< 0.00012	< 0.00012	< 0.00012	< 0.00012	< 0.00010	NA	< 0.00010	NA	< 0.00010	0.00018 J
Chromium	mg/L	< 0.0012	< 0.0012	< 0.0012	< 0.0012	< 0.0019	NA	< 0.0019	NA	< 0.0019	< 0.0019
Cobalt	mg/L	0.042	0.036	0.037	0.034	0.073	NA	0.084	NA	0.084	0.022
Lead	mg/L	< 0.00025	< 0.00025	< 0.00025	< 0.00025	< 0.00016	NA	< 0.00016	NA	< 0.00016	< 0.00016
Lithium	mg/L	0.049	0.0461	0.0433	0.0408	0.022 J	NA	0.025 J	NA	0.015 J	0.035
Mercury	mg/L	< 0.00036	< 0.00012	< 0.000091	< 0.000091	< 0.00013	NA	< 0.00013	NA	< 0.00013	< 0.00013
Molybdenum	mg/L	0.011	0.013	0.012	0.011	0.012	NA	0.011	NA	0.010	0.0098 J
Selenium	mg/L	< 0.0012	< 0.0012	< 0.0012	< 0.0012	< 0.00096	NA	< 0.00096	NA	< 0.00096	0.0013 J
Thallium	mg/L	0.00027 J	0.00019 J	0.00031 J	0.00028 J	< 0.00038	NA	< 0.00038	NA	< 0.00038	0.00050 J
Fluoride	mg/L	0.38	0.40	0.34	0.34	0.16	NA	< 0.050	NA	0.16	0.25
Additional Parameters											
Bicarbonate Alkalinity as CaCO3	mg/L	163	169	163	169	76.4	NA	89.7	NA	77.7	91.8
Carbonate Alkalinity as CaCO3	mg/L	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	NA	< 5.0	NA	< 5.0	< 1.9
Total Alkalinity as CaCO3	mg/L	163	169	163	169	76.4	NA	89.7	NA	77.7	91.8
Iron	mg/L	7.8	7.5	5.9	7.6	14.5	16.7	15.5	14.8	9.8	1.1
Magnesium	mg/L	16.5	16.8	15.5	14.4	11.9	NA	13.6	NA	13.2	14.3
Manganese	mg/L	3.2	3.4	3.3 J	3.0	4.1	NA	4.2	NA	3.0	2.5
Potassium	mg/L	5.8	5.5	5.7	5.4	5.0	NA	4.9	NA	5.3	5.3
Sodium	mg/L	8.1	8.4	8.3	7.6	6.8	NA	7.2	NA	8.2	9.1
Sulfide	mg/L	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	NA	< 0.022	NA	< 0.022	< 0.011 H
Supplemental											
Oxidation Reduction Potential, Field	mV	-65.22	-92.81	70.4	-83.52	-35.37	-39.64	-19.66	-30.2	-32.93	37.08
pH, Field	SU	6.86	6.88	6.94	6.92	6.48	6.48	6.58	6.4	6.48	6.5
Dissolved Oxygen, Field	mg/L	0.17	0.1	0.7	0.78	0.22	0.1	0.26	0.11	6.22	2.16
Specific Conductance, Field	uS/cm	681.45	759.86	747.64	759.6	609.92	666.62	585.2	689.81	605.65	587.82
Temperature, Field	deg C	15.75	18.64	17.38	18.74	23.17	20.1	21.67	21.81	20.13	22.19
Turbidity, Field	NTU	0.39	1.21	0.4	0.41	4.96	4.89	3.76	4.77	4.81	4.25
Total Iron (Field)	mg/L	6.2	6.0	5.0	NA	NA	NA	NA	NA	3.5	NA
Ferrous Iron (Field)	mg/L	6.2	4.5	3.4	4.3	NA	NA	NA	NA	3.0	NA

Table 7B Summary of 2024 Post-injection Performance Monitoring Groundwater Analytical Data Plant Hammond AP-1, Floyd County, Georgia												
Pilot Study Area		HGWC-13 Area										
Sample Location		PT-08	PT-08	PT-08	PT-08	PT-08	PT-08	PT-08	PT-08	PT-08	PT-13	PT-13
Sample Date		10/01/2024	10/08/2024	10/15/2024	11/04/2024	12/02/2024	01/06/2025	02/04/2025	03/05/2025	04/02/2025	08/01/2024	08/09/2024
ANALYTE	UNITS											
APPENDIX III												
Boron	mg/L	0.56	0.58	0.59	0.70	0.85	0.92 J	0.82	1.0	1.0	0.51	0.52
Calcium	mg/L	NA	106	NA	105	111	105	107	108	119	111	NA
Chloride	mg/L	NA	18.1	NA	15.6	17.5	17.7	19.6	19.3	18.8	15.5	NA
Fluoride	mg/L	NA	0.23	NA	0.15	0.14	0.23	0.18	0.20	0.19	0.26	NA
pH, Field	SU	6.63	6.69	6.84	6.39	6.49	6.51	6.36	6.53	6.5	6.69	6.86
Sulfate	mg/L	NA	242	NA	187	187	183	170	177	175	229	NA
TDS	mg/L	NA	524	NA	474	451	479	483	478	491	549	NA
APPENDIX IV												
Antimony	mg/L	NA	< 0.00054	NA	< 0.00054	< 0.00038	< 0.00050	< 0.00050	< 0.00050	< 0.00050	< 0.00054	NA
Arsenic	mg/L	0.085	0.066	0.052	0.027	0.010	0.062	0.033	0.018	0.027	0.20	0.26
Barium	mg/L	NA	0.051	NA	0.053	0.052	0.051	0.049	0.047	0.045	0.043	NA
Beryllium	mg/L	NA	< 0.000094	NA	< 0.000094	0.000070 J	< 0.00015	< 0.00015	< 0.00015	< 0.00015	< 0.000094	NA
Cadmium	mg/L	NA	0.00011 J	NA	< 0.00010	< 0.000041	< 0.00012	< 0.00012	< 0.00012	< 0.00012	< 0.00010	NA
Chromium	mg/L	NA	< 0.0019	NA	< 0.0019	0.00040 J	< 0.0012	< 0.0012	< 0.0012	< 0.0012	< 0.0019	NA
Cobalt	mg/L	NA	0.021	NA	0.032	0.048	0.042	0.040	0.033	0.024	0.040	NA
Lead	mg/L	NA	< 0.00016	NA	< 0.00016	< 0.000076	< 0.00025	< 0.00025	< 0.00025	< 0.00025	< 0.00016	NA
Lithium	mg/L	NA	0.035	NA	0.023 J	0.020 J	0.028 J	0.0201 J	0.0149 J	0.0129 J	0.058	NA
Mercury	mg/L	NA	< 0.00013	NA	< 0.00013	< 0.00013	< 0.000091	< 0.00012	< 0.000091	< 0.000091	< 0.00013	NA
Molybdenum	mg/L	NA	0.0086 J	NA	0.0097 J	0.0068 J	0.010 J	0.0096 J	0.010	0.012	0.0052 J	NA
Selenium	mg/L	NA	< 0.00096	NA	0.0014 J	0.0012 J	< 0.0012	< 0.0012	< 0.0012	< 0.0012	< 0.00096	NA
Thallium	mg/L	NA	< 0.00038	NA	< 0.00038	< 0.00020	0.00025 J	0.00018 J	0.00025 J	0.00025 J	< 0.00038	NA
Fluoride	mg/L	NA	0.23	NA	0.15	0.14	0.23	0.18	0.20	0.19	0.26	NA
Additional Parameters												
Bicarbonate Alkalinity as CaCO3	mg/L	NA	114	NA	98.7	84.2	111	113	111	124	115	NA
Carbonate Alkalinity as CaCO3	mg/L	NA	< 1.9	NA	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	NA
Total Alkalinity as CaCO3	mg/L	NA	114	NA	98.7	84.2	111	113	111	124	115	NA
Iron	mg/L	3.7	2.8	2.2	0.63	0.32	1.3	1.8	0.38	0.37	25.6	24.0
Magnesium	mg/L	NA	15.4	NA	14.4	14.3	13.7	13.4	13.0	12.5	15.5	NA
Manganese	mg/L	NA	2.2	NA	1.4	1.5	2.7	2.3	1.7	2.0	4.3	NA
Potassium	mg/L	NA	5.7	NA	5.7	6.0	5.5	5.0	5.2	4.9	5.3	NA
Sodium	mg/L	NA	9.9	NA	8.2	7.4	7.2	6.8	6.6	6.3	8.2	NA
Sulfide	mg/L	NA	< 0.011	NA	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	NA
Supplemental												
Oxidation Reduction Potential, Field	mV	-27.07	-19.98	-15.45	39.51	48.48	6.07	61.47	52.88	29.28	-86.24	-104.66
pH, Field	SU	6.63	6.69	6.84	6.39	6.49	6.51	6.36	6.53	6.5	6.69	6.86
Dissolved Oxygen, Field	mg/L	0.52	0.36	0.29	0.15	0.13	0.31	0.02	0.2	0.1	1.38	0.12
Specific Conductance, Field	uS/cm	732.73	669.84	702.16	643.29	607.25	670.03	674.81	698.87	695.92	719.27	745.85
Temperature, Field	deg C	21.51	20.42	19.46	19.37	18.52	15.56	19.17	17.66	20.01	23.83	20.66
Turbidity, Field	NTU	3.6	4.99	4.95	4.98	2.3	8.05	4.76	4.05	4.55	2.53	1.58
Total Iron (Field)	mg/L	NA	NA	2.5	0.60	0.40	2.0	1.0	0.50	NA	NA	NA
Ferrous Iron (Field)	mg/L	NA	NA	2.0	0.50	0.20	1.0	1.0	0.50	0.40	NA	NA

Table 7B Summary of 2024 Post-injection Performance Monitoring Groundwater Analytical Data Plant Hammond AP-1, Floyd County, Georgia												
Pilot Study Area		HGWC-13 Area										
Sample Location		PT-13	PT-13	PT-13	PT-13	PT-13	PT-13	PT-13	PT-13	PT-13	PT-13	PT-13
Sample Date		08/14/2024	08/20/2024	09/04/2024	09/24/2024	10/01/2024	10/08/2024	10/15/2024	11/04/2024	12/02/2024	01/06/2025	02/04/2025
ANALYTE	UNITS											
APPENDIX III												
Boron	mg/L	0.52	0.54	0.53	0.49	0.56	0.54	0.54	0.65	0.70	0.79 J	0.73
Calcium	mg/L	124	NA	120	122	NA	114	NA	119	129	113	114
Chloride	mg/L	17.7	NA	17.4	16.9	NA	18.8	NA	18.5	18.6	19.1	20.2
Fluoride	mg/L	0.28	NA	0.40	0.36	NA	0.35	NA	0.32	0.37	0.42	0.35
pH, Field	SU	6.93	6.62	6.76	6.52	6.63	6.65	6.66	6.7	6.82	6.8	6.82
Sulfate	mg/L	232	NA	241	261	NA	254	NA	199	200	186	161
TDS	mg/L	564	NA	570	518	NA	562	NA	550	528	540	527
APPENDIX IV												
Antimony	mg/L	< 0.00054	NA	< 0.00054	< 0.00054	NA	0.00066 J	NA	< 0.00054	< 0.00038	< 0.00050	< 0.00050
Arsenic	mg/L	0.26	0.25	0.31	0.021	0.0026 J	0.033	0.064	0.14	0.19	0.20	0.19
Barium	mg/L	0.043	NA	0.050	0.050	NA	0.050	NA	0.050	0.047	0.047	0.046
Beryllium	mg/L	< 0.000094	NA	< 0.000094	< 0.000094	NA	< 0.000094	NA	0.00011 J	0.000082 J	< 0.00015	< 0.00015
Cadmium	mg/L	< 0.00010	NA	< 0.00010	0.00011 J	NA	< 0.00010	NA	< 0.00010	0.000054 J	< 0.00012	< 0.00012
Chromium	mg/L	< 0.0019	NA	< 0.0019	< 0.0019	NA	< 0.0019	NA	< 0.0019	0.00039 J	< 0.0012	< 0.0012
Cobalt	mg/L	0.036	NA	0.038	0.022	NA	0.025	NA	0.024	0.023	0.021	0.018
Lead	mg/L	< 0.00016	NA	< 0.00016	0.00057 J	NA	< 0.00016	NA	< 0.00016	0.00011 J	< 0.00025	< 0.00025
Lithium	mg/L	0.058	NA	0.059	0.052	NA	0.053	NA	0.058	0.058	0.053	0.0520
Mercury	mg/L	< 0.00013	NA	< 0.00013	< 0.00013	NA	< 0.00013	NA	< 0.00013	< 0.00013	< 0.000091	< 0.00012
Molybdenum	mg/L	0.0072 J	NA	0.0088 J	0.0031 J	NA	0.0043 J	NA	0.0072 J	0.0085 J	0.0088 J	0.0099 J
Selenium	mg/L	< 0.00096	NA	< 0.00096	0.0013 J	NA	< 0.00096	NA	0.0011 J	0.0011 J	< 0.0012	< 0.0012
Thallium	mg/L	< 0.00038	NA	< 0.00038	< 0.00038	NA	< 0.00038	NA	< 0.00038	0.00023 J	0.00030 J	0.00021 J
Fluoride	mg/L	0.28	NA	0.40	0.36	NA	0.35	NA	0.32	0.37	0.42	0.35
Additional Parameters												
Bicarbonate Alkalinity as CaCO3	mg/L	118	NA	134	105	NA	132	NA	147	145	155	163
Carbonate Alkalinity as CaCO3	mg/L	< 5.0	NA	< 5.0	< 1.9	NA	< 1.9	NA	< 5.0	< 5.0	< 5.0	< 5.0
Total Alkalinity as CaCO3	mg/L	118	NA	134	105	NA	132	NA	147	145	155	163
Iron	mg/L	22.8	21.6	17.2	5.3	1.3	6.6	7.2	8.6	9.5	7.7	7.6
Magnesium	mg/L	16.9	NA	16.1	16.1	NA	16.2	NA	16.9	17.8	16.4	16.4
Manganese	mg/L	4.0	NA	4.1	3.2	NA	3.2	NA	2.9	3.0	2.8	2.9
Potassium	mg/L	5.4	NA	5.9	5.4	NA	5.7	NA	5.9	6.1	6.0	5.4
Sodium	mg/L	9.2	NA	10.6	9.2	NA	10.7	NA	11.3	10.1	8.8	8.4
Sulfide	mg/L	< 0.022	NA	< 0.022	< 0.011 H	NA	< 0.011	NA	< 0.022	< 0.022	< 0.022	< 0.022
Supplemental												
Oxidation Reduction Potential, Field	mV	-86.83	-61.57	-77.3	-13.81	716.91	-29.39	-50.75	-54.08	-59.12	-104.81	-84.83
pH, Field	SU	6.93	6.62	6.76	6.52	6.63	6.65	6.66	6.7	6.82	6.8	6.82
Dissolved Oxygen, Field	mg/L	0.59	0.97	0.03	0.37	0.06	0.15	0.92	3.41	0.52	0.04	0.13
Specific Conductance, Field	uS/cm	699.08	794.29	834.28	682.25	726.14	691.25	734.97	759.92	773.35	682.49	753.4
Temperature, Field	deg C	20.18	21.82	20.72	23.01	21.04	20.24	19.8	19.85	18.53	17.29	18.27
Turbidity, Field	NTU	2.64	3.99	2.64	4.97	4.83	4.83	4.98	4.66	4.74	4.96	4.9
Total Iron (Field)	mg/L	NA	NA	6.0	NA	NA	NA	5.0	5.0	4.0	6.8	5.5
Ferrous Iron (Field)	mg/L	NA	NA	5.5	NA	NA	NA	3.0	2.5	NA	6.6	4.0

Table 7B
Summary of 2024 Post-injection Performance Monitoring Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-13 Area										
Sample Location		PT-13	PT-13	PT-14	PT-14	PT-14	PT-14	PT-14	PT-14	PT-14	PT-14	PT-14
Sample Date		03/05/2025	04/02/2025	08/01/2024	08/08/2024	08/13/2024	08/20/2024	09/05/2024	09/24/2024	10/01/2024	10/08/2024	10/15/2024
ANALYTE	UNITS											
APPENDIX III												
Boron	mg/L	0.81	0.84	0.55	0.55	0.60	0.59	0.62	0.59	0.56	0.57	0.59
Calcium	mg/L	125	127	123	NA	136	NA	121	135	NA	116	NA
Chloride	mg/L	17.3	18.5	17.8	NA	19.6	NA	19.1	19.6	NA	20.4	NA
Fluoride	mg/L	0.36	0.36	0.22	NA	0.21	NA	0.27	0.28	NA	0.27	NA
pH, Field	SU	6.93	6.85	6.84	6.95	7.03	6.75	6.99	6.69	6.73	6.87	6.94
Sulfate	mg/L	167	166	224	NA	239	NA	236	259	NA	249	NA
TDS	mg/L	528	517	599	NA	621	NA	586	588	NA	557	NA
APPENDIX IV												
Antimony	mg/L	< 0.00050	< 0.00050	< 0.00054	NA	< 0.00054	NA	< 0.00054	< 0.00054	NA	< 0.00054	NA
Arsenic	mg/L	0.19	0.17	0.15	0.22	0.24	0.23	0.23	0.058	0.040	0.15	0.20
Barium	mg/L	0.054	0.047	0.045	NA	0.048	NA	0.048	0.050	NA	0.047	NA
Beryllium	mg/L	0.00019 J	< 0.00015	< 0.000094	NA	< 0.000094	NA	< 0.000094	< 0.000094	NA	0.00011 J	NA
Cadmium	mg/L	< 0.00012	< 0.00012	< 0.00010	NA	< 0.00010	NA	< 0.00010	< 0.00010	NA	< 0.00010	NA
Chromium	mg/L	< 0.0012	< 0.0012	< 0.0019	NA	< 0.0019	NA	< 0.0019	< 0.0019	NA	< 0.0019	NA
Cobalt	mg/L	0.019	0.018	0.025	NA	0.028	NA	0.025	0.022	NA	0.023	NA
Lead	mg/L	0.00055 J	< 0.00025	< 0.00016	NA	< 0.00016	NA	< 0.00016	0.00038 J	NA	0.00026 J	NA
Lithium	mg/L	0.0448	0.0423	0.049	NA	0.053	NA	0.049	0.049	NA	0.046	NA
Mercury	mg/L	< 0.000091	< 0.000091	< 0.00013	NA	< 0.00013	NA	< 0.00013	< 0.00013	NA	< 0.00013	NA
Molybdenum	mg/L	0.011	0.0079 J	0.011	NA	0.014	NA	0.015	0.010	NA	0.015	NA
Selenium	mg/L	< 0.0012	< 0.0012	< 0.00096	NA	< 0.00096	NA	< 0.00096	< 0.00096	NA	< 0.00096	NA
Thallium	mg/L	0.00031 J	0.00036 J	< 0.00038	NA	< 0.00038	NA	< 0.00038	< 0.00038	NA	< 0.00038	NA
Fluoride	mg/L	0.36	0.36	0.22	NA	0.21	NA	0.27	0.28	NA	0.27	NA
Additional Parameters												
Bicarbonate Alkalinity as CaCO3	mg/L	160	166	153	NA	153	NA	156	142	NA	151	NA
Carbonate Alkalinity as CaCO3	mg/L	< 5.0	< 5.0	< 5.0	NA	< 5.0	NA	< 5.0	< 1.9	NA	< 1.9	NA
Total Alkalinity as CaCO3	mg/L	160	166	153	NA	153	NA	156	142	NA	151	NA
Iron	mg/L	6.3	5.8	17.5	17.3	18.9	17.7	14.9	9.9	6.7	13.7	14.4
Magnesium	mg/L	16.4	15.1	18.7	NA	21.0	NA	18.6	19.5	NA	18.5	NA
Manganese	mg/L	3.5 J	3.2	3.4	NA	3.6	NA	3.0	3.4	NA	2.8	NA
Potassium	mg/L	6.0	5.8	5.9	NA	6.4	NA	6.1	5.8	NA	6.1	NA
Sodium	mg/L	8.3	8.2	8.8	NA	9.7	NA	9.6	10.3	NA	11.1	NA
Sulfide	mg/L	< 0.022	< 0.022	< 0.022	NA	< 0.022	NA	< 0.022	< 0.011 H	NA	< 0.011	NA
Supplemental												
Oxidation Reduction Potential, Field	mV	334.98	-50.1	-113.97	-70.38	-102.92	-81.07	-73.89	-69.92	-42.98	-125.1	-125.03
pH, Field	SU	6.93	6.85	6.84	6.95	7.03	6.75	6.99	6.69	6.73	6.87	6.94
Dissolved Oxygen, Field	mg/L	0.16	0.04	0.16	1.7	0.15	1.51	0.05	0.24	0.13	0.19	0.01
Specific Conductance, Field	uS/cm	750.54	731.33	824.67	790.64	734.47	834.47	826.47	783.86	778.06	793.03	795.29
Temperature, Field	deg C	17.89	19.86	19.24	20.85	21.1	21.02	20.59	21.91	19.49	20.83	18.94
Turbidity, Field	NTU	3.82	4.97	0.96	2.96	0.85	1.12	1.7	4.97	4.89	4.2	4.23
Total Iron (Field)	mg/L	5.2	NA	NA	NA	NA	NA	6.0	NA	NA	NA	10
Ferrous Iron (Field)	mg/L	5.2	3.6	NA	NA	NA	NA	6.4	NA	NA	NA	5.0

Table 7B
Summary of 2024 Post-injection Performance Monitoring Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-13 Area										
Sample Location		PT-14	PT-14	PT-14	PT-14	PT-14	PT-14	PT-15	PT-15	PT-15	PT-15	PT-15
Sample Date		11/04/2024	12/02/2024	01/06/2025	02/04/2025	03/05/2025	04/02/2025	08/01/2024	08/09/2024	08/14/2024	08/20/2024	09/04/2024
ANALYTE	UNITS											
APPENDIX III												
Boron	mg/L	0.66	0.74	0.80 J	0.75	0.78	0.81	0.63	0.60	0.63	0.63	0.69
Calcium	mg/L	123	137	125	123	114	111	117	NA	123	NA	107
Chloride	mg/L	15.2	17.8	19.5	20.5	16.4	15.8	14.4	NA	15.7	NA	15.2
Fluoride	mg/L	0.25	0.31	0.34	0.30	0.33	0.32	0.29	NA	0.29	NA	0.36
pH, Field	SU	6.9	7.18	6.9	6.81	7	6.96	6.79	6.91	6.97	6.72	6.82
Sulfate	mg/L	196	184	213	170	163	165	206	NA	212	NA	204
TDS	mg/L	628	560	551	546	510	515	544	NA	548	NA	521
APPENDIX IV												
Antimony	mg/L	< 0.00054	< 0.00038	< 0.00050	< 0.00050	< 0.00050	< 0.00050	< 0.00054	NA	< 0.00054	NA	< 0.00054
Arsenic	mg/L	0.26	0.27	0.26	0.26	0.37	0.42	0.42	0.43	0.42	0.42	0.43
Barium	mg/L	0.045	0.043	0.043	0.043	0.045	0.042	0.042	NA	0.044	NA	0.048
Beryllium	mg/L	< 0.000094	0.000056 J	< 0.00015	< 0.00015	< 0.00015	< 0.00015	< 0.000094	NA	0.000096 J	NA	0.000099 J
Cadmium	mg/L	< 0.00010	< 0.000041	< 0.00012	< 0.00012	< 0.00012	< 0.00012	< 0.00010	NA	< 0.00010	NA	< 0.00010
Chromium	mg/L	< 0.0019	0.00036 J	< 0.0012	< 0.0012	< 0.0012	< 0.0012	< 0.0019	NA	< 0.0019	NA	< 0.0019
Cobalt	mg/L	0.023	0.024	0.023	0.019	0.025	0.022	0.056	NA	0.061	NA	0.079
Lead	mg/L	< 0.00016	0.00015 J	< 0.00025	< 0.00025	< 0.00025	< 0.00025	< 0.00016	NA	< 0.00016	NA	< 0.00016
Lithium	mg/L	0.051	0.054	0.054	0.0528	0.0489	0.0470	0.050	NA	0.052	NA	0.042
Mercury	mg/L	< 0.00013	< 0.00013	< 0.000091	< 0.00012	< 0.000091	< 0.000091	< 0.00013	NA	< 0.00013	NA	< 0.00013
Molybdenum	mg/L	0.016	0.016	0.013	0.015	0.012	0.010	0.013	NA	0.013	NA	0.017
Selenium	mg/L	0.0012 J	0.0010 J	< 0.0012	< 0.0012	< 0.0012	< 0.0012	< 0.00096	NA	< 0.00096	NA	< 0.00096
Thallium	mg/L	< 0.00038	< 0.00020	0.00015 J	< 0.00015	0.00016 J	0.00019 J	< 0.00038	NA	< 0.00038	NA	< 0.00038
Fluoride	mg/L	0.25	0.31	0.34	0.30	0.33	0.32	0.29	NA	0.29	NA	0.36
Additional Parameters												
Bicarbonate Alkalinity as CaCO3	mg/L	148	149	161	170	154	163	129	NA	128	NA	149
Carbonate Alkalinity as CaCO3	mg/L	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	NA	< 5.0	NA	< 5.0
Total Alkalinity as CaCO3	mg/L	148	149	161	170	154	163	129	NA	128	NA	149
Iron	mg/L	13.5	14.2	10.5	11.7	10.7	10.7	13.4	14.5	12.8	13.3	7.4
Magnesium	mg/L	17.6	18.9	16.8	16.8	16.3	14.8	14.5	NA	15.3	NA	13.1
Manganese	mg/L	2.8	2.9	3.2	3.1	3.4 J	3.3	5.4	NA	5.5	NA	4.9
Potassium	mg/L	5.8	6.1	5.7	5.6	6.0	5.7	5.4	NA	5.3	NA	5.0
Sodium	mg/L	8.7	8.0	7.9	8.8	8.4	7.3	7.7	NA	8.1	NA	7.9
Sulfide	mg/L	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	NA	< 0.022	NA	< 0.022
Supplemental												
Oxidation Reduction Potential, Field	mV	-100.01	-85.02	-106.69	-71.64	-78.32	-102.32	-67.75	-77.45	-76.12	-64.13	-95.53
pH, Field	SU	6.9	7.18	6.9	6.81	7	6.96	6.79	6.91	6.97	6.72	6.82
Dissolved Oxygen, Field	mg/L	0.33	0.11	4.01	0.06	1.63	0.11	1.89	0.06	0.39	0.77	0.06
Specific Conductance, Field	uS/cm	769.88	787.18	760.72	790.08	719.2	726.72	705.43	706.7	660.8	740.25	765.04
Temperature, Field	deg C	19.23	18.13	17.13	18.25	17.84	20.72	23.76	20.77	21.85	21.77	20.77
Turbidity, Field	NTU	1.12	4.76	4.85	3.72	3.59	4.58	0.82	1.07	0.97	4.41	4.65
Total Iron (Field)	mg/L	16	5.6	7.0	6.5	7.0	NA	NA	NA	NA	NA	4.5
Ferrous Iron (Field)	mg/L	2.5	5.2	7.0	5.5	3.5	4.4	NA	NA	NA	NA	2.0

Table 7B
Summary of 2024 Post-injection Performance Monitoring Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-13 Area									
Sample Location		PT-15	PT-15	PT-15	PT-15	PT-15	PT-15	PT-15	PT-15	PT-15	PT-15
Sample Date		09/24/2024	10/01/2024	10/08/2024	10/15/2024	11/04/2024	12/02/2024	01/06/2025	02/04/2025	03/05/2025	04/02/2025
ANALYTE	UNITS										
APPENDIX III											
Boron	mg/L	0.64	0.63	0.60	0.62	0.74	0.86	0.90 J	0.80	0.86	0.87
Calcium	mg/L	118	NA	109	NA	119	129	121	117	120	122
Chloride	mg/L	14.5	NA	17.2	NA	16.0	17.4	16.1	17.4	15.2	16.9
Fluoride	mg/L	0.31	NA	0.31	NA	0.28	0.37	0.37	0.32	0.33	0.32
pH, Field	SU	6.73	6.81	6.72	7.04	6.7	6.76	6.76	6.79	6.88	6.78
Sulfate	mg/L	242	NA	245	NA	194	175	187	173	172	170
TDS	mg/L	473	NA	509	NA	543	497	519	515	524	511
APPENDIX IV											
Antimony	mg/L	0.00065 J	NA	0.00061 J	NA	< 0.00054	0.00063 J	< 0.00050	< 0.00050	< 0.00050	< 0.00050
Arsenic	mg/L	0.0097	0.0034 J	0.013	0.022	0.040	0.024	0.053	0.078	0.079	0.088
Barium	mg/L	0.049	NA	0.051	NA	0.051	0.051	0.049	0.052	0.053	0.051
Beryllium	mg/L	< 0.000094	NA	0.00012 J	NA	< 0.000094	0.000062 J	< 0.00015	< 0.00015	< 0.00015	< 0.00015
Cadmium	mg/L	0.00029 J	NA	0.00025 J	NA	0.00034 J	0.00025 J	0.00039 J	0.00031 J	0.00038 J	0.00032 J
Chromium	mg/L	< 0.0019	NA	< 0.0019	NA	< 0.0019	0.00026 J	< 0.0012	< 0.0012	< 0.0012	< 0.0012
Cobalt	mg/L	0.012	NA	0.016	NA	0.019	0.025	0.025	0.026	0.027	0.028
Lead	mg/L	< 0.00016	NA	< 0.00016	NA	< 0.00016	< 0.000076	< 0.00025	< 0.00025	< 0.00025	< 0.00025
Lithium	mg/L	0.040	NA	0.038	NA	0.046	0.041	0.043	0.0421	0.0390	0.0355
Mercury	mg/L	< 0.00013	NA	< 0.00013	NA	< 0.00013	< 0.00013	< 0.000091	< 0.00012	< 0.000091	< 0.000091
Molybdenum	mg/L	0.010	NA	0.011	NA	0.012	0.015	0.014	0.014	0.017	0.012
Selenium	mg/L	0.0038 J	NA	0.0029 J	NA	0.0020 J	0.0017 J	< 0.0012	< 0.0012	< 0.0012	< 0.0012
Thallium	mg/L	0.00044 J	NA	0.00039 J	NA	0.00041 J	0.00044 J	0.00055 J	0.00050 J	0.00063 J	0.00062 J
Fluoride	mg/L	0.31	NA	0.31	NA	0.28	0.37	0.37	0.32	0.33	0.32
Additional Parameters											
Bicarbonate Alkalinity as CaCO3	mg/L	81.7	NA	114	NA	140	141	155	146	153	157
Carbonate Alkalinity as CaCO3	mg/L	< 1.9	NA	< 1.9	NA	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0
Total Alkalinity as CaCO3	mg/L	81.7	NA	114	NA	140	141	155	146	153	157
Iron	mg/L	0.15	0.12	0.95	1.2	1.1	0.38	0.90	2.3	0.65	1.1
Magnesium	mg/L	12.3	NA	13.4	NA	14.2	14.6	14.3	14.6	14.3	13.3
Manganese	mg/L	2.3	NA	2.5	NA	2.9	2.4	4.0	4.1	4.7	4.1
Potassium	mg/L	5.1	NA	5.3	NA	5.3	6.1	5.7	5.4	5.6	5.5
Sodium	mg/L	7.7	NA	9.2	NA	8.8	9.3	7.7	7.4	7.0	7.0
Sulfide	mg/L	< 0.011 H	NA	< 0.011	NA	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022
Supplemental											
Oxidation Reduction Potential, Field	mV	41.74	61.86	13.17	-19.57	-26.73	13.95	-24.43	-47.44	571.81	48.82
pH, Field	SU	6.73	6.81	6.72	7.04	6.7	6.76	6.76	6.79	6.88	6.78
Dissolved Oxygen, Field	mg/L	0.43	0.55	0.91	0.05	0.16	0.32	0.48	0.11	0.22	0.13
Specific Conductance, Field	uS/cm	582.11	771.11	674.38	710.88	724.15	703.58	643.69	748.89	732.7	728.24
Temperature, Field	deg C	20.93	20.64	20.43	19.83	19.69	18.43	16.09	19.68	17.41	19.65
Turbidity, Field	NTU	0.55	4.97	3.69	3.45	0.21	2.7	4.4	2.75	1.38	1.05
Total Iron (Field)	mg/L	NA	NA	NA	1.5	1.5	0.20	1.2	5.5	1.2	NA
Ferrous Iron (Field)	mg/L	NA	NA	NA	1.0	1.5	ND	1.2	2.5	1.0	1.2

Table 7B
Summary of 2024 Post-injection Performance Monitoring Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-8 Area										
Sample Location		PT-09	PT-09	PT-09	PT-09	PT-09	PT-09	PT-09	PT-09	PT-09	PT-09	PT-09
Sample Date		06/26/2024	07/31/2024	08/06/2024	08/12/2024	08/21/2024	09/04/2024	09/25/2024	10/02/2024	10/09/2024	10/16/2024	11/05/2024
ANALYTE	UNITS											
APPENDIX III												
Boron	mg/L	1.5	1.1	1.1	1.2	1.3	1.4	1.2	1.4	1.4	1.3	1.6
Calcium	mg/L	93.2	96.9	NA	92.5	NA	87.9	111	NA	92.4	NA	106
Chloride	mg/L	48.9	29.3	NA	42.3	NA	45.3	39.4	NA	45.9	NA	48.3
Fluoride	mg/L	0.33	0.33	NA	0.35	NA	0.43	0.33	NA	0.39	NA	0.37
pH, Field	SU	6.91	6.9	6.93	7.02	6.83	6.86	6.67	6.81	6.9	6.79	6.79
Sulfate	mg/L	125	172	NA	157	NA	149	236	NA	200	NA	165
TDS	mg/L	469	500	NA	521	NA	486	547	NA	493	NA	563
APPENDIX IV												
Antimony	mg/L	< 0.00054	0.0010 J	NA	< 0.00054	NA	< 0.00054	< 0.00054	NA	< 0.00054	NA	0.00060 J
Arsenic	mg/L	< 0.00084	< 0.00084	NA	< 0.00084	NA	< 0.00084	0.0034 J	NA	< 0.00084	NA	0.0028 J
Barium	mg/L	0.070	0.072	NA	0.066	NA	0.068	0.089	NA	0.073	NA	0.072
Beryllium	mg/L	0.00015 J	0.00013 J	NA	< 0.000094	NA	< 0.000094	< 0.000094	NA	< 0.000094	NA	< 0.000094
Cadmium	mg/L	0.00010 J	0.00028 J	NA	0.00021 J	NA	0.00021 J	0.00030 J	NA	0.00018 J	NA	0.00023 J
Chromium	mg/L	< 0.0019	< 0.0019	NA	< 0.0019	NA	< 0.0019	< 0.0019	NA	< 0.0019	NA	< 0.0019
Cobalt	mg/L	0.0015 J	0.0037 J	NA	0.0033 J	NA	0.0027 J	0.0066	NA	0.0040 J	NA	0.0040 J
Lead	mg/L	0.00033 J	< 0.00016	NA	< 0.00016	NA	< 0.00016	< 0.00016	NA	< 0.00016	NA	< 0.00016
Lithium	mg/L	< 0.0016	0.0019 J	NA	0.0019 J	NA	0.0022 J	0.0035 J	NA	0.0021 J	NA	0.0029 J
Mercury	mg/L	< 0.00013	< 0.00013	NA	< 0.00013	NA	< 0.00013	< 0.00013	NA	< 0.00013	NA	< 0.00013
Molybdenum	mg/L	0.28	0.24	0.24	0.25	0.24	0.26	0.14	0.14	0.18	0.18	0.22
Selenium	mg/L	< 0.00096	< 0.00096	NA	< 0.00096	NA	< 0.00096	< 0.00096	NA	< 0.00096	NA	0.00099 J
Thallium	mg/L	< 0.00038	< 0.00038	NA	< 0.00038	NA	< 0.00038	< 0.00038	NA	< 0.00038	NA	< 0.00038
Fluoride	mg/L	0.33	0.33	NA	0.35	NA	0.43	0.33	NA	0.39	NA	0.37
Additional Parameters												
Bicarbonate Alkalinity as CaCO3	mg/L	117	119	NA	120	NA	121	112	NA	123	NA	122
Carbonate Alkalinity as CaCO3	mg/L	< 5.0	< 5.0	NA	< 5.0	NA	< 5.0	< 1.9	NA	< 1.9	NA	< 5.0
Total Alkalinity as CaCO3	mg/L	117	119	NA	120	NA	121	112	NA	123	NA	122
Iron	mg/L	1.2	0.13	0.31	0.34	0.23	0.31	0.24	0.12	0.073	0.34	0.37
Magnesium	mg/L	17.1	24.5	NA	23.9	NA	24.9	27.2	NA	25.3	NA	25.0
Manganese	mg/L	0.22	0.47	NA	0.36	NA	0.28	0.73	NA	0.58	NA	0.44
Potassium	mg/L	7.2	6.1	NA	6.1	NA	6.1	5.8	NA	6.0	NA	6.4
Sodium	mg/L	12.1	6.6	NA	7.8	NA	8.9	7.0	NA	9.5	NA	9.7
Sulfide	mg/L	< 0.022	< 0.022	NA	< 0.022	NA	< 0.022	< 0.011 H	NA	< 0.011	NA	< 0.022
Supplemental												
Oxidation Reduction Potential, Field	mV	29.99	113.75	36.62	53.69	107.95	39.09	45.21	447.23	100.9	39.18	74.25
pH, Field	SU	6.91	6.9	6.93	7.02	6.83	6.86	6.67	6.81	6.9	6.79	6.79
Dissolved Oxygen, Field	mg/L	0.16	0.54	0.22	0.04	0.3	0.01	0.83	0.05	0.04	0.04	0.15
Specific Conductance, Field	uS/cm	673.97	699.07	660	601.6	665.92	634.71	737.13	696.66	722.62	759.06	756.7
Temperature, Field	deg C	20.57	19.5	22.69	22.39	23.47	21.70	20.24	21.11	21.43	19.06	20.16
Turbidity, Field	NTU	9.9	3.03	4.97	4.48	4.84	4.74	4.9	3.87	3.46	4.92	3.78
Total Iron (Field)	mg/L	NA	NA	NA	NA	NA	3.5	NA	NA	NA	ND	ND
Ferrous Iron (Field)	mg/L	NA	NA	NA	NA	NA	3.0	NA	NA	NA	ND	ND

Table 7B
Summary of 2024 Post-injection Performance Monitoring Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-8 Area										
Sample Location		PT-09	PT-09	PT-09	PT-09	PT-09	PT-10	PT-10	PT-10	PT-10	PT-10	PT-10
Sample Date		12/03/2024	01/07/2025	02/05/2025	03/06/2025	04/03/2025	06/26/2024	07/31/2024	08/01/2024	08/05/2024	08/09/2024	08/13/2024
ANALYTE	UNITS											
APPENDIX III												
Boron	mg/L	1.6	1.8	1.6	1.8	1.8	1.4	1.6	NA	0.015 J	NA	1.7
Calcium	mg/L	116	90.2	89.3	98.6	102	104	102	NA	NA	NA	107
Chloride	mg/L	48.3	50.2	50.4	57.6	56.9	47.2	46.4	NA	NA	NA	47.5
Fluoride	mg/L	0.40	0.37	0.37	0.31	0.30	0.22	0.22	NA	NA	NA	0.25
pH, Field	SU	7.09	6.94	6.68	6.81	6.78	6.88	NA	6.85	NA	6.87	7.05
Sulfate	mg/L	157	127	111	128	122	135	117	NA	NA	NA	122
TDS	mg/L	521	490	422	488	516	480	535	NA	NA	NA	449
APPENDIX IV												
Antimony	mg/L	< 0.00038	< 0.00050	< 0.00050	< 0.00050	< 0.00050	< 0.00054	< 0.00054	NA	NA	NA	0.0010 J
Arsenic	mg/L	0.0020 J	< 0.0012	< 0.0012	< 0.0012	< 0.0012	< 0.00084	< 0.00084	NA	NA	NA	< 0.00084
Barium	mg/L	0.066	0.065	0.060	0.068	0.064	0.050	0.046	NA	NA	NA	0.049
Beryllium	mg/L	0.000030 J	< 0.00015	< 0.00015	< 0.00015	< 0.00015	< 0.000094	< 0.000094	NA	NA	NA	< 0.000094
Cadmium	mg/L	0.00024 J	0.00013 J	< 0.00012	0.00013 J	< 0.00012	< 0.00010	0.00012 J	NA	NA	NA	0.00013 J
Chromium	mg/L	0.00037 J	< 0.0012	< 0.0012	< 0.0012	< 0.0012	< 0.0019	< 0.0019	NA	NA	NA	< 0.0019
Cobalt	mg/L	0.0028 J	0.0023 J	0.0022 J	0.0022 J	0.0015 J	0.0015 J	0.0015 J	NA	NA	NA	0.0016 J
Lead	mg/L	< 0.000076	< 0.00025	< 0.00025	< 0.00025	< 0.00025	< 0.00016	< 0.00016	NA	NA	NA	< 0.00016
Lithium	mg/L	0.0025 J	0.0021 J	0.00155 J	0.00101 J	0.00124 J	< 0.0016	< 0.0016	NA	NA	NA	< 0.0016
Mercury	mg/L	< 0.00013	< 0.000091	< 0.00012	< 0.000091	< 0.000091	< 0.00013	< 0.00013	NA	NA	NA	< 0.00013
Molybdenum	mg/L	0.25	0.19	0.23	0.17	0.16	0.13	0.15	NA	< 0.00062	NA	0.17
Selenium	mg/L	0.00096 J	< 0.0012	< 0.0012	< 0.0012	< 0.0012	< 0.00096	< 0.00096	NA	NA	NA	< 0.00096
Thallium	mg/L	< 0.00020	0.00019 J	< 0.00015	0.00017 J	0.00017 J	< 0.00038	< 0.00038	NA	NA	NA	< 0.00038
Fluoride	mg/L	0.40	0.37	0.37	0.31	0.30	0.22	0.22	NA	NA	NA	0.25
Additional Parameters												
Bicarbonate Alkalinity as CaCO3	mg/L	121	131	131	130	126	121	133	NA	NA	NA	133
Carbonate Alkalinity as CaCO3	mg/L	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	NA	NA	NA	< 5.0
Total Alkalinity as CaCO3	mg/L	121	131	131	130	126	121	133	NA	NA	NA	133
Iron	mg/L	0.049	0.26	1.0	0.55	0.061	0.13	< 0.025	NA	0.11	NA	0.31
Magnesium	mg/L	23.1	20.7	20.6	20.3	17.1	14.1	13.7	NA	NA	NA	14.4
Manganese	mg/L	0.37	0.36 J	0.33	0.44	0.36 J	0.54	0.48	NA	NA	NA	0.50
Potassium	mg/L	6.9	6.7	6.2	7.1	6.3	7.2	6.7	NA	NA	NA	7.2
Sodium	mg/L	10.1	14.1	12.3	14.4	12.1	9.6	8.8	NA	NA	NA	9.1
Sulfide	mg/L	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	NA	NA	NA	< 0.022
Supplemental												
Oxidation Reduction Potential, Field	mV	40.04	33.41	79.84	406.97	55.27	37.29	NA	124.56	NA	33.6	44
pH, Field	SU	7.09	6.94	6.68	6.81	6.78	6.88	NA	6.85	NA	6.87	7.05
Dissolved Oxygen, Field	mg/L	0.69	0.13	0.1	0.1	0.05	0.06	NA	1.15	NA	0.11	0.04
Specific Conductance, Field	uS/cm	730.13	641.49	693.51	733.89	716.18	700.17	NA	667.61	NA	644.85	579.22
Temperature, Field	deg C	17.31	15.9	18.52	16.48	20.38	22.57	NA	17.27	NA	22.38	22.14
Turbidity, Field	NTU	1.41	4.93	4.62	4.73	4.85	2.14	NA	1.34	NA	3.87	4.87
Total Iron (Field)	mg/L	ND	0.20	ND	0.75	NA	NA	NA	NA	NA	NA	NA
Ferrous Iron (Field)	mg/L	ND	ND	ND	0.75	ND	NA	NA	NA	NA	NA	NA

Table 7B
Summary of 2024 Post-injection Performance Monitoring Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-8 Area										
Sample Location		PT-10	PT-10	PT-10	PT-10	PT-10	PT-10	PT-10	PT-10	PT-10	PT-10	PT-10
Sample Date		08/20/2024	09/04/2024	09/25/2024	10/02/2024	10/09/2024	10/16/2024	11/05/2024	12/03/2024	01/07/2025	02/05/2025	03/06/2025
ANALYTE	UNITS											
APPENDIX III												
Boron	mg/L	1.7	1.6	1.6	1.7	1.6	1.5	1.7	1.7	1.6	1.5	1.4
Calcium	mg/L	NA	99.0	113	NA	109	NA	107	114	93.1	98.1	96.7
Chloride	mg/L	NA	46.2	49.6	NA	50.0	NA	45.1	46.1	50.4	46.3	48.4
Fluoride	mg/L	NA	0.28	0.32	NA	0.29	NA	0.27	0.27	0.20	0.19	0.19
pH, Field	SU	6.86	6.96	6.69	6.99	7.01	8.15	6.9	6.83	6.6	6.66	6.71
Sulfate	mg/L	NA	118	158	NA	165	NA	129	130	112	110	114
TDS	mg/L	NA	473	521	NA	484	NA	527	470	414	401	455
APPENDIX IV												
Antimony	mg/L	NA	< 0.00054	< 0.00054	NA	< 0.00054	NA	< 0.00054	< 0.00038	< 0.00050	< 0.00050	< 0.00050
Arsenic	mg/L	NA	< 0.00084	0.0024 J	NA	< 0.00084	NA	0.0021 J	< 0.0016	< 0.0012	< 0.0012	< 0.0012
Barium	mg/L	NA	0.047	0.053	NA	0.054	NA	0.050	0.047	0.048	0.046	0.051
Beryllium	mg/L	NA	< 0.000094	< 0.000094	NA	< 0.000094	NA	< 0.000094	< 0.000026	< 0.00015	< 0.00015	< 0.00015
Cadmium	mg/L	NA	0.00011 J	0.00017 J	NA	< 0.00010	NA	0.00013 J	0.00015 J	< 0.00012	< 0.00012	< 0.00012
Chromium	mg/L	NA	< 0.0019	0.0039 J	NA	< 0.0019	NA	< 0.0019	0.00025 J	< 0.0012	< 0.0012	< 0.0012
Cobalt	mg/L	NA	0.0015 J	0.0019 J	NA	0.0013 J	NA	0.0014 J	0.0015 J	0.0013 J	0.0014 J	0.0013 J
Lead	mg/L	NA	< 0.00016	< 0.00016	NA	< 0.00016	NA	< 0.00016	< 0.000076	< 0.00025	< 0.00025	< 0.00025
Lithium	mg/L	NA	< 0.0016	< 0.0016	NA	< 0.0016	NA	< 0.0016	0.0010 J	0.00058 J	0.000905 J	0.00111 J
Mercury	mg/L	NA	< 0.00013	< 0.00013	NA	< 0.00013	NA	< 0.00013	< 0.00013	< 0.000091	< 0.00012	< 0.000091
Molybdenum	mg/L	0.16	0.18	0.23	0.16	0.18	0.16	0.21	0.18	0.043	0.079	0.052
Selenium	mg/L	NA	< 0.00096	< 0.00096	NA	< 0.00096	NA	0.0011 J	0.00095 J	< 0.0012	< 0.0012	< 0.0012
Thallium	mg/L	NA	< 0.00038	< 0.00038	NA	< 0.00038	NA	< 0.00038	< 0.00020	< 0.00015	< 0.00015	< 0.00015
Fluoride	mg/L	NA	0.28	0.32	NA	0.29	NA	0.27	0.27	0.20	0.19	0.19
Additional Parameters												
Bicarbonate Alkalinity as CaCO3	mg/L	NA	130	131	NA	141	NA	132	118	105	114	115
Carbonate Alkalinity as CaCO3	mg/L	NA	< 5.0	< 1.9	NA	< 1.9	NA	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0
Total Alkalinity as CaCO3	mg/L	NA	130	131	NA	141	NA	132	118	105	114	115
Iron	mg/L	0.18	0.077	0.060	0.17	0.12	0.51	0.033 J	< 0.025	0.19	1.0	0.17
Magnesium	mg/L	NA	13.1	14.2	NA	14.1	NA	13.9	13.8	12.3	12.9	12.5
Manganese	mg/L	NA	0.42	0.43	NA	0.60	NA	0.40	0.37	0.42 J	0.43	0.55
Potassium	mg/L	NA	6.8	6.6	NA	7.0	NA	6.9	7.1	7.1	6.6	6.9
Sodium	mg/L	NA	8.7	9.0	NA	9.1	NA	9.2	8.8	10.3	9.1	9.8
Sulfide	mg/L	NA	< 0.022	< 0.011 H	NA	< 0.011	NA	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022
Supplemental												
Oxidation Reduction Potential, Field	mV	149.87	410.18	51.4	-6.23	-19.44	-103.72	126.05	57.02	12.01	13.17	1.52
pH, Field	SU	6.86	6.96	6.69	6.99	7.01	8.15	6.9	6.83	6.6	6.66	6.71
Dissolved Oxygen, Field	mg/L	0.48	0.42	0.38	0.28	0.24	0.12	0.09	0.15	0.07	0.24	0.43
Specific Conductance, Field	uS/cm	664.93	662.09	661.53	674.4	679.88	708.42	677.87	678.04	546.13	623.67	672.95
Temperature, Field	deg C	22.76	22	19.71	21.62	20.49	17.85	19.54	18.32	15.87	17.9	15.74
Turbidity, Field	NTU	4.27	1.36	3.46	2.31	0.24	4.53	1.92	0.94	2.65	1.49	0.78
Total Iron (Field)	mg/L	NA	ND	NA	NA	NA	0.50	ND	ND	ND	1.0	ND
Ferrous Iron (Field)	mg/L	NA	ND	NA	NA	NA	0.25	ND	ND	ND	ND	ND

Table 7B
Summary of 2024 Post-injection Performance Monitoring Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-8 Area									
Sample Location		PT-10	PT-11	PT-11	PT-11	PT-11	PT-11	PT-11	PT-11	PT-11	PT-11
Sample Date		04/03/2025	08/07/2024	08/12/2024	08/21/2024	09/04/2024	09/25/2024	10/02/2024	10/09/2024	10/16/2024	11/05/2024
ANALYTE	UNITS										
APPENDIX III											
Boron	mg/L	1.7	1.3	1.5	1.5	1.4	1.5	1.3	1.5	1.3	1.6
Calcium	mg/L	124	NA	96.7	NA	94.9	109	NA	91.9	NA	112
Chloride	mg/L	54.3	NA	41.7	NA	46.1	48.3	NA	37.6	NA	46.9
Fluoride	mg/L	0.15	NA	0.32	NA	0.43	0.33	NA	0.32	NA	0.31
pH, Field	SU	6.82	6.79	6.97	6.82	6.95	6.63	6.64	6.64	6.57	6.8
Sulfate	mg/L	138	NA	139	NA	139	200	NA	211	NA	156
TDS	mg/L	532	NA	456	NA	483	546	NA	496	NA	563
APPENDIX IV											
Antimony	mg/L	< 0.00050	NA	< 0.00054	NA	< 0.00054	< 0.00054	NA	< 0.00054	NA	< 0.00054
Arsenic	mg/L	< 0.0012	NA	< 0.00084	NA	0.00087 J	0.0031 J	NA	0.0014 J	NA	0.0030 J
Barium	mg/L	0.056	NA	0.072	NA	0.070	0.078	NA	0.067	NA	0.074
Beryllium	mg/L	< 0.00015	NA	< 0.000094	NA	< 0.000094	< 0.000094	NA	< 0.000094	NA	< 0.000094
Cadmium	mg/L	< 0.00012	NA	0.00022 J	NA	0.00017 J	0.00030 J	NA	0.00017 J	NA	0.00018 J
Chromium	mg/L	< 0.0012	NA	< 0.0019	NA	< 0.0019	< 0.0019	NA	< 0.0019	NA	< 0.0019
Cobalt	mg/L	< 0.0012	NA	0.015	NA	0.0066	0.025	NA	0.015	NA	0.0079
Lead	mg/L	< 0.00025	NA	< 0.00016	NA	< 0.00016	< 0.00016	NA	< 0.00016	NA	< 0.00016
Lithium	mg/L	0.00160 J	NA	0.0059 J	NA	0.0039 J	0.0067 J	NA	0.0057 J	NA	0.0046 J
Mercury	mg/L	< 0.000091	NA	< 0.00013	NA	< 0.00013	< 0.00013	NA	< 0.00013	NA	< 0.00013
Molybdenum	mg/L	0.040	0.086	0.10	0.12	0.14	0.074	0.069	0.066	0.062	0.11
Selenium	mg/L	< 0.0012	NA	< 0.00096	NA	< 0.00096	< 0.00096	NA	< 0.00096	NA	< 0.00096
Thallium	mg/L	< 0.00015	NA	< 0.00038	NA	< 0.00038	< 0.00038	NA	< 0.00038	NA	< 0.00038
Fluoride	mg/L	0.15	NA	0.32	NA	0.43	0.33	NA	0.32	NA	0.31
Additional Parameters											
Bicarbonate Alkalinity as CaCO3	mg/L	134	NA	126	NA	133	98.0	NA	108	NA	128
Carbonate Alkalinity as CaCO3	mg/L	< 5.0	NA	< 5.0	NA	< 5.0	< 1.9	NA	< 1.9	NA	< 5.0
Total Alkalinity as CaCO3	mg/L	134	NA	126	NA	133	98.0	NA	108	NA	128
Iron	mg/L	0.18	0.36	0.25	0.10	0.41	3.7	1.8	0.24	0.82	0.19
Magnesium	mg/L	12.3	NA	20.6	NA	17.8	20.3	NA	21.6	NA	19.1
Manganese	mg/L	0.71	NA	1.0	NA	0.59	1.4	NA	1.1	NA	0.66
Potassium	mg/L	6.8	NA	6.1	NA	6.1	5.6	NA	5.7	NA	6.3
Sodium	mg/L	9.1	NA	8.5	NA	8.6	8.1	NA	7.8	NA	9.1
Sulfide	mg/L	< 0.022	NA	< 0.022	NA	< 0.022	< 0.011 H	NA	< 0.011	NA	< 0.022
Supplemental											
Oxidation Reduction Potential, Field	mV	139.02	30.21	55.49	112.47	55.38	-13.49	406.71	21.8	21.06	59.93
pH, Field	SU	6.82	6.79	6.97	6.82	6.95	6.63	6.64	6.64	6.57	6.8
Dissolved Oxygen, Field	mg/L	0.11	0.06	0.07	0.12	0	0.07	0.06	0.16	0.08	0.14
Specific Conductance, Field	uS/cm	767.32	642.12	586.44	660.19	619.84	676.04	658.94	664.68	735.6	735.89
Temperature, Field	deg C	20.49	21.8	21.66	21.37	21.51	20.04	21.2	20.48	18.96	19.82
Turbidity, Field	NTU	0.49	4.9	4.4	4.4	4.82	4.97	4.7	1.23	4.84	1.79
Total Iron (Field)	mg/L	NA	NA	NA	NA	0.30	NA	NA	NA	1.0	ND
Ferrous Iron (Field)	mg/L	ND	NA	NA	NA	ND	NA	NA	NA	0.5	ND



Table 7B
Summary of 2024 Post-injection Performance Monitoring Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-8 Area									
Sample Location		PT-11	PT-11	PT-11	PT-11	PT-11	PT-12	PT-12	PT-12	PT-12	PT-12
Sample Date		12/03/2024	01/07/2025	02/05/2025	03/06/2025	04/03/2025	08/06/2024	08/13/2024	08/21/2024	09/04/2024	09/25/2024
ANALYTE	UNITS										
APPENDIX III											
Boron	mg/L	1.6	1.7	1.5	1.6	1.5	1.1	1.1	1.2	1.0	0.81
Calcium	mg/L	120	88.8	95.8	89.2	97.3	NA	98.4	NA	90.2	106
Chloride	mg/L	44.0	34.5	37.7	34.7	39.0	NA	31.7	NA	28.7	22.9
Fluoride	mg/L	0.31	0.28	0.27	0.29	0.28	NA	0.32	NA	0.38	0.27
pH, Field	SU	7.08	6.87	6.65	6.86	6.75	6.87	7.04	6.84	6.88	6.51
Sulfate	mg/L	139	103	96.4	94.7	105	NA	178	NA	187	266
TDS	mg/L	486	424	400	420	460	NA	546	NA	500	573
APPENDIX IV											
Antimony	mg/L	< 0.00038	< 0.00050	< 0.00050	< 0.00050	< 0.00050	NA	< 0.00054	NA	< 0.00054	< 0.00054
Arsenic	mg/L	< 0.0016	< 0.0012	< 0.0012	< 0.0012	< 0.0012	NA	0.00089 J	NA	0.0017 J	0.0031 J
Barium	mg/L	0.067	0.060	0.062	0.066	0.063	NA	0.070	NA	0.068	0.087
Beryllium	mg/L	< 0.000026	< 0.00015	< 0.00015	< 0.00015	< 0.00015	NA	< 0.000094	NA	< 0.000094	< 0.000094
Cadmium	mg/L	0.00015 J	< 0.00012	< 0.00012	< 0.00012	< 0.00012	NA	0.00024 J	NA	0.00024 J	0.00055
Chromium	mg/L	0.00045 J	< 0.0012	< 0.0012	< 0.0012	< 0.0012	NA	< 0.0019	NA	< 0.0019	< 0.0019
Cobalt	mg/L	0.0044 J	0.0017 J	0.0024 J	0.0019 J	0.0014 J	NA	0.0022 J	NA	0.0028 J	0.011
Lead	mg/L	< 0.000076	< 0.00025	< 0.00025	< 0.00025	< 0.00025	NA	< 0.00016	NA	< 0.00016	< 0.00016
Lithium	mg/L	0.0027 J	0.0010 J	0.00159 J	0.00117 J	0.00125 J	NA	0.0025 J	NA	0.0020 J	0.0044 J
Mercury	mg/L	< 0.00013	< 0.000091	< 0.00012	< 0.000091	< 0.000091	NA	< 0.00013	NA	< 0.00013	< 0.00013
Molybdenum	mg/L	0.12	0.12	0.11	0.13	0.12	0.20	0.23	0.21	0.19	0.088
Selenium	mg/L	0.00092 J	< 0.0012	< 0.0012	< 0.0012	< 0.0012	NA	< 0.00096	NA	< 0.00096	< 0.00096
Thallium	mg/L	< 0.00020	< 0.00015	< 0.00015	< 0.00015	< 0.00015	NA	< 0.00038	NA	< 0.00038	< 0.00038
Fluoride	mg/L	0.31	0.28	0.27	0.29	0.28	NA	0.32	NA	0.38	0.27
Additional Parameters											
Bicarbonate Alkalinity as CaCO3	mg/L	122	121	121	117	121	NA	128	NA	124	90.2
Carbonate Alkalinity as CaCO3	mg/L	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	NA	< 5.0	NA	< 5.0	< 1.9
Total Alkalinity as CaCO3	mg/L	122	121	121	117	121	NA	128	NA	124	90.2
Iron	mg/L	0.17	0.014 J	0.89	0.41	0.48	0.33	0.082	0.078	0.14	0.21
Magnesium	mg/L	16.9	12.8	13.8	16.0	15.0	NA	24.5	NA	26.4	30.0
Manganese	mg/L	0.45	0.33 J	0.35	0.41	0.35 J	NA	0.62	NA	0.77	2.6
Potassium	mg/L	7.2	6.7	6.3	6.7	5.9	NA	5.8	NA	5.5	5.1
Sodium	mg/L	9.5	8.9	8.5	9.0	8.3	NA	6.6	NA	6.7	6.1
Sulfide	mg/L	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	NA	< 0.022	NA	< 0.022	< 0.011
Supplemental											
Oxidation Reduction Potential, Field	mV	28.87	35.71	80.6	449.53	54.25	34.9	51.29	63.32	37.07	76.57
pH, Field	SU	7.08	6.87	6.65	6.86	6.75	6.87	7.04	6.84	6.88	6.51
Dissolved Oxygen, Field	mg/L	0.11	0.09	0.1	0.12	0.09	0.07	0.02	0.06	0.01	0.86
Specific Conductance, Field	uS/cm	710	559.68	630.82	633.63	655.81	676.48	606.97	700.15	669.56	709.24
Temperature, Field	deg C	17	15.26	17.91	17.06	19.89	23.48	21.23	22.22	21.94	19.99
Turbidity, Field	NTU	0.7	0.35	2.26	4.2	4.32	4.98	4.38	2.92	4.42	4.72
Total Iron (Field)	mg/L	NA	ND	0.50	ND	NA	NA	NA	NA	ND	NA
Ferrous Iron (Field)	mg/L	NA	ND	0.50	ND	ND	NA	NA	NA	ND	NA

Table 7B
Summary of 2024 Post-injection Performance Monitoring Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area		HGWC-8 Area								
Sample Location		PT-12	PT-12	PT-12	PT-12	PT-12	PT-12	PT-12	PT-12	PT-12
Sample Date		10/02/2024	10/09/2024	10/16/2024	11/05/2024	12/03/2024	01/07/2025	02/05/2025	03/06/2025	04/03/2025
ANALYTE	UNITS									
APPENDIX III										
Boron	mg/L	1.3	1.3	1.2	1.1	1.6	1.8	1.6	1.7	1.7
Calcium	mg/L	NA	87.3	NA	98.0	105	90.2	91.4	92.3	100
Chloride	mg/L	NA	41.9	NA	32.2	44.2	55.0	44.0	49.4	52.4
Fluoride	mg/L	NA	0.32	NA	0.26	0.30	0.27	0.25	0.23	0.22
pH, Field	SU	6.71	6.79	9.50	6.61	6.65	6.62	6.53	6.47	6.43
Sulfate	mg/L	NA	203	NA	204	179	130	114	111	115
TDS	mg/L	NA	485	NA	549	526	506	416	445	431
APPENDIX IV										
Antimony	mg/L	NA	0.0022 J	NA	< 0.00054	< 0.00038	< 0.00050	< 0.00050	< 0.00050	< 0.00050
Arsenic	mg/L	NA	0.0015 J	NA	0.0046 J	0.0027 J	< 0.0012	< 0.0012	< 0.0012	< 0.0012
Barium	mg/L	NA	0.071	NA	0.074	0.062	0.057	0.055	0.056	0.054
Beryllium	mg/L	NA	< 0.000094	NA	< 0.000094	0.000057 J	< 0.00015	< 0.00015	< 0.00015	< 0.00015
Cadmium	mg/L	NA	0.00031 J	NA	0.00037 J	0.00028 J	0.00013 J	0.00015 J	0.00014 J	0.00013 J
Chromium	mg/L	NA	< 0.0019	NA	< 0.0019	0.00067 J	< 0.0012	< 0.0012	< 0.0012	< 0.0012
Cobalt	mg/L	NA	0.0044 J	NA	0.0053	0.0035 J	0.0019 J	0.0023 J	0.0020 J	0.0017 J
Lead	mg/L	NA	0.00074 J	NA	< 0.00016	0.000093 J	< 0.00025	< 0.00025	< 0.00025	< 0.00025
Lithium	mg/L	NA	0.0029 J	NA	0.0037 J	0.0023 J	0.00095 J	0.00122 J	0.000922 J	0.00110 J
Mercury	mg/L	NA	< 0.00013	NA	< 0.00013	< 0.00013	< 0.000091	< 0.00012	< 0.000091	< 0.000091
Molybdenum	mg/L	0.14	0.18	0.16	0.12	0.16	0.13	0.16	0.13	0.11
Selenium	mg/L	NA	< 0.00096	NA	< 0.00096	< 0.00092	< 0.0012	< 0.0012	< 0.0012	< 0.0012
Thallium	mg/L	NA	< 0.00038	NA	< 0.00038	< 0.00020	0.00017 J	< 0.00015	0.00016 J	0.00016 J
Fluoride	mg/L	NA	0.32	NA	0.26	0.30	0.27	0.25	0.23	0.22
Additional Parameters										
Bicarbonate Alkalinity as CaCO3	mg/L	NA	113	NA	107	116	126	120	116	115
Carbonate Alkalinity as CaCO3	mg/L	NA	< 1.9	NA	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0
Total Alkalinity as CaCO3	mg/L	NA	113	NA	107	116	126	120	116	115
Iron	mg/L	0.043 J	0.091	0.48	0.14	0.33	0.11	1.4	0.25	0.26
Magnesium	mg/L	NA	24.8	NA	31.4	28.7	17.8	19.1	16.9	14.9
Manganese	mg/L	NA	1.1	NA	1.4	0.86	0.41 J	0.44	0.43	0.41
Potassium	mg/L	NA	5.6	NA	5.4	6.1	6.5	6.0	6.7	6.0
Sodium	mg/L	NA	7.8	NA	7.6	10.9	12.8	11.0	10.8	10.2
Sulfide	mg/L	NA	< 0.011	NA	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022
Supplemental										
Oxidation Reduction Potential, Field	mV	75.58	92.77	4.4	94.28	68.68	57.17	55.94	431.41	485.45
pH, Field	SU	6.71	6.79	9.50	6.61	6.65	6.62	6.53	6.47	6.43
Dissolved Oxygen, Field	mg/L	2.21	0.07	0.05	0.08	0.18	0.09	0.09	0.11	0.11
Specific Conductance, Field	uS/cm	674.5	691.29	715.28	717.5	741.65	649.55	651.97	660.11	681.72
Temperature, Field	deg C	20.84	20.81	19.15	20.15	17.5	15.86	18.97	17.28	20.21
Turbidity, Field	NTU	2.93	4.65	6.8	3.23	3.47	4.9	3.89	4.71	2.97
Total Iron (Field)	mg/L	NA	NA	ND	ND	ND	0.20	4.0	ND	NA
Ferrous Iron (Field)	mg/L	NA	NA	ND	ND	ND	ND	ND	ND	ND

FIGURES



- LEGEND**
- Detection Monitoring Well
 - Horizontal Assessment Monitoring Well
 - Vertical Assessment Monitoring Well
 - Piezometer (see Note 1)
 - Surface Water Level Gauge Point
 - Injection Point
 - Approximate Groundwater Flow Direction
 - Approximate AP-1 Boundary
 - Plant Hammond Property Boundary

Notes:
1. Piezometers PT-07, PT-08, PT-09, PT-10, MW-53 and MW-54 were installed in support of an Assessment of Corrective Measures pre-design investigation and are not included in the monitoring well network.
2. Aerial photograph source: Google Earth Pro, August 2019 and Georgia Power Company, January 2024 and January 2025.


0 150 300 600
SCALE IN FEET

PILOT STUDY DPT INJECTION AND PERFORMANCE MONITORING WELL LOCATIONS
GEORGIA POWER COMPANY
PLANT HAMMOND AP-1
ROME, FLOYD COUNTY, GEORGIA

Prepared For: Georgia Power
Prepared By: Geosyntec consultants

KENNESAW, GA AUGUST 2025

FIGURE
1



- LEGEND**
- Detection Monitoring Well
 - Horizontal Assessment Monitoring Well
 - Vertical Assessment Monitoring Well
 - Piezometer (see Note 1 and 2)
 - Surface Water Level Gauge Point
 - Distance Between Well (in feet)
 - Approximate Groundwater Flow Direction
 - Approximate AP-1 Boundary
 - Plant Hammond Property Boundary

Notes:

1. Piezometers AS-01, AS-02, AS-03, AS-04, INW-03, INW-04, INW-05, PT-07, PT-08, PT-09, PT-10, PT-11, PT-12, PT-13, PT-14, PT-15, MW-53 and MW-54 were installed in support of an Assessment of Corrective Measures pre-design investigation and are not included in the monitoring well network.

2. INW-03, INW-04, and INW-05 are temporary pilot study injection wells. AS-01, AS-02, AS-03, and AS-04 are temporary pilot study air sparge wells.

3. Aerial photograph source: Google Earth Pro, August 2019 and Georgia Power Company, January 2024 and January 2025.

0 150 300 600
SCALE IN FEET


**PILOT STUDY INJECTION AND
PERFORMANCE MONITORING
WELL LOCATIONS**
GEORGIA POWER COMPANY
PLANT HAMMOND AP-1
ROME, FLOYD COUNTY, GEORGIA

Prepared For: Georgia Power

Prepared By: Geosyntec
consultants

KENNESAW, GA AUGUST 2025

**FIGURE
2**



Notes:

1. mg/L = milligrams per liter; g/L = grams per liter.
2. The Groundwater Protection Standard (GWPS) for molybdenum is 0.1 mg/L.

FIGURE 3 – HGWC-8 AREA – MOLYBDENUM TIME SERIES

GEORGIA POWER COMPANY
PLANT HAMMOND AP-1
ROME, FLOYD COUNTY, GEORGIA

PREPARED FOR:




PREPARED BY:



KENNESAW, GA

AUGUST 2025



Notes:

1. mg/L = milligrams per liter; g/L = grams per liter.
2. The Groundwater Protection Standard (GWPS) for arsenic is 0.01 mg/L.

FIGURE 4 – HGWC-13 AREA – ARSENIC TIME SERIES
GEORGIA POWER COMPANY
PLANT HAMMOND AP-1
ROME, FLOYD COUNTY, GEORGIA

PREPARED FOR:



PREPARED BY:



KENNESAW, GA

AUGUST 2025

APPENDIX A

2023 and 2024 Pilot Study Post-Injection Event Report, Plant Hammond Ash Pond 1

2023 Pilot Study Post- Injection Event Report, Plant Hammond Ash Pond 1



Prepared for

Georgia Power Company

241 Ralph McGill Blvd NE

Atlanta, Georgia 30308

PILOT STUDY POST-INJECTION EVENT REPORT

**PILOT TEST NO. UPT000062
PLANT HAMMOND ASH POND 1 (AP-1)**

Prepared by

Geosyntec 
consultants

engineers | scientists | innovators

1255 Roberts Boulevard, Suite 200
Kennesaw, Georgia 30144

Project Number GW6581G

November 2023

CERTIFICATION STATEMENT

I hereby certify that this *Pilot Study Post-Injection Event Report* was prepared by, or under the direct supervision of, a Qualified Groundwater Scientist, in accordance with the Georgia Environmental Protection Division Rules of Solid Waste Management. According to 391-3-4-.01, a Qualified Groundwater Scientist is “a professional engineer or geologist registered to practice in Georgia who has received a baccalaureate or post-graduate degree in the natural sciences or engineering and has sufficient training and experience in groundwater hydrology and related fields that enable individuals to make sound professional judgments regarding groundwater monitoring, contaminant fate and transport, and corrective action.” The design presented within this workplan was developed in compliance with the Georgia Rules of Solid Waste Management, Chapter 391-3-4.10.



Whitney B. Law
Georgia Professional Engineer No. 36641

November 7, 2023
Date

TABLE OF CONTENTS

1.	BACKGROUND AND OBJECTIVES	1
1.1	Site Background	1
2.	WELL INSTALLATION	3
3.	BASELINE CHARACTERIZATION.....	4
4.	INJECTION ACTIVITIES	5
4.1	HGWC-8 Injection Area (East Area)	5
4.2	HGWC-13 Injection Area (Southwest Area).....	6
5.	POST-INJECTION PERFORMANCE MONITORING AND REPORTING	8
6.	REFERENCES	9

LIST OF TABLES

Table 1	Summary of Well Construction Details
Table 2	Summary of Baseline Groundwater Analytical Data
Table 3	Summary of Daily Injection Volumes

LIST OF FIGURES

Figure 1	Site Location Map
Figure 2	Pilot Study Injection Point and Performance Monitoring Well Locations

LIST OF APPENDICES

Appendix A	Well Design, Installation, and Development Report – Addendum No. 5
Appendix B	Baseline Analytical Laboratory Results and Field Sampling Forms
Appendix C	Injection Field Forms

LIST OF ACRONYMS

ACM	Assessment of Corrective Measures
AP-1	Ash Pond 1
bgs	below ground surface
Cascade	Cascade Drilling, Inc.
CCR	coal combustion residual
CFR	Code of Federal Regulations
Co	cobalt
DO	dissolved oxygen
DPT	direct push technology
FeSO ₄	ferrous sulfate
ft	feet
gal	gallons
gpd	gallons per day
gpm	gallons per minute
GA EPD	Georgia Environmental Protection Division
Georgia Power	Georgia Power Company
Geosyntec	Geosyntec Consultants, Inc.
GWPS	Groundwater Protection Standard
IBC	intermediate bulk container
lb	pound
MNA	monitored natural attenuation
mg/L	milligrams per liter
MgO	magnesium oxide
ORP	oxidation-reduction potential
psi	pounds per square inch
PVC	polyvinyl chloride
ROI	radius of influence
SSL	statistically significant level
UIC	Underground Injection Control
US EPA	United States Environmental Protection Agency

1. BACKGROUND AND OBJECTIVES

On behalf of Georgia Power Company (Georgia Power), this *Pilot Study Post-Injection Event Report* (Report) was developed by Geosyntec Consultants, Inc. (Geosyntec) at the request of the Georgia Environmental Protection Division (GA EPD) Wastewater Regulatory Program in their pilot test notification approval, dated August 24, 2023. In-situ geochemical injections, coupled with monitored natural attenuation (MNA), have been proposed as corrective measures to address concentrations of molybdenum (Mo) and arsenic (As) reported at statistically significant levels (SSLs) above Groundwater Protection Standards (GWPS) in detection monitoring wells HGWC-8 and HGWC-13, respectively, at Georgia Power Plant Hammond Ash Pond 1 (AP-1; Site).

Design of in-situ geochemical injection corrective measures includes multiple assessment and design components, including pilot studies to evaluate injection delivery and the performance of injectates prior to implementing a full scale remedy. These pilot tests will collect data that will be used to evaluate:

1. Radius of influence (ROI) of the injected amendment to evaluate future injection point spacing requirements;
2. Sustainable injection pressure and flowrate; and
3. Injectate dosing and efficacy of treating As and Mo in groundwater to below the GWPS.

This Report summarizes the well installation activities completed in June 2023, baseline sampling activities completed in July and August 2023, and injection activities completed in September and October 2023. These field activities were conducted in accordance with the *HGWC-8 Pilot Study Workplan* and the *HGWC-13 Pilot Study Workplan* (collectively referred to herein as “Workplans”) (Geosyntec, 2023b, 2023c) associated with the Underground Injection Control (UIC) Pilot Test Notification Form. This Report has been prepared in accordance with requirements stipulated in the August 24, 2023 UIC Program pilot test notification approval letter.

1.1 Site Background

Plant Hammond, shown on **Figure 1**, is located in Floyd County, approximately 10 miles west of Rome, Georgia. Plant Hammond was a four-unit, coal-fired electric generating facility and was retired on July 29, 2019. The physical address of the plant is 5963 Alabama Highway, Rome, Georgia, 30165.

AP-1 is one of four coal combustion residual (CCR) ponds utilized over the course of power generation at Plant Hammond. AP-1 is a 35-acre surface impoundment located near the center of Plant Hammond and was used primarily as a dewatering facility for fly ash and bottom ash. AP-1 closure activities, consisting of closure by removal, have been initiated under GA EPD's approved closure permit No. 057-023D(CCR).

As documented in the *Draft Remedy Selection Report* (Geosyntec, 2022), CCR groundwater monitoring-related activities are performed at AP-1 in accordance with the United States Environmental Protection Agency (US EPA) CCR Rule (federal CCR Rule) (40 Code of Federal Regulations [CFR] 257 Subpart D). The locations of AP-1 detection monitoring wells, assessment monitoring wells, and piezometers are shown on **Figure 2**.

A Mo SSL was identified at detection well HGWC-8 along the eastern boundary of AP-1 and an As SSL was identified at detection monitoring well HGWC-13 along the southwest boundary of AP-1 (**Figure 2**) as part of the assessment monitoring program. These SSLs have been horizontally and vertically delineated to levels below the GWPS (Geosyntec, 2022).

As part of implementing the Assessment of Corrective Measures (ACM) process at AP-1, a high resolution site characterization was conducted in August 2022 for HGWC-8 and February 2023 for HGWC-13, to characterize and refine proposed treatment areas. The results are summarized in the Workplans (GEOS Submittal ID: 778366). The information collected informed the pilot study summarized in this Report.

2. WELL INSTALLATION

Four performance monitoring wells (PT-07 through PT-10) were installed in accordance with the Workplans in June 2023. The locations are shown on **Figure 2** and the well construction details are provided in **Table 1**. Actual screen interval elevations varied by less than 0.7 feet (ft) from the originally proposed depths based on field topographic variations and lithology. A copy of the *Well Design, Installation, and Development Report – Addendum No. 5* detailing the design, installation, and development of these wells is included in **Appendix A**.

Well drilling, installation, and surface completion activities were performed by Cascade Drilling, Inc. (Cascade). The boreholes were advanced using roto-sonic drilling techniques with continuous core collection. A Terra Sonic compact crawler size track mounted rig with a 6-inch sonic drill rod was used to install the wells.

3. BASELINE CHARACTERIZATION

Two rounds of groundwater samples were collected from the performance monitoring wells (PT-07 through PT-10) in July and August 2023 to establish pre-injection baseline conditions.

Groundwater samples and water quality field parameters (i.e., pH, conductivity, dissolved oxygen [DO], temperature, and oxidation-reduction potential [ORP]) were collected using low-flow sampling procedures in accordance with the current AP-1 *Groundwater Monitoring Plan* (Geosyntec, 2023a) and the Workplans. Groundwater samples were placed in ice-packed coolers and submitted to Pace Analytical Services, LLC (Pace Analytical) in Peachtree Corners, Georgia, following chain-of-custody protocol. Samples were analyzed for Appendix III and IV constituents, and select geochemical parameters and metals in accordance with the Workplans to support evaluation of injectate efficacy. The results for the July and August 2023 sampling events are presented in **Table 2**. The analytical laboratory results and field sampling and equipment calibration forms are provided in **Appendix B**.

4. INJECTION ACTIVITIES

Injection activities were performed over two shifts between September 25 and October 17, 2023, by Cascade with technical supervision conducted by Geosyntec. A staging and mixing area was established prior to injection. Three-hundred-gallon (gal) cone bottom mixing and storage tanks were set up within a secondary containment berm and spill kits were maintained on-site to manage any spills or daylighting. Injectate consisted of either ferrous sulfate (FeSO_4) heptahydrate or magnesium oxide (MgO) obtained from TerraSystems, Inc. mixed with potable water obtained from an on-site fire hydrant that was designated in the Workplans.

Pre-determined quantities of FeSO_4 or MgO were measured on a digital scale and combined with potable water in mix tanks. The injectate was mixed using a recirculation pump prior to injection, in accordance with the Workplan, in the 300-gal mix tanks. A pump was used to deliver injectate through steel rods to a 2-ft long steel well screen advanced using direct push technology (DPT) drilling. Injections were initiated at the top of injectable treatment zone and proceeded downward (i.e., top-down). In some injection point borings the DPT injection system was pressurized with potable water while advancing the tooling to prevent clogging of the injection screen with aquifer solids. After reaching the target treatment interval, potable water pressurization was stopped and the injection of injectate was initiated. Injection point boreholes were abandoned to the ground surface with bentonite chips upon completion of the injection boring in accordance with the Workplans.

Injection pressures, flowrates, and water levels in nearby performance monitoring wells were measured throughout injection activities, and the daily maximum injection volume across both pilot study areas was below the value included in the Pilot Test Notification Form (3,500 gal per day [gpd]). A summary of daily injected volumes is included in **Table 3**. Field forms are included in **Appendix C**.

4.1 HGWC-8 Injection Area (East Area)

Injections occurred at four injection locations surrounding PT-09 (located south of HGWC-8 and east of AP-1, as shown on **Figure 2**), starting with IP-05. An initial injection consisting of potable water (i.e., without FeSO_4 or MgO) was conducted to verify that injection instrumentation was functioning, no leaks in the system were present, and to assess the aquifer response to pressurized injection. Approximately 500 gal of potable water was injected in each 2-ft interval from 19 to 27 ft below ground surface (bgs).

Following completion of the potable water injections, 850 gal of 1.11×10^{-4} pounds per gallon (lb/gal) FeSO_4 (or 13 milligrams per liter (mg/L) FeSO_4 heptahydrate) was injected in 2-ft intervals from 19 to 27 ft bgs at IP-08, followed sequentially by IP-05, IP-07, and IP-06. Injections in the 17 to 19 ft interval were unsuccessful at all locations due to insufficient transmissivity in the aquifer. A second injection at IP-08 (denoted as IP-08A in field forms) consisting of 0.001% MgO was conducted to assess aquifer response. Prior to initiating the injection of MgO, approximately 1 gal of potable water was observed daylighting. Spilled potable water was addressed in accordance with the Workplans, the injection point was offset approximately 2 ft, and no additional daylighting was observed.

The maximum observed flowrate and injection pressure during HGWC-8 pilot study injections was approximately 6.8 gal per minute (gpm) and 4 pounds per square inch (psi), which were below the maximum proposed values included in the Pilot Test Notification Form¹. Approximately 2,000 gal of potable water and 17,000 gal of injectate was injected at the four injection locations associated with the HGWC-18 pilot study area over the course of twelve days, with a daily maximum of 2,350 gal injected.

4.2 HGWC-13 Injection Area (Southwest Area)

Starting at IP-01, DPT tooling was advanced at four injection locations surrounding PT-07 (located northeast of HGWC-13 and south of AP-1, as shown on **Figure 2**) using similar means and methods employed near HGWC-8. Consistent with the HGWC-8 pilot study approach, an initial injection consisting of potable water (i.e., without FeSO_4 or MgO) was conducted to verify that injection instrumentation was functioning, no leaks in the system were present, and to assess the aquifer response to pressurized injection. Between 55 and 238 gal potable water was injected in each 2-ft intervals starting from 35 ft bgs down to 45 ft bgs. In contrast with the HGWC-8 pilot study are injections, transmissivity varied substantially between injection points with groundwater mounding typically less than 2 ft. As such, smaller volumes were injected in intervals where transmissivity was low and minimal mounding was observed in nearby PT wells.

Following completion of potable water injections, 175 gal of 1.67×10^{-4} lb/gal (or 20 mg/L FeSO_4 heptahydrate) was injected at IP-04 from 35 to 43 ft bgs and 375 gal from 45 to 49 ft bgs. Injection volumes were increased in intervals 45 to 49 ft bgs² based on observed mounding PT-07 and PT-08. At IP-03, 350 gal of FeSO_4 was injected in each 2-ft

¹ The proposed injection flowrate and pressure included in the Pilot Test Notification Form for IP-05 through IP-08 were 15 gpm and 4 psi, respectively.

² The targeted bottom of the treatment zone was 49 ft based on the surveyed as-built bottom elevation of the PT-07 well screen.

intervals from 35 to 38.5 ft bgs and from 41 to 49 ft bgs³. At IP-02, 350 gal FeSO₄ was injected in each 2-ft interval from 35 to 39 ft bgs, 50 gal from 39 to 41 ft bgs, and 350 gal from 41 to 48.5 ft bgs⁴. At IP-01, 350 gal FeSO₄ was injected in 2-ft intervals from 33 to 41 ft bgs, 50 gal from 41 to 43 ft bgs, and 350 gal from 47 to 49 ft bgs.

The maximum observed flowrate and injection pressure during HGWC-13 pilot study injections was approximately 5 gpm and 11 psi, which were below the maximum proposed values included in the Pilot Test Notification Form⁵. Approximately 818 gal of potable water and 7,625 gal of injectate was injected at the four injection locations associated with the HGWC-13 pilot study area over the course of seven days, with a daily maximum of 1,975 gal injected.

³ The injection screen was raised to 36.5 to 38.5 ft bgs after encountering insufficient transmissivity at 37 to 39 ft bgs. Similarly, insufficient transmissivity was encountered from 39 to 41 ft bgs.

⁴ The injection screen was raised to 46.5 to 48.5 ft bgs after encountering insufficient transmissivity at 47 to 49 ft bgs.

⁵ The proposed injection flowrate and pressure included in the Pilot Test Notification Form for IP-01 through IP-04 were 15 gpm and 4 psi, respectively.

5. POST-INJECTION PERFORMANCE MONITORING AND REPORTING

In accordance with the Workplans, groundwater quality data from each performance monitoring event will be directly compared against the Mo and As GWPS and the results of the baseline characterization to evaluate the efficacy of FeSO₄ and MgO as a method of remediation. In addition, Appendix IV monitoring parameters⁶ will be analyzed and monitored over the duration of the pilot study to evaluate potential localized mobilization of other Appendix IV parameters following injections.

Post-injection performance monitoring was initiated on October 10 and October 17, 2023, for the HGWC-8 and HGWC-13 pilot study areas, respectively, with groundwater samples collected from their respective performance monitoring wells. The monitoring frequency will be weekly for four weeks, then monthly for a period of five months, and finally, quarterly for a period of one year for a maximum total duration of 1.5 years of performance monitoring.

Updates concerning the pilot study results will be reported to GA EPD Solid Waste Management Program as brief summaries included as part of semiannual groundwater monitoring and corrective action reporting. Links to these reports will be emailed to the GA EPD Wastewater Regulatory Program. A comprehensive technical memorandum will be prepared at the conclusion of the pilot study for inclusion in a semiannual groundwater monitoring report.

⁶ Excluding radium.

6. REFERENCES

Geosyntec, 2022. *Draft Remedy Selection Report, Georgia Power Company, Plant Hammond Ash Pond 1 (AP-1)*. August 2022.

Geosyntec, 2023a. *Groundwater Monitoring Plan – Plant Hammond Ash Pond 1 (AP-1)*. July 2023, revision 2.

Geosyntec, 2023b. *HGWC-8 Pilot Study Workplan, Plant Hammond Ash Pond 1 (AP-1)*. August 2023.

Geosyntec, 2023c. *HGWC-13 Pilot Study Workplan, Plant Hammond Ash Pond 1 (AP-1)*. August 2023.

TABLES

Table 1
Summary of Well Construction Details
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area	Well ID	Well Completion	Installation Date	Northing ⁽¹⁾	Easting ⁽¹⁾	Ground Surface Elevation ⁽²⁾ (ft)	Top of Casing Elevation ⁽²⁾ (ft)	Top of Screen Elevation (ft)	Bottom of Screen Elevation (ft)	Well Depth (ft bgs) ⁽³⁾	Screen Interval Length (ft)
HGWC-13 (Southwest Area)	PT-07	Flush Mount	6/3/2023	1548675.24	1940933.39	592.00	591.75	554.40	544.30	48.00	10
	PT-08	Flush Mount	6/3/2023	1548666.82	1940929.58	592.10	591.83	560.20	550.20	42.20	10
HGWC-8 (East Area)	PT-09	Protective Riser	6/1/2023	1549049.74	1942393.11	577.33	580.35	560.18	550.18	27.45	10
	PT-10	Protective Riser	6/1/2023	1549040.34	1942413.88	577.39	580.44	560.29	550.29	27.40	10

Notes:

ft bgs = feet below ground surface.

(1) Coordinates in North American Datum (NAD) 1983, State Plane, Georgia-West, feet. Survey was completed by GEL Solutions and certified July 17, 2023, and August 30, 2023.

(2) Vertical elevations are referenced to the North American Vertical Datum (NAVD) of 1988. Ground surface elevation defined at the survey nail installed within the well pad. Survey was completed by GEL Solutions and certified July 17, 2023, and August 30, 2023.

(3) Total well depth accounts for 0.3 ft sump.

Table 2
Summary of Baseline Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area:		Southwest Area				East Area			
Well ID:		PT-07	PT-07	PT-08	PT-08	PT-09	PT-09	PT-10	PT-10
Sample Date:		7/13/2023	8/9/2023	7/13/2023	8/9/2023	7/13/2023	8/9/2023	7/13/2023	8/9/2023
	Parameter ^(1,2,3)								
APPENDIX III	Boron	1.0	0.93	1.0	0.99	2.1	1.6	2.2	2.1
	Calcium	168	173	161	146	110	136	127	116
	Chloride	15.7	13.5	17.0	14.5	55.3	47.5	67.2	62.5
	Fluoride	0.36	0.28	0.36	0.27	0.24	0.26	0.33	0.27
	pH	6.76	6.82	6.66	6.82	6.57	6.89	7.01	7.18
	Sulfate	411	339	417	290	160	188	145	123
	TDS	808	771	734	682	534	594	557	553
APPENDIX IV	Antimony	<0.0012	<0.0012	<0.0012	<0.0012	0.0027 J	<0.0012	<0.0012	<0.0012
	Arsenic	0.34	0.27	0.33	0.32	<0.0037	<0.0037	<0.0037	<0.0037
	Barium	0.056	0.053	0.051	0.050	0.053	0.057	0.074	0.070
	Beryllium	0.00012 J	0.000095 J	0.00011 J	0.000073 J	0.000077 J	<0.000054	<0.000054	<0.000054
	Cadmium	<0.00011	<0.00011	<0.00011	<0.00011	<0.00011	<0.00011	<0.00011	<0.00011
	Chromium	<0.0011	<0.0011	<0.0011	<0.0011	<0.0011	<0.0011	<0.0011	<0.0011
	Cobalt	0.13	0.090	0.031	0.032	0.0045 J	0.0028 J	0.0026 J	0.0019 J
	Fluoride	0.36	0.28	0.36	0.27	0.24	0.26	0.33	0.27
	Lead	<0.00012	<0.00012	0.00019 J	<0.00012	0.00014 J	<0.00012	<0.00012	<0.00012
	Lithium	0.060	0.069	0.065	0.073	0.0013 J	0.0017 J	0.0014 J	0.0012 J
	Mercury	<0.00013	<0.00013	<0.00013	<0.00013	<0.00013	<0.00013	<0.00013	<0.00013
	Molybdenum	0.017	0.012	0.0079 J	0.0071 J	0.065	0.21	0.10	0.096
	Selenium	<0.0014	<0.0014	<0.0014	<0.0014	<0.0014	<0.0014	<0.0014	<0.0014
	Thallium	0.00024 J	0.00022 J	<0.00018	<0.00018	<0.00018	<0.00018	<0.00018	<0.00018
INORGANICS	Alkalinity (Bicarbonate) as CaCO ₃	102	116	107	118	144	150	185	199
	Alkalinity (Carbonate) as CaCO ₃	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
	Alkalinity (Total) as CaCO ₃	102	116	107	118	144	150	185	199
	Sodium	6.1	7.2	6.9	6.8	10.6	10.3	10.5	9.4
	Sulfide	<0.022	<0.022	0.036 J	<0.022	<0.022	<0.022	<0.022	0.045 J
METALS	Iron	23.8	27.1	24.2	22.0	0.33	0.10	3.1	2.9
	Magnesium	18.5	19.4	18.9	17.3	15.6	18.2	16.8	16.8
	Manganese	8.2	7.6	8.7	6.8	0.79	0.51	3.5	3.1
	Potassium	6.0	6.8	6.0	6.3	6.8	7.7	7.1	6.7
FIELD	Dissolved Oxygen	0.30	0.40	0.09	0.94	0.02	0.58	0.03	0.12
	Oxidation-Reduction Potential (mV)	-111	-90.9	-124.9	-84.4	18.4	14.4	-161.5	-80.9
	Temperature (°C)	27.26	21.19	24.53	20.60	24.48	21.59	21.95	21.79
	Specific Conductance (µS/cm)	1065	1012	1007	909.2	779.8	826.9	842.2	770.5
	pH (s.u.)	6.76	6.82	6.66	6.82	6.57	6.89	7.01	7.18
	Turbidity (NTU)	4.91	0.18	4.41	3.98	4.95	0.56	4.94	4.55

Notes:

< = Indicates the parameter was not detected above the analytical method detection limit (MDL).

°C = degrees Celsius

J = Indicates the parameter was estimated and detected between the MDL and the reporting limit (RL).

µS/cm = microsiemens per centimeter

mV = millivolts

NTU = nephelometric turbidity units

s.u. = standard units

TDS = Total dissolved solids

(1) Appendix III/IV parameter per 40 CFR 257 Subpart D. Analysis of combined radium omitted from the pilot study monitoring program. Unless otherwise indicated, parameters are reported in units of milligrams per liter (mg/L).

(2) Metals were analyzed by EPA Method 6010D, 6020B, and 7470A, anions were analyzed by EPA Method 300.0, TDS was analyzed by SM2540C-2015, and combined radium 226/228 by EPA Methods 9315/9320.

(3) The pH value presented was recorded at the time of sample collection in the field.

Table 3
Summary of Daily Injection Volumes
Plant Hammond AP-1, Floyd County, Georgia

Date	Daily Injection Volume (gal)	
	HGWC-8 (East Area)	HGWC-13 (Southwest Area)
9/25/2023*	500	--
9/26/2023*	1,500	--
09/27/2023	2,200	--
09/28/2023	2,250	--
09/29/2023	2,350	--
09/30/2023	2,000	--
10/01/2023	2,250	--
10/02/2023	2,300	--
10/03/2023	250	--
10/4/2023*	--	238
10/9/2023*	--	580
10/10/2023	--	1,050
10/11/2023	--	1,575
10/12/2023	--	1,975
10/13/2023	--	1,400
10/14/2023	--	1,625
10/15/2023	735	--
10/16/2023	2,080	--
10/17/2023	585	--
TOTAL:	19,000	8,443



Notes:

-- = indicates no injections occurred on this date

* = injection consisted of potable water

gal = gallons


FIGURES



LEGEND
[Red dashed line] Plant Hammond Property Boundary



Note:
1. Aerial photograph source: Google Earth Pro, August 2019 and Georgia Power Company, February 2023.





SITE LOCATION MAP

GEORGIA POWER COMPANY
PLANT HAMMOND AP-1
ROME, FLOYD COUNTY, GEORGIA

Prepared For:  Georgia Power
Prepared By: 

KENNESAW, GA NOVEMBER 2023


FIGURE
1



LEGEND

- Detection Monitoring Well
- Horizontal Assessment Monitoring
- Vertical Assessment Monitoring
- Piezometer (See Note 2)
- Surface Water Level Gauge Point
- Injection Point
- Approximate Groundwater Flow Direction
- Approximate AP-1
- Plant Hammond Property Boundary

- Notes:
1. Piezometers PT-07, PT-08, PT-09, PT-10, MW-53 and MW-54 were installed in support of an Assessment of Corrective Measures geochemical injections pilot study and are not included in the routine semiannual sampling of the monitoring well network.
 2. Piezometer water elevations for PT-07 through PT-09 were recorded on August 7, 2023. Elevation are in feet (ft) referenced to the North American Vertical Datum of 1998 (NAVD 88).
 3. "*" - The groundwater flow direction in this area is based on historical data for the site and does not consider PT-07.
 4. Aerial photograph source: Google Earth Pro, August 2019, and Georgia Power Company, February 2023.



SCALE IN FEET

**PILOT STUDY INJECTION POINT
AND MONITORING WELL LOCATIONS**

GEORGIA POWER COMPANY
PLANT HAMMOND AP-1
ROME, FLOYD COUNTY, GEORGIA

Prepared For: Georgia Power

Prepared By: Geosyntec
consultants

KENNESAW, GA

NOVEMBER 2023

**FIGURE
2**

APPENDIX A

Well Design, Installation, and Development Report – Addendum No. 5



Prepared for

Georgia Power Company

241 Ralph McGill Blvd NE

Atlanta, Georgia 30308

WELL DESIGN, INSTALLATION, AND DEVELOPMENT REPORT - ADDENDUM

No. 5

**PLANT HAMMOND ASH POND 1
(AP-1)**

Prepared by

Geosyntec 
consultants

engineers | scientists | innovators

1255 Roberts Boulevard, Suite 200
Kennesaw, Georgia 30144

Project Number GW6581E

October 2023



CERTIFICATION PAGE

I hereby certify that this *Well Design, Installation, and Development Report – Addendum No. 5, Plant Hammond Ash Pond 1 (AP-1)* has been prepared by, or under the direct supervision of, a Qualified Groundwater Scientist with Geosyntec Consultants, Inc. and is in compliance with the United States Environmental Protection Agency Coal Combustion Residual Rule [40 Code of Federal Regulations 257 Subpart D], specifically §257.91(e)(1), and the Georgia Environmental Protection Division Rules for Solid Waste Management 391-3-4-.10.

According to 391-3-4-.01, a Qualified Groundwater Scientist is “a professional engineer or geologist registered to practice in Georgia who has received a baccalaureate or post-graduate degree in the natural sciences or engineering and has sufficient training and experience in groundwater hydrology and related fields that enable individuals to make sound professional judgments regarding groundwater monitoring, contaminant fate and transport, and corrective action.”



A handwritten signature in blue ink that reads "Christine Hug".

Christine Hug P.G.
Georgia Professional Geologist No. 002221
Project Manager
Geosyntec Consultants

October 3, 2023

Date

TABLE OF CONTENTS

1. INTRODUCTION 1

2. DRILLING AND WELL INSTALLATION 2

2.1 Drilling Method 2

2.2 Screened Interval 2

2.3 Well Casings and Screens 2

2.4 Well Intake Design 3

2.5 Filter Pack 3

2.6 Annular Seal 4

2.7 Cap and Protective Casing 4

3. WELL DEVELOPMENT 5

4. SURVEY 6

5. REFERENCES 7

LIST OF TABLES

Table 1 Summary of Well Construction Details

LIST OF FIGURES

Figure 1 Groundwater Monitoring Network Map

LIST OF APPENDICES

Appendix A Well Driller Performance Bonds

Appendix B Boring and Well Construction Logs

Appendix C Well Development and Equipment Calibration Forms

Appendix D Certified Well Survey Data

LIST OF ACRONYMS

AP	Ash Pond
ASTM	American Society for Testing and Materials
CCR	coal combustion residual
CFR	Code of Federal Regulations
CFS	Civil Field Services
DO	dissolved oxygen
GA EPD	Georgia Environmental Protection Division
Georgia Power	Georgia Power Company
NAD	North America Datum
NAVD	North American Vertical Datum
NSF	National Sanitation Foundation
ORP	oxygen reduction potential
PVC	polyvinyl chloride
SCS	Southern Company Services
TOC	top of casing
US EPA	United States Environmental Protection Agency

1. INTRODUCTION

This report provides details regarding the design, installation, and development of six piezometers¹ (MW-53, MW-54, PT-07, PT-08, PT-09, and PT-10) to supplement the current groundwater monitoring system at Georgia Power Company (Georgia Power) Plant Hammond (Site) Ash Pond 1 (AP-1). The report was prepared as an addendum to previously submitted well design, installation, development and decommissioning reports issued for the Site (ERM, 2017; Geosyntec 2019, 2020a, 2020b, and 2020c), and meets the requirements promulgated in the United States Environmental Protection Agency (US EPA) coal combustion residual (CCR) rule [40 Code of Federal Regulations (CFR) Part 257, Subpart D], specifically 40 CFR §257.91(e)(1) and Georgia Environmental Protection Division (GA EPD) Rules for Solid Waste Management 391-3-4-.10.

Plant Hammond is located in Floyd County, approximately 10 miles west of Rome, Georgia. The current groundwater monitoring system at AP-1 includes a network of detection monitoring wells, assessment monitoring wells, and piezometers. The locations of these wells and piezometers are shown on **Figure 1**.

MW-53 and MW-54 were installed to characterize site conditions. PT-07, PT-08, PT-09, and PT-10 were installed to specifically monitor the performance of the pilot study injections in support of the Assessment of Corrective Measures program.

¹ For the purposes of this report, unless otherwise specified, the term “well” will be used interchangeably with “piezometer”.

2. DRILLING AND WELL INSTALLATION

Well installation and development activities were performed according to accepted industry standards and following guidelines within the Manual for Groundwater Monitoring (GA EPD, 1991). Well drilling, installation, and surface completion activities were performed by Cascade Drilling, Inc. of Midland, North Carolina. In accordance with the Georgia Water Well Standards Act, the driller was required to have an insurance bond on file with the State of Georgia at the time of drilling. A copy of this bond is provided in **Appendix A**. A geologist under the supervision of a professional geologist (PG) registered to practice in the State of Georgia, both of whom are employed with Geosyntec Consultants (Geosyntec), documented the drilling and installation efforts to record observations, soil and rock descriptions, subsurface stratigraphy, water elevations, and other field activities. Geosyntec was also responsible for the development of the newly installed wells.

The locations of the new piezometers are shown on **Figure 1**. Well construction details are provided in **Table 1**; boring and well construction logs are included in **Appendix B**.

2.1 Drilling Method

The boreholes were advanced using rotosonic drilling techniques with continuous core collection. Terra Sonic compact crawler size track mounted rig with a 6-inch sonic drill rod was used to install the wells. Care was taken so that the drilling methods did not introduce contamination of the groundwater from surface activities. Drilling equipment was cleaned prior to mobilizing to the site.

2.2 Screened Interval

Details regarding the well screened intervals are provided in **Table 1**. The wells are screened in the uppermost water bearing unit of the Site. Screened elevations across the new wells range from approximately 564.98 to 544.30 feet (referenced to the North American Vertical Datum of 1988). The wells were constructed with a 10 foot well screen segment.

2.3 Well Casings and Screens

The wells were constructed of 2-inch inner diameter Schedule 40 polyvinyl chloride (PVC) casing with flush-threaded fittings. The wells were installed with a 10-foot nominal length pre-packed dual-wall well screen with 0.010-inch slots. The casing and

pre-packed screens arrived pre-cleaned and packaged by the manufacturer. The pre-packed well screens were constructed onsite by packing sand between slotted PVC and the well screen. Well construction materials are sufficiently durable to resist chemical and physical degradation and do not interfere with the quality of groundwater samples. Casing and screen are flush-threaded. Solvent or glue was not used to construct the wells. A threaded bottom cap was attached to the bottom of each well screen. The PVC products used were American Society for Testing and Materials (ASTM) and National Sanitation Foundation (NSF) rated. Well screen interval details are provided in **Table 1**.

2.4 Well Intake Design

The wells were designed and constructed to: (1) allow sufficient groundwater flow to the well for sampling; (2) minimize the passage of formation materials (turbidity) into the well; and (3) ensure sufficient structural integrity to prevent collapse of the well. The annular space between the face of the formation and the screens was filled to minimize passage of formation materials into the well. A filter pack of clean, well-rounded, quartz sand was installed in each well. The 0.01-inch slot size was selected to minimize the inflow of formation material without impairing influent groundwater flow.

2.5 Filter Pack

Highly Pure Quartzite of Consolidated Aggregates Co. silica sand filter pack was used as the appropriate gradation for the wells. The filter pack material meets the ASTM D5092 uniformity coefficient specification of 2.5 or less, with a uniformity coefficient of 1.6.

Filter pack material was placed within the pre-packed dual-wall well screens and in the annular space between the outside of the pre-pack screen and borehole wall to ensure an adequate thickness of filter pack material between the wells and the formation. Placement of the filter pack between the borehole wall and PVC was placed via gravity-pouring. Filter pack material placed in the annular space outside of the well screens extended approximately 2 feet above the top of screens. No bridging occurred during filter pack placement at any of the well locations.

Upon placement of the filter pack, the wells were pumped with a submersible pump to assure settlement of the filter pack. The top of filter pack depth was measured following pumping to ensure appropriate extension of filter sand above the screens. The depth of top of filter pack was measured and recorded on the well construction logs provided in **Appendix B**.

2.6 Annular Seal

A minimum of two feet of bentonite chips (PelPlug un-coated 3/8-inch bentonite pellets) were placed immediately above the filter pack by gravity-pouring into the annular space and hydrated per manufacture's specifications. A tremie pipe was used to probe the annular space to ensure that no bridging occurred. The bentonite was hydrated with potable water for a duration meeting the manufacture's specifications prior to grouting the remaining annulus.

The annulus above the bentonite seal was grouted with AquaGuard bentonite grout placed via tremie pipe and direct pour methods from the top of the bentonite seal. During grouting, care was taken to assure that the bentonite seal was not disturbed by locating the base of the tremie pipe approximately 2 feet above the bentonite seal and injecting grout at low pressure/velocity. A cement apron 4-feet by 4-feet by 4-inches was poured around the protective risers at wells MW-53, PT-09, and PT-10. A cement apron 2-feet by 2-feet by 4-inches was poured around flush mount wells PT-07, PT-08, and MW-54. The pads were mounded slightly outward to direct surface drainage away from the wells.

2.7 Cap and Protective Casing

The well risers at MW-53, PT-09, and PT-10 were fitted with a locking cap and a lockable cover. A one-quarter inch vent hole was drilled into the PVC riser pipes to provide an avenue for the escape of gas. A weep hole was drilled in the outer protective casing near the bottom above the concrete pad. Pea gravel was placed inside the protective casing between the riser pipe and the outer casing. The wells were clearly marked with the proper well identification number on the stand-up casing. The lockable cover guards the casing from damage and the locking caps serve as a security device to prevent well tampering. Bollards were installed around MW-53, and well cluster PT-09, and PT-10 to protect the general well area.

MW-54, PT-07, and PT-08 were installed with flush-mounted well vaults and watertight flush-mounted well covers. The wells were clearly marked with the proper well identification number on a secured aluminum well tag on the manhole covers.

Construction details are documented on the well construction logs provided in **Appendix B**.

3. WELL DEVELOPMENT

The wells were developed using a combination of surging and pumping to (1) restore the natural hydraulic conductivity of the formation, and (2) to remove fine-grained sediment to ensure low-turbidity groundwater samples. The wells were alternately surged and purged until visually clear of particulates. Turbidity, pH, temperature, conductivity, oxidation-reduction potential (ORP), and dissolved oxygen (DO) measurements were recorded to ensure that each well was fully developed. The well development and calibration field forms are included in **Appendix C**.

4. SURVEY

Upon completion of the well installations, select horizontal locations and vertical elevations were surveyed by a Georgia-licensed surveyor. The top of the PVC well casing [top of casing (TOC) elevation] and the survey pin installed at the well pads were surveyed to within 0.5-foot horizontal accuracy and to 0.01-foot vertical accuracy. The horizontal location (i.e., northings and eastings) was recorded in feet relative to the North America Datum of 1983 (NAD) with the vertical elevation recorded in feet relative to the North American Vertical Datum of 1988. Certified survey data are provided in the well construction table (**Table 1**). A copy of the certified well survey data for the new wells are provided in **Appendix D**.

5. REFERENCES

- Environmental Resources Management (ERM), 2017. *Well Design, Installation, Development, and Decommissioning Report – Plant Hammond Ash Ponds 1 and 2*. October 2017.
- Georgia Environmental Protection Division (GA EPD), Georgia Department of Natural Resources, 1991. *Manual for Groundwater Monitoring*. September 1991.
- Geosyntec Consultants, 2019. Well Design, Installation and Development Report – Addendum, Plant Hammond Ash Ponds 1 and 2 (AP-1 and AP-2). June 2019.
- Geosyntec Consultants, 2020a. Well Design, Installation and Development Report – Addendum 2, Plant Hammond Ash Ponds 1 (AP-1). January 2020.
- Geosyntec Consultants, 2020b. Well Design, Installation and Development Report – Addendum No 3, Plant Hammond Ash Ponds 1 (AP-1). July 2020.
- Geosyntec Consultants, 2020c. Well Design, Installation and Development Report – Addendum No 4, Plant Hammond Ash Ponds 1 (AP-1). November 2020.
- United States Environmental Protection Agency. 2015a. Federal Register. Volume 80. No. 74. Friday April 17, 2015. Part II. Environmental Protection Agency. 40 CFR Parts 257 and 261. Hazardous and Solid Waste Management System; Disposal of Coal Combustion Residuals from Electric Utilities; Final Rule. [EPA-HQ-RCRA–2009–0640; FRL–9919–44–OSWER]. RIN–2050–AE81, April 2015

TABLE

Table 1
Summary of Well Construction Details
Plant Hammond AP-1, Floyd County, Georgia

Well ID	Purpose	Well Completion	Installation Date	Northing ⁽¹⁾	Easting ⁽¹⁾	Ground Surface Elevation ⁽²⁾ (ft)	Top of Casing Elevation ⁽²⁾ (ft)	Top of Screen Elevation (ft)	Bottom of Screen Elevation (ft)	Well Depth (ft bgs) ⁽³⁾
PT-07	Piezometer	Flush Mount	6/3/2023	1548675.24	1940933.39	592.00	591.75	554.40	544.30	48.00
PT-08	Piezometer	Flush Mount	6/3/2023	1548666.82	1940929.58	592.10	591.83	560.20	550.20	42.20
PT-09	Piezometer	Protective Riser	6/1/2023	1549049.74	1942393.11	577.33	580.35	560.18	550.18	27.45
PT-10	Piezometer	Protective Riser	6/1/2023	1549040.34	1942413.88	577.39	580.44	560.29	550.29	27.40
MW-53	Piezometer	Protective Riser	6/2/2023	1548835.51	1942399.62	577.64	580.59	554.54	544.54	33.40
MW-54	Piezometer	Flush mount	6/2/2023	1548699.51	1940805.03	592.98	592.66	564.98	554.98	38.30

Notes:



ft bgs = feet below ground surface.

(1) Coordinates in North American Datum (NAD) 1983, State Plane, Georgia-West, feet. Survey was completed by GEL Solutions and certified July 17, 2023, and August 30, 2023.

(2) Vertical elevations are referenced to the North American Vertical Datum (NAVD) of 1988. Ground surface elevation defined at the survey nail installed within the well pad. Survey was completed by GEL Solutions and certified July 17, 2023, and August 30, 2023.

(3) Total well depth accounts for 0.3 ft sump.

FIGURE



- LEGEND**
- Detection Monitoring Well
 - Horizontal Assessment Monitoring Well
 - Vertical Assessment Monitoring Well
 - Piezometer
 - Approximate AP-1 Boundary
 - Plant Hammond Property Boundary

Notes:
1. Aerial photograph source: Google Earth Pro, August 2019, and Georgia Power Company, February 2023.



SCALE IN FEET

GROUNDWATER MONITORING NETWORK MAP

GEORGIA POWER COMPANY
PLANT HAMMOND AP-1
ROME, FLOYD COUNTY, GEORGIA

Prepared For: Georgia Power

Prepared By: Geosyntec consultants

KENNESAW, GA

OCTOBER 2023

FIGURE
1

APPENDIX A

Well Driller Performance Bonds

CONTINUATION
CERTIFICATE

Atlantic Specialty Insurance Company

, Surety upon

a certain Bond No. 800033976

dated effective September 27, 2017
(MONTH-DAY-YEAR)

on behalf of Ricky Davis / Cascade Drilling, L.P.
(PRINCIPAL)

and in favor of Department of Natural Resources, State of Georgia
(OBLIGEE)

does hereby continue said bond in force for the further period

beginning on June 30, 2023
(MONTH-DAY-YEAR)

and ending on June 30, 2025
(MONTH-DAY-YEAR)

Amount of bond Thirty Thousand and 00/100 Dollars (\$30,000.00)

Description of bond Performance Bond for Water Well Contractors

Premium:

PROVIDED: That this continuation certificate does not create a new obligation and is executed upon the express condition and provision that the Surety's liability under said bond and this and all Continuation Certificates issued in connection therewith shall not be cumulative and that the said Surety's aggregate liability under said bond and this and all such Continuation Certificates on account of all defaults committed during the period (regardless of the number of years) said bond had been and shall be in force, shall not in any event exceed the amount of said bond as hereinbefore set forth.

Signed and dated on April 13, 2023
(MONTH-DAY-YEAR)

Atlantic Specialty Insurance Company

By 
ATTORNEY-IN-FACT Carlos A. Albelo



Power of Attorney

KNOW ALL MEN BY THESE PRESENTS, that ATLANTIC SPECIALTY INSURANCE COMPANY, a New York corporation with its principal office in Plymouth, Minnesota, does hereby constitute and appoint: **Megan Sivley, Melissa Haddick, Sandra Parker, Orlando Aguirre, Stacy Killebrew, Carlos A. Albelo**, each individually if there be more than one named, its true and lawful Attorney-in-Fact, to make, execute, seal and deliver, for and on its behalf as surety, any and all bonds, recognizances, contracts of indemnity, and all other writings obligatory in the nature thereof; provided that no bond or undertaking executed under this authority shall exceed in amount the sum of: **unlimited** and the execution of such bonds, recognizances, contracts of indemnity, and all other writings obligatory in the nature thereof in pursuance of these presents, shall be as binding upon said Company as if they had been fully signed by an authorized officer of the Company and sealed with the Company seal. This Power of Attorney is made and executed by authority of the following resolutions adopted by the Board of Directors of ATLANTIC SPECIALTY INSURANCE COMPANY on the twenty-fifth day of September, 2012:

Resolved: That the President, any Senior Vice President or Vice-President (each an "Authorized Officer") may execute for and in behalf of the Company any and all bonds, recognizances, contracts of indemnity, and all other writings obligatory in the nature thereof, and affix the seal of the Company thereto; and that the Authorized Officer may appoint and authorize an Attorney-in-Fact to execute on behalf of the Company any and all such instruments and to affix the Company seal thereto; and that the Authorized Officer may at any time remove any such Attorney-in-Fact and revoke all power and authority given to any such Attorney-in-Fact.

Resolved: That the Attorney-in-Fact may be given full power and authority to execute for and in the name and on behalf of the Company any and all bonds, recognizances, contracts of indemnity, and all other writings obligatory in the nature thereof, and any such instrument executed by any such Attorney-in-Fact shall be as binding upon the Company as if signed and sealed by an Authorized Officer and, further, the Attorney-in-Fact is hereby authorized to verify any affidavit required to be attached to bonds, recognizances, contracts of indemnity, and all other writings obligatory in the nature thereof.

This power of attorney is signed and sealed by facsimile under the authority of the following Resolution adopted by the Board of Directors of ATLANTIC SPECIALTY INSURANCE COMPANY on the twenty-fifth day of September, 2012:

Resolved: That the signature of an Authorized Officer, the signature of the Secretary or the Assistant Secretary, and the Company seal may be affixed by facsimile to any power of attorney or to any certificate relating thereto appointing an Attorney-in-Fact for purposes only of executing and sealing any bond, undertaking, recognizance or other written obligation in the nature thereof, and any such signature and seal where so used, being hereby adopted by the Company as the original signature of such officer and the original seal of the Company, to be valid and binding upon the Company with the same force and effect as though manually affixed.

IN WITNESS WHEREOF, ATLANTIC SPECIALTY INSURANCE COMPANY has caused these presents to be signed by an Authorized Officer and the seal of the Company to be affixed this first day of January, 2023.




By

Sarah A. Kolar, General Counsel

STATE OF MINNESOTA
HENNEPIN COUNTY

On this first day of January, 2023, before me personally came Sarah A. Kolar, General Counsel of ATLANTIC SPECIALTY INSURANCE COMPANY, to me personally known to be the individual and officer described in and who executed the preceding instrument, and she acknowledged the execution of the same, and being by me duly sworn, that she is the said officer of the Company aforesaid, and that the seal affixed to the preceding instrument is the seal of said Company and that the said seal and the signature as such officer was duly affixed and subscribed to the said instrument by the authority and at the direction of the Company.



Notary Public

I, the undersigned, Secretary of ATLANTIC SPECIALTY INSURANCE COMPANY, a New York Corporation, do hereby certify that the foregoing power of attorney is in full force and has not been revoked, and the resolutions set forth above are now in force.

Signed and sealed. Dated 13th day of April, 2023.




This Power of Attorney expires
January 31, 2025

Kara Barrow, Secretary

APPENDIX B

Boring and Well Construction Logs

CLIENT Southern Company Services	PROJECT NAME Plant Hammond Well Installation
PROJECT NUMBER GW6581E	PROJECT LOCATION Plant Hammond
DATE STARTED 06/03/23 COMPLETED 06/03/23	NORTHING 1548675.24 ft EASTING 1940933.39 ft
DRILLER Cascade Drilling	GROUND ELEVATION 592.00 ft BORING DIAMETER 6 in.
DRILLING METHOD Sonic	TOP OF CASING ELEVATION 591.75 ft
SAMPLING METHOD Sonic Core	GEOPHYSICAL CONTRACTOR ---
RIG TYPE Terrasonic Compact Crawler	LOGGED BY T. Kessler CHECKED BY C. Hug




CLIENT Southern Company Services	PROJECT NAME Plant Hammond Well Installation
PROJECT NUMBER GW6581E	PROJECT LOCATION Plant Hammond
DATE STARTED 06/03/23 COMPLETED 06/03/23	NORTHING 1548666.82 ft EASTING 1940929.58 ft
DRILLER Cascade Drilling	GROUND ELEVATION 592.10 ft BORING DIAMETER 6 in.
DRILLING METHOD Sonic	TOP OF CASING ELEVATION 591.83 ft
SAMPLING METHOD Sonic Core	GEOPHYSICAL CONTRACTOR ---
RIG TYPE Terrasonic Compact Crawler	LOGGED BY T. Kessler CHECKED BY C. Hug

DEPTH (ft)	ELEVATION (ft)	REMARKS	GRAPHIC LOG	MATERIAL DESCRIPTION	CONSTRUCTION DIAGRAM
0	590	Air knifed material		SILTY SAND, reddish-brown, fine sand, abundant angular fine to coarse gravel, moist.	Flush mount well cover set in concrete
10	580	Very soft drilling, no vibrations to 18 feet bgs. Fill material from 13-16 feet bgs.		CLAY, reddish-brown to gray, trace fine sand and angular to rounded fine gravel, trace silt, medium plasticity, moist, trace organic material.	Approx. 35 gallon of Aquauard Bentonite Grout
20	570	Drilling becomes harder; significant amount of return water to surface during overdrill.		CLAY, red to yellowish red, trace silt and trace fine sand from 20-21 feet bgs, medium plasticity, moist, gray mottling throughout.	Approx 2.5 gallon of uncoated 3/8" bentonite pellets
30	560			SILTY SAND, yellowish red, fine sand with trace rounded fine gravel, moist to wet.	Approx. 19 gallon of 20/40 Silica Sand
40	550			SILTY SAND, yellowish red, subrounded medium to fine sand, abundant rounded fine to coarse gravel, wet.	0.010 slot size 2" Pre Pack, U-Pack Screen
				SANDY CLAY, yellowish red, fine sand and trace gravel, medium plasticity, moist.	0.3 ft Sump


Bottom of borehole at 43.0 feet below ground surface (ft bgs).

CLIENT Southern Company Services	PROJECT NAME Plant Hammond Well Installation
PROJECT NUMBER GW6581E	PROJECT LOCATION Plant Hammond
DATE STARTED 05/31/23	COMPLETED 06/01/23
DRILLER Cascade Drilling	NORTHING 1549049.74 ft
DRILLING METHOD Sonic	EASTING 1942393.11 ft
SAMPLING METHOD Sonic Core	GROUND ELEVATION 577.33 ft
RIG TYPE Terrasonic Compact Crawler	BORING DIAMETER 6 in.
	TOP OF CASING ELEVATION 580.35 ft
	GEOPHYSICAL CONTRACTOR ---
	LOGGED BY T. Kessler
	CHECKED BY C. Hug




Bottom of borehole at 28.5 feet below ground surface (ft bgs).

CLIENT Southern Company Services	PROJECT NAME Plant Hammond Well Installation
PROJECT NUMBER GW6581E	PROJECT LOCATION Plant Hammond
DATE STARTED 06/01/23	COMPLETED 06/01/23
DRILLER Cascade Drilling	NORTHING 1549040.34 ft
DRILLING METHOD Sonic	EASTING 1942413.88 ft
SAMPLING METHOD Sonic Core	GROUND ELEVATION 577.39 ft
RIG TYPE Terrasonic Compact Crawler	BORING DIAMETER 6 in.
	TOP OF CASING ELEVATION 580.44 ft
	GEOPHYSICAL CONTRACTOR ---
	LOGGED BY T. Kessler
	CHECKED BY C. Hug



Bottom of borehole at 28.0 feet below ground surface (ft bgs).

CLIENT Southern Company Services	PROJECT NAME Plant Hammond Well Installation
PROJECT NUMBER GW6581E	PROJECT LOCATION Plant Hammond
DATE STARTED 06/01/23	COMPLETED 06/02/23
DRILLER Cascade Drilling	NORTHING 1548835.51 ft
DRILLING METHOD Sonic	EASTING 1942399.62 ft
SAMPLING METHOD Sonic Core	GROUND ELEVATION 577.64 ft
RIG TYPE Terrasonic Compact Crawler	BORING DIAMETER 6 in.
	TOP OF CASING ELEVATION 580.59 ft
	GEOPHYSICAL CONTRACTOR ---
	LOGGED BY T. Kessler
	CHECKED BY C. Hug



Bottom of borehole at 34.4 feet below ground surface (ft bgs).

CLIENT Southern Company Services

PROJECT NAME Plant Hammond Well Installation

PROJECT NUMBER GW6581E

PROJECT LOCATION Plant Hammond

DATE STARTED 06/02/23

COMPLETED 06/02/23

NORTHING 1548699.51 ft

EASTING 1940805.03 ft

DRILLER Cascade Drilling

GROUND ELEVATION 592.98 ft

BORING DIAMETER 6 in.

DRILLING METHOD Sonic

TOP OF CASING ELEVATION 592.66 ft


SAMPLING METHOD Sonic Core

GEOPHYSICAL CONTRACTOR ---

RIG TYPE Terrasonic Compact Crawler

LOGGED BY T. Kessler

CHECKED BY C. Hug

DEPTH (ft)	ELEVATION (ft)	REMARKS	GRAPHIC LOG	MATERIAL DESCRIPTION	CONSTRUCTION DIAGRAM
0		Air knifed material		CLAY, reddish yellow, trace silt, medium plasticity, wet, dark gray mottling.	
590					
10		Gravel from 10.5 feet bgs is collapse from air knife material.		SILTY SAND, dark gray to black, subrounded medium to fine sand, trace rounded gravel, moist.	Approx. 30 gallon of Aquauard Bentonite Grout
580					
20		Slow drilling.		CLAY, reddish yellow, medium plasticity, moist to dry, red black and gray mottling throughout.	
570					
20				SILTY CLAY, reddish yellow, hard, medium to low plasticity, dry to moist, red/gray mottling throughout.	Approx. 2.5 gallon of uncoated 3/8" bentonite pellets
560					
30				SILTY SAND, pink/light yellowish gray, fine, subrounded, moist.	Approx. 19 gallon of 20/40 Silica Sand
560				SANDY CLAY, reddish yellow, low plasticity, sand is fine to medium, moist.	
560					
30				SAND, reddish yellow/light gray, fine-grained with trace of fine, rounded gravel throughout, wet.	0.010 slot size 2" Pre Pack, U-Pack Screen
560					
40		Drilled to 39 feet bgs; core barrel sinks to 45 feet bgs; settles on rock.		36 to 36.3 ft: Clay.	0.3 ft Sump
550					Approx. 8 gallon of uncoated 3/8" bentonite pellets
548.0					
Bottom of borehole at 45.0 feet below ground surface (ft bgs).					

APPENDIX C

Well Development and Equipment Calibration Forms

GROUNDWATER SAMPLING LOG SHEET

Client:	SCS
Site:	Plant Hammond
Well ID:	PT-07
Total Depth (ft):	48.6
Depth to Water (ft):	24.3
Well Diameter (in):	2
Well Volume (gal) = $0.041d^2h$:	3.99
Well Volume (L) = gal * 3.785:	15.10

Project No.: GWR05816
Location: AP-1
Pump Type/Model: monsoon
Tubing Material: poly
Pump Intake Depth (ft): 43
Start/Stop Purge Time: 1205/1301
Purge Rate (mL/min): 8000
Total Purge Volume (L): 388

Sampling Date: 6/28/23
 Sampler's Name: AN
 Sample Collection Time: —
 Sample Purge Rate (mL/min): —
 Sample ID: —
 Laboratory Analyses: —

d = well diameter (inches); h = length of water column (feet)

Well Type: ☒ Flush ☐ Stick Up

Well Lock: Yes ☒ No ☐

Well Cap Condition: Good Replace

Well Tag Present: ☒ Yes ☐ No

Purge Method: Low-Flow Well Volume Other: —

QA/OC Collected?

Sampling Method: Pump Discharge Other:

QA/QC ID. —

All sample containers requiring chemical preservation properly preserved prior to demob from well?	Yes	No
---	-----	----

[illegible]

Sampling Date: 6/28/23
 Sampler's Name: AN
 Sample Collection Time: -
 Sample Purge Rate (mL/min): -
 Sample ID: -
 Laboratory Analyses: -

QA/QC Collected?
QA/QC I.D.

All sample containers requiring chemical preservation properly preserved prior to demob from well?	Yes	No
--	-----	----

[illegible]

GROUNDWATER SAMPLING LOG SHEET

Client:	SCS
Site:	Plant Hammond
Well ID:	PT-08
Total Depth (ft):	42.2
Depth to Water (ft):	22.7
Well Diameter (in):	2
Well Volume (gal) = $0.041d^2h$:	3.198
Well Volume (L) = gal * 3.785:	12.104

Project No.: GW0581G

Location: AP-1

Pump Type/Model: monsoon

Tubing Material: poly

Pump Intake Depth (ft): 32

Start/Stop Purge Time: 0820/0908

Purge Rate (mL/min): 10000

Total Purge Volume (L): 480

Sampling Date: 6/29/23
 Sampler's Name: AN
 Sample Collection Time: -
 Sample Purge Rate (mL/min): -
 Sample ID: -
 Laboratory Analyses: ~

d = well diameter (inches); h = length of water column (feet)

Well Type: Flush Stick UpWell Lock: Yes ☐ No ☒Well Cap Condition: Good Replace

Well Tag Present: ☒ Yes ☐ No

Purge Method: Low-Flow Well Volume Other: — QA/QC Collected? —

Sampling Method: Pump Discharge Other: — QA/QC I.D. —

All sample containers requiring chemical preservation properly preserved prior to demob from well?	Yes	No
--	-----	----

Time	pH (SU)	Spec. Cond. (µS/cm)	ORP (mV)	DO (mg/L)	Temp. (°C)	Turbidity (NTUs)	DTW (ft btoc)	Purge Rate (mL/min)	Purged Volume (L)	Notes (Purge method, water clarity, odor, purge rate, issues with pump/well/weather/etc.)
0843	6.56	1022.7	-54.0	0.03	18.88	61.4 AU	28.6	10000	230	pre-purge 20 mins
0848	6.103	1026.8	-87.0	0.02	18.79	70.8	28.6	10000	280	
0853	6.05	1026.8	-56.7	0.01	18.78	36.9	28.6	10000	330	
0858	6.05	1027.8	-55.6	0.01	18.75	22.8	28.6	10000	380	
0903	6.06	1028.1	-88.0	0.01	18.78	11.7	28.6	10000	430	
0908	6.06	1027.7	-88.0	0.01	18.78	9.55	28.6	10000	480	
Stabilizing Criteria	+/- 0.1 SU	+/- 5%		0.2 mg/L or 10% for DO > 0.5 mg/L (whichever is greater)		< 5 NTUs	< 0.3 ft	> 100 mL < 250 mL	> 3L	

GROUNDWATER SAMPLING LOG SHEET

Client:	SCS
Site:	Plant Hammond
Well ID:	PT-08
Total Depth (ft):	422
Depth to Water (ft):	227
Well Diameter (in):	2
Well Volume (gal) = $0.041d^2h$:	3.198
Well Volume (L) = gal * 3.785:	12.104

Project No.: GW65816

Location: AP-1

Pump Type/Model: monsoon

Tubing Material: poly

Pump Intake Depth (ft): 32

Start/Stop Purge Time: 0908/0940

Purge Rate (mL/min): 250

Total Purge Volume (L): 8

Sampling Date: 6/29/23
 Sampler's Name: AN
 Sample Collection Time: —
 Sample Purge Rate (mL/min): —
 Sample ID: —
 Laboratory Analyses: —

d = well diameter (inches); h = length of water column (feet)

Well Type:	Flush	Stick Up
Well Lock:	Yes	No
Well Cap Condition:	Good	Replace
Well Tag Present:	Yes	No

Purge Method: Low-Flow Well Volume Other: 1
Sampling Method: Pump Discharge Other: 1

QA/QC Collected? —
QA/QC ID —

All sample containers requiring chemical preservation properly preserved prior to demob from well?	Yes	No
--	-----	----

[illegible]

GROUNDWATER SAMPLING LOG SHEET

pg. 1 of 2

Client: Southern company
Site: Plant Hammond
Well ID: PT-09
Total Depth (ft): 31
Depth to Water (ft): 14.65
Well Diameter (in): 2
Well Volume (gal) = 0.041d²h: 2.681
Well Volume (L) = gal * 3.785: 10.14

Project No.: GNL6551
Location: Plant Hammond
Pump Type/Model: mega monsoon pro
Tubing Material: poly
Pump Intake Depth (ft): 26
Start/Stop Purge Time: 0830 / 1123
Purge Rate (mL/min): 15,000, 250
Total Purge Volume (L): 1458.75

Sampling Date: 6/27/23
Sampler's Name: AN
Sample Collection Time: —
Sample Purge Rate (mL/min): —
Sample ID: —
Laboratory Analyses: —

d = well diameter (inches); h = length of water column (feet)

Well Type: Flush Stick Up
Well Lock: Yes No
Well Cap Condition: Good Replace
Well Tag Present: Yes No

Purge Method: Low-Flow Well Volume Other: —
Sampling Method: Pump Discharge Other: —

QA/QC Collected? —
QA/QC ID: —

All sample containers requiring chemical preservation properly preserved prior to demob from well? Yes No

Time	pH (SU)	Spec. Cond. (µS/cm)	ORP (mV)	DO (mg/L)	Temp. (°C)	Turbidity (NTUs)	DTW (ft btoc)	Purge Rate (mL/min)	Purged Volume (L)	Notes (Purge method, water clarity, odor, purge rate, issues with pump/well/weather/etc.)
0852	6.72	865.25	2.9	0.03	18.39	3884 AU	15.35	15,000	330	pre-purged for 20 min
0858	6.74	868.23	8.7	0.02	18.21	2747 AU	15.3	15,000	405	
0902	6.74	867.77	-5.7	0.01	18.21	2249 AU	15.3	15,000	480	
0906	6.75	867.44	12.4	0.01	18.20	723 AU	15.3	15,000	540	
0911	6.75	865.02	-2.0	0.01	18.20	1203 AU	15.3	15,000	615	
0916	6.75	868.97	14.1	0.01	18.21	128 AU	15.3	15,000	690	
0921	6.75	864.78	16.3	0.01	18.23	69.1 AU	15.3	15,000	765	
0926	6.75	867.14	12.37	0.00	18.25	37.8	15.3	15,000	840	
0931	6.75	868.88	16.6	0.00	18.25	37.3	15.3	15,000	915	
0936	6.75	867.76	15.7	0.00	18.21	7.3	15.3	15,000	990	
0941	6.75	866.15	8.2	0.00	18.26	57	15.3	15,000	1065	
0946	6.75	870.58	17.5	0.00	18.26	23.8	15.3	15,000	1140	
0951	6.75	868.96	18.0	0.00	18.26	21.2	15.3	15,000	1215	
0956	6.75	869.41	18.5	0.00	18.25	14.3	15.3	15,000	1290	
1001	6.75	867.05	18.4	0.00	18.26	11.9	15.3	15,000	1365	
1006	6.75	866.04	16.4	0.00	18.16	8.37	15.3	15,000	1440	
1011	6.76	864.41	11.8	0.01	18.19	2.37	15.3	250	1441.25	Switch to low flow to stabilize
1016	6.72	864.51	15.3	0.04	21.5	17.4	14.9	250	1442.5	
1023	6.74	861.19	11.8	0.00	19.08	36.1	14.9	250	1443.75	
Stabilizing Criteria	+/- 0.1 SU	+/- 5%		0.2 mg/L or 10% for DO > 0.5 mg/L (whichever is greater)		< 5 NTUs	< 0.3 ft	> 100 mL < 250 mL	> 3L	

GROUNDWATER SAMPLING LOG SHEET

pg. 2052

Client: Southern Company
Site: Plant Hammond
Well ID: PT-09
Total Depth (ft): 31
Depth to Water (ft): 14.65
Well Diameter (in): 2
Well Volume (gal) = $0.041d^2h$: 2.08
Well Volume (L) = gal * 3.785: 10.14

d = well diameter (inches); h = length of water column (feet)

Well Type: ☒ Flush ☒ Stick Up
Well Lock: ☒ Yes ☐ No
Well Cap Condition: ☒ Good ☐ Replace
Well Tag Present: ☒ Yes ☐ No

Project No.: 6W0581
Location: Plant Hammond
Pump Type/Model: mega monsoon pro
Tubing Material: poly
Pump Intake Depth (ft): 26
Start/Stop Purge Time: 0830 / 1123
Purge Rate (mL/min): 15000, 250
Total Purge Volume (L): 1458.75

Sampling Date: 06/27/2023
Sampler's Name: AN
Sample Collection Time: -
Sample Purge Rate (mL/min): -
Sample ID: -
Laboratory Analyses: -

Purge Method: ☐ Low-Flow ☐ Well Volume ☐ Other: -
Sampling Method: ☒ Pump Discharge ☐ Other: -

QA/QC Collected? -
QA/QC ID: -

All sample containers requiring chemical preservation properly preserved prior to demob from well? Yes No

Time	pH (SU)	Spec. Cond. (µS/cm)	ORP (mV)	DO (mg/L)	Temp. (°C)	Turbidity (NTUs)	DTW (ft btoc)	Purge Rate (mL/min)	Purged Volume (L)	Notes (Purge method, water clarity, odor, purge rate, issues with pump/well/weather/etc.)
1028	6.74	8104.55	12.6	0.00	18.96	30.3	14.9	250	1445	
1033	6.74	8104.37	12.8	0.00	18.97	25.4	14.9	250	1446.25	
1038	6.75	8102.81	13.0	0.00	18.89	21.0	14.9	250	1447.5	
1043	6.74	8103.05	1.3	0.00	18.85	18.9	14.9	250	1448.75	
1048	6.75	8103.71	12.9	0.00	18.88	19.9	14.9	250	1450	
1053	6.75	8103.74	1.7	0.00	18.84	14.2	14.9	250	1451.25	
1058	6.75	8103.80	0.4	0.00	18.90	13.2	14.9	250	1452.5	
1103	6.75	8103.59	0.4	0.00	18.90	9.57	14.9	250	1453.75	
1108	6.75	8105.55	12.7	0.00	18.94	7.39	14.9	250	1455	
1113	6.75	8104.61	2.6	0.00	18.88	4.26	14.9	250	1456.25	
1118	6.75	8104.98	13.6	0.00	18.97	3.93	14.9	250	1457.5	
1123	6.75	8105.03	14.3	0.00	18.84	3.03	14.9	250	1458.75	
AN 6/27/23										
Stabilizing Criteria	+/- 0.1 SU	+/- 5%		0.2 mg/L or 10% for DO > 0.5 mg/L (whichever is greater)		< 5 NTUs	< 0.3 ft	> 100 mL < 250 mL	> 3L	

GROUNDWATER SAMPLING LOG SHEET

Client:	SCS
Site:	Plant Hammond
Well ID:	PT-10
Total Depth (ft):	30.7
Depth to Water (ft):	14.80
Well Diameter (in):	2
Well Volume (gal) = $0.041d^2h$:	2.61
Well Volume (L) = gal * 3.785:	9.88

Project No.: GW165816
Location: AD-1
Type/Model: monsoon
Purge Material: poly
Purge Depth (ft): 2.5
Purge Time: 1435/1618
Flow Rate (mL/min): 9000
Purge Volume (L): 585

Sampling Date: 06/27/23
 Sampler's Name: AN
 Sample Collection Time: —
 Sample Purge Rate (mL/min): —
 Sample ID: —
 Laboratory Analyses: —

d = well diameter (inches); h = length of water column (feet)

Well Type: Flush Stick Up

Well Lock: ☒ Yes ☐ No

Well Cap Condition: Good Replace

Well Tag Present: ☒ Yes ☐ No

Purge Method: Low-Flow Well Volume Other: —

QA/QC Collected? ☒

Sampling Method: Pump Discharge Other: —

QA/QC I.D. —

All sample containers requiring chemical preservation properly preserved prior to demob from well?	Yes	No
--	-----	----

[illegible]

GROUNDWATER SAMPLING LOG SHEET

[illegible]

Sampling Date: 6/29/23
 Sampler's Name: AN
 Sample Collection Time: -
 Sample Purge Rate (mL/min): -
 Sample ID: -
 Laboratory Analyses: -

QA/QC Collected?
QA/QC I D

All sample containers requiring chemical preservation properly preserved prior to demob from well?	Yes	No

[illegible]

GROUNDWATER SAMPLING LOG SHEET

Client: SCS
Site: Plant Hammond
Well ID: MW-S4
Total Depth (ft): 38.8
Depth to Water (ft): 23.3
Well Diameter (in): 2
Well Volume (gal) = $0.041d^2h$: 2.54
Well Volume (L) = gal * 3.785: 9.61

Project No.: GW105816
Location: AP-2
Pump Type/Model: monsoon
Tubing Material: poly
Pump Intake Depth (ft): 33.8
Start/Stop Purge Time: 1030/1116
Purge Rate (mL/min): 10000
Total Purge Volume (L): 460

Sampling Date: 6/29/23
Sampler's Name: AN
Sample Collection Time: -
Sample Purge Rate (mL/min): -
Sample ID: -
Laboratory Analyses: -

d = well diameter (inches); h = length of water column (feet)

Well Type: ☒ Flush ☐ Stick Up
Well Lock: ☐ Yes ☒ No
Well Cap Condition: ☒ Good ☐ Replace
Well Tag Present: ☒ Yes ☐ No

Purge Method: Low-Flow Well Volume Other: -
Sampling Method: Pump Discharge Other: -

QA/QC Collected? -
QA/QC I.D. -

All sample containers requiring chemical preservation properly preserved prior to demob from well? Yes No

Time	pH (SU)	Spec. Cond. (µS/cm)	ORP (mV)	DO (mg/L)	Temp. (°C)	Turbidity (NTUs)	DTW (ft btoc)	Purge Rate (mL/min)	Purged Volume (L)	Notes (Purge method, water clarity, odor, purge rate, issues with pump/well/weather/etc.)
1051	6.77	743.50	-1.8	0.02	20.88	863 AU	27.3	10000	210	
1056	6.77	745.92	-28.3	0.03	20.44	overrange	27.3	10000	260	
1101	6.78	753.73	-27.2	0.02	20.36	68.6	28.0	10000	310	
1106	6.78	756.16	-8.2	0.01	20.35	53.0	28.0	10000	360	
1111	6.78	755.90	-8.7	0.02	20.30	12.94	28.0	10000	410	
1116	6.77	747.9	-26.1	0.08	20.30	8.58 AU	28.0	10000	460	
AN 6/29/23										
Stabilizing Criteria	+/- 0.1 SU	+/- 5%		0.2 mg/L or 10% for DO > 0.5 mg/L (whichever is greater)		< 5 NTUs	< 0.3 ft	> 100 mL < 250 mL	> 3L	

GROUNDWATER SAMPLING LOG SHEET

Client: SCS
Site: Plant Hammond
Well ID: MW-54
Total Depth (ft): 38.8
Depth to Water (ft): 23.3
Well Diameter (in): 2
Well Volume (gal) = 0.041d²h: 2.54
Well Volume (L) = gal * 3.785: 9.61

Project No.: GW05816
Location: AP-1
Pump Type/Model: monsoon
Tubing Material: Poly
Pump Intake Depth (ft): 33.8
Start/Stop Purge Time: 1125/1237
Purge Rate (mL/min): 250
Total Purge Volume (L): 18

Sampling Date: 6/29/23
Sampler's Name: AN
Sample Collection Time: -
Sample Purge Rate (mL/min): -
Sample ID: -
Laboratory Analyses: -

d = well diameter (inches); h = length of water column (feet)

Well Type: ☒ Flush ☐ Stick Up
Well Lock: Yes ☒ No
Well Cap Condition: ☒ Good ☐ Replace
Well Tag Present: ☒ Yes ☐ No

Purge Method: Low-Flow Well Volume Other: -
Sampling Method: Pump Discharge Other: -

QA/QC Collected? -
QA/QC I.D. -

All sample containers requiring chemical preservation properly preserved prior to demob from well? Yes No

Time	pH (SU)	Spec. Cond. (µS/cm)	ORP (mV)	DO (mg/L)	Temp. (°C)	Turbidity (NTUs)	DTW (ft btoe)	Purge Rate (mL/min)	Purged Volume (L)	Notes (Purge method, water clarity, odor, purge rate, issues with pump/well/weather/etc.)
1127	6.69	748.01	-2.0	0.30	22.48	11.5	23.0	250	0.5	
1137	6.73	750.46	-22.8	0.15	24.17	12.80	23.0	250	1.75	
1137	6.74	739.19	-210.3	0.12	24.78	11.44	23.0	250	3	
1142	6.74	706.06	-26.6	0.11	23.82	37.7	23.0	250	4.25	
1147	6.71	708.08	-26.6	0.12	23.33	67.0	23.0	250	8.5	
1152	6.71	718.13	-28.5	0.11	24.04	56.1	23.0	250	6.75	
1157	6.71	723.43	-29.9	0.11	25.29	50.4	23.0	250	8	
1202	6.72	707.70	-8.4	0.10	25.15	7.0	23.0	250	9.25	
1207	6.70	704.43	-232	0.14	23.18	58.1	23.0	250	10.5	
1212	6.72	728.86	-24.4	0.08	23.18	27.0	23.0	250	11.75	
1217	6.67	684.7	-13.5	0.28	23.04	605.0	23.0	250	13	
1222	6.73	711.77	-17.7	0.11	22.27	108.0	23.0	250	14.25	
1227	6.77	731.69	-37.4	0.02	21.87	11.1	23.0	250	15.5	
1232	6.77	740.76	-16.0	0.09	21.87	5.18	23.0	250	16.75	
1237	6.77	746.91	-36.5	0.02	21.85	3.54	21.85	250	18	
AN 6/29/23										
Stabilizing Criteria	+/- 0.1 SU	+/- 5%		0.2 mg/L or 10% for DO > 0.5 mg/L (whichever is greater)		< 5 NTUs	< 0.3 ft	> 100 mL < 250 mL	> 3L	

EQUIPMENT CALIBRATION LOG

Field Technician: Amana Meely

Date: 6/27/23

Time (start): 0735

Time (finish): 0755

smarTroll SN: 883553

Turbidity Meter Type: LaMotte 2020we

SN: 7007-1416

Weather Conditions: 66-89°, sunny

Facility and Unit: Plant Hammond

Project No.: GW6581

Calibration log

	Standard Lot # / Date of Expiration	Temp of Standard (°C)	Value of Standard	Initial Reading	Post-Cal Reading	Acceptable Range	Pass?	Comments
Specific Conductance (µS/cm)	22250153	27.06	4490	4561.1	4486.0	+/- 5 %	☒ Yes No	
pH (4)	11/23		4.00	4.18	3.99	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (4) check	—	—	4.00	—	—	+/- 0.1 SU	Yes No	
pH (7)	2216893 11/23	26.72	7.00	6.97	7.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (7) check	—	—	7.00	—	—	+/- 0.1 SU	Yes No	
pH (10)	21320202 12/23	26.92	10.00	9.89	10.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (10) check	—	—	10.00	—	—	+/- 0.1 SU	Yes No	
ORP (mV)	2390144 11/23	25.06	228	217.0	228.2	+/- 20mV	☒ Yes No	
DO (%) (1pt, 100% water saturated air cal)			100	98.78%	99.78%	+/- 6 % saturation	☒ Yes No	
Turbidity 0 NTU			0	0.00	-0.01	+/- 0.5 NTU	☒ Yes No	
Turbidity 1 NTU			1.00	0.37	0.99	+/- 0.5 NTU	☒ Yes No	
Turbidity 10 NTU			10.00	12.42	9.87	+/- 0.5 NTU	☒ Yes No	

EQUIPMENT CALIBRATION LOG

Field Technician: Alan Avery

Date: 6/17/23

Time (start): 0730

Time (finish): 0800

smarTroll SN: 883553

Turbidity Meter Type: LaMotte 2020we

SN: 7007-1416

Weather Conditions: 62-92° sunny

Facility and Unit: Plant Hammond

Project No: GW6581

Calibration log

	Standard Lot # / Date of Expiration	Temp of Standard (°C)	Value of Standard	Initial Reading	Post-Cal Reading	Acceptable Range	Pass?	Comments
Specific Conductance (µS/cm)	22250153	24.51	4490	4435.3	4490.8	+/- 5 %	☒ Yes No	
pH (4)	11/23		4.00	4.21	3.99	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (4) check	-	-	4.00	-	-	+/- 0.1 SU	Yes No	
pH (7)	2210893 11/23	23.80	7.00	7.00	7.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (7) check	-	-	7.00	-	-	+/- 0.1 SU	Yes No	
pH (10)	21320202 12/23	24.24	10.00	9.85	10.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (10) check	-	-	10.00	-	-	+/- 0.1 SU	Yes No	
ORP (mV)	21390144 11/23	22.83	228	231	228.4	+/- 20mV	☒ Yes No	
DO (%) (1pt, 100% water saturated air cal)			100	98.60	100.52	+/- 6 % saturation	☒ Yes No	
Turbidity 0 NTU			0	-0.02	0.00	+/- 0.5 NTU	☒ Yes No	
Turbidity 1 NTU			1.00	0.62	0.75	+/- 0.5 NTU	☒ Yes No	
Turbidity 10 NTU			10.00	12.35	9.96	+/- 0.5 NTU	☒ Yes No	

EQUIPMENT CALIBRATION LOG

Field Technician: Ana Neeley

Date: 6/29/23

Time (start): 0735

Time (finish): 0755

smarTroll SN: 883553

Turbidity Meter Type: LaMotte 2020we

SN: 7007-1416

Weather Conditions: 65-94° sunny

Facility and Unit: Plant Hammond

Project No.: GW6581

Calibration log

	Standard Lot # / Date of Expiration	Temp of Standard (°C)	Value of Standard	Initial Reading	Post-Cal Reading	Acceptable Range	Pass?	Comments
Specific Conductance (µS/cm)	22250153	25.95	4490	4478.9	4494.5	+/- 5 %	☒ Yes ☐ No	
pH (4)	11/23		4.00	4.24	3.99	+/- 0.1 SU	☒ Yes ☐ No	
Mid-Day pH (4) check	-	-	4.00	-	-	+/- 0.1 SU	Yes ☐ No	
pH (7)	2216893	25.14	7.00	6.91	7.00	+/- 0.1 SU	☒ Yes ☐ No	
Mid-Day pH (7) check	11/23		7.00	-	-	+/- 0.1 SU	Yes ☐ No	
pH (10)	21320202	25.92	10.00	9.86	10.00	+/- 0.1 SU	☒ Yes ☐ No	
Mid-Day pH (10) check	12/23		10.00	-	-	+/- 0.1 SU	Yes ☐ No	
ORP (mV)	21390144	23.50	228	226.2	228.0	+/- 20mV	☒ Yes ☐ No	
DO (%) (1pt, 100% water saturated air cal)	11/23		100	99.65	100.48	+/- 6 % saturation	☒ Yes ☐ No	
Turbidity 0 NTU			0	0.27	0.00	+/- 0.5 NTU	☒ Yes ☐ No	
Turbidity 1 NTU			1.00	0.42	0.95	+/- 0.5 NTU	☒ Yes ☐ No	
Turbidity 10 NTU			10.00	9.82	10.04	+/- 0.5 NTU	☒ Yes ☐ No	

APPENDIX D

Certified Well Survey Data

Well ID	Casing Northing	Casing Easting	Top of Casing Elevation	Nail or Pad Northing	Nail or Pad Easting	Nail or Pad Elevation	Description
MW-53	1548835.51	1942399.62	580.59	1548835.08	1942400.25	577.64	NAIL ON PAD
PT-09	1549049.74	1942393.11	580.35	1549049.80	1942394.19	577.33	NAIL ON PAD
PT-10	1549040.34	1942413.88	580.44	1549040.30	1942415.26	577.39	NAIL ON PAD
Benchmark	Northing	Easting	Elevation				
BM-H3	1548237.413	1941013.571	574.63				

SURVEY DATA CERTIFICATION FOR SOUTHERN COMPANY TO DETERMINE NORTHING, EASTING, AND VERTICAL ELEVATION OF THE NAIL IN THE CONCRETE PAD & THE PVC WELL CASING. DATE OF FIELD SURVEY & INSPECTION: 07/11/2023. FIELD SURVEY POSITIONAL TOLERANCE=0.5 FEET HORIZONTAL-NAD'83, 0.01 VERTICAL-NAVD '88. EQUIPMENT USED FOR HORIZONTAL LOCATION: TRIMBLE R12 RTK GPS & TRIMBLE S5 ROBOTIC TOTAL STATION. THE VERTICAL LOCATION OF EACH SURVEYED POINT WAS ESTABLISHED BASED UPON LEVEL RUNS WITH A DIGITAL LEVEL LOOP FROM VERTICAL CONTROL ESTABLISHED BY ON-SITE BENCHMARK BM-H3 SET BY GEL SOLUTIONS USING A TRIMBLE DINI LEVEL

Derek Bradner

7/17/2023



COA - LS003119

Exp. 12/31/2023

Well ID	Casing Northing	Casing Easting	Top of Casing	Nail or Pad Northing	Nail or Pad Easting	Nail or Pad Elevation	Description
MW-54	1548699.509	1940805.028	592.66	1548699.426	1940804.22	592.977	Nail on Pad
PT-07	1548675.239	1940933.391	591.75	1548675.251	1940932.71	591.998	Nail on Pad
PT-08	1548666.824	1940929.582	591.83	1548666.667	1940928.983	592.104	Nail on Pad
Benchmark	Northing	Easting	Elevation				
BM-H3	1548237.413	1941013.571	574.63				

SURVEY DATA CERTIFICATION FOR SOUTHERN COMPANY TO DETERMINE NORTHING, EASTING, AND VERTICAL ELEVATION OF THE NAIL IN THE CONCRETE PAD & THE PVC WELL CASING. DATE OF FIELD SURVEY & INSPECTION: 08/29/2023. FIELD SURVEY POSITIONAL TOLERANCE=0.5 FEET HORIZONTAL-NAD'83, 0.01 VERTICAL-NAVD '88. EQUIPMENT USED FOR HORIZONTAL LOCATION: TRIMBLE R12 RTK GPS & TRIMBLE S5 ROBOTIC TOTAL STATION. THE VERTICAL LOCATION OF EACH SURVEYED POINT WAS ESTABLISHED BASED UPON LEVEL RUNS WITH A DIGITAL LEVEL LOOP FROM VERTICAL CONTROL ESTABLISHED BY ON-SITE BENCHMARK BM-H3 SET BY GEL SOLUTIONS USING A TRIMBLE DINI LEVEL

Derek Bradner

8/30/2023



COA - LS003119

Exp. 12/31/2023

APPENDIX B

Baseline Analytical Laboratory Results and Field Sampling Forms

Laboratory Analytical Reports



July 28, 2023

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1
Pace Project No.: 92677694

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on July 17, 2023. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Charlotte
- Pace Analytical Services - Peachtree Corners, GA

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
(704)875-9092
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1

Pace Project No.: 92677694

Pace Analytical Services Charlotte

South Carolina Laboratory ID: 99006
9800 Kinsey Ave. Ste 100, Huntersville, NC 28078
North Carolina Drinking Water Certification #: 37706
North Carolina Field Services Certification #: 5342
North Carolina Wastewater Certification #: 12
South Carolina Laboratory ID: 99006

South Carolina Certification #: 99006001
South Carolina Drinking Water Cert. #: 99006003
Florida/NELAP Certification #: E87627
Kentucky UST Certification #: 84
Louisiana DoH Drinking Water #: LA029
Virginia/VELAP Certification #: 460221

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804
Florida/NELAP Certification #: E87648
North Carolina Drinking Water Certification #: 37712
North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030
South Carolina Certification #: 99030001
Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092
Florida DOH Certification #: E87315
Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381
South Carolina Certification #: 98011001
Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1

Pace Project No.: 92677694

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92677694001	HAM-HGWC-8	Water	07/13/23 10:35	07/17/23 12:30
92677694002	HAM-PT-09	Water	07/13/23 12:47	07/17/23 12:30
92677694003	HAM-PT-10	Water	07/13/23 14:15	07/17/23 12:30
92677694004	HAM-PT-07	Water	07/13/23 16:22	07/17/23 12:30
92677694005	HAM-PT-08	Water	07/13/23 17:51	07/17/23 12:30
92677694006	HAM-AP1-FD-01	Water	07/13/23 00:00	07/17/23 12:30
92677694007	HAM-AP1-FB-01	Water	07/17/23 08:40	07/17/23 12:30
92677694008	HAM-HGWC-13	Water	07/17/23 11:47	07/17/23 12:30

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92677694

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92677694001	HAM-HGWC-8	EPA 6010D	MS	6
		EPA 6020B	CW1	12
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92677694002	HAM-PT-09	EPA 6010D	MS	6
		EPA 6020B	CW1	12
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92677694003	HAM-PT-10	EPA 6010D	MS	6
		EPA 6020B	CW1	12
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92677694004	HAM-PT-07	EPA 6010D	MS	6
		EPA 6020B	CW1	12
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92677694005	HAM-PT-08	EPA 6010D	MS	6
		EPA 6020B	CW1	12
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92677694006	HAM-AP1-FD-01	EPA 6010D	MS	6
		EPA 6020B	CW1	12

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92677694

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92677694007	HAM-AP1-FB-01	EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	MS	6
		EPA 6020B	CW1	12
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	MS	6
		EPA 6020B	CW1	12
92677694008	HAM-HGWC-13	EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	MS	6
		EPA 6020B	CW1	12

PASI-A = Pace Analytical Services - Asheville

PASI-C = Pace Analytical Services - Charlotte

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92677694

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92677694001	HAM-HGWC-8					
	Performed by	CUSTOMER			07/17/23 17:16	
	pH	6.65	Std. Units		07/17/23 17:16	
EPA 6010D	Manganese	0.28	mg/L	0.040	07/20/23 15:39	
EPA 6010D	Potassium	6.9	mg/L	0.50	07/20/23 15:39	
EPA 6010D	Sodium	8.8	mg/L	1.0	07/20/23 15:39	M1
EPA 6010D	Calcium	107	mg/L	1.0	07/20/23 15:39	M1
EPA 6010D	Magnesium	14.9	mg/L	0.050	07/20/23 15:39	M1
EPA 6010D	Iron	0.27	mg/L	0.040	07/25/23 15:53	
EPA 6020B	Barium	0.047	mg/L	0.0050	07/19/23 17:55	
EPA 6020B	Beryllium	0.000073J	mg/L	0.00050	07/19/23 17:55	
EPA 6020B	Boron	2.0	mg/L	0.20	07/21/23 16:37	
EPA 6020B	Cadmium	0.00031J	mg/L	0.00050	07/19/23 17:55	
EPA 6020B	Cobalt	0.0015J	mg/L	0.0050	07/19/23 17:55	
EPA 6020B	Lithium	0.0015J	mg/L	0.030	07/19/23 17:55	
EPA 6020B	Molybdenum	0.30	mg/L	0.010	07/19/23 17:55	
EPA 6020B	Thallium	0.00026J	mg/L	0.0010	07/19/23 17:55	
SM 2540C-2015	Total Dissolved Solids	513	mg/L	25.0	07/18/23 15:24	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	136	mg/L	5.0	07/19/23 19:16	
SM 2320B-2011	Alkalinity, Total as CaCO3	136	mg/L	5.0	07/19/23 19:16	
EPA 300.0 Rev 2.1 1993	Chloride	47.9	mg/L	1.0	07/19/23 03:12	
EPA 300.0 Rev 2.1 1993	Fluoride	0.49	mg/L	0.10	07/19/23 03:12	
EPA 300.0 Rev 2.1 1993	Sulfate	163	mg/L	3.0	07/19/23 09:10	
92677694002	HAM-PT-09					
	Performed by	CUSTOMER			07/17/23 17:16	
	pH	6.57	Std. Units		07/17/23 17:16	
EPA 6010D	Iron	0.33	mg/L	0.040	07/25/23 16:08	
EPA 6010D	Manganese	0.79	mg/L	0.040	07/20/23 15:59	
EPA 6010D	Potassium	6.8	mg/L	0.50	07/20/23 15:59	
EPA 6010D	Sodium	10.6	mg/L	1.0	07/20/23 15:59	
EPA 6010D	Calcium	110	mg/L	1.0	07/20/23 15:59	
EPA 6010D	Magnesium	15.6	mg/L	0.050	07/20/23 15:59	
EPA 6020B	Antimony	0.0027J	mg/L	0.0030	07/19/23 18:19	
EPA 6020B	Barium	0.053	mg/L	0.0050	07/19/23 18:19	
EPA 6020B	Beryllium	0.000077J	mg/L	0.00050	07/19/23 18:19	
EPA 6020B	Boron	2.1	mg/L	0.20	07/21/23 16:55	
EPA 6020B	Cobalt	0.0045J	mg/L	0.0050	07/19/23 18:19	
EPA 6020B	Lithium	0.0013J	mg/L	0.030	07/19/23 18:19	
EPA 6020B	Molybdenum	0.065	mg/L	0.010	07/19/23 18:19	
SM 2540C-2015	Total Dissolved Solids	534	mg/L	25.0	07/18/23 15:24	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	144	mg/L	5.0	07/19/23 19:26	
SM 2320B-2011	Alkalinity, Total as CaCO3	144	mg/L	5.0	07/19/23 19:26	
EPA 300.0 Rev 2.1 1993	Chloride	55.3	mg/L	1.0	07/19/23 03:27	
EPA 300.0 Rev 2.1 1993	Fluoride	0.24	mg/L	0.10	07/19/23 03:27	
EPA 300.0 Rev 2.1 1993	Sulfate	160	mg/L	3.0	07/19/23 09:53	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92677694

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92677694003	HAM-PT-10					
	Performed by	CUSTOMER			07/17/23 17:16	
	pH	7.01	Std. Units		07/17/23 17:16	
EPA 6010D	Manganese	3.5	mg/L	0.040	07/20/23 16:14	
EPA 6010D	Potassium	7.1	mg/L	0.50	07/20/23 16:14	
EPA 6010D	Sodium	10.5	mg/L	1.0	07/20/23 16:14	
EPA 6010D	Calcium	127	mg/L	1.0	07/20/23 16:14	
EPA 6010D	Magnesium	16.8	mg/L	0.050	07/20/23 16:14	
EPA 6010D	Iron	3.1	mg/L	0.040	07/25/23 16:12	
EPA 6020B	Barium	0.074	mg/L	0.0050	07/19/23 18:25	
EPA 6020B	Boron	2.2	mg/L	0.20	07/21/23 17:01	
EPA 6020B	Cobalt	0.0026J	mg/L	0.0050	07/19/23 18:25	
EPA 6020B	Lithium	0.0014J	mg/L	0.030	07/19/23 18:25	
EPA 6020B	Molybdenum	0.10	mg/L	0.010	07/19/23 18:25	
SM 2540C-2015	Total Dissolved Solids	557	mg/L	25.0	07/18/23 15:24	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	185	mg/L	5.0	07/20/23 16:41	
SM 2320B-2011	Alkalinity, Total as CaCO3	185	mg/L	5.0	07/20/23 16:41	
EPA 300.0 Rev 2.1 1993	Chloride	67.2	mg/L	1.0	07/19/23 04:10	
EPA 300.0 Rev 2.1 1993	Fluoride	0.33	mg/L	0.10	07/19/23 04:10	
EPA 300.0 Rev 2.1 1993	Sulfate	145	mg/L	3.0	07/19/23 10:07	
92677694004	HAM-PT-07					
	Performed by	CUSTOMER			07/17/23 17:16	
	pH	6.76	Std. Units		07/17/23 17:16	
EPA 6010D	Manganese	8.2	mg/L	0.040	07/20/23 16:19	
EPA 6010D	Potassium	6.0	mg/L	0.50	07/20/23 16:19	
EPA 6010D	Sodium	6.1	mg/L	1.0	07/20/23 16:19	
EPA 6010D	Calcium	168	mg/L	1.0	07/20/23 16:19	
EPA 6010D	Magnesium	18.5	mg/L	0.050	07/20/23 16:19	
EPA 6010D	Iron	23.8	mg/L	0.040	07/25/23 16:17	
EPA 6020B	Arsenic	0.34	mg/L	0.010	07/19/23 18:30	
EPA 6020B	Barium	0.056	mg/L	0.0050	07/19/23 18:30	
EPA 6020B	Beryllium	0.00012J	mg/L	0.00050	07/19/23 18:30	
EPA 6020B	Boron	1.0	mg/L	0.20	07/21/23 17:07	
EPA 6020B	Cobalt	0.13	mg/L	0.0050	07/19/23 18:30	
EPA 6020B	Lithium	0.060	mg/L	0.030	07/19/23 18:30	
EPA 6020B	Molybdenum	0.017	mg/L	0.010	07/19/23 18:30	
EPA 6020B	Thallium	0.00024J	mg/L	0.0010	07/19/23 18:30	
SM 2540C-2015	Total Dissolved Solids	808	mg/L	25.0	07/18/23 15:24	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	102	mg/L	5.0	07/20/23 16:53	
SM 2320B-2011	Alkalinity, Total as CaCO3	102	mg/L	5.0	07/20/23 16:53	
EPA 300.0 Rev 2.1 1993	Chloride	15.7	mg/L	1.0	07/19/23 04:24	
EPA 300.0 Rev 2.1 1993	Fluoride	0.36	mg/L	0.10	07/19/23 04:24	
EPA 300.0 Rev 2.1 1993	Sulfate	411	mg/L	9.0	07/19/23 10:21	
92677694005	HAM-PT-08					
	Performed by	CUSTOMER			07/17/23 17:17	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92677694

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92677694005	HAM-PT-08					
	pH	6.66	Std. Units		07/17/23 17:17	
EPA 6010D	Manganese	8.7	mg/L	0.040	07/20/23 16:24	
EPA 6010D	Potassium	6.0	mg/L	0.50	07/20/23 16:24	
EPA 6010D	Sodium	6.9	mg/L	1.0	07/20/23 16:24	
EPA 6010D	Calcium	161	mg/L	1.0	07/20/23 16:24	
EPA 6010D	Magnesium	18.9	mg/L	0.050	07/20/23 16:24	
EPA 6010D	Iron	24.2	mg/L	0.040	07/25/23 16:38	
EPA 6020B	Arsenic	0.33	mg/L	0.010	07/19/23 18:36	
EPA 6020B	Barium	0.051	mg/L	0.0050	07/19/23 18:36	
EPA 6020B	Beryllium	0.00011J	mg/L	0.00050	07/19/23 18:36	
EPA 6020B	Boron	1.0	mg/L	0.20	07/21/23 17:13	
EPA 6020B	Cobalt	0.031	mg/L	0.0050	07/19/23 18:36	
EPA 6020B	Lithium	0.065	mg/L	0.030	07/19/23 18:36	
EPA 6020B	Molybdenum	0.0079J	mg/L	0.010	07/19/23 18:36	
SM 2540C-2015	Total Dissolved Solids	734	mg/L	25.0	07/18/23 15:25	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	107	mg/L	5.0	07/20/23 17:03	
SM 2320B-2011	Alkalinity, Total as CaCO3	107	mg/L	5.0	07/20/23 17:03	
SM 4500-S2D-2011	Sulfide	0.036J	mg/L	0.10	07/20/23 03:42	
EPA 300.0 Rev 2.1 1993	Chloride	17.0	mg/L	1.0	07/19/23 04:38	
EPA 300.0 Rev 2.1 1993	Fluoride	0.36	mg/L	0.10	07/19/23 04:38	
EPA 300.0 Rev 2.1 1993	Sulfate	417	mg/L	8.0	07/19/23 12:00	
92677694006	HAM-AP1-FD-01					
EPA 6010D	Iron	24.6	mg/L	0.040	07/25/23 16:48	
EPA 6010D	Manganese	8.6	mg/L	0.040	07/20/23 16:29	
EPA 6010D	Potassium	6.4	mg/L	0.50	07/20/23 16:29	
EPA 6010D	Sodium	6.6	mg/L	1.0	07/20/23 16:29	
EPA 6010D	Calcium	180	mg/L	1.0	07/20/23 16:29	
EPA 6010D	Magnesium	19.6	mg/L	0.050	07/20/23 16:29	
EPA 6020B	Arsenic	0.34	mg/L	0.010	07/19/23 18:54	
EPA 6020B	Barium	0.057	mg/L	0.0050	07/19/23 18:54	
EPA 6020B	Beryllium	0.00011J	mg/L	0.00050	07/19/23 18:54	
EPA 6020B	Boron	0.99	mg/L	0.20	07/21/23 17:19	
EPA 6020B	Cobalt	0.14	mg/L	0.0050	07/19/23 18:54	
EPA 6020B	Lithium	0.060	mg/L	0.030	07/19/23 18:54	
EPA 6020B	Molybdenum	0.018	mg/L	0.010	07/19/23 18:54	
EPA 6020B	Thallium	0.00025J	mg/L	0.0010	07/19/23 18:54	
SM 2540C-2015	Total Dissolved Solids	804	mg/L	25.0	07/18/23 15:25	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	102	mg/L	5.0	07/20/23 17:12	
SM 2320B-2011	Alkalinity, Total as CaCO3	102	mg/L	5.0	07/20/23 17:12	
EPA 300.0 Rev 2.1 1993	Chloride	15.6	mg/L	1.0	07/19/23 04:53	
EPA 300.0 Rev 2.1 1993	Fluoride	0.31	mg/L	0.10	07/19/23 04:53	
EPA 300.0 Rev 2.1 1993	Sulfate	428	mg/L	9.0	07/19/23 12:56	
92677694008	HAM-HGWC-13					
	Performed by	CUSTOMER			07/17/23 17:17	
	pH	6.67	Std. Units		07/17/23 17:17	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92677694

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92677694008	HAM-HGWC-13					
EPA 6010D	Iron	7.2	mg/L	0.040	07/20/23 16:39	
EPA 6010D	Manganese	8.9	mg/L	0.040	07/20/23 16:39	
EPA 6010D	Potassium	6.0	mg/L	0.50	07/20/23 16:39	
EPA 6010D	Sodium	6.8	mg/L	1.0	07/20/23 16:39	
EPA 6010D	Calcium	179	mg/L	1.0	07/20/23 16:39	
EPA 6010D	Magnesium	19.5	mg/L	0.050	07/20/23 16:39	
EPA 6020B	Arsenic	0.63	mg/L	0.010	07/19/23 19:06	
EPA 6020B	Barium	0.056	mg/L	0.0050	07/19/23 19:06	
EPA 6020B	Beryllium	0.00012J	mg/L	0.00050	07/19/23 19:06	
EPA 6020B	Boron	1.0	mg/L	0.20	07/21/23 17:43	
EPA 6020B	Cobalt	0.018	mg/L	0.0050	07/19/23 19:06	
EPA 6020B	Lithium	0.048	mg/L	0.030	07/19/23 19:06	
EPA 6020B	Molybdenum	0.017	mg/L	0.010	07/19/23 19:06	
EPA 6020B	Thallium	0.00030J	mg/L	0.0010	07/19/23 19:06	
SM 2540C-2015	Total Dissolved Solids	817	mg/L	25.0	07/18/23 15:31	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	140	mg/L	5.0	07/20/23 17:26	
SM 2320B-2011	Alkalinity, Total as CaCO3	140	mg/L	5.0	07/20/23 17:26	
EPA 300.0 Rev 2.1 1993	Chloride	17.8	mg/L	1.0	07/19/23 05:50	
EPA 300.0 Rev 2.1 1993	Fluoride	0.32	mg/L	0.10	07/19/23 05:50	
EPA 300.0 Rev 2.1 1993	Sulfate	393	mg/L	8.0	07/19/23 13:10	M1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92677694

Sample: HAM-HGWC-8		Lab ID: 92677694001		Collected: 07/13/23 10:35		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Field Data		Analytical Method: Pace Analytical Services - Charlotte							
Performed by	CUSTOMER				1		07/17/23 17:16		
pH	6.65	Std. Units			1		07/17/23 17:16		
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Manganese	0.28	mg/L	0.040	0.011	1	07/20/23 09:50	07/20/23 15:39	7439-96-5	
Potassium	6.9	mg/L	0.50	0.15	1	07/20/23 09:50	07/20/23 15:39	7440-09-7	
Sodium	8.8	mg/L	1.0	0.58	1	07/20/23 09:50	07/20/23 15:39	7440-23-5	M1
Calcium	107	mg/L	1.0	0.12	1	07/20/23 09:50	07/20/23 15:39	7440-70-2	M1
Magnesium	14.9	mg/L	0.050	0.012	1	07/20/23 09:50	07/20/23 15:39	7439-95-4	M1
Iron	0.27	mg/L	0.040	0.025	1	07/20/23 09:50	07/25/23 15:53	7439-89-6	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.0012	1	07/18/23 13:46	07/19/23 17:55	7440-36-0	
Arsenic	ND	mg/L	0.010	0.0037	1	07/18/23 13:46	07/19/23 17:55	7440-38-2	
Barium	0.047	mg/L	0.0050	0.00067	1	07/18/23 13:46	07/19/23 17:55	7440-39-3	
Beryllium	0.000073J	mg/L	0.00050	0.000054	1	07/18/23 13:46	07/19/23 17:55	7440-41-7	
Boron	2.0	mg/L	0.20	0.043	5	07/18/23 13:46	07/21/23 16:37	7440-42-8	
Cadmium	0.00031J	mg/L	0.00050	0.00011	1	07/18/23 13:46	07/19/23 17:55	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	07/18/23 13:46	07/19/23 17:55	7440-47-3	
Cobalt	0.0015J	mg/L	0.0050	0.00039	1	07/18/23 13:46	07/19/23 17:55	7440-48-4	
Lithium	0.0015J	mg/L	0.030	0.00073	1	07/18/23 13:46	07/19/23 17:55	7439-93-2	
Molybdenum	0.30	mg/L	0.010	0.00074	1	07/18/23 13:46	07/19/23 17:55	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	07/18/23 13:46	07/19/23 17:55	7782-49-2	
Thallium	0.00026J	mg/L	0.0010	0.00018	1	07/18/23 13:46	07/19/23 17:55	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	07/27/23 12:00	07/27/23 14:51	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	513	mg/L	25.0	25.0	1		07/18/23 15:24		
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO3)	136	mg/L	5.0	5.0	1		07/19/23 19:16		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		07/19/23 19:16		
Alkalinity, Total as CaCO3	136	mg/L	5.0	5.0	1		07/19/23 19:16		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-HGWC-8		Lab ID: 92677694001		Collected: 07/13/23 10:35		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		07/20/23 03:39	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	47.9	mg/L	1.0	0.60	1		07/19/23 03:12	16887-00-6	
Fluoride	0.49	mg/L	0.10	0.050	1		07/19/23 03:12	16984-48-8	
Sulfate	163	mg/L	3.0	1.5	3		07/19/23 09:10	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-PT-09		Lab ID: 92677694002		Collected: 07/13/23 12:47		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Field Data		Analytical Method: Pace Analytical Services - Charlotte							
Performed by	CUSTOMER				1		07/17/23 17:16		
pH	6.57	Std. Units			1		07/17/23 17:16		
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	0.33	mg/L	0.040	0.025	1	07/20/23 09:50	07/25/23 16:08	7439-89-6	
Manganese	0.79	mg/L	0.040	0.011	1	07/20/23 09:50	07/20/23 15:59	7439-96-5	
Potassium	6.8	mg/L	0.50	0.15	1	07/20/23 09:50	07/20/23 15:59	7440-09-7	
Sodium	10.6	mg/L	1.0	0.58	1	07/20/23 09:50	07/20/23 15:59	7440-23-5	
Calcium	110	mg/L	1.0	0.12	1	07/20/23 09:50	07/20/23 15:59	7440-70-2	
Magnesium	15.6	mg/L	0.050	0.012	1	07/20/23 09:50	07/20/23 15:59	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	0.0027J	mg/L	0.0030	0.0012	1	07/18/23 13:46	07/19/23 18:19	7440-36-0	
Arsenic	ND	mg/L	0.010	0.0037	1	07/18/23 13:46	07/19/23 18:19	7440-38-2	
Barium	0.053	mg/L	0.0050	0.00067	1	07/18/23 13:46	07/19/23 18:19	7440-39-3	
Beryllium	0.000077J	mg/L	0.00050	0.000054	1	07/18/23 13:46	07/19/23 18:19	7440-41-7	
Boron	2.1	mg/L	0.20	0.043	5	07/18/23 13:46	07/21/23 16:55	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	07/18/23 13:46	07/19/23 18:19	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	07/18/23 13:46	07/19/23 18:19	7440-47-3	
Cobalt	0.0045J	mg/L	0.0050	0.00039	1	07/18/23 13:46	07/19/23 18:19	7440-48-4	
Lithium	0.0013J	mg/L	0.030	0.00073	1	07/18/23 13:46	07/19/23 18:19	7439-93-2	
Molybdenum	0.065	mg/L	0.010	0.00074	1	07/18/23 13:46	07/19/23 18:19	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	07/18/23 13:46	07/19/23 18:19	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00018	1	07/18/23 13:46	07/19/23 18:19	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	07/27/23 12:00	07/27/23 14:53	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	534	mg/L	25.0	25.0	1		07/18/23 15:24		
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO3)	144	mg/L	5.0	5.0	1		07/19/23 19:26		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		07/19/23 19:26		
Alkalinity, Total as CaCO3	144	mg/L	5.0	5.0	1		07/19/23 19:26		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-PT-09		Lab ID: 92677694002		Collected: 07/13/23 12:47		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		07/20/23 03:41	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	55.3	mg/L	1.0	0.60	1		07/19/23 03:27	16887-00-6	
Fluoride	0.24	mg/L	0.10	0.050	1		07/19/23 03:27	16984-48-8	
Sulfate	160	mg/L	3.0	1.5	3		07/19/23 09:53	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92677694

Sample: HAM-PT-10		Lab ID: 92677694003		Collected: 07/13/23 14:15		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Field Data									
Analytical Method: Pace Analytical Services - Charlotte									
Performed by	CUSTOMER				1		07/17/23 17:16		
pH	7.01	Std. Units			1		07/17/23 17:16		
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Manganese	3.5	mg/L	0.040	0.011	1	07/20/23 09:50	07/20/23 16:14	7439-96-5	
Potassium	7.1	mg/L	0.50	0.15	1	07/20/23 09:50	07/20/23 16:14	7440-09-7	
Sodium	10.5	mg/L	1.0	0.58	1	07/20/23 09:50	07/20/23 16:14	7440-23-5	
Calcium	127	mg/L	1.0	0.12	1	07/20/23 09:50	07/20/23 16:14	7440-70-2	
Magnesium	16.8	mg/L	0.050	0.012	1	07/20/23 09:50	07/20/23 16:14	7439-95-4	
Iron	3.1	mg/L	0.040	0.025	1	07/20/23 09:50	07/25/23 16:12	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	07/18/23 13:46	07/19/23 18:25	7440-36-0	
Arsenic	ND	mg/L	0.010	0.0037	1	07/18/23 13:46	07/19/23 18:25	7440-38-2	
Barium	0.074	mg/L	0.0050	0.00067	1	07/18/23 13:46	07/19/23 18:25	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000054	1	07/18/23 13:46	07/19/23 18:25	7440-41-7	
Boron	2.2	mg/L	0.20	0.043	5	07/18/23 13:46	07/21/23 17:01	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	07/18/23 13:46	07/19/23 18:25	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	07/18/23 13:46	07/19/23 18:25	7440-47-3	
Cobalt	0.0026J	mg/L	0.0050	0.00039	1	07/18/23 13:46	07/19/23 18:25	7440-48-4	
Lithium	0.0014J	mg/L	0.030	0.00073	1	07/18/23 13:46	07/19/23 18:25	7439-93-2	
Molybdenum	0.10	mg/L	0.010	0.00074	1	07/18/23 13:46	07/19/23 18:25	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	07/18/23 13:46	07/19/23 18:25	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00018	1	07/18/23 13:46	07/19/23 18:25	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	07/27/23 12:00	07/27/23 15:09	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	557	mg/L	25.0	25.0	1		07/18/23 15:24		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	185	mg/L	5.0	5.0	1		07/20/23 16:41		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		07/20/23 16:41		
Alkalinity, Total as CaCO3	185	mg/L	5.0	5.0	1		07/20/23 16:41		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-PT-10		Lab ID: 92677694003		Collected: 07/13/23 14:15		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		07/20/23 03:41	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	67.2	mg/L	1.0	0.60	1		07/19/23 04:10	16887-00-6	
Fluoride	0.33	mg/L	0.10	0.050	1		07/19/23 04:10	16984-48-8	
Sulfate	145	mg/L	3.0	1.5	3		07/19/23 10:07	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92677694

Sample: HAM-PT-07		Lab ID: 92677694004		Collected: 07/13/23 16:22		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Field Data									
Analytical Method: Pace Analytical Services - Charlotte									
Performed by	CUSTOMER				1		07/17/23 17:16		
pH	6.76	Std. Units			1		07/17/23 17:16		
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Manganese	8.2	mg/L	0.040	0.011	1	07/20/23 09:50	07/20/23 16:19	7439-96-5	
Potassium	6.0	mg/L	0.50	0.15	1	07/20/23 09:50	07/20/23 16:19	7440-09-7	
Sodium	6.1	mg/L	1.0	0.58	1	07/20/23 09:50	07/20/23 16:19	7440-23-5	
Calcium	168	mg/L	1.0	0.12	1	07/20/23 09:50	07/20/23 16:19	7440-70-2	
Magnesium	18.5	mg/L	0.050	0.012	1	07/20/23 09:50	07/20/23 16:19	7439-95-4	
Iron	23.8	mg/L	0.040	0.025	1	07/20/23 09:50	07/25/23 16:17	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	07/18/23 13:46	07/19/23 18:30	7440-36-0	
Arsenic	0.34	mg/L	0.010	0.0037	1	07/18/23 13:46	07/19/23 18:30	7440-38-2	
Barium	0.056	mg/L	0.0050	0.00067	1	07/18/23 13:46	07/19/23 18:30	7440-39-3	
Beryllium	0.00012J	mg/L	0.00050	0.000054	1	07/18/23 13:46	07/19/23 18:30	7440-41-7	
Boron	1.0	mg/L	0.20	0.043	5	07/18/23 13:46	07/21/23 17:07	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	07/18/23 13:46	07/19/23 18:30	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	07/18/23 13:46	07/19/23 18:30	7440-47-3	
Cobalt	0.13	mg/L	0.0050	0.00039	1	07/18/23 13:46	07/19/23 18:30	7440-48-4	
Lithium	0.060	mg/L	0.030	0.00073	1	07/18/23 13:46	07/19/23 18:30	7439-93-2	
Molybdenum	0.017	mg/L	0.010	0.00074	1	07/18/23 13:46	07/19/23 18:30	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	07/18/23 13:46	07/19/23 18:30	7782-49-2	
Thallium	0.00024J	mg/L	0.0010	0.00018	1	07/18/23 13:46	07/19/23 18:30	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	07/27/23 12:00	07/27/23 15:12	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	808	mg/L	25.0	25.0	1		07/18/23 15:24		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	102	mg/L	5.0	5.0	1		07/20/23 16:53		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		07/20/23 16:53		
Alkalinity, Total as CaCO3	102	mg/L	5.0	5.0	1		07/20/23 16:53		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-PT-07		Lab ID: 92677694004		Collected: 07/13/23 16:22		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		07/20/23 03:42	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	15.7	mg/L	1.0	0.60	1		07/19/23 04:24	16887-00-6	
Fluoride	0.36	mg/L	0.10	0.050	1		07/19/23 04:24	16984-48-8	
Sulfate	411	mg/L	9.0	4.5	9		07/19/23 10:21	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92677694

Sample: HAM-PT-08		Lab ID: 92677694005		Collected: 07/13/23 17:51		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Field Data		Analytical Method: Pace Analytical Services - Charlotte							
Performed by	CUSTOMER				1		07/17/23 17:17		
pH	6.66	Std. Units			1		07/17/23 17:17		
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Manganese	8.7	mg/L	0.040	0.011	1	07/20/23 09:50	07/20/23 16:24	7439-96-5	
Potassium	6.0	mg/L	0.50	0.15	1	07/20/23 09:50	07/20/23 16:24	7440-09-7	
Sodium	6.9	mg/L	1.0	0.58	1	07/20/23 09:50	07/20/23 16:24	7440-23-5	
Calcium	161	mg/L	1.0	0.12	1	07/20/23 09:50	07/20/23 16:24	7440-70-2	
Magnesium	18.9	mg/L	0.050	0.012	1	07/20/23 09:50	07/20/23 16:24	7439-95-4	
Iron	24.2	mg/L	0.040	0.025	1	07/20/23 09:50	07/25/23 16:38	7439-89-6	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.0012	1	07/18/23 13:46	07/19/23 18:36	7440-36-0	
Arsenic	0.33	mg/L	0.010	0.0037	1	07/18/23 13:46	07/19/23 18:36	7440-38-2	
Barium	0.051	mg/L	0.0050	0.00067	1	07/18/23 13:46	07/19/23 18:36	7440-39-3	
Beryllium	0.00011J	mg/L	0.00050	0.000054	1	07/18/23 13:46	07/19/23 18:36	7440-41-7	
Boron	1.0	mg/L	0.20	0.043	5	07/18/23 13:46	07/21/23 17:13	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	07/18/23 13:46	07/19/23 18:36	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	07/18/23 13:46	07/19/23 18:36	7440-47-3	
Cobalt	0.031	mg/L	0.0050	0.00039	1	07/18/23 13:46	07/19/23 18:36	7440-48-4	
Lithium	0.065	mg/L	0.030	0.00073	1	07/18/23 13:46	07/19/23 18:36	7439-93-2	
Molybdenum	0.0079J	mg/L	0.010	0.00074	1	07/18/23 13:46	07/19/23 18:36	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	07/18/23 13:46	07/19/23 18:36	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00018	1	07/18/23 13:46	07/19/23 18:36	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	07/27/23 12:00	07/27/23 15:14	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	734	mg/L	25.0	25.0	1		07/18/23 15:25		
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO3)	107	mg/L	5.0	5.0	1		07/20/23 17:03		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		07/20/23 17:03		
Alkalinity, Total as CaCO3	107	mg/L	5.0	5.0	1		07/20/23 17:03		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-PT-08		Lab ID: 92677694005		Collected: 07/13/23 17:51		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	0.036J	mg/L	0.10	0.022	1		07/20/23 03:42	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	17.0	mg/L	1.0	0.60	1		07/19/23 04:38	16887-00-6	
Fluoride	0.36	mg/L	0.10	0.050	1		07/19/23 04:38	16984-48-8	
Sulfate	417	mg/L	8.0	4.0	8		07/19/23 12:00	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92677694

Sample: HAM-AP1-FD-01		Lab ID: 92677694006		Collected: 07/13/23 00:00		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	24.6	mg/L	0.040	0.025	1	07/20/23 09:50	07/25/23 16:48	7439-89-6	
Manganese	8.6	mg/L	0.040	0.011	1	07/20/23 09:50	07/20/23 16:29	7439-96-5	
Potassium	6.4	mg/L	0.50	0.15	1	07/20/23 09:50	07/20/23 16:29	7440-09-7	
Sodium	6.6	mg/L	1.0	0.58	1	07/20/23 09:50	07/20/23 16:29	7440-23-5	
Calcium	180	mg/L	1.0	0.12	1	07/20/23 09:50	07/20/23 16:29	7440-70-2	
Magnesium	19.6	mg/L	0.050	0.012	1	07/20/23 09:50	07/20/23 16:29	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	07/18/23 13:46	07/19/23 18:54	7440-36-0	
Arsenic	0.34	mg/L	0.010	0.0037	1	07/18/23 13:46	07/19/23 18:54	7440-38-2	
Barium	0.057	mg/L	0.0050	0.00067	1	07/18/23 13:46	07/19/23 18:54	7440-39-3	
Beryllium	0.00011J	mg/L	0.00050	0.000054	1	07/18/23 13:46	07/19/23 18:54	7440-41-7	
Boron	0.99	mg/L	0.20	0.043	5	07/18/23 13:46	07/21/23 17:19	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	07/18/23 13:46	07/19/23 18:54	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	07/18/23 13:46	07/19/23 18:54	7440-47-3	
Cobalt	0.14	mg/L	0.0050	0.00039	1	07/18/23 13:46	07/19/23 18:54	7440-48-4	
Lithium	0.060	mg/L	0.030	0.00073	1	07/18/23 13:46	07/19/23 18:54	7439-93-2	
Molybdenum	0.018	mg/L	0.010	0.00074	1	07/18/23 13:46	07/19/23 18:54	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	07/18/23 13:46	07/19/23 18:54	7782-49-2	
Thallium	0.00025J	mg/L	0.0010	0.00018	1	07/18/23 13:46	07/19/23 18:54	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	07/27/23 12:00	07/27/23 15:17	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	804	mg/L	25.0	25.0	1		07/18/23 15:25		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	102	mg/L	5.0	5.0	1		07/20/23 17:12		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		07/20/23 17:12		
Alkalinity, Total as CaCO ₃	102	mg/L	5.0	5.0	1		07/20/23 17:12		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		07/20/23 03:42	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	15.6	mg/L	1.0	0.60	1		07/19/23 04:53	16887-00-6	
Fluoride	0.31	mg/L	0.10	0.050	1		07/19/23 04:53	16984-48-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-AP1-FD-01		Lab ID: 92677694006		Collected: 07/13/23 00:00		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Sulfate	428	mg/L	9.0	4.5	9		07/19/23 12:56	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92677694

Sample: HAM-AP1-FB-01		Lab ID: 92677694007		Collected: 07/17/23 08:40		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Manganese	ND	mg/L	0.040	0.011	1	07/20/23 09:50	07/20/23 16:34	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	07/20/23 09:50	07/20/23 16:34	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	07/20/23 09:50	07/20/23 16:34	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	07/20/23 09:50	07/20/23 16:34	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	07/20/23 09:50	07/20/23 16:34	7439-95-4	
Iron	ND	mg/L	0.040	0.025	1	07/20/23 09:50	07/25/23 16:53	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	07/18/23 13:46	07/19/23 19:00	7440-36-0	
Arsenic	ND	mg/L	0.010	0.0037	1	07/18/23 13:46	07/19/23 19:00	7440-38-2	
Barium	ND	mg/L	0.0050	0.00067	1	07/18/23 13:46	07/19/23 19:00	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000054	1	07/18/23 13:46	07/19/23 19:00	7440-41-7	
Boron	ND	mg/L	0.040	0.0086	1	07/18/23 13:46	07/21/23 17:37	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	07/18/23 13:46	07/19/23 19:00	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	07/18/23 13:46	07/19/23 19:00	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00039	1	07/18/23 13:46	07/19/23 19:00	7440-48-4	
Lithium	ND	mg/L	0.030	0.00073	1	07/18/23 13:46	07/19/23 19:00	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00074	1	07/18/23 13:46	07/19/23 19:00	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	07/18/23 13:46	07/19/23 19:00	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00018	1	07/18/23 13:46	07/19/23 19:00	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	07/27/23 12:00	07/27/23 15:19	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		07/18/23 15:30		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		07/20/23 17:22		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		07/20/23 17:22		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		07/20/23 17:22		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		07/20/23 04:00	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		07/19/23 05:07	16887-00-6	
Fluoride	ND	mg/L	0.10	0.050	1		07/19/23 05:07	16984-48-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-AP1-FB-01		Lab ID: 92677694007		Collected: 07/17/23 08:40		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Sulfate	ND	mg/L	1.0	0.50	1		07/19/23 05:07	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-HGWC-13		Lab ID: 92677694008		Collected: 07/17/23 11:47		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Field Data									
Analytical Method: Pace Analytical Services - Charlotte									
Performed by	CUSTOMER				1		07/17/23 17:17		
pH	6.67	Std. Units			1		07/17/23 17:17		
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	7.2	mg/L	0.040	0.025	1	07/20/23 09:50	07/20/23 16:39	7439-89-6	
Manganese	8.9	mg/L	0.040	0.011	1	07/20/23 09:50	07/20/23 16:39	7439-96-5	
Potassium	6.0	mg/L	0.50	0.15	1	07/20/23 09:50	07/20/23 16:39	7440-09-7	
Sodium	6.8	mg/L	1.0	0.58	1	07/20/23 09:50	07/20/23 16:39	7440-23-5	
Calcium	179	mg/L	1.0	0.12	1	07/20/23 09:50	07/20/23 16:39	7440-70-2	
Magnesium	19.5	mg/L	0.050	0.012	1	07/20/23 09:50	07/20/23 16:39	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	07/18/23 13:46	07/19/23 19:06	7440-36-0	
Arsenic	0.63	mg/L	0.010	0.0037	1	07/18/23 13:46	07/19/23 19:06	7440-38-2	
Barium	0.056	mg/L	0.0050	0.00067	1	07/18/23 13:46	07/19/23 19:06	7440-39-3	
Beryllium	0.00012J	mg/L	0.00050	0.000054	1	07/18/23 13:46	07/19/23 19:06	7440-41-7	
Boron	1.0	mg/L	0.20	0.043	5	07/18/23 13:46	07/21/23 17:43	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	07/18/23 13:46	07/19/23 19:06	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	07/18/23 13:46	07/19/23 19:06	7440-47-3	
Cobalt	0.018	mg/L	0.0050	0.00039	1	07/18/23 13:46	07/19/23 19:06	7440-48-4	
Lithium	0.048	mg/L	0.030	0.00073	1	07/18/23 13:46	07/19/23 19:06	7439-93-2	
Molybdenum	0.017	mg/L	0.010	0.00074	1	07/18/23 13:46	07/19/23 19:06	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	07/18/23 13:46	07/19/23 19:06	7782-49-2	
Thallium	0.00030J	mg/L	0.0010	0.00018	1	07/18/23 13:46	07/19/23 19:06	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	07/27/23 12:00	07/27/23 15:22	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	817	mg/L	25.0	25.0	1		07/18/23 15:31		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	140	mg/L	5.0	5.0	1		07/20/23 17:26		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		07/20/23 17:26		
Alkalinity, Total as CaCO3	140	mg/L	5.0	5.0	1		07/20/23 17:26		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-HGWC-13		Lab ID: 92677694008		Collected: 07/17/23 11:47		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		07/20/23 04:00	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	17.8	mg/L	1.0	0.60	1		07/19/23 05:50	16887-00-6	
Fluoride	0.32	mg/L	0.10	0.050	1		07/19/23 05:50	16984-48-8	
Sulfate	393	mg/L	8.0	4.0	8		07/19/23 13:10	14808-79-8	M1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch: 787863 Analysis Method: EPA 6010D
QC Batch Method: EPA 3010A Analysis Description: 6010D ATL
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008

METHOD BLANK: 4084625 Matrix: Water
Associated Lab Samples: 92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	07/20/23 15:30	
Iron	mg/L	ND	0.040	0.025	07/25/23 15:43	
Magnesium	mg/L	ND	0.050	0.012	07/20/23 15:30	
Manganese	mg/L	ND	0.040	0.011	07/20/23 15:30	
Potassium	mg/L	ND	0.50	0.15	07/20/23 15:30	
Sodium	mg/L	ND	1.0	0.58	07/20/23 15:30	

LABORATORY CONTROL SAMPLE: 4084626

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	0.92J	92	80-120	
Iron	mg/L	1	0.99	99	80-120	
Magnesium	mg/L	1	0.93	93	80-120	
Manganese	mg/L	1	0.94	94	80-120	
Potassium	mg/L	1	0.88	88	80-120	
Sodium	mg/L	1	0.84J	84	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4085060 4085061

Parameter	Units	92677694001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Calcium	mg/L	107	1	1	109	104	196	-279	75-125	4	20	M1
Iron	mg/L	0.27	1	1	1.3	1.3	99	105	75-125	5	20	
Magnesium	mg/L	14.9	1	1	16.2	15.6	128	74	75-125	3	20	M1
Manganese	mg/L	0.28	1	1	1.2	1.3	96	100	75-125	3	20	
Potassium	mg/L	6.9	1	1	8.1	7.8	118	90	75-125	3	20	
Sodium	mg/L	8.8	1	1	9.9	9.5	111	73	75-125	4	20	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch:	787489	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008		

METHOD BLANK: 4082463

Matrix: Water

Associated Lab Samples: 92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.0012	07/19/23 17:43	
Arsenic	mg/L	ND	0.010	0.0037	07/19/23 17:43	
Barium	mg/L	ND	0.0050	0.00067	07/19/23 17:43	
Beryllium	mg/L	ND	0.00050	0.000054	07/19/23 17:43	
Boron	mg/L	ND	0.040	0.0086	07/21/23 16:25	
Cadmium	mg/L	ND	0.00050	0.00011	07/19/23 17:43	
Chromium	mg/L	ND	0.0050	0.0011	07/19/23 17:43	
Cobalt	mg/L	ND	0.0050	0.00039	07/19/23 17:43	
Lithium	mg/L	ND	0.030	0.00073	07/19/23 17:43	
Molybdenum	mg/L	ND	0.010	0.00074	07/19/23 17:43	
Selenium	mg/L	ND	0.0050	0.0014	07/19/23 17:43	
Thallium	mg/L	ND	0.0010	0.00018	07/19/23 17:43	

LABORATORY CONTROL SAMPLE: 4082464

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.11	107	80-120	
Arsenic	mg/L	0.1	0.099	99	80-120	
Barium	mg/L	0.1	0.096	96	80-120	
Beryllium	mg/L	0.1	0.10	102	80-120	
Boron	mg/L	1	1.1	110	80-120	
Cadmium	mg/L	0.1	0.10	103	80-120	
Chromium	mg/L	0.1	0.10	102	80-120	
Cobalt	mg/L	0.1	0.10	101	80-120	
Lithium	mg/L	0.1	0.10	103	80-120	
Molybdenum	mg/L	0.1	0.10	102	80-120	
Selenium	mg/L	0.1	0.10	101	80-120	
Thallium	mg/L	0.1	0.097	97	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4082465 4082466

Parameter	Units	MS		MSD		MS		MSD		% Rec Limits	Max	
		92677694001	Spike Conc.	Spike Conc.	Result	Result	% Rec	% Rec	Result		RPD	RPD
Antimony	mg/L	ND	0.1	0.1	0.11	0.11	109	110	75-125	1	20	
Arsenic	mg/L	ND	0.1	0.1	0.10	0.11	104	106	75-125	2	20	
Barium	mg/L	0.047	0.1	0.1	0.16	0.16	114	113	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4082465 4082466											
Parameter	Units	92677694001	MS	MSD	MS	MSD	MS	MSD	% Rec	Limits	Max
		Result	Spike	Spike							
			Conc.	Conc.	Result	Result	% Rec	% Rec			RPD
Beryllium	mg/L	0.000073J	0.1	0.1	0.095	0.096	95	96	75-125	1	20
Boron	mg/L	2.0	1	1	3.1	2.9	108	94	75-125	5	20
Cadmium	mg/L	0.00031J	0.1	0.1	0.10	0.10	102	104	75-125	1	20
Chromium	mg/L	ND	0.1	0.1	0.10	0.099	101	99	75-125	2	20
Cobalt	mg/L	0.0015J	0.1	0.1	0.10	0.099	99	97	75-125	1	20
Lithium	mg/L	0.0015J	0.1	0.1	0.099	0.099	97	98	75-125	0	20
Molybdenum	mg/L	0.30	0.1	0.1	0.42	0.42	121	123	75-125	1	20
Selenium	mg/L	ND	0.1	0.1	0.11	0.11	106	106	75-125	0	20
Thallium	mg/L	0.00026J	0.1	0.1	0.097	0.096	97	96	75-125	1	20

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch:	789561	Analysis Method:	EPA 7470A
QC Batch Method:	EPA 7470A	Analysis Description:	7470 Mercury
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008		

METHOD BLANK:	4092350	Matrix:	Water
Associated Lab Samples:	92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	07/27/23 14:41	

LABORATORY CONTROL SAMPLE:	4092351					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0023	92	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:	4092352			4092353								
Parameter	Units	92677694002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.0025	0.0025	0.0021	0.0021	83	85	75-125	2	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch:	787441	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008		

METHOD BLANK:	4082157	Matrix:	Water
Associated Lab Samples:	92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	07/18/23 15:23	

LABORATORY CONTROL SAMPLE:	4082158					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	409	102	80-120	

SAMPLE DUPLICATE:	4082159					
Parameter	Units	92677694001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	513	511	0	10	

SAMPLE DUPLICATE:	4082160					
Parameter	Units	92677696005 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	1460	1570	8	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch: 787723

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92677694001, 92677694002

METHOD BLANK: 4083535

Matrix: Water

Associated Lab Samples: 92677694001, 92677694002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	07/19/23 16:09	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	07/19/23 16:09	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	07/19/23 16:09	

LABORATORY CONTROL SAMPLE: 4083536

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.8	106	80-120	

LABORATORY CONTROL SAMPLE: 4083537

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	49.5	99	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4083538 4083539

Parameter	Units	92677420019 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	48.7	50	50	102	103	106	108	80-120	1	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4083540 4083541

Parameter	Units	92677318002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	330	50	50	390	394	120	129	80-120	1	25 M1	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch: 788121

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008

METHOD BLANK: 4085797

Matrix: Water

Associated Lab Samples: 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	07/20/23 16:09	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	07/20/23 16:09	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	07/20/23 16:09	

LABORATORY CONTROL SAMPLE: 4085798

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.4	103	80-120	

LABORATORY CONTROL SAMPLE: 4085799

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	50.7	101	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4085800 4085801

Parameter	Units	92677753005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	121	50	50	180	180	118	118	80-120	0	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4085802 4085803

Parameter	Units	92677753006 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	76.8	50	50	129	131	103	108	80-120	2	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch: 787902 Analysis Method: SM 4500-S2D-2011
QC Batch Method: SM 4500-S2D-2011 Analysis Description: 4500S2D Sulfide Water
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006

METHOD BLANK: 4084741 Matrix: Water
Associated Lab Samples: 92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	07/20/23 03:38	

LABORATORY CONTROL SAMPLE: 4084742

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.49	98	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4084743 4084744

Parameter	Units	92677694001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.47	0.47	93	93	80-120	0	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4084745 4084746

Parameter	Units	92677696005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.48	0.46	94	90	80-120	5	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch: 787903

Analysis Method: SM 4500-S2D-2011

QC Batch Method: SM 4500-S2D-2011

Analysis Description: 4500S2D Sulfide Water

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92677694007, 92677694008

METHOD BLANK: 4084747

Matrix: Water

Associated Lab Samples: 92677694007, 92677694008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	07/20/23 03:57	

LABORATORY CONTROL SAMPLE: 4084748

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.49	97	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4084749 4084750

Parameter	Units	92678161006 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.53	0.54	105	108	80-120	3	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4084751 4084752

Parameter	Units	92677696012 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.43	0.47	84	93	80-120	10	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch: 787373 Analysis Method: EPA 300.0 Rev 2.1 1993
QC Batch Method: EPA 300.0 Rev 2.1 1993 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007

METHOD BLANK: 4081842 Matrix: Water
Associated Lab Samples: 92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	07/18/23 12:46	
Fluoride	mg/L	ND	0.10	0.050	07/18/23 12:46	
Sulfate	mg/L	ND	1.0	0.50	07/18/23 12:46	

LABORATORY CONTROL SAMPLE: 4081843

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	50.3	101	90-110	
Fluoride	mg/L	2.5	2.5	101	90-110	
Sulfate	mg/L	50	49.5	99	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4081844 4081845

Parameter	Units	92677589002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	2.9	50	50	54.1	54.7	102	104	90-110	1	10	
Fluoride	mg/L	ND	2.5	2.5	2.7	2.7	107	107	90-110	0	10	
Sulfate	mg/L	25.2	50	50	75.9	76.5	101	103	90-110	1	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4081846 4081847

Parameter	Units	92677589020 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	21.6	50	50	60.3	60.3	78	77	90-110	0	10	M1
Fluoride	mg/L	0.37J	2.5	2.5	2.8J	3.2J	96	113	90-110		10	M1
Sulfate	mg/L	3080	50	50	3000	2940	-145	-278	90-110	2	10	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch:	787377	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville

Associated Lab Samples: 92677694008

METHOD BLANK: 4081859 Matrix: Water

Associated Lab Samples: 92677694008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	07/19/23 05:21	
Fluoride	mg/L	ND	0.10	0.050	07/19/23 05:21	
Sulfate	mg/L	ND	1.0	0.50	07/19/23 05:21	

LABORATORY CONTROL SAMPLE: 4081860

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	50.4	101	90-110	
Fluoride	mg/L	2.5	2.4	98	90-110	
Sulfate	mg/L	50	49.8	100	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4081861 4081862

Parameter	Units	92677694008 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	17.8	50	50	69.7	70.1	104	105	90-110	1	10	
Fluoride	mg/L	0.32	2.5	2.5	2.8	2.8	98	99	90-110	1	10	
Sulfate	mg/L	393	50	50	422	418	58	49	90-110	1	10 M1	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1

Pace Project No.: 92677694

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above adjusted reporting limit.

TNTC - Too Numerous To Count

J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

MDL - Adjusted Method Detection Limit.

PQL - Practical Quantitation Limit.

RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected.

Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.

A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

ANALYTE QUALIFIERS

M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92677694

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92677694001	HAM-HGWC-8				
92677694002	HAM-PT-09				
92677694003	HAM-PT-10				
92677694004	HAM-PT-07				
92677694005	HAM-PT-08				
92677694008	HAM-HGWC-13				
92677694001	HAM-HGWC-8	EPA 3010A	787863	EPA 6010D	788067
92677694002	HAM-PT-09	EPA 3010A	787863	EPA 6010D	788067
92677694003	HAM-PT-10	EPA 3010A	787863	EPA 6010D	788067
92677694004	HAM-PT-07	EPA 3010A	787863	EPA 6010D	788067
92677694005	HAM-PT-08	EPA 3010A	787863	EPA 6010D	788067
92677694006	HAM-AP1-FD-01	EPA 3010A	787863	EPA 6010D	788067
92677694007	HAM-AP1-FB-01	EPA 3010A	787863	EPA 6010D	788067
92677694008	HAM-HGWC-13	EPA 3010A	787863	EPA 6010D	788067
92677694001	HAM-HGWC-8	EPA 3005A	787489	EPA 6020B	787561
92677694002	HAM-PT-09	EPA 3005A	787489	EPA 6020B	787561
92677694003	HAM-PT-10	EPA 3005A	787489	EPA 6020B	787561
92677694004	HAM-PT-07	EPA 3005A	787489	EPA 6020B	787561
92677694005	HAM-PT-08	EPA 3005A	787489	EPA 6020B	787561
92677694006	HAM-AP1-FD-01	EPA 3005A	787489	EPA 6020B	787561
92677694007	HAM-AP1-FB-01	EPA 3005A	787489	EPA 6020B	787561
92677694008	HAM-HGWC-13	EPA 3005A	787489	EPA 6020B	787561
92677694001	HAM-HGWC-8	EPA 7470A	789561	EPA 7470A	789666
92677694002	HAM-PT-09	EPA 7470A	789561	EPA 7470A	789666
92677694003	HAM-PT-10	EPA 7470A	789561	EPA 7470A	789666
92677694004	HAM-PT-07	EPA 7470A	789561	EPA 7470A	789666
92677694005	HAM-PT-08	EPA 7470A	789561	EPA 7470A	789666
92677694006	HAM-AP1-FD-01	EPA 7470A	789561	EPA 7470A	789666
92677694007	HAM-AP1-FB-01	EPA 7470A	789561	EPA 7470A	789666
92677694008	HAM-HGWC-13	EPA 7470A	789561	EPA 7470A	789666
92677694001	HAM-HGWC-8	SM 2540C-2015	787441		
92677694002	HAM-PT-09	SM 2540C-2015	787441		
92677694003	HAM-PT-10	SM 2540C-2015	787441		
92677694004	HAM-PT-07	SM 2540C-2015	787441		
92677694005	HAM-PT-08	SM 2540C-2015	787441		
92677694006	HAM-AP1-FD-01	SM 2540C-2015	787441		
92677694007	HAM-AP1-FB-01	SM 2540C-2015	787441		
92677694008	HAM-HGWC-13	SM 2540C-2015	787441		
92677694001	HAM-HGWC-8	SM 2320B-2011	787723		
92677694002	HAM-PT-09	SM 2320B-2011	787723		
92677694003	HAM-PT-10	SM 2320B-2011	788121		
92677694004	HAM-PT-07	SM 2320B-2011	788121		
92677694005	HAM-PT-08	SM 2320B-2011	788121		
92677694006	HAM-AP1-FD-01	SM 2320B-2011	788121		
92677694007	HAM-AP1-FB-01	SM 2320B-2011	788121		
92677694008	HAM-HGWC-13	SM 2320B-2011	788121		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92677694

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92677694001	HAM-HGWC-8	SM 4500-S2D-2011	787902		
92677694002	HAM-PT-09	SM 4500-S2D-2011	787902		
92677694003	HAM-PT-10	SM 4500-S2D-2011	787902		
92677694004	HAM-PT-07	SM 4500-S2D-2011	787902		
92677694005	HAM-PT-08	SM 4500-S2D-2011	787902		
92677694006	HAM-AP1-FD-01	SM 4500-S2D-2011	787902		
92677694007	HAM-AP1-FB-01	SM 4500-S2D-2011	787903		
92677694008	HAM-HGWC-13	SM 4500-S2D-2011	787903		
92677694001	HAM-HGWC-8	EPA 300.0 Rev 2.1 1993	787373		
92677694002	HAM-PT-09	EPA 300.0 Rev 2.1 1993	787373		
92677694003	HAM-PT-10	EPA 300.0 Rev 2.1 1993	787373		
92677694004	HAM-PT-07	EPA 300.0 Rev 2.1 1993	787373		
92677694005	HAM-PT-08	EPA 300.0 Rev 2.1 1993	787373		
92677694006	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	787373		
92677694007	HAM-AP1-FB-01	EPA 300.0 Rev 2.1 1993	787373		
92677694008	HAM-HGWC-13	EPA 300.0 Rev 2.1 1993	787377		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



DC#_Title: ENV-FRM-HUN1-0083 v02_Sample Condition Upon Receipt

Effective Date: 11/14/2022

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

GHPower

Project #:

WO#: 92677694



Courier:

☐ Commercial☒ Fed Ex☐ UPS☐ USPS☐ Client☒ Pace☐ Other:

Custody Seal Present?

☒ Yes☐ No

Seals Intact?

☒ Yes☐ No

Packing Material:

☐ Bubble Wrap☒ Bubble Bags☐ None☐ Other

Thermometer:

☒ IR Gun ID:

214

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

6.5

Correction Factor:

Add/Subtract (°C)

0.0

Cooler Temp Corrected (°C):

6.5

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

Comments/Discrepancy:

Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.
Rush Turn Around Time Requested?	☐ Yes ☐ No ☐ N/A	4.
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A	
Containers Intact?	☒ Yes ☐ No ☐ N/A	7.
Dissolved analysis: Samples Field Filtered?	☐ Yes ☒ No ☐ N/A	8.
Sample Labels Match COC?	☐ Yes ☐ No ☐ N/A	9.
-Includes Date/Time/ID/Analysis Matrix:	WG	
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10.
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A	

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_Title: ENV-FRM-HUN1-0083 v02_Sample Condition Upon Receipt

Effective Date: 11/14/2022

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

W0#: 92677694

PM: BV

Due Date: 07/31/23

CLIENT: 92- GP-HAM

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic ZN Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGFU-Wide-mouthed Glass jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG94-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit)-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A – lab)	SP2T-250 mL Sterile Plastic (N/A – lab)	BP3R-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	V5GU-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)
1		21																									
2		21																									
3		21																									
4		21																									
5		21																									
6		21																									
7		21																									
8		21																									
9																											
10																											
11																											
12																											

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers.

CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Page: 1 of

92677694

SAMPLE CONDITIONS

Temp in °C

Received on
Ice (Y/N)

Custody-Sealed
Cooler (Y/N)

Samples Intact
(Y/N)



August 25, 2023

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1 (CCR-CA)
Pace Project No.: 92682397

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on August 11, 2023. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Peachtree Corners, GA

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Angela Baioni for
Bonnie Vang
bonnie.vang@pacelabs.com
(704)875-9092
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92682397001	HAM-PT-07	Water	08/09/23 17:59	08/11/23 13:12
92682397002	HAM-PT-08	Water	08/09/23 10:50	08/11/23 13:12
92682397003	HAM-PT-09	Water	08/09/23 14:42	08/11/23 13:12
92682397004	HAM-PT-10	Water	08/09/23 13:05	08/11/23 13:12
92682397005	HAM-MW-53	Water	08/09/23 16:40	08/11/23 13:12
92682397006	HAM-MW-54	Water	08/09/23 16:51	08/11/23 13:12
92682397007	HAM-AP1-FD-06	Water	08/09/23 00:00	08/11/23 13:12
92682397008	HAM-AP1-FB-06	Water	08/09/23 16:50	08/11/23 13:12

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92682397001	HAM-PT-07	EPA 6010D	MS	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92682397002	HAM-PT-08	EPA 6010D	DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92682397003	HAM-PT-09	EPA 6010D	DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92682397004	HAM-PT-10	EPA 6010D	MS	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92682397005	HAM-MW-53	EPA 6020B	CW1	2
92682397006	HAM-MW-54	EPA 6020B	CW1	2
92682397007	HAM-AP1-FD-06	EPA 6010D	MS	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92682397008	HAM-AP1-FB-06	EPA 6010D	MS	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3

PASI-A = Pace Analytical Services - Asheville

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92682397001	HAM-PT-07					
EPA 6010D	Iron	27.1	mg/L	0.040	08/18/23 21:03	
EPA 6010D	Manganese	7.6	mg/L	0.040	08/18/23 21:03	
EPA 6010D	Potassium	6.8	mg/L	0.50	08/18/23 21:03	
EPA 6010D	Sodium	7.2	mg/L	1.0	08/18/23 21:03	
EPA 6010D	Calcium	173	mg/L	1.0	08/18/23 21:03	
EPA 6010D	Magnesium	19.4	mg/L	0.050	08/18/23 21:03	
EPA 6020B	Arsenic	0.27	mg/L	0.010	08/22/23 16:32	
EPA 6020B	Barium	0.053	mg/L	0.0050	08/22/23 16:32	
EPA 6020B	Beryllium	0.000095J	mg/L	0.00050	08/22/23 16:32	
EPA 6020B	Boron	0.93	mg/L	0.040	08/23/23 13:17	
EPA 6020B	Cobalt	0.090	mg/L	0.0050	08/23/23 13:17	
EPA 6020B	Lithium	0.069	mg/L	0.030	08/23/23 13:17	
EPA 6020B	Molybdenum	0.012	mg/L	0.010	08/22/23 16:32	
EPA 6020B	Thallium	0.00022J	mg/L	0.0010	08/22/23 16:32	
SM 2540C-2015	Total Dissolved Solids	771	mg/L	25.0	08/15/23 16:56	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	116	mg/L	5.0	08/16/23 15:20	
SM 2320B-2011	Alkalinity, Total as CaCO3	116	mg/L	5.0	08/16/23 15:20	
EPA 300.0 Rev 2.1 1993	Chloride	13.5	mg/L	1.0	08/15/23 21:32	
EPA 300.0 Rev 2.1 1993	Fluoride	0.28	mg/L	0.10	08/15/23 21:32	
EPA 300.0 Rev 2.1 1993	Sulfate	339	mg/L	7.0	08/16/23 08:19	
92682397002	HAM-PT-08					
EPA 6010D	Iron	22.0	mg/L	0.040	08/18/23 21:13	
EPA 6010D	Manganese	6.8	mg/L	0.040	08/18/23 21:13	
EPA 6010D	Potassium	6.3	mg/L	0.50	08/18/23 21:13	
EPA 6010D	Sodium	6.8	mg/L	1.0	08/18/23 21:13	
EPA 6010D	Calcium	146	mg/L	1.0	08/18/23 21:13	
EPA 6010D	Magnesium	17.3	mg/L	0.050	08/18/23 21:13	
EPA 6020B	Arsenic	0.32	mg/L	0.010	08/22/23 16:39	
EPA 6020B	Barium	0.050	mg/L	0.0050	08/22/23 16:39	
EPA 6020B	Beryllium	0.000073J	mg/L	0.00050	08/22/23 16:39	
EPA 6020B	Boron	0.99	mg/L	0.040	08/23/23 13:23	
EPA 6020B	Cobalt	0.032	mg/L	0.0050	08/22/23 16:39	
EPA 6020B	Lithium	0.073	mg/L	0.030	08/23/23 13:23	
EPA 6020B	Molybdenum	0.0071J	mg/L	0.010	08/22/23 16:39	
SM 2540C-2015	Total Dissolved Solids	682	mg/L	25.0	08/15/23 16:57	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	118	mg/L	5.0	08/16/23 15:40	
SM 2320B-2011	Alkalinity, Total as CaCO3	118	mg/L	5.0	08/16/23 15:40	
EPA 300.0 Rev 2.1 1993	Chloride	14.5	mg/L	1.0	08/15/23 22:30	
EPA 300.0 Rev 2.1 1993	Fluoride	0.27	mg/L	0.10	08/15/23 22:30	
EPA 300.0 Rev 2.1 1993	Sulfate	290	mg/L	6.0	08/16/23 09:16	M1
92682397003	HAM-PT-09					
EPA 6010D	Iron	0.10	mg/L	0.040	08/18/23 21:18	
EPA 6010D	Manganese	0.51	mg/L	0.040	08/18/23 21:18	
EPA 6010D	Potassium	7.7	mg/L	0.50	08/18/23 21:18	
EPA 6010D	Sodium	10.3	mg/L	1.0	08/18/23 21:18	
EPA 6010D	Calcium	136	mg/L	1.0	08/18/23 21:18	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92682397003	HAM-PT-09					
EPA 6010D	Magnesium	18.2	mg/L	0.050	08/18/23 21:18	
EPA 6020B	Barium	0.057	mg/L	0.0050	08/22/23 16:43	
EPA 6020B	Boron	1.6	mg/L	0.40	08/23/23 19:25	
EPA 6020B	Cobalt	0.0028J	mg/L	0.0050	08/22/23 16:43	
EPA 6020B	Lithium	0.0017J	mg/L	0.030	08/22/23 16:43	
EPA 6020B	Molybdenum	0.21	mg/L	0.010	08/22/23 16:43	
SM 2540C-2015	Total Dissolved Solids	594	mg/L	25.0	08/15/23 16:57	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	150	mg/L	5.0	08/16/23 15:50	
SM 2320B-2011	Alkalinity, Total as CaCO3	150	mg/L	5.0	08/16/23 15:50	
EPA 300.0 Rev 2.1 1993	Chloride	47.5	mg/L	1.0	08/15/23 23:14	
EPA 300.0 Rev 2.1 1993	Fluoride	0.26	mg/L	0.10	08/15/23 23:14	
EPA 300.0 Rev 2.1 1993	Sulfate	188	mg/L	4.0	08/16/23 09:59	
92682397004	HAM-PT-10					
EPA 6010D	Iron	2.9	mg/L	0.040	08/23/23 21:33	
EPA 6010D	Manganese	3.1	mg/L	0.040	08/23/23 21:33	
EPA 6010D	Potassium	6.7	mg/L	0.50	08/23/23 21:33	M1
EPA 6010D	Sodium	9.4	mg/L	1.0	08/23/23 21:33	M1
EPA 6010D	Calcium	116	mg/L	1.0	08/23/23 21:33	M1
EPA 6010D	Magnesium	16.8	mg/L	0.050	08/23/23 21:33	M1
EPA 6020B	Barium	0.070	mg/L	0.0050	08/22/23 16:51	
EPA 6020B	Boron	2.1	mg/L	0.40	08/23/23 19:48	
EPA 6020B	Cobalt	0.0019J	mg/L	0.0050	08/22/23 16:51	
EPA 6020B	Lithium	0.0012J	mg/L	0.030	08/22/23 16:51	
EPA 6020B	Molybdenum	0.096	mg/L	0.010	08/22/23 16:51	
SM 2540C-2015	Total Dissolved Solids	553	mg/L	25.0	08/15/23 16:57	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	199	mg/L	5.0	08/16/23 16:00	
SM 2320B-2011	Alkalinity, Total as CaCO3	199	mg/L	5.0	08/16/23 16:00	
SM 4500-S2D-2011	Sulfide	0.045J	mg/L	0.10	08/15/23 06:30	
EPA 300.0 Rev 2.1 1993	Chloride	62.5	mg/L	1.0	08/15/23 23:42	
EPA 300.0 Rev 2.1 1993	Fluoride	0.27	mg/L	0.10	08/15/23 23:42	
EPA 300.0 Rev 2.1 1993	Sulfate	123	mg/L	3.0	08/16/23 10:27	
92682397005	HAM-MW-53					
EPA 6020B	Boron	1.5	mg/L	0.040	08/22/23 20:17	
EPA 6020B	Molybdenum	0.14	mg/L	0.010	08/22/23 20:17	
92682397006	HAM-MW-54					
EPA 6020B	Arsenic	0.085	mg/L	0.010	08/22/23 20:23	
EPA 6020B	Boron	0.45	mg/L	0.040	08/22/23 20:23	
92682397007	HAM-AP1-FD-06					
EPA 6010D	Iron	21.3	mg/L	0.040	08/23/23 21:54	
EPA 6010D	Manganese	6.8	mg/L	0.040	08/23/23 21:54	
EPA 6010D	Potassium	5.6	mg/L	0.50	08/23/23 21:54	
EPA 6010D	Sodium	6.3	mg/L	1.0	08/23/23 21:54	
EPA 6010D	Calcium	128	mg/L	1.0	08/23/23 21:54	
EPA 6010D	Magnesium	16.7	mg/L	0.050	08/23/23 21:54	
EPA 6020B	Arsenic	0.36	mg/L	0.010	08/22/23 20:29	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92682397007	HAM-AP1-FD-06					
EPA 6020B	Barium	0.047	mg/L	0.0050	08/22/23 20:29	
EPA 6020B	Beryllium	0.000065J	mg/L	0.00050	08/22/23 20:29	
EPA 6020B	Boron	0.90	mg/L	0.040	08/22/23 20:29	
EPA 6020B	Cobalt	0.034	mg/L	0.0050	08/22/23 20:29	
EPA 6020B	Lithium	0.066	mg/L	0.030	08/22/23 20:29	
EPA 6020B	Molybdenum	0.0068J	mg/L	0.010	08/22/23 20:29	
SM 2540C-2015	Total Dissolved Solids	699	mg/L	25.0	08/15/23 16:57	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	111	mg/L	5.0	08/16/23 16:12	
SM 2320B-2011	Alkalinity, Total as CaCO3	111	mg/L	5.0	08/16/23 16:12	
EPA 300.0 Rev 2.1 1993	Chloride	14.6	mg/L	1.0	08/16/23 03:19	
EPA 300.0 Rev 2.1 1993	Fluoride	0.29	mg/L	0.10	08/16/23 03:19	
EPA 300.0 Rev 2.1 1993	Sulfate	293	mg/L	6.0	08/16/23 12:22	
92682397008	HAM-AP1-FB-06					
EPA 6020B	Boron	0.012J	mg/L	0.040	08/22/23 20:35	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-PT-07		Lab ID: 92682397001		Collected: 08/09/23 17:59		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	27.1	mg/L	0.040	0.025	1	08/18/23 10:36	08/18/23 21:03	7439-89-6	
Manganese	7.6	mg/L	0.040	0.011	1	08/18/23 10:36	08/18/23 21:03	7439-96-5	
Potassium	6.8	mg/L	0.50	0.15	1	08/18/23 10:36	08/18/23 21:03	7440-09-7	
Sodium	7.2	mg/L	1.0	0.58	1	08/18/23 10:36	08/18/23 21:03	7440-23-5	
Calcium	173	mg/L	1.0	0.12	1	08/18/23 10:36	08/18/23 21:03	7440-70-2	
Magnesium	19.4	mg/L	0.050	0.012	1	08/18/23 10:36	08/18/23 21:03	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	08/16/23 14:27	08/22/23 16:32	7440-36-0	
Arsenic	0.27	mg/L	0.010	0.0037	1	08/16/23 14:27	08/22/23 16:32	7440-38-2	
Barium	0.053	mg/L	0.0050	0.00067	1	08/16/23 14:27	08/22/23 16:32	7440-39-3	
Beryllium	0.000095J	mg/L	0.00050	0.000054	1	08/16/23 14:27	08/22/23 16:32	7440-41-7	
Boron	0.93	mg/L	0.040	0.0086	1	08/16/23 14:27	08/23/23 13:17	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	08/16/23 14:27	08/22/23 16:32	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	08/16/23 14:27	08/23/23 13:17	7440-47-3	
Cobalt	0.090	mg/L	0.0050	0.00039	1	08/16/23 14:27	08/23/23 13:17	7440-48-4	
Lead	ND	mg/L	0.0010	0.00012	1	08/16/23 14:27	08/22/23 16:32	7439-92-1	
Lithium	0.069	mg/L	0.030	0.00073	1	08/16/23 14:27	08/23/23 13:17	7439-93-2	
Molybdenum	0.012	mg/L	0.010	0.00074	1	08/16/23 14:27	08/22/23 16:32	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	08/16/23 14:27	08/22/23 16:32	7782-49-2	
Thallium	0.00022J	mg/L	0.0010	0.00018	1	08/16/23 14:27	08/22/23 16:32	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/17/23 12:00	08/17/23 15:18	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	771	mg/L	25.0	25.0	1		08/15/23 16:56		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	116	mg/L	5.0	5.0	1		08/16/23 15:20		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/16/23 15:20		
Alkalinity, Total as CaCO ₃	116	mg/L	5.0	5.0	1		08/16/23 15:20		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/15/23 06:29	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	13.5	mg/L	1.0	0.60	1		08/15/23 21:32	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-PT-07		Lab ID: 92682397001		Collected: 08/09/23 17:59		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.28	mg/L	0.10	0.050	1		08/15/23 21:32	16984-48-8	
Sulfate	339	mg/L	7.0	3.5	7		08/16/23 08:19	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-PT-08		Lab ID: 92682397002		Collected: 08/09/23 10:50		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	22.0	mg/L	0.040	0.025	1	08/18/23 10:36	08/18/23 21:13	7439-89-6	
Manganese	6.8	mg/L	0.040	0.011	1	08/18/23 10:36	08/18/23 21:13	7439-96-5	
Potassium	6.3	mg/L	0.50	0.15	1	08/18/23 10:36	08/18/23 21:13	7440-09-7	
Sodium	6.8	mg/L	1.0	0.58	1	08/18/23 10:36	08/18/23 21:13	7440-23-5	
Calcium	146	mg/L	1.0	0.12	1	08/18/23 10:36	08/18/23 21:13	7440-70-2	
Magnesium	17.3	mg/L	0.050	0.012	1	08/18/23 10:36	08/18/23 21:13	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	08/16/23 14:27	08/22/23 16:39	7440-36-0	
Arsenic	0.32	mg/L	0.010	0.0037	1	08/16/23 14:27	08/22/23 16:39	7440-38-2	
Barium	0.050	mg/L	0.0050	0.00067	1	08/16/23 14:27	08/22/23 16:39	7440-39-3	
Beryllium	0.000073J	mg/L	0.00050	0.000054	1	08/16/23 14:27	08/22/23 16:39	7440-41-7	
Boron	0.99	mg/L	0.040	0.0086	1	08/16/23 14:27	08/23/23 13:23	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	08/16/23 14:27	08/22/23 16:39	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	08/16/23 14:27	08/22/23 16:39	7440-47-3	
Cobalt	0.032	mg/L	0.0050	0.00039	1	08/16/23 14:27	08/22/23 16:39	7440-48-4	
Lead	ND	mg/L	0.0010	0.00012	1	08/16/23 14:27	08/22/23 16:39	7439-92-1	
Lithium	0.073	mg/L	0.030	0.00073	1	08/16/23 14:27	08/23/23 13:23	7439-93-2	
Molybdenum	0.0071J	mg/L	0.010	0.00074	1	08/16/23 14:27	08/22/23 16:39	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	08/16/23 14:27	08/22/23 16:39	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00018	1	08/16/23 14:27	08/22/23 16:39	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/17/23 12:00	08/17/23 15:34	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	682	mg/L	25.0	25.0	1		08/15/23 16:57		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	118	mg/L	5.0	5.0	1		08/16/23 15:40		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/16/23 15:40		
Alkalinity, Total as CaCO ₃	118	mg/L	5.0	5.0	1		08/16/23 15:40		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/15/23 06:29	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	14.5	mg/L	1.0	0.60	1		08/15/23 22:30	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-PT-08		Lab ID: 92682397002		Collected: 08/09/23 10:50		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.27	mg/L	0.10	0.050	1		08/15/23 22:30	16984-48-8	
Sulfate	290	mg/L	6.0	3.0	6		08/16/23 09:16	14808-79-8	M1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-PT-09		Lab ID: 92682397003		Collected: 08/09/23 14:42		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	0.10	mg/L	0.040	0.025	1	08/18/23 10:36	08/18/23 21:18	7439-89-6	
Manganese	0.51	mg/L	0.040	0.011	1	08/18/23 10:36	08/18/23 21:18	7439-96-5	
Potassium	7.7	mg/L	0.50	0.15	1	08/18/23 10:36	08/18/23 21:18	7440-09-7	
Sodium	10.3	mg/L	1.0	0.58	1	08/18/23 10:36	08/18/23 21:18	7440-23-5	
Calcium	136	mg/L	1.0	0.12	1	08/18/23 10:36	08/18/23 21:18	7440-70-2	
Magnesium	18.2	mg/L	0.050	0.012	1	08/18/23 10:36	08/18/23 21:18	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.0012	1	08/16/23 14:27	08/22/23 16:43	7440-36-0	
Arsenic	ND	mg/L	0.010	0.0037	1	08/16/23 14:27	08/22/23 16:43	7440-38-2	
Barium	0.057	mg/L	0.0050	0.00067	1	08/16/23 14:27	08/22/23 16:43	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000054	1	08/16/23 14:27	08/22/23 16:43	7440-41-7	
Boron	1.6	mg/L	0.40	0.086	10	08/16/23 14:27	08/23/23 19:25	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	08/16/23 14:27	08/22/23 16:43	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	08/16/23 14:27	08/22/23 16:43	7440-47-3	
Cobalt	0.0028J	mg/L	0.0050	0.00039	1	08/16/23 14:27	08/22/23 16:43	7440-48-4	
Lead	ND	mg/L	0.0010	0.00012	1	08/16/23 14:27	08/22/23 16:43	7439-92-1	
Lithium	0.0017J	mg/L	0.030	0.00073	1	08/16/23 14:27	08/22/23 16:43	7439-93-2	
Molybdenum	0.21	mg/L	0.010	0.00074	1	08/16/23 14:27	08/22/23 16:43	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	08/16/23 14:27	08/22/23 16:43	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00018	1	08/16/23 14:27	08/22/23 16:43	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	08/17/23 12:00	08/17/23 15:37	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	594	mg/L	25.0	25.0	1		08/15/23 16:57		
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	150	mg/L	5.0	5.0	1		08/16/23 15:50		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/16/23 15:50		
Alkalinity, Total as CaCO ₃	150	mg/L	5.0	5.0	1		08/16/23 15:50		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		08/15/23 06:30	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	47.5	mg/L	1.0	0.60	1		08/15/23 23:14	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-PT-09		Lab ID: 92682397003		Collected: 08/09/23 14:42		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.26	mg/L	0.10	0.050	1		08/15/23 23:14	16984-48-8	
Sulfate	188	mg/L	4.0	2.0	4		08/16/23 09:59	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-PT-10		Lab ID: 92682397004		Collected: 08/09/23 13:05		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	2.9	mg/L	0.040	0.025	1	08/23/23 12:06	08/23/23 21:33	7439-89-6	
Manganese	3.1	mg/L	0.040	0.011	1	08/23/23 12:06	08/23/23 21:33	7439-96-5	
Potassium	6.7	mg/L	0.50	0.15	1	08/23/23 12:06	08/23/23 21:33	7440-09-7	M1
Sodium	9.4	mg/L	1.0	0.58	1	08/23/23 12:06	08/23/23 21:33	7440-23-5	M1
Calcium	116	mg/L	1.0	0.12	1	08/23/23 12:06	08/23/23 21:33	7440-70-2	M1
Magnesium	16.8	mg/L	0.050	0.012	1	08/23/23 12:06	08/23/23 21:33	7439-95-4	M1
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	08/16/23 14:27	08/22/23 16:51	7440-36-0	
Arsenic	ND	mg/L	0.010	0.0037	1	08/16/23 14:27	08/22/23 16:51	7440-38-2	
Barium	0.070	mg/L	0.0050	0.00067	1	08/16/23 14:27	08/22/23 16:51	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000054	1	08/16/23 14:27	08/22/23 16:51	7440-41-7	
Boron	2.1	mg/L	0.40	0.086	10	08/16/23 14:27	08/23/23 19:48	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	08/16/23 14:27	08/22/23 16:51	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	08/16/23 14:27	08/22/23 16:51	7440-47-3	
Cobalt	0.0019J	mg/L	0.0050	0.00039	1	08/16/23 14:27	08/22/23 16:51	7440-48-4	
Lead	ND	mg/L	0.0010	0.00012	1	08/16/23 14:27	08/22/23 16:51	7439-92-1	
Lithium	0.0012J	mg/L	0.030	0.00073	1	08/16/23 14:27	08/22/23 16:51	7439-93-2	
Molybdenum	0.096	mg/L	0.010	0.00074	1	08/16/23 14:27	08/22/23 16:51	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	08/16/23 14:27	08/22/23 16:51	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00018	1	08/16/23 14:27	08/22/23 16:51	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/17/23 12:00	08/17/23 15:39	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	553	mg/L	25.0	25.0	1		08/15/23 16:57		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	199	mg/L	5.0	5.0	1		08/16/23 16:00		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/16/23 16:00		
Alkalinity, Total as CaCO ₃	199	mg/L	5.0	5.0	1		08/16/23 16:00		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	0.045J	mg/L	0.10	0.022	1		08/15/23 06:30	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	62.5	mg/L	1.0	0.60	1		08/15/23 23:42	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-PT-10		Lab ID: 92682397004		Collected: 08/09/23 13:05		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.27	mg/L	0.10	0.050	1		08/15/23 23:42	16984-48-8	
Sulfate	123	mg/L	3.0	1.5	3		08/16/23 10:27	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-MW-53		Lab ID: 92682397005		Collected: 08/09/23 16:40		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.5	mg/L	0.040	0.0086	1	08/17/23 10:25	08/22/23 20:17	7440-42-8	
Molybdenum	0.14	mg/L	0.010	0.00074	1	08/17/23 10:25	08/22/23 20:17	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-MW-54		Lab ID: 92682397006		Collected: 08/09/23 16:51		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.085	mg/L	0.010	0.0037	1	08/17/23 10:25	08/22/23 20:23	7440-38-2	
Boron	0.45	mg/L	0.040	0.0086	1	08/17/23 10:25	08/22/23 20:23	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-AP1-FD-06		Lab ID: 92682397007		Collected: 08/09/23 00:00		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	21.3	mg/L	0.040	0.025	1	08/23/23 12:06	08/23/23 21:54	7439-89-6	
Manganese	6.8	mg/L	0.040	0.011	1	08/23/23 12:06	08/23/23 21:54	7439-96-5	
Potassium	5.6	mg/L	0.50	0.15	1	08/23/23 12:06	08/23/23 21:54	7440-09-7	
Sodium	6.3	mg/L	1.0	0.58	1	08/23/23 12:06	08/23/23 21:54	7440-23-5	
Calcium	128	mg/L	1.0	0.12	1	08/23/23 12:06	08/23/23 21:54	7440-70-2	
Magnesium	16.7	mg/L	0.050	0.012	1	08/23/23 12:06	08/23/23 21:54	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	08/17/23 10:25	08/22/23 20:29	7440-36-0	
Arsenic	0.36	mg/L	0.010	0.0037	1	08/17/23 10:25	08/22/23 20:29	7440-38-2	
Barium	0.047	mg/L	0.0050	0.00067	1	08/17/23 10:25	08/22/23 20:29	7440-39-3	
Beryllium	0.000065J	mg/L	0.00050	0.000054	1	08/17/23 10:25	08/22/23 20:29	7440-41-7	
Boron	0.90	mg/L	0.040	0.0086	1	08/17/23 10:25	08/22/23 20:29	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	08/17/23 10:25	08/22/23 20:29	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	08/17/23 10:25	08/23/23 17:24	7440-47-3	
Cobalt	0.034	mg/L	0.0050	0.00039	1	08/17/23 10:25	08/22/23 20:29	7440-48-4	
Lead	ND	mg/L	0.0010	0.00012	1	08/17/23 10:25	08/22/23 20:29	7439-92-1	
Lithium	0.066	mg/L	0.030	0.00073	1	08/17/23 10:25	08/22/23 20:29	7439-93-2	
Molybdenum	0.0068J	mg/L	0.010	0.00074	1	08/17/23 10:25	08/22/23 20:29	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	08/17/23 10:25	08/22/23 20:29	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00018	1	08/17/23 10:25	08/22/23 20:29	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/17/23 12:00	08/17/23 15:42	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	699	mg/L	25.0	25.0	1		08/15/23 16:57		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	111	mg/L	5.0	5.0	1		08/16/23 16:12		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/16/23 16:12		
Alkalinity, Total as CaCO ₃	111	mg/L	5.0	5.0	1		08/16/23 16:12		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/15/23 06:31	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	14.6	mg/L	1.0	0.60	1		08/16/23 03:19	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-AP1-FD-06		Lab ID: 92682397007		Collected: 08/09/23 00:00		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.29	mg/L	0.10	0.050	1		08/16/23 03:19	16984-48-8	
Sulfate	293	mg/L	6.0	3.0	6		08/16/23 12:22	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-AP1-FB-06		Lab ID: 92682397008		Collected: 08/09/23 16:50		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	08/23/23 12:06	08/23/23 21:59	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	08/23/23 12:06	08/23/23 21:59	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	08/23/23 12:06	08/23/23 21:59	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	08/23/23 12:06	08/23/23 21:59	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	08/23/23 12:06	08/23/23 21:59	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	08/23/23 12:06	08/23/23 21:59	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	08/17/23 10:25	08/22/23 20:35	7440-36-0	
Arsenic	ND	mg/L	0.010	0.0037	1	08/17/23 10:25	08/22/23 20:35	7440-38-2	
Barium	ND	mg/L	0.0050	0.00067	1	08/17/23 10:25	08/22/23 20:35	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000054	1	08/17/23 10:25	08/22/23 20:35	7440-41-7	
Boron	0.012J	mg/L	0.040	0.0086	1	08/17/23 10:25	08/22/23 20:35	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	08/17/23 10:25	08/22/23 20:35	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	08/17/23 10:25	08/23/23 17:28	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00039	1	08/17/23 10:25	08/22/23 20:35	7440-48-4	
Lead	ND	mg/L	0.0010	0.00012	1	08/17/23 10:25	08/22/23 20:35	7439-92-1	
Lithium	ND	mg/L	0.030	0.00073	1	08/17/23 10:25	08/22/23 20:35	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00074	1	08/17/23 10:25	08/22/23 20:35	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	08/17/23 10:25	08/22/23 20:35	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00018	1	08/17/23 10:25	08/22/23 20:35	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/17/23 12:00	08/17/23 15:44	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		08/15/23 16:57		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/16/23 16:22		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/16/23 16:22		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		08/16/23 16:22		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/15/23 06:32	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		08/16/23 03:33	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-AP1-FB-06		Lab ID: 92682397008		Collected: 08/09/23 16:50		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		08/16/23 03:33	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		08/16/23 03:33	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

QC Batch: 793618

Analysis Method: EPA 6010D

QC Batch Method: EPA 3010A

Analysis Description: 6010D ATL

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92682397001, 92682397002, 92682397003

METHOD BLANK: 4112489

Matrix: Water

Associated Lab Samples: 92682397001, 92682397002, 92682397003

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	08/18/23 19:00	
Iron	mg/L	ND	0.040	0.025	08/18/23 19:00	
Magnesium	mg/L	ND	0.050	0.012	08/18/23 19:00	
Manganese	mg/L	ND	0.040	0.011	08/18/23 19:00	
Potassium	mg/L	ND	0.50	0.15	08/18/23 19:00	
Sodium	mg/L	ND	1.0	0.58	08/18/23 19:00	

LABORATORY CONTROL SAMPLE: 4112490

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	1.1	108	80-120	
Iron	mg/L	1	1.0	102	80-120	
Magnesium	mg/L	1	1.0	101	80-120	
Manganese	mg/L	1	0.99	99	80-120	
Potassium	mg/L	1	1.1	106	80-120	
Sodium	mg/L	1	1.1	106	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4112491 4112492

Parameter	Units	92682392001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Calcium	mg/L	8.4	1	1	8.8	9.3	35	92	75-125	6	20	M1
Iron	mg/L	ND	1	1	1.0	1.0	100	100	75-125	0	20	
Magnesium	mg/L	3.4	1	1	4.1	4.3	72	92	75-125	5	20	M1
Manganese	mg/L	ND	1	1	0.98	0.99	97	98	75-125	1	20	
Potassium	mg/L	0.32J	1	1	1.3	1.5	102	113	75-125	8	20	
Sodium	mg/L	9.5	1	1	10	10.5	44	103	75-125	6	20	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

QC Batch: 795409

Analysis Method: EPA 6010D

QC Batch Method: EPA 3010A

Analysis Description: 6010D ATL

Laboratory:

Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92682397004, 92682397007, 92682397008

METHOD BLANK: 4121384

Matrix: Water

Associated Lab Samples: 92682397004, 92682397007, 92682397008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	08/23/23 21:12	
Iron	mg/L	ND	0.040	0.025	08/23/23 21:12	
Magnesium	mg/L	ND	0.050	0.012	08/23/23 21:12	
Manganese	mg/L	ND	0.040	0.011	08/23/23 21:12	
Potassium	mg/L	ND	0.50	0.15	08/23/23 21:12	
Sodium	mg/L	ND	1.0	0.58	08/23/23 21:12	

LABORATORY CONTROL SAMPLE: 4121385

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	0.93J	93	80-120	
Iron	mg/L	1	1.0	102	80-120	
Magnesium	mg/L	1	1.1	109	80-120	
Manganese	mg/L	1	1.0	105	80-120	
Potassium	mg/L	1	1.0	100	80-120	
Sodium	mg/L	1	1.1	105	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4121386 4121387

Parameter	Units	92682397004 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Calcium	mg/L	116	1	1	112	116	-370	-33	75-125	3	20	M1
Iron	mg/L	2.9	1	1	3.7	3.8	84	95	75-125	3	20	
Magnesium	mg/L	16.8	1	1	17.0	17.5	22	63	75-125	2	20	M1
Manganese	mg/L	3.1	1	1	4.0	4.0	83	90	75-125	2	20	
Potassium	mg/L	6.7	1	1	7.5	7.7	73	98	75-125	3	20	M1
Sodium	mg/L	9.4	1	1	9.9	10.3	54	92	75-125	4	20	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

QC Batch: 794002

Analysis Method: EPA 6020B

QC Batch Method: EPA 3005A

Analysis Description: 6020 MET

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004

METHOD BLANK: 4114214

Matrix: Water

Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	0.0043	0.0030	0.0012	08/22/23 15:04	
Arsenic	mg/L	ND	0.010	0.0037	08/22/23 15:04	
Barium	mg/L	ND	0.0050	0.00067	08/22/23 15:04	
Beryllium	mg/L	ND	0.00050	0.000054	08/22/23 15:04	
Boron	mg/L	ND	0.040	0.0086	08/22/23 15:04	
Cadmium	mg/L	ND	0.00050	0.00011	08/22/23 15:04	
Chromium	mg/L	ND	0.0050	0.0011	08/22/23 15:04	
Cobalt	mg/L	ND	0.0050	0.00039	08/22/23 15:04	
Lead	mg/L	ND	0.0010	0.00012	08/22/23 15:04	
Lithium	mg/L	ND	0.030	0.00073	08/22/23 15:04	
Molybdenum	mg/L	ND	0.010	0.00074	08/22/23 15:04	
Selenium	mg/L	ND	0.0050	0.0014	08/22/23 15:04	
Thallium	mg/L	ND	0.0010	0.00018	08/22/23 15:04	

LABORATORY CONTROL SAMPLE: 4114215

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.11	112	80-120	
Arsenic	mg/L	0.1	0.10	102	80-120	
Barium	mg/L	0.1	0.10	100	80-120	
Beryllium	mg/L	0.1	0.11	110	80-120	
Boron	mg/L	1	1.1	110	80-120	
Cadmium	mg/L	0.1	0.10	102	80-120	
Chromium	mg/L	0.1	0.11	106	80-120	
Cobalt	mg/L	0.1	0.10	104	80-120	
Lead	mg/L	0.1	0.10	105	80-120	
Lithium	mg/L	0.1	0.11	110	80-120	
Molybdenum	mg/L	0.1	0.11	107	80-120	
Selenium	mg/L	0.1	0.11	105	80-120	
Thallium	mg/L	0.1	0.11	105	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4114216

4114217

Parameter	Units	92682396010 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	0.0014J	0.1	0.1	0.11	0.10	107	101	75-125	6	20	
Arsenic	mg/L	0.0040J	0.1	0.1	0.12	0.11	112	104	75-125	7	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4114216 4114217											
Parameter	Units	92682396010		MS		MSD		MS		MSD	
		Result		Spike	Conc.	Spike	Conc.	Result		MS	MSD
				Conc.		Conc.		% Rec		% Rec	Limits
Barium	mg/L	0.042		0.1		0.1		118		108	75-125
Beryllium	mg/L	0.00071		0.1		0.1		89		84	75-125
Boron	mg/L	10.1		1		1		77		57	75-125
Cadmium	mg/L	0.00059		0.1		0.1		98		94	75-125
Chromium	mg/L	ND		0.1		0.1		104		97	75-125
Cobalt	mg/L	0.21		0.1		0.1		102		83	75-125
Lead	mg/L	0.00013J		0.1		0.1		67		64	75-125
Lithium	mg/L	0.0024J		0.1		0.1		95		89	75-125
Molybdenum	mg/L	ND		0.1		0.1		109		104	75-125
Selenium	mg/L	0.013		0.1		0.1		122		113	75-125
Thallium	mg/L	0.00021J		0.1		0.1		68		65	75-125

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

QC Batch: 794177

Analysis Method: EPA 6020B

QC Batch Method: EPA 3005A

Analysis Description: 6020 MET

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92682397005, 92682397006, 92682397007, 92682397008

METHOD BLANK: 4115107

Matrix: Water

Associated Lab Samples: 92682397005, 92682397006, 92682397007, 92682397008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.0012	08/22/23 18:42	
Arsenic	mg/L	ND	0.010	0.0037	08/22/23 18:42	
Barium	mg/L	ND	0.0050	0.00067	08/22/23 18:42	
Beryllium	mg/L	ND	0.00050	0.000054	08/22/23 18:42	
Boron	mg/L	ND	0.040	0.0086	08/22/23 18:42	
Cadmium	mg/L	ND	0.00050	0.00011	08/22/23 18:42	
Chromium	mg/L	ND	0.0050	0.0011	08/23/23 16:28	
Cobalt	mg/L	ND	0.0050	0.00039	08/22/23 18:42	
Lead	mg/L	ND	0.0010	0.00012	08/22/23 18:42	
Lithium	mg/L	ND	0.030	0.00073	08/22/23 18:42	
Molybdenum	mg/L	ND	0.010	0.00074	08/22/23 18:42	
Selenium	mg/L	ND	0.0050	0.0014	08/22/23 18:42	
Thallium	mg/L	ND	0.0010	0.00018	08/22/23 18:42	

LABORATORY CONTROL SAMPLE: 4115108

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.10	104	80-120	
Arsenic	mg/L	0.1	0.094	94	80-120	
Barium	mg/L	0.1	0.096	96	80-120	
Beryllium	mg/L	0.1	0.093	93	80-120	
Boron	mg/L	1	0.94	94	80-120	
Cadmium	mg/L	0.1	0.096	96	80-120	
Chromium	mg/L	0.1	0.10	100	80-120	
Cobalt	mg/L	0.1	0.090	90	80-120	
Lead	mg/L	0.1	0.094	94	80-120	
Lithium	mg/L	0.1	0.098	98	80-120	
Molybdenum	mg/L	0.1	0.095	95	80-120	
Selenium	mg/L	0.1	0.097	97	80-120	
Thallium	mg/L	0.1	0.093	93	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4115109

4115110

Parameter	Units	92681886001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	ND	0.1	0.1	0.10	0.10	104	103	75-125	1	20	
Arsenic	mg/L	ND	0.1	0.1	0.099	0.098	99	98	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:			4115109		4115110							
Parameter	Units	92681886001	MS	MSD	MS	MSD	MS	MSD	% Rec	RPD	Max	Qual
		Result	Spike	Spike								
Barium	mg/L	0.039	0.1	0.1	0.14	0.14	103	103	75-125	1	20	
Beryllium	mg/L	0.000067J	0.1	0.1	0.094	0.091	94	91	75-125	4	20	
Boron	mg/L	0.029J	1	1	0.97	0.94	94	91	75-125	3	20	
Cadmium	mg/L	ND	0.1	0.1	0.098	0.099	98	99	75-125	1	20	
Chromium	mg/L	ND	0.1	0.1	0.10	0.10	102	101	75-125	1	20	
Cobalt	mg/L	0.00041J	0.1	0.1	0.092	0.091	91	91	75-125	0	20	
Lead	mg/L	ND	0.1	0.1	0.093	0.092	93	92	75-125	1	20	
Lithium	mg/L	ND	0.1	0.1	0.095	0.094	95	93	75-125	2	20	
Molybdenum	mg/L	ND	0.1	0.1	0.096	0.096	96	95	75-125	0	20	
Selenium	mg/L	ND	0.1	0.1	0.10	0.099	100	99	75-125	1	20	
Thallium	mg/L	ND	0.1	0.1	0.092	0.092	92	92	75-125	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

QC Batch: 794154

Analysis Method: EPA 7470A

QC Batch Method: EPA 7470A

Analysis Description: 7470 Mercury

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

METHOD BLANK: 4115033

Matrix: Water

Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	08/17/23 15:13	

LABORATORY CONTROL SAMPLE: 4115034

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0023	93	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4115035 4115036

Parameter	Units	92682397001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.0025	0.0025	0.0024	0.0024	94	94	75-125	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

QC Batch:	793700	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

METHOD BLANK: 4112841 Matrix: Water

Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	08/15/23 16:52	

LABORATORY CONTROL SAMPLE: 4112842

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	446	112	80-120	

SAMPLE DUPLICATE: 4112843

Parameter	Units	92682396001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	1890	1910	1	10	

SAMPLE DUPLICATE: 4112844

Parameter	Units	92682397001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	771	760	1	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

QC Batch: 793896

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

METHOD BLANK: 4113632

Matrix: Water

Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	08/16/23 13:58	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	08/16/23 13:58	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	08/16/23 13:58	

LABORATORY CONTROL SAMPLE: 4113633

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.1	104	80-120	

LABORATORY CONTROL SAMPLE: 4113634

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	55.0	110	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4113635 4113636

Parameter	Units	92682175001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	464	50	50	487	487	47	46	80-120	0	25	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4113637 4113638

Parameter	Units	92682175002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	12.5	50	50	65.7	65.4	106	106	80-120	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)
Pace Project No.: 92682397

QC Batch: 793500 Analysis Method: SM 4500-S2D-2011
QC Batch Method: SM 4500-S2D-2011 Analysis Description: 4500S2D Sulfide Water
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

METHOD BLANK: 4111958 Matrix: Water
Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	08/15/23 06:24	

LABORATORY CONTROL SAMPLE: 4111959

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.50	100	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4111960 4111961

Parameter	Units	92682396005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.50	0.45	99	89	80-120	11	10	R1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4111962 4111963

Parameter	Units	92682397007 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.53	0.55	104	108	80-120	4	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)
Pace Project No.: 92682397

QC Batch: 793550 Analysis Method: EPA 300.0 Rev 2.1 1993
QC Batch Method: EPA 300.0 Rev 2.1 1993 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92682397001

METHOD BLANK: 4112126 Matrix: Water
Associated Lab Samples: 92682397001

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	08/15/23 12:46	
Fluoride	mg/L	ND	0.10	0.050	08/15/23 12:46	
Sulfate	mg/L	ND	1.0	0.50	08/15/23 12:46	

LABORATORY CONTROL SAMPLE: 4112127

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	48.4	97	90-110	
Fluoride	mg/L	2.5	2.5	98	90-110	
Sulfate	mg/L	50	47.4	95	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4112128 4112129

Parameter	Units	92682198001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	ND	50	50	48.0	48.3	95	96	90-110	1	10	
Fluoride	mg/L	ND	2.5	2.5	2.4	2.4	94	95	90-110	1	10	
Sulfate	mg/L	ND	50	50	47.3	47.6	93	94	90-110	1	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4112130 4112131

Parameter	Units	92682396003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	141	50	50	179	180	77	78	90-110	0	10	M1
Fluoride	mg/L	0.56	2.5	2.5	3.1	3.2	102	104	90-110	2	10	
Sulfate	mg/L	762	50	50	787	789	50	53	90-110	0	10	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

QC Batch: 793553 Analysis Method: EPA 300.0 Rev 2.1 1993
QC Batch Method: EPA 300.0 Rev 2.1 1993 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

METHOD BLANK: 4112135 Matrix: Water
Associated Lab Samples: 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	08/15/23 22:01	
Fluoride	mg/L	ND	0.10	0.050	08/15/23 22:01	
Sulfate	mg/L	ND	1.0	0.50	08/15/23 22:01	

LABORATORY CONTROL SAMPLE: 4112136

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	49.5	99	90-110	
Fluoride	mg/L	2.5	2.5	100	90-110	
Sulfate	mg/L	50	48.3	97	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4112137 4112138

Parameter	Units	92682397002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	14.5	50	50	62.4	63.0	96	97	90-110	1	10	
Fluoride	mg/L	0.27	2.5	2.5	2.6	2.6	92	93	90-110	2	10	
Sulfate	mg/L	290	50	50	327	328	73	75	90-110	0	10 M1	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4112139 4112140

Parameter	Units	92682398009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	13.6	50	50	61.8	62.0	96	97	90-110	0	10	
Fluoride	mg/L	1.5	2.5	2.5	3.8	3.9	95	96	90-110	1	10	
Sulfate	mg/L	0.62J	50	50	47.3	47.5	93	94	90-110	1	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1 (CCR-CA)
Pace Project No.: 92682397

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above adjusted reporting limit.

TNTC - Too Numerous To Count

J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

MDL - Adjusted Method Detection Limit.

PQL - Practical Quantitation Limit.

RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected.

Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.

A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

ANALYTE QUALIFIERS

M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.
R1 RPD value was outside control limits.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92682397001	HAM-PT-07	EPA 3010A	793618	EPA 6010D	794582
92682397002	HAM-PT-08	EPA 3010A	793618	EPA 6010D	794582
92682397003	HAM-PT-09	EPA 3010A	793618	EPA 6010D	794582
92682397004	HAM-PT-10	EPA 3010A	795409	EPA 6010D	795455
92682397007	HAM-AP1-FD-06	EPA 3010A	795409	EPA 6010D	795455
92682397008	HAM-AP1-FB-06	EPA 3010A	795409	EPA 6010D	795455
92682397001	HAM-PT-07	EPA 3005A	794002	EPA 6020B	794064
92682397002	HAM-PT-08	EPA 3005A	794002	EPA 6020B	794064
92682397003	HAM-PT-09	EPA 3005A	794002	EPA 6020B	794064
92682397004	HAM-PT-10	EPA 3005A	794002	EPA 6020B	794064
92682397005	HAM-MW-53	EPA 3005A	794177	EPA 6020B	794304
92682397006	HAM-MW-54	EPA 3005A	794177	EPA 6020B	794304
92682397007	HAM-AP1-FD-06	EPA 3005A	794177	EPA 6020B	794304
92682397008	HAM-AP1-FB-06	EPA 3005A	794177	EPA 6020B	794304
92682397001	HAM-PT-07	EPA 7470A	794154	EPA 7470A	794256
92682397002	HAM-PT-08	EPA 7470A	794154	EPA 7470A	794256
92682397003	HAM-PT-09	EPA 7470A	794154	EPA 7470A	794256
92682397004	HAM-PT-10	EPA 7470A	794154	EPA 7470A	794256
92682397007	HAM-AP1-FD-06	EPA 7470A	794154	EPA 7470A	794256
92682397008	HAM-AP1-FB-06	EPA 7470A	794154	EPA 7470A	794256
92682397001	HAM-PT-07	SM 2540C-2015	793700		
92682397002	HAM-PT-08	SM 2540C-2015	793700		
92682397003	HAM-PT-09	SM 2540C-2015	793700		
92682397004	HAM-PT-10	SM 2540C-2015	793700		
92682397007	HAM-AP1-FD-06	SM 2540C-2015	793700		
92682397008	HAM-AP1-FB-06	SM 2540C-2015	793700		
92682397001	HAM-PT-07	SM 2320B-2011	793896		
92682397002	HAM-PT-08	SM 2320B-2011	793896		
92682397003	HAM-PT-09	SM 2320B-2011	793896		
92682397004	HAM-PT-10	SM 2320B-2011	793896		
92682397007	HAM-AP1-FD-06	SM 2320B-2011	793896		
92682397008	HAM-AP1-FB-06	SM 2320B-2011	793896		
92682397001	HAM-PT-07	SM 4500-S2D-2011	793500		
92682397002	HAM-PT-08	SM 4500-S2D-2011	793500		
92682397003	HAM-PT-09	SM 4500-S2D-2011	793500		
92682397004	HAM-PT-10	SM 4500-S2D-2011	793500		
92682397007	HAM-AP1-FD-06	SM 4500-S2D-2011	793500		
92682397008	HAM-AP1-FB-06	SM 4500-S2D-2011	793500		
92682397001	HAM-PT-07	EPA 300.0 Rev 2.1 1993	793550		
92682397002	HAM-PT-08	EPA 300.0 Rev 2.1 1993	793553		
92682397003	HAM-PT-09	EPA 300.0 Rev 2.1 1993	793553		
92682397004	HAM-PT-10	EPA 300.0 Rev 2.1 1993	793553		
92682397007	HAM-AP1-FD-06	EPA 300.0 Rev 2.1 1993	793553		
92682397008	HAM-AP1-FB-06	EPA 300.0 Rev 2.1 1993	793553		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



DC#_Title: ENV-FRM-HUN1-0083 v02_Sample Condition Upon Receipt

Effective Date: 11/14/2022

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

GA Power

Project #

WO# 92682397

Courier:

☐ Commercial☐ Fed Ex☒ Pace☐ UPS☐ USPS☐ Other:☐ Client

Custody Seal Present?

☐ Yes☒ No

Seals Intact?

☐ Yes☐ No

Packing Material:

☐ Bubble Wrap☐ Bubble Bags☒ None☐ Other

Thermometer:

☒ IR Gun ID:

230

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

3.1

Correction Factor:

Add/Subtract (°C)

0.0

Cooler Temp Corrected (°C):

3.1

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☒ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☒ No

Chain of Custody Present?

☒ Yes☐ No☐ N/A

Samples Arrived within Hold Time?

☒ Yes☐ No☐ N/A

Short Hold Time Analysis (<72 hr.)?

☒ Yes☐ No☐ N/A

Rush Turn Around Time Requested?

☐ Yes☐ No☐ N/A

Sufficient Volume?

☐ Yes☒ No☐ N/A

Correct Containers Used?

☒ Yes☐ No☐ N/A

-Pace Containers Used?

☒ Yes☐ No☐ N/A

Containers Intact?

☒ Yes☐ No☐ N/A

Dissolved analysis: Samples Field Filtered?

☐ Yes☐ No☒ N/A

Sample Labels Match COC?

☒ Yes☐ No☐ N/A

-Includes Date/Time/ID/Analysis Matrix:

W

Headspace in VOA Vials (>5-6mm)?

☐ Yes☐ No☒ N/A

Trip Blank Present?

☐ Yes☐ No☒ N/A

Trip Blank Custody Seals Present?

☐ Yes☐ No☒ N/A

Comments/Discrepancy:

Field Data Required? ☐ Yes ☒ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Project Manager SRF Review:

Date:

Date:



DC#_Title: ENV-FRM-HUN1-0083 v02_Sample Condition Upon Receipt

Effective Date: 11/14/2022

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

WO# 92682397

PM: BV

Due Date: 08/28/23

CLIENT: 92- GRHAM

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic ZN Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGFU-Wide-mouthed Glass jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG94-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit)-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A – lab)	SP2T-250 mL Sterile Plastic (N/A – lab)		BP3R-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	VSGU-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)
1		2	1																									
2		2	1																									
3		2	1																									
4		2	1																									
5																												
6																												
7		2	1																									
8		2	1																									
9																												
10																												
11																												
12																												

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers).

Field Sampling Forms

Low-Flow Test Report:

Test Date / Time: 7/13/2023 3:37:26 PM
Project: GW6581
Operator Name: Alana Neely

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 38.6 ft Total Depth: 48.6 ft Initial Depth to Water: 25.3 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 43.6 ft Estimated Total Volume Pumped: 9 L Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 884187
--	--	--

Test Notes:
Five bottles: Full App III and IV and Geochem

Weather Conditions:
73-91 deg F sunny

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
7/13/2023 3:37 PM	00:00	6.80 pH	28.25 °C	1,056.0 µS/cm	1.39 mg/L	21.70 NTU	-108.6 mV	25.30 ft	200.00 ml/min
7/13/2023 3:42 PM	05:00	6.81 pH	26.88 °C	1,079.0 µS/cm	0.68 mg/L	21.30 NTU	-111.1 mV	25.30 ft	200.00 ml/min
7/13/2023 3:47 PM	10:00	6.82 pH	26.52 °C	1,072.1 µS/cm	0.49 mg/L	18.70 NTU	-127.0 mV	25.30 ft	200.00 ml/min
7/13/2023 3:52 PM	15:00	6.80 pH	27.35 °C	1,080.9 µS/cm	0.48 mg/L	16.00 NTU	-128.2 mV	25.30 ft	200.00 ml/min
7/13/2023 3:57 PM	20:00	6.77 pH	27.44 °C	979.74 µS/cm	0.41 mg/L	9.81 NTU	-113.5 mV	25.30 ft	200.00 ml/min
7/13/2023 4:02 PM	25:00	6.76 pH	27.85 °C	1,068.5 µS/cm	0.35 mg/L	9.08 NTU	-126.8 mV	25.30 ft	200.00 ml/min
7/13/2023 4:07 PM	30:00	6.76 pH	27.68 °C	1,061.0 µS/cm	0.32 mg/L	6.69 NTU	-111.9 mV	25.30 ft	200.00 ml/min
7/13/2023 4:12 PM	35:00	6.75 pH	27.81 °C	1,069.4 µS/cm	0.29 mg/L	6.01 NTU	-125.6 mV	25.30 ft	200.00 ml/min
7/13/2023 4:17 PM	40:00	6.76 pH	27.26 °C	1,064.5 µS/cm	0.30 mg/L	4.91 NTU	-111.0 mV	25.30 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-07	Grab.

HAM-AP1-FD-01	Grab.
---------------	-------

Low-Flow Test Report:

Test Date / Time: 7/13/2023 5:11:34 PM
Project: GW6581
Operator Name: Alana Neely

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 33 ft Total Depth: 43 ft Initial Depth to Water: 22.2 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 38 ft Estimated Total Volume Pumped: 8 L Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.1 ft	Instrument Used: Aqua TROLL 400 Serial Number: 884187
--	---	--

Test Notes:
Five bottles: Full App III and IV and Geochem
Weather Conditions:
73-91 deg F sunny
Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
7/13/2023 5:11 PM	00:00	6.70 pH	26.09 °C	930.24 µS/cm	0.88 mg/L	20.20 NTU	-77.5 mV	22.30 ft	200.00 ml/min
7/13/2023 5:16 PM	05:00	6.68 pH	24.72 °C	960.77 µS/cm	1.07 mg/L	19.70 NTU	-81.4 mV	22.30 ft	200.00 ml/min
7/13/2023 5:21 PM	10:00	6.67 pH	24.21 °C	962.53 µS/cm	0.13 mg/L	24.30 NTU	-101.1 mV	22.30 ft	200.00 ml/min
7/13/2023 5:26 PM	15:00	6.66 pH	24.14 °C	972.51 µS/cm	0.11 mg/L	22.50 NTU	-107.9 mV	22.30 ft	200.00 ml/min
7/13/2023 5:31 PM	20:00	6.67 pH	24.49 °C	1,002.9 µS/cm	0.10 mg/L	8.59 NTU	-124.8 mV	22.30 ft	200.00 ml/min
7/13/2023 5:36 PM	25:00	6.68 pH	24.12 °C	999.67 µS/cm	0.08 mg/L	6.25 NTU	-115.1 mV	22.30 ft	200.00 ml/min
7/13/2023 5:41 PM	30:00	6.66 pH	24.79 °C	1,007.2 µS/cm	0.09 mg/L	7.11 NTU	-116.7 mV	22.30 ft	200.00 ml/min
7/13/2023 5:46 PM	35:00	6.66 pH	24.53 °C	1,007.1 µS/cm	0.09 mg/L	4.41 NTU	-124.9 mV	22.30 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.

Low-Flow Test Report:

Test Date / Time: 7/13/2023 11:06:04 AM
Project: GW6581
Operator Name: Alana Neely

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 18.5 ft Total Depth: 28.5 ft Initial Depth to Water: 14 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 23.5 ft Estimated Total Volume Pumped: 25.25 L Flow Cell Volume: 90 ml Final Flow Rate: 250 ml/min Final Draw Down: 0.1 ft	Instrument Used: Aqua TROLL 400 Serial Number: 884187
--	--	--

Test Notes:
Five bottles: Full App III and IV and Geochem

Weather Conditions:
73-91 deg F sunny

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
7/13/2023 11:06 AM	00:00	6.47 pH	23.91 °C	730.32 µS/cm	0.18 mg/L	3.55 NTU	32.8 mV	14.10 ft	250.00 ml/min
7/13/2023 11:07 AM	01:07	6.52 pH	23.22 °C	743.74 µS/cm	0.15 mg/L	-	11.4 mV	14.10 ft	250.00 ml/min
7/13/2023 11:12 AM	06:07	6.56 pH	22.23 °C	753.03 µS/cm	0.09 mg/L	2.51 NTU	6.0 mV	14.10 ft	250.00 ml/min
7/13/2023 11:17 AM	11:07	6.57 pH	22.47 °C	754.10 µS/cm	0.06 mg/L	2.49 NTU	3.4 mV	14.10 ft	250.00 ml/min
7/13/2023 11:22 AM	16:07	6.57 pH	22.10 °C	764.27 µS/cm	0.05 mg/L	4.55 NTU	-9.5 mV	14.10 ft	250.00 ml/min
7/13/2023 11:27 AM	21:07	6.58 pH	22.12 °C	768.51 µS/cm	0.04 mg/L	3.98 NTU	-12.2 mV	14.10 ft	250.00 ml/min
7/13/2023 11:32 AM	26:08	6.42 pH	22.27 °C	729.76 µS/cm	0.04 mg/L	4.56 NTU	4.1 mV	14.10 ft	250.00 ml/min
7/13/2023 11:37 AM	31:08	6.57 pH	22.45 °C	763.33 µS/cm	0.03 mg/L	10.50 NTU	3.6 mV	14.10 ft	250.00 ml/min
7/13/2023 11:42 AM	36:08	6.56 pH	22.99 °C	768.69 µS/cm	0.03 mg/L	16.20 NTU	-19.3 mV	14.10 ft	250.00 ml/min
7/13/2023 11:47 AM	41:08	6.45 pH	23.29 °C	723.65 µS/cm	0.03 mg/L	16.60 NTU	6.2 mV	14.10 ft	250.00 ml/min
7/13/2023 11:52 AM	46:08	6.54 pH	23.37 °C	768.73 µS/cm	0.04 mg/L	16.00 NTU	14.3 mV	14.10 ft	250.00 ml/min
7/13/2023 11:57 AM	51:08	6.56 pH	23.35 °C	767.51 µS/cm	0.03 mg/L	18.00 NTU	12.2 mV	14.10 ft	250.00 ml/min
7/13/2023 12:02 PM	56:08	6.56 pH	23.59 °C	770.87 µS/cm	0.02 mg/L	16.30 NTU	3.5 mV	14.10 ft	250.00 ml/min

7/13/2023 12:07 PM	01:01:08	6.56 pH	23.26 °C	771.12 µS/cm	0.02 mg/L	20.10 NTU	5.6 mV	14.10 ft	250.00 ml/min
7/13/2023 12:12 PM	01:06:08	6.56 pH	23.45 °C	773.37 µS/cm	0.02 mg/L	16.70 NTU	7.1 mV	14.10 ft	250.00 ml/min
7/13/2023 12:17 PM	01:11:08	6.56 pH	23.36 °C	775.77 µS/cm	0.02 mg/L	13.30 NTU	9.8 mV	14.10 ft	250.00 ml/min
7/13/2023 12:22 PM	01:16:08	6.57 pH	24.10 °C	773.97 µS/cm	0.02 mg/L	11.81 NTU	14.8 mV	14.10 ft	250.00 ml/min
7/13/2023 12:26 PM	01:20:29	6.57 pH	23.62 °C	771.90 µS/cm	0.02 mg/L	10.18 NTU	15.0 mV	14.10 ft	250.00 ml/min
7/13/2023 12:31 PM	01:25:29	6.57 pH	23.66 °C	776.24 µS/cm	0.02 mg/L	9.43 NTU	18.2 mV	14.10 ft	250.00 ml/min
7/13/2023 12:36 PM	01:30:29	6.57 pH	24.30 °C	779.12 µS/cm	0.02 mg/L	7.91 NTU	16.2 mV	14.10 ft	250.00 ml/min
7/13/2023 12:41 PM	01:35:29	6.57 pH	24.48 °C	779.77 µS/cm	0.02 mg/L	4.95 NTU	18.4 mV	14.10 ft	250.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.

Low-Flow Test Report:

Test Date / Time: 7/13/2023 1:16:15 PM
Project: GW6581
Operator Name: Alana Neely

Location Name: PT-10 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 18 ft Total Depth: 28 ft Initial Depth to Water: 14 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 23 ft Estimated Total Volume Pumped: 12 L Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.3 ft	Instrument Used: Aqua TROLL 400 Serial Number: 884187
--	--	--

Test Notes:
Five bottles: Full App III and IV and Geochem

Weather Conditions:
73-91 deg F; sunny

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 10	+/- 0.3	
7/13/2023 1:16 PM	00:00	7.05 pH	24.25 °C	808.38 µS/cm	0.31 mg/L	11.60 NTU	-135.4 mV	14.30 ft	200.00 ml/min
7/13/2023 1:21 PM	04:45	7.04 pH	22.90 °C	832.12 µS/cm	0.49 mg/L	20.60 NTU	-134.8 mV	14.30 ft	200.00 ml/min
7/13/2023 1:25 PM	09:02	7.05 pH	22.36 °C	827.40 µS/cm	0.12 mg/L	18.10 NTU	-142.1 mV	14.30 ft	200.00 ml/min
7/13/2023 1:30 PM	14:02	7.04 pH	21.87 °C	835.53 µS/cm	0.10 mg/L	13.20 NTU	-136.6 mV	14.30 ft	200.00 ml/min
7/13/2023 1:35 PM	19:02	7.03 pH	22.00 °C	831.33 µS/cm	0.08 mg/L	12.47 NTU	-182.4 mV	14.30 ft	200.00 ml/min
7/13/2023 1:40 PM	24:02	7.03 pH	22.23 °C	834.62 µS/cm	0.06 mg/L	10.64 NTU	-179.2 mV	14.30 ft	200.00 ml/min
7/13/2023 1:45 PM	29:02	7.02 pH	21.83 °C	837.40 µS/cm	0.05 mg/L	9.54 NTU	-126.6 mV	14.30 ft	200.00 ml/min
7/13/2023 1:50 PM	34:02	7.02 pH	22.13 °C	840.48 µS/cm	0.05 mg/L	8.72 NTU	-173.7 mV	14.30 ft	200.00 ml/min
7/13/2023 1:55 PM	39:02	7.02 pH	21.98 °C	834.18 µS/cm	0.04 mg/L	7.59 NTU	-122.1 mV	14.30 ft	200.00 ml/min
7/13/2023 2:00 PM	44:02	7.01 pH	21.89 °C	840.03 µS/cm	0.04 mg/L	6.56 NTU	-118.7 mV	14.30 ft	200.00 ml/min
7/13/2023 2:05 PM	49:02	7.01 pH	22.10 °C	840.92 µS/cm	0.03 mg/L	5.64 NTU	-163.8 mV	14.30 ft	200.00 ml/min
7/13/2023 2:10 PM	54:02	7.01 pH	21.95 °C	842.15 µS/cm	0.03 mg/L	4.94 NTU	-161.5 mV	14.30 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.

Low-Flow Test Report:

Test Date / Time: 8/9/2023 5:24:44 PM
Project: GP-Plant Hammond
Operator Name: Thomas Kessler

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 38.6 ft Total Depth: 47.94 ft Initial Depth to Water: 25.05 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 43.8 ft Estimated Total Volume Pumped: 8 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 850724
--	---	--

Test Notes:
Five bottles: Baseline Sampling and Major Ions

Weather Conditions:
Cloudy, 80 Degrees F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/9/2023 5:24 PM	00:00	6.69 pH	22.70 °C	979.72 µS/cm	0.65 mg/L	6.30 NTU	-88.9 mV	25.10 ft	200.00 ml/min
8/9/2023 5:29 PM	05:00	6.73 pH	21.85 °C	986.58 µS/cm	0.43 mg/L	4.87 NTU	-89.0 mV	25.10 ft	200.00 ml/min
8/9/2023 5:34 PM	10:00	6.76 pH	21.55 °C	992.34 µS/cm	0.48 mg/L	4.83 NTU	-89.8 mV	25.10 ft	200.00 ml/min
8/9/2023 5:39 PM	15:00	6.78 pH	21.44 °C	993.38 µS/cm	0.33 mg/L	5.08 NTU	-107.7 mV	25.10 ft	200.00 ml/min
8/9/2023 5:44 PM	20:00	6.79 pH	21.42 °C	1,008.3 µS/cm	0.41 mg/L	1.91 NTU	-90.6 mV	25.10 ft	200.00 ml/min
8/9/2023 5:49 PM	25:00	6.80 pH	21.36 °C	1,010.3 µS/cm	0.30 mg/L	0.80 NTU	-90.8 mV	25.10 ft	200.00 ml/min
8/9/2023 5:54 PM	30:00	6.82 pH	21.19 °C	1,012.4 µS/cm	0.40 mg/L	0.18 NTU	-90.9 mV	25.10 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-07	Grab.

Low-Flow Test Report:

Test Date / Time: 8/9/2023 10:03:54 AM
Project: GP-Plant Hammond
Operator Name: Elisabeth McDonnell

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 28.8 ft Total Depth: 42.0 ft Initial Depth to Water: 23.6 ft	Pump Type: Bladder pump Tubing Type: Peri Pump Intake From TOC: 37.3 ft Estimated Total Volume Pumped: 8 liter Flow Cell Volume: 90 ml Final Flow Rate: 160 ml/min Final Draw Down: 0.04 m	Instrument Used: Aqua TROLL 400 Serial Number: 989630
---	---	--

Test Notes:
Five bottles: Baseline Sampling and Major Ions

Weather Conditions:
Cloudy, 80 Degrees F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/9/2023 10:03 AM	00:00	6.80 pH	20.72 °C	943.04 µS/cm	2.15 mg/L	15.50 NTU	-57.8 mV	23.64 ft	160.00 ml/min
8/9/2023 10:08 AM	05:00	6.81 pH	20.71 °C	915.43 µS/cm	1.51 mg/L	10.90 NTU	-60.5 mV	23.63 ft	160.00 ml/min
8/9/2023 10:13 AM	10:00	6.81 pH	20.73 °C	905.45 µS/cm	1.62 mg/L	7.91 NTU	-61.7 mV	23.65 ft	160.00 ml/min
8/9/2023 10:18 AM	15:00	6.82 pH	20.59 °C	908.95 µS/cm	2.77 mg/L	4.08 NTU	-82.5 mV	23.64 ft	160.00 ml/min
8/9/2023 10:23 AM	20:00	6.82 pH	20.63 °C	911.77 µS/cm	1.38 mg/L	4.45 NTU	-84.8 mV	23.64 ft	160.00 ml/min
8/9/2023 10:28 AM	25:00	6.82 pH	20.57 °C	907.31 µS/cm	1.20 mg/L	4.04 NTU	-64.7 mV	23.63 ft	160.00 ml/min
8/9/2023 10:33 AM	30:00	6.83 pH	20.52 °C	905.19 µS/cm	0.97 mg/L	2.96 NTU	-85.5 mV	23.63 ft	160.00 ml/min
8/9/2023 10:38 AM	35:00	6.83 pH	20.58 °C	911.05 µS/cm	0.84 mg/L	3.40 NTU	-64.5 mV	23.63 ft	160.00 ml/min
8/9/2023 10:43 AM	40:00	6.82 pH	20.60 °C	909.15 µS/cm	0.94 mg/L	3.98 NTU	-84.4 mV	23.64 ft	160.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.
HAM-AP1-FD-06	Grab.

Low-Flow Test Report:

Test Date / Time: 8/9/2023 1:27:10 PM
Project: GP-Plant Hammond
Operator Name: Elisabeth McDonnell

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 28.8 ft Total Depth: 30.75 ft Initial Depth to Water: 14.99 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 26 ft Estimated Total Volume Pumped: 1.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 m	Instrument Used: Aqua TROLL 400 Serial Number: 989630
---	--	--

Test Notes:
Five bottles: Baseline Sampling and Major Ions

Weather Conditions:
Cloudy, 80 Degrees F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/9/2023 1:27 PM	00:00	6.76 pH	21.93 °C	745.27 µS/cm	4.47 mg/L	2.02 NTU	56.2 mV	14.99 ft	200.00 ml/min
8/9/2023 1:32 PM	05:00	6.81 pH	21.68 °C	771.52 µS/cm	3.35 mg/L	1.11 NTU	52.3 mV	14.99 ft	200.00 ml/min
8/9/2023 1:37 PM	10:00	6.85 pH	21.44 °C	786.50 µS/cm	2.58 mg/L	1.46 NTU	28.7 mV	14.99 ft	200.00 ml/min
8/9/2023 1:42 PM	15:00	6.86 pH	21.30 °C	797.33 µS/cm	6.17 mg/L	2.12 NTU	16.0 mV	14.99 ft	200.00 ml/min
8/9/2023 1:47 PM	20:00	6.87 pH	21.28 °C	797.79 µS/cm	2.58 mg/L	2.86 NTU	19.9 mV	14.99 ft	200.00 ml/min
8/9/2023 1:52 PM	25:00	6.88 pH	21.32 °C	806.94 µS/cm	3.88 mg/L	3.70 NTU	15.9 mV	14.99 ft	200.00 ml/min
8/9/2023 1:57 PM	30:00	6.88 pH	21.25 °C	797.98 µS/cm	0.84 mg/L	3.86 NTU	11.7 mV	14.99 ft	200.00 ml/min
8/9/2023 2:02 PM	35:00	6.88 pH	21.20 °C	794.19 µS/cm	0.80 mg/L	3.31 NTU	10.9 mV	14.99 ft	200.00 ml/min
8/9/2023 2:07 PM	40:00	6.88 pH	21.03 °C	791.25 µS/cm	1.44 mg/L	2.06 NTU	10.4 mV	14.99 ft	200.00 ml/min
8/9/2023 2:12 PM	45:00	6.89 pH	20.96 °C	770.10 µS/cm	0.72 mg/L	1.72 NTU	9.1 mV	14.99 ft	200.00 ml/min
8/9/2023 2:17 PM	50:00	6.88 pH	20.97 °C	792.63 µS/cm	0.55 mg/L	0.98 NTU	9.9 mV	14.99 ft	200.00 ml/min
8/9/2023 2:22 PM	55:00	6.89 pH	21.06 °C	791.96 µS/cm	1.03 mg/L	1.51 NTU	1.0 mV	14.99 ft	200.00 ml/min
8/9/2023 2:27 PM	01:00:00	6.89 pH	21.29 °C	791.26 µS/cm	0.63 mg/L	0.62 NTU	12.2 mV	14.99 ft	200.00 ml/min
8/9/2023 2:32 PM	01:05:00	6.89 pH	21.71 °C	825.29 µS/cm	0.44 mg/L	0.44 NTU	14.1 mV	14.99 ft	200.00 ml/min
8/9/2023 2:37 PM	01:10:00	6.89 pH	21.59 °C	826.86 µS/cm	0.58 mg/L	0.56 NTU	14.4 mV	14.99 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.

Low-Flow Test Report:

Test Date / Time: 8/9/2023 12:22:52 PM
Project: GP-Plant Hammond
Operator Name: Elisabeth McDonnell

Location Name: PT-10 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20 ft Total Depth: 31.75 ft Initial Depth to Water: 15.05 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 25 ft Estimated Total Volume Pumped: 5.8 liter Flow Cell Volume: 90 ml Final Flow Rate: 160 ml/min Final Draw Down: 0.13 m	Instrument Used: Aqua TROLL 400 Serial Number: 989630
--	--	--

Test Notes:
Five bottles: Baseline Sampling and Major Ions

Weather Conditions:
Cloudy, 80 Degrees F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/9/2023 12:22 PM	00:00	7.14 pH	22.18 °C	811.17 µS/cm	1.15 mg/L	24.10 NTU	-75.4 mV	15.18 ft	160.00 ml/min
8/9/2023 12:27 PM	05:00	7.15 pH	22.04 °C	798.04 µS/cm	0.38 mg/L	16.60 NTU	-75.5 mV	15.18 ft	160.00 ml/min
8/9/2023 12:32 PM	10:00	7.16 pH	21.96 °C	800.28 µS/cm	0.37 mg/L	11.80 NTU	-99.1 mV	15.18 ft	160.00 ml/min
8/9/2023 12:37 PM	15:00	7.16 pH	22.00 °C	793.73 µS/cm	0.33 mg/L	4.09 NTU	-78.0 mV	15.18 ft	160.00 ml/min
8/9/2023 12:42 PM	20:00	7.17 pH	21.46 °C	790.02 µS/cm	0.24 mg/L	4.11 NTU	-101.9 mV	15.18 ft	160.00 ml/min
8/9/2023 12:47 PM	25:00	7.18 pH	21.86 °C	782.36 µS/cm	0.16 mg/L	2.36 NTU	-81.4 mV	15.18 ft	160.00 ml/min
8/9/2023 12:52 PM	30:00	7.18 pH	21.79 °C	770.46 µS/cm	0.12 mg/L	4.55 NTU	-80.9 mV	15.18 ft	160.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.

Calibration Forms

EQUIPMENT CALIBRATION LOG

Field Technician: Amanda Neely

Date: 2/13/23

Time (start): 0850

Time (finish): 0910

smarTroll SN: 884187

Turbidity Meter Type: LaMotte 2020we

SN: 7009-1416

Weather Conditions: 73-91, sunny

Facility and Unit: Piant+Hammond

Project No.: GW6581

Calibration log

	Standard Lot # / Date of Expiration	Temp of Standard (°C)	Value of Standard	Initial Reading	Post-Cal Reading	Acceptable Range	Pass?	Comments
Specific Conductance (µS/cm)	22250153 11/23	25.72	4490	4122.4	4487.6	+/- 5 %	☒ Yes No	
pH (4)			4.00	4.02	4.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (4) check	-	-	4.00	-	-	+/- 0.1 SU	Yes No	
pH (7)	2216893 11/23	25.7	7.00	7.35	7.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (7) check	-	-	7.00	-	-	+/- 0.1 SU	Yes No	
pH (10)	21320202 12/23	25.5	10.00	10.3	10.0	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (10) check	-	-	10.00	-	-	+/- 0.1 SU	Yes No	
ORP (mV)	21390144 11/23	24.72	228	215.4	227.7	+/- 20mV	☒ Yes No	
DO (%) (1pt, 100% water saturated air cal)			100	101.11%	100.00%	+/- 6 % saturation	☒ Yes No	
Turbidity 0 NTU			0	0.20	0.00	+/- 0.5 NTU	☒ Yes No	
Turbidity 1 NTU			1.00	0.71	0.81	+/- 0.5 NTU	☒ Yes No	
Turbidity 10 NTU			10.00	11.30	9.99	+/- 0.5 NTU	☒ Yes No	

EQUIPMENT CALIBRATION LOG

Field Technician: Elisabeth McDonnell

Date: 8/9/23

Time (start): 830

Time (finish): 850

smarTroll SN: 989630

Turbidity Meter Type: La Motte 2020t

SN: 4109-2623

Weather Conditions: 10, cloudy

Facility and Unit: Plant Hammond

Project No.: GW6581

Calibration log

	Standard Lot # / Date of Expiration	Temp of Standard (°C)	Value of Standard	Initial Reading	Post-Cal Reading	Acceptable Range	Pass?	Comments
Specific Conductance (µS/cm)	22250153 11/23 ↓	23.18				+/- 5 %	Yes No	
pH (4)			4.00	3.94	4.00	+/- 0.1 SU	☒ Yes ☐ No	
Mid-Day pH (4) check						+/- 0.1 SU	Yes No	
pH (7)	2216893 11/23 ↓	23.48	7.0	6.85	7.0	+/- 0.1 SU	☒ Yes ☐ No	
Mid-Day pH (7) check						+/- 0.1 SU	Yes No	
pH (10)	21320202 12/23 ↓	23.70	10.0	10.0	10.0	+/- 0.1 SU	☒ Yes ☐ No	
Mid-Day pH (10) check						+/- 0.1 SU	Yes No	
ORP (mV)	21390149 11/23	23.85	228	230.90	228	+/- 20mV	☒ Yes ☐ No	
DO (%) (1pt, 100% water saturated air cal)			100%	102.36%	100%	+/- 6 % saturation	☒ Yes ☐ No	
Turbidity 0 NTU			0.0	0.0	0.0	+/- 0.5 NTU	☒ Yes ☐ No	
Turbidity 1 NTU			1.0	1.0	1.0	+/- 0.5 NTU	☒ Yes ☐ No	
Turbidity 10 NTU			10.0	11.1	10.4	+/- 0.5 NTU	☒ Yes ☐ No	

EQUIPMENT CALIBRATION LOG

Field Technician: Thomas Kessler

Date: 8/14/23

Time (start): 0800

Time (finish): 0825

smarTroll SN: 850729

Turbidity Meter Type: Lemotte 2020me

SN: 1475-2101

Weather Conditions: Seagun 75°

Facility and Unit: Plant Hammond

Project No: GLCS881

Calibration log

	Standard Lot # / Date of Expiration	Temp of Standard (°C)	Value of Standard	Initial Reading	Post-Cal Reading	Acceptable Range	Pass?	Comments
Specific Conductance (µS/cm)	2225053	21.91	4490	41562	4490	+/- 5 %	☒ Yes No	
pH (4)	11/23		4	4.04	4.0	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (4) check	↓	29	4	4.03	—	+/- 0.1 SU	☒ Yes No	
pH (7)	2226893 11/23	22.77	7.00 7.00	7.05	7.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (7) check	↓	29	7	6.98	—	+/- 0.1 SU	☒ Yes No	
pH (10)	21380202 12/23	22.62	10.00	10.01	10.0	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (10) check	↓	22	10	9.91	—	+/- 0.1 SU	☒ Yes No	
ORP (mV)	22260085 8/23		228	227.7	228	+/- 20mV	☒ Yes No	
DO (%) (1pt, 100% water saturated air cal)			100	99.08	100	+/- 6 % saturation	☒ Yes No	
Turbidity 0 NTU			0	.53	0	+/- 0.5 NTU	☒ Yes No	
Turbidity 1 NTU			1	.56	.93	+/- 0.5 NTU	☒ Yes No	
Turbidity 10 NTU			10	10.35	10.1	+/- 0.5 NTU	☒ Yes No	

APPENDIX C

Injection Field Forms

Injection Point Nomenclature Legend

IP-##	Injection point (IP) (<i>as shown on Figure 2</i>)
IP-## (#)	Offset IP with the distance (in ft) offset from the original IP indicated within parentheses.
IP-##A	Magnesium oxide (MgO) IP
IP-##A (#)	Offset MgO IP with the indicated offset distance from the original IP indicated with parentheses.

Injection Log

Project Name: Plant Hammond AP-Corrective Measure Date: 09/25/2023 Page 1 of

Project Number: 6N65161 Weather: Sunny

Field Personnel: M. Sadhasivan Activity: DPT Injection

Location: H6 WC-8 Area Start: Date 09/25/2023 Time 1415 Finish: Date Time

Well ID	Start Time (hr:mm)	Stop Time (hr:mm)	Volume Injected (gal)	Injection Pressure (psi)	Flowrate (GPM)	Notes
IP-05 17-18 ft	1415	1425	0	25psi	0.2	couldn't inject water
19-21 ft	1450			0	~3/12gpm	
19-21 ft	1500	1545	~240	1.6	4.8	Batch over Potable water
19-21 ft	1610			0.9	4.3	
19-21 ft	1620	1706	~492	1.0	4.4	Batch over
09/26/2023						
19-21 ft						
21-23 ft	0929	1003	~108	-1.9	3.4	Potable water
21-23 ft	1003	1156	~500	1.5	4.3	
23-25 ft	1206	1255	~250	3.2	5.2	
25-27 ft	1303	1352	~250	0.6	5.3	
25-27 ft	1400	1458	~250	1.2	5.5	
23-25 ft	1500	1550	~250	2.9	5.9	
09/27/2023						
IP-08 19-21 ft	1058	1130	~250	2.8	5.7	FeSO4 at 0.11 lbs per 1000 gal
19-21 ft	1130	1315	~250	4.0	5.9	
21-23 ft	1315	1540	~850	4.0	5.5	
23-25 ft	1540	1715	~500	3.9	6.4	
23-25 ft	09/28	2023		3.5ms	5.2ms	
23-25 ft	0844	0950	350	2.5	5.8	
25-27 ft	0950	1220	850	3.0	6.2	
IP-05 (2) 19-21 ft	1300	1310	50	3.9	5.2	stops injection due to
19-21 ft	1341	1430	250	3.9	5.4	lose an threaded from
19-21 ft	1430	1615	550	4.0	5.2	end cap
21-23 ft	1615	1650	200	4.0	6.0	

Injection Log

Project Name:	Plant Hammond AP 1 Corrosion ^{measures}	Date:	09/29/2023	Page	2 of
Project Number:	C9W 65816	Weather:	Sunny		
Field Personnel:	M. Sadhanvan	Activity:	DPT Injection		

Location: <u>H4WC-8 area</u>		Start: Date _____ Time _____		Finish: Date _____ Time _____		
Well ID	Start Time (hr:mm)	Stop Time (hr:mm)	Volume Injected (gal)	Injection Pressure (psi)	Flowrate (GPM)	Notes
9/2023						
(2) 21-23	0828	0913	250	3.6	5.6	
21-23	0913	0958	250	4	5.6	
21-23	0958	1025	150	4	5.6	
23-25	1025	1058	100	4	3	
23-25	1058	1119	750	4	4.2	
25-27	1119	1159	250	4	6.2	
25-27	1159	1241	250	4	6	
25-27	1241	1327	250	4	5.5	
25-27	1327	1345	100	4	5.6	
09/30/2023						
19-21	0853	0957	250	4	3.9	
19-21	0957	1116	250	4	3.2	
19-21	1116	1239	250	4	3	
19-21	1239	1312	100	4	3	
21-23	1312	1334	150	4	6.8	
21-23	1334	1412	250	4	6.6	
21-23	1412	1450	250	4	6.6	
21-23	1450	1521	200	4	6.5	
23-25	1521	1533	50	4	4.1	
23-25	1533	1637	250	4	3.9	
10/01/2023						
23-25	0745	0834	250	4	5.1	
23-25	0834	0919	250	4	5.6	
23-25	0919	0928	50	4	5.6	
25-27	0928	1002	200	4	5.9	

Injection Log

Project Name: Plant Hammond AP-1 corrective measure Date: 10/18/2023 Page 3 of

Project Number: GW65816 Weather: Sunny

Field Personnel: M. Sodhasivam Activity: DPT injection

Location: HGWC-8 area Start: Date Time Finish: Date Time

Well ID	Start Time (hr:mm)	Stop Time (hr:mm)	Volume Injected (gal)	Injection Pressure (psi)	Flowrate (GPM)	Notes
10/01/2023						
25-27	1002	1046	250	4	5.7	
25-27	1046	1132	250	4	5.5	
25-27	1132	1158	150	4	5.8	
19-21	1238	1257	100	4	5.3	
19-21	1257	1406	250	4	3.6	
19-21	1406	1526	250	4	3.1	
19-21	1526	1650	250	4	2.9	
10/02/2023						
21-23	0750	0839	250	4	5.1	
21-23	0839	0925	250	4	5.5	
21-23	0925	1009	250	4	5.7	
21-23	1009	1028	100	4	5.3	
23-25	1028	1116	150	4	3.1	
23-25	1116	1210	250	4	4.6	
23-25	1210	1305	250	4	4.5	
23-25	1305	1350	200	4	4.5	
25-27	1350	1407	50	4	2.9	
25-27	1407	1520	250	4	3.4	
25-27	1520	1630	250	4	3.6	
25-27	1630	1645	50	4	3.3	
10/03/2023						
25-27	0823	0925	250	4	3.2	

Injection Log

Project Name: Plant Hammond AP-1 corrective maintenance Date: 10/04/2023 Page 1 of 1

Project Number: 6-WB 5814 Weather: Sunny

Field Personnel: M. Sadhasivan Activity: DIT Injection

Location: HGWC-13 area Start Date: 10/04/23 Time: 11:15 Finish Date: 10/04/23 Time: 14:00

Well ID	Start Time (hr:mm)	Stop Time (hr:mm)	Volume Injected (gal)	Injection Pressure (psi)	Flowrate (GPM)	Notes
IP-01(2)						
10/04/2023						
35-37 ft	11:15	14:00	238	11	1.4	
10/09/2023						
IP-01(3) 37-39	1339	1415	175	11	3.9	
39-41	1419	1453	175	10	4.5	
41-43	1520	1601	175	11	4.5	
43-45	1605	1633	55	11	1.5	
10/10/2023						
IP-04(2) 35-37	0911	0949	175	11	5.0	
37-39	0953	1028	175	11	5.0	
39-41	1033	1118	175	11	3.9	
41-43	1124	1515	175	11	0.8	
45-47	1526	1735	350	11	4.4	
10/11/2023						
IP-04(2) 47-49	0750	0914	350	11	5.0	
IP-03 33-35	1049	1143	175	11	3.4	
IP-03 33-35	1147	1310	175	11	2.1	
IP-03 35-37	1315	1424	350	7.0	5.0	
IP-03 36.5-38.5	1442	1520	175	1.5	5.0	
IP-03 36.5-38.5	1520	1606	175	1.1	5.0	
IP-03(2) 41-43	1720	1754	175	1.2	5.0	
10/12/2023						
IP-03(2) 41-43	0800	0838	175	1.0	4.9	
IP-03(2) 43-45	0845	0956	350	3.5	5.0	

Injection Log

Project Name: Plant Hammond AP-1 Corrective Measure Date: 10/12/2023 Page 2 of

Project Number: GW6581G Weather: Cloudy

Field Personnel: M. Sadhasivan Activity: DPT Injection

Location: HGWC-13 area Start: Date 10/12/23 Time Finish: Date Time

	Well ID	Start Time (hr:mm)	Stop Time (hr:mm)	Volume Injected (gal)	Injection Pressure (psi)	Flowrate (GPM)	Notes
IP-032)	45-47	1003	1113	350	3.0	5.0	
IP-0312)	47-49	1120	1232	350	2.2	5.0	
IP-02	35-37	1317	1439	350	11	5.0	
IP-02	37-39	1445	1602	350	11	5.0	
IP-02	39-41	1613	1733	50	11	0.6	
	10/13/2023						
IP-02	41-43	0855	0955	350	11	3.5	
IP-02	43-45	1045	1207	175	11	2.2	
IP-02	43-45	1207	1250	175	11	3.6	
IP-02	45-47	1302	1415	350	3.8	4.6	
IP-02	47-49	1420	1537	350	4	4.7	
	465-485						
IP-0104)	33-35	1630	1726	175	11	3.0	
	10/14/2023						
IP-0104)	33-35	0847	0931	175	11	4.0	
IP-0104)	35-37	0942	1107	350	11	4.2	
IP-0104)	37-39	1114	1248	350	11	4.2	
IP-0104)	39-41	1254	1415	350	11	5.0	
IP-0104)	41-43	1420	1547	50	11	0.6	
IP-0104)	47-49	1604	1720	350	10	5.0	
	10/15/2023						
IP-08A	19-21	1148	1351	310	4.0	2.6	Daylighting
IP-08A	19-21	1457	1657	425	4.0	3.5	

Injection Log

Project Name: Plant Hemorrhoid Corrective measures Date: 10/16/2023 Page 3 of 3

Project Number: GN65816 Weather: Partly cloudy

Field Personnel: M. Sadhasivan Activity: BPT inspection

Location: <u>HC, WC - 8 area</u>	Start: Date <u>10/14/23</u> Time _____	Finish: Date _____ Time _____
----------------------------------	--	----------------------------------

TR-CHC

Injectate Batch Preparation Log

Project Name: Plant Hammond AP-1 injections Page 1 of 1
 Project Number: 6465816 Field Personnel: M. Sadhasivam
 Date: 09/25/2023 Weather: Sunny

Batch #	Tank Fill			FeSO4		Geochemical Parameters						Comments
	Start Time (hr:mm)	End Time (hr:mm)	Volume (gallons)	Time (hr:mm)	Amount (lb)	Time (hr:mm)	Temp (°C)	pH (SU)	Sp. Cond (µS/cm³)	DO (mg/L)	ORP (mV)	
09/25/23 Potable water	1100	1105	250	-	-	13:05	23.93	7.34	0.20	8.41	379.2	
09/25/23 Potable water	1550	1553	250	-	-	1555	25.01	7.66	0.19	7.86	562.0	
09/26/23 Potable water	0800	0820	500	-	-	0905	17.45	7.35	0.21	9.35	548.1	Batch 3 & 4
09/26/23 Potable water	1100	1115	500	-	-	1149	19.09	7.64	0.21	9.11	533.5	Batch 5 & 6
09/26/23 Potable water	1315	1330	500	-	-	1400	25.14	7.86	0.19	7.91	406.2	Batch 7 & 8
09/27/23 9	0945	0955	250	1015	0.0275	1020	19.94	8.61	0.65	8.61	122.5	IP-08 Batch 1 19-21
09/27/23 10	1115	1125	250	1125	0.0275	1130	20.51	8.52	0.83	8.52	81.2	IP-08 Batch 2 19-21
09/27/23 11	1150	1200	250	1200	0.0275	1208	20.02	8.25	0.66	8.71	545.7	IP-08 Batch 3 19-21
09/27/23 12	1245	1255	250	1256	0.0275	1258	19.82	8.27	0.48	8.75	621.4	IP-08 Batch 4 19-21
09/27/23 13	1340	1350	250	1350	0.0275	1351	19.80	8.24	0.44	8.92	543.6	IP-08 Batch 5 20-21
09/27/23 14	1430	1440	250	1440	0.0275	1450	19.54	8.26	0.40	8.79	513.2	IP-08 Batch 6 20-21
09/27/23 15	1540	1545	250	1545	0.0275	1551	18.96	8.31	0.42	8.94	200.4	IP-08 Batch 7 20-21
09/27/23 16	1625	1630	250	1630	0.0275	1632	18.84	8.14	0.31	8.96	179.3	IP-08 Batch 8 20-23 → add 200
09/28/23 17	0820	0830	250	0830	0.0275	0841	17.88	7.42	0.22	9.02	146.3	IP-08 Batch 9 (23-25)
09/28/23 18	0925	0930	250	0930	0.0275	0935	18.11	7.55	0.22	8.98	79.9	IP-08 Batch 10
09/28/23 19	1000	1005	250	1005	0.0275	1011	18.58	7.63	0.22	8.94	72.5	IP-08 Batch 11
09/28/23 20	1045	1050	250	1050	0.0275	1054	18.59	7.66	0.22	9.20	122.6	IP-08 Batch 12
09/28/23 21	1135	1140	250	1140	0.0275	1146	19.13	7.71	0.22	9.17	136.9	IP-08 Batch 13
09/28/23 22	1420	1425	250	1425	0.0275	1430	20.73	7.93	0.21	8.34	108.9	IP-05(2) Batch 2 ←
09/28/23 23	1300	1305	250	1305	0.0275	1320	19.85	7.88	0.22	8.81	87.1	IP-05(2) Batch 1 ←
09/28/23 24	1500	1505	250	1505	0.0275	1520	21.06	7.93	0.21	8.56	125.0	IP-05(2) Batch 3
09/28/23 25	1550	1555	250	1601	0.0275	1621	23.67	7.85	0.21	7.87	123.9	IP-05(2) Batch 4
09/29/23 26	0815	0820	250	0820	0.0275	0827	17.84	7.19	0.22	8.93	123.7	IP-05(2) Batch 5

Injectate Batch Preparation Log

Project Name: Plant Hammond AP-1 injections Page 2 of
 Project Number: GWN 6581 G Field Personnel: M. Sadhasivan
 Date: 09/29/2023 Weather: Sunny

Date	Batch #	Tank Fill			FeSO4		Geochemical Parameters						Comments
		Start Time (hr:mm)	End Time (hr:mm)	Volume (gallons)	Time (hr:mm)	Amount (lb)	Time (hr:mm)	Temp (°C)	pH (SU)	Sp. Cond (µs/cm³)	DO (mg/L)	ORP (mV)	
09/29/23	27	0900	0905	250	0905	0.0275	0910	18.69	7.56	0.22	8.68	83.1	
09/29/23	28	0950	0955	250	0955	0.0275	1000	18.90	7.64	0.21	8.73	64.4	
09/29/23	29	1055	1100	250	1100	0.0275	1102	19.82	7.70	0.22	8.86	145.7	
09/29/23	30	1155	1158	250	1158	0.0275	1201	19.97	7.76	0.22	8.74	123.1	
09/29/23	31	1300	1305	250	1305	0.0275	1306	25.54	7.68	0.20	7.48	68.8	
09/29/23	32	1415	1420	250	1420	0.0275	1425	24.68	7.88	0.21	7.98	126.7	
09/29/23	33	1450	1500	250	1500	0.0275	1502	22.61	7.96	0.22	8.61	68.4	
09/29/23	34	1535	1540	250	1540	0.0275	1545	23.14	7.94	0.21	8.42	96.5	
09/29/23	35	1622	1625	100	1625	0.011	1629	23.41	7.65	0.22	8.71	61.2	
					0840								
09/30/23	36	0835	0840	250	0837	0.0275	0842	17.38	7.47	0.22	9.00	76.2	
09/30/23	37	0950	1000	250	1000	0.0275	1003	19.14	7.49	0.22	8.79	85.2	
09/30/23	38	1115	1117	250	1117	0.0275	1119	24.31	7.51	0.20	7.11	105.8	
09/30/23	39	1237	1240	250	1240	0.0275	1242	23.16	7.48	0.21	8.61	97.6	
09/30/23	40	1335	1337	250	1337	0.0275	1341	25.43	7.63	0.18	6.14	104.5	
09/30/23	41	1414	1417	250	1417	0.0275	1420	24.76	7.54	0.21	7.21	103.2	
09/30/23	42	1448	1452	250	1452	0.0275	1454	23.34	7.86	0.21	8.08	143.2	
09/30/23	43	1533	1536	250	1536	0.0275	1540	23.41	7.68	0.22	8.16	121.3	
10/01/23	44	0730	0735	250	0735	0.0275	0755	17.41	7.36	0.22	9.16	141.7	
10/01/23	45	0834	0836	250	0836	0.0275	0840	16.16	7.66	0.22	10.01	94.9	
10/01/23	46	0919	0922	250	0922	0.0275	0925	18.21	7.85	0.21	9.86	121.1	
10/01/23	47	1003	1005	250	1005	0.0275	1007	19.58	7.59	0.21	8.69	146.9	
10/01/23	48	1046	1048	250	1048	0.0275	1050	22.16	7.64	0.22	8.42	139.6	
10/01/23	49	1121	1124	250	1124	0.0275	1128	24.59	7.49	0.21	7.75	152.4	
	50	1230	1235	250	1235	0.0275	1301	24.10	7.70	0.20	7.76	151.6	

Injectate Batch Preparation Log

Date: 10/01/23

Field Personnel: *M. Sadhasivan*

Weather

Summary

[illegible]

Injectate Batch Preparation Log

Project Name: Plant Hammond AP-1 injections Page 1 of
 Project Number: GWB5814 Field Personnel: M. Cadhavan
 Date: 10/09/2023 Weather: Sunny

Batch #	Tank Fill			FeSO4		Geochemical Parameters						Comments
	Start Time (hr:mm)	End Time (hr:mm)	Volume (gallons)	Time (hr:mm)	Amount (lb)	Time (hr:mm)	Temp (°C)	pH (SU)	Sp. Cond (µs/cm³)	DO (mg/L)	ORP (mV)	
10/01/2023 Potable	1250	1255	175	-	-	1305	15.21	7.31	0.21	8.61	303.6	
10/01/2023 Potable	1345	1407	175	-	-	1410	16.98	7.24	0.22	8.62	396.4	
10/01/2023 Potable	1510	1515	175	-	-	1520	18.26	7.16	0.21	7.90	385.7	
10/09/2023 Potable	1601	1604	175	-	-	1600	19.31	7.21	0.21	8.14	404.4	
10/10/23 #1	0902	0906	175	0906	0.0292	0908	15.61	7.48	0.19	8.63	80.2	
10/10/23 #2	0945	0948	175	0948	0.0292	0950	16.82	7.51	0.20	8.96	121.6	
10/10/23 #3	1028	1031	175	1031	0.0292	1033	18.44	7.46	0.20	8.56	196.8	
10/10/23 #4	1118	1121	175	1121	0.0292	1130	19.68	7.49	0.20	8.43	123.6	
10/10/23 #6	1521	1524	175	1524	0.0292	1530	22.61	7.32	0.21	8.96	186.4	
10/10/23 #6	1652	1654	175	1654	0.0292	1655	23.78	7.48	0.22	8.12	141.3	
10/11/23 #7	0759	0802	175	0802	0.0292	0804	16.41	7.39	0.20	8.21	128.6	
10/11/23 #8	0835	0835	175	0835	0.0292	0837	17.68	7.56	0.20	7.96	153.6	
10/11/23 IP-03												
10/11/23 #1	1044	1047	175	1047	0.0292	1051	18.71	7.44	0.20	8.33	129.6	
10/11/23 #2	1140	1145	175	1145	0.0292	1154	18.92	7.51	0.21	8.54	134.7	
10/11/23 #3	1310	1313	175	1313	0.0292	1317	19.01	7.53	0.20	7.96	102.9	
10/11/23 #4	1347	1349	175	1349	0.0292	1352	19.34	7.46	0.22	8.71	111.3	
10/11/23 #5	1437	1440	175	1440	0.0292	1445	19.51	7.37	0.19	7.88	127.4	
10/11/23 #6	1525	1530	175	1530	0.0292	1535	19.88	7.49	0.20	8.54	107.8	
10/11/23 #7	1710	1715	175	1715	0.0292	1720	20.71	7.50	0.21	8.31	148.6	
10/12/23 #8	0755	0757	175	0757	0.0292	0800	16.78	7.56	0.22	8.62	122.7	
10/12/23 #9	0838	0841	175	0841	0.0292	0843	16.96	7.48	0.21	7.99	135.4	
10/12/23 #10	0919	0921	175	0921	0.0292	0924	17.21	7.42	0.22	8.04	101.6	
10/12/23 #11	1000	1002	175	1002	0.0292	1005	17.48	7.49	0.20	8.36	86.9	

Injectate Batch Preparation Log

Project Name: Plant Hammond AP-1 Injection Page 2 of

Project Number: GWB5816

Field Personnel: M. Sedgewick

Date: 10/12/2023

Weather:

Batch #	Tank Fill			FeSO4		Geochemical Parameters						Comments
	Start Time (hr:mm)	End Time (hr:mm)	Volume (gallons)	Time (hr:mm)	Amount (lb)	Time (hr:mm)	Temp (°C)	pH (SU)	Sp. Cond (µs/cm³)	DO (mg/L)	ORP (mV)	
10/12/2023 #12	1033	1036	175	1036	0.0292	1038	18.26	7.48	0.20	8.65	86.7	
10/12/2023 #13	1116	1118	175	1118	0.0292	1120	18.91	7.66	0.21	7.98	103.4	
10/12/2023 #14	1153	1155	175	1155	0.0292	1200	18.74	7.50	0.20	8.32	99.8	
10/12/2023 #1	1311	1314	175	1314	0.0292	1318	18.38	7.52	0.21	8.04	121.8	
10/12/2023 #2	1354	1357	175	1357	0.0292	1400	19.21	7.39	0.21	8.96	116.7	
10/12/2023 #3	1443	1445	175	1448	0.0292	1448	19.74	7.54	0.21	7.44	125.5	
10/12/2023 #4	1519	1521	175	1521	0.0292	1525	19.62	7.49	0.21	9.31	136.9	
10/12/2023 #5	1604	1606	175	1606	0.0292	1615	20.17	7.68	0.22	8.76	120.4	
10/13/2023 #6	0850	0854	250	0854	0.041	0900	16.24	7.42	0.19	7.21	103.6	
10/13/2023 #7	1040	1044	175	1044	0.0292	1047	17.18	7.55	0.20	8.62	139.4	
10/13/2023 #8	1203	1206	175	1206	0.0292	1210	17.63	7.39	0.20	9.38	146.8	
10/13/2023 #9	1258	1300	175	1300	0.0292	1304	18.04	7.44	0.22	9.16	121.1	
10/13/2023 #10	1327	1330	175	1330	0.0292	1335	18.96	7.46	0.20	7.24	111.7	
10/13/2023 #11	1415	1418	175	1418	0.0292	1424	19.42	7.52	0.19	8.96	102.9	
10/13/2023 #12	1454	1458	175	1458	0.0292	1502	19.31	7.38	0.18	8.54	136.4	
10/13/2023 #1	1625	1629	175	1629	0.0292	1632	18.98	7.51	0.19	8.66	124.5	
10/14/2023 #2	0750	0755	175	0755	0.0292	0800	16.81	7.44	0.20	7.34	125.6	
10/14/2023 #3	0940	0943	175	0943	0.0292	0947	17.28	7.38	0.20	7.71	133.6	
10/14/2023 #4	1024	1027	175	1027	0.0292	1030	17.96	7.52	0.22	8.89	139.8	
10/14/2023 #5	1110	1112	175	1112	0.0292	1115	18.54	7.56	0.19	7.42	146.7	
10/14/2023 #6	1203	1205	175	1205	0.0292	1210	19.61	7.49	0.21	8.36	140.4	
10/14/2023 #7	1250	1253	175	1253	0.0292	1300	20.21	7.50	0.20	8.41	127.9	
10/14/2023 #8	1330	1333	175	1333	0.0292	1335	20.78	7.36	0.19	8.44	119.6	

2024 Pilot Study Post- Injection Event Report, Plant Hammond Ash Pond 1



Prepared for

Georgia Power Company
241 Ralph McGill Blvd NE
Atlanta, Georgia 30308

PILOT STUDY POST-INJECTION EVENT REPORT

**PILOT TEST NO. UPT000068
PLANT HAMMOND ASH POND 1 (AP-1)**

Prepared by

Geosyntec
consultants

engineers | scientists | innovators

1255 Roberts Boulevard, Suite 200
Kennesaw, Georgia 30144

Project Number GW6581G

August 2024

CERTIFICATION STATEMENT

I hereby certify that this *Pilot Study Post-Injection Event Report* was prepared by, or under the direct supervision of, a Qualified Groundwater Scientist, in accordance with the Georgia Environmental Protection Division Rules of Solid Waste Management. According to 391-3-4-.01, a Qualified Groundwater Scientist is “a professional engineer or geologist registered to practice in Georgia who has received a baccalaureate or post-graduate degree in the natural sciences or engineering and has sufficient training and experience in groundwater hydrology and related fields that enable individuals to make sound professional judgments regarding groundwater monitoring, contaminant fate and transport, and corrective action.” The design presented within this workplan was developed in compliance with the Georgia Rules of Solid Waste Management, Chapter 391-3-4.10.



Whitney B. Law
Georgia Professional Engineer No. 36641

August 23, 2024
Date

TABLE OF CONTENTS

1.	BACKGROUND AND OBJECTIVES	1
1.1	Site Background	1
2.	WELL INSTALLATION	3
3.	BASELINE CHARACTERIZATION.....	4
4.	INJECTION ACTIVITIES	5
4.1	HGWC-8 Injection Area (East Area)	6
4.2	HGWC-13 Injection Area (Southwest Area).....	6
5.	Pilot Study PERFORMANCE MONITORING AND REPORTING	7
6.	REFERENCES	8

LIST OF TABLES

Table 1	Summary of Well Construction Details
Table 2	Summary of Baseline Groundwater Analytical Data
Table 3	Summary of Daily Injection Volumes
Table 4	Summary of Air Sparging Activities
Table 5	Summary of Screening-Level Injection Activities Analytical Data

LIST OF FIGURES

Figure 1	Site Location Map
Figure 2	Pilot Study Well Locations

LIST OF APPENDICES

Appendix A	Well Design, Installation, and Development Report – Addendum No. 6
Appendix B	Baseline Analytical Laboratory Results and Field Sampling Forms
Appendix C	Injection Field Forms

Appendix D Screening-Level Injection Activities Analytical Laboratory Reports

LIST OF ACRONYMS

AP-1	Ash Pond 1
CCR	coal combustion residual
CFR	Code of Federal Regulations
DO	dissolved oxygen
FeSO ₄	ferrous sulfate
g/L	grams per liter
gal	gallons
gpd	gallons per day
gpm	gallons per minute
GA EPD	Georgia Environmental Protection Division
Georgia Power	Georgia Power Company
Geosyntec	Geosyntec Consultants, Inc.
GWPS	Groundwater Protection Standard
MNA	monitored natural attenuation
ORP	oxidation-reduction potential
Pathfinder	Pathfinder Automated Injection System
psi	pounds per square inch
ROI	radius of influence
SSL	statistically significant level
SCFM	standard cubic feet per minute
UIC	Underground Injection Control
US EPA	United States Environmental Protection Agency

1. BACKGROUND AND OBJECTIVES

This *Pilot Study Post-Injection Event Report* (Report) was developed by Geosyntec Consultants, Inc. (Geosyntec) on behalf of Georgia Power Company (Georgia Power) for submittal to the Georgia Environmental Protection Division (GA EPD). In-situ geochemical injections, coupled with monitored natural attenuation (MNA), have been proposed as corrective measures to address concentrations of molybdenum (Mo) and arsenic (As) reported at statistically significant levels (SSLs) above Groundwater Protection Standards (GWPS) in detection monitoring wells HGWC-8 and HGWC-13¹, respectively, at Georgia Power Plant Hammond Ash Pond 1 (AP-1; Site).

Design of in-situ geochemical injection corrective measures includes multiple assessment and design components, including pilot studies to evaluate injection delivery and the performance of injectates prior to implementing a full scale remedy. These pilot tests will collect data that will be used to evaluate:

1. Radius of influence (ROI) of the injected amendment to evaluate future injection point spacing requirements;
2. Sustainable injection pressure and flowrate; and
3. Injectate dosing and efficacy of treating As and Mo in groundwater to below the GWPS.

This Report summarizes pilot study field activities completed in April through July 2024. These field activities were conducted in accordance with the *HGWC-8 Supplemental Pilot Study Workplan* and the *HGWC-13 Supplemental Pilot Study Workplan*² (collectively referred to herein as “Workplans”; GEOS Submittal ID: 830620) (Geosyntec, 2024b, 2024c) and the Underground Injection Control (UIC) Pilot Test Notification Form approved by GA EPD’s UIC and Solid Waste Management Programs on May 6 and June 21, 2024, respectively.

1.1 Site Background

Plant Hammond, shown on **Figure 1**, is located in Floyd County, approximately 10 miles west of Rome, Georgia. Plant Hammond was a four-unit, coal-fired electric generating

¹ The Mo and As GWPS are 0.1 and 0.01 mg/L, respectively.

² These Workplans are in accordance with the GA EPD approved *HGWC-8 Pilot Study Workplan* and *HGWC-13 Pilot Study Workplan* (Geosyntec, 2023b; 2023c).

facility and was retired on July 29, 2019. The physical address of the plant is 5963 Alabama Highway, Rome, Georgia, 30165.

AP-1 is one of four coal combustion residual (CCR) ponds utilized over the course of power generation at Plant Hammond. AP-1 is a 35-acre surface impoundment located near the center of Plant Hammond and was used primarily as a dewatering facility for fly ash and bottom ash. AP-1 closure activities, consisting of closure by removal, have been initiated under GA EPD's approved closure permit No. 057-023D(CCR).

As documented in the *Draft Remedy Selection Report* (Geosyntec, 2022), CCR groundwater monitoring-related activities are performed at AP-1 in accordance with the United States Environmental Protection Agency (US EPA) CCR Rule (federal CCR Rule) (40 Code of Federal Regulations [CFR] 257 Subpart D). The locations of AP-1 detection monitoring wells, assessment monitoring wells, and piezometers are shown on **Figure 2**.

A Mo SSL was identified at detection well HGWC-8 along the eastern boundary of AP-1 and an As SSL was identified at detection monitoring well HGWC-13 along the southwest boundary of AP-1 (**Figure 2**) as part of the assessment monitoring program. These SSLs have been horizontally and vertically delineated to levels below the GWPS (Geosyntec, 2022).

2. WELL INSTALLATION

Three injection wells (INW-03 through INW-05), four air sparge wells (AS-01 through AS-04), and five performance monitoring wells (PT-11 through PT-15) were installed in April and May 2024 in accordance with the Workplans³. Well locations are shown on **Figure 2** and well construction details are provided in **Table 1**. A copy of the *Well Design, Installation, and Development Report – Addendum No. 6* detailing the design, installation, and development of these wells is included in **Appendix A**.

³ Well construction details were adjusted in the field based on lithological observations during installation.

3. BASELINE CHARACTERIZATION

Groundwater samples were collected from performance monitoring wells to establish pre-injection baseline conditions.

Groundwater samples and water quality field parameters (i.e., pH, conductivity, dissolved oxygen [DO], temperature, and oxidation-reduction potential [ORP]) were collected using low-flow sampling procedures in accordance with the current AP-1 *Groundwater Monitoring Plan* (Geosyntec, 2023a) and the Workplans. Groundwater samples were placed in ice-packed coolers and submitted to Pace Analytical Services, LLC (Pace Analytical) in Peachtree Corners, Georgia, following chain-of-custody protocol. Samples were analyzed for Appendix III and IV constituents, select geochemical parameters, and metals in accordance with the Workplans to support evaluation of injectate efficacy. The results for the May 2024 sampling events are presented in **Table 2**. The analytical laboratory results and field sampling and equipment calibration forms are provided in **Appendix B**.

4. INJECTION ACTIVITIES

Injection activities were performed July 9 – 31, 2024. Staging and mixing areas were established prior to injection, in accordance with the approved Workplans. Three-hundred-gallon (gal) cone bottom mixing tanks were set up within a secondary containment, with spill kits maintained on-site to manage any spills. Injectate consisted of Thermo Fisher Scientific, Inc. ferrous sulfate (FeSO_4) heptahydrate mixed with potable water obtained from an on-site fire hydrant designated in the Workplans.

Pre-determined quantities of FeSO_4 were measured on a digital scale and combined with potable water in mix tanks. The injectate was mixed using a recirculation pump prior to injection in accordance with the Workplans. Injectate batches consisted of 0.5 – 1.0 grams per liter (g/L) FeSO_4 heptahydrate, which is below the maximum allowable injectate concentration of 2 g/L FeSO_4 heptahydrate set forth in the Workplans.

Injection pressures, flowrates, and water levels in performance monitoring wells were measured throughout injection activities, and the daily maximum injection volume across pilot study areas was below maximum daily values included in the Pilot Test Notification Form (3,500 gal per day [gpd]). Injection volumes and compositions are summarized in **Table 3**. Field forms are included in **Appendix C**.

In addition to the injection of FeSO_4 heptahydrate, air sparging activities were performed in the HGWC-13 Injection Area (Southwest Area). Air sparging flow rates and pressures were monitored throughout the sparging activities and were below the values included in the Pilot Test Notification Form (25 standard cubic feet per minute [SCFM] and 15 pounds per square inch [psi]). Air sparging flowrates and durations are summarized in **Table 4**.

Screening level groundwater grab samples were collected and analyzed for select total and dissolved⁴ metals during injection activities to evaluate ongoing injection performance while in the field. Screening-level groundwater analytical results are summarized in **Table 5** and the associated analytical laboratory reports are included in **Appendix D**. Visual turbidity, resulting from concurrent injection and air sparge activities, was observed during sampling. As such, both total metals and filtered samples were collected for comparison.

⁴ Dissolved samples were filtered in the field.

4.1 HGWC-8 Injection Area (East Area)

Injections at INW-03 (shown on **Figure 2**) were primarily completed using the Pathfinder Automated Injection System (Pathfinder). All observed injection flowrates and pressures were below the Pilot Test Notification Form maximum allowable values⁵. Approximately 3,317 gal of injectate was injected over three days, with a daily maximum injected volume of 1,211 gal.

4.2 HGWC-13 Injection Area (Southwest Area)

Injections at INW-04 and INW-05 (shown on **Figure 2**) utilized two different methods. Injections were initially gravity fed by connecting injectate mix tanks located at ground surface and three feet above ground surface next to injection wellheads. Maximum observed flow rates and pressures during gravity fed injections were below Workplan maximums and were approximately 1 gal per minute (gpm) and 2.5 psi, respectively.

Subsequent injections utilized the Pathfinder system. The maximum observed flowrate and pressure was 5 gpm and 11 psi, respectively, while using the Pathfinder system. Approximately 9,709 gal of injectate was injected at INW-04 and INW-05 over 9 days, with a daily maximum of 1,805 gal injected.

⁵ 15 gpm and 4 psi, respectively.

5. PILOT STUDY PERFORMANCE MONITORING AND REPORTING

In accordance with the Workplans, groundwater quality data from each performance monitoring event will be compared against the Mo and As GWPS and the results of the baseline characterization to evaluate the efficacy geochemical injections. In addition, Appendix IV monitoring parameters⁶ will be analyzed and monitored over the duration of the pilot study to evaluate potential localized mobilization of other Appendix IV parameters following injections.

Pilot study results will be reported to GA EPD Solid Waste Management Program as part of semiannual groundwater monitoring and corrective action reporting. Links to these reports will be emailed to the GA EPD Wastewater Regulatory Program. A comprehensive technical memorandum will be prepared at the conclusion of the pilot study.

⁶ Excluding radium.

6. REFERENCES

Geosyntec, 2022. *Draft Remedy Selection Report, Georgia Power Company, Plant Hammond Ash Pond 1 (AP-1)*. August 2022.

Geosyntec, 2023a. *Groundwater Monitoring Plan – Plant Hammond Ash Pond 1 (AP-1)*. July 2023, revision 2.

Geosyntec, 2023b. *HGWC-8 Pilot Study Workplan, Plant Hammond Ash Pond 1 (AP-1)*. August 2023.

Geosyntec, 2023c. *HGWC-13 Pilot Study Workplan, Plant Hammond Ash Pond 1 (AP-1)*. August 2023.

Geosyntec, 2024a. *HGWC-8 Supplemental Pilot Study Workplan, Plant Hammond Ash Pond 1 (AP-1)*. August 2023.

Geosyntec, 2024b. *HGWC-13 Supplemental Pilot Study Workplan, Plant Hammond Ash Pond 1 (AP-1)*. August 2023.

TABLES

Table 1
Summary of Well Construction Details
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area	Well ID	Well Completion	Installation Date	Northing ⁽¹⁾	Easting ⁽¹⁾	Ground Surface Elevation ⁽¹⁾ (ft)	Top of Casing Elevation ⁽¹⁾ (ft)	Top of Screen Elevation (ft)	Bottom of Screen Elevation (ft)	Well Depth (ft bgs) ⁽²⁾
HGWC-13 (Southwest Area)	Temporary Sparge Wells									
	AS-03	Flush Mount	4/28/2024	1548670.10	1940933.87	591.98	591.60	545.98	543.98	48.30
	AS-04	Flush Mount	4/28/2024	1548680.80	1940930.83	591.97	591.50	544.97	542.97	49.30
	Injection Wells									
	INW-04	Flush Mount	4/28/2024	1548671.73	1940929.98	592.01	591.58	557.01	547.01	45.30
	INW-05	Flush Mount	4/28/2024	1548680.07	1940935.89	591.81	591.31	556.81	546.81	45.30
	Performance Monitoring Wells									
	PT-07 ⁽³⁾	Flush Mount	6/3/2023	1548675.24	1940933.39	592.00	591.75	554.40	544.30	48.00
	PT-08 ⁽³⁾	Flush Mount	6/3/2023	1548666.82	1940929.58	592.10	591.83	560.20	550.20	42.20
	PT-13	Flush Mount	4/28/2024	1548676.04	1940939.23	591.88	591.47	556.88	546.88	45.30
	PT-14	Flush Mount	4/28/2024	1548673.63	1940926.52	592.06	591.62	557.06	547.06	45.30
	PT-15	Flush Mount	4/28/2024	1548668.35	1940937.45	591.90	591.37	556.90	546.90	45.30
HGWC-8 (East Area)	Temporary Sparge Wells									
	AS-01	Flush Mount	5/7/2024	1549048.28	1942388.06	577.46	577.08	548.46	546.46	31.30
	AS-02	Flush Mount	5/6/2024	1549049.08	1942400.03	577.14	576.72	547.14	545.14	32.30
	Injection Well									
	INW-03	Flush Mount	5/6/2024	1549052.75	1942388.28	577.38	577.07	560.28	550.28	27.40
	Performance Monitoring Wells									
	PT-09 ⁽³⁾	Protective Riser	6/1/2023	1549049.74	1942393.11	577.33	580.35	560.18	550.18	27.45
	PT-10 ⁽³⁾	Protective Riser	6/1/2023	1549040.34	1942413.88	577.39	580.44	560.29	550.29	27.40
	PT-11	Flush Mount	5/7/2024	1549055.61	1942390.89	577.35	576.96	560.75	550.75	26.90
	PT-12	Flush Mount	5/7/2024	1549045.43	1942391.10	577.34	576.84	560.34	550.34	27.30

Notes:

ft = feet.

ft bgs = feet below ground surface.

(1) Coordinates in North American Datum (NAD) 1983, State Plane, Georgia-West, feet. Elevations referenced to the North American Vertical Datum of 1988 (NAVD88).

Survey data from wells installed in 2024 was certified by GEL Solutions (GEL) July 1, 2024. Survey data from wells installed in 2023 certified by GEL on July 17, 2023, and August 30, 2023.

(2) Total well depth accounts for 0.3 ft sump.

(3) Well was previously constructed in accordance with the HGWC-8 and HGWC-13 Pilot Study Workplans.

Table 2
Summary of Baseline Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area:		HGWC-13 (Southwest Area)													
Well ID:		INW-04	INW-04	INW-05	INW-05	PT-07	PT-07	PT-08	PT-08	PT-13	PT-13	PT-14	PT-14	PT-15	PT-15
Sample Date:		5/2/2024	5/15/2024	5/2/2024	5/15/2024	5/9/2024	5/16/2024	5/2/2024	5/16/2024	5/9/2024	5/15/2024	5/2/2024	5/15/2024	5/2/2024	5/15/2024
	Parameter ^(1,2,3)														
APPENDIX III	Boron	0.61	0.59	0.54	0.51	0.55	0.50	0.75	0.73	0.54	0.52	0.51	0.51	0.75	0.76
	Calcium	110	107	108	101	98.0	96.0	141	89.4	94.4	99.2	101	97.4	141	141
	Chloride	8.0	9.9	6.0	6.9	9.2	10	11.8	16.7	9.0	9.5	7.9	10.5	11.8	12.6
	Fluoride	0.47	0.28	0.59	0.37	0.33	0.31	0.55	0.19	0.35	0.34	0.43	0.26	0.55	0.35
	pH	6.78	6.84	6.87	7.01	6.86	6.98	6.53	6.49	6.84	6.93	6.83	6.78	6.95	7.01
	Sulfate	180	187	206	181	177	171	176	159	195	190	169	175	278	271
	TDS	482	483	526	456	463	450	477	410	472	459	462	461	638	639
APPENDIX IV	Antimony	< 0.00054	< 0.00054	0.00098 J	< 0.00054	0.00059 J	< 0.00054	< 0.00054	< 0.00054	< 0.00054	< 0.00054	< 0.00054	< 0.00054	< 0.00054	< 0.00054
	Arsenic	0.21	0.19	0.24	0.23	0.30	0.27	0.26	0.23	0.30	0.29	0.22	0.21	0.41	0.39
	Barium	0.042	0.043	0.032	0.033	0.037	0.034	0.045	0.041	0.036	0.033	0.037	0.038	0.044	0.043
	Beryllium	< 0.000094	< 0.000094	0.000099 J	0.00012 J	0.00010 J	< 0.000094	< 0.000094	< 0.000094	< 0.000094	< 0.000094	< 0.000094	0.00016 J	< 0.000094	< 0.000094
	Cadmium	< 0.00010	< 0.00010	< 0.00010	< 0.00010	< 0.00010	< 0.00010	< 0.00010	< 0.00010	< 0.00010	< 0.00010	< 0.00010	< 0.00010	< 0.00010	< 0.00010
	Chromium	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019
	Cobalt	0.029	0.031	0.028	0.026	0.041	0.052	0.054	0.046	0.026	0.024	0.021	0.020	0.052	0.059
	Fluoride	0.47	0.28	0.59	0.37	0.33	0.31	0.36	0.19	0.35	0.34	0.43	0.26	0.55	0.35
	Lead	< 0.0016	< 0.00016	< 0.00016	< 0.00016	< 0.00016	< 0.00016	< 0.00016	0.0079	< 0.00016	< 0.00016	< 0.00016	0.00046 J	< 0.00016	< 0.00016
	Lithium	0.048	0.043	0.060	0.057	0.064	0.056	0.016 J	0.010 J	0.061	0.058	0.055	0.051	0.051	0.047
	Mercury	< 0.00013	< 0.00013	< 0.00013	< 0.00013	12.5	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013
	Molybdenum	0.016	0.015	0.0094 J	0.0096 J	0.010	0.0093 J	0.017	0.017	0.0095 J	0.0087 J	0.011	0.011	0.017	0.021
	Selenium	0.0050 U	< 0.00096	0.0050 U	< 0.00096	< 0.00096	< 0.00096	0.0050 U	< 0.00096	< 0.00096	< 0.00096	0.0050 U	< 0.00096	< 0.00096	< 0.00096
	Thallium	0.00048 J	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038
INORGANICS	Alkalinity (Bicarbonate) as CaCO ₃	128	133	109	123	117	116	108	104	106	111	121	121	124	134
	Alkalinity (Carbonate) as CaCO ₃	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0
	Alkalinity (Total) as CaCO ₃	128	133	109	123	117	116	108	104	106	111	121	121	124	134
	Sodium	6.9	7.0	6.5	6.7	6.8	7.0	7.2	7.2	< 0.00096	7.8	6.7	6.7	6.8	8.1
	Sulfide	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.00038	< 0.022	< 0.022	< 0.022	278	< 0.022
METALS	Iron	10.3	8.4	17.3	16.9	16.9	15.7	8.5	8.0	15.5	15.0	13.7	14.9	9.7	9.2
	Magnesium	13.5	13.1	12.6	11.8	12.5	12.1	12.0	11.5	11.4	12.0	12.7	12.7	15.6	16.1
	Manganese	4.2	4.4	3.6	3.3	3.2	3.4	3.9	3.3	3.5	3.6	3.1	3.1	5.6	5.7
	Potassium	5.4	4.8	5.2	4.7	5.6	4.9	5.3	4.8	5.0	5.0	5.4	5.0	5.2	5.3
FIELD	Dissolved Oxygen	0.72	0.48	0.06	0.36	0.37	2.33	1.01	0.51	0.16	1.10	0.05	0.05	-0.03	0.10
	Oxidation-Reduction Potential (mV)	-96.1	-97.4	-120.9	-124.3	-100.6	-91.9	154.4	-29.0	-104.0	-98.3	-116.5	-110.0	93.8	-118.3
	Temperature (°C)	20.57	19.86	18.17	19.19	20.53	19.39	21.27	19.16	20.75	18.64	19.09	18.75	21.71	20.45
	Specific Conductance (µS/cm)	674.04	693.52	706.51	675.78	665.99	671.25	691.07	626.30	670.23	683.83	636.04	671.71	868.60	863.09
	pH (s.u.)	6.78	6.94	6.87	7.01	6.86	6.98	6.53	6.49	6.84	6.93	6.83	6.78	6.95	7.01
	Turbidity (NTU)	4.11	4.92	4.15	4.97	1.06	13.80	8.60	4.10	2.27	4.82	4.27	4.99	2.99	0.77

Notes:
< = Indicates the parameter was not detected above the analytical method detection limit (MDL)
°C = degrees Celsius
J = Indicates the parameter was estimated and detected between the MDL and the reporting limit (RL)
U = Data validation qualifier that indicates the parameter was analyzed for, but not detected.
µS/cm = microsiemens per centimeter
mV = millivolts
NTU = nephelometric turbidity units
s.u. = standard units
TDS = Total dissolved solids
(1) Appendix III/IV parameter per 40 CFR 257 Subpart D. Analysis of combined radium omitted from the pilot study monitoring program. Unless otherwise indicated, parameters are reported in units of milligrams per liter (mg/L)
(2) Metals were analyzed by EPA Method 6010D, 6020B, and 7470A, anions were analyzed by EPA Method 300.0, TDS was analyzed by SM2540C-2015
(3) The pH value presented was recorded at the time of sample collection in the field

Table 2
Summary of Baseline Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

Pilot Study Area:			HGWC-8 (East Area)								
Well ID:		INW-03	INW-03	PT-09	PT-09	PT-10	PT-10	PT-11	PT-11	PT-12	PT-12
Sample Date:		5/14/2024	5/29/2024	5/14/2024	5/30/2024	5/15/2024	5/30/2024	5/14/2024	5/30/2024	5/14/2024	5/30/2024
	Parameter ^(1,2,3)										
APPENDIX III	Boron	1.5	1.5	1.4	1.5	1.5	1.4	1.6	1.4	1.6	1.5
	Calcium	127	144	82.8	94.9	108	95.9	90.9	95.7	99.7	91.0
	Chloride	56.9	61.6	44.4	52.4	50.1	53.0	41.4	39.4	50.3	48.0
	Fluoride	0.20	0.13	0.37	0.33	0.22	0.17	0.34	0.31	0.20	0.31
	pH	7.68	7.36	7.16	7.06	6.92	6.81	6.98	7.00	6.58	6.82
	Sulfate	178	187	130 M1	133	146	124	122	118	125	131
	TDS	564	610	436	532	503	495	441	474	523	488
APPENDIX IV	Antimony	< 0.00054	<0.00054	< 0.00054	< 0.00054	< 0.00054	< 0.00054	< 0.00054	< 0.00054	< 0.00054	< 0.00054
	Arsenic	< 0.00084	< 0.0022 J	< 0.00084	0.0022 J	< 0.00084	0.0018 J	< 0.00084	0.0021 J	< 0.00084	0.0026 J
	Barium	0.075	0.12	0.058	0.062	0.054	0.052	0.057	0.072	0.069	0.069
	Beryllium	< 0.000094	< 0.000094	< 0.000094	< 0.000094	< 0.000094	< 0.000094	< 0.000094	< 0.000094	< 0.000094	< 0.000094
	Cadmium	< 0.0010	< 0.00010	0.00015 J	0.00010 J	< 0.00010	< 0.00010	0.00013 J	0.00013 J	0.00014 J	0.00011 J
	Chromium	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019	< 0.0019
	Cobalt	0.00070 J	0.00087 J	0.0012 J	0.0010 J	0.0016 J	0.0014 J	0.0016 J	0.0013 J	0.0044 J	0.0021 J
	Fluoride	0.20	0.13	0.37	0.33	0.22	0.17	0.34	0.31	0.20	0.31
	Lead	< 0.00016	< 0.00016	0.00017 J	< 0.00016	< 0.00016	< 0.00016	< 0.00016	< 0.00016	0.00017 J	< 0.00016
	Lithium	0.0050 J	0.0048 J	< 0.0016	< 0.0016	< 0.0016	< 0.0016	< 0.0016	< 0.0016	< 0.0016	< 0.0016
	Mercury	< 0.00013	< 0.00013	< 0.00013	<0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013	< 0.00013
	Molybdenum	0.082	0.060	0.27	0.24	0.092	0.053	0.24	0.17	0.085	0.22
	Selenium	< 0.00096	0.0016 J	< 0.00096	< 0.00096	< 0.00096	< 0.00096	< 0.00096	< 0.00096	< 0.00096	0.0015 J
	Thallium	< 0.00038	<0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038	< 0.00038
INORGANICS	Alkalinity (Bicarbonate) as CaCO ₃	175	176	139	138	132	116	125	143	129	136
	Alkalinity (Carbonate) as CaCO ₃	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0	< 5.0
	Alkalinity (Total) as CaCO ₃	175	176	139	138	132	116	125	143	129	136
	Sodium	12.4	11.1	9.3	11.5	9.2	9.5	8.8	9.2	11.8	9.6
	Sulfide	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022	< 0.022
METALS	Iron	0.11	0.14	0.42	0.24	0.24	0.21	< 0.025	0.10	0.33	0.032 J
	Magnesium	17.1	16.5	23.7	19.9	14.3	13.1	16.2	16.7	16.6	18.6
	Manganese	0.45	1.2	0.19	0.28	0.74	0.52	0.28	0.27	1.0	0.75
	Potassium	13.8	6.1	6.1	6.2	6.7	6.6	6.0	6.5	6.8	5.7
FIELD	Dissolved Oxygen	0.25	0.61	0.04	0.05	0.25	0.43	0.07	0.42	0.32	0.71
	Oxidation-Reduction Potential (mV)	43.0	-26.7	49.9	83.4	20.1	52.5	28.7	161.9	58.8	81.4
	Temperature (°C)	18.77	20.17	17.76	19.69	20.00	20.16	18.11	19.15	18.81	19.36
	Specific Conductance (µS/cm)	835.04	864.90	681.69	703.83	707.36	664.75	676.01	708.73	685.68	678.21
	pH (s.u.)	7.68	7.36	7.16	7.06	6.92	6.81	6.98	7.00	6.58	6.82
	Turbidity (NTU)	4.98	0.56	4.98	4.71	4.92	3.01	1.43	3.84	4.71	0.73

Notes:
< = Indicates the parameter was not detected
°C = degrees Celsius
J = Indicates the parameter was estimated an
U = Data validation qualifier that indicates th
µS/cm = microsiemens per centimeter
mV = millivolts
NTU = nephelometric turbidity units
s.u. = standard units
TDS = Total dissolved solids
(1) Appendix III/IV parameter per 40 CFR 2
in units of milligrams per liter (mg/L)
(2) Metals were analyzed by EPA Method 6
(3) The pH value presented was recorded at

Table 3
Summary of Daily Injection Volumes
Plant Hammond AP-1, Floyd County, Georgia

Date	HGWC-8 (East Area)		HGWC-13 (Southwest Area)	
	Daily Injection Volume (gal)	FeSO ₄ Concentration of Injectate (g/L)	Daily Injection Volume (gal)	FeSO ₄ Concentration of Injectate (g/L)
07/09/2024	--	--	480*	--
07/10/2024	--	--	950	0.5
07/11/2024	900	0.5	--	--
07/12/2024	--	--	947	0.5
07/13/2024	1,206	0.5	--	--
07/14/2024	--	--	1,798 ⁽¹⁾	0.5
07/15/2024	1,211	1.0	--	--
07/16/2024	--	--	1,800 ⁽¹⁾	0.5
07/23/2024	--	--	1,505 ⁽¹⁾	1.0
07/24/2024	--	--	1,805 ⁽¹⁾	1.0
07/29/2024	--	--	904 ⁽¹⁾	1.0
07/31/2024	--	--	307*	--
TOTAL:	3,317	--	10,496	--

Notes:

-- = indicates no injections occurred on this date.

* = indicates injection consisted of potable water.

gal = gallons

g/L = grams per liter.

(1) Injection volumes represent total volume injected simultaneously between two injection wells, INW-04 and INW-05.

Table 4
Summary of Air Sparging Activities
HGWC 13 Pilot Area, Plant Hammond AP-1, Floyd County, GA

Well-ID	Date	Flow Rate (SCFM)	Duration (hours)
AS-03	7/26/2024	<1.0	2
AS-03	7/27/2024	<1.0	3
AS-04	7/27/2024	<2.0	1
AS-03	7/28/2024	<1.7	3
AS-03	7/29/2024	1.8	3

Notes:

SCFM = standard cubic feet per minute.

Table 5
Summary of Screening-Level Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

	Parameter (^{1,2}):			Total Iron	Dissolved Iron	Total Boron	Dissolved Boron	Total Molybdenum	Dissolved Molybdenum	Total Arsenic	Dissolved Arsenic
	Well ID	Sample Date	Sample Time								
HGWC-8 (East Area)	PT-09	5/31/2024 ⁽³⁾	11:52 AM	0.24	--	1.5	--	0.24	--	0.0022 J	--
		7/11/2024	6:00 PM	0.56	0.02	1.5	1.4	0.43	0.42	--	--
		7/13/2024	8:45 AM	0.36	< 0.018	1.4	1.5	0.34	0.33	--	--
		7/13/2024	4:38 PM	0.66	0.3	1.1	1.2	0.29	0.29	--	--
		7/15/2024	8:22 AM	0.38	0.031	1.2	1.3	0.30	0.27	--	--
		7/15/2024	4:02 PM	6.3	3.8	1.0	1.0	0.13	0.12	--	--
		7/17/2024	1:42 PM	0.78	0.46	1.0	1.0	0.25	0.24	--	--
	PT-10	5/30/2024 ⁽³⁾	2:40 PM	0.21	--	1.4	--	0.053	--	0.0018 J	
		7/11/2024	6:00 PM	0.37	< 0.018	1.6	1.7	0.16	0.15	--	--
		7/13/2024	8:50 AM	0.19	< 0.018	1.6	1.7	0.16	0.17	--	--
		7/13/2024	4:40 PM	0.12	< 0.018	1.6	1.7	0.18	0.16	--	--
		7/15/2024	5:19 PM	0.14	--	1.7	--	0.16	--	--	--
		7/17/2024	1:44 PM	0.10	--	1.7	--	0.17	--	--	--
	PT-11	5/29/2024 ⁽³⁾	4:43 PM	0.10	--	1.4	--	0.17	--	0.0021 J	--
		7/11/2024	8:00 PM	3.2	2.4	0.69	0.72	0.05	0.05	--	--
		7/13/2024	5:56 PM	11	9	0.57	0.6	0.02	0.02	--	--
		7/15/2024	8:46 AM	2.4	1.6	0.85	0.87	0.04	0.04	--	--
		7/15/2024	4:15 PM	44	37	0.49	0.51	0.01	0.01	--	--
		7/17/2024	9:22 AM	13	12	0.8	0.82	0.01	0.01	--	--
		7/24/2024	10:05 AM	4.9	3.6	1.2	1.2	0.05	0.04	--	--
	PT-12	5/29/2024 ⁽³⁾	12:08 PM	0.032 J	--	1.5	--	0.22	--	0.0026 J	--
		7/11/2024	8:15 PM	0.1	< 0.018	1.5	1.6	0.31	0.30	--	--
		7/13/2024	5:54 PM	0.22	0.024	1.2	1.3	0.23	0.23	--	--
		7/15/2024	5:20 PM	0.49	--	1.2	--	0.14	--	--	--
		7/17/2024	12:04 PM	0.6	< 0.018	1.2	1.3	0.23	0.23	--	--

Table 5
Summary of Screening-Level Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia



	Parameter (^{1,2}):			Total Iron	Dissolved Iron	Total Boron	Dissolved Boron	Total Molybdenum	Dissolved Molybdenum	Total Arsenic	Dissolved Arsenic
	Well ID	Sample Date	Sample Time								
HWC-13 Area (Southwest Area)	PT-07	5/16/2024 ⁽³⁾	12:16 PM	15.7	--	0.50	--	0.0093 J	--	0.27	--
		7/10/2024	7:40 PM	41	14	0.54	0.49	--	--	0.32	0.23
		7/12/2024	6:12 PM	17	12	0.52	0.52	--	--	0.24	0.16
		7/18/2024	2:00 PM	21	16	0.58	0.59	--	--	0.28	0.26
		7/26/2024	8:10 PM	140	0.19	0.7	0.58	--	--	0.64	0.052
		7/27/2024	5:00 PM	190	0.6	0.71	0.56	--	--	0.29	0.025
		7/28/2024	5:00 PM	31	0.46	0.63	0.56	--	--	0.097	0.026
		7/29/2024	9:05 AM	26	6.4	0.6	0.54	--	--	0.13	0.055
		7/29/2024	6:43 PM	23	12	0.56	0.54	--	--	0.13	0.088
		7/30/2024	8:55 AM	31	12	0.62	0.57	--	--	0.18	0.091
		7/30/2024	6:00 PM	160	1.4	0.76	0.59	--	--	0.39	0.045
		7/31/2024	9:40 AM	110	2.8	0.61	0.51	--	--	0.44	0.03
	PT-08	5/16/2024 ⁽³⁾	10:37 AM	8.0	--	0.73	--	0.017	--	0.23	--
		7/10/2024	9:00 PM	22	9.1	0.74	0.69	--	--	0.33	0.26
		7/16/2024	6:00 AM	7.3	7.4	0.8	0.76	--	--	0.25	0.28
		7/16/2024	7:55 AM	22	9.9	0.76	0.65	--	--	0.34	0.30
		7/18/2024	8:47 PM	8.8	7.5	0.72	0.75	--	--	0.29	0.26
		7/24/2024	9:00 AM	21	11	0.7	0.71	--	--	0.3	0.26
		7/24/2024	8:00 PM	23	9.3	0.63	0.63	--	--	0.31	0.25
		7/25/2024	4:50 PM	17	--	0.67	--	--	--	0.35	--
		7/28/2024	4:30 PM	26	7.7	0.75	0.66	--	--	0.42	0.17
		7/30/2024	5:50 PM	25	7.7	0.78	0.7	--	--	0.34	0.12
		7/31/2024	10:00 AM	34	13	0.65	0.61	--	--	0.43	0.16
	PT-13	5/15/2024 ⁽³⁾	6:45 PM	15	--	0.52	--	0.0087 J	--	0.29	--
		7/10/2024	8:12 PM	80	11	0.56	0.56	--	--	0.29	0.23
		7/12/2024	7:14 PM	24	13	0.58	0.59	--	--	0.3	0.23
		7/14/2024	8:30 AM	27	15	0.61	0.57	--	--	0.3	0.29
		7/14/2024	5:00 PM	28	20	0.45	0.43	--	--	0.27	0.23
		7/18/2024	11:47 AM	18	15	0.53	0.56	--	--	0.29	0.27
		7/24/2024	8:00 PM	66	51	0.39	0.39	--	--	0.2	0.15
		7/25/2024	3:20 PM	38	--	0.55	--	--	--	0.3	--
		7/26/2024	8:20 PM	42	16	0.54	0.5	--	--	0.26	0.18
		7/27/2024	5:00 PM	30	12	0.6	0.5	--	--	0.26	0.083
		7/28/2024	4:20 PM	23	13	0.59	0.51	--	--	0.19	0.11
		7/30/2024	6:10 PM	24	13	0.57	0.56	--	--	0.17	0.076
		7/31/2024	9:50 AM	36	23	0.56	0.54	--	--	0.22	0.13

Table 5
Summary of Screening-Level Groundwater Analytical Data
Plant Hammond AP-1, Floyd County, Georgia

	Parameter (^{1,2}):			Total Iron	Dissolved Iron	Total Boron	Dissolved Boron	Total Molybdenum	Dissolved Molybdenum	Total Arsenic	Dissolved Arsenic
	Well ID	Sample Date	Sample Time								
HGWC-13 Area (Southwest Area)	PT-14	5/15/2024 ⁽³⁾	6:27 PM	15	--	0.51	--	0.011	--	0.21	--
		7/12/2024	6:47 PM	53	10	0.46	0.44	--	--	0.17	0.079
		7/14/2024	8:30 AM	48	14	0.68	0.66	--	--	0.20	0.18
		7/14/2024	5:15 PM	73	19	0.32	0.28	--	--	0.14	0.035
		7/16/2024	7:45 AM	63	13	0.62	0.64	--	--	0.24	0.15
		7/16/2024	6:00 PM	34	20	0.62	0.40	--	--	0.08	0.024
		7/18/2024	4:32 PM	18	14	0.64	0.66	--	--	0.21	0.2
		7/24/2024	9:00 AM	87	24	0.68	0.61	--	--	0.21	0.051
		7/24/2024	8:00 PM	250	71	0.53	0.37	--	--	0.21	0.0043
		7/25/2024	2:40 PM	130	28	0.60	0.58	--	--	0.20	0.056
		7/26/2024	10:10 AM	40	18	0.63	0.57	--	--	0.16	0.14
		7/26/2024	8:00 PM	38	18	0.62	0.57	--	--	0.16	0.15
		7/27/2024	5:00 PM	62	2.3	0.67	0.57	--	--	0.26	0.019
		7/28/2024	3:30 PM	22	15	0.65	0.59	--	--	0.13	0.12
		7/29/2024	9:05 AM	52	16	0.62	0.57	--	--	0.20	0.13
		7/29/2024	12:00 PM	64	22	0.46	0.5	--	--	0.04	0.019
		7/29/2024	1:00 PM	120	53	0.46	0.36	--	--	0.093	0.022
		7/29/2024	3:00 PM	160	75	0.36	0.31	--	--	0.098	0.02
		7/29/2024	6:33 PM	110	70	0.43	0.38	--	--	0.095	0.012
		7/30/2024	9:05 AM	25	19	0.63	0.58	--	--	0.053	0.034
		7/30/2024	5:40 PM	32	17	0.63	0.59	--	--	0.11	0.054
		7/31/2024	9:10 AM	34	18	0.61	0.56	--	--	0.18	0.11
		7/31/2024	3:40 PM	17	4.3	0.31	0.32	--	--	0.051	0.014
	PT-15	5/15/2024 ⁽³⁾	4:10 PM	9.2	--	0.76	--	0.021	--	0.39	--
		7/14/2024	5:30 PM	14	8.2	0.69	0.69	--	--	0.42	0.38
		7/18/2024	6:13 PM	9.4	7.7	0.7	0.72	--	--	0.42	0.41
		7/24/2024	9:00 AM	13	12	0.65	0.64	--	--	0.33	0.36
		7/25/2024	4:40 PM	18	--	0.69	--	--	--	0.48	--

Notes:
< = Indicates the parameter was not detected above the analytical method detection limit (MDL).
-- = indicates sample was not collected on this date or sample was not analyzed for that parameter.
J = Indicates the parameter was estimated and detected between the MDL and the reporting limit (RL).
(1) Parameters are reported in units of milligrams per liter (mg/L).
(2) Metals were analyzed by EPA Method 6010D, 6020B.
(3) Data was collected from a baseline sampling event that occurred pre-injection activities.


FIGURES




LEGEND
[Red dashed line] Plant Hammond Property Boundary




Note:
1. Aerial photograph source: Google Earth Pro, August 2019 and Georgia Power Company, February 2023.



SITE LOCATION MAP		
GEORGIA POWER COMPANY PLANT HAMMOND AP-1 ROME, FLOYD COUNTY, GEORGIA		
Prepared For:		FIGURE 1
Prepared By:		
KENNESAW, GA	AUGUST 2024	





LEGEND

-  Detection Monitoring Well
-  Horizontal Assessment Monitoring Well
-  Vertical Assessment Monitoring Well
-  Piezometer
-  Surface Water Level Gauge Point
-  Temporary Sparge Well
-  Injection Well
-  Performance Monitoring Well
-  Approximate AP-1 Boundary
-  Plant Hammond Property Boundary
-  Approximate Groundwater Flow Direction

Notes:

- Piezometers INW-03, INW-04, INW-05, AS-01 through AS-04, and PT-07 through PT-15 were installed in support of an Assessment of Corrective Measures (ACM) geochemical injections pilot study and are not included in the routine semiannual sampling of the monitoring well network.
- Aerial photograph source: Google Earth Pro, August 2019, and Georgia Power Company, January 2024.



SCALE IN FEET

PILOT STUDY WELL LOCATIONS

GEORGIA POWER COMPANY
PLANT HAMMOND AP-1
ROME, FLOYD COUNTY, GEORGIA

Prepared For: 	FIGURE 2
Prepared By: 	
KENNESAW, GA AUGUST 2024	

APPENDIX A

Well Design, Installation, and Development Report – Addendum No. 6



Prepared for

Georgia Power Company

241 Ralph McGill Blvd NE

Atlanta, Georgia 30308

WELL DESIGN, INSTALLATION, AND DEVELOPMENT REPORT - ADDENDUM

No. 6

**PLANT HAMMOND ASH POND 1
(AP-1)**

Prepared by

Geosyntec
consultants

engineers | scientists | innovators

1255 Roberts Boulevard, Suite 200

Kennesaw, Georgia 30144

Project Number GW6581E

August 2024



CERTIFICATION PAGE

I hereby certify that this *Well Design, Installation, and Development Report – Addendum No. 6, Plant Hammond Ash Pond 1 (AP-1)* has been prepared by, or under the direct supervision of, a Qualified Groundwater Scientist with Geosyntec Consultants, Inc. and is in compliance with the United States Environmental Protection Agency Coal Combustion Residual Rule [40 Code of Federal Regulations 257 Subpart D], specifically §257.91(e)(1), and the Georgia Environmental Protection Division Rules for Solid Waste Management 391-3-4-.10.

According to 391-3-4-.01, a Qualified Groundwater Scientist is “a professional engineer or geologist registered to practice in Georgia who has received a baccalaureate or post-graduate degree in the natural sciences or engineering and has sufficient training and experience in groundwater hydrology and related fields that enable individuals to make sound professional judgments regarding groundwater monitoring, contaminant fate and transport, and corrective action.”



A handwritten signature in blue ink that reads "Christine Hug".

Christine Hug P.G.
Georgia Professional Geologist No. 002221
Project Manager
Geosyntec Consultants

August 23, 2024

Date

TABLE OF CONTENTS

1. INTRODUCTION 1

2. DRILLING AND WELL INSTALLATION..... 2

2.1 Drilling Method 2

2.2 Screened Interval 2

2.3 Well Casings and Screens..... 2

2.4 Well Intake Design 3

2.5 Filter Pack..... 3

2.6 Annular Seal 4

2.7 Cap and Protective Casing..... 4

3. WELL DEVELOPMENT 4

4. SURVEY 5

5. REFERENCES 6

LIST OF TABLES

Table 1 Summary of Well Construction Details

LIST OF FIGURES

Figure 1 Groundwater Monitoring Network Map

LIST OF APPENDICES

Appendix A Well Driller Performance Bonds

Appendix B Boring and Well Construction Logs

Appendix C Well Development and Equipment Calibration Forms

Appendix D Certified Well Survey Data

LIST OF ACRONYMS

ACM	Assessment of Corrective Measures
AP	Ash Pond
ASTM	American Society for Testing and Materials
CCR	coal combustion residual
CFR	Code of Federal Regulations
DO	dissolved oxygen
GA EPD	Georgia Environmental Protection Division
Georgia Power	Georgia Power Company
Geosyntec	Geosyntec Consultants, Inc.
NAD	North America Datum
NAVD	North American Vertical Datum
NSF	National Sanitation Foundation
ORP	oxygen reduction potential
PG	professional geologist
PVC	polyvinyl chloride
SCS	Southern Company Services
TOC	top of casing
US EPA	United States Environmental Protection Agency

1. INTRODUCTION

This report provides details regarding the design, installation, and development of twelve piezometers¹ (AS-01, AS-02, AS-03, AS-04, INW-03, INW-04, INW-05, PT-11, PT-12, PT-13, PT-14, and PT-15) to supplement the current groundwater monitoring system at Georgia Power Company (Georgia Power) Plant Hammond (Site) Ash Pond 1 (AP-1). The report was prepared as an addendum to previously submitted well design, installation, development and decommissioning reports issued for the Site (ERM, 2017; Geosyntec 2019, 2020a, 2020b, 2020c, and 2023), and meets the requirements promulgated in the United States Environmental Protection Agency (US EPA) coal combustion residual (CCR) rule [40 Code of Federal Regulations (CFR) Part 257, Subpart D], specifically 40 CFR §257.91(e)(1) and Georgia Environmental Protection Division (GA EPD) Rules for Solid Waste Management 391-3-4-.10.

Plant Hammond is located in Floyd County, approximately 10 miles west of Rome, Georgia. The physical address of the plant is 5963 Alabama Highway, Rome, Georgia, 30165. The current groundwater monitoring system at AP-1 includes a network of detection monitoring wells, assessment monitoring wells, and piezometers. The locations of these wells and piezometers are shown on **Figure 1**.

Wells AS-01, AS-02, AS-03, and AS-04 were installed as air sparge points for the supplemental pilot study in support of the Assessment of Corrective Measures (ACM) Program. Wells INW-03, INW-04, and INW-05 were installed as injection points, and wells PT-11, PT-12, PT-13, PT-14, and PT-15 were installed to specifically monitor the performance of the supplemental pilot study injections in support of the ACM program.

¹ For the purposes of this report, unless otherwise specified, the term “well” will be used interchangeably with “piezometer”.

2. DRILLING AND WELL INSTALLATION

Well installation and development activities were performed according to accepted industry standards and following guidelines within the Manual for Groundwater Monitoring (GA EPD, 1991). Well drilling, installation, and surface completion activities were performed by Cascade Drilling, Inc. of Midland, North Carolina. In accordance with the Georgia Water Well Standards Act, the driller was required to have an insurance bond on file with the State of Georgia at the time of drilling. A copy of this bond is provided in **Appendix A**. A geologist under the supervision of a professional geologist (PG) registered to practice in the State of Georgia, both of whom are employed with Geosyntec Consultants (Geosyntec), documented the drilling and installation efforts to record observations, soil and rock descriptions, subsurface stratigraphy, water elevations, and other field activities. Geosyntec was also responsible for the development of the newly installed wells.

The locations of the new piezometers are shown on **Figure 1**. Well construction details are provided in **Table 1**; boring and well construction logs are included in **Appendix B**.

2.1 Drilling Method

The boreholes were advanced using rotosonic drilling techniques with continuous core collection. A Terra Sonic compact crawler size track mounted rig with a 6-inch sonic drill rod was used to install the wells. Care was taken so that the drilling methods did not introduce contamination of the groundwater from surface activities. Drilling equipment was cleaned prior to mobilizing to the site.

2.2 Screened Interval

Details regarding the well screened intervals are provided in **Table 1**. The wells are screened in the uppermost water bearing unit of the Site. Screened elevations across the new wells range from approximately 560.75 to 542.97 feet (referenced to the North American Vertical Datum of 1988). Performance monitoring and injection (PT and INW) wells were constructed with a 10 foot well screen segment. Air sparge (AS) wells were installed with a 2 foot well screen.

2.3 Well Casings and Screens

The wells were constructed of 2-inch inner diameter Schedule 40 polyvinyl chloride (PVC) casing with flush-threaded fittings. Performance monitoring and injection wells

were installed with a 10-foot nominal length pre-packed dual-wall well screen with 0.010-inch slots, air sparge wells were installed with a 2-foot nominal length well screen with 0.010-inch slots. The casing and pre-packed screens arrived pre-cleaned and packaged by the manufacturer. The pre-packed well screens were constructed onsite by packing sand between slotted PVC and the well screen. Well construction materials are sufficiently durable to resist chemical and physical degradation and do not interfere with the quality of groundwater samples. Casing and screen are flush-threaded. Solvent or glue was not used to construct the wells. A threaded bottom cap was attached to the bottom of each well screen. The PVC products used were American Society for Testing and Materials (ASTM) and National Sanitation Foundation (NSF) rated. Well screen interval details are provided in **Table 1**.

2.4 Well Intake Design

The wells were designed and constructed to: (1) allow sufficient groundwater flow to the well for sampling (for performance monitoring and injection wells); (2) minimize the passage of formation materials (turbidity) into the well; and (3) ensure sufficient structural integrity to prevent collapse of the well. The annular space between the face of the formation and the screens was filled to minimize passage of formation materials into the well. A filter pack of clean, well-rounded, quartz sand was installed in each well. The 0.010-inch slot size was selected to minimize the inflow of formation material without impairing influent groundwater flow.

2.5 Filter Pack

Highly Pure Quartzite silica sand filter pack was used as the appropriate gradation for the wells. The filter pack material meets the ASTM D5092 uniformity coefficient specification of 2.5 or less, with a uniformity coefficient of 1.6.

Filter pack material was placed within the pre-packed dual-wall well screens and in the annular space between the outside of the pre-pack screen and borehole wall to ensure an adequate thickness of filter pack material between the wells and the formation. Placement of the filter pack between the borehole wall and PVC was placed via gravity-pouring. Filter pack material placed in the annular space outside of the well screens extended a minimum of 2 feet above the top of screens. No bridging occurred during filter pack placement at any of the well locations.

Upon placement of the filter pack, the wells were pumped with a submersible pump to assure settlement of the filter pack. The top of filter pack depth was measured following

pumping to ensure appropriate extension of filter sand above the screens. The depth of top of filter pack was measured and recorded on the well construction logs provided in **Appendix B**.

2.6 Annular Seal

A minimum of two feet of bentonite chips (un-coated 3/8-inch and 1/2-inch bentonite pellets) were placed immediately above the filter pack by gravity-pouring into the annular space and hydrated per manufacture's specifications. A tremie pipe was used to probe the annular space to ensure that no bridging occurred. The bentonite was hydrated with potable water for a duration meeting the manufacture's specifications prior to grouting the remaining annulus.

The annulus above the bentonite seal was grouted with a bentonite grout placed via tremie pipe and direct pour methods from the top of the bentonite seal. During grouting, care was taken to assure that the bentonite seal was not disturbed by locating the base of the tremie pipe approximately 2 feet above the bentonite seal and injecting grout at low pressure/velocity. A cement apron 2-feet by 2-feet by 4-inches was poured around flush mount casings at all locations. A metal survey pin was placed on the front side of the concrete pad, several inches from the well vault. The pads were mounded slightly outward to direct surface drainage away from the wells.

2.7 Cap and Protective Casing

All wells were installed with flush-mounted well vaults and watertight flush-mounted well covers. The wells were clearly marked with the proper well identification number on a secured aluminum well tag on the manhole covers.

Construction details are documented on the well construction logs provided in **Appendix B**.

3. WELL DEVELOPMENT

The wells were developed using a combination of surging and pumping to (1) restore the natural hydraulic conductivity of the formation, and (2) to remove fine-grained sediment to ensure low-turbidity groundwater samples. The wells were alternately surged and purged until visually clear of particulates. Turbidity, pH, temperature, conductivity, oxidation-reduction potential (ORP), and dissolved oxygen (DO) measurements were

recorded to ensure that each well was fully developed. The well development and calibration field forms are included in **Appendix C**.

4. SURVEY

Upon completion of the well installations, select horizontal locations and vertical elevations were surveyed by a Georgia-licensed surveyor. The top of the PVC well casing [top of casing (TOC) elevation] and the survey pin installed at the well pads were surveyed to within 0.5-foot horizontal accuracy and to 0.01-foot vertical accuracy. The horizontal location (i.e., northings and eastings) was recorded in feet relative to the North America Datum of 1983 (NAD) with the vertical elevation recorded in feet relative to the North American Vertical Datum of 1988 (NAVD 88). Certified survey data are provided in the well construction table (**Table 1**). A copy of the certified well survey data for the new wells are provided in **Appendix D**.

5. REFERENCES

- Environmental Resources Management (ERM), 2017. *Well Design, Installation, Development, and Decommissioning Report – Plant Hammond Ash Ponds 1 and 2*. October 2017.
- Georgia Environmental Protection Division (GA EPD), Georgia Department of Natural Resources, 1991. *Manual for Groundwater Monitoring*. September 1991.
- Geosyntec Consultants, 2019. Well Design, Installation and Development Report – Addendum, Plant Hammond Ash Ponds 1 and 2 (AP-1 and AP-2). June 2019.
- Geosyntec Consultants, 2020a. Well Design, Installation and Development Report – Addendum No 2, Plant Hammond Ash Pond 1 (AP-1). January 2020.
- Geosyntec Consultants, 2020b. Well Design, Installation and Development Report – Addendum No 3, Plant Hammond Ash Pond 1 (AP-1). July 2020.
- Geosyntec Consultants, 2020c. Well Design, Installation and Development Report – Addendum No 4, Plant Hammond Ash Pond 1 (AP-1). November 2020.
- Geosyntec Consultants, 2023. Well Design, Installation and Development Report – Addendum No 5, Plant Hammond Ash Pond 1 (AP-1). October 2023.
- United States Environmental Protection Agency. 2015a. Federal Register. Volume 80. No. 74. Friday April 17, 2015. Part II. Environmental Protection Agency. 40 CFR Parts 257 and 261. Hazardous and Solid Waste Management System; Disposal of Coal Combustion Residuals from Electric Utilities; Final Rule. [EPA-HQ-RCRA-2009-0640; FRL-9919-44-OSWER]. RIN-2050-AE81, April 2015

TABLE

Table 1
Summary of Well Construction Details
Plant Hammond AP-1, Floyd County, Georgia

Well ID	Purpose	Well Completion	Geological Formation	Installation Date	Northing ⁽¹⁾	Easting ⁽¹⁾	Ground Surface Elevation ⁽¹⁾ (ft)	Top of Casing Elevation ⁽¹⁾ (ft)	Top of Screen Elevation (ft)	Bottom of Screen Elevation (ft)	Well Depth (ft bgs) ⁽²⁾
AS-01	Piezometer	Flush Mount	Residual	5/7/2024	1549048.28	1942388.06	577.46	577.08	548.46	546.46	31.30
AS-02	Piezometer	Flush Mount	Residual	5/6/2024	1549049.08	1942400.03	577.14	576.72	547.14	545.14	32.30
AS-03	Piezometer	Flush Mount	Residual/Limestone	4/28/2024	1548670.10	1940933.87	591.98	591.60	545.98	543.98	48.30
AS-04	Piezometer	Flush Mount	Residual/Limestone	4/28/2024	1548680.80	1940930.83	591.97	591.50	544.97	542.97	49.30
INW-03	Piezometer	Flush Mount	Alluvium	5/6/2024	1549052.75	1942388.28	577.38	577.07	560.28	550.28	27.40
INW-04	Piezometer	Flush Mount	Alluvium	4/28/2024	1548671.73	1940929.98	592.01	591.58	557.01	547.01	45.30
INW-05	Piezometer	Flush Mount	Alluvium	4/28/2024	1548680.07	1940935.89	591.81	591.31	556.81	546.81	45.30
PT-11	Piezometer	Flush Mount	Alluvium	5/7/2024	1549055.61	1942390.89	577.35	576.96	560.75	550.75	26.90
PT-12	Piezometer	Flush Mount	Alluvium	5/7/2024	1549045.43	1942391.10	577.34	576.84	560.34	550.34	27.30
PT-13	Piezometer	Flush Mount	Residual	4/28/2024	1548676.04	1940939.23	591.88	591.47	556.88	546.88	45.30
PT-14	Piezometer	Flush Mount	Alluvium	4/28/2024	1548673.63	1940926.52	592.06	591.62	557.06	547.06	45.30
PT-15	Piezometer	Flush Mount	Alluvium	4/28/2024	1548668.35	1940937.45	591.90	591.37	556.90	546.90	45.30

Notes:



ft = feet

ft bgs = feet below ground surface.

(1) Coordinates in North American Datum (NAD) 1983, State Plane, Georgia-West, feet. Elevations referenced to the North American Vertical Datum of 1988 (NAVD88). Survey data was certified by GEL Solutions July 1, 2024.

(2) Total well depth accounts for 0.3 ft sump.

FIGURE




LEGEND

- Detection Monitoring Well
- Horizontal Assessment Monitoring Well
- Vertical Assessment Monitoring Well
- Piezometer
- Surface Water Level Gauge Point
- Approximate AP-1 Boundary
- Plant Hammond Property Boundary

Notes:

1. Piezometers INW-03, INW-04, INW-05, AS-01 through AS-04, and PT-7 through PT-15 were installed in support of an Assessment of Corrective Measures (ACM) geochemical injections pilot study and are not included in the routine semiannual sampling of the monitoring well network.
2. Aerial photograph source: Google Earth Pro, August 2019, and Georgia Power Company, January 2024.



SCALE IN FEET

GROUNDWATER MONITORING NETWORK MAP

GEORGIA POWER COMPANY
PLANT HAMMOND AP-1
ROME, FLOYD COUNTY, GEORGIA

Prepared For: Georgia Power

Prepared By: Geosyntec
consultants

KENNESAW, GA

AUGUST 2024

FIGURE
1

APPENDIX A

Well Driller Performance Bonds

CONTINUATION
CERTIFICATE

Atlantic Specialty Insurance Company

, Surety upon

a certain Bond No. 800033976

dated effective September 27, 2017
(MONTH-DAY-YEAR)

on behalf of Ricky Davis / Cascade Drilling, L.P.
(PRINCIPAL)

and in favor of Department of Natural Resources, State of Georgia
(OBLIGEE)

does hereby continue said bond in force for the further period

beginning on June 30, 2023
(MONTH-DAY-YEAR)

and ending on June 30, 2025
(MONTH-DAY-YEAR)

Amount of bond Thirty Thousand and 00/100 Dollars (\$30,000.00)

Description of bond Performance Bond for Water Well Contractors

Premium:

PROVIDED: That this continuation certificate does not create a new obligation and is executed upon the express condition and provision that the Surety's liability under said bond and this and all Continuation Certificates issued in connection therewith shall not be cumulative and that the said Surety's aggregate liability under said bond and this and all such Continuation Certificates on account of all defaults committed during the period (regardless of the number of years) said bond had been and shall be in force, shall not in any event exceed the amount of said bond as hereinbefore set forth.

Signed and dated on April 13, 2023
(MONTH-DAY-YEAR)

Atlantic Specialty Insurance Company

By 
ATTORNEY-IN-FACT Carlos A. Albelo



Power of Attorney

KNOW ALL MEN BY THESE PRESENTS, that ATLANTIC SPECIALTY INSURANCE COMPANY, a New York corporation with its principal office in Plymouth, Minnesota, does hereby constitute and appoint: **Megan Sivley, Melissa Haddick, Sandra Parker, Orlando Aguirre, Stacy Killebrew, Carlos A. Albelo**, each individually if there be more than one named, its true and lawful Attorney-in-Fact, to make, execute, seal and deliver, for and on its behalf as surety, any and all bonds, recognizances, contracts of indemnity, and all other writings obligatory in the nature thereof; provided that no bond or undertaking executed under this authority shall exceed in amount the sum of: **unlimited** and the execution of such bonds, recognizances, contracts of indemnity, and all other writings obligatory in the nature thereof in pursuance of these presents, shall be as binding upon said Company as if they had been fully signed by an authorized officer of the Company and sealed with the Company seal. This Power of Attorney is made and executed by authority of the following resolutions adopted by the Board of Directors of ATLANTIC SPECIALTY INSURANCE COMPANY on the twenty-fifth day of September, 2012:

Resolved: That the President, any Senior Vice President or Vice-President (each an "Authorized Officer") may execute for and in behalf of the Company any and all bonds, recognizances, contracts of indemnity, and all other writings obligatory in the nature thereof, and affix the seal of the Company thereto; and that the Authorized Officer may appoint and authorize an Attorney-in-Fact to execute on behalf of the Company any and all such instruments and to affix the Company seal thereto; and that the Authorized Officer may at any time remove any such Attorney-in-Fact and revoke all power and authority given to any such Attorney-in-Fact.

Resolved: That the Attorney-in-Fact may be given full power and authority to execute for and in the name and on behalf of the Company any and all bonds, recognizances, contracts of indemnity, and all other writings obligatory in the nature thereof, and any such instrument executed by any such Attorney-in-Fact shall be as binding upon the Company as if signed and sealed by an Authorized Officer and, further, the Attorney-in-Fact is hereby authorized to verify any affidavit required to be attached to bonds, recognizances, contracts of indemnity, and all other writings obligatory in the nature thereof.

This power of attorney is signed and sealed by facsimile under the authority of the following Resolution adopted by the Board of Directors of ATLANTIC SPECIALTY INSURANCE COMPANY on the twenty-fifth day of September, 2012:

Resolved: That the signature of an Authorized Officer, the signature of the Secretary or the Assistant Secretary, and the Company seal may be affixed by facsimile to any power of attorney or to any certificate relating thereto appointing an Attorney-in-Fact for purposes only of executing and sealing any bond, undertaking, recognizance or other written obligation in the nature thereof, and any such signature and seal where so used, being hereby adopted by the Company as the original signature of such officer and the original seal of the Company, to be valid and binding upon the Company with the same force and effect as though manually affixed.

IN WITNESS WHEREOF, ATLANTIC SPECIALTY INSURANCE COMPANY has caused these presents to be signed by an Authorized Officer and the seal of the Company to be affixed this first day of January, 2023.




By

Sarah A. Kolar, General Counsel

STATE OF MINNESOTA
HENNEPIN COUNTY

On this first day of January, 2023, before me personally came Sarah A. Kolar, General Counsel of ATLANTIC SPECIALTY INSURANCE COMPANY, to me personally known to be the individual and officer described in and who executed the preceding instrument, and she acknowledged the execution of the same, and being by me duly sworn, that she is the said officer of the Company aforesaid, and that the seal affixed to the preceding instrument is the seal of said Company and that the said seal and the signature as such officer was duly affixed and subscribed to the said instrument by the authority and at the direction of the Company.



Notary Public

I, the undersigned, Secretary of ATLANTIC SPECIALTY INSURANCE COMPANY, a New York Corporation, do hereby certify that the foregoing power of attorney is in full force and has not been revoked, and the resolutions set forth above are now in force.

Signed and sealed. Dated 13th day of April, 2023.




This Power of Attorney expires
January 31, 2025

Kara Barrow, Secretary

APPENDIX B


Boring and Well Construction Logs

CLIENT Southern Company Services	PROJECT NAME Plant Hammond Well Installation
PROJECT NUMBER GW6581E	PROJECT LOCATION Plant Hammond
DATE STARTED 5/6/24	COMPLETED 5/7/24
DRILLER Cascade Drilling	NORTHING 1549048.28 ft
DRILLING METHOD Sonic	EASTING 1942388.06 ft
SAMPLING METHOD Sonic Core	GROUND ELEVATION 577.46 ft
RIG TYPE Terrasonic Compact Crawler	BORING DIAMETER 4x6 in
	TOP OF CASING ELEVATION 577.08 ft
	GEOPHYSICAL CONTRACTOR ---
	LOGGED BY T. Kessler
	CHECKED BY C. Hug




Bottom of borehole at 35.0 feet below ground surface (ft bgs).


CLIENT Southern Company Services	PROJECT NAME Plant Hammond Well Installation
PROJECT NUMBER GW6581E	PROJECT LOCATION Plant Hammond
DATE STARTED 4/29/24	COMPLETED 5/6/24
DRILLER Cascade Drilling	NORTHING 1549049.08 ft
DRILLING METHOD Sonic	EASTING 1942400.03 ft
SAMPLING METHOD Sonic Core	GROUND ELEVATION 577.14 ft
RIG TYPE Terrasonic Compact Crawler	BORING DIAMETER 4x6 in
	TOP OF CASING ELEVATION 576.72 ft
	GEOPHYSICAL CONTRACTOR ---
	LOGGED BY T. Kessler
	CHECKED BY C. Hug



CLIENT Southern Company Services	PROJECT NAME Plant Hammond Well Installation
PROJECT NUMBER GW6581E	PROJECT LOCATION Plant Hammond
DATE STARTED 4/27/24	COMPLETED 4/28/24
DRILLER Cascade Drilling	NORTHING 1548670.10 ft
DRILLING METHOD Sonic	EASTING 1940933.87 ft
SAMPLING METHOD Sonic Core	GROUND ELEVATION 591.98 ft
RIG TYPE Terrasonic Compact Crawler	BORING DIAMETER 4x6 in
	TOP OF CASING ELEVATION 591.60 ft
	GEOPHYSICAL CONTRACTOR ---
	LOGGED BY T. Kessler
	CHECKED BY C. Hug



CLIENT Southern Company Services	PROJECT NAME Plant Hammond Well Installation
PROJECT NUMBER GW6581E	PROJECT LOCATION Plant Hammond
DATE STARTED 4/28/24	COMPLETED 4/28/24
DRILLER Cascade Drilling	NORTHING 1548680.80 ft
DRILLING METHOD Sonic	EASTING 1940930.83 ft
SAMPLING METHOD Sonic Core	GROUND ELEVATION 591.97 ft
RIG TYPE Terrasonic Compact Crawler	BORING DIAMETER 4x6 in
	TOP OF CASING ELEVATION 591.50
	ft GEOPHYSICAL CONTRACTOR ---
	LOGGED BY T. Kessler
	CHECKED BY C. Hug



CLIENT <u>Southern Company Services</u>	PROJECT NAME <u>Plant Hammond Well Installation</u>
PROJECT NUMBER <u>GW6581E</u>	PROJECT LOCATION <u>Plant Hammond</u>
DATE STARTED <u>4/30/24</u> COMPLETED <u>5/6/24</u>	NORTHING <u>1549052.75 ft</u> EASTING <u>1942388.28 ft</u>
DRILLER <u>Cascade Drilling</u>	GROUND ELEVATION <u>577.38 ft</u> BORING DIAMETER <u>4x6 in</u>
DRILLING METHOD <u>Sonic</u>	TOP OF CASING ELEVATION <u>577.07 ft</u>
SAMPLING METHOD <u>Sonic Core</u>	GEOPHYSICAL CONTRACTOR <u>---</u>
RIG TYPE <u>Terrasonic Compact Crawler</u>	LOGGED BY <u>T. Kessler</u> CHECKED BY <u>C. Hug</u>

DEPTH (ft)	ELEVATION (ft)	REMARKS	GRAPHIC LOG	MATERIAL DESCRIPTION	CONSTRUCTION DIAGRAM
0				SILTY CLAY, yellowish-brown, trace fine sand, trace angular fine gravel, medium to low plasticity, abundant organics from 0-1 foot bgs, moist.	Flush mount well cover set in concrete
5	575				Approx. 11 gallon of Aquaguard Bentonite Grout
10	570			SILTY CLAY, brownish yellow, firm, trace sand, medium plasticity, trace light gray mottling throughout, moist.	Approx. 2.5 gallon of PelPlug Bentonite
15	565				Uncoated 3/8" Pellets
20	560			SANDY CLAY, light gray, firm, subrounded to subangular medium to fine sand, trace subangular medium gravel, medium to low plasticity, moist.	Approx. 15 gallon of Filtersil 20/40 Silica Sand
25	555			SILTY SAND, brownish yellow, abundant subrounded to rounded medium to coarse sand, some subangular to rounded medium gravel, trace rounded coarse gravel.	0.010 slot size 2" Pre Pack, U-Pack Screen
				SAND, very pale brown, subrounded to subangular medium to fine sand, trace rounded fine gravel, wet.	
				From 24 ft: Black staining.	
				SANDY CLAY, light yellowish-brown, soft, fine sand, some fine subangular to rounded gravel, low plasticity, wet.	
	550			No recovery (26.3 to 29.5 ft).	0.3 ft Sump


Bottom of borehole at 29.5 feet below ground surface (ft bgs).

CLIENT Southern Company Services	PROJECT NAME Plant Hammond Well Installation
PROJECT NUMBER GW6581E	PROJECT LOCATION Plant Hammond
DATE STARTED 4/26/24	COMPLETED 4/28/24
DRILLER Cascade Drilling	NORTHING 1548671.73 ft
DRILLING METHOD Sonic	EASTING 1940929.98 ft
SAMPLING METHOD Sonic Core	GROUND ELEVATION 592.01 ft
RIG TYPE Terrasonic Compact Crawler	BORING DIAMETER 4x6 in
	TOP OF CASING ELEVATION 591.58 ft
	GEOPHYSICAL CONTRACTOR ---
	LOGGED BY T. Kessler
	CHECKED BY C. Hug

DEPTH (ft)	ELEVATION (ft)	REMARKS	GRAPHIC LOG	MATERIAL DESCRIPTION	CONSTRUCTION DIAGRAM
0	590			SILTY SAND, dark grayish brown, angular medium to coarse sand, some coarse gravel, dry.	Flush mount well cover set in concrete
5	585			SANDY CLAY, brownish yellow, firm, trace rounded medium gravel, medium to low plasticity, with organic matter (roots) from 6-6.2 ft bgs, moist.	
				From 6 ft: Grades to grayish brown.	
				No recovery (7 to 10 ft).	
10	580			SILTY SAND, yellowish-brown, some angular medium gravel, dry.	
				SANDY CLAY, yellowish-brown, firm, medium to low plasticity, gray mottling throughout, moist.	
15	575			SILTY CLAY, brownish yellow, firm, trace fine sand, medium plasticity, grades to pale brown, moist.	
				No recovery (17.7 to 20 ft).	
20	570			SILTY CLAY, yellow, firm, trace fine sand and rounded medium gravel, sandy with angular medium to coarse gravel from 20-21 ft bgs, medium plasticity, reddish yellow and light gray mottling throughout, moist.	
25	565				
30	560	Easy drilling; no return on 6 inch.		From 30 ft: Becoming light gray.	
				SANDY CLAY, yellow, firm, abundant fine sand, trace rounded gravel, low plasticity, moist to wet.	
35	555			SILTY SAND, yellow, subrounded to subangular medium sand, some rounded medium to fine gravel, wet.	
				No recovery (37 to 40 ft).	
40	550			SILTY SAND, yellow, subrounded to subangular medium sand, some rounded medium to fine gravel, wet.	
				SILTY CLAY, yellow, firm, trace fine sand, medium plasticity, moist to wet.	
45					

Bottom of borehole at 46.4 feet below ground surface (ft bgs).

CLIENT <u>Southern Company Services</u> PROJECT NUMBER <u>GW6581E</u> DATE STARTED <u>4/27/24</u> COMPLETED <u>4/28/24</u> DRILLER <u>Cascade Drilling</u> DRILLING METHOD <u>Sonic</u> SAMPLING METHOD <u>Sonic Core</u> RIG TYPE <u>Terrasonic Compact Crawler</u>	PROJECT NAME <u>Plant Hammond Well Installation</u> PROJECT LOCATION <u>Plant Hammond</u> NORTHING <u>1548680.07 ft</u> EASTING <u>1940935.89 ft</u> GROUND ELEVATION <u>591.81 ft</u> BORING DIAMETER <u>4x6 in</u> TOP OF CASING ELEVATION <u>591.31 ft</u> GEOPHYSICAL CONTRACTOR <u>---</u> LOGGED BY <u>T. Kessler</u> CHECKED BY <u>C. Hug</u>
--	--




CLIENT <u>Southern Company Services</u>	PROJECT NAME <u>Plant Hammond Well Installation</u>
PROJECT NUMBER <u>GW6581E</u>	PROJECT LOCATION <u>Plant Hammond</u>
DATE STARTED <u>4/30/24</u> COMPLETED <u>5/7/24</u>	NORTHING <u>1549055.61 ft</u> EASTING <u>1942390.89 ft</u>
DRILLER <u>Cascade Drilling</u>	GROUND ELEVATION <u>577.35 ft</u> BORING DIAMETER <u>4x6 in</u>
DRILLING METHOD <u>Sonic</u>	TOP OF CASING ELEVATION <u>576.96 ft</u>
SAMPLING METHOD <u>Sonic Core</u>	GEOPHYSICAL CONTRACTOR <u>---</u>
RIG TYPE <u>Terrasonic Compact Crawler</u>	LOGGED BY <u>T. Kessler</u> CHECKED BY <u>C. Hug</u>

DEPTH (ft)	ELEVATION (ft)	REMARKS	GRAPHIC LOG	MATERIAL DESCRIPTION	CONSTRUCTION DIAGRAM
0		0		SILTY CLAY, yellowish-brown, trace fine sand, trace angular fine gravel, medium to low plasticity, abundant organics from 0-1 foot bgs, moist.	Flush mount well cover set in concrete
5	575				Approx. 10 gallon of Aquaguard Bentonite Grout
10	570			SILTY CLAY, brownish yellow, firm, trace sand, medium plasticity, trace light gray mottling throughout, moist.	Approx 2.5 gallon of PelPlug Bentonite
15	565			SANDY CLAY, light gray, firm, subrounded to subangular medium to fine sand, trace subangular medium gravel, medium to low plasticity, moist.	Uncoated 3/8" Pellets
20	560			SILTY SAND, brownish yellow, subrounded to rounded, fine to coarse sand, some subangular to rounded medium gravel, trace rounded coarse gravel, moist.	Approx. 13 gallon of Filtersil 20/40 Silica Sand
25	555			SAND, very pale brown, subrounded to subangular medium to fine sand, trace rounded fine gravel, wet.	0.010 slot size 2" Pre Pack, U-Pack Screen
550				SANDY CLAY, brownish yellow, soft, abundant subangular to rounded fine gravel, trace fine sand, low plasticity, wet.	0.3 ft Sump

No recovery (27 to 28 ft).

Bottom of borehole at 28.0 feet below ground surface (ft bgs).

CLIENT <u>Southern Company Services</u>	PROJECT NAME <u>Plant Hammond Well Installation</u>
PROJECT NUMBER <u>GW6581E</u>	PROJECT LOCATION <u>Plant Hammond</u>
DATE STARTED <u>5/1/24</u> COMPLETED <u>5/7/24</u>	NORTHING <u>1549045.43 ft</u> EASTING <u>1942391.10 ft</u>
DRILLER <u>Cascade Drilling</u>	GROUND ELEVATION <u>577.34 ft</u> BORING DIAMETER <u>4x6 in</u>
DRILLING METHOD <u>Sonic</u>	TOP OF CASING ELEVATION <u>576.84 ft</u>
SAMPLING METHOD <u>Sonic Core</u>	GEOPHYSICAL CONTRACTOR <u>---</u>
RIG TYPE <u>Terrasonic Compact Crawler</u>	LOGGED BY <u>T. Kessler</u> CHECKED BY <u>C. Hug</u>



30 Bottom of borehole at 30.0 feet below ground surface (ft bgs).

CLIENT Southern Company Services	PROJECT NAME Plant Hammond Well Installation
PROJECT NUMBER GW6581E	PROJECT LOCATION Plant Hammond
DATE STARTED 4/25/24 COMPLETED 4/28/24	NORTHING 1548676.04 ft EASTING 1940939.23 ft
DRILLER Cascade Drilling	GROUND ELEVATION 591.88 ft BORING DIAMETER 4x6 in
DRILLING METHOD Sonic	TOP OF CASING ELEVATION 591.47 ft
SAMPLING METHOD Sonic Core	GEOPHYSICAL CONTRACTOR ---
RIG TYPE Terrasonic Compact Crawler	LOGGED BY T. Kessler CHECKED BY C. Hug

DEPTH (ft)	ELEVATION (ft)	REMARKS	GRAPHIC LOG	MATERIAL DESCRIPTION	CONSTRUCTION DIAGRAM
0	590			SANDY CLAY, gray, abundant angular to rounded coarse gravel, abundant fine sand and silt, medium to low plasticity, wet.	Flush mount well cover set in concrete
5	585			CLAY, light brown, firm, trace rounded fine gravel, trace subrounded to subangular medium sand, trace silt, medium to low plasticity, dark reddish-brown mottling throughout, dry.	
10	580	Very easy drilling from 10-30 ft bgs.		SILTY SAND, pinkish gray, subrounded to subangular medium to coarse sand, some angular fine gravel, wet.	
15	575			CLAY, light brownish gray, firm, trace sand and fine silt, medium plasticity, moist.	Approx. 33.5 gallon of Aquaguard Bentonite Grout
20	570			No recovery (14 to 20 ft).	
25	565			CLAY, light brownish gray, firm, trace sand and fine silt, medium plasticity, moist.	
30	560	Drilling water observed daylighting around well pad to PT-07.		CLAY, yellowish-brown, firm, trace fine sand and silt, medium plasticity, abundant light gray and red mottling throughout, moist.	
35	555			From 26 ft: Some subrounded medium sand, subrounded fine gravel, dry to moist.	Approx. 7.5 gallon of PelPlug Bentonite Uncoated 1/2" Pellets
40	550	Daylighting observed above has stopped from 40-46 ft bgs.		SILTY SAND, yellowish-brown, some subrounded to rounded fine to coarse gravel, wet.	Approx. 15 gallon of Filtersil 20/40 Silica Sand
45				From 36 ft: Trace white mottling to 37 ft bgs.	0.010 slot size 2" Pre Pack, U-Pack Screen
				SILTY CLAY, yellowish-brown, trace fine sand, medium plasticity, moist.	
				SILTY CLAY, yellowish-brown, firm, trace fine sand, brown mottling throughout, moist.	
				LIMESTONE, very dark gray, recovered as angular medium to coarse gravel, dry.	0.3 ft Sump Native Soil

Bottom of borehole at 46.0 feet below ground surface (ft bgs).

CLIENT Southern Company Services	PROJECT NAME Plant Hammond Well Installation
PROJECT NUMBER GW6581E	PROJECT LOCATION Plant Hammond
DATE STARTED 4/25/24	COMPLETED 4/28/24
DRILLER Cascade Drilling	NORTHING 1548673.63 ft
DRILLING METHOD Sonic	EASTING 1940926.52 ft
SAMPLING METHOD Sonic Core	GROUND ELEVATION 592.06 ft
RIG TYPE Terrasonic Compact Crawler	BORING DIAMETER 4x6 in
	TOP OF CASING ELEVATION 591.62 ft
	GEOPHYSICAL CONTRACTOR ---
	LOGGED BY T. Kessler
	CHECKED BY C. Hug

DEPTH (ft)	ELEVATION (ft)	REMARKS	GRAPHIC LOG	MATERIAL DESCRIPTION	CONSTRUCTION DIAGRAM
0		Likely fill from 0-2 ft bgs.		SILTY SAND, light gray, fine sand, some angular medium gravel, dry.	
5	590			SANDY CLAY, brown, firm to hard, trace subrounded medium to fine gravel, medium to low plasticity, moist.	
				From 5.2 ft: Trace subangular medium sand ~1 inch thick.	
	585			No recovery (6 to 10 ft).	
10		Rods fall ~1 foot during over drill from 10-11 ft bgs.		SILTY SAND, light yellowish-brown, subangular fine to medium sand, some subrounded fine to medium gravel, yellowish-brown mottling throughout, dry.	
	580			CLAY, yellowish-brown, firm, medium plasticity, abundant silt from 12.3-15 ft bgs, trace fine sand, gray mottling throughout, moist.	
15		Driller describes drilling as "tight" from 16-34 ft bgs.		No recovery (17 to 20 ft).	
	575				
20				CLAY, yellowish-brown, firm, medium plasticity, abundant silt from 12.3-15 ft bgs, trace fine throughout, light olive brown mottling throughout, moist.	
	570			CLAY, reddish yellow, firm, trace silt and fine sand, medium to low plasticity, gray mottling throughout, moist.	
25				No recovery (27 to 30 ft).	
	565				
30				CLAY, gray, firm, trace silt and fine sand, medium plasticity, reddish yellow mottling throughout, moist.	
	560				
35		Grades to coarser with depth from 35-39 ft bgs.		SILTY SAND, brownish yellow, subrounded to subangular fine to medium sand, some subrounded to rounded medium to coarse gravel, wet.	
	555			From 36 ft: Trace rounded coarse gravel to 37 ft bgs.	
				No recovery (37 to 40 ft).	
40				SILTY SAND, brownish yellow, subrounded to subangular fine to medium sand, wet.	
	550			SILTY CLAY, yellow, soft to firm grading to firm with depth, trace fine sand, medium plasticity, moist.	
45				From 45 ft: Trace subrounded to subangular gravel to 46 ft bgs.	

Bottom of borehole at 46.3 feet below ground surface (ft bgs).

CLIENT Southern Company Services	PROJECT NAME Plant Hammond Well Installation
PROJECT NUMBER GW6581E	PROJECT LOCATION Plant Hammond
DATE STARTED 4/24/24	COMPLETED 4/28/24
DRILLER Cascade Drilling	NORTHING 1548668.35 ft
DRILLING METHOD Sonic	EASTING 1940937.45 ft
SAMPLING METHOD Sonic Core	GROUND ELEVATION 591.91 ft
RIG TYPE Terrasonic Compact Crawler	BORING DIAMETER 4x6 in
	TOP OF CASING ELEVATION 591.37 ft
	GEOPHYSICAL CONTRACTOR ---
	LOGGED BY T. Kessler
	CHECKED BY C. Hug

DEPTH (ft)	ELEVATION (ft)	REMARKS	GRAPHIC LOG	MATERIAL DESCRIPTION	CONSTRUCTION DIAGRAM
0		Likely fill from 0-2 ft bgs.		SILTY SAND, gray, fine sand, some angular fine to medium gravel, moist.	
5	590			CLAY, light reddish-brown, trace fine sand and subangular gravel, medium to low plasticity, dark reddish-brown mottling throughout, moist.	
10	585			From 10 ft: Moist to wet. From 11 ft: Grades to gray.	
15	580	Hard drilling with 6-inch override from 13-18 ft bgs.		SANDY CLAY, brown grading to reddish yellow, abundant fine sand, trace subangular medium gravel, trace silt, medium plasticity, trace organic material (roots), moist.	
20	575			SILTY CLAY, very pale brown, soft, abundant angular medium gravel, abundant fine sand, trace subangular medium sand, low plasticity, wet.	
25	570			CLAY, reddish yellow, firm, trace subangular gravel, trace fine sand, medium plasticity, trace pinkish white mottling throughout, moist.	
30	565				
35	560	Easy drilling/less resistance from 31-40 ft bgs.		SILTY SAND, brownish yellow, abundant subangular to angular fine to coarse sand, some angular medium to coarse gravel, wet. From 33.7 ft: Black to 34 feet bgs.	
40	555			From 37 ft: Abundant rounded gravel to 37.8 ft bgs.	
45	550			SILTY CLAY, yellow, soft, some fine sand, medium to low plasticity, moist.	
				SILTY CLAY, yellow grading to gray, soft, trace rounded fine gravel, trace fine sand, medium to low plasticity, moist.	

Bottom of borehole at 46.0 feet below ground surface (ft bgs).

Flush mount well cover set in concrete

Approx. 36 gallon of Aquaguard Bentonite Grout

Approx. 3 gallon of PelPlug Bentonite
Uncoated 3/8" Pellets
Approx. 13 gallon of Filtersil 20/40 Silica Sand
0.010 slot size 2" Pre Pack, U-Pack Screen

0.3 ft Sump Native Soil

APPENDIX C

Well Development and Equipment Calibration Forms

Low-Flow Test Report:

Test Date / Time: 5/10/2024 10:41:35 AM
Project: Plant Hammond
Operator Name: Jamie Newsome

Location Name: AS-01 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 29 ft Total Depth: 31 ft Initial Depth to Water: 11.25 ft	Pump Type: Monsoon Tubing Type: Polyethylene Pump Intake From TOC: 30 ft Estimated Total Volume Pumped: 112.5 gal Flow Cell Volume: 90 ml Final Flow Rate: 2.5 gal/min Final Draw Down: 2.58 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
---	--	--

Test Notes:
Well Development, Purge 1

Weather Conditions:
Cloudy, 75 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 3 %	+/- 0.2	+/- 10	+/- 10	+/- 0.3	
5/10/2024 10:41 AM	00:00	7.20 pH	18.52 °C	803.10 µS/cm	0.01 mg/L	877.00 NTU	-37.1 mV	12.75 ft	2.50 gal/min
5/10/2024 10:46 AM	05:00	7.18 pH	18.58 °C	784.96 µS/cm	-0.01 mg/L	108.00 NTU	-57.8 mV	12.75 ft	2.50 gal/min
5/10/2024 10:51 AM	10:00	7.18 pH	18.52 °C	783.98 µS/cm	-0.01 mg/L	91.00 NTU	-30.5 mV	12.75 ft	2.50 gal/min
5/10/2024 10:56 AM	15:00	7.44 pH	19.23 °C	790.32 µS/cm	0.40 mg/L	81.00 NTU	26.9 mV	12.75 ft	2.50 gal/min
5/10/2024 11:01 AM	20:00	7.22 pH	18.52 °C	785.34 µS/cm	-0.01 mg/L	22.10 NTU	-31.3 mV	12.75 ft	2.50 gal/min
5/10/2024 11:06 AM	25:00	7.22 pH	18.52 °C	781.98 µS/cm	-0.01 mg/L	29.10 NTU	-33.7 mV	13.70 ft	2.50 gal/min
5/10/2024 11:11 AM	30:00	7.19 pH	18.55 °C	779.75 µS/cm	-0.02 mg/L	25.90 NTU	-32.5 mV	13.70 ft	2.50 gal/min
5/10/2024 11:16 AM	35:00	7.19 pH	18.56 °C	776.73 µS/cm	-0.02 mg/L	11.48 NTU	-13.2 mV	13.83 ft	2.50 gal/min
5/10/2024 11:21 AM	40:00	7.18 pH	18.57 °C	775.47 µS/cm	-0.02 mg/L	7.48 NTU	-27.9 mV	13.83 ft	2.50 gal/min
5/10/2024 11:26 AM	45:00	7.17 pH	18.56 °C	773.67 µS/cm	-0.02 mg/L	4.99 NTU	-25.7 mV	13.83 ft	2.50 gal/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 5/10/2024 11:36:06 AM
Project: Plant Hammond
Operator Name: Jamie Newsome

Location Name: AS-01 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 29 ft Total Depth: 31 ft Initial Depth to Water: 11.25 ft	Pump Type: Monsoon Tubing Type: Polyethylene Pump Intake From TOC: 30 ft Estimated Total Volume Pumped: 25 liter Flow Cell Volume: 90 ml Final Flow Rate: 250 ml/min Final Draw Down: 0.00 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
---	---	--

Test Notes:
Well Development, Purge 2

Weather Conditions:
Sunny, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 3 %	+/- 0.2	+/- 10	+/- 10	+/- 0.3	
5/10/2024 11:36 AM	00:00	7.21 pH	19.99 °C	785.76 µS/cm	0.00 mg/L	10.84 NTU	-14.8 mV	11.25 ft	250.00 ml/min
5/10/2024 11:41 AM	05:00	7.24 pH	20.09 °C	781.31 µS/cm	0.01 mg/L	16.10 NTU	-9.5 mV	11.25 ft	250.00 ml/min
5/10/2024 11:46 AM	10:00	7.27 pH	19.95 °C	786.57 µS/cm	0.01 mg/L	23.20 NTU	-16.3 mV	11.25 ft	250.00 ml/min
5/10/2024 11:51 AM	15:00	7.29 pH	20.07 °C	791.85 µS/cm	0.01 mg/L	29.40 NTU	-8.1 mV	11.25 ft	250.00 ml/min
5/10/2024 11:56 AM	20:00	7.30 pH	20.26 °C	795.51 µS/cm	0.02 mg/L	32.90 NTU	6.3 mV	11.25 ft	250.00 ml/min
5/10/2024 12:01 PM	25:00	7.30 pH	19.97 °C	795.45 µS/cm	0.01 mg/L	29.50 NTU	4.7 mV	11.25 ft	250.00 ml/min
5/10/2024 12:06 PM	30:00	7.31 pH	20.11 °C	796.56 µS/cm	0.01 mg/L	27.20 NTU	9.4 mV	11.25 ft	250.00 ml/min
5/10/2024 12:11 PM	35:00	7.31 pH	20.04 °C	794.22 µS/cm	0.01 mg/L	24.50 NTU	13.7 mV	11.25 ft	250.00 ml/min
5/10/2024 12:16 PM	40:00	7.32 pH	19.97 °C	793.30 µS/cm	0.01 mg/L	17.70 NTU	16.8 mV	11.25 ft	250.00 ml/min
5/10/2024 12:21 PM	45:00	7.31 pH	20.16 °C	796.76 µS/cm	0.01 mg/L	14.10 NTU	18.8 mV	11.25 ft	250.00 ml/min
5/10/2024 12:26 PM	50:00	7.32 pH	19.72 °C	793.65 µS/cm	0.01 mg/L	15.66 NTU	20.6 mV	11.25 ft	250.00 ml/min
5/10/2024 12:31 PM	55:00	7.32 pH	19.32 °C	795.79 µS/cm	0.02 mg/L	11.30 NTU	20.8 mV	11.25 ft	250.00 ml/min
5/10/2024 12:36 PM	01:00:00	7.31 pH	19.70 °C	799.18 µS/cm	0.02 mg/L	10.54 NTU	20.5 mV	11.25 ft	250.00 ml/min

5/10/2024 12:41 PM	01:05:00	7.31 pH	19.90 °C	798.44 µS/cm	0.02 mg/L	8.90 NTU	20.6 mV	11.25 ft	250.00 ml/min
5/10/2024 12:46 PM	01:10:00	7.31 pH	20.07 °C	797.58 µS/cm	0.02 mg/L	6.96 NTU	21.2 mV	11.25 ft	250.00 ml/min
5/10/2024 12:51 PM	01:15:00	7.32 pH	19.41 °C	796.94 µS/cm	0.01 mg/L	7.96 NTU	21.9 mV	11.25 ft	250.00 ml/min
5/10/2024 12:56 PM	01:20:00	7.32 pH	19.96 °C	795.55 µS/cm	0.01 mg/L	6.71 NTU	21.9 mV	11.25 ft	250.00 ml/min
5/10/2024 1:01 PM	01:25:00	7.31 pH	19.43 °C	798.81 µS/cm	0.01 mg/L	5.89 NTU	22.3 mV	11.25 ft	250.00 ml/min
5/10/2024 1:06 PM	01:30:00	7.32 pH	19.67 °C	797.87 µS/cm	0.02 mg/L	5.41 NTU	22.2 mV	11.25 ft	250.00 ml/min
5/10/2024 1:11 PM	01:35:00	7.31 pH	19.99 °C	798.78 µS/cm	0.01 mg/L	5.39 NTU	22.3 mV	11.25 ft	250.00 ml/min
5/10/2024 1:16 PM	01:40:00	7.32 pH	19.53 °C	796.14 µS/cm	0.01 mg/L		23.4 mV	11.25 ft	250.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 5/13/2024 1:53:35 PM
Project: Plant Hammond
Operator Name: Jamie Newsome

Location Name: AS-02 Well Diameter: 2 in Casing Type: PVC Screen Length: 2 ft Top of Screen: 32 ft Total Depth: 34 ft Initial Depth to Water: 11.00 ft	Pump Type: Monsoon Tubing Type: Polyethylene Pump Intake From TOC: 33 ft Estimated Total Volume Pumped: 90 gal Flow Cell Volume: 90 ml Final Flow Rate: 2 gal/min Final Draw Down: 0.40 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
--	--	--

Test Notes:
Well Development, Purge 1

Weather Conditions:
Cloudy, 60 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 3 %	+/- 0.2	+/- 10	+/- 10	+/- 0.3	
5/13/2024 1:53 PM	00:00	7.16 pH	18.24 °C	688.19 µS/cm	0.02 mg/L	2,086.0 NTU	10.6 mV	11.32 ft	2.00 gal/min
5/13/2024 1:58 PM	05:00	7.13 pH	18.17 °C	683.36 µS/cm	-0.00 mg/L	61.00 NTU	9.5 mV	11.32 ft	2.00 gal/min
5/13/2024 2:03 PM	10:00	7.13 pH	18.08 °C	684.83 µS/cm	-0.01 mg/L	38.80 NTU	9.0 mV	11.35 ft	2.00 gal/min
5/13/2024 2:08 PM	15:00	7.12 pH	18.10 °C	684.54 µS/cm	-0.01 mg/L	85.00 NTU	8.7 mV	11.35 ft	2.00 gal/min
5/13/2024 2:13 PM	20:00	7.12 pH	18.11 °C	686.84 µS/cm	-0.01 mg/L	45.00 NTU	11.9 mV	11.35 ft	2.00 gal/min
5/13/2024 2:18 PM	25:00	7.11 pH	18.12 °C	686.59 µS/cm	-0.02 mg/L	18.10 NTU	12.8 mV	11.35 ft	2.00 gal/min
5/13/2024 2:23 PM	30:00	7.11 pH	18.11 °C	684.15 µS/cm	-0.02 mg/L	11.60 NTU	12.6 mV	11.35 ft	2.00 gal/min
5/13/2024 2:28 PM	35:00	7.11 pH	18.11 °C	684.87 µS/cm	-0.02 mg/L	9.41 NTU	13.1 mV	11.40 ft	2.00 gal/min
5/13/2024 2:33 PM	40:00	7.11 pH	18.11 °C	686.55 µS/cm	-0.02 mg/L	6.71 NTU	13.2 mV	11.40 ft	2.00 gal/min
5/13/2024 2:38 PM	45:00	7.11 pH	18.10 °C	684.20 µS/cm	-0.02 mg/L	4.22 NTU	12.9 mV	11.40 ft	2.00 gal/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 5/13/2024 2:54:11 PM
Project: Plant Hammond
Operator Name: Jamie Newsome

Location Name: AS-02 Well Diameter: 2 in Casing Type: PVC Screen Length: 2 ft Top of Screen: 32 ft Total Depth: 34 ft Initial Depth to Water: 11.11 ft	Pump Type: Monsoon Tubing Type: Polyethylene Pump Intake From TOC: 33 ft Estimated Total Volume Pumped: 21.25 liter Flow Cell Volume: 90 ml Final Flow Rate: 250 ml/min Final Draw Down: 0.04 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
--	--	--

Test Notes:
Well Development, Purge 2

Weather Conditions:
Cloudy, 60 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 3 %	+/- 0.2	+/- 10	+/- 10	+/- 0.3	
5/13/2024 2:54 PM	00:00	7.09 pH	18.78 °C	683.25 µS/cm	0.02 mg/L	4.47 NTU	0.4 mV	11.11 ft	250.00 ml/min
5/13/2024 2:59 PM	05:00	7.08 pH	18.83 °C	686.16 µS/cm	0.02 mg/L	11.80 NTU	-0.2 mV	11.11 ft	250.00 ml/min
5/13/2024 3:04 PM	10:00	7.07 pH	18.84 °C	684.77 µS/cm	0.03 mg/L	10.80 NTU	-0.4 mV	11.11 ft	250.00 ml/min
5/13/2024 3:09 PM	15:00	7.06 pH	18.79 °C	685.11 µS/cm	0.03 mg/L	13.37 NTU	-6.1 mV	11.11 ft	250.00 ml/min
5/13/2024 3:14 PM	20:00	7.06 pH	18.75 °C	685.82 µS/cm	0.03 mg/L	13.17 NTU	-4.6 mV	11.11 ft	250.00 ml/min
5/13/2024 3:19 PM	25:00	7.05 pH	18.72 °C	686.30 µS/cm	0.03 mg/L	11.00 NTU	-2.7 mV	11.11 ft	250.00 ml/min
5/13/2024 3:24 PM	30:00	7.05 pH	18.74 °C	686.60 µS/cm	0.04 mg/L	15.34 NTU	-0.9 mV	11.11 ft	250.00 ml/min
5/13/2024 3:29 PM	35:00	7.05 pH	18.74 °C	687.19 µS/cm	0.04 mg/L	13.25 NTU	0.7 mV	11.11 ft	250.00 ml/min
5/13/2024 3:34 PM	40:00	7.05 pH	18.79 °C	687.44 µS/cm	0.04 mg/L	11.65 NTU	1.9 mV	11.11 ft	250.00 ml/min
5/13/2024 3:39 PM	45:00	7.04 pH	18.79 °C	687.50 µS/cm	0.04 mg/L	11.08 NTU	2.7 mV	11.11 ft	250.00 ml/min
5/13/2024 3:44 PM	50:00	7.04 pH	18.79 °C	687.98 µS/cm	0.05 mg/L	11.35 NTU	3.5 mV	11.15 ft	250.00 ml/min
5/13/2024 3:49 PM	55:00	7.05 pH	18.81 °C	688.57 µS/cm	0.04 mg/L	10.49 NTU	7.5 mV	11.15 ft	250.00 ml/min
5/13/2024 3:54 PM	01:00:00	7.05 pH	18.88 °C	688.11 µS/cm	0.04 mg/L	9.80 NTU	4.5 mV	11.15 ft	250.00 ml/min

5/13/2024 3:59 PM	01:05:00	7.06 pH	18.94 °C	688.53 µS/cm	0.04 mg/L	8.79 NTU	5.1 mV	11.15 ft	250.00 ml/min
5/13/2024 4:04 PM	01:10:00	7.06 pH	19.01 °C	688.26 µS/cm	0.04 mg/L	8.07 NTU	8.6 mV	11.15 ft	250.00 ml/min
5/13/2024 4:09 PM	01:15:00	7.06 pH	19.05 °C	688.40 µS/cm	0.04 mg/L	7.97 NTU	6.6 mV	11.15 ft	250.00 ml/min
5/13/2024 4:14 PM	01:20:00	7.06 pH	19.14 °C	688.63 µS/cm	0.04 mg/L	5.43 NTU	6.9 mV	11.15 ft	250.00 ml/min
5/13/2024 4:19 PM	01:25:00	7.06 pH	19.23 °C	688.61 µS/cm	0.04 mg/L	4.94 NTU	7.1 mV	11.15 ft	250.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 4/30/2024 1:08:29 PM
Project: Plant Hammond
Operator Name: Elisabeth Russell

Location Name: AS-03 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 34.95 ft Total Depth: 44.95 ft Initial Depth to Water: 25.28 ft	Pump Type: Monsoon Tubing Type: Polyethylene Pump Intake From TOC: 43 ft Estimated Total Volume Pumped: 490 liter Flow Cell Volume: 90 ml Final Flow Rate: 5000 ml/min Final Draw Down: 2.12 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883546
---	---	--

Test Notes:
Well Development

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.5	
4/30/2024 1:08 PM	00:00	6.90 pH	25.15 °C	730.98 µS/cm	-0.03 mg/L	107.00 NTU	4.0 mV	27.08 ft	5,000.0 ml/min
4/30/2024 1:14 PM	06:06	6.88 pH	24.18 °C	783.00 µS/cm	-0.05 mg/L	105.10 NTU	1.4 mV	27.30 ft	5,000.0 ml/min
4/30/2024 1:19 PM	11:06	6.88 pH	22.64 °C	812.64 µS/cm	-0.06 mg/L	77.30 NTU	2.3 mV	27.50 ft	5,000.0 ml/min
4/30/2024 1:24 PM	16:06	6.88 pH	22.54 °C	820.73 µS/cm	-0.06 mg/L	50.00 NTU	3.8 mV	27.58 ft	5,000.0 ml/min
4/30/2024 1:29 PM	21:06	6.88 pH	22.28 °C	829.41 µS/cm	-0.06 mg/L	34.60 NTU	5.2 mV	27.62 ft	5,000.0 ml/min
4/30/2024 1:34 PM	26:06	6.87 pH	22.13 °C	835.25 µS/cm	0.03 mg/L	73.90 NTU	32.7 mV	27.50 ft	5,000.0 ml/min
4/30/2024 1:39 PM	31:06	6.88 pH	21.97 °C	840.38 µS/cm	-0.06 mg/L	18.80 NTU	6.7 mV	27.55 ft	5,000.0 ml/min
4/30/2024 1:44 PM	36:06	6.88 pH	21.79 °C	844.30 µS/cm	0.58 mg/L	39.70 NTU	5.5 mV	27.57 ft	5,000.0 ml/min
4/30/2024 1:49 PM	41:06	6.87 pH	21.75 °C	847.97 µS/cm	-0.06 mg/L	33.80 NTU	8.2 mV	27.60 ft	5,000.0 ml/min
4/30/2024 1:54 PM	46:06	6.87 pH	21.61 °C	849.37 µS/cm	-0.05 mg/L	14.40 NTU	8.1 mV	27.62 ft	5,000.0 ml/min
4/30/2024 1:59 PM	51:06	6.87 pH	21.73 °C	850.76 µS/cm	-0.05 mg/L	78.60 NTU	8.8 mV	27.63 ft	5,000.0 ml/min
4/30/2024 2:04 PM	56:06	6.87 pH	21.67 °C	851.17 µS/cm	-0.06 mg/L	19.50 NTU	10.5 mV	27.64 ft	5,000.0 ml/min
4/30/2024 2:09 PM	01:01:06	6.87 pH	21.71 °C	852.86 µS/cm	-0.07 mg/L	13.30 NTU	11.0 mV	27.65 ft	5,000.0 ml/min
4/30/2024 2:14 PM	01:06:06	6.88 pH	21.83 °C	851.85 µS/cm	0.01 mg/L	18.30 NTU	9.9 mV	27.66 ft	5,000.0 ml/min
4/30/2024 2:19 PM	01:11:06	6.87 pH	21.68 °C	856.52 µS/cm	-0.07 mg/L	16.70 NTU	12.1 mV	27.60 ft	5,000.0 ml/min

4/30/2024 2:24 PM	01:16:06	6.87 pH	21.70 °C	856.98 µS/cm	-0.07 mg/L	13.40 NTU	12.5 mV	27.40 ft	5,000.0 ml/min
4/30/2024 2:29 PM	01:21:06	6.87 pH	21.64 °C	856.30 µS/cm	-0.07 mg/L	7.11 NTU	12.7 mV	27.40 ft	5,000.0 ml/min
4/30/2024 2:34 PM	01:26:06	6.88 pH	21.68 °C	856.80 µS/cm	-0.07 mg/L	6.12 NTU	13.3 mV	27.40 ft	5,000.0 ml/min
4/30/2024 2:39 PM	01:31:06	6.88 pH	21.67 °C	857.41 µS/cm	-0.07 mg/L	4.74 NTU	13.5 mV	27.40 ft	5,000.0 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 4/30/2024 10:41:40 AM
Project: Plant Hammond
Operator Name: Zain W.

Location Name: AS-04 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 38.5 ft Total Depth: 48.5 ft Initial Depth to Water: 25.87 ft	Pump Type: Monsoon Tubing Type: Polyethylene Pump Intake From TOC: 43.5 ft Estimated Total Volume Pumped: 96 liter Flow Cell Volume: 90 ml Final Flow Rate: 8000 ml/min Final Draw Down: 0.91 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
---	--	--

Test Notes:
Well Development

Weather Conditions:
Rain, 65 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
4/30/2024 10:41 AM	00:00	7.78 pH	18.46 °C	3.57 µS/cm	8.76 mg/L	++++	87.2 mV	25.87 ft	8,000.0 ml/min
4/30/2024 10:46 AM	05:00	7.89 pH	18.30 °C	2.86 µS/cm	9.13 mg/L	++++	72.9 mV	25.87 ft	8,000.0 ml/min
4/30/2024 10:51 AM	10:00	7.13 pH	18.66 °C	677.09 µS/cm	0.07 mg/L	++++	48.0 mV	25.87 ft	8,000.0 ml/min
4/30/2024 10:56 AM	15:00	7.18 pH	18.65 °C	570.07 µS/cm	0.51 mg/L	++++	-36.9 mV	25.87 ft	8,000.0 ml/min
4/30/2024 11:01 AM	20:00	6.93 pH	18.56 °C	704.43 µS/cm	0.00 mg/L	870.00 NTU	-60.6 mV	25.87 ft	8,000.0 ml/min
4/30/2024 11:06 AM	25:00	6.99 pH	18.54 °C	621.54 µS/cm	1.96 mg/L	++++	-54.3 mV	25.87 ft	8,000.0 ml/min
4/30/2024 11:11 AM	30:00	6.92 pH	18.51 °C	706.93 µS/cm	-0.00 mg/L	++++	-71.8 mV	25.87 ft	8,000.0 ml/min
4/30/2024 11:16 AM	35:00	6.91 pH	18.51 °C	710.60 µS/cm	-0.01 mg/L	986.00 NTU	-54.2 mV	25.87 ft	8,000.0 ml/min
4/30/2024 11:21 AM	40:00	6.90 pH	18.52 °C	712.85 µS/cm	-0.01 mg/L	46.80 NTU	-79.4 mV	25.87 ft	8,000.0 ml/min
4/30/2024 11:26 AM	45:00	6.88 pH	18.52 °C	713.89 µS/cm	-0.01 mg/L	13.50 NTU	-57.7 mV	25.87 ft	8,000.0 ml/min
4/30/2024 11:31 AM	50:00	6.87 pH	18.52 °C	714.20 µS/cm	-0.01 mg/L	12.90 NTU	-81.1 mV	25.87 ft	8,000.0 ml/min
4/30/2024 11:36 AM	55:00	6.85 pH	18.52 °C	714.25 µS/cm	-0.01 mg/L	12.10 NTU	-81.8 mV	25.87 ft	8,000.0 ml/min
4/30/2024 11:41 AM	01:00:00	6.82 pH	18.52 °C	713.14 µS/cm	-0.01 mg/L	--	-58.2 mV	25.87 ft	8,000.0 ml/min

4/30/2024 11:46 AM	01:05:00	6.80 pH	18.52 °C	713.07 µS/cm	-0.01 mg/L	--	-80.0 mV	25.87 ft	8,000.0 ml/min
4/30/2024 11:51 AM	01:10:00	6.77 pH	18.54 °C	712.62 µS/cm	-0.01 mg/L	11.00 NTU	-62.8 mV	27.34 ft	8,000.0 ml/min
4/30/2024 11:56 AM	01:15:00	6.76 pH	18.55 °C	714.46 µS/cm	-0.01 mg/L	--	-50.7 mV	27.34 ft	8,000.0 ml/min
4/30/2024 12:01 PM	01:20:00	6.75 pH	18.52 °C	715.77 µS/cm	-0.01 mg/L	12.40 NTU	-72.6 mV	27.34 ft	8,000.0 ml/min
4/30/2024 12:06 PM	01:25:00	6.89 pH	18.84 °C	717.14 µS/cm	-0.01 mg/L	83.30 NTU	-57.2 mV	27.34 ft	8,000.0 ml/min
4/30/2024 12:11 PM	01:30:00	6.97 pH	19.18 °C	716.28 µS/cm	-0.01 mg/L	61.30 NTU	-84.9 mV	26.56 ft	8,000.0 ml/min
4/30/2024 12:16 PM	01:35:00	6.96 pH	19.17 °C	712.07 µS/cm	-0.01 mg/L	16.60 NTU	-83.8 mV	26.56 ft	8,000.0 ml/min
4/30/2024 12:21 PM	01:40:00	6.96 pH	19.27 °C	709.42 µS/cm	-0.01 mg/L	16.40 NTU	-84.9 mV	26.56 ft	8,000.0 ml/min
4/30/2024 12:26 PM	01:45:00	6.95 pH	19.93 °C	716.72 µS/cm	0.00 mg/L	35.20 NTU	-88.9 mV	26.56 ft	8,000.0 ml/min
4/30/2024 12:31 PM	01:50:00	6.96 pH	18.83 °C	703.66 µS/cm	-0.01 mg/L	12.98 NTU	-86.2 mV	26.56 ft	8,000.0 ml/min
4/30/2024 12:36 PM	01:55:00	6.96 pH	18.85 °C	702.93 µS/cm	-0.01 mg/L	8.91 NTU	-88.6 mV	26.56 ft	8,000.0 ml/min
4/30/2024 12:41 PM	02:00:00	6.96 pH	18.74 °C	701.17 µS/cm	-0.01 mg/L	3.40 NTU	-64.8 mV	26.78 ft	8,000.0 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 5/13/2024 10:03:08 AM
Project: Plant Hammond
Operator Name: Jamie Newsome

Location Name: INW-03 Well Diameter: 2 in Casing Type: PVC Screen Length: 2 ft Top of Screen: 17 ft Total Depth: 27 ft Initial Depth to Water: 11.15 ft	Pump Type: Monsoon Tubing Type: Polyethylene Pump Intake From TOC: 22 ft Estimated Total Volume Pumped: 120 gal Flow Cell Volume: 90 ml Final Flow Rate: 2 gal/min Final Draw Down: 0.55 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
---	---	--

Test Notes:
Well Development, Purge 1

Weather Conditions:
Light rain, 60 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 3 %	+/- 0.2	+/- 10	+/- 10	+/- 0.3	
5/13/2024 10:03 AM	00:00	7.62 pH	18.08 °C	745.76 µS/cm	0.03 mg/L	263.00 NTU	20.6 mV	11.65 ft	2.00 gal/min
5/13/2024 10:08 AM	05:00	7.58 pH	18.07 °C	717.23 µS/cm	0.01 mg/L	135.00 NTU	21.3 mV	11.65 ft	2.00 gal/min
5/13/2024 10:13 AM	10:00	7.55 pH	18.08 °C	715.83 µS/cm	-0.00 mg/L	41.30 NTU	10.1 mV	11.65 ft	2.00 gal/min
5/13/2024 10:18 AM	15:00	7.71 pH	18.07 °C	713.84 µS/cm	-0.01 mg/L	73.30 NTU	-6.0 mV	11.65 ft	2.00 gal/min
5/13/2024 10:23 AM	20:00	7.58 pH	18.07 °C	711.66 µS/cm	-0.01 mg/L	65.50 NTU	1.7 mV	11.65 ft	2.00 gal/min
5/13/2024 10:28 AM	25:00	7.57 pH	18.06 °C	712.92 µS/cm	-0.01 mg/L	19.70 NTU	-16.2 mV	11.70 ft	2.00 gal/min
5/13/2024 10:33 AM	30:00	7.58 pH	18.04 °C	711.15 µS/cm	-0.01 mg/L	15.00 NTU	-10.4 mV	11.70 ft	2.00 gal/min
5/13/2024 10:38 AM	35:00	7.59 pH	18.06 °C	713.24 µS/cm	-0.01 mg/L	12.00 NTU	-24.6 mV	11.70 ft	2.00 gal/min
5/13/2024 10:43 AM	40:00	7.59 pH	18.05 °C	713.65 µS/cm	-0.02 mg/L	10.94 NTU	-25.5 mV	11.70 ft	2.00 gal/min
5/13/2024 10:48 AM	45:00	7.59 pH	18.05 °C	712.34 µS/cm	-0.02 mg/L	8.49 NTU	-13.0 mV	11.70 ft	2.00 gal/min
5/13/2024 10:53 AM	50:00	7.59 pH	18.05 °C	710.78 µS/cm	-0.02 mg/L	7.61 NTU	-12.4 mV	11.70 ft	2.00 gal/min
5/13/2024 10:58 AM	55:00	7.58 pH	18.05 °C	711.66 µS/cm	-0.02 mg/L	6.09 NTU	-11.9 mV	11.70 ft	2.00 gal/min
5/13/2024 11:03 AM	01:00:00	7.59 pH	18.04 °C	712.48 µS/cm	-0.02 mg/L	4.89 NTU	-12.0 mV	11.70 ft	2.00 gal/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 5/13/2024 11:35:20 AM

Project: Plant Hammond

Operator Name: Jamie Newsome

Location Name: INW-03 Well Diameter: 2 in Casing Type: PVC Screen Length: 2 ft Top of Screen: 17 ft Total Depth: 27 ft Initial Depth to Water: 11.35 ft	Pump Type: Monsoon Tubing Type: Polyethylene Pump Intake From TOC: 22 ft Estimated Total Volume Pumped: 13.75 liter Flow Cell Volume: 90 ml Final Flow Rate: 250 ml/min Final Draw Down: 0.00 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
--	---	--

Test Notes:

Well Development, Purge 2

Weather Conditions:

Light rain, 60 degrees F.

Low-Flow Readings:

[illegible]

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 4/30/2024 3:55:27 PM
Project: Plant Hammond
Operator Name: Elisabeth Russell

Location Name: INW-04 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 34.95 ft Total Depth: 44.95 ft Initial Depth to Water: 25.28 ft	Pump Type: Monsoon Tubing Type: Polyethylene Pump Intake From TOC: 43 ft Estimated Total Volume Pumped: 1135 liter Flow Cell Volume: 90 ml Final Flow Rate: 8000 ml/min Final Draw Down: 1.71 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883546
---	---	--

Test Notes:
Well Development

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.5	
4/30/2024 3:55 PM	00:00	6.92 pH	24.47 °C	694.89 µS/cm	0.86 mg/L	1,750.0 NTU	10.8 mV	36.60 ft	10,000.0 ml/min
4/30/2024 4:00 PM	05:00	6.91 pH	22.93 °C	726.77 µS/cm	1.33 mg/L	161.00 NTU	5.7 mV	36.60 ft	10,000.0 ml/min
4/30/2024 4:04 PM	08:46	6.89 pH	23.33 °C	724.28 µS/cm	1.42 mg/L	125.00 NTU	7.9 mV	36.60 ft	10,000.0 ml/min
4/30/2024 4:09 PM	13:48	6.88 pH	22.57 °C	736.51 µS/cm	1.45 mg/L	84.00 NTU	7.5 mV	36.60 ft	10,000.0 ml/min
4/30/2024 4:11 PM	16:05	6.88 pH	22.24 °C	742.59 µS/cm	1.46 mg/L	80.20 NTU	7.1 mV	36.60 ft	10,000.0 ml/min
4/30/2024 4:16 PM	21:05	6.88 pH	21.35 °C	757.06 µS/cm	1.39 mg/L	79.50 NTU	5.7 mV	36.60 ft	10,000.0 ml/min
4/30/2024 4:21 PM	26:05	6.87 pH	21.13 °C	760.89 µS/cm	1.37 mg/L	119.00 NTU	5.7 mV	36.60 ft	8,000.0 ml/min
4/30/2024 4:26 PM	31:05	6.86 pH	21.11 °C	766.29 µS/cm	1.51 mg/L	2,272.0 NTU	15.8 mV	36.60 ft	8,000.0 ml/min
4/30/2024 4:31 PM	36:05	6.84 pH	21.12 °C	765.68 µS/cm	1.65 mg/L	1,290.0 NTU	19.4 mV	36.60 ft	8,000.0 ml/min
4/30/2024 4:33 PM	38:01	6.84 pH	21.42 °C	761.81 µS/cm	1.70 mg/L	172.00 NTU	19.0 mV	36.60 ft	8,000.0 ml/min
4/30/2024 4:38 PM	43:01	6.84 pH	21.26 °C	764.96 µS/cm	1.62 mg/L	37.00 NTU	18.0 mV	36.60 ft	8,000.0 ml/min
4/30/2024 4:43 PM	48:01	6.84 pH	21.17 °C	770.33 µS/cm	1.53 mg/L	92.00 NTU	18.3 mV	36.60 ft	8,000.0 ml/min
4/30/2024 4:45 PM	50:03	6.83 pH	21.35 °C	766.06 µS/cm	1.56 mg/L	77.00 NTU	18.1 mV	36.60 ft	8,000.0 ml/min
4/30/2024 4:50 PM	55:03	6.84 pH	21.19 °C	770.20 µS/cm	1.19 mg/L	49.30 NTU	20.1 mV	36.60 ft	8,000.0 ml/min
4/30/2024 4:53 PM	58:27	6.84 pH	21.21 °C	769.86 µS/cm	1.20 mg/L	43.00 NTU	13.8 mV	36.60 ft	8,000.0 ml/min

4/30/2024 4:58 PM	01:03:27	6.83 pH	20.92 °C	779.12 µS/cm	1.66 mg/L	38.90 NTU	15.7 mV	36.60 ft	8,000.0 ml/min
4/30/2024 5:03 PM	01:08:27	6.83 pH	20.97 °C	776.99 µS/cm	1.57 mg/L	23.60 NTU	16.1 mV	36.60 ft	8,000.0 ml/min
4/30/2024 5:08 PM	01:13:27	6.84 pH	20.91 °C	774.36 µS/cm	1.29 mg/L	84.10 NTU	16.3 mV	36.60 ft	8,000.0 ml/min
4/30/2024 5:13 PM	01:18:08	6.83 pH	21.22 °C	770.38 µS/cm	1.36 mg/L	10.84 NTU	18.2 mV	36.60 ft	8,000.0 ml/min
4/30/2024 5:18 PM	01:23:08	6.84 pH	21.07 °C	791.57 µS/cm	1.28 mg/L	76.00 NTU	35.1 mV	36.60 ft	8,000.0 ml/min
4/30/2024 5:23 PM	01:28:08	6.84 pH	21.14 °C	774.63 µS/cm	1.35 mg/L	37.60 NTU	9.7 mV	36.60 ft	8,000.0 ml/min
4/30/2024 5:28 PM	01:33:08	6.83 pH	21.15 °C	772.90 µS/cm	1.28 mg/L	18.00 NTU	9.9 mV	36.60 ft	8,000.0 ml/min
4/30/2024 5:33 PM	01:38:08	6.84 pH	21.01 °C	776.07 µS/cm	1.32 mg/L	15.00 NTU	23.8 mV	36.60 ft	8,000.0 ml/min
4/30/2024 5:38 PM	01:43:08	6.84 pH	20.75 °C	788.36 µS/cm	1.43 mg/L	14.90 NTU	11.6 mV	36.60 ft	8,000.0 ml/min
4/30/2024 5:43 PM	01:48:08	6.83 pH	20.68 °C	787.12 µS/cm	1.45 mg/L	16.60 NTU	15.1 mV	36.60 ft	8,000.0 ml/min
4/30/2024 5:48 PM	01:53:08	6.84 pH	20.64 °C	788.52 µS/cm	1.42 mg/L	16.00 NTU	11.8 mV	36.60 ft	8,000.0 ml/min
4/30/2024 5:53 PM	01:58:08	6.85 pH	20.72 °C	809.29 µS/cm	0.50 mg/L	18.70 NTU	48.4 mV	29.00 ft	8,000.0 ml/min
4/30/2024 5:58 PM	02:03:08	6.84 pH	21.15 °C	793.48 µS/cm	0.30 mg/L	12.00 NTU	48.9 mV	27.00 ft	8,000.0 ml/min
4/30/2024 6:03 PM	02:08:08	6.85 pH	20.72 °C	798.59 µS/cm	0.33 mg/L	10.70 NTU	37.5 mV	26.88 ft	8,000.0 ml/min
4/30/2024 6:08 PM	02:13:08	6.84 pH	20.57 °C	804.55 µS/cm	0.31 mg/L	7.67 NTU	48.8 mV	26.90 ft	8,000.0 ml/min
4/30/2024 6:13 PM	02:18:08	6.84 pH	20.55 °C	809.91 µS/cm	0.29 mg/L	4.56 NTU	72.4 mV	26.99 ft	8,000.0 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 4/30/2024 1:18:01 PM
Project: Plant Hammond
Operator Name: Zain W.

Location Name: INW-05 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 34.65 ft Total Depth: 44.65 ft Initial Depth to Water: 24.90 ft	Pump Type: Monsoon Tubing Type: Polyethylene Pump Intake From TOC: 39.65 ft Estimated Total Volume Pumped: 405 liter Flow Cell Volume: 90 ml Final Flow Rate: 4500 ml/min Final Draw Down: 1.51 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
---	---	--

Test Notes:
Well Development

Weather Conditions:
Cloudy, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
4/30/2024 1:18 PM	00:00	7.08 pH	17.75 °C	643.85 µS/cm	0.01 mg/L	154.00 NTU	-120.4 mV	24.90 ft	4500.0 ml/min
4/30/2024 1:23 PM	05:00	7.09 pH	17.72 °C	649.16 µS/cm	-0.00 mg/L	64.70 NTU	-122.3 mV	26.46 ft	4500.0 ml/min
4/30/2024 1:28 PM	10:00	7.09 pH	17.72 °C	651.66 µS/cm	-0.01 mg/L	26.90 NTU	-142.0 mV	26.46 ft	4500.0 ml/min
4/30/2024 1:33 PM	15:00	7.08 pH	17.70 °C	652.59 µS/cm	-0.01 mg/L	19.40 NTU	-142.9 mV	26.43 ft	4500.0 ml/min
4/30/2024 1:38 PM	20:00	7.07 pH	17.70 °C	653.95 µS/cm	-0.01 mg/L	12.89 NTU	-142.9 mV	26.50 ft	4500.0 ml/min
4/30/2024 1:43 PM	25:00	7.06 pH	17.68 °C	654.82 µS/cm	-0.01 mg/L	11.22 NTU	-142.7 mV	26.52 ft	4500.0 ml/min
4/30/2024 1:48 PM	30:00	7.05 pH	17.67 °C	655.84 µS/cm	-0.01 mg/L	5.94 NTU	-142.2 mV	26.53 ft	4500.0 ml/min
4/30/2024 1:53 PM	35:00	7.03 pH	17.72 °C	656.45 µS/cm	-0.00 mg/L	73.00 NTU	-138.4 mV	26.40 ft	4500.0 ml/min
4/30/2024 1:58 PM	40:00	7.03 pH	17.72 °C	656.14 µS/cm	-0.01 mg/L	11.90 NTU	-139.2 mV	26.40 ft	4500.0 ml/min
4/30/2024 2:03 PM	45:00	7.00 pH	17.77 °C	659.55 µS/cm	0.00 mg/L	93.90 NTU	-136.8 mV	26.30 ft	4500.0 ml/min
4/30/2024 2:08 PM	50:00	7.01 pH	17.79 °C	657.70 µS/cm	-0.01 mg/L	5.91 NTU	-136.8 mV	26.28 ft	4500.0 ml/min
4/30/2024 2:13 PM	55:00	7.02 pH	17.85 °C	657.01 µS/cm	-0.02 mg/L	2,111.0 NTU	-138.9 mV	26.20 ft	4500.0 ml/min
4/30/2024 2:18 PM	01:00:00	7.05 pH	17.80 °C	657.18 µS/cm	-0.02 mg/L	3.57 NTU	-141.3 mV	26.16 ft	4500.0 ml/min

4/30/2024 2:23 PM	01:05:00	7.06 pH	17.92 °C	660.31 µS/cm	-0.02 mg/L	3,147.0 NTU	-141.6 mV	26.17 ft	4500.0 ml/min
4/30/2024 2:28 PM	01:10:00	7.08 pH	17.84 °C	657.52 µS/cm	-0.02 mg/L	12.90 NTU	-143.2 mV	26.43 ft	4500.0 ml/min
4/30/2024 2:33 PM	01:15:00	7.09 pH	17.85 °C	658.45 µS/cm	-0.02 mg/L	1.33 NTU	-143.3 mV	26.31 ft	4500.0 ml/min
4/30/2024 2:38 PM	01:20:00	7.08 pH	17.86 °C	655.90 µS/cm	-0.02 mg/L	10.28 NTU	-140.8 mV	26.34 ft	4500.0 ml/min
4/30/2024 2:43 PM	01:25:00	7.09 pH	17.83 °C	656.39 µS/cm	-0.02 mg/L	0.25 NTU	-123.7 mV	26.41 ft	4500.0 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 5/9/2024 2:07:43 PM
Project: Plant Hammond
Operator Name: Jamie Newsome

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17 ft Total Depth: 27 ft Initial Depth to Water: 11.45 ft	Pump Type: Monsoon Tubing Type: Poly Pump Intake From TOC: 22 ft Estimated Total Volume Pumped: 424.02 gal Flow Cell Volume: 90 ml Final Flow Rate: 3.33 gal/min Final Draw Down: 0.15 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
---	---	--

Test Notes:
Well Development, Purge 1

Weather Conditions:
Sunny, 66 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 3 %	+/- 0.2	+/- 10	+/- 10	+/- 0.3	
5/9/2024 2:07 PM	00:00	7.11 pH	18.01 °C	683.08 µS/cm	-0.00 mg/L	1,273.0 NTU	-25.2 mV	11.50 ft	3.33 gal/min
5/9/2024 2:12 PM	05:00	7.13 pH	18.03 °C	682.27 µS/cm	-0.01 mg/L	2,053.0 NTU	-49.7 mV	11.53 ft	3.33 gal/min
5/9/2024 2:17 PM	10:00	7.16 pH	18.07 °C	685.05 µS/cm	-0.01 mg/L	2,185.0 NTU	-57.7 mV	11.55 ft	3.33 gal/min
5/9/2024 2:22 PM	15:00	7.16 pH	18.08 °C	685.58 µS/cm	-0.01 mg/L	1,089.0 NTU	-53.4 mV	11.55 ft	3.33 gal/min
5/9/2024 2:27 PM	20:00	7.14 pH	18.08 °C	686.10 µS/cm	-0.01 mg/L	1,903.0 NTU	-46.9 mV	11.55 ft	3.33 gal/min
5/9/2024 2:32 PM	25:00	7.16 pH	18.08 °C	686.60 µS/cm	-0.02 mg/L	644.00 NTU	-54.2 mV	11.56 ft	3.33 gal/min
5/9/2024 2:37 PM	30:00	7.16 pH	18.10 °C	686.88 µS/cm	-0.02 mg/L	1,745.0 NTU	-31.4 mV	11.56 ft	3.33 gal/min
5/9/2024 2:42 PM	35:00	7.15 pH	18.08 °C	686.81 µS/cm	-0.02 mg/L	946.00 NTU	-46.6 mV	11.60 ft	3.33 gal/min
5/9/2024 2:47 PM	40:00	7.16 pH	18.08 °C	687.83 µS/cm	-0.02 mg/L	1,047.0 NTU	-46.2 mV	11.60 ft	3.33 gal/min
5/9/2024 2:52 PM	45:00	7.15 pH	18.12 °C	688.22 µS/cm	-0.02 mg/L	1,166.0 NTU	-45.8 mV	11.60 ft	3.33 gal/min
5/9/2024 2:57 PM	50:00	7.15 pH	18.12 °C	687.10 µS/cm	-0.02 mg/L	1,228.0 NTU	-26.0 mV	11.60 ft	3.33 gal/min
5/9/2024 3:02 PM	55:00	7.14 pH	18.08 °C	687.74 µS/cm	-0.02 mg/L	822.00 NTU	-19.1 mV	11.60 ft	3.33 gal/min
5/9/2024 3:07 PM	01:00:00	7.14 pH	18.12 °C	688.51 µS/cm	-0.02 mg/L	1,080.0 NTU	-23.3 mV	11.60 ft	3.33 gal/min

5/9/2024 3:12 PM	01:05:00	7.14 pH	18.08 °C	689.21 µS/cm	-0.02 mg/L	727.00 NTU	-20.2 mV	11.60 ft	3.33 gal/min
5/9/2024 3:17 PM	01:10:00	7.15 pH	18.08 °C	689.08 µS/cm	-0.02 mg/L	127.00 NTU	-40.1 mV	11.60 ft	3.33 gal/min
5/9/2024 3:22 PM	01:15:00	7.14 pH	18.08 °C	689.64 µS/cm	-0.02 mg/L	865.00 NTU	-22.3 mV	11.60 ft	3.33 gal/min
5/9/2024 3:27 PM	01:20:00	7.16 pH	18.07 °C	687.61 µS/cm	-0.02 mg/L	104.00 NTU	-23.9 mV	11.60 ft	3.33 gal/min
5/9/2024 3:32 PM	01:25:00	7.15 pH	18.10 °C	689.15 µS/cm	-0.02 mg/L	54.20 NTU	-43.5 mV	11.60 ft	3.33 gal/min
5/9/2024 3:37 PM	01:30:00	7.14 pH	18.09 °C	689.93 µS/cm	-0.02 mg/L	33.70 NTU	-39.8 mV	11.60 ft	3.33 gal/min
5/9/2024 3:42 PM	01:35:00	7.15 pH	18.08 °C	689.12 µS/cm	-0.02 mg/L	15.70 NTU	-41.8 mV	11.60 ft	3.33 gal/min
5/9/2024 3:47 PM	01:40:00	7.13 pH	18.14 °C	688.20 µS/cm	-0.02 mg/L	53.20 NTU	-18.9 mV	11.60 ft	3.33 gal/min
5/9/2024 3:52 PM	01:45:00	7.13 pH	18.12 °C	690.98 µS/cm	-0.02 mg/L	11.80 NTU	-38.6 mV	11.60 ft	3.33 gal/min
5/9/2024 3:57 PM	01:50:00	7.13 pH	18.15 °C	691.02 µS/cm	-0.02 mg/L	11.46 NTU	-39.3 mV	11.60 ft	3.33 gal/min
5/9/2024 4:02 PM	01:55:00	7.13 pH	18.13 °C	691.85 µS/cm	-0.02 mg/L	6.82 NTU	-38.1 mV	11.60 ft	3.33 gal/min
5/9/2024 4:07 PM	02:00:00	7.13 pH	18.12 °C	690.99 µS/cm	-0.02 mg/L	6.44 NTU	-19.3 mV	11.60 ft	3.33 gal/min
5/9/2024 4:12 PM	02:05:00	7.12 pH	18.16 °C	690.87 µS/cm	-0.02 mg/L	3.28 NTU	-35.4 mV	11.60 ft	3.33 gal/min
5/9/2024 4:15 PM	02:07:20	7.13 pH	18.12 °C	691.93 µS/cm	-0.02 mg/L		-35.7 mV	11.60 ft	3.33 gal/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 5/9/2024 4:23:25 PM
Project: Plant Hammond
Operator Name: Jamie Newsome

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17 ft Total Depth: 27 ft Initial Depth to Water: 11.60 ft	Pump Type: Monsoon Tubing Type: Polyethylene Pump Intake From TOC: 22 ft Estimated Total Volume Pumped: 88.5 gal Flow Cell Volume: 90 ml Final Flow Rate: 1 gal/min Final Draw Down: 0.00 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
---	--	--

Test Notes:
Well Development, Purge 2

Weather Conditions:
Sunny, 66 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 3 %	+/- 0.2	+/- 10	+/- 10	+/- 0.3	
5/9/2024 4:23 PM	00:00	7.10 pH	19.12 °C	690.09 µS/cm	-0.02 mg/L	3.29 NTU	-25.2 mV	11.60 ft	1.00 gal/min
5/9/2024 4:28 PM	05:00	7.11 pH	19.11 °C	3.19 µS/cm	2.01 mg/L	8.18 NTU	24.3 mV	11.60 ft	1.00 gal/min
5/9/2024 4:33 PM	10:00	7.04 pH	21.96 °C	694.75 µS/cm	0.06 mg/L	12.50 NTU	-8.7 mV	11.60 ft	1.00 gal/min
5/9/2024 4:38 PM	15:00	7.02 pH	21.80 °C	691.97 µS/cm	0.01 mg/L	11.20 NTU	-14.0 mV	11.60 ft	1.00 gal/min
5/9/2024 4:43 PM	20:00	7.01 pH	21.46 °C	689.01 µS/cm	0.00 mg/L	12.18 NTU	-14.3 mV	11.60 ft	1.00 gal/min
5/9/2024 4:48 PM	25:00	7.01 pH	21.81 °C	688.57 µS/cm	0.00 mg/L	11.74 NTU	-28.2 mV	11.60 ft	1.00 gal/min
5/9/2024 4:53 PM	30:00	7.02 pH	21.80 °C	688.81 µS/cm	0.00 mg/L	11.08 NTU	-28.1 mV	11.60 ft	1.00 gal/min
5/9/2024 4:58 PM	35:00	7.03 pH	21.58 °C	689.43 µS/cm	0.00 mg/L	10.02 NTU	-28.8 mV	11.60 ft	1.00 gal/min
5/9/2024 5:03 PM	40:00	7.04 pH	21.42 °C	689.88 µS/cm	0.00 mg/L	9.68 NTU	-27.6 mV	11.60 ft	1.00 gal/min
5/9/2024 5:08 PM	45:00	7.04 pH	21.59 °C	689.25 µS/cm	-0.00 mg/L	10.90 NTU	-27.1 mV	11.60 ft	1.00 gal/min
5/9/2024 5:13 PM	50:00	7.05 pH	21.25 °C	695.17 µS/cm	-0.00 mg/L	8.56 NTU	-12.8 mV	11.60 ft	1.00 gal/min
5/9/2024 5:18 PM	55:00	7.05 pH	23.61 °C	698.55 µS/cm	0.02 mg/L	8.53 NTU	-11.8 mV	11.60 ft	1.00 gal/min
5/9/2024 5:23 PM	01:00:00	7.00 pH	24.67 °C	690.40 µS/cm	0.02 mg/L	11.60 NTU	-15.9 mV	11.60 ft	1.00 gal/min

5/9/2024 5:28 PM	01:05:00	6.94 pH	24.28 °C	695.53 µS/cm	0.02 mg/L	10.70 NTU	-12.6 mV	11.60 ft	1.00 gal/min
5/9/2024 5:33 PM	01:10:00	6.92 pH	21.74 °C	675.07 µS/cm	-0.00 mg/L	8.73 NTU	-5.6 mV	11.60 ft	1.00 gal/min
5/9/2024 5:38 PM	01:15:00	7.00 pH	21.15 °C	680.97 µS/cm	-0.01 mg/L	5.55 NTU	-17.4 mV	11.60 ft	1.00 gal/min
5/9/2024 5:43 PM	01:20:00	7.04 pH	20.75 °C	686.31 µS/cm	-0.01 mg/L	5.81 NTU	-20.9 mV	11.60 ft	1.00 gal/min
5/9/2024 5:48 PM	01:25:00	7.05 pH	21.17 °C	688.43 µS/cm	-0.01 mg/L	4.04 NTU	-10.1 mV	11.60 ft	1.00 gal/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 5/10/2024 2:44:37 PM
Project: Plant Hammond
Operator Name: Jamie Newsome

Location Name: PT-12 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 22 ft Total Depth: 27 ft Initial Depth to Water: 11.55 ft	Pump Type: Monsoon Tubing Type: Polyethylene Pump Intake From TOC: 22 ft Estimated Total Volume Pumped: 262.5 gal Flow Cell Volume: 90 ml Final Flow Rate: 2.5 gal/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
---	---	--

Test Notes:
Well Development, Purge 1

Weather Conditions:
Sunny, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 3 %	+/- 0.2	+/- 10	+/- 10	+/- 0.3	
5/10/2024 2:44 PM	00:00	6.97 pH	19.23 °C	680.65 µS/cm	0.01 mg/L	++++	55.7 mV	11.55 ft	2.50 gal/min
5/10/2024 2:49 PM	05:00	7.00 pH	18.30 °C	700.43 µS/cm	0.01 mg/L	++++	9.2 mV	11.55 ft	2.50 gal/min
5/10/2024 2:54 PM	10:00	7.02 pH	18.30 °C	697.77 µS/cm	-0.00 mg/L	1,696.0 NTU	-7.6 mV	11.55 ft	2.50 gal/min
5/10/2024 2:59 PM	15:00	7.02 pH	18.30 °C	698.80 µS/cm	-0.01 mg/L	1,304.0 NTU	3.8 mV	11.55 ft	2.50 gal/min
5/10/2024 3:04 PM	20:00	7.02 pH	18.25 °C	700.74 µS/cm	-0.01 mg/L	1,375.0 NTU	0.8 mV	11.55 ft	2.50 gal/min
5/10/2024 3:09 PM	25:00	7.03 pH	18.21 °C	698.85 µS/cm	-0.01 mg/L	1,551.0 NTU	1.9 mV	11.55 ft	2.50 gal/min
5/10/2024 3:14 PM	30:00	7.02 pH	18.27 °C	700.11 µS/cm	-0.01 mg/L	1,098.0 NTU	-6.9 mV	11.55 ft	2.50 gal/min
5/10/2024 3:19 PM	35:00	7.02 pH	18.25 °C	700.16 µS/cm	-0.01 mg/L	1,071.0 NTU	-9.6 mV	11.55 ft	2.50 gal/min
5/10/2024 3:24 PM	40:00	7.01 pH	18.31 °C	701.16 µS/cm	-0.01 mg/L	851.00 NTU	-13.5 mV	11.55 ft	2.50 gal/min
5/10/2024 3:29 PM	45:00	7.01 pH	18.31 °C	700.96 µS/cm	-0.01 mg/L	1,070.0 NTU	-15.7 mV	11.55 ft	2.50 gal/min
5/10/2024 3:34 PM	50:00	7.05 pH	18.30 °C	697.20 µS/cm	-0.01 mg/L	895.00 NTU	-15.8 mV	11.55 ft	2.50 gal/min
5/10/2024 3:39 PM	55:00	7.04 pH	18.29 °C	697.30 µS/cm	-0.01 mg/L	52.50 NTU	-7.1 mV	11.60 ft	2.50 gal/min
5/10/2024 3:44 PM	01:00:00	7.03 pH	18.29 °C	698.22 µS/cm	-0.01 mg/L	84.40 NTU	-8.4 mV	11.60 ft	2.50 gal/min

5/10/2024 3:49 PM	01:05:00	7.03 pH	18.27 °C	697.90 µS/cm	-0.01 mg/L	34.00 NTU	-2.5 mV	11.60 ft	2.50 gal/min
5/10/2024 3:54 PM	01:10:00	7.03 pH	18.27 °C	697.29 µS/cm	-0.01 mg/L	23.70 NTU	0.5 mV	11.60 ft	2.50 gal/min
5/10/2024 3:59 PM	01:15:00	7.03 pH	18.25 °C	698.23 µS/cm	-0.01 mg/L	16.40 NTU	1.9 mV	11.60 ft	2.50 gal/min
5/10/2024 4:04 PM	01:20:00	7.02 pH	18.25 °C	698.36 µS/cm	-0.01 mg/L	14.10 NTU	2.1 mV	11.60 ft	2.50 gal/min
5/10/2024 4:09 PM	01:25:00	7.03 pH	18.25 °C	698.99 µS/cm	-0.02 mg/L	15.19 NTU	3.8 mV	11.60 ft	2.50 gal/min
5/10/2024 4:14 PM	01:30:00	7.02 pH	18.25 °C	698.68 µS/cm	-0.01 mg/L	11.65 NTU	2.1 mV	11.60 ft	2.50 gal/min
5/10/2024 4:19 PM	01:35:00	7.02 pH	18.16 °C	699.46 µS/cm	-0.02 mg/L	9.86 NTU	1.0 mV	11.60 ft	2.50 gal/min
5/10/2024 4:24 PM	01:40:00	7.02 pH	18.12 °C	700.57 µS/cm	-0.02 mg/L	6.84 NTU	-1.0 mV	11.60 ft	2.50 gal/min
5/10/2024 4:29 PM	01:45:00	7.02 pH	18.15 °C	700.54 µS/cm	-0.02 mg/L	4.87 NTU	7.8 mV	11.60 ft	2.50 gal/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 5/10/2024 4:43:04 PM
Project: Plant Hammond
Operator Name: Jamie Newsome

Location Name: PT-12 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 22 ft Total Depth: 27 ft Initial Depth to Water: 11.60 ft	Pump Type: Monsoon Tubing Type: Polyethylene Pump Intake From TOC: 22 ft Estimated Total Volume Pumped: 10 liter Flow Cell Volume: 90 ml Final Flow Rate: 250 ml/min Final Draw Down: 0.00 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
---	---	--

Test Notes:
Well Development, Purge 2

Weather Conditions:
Clear, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 3 %	+/- 0.2	+/- 10	+/- 10	+/- 0.3	
5/10/2024 4:43 PM	00:00	7.00 pH	21.08 °C	700.69 µS/cm	0.01 mg/L	11.30 NTU	-4.3 mV	11.60 ft	250.00 ml/min
5/10/2024 4:48 PM	05:00	6.99 pH	21.92 °C	695.09 µS/cm	0.03 mg/L	12.20 NTU	-15.1 mV	11.60 ft	250.00 ml/min
5/10/2024 4:53 PM	10:00	6.98 pH	22.04 °C	692.50 µS/cm	0.03 mg/L	12.89 NTU	-42.4 mV	11.60 ft	250.00 ml/min
5/10/2024 4:58 PM	15:00	6.97 pH	22.03 °C	692.75 µS/cm	0.02 mg/L	12.27 NTU	-22.6 mV	11.60 ft	250.00 ml/min
5/10/2024 5:03 PM	20:00	6.97 pH	22.01 °C	693.64 µS/cm	0.02 mg/L	10.01 NTU	-39.3 mV	11.60 ft	250.00 ml/min
5/10/2024 5:08 PM	25:00	6.97 pH	22.04 °C	693.44 µS/cm	0.03 mg/L	9.80 NTU	-38.6 mV	11.60 ft	250.00 ml/min
5/10/2024 5:13 PM	30:00	6.96 pH	21.86 °C	693.81 µS/cm	0.03 mg/L	7.46 NTU	-37.4 mV	11.60 ft	250.00 ml/min
5/10/2024 5:18 PM	35:00	6.97 pH	21.76 °C	694.36 µS/cm	0.02 mg/L	5.72 NTU	-34.0 mV	11.60 ft	250.00 ml/min
5/10/2024 5:23 PM	40:00	6.97 pH	21.63 °C	694.76 µS/cm	0.03 mg/L	5.72 NTU	-36.7 mV	11.60 ft	250.00 ml/min
5/10/2024 5:28 PM	45:00	6.97 pH	21.64 °C	693.43 µS/cm	0.03 mg/L	4.89 NTU	-35.2 mV	11.60 ft	250.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 5/1/2024 9:42:55 AM
Project: Hammond
Operator Name: Zain W.

Location Name: PT-13 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35 ft Total Depth: 45 ft Initial Depth to Water: 25.37 ft	Pump Type: Monsoon Tubing Type: Polyethylene Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 74 liter Flow Cell Volume: 90 ml Final Flow Rate: 4500 ml/min Final Draw Down: 9.82 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
---	--	--

Test Notes:
Well Development

Weather Conditions:
Clear, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/1/2024 9:42 AM	00:00	6.83 pH	17.92 °C	725.46 µS/cm	0.01 mg/L	1,190.0 NTU	-115.4 mV	25.37 ft	4,500.0 ml/min
5/1/2024 9:47 AM	05:00	6.80 pH	17.98 °C	736.81 µS/cm	0.01 mg/L	1,181.0 NTU	-120.4 mV	30.55 ft	4,500.0 ml/min
5/1/2024 9:52 AM	10:00	6.79 pH	18.00 °C	742.73 µS/cm	-0.00 mg/L	1,124.0 NTU	-137.7 mV	32.47 ft	4,500.0 ml/min
5/1/2024 9:57 AM	15:00	6.77 pH	18.02 °C	741.81 µS/cm	-0.01 mg/L	803.00 NTU	-141.6 mV	33.93 ft	4,500.0 ml/min
5/1/2024 10:02 AM	20:00	6.75 pH	18.05 °C	747.78 µS/cm	-0.01 mg/L	787.00 NTU	-131.6 mV	33.94 ft	4,500.0 ml/min
5/1/2024 10:07 AM	25:00	6.74 pH	18.08 °C	752.23 µS/cm	-0.01 mg/L	1,079.0 NTU	-146.8 mV	33.96 ft	4,500.0 ml/min
5/1/2024 10:12 AM	30:00	6.72 pH	18.07 °C	753.58 µS/cm	-0.01 mg/L	1,095.0 NTU	-141.0 mV	33.57 ft	4,500.0 ml/min
5/1/2024 10:17 AM	35:00	6.71 pH	18.08 °C	755.56 µS/cm	-0.01 mg/L	1,013.0 NTU	-153.0 mV	33.32 ft	4,500.0 ml/min
5/1/2024 10:22 AM	40:00	6.69 pH	18.09 °C	756.22 µS/cm	-0.01 mg/L	760.00 NTU	-153.5 mV	32.94 ft	4,500.0 ml/min
5/1/2024 10:27 AM	45:00	6.68 pH	18.12 °C	758.42 µS/cm	-0.01 mg/L	1,094.0 NTU	-151.3 mV	33.62 ft	4,500.0 ml/min
5/1/2024 10:32 AM	50:00	6.66 pH	18.12 °C	760.08 µS/cm	-0.01 mg/L	485.00 NTU	-150.3 mV	33.31 ft	4,500.0 ml/min
5/1/2024 10:37 AM	55:00	6.65 pH	18.12 °C	759.71 µS/cm	-0.01 mg/L	62.00 NTU	-147.4 mV	33.60 ft	4,500.0 ml/min
5/1/2024 10:42 AM	01:00:00	6.65 pH	18.13 °C	758.25 µS/cm	0.00 mg/L	980.00 NTU	-141.2 mV	34.94 ft	4,500.0 ml/min

5/1/2024 10:47 AM	01:05:00	6.65 pH	18.18 °C	760.02 µS/cm	-0.01 mg/L	378.00 NTU	-148.7 mV	35.17 ft	4,500.0 ml/min
5/1/2024 10:52 AM	01:10:00	6.65 pH	18.16 °C	763.65 µS/cm	0.08 mg/L	--	-124.5 mV	34.94 ft	4,500.0 ml/min
5/1/2024 10:57 AM	01:15:00	6.65 pH	18.18 °C	762.86 µS/cm	0.33 mg/L	57.00 NTU	-116.9 mV	35.75 ft	4,500.0 ml/min
5/1/2024 11:02 AM	01:20:00	6.65 pH	18.20 °C	764.71 µS/cm	0.37 mg/L	59.00 NTU	-107.2 mV	35.75 ft	4,500.0 ml/min
5/1/2024 11:07 AM	01:25:00	6.64 pH	18.19 °C	767.48 µS/cm	0.33 mg/L	88.00 NTU	-101.7 mV	35.75 ft	4,500.0 ml/min
5/1/2024 11:12 AM	01:30:00	6.65 pH	18.23 °C	774.70 µS/cm	0.34 mg/L	--	-99.7 mV	35.75 ft	4,500.0 ml/min
5/1/2024 11:17 AM	01:35:00	6.64 pH	18.25 °C	776.37 µS/cm	0.33 mg/L	--	-83.9 mV	35.75 ft	4,500.0 ml/min
5/1/2024 11:22 AM	01:40:00	6.66 pH	18.28 °C	781.97 µS/cm	0.36 mg/L	87.00 NTU	-84.0 mV	36.44 ft	4,500.0 ml/min
5/1/2024 11:27 AM	01:45:00	6.79 pH	18.24 °C	785.41 µS/cm	0.31 mg/L	29.00 NTU	-98.9 mV	35.31 ft	4,500.0 ml/min
5/1/2024 11:32 AM	01:50:00	6.84 pH	18.25 °C	785.30 µS/cm	0.23 mg/L	--	-89.9 mV	36.44 ft	4,500.0 ml/min
5/1/2024 11:37 AM	01:55:00	6.82 pH	18.22 °C	787.69 µS/cm	0.23 mg/L	12.10 NTU	-100.1 mV	35.35 ft	4,500.0 ml/min
5/1/2024 11:42 AM	02:00:00	6.82 pH	18.29 °C	790.03 µS/cm	0.26 mg/L	31.20 NTU	-86.3 mV	35.42 ft	4,500.0 ml/min
5/1/2024 11:47 AM	02:05:00	6.85 pH	18.30 °C	789.10 µS/cm	0.18 mg/L	--	-98.3 mV	35.42 ft	4,500.0 ml/min
5/1/2024 11:52 AM	02:10:00	6.87 pH	18.30 °C	788.08 µS/cm	0.16 mg/L	17.10 NTU	-99.6 mV	35.47 ft	4,500.0 ml/min
5/1/2024 11:57 AM	02:15:00	6.88 pH	18.31 °C	787.47 µS/cm	0.20 mg/L	11.20 NTU	-99.4 mV	35.53 ft	4,500.0 ml/min
5/1/2024 12:02 PM	02:20:00	6.90 pH	18.33 °C	791.93 µS/cm	0.21 mg/L	6.91 NTU	-98.2 mV	35.34 ft	4,500.0 ml/min
5/1/2024 12:07 PM	02:25:00	6.99 pH	18.38 °C	789.32 µS/cm	0.20 mg/L	8.26 NTU	-102.7 mV	35.05 ft	4,500.0 ml/min
5/1/2024 12:12 PM	02:30:00	7.01 pH	18.36 °C	786.70 µS/cm	0.13 mg/L	8.82 NTU	-104.6 mV	35.00 ft	4,500.0 ml/min
5/1/2024 12:17 PM	02:35:00	7.02 pH	18.37 °C	787.34 µS/cm	0.14 mg/L	5.05 NTU	-105.8 mV	35.12 ft	4,500.0 ml/min
5/1/2024 12:22 PM	02:40:00	7.03 pH	18.34 °C	789.09 µS/cm	0.13 mg/L	5.61 NTU	-93.9 mV	35.18 ft	4,500.0 ml/min
5/1/2024 12:27 PM	02:45:00	7.04 pH	18.38 °C	788.66 µS/cm	0.11 mg/L	4.57 NTU	-106.2 mV	35.19 ft	4,500.0 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 4/30/2024 3:56:54 PM
Project: Hammond
Operator Name: Zain W.

Location Name: PT-14 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 34.65 ft Total Depth: 44.65 ft Initial Depth to Water: 25.00 ft	Pump Type: Monsoon Tubing Type: Polyethylene Pump Intake From TOC: 39.65 ft Estimated Total Volume Pumped: 63 liter Flow Cell Volume: 90 ml Final Flow Rate: 4500 ml/min Final Draw Down: 1.62 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
---	---	--

Test Notes:
Well Development

Weather Conditions:
Clear, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
4/30/2024 3:56 PM	00:00	6.92 pH	21.17 °C	574.44 µS/cm	0.02 mg/L	4,300.0 NTU	-85.9 mV	25.00 ft	4,500.0 ml/min
4/30/2024 4:01 PM	05:00	6.95 pH	21.57 °C	576.88 µS/cm	0.02 mg/L	--	-98.5 mV	26.50 ft	4,500.0 ml/min
4/30/2024 4:06 PM	10:00	6.96 pH	22.48 °C	582.08 µS/cm	0.02 mg/L	--	-119.9 mV	25.00 ft	4,500.0 ml/min
4/30/2024 4:11 PM	15:00	7.11 pH	23.15 °C	2.46 µS/cm	8.42 mg/L	--	-30.4 mV	25.00 ft	4,500.0 ml/min
4/30/2024 4:16 PM	20:00	7.31 pH	24.19 °C	2.37 µS/cm	8.39 mg/L	--	35.9 mV	25.00 ft	4,500.0 ml/min
4/30/2024 4:21 PM	25:00	6.99 pH	19.32 °C	570.89 µS/cm	0.05 mg/L	--	-88.5 mV	25.00 ft	4,500.0 ml/min
4/30/2024 4:26 PM	30:00	7.03 pH	18.88 °C	571.90 µS/cm	0.13 mg/L	-46.00 NTU	-109.7 mV	25.00 ft	4,500.0 ml/min
4/30/2024 4:31 PM	35:00	7.02 pH	18.88 °C	580.18 µS/cm	0.01 mg/L	675.00 NTU	-109.5 mV	26.45 ft	4,500.0 ml/min
4/30/2024 4:36 PM	40:00	7.02 pH	18.83 °C	582.68 µS/cm	0.01 mg/L	1,322.0 NTU	-111.4 mV	26.45 ft	4,500.0 ml/min
4/30/2024 4:41 PM	45:00	7.02 pH	18.77 °C	583.54 µS/cm	0.02 mg/L	683.00 NTU	-116.4 mV	26.46 ft	4,500.0 ml/min
4/30/2024 4:46 PM	50:00	7.00 pH	18.72 °C	585.85 µS/cm	0.01 mg/L	45.40 NTU	-116.8 mV	26.73 ft	4,500.0 ml/min
4/30/2024 4:51 PM	55:00	6.98 pH	18.75 °C	585.99 µS/cm	0.00 mg/L	97.00 NTU	-116.3 mV	26.77 ft	4,500.0 ml/min
4/30/2024 4:56 PM	01:00:00	6.97 pH	18.70 °C	587.95 µS/cm	-0.00 mg/L	25.60 NTU	-116.6 mV	26.77 ft	4,500.0 ml/min

4/30/2024 5:01 PM	01:05:00	6.95 pH	18.70 °C	588.09 µS/cm	0.00 mg/L	12.91 NTU	-115.8 mV	26.77 ft	4,500.0 ml/min
4/30/2024 5:06 PM	01:10:00	6.92 pH	18.70 °C	588.75 µS/cm	-0.01 mg/L	8.26 NTU	-115.2 mV	26.78 ft	4,500.0 ml/min
4/30/2024 5:11 PM	01:15:00	6.90 pH	18.77 °C	585.75 µS/cm	-0.01 mg/L	++++	-109.5 mV	26.78 ft	4,500.0 ml/min
4/30/2024 5:16 PM	01:20:00	6.87 pH	18.79 °C	586.13 µS/cm	-0.01 mg/L	++++	-101.9 mV	26.70 ft	4,500.0 ml/min
4/30/2024 5:21 PM	01:25:00	6.86 pH	18.74 °C	590.52 µS/cm	-0.01 mg/L	++++	-113.6 mV	26.70 ft	4,500.0 ml/min
4/30/2024 5:26 PM	01:30:00	6.85 pH	18.68 °C	590.92 µS/cm	-0.01 mg/L	1,288.0 NTU	-114.1 mV	26.80 ft	4,500.0 ml/min
4/30/2024 5:31 PM	01:35:00	6.83 pH	18.68 °C	591.55 µS/cm	-0.01 mg/L	40.20 NTU	-113.7 mV	26.80 ft	4,500.0 ml/min
4/30/2024 5:36 PM	01:40:00	6.82 pH	18.65 °C	591.95 µS/cm	-0.01 mg/L	13.30 NTU	-113.1 mV	26.82 ft	4,500.0 ml/min
4/30/2024 5:41 PM	01:45:00	6.81 pH	18.70 °C	602.23 µS/cm	-0.01 mg/L	--	-111.9 mV	26.85 ft	4,500.0 ml/min
4/30/2024 5:46 PM	01:50:00	6.83 pH	18.70 °C	591.42 µS/cm	-0.01 mg/L	++++	-115.1 mV	26.52 ft	4,500.0 ml/min
4/30/2024 5:51 PM	01:55:00	6.80 pH	18.64 °C	592.29 µS/cm	-0.02 mg/L	744.00 NTU	-114.1 mV	26.62 ft	4,500.0 ml/min
4/30/2024 5:56 PM	02:00:00	6.77 pH	18.63 °C	593.25 µS/cm	-0.02 mg/L	26.00 NTU	-112.7 mV	26.62 ft	4,500.0 ml/min
4/30/2024 6:01 PM	02:05:00	6.76 pH	18.64 °C	594.08 µS/cm	-0.02 mg/L	--	-111.9 mV	26.62 ft	4,500.0 ml/min
4/30/2024 6:06 PM	02:10:00	6.80 pH	18.68 °C	594.10 µS/cm	-0.02 mg/L	19.40 NTU	-114.2 mV	26.62 ft	4,500.0 ml/min
4/30/2024 6:11 PM	02:15:00	6.78 pH	18.65 °C	594.30 µS/cm	-0.02 mg/L	--	-113.2 mV	26.62 ft	4,500.0 ml/min
4/30/2024 6:16 PM	02:20:00	6.75 pH	18.61 °C	594.75 µS/cm	-0.02 mg/L	3.18 NTU	-111.5 mV	26.62 ft	4,500.0 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 4/30/2024 10:46:40 AM
Project: Plant Hammond
Operator Name: Elisabeth Russell

Location Name: PT-15 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 34.54 ft Total Depth: 44.54 ft Initial Depth to Water: 24.85 ft	Pump Type: Monsoon Tubing Type: Polyethylene Pump Intake From TOC: 42 ft Estimated Total Volume Pumped: 686 liter Flow Cell Volume: 90 ml Final Flow Rate: 7000 ml/min Final Draw Down: 1.25 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883546
---	---	--

Test Notes:
Well Development

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.5	
4/30/2024 10:46 AM	00:00	6.82 pH	24.30 °C	849.91 µS/cm	-0.06 mg/L	7.94 NTU	1.5 mV	25.85 ft	7,000.0 ml/min
4/30/2024 10:50 AM	04:09	6.82 pH	24.10 °C	856.11 µS/cm	-0.07 mg/L	7.94 NTU	0.1 mV	25.85 ft	7,000.0 ml/min
4/30/2024 10:55 AM	08:45	6.83 pH	23.53 °C	864.43 µS/cm	-0.07 mg/L	7.72 NTU	-1.0 mV	26.00 ft	7,000.0 ml/min
4/30/2024 11:00 AM	13:45	7.10 pH	23.10 °C	2.36 µS/cm	2.71 mg/L	7.69 NTU	108.5 mV	26.05 ft	7,000.0 ml/min
4/30/2024 11:05 AM	18:45	7.14 pH	23.23 °C	1.67 µS/cm	3.79 mg/L	--	121.4 mV	--	7,000.0 ml/min
4/30/2024 11:10 AM	23:45	7.24 pH	23.85 °C	1.47 µS/cm	4.75 mg/L	--	126.9 mV	--	7,000.0 ml/min
4/30/2024 11:15 AM	28:45	7.20 pH	24.25 °C	1.54 µS/cm	6.69 mg/L	--	129.8 mV	--	7,000.0 ml/min
4/30/2024 11:20 AM	33:45	7.36 pH	25.34 °C	1.45 µS/cm	7.52 mg/L	--	132.1 mV	--	7,000.0 ml/min
4/30/2024 11:26 AM	39:37	6.90 pH	24.14 °C	872.00 µS/cm	0.64 mg/L	145.00 NTU	35.0 mV	26.20 ft	7,000.0 ml/min
4/30/2024 11:31 AM	44:37	6.84 pH	22.20 °C	898.59 µS/cm	-0.04 mg/L	44.30 NTU	8.7 mV	25.90 ft	7,000.0 ml/min
4/30/2024 11:36 AM	49:37	6.84 pH	22.24 °C	894.88 µS/cm	-0.05 mg/L	13.10 NTU	1.0 mV	25.95 ft	7,000.0 ml/min
4/30/2024 11:41 AM	54:37	6.85 pH	22.15 °C	895.30 µS/cm	-0.06 mg/L	7.84 NTU	-2.8 mV	25.97 ft	7,000.0 ml/min
4/30/2024 11:46 AM	59:37	6.86 pH	22.15 °C	872.50 µS/cm	0.26 mg/L	924.00 NTU	-3.4 mV	25.97 ft	7,000.0 ml/min
4/30/2024 11:48 AM	01:01:47	6.87 pH	22.21 °C	909.50 µS/cm	-0.06 mg/L	920.00 NTU	-7.4 mV	26.00 ft	7,000.0 ml/min
4/30/2024 11:53 AM	01:06:47	6.87 pH	21.75 °C	912.43 µS/cm	-0.06 mg/L	66.80 NTU	-8.5 mV	26.03 ft	7,000.0 ml/min

4/30/2024 11:58 AM	01:11:47	6.88 pH	21.86 °C	911.93 µS/cm	-0.07 mg/L	22.40 NTU	-8.1 mV	26.06 ft	7,000.0 ml/min
4/30/2024 12:03 PM	01:16:47	6.88 pH	21.90 °C	908.80 µS/cm	-0.07 mg/L	108.00 NTU	-8.3 mV	26.08 ft	7,000.0 ml/min
4/30/2024 12:08 PM	01:21:47	6.86 pH	21.72 °C	899.92 µS/cm	-0.07 mg/L	16.00 NTU	-4.4 mV	26.08 ft	7,000.0 ml/min
4/30/2024 12:13 PM	01:26:47	6.86 pH	21.67 °C	900.82 µS/cm	-0.07 mg/L	5.78 NTU	-4.6 mV	26.09 ft	7,000.0 ml/min
4/30/2024 12:18 PM	01:31:47	6.86 pH	21.64 °C	899.12 µS/cm	-0.06 mg/L	72.00 NTU	-2.2 mV	26.10 ft	7,000.0 ml/min
4/30/2024 12:23 PM	01:36:47	6.86 pH	21.53 °C	900.50 µS/cm	-0.07 mg/L	6.61 NTU	-4.7 mV	26.10 ft	7,000.0 ml/min
4/30/2024 12:28 PM	01:41:47	6.86 pH	21.62 °C	898.96 µS/cm	-0.07 mg/L	3.49 NTU	-5.1 mV	26.10 ft	7,000.0 ml/min
4/30/2024 12:31 PM	01:45:16	6.86 pH	21.58 °C	899.92 µS/cm	-0.07 mg/L	3.40 NTU	-5.2 mV	26.10 ft	7,000.0 ml/min

Samples

Sample ID:	Description:
------------	--------------

Site Name: Hammond

Field Instrumentation Calibration Form

Date: 9/30/24Calibrated By: Elizabeth RussellField Conditions: wet

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aquatrail 400	823596
Turbidity Meter	2020We	1511-411

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	29005593	12/24	Air
pH (SU)	4.00	29005593	12/24	Air
pH (SU)	7.00	29004517	12/24	Air
pH (SU)	10.00	29000085	12/24	Air
D.O. (%)	N/A	N/A	N/A	Air
ORP (mV)	228.0	29006903	12/24	Air

Calibration					
Time Start	9:15				
Time Finish	9:45				
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	4.490	28.10	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.0	28.26	± 0.1	GWMP
pH (SU)	7.00	7.0	28.78	± 0.1	GWMP
pH (SU)	10.00	10.0	29.31	± 0.1	GWMP
D.O. (%)	N/A	100%	28.1	$\pm 10\%$	NA
ORP (mV)	228.0	228	28.80	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	$\pm 10\%$ of standard	EPA 2023
	1	1.01		
	10	10.02		

Calibration Check					
Time Start	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

Site Name: Hesperia

Field Instrumentation Calibration Form

Date: 4-30-24Calibrated By: Zuin W.Field Conditions: Rain

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Amprobe 1700400</u>	<u>966105</u>
Turbidity Meter	<u>La Motte</u>	<u>7009-146</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>24605593</u>	<u>12/24</u>	<u>AIR</u>
pH (SU)	4.00	<u>↓</u>	<u>↓</u>	
pH (SU)	7.00	<u>24064617</u>	<u>12/24</u>	
pH (SU)	10.00	<u>78000085</u>	<u>12/24</u>	
D.O. (%)	N/A	<u>-</u>	<u>-</u>	
ORP (mV)	228.0	<u>24006983</u>	<u>12/24</u>	

Calibration					
Time Start	<u>0910</u>	Time Finish	<u>0940</u>		
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>4.490</u>	<u>26.55</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>6.00</u>	<u>23.34</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>23.32</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>23.73</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>26.44</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228.0</u>	<u>23.74</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>10</u>	<u>10</u>		
	<u>10</u>	<u>10</u>		

Calibration Check					
Time Start	<u>---</u>	Time Finish	<u>---</u>		
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>---</u>	<u>---</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>---</u>	<u>---</u>	± 0.1	GWMP
pH (SU)	7.00	<u>---</u>	<u>---</u>	± 0.1	GWMP
pH (SU)	10.00	<u>---</u>	<u>---</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>---</u>	<u>---</u>	$\pm 10\%$ of standard	EPA 2023
	<u>---</u>	<u>---</u>		
	<u>---</u>	<u>---</u>		

Notes:

Site Name: Pland Hammond

Field Instrumentation Calibration Form

Date: 5/1/29Calibrated by: EPField Conditions: 90-20 sunny

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Ametek 700	466702
Turbidity Meter	Ametek 2016	1511-9111

SN: 683546

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (uS/cm)	4.490	24005593	12/24	MR
pH (SU)	4.00	24005593	12/24	MR
pH (SU)	7.00	24004517	12/24	MR
pH (SU)	10.00	24000080	12/24	MR
D.O. (%)	N/A			MR
ORP (mV)	228.0	24006903	12/24	MR

Calibration					
Time Start	830		Time Finish	900	
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (uS/cm)	4.490	4.490	25.68	± 10% of standard	EPA 2023
pH (SU)	4.00	4.0	25.31	± 0.1	GWMP
pH (SU)	7.00	7.0	25.30	± 0.1	GWMP
pH (SU)	10.00	10.0	24.95	± 0.1	GWMP
D.O. (%)	N/A	100.1	23.47	± 10%	NA
ORP (mV)	228.0	228	24.20	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0.15	± 10% of standard	EPA 2023
	1	0.97		
	10	9.17		

Calibration Check					
Time Start			Time Finish		
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (uS/cm)	4.490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			± 10% of standard	EPA 2023

Notes:

Site Name Higdon

Field Instrumentation Calibration Form

Date: 5/1/24Calibrated By: Zan W.Field Conditions: Clear, 60°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>9461 roll 400</u>	<u>946105</u>
Turbidity Meter	<u>1" a Nothe</u>	<u>7009-1416</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	<u>24665593</u>	<u>12/24</u>	<u>ATR</u>
pH (SU)	4.00	<u>↓</u>	<u>↓</u>	<u>↓</u>
pH (SU)	7.00	<u>74004517</u>	<u>7/24</u>	<u>↓</u>
pH (SU)	10.00	<u>74000685</u>	<u>2/24</u>	<u>↓</u>
D.O. (%)	N/A	<u>—</u>	<u>—</u>	<u>↓</u>
ORP (mV)	228.0	<u>74006903</u>	<u>12/24</u>	<u>↓</u>

Calibration					
Time Start <u>0857</u>		Time Finish <u>0911</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4490</u>	<u>20.97</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>21.04</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>21.38</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>21.55</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>21.10</u>	± 10%	NA
ORP (mV)	228.0	<u>228.0</u>	<u>21.37</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		

Calibration Check					
Time Start <u>—</u>		Time Finish <u>—</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>—</u>	<u>—</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	7.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	10.00	<u>—</u>	<u>—</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>—</u>	<u>—</u>	± 10% of standard	EPA 2023
	<u>—</u>	<u>—</u>		
	<u>—</u>	<u>—</u>		

Notes:

Site Name Plant Hammond

Field Instrumentation Calibration Form

Date 5-9-2024

Calibrated By A. Swartz

Field Conditions Thunderstorm, 66°F

Instrument	Manufacturer/Model	Serial Number
Water Quality Meter	<u>Genetec V80</u>	<u>130731</u>
Turbidity Meter	<u>LaMotte 2010T</u>	<u>3009-1916</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4 490	<u>2400491</u>	<u>12/2024</u>	<u>AIR</u>
pH (SU)	4.00	<u>2400493</u>	<u>12/2024</u>	<u>AIR</u>
pH (SU)	7.00	<u>2400497</u>	<u>11/2024</u>	<u>AIR</u>
pH (SU)	10.00	<u>2400496</u>	<u>11/2024</u>	<u>AIR</u>
D.O. (%)	N/A			
ORP (mV)	228.0	<u>2400493</u>		<u>AIR</u>

Calibration					
Time Start <u>1020</u>		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4 490	<u>4490.0</u>	<u>23.34</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>23.54</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>23.52</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>23.57</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>23.04</u>	± 10%	NR
ORP (mV)	228.0	<u>228.0</u>	<u>23.43</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0.00</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>0.70</u>		
	<u>10</u>	<u>10.12</u>		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4 490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			± 10% of standard	EPA 2023

Notes:

Site Name GP Plant Hammond Field Instrumentation Calibration FormDate 5/9/24Calibrated By J. NewsomeField Conditions Storms, Rain

Instrument	Manufacturer/Model	Serial Number
Water Quality Meter	<u>24004811</u>	<u>964105</u>
Turbidity Meter	<u>24004811</u>	<u>1911-4111</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (uS/cm)	4.450	<u>24005593</u>	<u>12/24</u>	<u>AKR</u>
pH (SU)	4.00	<u>24005593</u>	<u>12/24</u>	<u>AKR</u>
pH (SU)	7.00	<u>24004811</u>	<u>12/24</u>	<u>AKR</u>
pH (SU)	10.00	<u>24000085</u>	<u>12/24</u>	<u>AKR</u>
D.O. (%)	N/A	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>
ORP (mV)	228.0	<u>240004903</u>	<u>12/24</u>	<u>AKR</u>

Calibration					
Time Start	<u>0900 1000</u>	Time Finish	<u>1030</u>		
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (uS/cm)	4.450			± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.01</u>	<u>22.98</u>	± 0.1	GWMP
pH (SU)	7.00	<u>6.97</u>	<u>23.45</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>22.98</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>99.7%</u>	<u>20.58</u>	± 10%	NA
ORP (mV)	228.0	<u>229.0</u>	<u>22.42</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>1.01</u>		
	<u>10</u>	<u>9.87</u>		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (uS/cm)	4.450		<u>24</u>	± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>1.01</u>		
	<u>10</u>	<u>9.87</u>		

Notes

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 5-10-2024Calibrated By: A. SzwasfField Conditions: Sunny, 70°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>AquaTrak 800</u>	<u>350751</u>
Turbidity Meter	<u>LaMotte 2021+</u>	<u>7009-1416</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	<u>24015393</u>	<u>12/2024</u>	<u>AIR</u>
pH (SU)	4.00	<u>24005593</u>	<u>12/2024</u>	<u>AIR</u>
pH (SU)	7.00	<u>24005593</u>	<u>11/2024</u>	<u>AIR</u>
pH (SU)	10.00	<u>24004906</u>	<u>11/2024</u>	<u>AIR</u>
D.O. (%)	N/A	—	—	—
ORP (mV)	228.0	<u>24106403</u>	<u>11/2024</u>	<u>AIR</u>

Calibration					
Time Start	<u>7:50</u>	Time Finish	<u>8:05</u>		
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4490.0</u>	<u>23.29</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>23.70</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>23.64</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>23.43</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100.00</u>	<u>21.32</u>	± 10%	NA
ORP (mV)	228.0	<u>228.0</u>	<u>22.09</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0.00</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>0.81</u>		
	<u>10</u>	<u>9.96</u>		

Calibration Check					
Time Start	<u>1445</u>	Time Finish	<u>1455</u>		
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4490.0</u>	<u>30.88</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>30.88</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>30.00</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>29.60</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0.00</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>0.82</u>		
	<u>10</u>	<u>10.04</u>		

Notes:

Site Name: GP Plant Hammond

Field Instrumentation Calibration Form

Date: 5/10/24

Calibrated By: J. Newsome

Field Conditions: Clear, ⁵⁰
cloudy, 10°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Analytroll	9100105
Turbidity Meter	LaMotte 2020MP	1511-4111

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4.490	24005593	12/2024	A112
pH (SU)	4.00	24005593	12/2024	A112
pH (SU)	7.00	24004917	12/2024	A112
pH (SU)	10.00	24000085	12/2024	A112
D.O. (%)	N/A	—	—	—
ORP (mV)	228.0	24006903	12/2024	A112

Calibration					
Time Start	0745		Time Finish	0815	
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490	4425.7	23.25	± 10% of standard	EPA 2023
pH (SU)	4.00	4.05	23.61	± 0.1	GWMP
pH (SU)	7.00	7.05	24.01	± 0.1	GWMP
pH (SU)	10.00	10.02	24.24	± 0.1	GWMP
D.O. (%)	N/A	100.84	22.08	± 10%	NA
ORP (mV)	228.0	229.4	23.98	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	0.44		
	10	9.57		

Calibration Check					
Time Start	1415		Time Finish	1430	
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490	4478.4	24.06	± 10% of standard	EPA 2023
pH (SU)	4.00	4.01	24.07	± 0.1	GWMP
pH (SU)	7.00	7.07	23.92	± 0.1	GWMP
pH (SU)	10.00	9.98	24.51	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0.02	± 10% of standard	EPA 2023
	1	1.24		
	10	9.82		

Notes:

Site Name GP Plant Hammond

Field Instrumentation Calibration Form

Date 5/13/24Calibrated By J NewsomField Director Christy West

Instrument	Manufacturer/Model	Serial Number
Water Quality Meter	<u>Aquatro</u>	<u>944105</u>
Turbidity Meter	<u>LaMotte 2400WT</u>	<u>1511-4311</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu S/cm$)	4.490	<u>24005593</u>	<u>12/2024</u>	<u>A12</u>
pH (SU)	4.00	<u>24005593</u>	<u>12/2024</u>	<u>A12</u>
pH (SU)	7.00	<u>24004517</u>	<u>12/2024</u>	<u>A12</u>
pH (SU)	10.00	<u>24004517</u>	<u>12/2024</u>	<u>A12</u>
D.O. (%)	N/A			
ORP (mV)	228.0	<u>24004517</u>	<u>12/2024</u>	<u>A12</u>

Calibration					
Time Start	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance ($\mu S/cm$)	4.490	<u>44.914</u>	<u>19.05</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.04</u>	<u>19.14</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.04</u>	<u>19.24</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.03</u>	<u>19.35</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>99.95</u>	<u>19.24</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228.5</u>	<u>19.32</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	<u>0.01</u>	$\pm 10\%$ of standard	EPA 2023
	1	<u>1.01</u>		
	10	<u>9.98</u>		

Calibration Check					
Time Start	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance ($\mu S/cm$)	4.490	<u>44.609</u>	<u>20.12</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.03</u>	<u>20.12</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.02</u>	<u>19.63</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.04</u>	<u>20.05</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	1	<u>1.01</u>		
	10	<u>1.0</u>		

Notes:

APPENDIX D

Certified Well Survey Data

Well ID	Casing Northing	Casing Easting	Top of Casing Elevation	Nail or Pad Northing	Nail or Pad Easting	Nail or Pad Elevation	Description
AS-01	1549048.28	1942388.06	577.08	1549048.17	1942388.79	577.46	NAIL ON PAD
AS-02	1549049.08	1942400.03	576.72	1549049.00	1942400.65	577.14	NAIL ON PAD
AS-03	1548670.10	1940933.87	591.60	1548669.94	1940933.21	591.98	NAIL ON PAD
AS-04	1548680.80	1940930.83	591.50	1548680.66	1940930.25	591.97	NAIL ON PAD
INW-03	1549052.75	1942388.28	577.07	1549052.67	1942389.06	577.38	NAIL ON PAD
INW-04	1548671.73	1940929.98	591.58	1548671.52	1940929.36	592.01	NAIL ON PAD
INW-05	1548680.07	1940935.89	591.31	1548679.97	1940935.37	591.81	NAIL ON PAD
PT-11	1549055.61	1942390.89	576.96	1549055.62	1942391.58	577.35	NAIL ON PAD
PT-12	1549045.43	1942391.10	576.84	1549045.32	1942391.85	577.34	NAIL ON PAD
PT-13	1548676.04	1940939.23	591.47	1548675.94	1940938.61	591.88	NAIL ON PAD
PT-14	1548673.63	1940926.52	591.62	1548673.48	1940925.84	592.06	NAIL ON PAD
PT-15	1548668.35	1940937.45	591.37	1548668.21	1940936.90	591.90	NAIL ON PAD
Benchmark	Northing	Easting	Elevation				
BM-H3	1548237.413	1941013.571	574.63				

SURVEY DATA CERTIFICATION FOR SOUTHERN COMPANY TO DETERMINE NORTHING, EASTING, AND VERTICAL ELEVATION OF THE NAIL IN THE CONCRETE PAD & THE PVC WELL CASING. DATE OF FIELD SURVEY & INSPECTION: 06/03/2024. FIELD SURVEY POSITIONAL TOLERANCE=0.5 FEET HORIZONTAL-NAD'83, 0.01 VERTICAL-NAVD '88. EQUIPMENT USED FOR HORIZONTAL LOCATION: TRIMBLE R12 RTK GPS & TRIMBLE S5 ROBOTIC TOTAL STATION. THE VERTICAL LOCATION OF EACH SURVEYED POINT WAS ESTABLISHED BASED UPON LEVEL RUNS WITH A DIGITAL LEVEL LOOP FROM VERTICAL CONTROL ESTABLISHED BY ON-SITE BENCHMARK BM-H3 SET BY GEL SOLUTIONS USING A TRIMBLE DINI LEVEL

David Baker

7/1/2024



COA - LS003119
Exp. 12/31/2024

APPENDIX B

Baseline Analytical Laboratory Results and Field Sampling Forms



May 10, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1
Pace Project No.: 92728841

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on May 03, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Peachtree Corners, GA

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Tyriek Hooks for
Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Anthony Szwast, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1

Pace Project No.: 92728841

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1

Pace Project No.: 92728841

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92728841001	HAM-INW-04	Water	05/02/24 14:18	05/03/24 13:20
92728841002	HAM-INW-05	Water	05/02/24 09:55	05/03/24 13:20
92728841003	HAM-PT-08	Water	05/02/24 12:35	05/03/24 13:20
92728841004	HAM-PT-14	Water	05/02/24 12:06	05/03/24 13:20
92728841005	HAM-PT-15	Water	05/02/24 15:40	05/03/24 13:20
92728841006	HAM-AP1-EB-01	Water	05/02/24 15:20	05/03/24 13:20
92728841007	HAM-AP1-FB-01	Water	05/02/24 15:15	05/03/24 13:20
92728841008	HAM-AP1-FD-01	Water	05/02/24 00:00	05/03/24 13:20

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92728841

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92728841001	HAM-INW-04	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2320B-2011	YEG	3
		SM 2540C-2015	CMW1	1
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92728841002	HAM-INW-05	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2320B-2011	YEG	3
		SM 2540C-2015	CMW1	1
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92728841003	HAM-PT-08	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2320B-2011	YEG	3
		SM 2540C-2015	CMW1	1
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92728841004	HAM-PT-14	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2320B-2011	YEG	3
		SM 2540C-2015	CMW1	1
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92728841005	HAM-PT-15	EPA 6010D	AJM, DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2320B-2011	YEG	3
		SM 2540C-2015	CMW1	1
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92728841006	HAM-AP1-EB-01	EPA 6010D	AJM	6
		EPA 6020B	CW1	13

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92728841

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92728841007	HAM-AP1-FB-01	EPA 7470A	VB	1
		SM 2320B-2011	YEG	3
		SM 2540C-2015	CMW1	1
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2320B-2011	YEG	3
		SM 2540C-2015	CMW1	1
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
92728841008	HAM-AP1-FD-01	EPA 7470A	VB	1
		SM 2320B-2011	YEG	3
		SM 2540C-2015	CMW1	1
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13

PASI-A = Pace Analytical Services - Asheville

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92728841

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92728841001	HAM-INW-04					
EPA 6010D	Iron	10.3	mg/L	0.040	05/06/24 22:08	
EPA 6010D	Manganese	4.2	mg/L	0.040	05/06/24 22:08	
EPA 6010D	Potassium	5.4	mg/L	0.50	05/06/24 22:08	
EPA 6010D	Sodium	6.9	mg/L	1.0	05/06/24 22:08	
EPA 6010D	Calcium	110	mg/L	1.0	05/06/24 22:08	
EPA 6010D	Magnesium	13.5	mg/L	0.050	05/06/24 22:08	
EPA 6020B	Arsenic	0.21	mg/L	0.0050	05/06/24 14:29	
EPA 6020B	Barium	0.042	mg/L	0.0050	05/06/24 14:29	
EPA 6020B	Boron	0.61	mg/L	0.040	05/06/24 14:29	
EPA 6020B	Cobalt	0.029	mg/L	0.0050	05/06/24 14:29	
EPA 6020B	Lithium	0.048	mg/L	0.030	05/06/24 14:29	
EPA 6020B	Molybdenum	0.016	mg/L	0.010	05/06/24 14:29	
EPA 6020B	Selenium	0.0016J	mg/L	0.0050	05/06/24 14:29	B
EPA 6020B	Thallium	0.00048J	mg/L	0.0010	05/06/24 14:29	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	128	mg/L	5.0	05/07/24 16:02	
SM 2320B-2011	Alkalinity, Total as CaCO3	128	mg/L	5.0	05/07/24 16:02	
SM 2540C-2015	Total Dissolved Solids	482	mg/L	25.0	05/07/24 15:51	
EPA 300.0 Rev 2.1 1993	Chloride	8.0	mg/L	1.0	05/07/24 13:54	
EPA 300.0 Rev 2.1 1993	Fluoride	0.47	mg/L	0.10	05/07/24 13:54	M1
EPA 300.0 Rev 2.1 1993	Sulfate	180	mg/L	4.0	05/08/24 00:06	M1
92728841002	HAM-INW-05					
EPA 6010D	Iron	17.3	mg/L	0.040	05/06/24 22:13	M1
EPA 6010D	Manganese	3.6	mg/L	0.040	05/06/24 22:13	
EPA 6010D	Potassium	5.2	mg/L	0.50	05/06/24 22:13	M1
EPA 6010D	Sodium	6.5	mg/L	1.0	05/06/24 22:13	M1
EPA 6010D	Calcium	108	mg/L	1.0	05/06/24 22:13	M1
EPA 6010D	Magnesium	12.6	mg/L	0.050	05/06/24 22:13	M1
EPA 6020B	Antimony	0.00098J	mg/L	0.0030	05/06/24 14:44	
EPA 6020B	Arsenic	0.24	mg/L	0.0050	05/06/24 14:44	
EPA 6020B	Barium	0.032	mg/L	0.0050	05/06/24 14:44	
EPA 6020B	Beryllium	0.000099J	mg/L	0.00050	05/06/24 14:44	
EPA 6020B	Boron	0.54	mg/L	0.040	05/06/24 14:44	
EPA 6020B	Cobalt	0.028	mg/L	0.0050	05/06/24 14:44	
EPA 6020B	Lithium	0.060	mg/L	0.030	05/06/24 14:44	
EPA 6020B	Molybdenum	0.0094J	mg/L	0.010	05/06/24 14:44	
EPA 6020B	Selenium	0.0015J	mg/L	0.0050	05/06/24 14:44	B
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	109	mg/L	5.0	05/07/24 16:12	
SM 2320B-2011	Alkalinity, Total as CaCO3	109	mg/L	5.0	05/07/24 16:12	
SM 2540C-2015	Total Dissolved Solids	526	mg/L	25.0	05/07/24 15:51	
EPA 300.0 Rev 2.1 1993	Chloride	6.0	mg/L	1.0	05/07/24 14:38	
EPA 300.0 Rev 2.1 1993	Fluoride	0.59	mg/L	0.10	05/07/24 14:38	
EPA 300.0 Rev 2.1 1993	Sulfate	206	mg/L	5.0	05/08/24 01:37	
92728841003	HAM-PT-08					
EPA 6010D	Iron	8.5	mg/L	0.040	05/06/24 22:32	
EPA 6010D	Manganese	3.9	mg/L	0.040	05/06/24 22:32	
EPA 6010D	Potassium	5.3	mg/L	0.50	05/06/24 22:32	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92728841

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92728841003	HAM-PT-08					
EPA 6010D	Sodium	7.2	mg/L	1.0	05/06/24 22:32	
EPA 6010D	Calcium	98.2	mg/L	1.0	05/06/24 22:32	
EPA 6010D	Magnesium	12.0	mg/L	0.050	05/06/24 22:32	
EPA 6020B	Arsenic	0.26	mg/L	0.0050	05/06/24 14:48	
EPA 6020B	Barium	0.045	mg/L	0.0050	05/06/24 14:48	
EPA 6020B	Boron	0.83	mg/L	0.040	05/06/24 14:48	
EPA 6020B	Cobalt	0.054	mg/L	0.0050	05/06/24 14:48	
EPA 6020B	Lithium	0.016J	mg/L	0.030	05/06/24 14:48	
EPA 6020B	Molybdenum	0.017	mg/L	0.010	05/06/24 14:48	
EPA 6020B	Selenium	0.0012J	mg/L	0.0050	05/06/24 14:48	B
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO ₃)	108	mg/L	5.0	05/07/24 16:29	
SM 2320B-2011	Alkalinity, Total as CaCO ₃	108	mg/L	5.0	05/07/24 16:29	
SM 2540C-2015	Total Dissolved Solids	477	mg/L	25.0	05/07/24 15:58	
EPA 300.0 Rev 2.1 1993	Chloride	15.4	mg/L	1.0	05/07/24 14:53	
EPA 300.0 Rev 2.1 1993	Fluoride	0.36	mg/L	0.10	05/07/24 14:53	
EPA 300.0 Rev 2.1 1993	Sulfate	176	mg/L	4.0	05/08/24 01:51	
92728841004	HAM-PT-14					
EPA 6010D	Iron	13.7	mg/L	0.040	05/06/24 22:37	
EPA 6010D	Manganese	3.1	mg/L	0.040	05/06/24 22:37	
EPA 6010D	Potassium	5.4	mg/L	0.50	05/06/24 22:37	
EPA 6010D	Sodium	6.7	mg/L	1.0	05/06/24 22:37	
EPA 6010D	Calcium	101	mg/L	1.0	05/06/24 22:37	
EPA 6010D	Magnesium	12.7	mg/L	0.050	05/06/24 22:37	
EPA 6020B	Arsenic	0.22	mg/L	0.0050	05/06/24 14:51	
EPA 6020B	Barium	0.037	mg/L	0.0050	05/06/24 14:51	
EPA 6020B	Boron	0.51	mg/L	0.040	05/06/24 14:51	
EPA 6020B	Cobalt	0.021	mg/L	0.0050	05/06/24 14:51	
EPA 6020B	Lithium	0.055	mg/L	0.030	05/06/24 14:51	
EPA 6020B	Molybdenum	0.011	mg/L	0.010	05/06/24 14:51	
EPA 6020B	Selenium	0.0014J	mg/L	0.0050	05/06/24 14:51	B
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO ₃)	121	mg/L	5.0	05/07/24 16:38	
SM 2320B-2011	Alkalinity, Total as CaCO ₃	121	mg/L	5.0	05/07/24 16:38	
SM 2540C-2015	Total Dissolved Solids	462	mg/L	25.0	05/07/24 15:58	
EPA 300.0 Rev 2.1 1993	Chloride	7.9	mg/L	1.0	05/07/24 15:08	
EPA 300.0 Rev 2.1 1993	Fluoride	0.43	mg/L	0.10	05/07/24 15:08	
EPA 300.0 Rev 2.1 1993	Sulfate	169	mg/L	4.0	05/08/24 02:06	
92728841005	HAM-PT-15					
EPA 6010D	Manganese	5.6	mg/L	0.040	05/07/24 15:31	
EPA 6010D	Iron	9.7	mg/L	0.040	05/06/24 22:41	
EPA 6010D	Potassium	5.2	mg/L	0.50	05/06/24 22:41	
EPA 6010D	Sodium	6.8	mg/L	1.0	05/06/24 22:41	
EPA 6010D	Calcium	141	mg/L	1.0	05/06/24 22:41	
EPA 6010D	Magnesium	15.6	mg/L	0.050	05/06/24 22:41	
EPA 6020B	Arsenic	0.41	mg/L	0.0050	05/06/24 14:55	
EPA 6020B	Barium	0.044	mg/L	0.0050	05/06/24 14:55	
EPA 6020B	Boron	0.75	mg/L	0.040	05/06/24 14:55	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92728841

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92728841005	HAM-PT-15					
EPA 6020B	Cobalt	0.052	mg/L	0.0050	05/06/24 14:55	
EPA 6020B	Lithium	0.051	mg/L	0.030	05/06/24 14:55	
EPA 6020B	Molybdenum	0.017	mg/L	0.010	05/06/24 14:55	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	124	mg/L	5.0	05/07/24 16:47	
SM 2320B-2011	Alkalinity, Total as CaCO3	124	mg/L	5.0	05/07/24 16:47	
SM 2540C-2015	Total Dissolved Solids	638	mg/L	25.0	05/07/24 15:58	
EPA 300.0 Rev 2.1 1993	Chloride	11.8	mg/L	1.0	05/07/24 15:53	
EPA 300.0 Rev 2.1 1993	Fluoride	0.55	mg/L	0.10	05/07/24 15:53	
EPA 300.0 Rev 2.1 1993	Sulfate	278	mg/L	7.0	05/08/24 02:21	
92728841008	HAM-AP1-FD-01					
EPA 6010D	Iron	13.6	mg/L	0.040	05/06/24 23:05	
EPA 6010D	Manganese	3.1	mg/L	0.040	05/06/24 23:05	
EPA 6010D	Potassium	5.4	mg/L	0.50	05/06/24 23:05	
EPA 6010D	Sodium	6.7	mg/L	1.0	05/06/24 23:05	
EPA 6010D	Calcium	99.4	mg/L	1.0	05/06/24 23:05	
EPA 6010D	Magnesium	12.6	mg/L	0.050	05/06/24 23:05	
EPA 6020B	Arsenic	0.20	mg/L	0.0050	05/06/24 15:15	
EPA 6020B	Barium	0.036	mg/L	0.0050	05/06/24 15:15	
EPA 6020B	Boron	0.47	mg/L	0.040	05/06/24 15:15	
EPA 6020B	Cobalt	0.020	mg/L	0.0050	05/06/24 15:15	
EPA 6020B	Lithium	0.052	mg/L	0.030	05/06/24 15:15	
EPA 6020B	Molybdenum	0.010	mg/L	0.010	05/06/24 15:15	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	122	mg/L	5.0	05/07/24 17:38	
SM 2320B-2011	Alkalinity, Total as CaCO3	122	mg/L	5.0	05/07/24 17:38	
SM 2540C-2015	Total Dissolved Solids	442	mg/L	25.0	05/07/24 15:59	
EPA 300.0 Rev 2.1 1993	Chloride	7.9	mg/L	1.0	05/07/24 16:08	
EPA 300.0 Rev 2.1 1993	Fluoride	0.42	mg/L	0.10	05/07/24 16:08	
EPA 300.0 Rev 2.1 1993	Sulfate	167	mg/L	4.0	05/08/24 02:35	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-INW-04		Lab ID: 92728841001		Collected: 05/02/24 14:18		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	10.3	mg/L	0.040	0.025	1	05/04/24 10:00	05/06/24 22:08	7439-89-6	
Manganese	4.2	mg/L	0.040	0.011	1	05/04/24 10:00	05/06/24 22:08	7439-96-5	
Potassium	5.4	mg/L	0.50	0.15	1	05/04/24 10:00	05/06/24 22:08	7440-09-7	
Sodium	6.9	mg/L	1.0	0.58	1	05/04/24 10:00	05/06/24 22:08	7440-23-5	
Calcium	110	mg/L	1.0	0.12	1	05/04/24 10:00	05/06/24 22:08	7440-70-2	
Magnesium	13.5	mg/L	0.050	0.012	1	05/04/24 10:00	05/06/24 22:08	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/04/24 09:50	05/06/24 14:29	7440-36-0	
Arsenic	0.21	mg/L	0.0050	0.00084	1	05/04/24 09:50	05/06/24 14:29	7440-38-2	
Barium	0.042	mg/L	0.0050	0.00047	1	05/04/24 09:50	05/06/24 14:29	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/04/24 09:50	05/06/24 14:29	7440-41-7	
Boron	0.61	mg/L	0.040	0.012	1	05/04/24 09:50	05/06/24 14:29	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/04/24 09:50	05/06/24 14:29	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/04/24 09:50	05/06/24 14:29	7440-47-3	
Cobalt	0.029	mg/L	0.0050	0.00032	1	05/04/24 09:50	05/06/24 14:29	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/04/24 09:50	05/06/24 14:29	7439-92-1	
Lithium	0.048	mg/L	0.030	0.0016	1	05/04/24 09:50	05/06/24 14:29	7439-93-2	
Molybdenum	0.016	mg/L	0.010	0.00062	1	05/04/24 09:50	05/06/24 14:29	7439-98-7	
Selenium	0.0016J	mg/L	0.0050	0.00096	1	05/04/24 09:50	05/06/24 14:29	7782-49-2	B
Thallium	0.00048J	mg/L	0.0010	0.00038	1	05/04/24 09:50	05/06/24 14:29	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/06/24 12:30	05/06/24 16:54	7439-97-6	
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	128	mg/L	5.0	5.0	1		05/07/24 16:02		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/07/24 16:02		
Alkalinity, Total as CaCO3	128	mg/L	5.0	5.0	1		05/07/24 16:02		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	482	mg/L	25.0	25.0	1		05/07/24 15:51		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/09/24 04:42	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	8.0	mg/L	1.0	0.60	1		05/07/24 13:54	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92728841

Sample: HAM-INW-04		Lab ID: 92728841001		Collected: 05/02/24 14:18		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.47	mg/L	0.10	0.050	1		05/07/24 13:54	16984-48-8	M1
Sulfate	180	mg/L	4.0	2.0	4		05/08/24 00:06	14808-79-8	M1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-INW-05 Lab ID: 92728841002 Collected: 05/02/24 09:55 Received: 05/03/24 13:20 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	17.3	mg/L	0.040	0.025	1	05/04/24 10:00	05/06/24 22:13	7439-89-6	M1
Manganese	3.6	mg/L	0.040	0.011	1	05/04/24 10:00	05/06/24 22:13	7439-96-5	
Potassium	5.2	mg/L	0.50	0.15	1	05/04/24 10:00	05/06/24 22:13	7440-09-7	M1
Sodium	6.5	mg/L	1.0	0.58	1	05/04/24 10:00	05/06/24 22:13	7440-23-5	M1
Calcium	108	mg/L	1.0	0.12	1	05/04/24 10:00	05/06/24 22:13	7440-70-2	M1
Magnesium	12.6	mg/L	0.050	0.012	1	05/04/24 10:00	05/06/24 22:13	7439-95-4	M1
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	0.00098J	mg/L	0.0030	0.00054	1	05/04/24 09:50	05/06/24 14:44	7440-36-0	
Arsenic	0.24	mg/L	0.0050	0.00084	1	05/04/24 09:50	05/06/24 14:44	7440-38-2	
Barium	0.032	mg/L	0.0050	0.00047	1	05/04/24 09:50	05/06/24 14:44	7440-39-3	
Beryllium	0.000099J	mg/L	0.00050	0.000094	1	05/04/24 09:50	05/06/24 14:44	7440-41-7	
Boron	0.54	mg/L	0.040	0.012	1	05/04/24 09:50	05/06/24 14:44	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/04/24 09:50	05/06/24 14:44	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/04/24 09:50	05/06/24 14:44	7440-47-3	
Cobalt	0.028	mg/L	0.0050	0.00032	1	05/04/24 09:50	05/06/24 14:44	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/04/24 09:50	05/06/24 14:44	7439-92-1	
Lithium	0.060	mg/L	0.030	0.0016	1	05/04/24 09:50	05/06/24 14:44	7439-93-2	
Molybdenum	0.0094J	mg/L	0.010	0.00062	1	05/04/24 09:50	05/06/24 14:44	7439-98-7	
Selenium	0.0015J	mg/L	0.0050	0.00096	1	05/04/24 09:50	05/06/24 14:44	7782-49-2	B
Thallium	ND	mg/L	0.0010	0.00038	1	05/04/24 09:50	05/06/24 14:44	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/06/24 12:30	05/06/24 16:57	7439-97-6	
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	109	mg/L	5.0	5.0	1		05/07/24 16:12		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/07/24 16:12		
Alkalinity, Total as CaCO ₃	109	mg/L	5.0	5.0	1		05/07/24 16:12		
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	526	mg/L	25.0	25.0	1		05/07/24 15:51		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/09/24 04:42	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	6.0	mg/L	1.0	0.60	1		05/07/24 14:38	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-INW-05		Lab ID: 92728841002		Collected: 05/02/24 09:55		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.59	mg/L	0.10	0.050	1		05/07/24 14:38	16984-48-8	
Sulfate	206	mg/L	5.0	2.5	5		05/08/24 01:37	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-PT-08		Lab ID: 92728841003		Collected: 05/02/24 12:35		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	8.5	mg/L	0.040	0.025	1	05/04/24 10:00	05/06/24 22:32	7439-89-6	
Manganese	3.9	mg/L	0.040	0.011	1	05/04/24 10:00	05/06/24 22:32	7439-96-5	
Potassium	5.3	mg/L	0.50	0.15	1	05/04/24 10:00	05/06/24 22:32	7440-09-7	
Sodium	7.2	mg/L	1.0	0.58	1	05/04/24 10:00	05/06/24 22:32	7440-23-5	
Calcium	98.2	mg/L	1.0	0.12	1	05/04/24 10:00	05/06/24 22:32	7440-70-2	
Magnesium	12.0	mg/L	0.050	0.012	1	05/04/24 10:00	05/06/24 22:32	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/04/24 09:50	05/06/24 14:48	7440-36-0	
Arsenic	0.26	mg/L	0.0050	0.00084	1	05/04/24 09:50	05/06/24 14:48	7440-38-2	
Barium	0.045	mg/L	0.0050	0.00047	1	05/04/24 09:50	05/06/24 14:48	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/04/24 09:50	05/06/24 14:48	7440-41-7	
Boron	0.83	mg/L	0.040	0.012	1	05/04/24 09:50	05/06/24 14:48	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/04/24 09:50	05/06/24 14:48	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/04/24 09:50	05/06/24 14:48	7440-47-3	
Cobalt	0.054	mg/L	0.0050	0.00032	1	05/04/24 09:50	05/06/24 14:48	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/04/24 09:50	05/06/24 14:48	7439-92-1	
Lithium	0.016J	mg/L	0.030	0.0016	1	05/04/24 09:50	05/06/24 14:48	7439-93-2	
Molybdenum	0.017	mg/L	0.010	0.00062	1	05/04/24 09:50	05/06/24 14:48	7439-98-7	
Selenium	0.0012J	mg/L	0.0050	0.00096	1	05/04/24 09:50	05/06/24 14:48	7782-49-2	B
Thallium	ND	mg/L	0.0010	0.00038	1	05/04/24 09:50	05/06/24 14:48	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/06/24 12:30	05/06/24 16:59	7439-97-6	
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	108	mg/L	5.0	5.0	1		05/07/24 16:29		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/07/24 16:29		
Alkalinity, Total as CaCO3	108	mg/L	5.0	5.0	1		05/07/24 16:29		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	477	mg/L	25.0	25.0	1		05/07/24 15:58		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/09/24 04:42	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	15.4	mg/L	1.0	0.60	1		05/07/24 14:53	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-PT-08		Lab ID: 92728841003		Collected: 05/02/24 12:35		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.36	mg/L	0.10	0.050	1		05/07/24 14:53	16984-48-8	
Sulfate	176	mg/L	4.0	2.0	4		05/08/24 01:51	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-PT-14		Lab ID: 92728841004		Collected: 05/02/24 12:06		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	13.7	mg/L	0.040	0.025	1	05/04/24 10:00	05/06/24 22:37	7439-89-6	
Manganese	3.1	mg/L	0.040	0.011	1	05/04/24 10:00	05/06/24 22:37	7439-96-5	
Potassium	5.4	mg/L	0.50	0.15	1	05/04/24 10:00	05/06/24 22:37	7440-09-7	
Sodium	6.7	mg/L	1.0	0.58	1	05/04/24 10:00	05/06/24 22:37	7440-23-5	
Calcium	101	mg/L	1.0	0.12	1	05/04/24 10:00	05/06/24 22:37	7440-70-2	
Magnesium	12.7	mg/L	0.050	0.012	1	05/04/24 10:00	05/06/24 22:37	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/04/24 09:50	05/06/24 14:51	7440-36-0	
Arsenic	0.22	mg/L	0.0050	0.00084	1	05/04/24 09:50	05/06/24 14:51	7440-38-2	
Barium	0.037	mg/L	0.0050	0.00047	1	05/04/24 09:50	05/06/24 14:51	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/04/24 09:50	05/06/24 14:51	7440-41-7	
Boron	0.51	mg/L	0.040	0.012	1	05/04/24 09:50	05/06/24 14:51	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/04/24 09:50	05/06/24 14:51	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/04/24 09:50	05/06/24 14:51	7440-47-3	
Cobalt	0.021	mg/L	0.0050	0.00032	1	05/04/24 09:50	05/06/24 14:51	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/04/24 09:50	05/06/24 14:51	7439-92-1	
Lithium	0.055	mg/L	0.030	0.0016	1	05/04/24 09:50	05/06/24 14:51	7439-93-2	
Molybdenum	0.011	mg/L	0.010	0.00062	1	05/04/24 09:50	05/06/24 14:51	7439-98-7	
Selenium	0.0014J	mg/L	0.0050	0.00096	1	05/04/24 09:50	05/06/24 14:51	7782-49-2	B
Thallium	ND	mg/L	0.0010	0.00038	1	05/04/24 09:50	05/06/24 14:51	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/06/24 12:30	05/06/24 17:15	7439-97-6	
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	121	mg/L	5.0	5.0	1		05/07/24 16:38		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/07/24 16:38		
Alkalinity, Total as CaCO ₃	121	mg/L	5.0	5.0	1		05/07/24 16:38		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	462	mg/L	25.0	25.0	1		05/07/24 15:58		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/09/24 04:43	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	7.9	mg/L	1.0	0.60	1		05/07/24 15:08	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92728841

Sample: HAM-PT-14		Lab ID: 92728841004		Collected: 05/02/24 12:06		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.43	mg/L	0.10	0.050	1		05/07/24 15:08	16984-48-8	
Sulfate	169	mg/L	4.0	2.0	4		05/08/24 02:06	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-PT-15		Lab ID: 92728841005		Collected: 05/02/24 15:40		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Manganese	5.6	mg/L	0.040	0.011	1	05/04/24 10:00	05/07/24 15:31	7439-96-5	
Iron	9.7	mg/L	0.040	0.025	1	05/04/24 10:00	05/06/24 22:41	7439-89-6	
Potassium	5.2	mg/L	0.50	0.15	1	05/04/24 10:00	05/06/24 22:41	7440-09-7	
Sodium	6.8	mg/L	1.0	0.58	1	05/04/24 10:00	05/06/24 22:41	7440-23-5	
Calcium	141	mg/L	1.0	0.12	1	05/04/24 10:00	05/06/24 22:41	7440-70-2	
Magnesium	15.6	mg/L	0.050	0.012	1	05/04/24 10:00	05/06/24 22:41	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/04/24 09:50	05/06/24 14:55	7440-36-0	
Arsenic	0.41	mg/L	0.0050	0.00084	1	05/04/24 09:50	05/06/24 14:55	7440-38-2	
Barium	0.044	mg/L	0.0050	0.00047	1	05/04/24 09:50	05/06/24 14:55	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/04/24 09:50	05/06/24 14:55	7440-41-7	
Boron	0.75	mg/L	0.040	0.012	1	05/04/24 09:50	05/06/24 14:55	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/04/24 09:50	05/06/24 14:55	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/04/24 09:50	05/06/24 14:55	7440-47-3	
Cobalt	0.052	mg/L	0.0050	0.00032	1	05/04/24 09:50	05/06/24 14:55	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/04/24 09:50	05/06/24 14:55	7439-92-1	
Lithium	0.051	mg/L	0.030	0.0016	1	05/04/24 09:50	05/06/24 14:55	7439-93-2	
Molybdenum	0.017	mg/L	0.010	0.00062	1	05/04/24 09:50	05/06/24 14:55	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/04/24 09:50	05/06/24 14:55	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/04/24 09:50	05/06/24 14:55	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/06/24 12:30	05/06/24 17:18	7439-97-6	
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	124	mg/L	5.0	5.0	1		05/07/24 16:47		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/07/24 16:47		
Alkalinity, Total as CaCO3	124	mg/L	5.0	5.0	1		05/07/24 16:47		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	638	mg/L	25.0	25.0	1		05/07/24 15:58		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/09/24 04:43	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	11.8	mg/L	1.0	0.60	1		05/07/24 15:53	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92728841

Sample: HAM-PT-15		Lab ID: 92728841005		Collected: 05/02/24 15:40		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.55	mg/L	0.10	0.050	1		05/07/24 15:53	16984-48-8	
Sulfate	278	mg/L	7.0	3.5	7		05/08/24 02:21	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-AP1-EB-01 Lab ID: 92728841006 Collected: 05/02/24 15:20 Received: 05/03/24 13:20 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	05/04/24 10:00	05/06/24 22:56	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	05/04/24 10:00	05/06/24 22:56	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	05/04/24 10:00	05/06/24 22:56	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	05/04/24 10:00	05/06/24 22:56	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	05/04/24 10:00	05/06/24 22:56	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	05/04/24 10:00	05/06/24 22:56	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/04/24 09:50	05/06/24 15:07	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/04/24 09:50	05/06/24 15:07	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	05/04/24 09:50	05/06/24 15:07	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/04/24 09:50	05/06/24 15:07	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	05/04/24 09:50	05/06/24 15:07	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/04/24 09:50	05/06/24 15:07	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/04/24 09:50	05/06/24 15:07	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	05/04/24 09:50	05/06/24 15:07	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/04/24 09:50	05/06/24 15:07	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/04/24 09:50	05/06/24 15:07	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	05/04/24 09:50	05/06/24 15:07	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/04/24 09:50	05/06/24 15:07	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/04/24 09:50	05/06/24 15:07	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/06/24 12:30	05/06/24 17:20	7439-97-6	
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/07/24 16:57		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/07/24 16:57		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		05/07/24 16:57		
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		05/07/24 15:59		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/09/24 04:43	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		05/07/24 13:24	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92728841

Sample: HAM-AP1-EB-01		Lab ID: 92728841006		Collected: 05/02/24 15:20		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		05/07/24 13:24	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		05/07/24 13:24	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-AP1-FB-01 Lab ID: 92728841007 Collected: 05/02/24 15:15 Received: 05/03/24 13:20 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	05/04/24 10:00	05/06/24 23:01	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	05/04/24 10:00	05/06/24 23:01	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	05/04/24 10:00	05/06/24 23:01	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	05/04/24 10:00	05/06/24 23:01	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	05/04/24 10:00	05/06/24 23:01	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	05/04/24 10:00	05/06/24 23:01	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/04/24 09:50	05/06/24 15:11	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/04/24 09:50	05/06/24 15:11	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	05/04/24 09:50	05/06/24 15:11	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/04/24 09:50	05/06/24 15:11	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	05/04/24 09:50	05/06/24 15:11	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/04/24 09:50	05/06/24 15:11	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/04/24 09:50	05/06/24 15:11	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	05/04/24 09:50	05/06/24 15:11	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/04/24 09:50	05/06/24 15:11	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/04/24 09:50	05/06/24 15:11	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	05/04/24 09:50	05/06/24 15:11	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/04/24 09:50	05/06/24 15:11	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/04/24 09:50	05/06/24 15:11	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/06/24 12:30	05/06/24 17:23	7439-97-6	
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/07/24 17:00		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/07/24 17:00		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		05/07/24 17:00		
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		05/07/24 15:59		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/09/24 04:44	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		05/07/24 13:39	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-AP1-FB-01		Lab ID: 92728841007		Collected: 05/02/24 15:15		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		05/07/24 13:39	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		05/07/24 13:39	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-AP1-FD-01 Lab ID: 92728841008 Collected: 05/02/24 00:00 Received: 05/03/24 13:20 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	13.6	mg/L	0.040	0.025	1	05/04/24 10:00	05/06/24 23:05	7439-89-6	
Manganese	3.1	mg/L	0.040	0.011	1	05/04/24 10:00	05/06/24 23:05	7439-96-5	
Potassium	5.4	mg/L	0.50	0.15	1	05/04/24 10:00	05/06/24 23:05	7440-09-7	
Sodium	6.7	mg/L	1.0	0.58	1	05/04/24 10:00	05/06/24 23:05	7440-23-5	
Calcium	99.4	mg/L	1.0	0.12	1	05/04/24 10:00	05/06/24 23:05	7440-70-2	
Magnesium	12.6	mg/L	0.050	0.012	1	05/04/24 10:00	05/06/24 23:05	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/04/24 09:50	05/06/24 15:15	7440-36-0	
Arsenic	0.20	mg/L	0.0050	0.00084	1	05/04/24 09:50	05/06/24 15:15	7440-38-2	
Barium	0.036	mg/L	0.0050	0.00047	1	05/04/24 09:50	05/06/24 15:15	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/04/24 09:50	05/06/24 15:15	7440-41-7	
Boron	0.47	mg/L	0.040	0.012	1	05/04/24 09:50	05/06/24 15:15	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/04/24 09:50	05/06/24 15:15	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/04/24 09:50	05/06/24 15:15	7440-47-3	
Cobalt	0.020	mg/L	0.0050	0.00032	1	05/04/24 09:50	05/06/24 15:15	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/04/24 09:50	05/06/24 15:15	7439-92-1	
Lithium	0.052	mg/L	0.030	0.0016	1	05/04/24 09:50	05/06/24 15:15	7439-93-2	
Molybdenum	0.010	mg/L	0.010	0.00062	1	05/04/24 09:50	05/06/24 15:15	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/04/24 09:50	05/06/24 15:15	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/04/24 09:50	05/06/24 15:15	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/06/24 12:30	05/06/24 17:26	7439-97-6	
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	122	mg/L	5.0	5.0	1		05/07/24 17:38		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/07/24 17:38		
Alkalinity, Total as CaCO ₃	122	mg/L	5.0	5.0	1		05/07/24 17:38		
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	442	mg/L	25.0	25.0	1		05/07/24 15:59		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/09/24 04:45	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	7.9	mg/L	1.0	0.60	1		05/07/24 16:08	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92728841

Sample: HAM-AP1-FD-01		Lab ID: 92728841008		Collected: 05/02/24 00:00		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.42	mg/L	0.10	0.050	1		05/07/24 16:08	16984-48-8	
Sulfate	167	mg/L	4.0	2.0	4		05/08/24 02:35	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

QC Batch:	852144	Analysis Method:	EPA 6010D
QC Batch Method:	EPA 3010A	Analysis Description:	6010D ATL
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008		

METHOD BLANK:	4398182	Matrix:	Water
Associated Lab Samples:	92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	05/06/24 21:58	
Iron	mg/L	ND	0.040	0.025	05/06/24 21:58	
Magnesium	mg/L	ND	0.050	0.012	05/06/24 21:58	
Manganese	mg/L	ND	0.040	0.011	05/06/24 21:58	
Potassium	mg/L	ND	0.50	0.15	05/06/24 21:58	
Sodium	mg/L	ND	1.0	0.58	05/06/24 21:58	

LABORATORY CONTROL SAMPLE: 4398183

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	1.0	105	80-120	
Iron	mg/L	1	1.0	104	80-120	
Magnesium	mg/L	1	1.0	105	80-120	
Manganese	mg/L	1	1.0	103	80-120	
Potassium	mg/L	1	1.2	115	80-120	
Sodium	mg/L	1	1.1	114	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4398184 4398185

Parameter	Units	92728841002	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		Result										
Calcium	mg/L	108	1	1	118	115	975	695	75-125	2	20	M1
Iron	mg/L	17.3	1	1	19.5	19.1	217	174	75-125	2	20	M1
Magnesium	mg/L	12.6	1	1	14.5	14.2	189	162	75-125	2	20	M1
Manganese	mg/L	3.6	1	1	4.8	4.7	123	111	75-125	2	20	
Potassium	mg/L	5.2	1	1	6.7	6.6	152	138	75-125	2	20	M1
Sodium	mg/L	6.5	1	1	8.1	7.9	154	135	75-125	2	20	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

QC Batch:	852143	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008		

METHOD BLANK: 4398178

Matrix: Water

Associated Lab Samples: 92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00054	05/06/24 14:22	
Arsenic	mg/L	0.0039J	0.0050	0.00084	05/06/24 14:22	
Barium	mg/L	ND	0.0050	0.00047	05/06/24 14:22	
Beryllium	mg/L	ND	0.00050	0.000094	05/06/24 14:22	
Boron	mg/L	ND	0.040	0.012	05/06/24 14:22	
Cadmium	mg/L	ND	0.00050	0.00010	05/06/24 14:22	
Chromium	mg/L	ND	0.0050	0.0019	05/06/24 14:22	
Cobalt	mg/L	ND	0.0050	0.00032	05/06/24 14:22	
Lead	mg/L	ND	0.0010	0.00016	05/06/24 14:22	
Lithium	mg/L	ND	0.030	0.0016	05/06/24 14:22	
Molybdenum	mg/L	ND	0.010	0.00062	05/06/24 14:22	
Selenium	mg/L	0.0021J	0.0050	0.00096	05/06/24 14:22	
Thallium	mg/L	ND	0.0010	0.00038	05/06/24 14:22	

LABORATORY CONTROL SAMPLE: 4398179

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.097	97	80-120	
Arsenic	mg/L	0.1	0.10	102	80-120	
Barium	mg/L	0.1	0.093	93	80-120	
Beryllium	mg/L	0.1	0.099	99	80-120	
Boron	mg/L	1	1.0	100	80-120	
Cadmium	mg/L	0.1	0.094	94	80-120	
Chromium	mg/L	0.1	0.096	96	80-120	
Cobalt	mg/L	0.1	0.093	93	80-120	
Lead	mg/L	0.1	0.098	98	80-120	
Lithium	mg/L	0.1	0.10	102	80-120	
Molybdenum	mg/L	0.1	0.095	95	80-120	
Selenium	mg/L	0.1	0.10	101	80-120	
Thallium	mg/L	0.1	0.097	97	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4398180 4398181

Parameter	Units	92728841001	MS	MSD	MS	MSD	MS	MSD	% Rec	RPD	Max	Qual
		Result	Spike Conc.	Spike Conc.								
Antimony	mg/L	ND	0.1	0.1	0.10	0.10	102	101	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4398180 4398181											
Parameter	Units	92728841001		MS		MSD		MS		MSD	
		Result	Conc.	Spike	Conc.	Result	Conc.	% Rec	% Rec	Limits	Max
Arsenic	mg/L	0.21	0.1	0.1	0.1	0.31	0.32	93	104	75-125	3 20
Barium	mg/L	0.042	0.1	0.1	0.1	0.14	0.13	94	92	75-125	1 20
Beryllium	mg/L	ND	0.1	0.1	0.1	0.093	0.093	93	93	75-125	0 20
Boron	mg/L	0.61	1	1	1	1.6	1.6	95	100	75-125	3 20
Cadmium	mg/L	ND	0.1	0.1	0.1	0.094	0.095	94	95	75-125	1 20
Chromium	mg/L	ND	0.1	0.1	0.1	0.092	0.094	92	94	75-125	2 20
Cobalt	mg/L	0.029	0.1	0.1	0.1	0.12	0.12	90	91	75-125	1 20
Lead	mg/L	ND	0.1	0.1	0.1	0.097	0.10	97	100	75-125	2 20
Lithium	mg/L	0.048	0.1	0.1	0.1	0.14	0.14	97	96	75-125	0 20
Molybdenum	mg/L	0.016	0.1	0.1	0.1	0.11	0.11	98	97	75-125	1 20
Selenium	mg/L	0.0016J	0.1	0.1	0.1	0.10	0.10	99	102	75-125	3 20
Thallium	mg/L	0.00048J	0.1	0.1	0.1	0.098	0.098	97	98	75-125	1 20

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

QC Batch:	852339	Analysis Method:	EPA 7470A
QC Batch Method:	EPA 7470A	Analysis Description:	7470 Mercury
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008		

METHOD BLANK:	4398727	Matrix:	Water
Associated Lab Samples:	92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	05/06/24 16:49	

LABORATORY CONTROL SAMPLE:	4398728					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0025	101	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:	4398729			4398730								
Parameter	Units	92728841003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.0025	0.0025	0.0024	0.0024	97	97	75-125	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

QC Batch: 852662

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007

METHOD BLANK: 4400154

Matrix: Water

Associated Lab Samples: 92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	05/07/24 14:10	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/07/24 14:10	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/07/24 14:10	

LABORATORY CONTROL SAMPLE: 4400155

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.8	104	80-120	

LABORATORY CONTROL SAMPLE: 4400156

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.3	105	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4400157 4400158

Parameter	Units	92727753001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	7.4	50	50	58.7	58.5	103	102	80-120	0	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4400159 4400160

Parameter	Units	92727753002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	ND	50	50	52.8	52.6	103	103	80-120	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

QC Batch: 852668

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92728841008

METHOD BLANK: 4400185

Matrix: Water

Associated Lab Samples: 92728841008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	05/07/24 17:22	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/07/24 17:22	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/07/24 17:22	

LABORATORY CONTROL SAMPLE: 4400186

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	50.4	101	80-120	

LABORATORY CONTROL SAMPLE: 4400187

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.3	103	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4400188 4400189

Parameter	Units	92727828002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	270	50	50	318	305	96	71	80-120	4	25	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4400190 4400191

Parameter	Units	92727828003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	284	50	50	335	326	103	84	80-120	3	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

QC Batch: 852725

Analysis Method: SM 2540C-2015

QC Batch Method: SM 2540C-2015

Analysis Description: 2540C Total Dissolved Solids

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92728841001, 92728841002

METHOD BLANK: 4400519

Matrix: Water

Associated Lab Samples: 92728841001, 92728841002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	05/07/24 15:47	

LABORATORY CONTROL SAMPLE: 4400520

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	250	254	102	90-110	

SAMPLE DUPLICATE: 4400521

Parameter	Units	92728666001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	84.0	89.0	6	25	

SAMPLE DUPLICATE: 4400522

Parameter	Units	92728671010 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	109	107	2	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

QC Batch:	852726	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Asheville

Associated Lab Samples: 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008

METHOD BLANK: 4400526 Matrix: Water

Associated Lab Samples: 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	05/07/24 15:58	

LABORATORY CONTROL SAMPLE: 4400527

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	250	256	102	90-110	

SAMPLE DUPLICATE: 4400528

Parameter	Units	92728841003 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	477	460	4	25	

SAMPLE DUPLICATE: 4400529

Parameter	Units	92728786001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	1370	1360	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

QC Batch: 853221

Analysis Method: SM 4500-S2D-2011

QC Batch Method: SM 4500-S2D-2011

Analysis Description: 4500S2D Sulfide Water

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008

METHOD BLANK: 4403056

Matrix: Water

Associated Lab Samples: 92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	05/09/24 04:40	

LABORATORY CONTROL SAMPLE: 4403057

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.54	109	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4403058 4403059

Parameter	Units	92728841007 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.55	0.56	109	113	80-120	3	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4403060 4403061

Parameter	Units	92728860002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.46	0.52	92	104	80-120	12	10 R1	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

QC Batch:	852564	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008		

METHOD BLANK:	4399708	Matrix:	Water
Associated Lab Samples:	92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	05/07/24 12:54	
Fluoride	mg/L	ND	0.10	0.050	05/07/24 12:54	
Sulfate	mg/L	ND	1.0	0.50	05/07/24 12:54	

LABORATORY CONTROL SAMPLE: 4399709						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	48.7	97	90-110	
Fluoride	mg/L	2.5	2.5	101	90-110	
Sulfate	mg/L	50	47.6	95	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4399710 4399711												
Parameter	Units	92728841001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	8.0	50	50	58.4	58.9	101	102	90-110	1	10	
Fluoride	mg/L	0.47	2.5	2.5	4.1	4.1	146	145	90-110	0	10	M1
Sulfate	mg/L	180	50	50	231	223	101	86	90-110	3	10	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4399712 4399713												
Parameter	Units	92728877001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	1.5	50	50	58.2	53.1	113	103	90-110	9	10	M1
Fluoride	mg/L	0.47	2.5	2.5	4.1	3.7	145	129	90-110	10	10	M1
Sulfate	mg/L	37.7	50	50	84.1	86.7	93	98	90-110	3	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1
Pace Project No.: 92728841

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

B Analyte was detected in the associated method blank.
M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.
R1 RPD value was outside control limits.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92728841

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92728841001	HAM-INW-04	EPA 3010A	852144	EPA 6010D	852161
92728841002	HAM-INW-05	EPA 3010A	852144	EPA 6010D	852161
92728841003	HAM-PT-08	EPA 3010A	852144	EPA 6010D	852161
92728841004	HAM-PT-14	EPA 3010A	852144	EPA 6010D	852161
92728841005	HAM-PT-15	EPA 3010A	852144	EPA 6010D	852161
92728841006	HAM-AP1-EB-01	EPA 3010A	852144	EPA 6010D	852161
92728841007	HAM-AP1-FB-01	EPA 3010A	852144	EPA 6010D	852161
92728841008	HAM-AP1-FD-01	EPA 3010A	852144	EPA 6010D	852161
92728841001	HAM-INW-04	EPA 3005A	852143	EPA 6020B	852177
92728841002	HAM-INW-05	EPA 3005A	852143	EPA 6020B	852177
92728841003	HAM-PT-08	EPA 3005A	852143	EPA 6020B	852177
92728841004	HAM-PT-14	EPA 3005A	852143	EPA 6020B	852177
92728841005	HAM-PT-15	EPA 3005A	852143	EPA 6020B	852177
92728841006	HAM-AP1-EB-01	EPA 3005A	852143	EPA 6020B	852177
92728841007	HAM-AP1-FB-01	EPA 3005A	852143	EPA 6020B	852177
92728841008	HAM-AP1-FD-01	EPA 3005A	852143	EPA 6020B	852177
92728841001	HAM-INW-04	EPA 7470A	852339	EPA 7470A	852477
92728841002	HAM-INW-05	EPA 7470A	852339	EPA 7470A	852477
92728841003	HAM-PT-08	EPA 7470A	852339	EPA 7470A	852477
92728841004	HAM-PT-14	EPA 7470A	852339	EPA 7470A	852477
92728841005	HAM-PT-15	EPA 7470A	852339	EPA 7470A	852477
92728841006	HAM-AP1-EB-01	EPA 7470A	852339	EPA 7470A	852477
92728841007	HAM-AP1-FB-01	EPA 7470A	852339	EPA 7470A	852477
92728841008	HAM-AP1-FD-01	EPA 7470A	852339	EPA 7470A	852477
92728841001	HAM-INW-04	SM 2320B-2011	852662		
92728841002	HAM-INW-05	SM 2320B-2011	852662		
92728841003	HAM-PT-08	SM 2320B-2011	852662		
92728841004	HAM-PT-14	SM 2320B-2011	852662		
92728841005	HAM-PT-15	SM 2320B-2011	852662		
92728841006	HAM-AP1-EB-01	SM 2320B-2011	852662		
92728841007	HAM-AP1-FB-01	SM 2320B-2011	852662		
92728841008	HAM-AP1-FD-01	SM 2320B-2011	852668		
92728841001	HAM-INW-04	SM 2540C-2015	852725		
92728841002	HAM-INW-05	SM 2540C-2015	852725		
92728841003	HAM-PT-08	SM 2540C-2015	852726		
92728841004	HAM-PT-14	SM 2540C-2015	852726		
92728841005	HAM-PT-15	SM 2540C-2015	852726		
92728841006	HAM-AP1-EB-01	SM 2540C-2015	852726		
92728841007	HAM-AP1-FB-01	SM 2540C-2015	852726		
92728841008	HAM-AP1-FD-01	SM 2540C-2015	852726		
92728841001	HAM-INW-04	SM 4500-S2D-2011	853221		
92728841002	HAM-INW-05	SM 4500-S2D-2011	853221		
92728841003	HAM-PT-08	SM 4500-S2D-2011	853221		
92728841004	HAM-PT-14	SM 4500-S2D-2011	853221		
92728841005	HAM-PT-15	SM 4500-S2D-2011	853221		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92728841

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92728841006	HAM-AP1-EB-01	SM 4500-S2D-2011	853221		
92728841007	HAM-AP1-FB-01	SM 4500-S2D-2011	853221		
92728841008	HAM-AP1-FD-01	SM 4500-S2D-2011	853221		
92728841001	HAM-INW-04	EPA 300.0 Rev 2.1 1993	852564		
92728841002	HAM-INW-05	EPA 300.0 Rev 2.1 1993	852564		
92728841003	HAM-PT-08	EPA 300.0 Rev 2.1 1993	852564		
92728841004	HAM-PT-14	EPA 300.0 Rev 2.1 1993	852564		
92728841005	HAM-PT-15	EPA 300.0 Rev 2.1 1993	852564		
92728841006	HAM-AP1-EB-01	EPA 300.0 Rev 2.1 1993	852564		
92728841007	HAM-AP1-FB-01	EPA 300.0 Rev 2.1 1993	852564		
92728841008	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	852564		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



DC# Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

Project

WO#: 92728841

Courier:

☐ Commercial☐ Fed Ex☐ UPS☐ USPS☐ Other:☐ Client

Custody Seal Present?

☒ Yes☐ No

Seals Intact?

☒ Yes☐ No☐ N/A

Date/Initials Person Examining Contents:

Packing Material:

☒ Bubble Wrap☐ Bubble Bags☐ None☐ Other:

Thermometer:

☒ IR Gun (°C)

Type of Ice:

☒ Wet☐ Dry☐ None

Cooler Temp:

2.3

Correction Factor:

Add/Subtract (°C)

0.0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

2.3

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, HI, or SC (check maps)? ☐ Yes ☒ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☒ No

Comments/Discrepancy:

Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.
Samples Arrived within Hold Time?	☐ Yes ☐ No ☐ N/A	2.
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4.
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A	7.
Containers Intact?	☒ Yes ☐ No ☐ N/A	8.
Dissolved analysis: Samples Field Filtered?	☐ Yes ☐ No ☒ N/A	9.
Sample Labels Match COC?	☐ Yes ☒ No ☐ N/A	10.
-Includes Date/Time/ID/Analysis Matrix:		11.
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☒ No ☐ N/A	
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A	

Field Data Required? ☐ Yes ☒ No

COMMENTS/SAMPLE DISCREPANCY

Client name and 2 sample IDs sent still present on
 sent Home. Also HARM-AP-ED-02 is still present
 So 2 HARM-AP-ED-02 is

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

* Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRD/MS (water) DGC, L/Hg

** Bottom half of box is to list number of bottles

*** Check all unpreserved Nitrates for chlorine

Project #

W0#: 92728841

PM: BV

Due Date: 05/10/24

CLIENT: 92- GP-HAM

Sample	1	2	3	4	5	6	7	8	9	10	11	12
BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)												
BP1U-250 mL Plastic Unpreserved (N/A)												
BP2U-500 mL Plastic Unpreserved (N/A)												
BP1U-1 liter Plastic Unpreserved (N/A)												
BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)												
BP3H-250 mL plastic HNO3 (pH < 2)												
BP4S-125 mL Plastic Zn Acetate & NaOH (w/)												
BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)												
WSPU-Wide-mouthed Glass Jar Unpreserved												
AG1U-1 liter Amber Unpreserved (N/A) (Cl-)												
AG2U-1 liter Amber HCl (pH < 2)												
AG3U-250 mL Amber Unpreserved (N/A) (Cl-)												
AG1S-1 liter Amber H2SO4 (pH < 2)												
AG3S-250 mL Amber H2SO4 (pH < 2)												
DO94-40 mL Amber RH4D (N/A) (Cl-)												
DO9H-40 mL VOA HCl (N/A)												
VGST-40 mL VOA Na2S2O8 (N/A)												
VO9U-40 mL VOA Unpreserved (N/A)												
DO9V-40 mL VOA H3PO4 (N/A)												
NP7U-30 mL Plastic Unpreserved (N/A)												
V/GK (3 vials per kit) VPH/Gas kit (N/A)												
SPST-125 mL Sterile Plastic (N/A - lab)												
SP2T-250 mL Sterile Plastic (N/A - lab)												
BP3R-250 mL Plastic (N/A) H2SO4 (pH < 2)												
AGCU-100 mL Amber Unpreserved (N/A) (Cl-)												
VSGU-22 mL Scintillation vials (N/2)												
DO9U-40 mL Amber Unpreserved vials (N/A)												

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DNR Certification Division for review and resolution. (If possible, include a copy of the original sample analysis.)

Worksheet ID: 69614

Page 2 of 2

100

15 Feb 2007



May 20, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1
Pace Project No.: 92730250

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on May 10, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Peachtree Corners, GA

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Anthony Szwast, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1

Pace Project No.: 92730250

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1

Pace Project No.: 92730250

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92730250001	HAM-PT-07	Water	05/09/24 14:58	05/10/24 13:40
92730250002	HAM-PT-13	Water	05/09/24 16:45	05/10/24 13:40

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92730250

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92730250001	HAM-PT-07	EPA 6010D	DRB	6
		EPA 6020B	MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92730250002	HAM-PT-13	EPA 6010D	DRB	6
		EPA 6020B	MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3

PASI-A = Pace Analytical Services - Asheville

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92730250

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92730250001	HAM-PT-07					
EPA 6010D	Sodium	6.8	mg/L	1.0	05/15/24 22:05	
EPA 6010D	Iron	16.9	mg/L	0.040	05/14/24 17:10	
EPA 6010D	Manganese	3.2	mg/L	0.040	05/14/24 17:10	
EPA 6010D	Potassium	5.6	mg/L	0.50	05/14/24 17:10	
EPA 6010D	Calcium	98.0	mg/L	1.0	05/14/24 17:10	
EPA 6010D	Magnesium	12.5	mg/L	0.050	05/14/24 17:10	
EPA 6020B	Antimony	0.00059J	mg/L	0.0030	05/15/24 14:25	
EPA 6020B	Arsenic	0.30	mg/L	0.0050	05/15/24 14:25	
EPA 6020B	Barium	0.037	mg/L	0.0050	05/15/24 14:25	
EPA 6020B	Beryllium	0.00010J	mg/L	0.00050	05/15/24 14:25	
EPA 6020B	Boron	0.55	mg/L	0.040	05/15/24 14:25	
EPA 6020B	Cobalt	0.041	mg/L	0.0050	05/15/24 14:25	
EPA 6020B	Lithium	0.064	mg/L	0.030	05/15/24 14:25	
EPA 6020B	Molybdenum	0.010	mg/L	0.010	05/15/24 14:25	
SM 2540C-2015	Total Dissolved Solids	463	mg/L	25.0	05/14/24 12:37	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	117	mg/L	5.0	05/17/24 19:33	
SM 2320B-2011	Alkalinity, Total as CaCO3	117	mg/L	5.0	05/17/24 19:33	
EPA 300.0 Rev 2.1 1993	Chloride	9.2	mg/L	1.0	05/14/24 00:00	
EPA 300.0 Rev 2.1 1993	Fluoride	0.33	mg/L	0.10	05/14/24 00:00	
EPA 300.0 Rev 2.1 1993	Sulfate	177	mg/L	4.0	05/14/24 03:34	
92730250002	HAM-PT-13					
EPA 6010D	Iron	15.5	mg/L	0.040	05/14/24 17:13	
EPA 6010D	Manganese	3.5	mg/L	0.040	05/14/24 17:13	
EPA 6010D	Potassium	5.0	mg/L	0.50	05/14/24 17:13	
EPA 6010D	Calcium	94.4	mg/L	1.0	05/14/24 17:13	
EPA 6010D	Magnesium	11.4	mg/L	0.050	05/14/24 17:13	
EPA 6010D	Sodium	6.9	mg/L	1.0	05/15/24 22:10	
EPA 6020B	Arsenic	0.30	mg/L	0.0050	05/15/24 14:29	
EPA 6020B	Barium	0.036	mg/L	0.0050	05/15/24 14:29	
EPA 6020B	Boron	0.54	mg/L	0.040	05/15/24 14:29	
EPA 6020B	Cobalt	0.026	mg/L	0.0050	05/15/24 14:29	
EPA 6020B	Lithium	0.061	mg/L	0.030	05/15/24 14:29	
EPA 6020B	Molybdenum	0.0095J	mg/L	0.010	05/15/24 14:29	
SM 2540C-2015	Total Dissolved Solids	472	mg/L	25.0	05/14/24 12:37	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	106	mg/L	5.0	05/17/24 19:42	
SM 2320B-2011	Alkalinity, Total as CaCO3	106	mg/L	5.0	05/17/24 19:42	
EPA 300.0 Rev 2.1 1993	Chloride	9.0	mg/L	1.0	05/14/24 00:14	
EPA 300.0 Rev 2.1 1993	Fluoride	0.35	mg/L	0.10	05/14/24 00:14	
EPA 300.0 Rev 2.1 1993	Sulfate	195	mg/L	4.0	05/14/24 03:48	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92730250

Sample: HAM-PT-07		Lab ID: 92730250001		Collected: 05/09/24 14:58		Received: 05/10/24 13:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Sodium	6.8	mg/L	1.0	0.58	1	05/10/24 17:49	05/15/24 22:05	7440-23-5	
Iron	16.9	mg/L	0.040	0.025	1	05/10/24 17:49	05/14/24 17:10	7439-89-6	
Manganese	3.2	mg/L	0.040	0.011	1	05/10/24 17:49	05/14/24 17:10	7439-96-5	
Potassium	5.6	mg/L	0.50	0.15	1	05/10/24 17:49	05/14/24 17:10	7440-09-7	
Calcium	98.0	mg/L	1.0	0.12	1	05/10/24 17:49	05/14/24 17:10	7440-70-2	
Magnesium	12.5	mg/L	0.050	0.012	1	05/10/24 17:49	05/14/24 17:10	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	0.00059J	mg/L	0.0030	0.00054	1	05/11/24 13:00	05/15/24 14:25	7440-36-0	
Arsenic	0.30	mg/L	0.0050	0.00084	1	05/11/24 13:00	05/15/24 14:25	7440-38-2	
Barium	0.037	mg/L	0.0050	0.00047	1	05/11/24 13:00	05/15/24 14:25	7440-39-3	
Beryllium	0.00010J	mg/L	0.00050	0.000094	1	05/11/24 13:00	05/15/24 14:25	7440-41-7	
Boron	0.55	mg/L	0.040	0.012	1	05/11/24 13:00	05/15/24 14:25	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/11/24 13:00	05/15/24 14:25	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/11/24 13:00	05/15/24 14:25	7440-47-3	
Cobalt	0.041	mg/L	0.0050	0.00032	1	05/11/24 13:00	05/15/24 14:25	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/11/24 13:00	05/15/24 14:25	7439-92-1	
Lithium	0.064	mg/L	0.030	0.0016	1	05/11/24 13:00	05/15/24 14:25	7439-93-2	
Molybdenum	0.010	mg/L	0.010	0.00062	1	05/11/24 13:00	05/15/24 14:25	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/11/24 13:00	05/15/24 14:25	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/11/24 13:00	05/15/24 14:25	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/16/24 17:00	05/17/24 09:15	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	463	mg/L	25.0	25.0	1		05/14/24 12:37		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	117	mg/L	5.0	5.0	1		05/17/24 19:33		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/17/24 19:33		
Alkalinity, Total as CaCO3	117	mg/L	5.0	5.0	1		05/17/24 19:33		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/11/24 02:08	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	9.2	mg/L	1.0	0.60	1		05/14/24 00:00	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92730250

Sample: HAM-PT-07		Lab ID: 92730250001		Collected: 05/09/24 14:58		Received: 05/10/24 13:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.33	mg/L	0.10	0.050	1		05/14/24 00:00	16984-48-8	
Sulfate	177	mg/L	4.0	2.0	4		05/14/24 03:34	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92730250

Sample: HAM-PT-13		Lab ID: 92730250002		Collected: 05/09/24 16:45		Received: 05/10/24 13:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	15.5	mg/L	0.040	0.025	1	05/10/24 17:49	05/14/24 17:13	7439-89-6	
Manganese	3.5	mg/L	0.040	0.011	1	05/10/24 17:49	05/14/24 17:13	7439-96-5	
Potassium	5.0	mg/L	0.50	0.15	1	05/10/24 17:49	05/14/24 17:13	7440-09-7	
Calcium	94.4	mg/L	1.0	0.12	1	05/10/24 17:49	05/14/24 17:13	7440-70-2	
Magnesium	11.4	mg/L	0.050	0.012	1	05/10/24 17:49	05/14/24 17:13	7439-95-4	
Sodium	6.9	mg/L	1.0	0.58	1	05/10/24 17:49	05/15/24 22:10	7440-23-5	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/11/24 13:00	05/15/24 14:29	7440-36-0	
Arsenic	0.30	mg/L	0.0050	0.00084	1	05/11/24 13:00	05/15/24 14:29	7440-38-2	
Barium	0.036	mg/L	0.0050	0.00047	1	05/11/24 13:00	05/15/24 14:29	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/11/24 13:00	05/15/24 14:29	7440-41-7	
Boron	0.54	mg/L	0.040	0.012	1	05/11/24 13:00	05/15/24 14:29	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/11/24 13:00	05/15/24 14:29	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/11/24 13:00	05/15/24 14:29	7440-47-3	
Cobalt	0.026	mg/L	0.0050	0.00032	1	05/11/24 13:00	05/15/24 14:29	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/11/24 13:00	05/15/24 14:29	7439-92-1	
Lithium	0.061	mg/L	0.030	0.0016	1	05/11/24 13:00	05/15/24 14:29	7439-93-2	
Molybdenum	0.0095J	mg/L	0.010	0.00062	1	05/11/24 13:00	05/15/24 14:29	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/11/24 13:00	05/15/24 14:29	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/11/24 13:00	05/15/24 14:29	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/16/24 17:00	05/17/24 09:17	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	472	mg/L	25.0	25.0	1		05/14/24 12:37		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	106	mg/L	5.0	5.0	1		05/17/24 19:42		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/17/24 19:42		
Alkalinity, Total as CaCO ₃	106	mg/L	5.0	5.0	1		05/17/24 19:42		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/11/24 02:10	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	9.0	mg/L	1.0	0.60	1		05/14/24 00:14	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92730250

Sample: HAM-PT-13		Lab ID: 92730250002		Collected: 05/09/24 16:45		Received: 05/10/24 13:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.35	mg/L	0.10	0.050	1		05/14/24 00:14	16984-48-8	
Sulfate	195	mg/L	4.0	2.0	4		05/14/24 03:48	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92730250

QC Batch: 853813

Analysis Method: EPA 6010D

QC Batch Method: EPA 3010A

Analysis Description: 6010D ATL

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92730250001, 92730250002

METHOD BLANK: 4406154

Matrix: Water

Associated Lab Samples: 92730250001, 92730250002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	05/14/24 14:43	
Iron	mg/L	ND	0.040	0.025	05/14/24 14:43	
Magnesium	mg/L	ND	0.050	0.012	05/14/24 14:43	
Manganese	mg/L	ND	0.040	0.011	05/14/24 14:43	
Potassium	mg/L	ND	0.50	0.15	05/15/24 21:55	
Sodium	mg/L	ND	1.0	0.58	05/15/24 21:55	

LABORATORY CONTROL SAMPLE: 4406155

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	0.95J	95	80-120	
Iron	mg/L	1	0.97	97	80-120	
Magnesium	mg/L	1	0.98	98	80-120	
Manganese	mg/L	1	0.96	96	80-120	
Potassium	mg/L	1	0.89	89	80-120	
Sodium	mg/L	1	0.94J	94	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4406156 4406157

Parameter	Units	92729900005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Calcium	mg/L	ND	1	1	1.3J	1.3J	94	98	75-125		20	
Iron	mg/L	ND	1	1	0.96	0.98	96	98	75-125	2	20	
Magnesium	mg/L	ND	1	1	1.0	1.0	95	98	75-125	2	20	
Manganese	mg/L	ND	1	1	1.1	1.1	101	99	75-125	2	20	
Potassium	mg/L	3370 ug/L	1	1	3.6	5.6	19	224	75-125	45	20 M1, R1	
Sodium	mg/L	3680000 ug/L	1	1	3540	3590	-13800	-8670	75-125	1	20 M1	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92730250

QC Batch: 853920

Analysis Method: EPA 6020B

QC Batch Method: EPA 3005A

Analysis Description: 6020 MET

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92730250001, 92730250002

METHOD BLANK: 4406560

Matrix: Water

Associated Lab Samples: 92730250001, 92730250002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00054	05/15/24 13:55	
Arsenic	mg/L	ND	0.0050	0.00084	05/15/24 13:55	
Barium	mg/L	ND	0.0050	0.00047	05/15/24 13:55	
Beryllium	mg/L	ND	0.00050	0.000094	05/15/24 13:55	
Boron	mg/L	ND	0.040	0.012	05/15/24 13:55	
Cadmium	mg/L	ND	0.00050	0.00010	05/15/24 13:55	
Chromium	mg/L	ND	0.0050	0.0019	05/15/24 13:55	
Cobalt	mg/L	ND	0.0050	0.00032	05/15/24 13:55	
Lead	mg/L	ND	0.0010	0.00016	05/15/24 13:55	
Lithium	mg/L	ND	0.030	0.0016	05/15/24 13:55	
Molybdenum	mg/L	ND	0.010	0.00062	05/15/24 13:55	
Selenium	mg/L	ND	0.0050	0.00096	05/15/24 13:55	
Thallium	mg/L	ND	0.0010	0.00038	05/15/24 13:55	

LABORATORY CONTROL SAMPLE: 4406561

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.11	106	80-120	
Arsenic	mg/L	0.1	0.10	103	80-120	
Barium	mg/L	0.1	0.10	102	80-120	
Beryllium	mg/L	0.1	0.11	109	80-120	
Boron	mg/L	1	1.1	105	80-120	
Cadmium	mg/L	0.1	0.10	103	80-120	
Chromium	mg/L	0.1	0.10	103	80-120	
Cobalt	mg/L	0.1	0.10	102	80-120	
Lead	mg/L	0.1	0.10	105	80-120	
Lithium	mg/L	0.1	0.11	110	80-120	
Molybdenum	mg/L	0.1	0.11	106	80-120	
Selenium	mg/L	0.1	0.10	104	80-120	
Thallium	mg/L	0.1	0.10	101	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4406562

4406563

Parameter	Units	92730292001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	0.78J ug/L	0.1	0.1	0.11	0.11	107	105	75-125	2	20	
Arsenic	mg/L	1.9J ug/L	0.1	0.1	0.11	0.11	107	104	75-125	3	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92730250

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:			4406562		4406563							
Parameter	Units	92730292001	MS	MSD	MS	MSD	MS	MSD	% Rec	RPD	Max	Qual
		Result	Spike	Spike								
Barium	mg/L	82.1J ug/L	0.1	0.1	0.19	0.19	108	103	75-125	2	20	
Beryllium	mg/L	ND	0.1	0.1	0.10	0.10	103	102	75-125	1	20	
Boron	mg/L	19.1J ug/L	1	1	1.0	1.0	101	99	75-125	1	20	
Cadmium	mg/L	ND	0.1	0.1	0.10	0.10	104	103	75-125	1	20	
Chromium	mg/L	4.3J ug/L	0.1	0.1	0.11	0.11	106	104	75-125	2	20	
Cobalt	mg/L	ND	0.1	0.1	0.10	0.10	103	103	75-125	0	20	
Lead	mg/L	0.19J ug/L	0.1	0.1	0.10	0.10	103	102	75-125	1	20	
Lithium	mg/L	ND	0.1	0.1	0.10	0.10	103	101	75-125	2	20	
Molybdenum	mg/L	ND	0.1	0.1	0.11	0.11	107	107	75-125	0	20	
Selenium	mg/L	ND	0.1	0.1	0.11	0.10	106	103	75-125	3	20	
Thallium	mg/L	ND	0.1	0.1	0.10	0.099	101	99	75-125	2	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92730250

QC Batch: 855047

Analysis Method: EPA 7470A

QC Batch Method: EPA 7470A

Analysis Description: 7470 Mercury

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92730250001, 92730250002

METHOD BLANK: 4411728

Matrix: Water

Associated Lab Samples: 92730250001, 92730250002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	05/17/24 08:16	

LABORATORY CONTROL SAMPLE: 4411729

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0023	92	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4411730 4411731

Parameter	Units	92729900001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.0025	0.0025	0.0022	0.0023	88	92	75-125	4	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92730250

QC Batch:	854348	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92730250001, 92730250002

METHOD BLANK: 4408261 Matrix: Water

Associated Lab Samples: 92730250001, 92730250002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	05/14/24 12:36	

LABORATORY CONTROL SAMPLE: 4408262

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	399	100	80-120	

SAMPLE DUPLICATE: 4408263

Parameter	Units	92730149001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	125	125	0	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92730250

QC Batch: 855114

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92730250001, 92730250002

METHOD BLANK: 4412185

Matrix: Water

Associated Lab Samples: 92730250001, 92730250002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	05/17/24 16:58	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/17/24 16:58	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/17/24 16:58	

LABORATORY CONTROL SAMPLE: 4412186

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	50.3	101	80-120	

LABORATORY CONTROL SAMPLE: 4412187

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	49.5	99	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4412190 4412191

Parameter	Units	92731061002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	71.7	50	50	124	122	104	101	80-120	1	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4414712 4414713

Parameter	Units	92729999001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	52.3	50	50	88.4	86.8	72	69	80-120	2	25	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92730250

QC Batch: 853854

Analysis Method: SM 4500-S2D-2011

QC Batch Method: SM 4500-S2D-2011

Analysis Description: 4500S2D Sulfide Water

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92730250001, 92730250002

METHOD BLANK: 4406359

Matrix: Water

Associated Lab Samples: 92730250001, 92730250002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	05/11/24 01:56	

LABORATORY CONTROL SAMPLE: 4406360

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.49	98	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4406361 4406362

Parameter	Units	92729816001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.57	0.58	106	109	80-120	3	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4406363 4406364

Parameter	Units	92729816003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.54	0.54	106	107	80-120	1	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92730250

QC Batch: 854169 Analysis Method: EPA 300.0 Rev 2.1 1993
QC Batch Method: EPA 300.0 Rev 2.1 1993 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92730250001, 92730250002

METHOD BLANK: 4407338 Matrix: Water

Associated Lab Samples: 92730250001, 92730250002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	05/13/24 18:31	
Fluoride	mg/L	ND	0.10	0.050	05/13/24 18:31	
Sulfate	mg/L	ND	1.0	0.50	05/13/24 18:31	

LABORATORY CONTROL SAMPLE: 4407339

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	49.5	99	90-110	
Fluoride	mg/L	2.5	2.4	95	90-110	
Sulfate	mg/L	50	49.6	99	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4407340 4407341

Parameter	Units	92730282001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	907	50	50	942	940	71	66	90-110	0	10	M1
Fluoride	mg/L	ND	2.5	2.5	ND	ND	0	0	90-110		10	D3,M1
Sulfate	mg/L	171	50	50	211	211	81	81	90-110	0	10	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1
Pace Project No.: 92730250

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

D3	Sample was diluted due to the presence of high levels of non-target analytes or other matrix interference.
M1	Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.
R1	RPD value was outside control limits.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92730250

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92730250001	HAM-PT-07	EPA 3010A	853813	EPA 6010D	853829
92730250002	HAM-PT-13	EPA 3010A	853813	EPA 6010D	853829
92730250001	HAM-PT-07	EPA 3005A	853920	EPA 6020B	853946
92730250002	HAM-PT-13	EPA 3005A	853920	EPA 6020B	853946
92730250001	HAM-PT-07	EPA 7470A	855047	EPA 7470A	855155
92730250002	HAM-PT-13	EPA 7470A	855047	EPA 7470A	855155
92730250001	HAM-PT-07	SM 2540C-2015	854348		
92730250002	HAM-PT-13	SM 2540C-2015	854348		
92730250001	HAM-PT-07	SM 2320B-2011	855114		
92730250002	HAM-PT-13	SM 2320B-2011	855114		
92730250001	HAM-PT-07	SM 4500-S2D-2011	853854		
92730250002	HAM-PT-13	SM 4500-S2D-2011	853854		
92730250001	HAM-PT-07	EPA 300.0 Rev 2.1 1993	854169		
92730250002	HAM-PT-13	EPA 300.0 Rev 2.1 1993	854169		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



DC#_Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

Georgia Power

Project #:

WO#: 92730250

Courier:

☐ Commercial☐ Fed-Ex☒ Pace☐ UPS☐ USPS☐ Other:☐ Client

92730250

Custody Seal Present?

☐ Yes☒ No

Seals Intact?

☐ Yes☐ No☒ N/A

Date/Initials Person Examining Contents:

5/10/24

Packing Material:

☐ Bubble Wrap☐ Bubble Bags☒ None☐ Other

Biological Tissue Frozen?

☐ Yes☐ No☒ N/A

Thermometer:

☒ IR Gun ID:

083

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

2.1

Correction Factor:

Add/Subtract (°C)

+0.1

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

2.2

USDA Regulated Soil (☐ N/A, water sample)

Did samples originate in a quarantine zone within the United States: CA, NY, or SC

(check maps)? ☐ Yes ☐ No

Did samples originate from a foreign source (internationally,

including Hawaii and Puerto Rico)? ☐ Yes ☐ No

			Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.	
Samples Arrived within Hold Time?	☐ Yes ☐ No ☐ N/A	2.	
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.	
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4.	
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.	
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.	
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A		
Containers Intact?	☒ Yes ☐ No ☐ N/A	7.	
Dissolved analysis: Samples Field Filtered?	☐ Yes ☐ No ☐ N/A	8.	
Sample Labels Match COC?	☒ Yes ☐ No ☐ N/A	9.	
-Includes Date/Time/ID/Analysis Matrix:	WT		
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10.	
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.	
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A		

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.
 Exceptions: VOA, Coliform, TDC, Oil and Grease, DRO/8015 (water) DOC, LUN.

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

WO#: 92730250

PM: BV

Due Date: 05/24/24


CLIENT: 92- GP-HAM

Item#																												
SP4U-125 mL Plastic Unpreserved (N/A) (Cl-)																												
BP9U-250 mL Plastic Unpreserved (N/A)	2	2																										
BP2U-500 mL Plastic Unpreserved (N/A)	1	1																										
BP1U-1 liter Plastic Unpreserved (N/A)																												
BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)																												
BP4N-250 mL plastic HNO3 (pH < 2)	1	1																										
BP4Z-125 mL Plastic 2N Acetate & NaOH (>9)	1	1																										
BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)																												
WGFU-Wide-mouthed Glass Jar Unpreserved																												
AG1U-1 liter Amber Unpreserved (N/A) (Cl-)																												
AG1H-1 liter Amber HCl (pH < 2)																												
AG3U-250 mL Amber Unpreserved (N/A) (Cl-)																												
AG3S-1 liter Amber H2SO4 (pH < 2)																												
AG3N-250 mL Amber H2SO4 (pH < 2)																												
DG9S-40 mL Amber HNO3 (N/A) (Cl-)																												
DG9H-40 mL VOA HCl (N/A)																												
VG9T-40 mL VOA Na2SO3 (N/A)																												
VG9U-40 mL VOA Unpreserved (N/A)																												
DG9V-40 mL VOA H3PO4 (N/A)																												
KP7U-50 mL Plastic Unpreserved (N/A)																												
V/GK 13 vials per kit-VPH/GAS kit (N/A)																												
SP9T-125 mL Sterile Plastic (N/A - lab)																												
SP2T-250 mL Sterile Plastic (N/A - lab)																												
BP9R-250 mL Plastic (NH2)2SO4 (S-3-9-7)																												
AGOU-100 mL Amber Unpreserved (N/A) (Cl-)																												
V55U-20 mL Contamination vials (N/A)																												
DG9U-40 mL Amber Unpreserved vials (N/A)																												

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Int #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples a copy of this form will be sent to the North Carolina DE&M Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers).



CHAIN-OF-CUSTODY / Analytical Request Document

The Chain of Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Section A Required Client Information		Section B Required Project Information		Section C Project Information	
Company	GA Power	Requester	SCS Contacts	Organization	Southern Co.
Address	Atlanta, GA	Copy To	Geosyntec Contacts	Contract Name	
Email To	SCS Contacts	Purchase Order No.	GPRC2472-0031	Address	
Phone		Project Name	Hammond AP-1	State	GA
Requested Due Date/TIME	1 day	Project Number		Site Location	

Section D Requested Client Information		Section E Requested Analysis Filtered (Y/N)	
Valid Matrix Codes	CODE	Preservatives	Analysis Test
MAT05		Unpreserved	Other
MAT06		HCl	Mercuric
MAT07		HNO ₃	Na ₂ SO ₄
MAT08		H ₂ SO ₄	NaOH
MAT09		Ascorbic	Na ₂ S ₂ O ₅
MAT10		Ascorbic	Na ₂ S ₂ O ₃
MAT11		Ascorbic	Na ₂ S ₂ O ₄
MAT12		Ascorbic	Na ₂ S ₂ O ₆
MAT13		Ascorbic	Na ₂ S ₂ O ₇
MAT14		Ascorbic	Na ₂ S ₂ O ₈
MAT15		Ascorbic	Na ₂ S ₂ O ₉
MAT16		Ascorbic	Na ₂ S ₂ O ₁₀
MAT17		Ascorbic	Na ₂ S ₂ O ₁₁
MAT18		Ascorbic	Na ₂ S ₂ O ₁₂
MAT19		Ascorbic	Na ₂ S ₂ O ₁₃
MAT20		Ascorbic	Na ₂ S ₂ O ₁₄
MAT21		Ascorbic	Na ₂ S ₂ O ₁₅
MAT22		Ascorbic	Na ₂ S ₂ O ₁₆
MAT23		Ascorbic	Na ₂ S ₂ O ₁₇
MAT24		Ascorbic	Na ₂ S ₂ O ₁₈
MAT25		Ascorbic	Na ₂ S ₂ O ₁₉
MAT26		Ascorbic	Na ₂ S ₂ O ₂₀
MAT27		Ascorbic	Na ₂ S ₂ O ₂₁
MAT28		Ascorbic	Na ₂ S ₂ O ₂₂
MAT29		Ascorbic	Na ₂ S ₂ O ₂₃
MAT30		Ascorbic	Na ₂ S ₂ O ₂₄
MAT31		Ascorbic	Na ₂ S ₂ O ₂₅
MAT32		Ascorbic	Na ₂ S ₂ O ₂₆
MAT33		Ascorbic	Na ₂ S ₂ O ₂₇
MAT34		Ascorbic	Na ₂ S ₂ O ₂₈
MAT35		Ascorbic	Na ₂ S ₂ O ₂₉
MAT36		Ascorbic	Na ₂ S ₂ O ₃₀
MAT37		Ascorbic	Na ₂ S ₂ O ₃₁
MAT38		Ascorbic	Na ₂ S ₂ O ₃₂
MAT39		Ascorbic	Na ₂ S ₂ O ₃₃
MAT40		Ascorbic	Na ₂ S ₂ O ₃₄
MAT41		Ascorbic	Na ₂ S ₂ O ₃₅
MAT42		Ascorbic	Na ₂ S ₂ O ₃₆
MAT43		Ascorbic	Na ₂ S ₂ O ₃₇
MAT44		Ascorbic	Na ₂ S ₂ O ₃₈
MAT45		Ascorbic	Na ₂ S ₂ O ₃₉
MAT46		Ascorbic	Na ₂ S ₂ O ₄₀
MAT47		Ascorbic	Na ₂ S ₂ O ₄₁
MAT48		Ascorbic	Na ₂ S ₂ O ₄₂
MAT49		Ascorbic	Na ₂ S ₂ O ₄₃
MAT50		Ascorbic	Na ₂ S ₂ O ₄₄
MAT51		Ascorbic	Na ₂ S ₂ O ₄₅
MAT52		Ascorbic	Na ₂ S ₂ O ₄₆
MAT53		Ascorbic	Na ₂ S ₂ O ₄₇
MAT54		Ascorbic	Na ₂ S ₂ O ₄₈
MAT55		Ascorbic	Na ₂ S ₂ O ₄₉
MAT56		Ascorbic	Na ₂ S ₂ O ₅₀
MAT57		Ascorbic	Na ₂ S ₂ O ₅₁
MAT58		Ascorbic	Na ₂ S ₂ O ₅₂
MAT59		Ascorbic	Na ₂ S ₂ O ₅₃
MAT60		Ascorbic	Na ₂ S ₂ O ₅₄
MAT61		Ascorbic	Na ₂ S ₂ O ₅₅
MAT62		Ascorbic	Na ₂ S ₂ O ₅₆
MAT63		Ascorbic	Na ₂ S ₂ O ₅₇
MAT64		Ascorbic	Na ₂ S ₂ O ₅₈
MAT65		Ascorbic	Na ₂ S ₂ O ₅₉
MAT66		Ascorbic	Na ₂ S ₂ O ₆₀
MAT67		Ascorbic	Na ₂ S ₂ O



June 17, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1
Pace Project No.: 92731696

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on May 17, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Peachtree Corners, GA

Revision 1: Client requested that the lab re-check anions for HAM-AP1-FB-01 (Lab ID 92731696003) and HAM-AP1-FD-01 (lab ID 92731696005). The lab did a re-run for both samples and the results did not confirm the original. A revised report was issued.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc

Anthony Szwast, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1

Pace Project No.: 92731696

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1

Pace Project No.: 92731696

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92731696001	HAM-AP1-EB-01	Water	05/15/24 16:02	05/17/24 12:55
92731696002	HAM-AP1-EB-02	Water	05/15/24 16:20	05/17/24 12:55
92731696003	HAM-AP1-FB-01	Water	05/15/24 15:56	05/17/24 12:55
92731696004	HAM-AP1-FB-02	Water	05/15/24 17:19	05/17/24 12:55
92731696005	HAM-AP1-FD-01	Water	05/15/24 00:00	05/17/24 12:55
92731696006	HAM-AP1-FD-02	Water	05/15/24 00:00	05/17/24 12:55
92731696007	HAM-INW-03	Water	05/14/24 14:08	05/17/24 12:55
92731696008	HAM-INW-04	Water	05/15/24 14:20	05/17/24 12:55
92731696009	HAM-INW-05	Water	05/15/24 11:18	05/17/24 12:55
92731696010	HAM-PT-07	Water	05/16/24 12:16	05/17/24 12:55
92731696011	HAM-PT-08	Water	05/16/24 10:37	05/17/24 12:55
92731696012	HAM-PT-09	Water	05/14/24 10:40	05/17/24 12:55
92731696013	HAM-PT-10	Water	05/15/24 11:52	05/17/24 12:55
92731696014	HAM-PT-11	Water	05/14/24 15:20	05/17/24 12:55
92731696015	HAM-PT-12	Water	05/14/24 12:05	05/17/24 12:55
92731696016	HAM-PT-13	Water	05/15/24 18:45	05/17/24 12:55
92731696017	HAM-PT-14	Water	05/15/24 18:27	05/17/24 12:55
92731696018	HAM-PT-15	Water	05/15/24 16:10	05/17/24 12:55

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92731696

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92731696001	HAM-AP1-EB-01	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92731696002	HAM-AP1-EB-02	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92731696003	HAM-AP1-FB-01	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92731696004	HAM-AP1-FB-02	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92731696005	HAM-AP1-FD-01	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92731696006	HAM-AP1-FD-02	EPA 6010D	AJM	6
		EPA 6020B	CW1	13

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92731696

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92731696007	HAM-INW-03	EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM, DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
92731696008	HAM-INW-04	SM 4500-S2D-2011	MDW	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
92731696009	HAM-INW-05	EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
92731696010	HAM-PT-07	SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92731696011	HAM-PT-08	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92731696

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92731696012	HAM-PT-09	SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
92731696013	HAM-PT-10	SM 4500-S2D-2011	MDW	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
92731696014	HAM-PT-11	EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	MDW	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92731696015	HAM-PT-12	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	MDW	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
92731696016	HAM-PT-13	EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92731696

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92731696017	HAM-PT-14	EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
92731696018	HAM-PT-15	EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM, DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3

PASI-A = Pace Analytical Services - Asheville

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92731696

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92731696002	HAM-AP1-EB-02					
EPA 6020B	Antimony	0.0013J	mg/L	0.0030	05/22/24 15:20	
92731696005	HAM-AP1-FD-01					
EPA 6010D	Iron	0.20	mg/L	0.040	05/23/24 01:21	
EPA 6010D	Manganese	0.70	mg/L	0.040	05/23/24 01:21	
EPA 6010D	Potassium	6.5	mg/L	0.50	05/23/24 01:21	
EPA 6010D	Sodium	8.9	mg/L	1.0	05/23/24 01:21	
EPA 6010D	Calcium	103	mg/L	1.0	05/23/24 01:21	
EPA 6010D	Magnesium	13.8	mg/L	0.050	05/23/24 01:21	
EPA 6020B	Barium	0.053	mg/L	0.0050	05/22/24 15:31	
EPA 6020B	Boron	1.5	mg/L	0.040	05/22/24 15:31	
EPA 6020B	Cobalt	0.0016J	mg/L	0.0050	05/22/24 15:31	
EPA 6020B	Molybdenum	0.090	mg/L	0.010	05/22/24 15:31	
EPA 6020B	Selenium	0.0011J	mg/L	0.0050	05/22/24 15:31	
SM 2540C-2015	Total Dissolved Solids	528	mg/L	25.0	05/20/24 12:18	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	131	mg/L	5.0	05/21/24 18:48	
SM 2320B-2011	Alkalinity, Total as CaCO3	131	mg/L	5.0	05/21/24 18:48	
EPA 300.0 Rev 2.1 1993	Chloride	49.1	mg/L	1.0	06/12/24 13:41	
EPA 300.0 Rev 2.1 1993	Fluoride	0.19	mg/L	0.10	06/12/24 13:41	
EPA 300.0 Rev 2.1 1993	Sulfate	149	mg/L	3.0	06/12/24 14:39	
92731696006	HAM-AP1-FD-02					
EPA 6010D	Iron	7.9	mg/L	0.040	05/23/24 01:24	
EPA 6010D	Manganese	4.6	mg/L	0.040	05/23/24 01:24	
EPA 6010D	Potassium	4.8	mg/L	0.50	05/23/24 01:24	
EPA 6010D	Sodium	6.9	mg/L	1.0	05/23/24 01:24	
EPA 6010D	Calcium	103	mg/L	1.0	05/23/24 01:24	
EPA 6010D	Magnesium	12.8	mg/L	0.050	05/23/24 01:24	
EPA 6020B	Arsenic	0.19	mg/L	0.0050	05/22/24 15:45	
EPA 6020B	Barium	0.042	mg/L	0.0050	05/22/24 15:45	
EPA 6020B	Boron	0.59	mg/L	0.040	05/22/24 15:45	
EPA 6020B	Cobalt	0.031	mg/L	0.0050	05/22/24 15:45	
EPA 6020B	Lithium	0.044	mg/L	0.030	05/22/24 15:45	
EPA 6020B	Molybdenum	0.014	mg/L	0.010	05/22/24 15:45	
SM 2540C-2015	Total Dissolved Solids	491	mg/L	25.0	05/20/24 12:18	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	138	mg/L	5.0	05/21/24 19:06	
SM 2320B-2011	Alkalinity, Total as CaCO3	138	mg/L	5.0	05/21/24 19:06	
EPA 300.0 Rev 2.1 1993	Chloride	10.1	mg/L	1.0	05/20/24 10:17	
EPA 300.0 Rev 2.1 1993	Fluoride	0.26	mg/L	0.10	05/20/24 10:17	
EPA 300.0 Rev 2.1 1993	Sulfate	189	mg/L	4.0	05/20/24 20:43	
92731696007	HAM-INW-03					
EPA 6010D	Sodium	12.4	mg/L	1.0	05/24/24 11:34	
EPA 6010D	Iron	0.11	mg/L	0.040	05/23/24 02:19	
EPA 6010D	Manganese	0.45	mg/L	0.040	05/23/24 02:19	
EPA 6010D	Potassium	13.8	mg/L	0.50	05/23/24 02:19	
EPA 6010D	Calcium	127	mg/L	1.0	05/23/24 02:19	
EPA 6010D	Magnesium	17.1	mg/L	0.050	05/23/24 02:19	
EPA 6020B	Barium	0.075	mg/L	0.0050	05/22/24 16:41	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92731696

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92731696007	HAM-INW-03					
EPA 6020B	Boron	1.5	mg/L	0.040	05/22/24 16:41	
EPA 6020B	Cobalt	0.00070J	mg/L	0.0050	05/22/24 16:41	
EPA 6020B	Lithium	0.0050J	mg/L	0.030	05/22/24 16:41	
EPA 6020B	Molybdenum	0.082	mg/L	0.010	05/22/24 16:41	
SM 2540C-2015	Total Dissolved Solids	564	mg/L	25.0	05/20/24 12:16	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	175	mg/L	5.0	05/21/24 16:31	
SM 2320B-2011	Alkalinity, Total as CaCO3	175	mg/L	5.0	05/21/24 16:31	M1
EPA 300.0 Rev 2.1 1993	Chloride	56.9	mg/L	1.0	05/21/24 00:39	M1
EPA 300.0 Rev 2.1 1993	Fluoride	0.20	mg/L	0.10	05/21/24 00:39	
EPA 300.0 Rev 2.1 1993	Sulfate	178	mg/L	4.0	05/21/24 08:01	
92731696008	HAM-INW-04					
EPA 6010D	Iron	8.4	mg/L	0.040	05/23/24 01:35	
EPA 6010D	Manganese	4.4	mg/L	0.040	05/23/24 01:35	
EPA 6010D	Potassium	4.8	mg/L	0.50	05/23/24 01:35	
EPA 6010D	Sodium	7.0	mg/L	1.0	05/23/24 01:35	
EPA 6010D	Calcium	107	mg/L	1.0	05/23/24 01:35	
EPA 6010D	Magnesium	13.1	mg/L	0.050	05/23/24 01:35	
EPA 6020B	Arsenic	0.19	mg/L	0.0050	05/22/24 15:49	
EPA 6020B	Barium	0.043	mg/L	0.0050	05/22/24 15:49	
EPA 6020B	Boron	0.59	mg/L	0.040	05/22/24 15:49	
EPA 6020B	Cobalt	0.031	mg/L	0.0050	05/22/24 15:49	
EPA 6020B	Lithium	0.043	mg/L	0.030	05/22/24 15:49	
EPA 6020B	Molybdenum	0.015	mg/L	0.010	05/22/24 15:49	
SM 2540C-2015	Total Dissolved Solids	483	mg/L	25.0	05/20/24 12:19	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	133	mg/L	5.0	05/21/24 19:16	
SM 2320B-2011	Alkalinity, Total as CaCO3	133	mg/L	5.0	05/21/24 19:16	
EPA 300.0 Rev 2.1 1993	Chloride	9.9	mg/L	1.0	05/21/24 01:48	
EPA 300.0 Rev 2.1 1993	Fluoride	0.28	mg/L	0.10	05/21/24 01:48	
EPA 300.0 Rev 2.1 1993	Sulfate	187	mg/L	4.0	05/21/24 08:42	
92731696009	HAM-INW-05					
EPA 6010D	Iron	16.9	mg/L	0.040	05/23/24 01:38	
EPA 6010D	Manganese	3.3	mg/L	0.040	05/23/24 01:38	
EPA 6010D	Potassium	4.7	mg/L	0.50	05/23/24 01:38	
EPA 6010D	Sodium	6.7	mg/L	1.0	05/23/24 01:38	
EPA 6010D	Calcium	101	mg/L	1.0	05/23/24 01:38	
EPA 6010D	Magnesium	11.8	mg/L	0.050	05/23/24 01:38	
EPA 6020B	Arsenic	0.23	mg/L	0.0050	05/22/24 15:53	
EPA 6020B	Barium	0.033	mg/L	0.0050	05/22/24 15:53	
EPA 6020B	Beryllium	0.00012J	mg/L	0.00050	05/22/24 15:53	
EPA 6020B	Boron	0.51	mg/L	0.040	05/22/24 15:53	
EPA 6020B	Cobalt	0.026	mg/L	0.0050	05/22/24 15:53	
EPA 6020B	Lithium	0.057	mg/L	0.030	05/22/24 15:53	
EPA 6020B	Molybdenum	0.0096J	mg/L	0.010	05/22/24 15:53	
SM 2540C-2015	Total Dissolved Solids	456	mg/L	25.0	05/20/24 12:20	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	123	mg/L	5.0	05/21/24 19:25	
SM 2320B-2011	Alkalinity, Total as CaCO3	123	mg/L	5.0	05/21/24 19:25	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92731696

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92731696009	HAM-INW-05					
EPA 300.0 Rev 2.1 1993	Chloride	6.9	mg/L	1.0	05/21/24 02:02	
EPA 300.0 Rev 2.1 1993	Fluoride	0.37	mg/L	0.10	05/21/24 02:02	
EPA 300.0 Rev 2.1 1993	Sulfate	181	mg/L	4.0	05/21/24 08:56	
92731696010	HAM-PT-07					
EPA 6010D	Iron	15.7	mg/L	0.040	05/23/24 01:41	
EPA 6010D	Manganese	3.4	mg/L	0.040	05/23/24 01:41	
EPA 6010D	Potassium	4.9	mg/L	0.50	05/23/24 01:41	
EPA 6010D	Sodium	7.0	mg/L	1.0	05/23/24 01:41	
EPA 6010D	Calcium	96.0	mg/L	1.0	05/23/24 01:41	
EPA 6010D	Magnesium	12.1	mg/L	0.050	05/23/24 01:41	
EPA 6020B	Arsenic	0.27	mg/L	0.0050	05/22/24 15:56	
EPA 6020B	Barium	0.034	mg/L	0.0050	05/22/24 15:56	
EPA 6020B	Boron	0.50	mg/L	0.040	05/22/24 15:56	
EPA 6020B	Cobalt	0.052	mg/L	0.0050	05/22/24 15:56	
EPA 6020B	Lithium	0.056	mg/L	0.030	05/22/24 15:56	
EPA 6020B	Molybdenum	0.0093J	mg/L	0.010	05/22/24 15:56	
SM 2540C-2015	Total Dissolved Solids	450	mg/L	25.0	05/20/24 12:22	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	116	mg/L	5.0	05/28/24 17:56	
SM 2320B-2011	Alkalinity, Total as CaCO3	116	mg/L	5.0	05/28/24 17:56	
EPA 300.0 Rev 2.1 1993	Chloride	10	mg/L	1.0	05/21/24 02:16	
EPA 300.0 Rev 2.1 1993	Fluoride	0.31	mg/L	0.10	05/21/24 02:16	
EPA 300.0 Rev 2.1 1993	Sulfate	171	mg/L	4.0	05/21/24 09:10	
92731696011	HAM-PT-08					
EPA 6010D	Iron	8.0	mg/L	0.040	05/23/24 01:45	
EPA 6010D	Manganese	3.3	mg/L	0.040	05/23/24 01:45	
EPA 6010D	Potassium	4.8	mg/L	0.50	05/23/24 01:45	
EPA 6010D	Sodium	7.2	mg/L	1.0	05/23/24 01:45	
EPA 6010D	Calcium	89.4	mg/L	1.0	05/23/24 01:45	
EPA 6010D	Magnesium	11.5	mg/L	0.050	05/23/24 01:45	
EPA 6020B	Arsenic	0.23	mg/L	0.0050	05/22/24 16:00	
EPA 6020B	Barium	0.041	mg/L	0.0050	05/22/24 16:00	
EPA 6020B	Boron	0.73	mg/L	0.040	05/22/24 16:00	
EPA 6020B	Cobalt	0.046	mg/L	0.0050	05/22/24 16:00	
EPA 6020B	Lead	0.0079	mg/L	0.0010	05/22/24 16:00	
EPA 6020B	Lithium	0.010J	mg/L	0.030	05/22/24 16:00	
EPA 6020B	Molybdenum	0.017	mg/L	0.010	05/22/24 16:00	
SM 2540C-2015	Total Dissolved Solids	410	mg/L	25.0	05/20/24 12:22	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	104	mg/L	5.0	05/28/24 18:06	
SM 2320B-2011	Alkalinity, Total as CaCO3	104	mg/L	5.0	05/28/24 18:06	
EPA 300.0 Rev 2.1 1993	Chloride	16.7	mg/L	1.0	05/21/24 20:59	
EPA 300.0 Rev 2.1 1993	Fluoride	0.19	mg/L	0.10	05/21/24 20:59	
EPA 300.0 Rev 2.1 1993	Sulfate	159	mg/L	4.0	05/22/24 07:35	
92731696012	HAM-PT-09					
EPA 6010D	Iron	0.42	mg/L	0.040	05/23/24 01:48	
EPA 6010D	Manganese	0.19	mg/L	0.040	05/23/24 01:48	
EPA 6010D	Potassium	6.1	mg/L	0.50	05/23/24 01:48	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92731696

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92731696012	HAM-PT-09					
EPA 6010D	Sodium	9.3	mg/L	1.0	05/23/24 01:48	
EPA 6010D	Calcium	82.8	mg/L	1.0	05/23/24 01:48	
EPA 6010D	Magnesium	23.7	mg/L	0.050	05/23/24 01:48	
EPA 6020B	Barium	0.058	mg/L	0.0050	05/22/24 16:04	
EPA 6020B	Boron	1.4	mg/L	0.040	05/22/24 16:04	
EPA 6020B	Cadmium	0.00015J	mg/L	0.00050	05/22/24 16:04	
EPA 6020B	Cobalt	0.0012J	mg/L	0.0050	05/22/24 16:04	
EPA 6020B	Lead	0.00017J	mg/L	0.0010	05/22/24 16:04	
EPA 6020B	Molybdenum	0.27	mg/L	0.010	05/22/24 16:04	
SM 2540C-2015	Total Dissolved Solids	436	mg/L	25.0	05/20/24 12:17	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	139	mg/L	5.0	05/21/24 17:10	
SM 2320B-2011	Alkalinity, Total as CaCO3	139	mg/L	5.0	05/21/24 17:10	M1
EPA 300.0 Rev 2.1 1993	Chloride	44.4	mg/L	1.0	05/21/24 02:29	
EPA 300.0 Rev 2.1 1993	Fluoride	0.37	mg/L	0.10	05/21/24 02:29	
EPA 300.0 Rev 2.1 1993	Sulfate	130	mg/L	3.0	05/21/24 10:07	M1
92731696013	HAM-PT-10					
EPA 6010D	Iron	0.24	mg/L	0.040	05/23/24 01:51	
EPA 6010D	Manganese	0.74	mg/L	0.040	05/23/24 01:51	
EPA 6010D	Potassium	6.7	mg/L	0.50	05/23/24 01:51	
EPA 6010D	Sodium	9.2	mg/L	1.0	05/23/24 01:51	
EPA 6010D	Calcium	108	mg/L	1.0	05/23/24 01:51	
EPA 6010D	Magnesium	14.3	mg/L	0.050	05/23/24 01:51	
EPA 6020B	Barium	0.054	mg/L	0.0050	05/22/24 16:07	
EPA 6020B	Boron	1.5	mg/L	0.040	05/22/24 16:07	
EPA 6020B	Cobalt	0.0016J	mg/L	0.0050	05/22/24 16:07	
EPA 6020B	Molybdenum	0.092	mg/L	0.010	05/22/24 16:07	
SM 2540C-2015	Total Dissolved Solids	503	mg/L	25.0	05/20/24 12:20	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	132	mg/L	5.0	05/21/24 19:35	
SM 2320B-2011	Alkalinity, Total as CaCO3	132	mg/L	5.0	05/21/24 19:35	
EPA 300.0 Rev 2.1 1993	Chloride	50.1	mg/L	1.0	05/21/24 03:11	
EPA 300.0 Rev 2.1 1993	Fluoride	0.22	mg/L	0.10	05/21/24 03:11	
EPA 300.0 Rev 2.1 1993	Sulfate	146	mg/L	3.0	05/21/24 10:48	
92731696014	HAM-PT-11					
EPA 6010D	Manganese	0.28	mg/L	0.040	05/23/24 01:55	
EPA 6010D	Potassium	6.0	mg/L	0.50	05/23/24 01:55	
EPA 6010D	Sodium	8.8	mg/L	1.0	05/23/24 01:55	
EPA 6010D	Calcium	90.9	mg/L	1.0	05/23/24 01:55	
EPA 6010D	Magnesium	16.2	mg/L	0.050	05/23/24 01:55	
EPA 6020B	Barium	0.057	mg/L	0.0050	05/22/24 16:11	
EPA 6020B	Boron	1.6	mg/L	0.040	05/22/24 16:11	
EPA 6020B	Cadmium	0.00013J	mg/L	0.00050	05/22/24 16:11	
EPA 6020B	Cobalt	0.0016J	mg/L	0.0050	05/22/24 16:11	
EPA 6020B	Molybdenum	0.24	mg/L	0.010	05/22/24 16:11	
SM 2540C-2015	Total Dissolved Solids	441	mg/L	25.0	05/20/24 12:17	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	125	mg/L	5.0	05/21/24 17:33	
SM 2320B-2011	Alkalinity, Total as CaCO3	125	mg/L	5.0	05/21/24 17:33	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92731696

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92731696014	HAM-PT-11					
EPA 300.0 Rev 2.1 1993	Chloride	41.4	mg/L	1.0	05/21/24 03:25	
EPA 300.0 Rev 2.1 1993	Fluoride	0.34	mg/L	0.10	05/21/24 03:25	
EPA 300.0 Rev 2.1 1993	Sulfate	122	mg/L	3.0	05/21/24 11:03	
92731696015	HAM-PT-12					
EPA 6010D	Iron	0.33	mg/L	0.040	05/23/24 01:59	
EPA 6010D	Manganese	1.0	mg/L	0.040	05/23/24 01:59	
EPA 6010D	Potassium	6.8	mg/L	0.50	05/23/24 01:59	
EPA 6010D	Sodium	11.8	mg/L	1.0	05/23/24 01:59	
EPA 6010D	Calcium	99.7	mg/L	1.0	05/23/24 01:59	
EPA 6010D	Magnesium	16.6	mg/L	0.050	05/23/24 01:59	
EPA 6020B	Barium	0.069	mg/L	0.0050	05/22/24 16:15	
EPA 6020B	Boron	1.6	mg/L	0.040	05/22/24 16:15	
EPA 6020B	Cadmium	0.00014J	mg/L	0.00050	05/22/24 16:15	
EPA 6020B	Cobalt	0.0044J	mg/L	0.0050	05/22/24 16:15	
EPA 6020B	Lead	0.00017J	mg/L	0.0010	05/22/24 16:15	
EPA 6020B	Molybdenum	0.085	mg/L	0.010	05/22/24 16:15	
SM 2540C-2015	Total Dissolved Solids	523	mg/L	25.0	05/20/24 12:17	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	129	mg/L	5.0	05/21/24 17:51	
SM 2320B-2011	Alkalinity, Total as CaCO3	129	mg/L	5.0	05/21/24 17:51	
EPA 300.0 Rev 2.1 1993	Chloride	50.3	mg/L	1.0	05/21/24 03:38	
EPA 300.0 Rev 2.1 1993	Fluoride	0.20	mg/L	0.10	05/21/24 03:38	
EPA 300.0 Rev 2.1 1993	Sulfate	125	mg/L	3.0	05/21/24 11:17	
92731696016	HAM-PT-13					
EPA 6010D	Iron	15.0	mg/L	0.040	05/23/24 02:02	
EPA 6010D	Manganese	3.6	mg/L	0.040	05/23/24 02:02	
EPA 6010D	Potassium	5.0	mg/L	0.50	05/23/24 02:02	
EPA 6010D	Sodium	7.8	mg/L	1.0	05/23/24 02:02	
EPA 6010D	Calcium	99.2	mg/L	1.0	05/23/24 02:02	
EPA 6010D	Magnesium	12.0	mg/L	0.050	05/23/24 02:02	
EPA 6020B	Arsenic	0.29	mg/L	0.0050	05/22/24 16:19	
EPA 6020B	Barium	0.033	mg/L	0.0050	05/22/24 16:19	
EPA 6020B	Boron	0.52	mg/L	0.040	05/22/24 16:19	
EPA 6020B	Cobalt	0.024	mg/L	0.0050	05/22/24 16:19	
EPA 6020B	Lithium	0.058	mg/L	0.030	05/22/24 16:19	
EPA 6020B	Molybdenum	0.0087J	mg/L	0.010	05/22/24 16:19	
SM 2540C-2015	Total Dissolved Solids	459	mg/L	25.0	05/20/24 12:21	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	111	mg/L	5.0	05/21/24 19:44	
SM 2320B-2011	Alkalinity, Total as CaCO3	111	mg/L	5.0	05/21/24 19:44	
EPA 300.0 Rev 2.1 1993	Chloride	9.5	mg/L	1.0	05/21/24 04:20	
EPA 300.0 Rev 2.1 1993	Fluoride	0.34	mg/L	0.10	05/21/24 04:20	
EPA 300.0 Rev 2.1 1993	Sulfate	190	mg/L	4.0	05/21/24 11:31	
92731696017	HAM-PT-14					
EPA 6010D	Iron	14.9	mg/L	0.040	05/23/24 02:05	
EPA 6010D	Manganese	3.1	mg/L	0.040	05/23/24 02:05	
EPA 6010D	Potassium	5.0	mg/L	0.50	05/23/24 02:05	
EPA 6010D	Sodium	6.7	mg/L	1.0	05/23/24 02:05	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92731696

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92731696017	HAM-PT-14					
EPA 6010D	Calcium	97.4	mg/L	1.0	05/23/24 02:05	
EPA 6010D	Magnesium	12.7	mg/L	0.050	05/23/24 02:05	
EPA 6020B	Arsenic	0.21	mg/L	0.0050	05/22/24 16:33	
EPA 6020B	Barium	0.038	mg/L	0.0050	05/22/24 16:33	
EPA 6020B	Beryllium	0.00016J	mg/L	0.00050	05/22/24 16:33	
EPA 6020B	Boron	0.51	mg/L	0.040	05/22/24 16:33	
EPA 6020B	Cobalt	0.020	mg/L	0.0050	05/22/24 16:33	
EPA 6020B	Lead	0.00046J	mg/L	0.0010	05/22/24 16:33	
EPA 6020B	Lithium	0.051	mg/L	0.030	05/22/24 16:33	
EPA 6020B	Molybdenum	0.011	mg/L	0.010	05/22/24 16:33	
SM 2540C-2015	Total Dissolved Solids	461	mg/L	25.0	05/20/24 12:21	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	121	mg/L	5.0	05/21/24 19:53	
SM 2320B-2011	Alkalinity, Total as CaCO3	121	mg/L	5.0	05/21/24 19:53	
EPA 300.0 Rev 2.1 1993	Chloride	10.5	mg/L	1.0	05/21/24 04:34	
EPA 300.0 Rev 2.1 1993	Fluoride	0.26	mg/L	0.10	05/21/24 04:34	
EPA 300.0 Rev 2.1 1993	Sulfate	175	mg/L	4.0	05/21/24 11:44	
92731696018	HAM-PT-15					
EPA 6010D	Sodium	8.1	mg/L	1.0	05/24/24 11:31	
EPA 6010D	Iron	9.2	mg/L	0.040	05/23/24 02:16	
EPA 6010D	Manganese	5.7	mg/L	0.040	05/23/24 02:16	
EPA 6010D	Potassium	5.3	mg/L	0.50	05/23/24 02:16	
EPA 6010D	Calcium	141	mg/L	1.0	05/23/24 02:16	
EPA 6010D	Magnesium	16.1	mg/L	0.050	05/23/24 02:16	
EPA 6020B	Arsenic	0.39	mg/L	0.0050	05/22/24 16:37	
EPA 6020B	Barium	0.043	mg/L	0.0050	05/22/24 16:37	
EPA 6020B	Boron	0.76	mg/L	0.040	05/22/24 16:37	
EPA 6020B	Cobalt	0.059	mg/L	0.0050	05/22/24 16:37	
EPA 6020B	Lithium	0.047	mg/L	0.030	05/22/24 16:37	
EPA 6020B	Molybdenum	0.021	mg/L	0.010	05/22/24 16:37	
SM 2540C-2015	Total Dissolved Solids	639	mg/L	25.0	05/20/24 12:22	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	134	mg/L	5.0	05/21/24 20:02	
SM 2320B-2011	Alkalinity, Total as CaCO3	134	mg/L	5.0	05/21/24 20:02	
EPA 300.0 Rev 2.1 1993	Chloride	12.6	mg/L	1.0	05/21/24 04:48	
EPA 300.0 Rev 2.1 1993	Fluoride	0.35	mg/L	0.10	05/21/24 04:48	
EPA 300.0 Rev 2.1 1993	Sulfate	271	mg/L	6.0	05/21/24 11:58	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-AP1-EB-01 Lab ID: 92731696001 Collected: 05/15/24 16:02 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 00:56	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 00:56	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 00:56	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 00:56	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 00:56	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 00:56	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 15:05	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 15:05	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 15:05	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 15:05	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 15:05	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 15:05	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 15:05	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 15:05	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 15:05	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 15:05	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 15:05	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 15:05	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 15:05	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 12:35	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		05/20/24 12:17		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 18:33		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 18:33		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		05/21/24 18:33		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:09	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		05/20/24 01:22	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92731696

Sample: HAM-AP1-EB-01		Lab ID: 92731696001		Collected: 05/15/24 16:02		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		05/20/24 01:22	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		05/20/24 01:22	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-AP1-EB-02 Lab ID: 92731696002 Collected: 05/15/24 16:20 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:09	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:09	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:09	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:09	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:09	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:09	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	0.0013J	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 15:20	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 15:20	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 15:20	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 15:20	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 15:20	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 15:20	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 15:20	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 15:20	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 15:20	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 15:20	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 15:20	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 15:20	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 15:20	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 12:38	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		05/20/24 12:18		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 18:37		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 18:37		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		05/21/24 18:37		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:19	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		05/20/24 01:37	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92731696

Sample: HAM-AP1-EB-02		Lab ID: 92731696002		Collected: 05/15/24 16:20		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		05/20/24 01:37	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		05/20/24 01:37	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-AP1-FB-01 Lab ID: 92731696003 Collected: 05/15/24 15:56 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:13	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:13	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:13	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:13	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:13	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:13	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 15:24	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 15:24	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 15:24	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 15:24	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 15:24	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 15:24	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 15:24	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 15:24	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 15:24	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 15:24	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 15:24	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 15:24	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 15:24	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 12:48	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		05/20/24 12:18		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 18:41		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 18:41		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		05/21/24 18:41		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:10	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		06/12/24 13:26	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92731696

Sample: HAM-AP1-FB-01		Lab ID: 92731696003		Collected: 05/15/24 15:56		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		06/12/24 13:26	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		06/12/24 13:26	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-AP1-FB-02 Lab ID: 92731696004 Collected: 05/15/24 17:19 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:17	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:17	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:17	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:17	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:17	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:17	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 15:28	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 15:28	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 15:28	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 15:28	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 15:28	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 15:28	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 15:28	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 15:28	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 15:28	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 15:28	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 15:28	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 15:28	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 15:28	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 12:56	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		05/20/24 12:18		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 18:44		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 18:44		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		05/21/24 18:44		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:11	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		05/20/24 02:56	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92731696

Sample: HAM-AP1-FB-02		Lab ID: 92731696004		Collected: 05/15/24 17:19		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		05/20/24 02:56	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		05/20/24 02:56	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-AP1-FD-01 Lab ID: 92731696005 Collected: 05/15/24 00:00 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.20	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:21	7439-89-6	
Manganese	0.70	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:21	7439-96-5	
Potassium	6.5	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:21	7440-09-7	
Sodium	8.9	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:21	7440-23-5	
Calcium	103	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:21	7440-70-2	
Magnesium	13.8	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:21	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 15:31	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 15:31	7440-38-2	
Barium	0.053	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 15:31	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 15:31	7440-41-7	
Boron	1.5	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 15:31	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 15:31	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 15:31	7440-47-3	
Cobalt	0.0016J	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 15:31	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 15:31	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 15:31	7439-93-2	
Molybdenum	0.090	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 15:31	7439-98-7	
Selenium	0.0011J	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 15:31	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 15:31	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 12:59	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	528	mg/L	25.0	25.0	1		05/20/24 12:18		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	131	mg/L	5.0	5.0	1		05/21/24 18:48		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 18:48		
Alkalinity, Total as CaCO ₃	131	mg/L	5.0	5.0	1		05/21/24 18:48		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:12	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	49.1	mg/L	1.0	0.60	1		06/12/24 13:41	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92731696

Sample: HAM-AP1-FD-01		Lab ID: 92731696005		Collected: 05/15/24 00:00		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.19	mg/L	0.10	0.050	1		06/12/24 13:41	16984-48-8	
Sulfate	149	mg/L	3.0	1.5	3		06/12/24 14:39	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-AP1-FD-02		Lab ID: 92731696006		Collected: 05/15/24 00:00		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	7.9	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:24	7439-89-6	
Manganese	4.6	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:24	7439-96-5	
Potassium	4.8	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:24	7440-09-7	
Sodium	6.9	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:24	7440-23-5	
Calcium	103	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:24	7440-70-2	
Magnesium	12.8	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:24	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 15:45	7440-36-0	
Arsenic	0.19	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 15:45	7440-38-2	
Barium	0.042	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 15:45	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 15:45	7440-41-7	
Boron	0.59	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 15:45	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 15:45	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 15:45	7440-47-3	
Cobalt	0.031	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 15:45	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 15:45	7439-92-1	
Lithium	0.044	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 15:45	7439-93-2	
Molybdenum	0.014	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 15:45	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 15:45	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 15:45	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:01	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	491	mg/L	25.0	25.0	1		05/20/24 12:18		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	138	mg/L	5.0	5.0	1		05/21/24 19:06		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 19:06		
Alkalinity, Total as CaCO ₃	138	mg/L	5.0	5.0	1		05/21/24 19:06		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:12	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	10.1	mg/L	1.0	0.60	1		05/20/24 10:17	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92731696

Sample: HAM-AP1-FD-02		Lab ID: 92731696006		Collected: 05/15/24 00:00		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.26	mg/L	0.10	0.050	1		05/20/24 10:17	16984-48-8	
Sulfate	189	mg/L	4.0	2.0	4		05/20/24 20:43	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-INW-03 Lab ID: 92731696007 Collected: 05/14/24 14:08 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Sodium	12.4	mg/L	1.0	0.58	1	05/18/24 14:09	05/24/24 11:34	7440-23-5	
Iron	0.11	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 02:19	7439-89-6	
Manganese	0.45	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 02:19	7439-96-5	
Potassium	13.8	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 02:19	7440-09-7	
Calcium	127	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 02:19	7440-70-2	
Magnesium	17.1	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 02:19	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 16:41	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 16:41	7440-38-2	
Barium	0.075	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 16:41	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 16:41	7440-41-7	
Boron	1.5	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 16:41	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 16:41	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 16:41	7440-47-3	
Cobalt	0.00070J	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 16:41	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 16:41	7439-92-1	
Lithium	0.0050J	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 16:41	7439-93-2	
Molybdenum	0.082	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 16:41	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 16:41	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 16:41	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:04	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	564	mg/L	25.0	25.0	1		05/20/24 12:16		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	175	mg/L	5.0	5.0	1		05/21/24 16:31		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 16:31		
Alkalinity, Total as CaCO3	175	mg/L	5.0	5.0	1		05/21/24 16:31		M1
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/20/24 23:45	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	56.9	mg/L	1.0	0.60	1		05/21/24 00:39	16887-00-6	M1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92731696

Sample: HAM-INW-03		Lab ID: 92731696007		Collected: 05/14/24 14:08		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.20	mg/L	0.10	0.050	1		05/21/24 00:39	16984-48-8	
Sulfate	178	mg/L	4.0	2.0	4		05/21/24 08:01	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-INW-04		Lab ID: 92731696008		Collected: 05/15/24 14:20		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	8.4	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:35	7439-89-6	
Manganese	4.4	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:35	7439-96-5	
Potassium	4.8	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:35	7440-09-7	
Sodium	7.0	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:35	7440-23-5	
Calcium	107	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:35	7440-70-2	
Magnesium	13.1	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:35	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 15:49	7440-36-0	
Arsenic	0.19	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 15:49	7440-38-2	
Barium	0.043	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 15:49	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 15:49	7440-41-7	
Boron	0.59	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 15:49	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 15:49	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 15:49	7440-47-3	
Cobalt	0.031	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 15:49	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 15:49	7439-92-1	
Lithium	0.043	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 15:49	7439-93-2	
Molybdenum	0.015	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 15:49	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 15:49	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 15:49	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:07	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	483	mg/L	25.0	25.0	1		05/20/24 12:19		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	133	mg/L	5.0	5.0	1		05/21/24 19:16		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 19:16		
Alkalinity, Total as CaCO3	133	mg/L	5.0	5.0	1		05/21/24 19:16		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:13	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	9.9	mg/L	1.0	0.60	1		05/21/24 01:48	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92731696

Sample: HAM-INW-04		Lab ID: 92731696008		Collected: 05/15/24 14:20		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.28	mg/L	0.10	0.050	1		05/21/24 01:48	16984-48-8	
Sulfate	187	mg/L	4.0	2.0	4		05/21/24 08:42	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-INW-05		Lab ID: 92731696009		Collected: 05/15/24 11:18		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	16.9	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:38	7439-89-6	
Manganese	3.3	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:38	7439-96-5	
Potassium	4.7	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:38	7440-09-7	
Sodium	6.7	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:38	7440-23-5	
Calcium	101	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:38	7440-70-2	
Magnesium	11.8	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:38	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 15:53	7440-36-0	
Arsenic	0.23	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 15:53	7440-38-2	
Barium	0.033	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 15:53	7440-39-3	
Beryllium	0.00012J	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 15:53	7440-41-7	
Boron	0.51	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 15:53	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 15:53	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 15:53	7440-47-3	
Cobalt	0.026	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 15:53	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 15:53	7439-92-1	
Lithium	0.057	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 15:53	7439-93-2	
Molybdenum	0.0096J	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 15:53	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 15:53	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 15:53	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:09	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	456	mg/L	25.0	25.0	1		05/20/24 12:20		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	123	mg/L	5.0	5.0	1		05/21/24 19:25		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 19:25		
Alkalinity, Total as CaCO3	123	mg/L	5.0	5.0	1		05/21/24 19:25		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:13	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	6.9	mg/L	1.0	0.60	1		05/21/24 02:02	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92731696

Sample: HAM-INW-05		Lab ID: 92731696009		Collected: 05/15/24 11:18		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.37	mg/L	0.10	0.050	1		05/21/24 02:02	16984-48-8	
Sulfate	181	mg/L	4.0	2.0	4		05/21/24 08:56	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-07 Lab ID: 92731696010 Collected: 05/16/24 12:16 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	15.7	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:41	7439-89-6	
Manganese	3.4	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:41	7439-96-5	
Potassium	4.9	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:41	7440-09-7	
Sodium	7.0	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:41	7440-23-5	
Calcium	96.0	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:41	7440-70-2	
Magnesium	12.1	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:41	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 15:56	7440-36-0	
Arsenic	0.27	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 15:56	7440-38-2	
Barium	0.034	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 15:56	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 15:56	7440-41-7	
Boron	0.50	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 15:56	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 15:56	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 15:56	7440-47-3	
Cobalt	0.052	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 15:56	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 15:56	7439-92-1	
Lithium	0.056	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 15:56	7439-93-2	
Molybdenum	0.0093J	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 15:56	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 15:56	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 15:56	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:12	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	450	mg/L	25.0	25.0	1		05/20/24 12:22		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	116	mg/L	5.0	5.0	1		05/28/24 17:56		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/28/24 17:56		
Alkalinity, Total as CaCO3	116	mg/L	5.0	5.0	1		05/28/24 17:56		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:16	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	10	mg/L	1.0	0.60	1		05/21/24 02:16	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-07		Lab ID: 92731696010		Collected: 05/16/24 12:16		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.31	mg/L	0.10	0.050	1		05/21/24 02:16	16984-48-8	
Sulfate	171	mg/L	4.0	2.0	4		05/21/24 09:10	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-08 Lab ID: 92731696011 Collected: 05/16/24 10:37 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	8.0	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:45	7439-89-6	
Manganese	3.3	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:45	7439-96-5	
Potassium	4.8	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:45	7440-09-7	
Sodium	7.2	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:45	7440-23-5	
Calcium	89.4	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:45	7440-70-2	
Magnesium	11.5	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:45	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 16:00	7440-36-0	
Arsenic	0.23	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 16:00	7440-38-2	
Barium	0.041	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 16:00	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 16:00	7440-41-7	
Boron	0.73	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 16:00	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 16:00	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 16:00	7440-47-3	
Cobalt	0.046	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 16:00	7440-48-4	
Lead	0.0079	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 16:00	7439-92-1	
Lithium	0.010J	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 16:00	7439-93-2	
Molybdenum	0.017	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 16:00	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 16:00	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 16:00	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:14	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	410	mg/L	25.0	25.0	1		05/20/24 12:22		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	104	mg/L	5.0	5.0	1		05/28/24 18:06		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/28/24 18:06		
Alkalinity, Total as CaCO3	104	mg/L	5.0	5.0	1		05/28/24 18:06		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:17	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	16.7	mg/L	1.0	0.60	1		05/21/24 20:59	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92731696

Sample: HAM-PT-08		Lab ID: 92731696011		Collected: 05/16/24 10:37		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.19	mg/L	0.10	0.050	1		05/21/24 20:59	16984-48-8	
Sulfate	159	mg/L	4.0	2.0	4		05/22/24 07:35	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-09 Lab ID: 92731696012 Collected: 05/14/24 10:40 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.42	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:48	7439-89-6	
Manganese	0.19	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:48	7439-96-5	
Potassium	6.1	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:48	7440-09-7	
Sodium	9.3	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:48	7440-23-5	
Calcium	82.8	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:48	7440-70-2	
Magnesium	23.7	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:48	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 16:04	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 16:04	7440-38-2	
Barium	0.058	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 16:04	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 16:04	7440-41-7	
Boron	1.4	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 16:04	7440-42-8	
Cadmium	0.00015J	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 16:04	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 16:04	7440-47-3	
Cobalt	0.0012J	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 16:04	7440-48-4	
Lead	0.00017J	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 16:04	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 16:04	7439-93-2	
Molybdenum	0.27	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 16:04	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 16:04	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 16:04	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:17	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	436	mg/L	25.0	25.0	1		05/20/24 12:17		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	139	mg/L	5.0	5.0	1		05/21/24 17:10		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 17:10		
Alkalinity, Total as CaCO3	139	mg/L	5.0	5.0	1		05/21/24 17:10		M1
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/20/24 23:46	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	44.4	mg/L	1.0	0.60	1		05/21/24 02:29	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92731696

Sample: HAM-PT-09		Lab ID: 92731696012		Collected: 05/14/24 10:40		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.37	mg/L	0.10	0.050	1		05/21/24 02:29	16984-48-8	
Sulfate	130	mg/L	3.0	1.5	3		05/21/24 10:07	14808-79-8	M1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-10 Lab ID: 92731696013 Collected: 05/15/24 11:52 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.24	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:51	7439-89-6	
Manganese	0.74	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:51	7439-96-5	
Potassium	6.7	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:51	7440-09-7	
Sodium	9.2	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:51	7440-23-5	
Calcium	108	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:51	7440-70-2	
Magnesium	14.3	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:51	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 16:07	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 16:07	7440-38-2	
Barium	0.054	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 16:07	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 16:07	7440-41-7	
Boron	1.5	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 16:07	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 16:07	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 16:07	7440-47-3	
Cobalt	0.0016J	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 16:07	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 16:07	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 16:07	7439-93-2	
Molybdenum	0.092	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 16:07	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 16:07	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 16:07	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:25	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	503	mg/L	25.0	25.0	1		05/20/24 12:20		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	132	mg/L	5.0	5.0	1		05/21/24 19:35		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 19:35		
Alkalinity, Total as CaCO3	132	mg/L	5.0	5.0	1		05/21/24 19:35		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:13	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	50.1	mg/L	1.0	0.60	1		05/21/24 03:11	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92731696

Sample: HAM-PT-10		Lab ID: 92731696013		Collected: 05/15/24 11:52		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.22	mg/L	0.10	0.050	1		05/21/24 03:11	16984-48-8	
Sulfate	146	mg/L	3.0	1.5	3		05/21/24 10:48	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-11 Lab ID: 92731696014 Collected: 05/14/24 15:20 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:55	7439-89-6	
Manganese	0.28	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:55	7439-96-5	
Potassium	6.0	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:55	7440-09-7	
Sodium	8.8	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:55	7440-23-5	
Calcium	90.9	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:55	7440-70-2	
Magnesium	16.2	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:55	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 16:11	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 16:11	7440-38-2	
Barium	0.057	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 16:11	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 16:11	7440-41-7	
Boron	1.6	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 16:11	7440-42-8	
Cadmium	0.00013J	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 16:11	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 16:11	7440-47-3	
Cobalt	0.0016J	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 16:11	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 16:11	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 16:11	7439-93-2	
Molybdenum	0.24	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 16:11	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 16:11	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 16:11	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:28	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	441	mg/L	25.0	25.0	1		05/20/24 12:17		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	125	mg/L	5.0	5.0	1		05/21/24 17:33		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 17:33		
Alkalinity, Total as CaCO3	125	mg/L	5.0	5.0	1		05/21/24 17:33		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/20/24 23:46	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	41.4	mg/L	1.0	0.60	1		05/21/24 03:25	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92731696

Sample: HAM-PT-11		Lab ID: 92731696014		Collected: 05/14/24 15:20		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.34	mg/L	0.10	0.050	1		05/21/24 03:25	16984-48-8	
Sulfate	122	mg/L	3.0	1.5	3		05/21/24 11:03	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-12		Lab ID: 92731696015		Collected: 05/14/24 12:05		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.33	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:59	7439-89-6	
Manganese	1.0	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:59	7439-96-5	
Potassium	6.8	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:59	7440-09-7	
Sodium	11.8	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:59	7440-23-5	
Calcium	99.7	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:59	7440-70-2	
Magnesium	16.6	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:59	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 16:15	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 16:15	7440-38-2	
Barium	0.069	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 16:15	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 16:15	7440-41-7	
Boron	1.6	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 16:15	7440-42-8	
Cadmium	0.00014J	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 16:15	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 16:15	7440-47-3	
Cobalt	0.0044J	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 16:15	7440-48-4	
Lead	0.00017J	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 16:15	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 16:15	7439-93-2	
Molybdenum	0.085	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 16:15	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 16:15	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 16:15	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:30	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	523	mg/L	25.0	25.0	1		05/20/24 12:17		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	129	mg/L	5.0	5.0	1		05/21/24 17:51		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 17:51		
Alkalinity, Total as CaCO3	129	mg/L	5.0	5.0	1		05/21/24 17:51		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/20/24 23:47	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	50.3	mg/L	1.0	0.60	1		05/21/24 03:38	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92731696

Sample: HAM-PT-12		Lab ID: 92731696015		Collected: 05/14/24 12:05		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.20	mg/L	0.10	0.050	1		05/21/24 03:38	16984-48-8	
Sulfate	125	mg/L	3.0	1.5	3		05/21/24 11:17	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-13 Lab ID: 92731696016 Collected: 05/15/24 18:45 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	15.0	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 02:02	7439-89-6	
Manganese	3.6	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 02:02	7439-96-5	
Potassium	5.0	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 02:02	7440-09-7	
Sodium	7.8	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 02:02	7440-23-5	
Calcium	99.2	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 02:02	7440-70-2	
Magnesium	12.0	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 02:02	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 16:19	7440-36-0	
Arsenic	0.29	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 16:19	7440-38-2	
Barium	0.033	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 16:19	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 16:19	7440-41-7	
Boron	0.52	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 16:19	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 16:19	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 16:19	7440-47-3	
Cobalt	0.024	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 16:19	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 16:19	7439-92-1	
Lithium	0.058	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 16:19	7439-93-2	
Molybdenum	0.0087J	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 16:19	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 16:19	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 16:19	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:33	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	459	mg/L	25.0	25.0	1		05/20/24 12:21		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	111	mg/L	5.0	5.0	1		05/21/24 19:44		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 19:44		
Alkalinity, Total as CaCO3	111	mg/L	5.0	5.0	1		05/21/24 19:44		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:14	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	9.5	mg/L	1.0	0.60	1		05/21/24 04:20	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92731696

Sample: HAM-PT-13		Lab ID: 92731696016		Collected: 05/15/24 18:45		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.34	mg/L	0.10	0.050	1		05/21/24 04:20	16984-48-8	
Sulfate	190	mg/L	4.0	2.0	4		05/21/24 11:31	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-14		Lab ID: 92731696017		Collected: 05/15/24 18:27		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	14.9	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 02:05	7439-89-6	
Manganese	3.1	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 02:05	7439-96-5	
Potassium	5.0	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 02:05	7440-09-7	
Sodium	6.7	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 02:05	7440-23-5	
Calcium	97.4	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 02:05	7440-70-2	
Magnesium	12.7	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 02:05	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 16:33	7440-36-0	
Arsenic	0.21	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 16:33	7440-38-2	
Barium	0.038	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 16:33	7440-39-3	
Beryllium	0.00016J	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 16:33	7440-41-7	
Boron	0.51	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 16:33	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 16:33	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 16:33	7440-47-3	
Cobalt	0.020	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 16:33	7440-48-4	
Lead	0.00046J	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 16:33	7439-92-1	
Lithium	0.051	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 16:33	7439-93-2	
Molybdenum	0.011	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 16:33	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 16:33	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 16:33	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:35	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	461	mg/L	25.0	25.0	1		05/20/24 12:21		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	121	mg/L	5.0	5.0	1		05/21/24 19:53		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 19:53		
Alkalinity, Total as CaCO3	121	mg/L	5.0	5.0	1		05/21/24 19:53		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:14	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	10.5	mg/L	1.0	0.60	1		05/21/24 04:34	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92731696

Sample: HAM-PT-14		Lab ID: 92731696017		Collected: 05/15/24 18:27		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.26	mg/L	0.10	0.050	1		05/21/24 04:34	16984-48-8	
Sulfate	175	mg/L	4.0	2.0	4		05/21/24 11:44	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-15		Lab ID: 92731696018		Collected: 05/15/24 16:10		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Sodium	8.1	mg/L	1.0	0.58	1	05/18/24 14:09	05/24/24 11:31	7440-23-5	
Iron	9.2	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 02:16	7439-89-6	
Manganese	5.7	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 02:16	7439-96-5	
Potassium	5.3	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 02:16	7440-09-7	
Calcium	141	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 02:16	7440-70-2	
Magnesium	16.1	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 02:16	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 16:37	7440-36-0	
Arsenic	0.39	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 16:37	7440-38-2	
Barium	0.043	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 16:37	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 16:37	7440-41-7	
Boron	0.76	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 16:37	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 16:37	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 16:37	7440-47-3	
Cobalt	0.059	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 16:37	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 16:37	7439-92-1	
Lithium	0.047	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 16:37	7439-93-2	
Molybdenum	0.021	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 16:37	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 16:37	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 16:37	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:38	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	639	mg/L	25.0	25.0	1		05/20/24 12:22		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	134	mg/L	5.0	5.0	1		05/21/24 20:02		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 20:02		
Alkalinity, Total as CaCO ₃	134	mg/L	5.0	5.0	1		05/21/24 20:02		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:15	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	12.6	mg/L	1.0	0.60	1		05/21/24 04:48	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92731696

Sample: HAM-PT-15		Lab ID: 92731696018		Collected: 05/15/24 16:10		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.35	mg/L	0.10	0.050	1		05/21/24 04:48	16984-48-8	
Sulfate	271	mg/L	6.0	3.0	6		05/21/24 11:58	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch:	855608	Analysis Method:	EPA 6010D
QC Batch Method:	EPA 3010A	Analysis Description:	6010D ATL
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696010, 92731696011, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018		

METHOD BLANK:	4414794	Matrix:	Water
Associated Lab Samples:	92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696010, 92731696011, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	05/23/24 00:42	
Iron	mg/L	ND	0.040	0.025	05/23/24 00:42	
Magnesium	mg/L	ND	0.050	0.012	05/23/24 00:42	
Manganese	mg/L	ND	0.040	0.011	05/23/24 00:42	
Potassium	mg/L	ND	0.50	0.15	05/23/24 00:42	
Sodium	mg/L	ND	1.0	0.58	05/23/24 00:42	

LABORATORY CONTROL SAMPLE: 4414795

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	1.0	101	80-120	
Iron	mg/L	1	1.0	101	80-120	
Magnesium	mg/L	1	1.0	103	80-120	
Manganese	mg/L	1	0.99	99	80-120	
Potassium	mg/L	1	1.0	103	80-120	
Sodium	mg/L	1	1.0	100	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4414796 4414797

Parameter	Units	92731696001		MS		MSD		MS		MSD		% Rec		Max RPD	Qual
		Result	Conc.	Spike Conc.	Result	Spike Conc.	Result	% Rec	Result	% Rec	Result	Limits	RPD		
Calcium	mg/L	ND	1	1	1.0J	1.0	99	100	75-125	1	20				
Iron	mg/L	ND	1	1	0.99	1.0	99	100	75-125	1	20				
Magnesium	mg/L	ND	1	1	1.0	1.0	103	103	75-125	0	20				
Manganese	mg/L	ND	1	1	0.99	0.99	99	99	75-125	1	20				
Potassium	mg/L	ND	1	1	0.98	1.0	97	99	75-125	2	20				
Sodium	mg/L	ND	1	1	1.3	1.3	103	100	75-125	2	20				

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1
Pace Project No.: 92731696

QC Batch: 855534 Analysis Method: EPA 6020B
QC Batch Method: EPA 3005A Analysis Description: 6020 MET
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696010, 92731696011, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018

METHOD BLANK: 4414417 Matrix: Water
Associated Lab Samples: 92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696010, 92731696011, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00054	05/22/24 14:58	
Arsenic	mg/L	ND	0.0050	0.00084	05/22/24 14:58	
Barium	mg/L	ND	0.0050	0.00047	05/22/24 14:58	
Beryllium	mg/L	ND	0.00050	0.000094	05/22/24 14:58	
Boron	mg/L	ND	0.040	0.012	05/22/24 14:58	
Cadmium	mg/L	ND	0.00050	0.00010	05/22/24 14:58	
Chromium	mg/L	ND	0.0050	0.0019	05/22/24 14:58	
Cobalt	mg/L	ND	0.0050	0.00032	05/22/24 14:58	
Lead	mg/L	ND	0.0010	0.00016	05/22/24 14:58	
Lithium	mg/L	ND	0.030	0.0016	05/22/24 14:58	
Molybdenum	mg/L	ND	0.010	0.00062	05/22/24 14:58	
Selenium	mg/L	ND	0.0050	0.00096	05/22/24 14:58	
Thallium	mg/L	ND	0.0010	0.00038	05/22/24 14:58	

LABORATORY CONTROL SAMPLE: 4414418

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.11	106	80-120	
Arsenic	mg/L	0.1	0.10	101	80-120	
Barium	mg/L	0.1	0.10	101	80-120	
Beryllium	mg/L	0.1	0.10	104	80-120	
Boron	mg/L	1	1.0	103	80-120	
Cadmium	mg/L	0.1	0.10	103	80-120	
Chromium	mg/L	0.1	0.10	103	80-120	
Cobalt	mg/L	0.1	0.10	101	80-120	
Lead	mg/L	0.1	0.10	104	80-120	
Lithium	mg/L	0.1	0.11	106	80-120	
Molybdenum	mg/L	0.1	0.10	105	80-120	
Selenium	mg/L	0.1	0.10	101	80-120	
Thallium	mg/L	0.1	0.10	100	80-120	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4414419 4414420												
Parameter	Units	92731696001 Result	MS	MSD	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
			Spike Conc.	Spike Conc.								
Antimony	mg/L	ND	0.1	0.1	0.10	0.10	105	103	75-125	1	20	
Arsenic	mg/L	ND	0.1	0.1	0.098	0.099	98	99	75-125	1	20	
Barium	mg/L	ND	0.1	0.1	0.10	0.098	100	98	75-125	2	20	
Beryllium	mg/L	ND	0.1	0.1	0.10	0.10	102	102	75-125	0	20	
Boron	mg/L	ND	1	1	1.0	1.0	101	100	75-125	1	20	
Cadmium	mg/L	ND	0.1	0.1	0.10	0.10	100	100	75-125	0	20	
Chromium	mg/L	ND	0.1	0.1	0.099	0.098	99	98	75-125	1	20	
Cobalt	mg/L	ND	0.1	0.1	0.098	0.099	98	99	75-125	1	20	
Lead	mg/L	ND	0.1	0.1	0.10	0.10	100	101	75-125	1	20	
Lithium	mg/L	ND	0.1	0.1	0.10	0.10	104	104	75-125	0	20	
Molybdenum	mg/L	ND	0.1	0.1	0.10	0.10	102	101	75-125	1	20	
Selenium	mg/L	ND	0.1	0.1	0.097	0.098	97	98	75-125	1	20	
Thallium	mg/L	ND	0.1	0.1	0.097	0.099	97	98	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1
Pace Project No.: 92731696

QC Batch: 856966 Analysis Method: EPA 7470A
QC Batch Method: EPA 7470A Analysis Description: 7470 Mercury
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696010, 92731696011, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018

METHOD BLANK: 4421300 Matrix: Water
Associated Lab Samples: 92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696010, 92731696011, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	05/24/24 12:26	

LABORATORY CONTROL SAMPLE: 4421301

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0024	97	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4421302 4421303

Parameter	Units	92731696002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.0025	0.0025	0.0024	0.0024	95	95	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch:	855801	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696010, 92731696011, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018		

METHOD BLANK:	4415457	Matrix:	Water
Associated Lab Samples:	92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696010, 92731696011, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	05/20/24 12:16	

LABORATORY CONTROL SAMPLE:	4415458					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	396	99	80-120	

SAMPLE DUPLICATE:	4415459					
Parameter	Units	92731696007 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	564	575	2	10	

SAMPLE DUPLICATE:	4415460					
Parameter	Units	92731696008 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	483	478	1	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch:	856180	Analysis Method:	SM 2320B-2011
QC Batch Method:	SM 2320B-2011	Analysis Description:	2320B Alkalinity
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018		

METHOD BLANK:	4417200	Matrix:	Water
Associated Lab Samples:	92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	05/21/24 16:14	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/21/24 16:14	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/21/24 16:14	

LABORATORY CONTROL SAMPLE:	4417201					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.4	103	80-120	

LABORATORY CONTROL SAMPLE:	4417202					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	49.9	100	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:	4417203			4417204								
Parameter	Units	92731696007 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	175	50	50	214	211	79	72	80-120	2	25	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:	4417205			4417206								
Parameter	Units	92731696012 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	139	50	50	181	177	83	77	80-120	2	25	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch: 857348

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92731696010, 92731696011

METHOD BLANK: 4422747

Matrix: Water

Associated Lab Samples: 92731696010, 92731696011

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	05/28/24 16:34	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/28/24 16:34	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/28/24 16:34	

LABORATORY CONTROL SAMPLE: 4422748

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	50.4	101	80-120	

LABORATORY CONTROL SAMPLE: 4422749

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	50.0	100	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4422750 4422751

Parameter	Units	92731615001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	75300 ug/L	50	50	124	125	98	99	80-120	0	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4422752 4422753

Parameter	Units	92732006003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	766	50	50	804	820	76	109	80-120	2	25	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch: 855942 Analysis Method: SM 4500-S2D-2011
QC Batch Method: SM 4500-S2D-2011 Analysis Description: 4500S2D Sulfide Water
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92731696007, 92731696012, 92731696014, 92731696015

METHOD BLANK: 4416179 Matrix: Water
Associated Lab Samples: 92731696007, 92731696012, 92731696014, 92731696015

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	05/20/24 23:35	

LABORATORY CONTROL SAMPLE: 4416180

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.53	105	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4416181 4416182

Parameter	Units	92731245002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.55	0.55	106	106	80-120	0	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch:	856274	Analysis Method:	SM 4500-S2D-2011
QC Batch Method:	SM 4500-S2D-2011	Analysis Description:	4500S2D Sulfide Water
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92731696001, 92731696003, 92731696004, 92731696005, 92731696006, 92731696008, 92731696009, 92731696010, 92731696011, 92731696013, 92731696016, 92731696017, 92731696018		

METHOD BLANK:	4417824	Matrix:	Water
Associated Lab Samples:	92731696001, 92731696003, 92731696004, 92731696005, 92731696006, 92731696008, 92731696009, 92731696010, 92731696011, 92731696013, 92731696016, 92731696017, 92731696018		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	05/22/24 05:06	

LABORATORY CONTROL SAMPLE: 4417825						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.45	89	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:												
4417826					4417827							
		92731245003	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Parameter	Units	Result										
Sulfide	mg/L	ND	0.5	0.5	0.49	0.49	94	95	80-120	1	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:													4417828		4417829	
Parameter	Units	92731696001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual				
Sulfide	mg/L	ND	0.5	0.5	0.48	0.50	96	100	80-120	4	10					

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch: 856275

Analysis Method: SM 4500-S2D-2011

QC Batch Method: SM 4500-S2D-2011

Analysis Description: 4500S2D Sulfide Water

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92731696002

METHOD BLANK: 4417830

Matrix: Water

Associated Lab Samples: 92731696002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	05/22/24 05:18	

LABORATORY CONTROL SAMPLE: 4417831

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.49	98	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4417832 4417833

Parameter	Units	92731696002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.49	0.48	99	97	80-120	2	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch: 855697 Analysis Method: EPA 300.0 Rev 2.1 1993
QC Batch Method: EPA 300.0 Rev 2.1 1993 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92731696001, 92731696002, 92731696004, 92731696006

METHOD BLANK: 4415009 Matrix: Water
Associated Lab Samples: 92731696001, 92731696002, 92731696004, 92731696006

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	05/20/24 00:22	
Fluoride	mg/L	ND	0.10	0.050	05/20/24 00:22	
Sulfate	mg/L	ND	1.0	0.50	05/20/24 00:22	

LABORATORY CONTROL SAMPLE: 4415010

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	49.3	99	90-110	
Fluoride	mg/L	2.5	2.4	97	90-110	
Sulfate	mg/L	50	49.1	98	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4415011 4415012

Parameter	Units	92731542009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	151	50	50	199	199	95	96	90-110	0	10	
Fluoride	mg/L	0.081J	2.5	2.5	2.7	2.7	104	103	90-110	1	10	
Sulfate	mg/L	3.0	50	50	55.7	55.2	105	104	90-110	1	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4415013 4415014

Parameter	Units	92731735001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	492	50	50	530	529	75	74	90-110	0	10	M1
Fluoride	mg/L	ND	2.5	2.5	ND	ND	0	0	90-110		10	M1
Sulfate	mg/L	16.9	50	50	70.8	69.6	108	105	90-110	2	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch:	855920	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92731696007, 92731696008, 92731696009, 92731696010, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018		

METHOD BLANK:	4416092	Matrix:	Water
Associated Lab Samples:	92731696007, 92731696008, 92731696009, 92731696010, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	05/20/24 20:15	
Fluoride	mg/L	ND	0.10	0.050	05/20/24 20:15	
Sulfate	mg/L	ND	1.0	0.50	05/20/24 20:15	

LABORATORY CONTROL SAMPLE: 4416093						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	53.3	107	90-110	
Fluoride	mg/L	2.5	2.6	103	90-110	
Sulfate	mg/L	50	53.5	107	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4416094 4416095												
Parameter	Units	92731696007 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	56.9	50	50	97.8	98.5	82	83	90-110	1	10	M1
Fluoride	mg/L	0.20	2.5	2.5	2.7	2.7	99	102	90-110	2	10	
Sulfate	mg/L	178	50	50	224	225	93	93	90-110	0	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4416096 4416097												
Parameter	Units	92731696012 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	44.4	50	50	96.7	97.9	105	107	90-110	1	10	
Fluoride	mg/L	0.37	2.5	2.5	2.9	2.9	100	103	90-110	2	10	
Sulfate	mg/L	130	50	50	175	177	89	94	90-110	1	10	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch: 856238

Analysis Method: EPA 300.0 Rev 2.1 1993

QC Batch Method: EPA 300.0 Rev 2.1 1993

Analysis Description: 300.0 IC Anions

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92731696011

METHOD BLANK: 4417658

Matrix: Water

Associated Lab Samples: 92731696011

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	05/21/24 20:18	
Fluoride	mg/L	ND	0.10	0.050	05/21/24 20:18	
Sulfate	mg/L	ND	1.0	0.50	05/21/24 20:18	

LABORATORY CONTROL SAMPLE: 4417659

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	52.0	104	90-110	
Fluoride	mg/L	2.5	2.6	102	90-110	
Sulfate	mg/L	50	52.1	104	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4417660 4417661

Parameter	Units	92732137001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	533	50	50	569	579	73	92	90-110	2	10	M1
Fluoride	mg/L	0.74	2.5	2.5	2.3	2.4	64	66	90-110	2	10	M1
Sulfate	mg/L	357	50	50	398	404	81	95	90-110	2	10	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4417662 4417663

Parameter	Units	92732121002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	4.5	50	50	58.4	60.2	108	111	90-110	3	10	M1
Fluoride	mg/L	0.061J	2.5	2.5	2.6	2.7	101	106	90-110	5	10	
Sulfate	mg/L	88.0	50	50	125	128	74	79	90-110	2	10	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch: 860766 Analysis Method: EPA 300.0 Rev 2.1 1993
QC Batch Method: EPA 300.0 Rev 2.1 1993 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92731696003, 92731696005

METHOD BLANK: 4439360 Matrix: Water

Associated Lab Samples: 92731696003, 92731696005

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	06/12/24 12:57	
Fluoride	mg/L	ND	0.10	0.050	06/12/24 12:57	
Sulfate	mg/L	ND	1.0	0.50	06/12/24 12:57	

LABORATORY CONTROL SAMPLE: 4439361

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	51.5	103	90-110	
Fluoride	mg/L	2.5	2.6	105	90-110	
Sulfate	mg/L	50	51.5	103	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4439362 4439363

Parameter	Units	92735940001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	14.2	50	50	64.9	65.3	101	102	90-110	1	10	
Fluoride	mg/L	0.056J	2.5	2.5	2.7	2.7	104	105	90-110	1	10	
Sulfate	mg/L	11.5	50	50	62.8	63.0	103	103	90-110	0	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1

Pace Project No.: 92731696

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above adjusted reporting limit.

TNTC - Too Numerous To Count

J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

MDL - Adjusted Method Detection Limit.

PQL - Practical Quantitation Limit.

RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected.

Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.

A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

ANALYTE QUALIFIERS

M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92731696

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92731696001	HAM-AP1-EB-01	EPA 3010A	855608	EPA 6010D	855649
92731696002	HAM-AP1-EB-02	EPA 3010A	855608	EPA 6010D	855649
92731696003	HAM-AP1-FB-01	EPA 3010A	855608	EPA 6010D	855649
92731696004	HAM-AP1-FB-02	EPA 3010A	855608	EPA 6010D	855649
92731696005	HAM-AP1-FD-01	EPA 3010A	855608	EPA 6010D	855649
92731696006	HAM-AP1-FD-02	EPA 3010A	855608	EPA 6010D	855649
92731696007	HAM-INW-03	EPA 3010A	855608	EPA 6010D	855649
92731696008	HAM-INW-04	EPA 3010A	855608	EPA 6010D	855649
92731696009	HAM-INW-05	EPA 3010A	855608	EPA 6010D	855649
92731696010	HAM-PT-07	EPA 3010A	855608	EPA 6010D	855649
92731696011	HAM-PT-08	EPA 3010A	855608	EPA 6010D	855649
92731696012	HAM-PT-09	EPA 3010A	855608	EPA 6010D	855649
92731696013	HAM-PT-10	EPA 3010A	855608	EPA 6010D	855649
92731696014	HAM-PT-11	EPA 3010A	855608	EPA 6010D	855649
92731696015	HAM-PT-12	EPA 3010A	855608	EPA 6010D	855649
92731696016	HAM-PT-13	EPA 3010A	855608	EPA 6010D	855649
92731696017	HAM-PT-14	EPA 3010A	855608	EPA 6010D	855649
92731696018	HAM-PT-15	EPA 3010A	855608	EPA 6010D	855649
92731696001	HAM-AP1-EB-01	EPA 3005A	855534	EPA 6020B	855663
92731696002	HAM-AP1-EB-02	EPA 3005A	855534	EPA 6020B	855663
92731696003	HAM-AP1-FB-01	EPA 3005A	855534	EPA 6020B	855663
92731696004	HAM-AP1-FB-02	EPA 3005A	855534	EPA 6020B	855663
92731696005	HAM-AP1-FD-01	EPA 3005A	855534	EPA 6020B	855663
92731696006	HAM-AP1-FD-02	EPA 3005A	855534	EPA 6020B	855663
92731696007	HAM-INW-03	EPA 3005A	855534	EPA 6020B	855663
92731696008	HAM-INW-04	EPA 3005A	855534	EPA 6020B	855663
92731696009	HAM-INW-05	EPA 3005A	855534	EPA 6020B	855663
92731696010	HAM-PT-07	EPA 3005A	855534	EPA 6020B	855663
92731696011	HAM-PT-08	EPA 3005A	855534	EPA 6020B	855663
92731696012	HAM-PT-09	EPA 3005A	855534	EPA 6020B	855663
92731696013	HAM-PT-10	EPA 3005A	855534	EPA 6020B	855663
92731696014	HAM-PT-11	EPA 3005A	855534	EPA 6020B	855663
92731696015	HAM-PT-12	EPA 3005A	855534	EPA 6020B	855663
92731696016	HAM-PT-13	EPA 3005A	855534	EPA 6020B	855663
92731696017	HAM-PT-14	EPA 3005A	855534	EPA 6020B	855663
92731696018	HAM-PT-15	EPA 3005A	855534	EPA 6020B	855663
92731696001	HAM-AP1-EB-01	EPA 7470A	856966	EPA 7470A	856985
92731696002	HAM-AP1-EB-02	EPA 7470A	856966	EPA 7470A	856985
92731696003	HAM-AP1-FB-01	EPA 7470A	856966	EPA 7470A	856985
92731696004	HAM-AP1-FB-02	EPA 7470A	856966	EPA 7470A	856985
92731696005	HAM-AP1-FD-01	EPA 7470A	856966	EPA 7470A	856985
92731696006	HAM-AP1-FD-02	EPA 7470A	856966	EPA 7470A	856985
92731696007	HAM-INW-03	EPA 7470A	856966	EPA 7470A	856985
92731696008	HAM-INW-04	EPA 7470A	856966	EPA 7470A	856985
92731696009	HAM-INW-05	EPA 7470A	856966	EPA 7470A	856985
92731696010	HAM-PT-07	EPA 7470A	856966	EPA 7470A	856985
92731696011	HAM-PT-08	EPA 7470A	856966	EPA 7470A	856985
92731696012	HAM-PT-09	EPA 7470A	856966	EPA 7470A	856985

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92731696

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92731696013	HAM-PT-10	EPA 7470A	856966	EPA 7470A	856985
92731696014	HAM-PT-11	EPA 7470A	856966	EPA 7470A	856985
92731696015	HAM-PT-12	EPA 7470A	856966	EPA 7470A	856985
92731696016	HAM-PT-13	EPA 7470A	856966	EPA 7470A	856985
92731696017	HAM-PT-14	EPA 7470A	856966	EPA 7470A	856985
92731696018	HAM-PT-15	EPA 7470A	856966	EPA 7470A	856985
92731696001	HAM-AP1-EB-01	SM 2540C-2015	855801		
92731696002	HAM-AP1-EB-02	SM 2540C-2015	855801		
92731696003	HAM-AP1-FB-01	SM 2540C-2015	855801		
92731696004	HAM-AP1-FB-02	SM 2540C-2015	855801		
92731696005	HAM-AP1-FD-01	SM 2540C-2015	855801		
92731696006	HAM-AP1-FD-02	SM 2540C-2015	855801		
92731696007	HAM-INW-03	SM 2540C-2015	855801		
92731696008	HAM-INW-04	SM 2540C-2015	855801		
92731696009	HAM-INW-05	SM 2540C-2015	855801		
92731696010	HAM-PT-07	SM 2540C-2015	855801		
92731696011	HAM-PT-08	SM 2540C-2015	855801		
92731696012	HAM-PT-09	SM 2540C-2015	855801		
92731696013	HAM-PT-10	SM 2540C-2015	855801		
92731696014	HAM-PT-11	SM 2540C-2015	855801		
92731696015	HAM-PT-12	SM 2540C-2015	855801		
92731696016	HAM-PT-13	SM 2540C-2015	855801		
92731696017	HAM-PT-14	SM 2540C-2015	855801		
92731696018	HAM-PT-15	SM 2540C-2015	855801		
92731696001	HAM-AP1-EB-01	SM 2320B-2011	856180		
92731696002	HAM-AP1-EB-02	SM 2320B-2011	856180		
92731696003	HAM-AP1-FB-01	SM 2320B-2011	856180		
92731696004	HAM-AP1-FB-02	SM 2320B-2011	856180		
92731696005	HAM-AP1-FD-01	SM 2320B-2011	856180		
92731696006	HAM-AP1-FD-02	SM 2320B-2011	856180		
92731696007	HAM-INW-03	SM 2320B-2011	856180		
92731696008	HAM-INW-04	SM 2320B-2011	856180		
92731696009	HAM-INW-05	SM 2320B-2011	856180		
92731696010	HAM-PT-07	SM 2320B-2011	857348		
92731696011	HAM-PT-08	SM 2320B-2011	857348		
92731696012	HAM-PT-09	SM 2320B-2011	856180		
92731696013	HAM-PT-10	SM 2320B-2011	856180		
92731696014	HAM-PT-11	SM 2320B-2011	856180		
92731696015	HAM-PT-12	SM 2320B-2011	856180		
92731696016	HAM-PT-13	SM 2320B-2011	856180		
92731696017	HAM-PT-14	SM 2320B-2011	856180		
92731696018	HAM-PT-15	SM 2320B-2011	856180		
92731696001	HAM-AP1-EB-01	SM 4500-S2D-2011	856274		
92731696002	HAM-AP1-EB-02	SM 4500-S2D-2011	856275		
92731696003	HAM-AP1-FB-01	SM 4500-S2D-2011	856274		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92731696

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92731696004	HAM-AP1-FB-02	SM 4500-S2D-2011	856274		
92731696005	HAM-AP1-FD-01	SM 4500-S2D-2011	856274		
92731696006	HAM-AP1-FD-02	SM 4500-S2D-2011	856274		
92731696007	HAM-INW-03	SM 4500-S2D-2011	855942		
92731696008	HAM-INW-04	SM 4500-S2D-2011	856274		
92731696009	HAM-INW-05	SM 4500-S2D-2011	856274		
92731696010	HAM-PT-07	SM 4500-S2D-2011	856274		
92731696011	HAM-PT-08	SM 4500-S2D-2011	856274		
92731696012	HAM-PT-09	SM 4500-S2D-2011	855942		
92731696013	HAM-PT-10	SM 4500-S2D-2011	856274		
92731696014	HAM-PT-11	SM 4500-S2D-2011	855942		
92731696015	HAM-PT-12	SM 4500-S2D-2011	855942		
92731696016	HAM-PT-13	SM 4500-S2D-2011	856274		
92731696017	HAM-PT-14	SM 4500-S2D-2011	856274		
92731696018	HAM-PT-15	SM 4500-S2D-2011	856274		
92731696001	HAM-AP1-EB-01	EPA 300.0 Rev 2.1 1993	855697		
92731696002	HAM-AP1-EB-02	EPA 300.0 Rev 2.1 1993	855697		
92731696003	HAM-AP1-FB-01	EPA 300.0 Rev 2.1 1993	860766		
92731696004	HAM-AP1-FB-02	EPA 300.0 Rev 2.1 1993	855697		
92731696005	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	860766		
92731696006	HAM-AP1-FD-02	EPA 300.0 Rev 2.1 1993	855697		
92731696007	HAM-INW-03	EPA 300.0 Rev 2.1 1993	855920		
92731696008	HAM-INW-04	EPA 300.0 Rev 2.1 1993	855920		
92731696009	HAM-INW-05	EPA 300.0 Rev 2.1 1993	855920		
92731696010	HAM-PT-07	EPA 300.0 Rev 2.1 1993	855920		
92731696011	HAM-PT-08	EPA 300.0 Rev 2.1 1993	856238		
92731696012	HAM-PT-09	EPA 300.0 Rev 2.1 1993	855920		
92731696013	HAM-PT-10	EPA 300.0 Rev 2.1 1993	855920		
92731696014	HAM-PT-11	EPA 300.0 Rev 2.1 1993	855920		
92731696015	HAM-PT-12	EPA 300.0 Rev 2.1 1993	855920		
92731696016	HAM-PT-13	EPA 300.0 Rev 2.1 1993	855920		
92731696017	HAM-PT-14	EPA 300.0 Rev 2.1 1993	855920		
92731696018	HAM-PT-15	EPA 300.0 Rev 2.1 1993	855920		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



DC# Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

Project #

WO#: 92731696

Courier:
☐ Commercial☐ Fed Ex
☒ Pace☐ UPS☐ USPS
☐ Other☐ Client

Custody Seal Present?

☒ Yes☐ No

Seals Intact?

☒ Yes☐ No☐ N/A

Date/Initials Person Examining Contents: 5/17/18 JCC

Packing Material:

☒ Bubble Wrap☐ Bubble Bags☐ None☐ Other

Biological Tissue Frozen?

☐ Yes☐ No☒ N/A

Thermometer:

☒ In Gun ID:

250

Type of Ice:

☒ Dry Ice☐ Blue☐ None

Cooler Temp:

3.1

Correction Factor:

Add/Subtract (°C)

0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

3.1

USDA Regulated Soil (☐ N/A, water sample)

Did samples originate in a quarantine zone within the United States: CA, NY, or SC

(check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

Comments/Discrepancy:

Chain of Custody Present?

☒ Yes☐ No☐ N/A

1.

Samples Arrived within Hold Time?

☒ Yes☐ No☐ N/A

2.

Short Hold Time Analysis (<22 hr.)?

☐ Yes☒ No☐ N/A

3.

Rush Turn Around Time Requested?

☐ Yes☒ No☐ N/A

4.

Sufficient Volume?

☒ Yes☐ No☐ N/A

5.

Correct Containers Used?

☒ Yes☐ No☐ N/A

6.

-Pace Containers Used?

☒ Yes☐ No☐ N/A

Containers Intact?

☒ Yes☐ No☐ N/A

7.

Dissolved analysis: Samples Field Filtered?

☐ Yes☐ No☐ N/A

8.

Sample Labels Match COC?

☒ Yes☐ No☐ N/A

9.

-Includes Date/Time/ID/Analysis Matrix: 12

Headspace in VOA Vials (>5-6mm)?

☐ Yes☐ No☒ N/A

10.

Trip Blank Present?

☐ Yes☐ No☒ N/A

11.

Trip Blank Custody Seals Present?

☐ Yes☐ No☒ N/AField Data Required? ☐ Yes ☐ No

COMMENTS/SAMPLE DISCREPANCY

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC# Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.
(exceptions: VOA, Coliform, TOC, Oil and Grease, DBO/DO25 (water), DOC, LUNG)

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

Item #	BP4U-125 mL Plastic Unpreserved (N/A) (C-)	BP2U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (C-)	BP4N-250 mL Plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic 2N Acetic & NaOH (S)	BP4B-125 mL Plastic NaOH (pH > 12) (C-)	WGRU-Wide-mouthed plastic jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (C-)	AG3H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (C-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG84-40 mL Amber HNO3 (N/A) (C-)	DG8H-40 mL VOA HCl (N/A)	VG8T-40 mL VOA H2SO4 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG8V-30 mL VOA HPO4 (N/A)	KG7U-50 mL Plastic Unpreserved (N/A)	VJDC 19 vials per kit-VPH/Gas kit (N/A)	SP3T-125 mL Sterile Plastic (N/A - 100)	SP2T-250 mL Sterile Plastic (N/A - 100)		BP2B-250 mL Plastic H2SO4 (pH < 2)	AGOU-200 mL Amber Unpreserved (N/A) (C-)	VSQU-25 mL Sedimentation Vials (N/A)	OD5U-40 mL Amber Unpreserved Vials (N/A)		
1	/	2	1		/	/	/	/		/	/	/	/	/	/										/	/				
2	/	2	1		/	/	/	/		/	/	/	/	/	/										/	/				
3	/	2	1		/	/	/	/		/	/	/	/	/	/										/	/				
4	/	2	1		/	/	/	/		/	/	/	/	/	/										/	/				
5	/	2	1		/	/	/	/		/	/	/	/	/	/										/	/				
6	/	2	1		/	/	/	/		/	/	/	/	/	/										/	/				
7	/				/	/	/	/		/	/	/	/	/	/										/	/				
8	/				/	/	/	/		/	/	/	/	/	/										/	/				
9	/				/	/	/	/		/	/	/	/	/	/										/	/				
10	/				/	/	/	/		/	/	/	/	/	/										/	/				
11	/				/	/	/	/		/	/	/	/	/	/										/	/				
12	/				/	/	/	/		/	/	/	/	/	/										/	/				


pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office in One Central, Research Triangle, and all other relevant offices.

CHAIN-OF-CUSTODY / Analytical Request Document

[illegible]



CHAIN-OF-CUSTODY / Analytical Request Document

[illegible][illegible]



DC# Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐

Sample Condition
Upon Receipt

Client Name:

Project #:

Courier:
☐ Commercial

☒ Fed Ex ☐ UPS ☐ USPS ☐ Other: ☐ Client

Custody Seal Present? ☒ Yes ☐ No Seals Intact? ☐ Yes ☐ No ☐ N/A

Date/Initials Person Examining Contents: 5/17/24 JMC

Packing Material: ☒ Bubble Wrap ☐ Bubble Bags ☐ Monel ☐ Other:

Biological Tissue Frozen? ☐ Yes ☐ No ☒ N/A

Thermometer: ☐ IR Gun ID: 7324 Type of Ice: ☒ Wet ☐ Blue ☐ None

Cooler Temp: 3.1 Correction Factor: Add/Subtract (°C) 0.6

Temp should be above freezing to 6°C
☐ Samples out of temp criteria. Samples on ice; cooling process has begun

Cooler Temp Corrected (°C): 3.1

USDA Regulated Soil? ☐ N/A, water sample

Did samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ No

			Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.	
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.	
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.	
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4.	
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.	
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.	
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A	7.	
Containers Intact?	☒ Yes ☐ No ☐ N/A	8.	
Dissolved analysis: Samples Field Filtered?	☐ Yes ☒ No ☐ N/A	9.	
Sample Labels Match COC?	☒ Yes ☐ No ☐ N/A		
-Includes Date/Time/ID/Analysis Matrix: 3.1			
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☐ N/A	10.	
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.	
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A		

Field Data Required? ☐ Yes ☐ No

COMMENTS/SAMPLE DISCREPANCY

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted: _____ Date/Time: _____

Project Manager SCURF Review: _____ Date: _____

Project Manager SRF Review: _____ Date: _____



DC# Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Caliform, TOC, Oil and Grease, DOC/BSL5 (water) DOC, LUNG

** Bottom half of box is to list number of bottles

*** Check all unpreserved Nitrates for chlorine

Project #

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #
BP40-125 mL Plastic Unpreserved (N/A) (C-1)						
BP20-250 mL Plastic Unpreserved (N/A)						
BP20-500 mL Plastic Unpreserved (N/A)						
BP20-1 L Plastic Unpreserved (N/A)						
BP25-125 mL Plastic H2SO4 (pH < 2) (C-1)						
BP30-250 mL Plastic HNO3 (pH < 2)						
BP40-125 mL Plastic Zn Acetate & NaOH (pH < 2)						
BP40-125 mL Plastic NaOH (pH > 12) (C-1)						
W620-Wide-mouthed Glass jar Unpreserved						
AG10-1 liter Amber Unpreserved (N/A) (C-1)						
AG10-1 liter Amber HD (pH < 2)						
AG30-250 mL Amber Unpreserved (N/A) (C-1)						
AG10-1 liter Amber H2SO4 (pH < 2)						
AG30-250 mL Amber H2SO4 (pH < 2)						
DO84-40 mL Amber HNO3 (N/A) (C-1)						
DO84-40 mL VOA HD (N/A)						
VG84-40 mL VOA H2SO3 (N/A)						
VG80-40 mL VOA Unpreserved (N/A)						
DO8V-40 mL VOA H2PO4 (N/A)						
BP20-50 mL Plastic Unpreserved (N/A)						
V100-100 mL per lot V100/Dos UN (N/A)						
SP57-125 mL Sterile Plastic (N/A - lab)						
SP27-500 mL Sterile Plastic (N/A - lab)						
BP30-250 mL Plastic (H2) H2O4 (pH < 2)						
AG10-1 liter Amber Unpreserved (N/A) (C-1)						
VS60-20 mL Solulution vials (N/A)						
DO80-40 mL Amber Unpreserved vials (N/A)						

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever this data is prepared by a laboratory, it is the responsibility of the laboratory to ensure that the data is accurate and that the data is consistent with the data from the North Carolina Office of Certification, Division of Environmental Protection, and the Department of Health and Human Services.



June 17, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1
Pace Project No.: 92733822

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on May 31, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Peachtree Corners, GA

Revision 1: EB/FB/FD sample ID's amended.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Anthony Szwast, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1

Pace Project No.: 92733822

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1

Pace Project No.: 92733822

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92733822001	HAM-INW-03	Water	05/29/24 14:14	05/31/24 12:05
92733822002	HAM-PT-09	Water	05/30/24 11:52	05/31/24 12:05
92733822003	HAM-PT-10	Water	05/30/24 14:40	05/31/24 12:05
92733822004	HAM-PT-11	Water	05/29/24 16:43	05/31/24 12:05
92733822005	HAM-PT-12	Water	05/29/24 12:08	05/31/24 12:05
92733822006	HAM-AP1-EB-01	Water	05/30/24 16:59	05/31/24 12:05
92733822007	HAM-AP1-FB-01	Water	05/30/24 16:52	05/31/24 12:05
92733822008	HAM-AP1-FD-01	Water	05/30/24 00:00	05/31/24 12:05

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92733822

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92733822001	HAM-INW-03	EPA 6010D	AJM	6
		EPA 6020B	MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92733822002	HAM-PT-09	EPA 6010D	AJM	6
		EPA 6020B	MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92733822003	HAM-PT-10	EPA 6010D	AJM	6
		EPA 6020B	MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92733822004	HAM-PT-11	EPA 6010D	AJM	6
		EPA 6020B	MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92733822005	HAM-PT-12	EPA 6010D	AJM	6
		EPA 6020B	MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92733822006	HAM-AP1-EB-01	EPA 6010D	AJM	6
		EPA 6020B	MT1	13

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92733822

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92733822007	HAM-AP1-FB-01	EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	AJM	6
		EPA 6020B	MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	AJM	6
		EPA 6020B	MT1	13
92733822008	HAM-AP1-FD-01	EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	AJM	6
		EPA 6020B	MT1	13

PASI-A = Pace Analytical Services - Asheville

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92733822

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92733822001	HAM-INW-03					
EPA 6010D	Iron	0.14	mg/L	0.040	06/03/24 20:27	
EPA 6010D	Manganese	1.2	mg/L	0.040	06/03/24 20:27	
EPA 6010D	Potassium	6.1	mg/L	0.50	06/03/24 20:27	
EPA 6010D	Sodium	11.1	mg/L	1.0	06/03/24 20:27	
EPA 6010D	Calcium	144	mg/L	1.0	06/03/24 20:27	
EPA 6010D	Magnesium	16.5	mg/L	0.050	06/03/24 20:27	
EPA 6020B	Arsenic	0.0022J	mg/L	0.0050	06/04/24 16:51	
EPA 6020B	Barium	0.12	mg/L	0.0050	06/04/24 16:51	
EPA 6020B	Boron	1.5	mg/L	0.040	06/04/24 16:51	
EPA 6020B	Cobalt	0.00087J	mg/L	0.0050	06/04/24 16:51	
EPA 6020B	Lithium	0.0048J	mg/L	0.030	06/04/24 16:51	
EPA 6020B	Molybdenum	0.060	mg/L	0.010	06/04/24 16:51	
EPA 6020B	Selenium	0.0016J	mg/L	0.0050	06/04/24 16:51	
SM 2540C-2015	Total Dissolved Solids	610	mg/L	25.0	06/03/24 12:08	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	176	mg/L	5.0	06/05/24 17:10	
SM 2320B-2011	Alkalinity, Total as CaCO3	176	mg/L	5.0	06/05/24 17:10	
EPA 300.0 Rev 2.1 1993	Chloride	61.6	mg/L	1.0	06/01/24 22:59	
EPA 300.0 Rev 2.1 1993	Fluoride	0.13	mg/L	0.10	06/01/24 22:59	
EPA 300.0 Rev 2.1 1993	Sulfate	187	mg/L	4.0	06/02/24 04:57	
92733822002	HAM-PT-09					
EPA 6010D	Iron	0.24	mg/L	0.040	06/03/24 20:31	
EPA 6010D	Manganese	0.28	mg/L	0.040	06/03/24 20:31	
EPA 6010D	Potassium	6.2	mg/L	0.50	06/03/24 20:31	
EPA 6010D	Sodium	11.5	mg/L	1.0	06/03/24 20:31	
EPA 6010D	Calcium	94.9	mg/L	1.0	06/03/24 20:31	
EPA 6010D	Magnesium	19.9	mg/L	0.050	06/03/24 20:31	
EPA 6020B	Arsenic	0.0022J	mg/L	0.0050	06/04/24 16:55	
EPA 6020B	Barium	0.062	mg/L	0.0050	06/04/24 16:55	
EPA 6020B	Boron	1.5	mg/L	0.040	06/04/24 16:55	
EPA 6020B	Cadmium	0.00010J	mg/L	0.00050	06/04/24 16:55	
EPA 6020B	Cobalt	0.0010J	mg/L	0.0050	06/04/24 16:55	
EPA 6020B	Molybdenum	0.24	mg/L	0.010	06/04/24 16:55	
SM 2540C-2015	Total Dissolved Solids	532	mg/L	25.0	06/03/24 12:09	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	138	mg/L	5.0	06/07/24 15:22	
SM 2320B-2011	Alkalinity, Total as CaCO3	138	mg/L	5.0	06/07/24 15:22	
EPA 300.0 Rev 2.1 1993	Chloride	52.4	mg/L	1.0	06/01/24 23:14	
EPA 300.0 Rev 2.1 1993	Fluoride	0.33	mg/L	0.10	06/01/24 23:14	
EPA 300.0 Rev 2.1 1993	Sulfate	133	mg/L	3.0	06/02/24 05:41	
92733822003	HAM-PT-10					
EPA 6010D	Iron	0.21	mg/L	0.040	06/03/24 20:35	
EPA 6010D	Manganese	0.52	mg/L	0.040	06/03/24 20:35	
EPA 6010D	Potassium	6.6	mg/L	0.50	06/03/24 20:35	
EPA 6010D	Sodium	9.5	mg/L	1.0	06/03/24 20:35	
EPA 6010D	Calcium	95.9	mg/L	1.0	06/03/24 20:35	
EPA 6010D	Magnesium	13.1	mg/L	0.050	06/03/24 20:35	
EPA 6020B	Arsenic	0.0018J	mg/L	0.0050	06/04/24 16:59	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92733822

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92733822003	HAM-PT-10					
EPA 6020B	Barium	0.052	mg/L	0.0050	06/04/24 16:59	
EPA 6020B	Boron	1.4	mg/L	0.040	06/04/24 16:59	
EPA 6020B	Cobalt	0.0014J	mg/L	0.0050	06/04/24 16:59	
EPA 6020B	Molybdenum	0.053	mg/L	0.010	06/04/24 16:59	
SM 2540C-2015	Total Dissolved Solids	495	mg/L	25.0	06/03/24 12:10	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	116	mg/L	5.0	06/07/24 15:31	
SM 2320B-2011	Alkalinity, Total as CaCO3	116	mg/L	5.0	06/07/24 15:31	
EPA 300.0 Rev 2.1 1993	Chloride	53.0	mg/L	1.0	06/01/24 23:57	
EPA 300.0 Rev 2.1 1993	Fluoride	0.17	mg/L	0.10	06/01/24 23:57	
EPA 300.0 Rev 2.1 1993	Sulfate	124	mg/L	3.0	06/02/24 05:55	
92733822004	HAM-PT-11					
EPA 6010D	Iron	0.10	mg/L	0.040	06/03/24 20:39	
EPA 6010D	Manganese	0.27	mg/L	0.040	06/03/24 20:39	
EPA 6010D	Potassium	6.5	mg/L	0.50	06/03/24 20:39	
EPA 6010D	Sodium	9.2	mg/L	1.0	06/03/24 20:39	
EPA 6010D	Calcium	95.7	mg/L	1.0	06/03/24 20:39	
EPA 6010D	Magnesium	16.7	mg/L	0.050	06/03/24 20:39	
EPA 6020B	Arsenic	0.0021J	mg/L	0.0050	06/04/24 17:03	
EPA 6020B	Barium	0.072	mg/L	0.0050	06/04/24 17:03	
EPA 6020B	Boron	1.4	mg/L	0.040	06/04/24 17:03	
EPA 6020B	Cadmium	0.00013J	mg/L	0.00050	06/04/24 17:03	
EPA 6020B	Cobalt	0.0013J	mg/L	0.0050	06/04/24 17:03	
EPA 6020B	Molybdenum	0.17	mg/L	0.010	06/04/24 17:03	
SM 2540C-2015	Total Dissolved Solids	474	mg/L	25.0	06/03/24 12:08	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	143	mg/L	5.0	06/05/24 17:35	
SM 2320B-2011	Alkalinity, Total as CaCO3	143	mg/L	5.0	06/05/24 17:35	
EPA 300.0 Rev 2.1 1993	Chloride	39.4	mg/L	1.0	06/02/24 00:11	
EPA 300.0 Rev 2.1 1993	Fluoride	0.31	mg/L	0.10	06/02/24 00:11	
EPA 300.0 Rev 2.1 1993	Sulfate	118	mg/L	3.0	06/02/24 06:09	
92733822005	HAM-PT-12					
EPA 6010D	Iron	0.032J	mg/L	0.040	06/03/24 20:43	
EPA 6010D	Manganese	0.75	mg/L	0.040	06/03/24 20:43	
EPA 6010D	Potassium	5.7	mg/L	0.50	06/03/24 20:43	
EPA 6010D	Sodium	9.6	mg/L	1.0	06/03/24 20:43	
EPA 6010D	Calcium	91.0	mg/L	1.0	06/03/24 20:43	
EPA 6010D	Magnesium	18.6	mg/L	0.050	06/03/24 20:43	
EPA 6020B	Arsenic	0.0026J	mg/L	0.0050	06/04/24 17:07	
EPA 6020B	Barium	0.069	mg/L	0.0050	06/04/24 17:07	
EPA 6020B	Boron	1.5	mg/L	0.040	06/04/24 17:07	
EPA 6020B	Cadmium	0.00011J	mg/L	0.00050	06/04/24 17:07	
EPA 6020B	Cobalt	0.0021J	mg/L	0.0050	06/04/24 17:07	
EPA 6020B	Molybdenum	0.22	mg/L	0.010	06/04/24 17:07	
EPA 6020B	Selenium	0.0015J	mg/L	0.0050	06/04/24 17:07	
SM 2540C-2015	Total Dissolved Solids	488	mg/L	25.0	06/03/24 12:08	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	136	mg/L	5.0	06/07/24 13:55	
SM 2320B-2011	Alkalinity, Total as CaCO3	136	mg/L	5.0	06/07/24 13:55	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92733822

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92733822005	HAM-PT-12					
EPA 300.0 Rev 2.1 1993	Chloride	48.0	mg/L	1.0	06/03/24 00:51	
EPA 300.0 Rev 2.1 1993	Fluoride	0.31	mg/L	0.10	06/03/24 00:51	
EPA 300.0 Rev 2.1 1993	Sulfate	131	mg/L	3.0	06/03/24 03:15	
92733822006	HAM-AP1-EB-01					
EPA 6010D	Calcium	0.13J	mg/L	1.0	06/03/24 20:47	
EPA 6010D	Magnesium	0.030J	mg/L	0.050	06/03/24 20:47	
EPA 6020B	Arsenic	0.0044J	mg/L	0.0050	06/04/24 17:16	
92733822007	HAM-AP1-FB-01					
EPA 6020B	Arsenic	0.0040J	mg/L	0.0050	06/04/24 17:20	
EPA 6020B	Selenium	0.0011J	mg/L	0.0050	06/04/24 17:20	
92733822008	HAM-AP1-FD-01					
EPA 6010D	Iron	0.26	mg/L	0.040	06/03/24 21:41	
EPA 6010D	Manganese	0.27	mg/L	0.040	06/03/24 21:41	
EPA 6010D	Calcium	97.3	mg/L	1.0	06/03/24 21:41	
EPA 6010D	Magnesium	20.9	mg/L	0.050	06/03/24 21:41	
EPA 6010D	Potassium	6.4	mg/L	0.50	06/04/24 14:10	
EPA 6010D	Sodium	12.0	mg/L	1.0	06/04/24 14:10	
EPA 6020B	Arsenic	0.0025J	mg/L	0.0050	06/04/24 17:24	
EPA 6020B	Barium	0.062	mg/L	0.0050	06/04/24 17:24	
EPA 6020B	Boron	1.4	mg/L	0.040	06/04/24 17:24	
EPA 6020B	Cadmium	0.00014J	mg/L	0.00050	06/04/24 17:24	
EPA 6020B	Cobalt	0.0010J	mg/L	0.0050	06/04/24 17:24	
EPA 6020B	Molybdenum	0.24	mg/L	0.010	06/04/24 17:24	
EPA 6020B	Selenium	0.0012J	mg/L	0.0050	06/04/24 17:24	
SM 2540C-2015	Total Dissolved Solids	500	mg/L	25.0	06/03/24 12:10	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	140	mg/L	5.0	06/07/24 15:48	
SM 2320B-2011	Alkalinity, Total as CaCO3	140	mg/L	5.0	06/07/24 15:48	
EPA 300.0 Rev 2.1 1993	Chloride	51.3	mg/L	1.0	06/03/24 01:06	
EPA 300.0 Rev 2.1 1993	Fluoride	0.32	mg/L	0.10	06/03/24 01:06	
EPA 300.0 Rev 2.1 1993	Sulfate	129	mg/L	3.0	06/03/24 03:29	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-INW-03 Lab ID: 92733822001 Collected: 05/29/24 14:14 Received: 05/31/24 12:05 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.14	mg/L	0.040	0.025	1	05/31/24 17:19	06/03/24 20:27	7439-89-6	
Manganese	1.2	mg/L	0.040	0.011	1	05/31/24 17:19	06/03/24 20:27	7439-96-5	
Potassium	6.1	mg/L	0.50	0.15	1	05/31/24 17:19	06/03/24 20:27	7440-09-7	
Sodium	11.1	mg/L	1.0	0.58	1	05/31/24 17:19	06/03/24 20:27	7440-23-5	
Calcium	144	mg/L	1.0	0.12	1	05/31/24 17:19	06/03/24 20:27	7440-70-2	
Magnesium	16.5	mg/L	0.050	0.012	1	05/31/24 17:19	06/03/24 20:27	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/31/24 16:57	06/04/24 16:51	7440-36-0	
Arsenic	0.0022J	mg/L	0.0050	0.00084	1	05/31/24 16:57	06/04/24 16:51	7440-38-2	
Barium	0.12	mg/L	0.0050	0.00047	1	05/31/24 16:57	06/04/24 16:51	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/31/24 16:57	06/04/24 16:51	7440-41-7	
Boron	1.5	mg/L	0.040	0.012	1	05/31/24 16:57	06/04/24 16:51	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/31/24 16:57	06/04/24 16:51	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/31/24 16:57	06/04/24 16:51	7440-47-3	
Cobalt	0.00087J	mg/L	0.0050	0.00032	1	05/31/24 16:57	06/04/24 16:51	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/31/24 16:57	06/04/24 16:51	7439-92-1	
Lithium	0.0048J	mg/L	0.030	0.0016	1	05/31/24 16:57	06/04/24 16:51	7439-93-2	
Molybdenum	0.060	mg/L	0.010	0.00062	1	05/31/24 16:57	06/04/24 16:51	7439-98-7	
Selenium	0.0016J	mg/L	0.0050	0.00096	1	05/31/24 16:57	06/04/24 16:51	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/31/24 16:57	06/04/24 16:51	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	06/10/24 17:00	06/11/24 09:10	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	610	mg/L	25.0	25.0	1		06/03/24 12:08		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	176	mg/L	5.0	5.0	1		06/05/24 17:10		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		06/05/24 17:10		
Alkalinity, Total as CaCO3	176	mg/L	5.0	5.0	1		06/05/24 17:10		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		06/02/24 02:01	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	61.6	mg/L	1.0	0.60	1		06/01/24 22:59	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92733822

Sample: HAM-INW-03		Lab ID: 92733822001		Collected: 05/29/24 14:14		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.13	mg/L	0.10	0.050	1		06/01/24 22:59	16984-48-8	
Sulfate	187	mg/L	4.0	2.0	4		06/02/24 04:57	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-PT-09 Lab ID: 92733822002 Collected: 05/30/24 11:52 Received: 05/31/24 12:05 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.24	mg/L	0.040	0.025	1	05/31/24 17:19	06/03/24 20:31	7439-89-6	
Manganese	0.28	mg/L	0.040	0.011	1	05/31/24 17:19	06/03/24 20:31	7439-96-5	
Potassium	6.2	mg/L	0.50	0.15	1	05/31/24 17:19	06/03/24 20:31	7440-09-7	
Sodium	11.5	mg/L	1.0	0.58	1	05/31/24 17:19	06/03/24 20:31	7440-23-5	
Calcium	94.9	mg/L	1.0	0.12	1	05/31/24 17:19	06/03/24 20:31	7440-70-2	
Magnesium	19.9	mg/L	0.050	0.012	1	05/31/24 17:19	06/03/24 20:31	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/31/24 16:57	06/04/24 16:55	7440-36-0	
Arsenic	0.0022J	mg/L	0.0050	0.00084	1	05/31/24 16:57	06/04/24 16:55	7440-38-2	
Barium	0.062	mg/L	0.0050	0.00047	1	05/31/24 16:57	06/04/24 16:55	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/31/24 16:57	06/04/24 16:55	7440-41-7	
Boron	1.5	mg/L	0.040	0.012	1	05/31/24 16:57	06/04/24 16:55	7440-42-8	
Cadmium	0.00010J	mg/L	0.00050	0.00010	1	05/31/24 16:57	06/04/24 16:55	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/31/24 16:57	06/04/24 16:55	7440-47-3	
Cobalt	0.0010J	mg/L	0.0050	0.00032	1	05/31/24 16:57	06/04/24 16:55	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/31/24 16:57	06/04/24 16:55	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/31/24 16:57	06/04/24 16:55	7439-93-2	
Molybdenum	0.24	mg/L	0.010	0.00062	1	05/31/24 16:57	06/04/24 16:55	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/31/24 16:57	06/04/24 16:55	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/31/24 16:57	06/04/24 16:55	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	06/10/24 17:00	06/11/24 09:32	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	532	mg/L	25.0	25.0	1		06/03/24 12:09		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	138	mg/L	5.0	5.0	1		06/07/24 15:22		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		06/07/24 15:22		
Alkalinity, Total as CaCO3	138	mg/L	5.0	5.0	1		06/07/24 15:22		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		06/02/24 02:05	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	52.4	mg/L	1.0	0.60	1		06/01/24 23:14	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92733822

Sample: HAM-PT-09		Lab ID: 92733822002		Collected: 05/30/24 11:52		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.33	mg/L	0.10	0.050	1		06/01/24 23:14	16984-48-8	
Sulfate	133	mg/L	3.0	1.5	3		06/02/24 05:41	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-PT-10 Lab ID: 92733822003 Collected: 05/30/24 14:40 Received: 05/31/24 12:05 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.21	mg/L	0.040	0.025	1	05/31/24 17:19	06/03/24 20:35	7439-89-6	
Manganese	0.52	mg/L	0.040	0.011	1	05/31/24 17:19	06/03/24 20:35	7439-96-5	
Potassium	6.6	mg/L	0.50	0.15	1	05/31/24 17:19	06/03/24 20:35	7440-09-7	
Sodium	9.5	mg/L	1.0	0.58	1	05/31/24 17:19	06/03/24 20:35	7440-23-5	
Calcium	95.9	mg/L	1.0	0.12	1	05/31/24 17:19	06/03/24 20:35	7440-70-2	
Magnesium	13.1	mg/L	0.050	0.012	1	05/31/24 17:19	06/03/24 20:35	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/31/24 16:57	06/04/24 16:59	7440-36-0	
Arsenic	0.0018J	mg/L	0.0050	0.00084	1	05/31/24 16:57	06/04/24 16:59	7440-38-2	
Barium	0.052	mg/L	0.0050	0.00047	1	05/31/24 16:57	06/04/24 16:59	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/31/24 16:57	06/04/24 16:59	7440-41-7	
Boron	1.4	mg/L	0.040	0.012	1	05/31/24 16:57	06/04/24 16:59	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/31/24 16:57	06/04/24 16:59	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/31/24 16:57	06/04/24 16:59	7440-47-3	
Cobalt	0.0014J	mg/L	0.0050	0.00032	1	05/31/24 16:57	06/04/24 16:59	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/31/24 16:57	06/04/24 16:59	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/31/24 16:57	06/04/24 16:59	7439-93-2	
Molybdenum	0.053	mg/L	0.010	0.00062	1	05/31/24 16:57	06/04/24 16:59	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/31/24 16:57	06/04/24 16:59	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/31/24 16:57	06/04/24 16:59	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	06/10/24 17:00	06/11/24 09:35	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	495	mg/L	25.0	25.0	1		06/03/24 12:10		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	116	mg/L	5.0	5.0	1		06/07/24 15:31		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		06/07/24 15:31		
Alkalinity, Total as CaCO3	116	mg/L	5.0	5.0	1		06/07/24 15:31		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		06/02/24 02:05	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	53.0	mg/L	1.0	0.60	1		06/01/24 23:57	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92733822

Sample: HAM-PT-10		Lab ID: 92733822003		Collected: 05/30/24 14:40		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.17	mg/L	0.10	0.050	1		06/01/24 23:57	16984-48-8	
Sulfate	124	mg/L	3.0	1.5	3		06/02/24 05:55	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-PT-11		Lab ID: 92733822004		Collected: 05/29/24 16:43		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.10	mg/L	0.040	0.025	1	05/31/24 17:19	06/03/24 20:39	7439-89-6	
Manganese	0.27	mg/L	0.040	0.011	1	05/31/24 17:19	06/03/24 20:39	7439-96-5	
Potassium	6.5	mg/L	0.50	0.15	1	05/31/24 17:19	06/03/24 20:39	7440-09-7	
Sodium	9.2	mg/L	1.0	0.58	1	05/31/24 17:19	06/03/24 20:39	7440-23-5	
Calcium	95.7	mg/L	1.0	0.12	1	05/31/24 17:19	06/03/24 20:39	7440-70-2	
Magnesium	16.7	mg/L	0.050	0.012	1	05/31/24 17:19	06/03/24 20:39	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/31/24 16:57	06/04/24 17:03	7440-36-0	
Arsenic	0.0021J	mg/L	0.0050	0.00084	1	05/31/24 16:57	06/04/24 17:03	7440-38-2	
Barium	0.072	mg/L	0.0050	0.00047	1	05/31/24 16:57	06/04/24 17:03	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/31/24 16:57	06/04/24 17:03	7440-41-7	
Boron	1.4	mg/L	0.040	0.012	1	05/31/24 16:57	06/04/24 17:03	7440-42-8	
Cadmium	0.00013J	mg/L	0.00050	0.00010	1	05/31/24 16:57	06/04/24 17:03	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/31/24 16:57	06/04/24 17:03	7440-47-3	
Cobalt	0.0013J	mg/L	0.0050	0.00032	1	05/31/24 16:57	06/04/24 17:03	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/31/24 16:57	06/04/24 17:03	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/31/24 16:57	06/04/24 17:03	7439-93-2	
Molybdenum	0.17	mg/L	0.010	0.00062	1	05/31/24 16:57	06/04/24 17:03	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/31/24 16:57	06/04/24 17:03	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/31/24 16:57	06/04/24 17:03	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	06/10/24 17:00	06/11/24 09:37	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	474	mg/L	25.0	25.0	1		06/03/24 12:08		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	143	mg/L	5.0	5.0	1		06/05/24 17:35		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		06/05/24 17:35		
Alkalinity, Total as CaCO3	143	mg/L	5.0	5.0	1		06/05/24 17:35		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		06/02/24 02:01	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	39.4	mg/L	1.0	0.60	1		06/02/24 00:11	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92733822

Sample: HAM-PT-11		Lab ID: 92733822004		Collected: 05/29/24 16:43		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.31	mg/L	0.10	0.050	1		06/02/24 00:11	16984-48-8	
Sulfate	118	mg/L	3.0	1.5	3		06/02/24 06:09	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-PT-12		Lab ID: 92733822005		Collected: 05/29/24 12:08		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.032J	mg/L	0.040	0.025	1	05/31/24 17:19	06/03/24 20:43	7439-89-6	
Manganese	0.75	mg/L	0.040	0.011	1	05/31/24 17:19	06/03/24 20:43	7439-96-5	
Potassium	5.7	mg/L	0.50	0.15	1	05/31/24 17:19	06/03/24 20:43	7440-09-7	
Sodium	9.6	mg/L	1.0	0.58	1	05/31/24 17:19	06/03/24 20:43	7440-23-5	
Calcium	91.0	mg/L	1.0	0.12	1	05/31/24 17:19	06/03/24 20:43	7440-70-2	
Magnesium	18.6	mg/L	0.050	0.012	1	05/31/24 17:19	06/03/24 20:43	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/31/24 16:57	06/04/24 17:07	7440-36-0	
Arsenic	0.0026J	mg/L	0.0050	0.00084	1	05/31/24 16:57	06/04/24 17:07	7440-38-2	
Barium	0.069	mg/L	0.0050	0.00047	1	05/31/24 16:57	06/04/24 17:07	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/31/24 16:57	06/04/24 17:07	7440-41-7	
Boron	1.5	mg/L	0.040	0.012	1	05/31/24 16:57	06/04/24 17:07	7440-42-8	
Cadmium	0.00011J	mg/L	0.00050	0.00010	1	05/31/24 16:57	06/04/24 17:07	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/31/24 16:57	06/04/24 17:07	7440-47-3	
Cobalt	0.0021J	mg/L	0.0050	0.00032	1	05/31/24 16:57	06/04/24 17:07	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/31/24 16:57	06/04/24 17:07	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/31/24 16:57	06/04/24 17:07	7439-93-2	
Molybdenum	0.22	mg/L	0.010	0.00062	1	05/31/24 16:57	06/04/24 17:07	7439-98-7	
Selenium	0.0015J	mg/L	0.0050	0.00096	1	05/31/24 16:57	06/04/24 17:07	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/31/24 16:57	06/04/24 17:07	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	06/10/24 17:00	06/11/24 09:40	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	488	mg/L	25.0	25.0	1		06/03/24 12:08		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	136	mg/L	5.0	5.0	1		06/07/24 13:55		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		06/07/24 13:55		
Alkalinity, Total as CaCO3	136	mg/L	5.0	5.0	1		06/07/24 13:55		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		06/02/24 02:01	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	48.0	mg/L	1.0	0.60	1		06/03/24 00:51	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92733822

Sample: HAM-PT-12		Lab ID: 92733822005		Collected: 05/29/24 12:08		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.31	mg/L	0.10	0.050	1		06/03/24 00:51	16984-48-8	
Sulfate	131	mg/L	3.0	1.5	3		06/03/24 03:15	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-AP1-EB-01 Lab ID: 92733822006 Collected: 05/30/24 16:59 Received: 05/31/24 12:05 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	05/31/24 17:19	06/03/24 20:47	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	05/31/24 17:19	06/03/24 20:47	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	05/31/24 17:19	06/03/24 20:47	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	05/31/24 17:19	06/03/24 20:47	7440-23-5	
Calcium	0.13J	mg/L	1.0	0.12	1	05/31/24 17:19	06/03/24 20:47	7440-70-2	
Magnesium	0.030J	mg/L	0.050	0.012	1	05/31/24 17:19	06/03/24 20:47	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/31/24 16:57	06/04/24 17:16	7440-36-0	
Arsenic	0.0044J	mg/L	0.0050	0.00084	1	05/31/24 16:57	06/04/24 17:16	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	05/31/24 16:57	06/04/24 17:16	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/31/24 16:57	06/04/24 17:16	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	05/31/24 16:57	06/04/24 17:16	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/31/24 16:57	06/04/24 17:16	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/31/24 16:57	06/04/24 17:16	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	05/31/24 16:57	06/04/24 17:16	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/31/24 16:57	06/04/24 17:16	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/31/24 16:57	06/04/24 17:16	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	05/31/24 16:57	06/04/24 17:16	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/31/24 16:57	06/04/24 17:16	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/31/24 16:57	06/04/24 17:16	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	06/10/24 17:00	06/11/24 09:43	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		06/03/24 12:10		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	ND	mg/L	5.0	5.0	1		06/07/24 15:40		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		06/07/24 15:40		
Alkalinity, Total as CaCO3	ND	mg/L	5.0	5.0	1		06/07/24 15:40		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		06/02/24 02:06	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		06/02/24 22:00	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92733822

Sample: HAM-AP1-EB-01		Lab ID: 92733822006		Collected: 05/30/24 16:59		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		06/02/24 22:00	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		06/02/24 22:00	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-AP1-FB-01 Lab ID: 92733822007 Collected: 05/30/24 16:52 Received: 05/31/24 12:05 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	05/31/24 17:19	06/03/24 20:51	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	05/31/24 17:19	06/03/24 20:51	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	05/31/24 17:19	06/03/24 20:51	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	05/31/24 17:19	06/03/24 20:51	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	05/31/24 17:19	06/03/24 20:51	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	05/31/24 17:19	06/03/24 20:51	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/31/24 16:57	06/04/24 17:20	7440-36-0	
Arsenic	0.0040J	mg/L	0.0050	0.00084	1	05/31/24 16:57	06/04/24 17:20	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	05/31/24 16:57	06/04/24 17:20	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/31/24 16:57	06/04/24 17:20	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	05/31/24 16:57	06/04/24 17:20	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/31/24 16:57	06/04/24 17:20	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/31/24 16:57	06/04/24 17:20	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	05/31/24 16:57	06/04/24 17:20	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/31/24 16:57	06/04/24 17:20	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/31/24 16:57	06/04/24 17:20	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	05/31/24 16:57	06/04/24 17:20	7439-98-7	
Selenium	0.0011J	mg/L	0.0050	0.00096	1	05/31/24 16:57	06/04/24 17:20	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/31/24 16:57	06/04/24 17:20	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	06/10/24 17:00	06/11/24 09:45	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		06/03/24 12:10		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		06/07/24 15:44		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		06/07/24 15:44		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		06/07/24 15:44		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		06/02/24 02:06	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		06/02/24 22:14	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-AP1-FB-01		Lab ID: 92733822007		Collected: 05/30/24 16:52		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		06/02/24 22:14	16984-48-8	M1
Sulfate	ND	mg/L	1.0	0.50	1		06/02/24 22:14	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-AP1-FD-01 Lab ID: 92733822008 Collected: 05/30/24 00:00 Received: 05/31/24 12:05 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.26	mg/L	0.040	0.025	1	05/31/24 17:19	06/03/24 21:41	7439-89-6	
Manganese	0.27	mg/L	0.040	0.011	1	05/31/24 17:19	06/03/24 21:41	7439-96-5	
Calcium	97.3	mg/L	1.0	0.12	1	05/31/24 17:19	06/03/24 21:41	7440-70-2	
Magnesium	20.9	mg/L	0.050	0.012	1	05/31/24 17:19	06/03/24 21:41	7439-95-4	
Potassium	6.4	mg/L	0.50	0.15	1	05/31/24 17:19	06/04/24 14:10	7440-09-7	
Sodium	12.0	mg/L	1.0	0.58	1	05/31/24 17:19	06/04/24 14:10	7440-23-5	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/31/24 16:57	06/04/24 17:24	7440-36-0	
Arsenic	0.0025J	mg/L	0.0050	0.00084	1	05/31/24 16:57	06/04/24 17:24	7440-38-2	
Barium	0.062	mg/L	0.0050	0.00047	1	05/31/24 16:57	06/04/24 17:24	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/31/24 16:57	06/04/24 17:24	7440-41-7	
Boron	1.4	mg/L	0.040	0.012	1	05/31/24 16:57	06/04/24 17:24	7440-42-8	
Cadmium	0.00014J	mg/L	0.00050	0.00010	1	05/31/24 16:57	06/04/24 17:24	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/31/24 16:57	06/04/24 17:24	7440-47-3	
Cobalt	0.0010J	mg/L	0.0050	0.00032	1	05/31/24 16:57	06/04/24 17:24	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/31/24 16:57	06/04/24 17:24	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/31/24 16:57	06/04/24 17:24	7439-93-2	
Molybdenum	0.24	mg/L	0.010	0.00062	1	05/31/24 16:57	06/04/24 17:24	7439-98-7	
Selenium	0.0012J	mg/L	0.0050	0.00096	1	05/31/24 16:57	06/04/24 17:24	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/31/24 16:57	06/04/24 17:24	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	06/10/24 17:00	06/11/24 09:48	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	500	mg/L	25.0	25.0	1		06/03/24 12:10		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	140	mg/L	5.0	5.0	1		06/07/24 15:48		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		06/07/24 15:48		
Alkalinity, Total as CaCO3	140	mg/L	5.0	5.0	1		06/07/24 15:48		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		06/02/24 02:06	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	51.3	mg/L	1.0	0.60	1		06/03/24 01:06	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92733822

Sample: HAM-AP1-FD-01		Lab ID: 92733822008		Collected: 05/30/24 00:00		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.32	mg/L	0.10	0.050	1		06/03/24 01:06	16984-48-8	
Sulfate	129	mg/L	3.0	1.5	3		06/03/24 03:29	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

QC Batch: 858318

Analysis Method: EPA 6010D

QC Batch Method: EPA 3010A

Analysis Description: 6010D ATL

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008

METHOD BLANK: 4427514

Matrix: Water

Associated Lab Samples: 92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	06/03/24 19:29	
Iron	mg/L	ND	0.040	0.025	06/03/24 19:29	
Magnesium	mg/L	ND	0.050	0.012	06/03/24 19:29	
Manganese	mg/L	ND	0.040	0.011	06/03/24 19:29	
Potassium	mg/L	ND	0.50	0.15	06/03/24 19:29	
Sodium	mg/L	ND	1.0	0.58	06/03/24 19:29	

LABORATORY CONTROL SAMPLE: 4427515

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	1.0	102	80-120	
Iron	mg/L	1	1.0	103	80-120	
Magnesium	mg/L	1	1.0	104	80-120	
Manganese	mg/L	1	1.0	102	80-120	
Potassium	mg/L	1	1.0	102	80-120	
Sodium	mg/L	1	1.1	110	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4427516 4427517

Parameter	Units	92733547001	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		Result										
Calcium	mg/L	37.2	1	1	38.6	39.0	141	186	75-125	1	20	M1
Iron	mg/L	0.21	1	1	1.2	1.2	100	100	75-125	0	20	
Magnesium	mg/L	8.5	1	1	9.5	9.6	101	112	75-125	1	20	
Manganese	mg/L	ND	1	1	0.99	1.0	97	98	75-125	1	20	
Potassium	mg/L	2580 ug/L	1	1	3.4	3.5	85	88	75-125	1	20	
Sodium	mg/L	67.1	1	1	68.5	69.1	139	197	75-125	1	20	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

QC Batch:	858301	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008		

METHOD BLANK: 4427464

Matrix: Water

Associated Lab Samples: 92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	0.0010J	0.0030	0.00054	06/04/24 15:49	
Arsenic	mg/L	ND	0.0050	0.00084	06/04/24 15:49	
Barium	mg/L	ND	0.0050	0.00047	06/04/24 15:49	
Beryllium	mg/L	ND	0.00050	0.000094	06/04/24 15:49	
Boron	mg/L	ND	0.040	0.012	06/04/24 15:49	
Cadmium	mg/L	ND	0.00050	0.00010	06/04/24 15:49	
Chromium	mg/L	ND	0.0050	0.0019	06/04/24 15:49	
Cobalt	mg/L	ND	0.0050	0.00032	06/04/24 15:49	
Lead	mg/L	ND	0.0010	0.00016	06/04/24 15:49	
Lithium	mg/L	ND	0.030	0.0016	06/04/24 15:49	
Molybdenum	mg/L	ND	0.010	0.00062	06/04/24 15:49	
Selenium	mg/L	ND	0.0050	0.00096	06/04/24 15:49	
Thallium	mg/L	ND	0.0010	0.00038	06/04/24 15:49	

LABORATORY CONTROL SAMPLE: 4427465

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.11	111	80-120	
Arsenic	mg/L	0.1	0.11	106	80-120	
Barium	mg/L	0.1	0.11	105	80-120	
Beryllium	mg/L	0.1	0.10	103	80-120	
Boron	mg/L	1	0.98	98	80-120	
Cadmium	mg/L	0.1	0.10	101	80-120	
Chromium	mg/L	0.1	0.096	96	80-120	
Cobalt	mg/L	0.1	0.096	96	80-120	
Lead	mg/L	0.1	0.10	102	80-120	
Lithium	mg/L	0.1	0.10	104	80-120	
Molybdenum	mg/L	0.1	0.10	104	80-120	
Selenium	mg/L	0.1	0.11	107	80-120	
Thallium	mg/L	0.1	0.10	100	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4427466

4427467

Parameter	Units	92732634001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	ND	0.1	0.1	0.10	0.11	104	108	75-125	4	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4427466 4427467											
Parameter	Units	92732634001	MS	MSD	MS	MSD	MS	MSD	% Rec	Limits	Max
		Result	Spike	Spike							
			Conc.	Conc.	Result	Result	% Rec	% Rec			RPD
Arsenic	mg/L	6.5 ug/L	0.1	0.1	0.12	0.13	118	120	75-125	1	20
Barium	mg/L	73.4 ug/L	0.1	0.1	0.19	0.20	120	123	75-125	2	20
Beryllium	mg/L	ND	0.1	0.1	0.080	0.081	80	81	75-125	1	20
Boron	mg/L	16.1	1	1	17.8	17.4	179	137	75-125	2	20 M1
Cadmium	mg/L	0.16J ug/L	0.1	0.1	0.097	0.098	97	97	75-125	1	20
Chromium	mg/L	ND	0.1	0.1	0.10	0.10	103	100	75-125	3	20
Cobalt	mg/L	0.011	0.1	0.1	0.11	0.11	103	99	75-125	3	20
Lead	mg/L	ND	0.1	0.1	0.080	0.083	80	83	75-125	4	20
Lithium	mg/L	16.2J ug/L	0.1	0.1	0.10	0.11	88	89	75-125	1	20
Molybdenum	mg/L	41.5 ug/L	0.1	0.1	0.15	0.15	104	109	75-125	4	20
Selenium	mg/L	2.9J ug/L	0.1	0.1	0.12	0.12	115	120	75-125	5	20
Thallium	mg/L	0.75J ug/L	0.1	0.1	0.086	0.090	85	89	75-125	5	20

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

QC Batch:	860215	Analysis Method:	EPA 7470A
QC Batch Method:	EPA 7470A	Analysis Description:	7470 Mercury
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008

METHOD BLANK:	4436712	Matrix:	Water
---------------	---------	---------	-------

Associated Lab Samples: 92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	06/11/24 09:02	

LABORATORY CONTROL SAMPLE: 4436713						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0026	106	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:		4436714		4436715								
Parameter	Units	92733822001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.0025	0.0025	0.0027	0.0026	106	105	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

QC Batch:	858596	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008		

METHOD BLANK:	4428622	Matrix:	Water
Associated Lab Samples:	92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	06/03/24 12:07	

LABORATORY CONTROL SAMPLE:	4428623					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	394	98	80-120	

SAMPLE DUPLICATE:	4428624					
Parameter	Units	92733822001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	610	630	3	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

QC Batch: 859203

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92733822001, 92733822004

METHOD BLANK: 4431658

Matrix: Water

Associated Lab Samples: 92733822001, 92733822004

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	06/05/24 14:59	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	06/05/24 14:59	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	06/05/24 14:59	

LABORATORY CONTROL SAMPLE: 4431659

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	50.6	101	80-120	

LABORATORY CONTROL SAMPLE: 4431660

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.5	105	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4431661 4431662

Parameter	Units	92733822001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	176	50	50	221	222	90	90	80-120	0	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4431663 4431664

Parameter	Units	92733822004 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	143	50	50	190	190	94	93	80-120	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

QC Batch: 859504

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92733822002, 92733822003, 92733822005, 92733822006, 92733822007, 92733822008

METHOD BLANK: 4433372

Matrix: Water

Associated Lab Samples: 92733822002, 92733822003, 92733822005, 92733822006, 92733822007, 92733822008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	06/07/24 13:37	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	06/07/24 13:37	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	06/07/24 13:37	

LABORATORY CONTROL SAMPLE: 4433373

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	49.9	100	80-120	

LABORATORY CONTROL SAMPLE: 4433374

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	49.7	99	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4433375 4433376

Parameter	Units	92733822005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	136	50	50	184	183	97	96	80-120	0	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4433377 4433378

Parameter	Units	92734198001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	67.0	50	50	114	115	95	96	80-120	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

QC Batch:	858390	Analysis Method:	SM 4500-S2D-2011
QC Batch Method:	SM 4500-S2D-2011	Analysis Description:	4500S2D Sulfide Water
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008		

METHOD BLANK:	4428023	Matrix:	Water
Associated Lab Samples:	92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	06/02/24 01:56	

LABORATORY CONTROL SAMPLE: 4428024						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	ma/L	0.5	0.52	105	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:		4428025	4428026									
Parameter	Units	92733542001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.53	0.54	104	107	80-120	3	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:		4428027	4428028									
Parameter	Units	92733542003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.52	0.56	102	110	80-120	8	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

QC Batch: 858418 Analysis Method: EPA 300.0 Rev 2.1 1993
QC Batch Method: EPA 300.0 Rev 2.1 1993 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92733822001, 92733822002, 92733822003, 92733822004

METHOD BLANK: 4428096 Matrix: Water
Associated Lab Samples: 92733822001, 92733822002, 92733822003, 92733822004

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	06/01/24 16:46	
Fluoride	mg/L	ND	0.10	0.050	06/01/24 16:46	
Sulfate	mg/L	ND	1.0	0.50	06/01/24 16:46	

LABORATORY CONTROL SAMPLE: 4428097

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	51.1	102	90-110	
Fluoride	mg/L	2.5	2.6	104	90-110	
Sulfate	mg/L	50	51.1	102	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4428098 4428099

Parameter	Units	92733871001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	11.7	50	50	66.7	63.3	110	103	90-110	5	10	
Fluoride	mg/L	0.33	2.5	2.5	3.2	2.9	113	104	90-110	7	10	M1
Sulfate	mg/L	3.5	50	50	58.5	55.1	110	103	90-110	6	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4428102 4428103

Parameter	Units	92733765025 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	3.2	50	50	56.9	57.5	107	109	90-110	1	10	
Fluoride	mg/L	0.30	2.5	2.5	3.1	3.1	110	111	90-110	1	10	M1
Sulfate	mg/L	43.6	50	50	96.9	97.5	107	108	90-110	1	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

QC Batch: 858511 Analysis Method: EPA 300.0 Rev 2.1 1993
QC Batch Method: EPA 300.0 Rev 2.1 1993 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92733822005, 92733822006, 92733822007, 92733822008

METHOD BLANK: 4428289 Matrix: Water
Associated Lab Samples: 92733822005, 92733822006, 92733822007, 92733822008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	06/02/24 21:31	
Fluoride	mg/L	ND	0.10	0.050	06/02/24 21:31	
Sulfate	mg/L	ND	1.0	0.50	06/02/24 21:31	

LABORATORY CONTROL SAMPLE: 4428290

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	51.0	102	90-110	
Fluoride	mg/L	2.5	2.7	107	90-110	
Sulfate	mg/L	50	51.1	102	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4428291 4428292

Parameter	Units	92733788001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	70.2	50	50	108	109	75	78	90-110	1	10	M1
Fluoride	mg/L	ND	2.5	2.5	2.6	2.8	105	110	90-110	5	10	
Sulfate	mg/L	22.8	50	50	73.4	75.8	101	106	90-110	3	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4428293 4428294

Parameter	Units	92733822007 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	ND	50	50	49.3	53.2	99	106	90-110	7	10	
Fluoride	mg/L	ND	2.5	2.5	2.6	2.8	105	112	90-110	6	10	M1
Sulfate	mg/L	ND	50	50	49.3	53.1	99	106	90-110	7	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1
Pace Project No.: 92733822

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92733822

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92733822001	HAM-INW-03	EPA 3010A	858318	EPA 6010D	858334
92733822002	HAM-PT-09	EPA 3010A	858318	EPA 6010D	858334
92733822003	HAM-PT-10	EPA 3010A	858318	EPA 6010D	858334
92733822004	HAM-PT-11	EPA 3010A	858318	EPA 6010D	858334
92733822005	HAM-PT-12	EPA 3010A	858318	EPA 6010D	858334
92733822006	HAM-AP1-EB-01	EPA 3010A	858318	EPA 6010D	858334
92733822007	HAM-AP1-FB-01	EPA 3010A	858318	EPA 6010D	858334
92733822008	HAM-AP1-FD-01	EPA 3010A	858318	EPA 6010D	858334
92733822001	HAM-INW-03	EPA 3005A	858301	EPA 6020B	858345
92733822002	HAM-PT-09	EPA 3005A	858301	EPA 6020B	858345
92733822003	HAM-PT-10	EPA 3005A	858301	EPA 6020B	858345
92733822004	HAM-PT-11	EPA 3005A	858301	EPA 6020B	858345
92733822005	HAM-PT-12	EPA 3005A	858301	EPA 6020B	858345
92733822006	HAM-AP1-EB-01	EPA 3005A	858301	EPA 6020B	858345
92733822007	HAM-AP1-FB-01	EPA 3005A	858301	EPA 6020B	858345
92733822008	HAM-AP1-FD-01	EPA 3005A	858301	EPA 6020B	858345
92733822001	HAM-INW-03	EPA 7470A	860215	EPA 7470A	860356
92733822002	HAM-PT-09	EPA 7470A	860215	EPA 7470A	860356
92733822003	HAM-PT-10	EPA 7470A	860215	EPA 7470A	860356
92733822004	HAM-PT-11	EPA 7470A	860215	EPA 7470A	860356
92733822005	HAM-PT-12	EPA 7470A	860215	EPA 7470A	860356
92733822006	HAM-AP1-EB-01	EPA 7470A	860215	EPA 7470A	860356
92733822007	HAM-AP1-FB-01	EPA 7470A	860215	EPA 7470A	860356
92733822008	HAM-AP1-FD-01	EPA 7470A	860215	EPA 7470A	860356
92733822001	HAM-INW-03	SM 2540C-2015	858596		
92733822002	HAM-PT-09	SM 2540C-2015	858596		
92733822003	HAM-PT-10	SM 2540C-2015	858596		
92733822004	HAM-PT-11	SM 2540C-2015	858596		
92733822005	HAM-PT-12	SM 2540C-2015	858596		
92733822006	HAM-AP1-EB-01	SM 2540C-2015	858596		
92733822007	HAM-AP1-FB-01	SM 2540C-2015	858596		
92733822008	HAM-AP1-FD-01	SM 2540C-2015	858596		
92733822001	HAM-INW-03	SM 2320B-2011	859203		
92733822002	HAM-PT-09	SM 2320B-2011	859504		
92733822003	HAM-PT-10	SM 2320B-2011	859504		
92733822004	HAM-PT-11	SM 2320B-2011	859203		
92733822005	HAM-PT-12	SM 2320B-2011	859504		
92733822006	HAM-AP1-EB-01	SM 2320B-2011	859504		
92733822007	HAM-AP1-FB-01	SM 2320B-2011	859504		
92733822008	HAM-AP1-FD-01	SM 2320B-2011	859504		
92733822001	HAM-INW-03	SM 4500-S2D-2011	858390		
92733822002	HAM-PT-09	SM 4500-S2D-2011	858390		
92733822003	HAM-PT-10	SM 4500-S2D-2011	858390		
92733822004	HAM-PT-11	SM 4500-S2D-2011	858390		
92733822005	HAM-PT-12	SM 4500-S2D-2011	858390		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1
Pace Project No.: 92733822

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92733822006	HAM-AP1-EB-01	SM 4500-S2D-2011	858390		
92733822007	HAM-AP1-FB-01	SM 4500-S2D-2011	858390		
92733822008	HAM-AP1-FD-01	SM 4500-S2D-2011	858390		
92733822001	HAM-INW-03	EPA 300.0 Rev 2.1 1993	858418		
92733822002	HAM-PT-09	EPA 300.0 Rev 2.1 1993	858418		
92733822003	HAM-PT-10	EPA 300.0 Rev 2.1 1993	858418		
92733822004	HAM-PT-11	EPA 300.0 Rev 2.1 1993	858418		
92733822005	HAM-PT-12	EPA 300.0 Rev 2.1 1993	858511		
92733822006	HAM-AP1-EB-01	EPA 300.0 Rev 2.1 1993	858511		
92733822007	HAM-AP1-FB-01	EPA 300.0 Rev 2.1 1993	858511		
92733822008	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	858511		

REPORT OF LABORATORY ANALYSIS



DC#_Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

Project #:

WO#: 92733822

Courier: ☐ Fed Ex ☐ UPS ☐ USPS ☐ Client
☐ Commercial ☒ Pace ☐ Other:Custody Seal Present? ☒ Yes ☐ No Seals Intact? ☒ Yes ☐ No ☐ N/A

Date/Initials Person Examining Contents: 12/1/24 DW

Packing Material: ☒ Bubble Wrap ☐ Bubble Bags ☐ None ☐ Other:

Biological Tissue Frozen?

☐ Yes ☐ No ☒ N/A

Thermometer:

IR Gun ID: 230 Type of Ice: ☒ Wet ☐ Blue ☐ None

Cooler Temp: 2.6 Correction Factor: Add/Subtract (°C) 0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria, Samples on ice, cooling process has begun

Cooler Temp Corrected (°C): 2.6

USDA Regulated Soil (☐ N/A, water sample)Did samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ NoDid samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ No

			Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.	
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.	
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.	
Rush Turn Around Time Requested?	☐ Yes ☐ No ☐ N/A	4.	5 Day Lat
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.	
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.	
Pace Containers Used?	☒ Yes ☐ No ☐ N/A		
Containers Intact?	☒ Yes ☐ No ☐ N/A	7.	
Dissolved analysis: Samples Field Filtered?	☐ Yes ☒ No ☐ N/A	8.	
Sample Labels Match COC?	☒ Yes ☐ No ☐ N/A	9.	
Includes Date/Time/ID/Analysis: Matrix: W L, L, L			
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10.	
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.	
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A		

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted: Date/Time:

Project Manager SCURF Review: Date:

Project Manager SRF Review: Date:



DC#_Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

WO#: 92733822

PM: BV

Due Date: 06/14/24

CLIENT: 92- GP-HAM

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRD/BD15 (water) DOC, U.Hg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic ZN Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (C-)	WQFLU-Wide-mouthed Glass Jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG94-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2SO3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit) VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)		BP3B-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AG0U-100 mL Amber unpreserved (N/A) (Cl-)	VG6U-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)	
1		2	1																										
2		2	1																										
3		2	1																										
4		2	1																										
5		2	1																										
6		2	1																										
7		2	1																										
8		2	1																										
9																													
10																													
11																													
12																													

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers).

Site Name: Hammond

Field Instrumentation Calibration Form

Date: 5/2/23Calibrated By: ERField Conditions: 60-80 sunny

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aqua Troll 400	183546
Turbidity Meter	14004022	1511-4811

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (uS/cm)	4,490	24005593	12/29	AV
pH (SU)	4.00	24004012	12/29	AV
pH (SU)	7.00	24004517	12/29	AV
pH (SU)	10.00	24000083	12/29	AV
D.O. (%)	N/A	—	12/29	AV
ORP (mV)	228.0	24006805	12/29	AV

Calibration					
Time Start	8:15		Time Finish	8:17	
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (uS/cm)	4,490	4490	17.86	± 10% of standard	EPA 2023
pH (SU)	4.00	4.00	27.25	± 0.1	GWMP
pH (SU)	7.00	7.00	27.26	± 0.1	GWMP
pH (SU)	10.00	10.00	26.99	± 0.1	GWMP
D.O. (%)	N/A	100.1	27.22	± 10%	NA
ORP (mV)	228.0	228	26.52	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	1		
	10	9.91		
	—	—		

Calibration Check					
Time Start	13:15		Time Finish	2:40	
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (uS/cm)	4,490	2490	36.04	± 10% of standard	EPA 2023
pH (SU)	4.00	4	34.13	± 0.1	GWMP
pH (SU)	7.00	7	33.21	± 0.1	GWMP
pH (SU)	10.00	10	31.94	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	0.97		
	10	9.71		
	—	—		

Notes:

Site Name: Pland Hammal

Field Instrumentation Calibration Form

Date: 6-2-24

Calibrated By: Zain W.

Field Conditions: Clear, 70°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Amprobe</u>	<u>9166185</u>
Turbidity Meter	<u>LA M-100</u>	<u>7009-1416</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (uS/cm)	4,490	<u>74005593</u>	<u>12/24</u>	<u>ATR</u>
pH (SU)	4.00	<u>24005595</u>	<u>12/24</u>	
pH (SU)	7.00	<u>24004511</u>	<u>12/24</u>	
pH (SU)	10.00	<u>24000085</u>	<u>12/24</u>	
D.O. (%)	N/A	<u>-</u>	<u>-</u>	
ORP (mV)	228.0	<u>24006903</u>	<u>12/24</u>	

Calibration					
Time Start <u>0828</u>		Time Finish <u>0948</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (uS/cm)	4,490	<u>4690</u>	<u>22.01</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.0</u>	<u>22.17</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.0</u>	<u>22.33</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.0</u>	<u>22.55</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>-</u>	<u>97.56</u>	± 10%	NA
ORP (mV)	228.0	<u>228.0</u>	<u>22.19</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		

Calibration Check					
Time Start <u>1510</u>		Time Finish <u>1523</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (uS/cm)	4,490	<u>4490</u>	<u>26.05</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.0</u>	<u>26.33</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.0</u>	<u>25.26</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.0</u>	<u>24.38</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		

Notes: Had problems w/ conductivity; solved by restoring factory calibration

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 5-9-2024Calibrated By: A. SzwastField Conditions: Thunderstorms, 66°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>AquaTronics 400</u>	<u>850751</u>
Turbidity Meter	<u>La Motte 2120T</u>	<u>7009-1416</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	<u>24000093</u>	<u>12/2024</u>	<u>AIR</u>
pH (SU)	4.00	<u>240015593</u>	<u>12/2024</u>	<u>AIR</u>
pH (SU)	7.00	<u>24003397</u>	<u>11/2024</u>	<u>AIR</u>
pH (SU)	10.00	<u>240014996</u>	<u>11/2024</u>	<u>AIR</u>
D.O. (%)	N/A	<u>-</u>	<u>-</u>	<u>-</u>
ORP (mV)	228.0	<u>24006903</u>	<u>11/2024</u>	<u>AIR</u>

Calibration					
Time Start	Time Finish				
<u>1020</u>	<u>1040</u>				
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4490.0</u>	<u>23.34</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>23.54</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>23.52</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>23.57</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>23.04</u>	± 10%	NA
ORP (mV)	228.0	<u>228.0</u>	<u>23.48</u>	± 10	EPA 2023

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)	<u>0</u>	<u>0.00</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>0.70</u>		
	<u>10</u>	<u>10.12</u>		

Calibration Check					
Time Start	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)			± 10% of standard	EPA 2023

Notes:

Site Name: GP Plant Hammond

Field Instrumentation Calibration Form

Date: 5/13/24Calibrated By: J. NewsomField Conditions: Cloudy, 60°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Raustron	966105
Turbidity Meter	Lamotte 2020 WC	1511-4111

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	24005593	12/2024	AIR
pH (SU)	4.00	24005593	12/2024	AIR
pH (SU)	7.00	24004517	12/2024	AIR
pH (SU)	10.00	24011080	12/2024	AIR
D.O. (%)	N/A			
ORP (mV)	228.0	24000903	12/2024	AIR

Calibration					
Time Start	0750	Time Finish	820		
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	4.591	19.05	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.04	19.14	± 0.1	GWMP
pH (SU)	7.00	7.04	19.24	± 0.1	GWMP
pH (SU)	10.00	10.13	19.33	± 0.1	GWMP
D.O. (%)	N/A	99.75	19.24	$\pm 10\%$	NA
ORP (mV)	228.0	228.5	19.32	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0.01	$\pm 10\%$ of standard	EPA 2023
	1	1.01		
	10	9.98		

Calibration Check					
Time Start	1230	Time Finish	1245		
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	4460.91	20.12	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.03	20.12	± 0.1	GWMP
pH (SU)	7.00	7.02	19.123	± 0.1	GWMP
pH (SU)	10.00	10.04	20.05	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	$\pm 10\%$ of standard	EPA 2023
	1	1.01		
	10	10		

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 5-15-2024Calibrated By: A. SwastField Conditions: Cloudy, 70°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Amatech 400</u>	<u>850751</u>
Turbidity Meter	<u>10/10/10 2020</u>	<u>2009-1416</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (uS/cm)	4.490	<u>2400593</u>	<u>12/2024</u>	<u>AIR</u>
pH (SU)	4.00	<u>2400593</u>	<u>12/2024</u>	<u>AIR</u>
pH (SU)	7.00	<u>2400593</u>	<u>11/2024</u>	<u>AIR</u>
pH (SU)	10.00	<u>2400494</u>	<u>11/2024</u>	<u>AIR</u>
D.O. (%)	N/A			
ORP (mV)	228.0	<u>2400693</u>	<u>11/2024</u>	<u>AIR</u>

Calibration					
Time Start <u>7:45</u>		Time Finish <u>8:10</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (uS/cm)	4.490	<u>4490.0</u>	<u>18.97</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>19.15</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>19.33</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>19.47</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100.00</u>	<u>18.62</u>	± 10%	NA
ORP (mV)	228.0	<u>228.0</u>	<u>19.46</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0.00</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>0.73</u>		
	<u>10</u>	<u>9.47</u>		

Calibration Check					
Time Start <u>1:30</u>		Time Finish <u>1:40</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (uS/cm)	4.490	<u>4490.0</u>	<u>20.19</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>7.00</u>	<u>29.82</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>28.04</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>27.03</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0.02</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>0.83</u>		
	<u>10</u>	<u>10.08</u>		

Notes:

Site Name: Run 1 Hammond

Field Instrumentation Calibration Form

Date: 5/15/24Calibrated By: J. NewcomeField Conditions: cloudy, 60°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aqua Troll	966105
Turbidity Meter	LaMotte 7020T	1711-411

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4.490	74 (105593)	12/2024	A1V2
pH (SU)	4.00	71 (105543)	12/2024	A1V2
pH (SU)	7.00	74004517	12/2024	A1V2
pH (SU)	10.00	74000005	12/2024	A1V2
D.O. (%)	N/A	—	—	—
ORP (mV)	228.0	24 (106905)	12/2024	A1V2

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490	4034.6	20.20	± 10% of standard	EPA 2023
pH (SU)	4.00	4.02	20.35	± 0.1	GWMP
pH (SU)	7.00	7.03	20.30	± 0.1	GWMP
pH (SU)	10.00	10.05	21.01	± 0.1	GWMP
D.O. (%)	N/A	100.11	20.23	± 10%	NA
ORP (mV)	228.0	237.0	20.97	± 10	EPA 2023

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)	0	0	± 10% of standard	EPA 2023
	1	0.98		
	10	10.01		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490	4109.7	22.4	± 10% of standard	EPA 2023
pH (SU)	4.00	4.02	22.4	± 0.1	GWMP
pH (SU)	7.00	7.03	21.6	± 0.1	GWMP
pH (SU)	10.00	10.0	22.7	± 0.1	GWMP

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)	0	0	± 10% of standard	EPA 2023
	1	1.01		
	10	10.01		

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 5-16-2024Calibrated By: A. S. WestField Conditions: Sunny 70°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Hanna HI9142	8501751
Turbidity Meter	La Motte 2004	7001-1466

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4.490	24005593	12/2024	AIR
pH (SU)	4.00	24005593	12/2024	AIR
pH (SU)	7.00	24005594	11/2024	AIR
pH (SU)	10.00	24004996	11/2024	AIR
D.O. (%)	N/A	~	~	~
ORP (mV)	228.0	24006903	11/2024	AIR

Calibration					
Time Start <u>800</u>		Time Finish <u>830</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490	<u>4480.0</u>	<u>20.04</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.08</u>	<u>20.02</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.08</u>	<u>20.13</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>20.20</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100.00</u>	<u>20.04</u>	± 10%	NA
ORP (mV)	228.0	<u>228.0</u>	<u>20.04</u>	± 10	EPA 2023

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)	<u>0</u>	<u>0.00</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>0.81</u>		
	<u>10</u>	<u>10.10</u>		
	<u>~</u>	<u>~</u>		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)			± 10% of standard	EPA 2023

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 5/14/24Calibrated By: J. NewsumField Conditions: Sunny, 100°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aqua-trail	11012106
Turbidity Meter	12101106	1511-1111

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	24005593	12/2024	AIR
pH (SU)	4.00	24005593	12/2024	AIR
pH (SU)	7.00	24004517	12/2024	AIR
pH (SU)	10.00	24000086	12/2024	AIR
D.O. (%)	N/A	—	—	—
ORP (mV)	228.0	24006903	12/2024	AIR

Calibration					
Time Start		Time Finish			
740		0800			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	1455.91	19.9	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.00	20.17	± 0.1	GWMP
pH (SU)	7.00	6.97	20.25	± 0.1	GWMP
pH (SU)	10.00	10.02	20.29	± 0.1	GWMP
D.O. (%)	N/A	100.53	20.3	$\pm 10\%$	NA
ORP (mV)	228.0	234.7	20.52	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0.00	$\pm 10\%$ of standard	EPA 2023
	1	0.13		
	10	1.98		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 5-29-24Calibrated By: Jason WebbField Conditions: Sunny, 75°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Hanate Aqua Troll 4M</u>	<u>965586</u>
Turbidity Meter	<u>Uco Motte 90007</u>	<u>-</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (uS/cm)	4.490	<u>24002595</u>	<u>12/24</u>	<u>ATR</u>
pH (SU)	4.00	<u>24005593</u>	<u>12/24</u>	<u>ATR</u>
pH (SU)	7.00	<u>24003597</u>	<u>11/24</u>	<u>ATR</u>
pH (SU)	10.00	<u>24000085</u>	<u>12/24</u>	<u>ATR</u>
D.O. (%)	N/A	<u>-</u>	<u>-</u>	<u>ATR</u>
ORP (mV)	228.0	<u>24006203</u>	<u>12/25</u>	<u>ATR</u>

Calibration					
Time Start	<u>0937</u>	Time Finish	<u>0959</u>		
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (uS/cm)	4.490	<u>4490</u>	<u>73.69</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>23.87</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>24.17</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>24.35</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>-</u>	<u>24.51</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228.0</u>	<u>24.51</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		

Calibration Check					
Time Start	<u>1500</u>	Time Finish	<u>1515</u>		
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (uS/cm)	4.490	<u>4490</u>	<u>29.03</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>28.59</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>26.87</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>25.93</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		

Notes:

Site Name Plant Hammond

Field Instrumentation Calibration Form

Date: 5-30-24Calibrated By: Zain W.Field Conditions: Sunny 70°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Hi-Flow Aqua-Controller</u>	<u>465526</u>
Turbidity Meter	<u>La Motte 90207</u>	<u>—</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>24005593</u>	<u>12/24</u>	<u>ATR</u>
pH (SU)	4.00	<u>24005593</u>	<u>12/24</u>	↓
pH (SU)	7.00	<u>24003599</u>	<u>11/24</u>	
pH (SU)	10.00	<u>24000085</u>	<u>12/24</u>	
D.O. (%)	N/A	—	—	
ORP (mV)	228.0	<u>24006903</u>	<u>12/24</u>	

Calibration					
Time Start <u>0819</u>		Time Finish <u>0844</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>4.490</u>	<u>20.32</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>20.75</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>21.90</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>22.55</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>22.21</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>229.0</u>	<u>22.68</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	1	<u>1</u>		
	10	<u>10</u>		

Calibration Check					
Time Start <u>—</u>		Time Finish <u>—</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>—</u>	<u>—</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	7.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	10.00	<u>—</u>	<u>—</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>—</u>	<u>—</u>	$\pm 10\%$ of standard	EPA 2023
	<u>—</u>	<u>—</u>		
	<u>—</u>	<u>—</u>		

Notes:

APPENDIX C

Injection Field Forms

Injection Log

Project Name: GP Plant Hammond

Date: 7/11/24 Page 1 of 1

Project Number: HW45816

Weather: sunny, 85°

Field Personnel: T. Newberry, A. Akkara Activity: injections

Activity: injections

Location: AP 1

Start: Date <u>7/11/24</u> Time <u>1045</u>	Finish: Date _____ Time _____
---	----------------------------------

Finish Date _____
Time _____

711

A 115

11/15

Injectate Batch Preparation Log

Project Name: Hammond Page: 1 of 1
 Project Number: 06-015 Field Personnel: AA JH
 Date: 07-13-24 Weather: Sunny

Batch #	Tank Fill			Injectate		Geochemical Parameters						Comments
	Start Time (hr:mm)	End Time (hr:mm)	Volume (gallons)	Time (hr:mm)	Amount (lb)	Time (hr:mm)	Temp (°C)	pH (SU)	Sp. Cond (µS/cm)	DO (mg/L)	ORP (mV)	
1						0952	27.03	7.88	0.20	7.95	3708	Potable water
1	1000	1059	300	1000	1.25	1000	26.90	6.03	0.45	5.14	-27.0	5 min after mixing / start inject
1						1015	27.15	5.86	0.45	3.37	-6.10	
1						1030	27.38	5.72	0.44	2.80	12.3	
2(1)						1045	27.63	5.65	0.43	2.60	19.3	
2	1115	1213	303	1115	1.25	1100	25.63	7.79	0.20	7.98	3020	Potable water
2						1115	26.06	6.00	0.47	4.98	-25.1	5 min after mixing / start inject
2						1130	26.24	5.90	0.43	3.53	-11.1	
2						1145	26.51	5.78	0.42	2.98	4.1	
2						1200	26.64	5.73	0.42	2.52	16.3	
2						1207	26.84	5.73	0.42	3.77	10.6	↓ moved sensor down
3			300			1255	26.29	7.99	0.2	7.94	2918	Potable water
3								7.78				
3	1300	1356		1300		1300	26.28	5.99	0.47	4.63	-28.9	after 5 min mix / start of inj
3						1315	26.46	5.89	0.45	3.50	-17.0	
3						1330	26.73	5.79	0.44	2.97	-3.8	
3						1345	27.03	5.68	0.43	2.71	9.7	
3						1355	27.46	5.64	0.43	2.62	6.9	
4				1410	1.25	1410	25.84	7.75	0.19	7.99	238.8	Potable water
4	1415		303	1415		1415	26.27	6.00	0.46	5.34	-32.0	start of injection / 5 min mix
4				1430		1430						
4						1445	26.82	5.78	0.41	2.93	-1.1	
4						1500	27.15	5.75	0.41	4.17	5.3	
4						1515	27.38	5.68	0.41	4.34	30.3	

was injected

start inject

start of inj

5 min mix

Injection Log

Project Name: Plant Hammond Date: 7/9/24 Page 1 of 1
 Project Number: AW4581G Weather: Sunny, 94F
 Field Personnel: A. Akbar, J. Newcomb Activity: injections

Location: HGW-13 Start Date: 7/9/24 Time: 1225 Finish Date: _____ Time: _____

Well ID	Start Time (hr:mm)	Stop Time (hr:mm)	Volume Injected (gal)	Injection Pressure (psi)	Flowrate (GPM)	Notes
INW-04	1223	1308	22	0	0.5	potable water
INW-05	1310	1321	3	0	2.5	
INW-04	1324	1426	225	0	5	
INW-05	1700	1815	225	0	2	
INW-04	903	1240	300	2	3	FeSO ₄ gravity feed
INW-04	1700	1840	325	1.5	3.2	FeSO ₄ gravity feed, pathfinder 150 gal
INW-04	1730	1912	325	1.5	3.0	FeSO ₄ gravity feed, pathfinder, batch 2
INW-04	1045	1248	325	3.6	3.9	FeSO ₄ gravity feed
INW-04	1315	1451	325	0.4	3.5	FeSO ₄ gravity feed
INW-04	1600	1734	304	0.7	3.45	FeSO ₄ gravity feed
INW-04	920	1000	141	3.5	3.5	
INW-05	920	1000	153	3.5	3.8	
INW-04	1015	1059	151	2.3	3.4	
INW-05	1015	1059	142	2.7	3.2	
INW-04	1145	1236	148	1.5	2.9	
INW-05	1145	1236	157	1.5	3.1	
INW-04	1245	1337	150	2.5	4.1	
INW-05	1245	1337	1484	2.5	3.8	
INW-04	1415	1503	151	1.7	3.1	
INW-05	1415	1503	153	1.7	3.2	
INW-04	1515	1602	151	1.8	3.2	
INW-05	1515	1602	151	1.8	3.2	

7/9/24
 7/10/24
 7/11/24
 7/12/24
 7/13/24

gravity feed
 150 gal pathfinder 150 gal
 FeSO₄ gravity feed
 switch to gravity feed
 water log

Injection Log

Activity: Injection

Finish: Date 7/24/29
Time _____

[illegible]

Injection Log

Activity: Air Sparge

Finish: Date _____
Time _____

[illegible]

Injection Log

Project Name: Hammond

Date: 7.30.24

Page 1 of 1

Project Number: _____

Weather:

Field Personnel: Ali A / Zain W

Activity: Sponge

Location: HGWC-13 pilot area

Start: Date 7/30/24 Time

Finish: Date _____
Time _____

[illegible]

Injection Log

Date: 7/31/24

Page of

Weather: Injection

Activity: Summa

Finish: Date _____
Time _____

[illegible]

Injectate Batch Preparation Log

Project Name: Plant 4 Hanford Page 1 of 1
 Project Number: SWUSRI5 Field Personnel: A. Alvarado, J. Newsum
 Date: 7/10/24 Weather: Sunny, 90°F

Batch #	Tank Fill			Injectate		Geochemical Parameters						Comments
	Start Time (hr:mm)	End Time (hr:mm)	Volume (gallons)	Time (hr:mm)	Amount (lb)	Time (hr:mm)	Temp (°C)	pH (SU)	Sp. Cond (µS/cm)	DO (mg/L)	ORP (mV)	
Tank 1	1155		250				28.68	7.6	0.23	7.55	651.4	Potable water
Tank 2	1155		250				27.61	7.7	0.23	7.68	667.6	
INW-04_1			300	900	1.25	903	27.29	6.03	0.24	7.87	499.5	7/10/24
INW-04_2						917	27.29	6.03	0.89	3.68	7.2	650, top of tank
						959	27.39	5.35	0.71	1.95	59.7	middle of tank
						1042	27.67	5.63	0.44	2.25	44.6	50 gall injected
						1126	27.67	6.90	0.25	6.54	77.7	100 gall injected
						1215	28.5	6.66	0.25	5.64	62.4	150 gall injected
			25			1230	27.67	6.90	0.25	6.54	77.7	200 gall
INW-04_2	1254		225	1700		1500	27.41	5.94	0.45	4.75	-2.7	250 gallons
			225	1710		1523	27.85	5.79	0.44	4.42	15.9	200 gallons
						1531	28.08	5.76	0.43	5.05	30.0	110 gall
						1552	28.30	5.46	0.42	6.23	28.0	170 gall
						1607	28.71	5.98	0.41	7.17	52.4	220 gall
						1621	29.20	5.37	0.41	7.63	88.0	270 gall
		1719				1640						325
INW-04_3	1455	1725	300	1725	1.25	1729	27.89	7.89	0.24	7.93	481.2	in tank, not injecting
		7/10/24		1730		1730	27.97	6.08	0.49	5.18	46.9	begin injecting
						1745	28.24	5.84	0.47	3.65	23.2	50 gall
						1819	28.33	5.66	0.45	4.34	39.7	100 gall
						1845	29.2	5.40	0.09	7.50	91.7	242 gall
						1900	26.92	5.19	0.43	7.64	193.3	280 gall

potable water

7/10/24
NW

40
30
20

Injectate Batch Preparation Log

Project Name: Plant Harmonizer

Page 2 of

Project Number: 644521G

Field Personnel

A. A. Khan, D. Newson

Date: 3/9/24

Weather

[illegible]

7/12/20

Switch to path A if clear

4. При 3 сурми

Injectate Batch Preparation Log

Project Name Hammond Page 1 of 2
 Project Number: _____ Field Personnel: AA JN
 Date: 07/14/2024 Weather: Sunny

Injectate Batch Preparation Log				Project Number		Date		Weather		Geochemical Parameters						Comments
Batch #	Tank Fill			Injectate		Time (hr:mm)	Temp (°C)	pH (SU)	Sp. Cond (µS/cm)	DO (mg/L)	ORP (mV)					
	Start Time (hr:mm)	End Time (hr:mm)	Volume (gallons)	Time (hr:mm)	Amount (lb)											
#1	0920	1000	294	0920	1.25	0915	26.66	7.96	0.2	7.82	335.9	Potable water				
						0920	26.74	6.02	0.47	5.15	-37.8	Start of Injection				
						0935	26.89	5.89	0.45	3.31	-16.7					
						0950	27.14	5.75	0.44	4.71	8.5	141 INW04 / 1531 NW05				
#2	1015	1059	297	1015	1.25	1010	25.55	7.52	0.20	7.87	239.5	Potable water				
						1015	25.87	6.06	0.46	5.07	-32.4	Start of Injection				
						1030	26.13	5.92	0.46	3.59	-17.4					
						1045	26.26	5.80	0.44	3.17	-7.5					
#3	1145	1236	305	1145	1.25	1100	26.73	5.60	0.44	4.71	8.5	151 INW04 / 1421 NW05				
						1140	26.64	7.82	0.20	7.82	291.8	Potable water				
						1145	26.69	6.06	0.43	5.2	-37.7	Start of Injection				
						1200	26.85	5.94	0.43	3.68	-23.4					
#4	1245	1336	302	1245	1.25	1215	27.70	5.73	0.44	2.9	-2.5					
						1230	27.36	5.71	0.44	2.61	-3.7	1481 INW04 / 157 INW05				
						1240	25.66	0.20	7.86	7.54	19.7	Potable water				
						1245	26.20	6.05	0.45	5.31	-37.0	Start of Injection				
#5	1415	1503	302	1415	1.25	1300	26.46	5.91	0.45	3.56	-20.2					
						1315	26.75	5.80	0.45	3.09	-10.2					
						1325	26.99	5.71	0.44	2.73	-0.6					
						1415	26.79	6.04	0.43	5.09	39.8	156 INW04 / 144 INW05				
#6	1515	1503	302	1515	1.25	1430	27.01	5.87	0.44	3.30	-19.1	Start of Injection				
						1445	27.27	5.82	0.44	3.04	-12.5					
						1510	25.80	07.99	0.20	8.18	186.40	151 INW04 / 151 INW05				
												Potable water				

Injectate Batch Preparation Log

Project Name:

Project Number:

Date: 7/19/2024

Field Personnel

Page 2 of 2

AA CN

Weather

Summit

[illegible]

Injectate Batch Preparation Log

Project Name: Hammoriel

Page: 1 of 2

Project Number:

Field Personnel:

Ali A / Zain W

Date: 7/22/2019

Weather:

clear

Batch #	Tank Fill			Injectate		Geochemical Parameters						Comments
	Start Time (hr:mm)	End Time (hr:mm)	Volume (gallons)	Time (hr:mm)	Amount (lb)	Time (hr:mm)	Temp (°C)	pH (SU)	Sp. Cond (µs/cm)	DO (mg/L)	ORP (mV)	
#1						1028						
↓	1030	1113	297		2.5	1030	29.67	8.02	226.90	6.96	153.7	Potable water
						1030	29.78	5.73	739.60	3.71	-2.3	Start of injection
						1045	29.86	5.39	733.46	2.36	40.2	
						1100	29.97	5.23	730.06	2.19	59.5	
		111				1110	30.05	5.13	675.02	2.13	75.4	
#2	1130	1214	296		2.5	1125	30.19	8.28	218.06	7.13	54.7	Potable water
↓						1130	30.23	5.68	725.98	3.49	4.0	Start of injection
						1145	30.33	5.37	720.95	2.22	37.7	20
						1200	30.47	5.22	716.19	2.27	56.1	
						1210	30.61	5.11	708.22	2.17	69.2	
#3	1300	1347	306		2.5	1255	25.78	7.91	196.22	7.77	147.3	Potable water
↓						1300	25.89	5.80	698.97	4.72	-0.5	start of injection
						1315	26.08	5.64	693.69	2.88	18.8	
						1330	26.32	5.51	672.27	2.49	32.4	
						1345	26.65	5.41	665.84	2.37	41.7	
#4	1400	1444	306		2.5	1355	25.41	7.88	184.7	7.98	78.7	Potable water
↓						1400	25.50	5.77	690.56	4.78	1.5	Start of injection
						1415	25.76	5.60	665.23	3.13	19.1	
						1430	26.05	5.49	657.61	2.98	30.4	
						1440	26.23	5.40	653.13	2.87	43.5	
#5	1530	1622	300		2.5	1525	26.08	7.56	167.81	7.87	150.2	Potable water
↓						1530	26.11	5.78	653.93	5.12	2.4	Start of injection
						1538	26.16	5.64	652.04	3.13	17.8	
						1555	26.26	5.50	666.75	2.50	26.8	
						1600	26.36	5.49	664.77	2.62	28.6	

[illegible]

Project Name: Hammond

Page 2 of 2

Project Number:

Field Personnel:

Date: 7/22/24

Weather

clear / fresh through the day

[illegible]

Injectate Batch Preparation Log

Project Name: Hammond

TAN: of

Project Number:

Field Personnel: Ell A Zan W

Date: 7/24/24

Weather: cloudy

Batch #	Tank Fill			Injectate		Geochemical Parameters						Comments
	Start Time (hr:mm)	End Time (hr:mm)	Volume (gallons)	Time (hr:mm)	Amount (lb)	Time (hr:mm)	Temp (°C)	pH (SU)	Sp. Cond (µs/cm)	DO (mg/L)	ORP (mV)	
#1	1045	1131	297		2.5	1040	25.56	7.54	191.36	7.74	76.8	Potable water
						1045	25.59	5.80	1167.3	4.75	2.6	start of inj
						1100	25.68	5.62	688.62	3.02	29.4	
						1115	25.79	5.47	683.16	2.61	46.1	
#2	1145	1229	301		2.5	1140	24.83	7.79	183.52	7.84	59.6	Potable water
						1145	24.93	5.76	666.18	4.07	15.3	start of inj
						1200	25.05	5.66	681.63	3.31	21.9	
						1215	25.23	5.54	670.19	2.92	33.8	
						1230	25.41	5.43	604.79	2.70	42.5	
#3	1305	1349	302		2.5	1300	25.64	7.58	188.17	7.75	115.2	Potable water
						1305	25.57	5.77	671.97	4.97	3.8	start of inj
						1320	25.67	5.62	680.35	3.00	17.9	
						1335	25.81	5.51	673.26	2.77	30.2	
						1350	25.96	5.42	670.30	2.61	37.4	End of batch
#4	1400	1449	304		2.5	1355	24.84	7.61	188.16	7.79	29.7	Potable water
						1400	24.90	5.76	702.07	4.86	3.0	start of inj
						1415	25.09	5.59	675.74	3.09	28.9	
						1430	25.32	5.50	668.79	2.82	29.9	
						1445	25.55	5.44	653.00	4.30	36.1	
#5	1530	1619	301		2.5	1525	24.88	7.41	187.05	7.64	139.0	Potable water
						1530	25.52	5.71	683.24	4.70	2.2	start of injection
						1545	25.59	5.61	680.56	3.22	13.2	
						1600	25.78	5.49	669.26	2.77	27.8	
						1615	26.00	5.41	662.64	3.89	40.4	
#6	1630	1717	300		2.5	1625	24.96	7.62	184.22	7.99	53.8	Potable water
						1630	25.03	5.73	686.93	5.11	1.6	start of inj

Injectate Batch Preparation Log

Project Name: Plant Hammond Page 2 of 2
Project Number: _____ Field Personnel: Ali A. Bain
Date: 7/24/24 Weather: Cloudy

[illegible]

[illegible]

Project Number:

Date: 7/29/24

ALLA

Weather Sunny

Physical Parameters

[illegible]

Injectate Batch Preparation Log

Project Name: Hammond

Page ____ of ____

Project Number:

Field Personnel:

Date: 7/31/24

Weather

Symptoms

[illegible]

APPENDIX D

Screening-Level Groundwater Analytical Data



ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 7/15/2024 7:01:03 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-1392-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
7/15/2024 7:01:03 PM



Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	13
Lab Chronicle	16
Certification Summary	18
Method Summary	19
Sample Summary	20
Receipt Checklists	21
End Of Report	22

Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1392-1

Qualifiers

Metals

Qualifier	Qualifier Description
4	MS, MSD: The analyte present in the original sample is greater than 4 times the matrix spike concentration; therefore, control limits are not applicable.
F1	MS and/or MSD recovery exceeds control limits.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Environment Testing

[illegible]

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-1392-1

Job ID: 705-1392-1

Eurofins Atlanta

Job Narrative 705-1392-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers are applied to indicate exceptions. Noncompliant quality control (QC) is further explained in narrative comments.

- Matrix QC may not be reported if insufficient sample or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 7/11/2024 9:05 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 5.0°C.

Receipt Exceptions

Per client, Arsenic & Iron are the only 6020B metals to be reported with these samples.

Limited sample volume was received for the following samples: PT-07-0710-FIL (705-1392-1), PT-08-0710-FIL (705-1392-3) and PT-13-0710-FIL (705-1392-5).

Metals

Method 6020B - Total Recoverable: The matrix spike / matrix spike duplicate (MS/MSD) recoveries for preparation batch 705-3002 and analytical batch 705-3132 were outside control limits. Sample matrix interference is suspected because the associated laboratory control sample (LCS) recovery was within acceptance limits.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1392-1

Client Sample ID: PT-07-0710-FIL

Lab Sample ID: 705-1392-1

Date Collected: 07/10/24 19:40

Matrix: Water

Date Received: 07/11/24 09:05

Method: SW846 6010D - Metals (ICP) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.49		0.040	0.026	mg/L			07/11/24 17:24	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.23		0.0050	0.0013	mg/L			07/12/24 11:39	1
Iron, Dissolved	14		0.040	0.018	mg/L			07/12/24 11:39	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1392-1

Client Sample ID: PT-07-0710-UNF

Lab Sample ID: 705-1392-2

Date Collected: 07/10/24 19:40

Matrix: Water

Date Received: 07/11/24 09:05

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.54		0.040	0.026	mg/L		07/11/24 12:55	07/11/24 20:13	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.32		0.0050	0.0013	mg/L		07/11/24 13:12	07/11/24 19:44	1
Iron	41		0.20	0.089	mg/L		07/11/24 13:12	07/12/24 15:36	5

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1392-1

Client Sample ID: PT-08-0710-FIL

Lab Sample ID: 705-1392-3

Date Collected: 07/10/24 21:00

Matrix: Water

Date Received: 07/11/24 09:05

Method: SW846 6010D - Metals (ICP) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.69		0.040	0.026	mg/L			07/11/24 17:27	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.26		0.0050	0.0013	mg/L			07/12/24 11:41	1
Iron, Dissolved	9.1		0.040	0.018	mg/L			07/12/24 11:41	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1392-1

Client Sample ID: PT-08-0710-UNF

Lab Sample ID: 705-1392-4

Date Collected: 07/10/24 21:00

Matrix: Water

Date Received: 07/11/24 09:05

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.74		0.040	0.026	mg/L		07/11/24 12:55	07/11/24 20:17	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.33	F1	0.0050	0.0013	mg/L		07/11/24 13:12	07/11/24 19:25	1
Iron	22		0.20	0.089	mg/L		07/11/24 13:12	07/12/24 15:24	5

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1392-1

Client Sample ID: PT-13-0710-FIL

Lab Sample ID: 705-1392-5

Date Collected: 07/10/24 20:12

Matrix: Water

Date Received: 07/11/24 09:05

Method: SW846 6010D - Metals (ICP) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.56		0.040	0.026	mg/L			07/11/24 17:30	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.23		0.0050	0.0013	mg/L			07/12/24 11:44	1
Iron, Dissolved	11		0.040	0.018	mg/L			07/12/24 11:44	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1392-1

Client Sample ID: PT-13-0710-UNF

Lab Sample ID: 705-1392-6

Date Collected: 07/10/24 20:12

Matrix: Water

Date Received: 07/11/24 09:05

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.56		0.040	0.026	mg/L		07/11/24 12:55	07/11/24 20:20	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.29		0.0050	0.0013	mg/L		07/11/24 13:12	07/11/24 19:48	1
Iron	80		20	8.9	mg/L		07/11/24 13:12	07/12/24 11:26	500

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1392-1

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-2944/1-A
Matrix: Water
Analysis Batch: 3123

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 2944

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	ND		0.040	0.026	mg/L		07/11/24 09:22	07/11/24 19:27	1

Lab Sample ID: LCS 705-2944/2-A
Matrix: Water
Analysis Batch: 3123

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 2944

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	1.00	1.03		mg/L		103	80 - 120

Lab Sample ID: 705-1262-F-3-B MS
Matrix: Water
Analysis Batch: 3123

Client Sample ID: Matrix Spike
Prep Type: Total/NA
Prep Batch: 2944

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	ND		1.00	1.05		mg/L		105	75 - 125

Lab Sample ID: 705-1262-F-3-C MSD
Matrix: Water
Analysis Batch: 3123

Client Sample ID: Matrix Spike Duplicate
Prep Type: Total/NA
Prep Batch: 2944

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron	ND		1.00	1.06		mg/L		106	75 - 125	1	20

Lab Sample ID: MB 705-3013/1-A
Matrix: Water
Analysis Batch: 3163

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	ND		0.040	0.026	mg/L			07/11/24 17:10	1

Lab Sample ID: LCS 705-3013/2-A
Matrix: Water
Analysis Batch: 3163

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron, Dissolved	1.00	0.979		mg/L		98	80 - 120

Lab Sample ID: LCSD 705-3013/6-A
Matrix: Water
Analysis Batch: 3163

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron, Dissolved	1.00	0.973		mg/L		97	80 - 120	1	20

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1392-1

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-3002/1-A

Matrix: Water

Analysis Batch: 3132

Client Sample ID: Method Blank

Prep Type: Total Recoverable

Prep Batch: 3002

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	ND		0.0050	0.0013	mg/L		07/11/24 13:12	07/11/24 19:17	1
Iron	ND		0.040	0.018	mg/L		07/11/24 13:12	07/11/24 19:17	1

Lab Sample ID: LCS 705-3002/2-A

Matrix: Water

Analysis Batch: 3132

Client Sample ID: Lab Control Sample

Prep Type: Total Recoverable

Prep Batch: 3002

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.100	0.0932		mg/L		93	80 - 120
Iron	1.00	1.02		mg/L		102	80 - 120

Lab Sample ID: 705-1392-4 MS

Matrix: Water

Analysis Batch: 3132

Client Sample ID: PT-08-0710-UNF

Prep Type: Total Recoverable

Prep Batch: 3002

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.33	F1	0.100	0.405		mg/L		71	75 - 125

Lab Sample ID: 705-1392-4 MS

Matrix: Water

Analysis Batch: 3279

Client Sample ID: PT-08-0710-UNF

Prep Type: Total Recoverable

Prep Batch: 3002

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Iron	22		1.00	22.8	4	mg/L		66	75 - 125

Lab Sample ID: 705-1392-4 MSD

Matrix: Water

Analysis Batch: 3132

Client Sample ID: PT-08-0710-UNF

Prep Type: Total Recoverable

Prep Batch: 3002

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic	0.33	F1	0.100	0.419		mg/L		85	75 - 125	3	20

Lab Sample ID: 705-1392-4 MSD

Matrix: Water

Analysis Batch: 3279

Client Sample ID: PT-08-0710-UNF

Prep Type: Total Recoverable

Prep Batch: 3002

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Iron	22		1.00	24.5	4	mg/L		236	75 - 125	7	20

Lab Sample ID: MB 705-3021/1-A

Matrix: Water

Analysis Batch: 3175

Client Sample ID: Method Blank

Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	ND		0.0050	0.0013	mg/L			07/12/24 11:31	1
Iron, Dissolved	ND		0.040	0.018	mg/L			07/12/24 11:31	1

Eurofins Atlanta

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1392-1

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: LCS 705-3021/2-A				Client Sample ID: Lab Control Sample			
Matrix: Water				Prep Type: Dissolved			
Analysis Batch: 3175							
Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic, Dissolved	0.100	0.0933		mg/L		93	80 - 120
Iron, Dissolved	1.00	0.868		mg/L		87	80 - 120

Lab Sample ID: LCSD 705-3021/3-A					Client Sample ID: Lab Control Sample Dup						
Matrix: Water					Prep Type: Dissolved						
Analysis Batch: 3175											
				Spike	LCSD	LCSD			%Rec		RPD
Analyte				Added	Result	Qualifier	Unit	D	%Rec	Limits	RPD
Arsenic, Dissolved				0.100	0.0894		mg/L		89	80 - 120	4
Iron, Dissolved				1.00	0.829		mg/L		83	80 - 120	5

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1392-1

Client Sample ID: PT-07-0710-FIL

Lab Sample ID: 705-1392-1

Date Collected: 07/10/24 19:40

Matrix: Water

Date Received: 07/11/24 09:05

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	3163	DAB	EET ATL	07/11/24 17:24
Dissolved	Analysis	6020B		1	3175	AD	EET ATL	07/12/24 11:39

Client Sample ID: PT-07-0710-UNF

Lab Sample ID: 705-1392-2

Date Collected: 07/10/24 19:40

Matrix: Water

Date Received: 07/11/24 09:05

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			2944	SA	EET ATL	07/11/24 12:55
Total/NA	Analysis	6010D		1	3123	DS	EET ATL	07/11/24 20:13
Total Recoverable	Prep	3005A			3002	BL	EET ATL	07/11/24 13:12
Total Recoverable	Analysis	6020B		5	3279	AD	EET ATL	07/12/24 15:36
Total Recoverable	Prep	3005A			3002	BL	EET ATL	07/11/24 13:12
Total Recoverable	Analysis	6020B		1	3132	IF	EET ATL	07/11/24 19:44

Client Sample ID: PT-08-0710-FIL

Lab Sample ID: 705-1392-3

Date Collected: 07/10/24 21:00

Matrix: Water

Date Received: 07/11/24 09:05

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	3163	DAB	EET ATL	07/11/24 17:27
Dissolved	Analysis	6020B		1	3175	AD	EET ATL	07/12/24 11:41

Client Sample ID: PT-08-0710-UNF

Lab Sample ID: 705-1392-4

Date Collected: 07/10/24 21:00

Matrix: Water

Date Received: 07/11/24 09:05

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			2944	SA	EET ATL	07/11/24 12:55
Total/NA	Analysis	6010D		1	3123	DS	EET ATL	07/11/24 20:17
Total Recoverable	Prep	3005A			3002	BL	EET ATL	07/11/24 13:12
Total Recoverable	Analysis	6020B		5	3279	AD	EET ATL	07/12/24 15:24
Total Recoverable	Prep	3005A			3002	BL	EET ATL	07/11/24 13:12
Total Recoverable	Analysis	6020B		1	3132	IF	EET ATL	07/11/24 19:25

Client Sample ID: PT-13-0710-FIL

Lab Sample ID: 705-1392-5

Date Collected: 07/10/24 20:12

Matrix: Water

Date Received: 07/11/24 09:05

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	3163	DAB	EET ATL	07/11/24 17:30
Dissolved	Analysis	6020B		1	3175	AD	EET ATL	07/12/24 11:44

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1392-1

Client Sample ID: PT-13-0710-UNF

Lab Sample ID: 705-1392-6

Date Collected: 07/10/24 20:12

Matrix: Water

Date Received: 07/11/24 09:05

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			2944	SA	EET ATL	07/11/24 12:55
Total/NA	Analysis	6010D		1	3123	DS	EET ATL	07/11/24 20:20
Total Recoverable	Prep	3005A			3002	BL	EET ATL	07/11/24 13:12
Total Recoverable	Analysis	6020B		500	3175	AD	EET ATL	07/12/24 11:26
Total Recoverable	Prep	3005A			3002	BL	EET ATL	07/11/24 13:12
Total Recoverable	Analysis	6020B		1	3132	IF	EET ATL	07/11/24 19:48

Laboratory References:
EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1392-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

1
2
3
4
5
6
7
8
9
10
11
12
13

Method Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1392-1

Method	Method Description	Protocol	Laboratory
6010D	Metals (ICP)	SW846	EET ATL
6020B	Metals (ICP/MS)	SW846	EET ATL
3005A	Preparation, Total Recoverable or Dissolved Metals	SW846	EET ATL
3010A	Preparation, Total Metals	SW846	EET ATL

Protocol References:

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Sample Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1392-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-1392-1	PT-07-0710-FIL	Water	07/10/24 19:40	07/11/24 09:05
705-1392-2	PT-07-0710-UNF	Water	07/10/24 19:40	07/11/24 09:05
705-1392-3	PT-08-0710-FIL	Water	07/10/24 21:00	07/11/24 09:05
705-1392-4	PT-08-0710-UNF	Water	07/10/24 21:00	07/11/24 09:05
705-1392-5	PT-13-0710-FIL	Water	07/10/24 20:12	07/11/24 09:05
705-1392-6	PT-13-0710-UNF	Water	07/10/24 20:12	07/11/24 09:05

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-1392-1

Login Number: 1392

List Source: Eurofins Atlanta

List Number: 1

Creator: Pomuti, Carmen

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	N/A	
Sample custody seals, if present, are intact.	N/A	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	False	Limited volume received.
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT



ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 7/12/2024 6:18:03 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-1526-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
7/12/2024 6:18:03 PM



Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
Lab Chronicle	15
Certification Summary	17
Method Summary	18
Sample Summary	19
Receipt Checklists	20
End Of Report	21

Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1526-1

Qualifiers

Metals

Qualifier	Qualifier Description
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Environment Testing

Client Information		Sampler: Jamie Newsome		Lab PM: David Fuller / Phone 770-344-8986		Carrier Tracking No(s)		COC No.	
Client Contact: Kip Gray		Phone		E-Mail: David.Fuller@et.eurofinsus.com		State of Origin: GA		Page 1 of 1	
Company: Geosyntec Consultants Inc				PWSID:		Analysis Requested			
Address: 1255 Roberts Blvd, NW Suite 200		Due Date Requested		6010D - Total Boron 6020B - Total Arsenic and Iron 6020B - Total Iron and Molybdenum 6010D - Dissolved Boron - Field Filtered (FF) 6020B - Dissolved Arsenic and Iron (FF) 6020B - Dissolved Iron and Molybdenum (FF)		Preservation Codes D - HNO3			
City: Kennesaw		TAT Requested (days): Same day RUSH / 1-Day TAT				Other:			
State Zip: GA, 30144		Compliance Project: ☐ Yes ☐ No							
Phone		Lab Project #: 70500911 (DO NOT REMOVE)							
Email: Kip.Gray@Geosyntec.com		PO #:							
Project Name: Plant Hammond		Project #:							
Task Code: Task Code#:		SSOW#:							
Sample Identification		Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, B=soil, O=wastewater, BT=Tissue, A=Air)				
PT-9-07-11-FIL		7/11/24	1800	G	W	X			
PT-9-07-11-UNF		7/11/24	1800	G	W		X	X	
PT-10-07-11-FIL		7/11/24	1800	G	W	X			
PT-10-07-11-UNF		7/11/24	1800	G	W		X	X	
PT-11-07-11-FIL		7/11/24	1800	G	W	X			
PT-11-07-11-UNF		7/11/24	2000	G	W		X	X	
PT-12-07-11-FIL		7/11/24	2000	G	W	X			
PT-12-07-11-UNF		7/11/24	2000	G	W		X	X	
Possible Hazard Identification ☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☐ Unknown ☐ Radiological Sample Disposal (A fee may be assessed if samples are retained longer than 1 month) ☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months									
Deliverable Requested I, II, III, IV, Other (specify)						Special Instructions/QC Requirements			
Empty Kit Relinquished by		Date		Time		Method of Shipment			
Relinquished by: Jamie Newsome		Date/Time: 7/12/24 1700		Company: Geosyntec		Received by: [Signature]		Date/Time: 7-12-24 7:00	
Relinquished by: [Signature]		Date/Time: 7-12-24 8:45		Company: Geosyntec		Received by: Anna Neal		Date/Time: 7-12-24 845	
Relinquished by: [Signature]		Date/Time: 7-12-24 845		Company: Geosyntec		Received by: [Signature]		Date/Time: 7-12-24 845	
Custody Seals Intact: ☐ Yes ☐ No		Custody Seal No		Cooler Temperature(s) °C and Other Remarks: # 2655 4.9°C					

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-1526-1

Job ID: 705-1526-1

Eurofins Atlanta

Job Narrative 705-1526-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers are applied to indicate exceptions. Noncompliant quality control (QC) is further explained in narrative comments.

- Matrix QC may not be reported if insufficient sample or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 7/12/2024 8:45 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 4.9°C.

Metals

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1526-1

Client Sample ID: PT-9-07-11-FIL

Lab Sample ID: 705-1526-1

Date Collected: 07/11/24 18:00

Matrix: Water

Date Received: 07/12/24 08:45

Method: SW846 6010D - Metals (ICP) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	1.4		0.040	0.026	mg/L			07/12/24 12:00	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron, Dissolved	0.020	J	0.040	0.018	mg/L			07/12/24 15:53	1
Molybdenum, Dissolved	0.42		0.0050	0.00069	mg/L			07/12/24 15:53	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1526-1

Client Sample ID: PT-9-07-11-UNF

Lab Sample ID: 705-1526-2

Date Collected: 07/11/24 18:00

Matrix: Water

Date Received: 07/12/24 08:45

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	1.5		0.040	0.026	mg/L		07/12/24 09:41	07/12/24 12:06	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron	0.56		0.040	0.018	mg/L		07/12/24 09:45	07/12/24 16:02	1
Molybdenum	0.43		0.0050	0.00069	mg/L		07/12/24 09:45	07/12/24 16:02	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1526-1

Client Sample ID: PT-10-07-11-FIL

Lab Sample ID: 705-1526-3

Date Collected: 07/11/24 18:00

Matrix: Water

Date Received: 07/12/24 08:45

Method: SW846 6010D - Metals (ICP) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	1.7		0.040	0.026	mg/L			07/12/24 12:07	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron, Dissolved	ND		0.040	0.018	mg/L			07/12/24 15:55	1
Molybdenum, Dissolved	0.15		0.0050	0.00069	mg/L			07/12/24 15:55	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1526-1

Client Sample ID: PT-10-07-11-UNF

Lab Sample ID: 705-1526-4

Date Collected: 07/11/24 18:00

Matrix: Water

Date Received: 07/12/24 08:45

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	1.6		0.040	0.026	mg/L		07/12/24 09:41	07/12/24 12:15	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron	0.37		0.040	0.018	mg/L		07/12/24 09:45	07/12/24 16:05	1
Molybdenum	0.16		0.0050	0.00069	mg/L		07/12/24 09:45	07/12/24 16:05	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1526-1

Client Sample ID: PT-11-07-11-FIL

Lab Sample ID: 705-1526-5

Date Collected: 07/11/24 20:00

Matrix: Water

Date Received: 07/12/24 08:45

Method: SW846 6010D - Metals (ICP) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.72		0.040	0.026	mg/L			07/12/24 12:10	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron, Dissolved	2.4		0.040	0.018	mg/L			07/12/24 15:57	1
Molybdenum, Dissolved	0.047		0.0050	0.00069	mg/L			07/12/24 15:57	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1526-1

Client Sample ID: PT-11-07-11-UNF

Lab Sample ID: 705-1526-6

Date Collected: 07/11/24 20:00

Matrix: Water

Date Received: 07/12/24 08:45

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.69		0.040	0.026	mg/L		07/12/24 09:41	07/12/24 12:18	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron	3.2		0.040	0.018	mg/L		07/12/24 09:45	07/12/24 16:07	1
Molybdenum	0.046		0.0050	0.00069	mg/L		07/12/24 09:45	07/12/24 16:07	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1526-1

Client Sample ID: PT-12-07-11-FIL

Lab Sample ID: 705-1526-7

Date Collected: 07/11/24 20:00

Matrix: Water

Date Received: 07/12/24 08:45

Method: SW846 6010D - Metals (ICP) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	1.6		0.040	0.026	mg/L			07/12/24 12:13	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron, Dissolved	ND		0.040	0.018	mg/L			07/12/24 16:00	1
Molybdenum, Dissolved	0.30		0.0050	0.00069	mg/L			07/12/24 16:00	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1526-1

Client Sample ID: PT-12-07-11-UNF

Lab Sample ID: 705-1526-8

Date Collected: 07/11/24 20:00

Matrix: Water

Date Received: 07/12/24 08:45

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	1.5		0.040	0.026	mg/L		07/12/24 09:41	07/12/24 12:21	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron	0.10		0.040	0.018	mg/L		07/12/24 09:45	07/12/24 16:09	1
Molybdenum	0.31		0.0050	0.00069	mg/L		07/12/24 09:45	07/12/24 16:09	1

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1526-1

Client Sample ID: PT-0-71-FF-5IL

Lab Sample ID: 173-F392-F

Date Collected: 71/FF/94 FR:77

Matrix: Water

Date v eceiyed: 71/F9/94 7R:43

Prep TBpe	Aatch TBpe	Aatch Method	v z n	Dilz tion 5actor	Aatch Uz mber	s nalBut	Lab	Prepared or s nalBnd
Dissolved	Analysis	6010D		1	3200	DAB	EET ATL	07/12/24 12:00
Dissolved	Analysis	6020B		1	3279	AD	EET ATL	07/12/24 15:53

Client Sample ID: PT-0-71-FF-8 U5

Lab Sample ID: 173-F392-9

Date Collected: 71/FF/94 FR:77

Matrix: Water

Date v eceiyed: 71/F9/94 7R:43

Prep TBpe	Aatch TBpe	Aatch Method	v z n	Dilz tion 5actor	Aatch Uz mber	s nalBut	Lab	Prepared or s nalBnd
Total/NA	Prep	3010A			2944	SA	EET ATL	07/12/24 09:41
Total/NA	Analysis	6010D		1	3192	DS	EET ATL	07/12/24 12:06
Total Recoverable	Prep	3005A			3002	BL	EET ATL	07/12/24 09:45
Total Recoverable	Analysis	6020B		1	3279	AD	EET ATL	07/12/24 16:02

Client Sample ID: PT-F7-71-FF-5IL

Lab Sample ID: 173-F392-6

Date Collected: 71/FF/94 FR:77

Matrix: Water

Date v eceiyed: 71/F9/94 7R:43

Prep TBpe	Aatch TBpe	Aatch Method	v z n	Dilz tion 5actor	Aatch Uz mber	s nalBut	Lab	Prepared or s nalBnd
Dissolved	Analysis	6010D		1	3200	DAB	EET ATL	07/12/24 12:07
Dissolved	Analysis	6020B		1	3279	AD	EET ATL	07/12/24 15:55

Client Sample ID: PT-F7-71-FF-8 U5

Lab Sample ID: 173-F392-4

Date Collected: 71/FF/94 FR:77

Matrix: Water

Date v eceiyed: 71/F9/94 7R:43

Prep TBpe	Aatch TBpe	Aatch Method	v z n	Dilz tion 5actor	Aatch Uz mber	s nalBut	Lab	Prepared or s nalBnd
Total/NA	Prep	3010A			2944	SA	EET ATL	07/12/24 09:41
Total/NA	Analysis	6010D		1	3192	DS	EET ATL	07/12/24 12:15
Total Recoverable	Prep	3005A			3002	BL	EET ATL	07/12/24 09:45
Total Recoverable	Analysis	6020B		1	3279	AD	EET ATL	07/12/24 16:05

Client Sample ID: PT-FF-71-FF-5IL

Lab Sample ID: 173-F392-3

Date Collected: 71/FF/94 97:77

Matrix: Water

Date v eceiyed: 71/F9/94 7R:43

Prep TBpe	Aatch TBpe	Aatch Method	v z n	Dilz tion 5actor	Aatch Uz mber	s nalBut	Lab	Prepared or s nalBnd
Dissolved	Analysis	6010D		1	3200	DAB	EET ATL	07/12/24 12:10
Dissolved	Analysis	6020B		1	3279	AD	EET ATL	07/12/24 15:57

Client Sample ID: PT-FF-71-FF-8 U5

Lab Sample ID: 173-F392-2

Date Collected: 71/FF/94 97:77

Matrix: Water

Date v eceiyed: 71/F9/94 7R:43

Prep TBpe	Aatch TBpe	Aatch Method	v z n	Dilz tion 5actor	Aatch Uz mber	s nalBut	Lab	Prepared or s nalBnd
Total/NA	Prep	3010A			2944	SA	EET ATL	07/12/24 09:41
Total/NA	Analysis	6010D		1	3192	DS	EET ATL	07/12/24 12:18

Eurofins Atlanta

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1526-1

Client Sample ID: PT-FF-71-FF-8 U5
Date Collected: 71/FF/94 97:77
Date v eceiyed: 71/F9/94 7R43

Lab Sample ID: 173-F392-2
Matrix: Water

Prep TBpe	Aatch TBpe	Aatch Method	v z n	Dilz tion 5actor	Aatch Uz mber	s nalBut	Lab	Prepared or s nalBEd
Total Recoverable	Prep	3005A			3002	BL	EET ATL	07/12/24 09:45
Total Recoverable	Analysis	6020B		1	3279	AD	EET ATL	07/12/24 16:07

Client Sample ID: PT-F9-71-FF-5IL
Date Collected: 71/FF/94 97:77
Date v eceiyed: 71/F9/94 7R43

Lab Sample ID: 173-F392-1
Matrix: Water

Prep TBpe	Aatch TBpe	Aatch Method	v z n	Dilz tion 5actor	Aatch Uz mber	s nalBut	Lab	Prepared or s nalBEd
Dissolved	Analysis	6010D		1	3200	DAB	EET ATL	07/12/24 12:13
Dissolved	Analysis	6020B		1	3279	AD	EET ATL	07/12/24 16:00

Client Sample ID: PT-F9-71-FF-8 U5
Date Collected: 71/FF/94 97:77
Date v eceiyed: 71/F9/94 7R43

Lab Sample ID: 173-F392-R
Matrix: Water

Prep TBpe	Aatch TBpe	Aatch Method	v z n	Dilz tion 5actor	Aatch Uz mber	s nalBut	Lab	Prepared or s nalBEd
Total/NA	Prep	3010A			2944	SA	EET ATL	07/12/24 09:41
Total/NA	Analysis	6010D		1	3192	DS	EET ATL	07/12/24 12:21
Total Recoverable	Prep	3005A			3002	BL	EET ATL	07/12/24 09:45
Total Recoverable	Analysis	6020B		1	3279	AD	EET ATL	07/12/24 16:09

LaboratorB v eferenceu:
EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1526-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12

Method Summary

2025-01-20 10:00 AM
aPbri yrf/ lri : aQenSuHHoem

Job ID: 705-1539-1

Method	Method Description	Protocol	Laboratory
9010D	4 i ruG82aM	/ d V89	(() E) T
9030A	4 i ruG82aj4 / M	/ d V89	(() E) T
L005E	aR BuRurloep)onuG, i yoR RubC oPDIGbCR m4 i ruG	/ d V89	(() E) T
L010E	aR BuRurloep)onuG i ruG	/ d V89	(() E) T

Protocol References:
/ d V89 v =>i Gh4 i r' onGhoP(RuGurleF / oQnd uGi pa"sGyuG2"i HlyuG4 i r' onGp) "IRn(mtrloepg oR Hbi P1NwEemlrGUBmuri G

Laboratory References:
(() E) T v (cRfleGEnQerupL0W0 aR Gmi erluCDPqErQerupt E L0L80p) (T 6770N857-VI77



Sample Summary

Client: Geosyntec Consultants Inc
2025-07-12 10:00 AM

Job ID: 705-1539-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-1539-1	2d-T-07-11-FIL	Water	07/11/24 10:00	07/13/24 00:45
705-1539-3	2d-T-07-11-N8 F	Water	07/11/24 10:00	07/13/24 00:45
705-1539-6	2d-10-07-11-FIL	Water	07/11/24 10:00	07/13/24 00:45
705-1539-4	2d-10-07-11-N8 F	Water	07/11/24 10:00	07/13/24 00:45
705-1539-5	2d-11-07-11-FIL	Water	07/11/24 30:00	07/13/24 00:45
705-1539-9	2d-11-07-11-N8 F	Water	07/11/24 30:00	07/13/24 00:45
705-1539-7	2d-13-07-11-FIL	Water	07/11/24 30:00	07/13/24 00:45
705-1539-U	2d-13-07-11-N8 F	Water	07/11/24 30:00	07/13/24 00:45

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-1526-1

Login Number: 1526

List Source: Eurofins Atlanta

List Number: 1

Creator: Pomuti, Carmen

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	N/A	
Sample custody seals, if present, are intact.	N/A	Not Present
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT



ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 7/13/2024 3:21:28 PM

JOB DESCRIPTION

Plant Hammond - HAM

JOB NUMBER

705-1720-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
7/13/2024 3:21:28 PM

Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	13
Lab Chronicle	15
Certification Summary	17
Method Summary	18
Sample Summary	19
Receipt Checklists	20
End Of Report	21



Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond - HAM

Job ID: 705-1720-1

Qualifiers

Metals

Qualifier	Qualifier Description
4	MS, MSD: The analyte present in the original sample is greater than 4 times the matrix spike concentration; therefore, control limits are not applicable.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Chain of Custody Record

Client Information		Sampler Tammie Newsome		Lab PM David Fuller / Phone 770-344-8986		Carrier Tracking No(s):		COC No:																			
Client Contact: Kip Gray		Phone:		E-Mail: David.Fuller@et.eurofinsus.com		State of Origin GA		Page of																			
Company: Geosyntec Consultants Inc		PWSID:		Analysis Requested						Job #:																	
Address: 1255 Roberts Blvd, NW Suite 200		Due Date Requested:								Preservation Codes: D - HNO ₃																	
City: Kennesaw		TAT Requested (days) RUSH / 1 Day TAT																									
State, Zip: GA, 30144		Compliance Project Δ Yes Δ No																									
Phone:		Lab Project #: 70500811 (DO NOT REMOVE)																									
Email: Kip.Gray@Geosyntec.com		PO #:																									
Project Name Plant Hammond		Project #:								Other:																	
Task Code: Task Code#: HAM		SSOW#:																									
Sample Identification		Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=soil/silt, BT=Tree, A=Air)	60100 - Total Boron	60208 - Total Arsenic and Iron	60209 - Total Iron and Molybdenum	60100 - Dissolved Boron - Field Filtered (FF)	60208 - Dissolved Arsenic and Iron (FF)	60209 - Dissolved Iron and Molybdenum (FF)	Special Instructions/Note:															
HAM PT 07-0712 UNF		7/12/24	1812	G	WI	X	X					 70 05 1720 COC															
HAM - PT-07-0712 FIL		7/12/24	1812	G	WI	X			X	X																	
HAM - PT-13-0712 UNF		7/12/24	1847	G	WI		X	X																			
HAM - PT-13-0712 FIL		7/12/24	1847	G	AI	A			X	X																	
HAM - PT-14-0712 UNF		7/12/24		G	WI		X	X																			
HAM - PT-14-0712-FIL		7/12/24		G	WI	A			X	X																	
Possible Hazard Identification														Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)													
☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☐ Unknown ☐ Radiological														☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months													
Deliverable Requested I, II, III, IV, Other (specify)														Special Instructions/QC Requirements													
Empty Kit Relinquished by														Date		Time		Method of Shipment:									
Relinquished by: Tammie Newsome														Date/Time: 7/13/24 7:00		Company		Received by: [Signature]		Date/Time: 7-15-24 7:00		Company					
Relinquished by: [Signature]														Date/Time: 7-13-24 8:15		Company		Received by: Fullana Williams 8:30		Date/Time: 7-13 8:30		Company					
Relinquished by: [Signature]														Date/Time:		Company		Received by:		Date/Time:		Company					
Custody Seals Intact: Δ Yes Δ No														Custody Seal No.		Cooler Temperature(s) °C and Other Remarks: 1.2 Courier											

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond - HAM

Job ID: 705-1720-1

Job ID: 705-1720-1

Eurofins Atlanta

Job Narrative 705-1720-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers are applied to indicate exceptions. Noncompliant quality control (QC) is further explained in narrative comments.

- Matrix QC may not be reported if insufficient sample or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 7/1 /2024 8: 0 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 1.2°C.

Metals

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond - HAM

Job ID: 705-1720-1

Client Sample ID: HAM-PT-07-0712-UNF
Date Collected: 07/12/24 18:12
Date Received: 07/13/24 08:30

Lab Sample ID: 705-1720-1
Matrix: Water

Method: SW846 6010D - Metals (ICP)										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Boron	0.52		0.040	0.026	mg/L		07/13/24 09:52	07/13/24 13:36	1	

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Arsenic	0.24		0.0050	0.0013	mg/L		07/13/24 09:27	07/13/24 13:45	1	
Iron	17		0.040	0.018	mg/L		07/13/24 09:27	07/13/24 13:45	1	

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond - HAM

Job ID: 705-1720-1

Client Sample ID: HAM-PT-07-0712-FIL
Date Collected: 07/12/24 18:12
Date Received: 07/13/24 08:30

Lab Sample ID: 705-1720-2
Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.53		0.040	0.026	mg/L			07/13/24 11:34	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.16		0.0050	0.0013	mg/L			07/13/24 12:47	1
Iron, Dissolved	12		0.040	0.018	mg/L			07/13/24 12:47	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond - HAM

Job ID: 705-1720-1

Client Sample ID: HAM-PT-13-0712-UNF
Date Collected: 07/12/24 18:47
Date Received: 07/13/24 08:30

Lab Sample ID: 705-1720-3
Matrix: Water

Method: SW846 6010D - Metals (ICP)										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Boron	0.58		0.040	0.026	mg/L		07/13/24 09:52	07/13/24 13:39	1	

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Arsenic	0.30		0.0050	0.0013	mg/L		07/13/24 09:27	07/13/24 13:23	1	
Iron	24		0.040	0.018	mg/L		07/13/24 09:27	07/13/24 13:23	1	

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond - HAM

Job ID: 705-1720-1

Client Sample ID: HAM-PT-13-0712-FIL
Date Collected: 07/12/24 18:47
Date Received: 07/13/24 08:30

Lab Sample ID: 705-1720-4
Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.59		0.040	0.026	mg/L			07/13/24 11:37	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.23		0.0050	0.0013	mg/L			07/13/24 12:49	1
Iron, Dissolved	13		0.040	0.018	mg/L			07/13/24 12:49	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond - HAM

Job ID: 705-1720-1

Client Sample ID: HAM-PT-14-0712-UNF
Date Collected: 07/12/24 00:00
Date Received: 07/13/24 08:30

Lab Sample ID: 705-1720-5
Matrix: Water

Method: SW846 6010D - Metals (ICP)									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.46		0.040	0.026	mg/L		07/13/24 09:52	07/13/24 13:15	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.17		0.0050	0.0013	mg/L		07/13/24 09:27	07/13/24 13:48	1
Iron	53		0.20	0.089	mg/L		07/13/24 09:27	07/13/24 13:56	5

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond - HAM

Job ID: 705-1720-1

Client Sample ID: HAM-PT-14-0712-FIL
Date Collected: 07/12/24 00:00
Date Received: 07/13/24 08:30

Lab Sample ID: 705-1720-6
Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.44		0.040	0.026	mg/L			07/13/24 11:40	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.079		0.0050	0.0013	mg/L			07/13/24 12:59	1
Iron, Dissolved	10		0.040	0.018	mg/L			07/13/24 12:59	1

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond - HAM

Job ID: 705-1720-1

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-3323/1-A
Matrix: Water
Analysis Batch: 3347

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 3323

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	ND		0.040	0.026	mg/L		07/13/24 09:52	07/13/24 13:10	1

Lab Sample ID: LCS 705-3323/2-A
Matrix: Water
Analysis Batch: 3347

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 3323

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	1.00	0.968		mg/L		97	80 - 120

Lab Sample ID: 705-1720-5 MS
Matrix: Water
Analysis Batch: 3347

Client Sample ID: HAM-PT-14-0712-UNF
Prep Type: Total/NA
Prep Batch: 3323

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	0.46		1.00	1.38		mg/L		92	75 - 125

Lab Sample ID: 705-1720-5 MSD
Matrix: Water
Analysis Batch: 3347

Client Sample ID: HAM-PT-14-0712-UNF
Prep Type: Total/NA
Prep Batch: 3323

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	Limit
Boron	0.46		1.00	1.38		mg/L		92	75 - 125	0	20

Lab Sample ID: MB 705-3325/1-A
Matrix: Water
Analysis Batch: 3331

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	ND		0.040	0.026	mg/L			07/13/24 11:19	1

Lab Sample ID: LCS 705-3325/2-A
Matrix: Water
Analysis Batch: 3331

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron, Dissolved	1.00	1.04		mg/L		104	80 - 120

Lab Sample ID: LCSD 705-3325/3-A
Matrix: Water
Analysis Batch: 3331

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	Limit
Boron, Dissolved	1.00	1.04		mg/L		104	80 - 120	0	20

Eurofins Atlanta

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond - HAM

Job ID: 705-1720-1

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-3321/1-A
Matrix: Water
Analysis Batch: 3350

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 3321

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	ND		0.0050	0.0013	mg/L		07/13/24 09:27	07/13/24 13:18	1
Iron	ND		0.040	0.018	mg/L		07/13/24 09:27	07/13/24 13:18	1

Lab Sample ID: LCS 705-3321/2-A
Matrix: Water
Analysis Batch: 3350

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 3321

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.100	0.0909		mg/L		91	80 - 120
Iron	1.00	0.812		mg/L		81	80 - 120

Lab Sample ID: 705-1720-3 MS
Matrix: Water
Analysis Batch: 3350

Client Sample ID: HAM-PT-13-0712-UNF
Prep Type: Total Recoverable
Prep Batch: 3321

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.30		0.100	0.393		mg/L		97	75 - 125
Iron	24		1.00	25.2	4	mg/L		96	75 - 125

Lab Sample ID: 705-1720-3 MSD
Matrix: Water
Analysis Batch: 3350

Client Sample ID: HAM-PT-13-0712-UNF
Prep Type: Total Recoverable
Prep Batch: 3321

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic	0.30		0.100	0.386		mg/L		90	75 - 125	2	20
Iron	24		1.00	25.1	4	mg/L		88	75 - 125	0	20

Lab Sample ID: MB 705-3324/1-A
Matrix: Water
Analysis Batch: 3350

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	ND		0.0050	0.0013	mg/L			07/13/24 12:40	1
Iron, Dissolved	ND		0.040	0.018	mg/L			07/13/24 12:40	1

Lab Sample ID: LCS 705-3324/2-A
Matrix: Water
Analysis Batch: 3350

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic, Dissolved	0.100	0.0912		mg/L		91	80 - 120
Iron, Dissolved	1.00	0.829		mg/L		83	80 - 120

Lab Sample ID: LCSD 705-3324/3-A
Matrix: Water
Analysis Batch: 3350

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic, Dissolved	0.100	0.0876		mg/L		88	80 - 120	4	20
Iron, Dissolved	1.00	0.800		mg/L		80	80 - 120	4	20

Eurofins Atlanta

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond - HAM

Job ID: 705-1720-1

Client Sample ID: HAM-PT-07-0712-UNF

Lab Sample ID: 705-1720-1

Date Collected: 07/12/24 18:12

Matrix: Water

Date Received: 07/13/24 08:30

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			3323	EF	EET ATL	07/13/24 09:52
Total/NA	Analysis	6010D		1	3347	KB	EET ATL	07/13/24 13:36
Total Recoverable	Prep	3005A			3321	EF	EET ATL	07/13/24 09:27
Total Recoverable	Analysis	6020B		1	3350	TA	EET ATL	07/13/24 13:45

Client Sample ID: HAM-PT-07-0712-FIL

Lab Sample ID: 705-1720-2

Date Collected: 07/12/24 18:12

Matrix: Water

Date Received: 07/13/24 08:30

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	3331	KB	EET ATL	07/13/24 11:34
Dissolved	Analysis	6020B		1	3350	TA	EET ATL	07/13/24 12:47

Client Sample ID: HAM-PT-13-0712-UNF

Lab Sample ID: 705-1720-3

Date Collected: 07/12/24 18:47

Matrix: Water

Date Received: 07/13/24 08:30

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			3323	EF	EET ATL	07/13/24 09:52
Total/NA	Analysis	6010D		1	3347	KB	EET ATL	07/13/24 13:39
Total Recoverable	Prep	3005A			3321	EF	EET ATL	07/13/24 09:27
Total Recoverable	Analysis	6020B		1	3350	TA	EET ATL	07/13/24 13:23

Client Sample ID: HAM-PT-13-0712-FIL

Lab Sample ID: 705-1720-4

Date Collected: 07/12/24 18:47

Matrix: Water

Date Received: 07/13/24 08:30

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	3331	KB	EET ATL	07/13/24 11:37
Dissolved	Analysis	6020B		1	3350	TA	EET ATL	07/13/24 12:49

Client Sample ID: HAM-PT-14-0712-UNF

Lab Sample ID: 705-1720-5

Date Collected: 07/12/24 00:00

Matrix: Water

Date Received: 07/13/24 08:30

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			3323	EF	EET ATL	07/13/24 09:52
Total/NA	Analysis	6010D		1	3347	KB	EET ATL	07/13/24 13:15
Total Recoverable	Prep	3005A			3321	EF	EET ATL	07/13/24 09:27
Total Recoverable	Analysis	6020B		1	3350	TA	EET ATL	07/13/24 13:48
Total Recoverable	Prep	3005A			3321	EF	EET ATL	07/13/24 09:27
Total Recoverable	Analysis	6020B		5	3350	TA	EET ATL	07/13/24 13:56

Eurofins Atlanta

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond - HAM

Job ID: 705-1720-1

Client Sample ID: HAM-PT-14-0712-FIL
Date Collected: 07/12/24 00:00
Date Received: 07/13/24 08:30

Lab Sample ID: 705-1720-6
Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	3331	KB	EET ATL	07/13/24 11:40
Dissolved	Analysis	6020B		1	3350	TA	EET ATL	07/13/24 12:59

Laboratory References:
EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond - HAM

Job ID: 705-1720-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13

Method Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond - HAM

Job ID: 705-1720-1

Method	Method Description	Protocol	Laboratory
6010D	Metals (ICP)	SW846	EET ATL
6020B	Metals (ICP/MS)	SW846	EET ATL
3005A	Preparation, Total Recoverable or Dissolved Metals	SW846	EET ATL
3010A	Preparation, Total Metals	SW846	EET ATL

Protocol References:

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Sample Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond - HAM

Job ID: 705-1720-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-1720-1	HAM-PT-07-0712-UNF	Water	07/12/24 18:12	07/13/24 08:30
705-1720-2	HAM-PT-07-0712-FIL	Water	07/12/24 18:12	07/13/24 08:30
705-1720-3	HAM-PT-13-0712-UNF	Water	07/12/24 18:47	07/13/24 08:30
705-1720-4	HAM-PT-13-0712-FIL	Water	07/12/24 18:47	07/13/24 08:30
705-1720-5	HAM-PT-14-0712-UNF	Water	07/12/24 00:00	07/13/24 08:30
705-1720-6	HAM-PT-14-0712-FIL	Water	07/12/24 00:00	07/13/24 08:30

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-1720-1

Login Number: 1720

List Source: Eurofins Atlanta

List Number: 1

Creator: Mohamud, Fardowsa

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	N/A	Not present
Sample custody seals, if present, are intact.	N/A	Not Present
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT



ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 7/14/2024 3:19:46 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-1754-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
7/14/2024 3:19:46 PM



Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	7
Client Sample Results	8
QC Sample Results	20
Lab Chronicle	22
Certification Summary	25
Method Summary	26
Sample Summary	27
Receipt Checklists	28
End Of Report	29

Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1754-1

Qualifiers

Metals

Qualifier	Qualifier Description
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Eurofins Atlanta

3080 Presidential Dr
Atlanta, GA 30340
Phone (770) 457-8177

Chain of Custody Record



Environment Testing

Client Information		Sampler <i>James Newberry</i>		Lab PM David Fuller / Phone 770-344-8986		Carrier Tracking No(s)		COC No:				
Client Contact Kip Gray		Phone		E-Mail David.Fuller@et.eurofins.com		State of Origin GA		Page: Page 1 of 2				
Company Geosyntec Consultants Inc		PWSID		Analysis Requested								
Address 1255 Roberts Blvd, NW Suite 200		Due Date Requested		 705 1754 COC								
City Kennesaw		TAT Requested (days) RUSH / 1 Day TAT										
State Zip GA, 30144		Compliance Project. ☐ Yes ☐ No										
Phone		Lab Project #: 70500811 (DO NOT REMOVE)										
Email Kip.Gray@Geosyntec.com		PO #:										
Project Name Plant Hammond		Project #:		Other								
Task Code Task Code#:		SSOW#:										
Sample Identification		Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, S=solid, O=waste/soil, BT=Tissue, A=Air)	60100 - Total Boron	60208 - Total Arsenic and Iron	60208 - Total Iron and Molybdenum	60100 - Dissolved Boron - Field Filtered (FF)	60208 - Dissolved Arsenic and Iron (FF)	60208 - Dissolved Iron and Molybdenum (FF)	Special Instructions/Note:
HAM-PT-09-0713-FIL-AM		7/13/24	850	G	W	X			X	X		
HAM-PT-09-0713-VNF-AM		7/13/24	850	G	W		X	X				
HAM-PT-09-0713-FIL-PM		7/13/24	1640	G	W	X			X	X		
HAM-PT-09-0713-VNF-PM		7/13/24	1640	G	W		X	X				
HAM-PT-10-0713-FIL-AM		7/13/24	850	G	W	X			X	X		
HAM-PT-10-0713-VNF-AM		7/13/24	850	G	W		X	X				
HAM-PT-10-0713-FIL-PM		7/13/24	1640	G	W	X			X	X		
HAM-PT-10-0713-VNF-PM		7/13/24	1640	G	W		X	X				
HAM-PT-11-0713-FIL		7/13/24	1800	G	W	X			X	X		
HAM-PT-11-0713-VNF		7/13/24	1800	G	W		X	X				
HAM-PT-12-0713-FIL		7/13/24	1800	G	W	X			X	X		
Possible Hazard Identification ☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☐ Unknown ☐ Radiological						Sample Disposal (A fee may be assessed if samples are retained longer than 1 month) ☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months						
Deliverable Requested I, II, III, IV, Other (specify)						Special Instructions/QC Requirements						
Empty Kit Relinquished by		Date		Time		Method of Shipment:						
Relinquished by <i>James Newberry</i>		Date/Time 7/14/24 7:05		Company		Received by <i>David Fuller</i>		Date/Time 7/14/24 7:08		Company		
Relinquished by <i>[Signature]</i>		Date/Time 7/14/24 8:45		Company		Received by <i>David Fuller</i>		Date/Time 7/14/24 8:46		Company		
Relinquished by		Date/Time		Company		Received by 5.9°C #2641		Date/Time		Company		
Custody Seals Intact: ☐ Yes ☐ No		Custody Seal No		Cooler Temperature(s) °C and Other Remarks.								

Environment Testing

Page 6 of 29

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-1754-1

Job ID: 705-1754-1

Eurofins Atlanta

Job Narrative 705-1754-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers are applied to indicate exceptions. Noncompliant quality control (QC) is further explained in narrative comments.

- Matrix QC may not be reported if insufficient sample or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 7/14/2024 8:4 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 5.9°C.

Receipt Exceptions

The following sample was received at the laboratory without a sample collection time documented on the chain of custody: AM-PT-12-071 -UN (705-1754-12). Sample was logged in using the collection time on the bottle label.

Metals

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1754-1

Client Sample ID: HAM-PT-09-0713-FIL-AM

Lab Sample ID: 705-1754-1

Date Collected: 07/13/24 08:50

Matrix: Water

Date Received: 07/14/24 08:46

Method: SW846 6010D - Metals (ICP) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	1.5		0.040	0.026	mg/L			07/14/24 11:10	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron, Dissolved	ND		0.040	0.018	mg/L			07/14/24 12:27	1
Molybdenum, Dissolved	0.33		0.0050	0.00069	mg/L			07/14/24 12:27	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1754-1

Client Sample ID: HAM-PT-09-0713-UNF-AM

Lab Sample ID: 705-1754-2

Date Collected: 07/13/24 08:50

Matrix: Water

Date Received: 07/14/24 08:46

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	1.4		0.040	0.026	mg/L		07/14/24 10:04	07/14/24 12:36	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron	0.36		0.040	0.018	mg/L		07/14/24 10:25	07/14/24 14:02	1
Molybdenum	0.34		0.0050	0.00069	mg/L		07/14/24 10:25	07/14/24 14:02	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1754-1

Client Sample ID: HAM-PT-09-0713-FIL-PM
Date Collected: 07/13/24 16:40
Date Received: 07/14/24 08:46

Lab Sample ID: 705-1754-3
Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	1.2		0.040	0.026	mg/L			07/14/24 11:13	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron, Dissolved	0.30		0.040	0.018	mg/L			07/14/24 12:29	1
Molybdenum, Dissolved	0.29		0.0050	0.00069	mg/L			07/14/24 12:29	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1754-1

Client Sample ID: HAM-PT-09-0713-UNF-PM

Lab Sample ID: 705-1754-4

Date Collected: 07/13/24 16:40

Matrix: Water

Date Received: 07/14/24 08:46

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	1.1		0.040	0.026	mg/L		07/14/24 10:04	07/14/24 12:39	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron	0.66		0.040	0.018	mg/L		07/14/24 10:25	07/14/24 14:05	1
Molybdenum	0.29		0.0050	0.00069	mg/L		07/14/24 10:25	07/14/24 14:05	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1754-1

Client Sample ID: HAM-PT-10-0713-FIL-AM

Lab Sample ID: 705-1754-5

Date Collected: 07/13/24 08:50

Matrix: Water

Date Received: 07/14/24 08:46

Method: SW846 6010D - Metals (ICP) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	1.7		0.040	0.026	mg/L			07/14/24 11:22	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron, Dissolved	ND		0.040	0.018	mg/L			07/14/24 12:31	1
Molybdenum, Dissolved	0.17		0.0050	0.00069	mg/L			07/14/24 12:31	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1754-1

Client Sample ID: HAM-PT-10-0713-UNF-AM

Lab Sample ID: 705-1754-6

Date Collected: 07/13/24 08:50

Matrix: Water

Date Received: 07/14/24 08:46

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	1.6		0.040	0.026	mg/L		07/14/24 10:04	07/14/24 12:42	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron	0.19		0.040	0.018	mg/L		07/14/24 10:25	07/14/24 14:07	1
Molybdenum	0.16		0.0050	0.00069	mg/L		07/14/24 10:25	07/14/24 14:07	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1754-1

Client Sample ID: HAM-PT-10-0713-FIL-PM
Date Collected: 07/13/24 16:40
Date Received: 07/14/24 08:46

Lab Sample ID: 705-1754-7
Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	1.7		0.040	0.026	mg/L			07/14/24 11:24	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron, Dissolved	ND		0.040	0.018	mg/L			07/14/24 12:34	1
Molybdenum, Dissolved	0.16		0.0050	0.00069	mg/L			07/14/24 12:34	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1754-1

Client Sample ID: HAM-PT-10-0713-UNF-PM

Lab Sample ID: 705-1754-8

Date Collected: 07/13/24 16:40

Matrix: Water

Date Received: 07/14/24 08:46

Method: SW846 6010D - Metals (ICP)										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Boron	1.6		0.040	0.026	mg/L		07/14/24 10:04	07/14/24 12:44	1	

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Iron	0.12		0.040	0.018	mg/L		07/14/24 10:25	07/14/24 14:09	1	
Molybdenum	0.18		0.0050	0.00069	mg/L		07/14/24 10:25	07/14/24 14:09	1	

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1754-1

Client Sample ID: HAM-PT-11-0713-FIL
Date Collected: 07/13/24 18:00
Date Received: 07/14/24 08:46

Lab Sample ID: 705-1754-9
Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.60		0.040	0.026	mg/L			07/14/24 11:27	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron, Dissolved	9.0		0.040	0.018	mg/L			07/14/24 12:36	1
Molybdenum, Dissolved	0.022		0.0050	0.00069	mg/L			07/14/24 12:36	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1754-1

Client Sample ID: HAM-PT-11-0713-UNF
Date Collected: 07/13/24 18:00
Date Received: 07/14/24 08:46

Lab Sample ID: 705-1754-10
Matrix: Water

Method: SW846 6010D - Metals (ICP)										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Boron	0.57		0.040	0.026	mg/L		07/14/24 10:04	07/14/24 12:47	1	

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Iron	11		0.040	0.018	mg/L		07/14/24 10:25	07/14/24 14:12	1	
Molybdenum	0.024		0.0050	0.00069	mg/L		07/14/24 10:25	07/14/24 14:12	1	

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1754-1

Client Sample ID: HAM-PT-12-0713-FIL
Date Collected: 07/13/24 18:00
Date Received: 07/14/24 08:46

Lab Sample ID: 705-1754-11
Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	1.3		0.040	0.026	mg/L			07/14/24 11:30	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron, Dissolved	0.024	J	0.040	0.018	mg/L			07/14/24 12:39	1
Molybdenum, Dissolved	0.23		0.0050	0.00069	mg/L			07/14/24 12:39	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1754-1

Client Sample ID: HAM-PT-12-0713-UNF

Lab Sample ID: 705-1754-12

Date Collected: 07/13/24 18:00

Matrix: Water

Date Received: 07/14/24 08:46

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	1.2		0.040	0.026	mg/L		07/14/24 10:04	07/14/24 12:50	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron	0.22		0.040	0.018	mg/L		07/14/24 10:25	07/14/24 13:39	1
Molybdenum	0.23		0.0050	0.00069	mg/L		07/14/24 10:25	07/14/24 13:39	1

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1752-1

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-3323/1-A
Matrix: Water
Analysis Batch: 3347

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 3323

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aoron	MD		0.020	0.00N	m4/6		07/1g/N2 0L:5N	07/1g/N2 1g:10	1

Lab Sample ID: LCS 705-3323/2-A
Matrix: Water
Analysis Batch: 3347

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 3323

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Aoron	1.00	0.03		m4/6		L7	30 - 1N0

Lab Sample ID: 705-1720-A-5-C MS
Matrix: Water
Analysis Batch: 3347

Client Sample ID: Matrix Spike
Prep Type: Total/NA
Prep Batch: 3323

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Aoron	0.02		1.00	1.03		m4/6		LN	75 - 1N5

Lab Sample ID: 705-1720-A-5-D MSD
Matrix: Water
Analysis Batch: 3347

Client Sample ID: Matrix Spike Duplicate
Prep Type: Total/NA
Prep Batch: 3323

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	Limit
Aoron	0.02		1.00	1.03		m4/6		LN	75 - 1N5	0	N0

Lab Sample ID: MB 705-3325/1-A
Matrix: Water
Analysis Batch: 3331

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aoron9Dissolved	MD		0.020	0.00N	m4/6			07/1g/N2 11:1L	1

Lab Sample ID: LCS 705-3325/2-A
Matrix: Water
Analysis Batch: 3331

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Aoron9Dissolved	1.00	1.02		m4/6		102	30 - 1N0

Lab Sample ID: LCSD 705-3325/3-A
Matrix: Water
Analysis Batch: 3331

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	Limit
Aoron9Dissolved	1.00	1.02		m4/6		102	30 - 1N0	0	N0

, urovins Etanta

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1752-1

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-3357/1-A
Matrix: Water
Analysis Batch: 3374

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 3357

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron	MD		0.020	0.013	m4/6		07/12/2010:05	07/12/2010:05	1
Iron	MD		0.050	0.000 L	m4/6		07/12/2010:05	07/12/2010:05	1

Lab Sample ID: LCS 705-3357/2-A
Matrix: Water
Analysis Batch: 3374

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 3357

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Iron	1.00	1.00		m4/6		100	30 - 110
Iron	0.100	0.10g		m4/6		10g	30 - 110

Lab Sample ID: 705-1754-12 MS
Matrix: Water
Analysis Batch: 3374

Client Sample ID: v AM-PT-12-0713-UNF
Prep Type: Total Recoverable
Prep Batch: 3357

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Iron	0.000		1.00	1.00		m4/6		102	75 - 115
Iron	0.00g		0.100	0.000		m4/6		LL	75 - 115

Lab Sample ID: 705-1754-12 MSD
Matrix: Water
Analysis Batch: 3374

Client Sample ID: v AM-PT-12-0713-UNF
Prep Type: Total Recoverable
Prep Batch: 3357

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	Limit
Iron	0.000		1.00	1.00		m4/6		105	75 - 115	1	ND
Iron	0.00g		0.100	0.000		m4/6		102	75 - 115	N	ND

Lab Sample ID: MB 705-3324/1-A
Matrix: Water
Analysis Batch: 3350

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron9Dissolved	MD		0.020	0.013	m4/6			07/10/2010:20	1
Iron9Dissolved	MD		0.050	0.000 L	m4/6			07/10/2010:20	1

Lab Sample ID: LCS 705-3324/2-A
Matrix: Water
Analysis Batch: 3350

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Iron9Dissolved	1.00	0.000		m4/6		3g	30 - 110
Iron9Dissolved	0.100	0.000		m4/6		LN	30 - 110

Lab Sample ID: LCSD 705-3324/3-A
Matrix: Water
Analysis Batch: 3350

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	Limit
Iron9Dissolved	1.00	0.000		m4/6		30	30 - 110	2	ND
Iron9Dissolved	0.100	0.000		m4/6		3L	30 - 110	2	ND

, urovins Etanta

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1754-1

Client Sample ID: HAM-PT-09-0713-FIL-AM

Lab Sample ID: 705-1754-1

Date Collected: 07/13/24 08:50

Matrix: Water

Date Received: 07/14/24 08:46

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	3362	KB	EET ATL	07/14/24 11:10
Dissolved	Analysis	6020B		1	3373	TA	EET ATL	07/14/24 12:27

Client Sample ID: HAM-PT-09-0713-UNF-AM

Lab Sample ID: 705-1754-2

Date Collected: 07/13/24 08:50

Matrix: Water

Date Received: 07/14/24 08:46

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			3323	EF	EET ATL	07/14/24 10:04
Total/NA	Analysis	6010D		1	3370	KB	EET ATL	07/14/24 12:36
Total Recoverable	Prep	3005A			3357	EF	EET ATL	07/14/24 10:25
Total Recoverable	Analysis	6020B		1	3374	TA	EET ATL	07/14/24 14:02

Client Sample ID: HAM-PT-09-0713-FIL-PM

Lab Sample ID: 705-1754-3

Date Collected: 07/13/24 16:40

Matrix: Water

Date Received: 07/14/24 08:46

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	3362	KB	EET ATL	07/14/24 11:13
Dissolved	Analysis	6020B		1	3373	TA	EET ATL	07/14/24 12:29

Client Sample ID: HAM-PT-09-0713-UNF-PM

Lab Sample ID: 705-1754-4

Date Collected: 07/13/24 16:40

Matrix: Water

Date Received: 07/14/24 08:46

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			3323	EF	EET ATL	07/14/24 10:04
Total/NA	Analysis	6010D		1	3370	KB	EET ATL	07/14/24 12:39
Total Recoverable	Prep	3005A			3357	EF	EET ATL	07/14/24 10:25
Total Recoverable	Analysis	6020B		1	3374	TA	EET ATL	07/14/24 14:05

Client Sample ID: HAM-PT-10-0713-FIL-AM

Lab Sample ID: 705-1754-5

Date Collected: 07/13/24 08:50

Matrix: Water

Date Received: 07/14/24 08:46

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	3362	KB	EET ATL	07/14/24 11:22
Dissolved	Analysis	6020B		1	3373	TA	EET ATL	07/14/24 12:31

Client Sample ID: HAM-PT-10-0713-UNF-AM

Lab Sample ID: 705-1754-6

Date Collected: 07/13/24 08:50

Matrix: Water

Date Received: 07/14/24 08:46

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			3323	EF	EET ATL	07/14/24 10:04
Total/NA	Analysis	6010D		1	3370	KB	EET ATL	07/14/24 12:42

Eurofins Atlanta

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1754-1

Client Sample ID: HAM-PT-10-0713-UNF-AM

Lab Sample ID: 705-1754-6

Date Collected: 07/13/24 08:50

Matrix: Water

Date Received: 07/14/24 08:46

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total Recoverable	Prep	3005A			3357	EF	EET ATL	07/14/24 10:25
Total Recoverable	Analysis	6020B		1	3374	TA	EET ATL	07/14/24 14:07

Client Sample ID: HAM-PT-10-0713-FIL-PM

Lab Sample ID: 705-1754-7

Date Collected: 07/13/24 16:40

Matrix: Water

Date Received: 07/14/24 08:46

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	3362	KB	EET ATL	07/14/24 11:24
Dissolved	Analysis	6020B		1	3373	TA	EET ATL	07/14/24 12:34

Client Sample ID: HAM-PT-10-0713-UNF-PM

Lab Sample ID: 705-1754-8

Date Collected: 07/13/24 16:40

Matrix: Water

Date Received: 07/14/24 08:46

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			3323	EF	EET ATL	07/14/24 10:04
Total/NA	Analysis	6010D		1	3370	KB	EET ATL	07/14/24 12:44
Total Recoverable	Prep	3005A			3357	EF	EET ATL	07/14/24 10:25
Total Recoverable	Analysis	6020B		1	3374	TA	EET ATL	07/14/24 14:09

Client Sample ID: HAM-PT-11-0713-FIL

Lab Sample ID: 705-1754-9

Date Collected: 07/13/24 18:00

Matrix: Water

Date Received: 07/14/24 08:46

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	3362	KB	EET ATL	07/14/24 11:27
Dissolved	Analysis	6020B		1	3373	TA	EET ATL	07/14/24 12:36

Client Sample ID: HAM-PT-11-0713-UNF

Lab Sample ID: 705-1754-10

Date Collected: 07/13/24 18:00

Matrix: Water

Date Received: 07/14/24 08:46

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			3323	EF	EET ATL	07/14/24 10:04
Total/NA	Analysis	6010D		1	3370	KB	EET ATL	07/14/24 12:47
Total Recoverable	Prep	3005A			3357	EF	EET ATL	07/14/24 10:25
Total Recoverable	Analysis	6020B		1	3374	TA	EET ATL	07/14/24 14:12

Client Sample ID: HAM-PT-12-0713-FIL

Lab Sample ID: 705-1754-11

Date Collected: 07/13/24 18:00

Matrix: Water

Date Received: 07/14/24 08:46

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	3362	KB	EET ATL	07/14/24 11:30
Dissolved	Analysis	6020B		1	3373	TA	EET ATL	07/14/24 12:39

Eurofins Atlanta

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1754-1

Client Sample ID: HAM-PT-12-0713-UNF
Date Collected: 07/13/24 18:00
Date Received: 07/14/24 08:46

Lab Sample ID: 705-1754-12
Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			3323	EF	EET ATL	07/14/24 10:04
Total/NA	Analysis	6010D		1	3370	KB	EET ATL	07/14/24 12:50
Total Recoverable	Prep	3005A			3357	EF	EET ATL	07/14/24 10:25
Total Recoverable	Analysis	6020B		1	3374	TA	EET ATL	07/14/24 13:39

Laboratory References:
EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1754-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13

Method Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1752-1

Method	Method Description	Protocol	Laboratory
V010D	8 etals 4CP6	SA M2W	(() E) T
V0L0B	8 etals 4CP/8 S6	SA M2W	(() E) T
3005E	Preparation,)otal Recoverable or Dissolved 8 etals	SA M2W	(() E) T
3010E	Preparation,)otal 8 etals	SA M2W	(() E) T

Protocol References:
SA M2W= "est 8 ethods For (valuating Solid A aste, Physical/Chemical 8 ethods",) hird (dition, November 19MWEnd Its Updates.

Laboratory References:
(() E) T = (urofins Etlanta, 30M0 Presidential Dr, Etlanta, GE 30320,) (T 47706257-MI77

Sample Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1754-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-1754-1	HAM-PT-09-0713-FIL-AM	Water	07/13/24 08:50	07/14/24 08:46
705-1754-2	HAM-PT-09-0713-UNF-AM	Water	07/13/24 08:50	07/14/24 08:46
705-1754-3	HAM-PT-09-0713-FIL-PM	Water	07/13/24 16:40	07/14/24 08:46
705-1754-4	HAM-PT-09-0713-UNF-PM	Water	07/13/24 16:40	07/14/24 08:46
705-1754-5	HAM-PT-10-0713-FIL-AM	Water	07/13/24 08:50	07/14/24 08:46
705-1754-6	HAM-PT-10-0713-UNF-AM	Water	07/13/24 08:50	07/14/24 08:46
705-1754-7	HAM-PT-10-0713-FIL-PM	Water	07/13/24 16:40	07/14/24 08:46
705-1754-8	HAM-PT-10-0713-UNF-PM	Water	07/13/24 16:40	07/14/24 08:46
705-1754-9	HAM-PT-11-0713-FIL	Water	07/13/24 18:00	07/14/24 08:46
705-1754-10	HAM-PT-11-0713-UNF	Water	07/13/24 18:00	07/14/24 08:46
705-1754-11	HAM-PT-12-0713-FIL	Water	07/13/24 18:00	07/14/24 08:46
705-1754-12	HAM-PT-12-0713-UNF	Water	07/13/24 18:00	07/14/24 08:46

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-1754-1

Login Number: 1754

List Source: Eurofins Atlanta

List Number: 1

Creator: Bellinger, Arabia

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	N/A	
Sample custody seals, if present, are intact.	N/A	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	False	No time on COC for PT-12 UNF, logged in per container labell
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	N/A	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT



ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 7/15/2024 6:58:03 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-1758-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
7/15/2024 6:58:03 PM



Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	17
Lab Chronicle	19
Certification Summary	21
Method Summary	22
Sample Summary	23
Receipt Checklists	24
End Of Report	25

Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1758-1

Qualifiers

Metals

Qualifier	Qualifier Description
4	MS, MSD: The analyte present in the original sample is greater than 4 times the matrix spike concentration; therefore, control limits are not applicable.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Chain of Custody Record

Client Information		Sampler: Jamie Newsome		Lab PM: David Fuller / Phone 770-344-8986		Carrier Tracking No(s)		COC No:											
Client Contact: Kip Gray		Phone:		E-Mail: David.Fuller@et.eurofinsus.com		State of Origin: GA		Page 1 of 1											
Company: Geosyntec Consultants Inc				PWSID:		Analysis Requested													
Address: 1255 Roberts Blvd, NW Suite 200		Due Date Requested:		60100 - Total Boron 60208 - Total Arsenic and Iron 60208 - Total Iron and Molybdenum 60100 - Dissolved Boron - Field Filtered (FF) 60208 - Dissolved Arsenic and Iron (FF) 60208 - Dissolved Iron and Molybdenum (FF)		Preservation Codes: O - HNO3		Other:											
City: Kennesaw		TAT Requested (days): RUSH / 1 Day TAT																	
State, Zip: GA, 30144		Compliance Project: ☐ Yes ☐ No																	
Phone:		Lab Project #: 70500911 (DO NOT REMOVE)																	
Email: Kip.Gray@Geosyntec.com		PO #:																	
Project Name: Plant Hammond		Project #:																	
Task Code:		SSOW#:																	
Task Code#:																			
Sample Identification		Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=tissue, AA=air)														
HAM PT 13-0714-FIL AM		7/14/24	835	G	W	X													
HAM PT-13-0714 UNF-AM		7/14/24	835	G	W		X	X											
HAM-PT 13 0714-FIL PM		7/14/24	1700	G	W	X					X	X							
HAM PT-13 0714 UNF PM		7/14/24	1700	G	W		X	X											
HAM-PT 14-0714-FIL AM		7/14/24	815	G	W	X					X	X							
HAM PT 14-0714-UNF-AM		7/14/24	815	G	W		X	X											
HAM-PT-14-0714-FIL-PM		7/14/24	1715	G	W	X					X	X							
HAM-PT-14 0714-UNF-PM		7/14/24	1715	G	W		X	X											
HAM PT-15-0714-FIL-PM		7/14/24	1730	G	W	X					X	X							
HAM PT 15 0714-UNF PM		7/14/24	1730	G	W		X	X											
Possible Hazard Identification		☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☐ Unknown ☐ Radiological				Sample Disposal (A fee may be assessed if samples are retained longer than 1 month) ☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months													
Deliverable Requested I, II, III, IV, Other (specify)						Special Instructions/QC Requirements													
Empty Kit Relinquished by			Date		Time		Method of Shipment:												
Relinquished by: <i>[Signature]</i>			Date/Time: <i>7/15/24 7:00</i>		Company:		Received by: <i>[Signature]</i>		Date/Time: <i>7/15/24 7:00</i>		Company:								
Relinquished by: <i>[Signature]</i>			Date/Time: <i>7-15-24 9:08</i>		Company:		Received by: <i>[Signature]</i>		Date/Time: <i>07-15-24 9:08</i>		Company: <i>Eurofins</i>								
Relinquished by:			Date/Time:		Company:		Received by:		Date/Time:		Company:								
Custody Seals Intact: ☐ Yes ☐ No		Custody Seal No.				Cooler Temperature(s) °C and Other Remarks: <i>#2625 35°C</i>													

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-1758-1

Job ID: 705-1758-1

Eurofins Atlanta

Job Narrative 705-1758-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers are applied to indicate exceptions. Noncompliant quality control (QC) is further explained in narrative comments.

- Matrix QC may not be reported if insufficient sample or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 7/15/2024 9:08 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was .5°C.

Metals

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client Sample ID: HAM-PT-13-0714-FIL-AM
Date Collected: 07/14/24 08:35
Date Received: 07/15/24 09:08

Job ID: 705-1753-1

Lab Sample ID: 705-1758-1

Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.57		0.000	0.004	mg/L			07/15/24 11:13	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.29		0.0050	0.0010	mg/L			07/15/24 15:00	1
Iron, Dissolved	15		0.000	0.013	mg/L			07/15/24 15:00	1

8/15/2024

Client Sample Results

Client Sample ID: HAM-PT-13-0714-UNF-AM
Date Collected: 07/14/24 08:35
Date Received: 07/15/24 09:08

Job ID: 705-1753-1

Lab Sample ID: 705-1758-2

Matrix: Water

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.61		0.000	0.004	mg/L		07/15/24 11:00	07/15/24 15:17	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.30		0.005	0.001	mg/L		07/15/24 11:00	07/15/24 17:03	1
Iron	27		0.000	0.013	mg/L		07/15/24 11:00	07/15/24 17:03	1

8/15/2024

Client Sample Results

Client Name: Gessio, David
Project: Uzi / cSSoi H

Job ID: 705-1753-1

Client Sample ID: HAM-PT-13-0714-FIL-PM

Lab Sample ID: 705-1758-3

Date Collected: 07/14/24 17:00

Matrix: Water

Date Received: 07/15/24 09:08

Method: SW846 6010D - Metals (ICP) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.43		0.00	0.04	mg/L			07/15/24 15:00	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.23		0.05	0.01	mg/L			07/15/24 15:00	1
Iron, Dissolved	20		0.00	0.13	mg/L			07/15/24 15:00	1

8/15/24 15:00

Client Sample Results

Client Name: **Geoscientific**
Project: **US Soil**

Job ID: 705-1753-1

Client Sample ID: **HAM-PT-13-0714-UNF-PM**

Lab Sample ID: **705-1758-4**

Date Collected: **07/14/24 17:00**

Matrix: **Water**

Date Received: **07/15/24 09:08**

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.45		0.000	0.004	mg		07/15/24 11:00	07/15/24 15:05	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.27		0.0050	0.0010	mg		07/15/24 11:00	07/15/24 14:54	1
Iron	28		0.000	0.013	mg		07/15/24 11:00	07/15/24 14:54	1

8/15/24

Client Sample Results

Client Name: **Geoscientific**
Project: **U.S. Soil**

Job ID: 705-1753-1

Client Sample ID: **HAM-PT-14-0714-FIL-AM**

Lab Sample ID: **705-1758-5**

Date Collected: **07/14/24 08:15**

Matrix: **Water**

Date Received: **07/15/24 09:08**

Method: SW846 6010D - Metals (ICP) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.66		0.00	0.04	mg			0.15r. d 1L.: d	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.18		0.050	0.01L	mg			0.15r. d 15.: 5	1
Iron, Dissolved	14		0.00	0.013	mg			0.15r. d 15.: 5	1

8/15/24

Client Sample Results

Client Name: **Geoscientific**
Project: **US Soil**

Job ID: 705-1753-1

Client Sample ID: **HAM-PT-14-0714-UNF-AM**

Lab Sample ID: **705-1758-6**

Date Collected: **07/14/24 08:15**

Matrix: **Water**

Date Received: **07/15/24 09:08**

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.68		0.00	0.04	mg		07/15/24 11:00	07/15/24 15:55	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.20		0.05	0.01	mg		07/15/24 11:00	07/15/24 17:10	1
Iron	48		0.00	0.13	mg		07/15/24 11:00	07/15/24 17:10	1

Page 12 of 25

Client Sample Results

Client Name: **Geoscientific**
Project: **U.S. Soil**

Job ID: 705-1753-1

Client Sample ID: **HAM-PT-14-0714-FIL-PM**

Lab Sample ID: **705-1758-7**

Date Collected: **07/14/24 17:15**

Matrix: **Water**

Date Received: **07/15/24 09:08**

Method: SW846 6010D - Metals (ICP) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.28		0.00	0.04	mg			07/15/24 15:30	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.035		0.050	0.010	mg			07/15/24 15:07	1
Iron, Dissolved	19		0.00	0.013	mg			07/15/24 15:07	1

8/15/24

Client Sample Results

Client Name: **Geoscientific**
Project: **US Soil**

Job ID: 705-1753-1

Client Sample ID: **HAM-PT-14-0714-UNF-PM**

Lab Sample ID: **705-1758-8**

Date Collected: **07/14/24 17:15**

Matrix: **Water**

Date Received: **07/15/24 09:08**

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.32		0.00	0.04	mg		07/15/24 11:00	07/15/24 15:53	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.14		0.0050	0.001L	mg		07/15/24 11:00	07/15/24 17:11L	1
Iron	73		0.00	0.03	mg		07/15/24 11:00	07/15/24 17:00 A	10

8/15/24

Client Sample Results

Client Name: **Geoscientific**
Project: **U.S. Soil**

Job ID: 705-1753-1

Client Sample ID: **HAM-PT-15-0714-FIL-PM**

Lab Sample ID: **705-1758-9**

Date Collected: **07/14/24 17:30**

Matrix: **Water**

Date Received: **07/15/24 09:08**

Method: SW846 6010D - Metals (ICP) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.69		0.00	0.04	mg			07/15/24 15:11	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.38		0.05	0.01	mg			07/15/24 15:10	1
Iron, Dissolved	8.2		0.00	0.13	mg			07/15/24 15:10	1

8/15/24 15:11

Client Sample Results

Client Sample ID: HAM-PT-15-0714-UNF-PM
Date Collected: 07/14/24 17:30
Date Received: 07/15/24 09:08

Job ID: 705-1753-1

Lab Sample ID: 705-1758-10

Matrix: Water

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.69		0.000	0.004	mg/L		07/15/24 11:00	07/15/24 14:01	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.42		0.005	0.001	mg/L		07/15/24 11:00	07/15/24 17:00	1
Iron	14		0.000	0.013	mg/L		07/15/24 11:00	07/15/24 17:00	1

8/15/2024

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1758-1

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-3429/1-A

Matrix: Water

Analysis Batch: 3496

Client Sample ID: Method Blank

Prep Type: Total/NA

Prep Batch: 3429

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	ND		0.040	0.026	mg/L		07/15/24 12:02	07/15/24 15:11	1

Lab Sample ID: LCS 705-3429/2-A

Matrix: Water

Analysis Batch: 3496

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Prep Batch: 3429

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	1.00	1.04		mg/L		104	80 - 120

Lab Sample ID: 705-1758-2 MS

Matrix: Water

Analysis Batch: 3496

Client Sample ID: HAM-PT-13-0714-UNF-AM

Prep Type: Total/NA

Prep Batch: 3429

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	0.61		1.00	1.66		mg/L		105	75 - 125

Lab Sample ID: 705-1758-2 MSD

Matrix: Water

Analysis Batch: 3496

Client Sample ID: HAM-PT-13-0714-UNF-AM

Prep Type: Total/NA

Prep Batch: 3429

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron	0.61		1.00	1.66		mg/L		105	75 - 125	0	20

Lab Sample ID: MB 705-3434/1-A

Matrix: Water

Analysis Batch: 3463

Client Sample ID: Method Blank

Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	ND		0.040	0.026	mg/L			07/15/24 13:03	1

Lab Sample ID: LCS 705-3434/2-A

Matrix: Water

Analysis Batch: 3463

Client Sample ID: Lab Control Sample

Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron, Dissolved	1.00	1.04		mg/L		104	80 - 120

Lab Sample ID: LCSD 705-3434/3-A

Matrix: Water

Analysis Batch: 3463

Client Sample ID: Lab Control Sample Dup

Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron, Dissolved	1.00	0.973		mg/L		97	80 - 120	7	20

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1758-1

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-3424/1-A

Matrix: Water

Analysis Batch: 3516

Client Sample ID: Method Blank

Prep Type: Total Recoverable

Prep Batch: 3424

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	ND		0.0050	0.0013	mg/L		07/15/24 11:20	07/15/24 16:51	1
Iron	ND		0.040	0.018	mg/L		07/15/24 11:20	07/15/24 16:51	1

Lab Sample ID: LCS 705-3424/2-A

Matrix: Water

Analysis Batch: 3516

Client Sample ID: Lab Control Sample

Prep Type: Total Recoverable

Prep Batch: 3424

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.100	0.0898		mg/L		90	80 - 120
Iron	1.00	0.905		mg/L		91	80 - 120

Lab Sample ID: 705-1758-4 MS

Matrix: Water

Analysis Batch: 3516

Client Sample ID: HAM-PT-13-0714-UNF-PM

Prep Type: Total Recoverable

Prep Batch: 3424

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.27		0.100	0.355		mg/L		86	75 - 125
Iron	28		1.00	27.0	4	mg/L		-95	75 - 125

Lab Sample ID: 705-1758-4 MSD

Matrix: Water

Analysis Batch: 3516

Client Sample ID: HAM-PT-13-0714-UNF-PM

Prep Type: Total Recoverable

Prep Batch: 3424

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic	0.27		0.100	0.368		mg/L		99	75 - 125	4	20
Iron	28		1.00	27.8	4	mg/L		-16	75 - 125	3	20

Lab Sample ID: MB 705-3432/1-A

Matrix: Water

Analysis Batch: 3500

Client Sample ID: Method Blank

Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	ND		0.0050	0.0013	mg/L			07/15/24 15:13	1
Iron, Dissolved	ND		0.040	0.018	mg/L			07/15/24 15:13	1

Lab Sample ID: LCS 705-3432/2-A

Matrix: Water

Analysis Batch: 3500

Client Sample ID: Lab Control Sample

Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic, Dissolved	0.100	0.0978		mg/L		98	80 - 120
Iron, Dissolved	1.00	0.924		mg/L		92	80 - 120

Lab Sample ID: LCSD 705-3432/3-A

Matrix: Water

Analysis Batch: 3500

Client Sample ID: Lab Control Sample Dup

Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic, Dissolved	0.100	0.0956		mg/L		96	80 - 120	2	20
Iron, Dissolved	1.00	0.893		mg/L		89	80 - 120	3	20

Eurofins Atlanta

Lab Chronicle

Client: Geosyntec Consultants Inc
920 Rectrj ite: 91ant / aS S onH

Job ID: 705-1753-1

Client Sample ID: HAM-PT-13-0714-FIL-AM

Lab Sample ID: 705-1758-1

Date Collected: 07/14/24 08:35

Matrix: Water

Date Received: 07/15/24 09:08

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
DissolLeH	rmalysis	d010D		1	A6dA	Dj	BBE nET	07r15rv6 1A:13
DissolLeH	rmalysis	d0v04		1	A500	mD	BBE nET	07r15rv6 15:v0

Client Sample ID: HAM-PT-13-0714-UNF-AM

Lab Sample ID: 705-1758-2

Date Collected: 07/14/24 08:35

Matrix: Water

Date Received: 07/15/24 09:08

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
EotalrRm	92ep	A010m			A6vN	j m	BBE nET	07r15rv6 1v:0v
EotalrRm	rmalysis	d010D		1	A6Nd	Dj	BBE nET	07r15rv6 15:17
Eotal FecoLe2able	92ep	A005m			A6v6	4T	BBE nET	07r15rv6 11:v0
Eotal FecoLe2able	rmalysis	d0v04		1	A51d	If	BBE nET	07r15rv6 17:03

Client Sample ID: HAM-PT-13-0714-FIL-PM

Lab Sample ID: 705-1758-3

Date Collected: 07/14/24 17:00

Matrix: Water

Date Received: 07/15/24 09:08

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
DissolLeH	rmalysis	d010D		1	A6dA	Dj	BBE nET	07r15rv6 1A:v1
DissolLeH	rmalysis	d0v04		1	A500	mD	BBE nET	07r15rv6 15:vv

Client Sample ID: HAM-PT-13-0714-UNF-PM

Lab Sample ID: 705-1758-4

Date Collected: 07/14/24 17:00

Matrix: Water

Date Received: 07/15/24 09:08

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
EotalrRm	92ep	A010m			A6vN	j m	BBE nET	07r15rv6 1v:0v
EotalrRm	rmalysis	d010D		1	A6Nd	Dj	BBE nET	07r15rv6 15:5v
Eotal FecoLe2able	92ep	A005m			A6v6	4T	BBE nET	07r15rv6 11:v0
Eotal FecoLe2able	rmalysis	d0v04		1	A51d	If	BBE nET	07r15rv6 1d:5d

Client Sample ID: HAM-PT-14-0714-FIL-AM

Lab Sample ID: 705-1758-5

Date Collected: 07/14/24 08:15

Matrix: Water

Date Received: 07/15/24 09:08

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
DissolLeH	rmalysis	d010D		1	A6dA	Dj	BBE nET	07r15rv6 1A:v6
DissolLeH	rmalysis	d0v04		1	A500	mD	BBE nET	07r15rv6 15:v5

Client Sample ID: HAM-PT-14-0714-UNF-AM

Lab Sample ID: 705-1758-6

Date Collected: 07/14/24 08:15

Matrix: Water

Date Received: 07/15/24 09:08

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
EotalrRm	92ep	A010m			A6vN	j m	BBE nET	07r15rv6 1v:0v
EotalrRm	rmalysis	d010D		1	A6Nd	Dj	BBE nET	07r15rv6 15:55

Bu28ns mtlanta

Lab Chronicle

Client: Geosyntec Consultants Inc
920 Rectrj ite: 9 lant / aS S onH

Job ID: 705-1753-1

Client Sample ID: HAM-PT-14-0714-UNF-AM

Lab Sample ID: 705-1758-6

Date Collected: 07/14/24 08:15

Matrix: Water

Date Received: 07/15/24 09:08

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Eotal FecoLe2able	92ep	A005m			A6v6	4T	BBE nET	07r15rv6 11:v0
Eotal FecoLe2able	rmalysis	d0v04		1	A51d	If	BBE nET	07r15rv6 17:10

Client Sample ID: HAM-PT-14-0714-FIL-PM

Lab Sample ID: 705-1758-7

Date Collected: 07/14/24 17:15

Matrix: Water

Date Received: 07/15/24 09:08

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
DissolLeH	rmalysis	d010D		1	A6dA	Dj	BBE nET	07r15rv6 1A:v3
DissolLeH	rmalysis	d0v04		1	A500	mD	BBE nET	07r15rv6 15:v7

Client Sample ID: HAM-PT-14-0714-UNF-PM

Lab Sample ID: 705-1758-8

Date Collected: 07/14/24 17:15

Matrix: Water

Date Received: 07/15/24 09:08

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
EotalrRm	92ep	A010m			A6vN	j m	BBE nET	07r15rv6 1v:0v
EotalrRm	rmalysis	d010D		1	A6Nd	Dj	BBE nET	07r15rv6 15:53
Eotal FecoLe2able	92ep	A005m			A6v6	4T	BBE nET	07r15rv6 11:v0
Eotal FecoLe2able	rmalysis	d0v04		1	A51d	If	BBE nET	07r15rv6 17:1A
Eotal FecoLe2able	92ep	A005m			A6v6	4T	BBE nET	07r15rv6 11:v0
Eotal FecoLe2able	rmalysis	d0v04		10	A51d	If	BBE nET	07r15rv6 17:vN

Client Sample ID: HAM-PT-15-0714-FIL-PM

Lab Sample ID: 705-1758-9

Date Collected: 07/14/24 17:30

Matrix: Water

Date Received: 07/15/24 09:08

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
DissolLeH	rmalysis	d010D		1	A6dA	Dj	BBE nET	07r15rv6 1A:A1
DissolLeH	rmalysis	d0v04		1	A500	mD	BBE nET	07r15rv6 15:A0

Client Sample ID: HAM-PT-15-0714-UNF-PM

Lab Sample ID: 705-1758-10

Date Collected: 07/14/24 17:30

Matrix: Water

Date Received: 07/15/24 09:08

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
EotalrRm	92ep	A010m			A6vN	j m	BBE nET	07r15rv6 1v:0v
EotalrRm	rmalysis	d010D		1	A6Nd	Dj	BBE nET	07r15rv6 1d:01
Eotal FecoLe2able	92ep	A005m			A6v6	4T	BBE nET	07r15rv6 11:v0
Eotal FecoLe2able	rmalysis	d0v04		1	A51d	If	BBE nET	07r15rv6 17:v0

Laboratory References:

BBE nET = Bu2b8ns mtanta, A030 92esilHential D2 mtanta, GmA0A60, EBT (770)657-3177

Bu2b8ns mtanta

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1758-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13

Method Summary

92
Di en l ot G e s 9 oi ty 2 ci e li s
u a p s e j G : u 2 i e / c S S oi H

Job ID: 705-1753-1

Method	Method Description	Protocol	Laboratory
V010D	8 l e 2 49 u 6	j m 3 d W	M M () (E
V0T0A	8 l e 2 49 u r 8 j 6	j m 3 d W	M M () (E
L005)	u a B c a e o i p (o e 2 , l s o R a b 2 o a D C t o 2 R H 8 l e 2	j m 3 d W	M M () (E
L010)	u a B c a e o i p (o e 2 8 l e 2	j m 3 d W	M M () (E

Protocol References:

j m 3 d W v r (l t e 8 l e o H t h o a M R c y c e F j o 2 H m c t e p u " G G c 2 9 " l S G c 2 8 l e o H t p (" G H M H 3 3 i p g o R S b l a 1 N 3 W) i H l e U B H t e t .

Laboratory References:

M M () (E v M y a f C t) e i e p L 0 3 0 u a t t e l i e 2 D a p) e i e p n) L 0 L d 0 p (M E 4 7 7 0 d 5 7 - 3 1 7 7

Sample Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1758-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-1758-1	HAM-PT-13-0714-FIL-AM	Water	07/14/24 08:35	07/15/24 09:08
705-1758-2	HAM-PT-13-0714-UNF-AM	Water	07/14/24 08:35	07/15/24 09:08
705-1758-3	HAM-PT-13-0714-FIL-PM	Water	07/14/24 17:00	07/15/24 09:08
705-1758-4	HAM-PT-13-0714-UNF-PM	Water	07/14/24 17:00	07/15/24 09:08
705-1758-5	HAM-PT-14-0714-FIL-AM	Water	07/14/24 08:15	07/15/24 09:08
705-1758-6	HAM-PT-14-0714-UNF-AM	Water	07/14/24 08:15	07/15/24 09:08
705-1758-7	HAM-PT-14-0714-FIL-PM	Water	07/14/24 17:15	07/15/24 09:08
705-1758-8	HAM-PT-14-0714-UNF-PM	Water	07/14/24 17:15	07/15/24 09:08
705-1758-9	HAM-PT-15-0714-FIL-PM	Water	07/14/24 17:30	07/15/24 09:08
705-1758-10	HAM-PT-15-0714-UNF-PM	Water	07/14/24 17:30	07/15/24 09:08

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-1758-1

Login Number: 1758

List Source: Eurofins Atlanta

List Number: 1

Creator: Pomuti, Carmen

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	N/A	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	False	Limited volume received.
Sample Preservation Verified.	True	Preservation labels on samples match COC
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	N/A	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT



ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 7/16/2024 7:07:45 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-1800-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
7/16/2024 7:07:45 PM

Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	17
Lab Chronicle	19
Certification Summary	21
Method Summary	22
Sample Summary	23
Receipt Checklists	24
End Of Report	25



Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1800-1

Qualifiers

Metals

Qualifier	Qualifier Description
4	MS, MSD: The analyte present in the original sample is greater than 4 times the matrix spike concentration; therefore, control limits are not applicable.
J	Result is less than the μ L but greater than or equal to the MDL and the concentration is an approximate value.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
%	Listed under the μ R column to designate that the result is reported on a dry weight basis
F μ	Percent μ recovery
CqL	Contains μ ree Li ⁺ uid
CqU	Colony forming Unit
CNq	Contains No μ ree Li ⁺ uid
DE μ	Duplicate Error μ atio (normalized absolute difference)
Dil μ ac	Dilution μ actor
DL	Detection Limit (DoD/DOE)
DL, μ A, μ E, IN	Indicates a Dilution, μ e-analysis, μ e-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (μ adiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended Maximum Contaminant Level
MDA	Minimum Detectable Activity (μ adiochemistry)
MDC	Minimum Detectable Concentration (μ adiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
P μ ES	Presumptive
QC	Quality Control
μ E μ	μ relative Error μ atio (μ adiochemistry)
μ L	Reporting Limit or μ e ⁺ uested Limit (μ adiochemistry)
μ PD	μ relative Percent Difference, a measure of the relative difference between two points
TEq	Toxicity Equivalent μ actor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Eurofins Atlanta

3080 Presidential Dr
Atlanta, GA 30340
Phone (770) 457-8177

Chain of Custody Record



Environment Testing

Client Information		Sampler <i>Jamie Newsome</i>		Lab PM David Fuller / Phone 770-344-8986		Carrier Tracking No(s):		COC No:					
Client Contact: Kip Gray		Phone:		E-Mail: David.Fuller@et.eurofinsus.com		State of Origin: GA		Page: Page 1 of 1					
Company: Geosyntec Consultants Inc				PWSID:		Analysis Requested							
Address: 1255 Roberts Blvd, NW Suite 200		Due Date Requested:						Preservation Codes: D - HNO3					
City: Kennesaw		TAT Requested (days) <i>Same day RUSH 1 Day TAT TAT</i>											
State, Zip: GA, 30144		Compliance Project. ☐ Yes ☐ No											
Phone:		Lab Project #: 70500911 (DO NOT REMOVE)											
Email: Kip.Gray@Geosyntec.com		PO #:											
Project Name: Plant Hammond		Project #:											
Task Code:		SSOW#:											
Task Code#:													
Sample Identification		Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=bioreactor, A=air)	6010D - Total Boron	6020B - Total Arsenic and Iron	6020B - Total Iron and Molybdenum	6010D - Dissolved Boron - Field Filtered (FF)	6020B - Dissolved Arsenic and Iron (FF)	6020B - Dissolved Iron and Molybdenum (FF)	Other	Special Instructions/Note:
HAM-PT-09-0715-FIL-AM	7/15/24	822	G	W	X				X	X			
HAM-PT-09-0715-FIL-PM	7/15/24	1615	G	W	X				X	X			
HAM-PT-09-0715-UNF-AM	7/15/24	822	G	W		X	X						
HAM-PT-09-0715-UNF-PM	7/15/24	1615	G	W		X	X						
HAM-PT-10-0715-UNF	7/15/24	1720	G	W		X	X						
HAM-PT-11-0715-FIL-AM	7/15/24	846	G	W	X				X	X			
HAM-PT-11-0715-FIL-PM	7/15/24	1615	G	W	X				X	X			
HAM-PT-11-0715-UNF-AM	7/15/24	846	G	W		X	X						
HAM-PT-11-0715-UNF-PM	7/15/24	1615	G	W		X	X						
HAM-PT-12-0715-UNF	7/15/24	1720	G	W		X	X						
Possible Hazard Identification					Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)								
☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☐ Unknown ☐ Radiological					☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months								
Deliverable Requested I, II, III, IV, Other (specify)					Special Instructions/QC Requirements								
Empty Kit Relinquished by		Date		Time		Method of Shipment:							
Relinquished by: <i>Jamie Newsome</i>		Date/Time: 7/16/24 700		Company:		Received by: <i>[Signature]</i>		Date/Time: 7-16-24 7:00		Company:			
Relinquished by: <i>[Signature]</i>		Date/Time: 7/16/24 914		Company:		Received by: <i>[Signature]</i>		Date/Time: 07/16/24 0914		Company: Eurofins			
Relinquished by:		Date/Time:		Company:		Received by:		Date/Time:		Company:			
Custody Seals Intact: ☐ Yes ☐ No		Custody Seal No		Cooler Temperature(s) °C and Other Remarks: #2665 49°C									

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-1800-1

Job ID: 705-1800-1

Eurofins Atlanta

Job Narrative 705-1800-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers are applied to indicate exceptions. Noncompliant quality control (QC) is further explained in narrative comments.

- Matrix QC may not be reported if insufficient sample or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Regulated compliance samples (e.g. SDWA, NPDES) must comply with the associated agency requirements/permits.

Receipt

The samples were received on 7/16/2024 9:14 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 4.9°C.

Metals

Method 6010D - Dissolved: Insufficient sample volume was available to perform a matrix spike/matrix spike duplicate/sample duplicate (MS/MSD/DUP) associated with preparation batch 705-3582 and analytical batch 705-3647.

Method 6020B - Dissolved: Insufficient sample volume was available to perform a matrix spike/matrix spike duplicate (MS/MSD) associated with analytical batch 705-3681.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

92
Client Name: Gessio, David
uap
Pseq
G : u
2i e/
cSSoi H

Job ID: 705-1300-1

Client Sample ID: HAM-PT-09-0715-FIL-AM
Date Collected: 07/15/24 08:22
Date Received: 07/16/24 09:14

Lab Sample ID: 705-1800-1
Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	1.3		0.0d0	0.0. 4	S 6rg			07r14r. d 1L:11	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron, Dissolved	0.031	J	0.0d0	0.0r13	S 6rg			07r14r. d 15:05	1
Molybdenum, Dissolved	0.27		0.0050	0.00048	S 6rg			07r14r. d 15:05	1

Client Sample Results

92
Client Name: Gessio, David
uap
Project: u2ie/ cSSoi H

Job ID: 705-1300-1

Client Sample ID: HAM-PT-09-0715-FIL-PM
Date Collected: 07/15/24 16:15
Date Received: 07/16/24 09:14

Lab Sample ID: 705-1800-2
Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	1.0		0.000	0.004	mg/L			07/14/24 15:07	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron, Dissolved	3.8		0.000	0.013	mg/L			07/14/24 15:07	1
Molybdenum, Dissolved	0.12		0.0050	0.00048	mg/L			07/14/24 15:07	1

Client Sample Results

Client Sample ID: HAM-PT-09-0715-UNF-AM
Date Collected: 07/15/24 08:22
Date Received: 07/16/24 09:14

Job ID: 705-1300-1

Lab Sample ID: 705-1800-3

Matrix: Water

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	1.2		0.000	0.004	mg		07/14/24 10:00	07/14/24 10:00	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron	0.38		0.000	0.001	mg		07/14/24 10:05	07/14/24 10:08	1
Molybdenum	0.30		0.005	0.0004	mg		07/14/24 10:05	07/14/24 10:08	1

Client Sample Results

Client Sample ID: HAM-PT-09-0715-UNF-PM
Date Collected: 07/15/24 16:15
Date Received: 07/16/24 09:14

Job ID: 705-1300-1

Lab Sample ID: 705-1800-4

Matrix: Water

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	1.0		0.000	0.004	mg		07/14/24 10:00L	07/14/24 15:17	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Molybdenum	0.13		0.0050	0.00048	mg		07/14/24 10:15L	07/14/24 15:53	1
Iron	6.3		0.000	0.013	mg		07/14/24 10:15L	07/14/24 15:53	1

Client Sample Results

92
Client Name: **Geoscientific**
Project: **U.S. Soil**

Job ID: 705-1300-1

Client Sample ID: **HAM-PT-10-0715-UNF**
Date Collected: **07/15/24 17:20**
Date Received: **07/16/24 09:14**

Lab Sample ID: **705-1800-5**
Matrix: **Water**

Method: SW846 6010D - Metals (ICP)										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Boron	1.7		0.000	0.004	mg		07/14/24 10:00L	07/14/24 14:05	1	

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Molybdenum	0.16		0.0050	0.00048	mg		07/14/24 10:05L	07/14/24 14:11	1	
Iron	0.14		0.000	0.0013	mg		07/14/24 10:05L	07/14/24 14:11	1	

Client Sample Results

Client Sample ID: HAM-PT-11-0715-FIL-AM
Date Collected: 07/15/24 08:46
Date Received: 07/16/24 09:14

Job ID: 705-1300-1

Lab Sample ID: 705-1800-6

Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.87		0.000	0.004	mg/L			07/14/24 15:08	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron, Dissolved	1.6		0.000	0.0013	mg/L			07/14/24 15:08	1
Molybdenum, Dissolved	0.040		0.0050	0.00048	mg/L			07/14/24 15:08	1

Client Sample Results

Client Sample ID: HAM-PT-11-0715-FIL-PM
Date Collected: 07/15/24 16:15
Date Received: 07/16/24 09:14

Job ID: 705-1300-1

Lab Sample ID: 705-1800-7

Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.51		0.0000	0.0004	mg/L			07/14/24 15:14	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron, Dissolved	37		0.0000	0.0013	mg/L			07/14/24 15:14	1
Molybdenum, Dissolved	0.0069		0.00050	0.00048	mg/L			07/14/24 15:14	1

Client Sample Results

92
Client Name: **Geoscientific**
Project: **U.S. Soil**

Job ID: 705-1300-1

Client Sample ID: **HAM-PT-11-0715-UNF-AM**
Date Collected: **07/15/24 08:46**
Date Received: **07/16/24 09:14**

Lab Sample ID: **705-1800-8**
Matrix: **Water**

Method: SW846 6010D - Metals (ICP)										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Boron	0.85		0.000	0.004	mg		07/14/24 10:00L	07/14/24 14:03	1	

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Molybdenum	0.043		0.0050	0.00048	mg		07/14/24 10:15L	07/14/24 14:07	1	
Iron	2.4		0.000	0.013	mg		07/14/24 10:15L	07/14/24 14:07	1	

Client Sample Results

92
Client Name: **Geoscientific**
Project: **U.S. Soil**

Job ID: 705-1300-1

Client Sample ID: **HAM-PT-11-0715-UNF-PM**
Date Collected: **07/15/24 16:15**
Date Received: **07/16/24 09:14**

Lab Sample ID: **705-1800-9**
Matrix: **Water**

Method: SW846 6010D - Metals (ICP)										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Boron	0.49		0.00	0.04	mg		07/14/24 10:00L	07/14/24 14:00L	1	

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Molybdenum	0.0086		0.0050	0.00048	mg		07/14/24 10:00L	07/14/24 14:00L	1	
Iron	44		0.00	0.013	mg		07/14/24 10:00L	07/14/24 14:00L	1	

Client Sample Results

Client Sample ID: HAM-PT-12-0715-UNF
Date Collected: 07/15/24 17:20
Date Received: 07/16/24 09:14

Job ID: 705-1300-1

Lab Sample ID: 705-1800-10

Matrix: Water

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	1.2		0.000	0.0004	mg		07/14/24 10:00L	07/14/24 14:00L	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Molybdenum	0.14		0.0005	0.000048	mg		07/14/24 10:00L	07/14/24 14:00L	1
Iron	0.49		0.000	0.00013	mg		07/14/24 10:00L	07/14/24 14:00L	1

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1800-1

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-3576/1-A
Matrix: Water
Analysis Batch: 3668

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 3576

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	ND		0.040	0.026	mg/L		07/16/24 10:03	07/16/24 13:56	1

Lab Sample ID: LCS 705-3576/2-A
Matrix: Water
Analysis Batch: 3668

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 3576

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	1.00	1.02		mg/L		102	80 - 120

Lab Sample ID: 705-1800-3 MS
Matrix: Water
Analysis Batch: 3668

Client Sample ID: HAM-PT-09-0715-UNF-AM
Prep Type: Total/NA
Prep Batch: 3576

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	1.2		1.00	2.26		mg/L		101	75 - 125

Lab Sample ID: 705-1800-3 MSD
Matrix: Water
Analysis Batch: 3668

Client Sample ID: HAM-PT-09-0715-UNF-AM
Prep Type: Total/NA
Prep Batch: 3576

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron	1.2		1.00	2.29		mg/L		105	75 - 125	2	20

Lab Sample ID: MB 705-3582/1-A
Matrix: Water
Analysis Batch: 3647

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	ND		0.040	0.026	mg/L			07/16/24 12:55	1

Lab Sample ID: LCSD 705-3582/3-A
Matrix: Water
Analysis Batch: 3647

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron, Dissolved	1.00	1.01		mg/L		101	80 - 120	1	20

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-3577/1-A
Matrix: Water
Analysis Batch: 3701

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 3577

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron	ND		0.040	0.018	mg/L		07/16/24 10:35	07/16/24 15:53	1
Molybdenum	ND		0.0050	0.00069	mg/L		07/16/24 10:35	07/16/24 15:53	1

Eurofins Atlanta

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1800-1

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: LCS 705-3577/2-A

Matrix: Water

Analysis Batch: 3701

Client Sample ID: Lab Control Sample

Prep Type: Total Recoverable

Prep Batch: 3577

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Iron	1.00	0.955		mg/L		95	80 - 120
Molybdenum	0.100	0.0936		mg/L		94	80 - 120

Lab Sample ID: 705-1800-4 MS

Matrix: Water

Analysis Batch: 3701

Client Sample ID: HAM-PT-09-0715-UNF-PM

Prep Type: Total Recoverable

Prep Batch: 3577

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Iron	6.3		1.00	7.00	4	mg/L		70	75 - 125
Molybdenum	0.13		0.100	0.225		mg/L		95	75 - 125

Lab Sample ID: 705-1800-4 MSD

Matrix: Water

Analysis Batch: 3701

Client Sample ID: HAM-PT-09-0715-UNF-PM

Prep Type: Total Recoverable

Prep Batch: 3577

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Iron	6.3		1.00	7.34	4	mg/L		105	75 - 125	5	20
Molybdenum	0.13		0.100	0.234		mg/L		104	75 - 125	4	20

Lab Sample ID: MB 705-3581/1-A

Matrix: Water

Analysis Batch: 3681

Client Sample ID: Method Blank

Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron, Dissolved	ND		0.040	0.018	mg/L			07/16/24 14:58	1
Molybdenum, Dissolved	ND		0.0050	0.00069	mg/L			07/16/24 14:58	1

Lab Sample ID: LCS 705-3581/2-A

Matrix: Water

Analysis Batch: 3681

Client Sample ID: Lab Control Sample

Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Iron, Dissolved	1.00	0.920		mg/L		92	80 - 120
Molybdenum, Dissolved	0.100	0.0923		mg/L		92	80 - 120

Lab Sample ID: LCSD 705-3581/3-A

Matrix: Water

Analysis Batch: 3681

Client Sample ID: Lab Control Sample Dup

Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Iron, Dissolved	1.00	0.877		mg/L		88	80 - 120	5	20
Molybdenum, Dissolved	0.100	0.0897		mg/L		90	80 - 120	3	20

Lab Chronicle

Client: Geosyntec Consultants Inc
6 Rectj/ ite: 6 lant SaH Honm

Job ID: 705-1200-1

Client Sample ID: HAM-PT-13-1074-FIL-AM
Date CollecteW 10d4d 2 15:/ /
Date ReceiveW 10d9d 2 13:72

Lab Sample ID: 014-7511-7
Matri8: x ater

Prep Type	Batch Type	Batch MethoW	Run	Dilution Factor	Batch Number	Analyst	Lab	PrepareW or AnalyzeW
Dissolvem	d nalysis	A010D		1	BA37	D/	EET dTL	07j1Aj43 1B:11
Dissolvem	d nalysis	A0409		1	BA21	dD	EET dTL	07j1Aj43 15:05

Client Sample ID: HAM-PT-13-1074-FIL-PM
Date CollecteW 10d4d 2 79:74
Date ReceiveW 10d9d 2 13:72

Lab Sample ID: 014-7511-/
Matri8: x ater

Prep Type	Batch Type	Batch MethoW	Run	Dilution Factor	Batch Number	Analyst	Lab	PrepareW or AnalyzeW
Dissolvem	d nalysis	A010D		1	BA37	D/	EET dTL	07j1Aj43 1B:40
Dissolvem	d nalysis	A0409		1	BA21	dD	EET dTL	07j1Aj43 15:07

Client Sample ID: HAM-PT-13-1074-UNF-AM
Date CollecteW 10d4d 2 15:/ /
Date ReceiveW 10d9d 2 13:72

Lab Sample ID: 014-7511-6
Matri8: x ater

Prep Type	Batch Type	Batch MethoW	Run	Dilution Factor	Batch Number	Analyst	Lab	PrepareW or AnalyzeW
TotaljNd	6Rep	B010d			B57A	/ d	EET dTL	07j1Aj43 10:0B
TotaljNd	d nalysis	A010D		1	BAA2	Dd9	EET dTL	07j1Aj43 13:04
Total RecoveFable	6Rep	B005d			B577	/ d	EET dTL	07j1Aj43 10:B5
Total RecoveFable	d nalysis	A0409		1	B701	dD	EET dTL	07j1Aj43 1A:08

Client Sample ID: HAM-PT-13-1074-UNF-PM
Date CollecteW 10d4d 2 79:74
Date ReceiveW 10d9d 2 13:72

Lab Sample ID: 014-7511-2
Matri8: x ater

Prep Type	Batch Type	Batch MethoW	Run	Dilution Factor	Batch Number	Analyst	Lab	PrepareW or AnalyzeW
TotaljNd	6Rep	B010d			B57A	/ d	EET dTL	07j1Aj43 10:0B
TotaljNd	d nalysis	A010D		1	BAA2	Dd9	EET dTL	07j1Aj43 13:17
Total RecoveFable	6Rep	B005d			B577	/ d	EET dTL	07j1Aj43 10:B5
Total RecoveFable	d nalysis	A0409		1	B701	dD	EET dTL	07j1Aj43 15:52

Client Sample ID: HAM-PT-71-1074-UNF
Date CollecteW 10d4d 2 70:/ 1
Date ReceiveW 10d9d 2 13:72

Lab Sample ID: 014-7511-4
Matri8: x ater

Prep Type	Batch Type	Batch MethoW	Run	Dilution Factor	Batch Number	Analyst	Lab	PrepareW or AnalyzeW
TotaljNd	6Rep	B010d			B57A	/ d	EET dTL	07j1Aj43 10:0B
TotaljNd	d nalysis	A010D		1	BAA2	Dd9	EET dTL	07j1Aj43 13:45
Total RecoveFable	6Rep	B005d			B577	/ d	EET dTL	07j1Aj43 10:B5
Total RecoveFable	d nalysis	A0409		1	B701	dD	EET dTL	07j1Aj43 1A:11

Lab Chronicle

Client: Geosyntec Consultants Inc
6 Rectj/ ite: 6 lant SaH Honm

Job ID: 705-1200-1

Client Sample ID: HAM-PT-77-1074-FIL-AM

Lab Sample ID: 014-7511-9

Date CollecteW 10d4d 2 15:29

Matri8: x ater

Date ReceiveW 10d9d 2 13:72

Prep Type	Batch Type	Batch MethoW	Run	Dilution Factor	Batch Number	Analyst	Lab	PrepareW or AnalyzeW
Dissolvem	d nalysis	A010D		1	BA37	D/	EET dTL	07j1Aj43 1B:4B
Dissolvem	d nalysis	A0409		1	BA21	dD	EET dTL	07j1Aj43 15:08

Client Sample ID: HAM-PT-77-1074-FIL-PM

Lab Sample ID: 014-7511-0

Date CollecteW 10d4d 2 79:74

Matri8: x ater

Date ReceiveW 10d9d 2 13:72

Prep Type	Batch Type	Batch MethoW	Run	Dilution Factor	Batch Number	Analyst	Lab	PrepareW or AnalyzeW
Dissolvem	d nalysis	A010D		1	BA37	D/	EET dTL	07j1Aj43 1B:4A
Dissolvem	d nalysis	A0409		1	BA21	dD	EET dTL	07j1Aj43 15:14

Client Sample ID: HAM-PT-77-1074-UNF-AM

Lab Sample ID: 014-7511-5

Date CollecteW 10d4d 2 15:29

Matri8: x ater

Date ReceiveW 10d9d 2 13:72

Prep Type	Batch Type	Batch MethoW	Run	Dilution Factor	Batch Number	Analyst	Lab	PrepareW or AnalyzeW
TotaljNd	6Rep	B010d			B57A	/ d	EET dTL	07j1Aj43 10:0B
TotaljNd	d nalysis	A010D		1	BAA2	Dd9	EET dTL	07j1Aj43 13:42
Total RecovePable	6Rep	B005d			B577	/ d	EET dTL	07j1Aj43 10:B5
Total RecovePable	d nalysis	A0409		1	B701	dD	EET dTL	07j1Aj43 1A:37

Client Sample ID: HAM-PT-77-1074-UNF-PM

Lab Sample ID: 014-7511-3

Date CollecteW 10d4d 2 79:74

Matri8: x ater

Date ReceiveW 10d9d 2 13:72

Prep Type	Batch Type	Batch MethoW	Run	Dilution Factor	Batch Number	Analyst	Lab	PrepareW or AnalyzeW
TotaljNd	6Rep	B010d			B57A	/ d	EET dTL	07j1Aj43 10:0B
TotaljNd	d nalysis	A010D		1	BAA2	Dd9	EET dTL	07j1Aj43 13:B1
Total RecovePable	6Rep	B005d			B577	/ d	EET dTL	07j1Aj43 10:B5
Total RecovePable	d nalysis	A0409		1	B701	dD	EET dTL	07j1Aj43 1A:38

Client Sample ID: HAM-PT-7/ -1074-UNF

Lab Sample ID: 014-7511-71

Date CollecteW 10d4d 2 70:/ 1

Matri8: x ater

Date ReceiveW 10d9d 2 13:72

Prep Type	Batch Type	Batch MethoW	Run	Dilution Factor	Batch Number	Analyst	Lab	PrepareW or AnalyzeW
TotaljNd	6Rep	B010d			B57A	/ d	EET dTL	07j1Aj43 10:0B
TotaljNd	d nalysis	A010D		1	BAA2	Dd9	EET dTL	07j1Aj43 13:B3
Total RecovePable	6Rep	B005d			B577	/ d	EET dTL	07j1Aj43 10:B5
Total RecovePable	d nalysis	A0409		1	B701	dD	EET dTL	07j1Aj43 1A:54

Laboratory References:

EET dTL = EuRfins d tlanda, B020 6Resinential DP, d tlanda, Gd B0B30, TEL (770)357-2177

EuRfins d tlanda

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1800-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

1
2
3
4
5
6
7
8
9
10
11
12
13

Method Summary

92
Di en l ot G e s 9 oi ty 2 ci e li s
u æ P s æ j æ : u 2 i e / c S S oi H

Job ID: 705-1300-1

Method	Method Description	Protocol	Laboratory
V010D	8 l æ 2 49 u 6	j m 3 d W	M M () (E
V0T0A	8 l æ 2 49 u r 8 j 6	j m 3 d W	M M () (E
L005)	u æ B c æ æ o i p (o æ 2 , l s o R æ b 2 o a D C t o 2 R H 8 l æ 2	j m 3 d W	M M () (E
L010)	u æ B c æ æ o i p (o æ 2 8 l æ 2	j m 3 d W	M M () (E

Protocol References:

j m 3 d W v æ (l t e 8 l æ o H t h o a M R æ æ æ F j o æ æ H m c t æ p u " G æ c 2 9 " l S æ c 2 8 l æ o H t æ p (" æ H M H æ æ i p g o R S b l a 1 N 3 W) i H l æ U B H t æ t .

Laboratory References:

M M () (E v M y æ f æ t æ) æ i æ p L 0 3 0 u æ t æ i æ æ 2 D æ p æ i æ p n æ L 0 L d 0 p (M E 4 7 7 0 æ d 5 7 - 3 1 7 7

Sample Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1800-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-1800-1	HAM-PT-03-0715-4IF-AM	L ater	07/15/V2 08:VV	07/19/V2 03:12
705-1800-W	HAM-PT-03-0715-4IF-PM	L ater	07/15/V2 19:15	07/19/V2 03:12
705-1800-U	HAM-PT-03-0715-N6 4-AM	L ater	07/15/V2 08:VV	07/19/V2 03:12
705-1800-2	HAM-PT-03-0715-N6 4-PM	L ater	07/15/V2 19:15	07/19/V2 03:12
705-1800-5	HAM-PT-10-0715-N6 4	L ater	07/15/V2 17:V0	07/19/V2 03:12
705-1800-9	HAM-PT-11-0715-4IF-AM	L ater	07/15/V2 08:29	07/19/V2 03:12
705-1800-7	HAM-PT-11-0715-4IF-PM	L ater	07/15/V2 19:15	07/19/V2 03:12
705-1800-8	HAM-PT-11-0715-N6 4-AM	L ater	07/15/V2 08:29	07/19/V2 03:12
705-1800-3	HAM-PT-11-0715-N6 4-PM	L ater	07/15/V2 19:15	07/19/V2 03:12
705-1800-10	HAM-PT-1W0715-N6 4	L ater	07/15/V2 17:V0	07/19/V2 03:12

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-1800-1

Login Number: 1800

List Number: 1

Creator: Pomuti, Carmen

List Source: Eurofins Atlanta

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT



ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 7/24/2024 4:33:36 PM Revision 1

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-1889-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
7/24/2024 4:33:36 PM
Revision 1

1
2
3
4
5
6
7
8
9
10
11
12
13

Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	15
Lab Chronicle	17
Certification Summary	19
Method Summary	20
Sample Summary	21
Receipt Checklists	22
End Of Report	23

Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1889-1

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
□	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Environment Testing

[illegible]

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-1889-1

Job ID: 705-1889-1

Eurofins Atlanta

Job Narrative 705-1889-1

Revision

The report being provided is a revision of the original report sent on 7/17/2024. The report (revision 1) is being revised in order to correct a sample-switch issue in the metals prep lab.

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers and/or narrative comments are included to explain any exceptions, if applicable.

- Matrix QC may not be reported if insufficient sample is provided or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 7/17/2024 9:10 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 4.2°C.

Metals

Method 020 - Total recoverable: Samples AM-PT-08-071 -UN -AM (705-1889-1) and AM-PT-14-071 -UN -PM (705-1889-7) were switched during the method preparation step. The samples were analyzed directly from the bottle and results confirmed that these two samples were switched. The samples were reprocessed to report correctly.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1889-1

Client Sample ID: AMP-TU-02-071N-F r x-MP

Lab Sample ID: 705-122H-1

Date Cdlle/ te4: 0781N/3 07:55

PatWb: c ateW

Date Re/ eihe4: 078178/3 0H10

Pet6d4: Sc 23NN010D - Petals (ICT)									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
BdWln	0.20		0.040	0.026	mg/L		07/17/24 09:54	07/17/24 16:52	1
Pet6d4: Sc 23NN0v0B - Petals (ICTP S) - Udtal Re/ dheWble									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
MWeni/	0.v5		0.0050	0.0013	mg/L		07/17/24 10:15	07/17/24 15:34	1
IWln	7.,		0.040	0.018	mg/L		07/17/24 10:15	07/17/24 15:34	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1889-1

Client Sample ID: AMP-TU-02-071N-xIL-MP

Lab Sample ID: 705-122H-v

Date Cdllle/ te4: 0781N3 07:55

PatWb: c ateW

Date Re/ eihe4: 078178/3 0H10

Pet6d4: Sc 23NN010D - Petals (ICT) - Dissdlhe4									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
BdWln9Dissdlhe4	0.7N		0.040	0.026	mg/L			07/17/24 13:42	1
Pet6d4: Sc 23NN0v0B - Petals (ICT8P S) - Dissdlhe4									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
MWeni/ 9Dissdlhe4	0.v2		0.0050	0.0013	mg/L			07/17/24 16:46	1
IWln9Dissdlhe4	7.3		0.040	0.018	mg/L			07/17/24 16:46	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1889-1

Client Sample ID: AMP-TU-13-071N-F r x-MP

Lab Sample ID: 705-122H,
PatWb: c ateW

Date Cdille/ te4: 0781N/3 07:35

Date Re/ eihe4: 078178/3 0H10

Pet6d4: Sc 23NN010D - Petals (ICT)									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
BdWIn	0.Nv		0.040	0.026	mg/L		07/17/24 09:54	07/17/24 14:13	1
Pet6d4: Sc 23NN0v0B - P etals (ICTP S) - Udtal Re/ dheWble									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
Mvni/	0.v3		0.0050	0.0013	mg/L		07/17/24 10:15	07/17/24 15:27	1
IWIn	N,		4.0	1.8	mg/L		07/17/24 10:15	07/17/24 16:18	100

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1889-1

Client Sample ID: AMP-TU-13-071N-xIL-MP

Lab Sample ID: 705-122H-3

Date Cdll/ te4: 0781N/3 07:35

PatWb: c ateW

Date Re/ eihe4: 078178/3 0H:10

Pet6d4: Sc 23NN010D - Petals (ICT) - Dissdlhe4									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
BdWln9Dissdlhe4	0.N3		0.040	0.026	mg/L			07/17/24 13:45	1
Pet6d4: Sc 23NN0v0B - Petals (ICT&P S) - Dissdlhe4									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
MWeni/ 9Dissdlhe4	0.15		0.0050	0.0013	mg/L			07/17/24 16:50	1
IWln9Dissdlhe4	1,		0.040	0.018	mg/L			07/17/24 16:50	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1889-1

Client Sample ID: AMP-TU-02-071N-F r x-TP

Lab Sample ID: 705-122H-5

Date Cdille/ te4: 0781N/3 12:35

PatWb: c ateW

Date Re/ eihe4: 078178/3 0H10

Pet6d4: Sc 23NN010D - Petals (ICT)									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
BdWIn	0.7N		0.040	0.026	mg/L		07/17/24 09:54	07/17/24 14:16	1
Pet6d4: Sc 23NN0v0B - Petals (ICTP S) - Udtal Re/ dheWble									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
MWeni/	0., 3		0.0050	0.0013	mg/L		07/17/24 10:15	07/17/24 15:30	1
IWIn	vv		0.040	0.018	mg/L		07/17/24 10:15	07/17/24 15:30	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1889-1

Client Sample ID: AMP-TU-02-071N-xIL-TP

Lab Sample ID: 705-122H-N

Date Cdlle/ te4: 07/18/23 12:35

PatWb: c ateW

Date Re/ eihe4: 07/18/23 0H:10

Pet6d4: Sc 23NN010D - Petals (ICT) - Dissdlhe4									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
BdWIn9Dissdlhe4	0.N5		0.040	0.026	mg/L			07/17/24 13:49	1
Pet6d4: Sc 23NN0v0B - Petals (ICT&P S) - Dissdlhe4									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
MWeni/ 9Dissdlhe4	0., 0		0.0050	0.0013	mg/L			07/17/24 16:14	1
IWIn9Dissdlhe4	H.H		0.040	0.018	mg/L			07/17/24 16:14	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1889-1

Client Sample ID: AMP-TU-13-071N-F r x-TP

Lab Sample ID: 705-122H-7

Date Cdille/ te4: 0781N/3 12:35

PatWb: c ateW

Date Re/ eihe4: 078178/3 0H10

Pet6d4: Sc 23NN010D - Petals (ICT)									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
BdWIn	0.04		0.040	0.026	mg/L		07/17/24 09:54	07/17/24 14:19	1
Pet6d4: Sc 23NN0v0B - Petals (ICTP S) - Udtal Re/ dheWble									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
MWeni/	0.020		0.0050	0.0013	mg/L		07/17/24 10:15	07/17/24 15:23	1
IWIn	, 3		0.040	0.018	mg/L		07/17/24 10:15	07/17/24 15:23	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1889-1

Client Sample ID: AMP-TU-13-071N-xIL-TP
Date Cdlle/ te4: 0781N/3 12:35
Date Re/ eihe4: 078178/3 0H10

Lab Sample ID: 705-122H-2
PatWb: c ateW

Pet6d4: Sc 23NN010D - Petals (ICT) - Dissdlhe4									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
BdWln9Dissdlhe4	0.30		0.040	0.026	mg/L			07/17/24 13:52	1

Pet6d4: Sc 23NN0v0B - Petals (ICT&P S) - Dissdlhe4									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
MWeni/ 9Dissdlhe4	0.0v3		0.0050	0.0013	mg/L			07/17/24 16:54	1
IWln9Dissdlhe4	v0		0.040	0.018	mg/L			07/17/24 16:54	1

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1889-1

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-3776/1-A
Matrix: Water
Analysis Batch: 3915

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 3776

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	ND		0.040	0.026	mg/L		07/17/24 09:54	07/17/24 13:55	1

Lab Sample ID: LCS 705-3776/2-A
Matrix: Water
Analysis Batch: 3915

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 3776

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	1.00	1.03		mg/L		103	80 - 120

Lab Sample ID: LCSD 705-3776/3-A
Matrix: Water
Analysis Batch: 3915

Client Sample ID: Lab Control Sample Dup
Prep Type: Total/NA
Prep Batch: 3776

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron	1.00	1.03		mg/L		103	80 - 120	0	20

Lab Sample ID: MB 705-3817/1-A
Matrix: Water
Analysis Batch: 3915

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	ND		0.040	0.026	mg/L			07/17/24 13:33	1

Lab Sample ID: LCS 705-3817/2-A
Matrix: Water
Analysis Batch: 3915

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron, Dissolved	1.00	1.03		mg/L		103	80 - 120

Lab Sample ID: LCSD 705-3817/3-A
Matrix: Water
Analysis Batch: 3915

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron, Dissolved	1.00	1.01		mg/L		101	80 - 120	2	20

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-3771/1-A
Matrix: Water
Analysis Batch: 3925

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 3771

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	ND		0.0050	0.0013	mg/L		07/17/24 10:15	07/17/24 15:11	1
Iron	ND		0.040	0.018	mg/L		07/17/24 10:15	07/17/24 15:11	1

Eurofins Atlanta

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1889-1

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: LCS 705-3771/2-A

Matrix: Water

Analysis Batch: 3925

Client Sample ID: Lab Control Sample

Prep Type: Total Recoverable

Prep Batch: 3771

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.100	0.105		mg/L		105	80 - 120
Iron	1.00	1.10		mg/L		110	80 - 120

Lab Sample ID: LCSD 705-3771/3-A

Matrix: Water

Analysis Batch: 3925

Client Sample ID: Lab Control Sample Dup

Prep Type: Total Recoverable

Prep Batch: 3771

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic	0.100	0.0977		mg/L		98	80 - 120	7	20
Iron	1.00	1.02		mg/L		102	80 - 120	7	20

Lab Sample ID: MB 705-3811/1-A

Matrix: Water

Analysis Batch: 3951

Client Sample ID: Method Blank

Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	ND		0.0050	0.0013	mg/L			07/17/24 16:02	1
Iron, Dissolved	ND		0.040	0.018	mg/L			07/17/24 16:02	1

Lab Sample ID: LCS 705-3811/2-A

Matrix: Water

Analysis Batch: 3951

Client Sample ID: Lab Control Sample

Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic, Dissolved	0.100	0.0951		mg/L		95	80 - 120
Iron, Dissolved	1.00	1.00		mg/L		100	80 - 120

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1889-1

Client Sample ID: HAM-PT-09-0713-F 5 4-AM

Lab Sample ID: 70x-199W1

Date Collecte2: 07/13/2024 07:xx

Matrid: / ater

Date 6 eceiye2: 07/17/2024 0W10

Prep TBpe	s atch TBpe	s atch Metho2	6 zn	Dilztion 4actor	s atch 5 zmber	AnalBut	Lab	Prepare2 or AnalBNe2
Total/NA	Prep	3010A			3776	BR	EET ATL	07/17/24 09:54
Total/NA	Analysis	6010D		1	3915	DS	EET ATL	07/17/24 16:52
Total Recoverable	Prep	3005A			3771	BR	EET ATL	07/17/24 10:15
Total Recoverable	Analysis	6020B		1	3925	IF	EET ATL	07/17/24 15:34

Client Sample ID: HAM-PT-09-0713-4IL-AM

Lab Sample ID: 70x-199WR

Date Collecte2: 07/13/2024 07:xx

Matrid: / ater

Date 6 eceiye2: 07/17/2024 0W10

Prep TBpe	s atch TBpe	s atch Metho2	6 zn	Dilztion 4actor	s atch 5 zmber	AnalBut	Lab	Prepare2 or AnalBNe2
Dissolved	Analysis	6010D		1	3915	DS	EET ATL	07/17/24 13:42
Dissolved	Analysis	6020B		1	3951	IF	EET ATL	07/17/24 16:46

Client Sample ID: HAM-PT-1v-0713-F 5 4-AM

Lab Sample ID: 70x-199WU

Date Collecte2: 07/13/2024 07:vx

Matrid: / ater

Date 6 eceiye2: 07/17/2024 0W10

Prep TBpe	s atch TBpe	s atch Metho2	6 zn	Dilztion 4actor	s atch 5 zmber	AnalBut	Lab	Prepare2 or AnalBNe2
Total/NA	Prep	3010A			3776	BR	EET ATL	07/17/24 09:54
Total/NA	Analysis	6010D		1	3915	DS	EET ATL	07/17/24 14:13
Total Recoverable	Prep	3005A			3771	BR	EET ATL	07/17/24 10:15
Total Recoverable	Analysis	6020B		1	3925	IF	EET ATL	07/17/24 15:27
Total Recoverable	Prep	3005A			3771	BR	EET ATL	07/17/24 10:15
Total Recoverable	Analysis	6020B		100	3925	IF	EET ATL	07/17/24 16:18

Client Sample ID: HAM-PT-1v-0713-4IL-AM

Lab Sample ID: 70x-199Wv

Date Collecte2: 07/13/2024 07:vx

Matrid: / ater

Date 6 eceiye2: 07/17/2024 0W10

Prep TBpe	s atch TBpe	s atch Metho2	6 zn	Dilztion 4actor	s atch 5 zmber	AnalBut	Lab	Prepare2 or AnalBNe2
Dissolved	Analysis	6010D		1	3915	DS	EET ATL	07/17/24 13:45
Dissolved	Analysis	6020B		1	3951	IF	EET ATL	07/17/24 16:50

Client Sample ID: HAM-PT-09-0713-F 5 4-PM

Lab Sample ID: 70x-199Wx

Date Collecte2: 07/13/2024 19:vx

Matrid: / ater

Date 6 eceiye2: 07/17/2024 0W10

Prep TBpe	s atch TBpe	s atch Metho2	6 zn	Dilztion 4actor	s atch 5 zmber	AnalBut	Lab	Prepare2 or AnalBNe2
Total/NA	Prep	3010A			3776	BR	EET ATL	07/17/24 09:54
Total/NA	Analysis	6010D		1	3915	DS	EET ATL	07/17/24 14:16
Total Recoverable	Prep	3005A			3771	BR	EET ATL	07/17/24 10:15
Total Recoverable	Analysis	6020B		1	3925	IF	EET ATL	07/17/24 15:30

Eurofins Atlanta

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1889-1

Client Sample ID: HAM-PT-09-0713-4IL-PM

Lab Sample ID: 70x-199W3

Date Collecte2: 07/13/2019 19:vx

Matrid: / ater

Date 6 eceiye2: 07/17/2019 0W10

Prep TBpe	s atch TBpe	s atch Metho2	6 z n	Dilz tion 4actor	s atch 5 z mber	AnalBut	Lab	Prepare2 or AnalBut
Dissolved	Analysis	6010D		1	3915	DS	EET ATL	07/17/24 13:49
Dissolved	Analysis	6020B		1	3951	IF	EET ATL	07/17/24 16:14

Client Sample ID: HAM-PT-1v-0713-F 5 4-PM

Lab Sample ID: 70x-199W7

Date Collecte2: 07/13/2019 19:vx

Matrid: / ater

Date 6 eceiye2: 07/17/2019 0W10

Prep TBpe	s atch TBpe	s atch Metho2	6 z n	Dilz tion 4actor	s atch 5 z mber	AnalBut	Lab	Prepare2 or AnalBut
Total/NA	Prep	3010A			3776	BR	EET ATL	07/17/24 09:54
Total/NA	Analysis	6010D		1	3915	DS	EET ATL	07/17/24 14:19
Total Recoverable	Prep	3005A			3771	BR	EET ATL	07/17/24 10:15
Total Recoverable	Analysis	6020B		1	3925	IF	EET ATL	07/17/24 15:23

Client Sample ID: HAM-PT-1v-0713-4IL-PM

Lab Sample ID: 70x-199W9

Date Collecte2: 07/13/2019 19:vx

Matrid: / ater

Date 6 eceiye2: 07/17/2019 0W10

Prep TBpe	s atch TBpe	s atch Metho2	6 z n	Dilz tion 4actor	s atch 5 z mber	AnalBut	Lab	Prepare2 or AnalBut
Dissolved	Analysis	6010D		1	3915	DS	EET ATL	07/17/24 13:52
Dissolved	Analysis	6020B		1	3951	IF	EET ATL	07/17/24 16:54

LaboratorB 6 eferenceu:

EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1889-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13

Method Summary

Client: Gs noyct Bu l ot yai Pt Q It u
r jo/nuSho: r iPt GmPd d ot A

Job ID: 705-122C-1

Method	Method Description	Protocol	Laboratory
8010D	4 nCy dl r (	HM2V8	)) E TEL
80B03	4 nCy dl r S H(	HM2V8	)) E TEL
p005T	r jn, PjPot REoCi v nuo=njPbin oj Deyoi=nA 4 nCy	HM2V8	)) E TEL
p010T	r jn, PjPot REoCi 4 nCy	HM2V8	)) E TEL

Protocol References:
HM2V8 " HEnyG4 nCoAy goj) =PlaPa NHoia AMPyGR FcyaiPIS Fnd aiPi 4 nCoAyhREFeA) Asot R9 o=nd bnj 1C28 Tt AIQ U, APay.

Laboratory References:
)) E TEL ") ajofey TQPt PRp020 r jnyAnt ai DjRTQPt PRs T p0pWRE) L 6770(V87-2177

Sample Summary

Client: Geosyntec Consultants Inc
r jo/ectSite: r lant mad d onA

Job ID: 705-144P-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-144P-1	mMT -r 9-04-0713-FL WMT	2 atej	07S336 07:55	07S736 0P:10
705-144P-8	mMT -r 9-04-0713-WU-MT	2 atej	07S336 07:55	07S736 0P:10
705-144P-N	mMT -r 9-16-0713-FL WMT	2 atej	07S336 07:65	07S736 0P:10
705-144P-6	mMT -r 9-16-0713-WU-MT	2 atej	07S336 07:65	07S736 0P:10
705-144P-5	mMT -r 9-04-0713-FL Wr T	2 atej	07S336 14:65	07S736 0P:10
705-144P-3	mMT -r 9-04-0713-WU-r T	2 atej	07S336 14:65	07S736 0P:10
705-144P-7	mMT -r 9-16-0713-FL Wr T	2 atej	07S336 14:65	07S736 0P:10
705-144P-4	mMT -r 9-16-0713-WU-r T	2 atej	07S336 14:65	07S736 0P:10



Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-1889-1

Login Number: 1889

List Number: 1

Creator: Wallace, Ryan

List Source: Eurofins Atlanta

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	True	

END OF REPORT



ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 7/18/2024 6:33:25 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-2068-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
7/18/2024 6:33:25 PM



Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	14
Lab Chronicle	16
Certification Summary	18
Method Summary	19
Sample Summary	20
Receipt Checklists	21
End Of Report	22

Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2068-1

Qualifiers

Metals

Qualifier	Qualifier Description
4	MS, MSD: The analyte present in the original sample is greater than 4 times the matrix spike concentration; therefore, control limits are not applicable.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Chain of Custody Record

[illegible]

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-2068-1

Job ID: 705-2068-1

Eurofins Atlanta

Job Narrative 705-2068-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers and/or narrative comments are included to explain any exceptions, if applicable.

- Matrix QC may not be reported if insufficient sample is provided or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 7/18/2024 9: 9 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 0.2°C.

Metals

Method 020 - Total recoverable: The matrix spike / matrix spike duplicate (MS/MSD) recoveries for the following sample associated with preparation batch 705-404 and analytical batch 705-4209 were outside control limits: AM-PT-11-0717-UN (705-20 8-1), AM-PT-12-07-17-UN (705-20 8-), AM-PT-9-07-17-UN (705-20 8-5) and AM-PT-10-07-17-UN (705-20 8-7). The associated laboratory control sample (LCS) recovery met acceptance criteria.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

i a G y t o c u G a i o G c P a r G c I G a
j / o S a h n t : j e G s d r . . o G 2

Job ID: 705-104C-I

Client Sample ID: MPT -UN-AA-07A7-Fr x

Lab Sample ID: 705-102H-A

Date Cdlle/ te4: 078A78lv A0:00

T atWb: c ateW

Date Re/ ei3e4: 078A78lv 0h:6h

T et(d4: Sc Hv2 20A0D - T etals)ICU.									
Pnalzte	Result	f ualiBeW	RL	T DL	F nit	D	UWpaW4	PnalzQe4	Dil xa/
, dWln	0yH0		00g0	0014	. LHN		07H Q1g l 0:g1	07H Q1g l g:55	I
T et(d4: Sc Hv2 2010, - T etals)ICU8T S. - Ndtal Re/ d3eWble									
Pnalzte	Result	f ualiBeW	RL	T DL	F nit	D	UWpaW4	PnalzQe4	Dil xa/
IWln	A6		00g0	00I C	. LHN		07H Q1g l 0:50	07H Q1g l 7:g0	I
T dlzb4enum	0y00H7		00050	000048	. LHN		07H Q1g l 0:50	07H Q1g l 7:g0	I

Client Sample Results

i a G y t o c u G a i o G c P a r G c I G a
j / o S a h n s t : j e G s d r . . o G 2

Job ID: 705-104C-I

Client Sample ID: MPT -UN-AA-07A7-xIL

Lab Sample ID: 705-102H-1

Date Cdlle/ te4: 078A78lv A0:00

T atWb: c ateW

Date Re/ ei3e4: 078A78lv 0h:6h

T et(d4: Sc Hv2 20A0D - T etals)ICU. - Dissdl3e4									
Pnalzte	Result	f ualiBeW	RL	T DL	F nit	D	UWpaW4	PnalzQe4	Dil xa/
, dWln9Dissdl3e4	0yH		00g0	0014	. LHN			07H C4g l 5:l 8	I
T et(d4: Sc Hv2 2010, - T etals)ICU8T S. - Dissdl3e4									
Pnalzte	Result	f ualiBeW	RL	T DL	F nit	D	UWpaW4	PnalzQe4	Dil xa/
IWln9Dissdl3e4	A1		00g0	00I C	. LHN			07H C4g l 5:gC	I
T dlzb4enum9Dissdl3e4	0y00HA		00050	000048	. LHN			07H C4g l 5:gC	I

Client Sample Results

i a G y t o c u G a i o G c P a r G c I G a
j / o S a h n s t : j e G s d r . . o G 2

Job ID: 705-104C-I

Client Sample ID: MPT -UN-A1-07-A7-F r x

Lab Sample ID: 705-102H-6

Date Cdlle/ te4: 078A78lv A1:00

T atWb: c ateW

Date Re/ ei3e4: 078A78lv 0h:6h

T et(d4: Sc Hv2 20A0D - T etals)ICU.									
Pnalzte	Result	f ualiBeW	RL	T DL	F nit	D	UWpaW4	PnalzQe4	Dil xa/
, dWln	Ayl		00g0	0014	. LHN		07H Q1g l 0:g1	07H Q1g l g:E8	I
T et(d4: Sc Hv2 2010, - T etals)ICU8T S. - Ndtal Re/ d3eWble									
Pnalzte	Result	f ualiBeW	RL	T DL	F nit	D	UWpaW4	PnalzQe4	Dil xa/
T dlzb4enum	0y16		00050	000048	. LHN		07H Q1g l 0:50	07H Q1g l 7:51	I
IWln	0y20		00g0	00I C	. LHN		07H Q1g l 0:50	07H Q1g l 7:51	I

Client Sample Results

i a G y t o c u G a i o G c P a r G c I G a
j / o S a h n t : j e G d r . . o G 2

Job ID: 705-104C-I

Client Sample ID: MPT -UN-A1-07-A7-xIL

Lab Sample ID: 705-102H-v

Date Cdlle/ te4: 078A78lv A1:00

T atWb: c ateW

Date Re/ ei3e4: 078A78lv 0h:6h

T et(d4: Sc Hv2 20A0D - T etals)ICU. - Dissdl3e4									
Pnalzte	Result	f ualiBeW	RL	T DL	F nit	D	UWpaW4	PnalzQe4	Dil xa/
, dWln9Dissdl3e4	Ay6		00g0	0014	. LHN			07H C4g l 5:11	I
T et(d4: Sc Hv2 2010, - T etals)ICU8T S. - Dissdl3e4									
Pnalzte	Result	f ualiBeW	RL	T DL	F nit	D	UWpaW4	PnalzQe4	Dil xa/
T dlzb4enum9Dissdl3e4	0y16		00050	000048	. LHN			07H C4g l 5:51	I
I/oCADmcoet 2	f D		00g0	00I C	. LHN			07H C4g l 5:51	I

Client Sample Results

i a G y t o c u G a i o G c P a G c I G a
j / o S a h n t : j e G d r . . o G 2

Job ID: 705-104C-I

Client Sample ID: MPT -UN-h-07-A7-F r x

Lab Sample ID: 705-102H-5

Date Cdlle/ te4: 078A781v Av:00

T at Wb: c ateW

Date Re/ ei3e4: 078A781v 0h:6h

T et(d4: Sc Hv2 20A0D - T etals)ICU.

Pnalzte	Result	f ualiBeW	RL	T DL	F nit	D	UWpaW4	PnalzQe4	Dil xa/
, dWIn	Ay0		00g0	0014	. LHN		07H Q1g l 0:g1	07H Q1g l g:5C	I

T et(d4: Sc Hv2 2010, - T etals)ICU8T S. - Ndtal Re/ d3eWble

Pnalzte	Result	f ualiBeW	RL	T DL	F nit	D	UWpaW4	PnalzQe4	Dil xa/
T dlzb4enum	0y15		00050	000048	. LHN		07H Q1g l 0:50	07H Q1g l 7:54	I
IWIn	0y7H		00g0	00I C	. LHN		07H Q1g l 0:50	07H Q1g l 7:54	I

, P/ovGc 9se Gc

Client Sample Results

i a G y t o c u G a i o G c P a r G c I G a
j / o S a h n t : j e G d r . . o G 2

Job ID: 705-104C-I

Client Sample ID: MPT -UN-h-07-A7-xIL

Lab Sample ID: 705-102H-2

Date Cdlle/ te4: 078A781v Av:00

T atWb: c ateW

Date Re/ ei3e4: 078A781v 0h:6h

T et(d4: Sc Hv2 20A0D - T etals)ICU. - Dissdl3e4									
Pnalzte	Result	f ualiBeW	RL	T DL	F nit	D	UWpaW4	PnalzQe4	Dil xa/
, dWln9Dissdl3e4	Ay0		00g0	0014	. LHN			07H C4g l 5:15	I
T et(d4: Sc Hv2 2010, - T etals)ICU8T S. - Dissdl3e4									
Pnalzte	Result	f ualiBeW	RL	T DL	F nit	D	UWpaW4	PnalzQe4	Dil xa/
T dlzb4enum9Dissdl3e4	0y1v		00050	000048	. LHN			07H C4g l 5:54	I
IWln9Dissdl3e4	0yv2		00g0	00I C	. LHN			07H C4g l 5:54	I

Client Sample Results

i a G y t o c u G a i o G c P a r G c I G a
j / o S a h n s t : j e G s d r . . o G 2

Job ID: 705-104C-I

Client Sample ID: MPT -UN-A0-07-A7-F r x

Lab Sample ID: 705-102H-7

Date Cdlle/ te4: 078A781v Av:00

T at Wb: c ateW

Date Re/ ei3e4: 078A781v 0h:6h

T et(d4: Sc Hv2 20A0D - T etals)ICU.

Pnalzte	Result	f ualiBeW	RL	T DL	F nit	D	UWpaW4	PnalzQe4	Dil xa/
, dWIn	Ay7		00g0	0014	. LHN		07H Q1g 0:g1	07H Q1g 5:0l	I

T et(d4: Sc Hv2 2010, - T etals)ICU8T S. - Ndtal Re/ d3eWble

Pnalzte	Result	f ualiBeW	RL	T DL	F nit	D	UWpaW4	PnalzQe4	Dil xa/
T dlzb4enum	0yA7		00050	000048	. LHN		07H Q1g 0:50	07H Q1g C:00	I
IWIn	0yA0		00g0	00I C	. LHN		07H Q1g 0:50	07H Q1g C:00	I

, P/ovG 9 s G r

QC Sample Results

i a G y t o c u G a i o G c P a r G c I G a
j / o \$ a h n t : j e G s d r A A o G M

Job ID: 705-102C-I

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-4045/1-A
Matrix: Water
Analysis Batch: 4166

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 4045

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Bo/oG	ND		0.040	0.012	A 6Hg		07/11/24 10:41	07/11/24 14:LL	1

Lab Sample ID: LCS 705-4045/2-A
Matrix: Water
Analysis Batch: 4166

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 4045

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Bo/oG	1.00	1.0L		A 6Hg		10L	00 - 110

Lab Sample ID: 705-2068-3 MS
Matrix: Water
Analysis Batch: 4166

Client Sample ID: HAM-PT-12-07-17-UNF
Prep Type: Total/NA
Prep Batch: 4045

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Bo/oG	1.1		1.00	1.10		A 6Hg		100	75 - 115

Lab Sample ID: 705-2068-3 MSD
Matrix: Water
Analysis Batch: 4166

Client Sample ID: HAM-PT-12-07-17-UNF
Prep Type: Total/NA
Prep Batch: 4045

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Bo/oG	1.1		1.00	1.15		A 6Hg		105	75 - 115	1	10

Lab Sample ID: MB 705-4056/1-A
Matrix: Water
Analysis Batch: 4166

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Bo/oG3Drcco0t M	ND		0.040	0.012	A 6Hg			07/11/24 15:10	1

Lab Sample ID: LCS 705-4056/2-A
Matrix: Water
Analysis Batch: 4166

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Bo/oG3Drcco0t M	1.00	1.04		A 6Hg		104	00 - 110

Lab Sample ID: LCSD 705-4056/3-A
Matrix: Water
Analysis Batch: 4166

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Bo/oG3Drcco0t M	1.00	1.04		A 6Hg		104	00 - 110	1	10

8P/o, rG v s G r

QC Sample Results

i a G y t o c u G a i o G P a r G c I G a
j / o S a h n s t : j e G d r A A o G M

Job ID: 705-102C-I

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-4043/1-A
Matrix: Water
Analysis Batch: 4209

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 4043

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
I/oG	ND		0.040	0.01 C	A6Hg		07H Q14 10:50	07H Q14 17:L1	I
f o a b M GPA	ND		0.0050	0.0002E	A6Hg		07H Q14 10:50	07H Q14 17:L1	I

Lab Sample ID: LCS 705-4043/2-A
Matrix: Water
Analysis Batch: 4209

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 4043

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
I/oG	1.00	1.07		A6Hg		107	100 - 110
f o a b M GPA	0.100	0.102		A6Hg		102	100 - 110

Lab Sample ID: 705-2068-1 MS
Matrix: Water
Analysis Batch: 4209

Client Sample ID: HAM-PT-11-0717-UNF
Prep Type: Total Recoverable
Prep Batch: 4043

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
I/oG	1 L		1.00	14.2	4	A6Hg		141	75 - 115
f o a b M GPA	0.00C7		0.100	0.111		A6Hg		104	75 - 115

Lab Sample ID: 705-2068-1 MSD
Matrix: Water
Analysis Batch: 4209

Client Sample ID: HAM-PT-11-0717-UNF
Prep Type: Total Recoverable
Prep Batch: 4043

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	Limit
I/oG	1 L		1.00	14.5	4	A6Hg		111	75 - 115	I	10
f o a b M GPA	0.00C7		0.100	0.111		A6Hg		101	75 - 115	I	10

Lab Sample ID: MB 705-4051/1-A
Matrix: Water
Analysis Batch: 4197

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
I/oG3Drcoet M	ND		0.040	0.01 C	A6Hg			07H Q14 15:L2	I
f o a b M GPA 3Drcoet M	ND		0.0050	0.0002E	A6Hg			07H Q14 15:L2	I

Lab Sample ID: LCS 705-4051/2-A
Matrix: Water
Analysis Batch: 4197

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
I/oG3Drcoet M	1.00	0.022		A6Hg		07	100 - 110
f o a b M GPA 3Drcoet M	0.100	0.000		A6Hg		00	100 - 110

Lab Sample ID: LCSD 705-4051/3-A
Matrix: Water
Analysis Batch: 4197

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	Limit
I/oG3Drcoet M	1.00	0.071		A6Hg		07	100 - 110	I	10
f o a b M GPA 3Drcoet M	0.100	0.101		A6Hg		101	100 - 110	I	10

8P/o, n G v s G r

Lab Chronicle

Client: Geosyntec Consultants Inc
 r jo/ect\$ite: r lant mad d onp

Job ID: 705-1089-P

Client Sample ID: HAM-PT-00-9707-1 3 F

Lab Sample ID: 795-49xW0

Date Collecte2: 97878R09:99

Matrid: / ater

Date v ecei6e2: 97878R9y:By

Prep Tspe	u atch Tspe	u atch Metho2	v Nn	DiilNtion Factor	u atch 3 Nmber	Analstz	Lab	Prepare2 or Analstz
Eotal\$ B	r je3	A0P0B			R0R5	HB	66 E BET	07\$9\$IRP0:R1
Eotal\$ B	Bnalysis	80P0D		P	RP88	DH	66 E BET	07\$9\$IRPR:55
Eotal Neco2ejable	r je3	A005B			R0RA	HB	66 E BET	07\$9\$IRP0:50
Eotal Neco2ejable	Bnalysis	80104		P	R10v	IF	66 E BET	07\$9\$IRP7:R0

Client Sample ID: HAM-PT-00-9707-FIL

Lab Sample ID: 795-49xW4

Date Collecte2: 97878R09:99

Matrid: / ater

Date v ecei6e2: 97878R9y:By

Prep Tspe	u atch Tspe	u atch Metho2	v Nn	DiilNtion Factor	u atch 3 Nmber	Analstz	Lab	Prepare2 or Analstz
Dissol2ep	Bnalysis	80P0D		P	RP88	DH	66 E BET	07\$9\$IRP5:Pv
Dissol2ep	Bnalysis	80104		P	RPv7	IF	66 E BET	07\$9\$IRP5:R9

Client Sample ID: HAM-PT-04-97-07-1 3 F

Lab Sample ID: 795-49xWB

Date Collecte2: 97878R04:99

Matrid: / ater

Date v ecei6e2: 97878R9y:By

Prep Tspe	u atch Tspe	u atch Metho2	v Nn	DiilNtion Factor	u atch 3 Nmber	Analstz	Lab	Prepare2 or Analstz
Eotal\$ B	r je3	A0P0B			R0R5	HB	66 E BET	07\$9\$IRP0:R1
Eotal\$ B	Bnalysis	80P0D		P	RP88	DH	66 E BET	07\$9\$IRPR:Av
Eotal Neco2ejable	r je3	A005B			R0RA	HB	66 E BET	07\$9\$IRP0:50
Eotal Neco2ejable	Bnalysis	80104		P	R10v	IF	66 E BET	07\$9\$IRP7:51

Client Sample ID: HAM-PT-04-97-07-FIL

Lab Sample ID: 795-49xWR

Date Collecte2: 97878R04:99

Matrid: / ater

Date v ecei6e2: 97878R9y:By

Prep Tspe	u atch Tspe	u atch Metho2	v Nn	DiilNtion Factor	u atch 3 Nmber	Analstz	Lab	Prepare2 or Analstz
Dissol2ep	Bnalysis	80P0D		P	RP88	DH	66 E BET	07\$9\$IRP5:11
Dissol2ep	Bnalysis	80104		P	RPv7	IF	66 E BET	07\$9\$IRP5:51

Client Sample ID: HAM-PT-y-97-07-1 3 F

Lab Sample ID: 795-49xW5

Date Collecte2: 97878R0R:99

Matrid: / ater

Date v ecei6e2: 97878R9y:By

Prep Tspe	u atch Tspe	u atch Metho2	v Nn	DiilNtion Factor	u atch 3 Nmber	Analstz	Lab	Prepare2 or Analstz
Eotal\$ B	r je3	A0P0B			R0R5	HB	66 E BET	07\$9\$IRP0:R1
Eotal\$ B	Bnalysis	80P0D		P	RP88	DH	66 E BET	07\$9\$IRPR:59
Eotal Neco2ejable	r je3	A005B			R0RA	HB	66 E BET	07\$9\$IRP0:50
Eotal Neco2ejable	Bnalysis	80104		P	R10v	IF	66 E BET	07\$9\$IRP7:58

Lab Chronicle

Client: Geosyntec Consultants Inc

Job ID: 705-1089-P

Project: Btanta mad onp

Client Sample ID: HAM-PT-y-97-07-FIL

Lab Sample ID: 795-49xWx

Date Collected: 970708R0R99

Matrid: / ater

Date received: 970708R9y:By

Prep Tspe	uatch Tspe	uatch Metho2	v Nn	DilNtion Factor	uatch 3 Nmber	Analstz	Lab	Prepare2 or Analstz
Dissol2ep	Bnalysis	80P0D		P	RP88	DH	66E BET	070908RP5:15
Dissol2ep	Bnalysis	80104		P	RPv7	IF	66E BET	070908RP5:58

Client Sample ID: HAM-PT-09-97-07-1 3 F

Lab Sample ID: 795-49xW7

Date Collected: 970708R0R99

Matrid: / ater

Date received: 970708R9y:By

Prep Tspe	uatch Tspe	uatch Metho2	v Nn	DilNtion Factor	uatch 3 Nmber	Analstz	Lab	Prepare2 or Analstz
Eotal B	r je3	A0P0B			R0R5	HB	66E BET	070908RP0:R1
Eotal B	Bnalysis	80P0D		P	RP88	DH	66E BET	070908RP5:0P
Eotal Neco2ejable	r je3	A005B			R0RA	HB	66E BET	070908RP0:50
Eotal Neco2ejable	Bnalysis	80104		P	R10v	IF	66E BET	070908RP9:00

Laborators v eferencez:

66E BET = 6ujofins Btlanta, A090 r jesipential Dj, Btlanta, GB A0AR0, E6T (770)R57-9P77

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2068-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13

Method Summary

i a G y t ocuG a i oGcP a Gc IGa
j /o\$ a h n t : j e G s d r A A o G M

Job ID: 705-102C-I

Method	Method Description	Protocol	Laboratory
20I 0D	4 t s e d i j (	mWC82	)) E TEL
2010B	4 t s e d i j H m(	mWC82	)) E TEL
3005T	j /t pr /r s o G E o s e R t a o v t /r b e o/ D r e c c o a r t M 4 t s e	mWC82	)) E TEL
30I 0T	j /t pr /r s o G E o s e 4 t s e	mWC82	)) E TEL

Protocol References:

mWC82 = "E cs4 t shoMc Fo/) vr ePr sG m o a W r c d , j h u c r a r d i l h t A r a r e 4 t shoMc", EhrilM) M s o G N o v t A b t / I 9 C 2 T G M l s c U p M t d c.

Laboratory References:

)) E TEL =) P / o f r G c T s s G s , 3000 j / t c r i M G a n e D / , T s s G s , y T 30380, E) L 6770(857-Q 77

Sample Summary

Client: Geosyntec Consultants Inc
Section: j lant d aA A onM

Job ID: 705-104P-r

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-104P-r	d T9 -j 3-r r -07r 7-FL W	2 ate/	07H 7H8 r 0:00	07H PH8 06:U6
705-104P-1	d T9 -j 3-r r -07r 7-WN	2 ate/	07H 7H8 r 0:00	07H PH8 06:U6
705-104P-U	d T9 -j 3-r 1-07-r 7-FL W	2 ate/	07H 7H8 r 1:00	07H PH8 06:U6
705-104P-8	d T9 -j 3-r 1-07-r 7-WN	2 ate/	07H 7H8 r 1:00	07H PH8 06:U6
705-104P-5	d T9 -j 3-6-07-r 7-FL W	2 ate/	07H 7H8 r 8:00	07H PH8 06:U6
705-104P-4	d T9 -j 3-6-07-r 7-WN	2 ate/	07H 7H8 r 8:00	07H PH8 06:U6
705-104P-7	d T9 -j 3-r 0-07-r 7-FL W	2 ate/	07H 7H8 r 8:00	07H PH8 06:U6

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-2068-1

Login Number: 2068

List Number: 1

Creator: Pomuti, Carmen

List Source: Eurofins Atlanta

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT



ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 7/22/2024 8:12:46 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-2266-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
7/22/2024 8:12:46 PM

Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	17
Lab Chronicle	19
Certification Summary	21
Method Summary	22
Sample Summary	23
Receipt Checklists	24
End Of Report	25



Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2266-1

Qualifiers

Metals

Qualifier	Qualifier Description
4	MS, MSD: The analyte present in the original sample is greater than 4 times the matrix spike concentration; therefore, control limits are not applicable.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Environment Testing

[illegible]

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-2266-1

Job ID: 705-2266-1

Eurofins Atlanta

Job Narrative 705- -1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers and/or narrative comments are included to explain any exceptions, if applicable.

- Matrix QC may not be reported if insufficient sample is provided or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 7/19/2024 2:14 PM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 2.1°C.

Receipt Exceptions

Limited sample volume was received for the following samples: AM-PT-07-0718- IL (705-22 -2), AM-PT-08-0718- IL (705-22 -4), AM-PT-1 -0718- IL (705-22 -), AM-PT-14-0718- IL (705-22 -8) and AM-PT-15-0718- IL (705-22 -10).

Metals

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1188-9

Client Sample ID: AMP-TU-07-07HN-F r x

Lab Sample ID: 705-1122-H

Date Cdille/ te4: 078-N81v Hv:05

PatWb: c ateW

Date Re/ ei3e4: 078-h81v Hv:Hv

Pet6d4: Sc Nr2 20H0D - Petals (ICT)									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
BdWln	0.5N		0.040	0.018	m2/6		07/11/14 07:01	07/11/14 9g:9L	9
Pet6d4: Sc Nr2 2010B - Petals (ICTP S) - Udtal Re/ d3eWble									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
MWeni/	0.1N		0.0050	0.009g	m2/6		07/11/14 08:55	07/11/14 98:47	9
IWln	1H		0.040	0.09L	m2/6		07/11/14 08:55	07/11/14 98:47	9

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1188-9

Client Sample ID: AMP-TU-07-07HN-xIL

Lab Sample ID: 705-1122-1

Date Cdile/ te4: 078-N81v Hv:05

PatWb: c ateW

Date Re/ ei3e4: 078-h81v Hv:Hv

Pet6d4: Sc Nr2 20H0D - P etals (ICT) - Dissdl3e4									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
BdWln, Dissdl3e4	0.5h		0.040	0.018	m2/6			07/11/14 91:07	9
Pet6d4: Sc Nr2 2010B - P etals (ICT&P S) - Dissdl3e4									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
MWeni/ , Dissdl3e4	0.12		0.0050	0.009g	m2/6			07/11/14 9A:05	9
IWln, Dissdl3e4	H2		0.040	0.09L	m2/6			07/11/14 94:05	9

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1188-9

Client Sample ID: AMP-TU-0N-07HN-F r x
Date Cdille/ te4: 078-N81v 10:51
Date Re/ ei3e4: 078-h81v Hv:Hv

Lab Sample ID: 705-1122-9
PatWb: c ateW

Pet6d4: Sc Nr2 20H0D - Petals (ICT)										
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/	
BdWln	0.71		0.040	0.018	m2/6		07/11/14 07:01	07/11/14 9g:gg	9	

Pet6d4: Sc Nr2 2010B - Petals (ICTP S) - Udtal Re/ d3eWble										
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/	
MNeni/	0.1h		0.0050	0.009g	m2/6		07/11/14 08:55	07/11/14 98:17	9	
IWln	NN		0.040	0.09L	m2/6		07/11/14 08:55	07/11/14 98:17	9	

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1188-9

Client Sample ID: AMP-TU-0N-07HN-xIL

Lab Sample ID: 705-1122-v

Date Cdille/ te4: 078-N81v 10:51

PatWb: c ateW

Date Re/ ei3e4: 078-h81v Hv:Hv

Pet6d4: Sc Nr2 20H0D - P etals (ICT) - Dissdl3e4									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
BdWln, Dissdl3e4	0.75		0.040	0.018	m2/6			07/11/14 91:90	9
Pet6d4: Sc Nr2 2010B - P etals (ICT&P S) - Dissdl3e4									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
MWeni/ , Dissdl3e4	0.12		0.0050	0.009g	m2/6			07/11/14 9A:0A	9
IWln, Dissdl3e4	7.5		0.040	0.09L	m2/6			07/11/14 94:0A	9

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1188-9

Client Sample ID: AMP-TU-H9-07HN-F r x
Date Cdille/ te4: 078-H81v Ht:51
Date Re/ ei3e4: 078-H81v Hv:Hv

Lab Sample ID: 705-1122-5
PatWb: c ateW

Pet6d4: Sc Nr2 20H0D - P etals (ICT)									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
BdWln	0.59		0.040	0.018	m2/6		07/11/14 07:01	07/11/14 9g:g8	9
Pet6d4: Sc Nr2 2010B - P etals (ICTP S) - Udtal Re/ d3eWble									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
MWeni/	0.1h		0.0050	0.009g	m2/6		07/11/14 08:55	07/11/14 98:59	9
IWln	HN		0.040	0.09L	m2/6		07/11/14 08:55	07/11/14 98:59	9

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1188-9

Client Sample ID: AMP-TU-H9-07HN-xIL

Lab Sample ID: 705-1122-2

Date Cdile/ te4: 078-H81v Ht:51

PatWb: c ateW

Date Re/ ei3e4: 078-h81v Hv:Hv

Pet6d4: Sc Nr2 20H0D - P etals (ICT) - Dissdl3e4									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
BdWln, Dissdl3e4	0.52		0.040	0.018	m2/6			07/11/14 91:9g	9
Pet6d4: Sc Nr2 2010B - P etals (ICT&P S) - Dissdl3e4									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
MWeni/ , Dissdl3e4	0.17		0.0050	0.009g	m2/6			07/11/14 9A:9g	9
IWln, Dissdl3e4	H5		0.040	0.09L	m2/6			07/11/14 94:91	9

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1188-9

Client Sample ID: AMP-TU-Hv-07HN-F r x

Lab Sample ID: 705-1122-7

Date Cdille/ te4: 078-HN1v H2:97

PatWb: c ateW

Date Re/ ei3e4: 078-Hh81v Hv:Hv

Pet6d4: Sc Nv2 20H0D - Petals (ICT)									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
BdWln	0.2v		0.040	0.018	m2/6		07/11/14 07:01	07/11/14 9g:gA	9
Pet6d4: Sc Nv2 2010B - Petals (ICTP S) - Udtal Re/ d3eWble									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
MWeni/	0.1H		0.0050	0.009g	m2/6		07/11/14 08:55	07/11/14 97:99	9
IWln	HN		0.040	0.09L	m2/6		07/11/14 08:55	07/11/14 97:99	9

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1188-9

Client Sample ID: AMP-TU-Hv-07HN-xIL

Lab Sample ID: 705-1122-N

Date Cdll/ te4: 078-N81v H2:97

PatWb: c ateW

Date Re/ ei3e4: 078-h81v Hv:Hv

Pet6d4: Sc Nv2 20H0D - P etals (ICT) - Dissdl3e4									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
BdWln, Dissdl3e4	0.22		0.040	0.018	m2/6			07/11/14 91:95	9
Pet6d4: Sc Nv2 2010B - P etals (ICT&P S) - Dissdl3e4									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
MWeni/ , Dissdl3e4	0.10		0.0050	0.009g	m2/6			07/11/14 9A:97	9
IWln, Dissdl3e4	Hv		0.040	0.09L	m2/6			07/11/14 94:94	9

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1188-9

Client Sample ID: AMP-TU-H5-07HN-F r x
Date Cdille/ te4: 078-H81v HN:HN
Date Re/ ei3e4: 078-h81v Hv:Hv

Lab Sample ID: 705-1122-h
PatWb: c ateW

Pet6d4: Sc Nr2 20H0D - Petals (ICT)										
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/	
BdWln	0.70		0.040	0.018	m2/6		07/11/14 07:01	07/11/14 9g:41	9	

Pet6d4: Sc Nr2 2010B - Petals (ICTP S) - Udtal Re/ d3eWble										
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/	
Mvni/	0.v1		0.0050	0.009g	m2/6		07/11/14 08:55	07/11/14 97:95	9	
IWln	h.v		0.040	0.09L	m2/6		07/11/14 08:55	07/11/14 97:95	9	

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1188-9

Client Sample ID: AMP-TU-H5-07HN-xIL
Date Cdll/ te4: 078-H8lv HN:HN
Date Re/ ei3e4: 078-h8lv Hv:Hv

Lab Sample ID: 705-1122-H0
PatWb: c ateW

Pet6d4: Sc Nr2 20H0D - P etals (ICT) - Dissdl3e4									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
BdWln, Dissdl3e4	0.71		0.040	0.018	m2/6			07/11/14 91:9L	9

Pet6d4: Sc Nr2 2010B - P etals (ICT&P S) - Dissdl3e4									
Mnalyte	Result	QualifieW	RL	P DL	F nit	D	TWpaW4	Mnalyze4	Dil xa/
MWeni/ , Dissdl3e4	0.vH		0.0050	0.009g	m2/6			07/11/14 9A:19	9
IWln, Dissdl3e4	7.7		0.040	0.09L	m2/6			07/11/14 94:98	9

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1188-9

Method: 6010D - Metals (ICP)

Lab Sample ID: 705-2266-1 MSD
Matrix: Water
Analysis Batch: 4541

Client Sample ID: HAM-PT-07-0718-UNF
Prep Type: Total/NA
Prep Batch: 4417

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron	0N		9N0	9N4		m2/6					

Lab Sample ID: MB 705-4419/1-A
Matrix: Water
Analysis Batch: 4514

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
BorongDissolLed	3D		0N, 0	0N18	m2/6			07/11/1, 99:51	9

Lab Sample ID: LCS 705-4419/2-A
Matrix: Water
Analysis Batch: 4514

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
BorongDissolLed	9N0	9N1		m2/6		901	.0 - 910

Lab Sample ID: LCSD 705-4419/3-A
Matrix: Water
Analysis Batch: 4514

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
BorongDissolLed	9N0	9N,		m2/6		90,	.0 - 910	1	10

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-4416/1-A
Matrix: Water
Analysis Batch: 4580

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 4416

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
vrseic	3D		0N050	0N094	m2/6		07/11/1, 08:55	07/11/1, 98:9A	9
Iron	3D		0N, 0	0N9.	m2/6		07/11/1, 08:55	07/11/1, 98:9A	9

Lab Sample ID: LCS 705-4416/2-A
Matrix: Water
Analysis Batch: 4580

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 4416

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
vrseic	0N00	0N0A, 4		m2/6		A,	.0 - 910
Iron	9N0	9N9		m2/6		909	.0 - 910

Lab Sample ID: 705-2266-3 MS
Matrix: Water
Analysis Batch: 4580

Client Sample ID: HAM-PT-08-0718-UNF
Prep Type: Total Recoverable
Prep Batch: 4416

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
vrseic	0NA		0N00	0M.		m2/6		900	75 - 915
Iron	. N		9N0	AM8 ,		m2/6		997	75 - 915

Eurofins v tlanta

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1188-9

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: 705-2266-3 MSD
Matrix: Water
Analysis Batch: 4580

Client Sample ID: HAM-PT-08-0718-UNF
Prep Type: Total Recoverable
Prep Batch: 4416

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
vrseic	0NA		0000	0MAA		m2/6		999	75 - 915	4	10
Iron	. N		900	AN87		m2/6		. A	75 - 915	4	10

Lab Sample ID: MB 705-4418/1-B
Matrix: Water
Analysis Batch: 4564

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
vrseicgDissolLed	3 D		00050	00094	m2/6			07/11/1, 94:5.	9
IrongDissolLed	3 D		00, 0	009.	m2/6			07/11/1, 94:5.	9

Lab Sample ID: LCS 705-4418/2-B
Matrix: Water
Analysis Batch: 4564

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
vrseicgDissolLed	0000	0004		m2/6		904	. 0 - 910
IrongDissolLed	900	0N15		m2/6		. 4	. 0 - 910

Lab Sample ID: LCSD 705-4418/3-B
Matrix: Water
Analysis Batch: 4564

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
vrseicgDissolLed	0000	0097		m2/6		997	. 0 - 910	94	10
IrongDissolLed	900	0N44		m2/6		. 4	. 0 - 910	9	10

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1188-9

Client Sample ID: HAM-PT-09-0971-3 F 5

Lab Sample ID: 904-xxVWV7

Date Collecte2: 09/18/2017

Matrid: / ater

Date v ecei6e2: 09/18/2017

Prep TBpe	s atch TBpe	s atch Metho2	v z n	Dilztion 5actor	s atch Fz mber	AnalBut	Lab	Prepare2 or AnalBNe2
Total/NA	Prep	3090A			6697	BR	EET ATL	07/11/16 07:01
Total/NA	Analysis	8090D		9	6569	DAB	EET ATL	07/11/16 93:92
Total Reco4erable	Prep	3005A			6698	BR	EET ATL	07/11/16 08:55
Total Reco4erable	Analysis	8010B		9	6520	Iv	EET ATL	07/11/16 98:67

Client Sample ID: HAM-PT-09-0971-5IL

Lab Sample ID: 904-xxVWVx

Date Collecte2: 09/18/2017

Matrid: / ater

Date v ecei6e2: 09/18/2017

Prep TBpe	s atch TBpe	s atch Metho2	v z n	Dilztion 5actor	s atch Fz mber	AnalBut	Lab	Prepare2 or AnalBNe2
Dissol4ed	Analysis	8090D		9	6596	DAB	EET ATL	07/11/16 91:07
Dissol4ed	Analysis	8010B		9	6586	AD	EET ATL	07/11/16 96:05
Dissol4ed	Analysis	8010B		9	6800	Iv	EET ATL	07/11/16 9F:05

Client Sample ID: HAM-PT-01-0971-3 F 5

Lab Sample ID: 904-xxVWU

Date Collecte2: 09/18/2017

Matrid: / ater

Date v ecei6e2: 09/18/2017

Prep TBpe	s atch TBpe	s atch Metho2	v z n	Dilztion 5actor	s atch Fz mber	AnalBut	Lab	Prepare2 or AnalBNe2
Total/NA	Prep	3090A			6697	BR	EET ATL	07/11/16 07:01
Total/NA	Analysis	8090D		9	6569	DAB	EET ATL	07/11/16 93:33
Total Reco4erable	Prep	3005A			6698	BR	EET ATL	07/11/16 08:55
Total Reco4erable	Analysis	8010B		9	6520	Iv	EET ATL	07/11/16 98:17

Client Sample ID: HAM-PT-01-0971-5IL

Lab Sample ID: 904-xxVWVr

Date Collecte2: 09/18/2017

Matrid: / ater

Date v ecei6e2: 09/18/2017

Prep TBpe	s atch TBpe	s atch Metho2	v z n	Dilztion 5actor	s atch Fz mber	AnalBut	Lab	Prepare2 or AnalBNe2
Dissol4ed	Analysis	8090D		9	6596	DAB	EET ATL	07/11/16 91:90
Dissol4ed	Analysis	8010B		9	6586	AD	EET ATL	07/11/16 96:0F
Dissol4ed	Analysis	8010B		9	6800	Iv	EET ATL	07/11/16 9F:0F

Client Sample ID: HAM-PT-7U-0971-3 F 5

Lab Sample ID: 904-xxVWV4

Date Collecte2: 09/18/2017

Matrid: / ater

Date v ecei6e2: 09/18/2017

Prep TBpe	s atch TBpe	s atch Metho2	v z n	Dilztion 5actor	s atch Fz mber	AnalBut	Lab	Prepare2 or AnalBNe2
Total/NA	Prep	3090A			6697	BR	EET ATL	07/11/16 07:01
Total/NA	Analysis	8090D		9	6569	DAB	EET ATL	07/11/16 93:38
Total Reco4erable	Prep	3005A			6698	BR	EET ATL	07/11/16 08:55
Total Reco4erable	Analysis	8010B		9	6520	Iv	EET ATL	07/11/16 98:59

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1188-9

Client Sample ID: HAM-PT-7U-0971-5IL

Lab Sample ID: 904-xxVWW

Date Collecte2: 09/18/2017 7:4x

Matrid: / ater

Date v ecei6e2: 09/18/2017 7:7R

Prep TBpe	s atch TBpe	s atch Metho2	v z n	Dilztion 5actor	s atch Fz mber	AnalBut	Lab	Prepare2 or AnalBne2
Dissol4ed	Analysis	8090D		9	6596	DAB	EET ATL	07/11/16 91:93
Dissol4ed	Analysis	8010B		9	6586	AD	EET ATL	07/11/16 96:91
Dissol4ed	Analysis	8010B		9	6800	Iv	EET ATL	07/11/16 9F:93

Client Sample ID: HAM-PT-7R-0971-3 F 5

Lab Sample ID: 904-xxVWV9

Date Collecte2: 09/18/2017 7WU9

Matrid: / ater

Date v ecei6e2: 09/18/2017 7:7R

Prep TBpe	s atch TBpe	s atch Metho2	v z n	Dilztion 5actor	s atch Fz mber	AnalBut	Lab	Prepare2 or AnalBne2
Total/NA	Prep	3090A			6697	BR	EET ATL	07/11/16 07:01
Total/NA	Analysis	8090D		9	6569	DAB	EET ATL	07/11/16 93:3F
Total Reco4erable	Prep	3005A			6698	BR	EET ATL	07/11/16 08:55
Total Reco4erable	Analysis	8010B		9	6520	Iv	EET ATL	07/11/16 97:99

Client Sample ID: HAM-PT-7R-0971-5IL

Lab Sample ID: 904-xxVWV1

Date Collecte2: 09/18/2017 7WU9

Matrid: / ater

Date v ecei6e2: 09/18/2017 7:7R

Prep TBpe	s atch TBpe	s atch Metho2	v z n	Dilztion 5actor	s atch Fz mber	AnalBut	Lab	Prepare2 or AnalBne2
Dissol4ed	Analysis	8090D		9	6596	DAB	EET ATL	07/11/16 91:95
Dissol4ed	Analysis	8010B		9	6586	AD	EET ATL	07/11/16 96:96
Dissol4ed	Analysis	8010B		9	6800	Iv	EET ATL	07/11/16 9F:97

Client Sample ID: HAM-PT-74-0971-3 F 5

Lab Sample ID: 904-xxVWV7

Date Collecte2: 09/18/2017 71:71

Matrid: / ater

Date v ecei6e2: 09/18/2017 7:7R

Prep TBpe	s atch TBpe	s atch Metho2	v z n	Dilztion 5actor	s atch Fz mber	AnalBut	Lab	Prepare2 or AnalBne2
Total/NA	Prep	3090A			6697	BR	EET ATL	07/11/16 07:01
Total/NA	Analysis	8090D		9	6569	DAB	EET ATL	07/11/16 93:61
Total Reco4erable	Prep	3005A			6698	BR	EET ATL	07/11/16 08:55
Total Reco4erable	Analysis	8010B		9	6520	Iv	EET ATL	07/11/16 97:95

Client Sample ID: HAM-PT-74-0971-5IL

Lab Sample ID: 904-xxVWV70

Date Collecte2: 09/18/2017 71:71

Matrid: / ater

Date v ecei6e2: 09/18/2017 7:7R

Prep TBpe	s atch TBpe	s atch Metho2	v z n	Dilztion 5actor	s atch Fz mber	AnalBut	Lab	Prepare2 or AnalBne2
Dissol4ed	Analysis	8090D		9	6596	DAB	EET ATL	07/11/16 91:92
Dissol4ed	Analysis	8010B		9	6586	AD	EET ATL	07/11/16 96:98
Dissol4ed	Analysis	8010B		9	6800	Iv	EET ATL	07/11/16 9F:19

LaboratorB v eferenceu:

EET ATL = Eurofins Atlanta, 3020 Presidential Dr, Atlanta, GA 30360, TEL (770)657-2977

Eurofins Atlanta

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2266-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13

Method Summary

Client: Gs noyct G u l ot yai P t Q It u
r jo/hu S e: r i P t G m P d ot A

Job ID: 705-1122-C

Method	Method Description	Protocol	Laboratory
2000D	4 n G y d l r (	HMV82	)) E TEL
2010B	4 n G y d l r S H(	HMV82	)) E TEL
3005T	r jnp P j P o t , E o P i Rnuovnj P bin oj Deyyoivn A 4 n G y	HMV82	)) E TEL
3000T	r jnp P j P o t , E o P i 4 n G y	HMV82	)) E TEL

Protocol References:

HMV82 = "Eny G 4 n G o Ay Foj) vPla P g Hoie A MPy G, r hcy e P i S hnd e P i 4 n G o Ay", Eh e A) A e o t , Novnd bnj C9V2 T t A I G Up A P G y.

Laboratory References:

)) E TEL =) ajof e y T G P t P , 30V0 r jny e Ant G P i Dj, T G P t P , s T 30380, E) L 6770(857-WC77

Sample Summary

Client: Geosyntec Consultants Inc
r jo/ect\$ite: r lant mad d onA

Job ID: 705-1144-P

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-1144-P	mMT -r 9-07-07P3-FL W	2 atej	07\$P3\$8 P8:05	07\$P6\$8 P8:P8
705-1144-1	mMT -r 9-07-07P3-WU	2 atej	07\$P3\$8 P8:05	07\$P6\$8 P8:P8
705-1144-N	mMT -r 9-03-07P3-FL W	2 atej	07\$P3\$8 10:51	07\$P6\$8 P8:P8
705-1144-8	mMT -r 9-03-07P3-WU	2 atej	07\$P3\$8 10:51	07\$P6\$8 P8:P8
705-1144-5	mMT -r 9-PN-07P3-FL W	2 atej	07\$P3\$8 PP:51	07\$P6\$8 P8:P8
705-1144-4	mMT -r 9-PN-07P3-WU	2 atej	07\$P3\$8 PP:51	07\$P6\$8 P8:P8
705-1144-7	mMT -r 9-P8-07P3-FL W	2 atej	07\$P3\$8 P4:N7	07\$P6\$8 P8:P8
705-1144-3	mMT -r 9-P8-07P3-WU	2 atej	07\$P3\$8 P4:N7	07\$P6\$8 P8:P8
705-1144-6	mMT -r 9-P5-07P3-FL W	2 atej	07\$P3\$8 P3:P3	07\$P6\$8 P8:P8
705-1144-P0	mMT -r 9-P5-07P3-WU	2 atej	07\$P3\$8 P3:P3	07\$P6\$8 P8:P8

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-2266-1

Login Number: 2266

List Source: Eurofins Atlanta

List Number: 1

Creator: Stephens, Andrena

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	N/A	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	False	Limited volume received.
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	N/A	
Multiphasic samples are not present.	N/A	
Samples do not require splitting or compositing.	N/A	
Residual Chlorine Checked.	N/A	

END OF REPORT

ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 7/25/2024 6:03:35 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-2571-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Generated
7/25/2024 6:03:35 PM

Authorized for release by
Nikita Kuruganty, Project Manager
Nikita.Kuruganty@et.eurofinsus.com
Designee for
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986



Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	7
Client Sample Results	8
QC Sample Results	14
Lab Chronicle	17
Certification Summary	19
Method Summary	20
Sample Summary	21
Receipt Checklists	22
End Of Report	23

Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2571-1

Qualifiers

Metals

Qualifier	Qualifier Description
B	Compound was found in the blank and sample.
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Environment Testing

Ver: 04/02/2024 7/25/2024

Chain of Custody Record



Environment Testing

Client Information		Lab PM: David Fuller / Phone: 770-344-8896		COC No:	
Client Contact: Kip Gray		E-Mail: David Fuller@atl.eurofins.com		Page 1 of 1	
Company: Geosynlec Consultants Inc		PWSID:		Job #:	
Address: 1265 Roberts Blvd, NW Suite 200		Due Date Requested:		Analysis Requested	
City: Kennesaw		TAT Requested (days): RUSH / 1-BW-TAT		Preservation Codes: D - HPO3	
State: GA, 30144		Compliance Project: & Yes & No		7/15-25/21 COC	
Phone:		Lab Project #: 70500911 (DO NOT REMOVE)		Other:	
Email: Kip Gray@Geosynlec.com		PO #:		Special Instructions/Note:	
Project Name: Plant Hammond		Project #:			
Task Code:		SSOW#:			
Task Code#:					
Sample Identification		Sample Date	Sample Time	Sample Type (C-Comp, G-grab)	Matrix (Inert, Acid, Organic, Aqueous)
HAM-PT-08-7-24-VNF-AH	7/24/24	900	G	W	
HAM-PT-08-7-24-FIL-AH	7/24/24	900	G	N	
HAM-PT-14-7-24-VNF-AH	7/24/24	900	G	W	
HAM-PT-14-7-24-FIL-AH	7/24/24	900	G	W	
HAM-PT-11-7-24-VNF-AH	7/24/24	1000	G	W	
HAM-PT-11-7-24-FIL-AH	7/24/24	1000	G	W	
Possible Hazard Identification		☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☒ Unknown ☐ Radiological		Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)	
Deliverable Requested I, II, III, IV, Other (specify)				☐ Return To Client ☐ Disposal By Lab ☐ Archive For Months	
Empty Kit Relinquished by		Date		Method of Shipment	
Relinquished by: Zari Webb		7/24/24 11:16		Express	
Relinquished by: Zari Webb		7/24 1:05 PM		7/24 11:16 AM	
Relinquished by: Zari Webb		7/24 1:05 PM		7/24/24 15:06	
Custody Seals Intact: Δ Yes Δ No		Custody Seal No		Cooler Temperature: °C and Other Remarks	

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-2571-1

Job ID: 705-2571-1

Eurofins Atlanta

Job Narrative 705-2571-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers and/or narrative comments are included to explain any exceptions, if applicable.

- Matrix QC may not be reported if insufficient sample is provided or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 7/24/2024 1:06 PM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 0.6°C.

Metals

Method 6010D - Dissolved: Insufficient sample volume was available to perform a matrix spike/matrix spike duplicate/sample duplicate (MS/MSD/DUP) associated with preparation batch 705-4898 and analytical batch 705-5015.

Method 6020B - Total Recoverable: The method blank for preparation batch 705-4891 and analytical batch 705-5104 contained Molybdenum above the method detection limit (MDL). Associated sample(s) were not re-extracted and/or re-analyzed because results were greater than 10X the value found in the method blank.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2571-1

Client Sample ID: HAM-PT-08-7-24-UNF-AM
Date Collected: 07/24/24 09:00
Date Received: 07/24/24 13:06

Lab Sample ID: 705-2571-1
Matrix: Water

Method: SW846 6010D - Metals (ICP)										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Boron	0.70		0.050	0.026	mg/L		07/24/24 14:40	07/25/24 11:27	1	

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Arsenic	0.30		0.0050	0.0013	mg/L		07/24/24 13:49	07/25/24 12:04	1	
Iron	21		0.10	0.018	mg/L		07/24/24 13:49	07/25/24 12:04	1	

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2571-1

Client Sample ID: HAM-PT-08-7-24-FIL-AM
Date Collected: 07/24/24 09:00
Date Received: 07/24/24 13:06

Lab Sample ID: 705-2571-2
Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.71		0.050	0.026	mg/L			07/24/24 19:30	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.26		0.0050	0.0013	mg/L			07/25/24 11:33	1
Iron, Dissolved	11		0.10	0.018	mg/L			07/25/24 11:33	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2571-1

Client Sample ID: HAM-PT-14-7-24-UNF-AM
Date Collected: 07/24/24 09:00
Date Received: 07/24/24 13:06

Lab Sample ID: 705-2571-3
Matrix: Water

Method: SW846 6010D - Metals (ICP)										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Boron	0.68		0.050	0.026	mg/L		07/24/24 14:40	07/25/24 11:49	1	

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Arsenic	0.21		0.0050	0.0013	mg/L		07/24/24 13:49	07/25/24 12:06	1	
Iron	87		1.0	0.18	mg/L		07/24/24 13:49	07/25/24 12:24	10	

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2571-1

Client Sample ID: HAM-PT-14-7-24-FIL-AM
Date Collected: 07/24/24 09:00
Date Received: 07/24/24 13:06

Lab Sample ID: 705-2571-4
Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.61		0.050	0.026	mg/L			07/24/24 19:33	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.051		0.0050	0.0013	mg/L			07/25/24 11:35	1
Iron, Dissolved	24		0.10	0.018	mg/L			07/25/24 11:35	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2571-1

Client Sample ID: HAM-PT-11-7-24-UNF-AM
Date Collected: 07/24/24 10:00
Date Received: 07/24/24 13:06

Lab Sample ID: 705-2571-5
Matrix: Water

Method: SW846 6010D - Metals (ICP)										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Boron	1.2		0.050	0.026	mg/L		07/24/24 14:40	07/25/24 11:52	1	

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Iron	4.9		0.040	0.018	mg/L		07/24/24 13:49	07/25/24 11:52	1	
Molybdenum	0.045	B	0.0050	0.00069	mg/L		07/24/24 13:49	07/25/24 11:52	1	

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2571-1

Client Sample ID: HAM-PT-11-7-24-FIL-AM
Date Collected: 07/24/24 10:00
Date Received: 07/24/24 13:06

Lab Sample ID: 705-2571-6
Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	1.2		0.050	0.026	mg/L			07/24/24 19:36	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron, Dissolved	3.6		0.040	0.018	mg/L			07/25/24 11:38	1
Molybdenum, Dissolved	0.037		0.0050	0.00069	mg/L			07/25/24 11:38	1

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2571-1

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-4894/1-A
Matrix: Water
Analysis Batch: 5076

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 4894

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	ND		0.050	0.026	mg/L		07/24/24 14:40	07/25/24 11:21	1

Lab Sample ID: LCS 705-4894/2-A
Matrix: Water
Analysis Batch: 5076

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 4894

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	1.00	1.03		mg/L		103	80 - 120

Lab Sample ID: 705-2571-1 MS
Matrix: Water
Analysis Batch: 5076

Client Sample ID: HAM-PT-08-7-24-UNF-AM
Prep Type: Total/NA
Prep Batch: 4894

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	0.70		1.00	1.69		mg/L		99	75 - 125

Lab Sample ID: 705-2571-1 MSD
Matrix: Water
Analysis Batch: 5076

Client Sample ID: HAM-PT-08-7-24-UNF-AM
Prep Type: Total/NA
Prep Batch: 4894

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron	0.70		1.00	1.71		mg/L		101	75 - 125	1	20

Lab Sample ID: MB 705-4898/1-A
Matrix: Water
Analysis Batch: 5015

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	ND		0.050	0.026	mg/L			07/24/24 19:14	1

Lab Sample ID: LCS 705-4898/2-A
Matrix: Water
Analysis Batch: 5015

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron, Dissolved	1.00	1.04		mg/L		104	80 - 120

Lab Sample ID: LCSD 705-4898/3-A
Matrix: Water
Analysis Batch: 5015

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron, Dissolved	1.00	1.03		mg/L		103	80 - 120	1	20

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2571-1

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-4891/1-A
Matrix: Water
Analysis Batch: 5104

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 4891

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Molybdenum	0.000965	J	0.0050	0.00069	mg/L		07/24/24 13:49	07/25/24 11:48	1
Arsenic	ND		0.0050	0.0013	mg/L		07/24/24 13:49	07/25/24 11:48	1
Iron	ND		0.040	0.018	mg/L		07/24/24 13:49	07/25/24 11:48	1

Lab Sample ID: LCS 705-4891/2-A
Matrix: Water
Analysis Batch: 5104

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 4891

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Molybdenum	0.100	0.119		mg/L		119	80 - 120
Arsenic	0.100	0.101		mg/L		101	80 - 120

Lab Sample ID: LCS 705-4891/2-A
Matrix: Water
Analysis Batch: 5104

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 4891

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Iron	1.00	1.18		mg/L		118	80 - 120

Lab Sample ID: 705-2571-5 MS
Matrix: Water
Analysis Batch: 5104

Client Sample ID: HAM-PT-11-7-24-UNF-AM
Prep Type: Total Recoverable
Prep Batch: 4891

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Molybdenum	0.045	B	0.100	0.153		mg/L		107	75 - 125
Arsenic	ND		0.100	0.0925		mg/L		92	75 - 125
Iron	4.9		1.00	5.86		mg/L		96	75 - 125

Lab Sample ID: 705-2571-5 MSD
Matrix: Water
Analysis Batch: 5104

Client Sample ID: HAM-PT-11-7-24-UNF-AM
Prep Type: Total Recoverable
Prep Batch: 4891

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Molybdenum	0.045	B	0.100	0.156		mg/L		110	75 - 125	2	20
Arsenic	ND		0.100	0.0919		mg/L		92	75 - 125	1	20
Iron	4.9		1.00	6.00		mg/L		110	75 - 125	2	20

Lab Sample ID: MB 705-4896/1-A
Matrix: Water
Analysis Batch: 5107

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Molybdenum, Dissolved	ND		0.0050	0.00069	mg/L			07/25/24 11:26	1
Arsenic, Dissolved	ND		0.0050	0.0013	mg/L			07/25/24 11:26	1
Iron, Dissolved	ND		0.10	0.018	mg/L			07/25/24 11:26	1

Eurofins Atlanta

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2571-1

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: LCS 705-4896/2-A
Matrix: Water
Analysis Batch: 5107

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Molybdenum, Dissolved	0.100	0.0976		mg/L		98	80 - 120
Arsenic, Dissolved	0.100	0.0896		mg/L		90	80 - 120
Iron, Dissolved	1.00	1.05		mg/L		105	80 - 120

Lab Sample ID: LCSD 705-4896/3-A
Matrix: Water
Analysis Batch: 5107

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Molybdenum, Dissolved	0.100	0.0989		mg/L		99	80 - 120	1	20
Arsenic, Dissolved	0.100	0.0912		mg/L		91	80 - 120	2	20
Iron, Dissolved	1.00	1.08		mg/L		108	80 - 120	2	20

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2571-1

Client Sample ID: HAM-PT-08-7-24-UNF-AM

Lab Sample ID: 705-2571-1

Date Collected: 07/24/24 09:00

Matrix: Water

Date Received: 07/24/24 13:06

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			4894	BR	EET ATL	07/24/24 14:40
Total/NA	Analysis	6010D		1	5076	DS	EET ATL	07/25/24 11:27
Total Recoverable	Prep	3005A			4891	BR	EET ATL	07/24/24 13:49
Total Recoverable	Analysis	6020B		1	5104	AD	EET ATL	07/25/24 12:04

Client Sample ID: HAM-PT-08-7-24-FIL-AM

Lab Sample ID: 705-2571-2

Date Collected: 07/24/24 09:00

Matrix: Water

Date Received: 07/24/24 13:06

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	5015	DS	EET ATL	07/24/24 19:30
Dissolved	Analysis	6020B		1	5107	AD	EET ATL	07/25/24 11:33

Client Sample ID: HAM-PT-14-7-24-UNF-AM

Lab Sample ID: 705-2571-3

Date Collected: 07/24/24 09:00

Matrix: Water

Date Received: 07/24/24 13:06

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			4894	BR	EET ATL	07/24/24 14:40
Total/NA	Analysis	6010D		1	5076	DS	EET ATL	07/25/24 11:49
Total Recoverable	Prep	3005A			4891	BR	EET ATL	07/24/24 13:49
Total Recoverable	Analysis	6020B		1	5104	AD	EET ATL	07/25/24 12:06
Total Recoverable	Prep	3005A			4891	BR	EET ATL	07/24/24 13:49
Total Recoverable	Analysis	6020B		10	5104	AD	EET ATL	07/25/24 12:24

Client Sample ID: HAM-PT-14-7-24-FIL-AM

Lab Sample ID: 705-2571-4

Date Collected: 07/24/24 09:00

Matrix: Water

Date Received: 07/24/24 13:06

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	5015	DS	EET ATL	07/24/24 19:33
Dissolved	Analysis	6020B		1	5107	AD	EET ATL	07/25/24 11:35

Client Sample ID: HAM-PT-11-7-24-UNF-AM

Lab Sample ID: 705-2571-5

Date Collected: 07/24/24 10:00

Matrix: Water

Date Received: 07/24/24 13:06

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			4894	BR	EET ATL	07/24/24 14:40
Total/NA	Analysis	6010D		1	5076	DS	EET ATL	07/25/24 11:52
Total Recoverable	Prep	3005A			4891	BR	EET ATL	07/24/24 13:49
Total Recoverable	Analysis	6020B		1	5104	AD	EET ATL	07/25/24 11:52

Eurofins Atlanta

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2571-1

Client Sample ID: HAM-PT-11-7-24-FIL-AM
Date Collected: 07/24/24 10:00
Date Received: 07/24/24 13:06

Lab Sample ID: 705-2571-6
Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	5015	DS	EET ATL	07/24/24 19:36
Dissolved	Analysis	6020B		1	5107	AD	EET ATL	07/25/24 11:38

Laboratory References:
EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2571-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

1
2
3
4
5
6
7
8
9
10
11
12
13

Method Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2571-1

Method	Method Description	Protocol	Laboratory
6010D	Metals (ICP)	SW846	EET ATL
6020B	Metals (ICP/MS)	SW846	EET ATL
3005A	Preparation, Total Recoverable or Dissolved Metals	SW846	EET ATL
3010A	Preparation, Total Metals	SW846	EET ATL

Protocol References:

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Sample Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2571-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-2571-1	HAM-PT-08-7-24-UNF-AM	Water	07/24/24 09:00	07/24/24 13:06
705-2571-2	HAM-PT-08-7-24-FIL-AM	Water	07/24/24 09:00	07/24/24 13:06
705-2571-3	HAM-PT-14-7-24-UNF-AM	Water	07/24/24 09:00	07/24/24 13:06
705-2571-4	HAM-PT-14-7-24-FIL-AM	Water	07/24/24 09:00	07/24/24 13:06
705-2571-5	HAM-PT-11-7-24-UNF-AM	Water	07/24/24 10:00	07/24/24 13:06
705-2571-6	HAM-PT-11-7-24-FIL-AM	Water	07/24/24 10:00	07/24/24 13:06

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-2571-1

Login Number: 2571

List Number: 1

Creator: Bellinger, Arabia

List Source: Eurofins Atlanta

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	N/A	
Sample custody seals, if present, are intact.	N/A	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	N/A	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	N/A	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT

ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 7/26/2024 3:32:49 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-2662-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
7/26/2024 3:32:49 PM



Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	15
Lab Chronicle	18
Certification Summary	20
Method Summary	21
Sample Summary	22
Receipt Checklists	23
End Of Report	24

Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2662-1

Qualifiers

Metals

Qualifier	Qualifier Description
4	MS, MSD: The analyte present in the original sample is greater than 4 times the matrix spike concentration; therefore, control limits are not applicable.
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
V	Serial Dilution exceeds the control limits

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Chain of Custody Record

Client Information		Lab PM: David Fuller / Phone: 770-344-8886		Carrier Tracking No(s)		COC No:	
Client Contact: Kip Gray		E-Mail: David Fuller@eurofins.com		State of Origin: GA		Page: Page 1 of 1	
Company: Geosyntec Consultants Inc		Address: 1255 Roberts Blvd, NW Suite 200		City: Kennesaw		State: GA	
Phone: 770-30144		Lab Project #: 70500911 (DO NOT REMOVE)		PO #:		Preservation Codes: G - HMO	
Email: Kip.Gray@Geosyntec.com		Project Name: Plant Hammond		Task Code: SSOW		Other:	
Due Date Requested:		FAT Requested (days): RUSH / 1 Day FAT		Compliance Project: A Yes A No		Analysis Requested:	
Sample Date		Sample Time		Sample Type (C=Comp, Grab)		Matrix (V=Vials, B=Bag, D=Drum, A=Air)	
Sample Identification		Sample Date		Sample Time		Sample Type (C=Comp, Grab)	
HAM-PT-14-07-24 - UNF - PM		7-24-2024		2000		705	
HAM-PT-14-07-24 - FIL - PM		7-24-2024		2000		705	
HAM-PT-08-07-24 - UNF - PM		7-24-2024		2000		705	
HAM-PT-08-07-24 - FIL - PM		7-24-2024		2000		705	
HAM-PT-13-07-24 - UNF - PM		7-24-2024		2000		705	
HAM-PT-13-07-24 - FIL - PM		7-24-2024		2000		705	
HAM-PT-15-07-24 - UNF - PM		7-24-2024		2000		705	
HAM-PT-15-07-24 - FIL - PM		7-24-2024		2000		705	
Possible Hazard Identification		Non-Hazard		Flammable		Skin Irritant	
Deliverable Requested I, II, III, IV, Other (specify)		Unknown		Radiological		Special Instructions/QC Requirements	
Empty Kit Relinquished by		Date		Time		Method of Shipment	
Relinquished by: [Signature]		7/11/2024		7:25		Company: Eurofins	
Relinquished by: [Signature]		7-25-24		7:25		Company: Eurofins	
Relinquished by: [Signature]		7-25-24		7:25		Company: Eurofins	
Custody Seals Intact: A Yes A No		Custody Seal No		Custody Seal No		Custody Seal No	

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-2662-1

Job ID: 705-2662-1

Eurofins Atlanta

Job Narrative 705-2662-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers and/or narrative comments are included to explain any exceptions, if applicable.

- Matrix QC may not be reported if insufficient sample is provided or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 7/25/2024 9:05 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 1.9°C.

Metals

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2662-1

Client Sample ID: HAM-PT-14-07-24-UNF-PM
Date Collected: 07/24/24 20:00
Date Received: 07/25/24 09:05

Lab Sample ID: 705-2662-1
Matrix: Water

Method: SW846 6010D - Metals (ICP)										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Boron	0.53		0.040	0.026	mg/L		07/25/24 10:28	07/25/24 15:22	1	

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Arsenic	0.21		0.0050	0.0013	mg/L		07/25/24 10:33	07/25/24 17:17	1	
Iron	250		0.40	0.18	mg/L		07/25/24 10:33	07/25/24 17:05	10	

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2662-1

Client Sample ID: HAM-PT-14-07-24-FIL-PM
Date Collected: 07/24/24 20:00
Date Received: 07/25/24 09:05

Lab Sample ID: 705-2662-2
Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.37		0.040	0.026	mg/L			07/25/24 12:26	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.0043	J	0.0050	0.0013	mg/L			07/25/24 14:38	1
Iron, Dissolved	71		0.40	0.18	mg/L			07/25/24 16:10	10

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2662-1

Client Sample ID: HAM-PT-08-07-24-UNF-PM
Date Collected: 07/24/24 20:00
Date Received: 07/25/24 09:05

Lab Sample ID: 705-2662-3
Matrix: Water

Method: SW846 6010D - Metals (ICP)										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Boron	0.63		0.040	0.026	mg/L		07/25/24 10:28	07/25/24 15:26	1	

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Arsenic	0.31		0.0050	0.0013	mg/L		07/25/24 10:33	07/25/24 17:07	1	
Iron	23		0.040	0.018	mg/L		07/25/24 10:33	07/25/24 17:07	1	

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2662-1

Client Sample ID: HAM-PT-08-07-24-FIL-PM
Date Collected: 07/24/24 20:00
Date Received: 07/25/24 09:05

Lab Sample ID: 705-2662-4
Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.63		0.040	0.026	mg/L			07/25/24 12:29	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.25		0.0050	0.0013	mg/L			07/25/24 14:40	1
Iron, Dissolved	9.3		0.040	0.018	mg/L			07/25/24 14:40	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2662-1

Client Sample ID: HAM-PT-13-07-24-UNF-PM
Date Collected: 07/24/24 20:00
Date Received: 07/25/24 09:05

Lab Sample ID: 705-2662-5
Matrix: Water

Method: SW846 6010D - Metals (ICP)										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Boron	0.39		0.040	0.026	mg/L		07/25/24 10:28	07/25/24 15:29	1	

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Arsenic	0.20		0.0050	0.0013	mg/L		07/25/24 10:33	07/25/24 17:09	1	
Iron	66		0.40	0.18	mg/L		07/25/24 10:33	07/25/24 17:29	10	

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2662-1

Client Sample ID: HAM-PT-13-07-24-FIL-PM
Date Collected: 07/24/24 20:00
Date Received: 07/25/24 09:05

Lab Sample ID: 705-2662-6
Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.39		0.040	0.026	mg/L			07/25/24 12:32	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.15		0.0050	0.0013	mg/L			07/25/24 14:42	1
Iron, Dissolved	51		0.40	0.18	mg/L			07/25/24 17:31	10

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2662-1

Client Sample ID: HAM-PT-15-07-24-UNF-PM
Date Collected: 07/24/24 20:00
Date Received: 07/25/24 09:05

Lab Sample ID: 705-2662-7
Matrix: Water

Method: SW846 6010D - Metals (ICP)										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Boron	0.65		0.040	0.026	mg/L		07/25/24 10:28	07/25/24 15:32	1	

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Arsenic	0.33		0.025	0.0066	mg/L		07/25/24 10:33	07/25/24 17:15	5	
Iron	13		0.20	0.089	mg/L		07/25/24 10:33	07/25/24 17:15	5	

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2662-1

Client Sample ID: HAM-PT-15-07-24-FIL-PM
Date Collected: 07/24/24 20:00
Date Received: 07/25/24 09:05

Lab Sample ID: 705-2662-8
Matrix: Water

Method: SW846 6010D - Metals (ICP) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	0.64		0.040	0.026	mg/L			07/25/24 12:35	1

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.36		0.025	0.0066	mg/L			07/25/24 16:28	5
Iron, Dissolved	12		0.20	0.089	mg/L			07/25/24 16:28	5

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2662-1

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-4894/1-A
Matrix: Water
Analysis Batch: 5076

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 4894

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	ND		0.040	0.026	mg/L		07/24/24 14:40	07/25/24 11:21	1

Lab Sample ID: LCS 705-4894/2-A
Matrix: Water
Analysis Batch: 5076

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 4894

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	1.00	1.03		mg/L		103	80 - 120

Lab Sample ID: 705-2571-A-1-C MS
Matrix: Water
Analysis Batch: 5076

Client Sample ID: Matrix Spike
Prep Type: Total/NA
Prep Batch: 4894

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	0.70		1.00	1.69		mg/L		99	75 - 125

Lab Sample ID: 705-2571-A-1-D MSD
Matrix: Water
Analysis Batch: 5076

Client Sample ID: Matrix Spike Duplicate
Prep Type: Total/NA
Prep Batch: 4894

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron	0.70		1.00	1.71		mg/L		101	75 - 125	1	20

Lab Sample ID: MB 705-4898/1-A
Matrix: Water
Analysis Batch: 5015

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	ND		0.040	0.026	mg/L			07/24/24 19:14	1

Lab Sample ID: LCS 705-4898/2-A
Matrix: Water
Analysis Batch: 5015

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron, Dissolved	1.00	1.04		mg/L		104	80 - 120

Lab Sample ID: LCSD 705-4898/3-A
Matrix: Water
Analysis Batch: 5015

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron, Dissolved	1.00	1.03		mg/L		103	80 - 120	1	20

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2662-1

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-4891/1-A
Matrix: Water
Analysis Batch: 5104

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 4891

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	ND		0.0050	0.0013	mg/L		07/24/24 13:49	07/25/24 11:48	1
Iron	ND		0.040	0.018	mg/L		07/24/24 13:49	07/25/24 11:48	1

Lab Sample ID: LCS 705-4891/2-A
Matrix: Water
Analysis Batch: 5104

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 4891

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.100	0.101		mg/L		101	80 - 120

Lab Sample ID: LCS 705-4891/2-A
Matrix: Water
Analysis Batch: 5104

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 4891

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Iron	1.00	1.18		mg/L		118	80 - 120

Lab Sample ID: 705-2571-A-5-B MS
Matrix: Water
Analysis Batch: 5104

Client Sample ID: Matrix Spike
Prep Type: Total Recoverable
Prep Batch: 4891

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	ND		0.100	0.0925		mg/L		92	75 - 125
Iron	4.9		1.00	5.86	4	mg/L		96	75 - 125

Lab Sample ID: 705-2571-A-5-C MSD
Matrix: Water
Analysis Batch: 5104

Client Sample ID: Matrix Spike Duplicate
Prep Type: Total Recoverable
Prep Batch: 4891

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic	ND		0.100	0.0919		mg/L		92	75 - 125	1	20
Iron	4.9		1.00	6.00	4	mg/L		110	75 - 125	2	20

Lab Sample ID: MB 705-4896/1-A
Matrix: Water
Analysis Batch: 5107

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	ND		0.0050	0.0013	mg/L			07/25/24 11:26	1
Iron, Dissolved	ND		0.040	0.018	mg/L			07/25/24 11:26	1

Lab Sample ID: LCS 705-4896/2-A
Matrix: Water
Analysis Batch: 5107

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic, Dissolved	0.100	0.0896		mg/L		90	80 - 120
Iron, Dissolved	1.00	1.05		mg/L		105	80 - 120

Eurofins Atlanta

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2662-1

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: LCSD 705-4896/3-A				Client Sample ID: Lab Control Sample Dup							
Matrix: Water				Prep Type: Dissolved							
Analysis Batch: 5107											
Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit		
Arsenic, Dissolved	0.100	0.0912		mg/L		91	80 - 120	2	20		
Iron, Dissolved	1.00	1.08		mg/L		108	80 - 120	2	20		

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2662-1

Client Sample ID: HAM-PT-14-07-24-UNF-PM

Lab Sample ID: 705-2662-1

Date Collected: 07/24/24 20:00

Matrix: Water

Date Received: 07/25/24 09:05

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			4894	BR	EET ATL	07/25/24 10:28
Total/NA	Analysis	6010D		1	5139	DS	EET ATL	07/25/24 15:22
Total Recoverable	Prep	3005A			4891	BR	EET ATL	07/25/24 10:33
Total Recoverable	Analysis	6020B		10	5174	AD	EET ATL	07/25/24 17:05
Total Recoverable	Prep	3005A			4891	BR	EET ATL	07/25/24 10:33
Total Recoverable	Analysis	6020B		1	5174	AD	EET ATL	07/25/24 17:17

Client Sample ID: HAM-PT-14-07-24-FIL-PM

Lab Sample ID: 705-2662-2

Date Collected: 07/24/24 20:00

Matrix: Water

Date Received: 07/25/24 09:05

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	5094	DS	EET ATL	07/25/24 12:26
Dissolved	Analysis	6020B		1	5173	AD	EET ATL	07/25/24 14:38
Dissolved	Analysis	6020B		10	5173	AD	EET ATL	07/25/24 16:10

Client Sample ID: HAM-PT-08-07-24-UNF-PM

Lab Sample ID: 705-2662-3

Date Collected: 07/24/24 20:00

Matrix: Water

Date Received: 07/25/24 09:05

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			4894	BR	EET ATL	07/25/24 10:28
Total/NA	Analysis	6010D		1	5139	DS	EET ATL	07/25/24 15:26
Total Recoverable	Prep	3005A			4891	BR	EET ATL	07/25/24 10:33
Total Recoverable	Analysis	6020B		1	5174	AD	EET ATL	07/25/24 17:07

Client Sample ID: HAM-PT-08-07-24-FIL-PM

Lab Sample ID: 705-2662-4

Date Collected: 07/24/24 20:00

Matrix: Water

Date Received: 07/25/24 09:05

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	5094	DS	EET ATL	07/25/24 12:29
Dissolved	Analysis	6020B		1	5173	AD	EET ATL	07/25/24 14:40

Client Sample ID: HAM-PT-13-07-24-UNF-PM

Lab Sample ID: 705-2662-5

Date Collected: 07/24/24 20:00

Matrix: Water

Date Received: 07/25/24 09:05

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			4894	BR	EET ATL	07/25/24 10:28
Total/NA	Analysis	6010D		1	5139	DS	EET ATL	07/25/24 15:29
Total Recoverable	Prep	3005A			4891	BR	EET ATL	07/25/24 10:33
Total Recoverable	Analysis	6020B		1	5174	AD	EET ATL	07/25/24 17:09
Total Recoverable	Prep	3005A			4891	BR	EET ATL	07/25/24 10:33
Total Recoverable	Analysis	6020B		10	5174	AD	EET ATL	07/25/24 17:29

Eurofins Atlanta

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2662-1

Client Sample ID: HAM-PT-13-07-24-FIL-PM

Lab Sample ID: 705-2662-6

Date Collected: 07/24/24 20:00

Matrix: Water

Date Received: 07/25/24 09:05

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	5094	DS	EET ATL	07/25/24 12:32
Dissolved	Analysis	6020B		1	5173	AD	EET ATL	07/25/24 14:42
Dissolved	Analysis	6020B		10	5173	AD	EET ATL	07/25/24 17:31

Client Sample ID: HAM-PT-15-07-24-UNF-PM

Lab Sample ID: 705-2662-7

Date Collected: 07/24/24 20:00

Matrix: Water

Date Received: 07/25/24 09:05

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			4894	BR	EET ATL	07/25/24 10:28
Total/NA	Analysis	6010D		1	5139	DS	EET ATL	07/25/24 15:32
Total Recoverable	Prep	3005A			4891	BR	EET ATL	07/25/24 10:33
Total Recoverable	Analysis	6020B		5	5174	AD	EET ATL	07/25/24 17:15

Client Sample ID: HAM-PT-15-07-24-FIL-PM

Lab Sample ID: 705-2662-8

Date Collected: 07/24/24 20:00

Matrix: Water

Date Received: 07/25/24 09:05

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6010D		1	5094	DS	EET ATL	07/25/24 12:35
Dissolved	Analysis	6020B		5	5173	AD	EET ATL	07/25/24 16:28

Laboratory References:

EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2662-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

1
2
3
4
5
6
7
8
9
10
11
12
13

Method Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2662-1

Method	Method Description	Protocol	Laboratory
6010D	Metals (ICP)	SW846	EET ATL
6020B	Metals (ICP/MS)	SW846	EET ATL
3005A	Preparation, Total Recoverable or Dissolved Metals	SW846	EET ATL
3010A	Preparation, Total Metals	SW846	EET ATL

Protocol References:

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Sample Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2662-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-2662-1	HAM-PT-14-07-24-UNF-PM	Water	07/24/24 20:00	07/25/24 09:05
705-2662-2	HAM-PT-14-07-24-FIL-PM	Water	07/24/24 20:00	07/25/24 09:05
705-2662-3	HAM-PT-08-07-24-UNF-PM	Water	07/24/24 20:00	07/25/24 09:05
705-2662-4	HAM-PT-08-07-24-FIL-PM	Water	07/24/24 20:00	07/25/24 09:05
705-2662-5	HAM-PT-13-07-24-UNF-PM	Water	07/24/24 20:00	07/25/24 09:05
705-2662-6	HAM-PT-13-07-24-FIL-PM	Water	07/24/24 20:00	07/25/24 09:05
705-2662-7	HAM-PT-15-07-24-UNF-PM	Water	07/24/24 20:00	07/25/24 09:05
705-2662-8	HAM-PT-15-07-24-FIL-PM	Water	07/24/24 20:00	07/25/24 09:05



Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-2662-1

Login Number: 2662

List Number: 1

Creator: Pomuti, Carmen

List Source: Eurofins Atlanta

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	N/A	Not present
Sample custody seals, if present, are intact.	N/A	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	N/A	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	N/A	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT



ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 7/30/2024 12:51:25 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-2786-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
7/30/2024 12:51:25 PM

Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	12
Lab Chronicle	14
Certification Summary	15
Method Summary	16
Sample Summary	17
Receipt Checklists	18
End Of Report	19



Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2786-1

Qualifiers

Metals

Qualifier	Qualifier Description
4	MS, MSD: The analyte present in the original sample is greater than 4 times the matrix spike concentration; therefore, control limits are not applicable.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Environment Testing

[illegible]

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-2786-1

Job ID: 705-2786-1

Eurofins Atlanta

Job Narrative 705-2786-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers and/or narrative comments are included to explain any exceptions, if applicable.

- Matrix QC may not be reported if insufficient sample is provided or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 7/2 /2024 8:50 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 2.9°C.

Metals

Method 020 - Total recoverable: The matrix spike / matrix spike duplicate (MS/MSD) Iron recoveries for the following sample associated with preparation batch 705-5244 and analytical batch 705-55 1 were outside control limits: AM-PT-14-07-25-UN (705-278 -1), AM-PT-1 -07-25-UN (705-278 -), AM-PT-15-07-25-UN (705-278 -4) and AM-PT-08-07-25-UN (705-278 -5). The associated laboratory control sample (LCS) recovery met acceptance criteria.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1739-2

Client Sample ID: MPT -34-AF-07-15-r x W

Lab Sample ID: 705-178H-A

Date C/ Ile2tev: 0791591F AF:F0

T atdc: d ateo

Date Re2eihev: 0791H91F 08:50

T et6/ v: Sd 8FH H0A0D - T etals (IC3)

Pnalyte	Result	Uualioeo	RL	T DL	r nit	D	3œpœœv	Pnalyzev	Dil W&2
f / d' n	0.H0		0.040	0.019	m6/g		07/19/14 22:11	07/19/14 25:L3	2

T et6/ v: Sd 8FH H010f - T etals (IC39 S) - 4/ tal Re2/ heœœble

Pnalyte	Result	Uualioeo	RL	T DL	r nit	D	3œpœœv	Pnalyzev	Dil W&2
Pœœni2	0.10		0.050	0.02L	m6/g		07/19/14 22:25	07/18/14 24:27	20
ld' n	AB0		0.40	0.23	m6/g		07/19/14 22:25	07/18/14 24:27	20

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1739-2

Client Sample ID: MPT -34-AF-07-15-WL

Lab Sample ID: 705-178H-1

Date C/ Ile2tev: 07/15/14 AF:F0

T atdc: d ateo

Date Re2eihev: 07/15/14 08:50

T et6/ v: Sd 8FH0A0D - T etals (IC3) - Diss/ lhev

Pnalyte	Result	Uualieo	RL	T DL	r nit	D	3æpæv	Pnalyzev	Dil W&2
f / d' n, Diss/ lhev	0.58		0.040	0.019	m6/g			07/19/14 25:02	2

T et6/ v: Sd 8FH010f - T etals (IC39 S) - Diss/ lhev

Pnalyte	Result	Uualieo	RL	T DL	r nit	D	3æpæv	Pnalyzev	Dil W&2
Pæeni2, Diss/ lhev	0.05H		0.015	0.0099	m6/g			07/19/14 23:L5	5
ld' n, Diss/ lhev	18		0.40	0.23	m6/g			07/18/14 24:18	20

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1739-2

Client Sample ID: MPT -34-AB-07-15-r x W

Lab Sample ID: 705-178HB

Date C/ Ile2tev: 07/15/14 05:10

T atdc: d ateo

Date Re2eihev: 07/15/14 08:50

T et6/ v: Sd 8FH H0A0D - T etals (IC3)

Pnalyte	Result	Uualioeo	RL	T DL	r nit	D	3œpœœv	Pnalyzev	Dil W&2
f / d' n	0.55		0.040	0.019	m6/g		07/19/14 22:11	07/19/14 25:10	2

T et6/ v: Sd 8FH H010f - T etals (IC39 S) - 4/ tal Re2/ heœœble

Pnalyte	Result	Uualioeo	RL	T DL	r nit	D	3œpœœv	Pnalyzev	Dil W&2
Pœœni2	0.60		0.0050	0.002L	m6/g		07/19/14 22:25	07/18/14 24:12	2
ld' n	B6		0.040	0.023	m6/g		07/19/14 22:25	07/18/14 24:12	2

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1739-2

Client Sample ID: MPT -34-A5-07-15-r x W

Lab Sample ID: 705-178HF

Date C/ Ile2tev: 0791591F AHF0

T atdc: d ateo

Date Re2eihev: 0791H91F 08:50

T et6/ v: Sd 8FH H0A0D - T etals (IC3)

Pnalyte	Result	Uualioeo	RL	T DL	r nit	D	3œpæœv	Pnalyzev	Dil V&2
f / d' n	0.FN		0.040	0.019	m6/g		07/19/14 22:11	07/19/14 25:42	2

T et6/ v: Sd 8FH H010f - T etals (IC39 S) - 4/ tal Re2/ heœable

Pnalyte	Result	Uualioeo	RL	T DL	r nit	D	3œpæœv	Pnalyzev	Dil V&2
Pœeni2	0.F8		0.0050	0.002L	m6/g		07/19/14 22:25	07/18/14 24:15	2
ld' n	A8		0.040	0.023	m6/g		07/19/14 22:25	07/18/14 24:15	2

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1739-2

Client Sample ID: MPT -34-08-07-15-r x W

Lab Sample ID: 705-178H-5

Date C/ Ile2tev: 07/15/14 14:50

T atdc: d ateo

Date Re2eihev: 07/15/14 08:50

T et6/ v: Sd 8FH H0A0D - T etals (IC3)

Pnalyte	Result	Uualioeo	RL	T DL	r nit	D	3œpœœv	Pnalyzev	Dil W&2
f / d' n	0.17		0.040	0.019	m6/g		07/19/14 22:11	07/19/14 25:44	2

T et6/ v: Sd 8FH H010f - T etals (IC39 S) - 4/ tal Re2/ heœœble

Pnalyte	Result	Uualioeo	RL	T DL	r nit	D	3œpœœv	Pnalyzev	Dil W&2
Pœœni2	0.15		0.0050	0.002L	m6/g		07/19/14 22:25	07/18/14 24:05	2
ld' n	A7		0.040	0.023	m6/g		07/19/14 22:25	07/18/14 24:05	2

QC Sample Results

i a G y t o c u G t a i o G c P a r G c I G a
j / o S a s h n t : j e G s d r B B o G N

Job ID: 705-178C-I

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-53/ 7A-r
MatxiW T atex
r nalNsis Bat8h: 5F36

Client Sample ID: Method Blank
Pæp yNpe: yotalA r
Pæp Bat8h: 53/ 7

r nalNte	MB Result	MB Qualizex	RL	MDL f nit	D	Pæpaxed	r nalNled	Dil za8
. o/oG	4 D		02060	0201C B gHL		07HQ46 I I :11	07HQ46 I 5:08	I

Lab Sample ID: LCS 705-53/ 7A-r
MatxiW T atex
r nalNsis Bat8h: 5F36

Client Sample ID: Lab Contxol Sample
Pæp yNpe: yotalA r
Pæp Bat8h: 53/ 7

r nalNte	Spike r dded	LCS Result	LCS Qualizex	f nit	D	%Re8	%Re8 Limits
. o/oG	I 20	I 20,		B gHL		I 0,	80 - I 10

Lab Sample ID: 705-3796-F MS
MatxiW T atex
r nalNsis Bat8h: 5F36

Client Sample ID: Hr M-Py-1F-07-35-f cz
Pæp yNpe: yotalA r
Pæp Bat8h: 53/ 7

r nalNte	Sample Result	Sample Qualizex	Spike r dded	MS Result	MS Qualizex	f nit	D	%Re8	%Re8 Limits
. o/oG	0255		I 20	I 2C1		B gHL		I 07	75 - I 15

Lab Sample ID: 705-3796-F MSD
MatxiW T atex
r nalNsis Bat8h: 5F36

Client Sample ID: Hr M-Py-1F-07-35-f cz
Pæp yNpe: yotalA r
Pæp Bat8h: 53/ 7

r nalNte	Sample Result	Sample Qualizex	Spike r dded	MSD Result	MSD Qualizex	f nit	D	%Re8	%Re8 Limits	RPD	RPD Limit
. o/oG	0255		I 20	I 206		B gHL		I 0v	75 - I 15	I	10

Lab Sample ID: MB 705-5397A-r
MatxiW T atex
r nalNsis Bat8h: 5F14

Client Sample ID: Method Blank
Pæp yNpe: Dissolved

r nalNte	MB Result	MB Qualizex	RL	MDL f nit	D	Pæpaxed	r nalNled	Dil za8
. o/oG3Dreco0t N	4 D		02060	0201C B gHL			07HQ46 I 6:51	I

Lab Sample ID: LCS 705-5397A-r
MatxiW T atex
r nalNsis Bat8h: 5F14

Client Sample ID: Lab Contxol Sample
Pæp yNpe: Dissolved

r nalNte	Spike r dded	LCS Result	LCS Qualizex	f nit	D	%Re8	%Re8 Limits
. o/oG3Dreco0t N	I 20	I 206		B gHL		I 06	80 - I 10

Lab Sample ID: LCSD 705-5397A-r
MatxiW T atex
r nalNsis Bat8h: 5F14

Client Sample ID: Lab Contxol Sample Dup
Pæp yNpe: Dissolved

r nalNte	Spike r dded	LCSD Result	LCSD Qualizex	f nit	D	%Re8	%Re8 Limits	RPD	RPD Limit
. o/oG3Dreco0t N	I 20	I 201		B gHL		I 01	80 - I 10	1	10

EP/ofrGc Ass Gr

QC Sample Results

i a G y t o c u G t a i o G P e G c I G a
j / o S a s h n t : j e G d r B B o G N

Job ID: 705-178C-I

Method: 6030B - Metals (ICP/MS)

Lab Sample ID: MB 705-53/ / A-r
Matix W T atex
r nalNsis Bat8h: 5561

Client Sample ID: Method Blank
P x e p y N p e: y o t a l R e 8 o v e x a b l e
P x e p Bat8h: 53/ /

r nalNte	MB Result	MB Qualizex	RL	MDL f nit	D	P x e p a x e d	r nalNted	Dil za8
A/ct Ga	4 D		02050	0201 , B gHL		07HCH6 I I : 5	07HvH6 I , :57	I
I/oG	4 D		02060	0201 8 B gHL		07HCH6 I I : 5	07HvH6 I , :57	I

Lab Sample ID: LCS 705-53/ / A-r
Matix W T atex
r nalNsis Bat8h: 5561

Client Sample ID: Lab Control Sample
P x e p y N p e: y o t a l R e 8 o v e x a b l e
P x e p Bat8h: 53/ /

r nalNte	Spike r dded	LCS Result	LCS Qualizex	f nit	D	%Re8	%Re8 Limits
A/ct Ga	02 00	02 01		B gHL		1 01	80 - 1 10
I/oG	1 20	1 20C		B gHL		1 0C	80 - 1 10

Lab Sample ID: 705-3796-5 MS
Matix W T atex
r nalNsis Bat8h: 5561

Client Sample ID: Hr M-Py-09-07-35-f c z
P x e p y N p e: y o t a l R e 8 o v e x a b l e
P x e p Bat8h: 53/ /

r nalNte	Sample Result	Sample Qualizex	Spike r dded	MS Result	MS Qualizex	f nit	D	%Re8	%Re8 Limits
A/ct Ga	02 5		02 00	02, 8		B gHL		88	75 - 1 15
I/oG	1 7		1 20	1 C2 6		B gHL		-1 ,	75 - 1 15

Lab Sample ID: 705-3796-5 MSD
Matix W T atex
r nalNsis Bat8h: 5561

Client Sample ID: Hr M-Py-09-07-35-f c z
P x e p y N p e: y o t a l R e 8 o v e x a b l e
P x e p Bat8h: 53/ /

r nalNte	Sample Result	Sample Qualizex	Spike r dded	MSD Result	MSD Qualizex	f nit	D	%Re8	%Re8 Limits	RPD	RPD Limit
A/ct Ga	02 5		02 00	02, 0		B gHL		80	75 - 1 15	1	10
I/oG	1 7		1 20	1 C2 6		B gHL		-8	75 - 1 15	0	10

Lab Sample ID: MB 705-534/ / A-r
Matix W T atex
r nalNsis Bat8h: 5/ 53

Client Sample ID: Method Blank
P x e p y N p e: D i s s o l v e d

r nalNte	MB Result	MB Qualizex	RL	MDL f nit	D	P x e p a x e d	r nalNted	Dil za8
A/ct Ga3Drecoet N	4 D		02050	0201 , B gHL			07HCH6 I 8:I v	I
I/oG3Drecoet N	4 D		02060	0201 8 B gHL			07HCH6 I 8:I v	I

Lab Sample ID: LCS 705-534/ / A-r
Matix W T atex
r nalNsis Bat8h: 5/ 53

Client Sample ID: Lab Control Sample
P x e p y N p e: D i s s o l v e d

r nalNte	Spike r dded	LCS Result	LCS Qualizex	f nit	D	%Re8	%Re8 Limits
A/ct Ga3Drecoet N	02 00	0208v,		B gHL		8v	80 - 1 10
I/oG3Drecoet N	1 20	02C1		B gHL		8C	80 - 1 10

Lab Sample ID: LCSD 705-534/ / A-r
Matix W T atex
r nalNsis Bat8h: 5/ 53

Client Sample ID: Lab Control Sample Dup
P x e p y N p e: D i s s o l v e d

r nalNte	Spike r dded	LCSD Result	LCSD Qualizex	f nit	D	%Re8	%Re8 Limits	RPD	RPD Limit
A/ct Ga3Drecoet N	02 00	02081 7		B gHL		81	80 - 1 10	v	10
I/oG3Drecoet N	1 20	0258		B gHL		8C	80 - 1 10	I	10

EP/ofrGc Ass Gr

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1739-2

Client Sample ID: HAM-PT-14-07-25-UNF

Date Collected: 07/25/24 14:40

Date Received: 07/26/24 08:50

Lab Sample ID: 705-2786-1

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
votal/p B	PreA	6020B			51L7	ET	EEv Bv4	07/19/1L 22:11
votal/p B	Banalysis	9020D		2	5619	DBN	EEv Bv4	07/19/1L 25:63
votal RecoFerale	PreA	6005B			51LL	N4	EEv Bv4	07/19/1L 22:25
votal RecoFerale	Banalysis	9010N		20	5592	IT	EEv Bv4	07/1f /1L 2L:27

Client Sample ID: HAM-PT-14-07-25-FIL

Date Collected: 07/25/24 14:40

Date Received: 07/26/24 08:50

Lab Sample ID: 705-2786-2

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
DissolFed	Banalysis	9020D		2	562f	DS	EEv Bv4	07/19/1L 25:02
DissolFed	Banalysis	9010N		5	5L51	IT	EEv Bv4	07/19/1L 23:65
DissolFed	Banalysis	9010N		20	5592	IT	EEv Bv4	07/1f /1L 2L:1f

Client Sample ID: HAM-PT-13-07-25-UNF

Date Collected: 07/25/24 15:20

Date Received: 07/26/24 08:50

Lab Sample ID: 705-2786-3

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
votal/p B	PreA	6020B			51L7	ET	EEv Bv4	07/19/1L 22:11
votal/p B	Banalysis	9020D		2	5619	DBN	EEv Bv4	07/19/1L 25:10
votal RecoFerale	PreA	6005B			51LL	N4	EEv Bv4	07/19/1L 22:25
votal RecoFerale	Banalysis	9010N		2	5592	IT	EEv Bv4	07/1f /1L 2L:12

Client Sample ID: HAM-PT-15-07-25-UNF

Date Collected: 07/25/24 16:40

Date Received: 07/26/24 08:50

Lab Sample ID: 705-2786-4

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
votal/p B	PreA	6020B			51L7	ET	EEv Bv4	07/19/1L 22:11
votal/p B	Banalysis	9020D		2	5619	DBN	EEv Bv4	07/19/1L 25:L2
votal RecoFerale	PreA	6005B			51LL	N4	EEv Bv4	07/19/1L 22:25
votal RecoFerale	Banalysis	9010N		2	5592	IT	EEv Bv4	07/1f /1L 2L:15

Client Sample ID: HAM-PT-08-07-25-UNF

Date Collected: 07/25/24 16:50

Date Received: 07/26/24 08:50

Lab Sample ID: 705-2786-5

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
votal/p B	PreA	6020B			51L7	ET	EEv Bv4	07/19/1L 22:11
votal/p B	Banalysis	9020D		2	5619	DBN	EEv Bv4	07/19/1L 25:LL
votal RecoFerale	PreA	6005B			51LL	N4	EEv Bv4	07/19/1L 22:25
votal RecoFerale	Banalysis	9010N		2	5592	IT	EEv Bv4	07/1f /1L 2L:05

Laboratory References:

EEv Bv4 8 Euro-ins Btlanta, 6030 Presidential Dr, Btlanta, GB 606L0, vE4 (770)L57-3277

Euro-ins Btlanta

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2786-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

1
2
3
4
5
6
7
8
9
10
11
12
13

Method Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1739-2

Method	Method Description	Protocol	Laboratory
9020D	4 etals 6CPM	SW389	(() E) T
9010A	4 etals 6CP/4 SM	SW389	(() E) T
L005E	PreBarationp)otal , ecoPerable or DissolFed 4 etals	SW389	(() E) T
L020E	PreBarationp)otal 4 etals	SW389	(() E) T

Protocol References:

SW389 v 3 est 4 et" ods hor (Baluatinf Solid WastepP" ytical/C" emical 4 et" ods-p) " ird (ditionpg oFember 2N39 End Its UBdates.

Laboratory References:

(() E) T v (urofins EtlantapL030 Presidential DrpEtlantapGE L0L80p) (T 6770N857-3277

Sample Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2786-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-2786-1	HAM-PT-14-07-25-UNF	Water	07/25/24 14:40	07/26/24 08:50
705-2786-2	HAM-PT-14-07-25-FIL	Water	07/25/24 14:40	07/26/24 08:50
705-2786-3	HAM-PT-13-07-25-UNF	Water	07/25/24 15:20	07/26/24 08:50
705-2786-4	HAM-PT-15-07-25-UNF	Water	07/25/24 16:40	07/26/24 08:50
705-2786-5	HAM-PT-08-07-25-UNF	Water	07/25/24 16:50	07/26/24 08:50

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-2786-1

Login Number: 2786

List Source: Eurofins Atlanta

List Number: 1

Creator: Pomuti, Carmen

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	N/A	
Sample custody seals, if present, are intact.	N/A	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	N/A	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	N/A	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT



ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 7/30/2024 5:57:49 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-2894-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
7/30/2024 5:57:49 PM



Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	15
Lab Chronicle	17
Certification Summary	19
Method Summary	20
Sample Summary	21
Receipt Checklists	22
End Of Report	23

Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2894-1

Qualifiers

Metals

Qualifier	Qualifier Description
^3-	Reporting Limit Check Standard is outside acceptance limits, low biased.
^5+	Linear Range Check (LRC) is outside acceptance limits, high biased.
4	MS, MSD: The analyte present in the original sample is greater than 4 times the matrix spike concentration; therefore, control limits are not applicable.
F1	MS and/or MSD recovery exceeds control limits.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
□	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

[illegible]

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-2894-1

Job ID: 705-2894-1

Eurofins Atlanta

Job Narrative 705-2894-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers and/or narrative comments are included to explain any exceptions, if applicable.

- Matrix QC may not be reported if insufficient sample is provided or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 7/27/2024 9:15 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 4.2°C.

Metals

Method 020 - Total recoverable: The matrix spike / matrix spike duplicate (MS/MSD) recoveries for Prep batch 5412 were outside control limits for Arsenic. See QC Sample results for detail. Sample matrix interference and/or non-homogeneity are suspected because the associated laboratory control sample (LCS) recovery is within acceptance limits.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client Sample ID: PT3-4F-MA-07-1r-xWb-T3
Date Received: 07/17/2024

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-M

3 atcid: / atec

3 et(29: S/ 8Ar r0MD - 3 etals)IC4.

TnalUte	Result	f ualiBec	RL	3 DL	x nit	D	4æpææ9	TnalUæ9	Dil oav
, 2æn	0yz		0420	0416	d g\$		07S9S2 07:29	07S9S2 08:00	C

3 et(29: S/ 8Ar r010, - 3 etals)IC418 S. - F2tal Rev26ecable

TnalUte	Result	f ualiBec	RL	3 DL	x nit	D	4æpææ9	TnalUæ9	Dil oav
Tæeniv	0yM	oM	04050	04008	d g\$		07S9S2 07:16	07S9S2 05:59	C
læ2n	A0		0420	0403	d g\$		07S9S2 07:16	07S9S2 05:59	C

Client Sample Results

Client Sample ID: PT3-4F-MA-07-1r-oIL-T3
Date Received: 07/17/2024
Date Released: 07/17/2024

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-1
3 atcid: / atec

3 et(29: S/ 8Ar r0MD - 3 etals)IC4. - Diss2I6e9

TnalUte	Result	f ualiBec	RL	3 DL	x nit	D	4æpææ9	TnalUæ9	Dil oav
, 2ænNDiss2I6e9	0y57		04020	04016	d g\$.			07/19/24 06:16	C

3 et(29: S/ 8Ar r010, - 3 etals)IC4I8 S. - Diss2I6e9

TnalUte	Result	f ualiBec	RL	3 DL	x nit	D	4æpææ9	TnalUæ9	Dil oav
TæsenivNDiss2I6e9	0yMA		04050	04008	d g\$.			07/30/24 02:80	C
Iæ2nNDiss2I6e9	MB		04020	04003	d g\$.			07/30/24 02:80	C

Client Sample Results

Client Sample ID: PT3-4F-MA-07-1r-xWb-43
Date Received: 07/17/2024
Date Released: 07/17/2024

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-3
3 atcid: / atec

3 et(29: S/ 8Ar r0MD - 3 etals)IC4.

TnalUte	Result	f ualiBec	RL	3 DL	x nit	D	4æpææ9	TnalUæ9	Dil oav
, 2æn	0y1		0420	0416	d g\$		07S9S2 07:29	07S9S2 C1:83	C

3 et(29: S/ 8Ar r010, - 3 etals)IC418 S. - F2tal Rev26ecable

TnalUte	Result	f ualiBec	RL	3 DL	x nit	D	4æpææ9	TnalUæ9	Dil oav
Tæeniv	0y1		04050	04008	d g\$		07S9S2 07:16	07S9S2 06:05	C
læ2n	z8		0420	0403	d g\$		07S9S2 07:16	07S9S2 06:05	C

Client Sample Results

Client Sample ID: PT3-4F-MA-07-1r-oIL-43
Date Received: 07/17/2024
Date Released: 07/17/2024

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-A

3 atcid: / atec

3 et(29: S/ 8Ar r0MD - 3 etals)IC4. - Diss2I6e9

TnalUte	Result	f ualiBec	RL	3 DL	x nit	D	4æpææ9	TnalUæ9	Dil oav
, 2ænNDiss2I6e9	0y57		04020	04016	d g\$.			07/19/24 06:19	C

3 et(29: S/ 8Ar r010, - 3 etals)IC4I8 S. - Diss2I6e9

TnalUte	Result	f ualiBec	RL	3 DL	x nit	D	4æpææ9	TnalUæ9	Dil oav
TæsenivNDiss2I6e9	0yM5		04050	04008	d g\$.			07/30/24 02:82	C
Iæ2nNDiss2I6e9	M5		04020	04003	d g\$.			07/30/24 02:82	C

Client Sample Results

Client Sample ID: PT3-4F-07-07-1r-xWb-43
Date Received: 07/11/2023
Date Released: 07/11/2023

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-5

3 atcid: / atec

3 et(29: S/ 8Ar r0MD - 3 etals)IC4.

TnalUte	Result	f ualiBec	RL	3 DL	x nit	D	4æpææ9	TnalUæ9	Dil oav
, 2æn	0y70		0420	0416	d g\$		07S9S2 07:29	07S9S2 08:08	C

3 et(29: S/ 8Ar r010, - 3 etals)IC418 S. - F2tal Rev26ecable

TnalUte	Result	f ualiBec	RL	3 DL	x nit	D	4æpææ9	TnalUæ9	Dil oav
Tæeniv	0yA		0450	0408	d g\$		07S9S2 07:16	07S0S2 05:02	00
læ2n	MA0		0420	0403	d g\$		07S9S2 07:16	07S0S2 05:02	00

Client Sample Results

Client Sample ID: PT3-4F-07-07-1r-oIL-43
Date Received: 07/11/2024
Date Released: 07/11/2024

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-r
3 atcid: / atec

3 et(29: S/ 8Ar r0MD - 3 etals)IC4. - Diss2I6e9

TnalUte	Result	f ualiBec	RL	3 DL	x nit	D	4 cepacø9	TnalUø9	Dil oav
, 2c2nNDiss2I6e9	0y58		0420	0416	d g\$.			075952 06:81	C

3 et(29: S/ 8Ar r010, - 3 etals)IC4I8 S. - Diss2I6e9

TnalUte	Result	f ualiBec	RL	3 DL	x nit	D	4 cepacø9	TnalUø9	Dil oav
TcsenivNDiss2I6e9	0y051		0450	0408	d g\$.			075052 02:26	00
Ic2nNDiss2I6e9	0yMH		0420	0403	d g\$.			075052 02:83	C

Client Sample Results

Client Sample ID: PT3-4F-Mz-07-1r-xWb-43
Date Received: 07/17/2024
Date Released: 07/17/2024

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-7

3 atcid: / atec

3 et(29: S/ 8Ar r0MD - 3 etals)IC4.

TnalUte	Result	f ualiBec	RL	3 DL	x nit	D	4æpææ9	TnalUæ9	Dil oav
, 2æn	0y5A		04020	04016	d g\$		07S9S2 07:29	07S9S2 08:06	C

3 et(29: S/ 8Ar r010, - 3 etals)IC418 S. - F2tal Rev26ecable

TnalUte	Result	f ualiBec	RL	3 DL	x nit	D	4æpææ9	TnalUæ9	Dil oav
Tæseniv	0y1r		04050	04008	d g\$		07S9S2 07:16	07S0S2 05:03	C
læ2n	A1		04020	04003	d g\$		07S9S2 07:16	07S9S2 06:13	C

Client Sample Results

Client Sample ID: PT3-4F-MZ-07-1r-oIL-43
Date Received: 07/17/2024
Date Released: 07/17/2024

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-8
3 atcid: / atec

3 et(29: S/ 8Ar r0MD - 3 etals)IC4. - Diss2I6e9

TnalUte	Result	f ualiBec	RL	3 DL	x nit	D	4æpææ9	TnalUæ9	Dil oav
, 2ænNDiss2I6e9	0y50		04020	04016	d g\$.			07/19/2024 06:20	C

3 et(29: S/ 8Ar r010, - 3 etals)IC4I8 S. - Diss2I6e9

TnalUte	Result	f ualiBec	RL	3 DL	x nit	D	4æpææ9	TnalUæ9	Dil oav
TæsenivNDiss2I6e9	0yM6		04050	04008	d g\$.			07/30/2024 02:50	C
Iæ2nNDiss2I6e9	M		04020	04003	d g\$.			07/30/2024 02:50	C

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2894-1

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-5413/1-A
Matrix: Water
Analysis Batch: 5542

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 5413

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	ND		0.040	0.026	mg/L		07/29/24 07:49	07/29/24 12:32	1

Lab Sample ID: LCS 705-5413/2-A
Matrix: Water
Analysis Batch: 5542

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 5413

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	1.00	1.03		mg/L		103	80 - 120

Lab Sample ID: 705-2894-3 MS
Matrix: Water
Analysis Batch: 5542

Client Sample ID: HAM-PT-14-07-26-UNF-PM
Prep Type: Total/NA
Prep Batch: 5413

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	0.62		1.00	1.62		mg/L		100	75 - 125

Lab Sample ID: 705-2894-3 MSD
Matrix: Water
Analysis Batch: 5542

Client Sample ID: HAM-PT-14-07-26-UNF-PM
Prep Type: Total/NA
Prep Batch: 5413

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron	0.62		1.00	1.63		mg/L		101	75 - 125	1	20

Lab Sample ID: MB 705-5500/1-A
Matrix: Water
Analysis Batch: 5594

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	ND		0.040	0.026	mg/L			07/29/24 15:49	1

Lab Sample ID: LCS 705-5500/2-A
Matrix: Water
Analysis Batch: 5594

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron, Dissolved	1.00	0.961		mg/L		96	80 - 120

Lab Sample ID: LCSD 705-5500/3-A
Matrix: Water
Analysis Batch: 5594

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron, Dissolved	1.00	0.958		mg/L		96	80 - 120	0	20

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2894-1

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-5412/1-A

Matrix: Water

Analysis Batch: 5610

Client Sample ID: Method Blank

Prep Type: Total Recoverable

Prep Batch: 5412

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	ND	^3- ^5+	0.0050	0.0013	mg/L		07/29/24 07:26	07/29/24 15:51	1
Iron	ND		0.040	0.018	mg/L		07/29/24 07:26	07/29/24 15:51	1

Lab Sample ID: LCS 705-5412/2-A

Matrix: Water

Analysis Batch: 5610

Client Sample ID: Lab Control Sample

Prep Type: Total Recoverable

Prep Batch: 5412

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.100	0.0902	^3- ^5+	mg/L		90	80 - 120
Iron	1.00	1.05		mg/L		105	80 - 120

Lab Sample ID: 705-2894-1 MS

Matrix: Water

Analysis Batch: 5610

Client Sample ID: HAM-PT-14-07-26-UNF-AM

Prep Type: Total Recoverable

Prep Batch: 5412

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.16	F1	0.100	0.208	F1	mg/L		52	75 - 125
Iron	40		1.00	40.4	4	mg/L		26	75 - 125

Lab Sample ID: 705-2894-1 MSD

Matrix: Water

Analysis Batch: 5610

Client Sample ID: HAM-PT-14-07-26-UNF-AM

Prep Type: Total Recoverable

Prep Batch: 5412

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic	0.16	F1	0.100	0.239		mg/L		83	75 - 125	14	20
Iron	40		1.00	40.7	4	mg/L		57	75 - 125	1	20

Lab Sample ID: MB 705-5495/1-A

Matrix: Water

Analysis Batch: 5745

Client Sample ID: Method Blank

Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	ND		0.0050	0.0013	mg/L			07/30/24 13:33	1
Iron, Dissolved	ND		0.040	0.018	mg/L			07/30/24 13:33	1

Lab Sample ID: LCS 705-5495/2-A

Matrix: Water

Analysis Batch: 5745

Client Sample ID: Lab Control Sample

Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic, Dissolved	0.100	0.0988		mg/L		99	80 - 120
Iron, Dissolved	1.00	0.877		mg/L		88	80 - 120

Lab Sample ID: LCSD 705-5495/3-A

Matrix: Water

Analysis Batch: 5745

Client Sample ID: Lab Control Sample Dup

Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic, Dissolved	0.100	0.0984		mg/L		98	80 - 120	0	20
Iron, Dissolved	1.00	0.942		mg/L		94	80 - 120	7	20

Eurofins Atlanta

Lab Chronicle

Client: Geosyntec Consultants Inc
 r j o l e c t S i t e : r l a n t m a d d o n A

Job ID: 705-1392-P

Client Sample ID: HAM-PT-13-07-4F-5 8 x-AM

Lab Sample ID: 70W4d/ 3-1

Date Collectev: 0794F943 10:10

Matri2: R ater

Date y e c e i B e v : 07947943 0/ :1W

Prep Tspe	uatch Tspe	uatch Methov	y Nn	DilNtion xactor	uatch 8 Nmber	Analstz	Lab	Preparev or Analstz
Total S E	r je6	B0P0E			52PB	HE	TTL ELv	0794942 07:29
Total S E	Enalstz	p0P0D		P	5521	DH	TTL ELv	0794942 P8:00
Total NecoRejable	r je6	B005E			52P1	HE	TTL ELv	0794942 07:1p
Total NecoRejable	Enalstz	p010F		P	5pP0	If	TTL ELv	0794942 P5:59

Client Sample ID: HAM-PT-13-07-4F-xIL-AM

Lab Sample ID: 70W4d/ 3-4

Date Collectev: 0794F943 10:10

Matri2: R ater

Date y e c e i B e v : 07947943 0/ :1W

Prep Tspe	uatch Tspe	uatch Methov	y Nn	DilNtion xactor	uatch 8 Nmber	Analstz	Lab	Preparev or Analstz
DissolReA	Enalstz	p0P0D		P	5592	DH	TTL ELv	0794942 Pp:1p
DissolReA	Enalstz	p010F		P	5725	If	TTL ELv	0794942 P2:B0

Client Sample ID: HAM-PT-13-07-4F-5 8 x-PM

Lab Sample ID: 70W4d/ 3-6

Date Collectev: 0794F943 40:00

Matri2: R ater

Date y e c e i B e v : 07947943 0/ :1W

Prep Tspe	uatch Tspe	uatch Methov	y Nn	DilNtion xactor	uatch 8 Nmber	Analstz	Lab	Preparev or Analstz
Total S E	r je6	B0P0E			52PB	HE	TTL ELv	0794942 07:29
Total S E	Enalstz	p0P0D		P	5521	DH	TTL ELv	0794942 P1:B3
Total NecoRejable	r je6	B005E			52P1	HE	TTL ELv	0794942 07:1p
Total NecoRejable	Enalstz	p010F		P	5pP0	If	TTL ELv	0794942 Pp:P5

Client Sample ID: HAM-PT-13-07-4F-xIL-PM

Lab Sample ID: 70W4d/ 3-3

Date Collectev: 0794F943 40:00

Matri2: R ater

Date y e c e i B e v : 07947943 0/ :1W

Prep Tspe	uatch Tspe	uatch Methov	y Nn	DilNtion xactor	uatch 8 Nmber	Analstz	Lab	Preparev or Analstz
DissolReA	Enalstz	p0P0D		P	5592	DH	TTL ELv	0794942 Pp:19
DissolReA	Enalstz	p010F		P	5725	If	TTL ELv	0794942 P2:B2

Client Sample ID: HAM-PT-07-07-4F-5 8 x-PM

Lab Sample ID: 70W4d/ 3-W

Date Collectev: 0794F943 40:10

Matri2: R ater

Date y e c e i B e v : 07947943 0/ :1W

Prep Tspe	uatch Tspe	uatch Methov	y Nn	DilNtion xactor	uatch 8 Nmber	Analstz	Lab	Preparev or Analstz
Total S E	r je6	B0P0E			52PB	HE	TTL ELv	0794942 07:29
Total S E	Enalstz	p0P0D		P	5521	DH	TTL ELv	0794942 P8:0B
Total NecoRejable	r je6	B005E			52P1	HE	TTL ELv	0794942 07:1p
Total NecoRejable	Enalstz	p010F		P0	577P	If	TTL ELv	0794942 P5:P2

Lab Chronicle

Client: Geosyntec Consultants Inc
r jo/ectSite: r lant mad d onA

Job ID: 705-1392-P

Client Sample ID: HAM-PT-07-07-4F-xIL-PM
Date Collectev: 0794F943 40:10
Date y eceiBev: 07947943 0/ :1W

Lab Sample ID: 70W4d/ 3-F
Matri2: R ater

Prep Tspe	uatch Tspe	uatch Methov	y Nn	DilNtion xactor	uatch 8 Nmber	Analstz	Lab	Preparev or Analstz
DissolReA	Enalysis	p0P0D		P	5592	DH	TTL ELv	0794942 Pp:B1
DissolReA	Enalysis	p010F		P	5725	If	TTL ELv	0794092 P2:B3
DissolReA	Enalysis	p010F		P0	5725	If	TTL ELv	0794092 P2:2p

Client Sample ID: HAM-PT-16-07-4F-5 8 x-PM
Date Collectev: 0794F943 40:40
Date y eceiBev: 07947943 0/ :1W

Lab Sample ID: 70W4d/ 3-7
Matri2: R ater

Prep Tspe	uatch Tspe	uatch Methov	y Nn	DilNtion xactor	uatch 8 Nmber	Analstz	Lab	Preparev or Analstz
LotalS E	r je6	B0P0E			52PB	HE	TTL ELv	0794942 07:29
LotalS E	Enalysis	p0P0D		P	5521	DH	TTL ELv	0794942 PB:0p
Lotal NecoRejable	r je6	B005E			52P1	HE	TTL ELv	0794942 07:1p
Lotal NecoRejable	Enalysis	p010F		P	5pP0	If	TTL ELv	0794942 Pp:13
Lotal NecoRejable	r je6	B005E			52P1	HE	TTL ELv	0794942 07:1p
Lotal NecoRejable	Enalysis	p010F		P	577P	If	TTL ELv	0794092 P5:P3

Client Sample ID: HAM-PT-16-07-4F-xIL-PM
Date Collectev: 0794F943 40:40
Date y eceiBev: 07947943 0/ :1W

Lab Sample ID: 70W4d/ 3-d
Matri2: R ater

Prep Tspe	uatch Tspe	uatch Methov	y Nn	DilNtion xactor	uatch 8 Nmber	Analstz	Lab	Preparev or Analstz
DissolReA	Enalysis	p0P0D		P	5592	DH	TTL ELv	0794942 Pp:2P
DissolReA	Enalysis	p010F		P	5725	If	TTL ELv	0794092 P2:50

Laborators y eferencez:

TTL ELv = Tujo8ns Etlanta, B030 r jesiAential Dj, Etlanta, GE B0B20, LTv (770)257-3P77

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2894-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

1
2
3
4
5
6
7
8
9
10
11
12
13

Method Summary

Int Gs noyct Au l ot yaiPt Q It u
r jo/nuShA: r iPt GmPd d ot W

Job ID: 705-1392-C

Method	Method Description	Protocol	Laboratory
4000D	6 nGiy M r (	H8 324	)) E TEA
4010L	6 nGiy M r \$ H(	H8 324	)) E TEA
B005T	r jnpPjPQt , EoCi RnuovnjPbin oj DeyoivnW6 nGiy	H8 324	)) E TEA
B000T	r jnpPjPQt , EoCi 6 nGiy	H8 324	)) E TEA

Protocol References:

H8 324 = "EnyG6 nGBoVy Foj) vPlaPa g HoiéV8 PyG, r hcyaPi\$ hnd aPi 6 nGBoVy", EhéW) Váot , Novnd bnj C934 Tt WlQ UpVPáy.

Laboratory References:

)) E TEA=) ajofé y TGPt Q, B030 r jnyéVt GPi Dj, TGPt Q, s T B0B20, E) AM70(257-3C77

Sample Summary

Client: Geosyntec Consultants Inc
/ Selectrite: / Iant AaMMonT

Job ID: 705-18Pr-j

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-18Pr-j	A34 -/ F-j r-07-1L-W29-34	U ateS	07mLmtr j 0:j 0	07m7mtr 0Pj 5
705-18Pr-1	A34 -/ F-j r-07-1L-9IN-34	U ateS	07mLmtr j 0:j 0	07m7mtr 0Pj 5
705-18Pr-6	A34 -/ F-j r-07-1L-W29-/ 4	U ateS	07mLmtr 10:00	07m7mtr 0Pj 5
705-18Pr-r	A34 -/ F-j r-07-1L-9IN-/ 4	U ateS	07mLmtr 10:00	07m7mtr 0Pj 5
705-18Pr-5	A34 -/ F-07-07-1L-W29-/ 4	U ateS	07mLmtr 10:j 0	07m7mtr 0Pj 5
705-18Pr-L	A34 -/ F-07-07-1L-9IN-/ 4	U ateS	07mLmtr 10:j 0	07m7mtr 0Pj 5
705-18Pr-7	A34 -/ F-j 6-07-1L-W29-/ 4	U ateS	07mLmtr 10:10	07m7mtr 0Pj 5
705-18Pr-8	A34 -/ F-j 6-07-1L-9IN-/ 4	U ateS	07mLmtr 10:10	07m7mtr 0Pj 5

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-2894-1

Login Number: 2894

List Source: Eurofins Atlanta

List Number: 1

Creator: Bellinger, Arabia

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	N/A	
Sample custody seals, if present, are intact.	N/A	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	N/A	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT



ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 7/31/2024 8:19:08 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-2915-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
7/31/2024 8:19:08 PM

Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	13
Lab Chronicle	16
Certification Summary	18
Method Summary	19
Sample Summary	20
Receipt Checklists	21
End Of Report	22



Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2915-1

Qualifiers

Metals

Qualifier	Qualifier Description
4	MS, MSD: The analyte present in the original sample is greater than 4 times the matrix spike concentration; therefore, control limits are not applicable.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

eurolins | Environment Testing

Ver: 04/02/20247/31/2024

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-2915-1

Job ID: 705-2915-1

Eurofins Atlanta

Job Narrative 705-2915-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers and/or narrative comments are included to explain any exceptions, if applicable.

- Matrix QC may not be reported if insufficient sample is provided or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 7/28/2024 8: AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 1.9°C.

Metals

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

20 ent i oGer y 2oeGuerGley
aPori yj/ lri : aQenSuHHoem

Job ID: 705-1395-9

Client Sample ID: AMP -T3-H4-7-17-Fr x

Lab Sample ID: 705-18H5-H

Date Cdlle/ te2: 07v17v14 H7:00

PatWb: c ateW

Date Re/ ei9e2: 07v1h14 0h:6(

Pet) d2: Sc h4((0H0D - Petals .ICTy

MnalUte	Result	f ualiBeW	RL	P DL	F nit	D	TWpaW2	MnalUQ2	Dil xa/
, dWln	0z 7		0d. 0	0d14	H6jg		07j13j1. 99:. 3	07jL0j1. 9. :01	9

Pet) d2: Sc h4((010, - Petals .ICTv Sy- 3dtal Re/ d9eWble

MnalUte	Result	f ualiBeW	RL	P DL	F nit	D	TWpaW2	MnalUQ2	Dil xa/
Mneni/	0z(		0d050	0d09L	H6jg		07j13j1. 91:. 0	07jL0j1. 97:L3	9
IWln	(1		0d 0	0d8	H6jg		07j13j1. 91:. 0	07jL9j1. 97:L8	90

Client Sample Results

20 ent i oGer y 2oeG@uerGley
aPöri yry/ lri : aQenSuHHoem

Job ID: 705-1395-9

Client Sample ID: AMP -T3-H4-7-17-xIL

Lab Sample ID: 705-18H5-1

Date Cdlle/ te2: 07v17v14 H7:00

PatWb: c ateW

Date Re/ ei9e2: 07v1h14 0h:6(

Pet) d2: Sc h4((0H0D - P etals .ICTy - Dissdl9e2

MnalUte	Result	f ualiBeW	RL	P DL	F nit	D	TWpaW2	MnalUQe2	Dil xa/
, dWnNDissdl9e2	0z57		0d050	0d014	H6jg			07j13j1. 95:58	9

Pet) d2: Sc h4((010, - P etals .ICTvP Sy - Dissdl9e2

MnalUte	Result	f ualiBeW	RL	P DL	F nit	D	TWpaW2	MnalUQe2	Dil xa/
MWeni/ NDissdl9e2	0d0H8		0d0050	0d009L	H6jg			07jL0j1. 9L.: 5	9
IWnNDissdl9e2	1z6		0d. 0	0d098	H6jg			07jL0j1. 9L.: 5	9

Client Sample Results

20 ent i oGer y 2oeGuerGley
aPori yj/ lri : aQenSuHHoem

Job ID: 705-1395-9

Client Sample ID: AMP -T3-07-7-17-Fr x

Lab Sample ID: 705-18H5-6

Date Cdille/ te2: 07v17v14 H7:00

PatWb: c ateW

Date Re/ ei9e2: 07v1h14 0h:6(

Pet) d2: Sc h4((0H0D - Petals .ICTy

MnalUte	Result	f ualiBeW	RL	P DL	F nit	D	TWpaW2	MnalUQ2	Dil xa/
, dWln	0z7H		0d. 0	0d14	H6jg		07j13j1. 99:. 3	07jL0j1. 9. :05	9

Pet) d2: Sc h4((010, - Petals .ICTv Sy- 3dtal Re/ d9eWble

MnalUte	Result	f ualiBeW	RL	P DL	F nit	D	TWpaW2	MnalUQ2	Dil xa/
Mvleni/	0z18		0d050	0d09L	H6jg		07j13j1. 91:. 0	07jL0j1. 97:. L	9
IWln	H80		0d 0	0d8	H6jg		07j13j1. 91:. 0	07jL9j1. 94:14	90

Client Sample Results

20 ent i oGer y 2oeG@uerGley
aPori ynj/ lri : aQenSuHHoem

Job ID: 705-1395-9

Client Sample ID: AMP -T3-07-7-17-xIL

Lab Sample ID: 705-18H5-4

Date Cdlle/ te2: 07v17v14 H7:00

PatWb: c ateW

Date Re/ ei9e2: 07v1h14 0h:6(

Pet) d2: Sc h4((0H0D - Petals .ICTy - Dissdl9e2

MnalUte	Result	f ualiBeW	RL	P DL	F nit	D	TWpaW2	MnalUQe2	Dil xa/
, dWnNDissdl9e2	0z5(		0d050	0d014	H6jg			07j13j1. 94:09	9

Pet) d2: Sc h4((010, - Petals .ICTvP Sy - Dissdl9e2

MnalUte	Result	f ualiBeW	RL	P DL	F nit	D	TWpaW2	MnalUQe2	Dil xa/
MWeni/ NDissdl9e2	0d015		0d050	0d09L	H6jg			07jL0j1. 9L.: 3	9
IWnNDissdl9e2	0z 0		0d. 0	0d098	H6jg			07jL0j1. 9L.: 3	9

Client Sample Results

20 ent i oGer y 2oeGuerGley
aPori yj/ lri : aQenSuHHoem

Job ID: 705-1395-9

Client Sample ID: AMP -T3-H6-7-17-Fr x

Lab Sample ID: 705-18H5-5

Date Cdile/ te2: 07v17v14 H7:00

PatWb: c ateW

Date Re/ ei9e2: 07v1h14 0h:6(

Pet) d2: Sc h4((0H0D - Petals .ICTy

MnalUte	Result	f ualiBeW	RL	P DL	F nit	D	TWpaW2	MnalUQ2	Dil xa/
, dWln	0z 0		0d. 0	0d14	H6jg		07j13j1. 99:. 3	07jL0j1. 9. :08	9

Pet) d2: Sc h4((010, - P etals .ICTv Sy- 3dtal Re/ d9eWble

MnalUte	Result	f ualiBeW	RL	P DL	F nit	D	TWpaW2	MnalUQ2	Dil xa/
Mneni/	0z(		0d050	0d09L	H6jg		07j13j1. 91:. 0	07jL0j1. 97:59	9
IWln	60		0d. 0	0d098	H6jg		07j13j1. 91:. 0	07jL9j1. 94:L0	9

Client Sample Results

20 ent i oGer y 2oeGuerGley
aPori ynj/ lri : aQenSuHHoem

Job ID: 705-1395-9

Client Sample ID: AMP -T3-H6-7-17-xIL

Lab Sample ID: 705-18H5-(

Date Cdlle/ te2: 07v17v14 H7:00

PatWb: c ateW

Date Re/ ei9e2: 07v1h14 0h:6(

Pet) d2: Sc h4((0H0D - Petals .ICTy- Dissdl9e2

MnalUte	Result	f ualiBeW	RL	P DL	F nit	D	TWpaW2	MnalUQ2	Dil xa/
, dWnNDissdl9e2	0z0		0d050	0d14	H6jg			07j13j1. 94:0.	9

Pet) d2: Sc h4((010, - Petals .ICTvP Sy- Dissdl9e2

MnalUte	Result	f ualiBeW	RL	P DL	F nit	D	TWpaW2	MnalUQ2	Dil xa/
MWeni/ NDissdl9e2	0d0h6		0d050	0d09L	H6jg			07jL0j1. 9L:5L	9
IWnNDissdl9e2	H1		0d. 0	0d098	H6jg			07jL0j1. 9L:5L	9

QC Sample Results

Internet Gateway
rjohu.com

Job ID: 705-18C5-C

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-5490/1-A
Matrix: Water
Analysis Batch: 5742

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 5490

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Nojot	. D		04020	04016	d g\$		07/8/2008	07/08/2008	2

Lab Sample ID: LCS 705-5490/2-A
Matrix: Water
Analysis Batch: 5742

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 5490

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Nojot	C400	C402		d g\$		C002	v0 - C10

Lab Sample ID: 705-2922-A-5-B MS
Matrix: Water
Analysis Batch: 5742

Client Sample ID: Matrix Spike
Prep Type: Total/NA
Prep Batch: 5490

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Nojot	0458		C400	C46C		d g\$		C00C	75 - C15

Lab Sample ID: 705-2922-A-5-C MSD
Matrix: Water
Analysis Batch: 5742

Client Sample ID: Matrix Spike Duplicate
Prep Type: Total/NA
Prep Batch: 5490

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Nojot	0458		C400	C46,		d g\$		C00,	75 - C15	C	10

Lab Sample ID: MB 705-5500/1-A
Matrix: Water
Analysis Batch: 5594

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Nojot 3Deyoi9nB	. D		04050	04016	d g\$			07/8/2008	5:28

Lab Sample ID: LCS 705-5500/2-A
Matrix: Water
Analysis Batch: 5594

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Nojot 3Deyoi9nB	C400	0466C		d g\$		86	v0 - C10

Lab Sample ID: LCSD 705-5500/3-A
Matrix: Water
Analysis Batch: 5594

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Nojot 3Deyoi9nB	C400	0465v		d g\$		86	v0 - C10	0	10

Eajofey AGP

QC Sample Results

Interpretation of results
 rjo/nucl: r iPt GmPd d ot B

Job ID: 705-18C5-C

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-5484/1-A
 Matrix: Water
 Analysis Batch: 5872

Client Sample ID: Method Blank
 Prep Type: Total Recoverable
 Prep Batch: 5484

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ajynt a	. D		040050	0400C	d g\$		07\$0\$2 C1:20	07\$0\$2 C7:05	C
Ijot	. D		04020	040Cv	d g\$		07\$0\$2 C1:20	07\$0\$2 C7:05	C

Lab Sample ID: LCS 705-5484/2-A
 Matrix: Water
 Analysis Batch: 5872

Client Sample ID: Lab Control Sample
 Prep Type: Total Recoverable
 Prep Batch: 5484

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Ajynt a	04000	0408v,		d g\$		8v	v0 - C10
Ijot	0400	0408, 5		d g\$		82	v0 - C10

Lab Sample ID: 705-2922-A-1-B MS
 Matrix: Water
 Analysis Batch: 5872

Client Sample ID: Matrix Spike
 Prep Type: Total Recoverable
 Prep Batch: 5484

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Ajynt a	040C		04000	04116		d g\$		87	75 - C15

Lab Sample ID: 705-2922-A-1-B MS
 Matrix: Water
 Analysis Batch: 5997

Client Sample ID: Matrix Spike
 Prep Type: Total Recoverable
 Prep Batch: 5484

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Ijot	11		0400	1042	2	d g\$		-61	75 - C15

Lab Sample ID: 705-2922-A-1-C MSD
 Matrix: Water
 Analysis Batch: 5872

Client Sample ID: Matrix Spike Duplicate
 Prep Type: Total Recoverable
 Prep Batch: 5484

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Ajynt a	040C		04000	04117		d g\$		88	75 - C15	C	10

Lab Sample ID: 705-2922-A-1-C MSD
 Matrix: Water
 Analysis Batch: 5997

Client Sample ID: Matrix Spike Duplicate
 Prep Type: Total Recoverable
 Prep Batch: 5484

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Ijot	11		0400	104v	2	d g\$		-11	75 - C15	1	10

Lab Sample ID: MB 705-5495/1-A
 Matrix: Water
 Analysis Batch: 5745

Client Sample ID: Method Blank
 Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ajynt a3Deyoi9nB	. D		040050	0400C	d g\$			07\$0\$2 C, , ,	C
Ijot 3Deyoi9nB	. D		04020	040Cv	d g\$			07\$0\$2 C, , ,	C

Eajofa y AGPt

QC Sample Results

Int Gs noyct Au l ot yai Pt Q It u
r jo/nuc: r iPt GmPd d ot B

Job ID: 705-18C5-C

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: LCS 705-5495/2-A				Client Sample ID: Lab Control Sample			
Matrix: Water				Prep Type: Dissolved			
Analysis Batch: 5745							
Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Ajynt a3Deyoi9nB	0400	0408vv		d g\$		88	v0 - C10
Ijot 3Deyoi9nB	040	0477		d g\$		vv	v0 - C10

Lab Sample ID: LCSD 705-5495/3-A					Client Sample ID: Lab Control Sample Dup						
Matrix: Water					Prep Type: Dissolved						
Analysis Batch: 5745											
				Spike	LCSD	LCSD			%Rec		RPD
Analyte				Added	Result	Qualifier	Unit	D	%Rec	Limits	RPD
Ajynt a3Deyoi9nB				0400	0408v2		d g\$		8v	v0 - C10	0
Ijot 3Deyoi9nB				040	0421		d g\$		82	v0 - C10	7

Lab Chronicle

Client: Geosyntec Consultants Inc
2 Rectj/ ite: 2 lant SaH Honm

Job ID: 705-1395-9

Client Sample ID: HAM-PT-13-0-70-4 F 5
Date Collecte2: 80R0R3 10:88
Date v ecei9e2: 80RyR3 8y:Bs

Lab Sample ID: 08x-7Wx-1
Matrid: / ater

Prep Tupe	z atch Tupe	z atch Metho2	v Un	DilUtion 5actor	z atch F Uumber	AnalunNt	Lab	Prepare2 or Analu6e2
votaljp 6	2Red	A0906			5T30	BE	LL v 6v4	07j13j1T 99:T3
votaljp 6	6nalysis	N090D		9	57T1	D/	LL v 6v4	07jA0j1T 9T:01
votal EecoFePable	2Red	A0056			5TRT	BE	LL v 6v4	07j13j1T 91:T0
votal EecoFePable	6nalysis	N010B		9	5R71	If	LL v 6v4	07jA0j1T 97:A3
votal EecoFePable	2Red	A0056			5TRT	BE	LL v 6v4	07j13j1T 91:T0
votal EecoFePable	6nalysis	N010B		90	5337	If	LL v 6v4	07jA9j1T 97:AR

Client Sample ID: HAM-PT-13-0-70-5IL
Date Collecte2: 80R0R3 10:88
Date v ecei9e2: 80RyR3 8y:Bs

Lab Sample ID: 08x-7Wx-7
Matrid: / ater

Prep Tupe	z atch Tupe	z atch Metho2	v Un	DilUtion 5actor	z atch F Uumber	AnalunNt	Lab	Prepare2 or Analu6e2
DissolFem	6nalysis	N090D		9	553T	D/	LL v 6v4	07j13j1T 95:5R
DissolFem	6nalysis	N010B		9	57T5	If	LL v 6v4	07jA0j1T 9A:T5

Client Sample ID: HAM-PT-80-0-70-4 F 5
Date Collecte2: 80R0R3 10:88
Date v ecei9e2: 80RyR3 8y:Bs

Lab Sample ID: 08x-7Wx-B
Matrid: / ater

Prep Tupe	z atch Tupe	z atch Metho2	v Un	DilUtion 5actor	z atch F Uumber	AnalunNt	Lab	Prepare2 or Analu6e2
votaljp 6	2Red	A0906			5T30	BE	LL v 6v4	07j13j1T 99:T3
votaljp 6	6nalysis	N090D		9	57T1	D/	LL v 6v4	07jA0j1T 9T:05
votal EecoFePable	2Red	A0056			5TRT	BE	LL v 6v4	07j13j1T 91:T0
votal EecoFePable	6nalysis	N010B		9	5R71	If	LL v 6v4	07jA0j1T 97:TA
votal EecoFePable	2Red	A0056			5TRT	BE	LL v 6v4	07j13j1T 91:T0
votal EecoFePable	6nalysis	N010B		90	5337	If	LL v 6v4	07jA9j1T 9N:1N

Client Sample ID: HAM-PT-80-0-70-5IL
Date Collecte2: 80R0R3 10:88
Date v ecei9e2: 80RyR3 8y:Bs

Lab Sample ID: 08x-7Wx-3
Matrid: / ater

Prep Tupe	z atch Tupe	z atch Metho2	v Un	DilUtion 5actor	z atch F Uumber	AnalunNt	Lab	Prepare2 or Analu6e2
DissolFem	6nalysis	N090D		9	553T	D/	LL v 6v4	07j13j1T 9N:09
DissolFem	6nalysis	N010B		9	57T5	If	LL v 6v4	07jA0j1T 9A:T3

Client Sample ID: HAM-PT-1B-0-70-4 F 5
Date Collecte2: 80R0R3 10:88
Date v ecei9e2: 80RyR3 8y:Bs

Lab Sample ID: 08x-7Wx-x
Matrid: / ater

Prep Tupe	z atch Tupe	z atch Metho2	v Un	DilUtion 5actor	z atch F Uumber	AnalunNt	Lab	Prepare2 or Analu6e2
votaljp 6	2Red	A0906			5T30	BE	LL v 6v4	07j13j1T 99:T3
votaljp 6	6nalysis	N090D		9	57T1	D/	LL v 6v4	07jA0j1T 9T:0R
votal EecoFePable	2Red	A0056			5TRT	BE	LL v 6v4	07j13j1T 91:T0
votal EecoFePable	6nalysis	N010B		9	5R71	If	LL v 6v4	07jA0j1T 97:59

Lab Chronicle

Client: Geosyntec Consultants Inc
2 Prectj/ ite: 2 lant SaH Honm

Job ID: 705-1395-9

Client Sample ID: HAM-PT-1B-0-70-4 F 5
Date Collecte2: 80R0R3 10:88
Date v ecei9e2: 80RyR3 8y:Bs

Lab Sample ID: 08x-7Wx-x
Matrid: / ater

Prep Tupe	z atch Tupe	z atch Metho2	v Un	DilUtion 5actor	z atch F Uumber	Analun	Lab	Prepare2 or Analu6e2
votal EecoFeRable	2 Rd	A0056			5TRT	BE	LL v 6v4	07j13j1T 91:T0
votal EecoFeRable	6 nalysis	N010B		9	5337	If	LL v 6v4	07jA9j1T 9NA0

Client Sample ID: HAM-PT-1B-0-70-5IL
Date Collecte2: 80R0R3 10:88
Date v ecei9e2: 80RyR3 8y:Bs

Lab Sample ID: 08x-7Wx-s
Matrid: / ater

Prep Tupe	z atch Tupe	z atch Metho2	v Un	DilUtion 5actor	z atch F Uumber	Analun	Lab	Prepare2 or Analu6e2
DissolFem	6 nalysis	N090D		9	553T	D/	LL v 6v4	07j13j1T 9N0T
DissolFem	6 nalysis	N010B		9	57T5	If	LL v 6v4	07jA0j1T 9A:5A

Laboratoru v eferenceN

LL v 6v4 = LuR8ns 6 tlanta, A0R0 2 Rsirential DP, 6 tlanta, G6 A0AT0, vL4 (770)T57-R977

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2915-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

1
2
3
4
5
6
7
8
9
10
11
12
13

Method Summary

2025-01-20 10:00 AM
aPurification: aPurification

Job ID: 705-1395-9

Method	Method Description	Protocol	Laboratory
4090D	6 i n u G N 2 a (	/ d V 8 4	)) E TEA
4010L	6 i n u G N 2 a j 6 / (	/ d V 8 4	)) E TEA
B005T	a P p u R i l o e , E o n u C R i y o v i R i b C o P D I G 3 b O i m 6 i n u G	/ d V 8 4	)) E TEA
B090T	a P p u R i l o e , E o n u C 6 i n u G	/ d V 8 4	)) E TEA

Protocol References:
/ d V 8 4 = "E G h 6 i r h o n G F o P) v u G u r l e g / o Q n d u G i , a h s G y u Q 2 h i H l y u C 6 i r h o n G , E h l P n) m l r l o e , N o v i H b i P 9 3 V 4 T e m l r G U p m u r i G

Laboratory References:
)) E TEA =) c R f l e G T r Q e r u , B 0 V 0 a P G m i e r l u C D P , T r Q e r u , t T B 0 B 8 0 , E) A M 7 0 (8 5 7 - V 0 7 7

Sample Summary

Client: Geosyntec Consultants Inc
Project: Site: r lant mad d onA

Job ID: 705-18P5-P

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-18P5-P	mMT -r 3-P4-7-17-FLW	2 atej	07S7S4 P7:00	07S9S4 09:UN
705-18P5-1	mMT -r 3-P4-7-17-W6	2 atej	07S7S4 P7:00	07S9S4 09:UN
705-18P5-U	mMT -r 3-07-7-17-FLW	2 atej	07S7S4 P7:00	07S9S4 09:UN
705-18P5-4	mMT -r 3-07-7-17-W6	2 atej	07S7S4 P7:00	07S9S4 09:UN
705-18P5-5	mMT -r 3-PU-7-17-FLW	2 atej	07S7S4 P7:00	07S9S4 09:UN
705-18P5-N	mMT -r 3-PU-7-17-W6	2 atej	07S7S4 P7:00	07S9S4 09:UN

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-2915-1

Login Number: 2915

List Source: Eurofins Atlanta

List Number: 1

Creator: Pomuti, Carmen

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	N/A	Not present
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	False	Limited volume received.
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	False	Insufficient volume received for requested analysis.
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	True	

END OF REPORT



ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 7/31/2024 8:33:54 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-2922-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
7/31/2024 8:33:54 PM

Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	15
Lab Chronicle	18
Certification Summary	20
Method Summary	21
Sample Summary	22
Receipt Checklists	23
End Of Report	24



Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2922-1

Qualifiers

Metals

Qualifier	Qualifier Description
^~	Continuing Calibration Verification (CCV) is outside acceptance limits, low biased.
4	MS, MSD: The analyte present in the original sample is greater than 4 times the matrix spike concentration; therefore, control limits are not applicable.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Environment Testing

[illegible]

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-2922-1

Job ID: 705-2922-1

Eurofins Atlanta

Job Narrative 705- -1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers and/or narrative comments are included to explain any exceptions, if applicable.

- Matrix QC may not be reported if insufficient sample is provided or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 7/29/2024 9:10 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was .8°C.

Receipt Exceptions

All samples were received at the laboratory without a sample collection time documented on the chain of custody or on the bottles.

Metals

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

20 ent i oGeri y 2oeG@uerGley
aPöri yry/ lri : aQenSuHHoem

Job ID: 705-1311-9

Client Sample ID: AMP -T3-H4-07-1F-r x W

Lab Sample ID: 705-1811-H

Date C/ lle2tev: 0791F914 00:00

Patdc: d ateo

Date Re2eihev: 07918914 08:10

Pet6/ v: Sd F4((0H0D - P etals)ICT.

Mnalzte	Result	Qualifieo	RL	P DL	r nit	D	Tœpæœv	MnalzUev	Dil V&2
B/ d' n	0y 5		0d. 0	0d14	H6jg		07j13j1. 99:.. 3	07jL0j1. 9. :99	9

Pet6/ v: Sd F4((010B - P etals)ICTP S. - 3/ tal Re2/ heœable

Mnalzte	Result	Qualifieo	RL	P DL	r nit	D	Tœpæœv	MnalzUev	Dil V&2
Mœeni2	0yL		0d050	0d09L	H6jg		07j13j1. 91:.. 0	07jL0j1. 97:1L	9
ld' n	11		0d 0	0d8	H6jg		07j13j1. 91:.. 0	07jL9j1. 94:90	90

Client Sample Results

20 ent i oGeri y 2oeG@uerGley
aPöri yry/ lri : aQenSuHHoem

Job ID: 705-1311-9

Client Sample ID: AMP -T3-H4-07-1F-WL

Lab Sample ID: 705-1811-1

Date C/ lle2tev: 0791F914 00:00

Patdıc: d ateo

Date Re2eihev: 07918914 08:H0

Pet6/ v: Sd F4((0H0D - P etals)ICT. - Diss/ lhev

Mnalzte	Result	Qualifieo	RL	P DL	r nit	D	Tœpaeœv	MnalzUev	Dil W&2
B/ d' nNDiss/ lhev	0y58		0d050	0d014	H6jg			07j13j1. 94:07	9

Pet6/ v: Sd F4((010B - P etals)ICTP S. - Diss/ lhev

Mnalzte	Result	Qualifieo	RL	P DL	r nit	D	Tœpaeœv	MnalzUev	Dil W&2
Mœeni2NDiss/ lhev	0yH1		0d050	0d09L	H6jg			07jL0j1. 9L:57	9
ld' nNDiss/ lhev	H5		0d. 0	0d098	H6jg			07jL0j1. 9L:57	9

Client Sample Results

20 ent i oGeri y 2oeG@erGley
aPöri yry/ lri : aQenSuHHoem

Job ID: 705-1311-9

Client Sample ID: AMP -T3-0F-07-1F-r x W

Lab Sample ID: 705-1811-,
Patdıc: d ateo

Date C/ lle2tev: 0791F914 00:00

Date Re2eihev: 07918914 08:10

Pet6/ v: Sd F4((0H0D - P etals)ICT.

Mnalzte	Result	Qualifieo	RL	P DL	r nit	D	Tœpaeœv	MnalzUev	Dil V&2
B/ d' n	0y75		0d. 0	0d14	H6jg		07j13j1. 99:.. 3	07jL0j1. 9. :9.	9

Pet6/ v: Sd F4((010B - P etals)ICTP S. - 3/ tal Re2/ heœable

Mnalzte	Result	Qualifieo	RL	P DL	r nit	D	Tœpaeœv	MnalzUev	Dil V&2
Mœeni2	0y41		0d050	0d09L	H6jg		07j13j1. 91:.. 0	07jL0j1. 98:1L	9
ld' n	1(		0d. 0	0d098	H6jg		07j13j1. 91:.. 0	07jL9j1. 94:L.	9

Client Sample Results

20 ent i oGeri y 2oeG@erGley
aPöri yry/ lri : aQenSuHHoem

Job ID: 705-1311-9

Client Sample ID: AMP -T3-0F-07-1F-WL

Lab Sample ID: 705-1811-4

Date C/ lle2tev: 0791F914 00:00

Patdc: d ateo

Date Re2eihev: 07918914 08:10

Pet6/ v: Sd F4((0H0D - P etals)ICT. - Diss/ lhev

Mnalzte	Result	Qualifieo	RL	P DL	r nit	D	Tœpæœv	MnalzUev	Dil W&2
B/ d' nNDiss/ lhev	0x (		0d050	0d014	H6jg			07j13j1. 94:90	9

Pet6/ v: Sd F4((010B - P etals)ICTP S. - Diss/ lhev

Mnalzte	Result	Qualifieo	RL	P DL	r nit	D	Tœpæœv	MnalzUev	Dil W&2
Mœeni2NDiss/ lhev	0yH7		0d050	0d09L	H6jg			07jL0j1. 9. :09	9
ld' nNDiss/ lhev	7y7		0d. 0	0d098	H6jg			07jL0j1. 9. :09	9

Client Sample Results

20 ent i oGeri y 2oeG@uerGley
aPöri yry/ lri : aQenSuHHoem

Job ID: 705-1311-9

Client Sample ID: AMP -T3-H₂ -07-1F-r x W

Lab Sample ID: 705-1811-5

Date C/ lle2tev: 0791F914 00:00

Patdıc: d ateo

Date Re2eihev: 07918914 08:10

Pet6/ v: Sd F4((0H0D - P etals)ICT.

Mnalzte	Result	Qualifieo	RL	P DL	r nit	D	Tœpaeœv	MnalzUev	Dil V&2
B/ d' n	0y58		0d. 0	0d14	H6jg		07j13j1. 99:.. 3	07jL0j1. 9L:.. 0	9

Pet6/ v: Sd F4((010B - P etals)ICTP S. - 3/ tal Re2/ heœable

Mnalzte	Result	Qualifieo	RL	P DL	r nit	D	Tœpaeœv	MnalzUev	Dil V&2
Mœeni2	0yH8		0d050	0d09L	H6jg		07j13j1. 91:.. 0	07jL0j1. 98:17	9
ld' n	1,		0d. 0	0d098	H6jg		07j13j1. 91:.. 0	07jL9j1. 94:L8	9

Client Sample Results

20 ent i oGer y 2oeGuerGley
aPori yry/ lri : aQenSuHHoem

Job ID: 705-1311-9

Client Sample ID: AMP -T3-H₂ -07-1F-WL

Lab Sample ID: 705-1811-(

Date C/ Ile2tev: 0791F914 00:00

Patdc: d ateo

Date Re2eihev: 07918914 08:10

Pet6/ v: Sd F4((0H0D - Petals)ICT. - Diss/ lhev

Mnalzte	Result	Qualifieo	RL	P DL	r nit	D	Tœpæœv	MnalzUev	Dil V&2
B/ d' nNDiss/ lhev	0y6H		0d050	0d014	H6jg			07j13j1. 94:9L	9

Pet6/ v: Sd F4((010B - Petals)ICTP S. - Diss/ lhev

Mnalzte	Result	Qualifieo	RL	P DL	r nit	D	Tœpæœv	MnalzUev	Dil V&2
Mœeni2NDiss/ lhev	0yH		0d050	0d09L	H6jg			07jL0j1. 9. :05	9
ld' nNDiss/ lhev	H ₂		0d. 0	0d098	H6jg			07jL0j1. 9. :05	9

Client Sample Results

20 ent i oGeri y 2oeG@uerGley
aPöri yry/ lri : aQenSuHHoem

Job ID: 705-1311-9

Client Sample ID: AMP -T3-07-07-1F-r x W

Lab Sample ID: 705-1811-7

Date C/ lle2tev: 0791F914 00:00

Patdc: d ateo

Date Re2eihev: 07918914 08:10

Pet6/ v: Sd F4((0H0D - P etals)ICT.

Mnalzte	Result	Qualifio	RL	P DL	r nit	D	Tœpæœv	MnalzUev	Dil V&2
B/ d' n	0y,		0d. 0	0d14	H6jg		07j13j1. 99.: 3	07jL0j1. 9. :98	9

Pet6/ v: Sd F4((010B - P etals)ICTP S. - 3/ tal Re2/ heœable

Mnalzte	Result	Qualifio	RL	P DL	r nit	D	Tœpæœv	MnalzUev	Dil V&2
Mœeni2	0y087		0d050	0d09L	H6jg		07j13j1. 91.: 0	07jL0j1. 98.:L9	9
ld' n	, H		0d. 0	0d098	H6jg		07j13j1. 91.: 0	07jL9j1. 94.: 1	9

Client Sample Results

20 ent i oGeri y 2oeG@uerGley
aPöri yry/ lri : aQenSuHHoem

Job ID: 705-1311-9

Client Sample ID: AMP -T3-07-07-1F-WL

Lab Sample ID: 705-1811-F

Date C/ lle2tev: 0791F914 00:00

Patdıc: d ateo

Date Re2eihev: 07918914 08:10

Pet6/ v: Sd F4((0H0D - P etals)ICT. - Diss/ lhev

Mnalzte	Result	Qualifieo	RL	P DL	r nit	D	Tœpaeœv	MnalzUev	Dil V&2
B/ d' nNDiss/ lhev	0y5(		0d050	0d014	H6jg			07j13j1. 94:94	9

Pet6/ v: Sd F4((010B - P etals)ICTP S. - Diss/ lhev

Mnalzte	Result	Qualifieo	RL	P DL	r nit	D	Tœpaeœv	MnalzUev	Dil V&2
Moseni2NDiss/ lhev	0y01(		0d050	0d09L	H6jg			07jL0j1. 9. :14	9
ld' nNDiss/ lhev	0y4(		0d. 0	0d098	H6jg			07jL0j1. 9. :14	9

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2922-1

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-5490/1-A
Matrix: Water
Analysis Batch: 5742

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 5490

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	ND		0.040	0.026	mg/L		07/29/24 11:49	07/30/24 13:34	1

Lab Sample ID: LCS 705-5490/2-A
Matrix: Water
Analysis Batch: 5742

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 5490

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	1.00	1.04		mg/L		104	80 - 120

Lab Sample ID: 705-2922-5 MS
Matrix: Water
Analysis Batch: 5742

Client Sample ID: HAM-PT-13-07-28-UNF
Prep Type: Total/NA
Prep Batch: 5490

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	0.59		1.00	1.61		mg/L		101	75 - 125

Lab Sample ID: 705-2922-5 MSD
Matrix: Water
Analysis Batch: 5742

Client Sample ID: HAM-PT-13-07-28-UNF
Prep Type: Total/NA
Prep Batch: 5490

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron	0.59		1.00	1.63		mg/L		103	75 - 125	1	20

Lab Sample ID: MB 705-5500/1-A
Matrix: Water
Analysis Batch: 5594

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron, Dissolved	ND		0.050	0.026	mg/L			07/29/24 15:49	1

Lab Sample ID: LCS 705-5500/2-A
Matrix: Water
Analysis Batch: 5594

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron, Dissolved	1.00	0.961		mg/L		96	80 - 120

Lab Sample ID: LCSD 705-5500/3-A
Matrix: Water
Analysis Batch: 5594

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron, Dissolved	1.00	0.958		mg/L		96	80 - 120	0	20

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2922-1

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-5484/1-A
Matrix: Water
Analysis Batch: 5872

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 5484

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	ND		0.0050	0.0013	mg/L		07/29/24 12:40	07/30/24 17:15	1
Iron	ND	^	0.040	0.018	mg/L		07/29/24 12:40	07/30/24 17:15	1

Lab Sample ID: LCS 705-5484/2-A
Matrix: Water
Analysis Batch: 5872

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 5484

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.100	0.0983		mg/L		98	80 - 120
Iron	1.00	0.935	^	mg/L		94	80 - 120

Lab Sample ID: 705-2922-1 MS
Matrix: Water
Analysis Batch: 5872

Client Sample ID: HAM-PT-14-07-28-UNF
Prep Type: Total Recoverable
Prep Batch: 5484

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.13		0.100	0.226		mg/L		97	75 - 125

Lab Sample ID: 705-2922-1 MS
Matrix: Water
Analysis Batch: 5997

Client Sample ID: HAM-PT-14-07-28-UNF
Prep Type: Total Recoverable
Prep Batch: 5484

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Iron	22		1.00	21.4	4	mg/L		-62	75 - 125

Lab Sample ID: 705-2922-1 MSD
Matrix: Water
Analysis Batch: 5872

Client Sample ID: HAM-PT-14-07-28-UNF
Prep Type: Total Recoverable
Prep Batch: 5484

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic	0.13		0.100	0.227		mg/L		99	75 - 125	1	20

Lab Sample ID: 705-2922-1 MSD
Matrix: Water
Analysis Batch: 5997

Client Sample ID: HAM-PT-14-07-28-UNF
Prep Type: Total Recoverable
Prep Batch: 5484

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Iron	22		1.00	21.8	4	mg/L		-22	75 - 125	2	20

Lab Sample ID: MB 705-5495/1-A
Matrix: Water
Analysis Batch: 5745

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	ND		0.0050	0.0013	mg/L			07/30/24 13:33	1
Iron, Dissolved	ND		0.040	0.018	mg/L			07/30/24 13:33	1

Eurofins Atlanta

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2922-1

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: LCS 705-5495/2-A				Client Sample ID: Lab Control Sample			
Matrix: Water				Prep Type: Dissolved			
Analysis Batch: 5745							
Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic, Dissolved	0.100	0.0988		mg/L		99	80 - 120
Iron, Dissolved	1.00	0.877		mg/L		88	80 - 120

Lab Sample ID: LCSD 705-5495/3-A					Client Sample ID: Lab Control Sample Dup						
Matrix: Water					Prep Type: Dissolved						
Analysis Batch: 5745											
				Spike	LCSD	LCSD			%Rec		RPD
Analyte				Added	Result	Qualifier	Unit	D	%Rec	Limits	RPD
Arsenic, Dissolved				0.100	0.0984		mg/L		98	80 - 120	0
Iron, Dissolved				1.00	0.942		mg/L		94	80 - 120	7

Lab Chronicle

Client: Geosyntec Consultants Inc
2 Rectj/ ite: 2 lant SaH Honm

Job ID: 705-1311-9

Client Sample ID: HAM-PT-13-07-4F-5 8 x
Date CollecteR: 074F43 00:00
Date 9 eceiyeR: 074d43 0d:10

Lab Sample ID: 70W4d44-1
Matri/ : 2 ater

Prep TBpe	s atch TBpe	s atch MethoR	9 z n	Dilz tion x actor	s atch 8 z mber	AnalBut	Lab	PrepareR or AnalBNeR
votaljp 6	2Red	A0906			5T30	BE	LL v 6v4	07j13j1T 99:T3
votaljp 6	6nalysis	N090D		9	57T1	D/	LL v 6v4	07jA0j1T 9T:99
votal EecoFePable	2Red	A0056			5TRT	BE	LL v 6v4	07j13j1T 91:T0
votal EecoFePable	6nalysis	N010B		9	5R71	If	LL v 6v4	07jA0j1T 97:1A
votal EecoFePable	2Red	A0056			5TRT	BE	LL v 6v4	07j13j1T 91:T0
votal EecoFePable	6nalysis	N010B		90	5337	If	LL v 6v4	07jA9j1T 9N:90

Client Sample ID: HAM-PT-13-07-4F-xIL
Date CollecteR: 074F43 00:00
Date 9 eceiyeR: 074d43 0d:10

Lab Sample ID: 70W4d44-4
Matri/ : 2 ater

Prep TBpe	s atch TBpe	s atch MethoR	9 z n	Dilz tion x actor	s atch 8 z mber	AnalBut	Lab	PrepareR or AnalBNeR
DissolFem	6nalysis	N090D		9	553T	D/	LL v 6v4	07j13j1T 9N:07
DissolFem	6nalysis	N010B		9	57T5	If	LL v 6v4	07jA0j1T 9A:57

Client Sample ID: HAM-PT-0F-07-4F-5 8 x
Date CollecteR: 074F43 00:00
Date 9 eceiyeR: 074d43 0d:10

Lab Sample ID: 70W4d44-U
Matri/ : 2 ater

Prep TBpe	s atch TBpe	s atch MethoR	9 z n	Dilz tion x actor	s atch 8 z mber	AnalBut	Lab	PrepareR or AnalBNeR
votaljp 6	2Red	A0906			5T30	BE	LL v 6v4	07j13j1T 99:T3
votaljp 6	6nalysis	N090D		9	57T1	D/	LL v 6v4	07jA0j1T 9T:9T
votal EecoFePable	2Red	A0056			5TRT	BE	LL v 6v4	07j13j1T 91:T0
votal EecoFePable	6nalysis	N010B		9	5R71	If	LL v 6v4	07jA0j1T 9R:1A
votal EecoFePable	2Red	A0056			5TRT	BE	LL v 6v4	07j13j1T 91:T0
votal EecoFePable	6nalysis	N010B		9	5337	If	LL v 6v4	07jA9j1T 9N:AT

Client Sample ID: HAM-PT-0F-07-4F-xIL
Date CollecteR: 074F43 00:00
Date 9 eceiyeR: 074d43 0d:10

Lab Sample ID: 70W4d44-3
Matri/ : 2 ater

Prep TBpe	s atch TBpe	s atch MethoR	9 z n	Dilz tion x actor	s atch 8 z mber	AnalBut	Lab	PrepareR or AnalBNeR
DissolFem	6nalysis	N090D		9	553T	D/	LL v 6v4	07j13j1T 9N:90
DissolFem	6nalysis	N010B		9	57T5	If	LL v 6v4	07jA0j1T 9T:09

Client Sample ID: HAM-PT-1U-07-4F-5 8 x
Date CollecteR: 074F43 00:00
Date 9 eceiyeR: 074d43 0d:10

Lab Sample ID: 70W4d44-W
Matri/ : 2 ater

Prep TBpe	s atch TBpe	s atch MethoR	9 z n	Dilz tion x actor	s atch 8 z mber	AnalBut	Lab	PrepareR or AnalBNeR
votaljp 6	2Red	A0906			5T30	BE	LL v 6v4	07j13j1T 99:T3
votaljp 6	6nalysis	N090D		9	57T1	D/	LL v 6v4	07jA0j1T 9A:T0
votal EecoFePable	2Red	A0056			5TRT	BE	LL v 6v4	07j13j1T 91:T0
votal EecoFePable	6nalysis	N010B		9	5R71	If	LL v 6v4	07jA0j1T 9R:17

Lab Chronicle

Client: Geosyntec Consultants Inc
 20rectj/ ite: 2lant SaHHonm

Job ID: 705-1311-9

Client Sample ID: HAM-PT-1U-07-4F-5 8 x

Lab Sample ID: 70W4d44-W

Date CollecteR: 074F43 00:00

Matri/ : 2 ater

Date 9 eceiyeR: 074d43 0d:10

Prep TBpe	s atch TBpe	s atch MethoR	9 z n	Dilz tion x actor	s atch 8 z mber	AnalBut	Lab	PrepareR or AnalBNeR
votal EecoFePable	2Red	A0056			5TRT	BE	LL v 6v4	07j13j1T 91:T0
votal EecoFePable	6nalysis	N010B		9	5337	If	LL v 6v4	07jA9j1T 9NAR

Client Sample ID: HAM-PT-1U-07-4F-xIL

Lab Sample ID: 70W4d44-6

Date CollecteR: 074F43 00:00

Matri/ : 2 ater

Date 9 eceiyeR: 074d43 0d:10

Prep TBpe	s atch TBpe	s atch MethoR	9 z n	Dilz tion x actor	s atch 8 z mber	AnalBut	Lab	PrepareR or AnalBNeR
DissolFem	6nalysis	N090D		9	553T	D/	LL v 6v4	07j13j1T 9N9A
DissolFem	6nalysis	N010B		9	57T5	If	LL v 6v4	07jA0j1T 9T:05

Client Sample ID: HAM-PT-07-07-4F-5 8 x

Lab Sample ID: 70W4d44-7

Date CollecteR: 074F43 00:00

Matri/ : 2 ater

Date 9 eceiyeR: 074d43 0d:10

Prep TBpe	s atch TBpe	s atch MethoR	9 z n	Dilz tion x actor	s atch 8 z mber	AnalBut	Lab	PrepareR or AnalBNeR
votaljp 6	2Red	A0906			5T30	BE	LL v 6v4	07j13j1T 99:T3
votaljp 6	6nalysis	N090D		9	57T1	D/	LL v 6v4	07jA0j1T 9T:9R
votal EecoFePable	2Red	A0056			5TRT	BE	LL v 6v4	07j13j1T 91:T0
votal EecoFePable	6nalysis	N010B		9	5R71	If	LL v 6v4	07jA0j1T 9RA9
votal EecoFePable	2Red	A0056			5TRT	BE	LL v 6v4	07j13j1T 91:T0
votal EecoFePable	6nalysis	N010B		9	5337	If	LL v 6v4	07jA9j1T 9NT1

Client Sample ID: HAM-PT-07-07-4F-xIL

Lab Sample ID: 70W4d44-F

Date CollecteR: 074F43 00:00

Matri/ : 2 ater

Date 9 eceiyeR: 074d43 0d:10

Prep TBpe	s atch TBpe	s atch MethoR	9 z n	Dilz tion x actor	s atch 8 z mber	AnalBut	Lab	PrepareR or AnalBNeR
DissolFem	6nalysis	N090D		9	553T	D/	LL v 6v4	07j13j1T 9N9N
DissolFem	6nalysis	N010B		9	57T5	If	LL v 6v4	07jA0j1T 9T:1N

LaboratorB9 eferenceur:

LL v 6v4 = LuR8ns 6tlanta, A0R0 2Resimental DP, 6tlanta, G6 A0AT0, vL4 (770)T57-R977

LuR8ns 6tlanta

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2922-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

1
2
3
4
5
6
7
8
9
10
11
12
13

Method Summary

2025-01-20 10:00 AM
aPurification: aPurification

Job ID: 705-1311-9

Method	Method Description	Protocol	Laboratory
4090D	6 i n u G N 2 a (	/ d V 8 4	)) E TEA
4010L	6 i n u G N 2 a j 6 / (	/ d V 8 4	)) E TEA
B005T	a P p u R i t o e , E o n u C R i y o v i R i b C o P D I G 3 b Q i m 6 i n u G	/ d V 8 4	)) E TEA
B090T	a P p u R i t o e , E o n u C 6 i n u G	/ d V 8 4	)) E TEA

Protocol References:
/ d V 8 4 = "E G h 6 i r h o n G F o P) v u G u r l e g / o Q n d u G i , a h s G y u Q 2 h i H l y u C 6 i r h o n G , E h l P n) m l r o e , N o v i H b i P 9 3 V 4 T e m l r G U p m u r i G

Laboratory References:
)) E TEA =) c R f l e G T r Q e r u , B 0 V 0 a P G m e r l u C D P , T r Q e r u , t T B 0 B 8 0 , E) A M 7 0 (8 5 7 - V 0 7 7

Sample Summary

Client: Geosyntec Consultants Inc
Project: Site: r lant mad d onA

Job ID: 705-1811-P

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-1811-P	mMT -r 3-P4-07-1F-L W2	9 atej	07/31/2024 00:00	07/31/2024 08:00
705-1811-1	mMT -r 3-P4-07-1F-2IU	9 atej	07/31/2024 00:00	07/31/2024 08:00
705-1811-N	mMT -r 3-0F-07-1F-L W2	9 atej	07/31/2024 00:00	07/31/2024 08:00
705-1811-4	mMT -r 3-0F-07-1F-2IU	9 atej	07/31/2024 00:00	07/31/2024 08:00
705-1811-5	mMT -r 3-PN-07-1F-L W2	9 atej	07/31/2024 00:00	07/31/2024 08:00
705-1811-6	mMT -r 3-PN-07-1F-2IU	9 atej	07/31/2024 00:00	07/31/2024 08:00
705-1811-7	mMT -r 3-07-07-1F-L W2	9 atej	07/31/2024 00:00	07/31/2024 08:00
705-1811-F	mMT -r 3-07-07-1F-2IU	9 atej	07/31/2024 00:00	07/31/2024 08:00



Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-2922-1

Login Number: 2922

List Source: Eurofins Atlanta

List Number: 1

Creator: Pomuti, Carmen

Question	Answer	Comment
Radioactivity wasn't checked or is <= background as measured by a survey meter.	True	
The cooler's custody seal/Ai, f resent/Ais intact.	True	Not f resent
pamf le custody sealsAi, f resent/Aare intact.	True	
The cooler or samf les do not af f ear to have been comf romised or tamf ered with.	True	
pamf les were received on ice.	True	
Cooler Temf erature is accef table.	True	
Cooler Temf erature is recorded.	True	
CSC is f resent.	True	
CSC is ,illed out in ink and legible.	True	
CSC is ,illed out with all f ertinent in,ormation.	True	
Is the Qield pamf ler's name f resent on CSCF	True	
There are no discref ancies between the containers received and the CSC.	True	
pamf les are received within ?olding Time He(cluding tests with immediate ? Tsx	True	
pamf le containers have legible labels.	True	
Containers are not broken or leaking.	True	
pamf le collection date/times are f rovided.	Qalse	No date or time on CSC or samf le containers
) f f rof riate samf le containers are used.	True	
pamf le bottles are comf letely ,illed.	Qalse	Limited volume received.
pamf le Preservation Veri,ied.	True	
There is su,,icient vol. ,or all requested analysesAincl. any requested Mp/MpDs	Qalse	Insu,,icient volume received ,or requested analysis.
Containers requiring zero headsf ace have no headsf ace or bubble is <6mm H/4"x	True	
Multif hasic samf les are not f resent.	True	
pamf les do not require sf litting or comf ositing.	True	
Residual Chlorine Checked.	N/)	

END OF REPORT



ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 7/31/2024 3:22:12 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-2983-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
7/31/2024 3:22:12 PM



Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	7
Client Sample Results	8
QC Sample Results	22
Lab Chronicle	25
Certification Summary	29
Method Summary	30
Sample Summary	31
Receipt Checklists	32
End Of Report	33

Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2983-1

Qualifiers

Metals

Qualifier	Qualifier Description
4	MS, MSD: The analyte present in the original sample is greater than 4 times the matrix spike concentration; therefore, control limits are not applicable.
F1	MS and/or MSD recovery exceeds control limits.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Chain of Custody Record

Client Information		Sampler: <u>Zain Webb</u>		Lab PM David Fuller / Phone 770-344-8986		Carrier Tracking No(s):		COC No:			
Client Contact: Kip Gray		Phone: <u>404-434-2074</u>		E-Mail: David Fuller@et.eurofinsus.com		State of Origin GA		Page: Page 1 of 2			
Company: Geosyntec Consultants Inc				PWSID		Analysis Requested				Job #:	
Address: 1255 Roberts Blvd, NW Suite 200		Due Date Requested		Field Filtered Sample (Yes or No) Performance SW/SP (Yes or No) 6010D - Total Boron 6020B - Total Arsenic and Iron 6020B - Total Iron and Molybdenum 6010D - Dissolved Boron - Field Filtered (FF) 6020B - Dissolved Arsenic and Iron (FF) 6020B - Dissolved Iron and Molybdenum (FF) Total Number of containers		Preservation Codes: D - HNO3		Other:			
City: Kennesaw		TAT Requested (days) RUSH / 1 Day TAT									
State, Zip: GA, 30144		Compliance Project: ☐ Yes ☐ No									
Phone:		Lab Project #: 70500911 (DO NOT REMOVE)									
Email: Kip Gray@Geosyntec.com		PO #: 100061163									
Project Name: Plant Hammond		Project #: GW6581G									
Task Code: Task Code#		SSOW#:									
Sample Identification		Sample Date		Sample Time		Sample Type (C=Comp, G=grab)		Matrix (W=water, Seawater, O=wastewater, BT=Trace, A=Air)		Preservation Code:	
HAM-PT-07-07-29-FIL-AM		7/29/24		0905		G		W		D	
HAM-PT-07-07-29-UNF-AM		7/29/24		0905		G		W		D	
HAM-PT-14-07-29-FIL-AM		7/29/24		0905		G		W		D	
HAM-PT-14-07-29-UNF-AM		7/29/24		0905		G		W		D	
HAM-PT-07-07-29-FIL-PM		7/29/24		1843		G		W		D	
HAM-PT-07-07-29-UNF-PM		7/29/24		1843		G		W		D	
HAM-PT-14-07-29-FIL-PM		7/29/24		1833		G		W		D	
HAM-PT-14-07-29-UNF-PM		7/29/24		1833		G		W		D	
		ZW		7/29/24							
Possible Hazard Identification ☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☒ Unknown ☐ Radiological										Sample Disposal (A fee may be assessed if samples are retained longer than 1 month) ☐ Return To Client ☒ Disposal By Lab ☐ Archive For _____ Months	
Deliverable Requested I, II, III, IV, Other (specify)										Special Instructions/QC Requirements	
Empty Kit Relinquished by:				Date		Time		Method of Shipment			
Relinquished by: <u>[Signature]</u>				Date/Time: <u>7/30/24 7:00</u>		Company		Received by: <u>[Signature]</u>			
Relinquished by: <u>[Signature]</u>				Date/Time: <u>7-30-24 9:00</u>		Company		Received by: <u>[Signature]</u>			
Relinquished by: <u>[Signature]</u>				Date/Time: <u>07/30/24 09:00</u>		Company		Received by: <u>[Signature]</u>			
Custody Seals Intact: ☐ Yes ☐ No		Custody Seal No		Page 5 of 33		Cooler Temperature(s) °C and Other Remarks: #2665 1.8°C		7/31/2024			

Chain of Custody Record

Client Information		Sampler: <u>Zain Webb</u>		Lab PM David Fuller / Phone 770-344-8986		Carrier Tracking No(s):		COC No:																	
Client Contact: Kip Gray		Phone: <u>404-434-2074</u>		E-Mail: David Fuller@et.eurofinsus.com		State of Origin GA		Page: Page 2 of 2																	
Company: Geosyntec Consultants Inc		PWSID:		Analysis Requested																					
Address: 1255 Roberts Blvd, NW Suite 200		Due Date Requested		Total Number of containers																					
City: Kennesaw		TAT Requested (days) RUSH / 1 Day TAT																							
State, Zip GA, 30144		Compliance Project. Δ Yes Δ No																							
Phone:		Lab Project #: 70500911 (DO NOT REMOVE)																							
Email: Kip Gray@Geosyntec.com		PO #: 100061163																							
Project Name: Plant Hammond		Project #: GW6581G		Other																					
Task Code		SSOW#																							
Task Code#																									
Sample Identification		Sample Date		Sample Time		Sample Type (C=Comp, G=grab)		Matrix (W=water, S=solid, O=wastewater, BT=tissue, A=air)		Field Filtered Sample (Yes or No)		6010D - Total Boron		6020B - Total Arsenic and Iron		6020B - Total Iron and Molybdenum		6010D - Dissolved Boron - Field Filtered (FF)		6020B - Dissolved Arsenic and Iron (FF)		6020B - Dissolved Iron and Molybdenum (FF)		Preservation Codes: D - HNO3	
																								Special Instructions/Note:	
HAM-PT-14-07-29-FIL-12		7/29/24		1200		G		W		Yes		1		1		1		X		X		1			
HAM-PT-14-07-29-UNF-12		7/29/24		1200		G		W		Yes		2		X		X		1		1		1			
HAM-PT-14-07-29-FIL-13		7/29/24		1300		G		W		Yes		2		1		1		X		X		1			
HAM-PT-14-07-29-UNF-13		7/29/24		1300		G		W		Yes		2		X		X		1		1		1			
HAM-PT-14-07-29-FIL-15		7/29/24		1500		G		W		Yes		2		1		1		X		X		1			
HAM-PT-14-07-29-UNF-15		7/29/24		1500		G		W		Yes		2		X		X		1		1		1			

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-2983-1

Job ID: 705-2983-1

Eurofins Atlanta

Job Narrative 705-2983-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers and/or narrative comments are included to explain any exceptions, if applicable.

- Matrix QC may not be reported if insufficient sample is provided or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 7/ 0/2024 9:00 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 1.8°C.

Metals

Method 020 - Total recoverable: The matrix spike / matrix spike duplicate (MS/MSD) recoveries and precision for preparation batch 705-515 and analytical batch 705-5844 was outside control limits. Sample matrix interference is suspected.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client Sample ID: PT3-4F-07-07-18-r IL-T3
Date Collected: 07/21/2021 08:05
Date Received: 07/21/2021 08:00

Job ID: 705-1392-C

Lab Sample ID: 705-18HAM

3 atxW o atex

3 ethc/ : So Hv6 60MD - 3 etals (IC4) - Disscl9e/

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Bcxn, Disscl9e/	0.5v		04060	0401g	d L\$			072016 C2:C7	C

3 ethc/ : So Hv6 6010B - 3 etals (IC43 S) - Disscl9e/

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Tsenid, Disscl9e/	0.055		04050	0400C2	d L\$			072016 Cg:6g	C
lxcn, Disscl9e/	6.v		04060	04009	d L\$			072016 Cg:6g	C

Client Sample Results

Client Sample ID: PT3-4F-07-07-18-UNr-T3
 Date Collected: 07/21/2021 08:05
 Date Received: 07/21/2021 08:00

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-1
 3 atxW o atex

3 ethc/ : So Hv6 60MD - 3 etals (IC4)

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxel	Tnalyze/	Dil r ad
Bcxn	0.60		04060	0401g	d L\$		072021 07:03	072021 07:05	C

3 ethc/ : So Hv6 6010B - 3 etals (IC42 S) - Fctal Redc9exable

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxel	Tnalyze/	Dil r ad
Tsenid	0.16		04050	04002	d L\$		072021 07:03	072021 07:06	C
lxcn	16		04060	04009	d L\$		072021 07:03	072021 07:06	C

Client Sample Results

Client Sample ID: PT3 -4F-M-07-18-r IL-T3
 Date Collected: 07/21/2021 08:05
 Date Received: 07/21/2021 08:00

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-A

3 atxW o atex

3 ethc / : So Hv6 60MD - 3 etals (IC4) - Disscl9e/

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Bcxn, Disscl9e/	0.57		0460	0401g	d L\$			072021 02:10	C

3 ethc / : So Hv6 6010B - 3 etals (IC43 S) - Disscl9e/

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Tsenid, Disscl9e/	0.14		04050	04002	d L\$			072021 09:63	C
lxcn, Disscl9e/	16		0460	0409	d L\$			072021 09:12	00

Client Sample Results

Client Sample ID: PT3-4F-M-07-18-UNr-T3
 Date Collected: 07/21/2021 08:05
 Date Received: 07/21/2021 08:00

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-v
 3 atxW o atex

3 ethc / : So Hv6 60MD - 3 etals (IC4)

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Bcxn	0.61		04060	0401g	d L\$		072021 00:03	072021 09:16	C

3 ethc / : So Hv6 6010B - 3 etals (IC42 S) - Fctal Redc9exable

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Tsenid	0.10		04050	04002	d L\$		072021 00:00	072021 07:6g	C
lxcn	51		040	0409	d L\$		072021 00:00	072021 09:1g	00

Client Sample Results

Client Sample ID: PT3-4F-07-07-18-r IL-43
Date Collected: 07/21/2021
Date Received: 07/21/2021

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-5

3 atxW o atex

3 ethc / : So Hv6 60MD - 3 etals (IC4) - DisscI9e/

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Bcxn, DisscI9e/	0.5v		04060	0401g	d L\$			072016 C2:12	C

3 ethc / : So Hv6 6010B - 3 etals (IC43 S) - DisscI9e/

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Tsenid, DisscI9e/	0.0H		04050	0400C2	d L\$			072016 Cg:5C	C
lxcn, DisscI9e/	M		04060	04009	d L\$			072016 Cg:5C	C

Client Sample Results

Client Sample ID: PT3-4F-07-07-18-UNr-43
 Date Collected: 07/21/2021
 Date Received: 07/21/2021

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-6

3 atxW o atex

3 ethc / : So Hv6 60MD - 3 etals (IC4)

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Bcxn	0.56		04060	0401g	d L\$		072021 06:00	072021 06:00	C

3 ethc / : So Hv6 6010B - 3 etals (IC43 S) - Fctal Redc9exable

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Tsenid	0.1A		04050	04002	d L\$		072021 06:00	072021 07:03	C
lxcn	1A		04060	04009	d L\$		072021 06:00	072021 07:03	C

Client Sample Results

Client Sample ID: PT3-4F-M-07-18-r IL-43
 Date Collected: 07/21/2021
 Date Received: 07/22/2021

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-7
 3 atxW o atex

3 ethc / : So Hv6 60MD - 3 etals (IC4) - Disscl9e/									
Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Bcxn, Disscl9e/	0.4H		0460	0401g	d L\$			072016 C2:1g	C
3 ethc / : So Hv6 6010B - 3 etals (IC43 S) - Disscl9e/									
Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Txenid, Disscl9e/	0.0M		04050	0400C2	d L\$			072016 Cg:52	C
lxcn, Disscl9e/	70		0460	0409	d L\$			072016 C7:10	00

Client Sample Results

Client Sample ID: PT3-4F-M-07-18-UNr-43
Date Collected: 07/21/2021
Date Received: 07/21/2021

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-H

3 atxW o atex

3 ethc / : So Hv6 60MD - 3 etals (IC4)

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Bcxn	0.vA		04060	0401g	d L\$		072021 06:03	072021 06:17	C

3 ethc / : So Hv6 6010B - 3 etals (IC43 S) - Fctal Redc9exable

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Tsenid	0.085		04050	04002	d L\$		072021 06:03	072021 07:5g	C
lxcn	MD		040	0409	d L\$		072021 06:03	072021 09:02	00

Client Sample Results

Client Sample ID: PT3-4F-M-07-18-r IL-M
 Date Collected: 07/21/2021 v MI:00
 Date Received: 07/21/2021 v 08:00

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-8

3 atxW o atex

3 ethc / : So Hv6 60MD - 3 etals (IC4) - Disscl9e/

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Bcxn, Disscl9e/	0.50		04060	0401g	d L\$			072021 06 C2:13	C

3 ethc / : So Hv6 6010B - 3 etals (IC43 S) - Disscl9e/

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Tsenid, Disscl9e/	0.0M		04050	0400C2	d L\$			072021 06 Cg:5g	C
lxcn, Disscl9e/	11		040	0409	d L\$			072021 06 C9:1C	00

Client Sample Results

Int Gs noyct Au l ot yai Pt Q It u
r jo/nuc: r iPt GmPd d ot .

Job ID: 705-1392-C

Client Sample ID: PT3 -4F-M-07-18-UNr -M

Lab Sample ID: 705-18HA-M

Date Ccldete/ : 0721821v MI:00

3 atxiW o atex

Date Redeie/ : 0721021v 08:00

3 ethc/ : So Hv6 60MD - 3 etals (IC4)

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Bcxn	0.v6		04060	0401g	d L\$		0720916 00:03	0720916 09:20	C

3 ethc/ : So Hv6 6010B - 3 etals (IC43 S) - Fctal Redc9exable

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Txenid	0.0v0		040050	040002	d L\$		0720916 00:00	0720916 07:27	C
lxcn	6v		040	0409	d L\$		0720916 00:00	0720916 09:06	00

Client Sample Results

Client Sample ID: PT3 -4F-M-07-18-r IL-MA
 Date Collected: 07/21/2021 v 08:00
 Date Received: 07/21/2021 v 08:00

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-MM

3 atxW o atex

3 ethc / : So Hv6 60MD - 3 etals (IC4) - Disscl9e/

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Bcxn, Disscl9e/	0.46		0460	0401g	d L\$			072021 06:21	C

3 ethc / : So Hv6 6010B - 3 etals (IC43 S) - Disscl9e/

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Txenid, Disscl9e/	0.011		04050	04002	d L\$			072021 06:59	C
lxcn, Disscl9e/	5A		0460	0409	d L\$			072021 06:11	00

Client Sample Results

Client Sample ID: PT3 -4F-M-07-18-UNr -MA
 Date Collected: 07/21/2021 v 08:00
 Date Received: 07/21/2021 v 08:00

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-M
 3 atxW o atex

3 ethc/ : So Hv6 60MD - 3 etals (IC4)

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Bcxn	0.v6		04060	0401g	d L\$		07\$0\$16 00:03	07\$0\$16 09:22	C

3 ethc/ : So Hv6 6010B - 3 etals (IC4B S) - Fctal Redc9exable

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Txenid	0.08A		040050	0400C2	d L\$		07\$0\$16 00:00	07\$0\$16 07:59	C
lxcn	M10		040	0409	d L\$		07\$0\$16 00:00	07\$0\$16 09:05	00

Client Sample Results

Client Sample ID: PT3 -4F-M-07-18-r IL-M5
 Date Collected: 07/21/2021 v 08:00
 Date Received: 07/21/2021 v 08:00

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-MA

3 atxW o atex

3 ethc / : So Hv6 60MD - 3 etals (IC4) - Disscl9e/

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Bcxn, Disscl9e/	0.AM		0460	041g	d L\$			072016 C2:65	C

3 ethc / : So Hv6 6010B - 3 etals (IC43 S) - Disscl9e/

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Txenid, Disscl9e/	0.010		04050	040C2	d L\$			072016 C7:00	C
lxcn, Disscl9e/	75		040	0409	d L\$			072016 C7:15	00

Client Sample Results

Client Sample ID: PT3 -4F-M-07-18-UNr -M5
 Date Collected: 07/21/2021 v 08:00
 Date Received: 07/21/2021 v 08:00

Job ID: 705-1392-C

Lab Sample ID: 705-18HA-M
 3 atxW o atex

3 ethc/ : So Hv6 60MD - 3 etals (IC4)

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Bcxn	0.46		04060	0401g	d L\$		072021 08:03	072021 08:2g	C

3 ethc/ : So Hv6 6010B - 3 etals (IC43 S) - Fctal Redc9exable

Tnalyte	Result	Qualifiex	RL	3 DL	Unit	D	4xepaxe/	Tnalyze/	Dil r ad
Tsenid	0.08H		04050	04002	d L\$		072021 08:03	072021 08:00	C
lxcn	M60		040	0409	d L\$		072021 08:03	072021 08:07	00

QC Sample Results

Int Gs noyct Au l ot yaiPt Q It u
r jo/nucle: r iPt GmPd d ot B

Job ID: 705-1392-C

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-5670/1-A
Matrix: Water
Analysis Batch: 5777

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 5670

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Nojot	. D		0460	0401g	d L\$		072036 C2:03	072036 C5:55	C

Lab Sample ID: LCS 705-5670/2-A
Matrix: Water
Analysis Batch: 5777

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 5670

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Nojot	C400	048g1		d L\$		3g	90 - C10

Lab Sample ID: 705-2983-6 MS
Matrix: Water
Analysis Batch: 5777

Client Sample ID: HAM-PT-07-07-29-UNF-PM
Prep Type: Total/NA
Prep Batch: 5670

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Nojot	045g		C400	C452		d L\$		37	75 - C15

Lab Sample ID: 705-2983-6 MSD
Matrix: Water
Analysis Batch: 5777

Client Sample ID: HAM-PT-07-07-29-UNF-PM
Prep Type: Total/NA
Prep Batch: 5670

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Nojot	045g		C400	C455		d L\$		33	75 - C15	C	10

Lab Sample ID: MB 705-5676/1-A
Matrix: Water
Analysis Batch: 5763

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Nojot , DeyoivnB	. D		0460	0401g	d L\$			072036 C2:03	C

Lab Sample ID: LCS 705-5676/2-A
Matrix: Water
Analysis Batch: 5763

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Nojot , DeyoivnB	C400	C40C		d L\$		C0C	90 - C10

Lab Sample ID: LCSD 705-5676/3-A
Matrix: Water
Analysis Batch: 5763

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Nojot , DeyoivnB	C400	04893		d L\$		33	90 - C10	1	10

Eajof y AGPt

QC Sample Results

Internet Gateway
rjoh/nucl: r iPt GmPd d ot B

Job ID: 705-1392-C

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-5665/1-A
Matrix: Water
Analysis Batch: 5844

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 5665

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ajynt a	. D		04050	040C2	d L\$		07\$0\$16 00:00	07\$0\$16 C7:22	C
Ijot	. D		04060	040C9	d L\$		07\$0\$16 00:00	07\$0\$16 C7:22	C

Lab Sample ID: LCS 705-5665/2-A
Matrix: Water
Analysis Batch: 5844

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 5665

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Ajynt a	04000	040975		d L\$		97	90 - C10
Ijot	0400	0402		d L\$		002	90 - C10

Lab Sample ID: 705-2983-10 MS
Matrix: Water
Analysis Batch: 5844

Client Sample ID: HAM-PT-14-07-29-UNF-12
Prep Type: Total Recoverable
Prep Batch: 5665

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Ajynt a	04067	J	04000	04C15		d L\$		79	75 - C15

Lab Sample ID: 705-2983-10 MS
Matrix: Water
Analysis Batch: 5844

Client Sample ID: HAM-PT-14-07-29-UNF-12
Prep Type: Total Recoverable
Prep Batch: 5665

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Ijot	g6		0400	g64C	6	d L\$		C	75 - C15

Lab Sample ID: 705-2983-10 MSD
Matrix: Water
Analysis Batch: 5844

Client Sample ID: HAM-PT-14-07-29-UNF-12
Prep Type: Total Recoverable
Prep Batch: 5665

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Ajynt a	04067	J	04000	04C1C	FC	d L\$		76	75 - C15	2	10

Lab Sample ID: 705-2983-10 MSD
Matrix: Water
Analysis Batch: 5844

Client Sample ID: HAM-PT-14-07-29-UNF-12
Prep Type: Total Recoverable
Prep Batch: 5665

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Ijot	g6		0400	gg45	6	d L\$		12g	75 - C15	6	10

Lab Sample ID: MB 705-5674/1-A
Matrix: Water
Analysis Batch: 5845

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ajynt a, DeyoivnB	. D		04050	040C2	d L\$			07\$0\$16 Cg:60	C
Ijot , DeyoivnB	. D		04060	040C9	d L\$			07\$0\$16 Cg:60	C

Eajof y AGPt

QC Sample Results

Int Gs noyct Au l ot yaiPt Q It u
r jo/nucle: r iPt GmPd d ot B

Job ID: 705-1392-C

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: LCS 705-5674/2-A					Client Sample ID: Lab Control Sample						
Matrix: Water					Prep Type: Dissolved						
Analysis Batch: 5845											
			Spike	LCS	LCS				%Rec		
Analyte			Added	Result	Qualifier	Unit	D	%Rec	Limits		
Ajynt a, DeyoivnB			0400	04031	C	d L\$		31	90 - C10		
Ijot , DeyoivnB			040	040		d L\$		000	90 - C10		

Lab Sample ID: LCSD 705-5674/3-A					Client Sample ID: Lab Control Sample Dup						
Matrix: Water					Prep Type: Dissolved						
Analysis Batch: 5845											
			Spike	LCSD	LCSD				%Rec		RPD
Analyte			Added	Result	Qualifier	Unit	D	%Rec	Limits	RPD	Limit
Ajynt a, DeyoivnB			0400	040326		d L\$		32	90 - C10	C	10
Ijot , DeyoivnB			040	04019		d L\$		32	90 - C10	9	10

Lab Chronicle

Client: Geosyntec Consultants Inc
 j /o scthrte: j lant d aA onB

Job ID: 705-126P-r

Client Sample ID: HAM-PT-13-13-07-4IL-AM

Lab Sample ID: 31F-0758-x

Date Collecte/ : 13272R17:1F

MatriW d ater

Date v ecei9e/ : 13212R17:11

Prep Type	Batch Type	Batch Metho/	v un	Dilution 4actor	Batch Number	Analyst	Lab	Prepare/ or Analyze/
Dissol9eB	3nalysis	E0r 0D		r	57EP	D3T	LL v 3v4	07HPOHp r P:r 7
Dissol9eB	3nalysis	E010T		r	56p5	3D	LL v 3v4	07HPOHp r EpE

Client Sample ID: HAM-PT-13-13-07-UN4-AM

Lab Sample ID: 31F-0758-0

Date Collecte/ : 13272R17:1F

MatriW d ater

Date v ecei9e/ : 13212R17:11

Prep Type	Batch Type	Batch Metho/	v un	Dilution 4actor	Batch Number	Analyst	Lab	Prepare/ or Analyze/
votalHR3	j /eN	P0r 03			5E70	T4	LL v 3v4	07HPOHp rr:r 2
votalHR3	3nalysis	E0r 0D		r	5777	D3T	LL v 3v4	07HPOHp r Er 5
votal 8 eco9e/able	j /eN	P0053			5EE5	T4	LL v 3v4	07HPOHp rr:rr
votal 8 eco9e/able	3nalysis	E010T		r	56pp	3D	LL v 3v4	07HPOHp r 7:pp

Client Sample ID: HAM-PT-xR-13-07-4IL-AM

Lab Sample ID: 31F-0758-8

Date Collecte/ : 13272R17:1F

MatriW d ater

Date v ecei9e/ : 13212R17:11

Prep Type	Batch Type	Batch Metho/	v un	Dilution 4actor	Batch Number	Analyst	Lab	Prepare/ or Analyze/
Dissol9eB	3nalysis	E0r 0D		r	57EP	D3T	LL v 3v4	07HPOHp r P:10
Dissol9eB	3nalysis	E010T		r	56p5	3D	LL v 3v4	07HPOHp r Ep2
Dissol9eB	3nalysis	E010T		r 0	56p5	3D	LL v 3v4	07HPOHp r 6:1P

Client Sample ID: HAM-PT-xR-13-07-UN4-AM

Lab Sample ID: 31F-0758-R

Date Collecte/ : 13272R17:1F

MatriW d ater

Date v ecei9e/ : 13212R17:11

Prep Type	Batch Type	Batch Metho/	v un	Dilution 4actor	Batch Number	Analyst	Lab	Prepare/ or Analyze/
votalHR3	j /eN	P0r 03			5E70	T4	LL v 3v4	07HPOHp rr:r 2
votalHR3	3nalysis	E0r 0D		r	5777	D3T	LL v 3v4	07HPOHp r E:1p
votal 8 eco9e/able	j /eN	P0053			5EE5	T4	LL v 3v4	07HPOHp rr:rr
votal 8 eco9e/able	3nalysis	E010T		r	56pp	3D	LL v 3v4	07HPOHp r 7:pE
votal 8 eco9e/able	j /eN	P0053			5EE5	T4	LL v 3v4	07HPOHp rr:rr
votal 8 eco9e/able	3nalysis	E010T		r 0	56pp	3D	LL v 3v4	07HPOHp r 6:1E

Client Sample ID: HAM-PT-13-13-07-4IL-PM

Lab Sample ID: 31F-0758-F

Date Collecte/ : 13272Rx5:R8

MatriW d ater

Date v ecei9e/ : 13212R17:11

Prep Type	Batch Type	Batch Metho/	v un	Dilution 4actor	Batch Number	Analyst	Lab	Prepare/ or Analyze/
Dissol9eB	3nalysis	E0r 0D		r	57EP	D3T	LL v 3v4	07HPOHp r P:1P
Dissol9eB	3nalysis	E010T		r	56p5	3D	LL v 3v4	07HPOHp r E:5r

Lu/ofins 3tlanta

Lab Chronicle

Client: Geosyntec Consultants Inc
 j /o Scthrte: j lant d aA onB

Job ID: 705-126P-r

Client Sample ID: HAM-PT-13-13-07-UN4-PM

Lab Sample ID: 31F-0758-6

Date Collecte/ : 132720R x5:R8

MatriW d ater

Date v ecei9e/ : 132120R 17:11

Prep Type	Batch Type	Batch Metho/	v un	Dilution 4actor	Batch Number	Analyst	Lab	Prepare/ or Analyze/
votalHR3	j /eN	P0r 03			5E70	T4	LL v 3v4	07HPOHp rr:r 2
votalHR3	3nalysis	E0r 0D		r	5777	D3T	LL v 3v4	07HPOHp r E:0r
votal 8 eco9e/able	j /eN	P0053			5EE5	T4	LL v 3v4	07HPOHp rr:rr
votal 8 eco9e/able	3nalysis	E010T		r	56pp	3D	LL v 3v4	07HPOHp r 7:p2

Client Sample ID: HAM-PT-xR-13-07-4IL-PM

Lab Sample ID: 31F-0758-3

Date Collecte/ : 132720R x5:88

MatriW d ater

Date v ecei9e/ : 132120R 17:11

Prep Type	Batch Type	Batch Metho/	v un	Dilution 4actor	Batch Number	Analyst	Lab	Prepare/ or Analyze/
Dissol9eB	3nalysis	E0r 0D		r	57EP	D3T	LL v 3v4	07HPOHp r P:1E
Dissol9eB	3nalysis	E010T		r	56p5	3D	LL v 3v4	07HPOHp r E:5P
Dissol9eB	3nalysis	E010T		r 0	56p5	3D	LL v 3v4	07HPOHp r 7:10

Client Sample ID: HAM-PT-xR-13-07-UN4-PM

Lab Sample ID: 31F-0758-5

Date Collecte/ : 132720R x5:88

MatriW d ater

Date v ecei9e/ : 132120R 17:11

Prep Type	Batch Type	Batch Metho/	v un	Dilution 4actor	Batch Number	Analyst	Lab	Prepare/ or Analyze/
votalHR3	j /eN	P0r 03			5E70	T4	LL v 3v4	07HPOHp rr:r 2
votalHR3	3nalysis	E0r 0D		r	5777	D3T	LL v 3v4	07HPOHp r E:17
votal 8 eco9e/able	j /eN	P0053			5EE5	T4	LL v 3v4	07HPOHp rr:rr
votal 8 eco9e/able	3nalysis	E010T		r	56pp	3D	LL v 3v4	07HPOHp r 7:5E
votal 8 eco9e/able	j /eN	P0053			5EE5	T4	LL v 3v4	07HPOHp rr:rr
votal 8 eco9e/able	3nalysis	E010T		r 0	56pp	3D	LL v 3v4	07HPOHp r 6:0P

Client Sample ID: HAM-PT-xR-13-07-4IL-x0

Lab Sample ID: 31F-0758-7

Date Collecte/ : 132720R x0:11

MatriW d ater

Date v ecei9e/ : 132120R 17:11

Prep Type	Batch Type	Batch Metho/	v un	Dilution 4actor	Batch Number	Analyst	Lab	Prepare/ or Analyze/
Dissol9eB	3nalysis	E0r 0D		r	57EP	D3T	LL v 3v4	07HPOHp r P:12
Dissol9eB	3nalysis	E010T		r	56p5	3D	LL v 3v4	07HPOHp r E:5E
Dissol9eB	3nalysis	E010T		r 0	56p5	3D	LL v 3v4	07HPOHp r 6:1r

Client Sample ID: HAM-PT-xR-13-07-UN4-x0

Lab Sample ID: 31F-0758-x1

Date Collecte/ : 132720R x0:11

MatriW d ater

Date v ecei9e/ : 132120R 17:11

Prep Type	Batch Type	Batch Metho/	v un	Dilution 4actor	Batch Number	Analyst	Lab	Prepare/ or Analyze/
votalHR3	j /eN	P0r 03			5E70	T4	LL v 3v4	07HPOHp rr:r 2
votalHR3	3nalysis	E0r 0D		r	5777	D3T	LL v 3v4	07HPOHp r E:P0
votal 8 eco9e/able	j /eN	P0053			5EE5	T4	LL v 3v4	07HPOHp rr:rr
votal 8 eco9e/able	3nalysis	E010T		r	56pp	3D	LL v 3v4	07HPOHp r 7:P7

Lu/ofins 3tlanta

Lab Chronicle

Client: Geosyntec Consultants Inc
 j /o scthrte: j lant d aA onB

Job ID: 705-126P-r

Client Sample ID: HAM-PT-xR-13-07-UN4-x0

Lab Sample ID: 31F-0758-x1

Date Collecte/ : 132720R x0:11

MatriW d ater

Date v ecei9e/ : 1328120R 17:11

Prep Type	Batch Type	Batch Metho/	v un	Dilution 4actor	Batch Number	Analyst	Lab	Prepare/ or Analyze/
votal 8 eco9e/able	j /eN	P0053			5EE5	T4	LL v 3v4	07HPOHp rr:rr
votal 8 eco9e/able	3nalysis	E010T		r 0	56pp	3D	LL v 3v4	07HPOHp r6:r p

Client Sample ID: HAM-PT-xR-13-07-4IL-x8

Lab Sample ID: 31F-0758-xx

Date Collecte/ : 132720R x8:11

MatriW d ater

Date v ecei9e/ : 1328120R 17:11

Prep Type	Batch Type	Batch Metho/	v un	Dilution 4actor	Batch Number	Analyst	Lab	Prepare/ or Analyze/
Dissol9eB	3nalysis	E0r 0D		r	57EP	D3T	LL v 3v4	07HPOHp r P:p1
Dissol9eB	3nalysis	E010T		r	56p5	3D	LL v 3v4	07HPOHp r E:56
Dissol9eB	3nalysis	E010T		r 0	56p5	3D	LL v 3v4	07HPOHp r 7:11

Client Sample ID: HAM-PT-xR-13-07-UN4-x8

Lab Sample ID: 31F-0758-x0

Date Collecte/ : 132720R x8:11

MatriW d ater

Date v ecei9e/ : 1328120R 17:11

Prep Type	Batch Type	Batch Metho/	v un	Dilution 4actor	Batch Number	Analyst	Lab	Prepare/ or Analyze/
votalIR3	j /eN	P0r 03			5E70	T4	LL v 3v4	07HPOHp rr:r 2
votalIR3	3nalysis	E0r 0D		r	5777	D3T	LL v 3v4	07HPOHp r E:PP
votal 8 eco9e/able	j /eN	P0053			5EE5	T4	LL v 3v4	07HPOHp rr:rr
votal 8 eco9e/able	3nalysis	E010T		r	56pp	3D	LL v 3v4	07HPOHp r 7:56
votal 8 eco9e/able	j /eN	P0053			5EE5	T4	LL v 3v4	07HPOHp rr:rr
votal 8 eco9e/able	3nalysis	E010T		r 0	56pp	3D	LL v 3v4	07HPOHp r6:05

Client Sample ID: HAM-PT-xR-13-07-4IL-xF

Lab Sample ID: 31F-0758-x8

Date Collecte/ : 132720R xF:11

MatriW d ater

Date v ecei9e/ : 1328120R 17:11

Prep Type	Batch Type	Batch Metho/	v un	Dilution 4actor	Batch Number	Analyst	Lab	Prepare/ or Analyze/
Dissol9eB	3nalysis	E0r 0D		r	57EP	D3T	LL v 3v4	07HPOHp r P:p5
Dissol9eB	3nalysis	E010T		r	56p5	3D	LL v 3v4	07HPOHp r 7:00
Dissol9eB	3nalysis	E010T		r 0	56p5	3D	LL v 3v4	07HPOHp r 7:15

Client Sample ID: HAM-PT-xR-13-07-UN4-xF

Lab Sample ID: 31F-0758-xR

Date Collecte/ : 132720R xF:11

MatriW d ater

Date v ecei9e/ : 1328120R 17:11

Prep Type	Batch Type	Batch Metho/	v un	Dilution 4actor	Batch Number	Analyst	Lab	Prepare/ or Analyze/
votalIR3	j /eN	P0r 03			5E70	T4	LL v 3v4	07HPOHp rr:r 2
votalIR3	3nalysis	E0r 0D		r	5777	D3T	LL v 3v4	07HPOHp r E:PE
votal 8 eco9e/able	j /eN	P0053			5EE5	T4	LL v 3v4	07HPOHp rr:rr
votal 8 eco9e/able	3nalysis	E010T		r	56pp	3D	LL v 3v4	07HPOHp r6:00
votal 8 eco9e/able	j /eN	P0053			5EE5	T4	LL v 3v4	07HPOHp rr:rr
votal 8 eco9e/able	3nalysis	E010T		r 0	56pp	3D	LL v 3v4	07HPOHp r6:07

Lu/ofins 3tlanta

Client: Geosyntec Consultants Inc
j /o Section: j lant d aA A onB

Job ID: 705-126P-r

Laboratory v eferences:

LLv 3v4 = Lu/ofins 3tlanta, P060 j /esiBential D/, 3tlanta, G3 P0Pp0, vL4 (770)p57-6r 77

1
2
3
4
5
6
7
8
9
10
11
12
13

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-2983-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

1
2
3
4
5
6
7
8
9
10
11
12
13

Method Summary

Int Gs noyct Au l ot yaiPt Q It u
r jo/nucH: r iPt GmPd d ot W

Job ID: 705-1392-C

Method	Method Description	Protocol	Laboratory
6000D	MnCy (II r)	H8 946	EET ATL
6010B	MnCy (II r 3MH)	H8 946	EET ATL
2005A	r jnpPjPot , ToCi RnuovnjPbin oj DeyoivnWMnCy	H8 946	EET ATL
2000A	r jnpPjPot , ToCi MnCy	H8 946	EET ATL

Protocol References:

H8 946 = "TnyGMnBoVy Foj EvPlaPa g Hoiw8 PyG, r hcyuPIS hnd aPi MnBoVy", TheWEVot , Novnd bnj C396 At WIG UpVPay.

Laboratory References:

EET ATL = Eajofa y AGPt Q, 2090 r jnyvmt Gf Dj, AGPt Q, s A 20240, TEL (770)457-9C77

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13

Job ID: 705-18Pr -j

EuSofins 3 tlanda
7/31/2024

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-2983-1

Login Number: 2983

List Source: Eurofins Atlanta

List Number: 1

Creator: Pomuti, Carmen

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	N/A	Not present
Sample custody seals, if present, are intact.	N/A	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	N/A	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	N/A	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT



ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 7/31/2024 8:41:36 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-3073-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
7/31/2024 8:41:36 PM



Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	11
Lab Chronicle	13
Certification Summary	14
Method Summary	15
Sample Summary	16
Receipt Checklists	17
End Of Report	18

Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-3073-1

Qualifiers

Metals

Qualifier	Qualifier Description
4	MS, MSD: The analyte present in the original sample is greater than 4 times the matrix spike concentration; therefore, control limits are not applicable.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

[illegible]

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-3073-1

Job ID: 705-3073-1

Eurofins Atlanta

Job Narrative 705-3073-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers and/or narrative comments are included to explain any exceptions, if applicable.

- Matrix QC may not be reported if insufficient sample is provided or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 7/ 0/2024 4:00 PM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 0.8°C.

Metals

Method 020 - Total recoverable: The matrix spike / matrix spike duplicate (MS/MSD) recoveries for preparation batch 705-5829 and analytical batch 705-598 was outside control limits. Sample matrix interference is suspected. The post digestion spike passed.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client Sample ID: HAM-PT-07-07-10-34 F-AM
Date Collected: 07/10/2009 09:55
Date Received: 07/10/2009 86:00

Job ID: 705-1071-3

Lab Sample ID: 705-1071-8

Matrix: Water

Met(od: SW9v6 6080D - Metals)ICP.

AnalzUed	Result	Qualifier	RL	MDL	3 nit	D	Prepared	AnalzUed	Dil Fac
Boron	0.62		0.000	0.004	5.6rg		07r13r. d 0L:d1	07r13r. d 3d:38	3

Met(od: SW9v6 6020B - Metals)ICP/MS. - Total Recoherable

AnalzUed	Result	Qualifier	RL	MDL	3 nit	D	Prepared	AnalzUed	Dil Fac
Arsenic	0.89		0.0050	0.0031	5.6rg		07r13r. d 0L:d1	07r13r. d 35:d1	3
Iron	18		0.000	0.0038	5.6rg		07r13r. d 0L:d1	07r13r. d 35:d1	3

Client Sample Results

Client Sample ID: HAM-PT-07-07-10-FIL-AM
Date Collected: 07/10/2v 09:55
Date Received: 07/10/2v 86:00

Job ID: 705-1071-3

Lab Sample ID: 705-1071-2

Matrix: Water

Met(od: SW9v6 6080D - Metals)ICP. - Dissolhed

Analzte	Result	Qualifier	RL	MDL	3 nit	D	Prepared	AnalzUed	Dil Fac
Boron, Dissolhed	0y57		0r0d0	0r0. 4	S 6rg			07r13r. d 35:.. 4	3

Met(od: SW9v6 6020B - Metals)ICP/MS. - Dissolhed

Analzte	Result	Qualifier	RL	MDL	3 nit	D	Prepared	AnalzUed	Dil Fac
Arsenic, Dissolhed	0y0N8		0r0050	0r0031	S 6rg			07r13r. d 3d:.. 5	3
Iron, Dissolhed	82		0r0d0	0r038	S 6rg			07r13r. d 3d:.. 5	3

Client Sample Results

Client Name: **Geoscientific**
 Project: **u2e/ cSSoi H**

Job ID: 705-1071-3

Client Sample ID: HAM-PT-8v-07-10-34 F-AM

Lab Sample ID: 705-1071-1

Date Collected: 07/10/2v 0N:05

Matrix: **Water**

Date Received: 07/10/2v 86:00

Met(od: SW9v6 6080D - Metals)ICP.

Analzte	Result	Qualifier	RL	MDL	3 nit	D	Prepared	AnalzUed	Dil Fac
Boron	0y61		0r0d0	0r0. 4	S 6rg		07r13r. d 0L:d1	07r13r. d 3d:1d	3

Met(od: SW9v6 6020B - Metals)ICP/MS. - Total Recoherable

Analzte	Result	Qualifier	RL	MDL	3 nit	D	Prepared	AnalzUed	Dil Fac
Arsenic	0y051		0r0050	0r0031	S 6rg		07r13r. d 0L:d1	07r13r. d 35:1.	3
Iron	25		0r0d0	0r038	S 6rg		07r13r. d 0L:d1	07r13r. d 35:1.	3

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13

Job ID: 705-1071-3

Lab Sample ID: 705-1071-v

Matrix: Water

5

5

6

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1071-8

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-5830/1-A
Matrix: Water
Analysis Batch: 5965

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 5830

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	ND		0.040	0.026	mg/L		07/18/24 0, :41	07/18/24 84:82	8

Lab Sample ID: LCS 705-5830/2-A
Matrix: Water
Analysis Batch: 5965

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 5830

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	8.00	8.06		mg/L		806	v0 - 820

Lab Sample ID: 705-3073-1 MS
Matrix: Water
Analysis Batch: 5965

Client Sample ID: HAM-PT-07-07-30-UNF-AM
Prep Type: Total/NA
Prep Batch: 5830

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	0.62		8.00	8.6,		mg/L		807	75 - 825

Lab Sample ID: 705-3073-1 MSD
Matrix: Water
Analysis Batch: 5965

Client Sample ID: HAM-PT-07-07-30-UNF-AM
Prep Type: Total/NA
Prep Batch: 5830

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron	0.62		8.00	8.6v		mg/L		806	75 - 825	8	20

Lab Sample ID: MB 705-5893/1-A
Matrix: Water
Analysis Batch: 5965

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron3Dissol9ed	ND		0.040	0.026	mg/L			07/18/24 85:88	8

Lab Sample ID: LCS 705-5893/2-A
Matrix: Water
Analysis Batch: 5965

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron3Dissol9ed	8.00	8.01		mg/L		801	v0 - 820

Lab Sample ID: LCSD 705-5893/3-A
Matrix: Water
Analysis Batch: 5965

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron3Dissol9ed	8.00	8.02		mg/L		802	v0 - 820	8	20

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1071-8

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-5829/1-A

Matrix: Water

Analysis Batch: 5986

Client Sample ID: Method Blank

Prep Type: Total Recoverable

Prep Batch: 5829

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	ND		0.0050	0.0081	mg/L		07/18/24 0, :41	07/18/24 85:27	8
Iron	ND		0.040	0.08v	mg/L		07/18/24 0, :41	07/18/24 85:27	8

Lab Sample ID: LCS 705-5829/2-A

Matrix: Water

Analysis Batch: 5986

Client Sample ID: Lab Control Sample

Prep Type: Total Recoverable

Prep Batch: 5829

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.800	0.0v, 8		mg/L		v,	v0 - 820
Iron	8.00	0., 17		mg/L		, 4	v0 - 820

Lab Sample ID: 705-3073-3 MS

Matrix: Water

Analysis Batch: 5986

Client Sample ID: HAM-PT-14-07-30-UNF-AM

Prep Type: Total Recoverable

Prep Batch: 5829

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.051		0.800	0.81,		mg/L		v5	75 - 825
Iron	25		8.00	25.4	4	mg/L		62	75 - 825

Lab Sample ID: 705-3073-3 MSD

Matrix: Water

Analysis Batch: 5986

Client Sample ID: HAM-PT-14-07-30-UNF-AM

Prep Type: Total Recoverable

Prep Batch: 5829

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic	0.051		0.800	0.815		mg/L		v2	75 - 825	2	20
Iron	25		8.00	25.2	4	mg/L		17	75 - 825	8	20

Lab Sample ID: MB 705-5859/1-A

Matrix: Water

Analysis Batch: 5987

Client Sample ID: Method Blank

Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic3Dissol9ed	ND		0.0050	0.0081	mg/L			07/18/24 84:8v	8
Iron3Dissol9ed	ND		0.040	0.08v	mg/L			07/18/24 84:8v	8

Lab Sample ID: LCS 705-5859/2-A

Matrix: Water

Analysis Batch: 5987

Client Sample ID: Lab Control Sample

Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic3Dissol9ed	0.800	0.0, 02		mg/L		, 0	v0 - 820
Iron3Dissol9ed	8.00	0., 44		mg/L		, 4	v0 - 820

Lab Sample ID: LCSD 705-5859/3-A

Matrix: Water

Analysis Batch: 5987

Client Sample ID: Lab Control Sample Dup

Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic3Dissol9ed	0.800	0.0v, 8		mg/L		v,	v0 - 820	8	20
Iron3Dissol9ed	8.00	0., 12		mg/L		, 1	v0 - 820	8	20

Eurofins Atlanta

Lab Chronicle

Client: Geosyntec Consultants Inc
6 Røctj/ ite: 6 lant SaH Honm

Job ID: 705-1071-2

Client Sample ID: HAM-PT-13-13-01-7 4 F-AM
Date Collected: 13/01/2R 1v:55
Date 9 eceiyed: 13/01/2R 8B:11

Lab Sample ID: 315-0130-8
Matrix: Water

Prep Tspe	uatch Tspe	uatch Method	9 Nn	DilNtion Factor	uatch 4 Nmber	Analstz	Lab	Prepared or AnalsUed
EotaljL A	6 Rød	1020A			5B10	/ A	33 E AET	07j12jv4 09:41
EotaljL A	Analysis	p020D		2	59p5	D/	33 E AET	07j12jv4 24:2B
Eotal NecoRøPøble	6 Rød	1005A			5Bv9	/ A	33 E AET	07j12jv4 09:41
Eotal NecoRøPøble	Analysis	p0v08		2	59Bp	AD	33 E AET	07j12jv4 25:41

Client Sample ID: HAM-PT-13-13-01-FIL-AM
Date Collected: 13/01/2R 1v:55
Date 9 eceiyed: 13/01/2R 8B:11

Lab Sample ID: 315-0130-2
Matrix: Water

Prep Tspe	uatch Tspe	uatch Method	9 Nn	DilNtion Factor	uatch 4 Nmber	Analstz	Lab	Prepared or AnalsUed
DissolRøM	Analysis	p020D		2	59p5	D/	33 E AET	07j12jv4 25:vp
DissolRøM	Analysis	p0v08		2	59B7	AD	33 E AET	07j12jv4 24:v5

Client Sample ID: HAM-PT-8R-13-01-7 4 F-AM
Date Collected: 13/01/2R 16:15
Date 9 eceiyed: 13/01/2R 8B:11

Lab Sample ID: 315-0130-0
Matrix: Water

Prep Tspe	uatch Tspe	uatch Method	9 Nn	DilNtion Factor	uatch 4 Nmber	Analstz	Lab	Prepared or AnalsUed
EotaljL A	6 Rød	1020A			5B10	/ A	33 E AET	07j12jv4 09:41
EotaljL A	Analysis	p020D		2	59p5	D/	33 E AET	07j12jv4 24:14
Eotal NecoRøPøble	6 Rød	1005A			5Bv9	/ A	33 E AET	07j12jv4 09:41
Eotal NecoRøPøble	Analysis	p0v08		2	59Bp	AD	33 E AET	07j12jv4 25:1v

Client Sample ID: HAM-PT-8R-13-01-FIL-AM
Date Collected: 13/01/2R 16:15
Date 9 eceiyed: 13/01/2R 8B:11

Lab Sample ID: 315-0130-R
Matrix: Water

Prep Tspe	uatch Tspe	uatch Method	9 Nn	DilNtion Factor	uatch 4 Nmber	Analstz	Lab	Prepared or AnalsUed
DissolRøM	Analysis	p020D		2	59p5	D/	33 E AET	07j12jv4 25:v9
DissolRøM	Analysis	p0v08		2	59B7	AD	33 E AET	07j12jv4 24:v7

Laborators 9 eferencez:
33 E AET f 3 uRøøns Atlanta, 10B0 6Røsinental DP, Atlanta, GA 10140, E3T (770)457-B277

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-3073-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

1
2
3
4
5
6
7
8
9
10
11
12
13

Method Summary

92
Di en l ot G e s 9 oi t y 2 i e l i s
u a P s e j G : u 2 i e / c S S o i H

Job ID: 705-1071-3

Method	Method Description	Protocol	Laboratory
8030D	4 l e 2 69 u M	j m d V 8	(() E) T
80A0L	4 l e 2 69 u r 4 j M	j m d V 8	(() E) T
1005E	u a B c a e o i p) o e 2, l s o R a b 2 o a D C t o 2 R H 4 l e 2	j m d V 8	(() E) T
1030E	u a B c a e o i p) o e 2 4 l e 2	j m d V 8	(() E) T

Protocol References:

j m d V 8 v =) l t e 4 l e o H t h o a (R c 2 y c e F j o 2 H m c t e p u " G G c 2 9 " l S G c 2 4 l e o H t = p) " G H (H a o i p g o R S b l a 3 N d 8 E i H l e U B h t e t .

Laboratory References:

(() E) T v (y a o f C t E e i e p 10 d 0 u a t C l i e 6 2 D a p E e i e p n E 101 V 0 p) (T 6 7 7 0 M 6 7 - d 3 7 7

Sample Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1071-8

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-1071-8	HAM-PT-07-07-10-34 F-AM	L ater	07/10/2024 09:55	07/10/2024 8:00
705-1071-W	HAM-PT-07-07-10-FIN-AM	L ater	07/10/2024 09:55	07/10/2024 8:00
705-1071-1	HAM-PT-82-07-10-34 F-AM	L ater	07/10/2024 06:05	07/10/2024 8:00
705-1071-2	HAM-PT-82-07-10-FIN-AM	L ater	07/10/2024 06:05	07/10/2024 8:00

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-3073-1

Login Number: 3073

List Source: Eurofins Atlanta

List Number: 1

Creator: Woods, Autumn

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	N/A	
Sample custody seals, if present, are intact.	N/A	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	False	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	N/A	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT



ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 7/31/2024 8:23:17 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-3104-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
7/31/2024 8:23:17 PM

Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	8
Client Sample Results	9
QC Sample Results	17
Lab Chronicle	19
Certification Summary	21
Method Summary	22
Sample Summary	23
Receipt Checklists	24
End Of Report	25



Definitions/Glossary

Job ID: 705-310C-1

I iet Gs noyct Au l ot yaiPt Q It u
r jo/nuCHe: r iPt GnPd d ot 4

Qualifiers

Metals

Qualifier	Qualifier Description
C	MH, MHD: Thn Pt PtcA pjnynt G An ojePt yPd pin er gjnPaj BPT C G ny An d Pex ypan uot unt PPT; Anjnfojn, uot Poi id Pjn t oG PpiaPbin.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	LeG4 at 4nj An "D" uoiad t G 4nygt PG BPGAn jnyaiGy jnpojG4 ot P 4jc wneghGPyey
%R	r njunt GRnuovnjc
I FL	I ot Gey Fjnn Lqael
I FU	I oiot c Fojd eg Ut G
I NF	I ot Gey No Fjnn Lqael
DER	DapiaPG Ejjoj RPQ (t ojd Pten4 PbyoiaG 4fnjnt un)
DéFPu	DéaGt FPUg
DL	DnGut Lel G(DoD\$OE)
DL, RA, RE, IN	It 4ePgy P DéaGt , Rn-Pt Picye, Rn-nxGPuGt , oj P44Gt Pt It G d nGyPt ot Pt Picye of Gn yPd pin
DLI	Dnuget Lnvni I ot unt PPT (RP4euhnd eyGc)
EDL	EyG P44 DnGut Lel G(Dexé)
LOD	Lel Gof DnGut (DoD\$OE)
LOQ	Lel Gof QaPt GPT (DoD\$OE)
MI L	Er Ajnuod d nt 4n4 "MPxel ad I ot Gd é Pt GLnvni"
MDA	Méel ad DnGutbin AuG (RP4euhnd eyGc)
MDI	Méel ad DnGutbin I ot unt PPT (RP4euhnd eyGc)
MDL	MnG4 DnGut Lel G
ML	Méel ad Lnvni (Dexé)
Mr N	MoyG jobPbin Nad bnj
MQL	MnG4 QaPt GPT Lel G
NI	NoG PtuaiPG4
ND	NoGnG4 PGAn jnpojG g iel Goj MDL oj EDL é yhowt)
NEs	NngPAn SAbynt G
r OH	r oyGAn Sr jnynt G
r QL	r jPuGPI QaPt GPT Lel G
r REH	r jnyad pAn
QI	QaPé I ot Poi
RER	RniPAn Ejjoj RPQ (RP4euhnd eyGc)
RL	RnpojG g Lel G RnqanyG4 Lel G(RP4euhnd eyGc)
Rr D	RniPAn r njunt Gfnjnt un, P d nPyajn of Gn jniPAn 4fnjnt un bnGvnt Gvo poé G
TEF	ToxéE EqaePint GFPuGj (Dexé)
TEQ	ToxéE EqaePint GQaoGt G(Dexé)
TNTI	Too Nad njoay To I oat G

eurolins Equipment Testers

7/31/2024

Chain of Custody Record

Client Information		Sampler: <u>Zain W.</u>		Lab PM: David Fuller / Phone: 770-344-8986		Carrier Tracking No(s):		COC No:		
Client Contact: Kip Gray		Phone: <u>404-434-2074</u>		E-Mail: David.Fuller@et.eurofinsus.com		State of Origin: GA		Page: <u>1</u> of <u>1</u>		
Company: Geosyntec Consultants Inc		PWSID:		Analysis Requested						
Address: 1255 Roberts Blvd, NW Suite 200		Due Date Requested:		Field Filtered Sample (Yes or No) 60100 - Total Boron 60208 - Total Arsenic and Iron 60208 - Total Iron and Molybdenum 60100 - Dissolved Boron - Field Filtered (FF) 60208 - Dissolved Arsenic and Iron (FF) 60208 - Dissolved Iron and Molybdenum (FF) Total Number of Containers						
City: Kennesaw		TAT Requested (days): RUSH / 1 Day TAT								
State, Zip: GA, 30144		Compliance Project: ☐ Yes ☐ No								
Phone:		Lab Project #: 70500911 (DO NOT REMOVE)								
Email: Kip.Gray@Geosyntec.com		PO #: 100061163								
Project Name: Plant Hammond		Project #: GW6581G		Other: Preservation Codes: D - HNO3						
Task Code: Task Code#:		SSOW#:								
Sample Identification		Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	MATRIX (W=Water, S=Soils, G=Geosolids, ST=Sludge, A=Air)	Special Instructions/Note:				
				Preservation Code:						
HAM-PT-14-07-30-UNF-PM		7-30-24	1740	G	W	NO	NO	X	X	
HAM-PT-14-07-30-FIL-PM		7-30-24	1740	G	W	YES	YES	-	-	
HAM-PT-08-07-30-UNF-PM		7-30-24	1750	G	W	YES	YES	X	X	
HAM-PT-08-07-30-FIL-PM		7-30-24	1750	G	W	YES	YES	-	-	
HAM-PT-07-07-30-UNF-PM		7-30-24	1800	G	W	YES	YES	X	X	
HAM-PT-07-07-30-FIL-PM		7-30-24	1800	G	W	YES	YES	-	-	
HAM-PT-13-07-30-UNF-PM		7-30-24	1810	G	W	YES	YES	X	X	
HAM-PT-13-07-30-FIL-PM		7-30-24	1810	G	W	YES	YES	-	-	
Zw 7/30/24										
Possible Hazard Identification ☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☒ Unknown ☐ Radiological						Sample Disposal (A fee may be assessed if samples are retained longer than 1 month) ☐ Return To Client ☒ Disposal By Lab ☐ Archive For _____ Months				
Deliverable Requested: I, II, III, IV, Other (specify)						Special Instructions/OC Requirements:				
Empty Kit Relinquished by:		Date:		Time:		Method of Shipment: <u>Client</u>				
Relinquished by: <u>[Signature]</u>		Date/Time: <u>7/31/24 7:05</u>		Company:		Received by: <u>[Signature]</u>		Date/Time: <u>7-31-24 7:05</u>		
Relinquished by: <u>[Signature]</u>		Date/Time: <u>7-31-24 9:47</u>		Company:		Received by: <u>Anna Neal</u>		Date/Time: <u>7-31-24 947</u>		
Relinquished by:		Date/Time:		Company:		Received by:		Date/Time:		
Custody Seals Intact: ☐ Yes ☐ No		Custody Seal No.:		Cooler Temperature(s) °C and Other Remarks: <u>#2665 4.3°C</u>						

7/31/2024

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-3104-1

Job ID: 705-3104-1

Eurofins Atlanta

Job Narrative 705- 104-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers and/or narrative comments are included to explain any exceptions, if applicable.

- Matrix QC may not be reported if insufficient sample is provided or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 7/ 1/2024 9:47 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 4. °C.

Receipt Exceptions

The reference method requires samples to be preserved to a p of 2. The following samples were received at a p of 2, , and 2, respectively: AM-PT-08-07- 0-UN -PM (705- 104-), AM-PT-07-07- 0-UN -PM (705- 104-5) and AM-PT-1 -07- 0-UN -PM (705- 104-7). AM-PT-08-07- 0-UN -PM (705- 104-), AM-PT-07-07- 0-UN -PM (705- 104-5) and AM-PT-1 -07- 0-UN -PM (705- 104-7). The samples were preserved to the appropriate p in the laboratory.

Metals

Method 020 - Total recoverable: The matrix spi e / matrix spi e duplicate (MS/MSD) recoveries for preparation batch 705-5829 and analytical batch 705-598 was outside control limits. Sample matrix interference is suspected. The post digestion spi e passed.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

20 ent i oGer y 2oeG@erGley
aPri yj/ lri : aQenSuHHoem

Job ID: 705-1309-3

Client Sample ID: AMP -T3-8H-07-10-4Fr-TP

Lab Sample ID: 705-180H-8

Date Ccllected/ : 072102/H87:H0

PatxiW o atex

Date Redeige/ : 072182/H0h:H7

Pet6c/ : So (H) 080D - Petals .ICTy

MnalUte	Result	f ualiBex	RL	P DL	4 nit	D	Txepaxe/	MnalUQe/	Dil r ad
, cxcn	021		0090	00.4	H6jg		07j13j.93.:3L	07j13j.935:99	3

Pet6c/ : So (H) 0v0, - Petals .ICTP Sy- 3ctal Redc9exable

MnalUte	Result	f ualiBex	RL	P DL	4 nit	D	Txepaxe/	MnalUQe/	Dil r ad
Msenid	028		00050	00031	H6jg		07j13j.93.:3L	07j13j.934:3L	3
lxcn	1v		0090	003L	H6jg		07j13j.93.:3L	07j13j.934:3L	3

8cRBeGf rQeru

Client Sample Results

20 ent i oGer y 2oeG@uerGley
aPori yj/ lri : aQenSuHHoem

Job ID: 705-1309-3

Client Sample ID: AMP -T3-8H-07-10-r IL-TP

Lab Sample ID: 705-180H-v

Date Ccldedte/ : 072102/H87:H0

PatxiW o atex

Date Redei9e/ : 072182/H0h:H7

Pet6c/ : So (H) 080D - Petals .ICTy- Disscl9e/

MnalUte	Result	f ualiBex	RL	P DL	4 nit	D	Txepaxe/	MnalUQe/	Dil r ad
, cxcnNDisscl9e/	005h		00090	00. 4	H6jg			07j13j. 9 35:1.	3

Pet6c/ : So (H) 0v0, - Petals .ICTP Sy- Disscl9e/

MnalUte	Result	f ualiBex	RL	P DL	4 nit	D	Txepaxe/	MnalUQe/	Dil r ad
MsenidNDisscl9e/	005H		00050	00031	H6jg			07j13j. 9 39:.. A	3
lxcnNDisscl9e/	87		00090	0003L	H6jg			07j13j. 9 39:.. A	3

8cRBeGf rQenu

Client Sample Results

20 ent i oGer y 2oeG@erGley
aPri yj/ lri : aQenSuHHoem

Job ID: 705-1309-3

Client Sample ID: AMP-T3-0(-07-10-4Fr-TP

Lab Sample ID: 705-180H-1

Date Cclledte/ : 072102/H87:50

PatxiW o atex

Date Redei9e/ : 072182/H0h:H7

Pet6c/ : So (H) 080D - Petals .ICTy

MnalUte	Result	f ualiBex	RL	P DL	4 nit	D	Txepaxe/	MnalUQe/	Dil r ad
, cxcn	0z/		0d090	0d. 4	H6jg		07j13j. 9 3. :3L	07j13j. 9 35:97	3

Pet6c/ : So (H) 0v0, - Petals .ICTP Sy- 3ctal Redc9exable

MnalUte	Result	f ualiBex	RL	P DL	4 nit	D	Txepaxe/	MnalUQe/	Dil r ad
Msenid	0z/H		0d050	0d031	H6jg		07j13j. 9 3. :3L	07j13j. 9 34:. 0	3
lxcn	v5		0d090	0d03L	H6jg		07j13j. 9 3. :3L	07j13j. 9 34:. 0	3

8cRBeGf rQeru

Client Sample Results

20 ent i oGer y 2oeG@erGley
aPori yj/ lri : aQenSuHHoem

Job ID: 705-1309-3

Client Sample ID: AMP -T3-0(-07-10-r IL-TP

Lab Sample ID: 705-180HH

Date Ccllede/ : 072102/H87:50

PatxiW o atex

Date Redeie/ : 072182/H0h:H7

Pet6c/ : So (H) 080D - Petals .ICTy- Disscl9e/

MnalUte	Result	f ualiBex	RL	P DL	4 nit	D	Txepaxe/	MnalUQe/	Dil r ad
, cxcnNDisscl9e/	0z70		0d090	0d. 4	H6jg			07j13j. 9 35:15	3

Pet6c/ : So (H) 0v0, - Petals .ICTP Sy- Disscl9e/

MnalUte	Result	f ualiBex	RL	P DL	4 nit	D	Txepaxe/	MnalUQe/	Dil r ad
MsenidNDisscl9e/	0zv		0d050	0d031	H6jg			07j13j. 9 39:13	3
lxcnNDisscl9e/	7z7		0d090	0d03L	H6jg			07j13j. 9 39:13	3

8cRBeGf rQeru

Client Sample Results

20 ent i oGer y 2oeG@erGley
aPri yj/ lri : aQenSuHHoem

Job ID: 705-1309-3

Client Sample ID: AMP -T3-07-07-10-4Fr-TP

Lab Sample ID: 705-180H-5

Date Ccldedte/ : 072102/H8(:00

PatxiW o atex

Date Redei9e/ : 072182/H0h:H7

Pet6c/ : So (H) 080D - Petals .ICTy

MnalUte	Result	f ualiBex	RL	P DL	4 nit	D	Txepaxe/	MnalUQe/	Dil r ad
, cxcn	0z7)		0d090	0d. 4	H6jg		07j13j. 9 3. :3L	07j13j. 9 35:53	3

Pet6c/ : So (H) 0v0, - Petals .ICTP Sy- 3ctal Redc9exable

MnalUte	Result	f ualiBex	RL	P DL	4 nit	D	Txepaxe/	MnalUQe/	Dil r ad
Msenid	0zlh		0d050	0d031	H6jg		07j13j. 9 3. :3L	07j13j. 9 34:. 1	3
lxcn	8) 0		0d0	0dL	H6jg		07j13j. 9 3. :3L	07j13j. 9 34:94	30

8cRBeGf rQeru

Client Sample Results

20 ent i oGer y 2oeGuerGley
aPori yj/ lri : aQenSuHHoem

Job ID: 705-1309-3

Client Sample ID: AMP -T3-07-07-10-r IL-TP

Lab Sample ID: 705-180H)

Date Ccldedte/ : 072102/H8(:00

PatxiW o atex

Date Redei9e/ : 072182/H0h:H7

Pet6c/ : So (H) 080D - Petals .ICTy- Disscl9e/

MnalUte	Result	f ualiBex	RL	P DL	4 nit	D	Txepaxe/	MnalUQe/	Dil r ad
, cxcnNDisscl9e/	005h		00090	00. 4	H6jg			07j13j. 9 35:1L	3

Pet6c/ : So (H) 0v0, - Petals .ICTP Sy- Disscl9e/

MnalUte	Result	f ualiBex	RL	P DL	4 nit	D	Txepaxe/	MnalUQe/	Dil r ad
MsenidNDisscl9e/	00H5		00050	00031	H6jg			07j13j. 9 39:19	3
lxcnNDisscl9e/	82H		000	00L	H6jg			07j13j. 9 34:99	30

8cRBeGf rQenu

Client Sample Results

20 ent i oGer y 2oeG@erGley
aPri yj/ lri : aQenSuHHoem

Job ID: 705-1309-3

Client Sample ID: AMP -T3-81-07-10-4Fr-TP

Lab Sample ID: 705-180H-7

Date Ccledte/ : 072102/H8(:80

PatxiW o atex

Date Redei9e/ : 072182/H0h:H7

Pet6c/ : So (H) 080D - Petals .ICTy

MnalUte	Result	f ualiBex	RL	P DL	4 nit	D	Txepaxe/	MnalUQe/	Dil r ad
, cxcn	0z57		0d090	0d. 4	H6jg		07j13j. 9 3. :3L	07j13j. 9 34:00	3

Pet6c/ : So (H) 0v0, - Petals .ICTP Sy- 3ctal Redc9exable

MnalUte	Result	f ualiBex	RL	P DL	4 nit	D	Txepaxe/	MnalUQe/	Dil r ad
Msenid	0z87		0d050	0d031	H6jg		07j13j. 9 3. :3L	07j13j. 9 34:. 5	3
lxcn	vH		0d090	0d03L	H6jg		07j13j. 9 3. :3L	07j13j. 9 34:. 5	3

8cRBeGf rQeru

Client Sample Results

20 ent i oGer y 2oeG@erGley
aPri yj/ lri : aQenSuHHoem

Job ID: 705-1309-3

Client Sample ID: AMP -T3-81-07-10-r IL-TP

Lab Sample ID: 705-180H-

Date Ccldedte/ : 072102/H8(:80

PatxiW o atex

Date Redei9e/ : 072182/H0h:H7

Pet6c/ : So (H) 080D - Petals .ICTy- Disscl9e/

MnalUte	Result	f ualiBex	RL	P DL	4 nit	D	Txepaxe/	MnalUQe/	Dil r ad
, cxcnNDisscl9e/	005)		00090	00. 4	H6jg			07j13j. 9 35:93	3

Pet6c/ : So (H) 0v0, - Petals .ICTP Sy- Disscl9e/

MnalUte	Result	f ualiBex	RL	P DL	4 nit	D	Txepaxe/	MnalUQe/	Dil r ad
MsenidNDisscl9e/	007)		00050	00031	H6jg			07j13j. 9 39:14	3
lxcnNDisscl9e/	81		00090	0003L	H6jg			07j13j. 9 39:14	3

8cRBeGf rQeru

QC Sample Results

Int Gs noyct Au l ot yaiPt Q l t u
r jo/nucHe: r iPt GmPd d ot B

Job ID: 705-180C-8

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-5830/1-A
Matrix: Water
Analysis Batch: 5965

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 5830

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Nojot	. D		0400	0426	d g\$		07989C0, :C1	07989C8C82	8

Lab Sample ID: LCS 705-5830/2-A
Matrix: Water
Analysis Batch: 5965

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 5830

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Nojot	840	846		d g\$		806	v0 - 820

Lab Sample ID: 705-3073-A-1-C MS
Matrix: Water
Analysis Batch: 5965

Client Sample ID: Matrix Spike
Prep Type: Total/NA
Prep Batch: 5830

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Nojot	0462		840	846,		d g\$		807	75 - 825

Lab Sample ID: 705-3073-A-1-D MSD
Matrix: Water
Analysis Batch: 5965

Client Sample ID: Matrix Spike Duplicate
Prep Type: Total/NA
Prep Batch: 5830

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Nojot	0462		840	846v		d g\$		806	75 - 825	8	20

Lab Sample ID: MB 705-5893/1-A
Matrix: Water
Analysis Batch: 5965

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Nojot	. D		0400	0426	d g\$			07989C85:88	8
Nojot 3Deyoi9nB	. D		0400	0426	d g\$			07989C85:88	8

Lab Sample ID: LCS 705-5893/2-A
Matrix: Water
Analysis Batch: 5965

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Nojot	840	841		d g\$		801	v0 - 820
Nojot 3Deyoi9nB	840	841		d g\$		801	v0 - 820

Lab Sample ID: LCSD 705-5893/3-A
Matrix: Water
Analysis Batch: 5965

Client Sample ID: Lab Control Sample Dup
Prep Type: Total/NA

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Nojot	840	842		d g\$		802	v0 - 820	8	20
Nojot 3Deyoi9nB	840	842		d g\$		802	v0 - 820	8	20

Eajof y AGPt Q

QC Sample Results

Int Gs noyct Au l ot yai Pt Q It u
r jo/nuc: r iPt GmPd ot B

Job ID: 705-180C-8

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-5829/1-A
Matrix: Water
Analysis Batch: 5986

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 5829

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ajynt a	. D		04050	04081	d g\$		07S82C0, :C1	07S82C85:27	8
Ijot	. D		0400	0408v	d g\$		07S82C0, :C1	07S82C85:27	8

Lab Sample ID: LCS 705-5829/2-A
Matrix: Water
Analysis Batch: 5986

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 5829

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Ajynt a	0400	040v, 8		d g\$		v,	v0 - 820
Ijot	840	04 17		d g\$		, C	v0 - 820

Lab Sample ID: 705-3073-A-3-B MS
Matrix: Water
Analysis Batch: 5986

Client Sample ID: Matrix Spike
Prep Type: Total Recoverable
Prep Batch: 5829

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Ajynt a	04051		0400	041,		d g\$		v5	75 - 825
Ijot	25		840	254C	C	d g\$		62	75 - 825

Lab Sample ID: 705-3073-A-3-C MSD
Matrix: Water
Analysis Batch: 5986

Client Sample ID: Matrix Spike Duplicate
Prep Type: Total Recoverable
Prep Batch: 5829

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Ajynt a	04051		0400	0415		d g\$		v2	75 - 825	2	20
Ijot	25		840	254	C	d g\$		17	75 - 825	8	20

Lab Sample ID: MB 705-5859/1-A
Matrix: Water
Analysis Batch: 5987

Client Sample ID: Method Blank
Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ajynt a3Deyoi9nB	. D		04050	04081	d g\$			07S82C8C8v	8
Ijot 3Deyoi9nB	. D		0400	0408v	d g\$			07S82C8C8v	8

Lab Sample ID: LCS 705-5859/2-A
Matrix: Water
Analysis Batch: 5987

Client Sample ID: Lab Control Sample
Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Ajynt a3Deyoi9nB	0400	040, 02		d g\$		, 0	v0 - 820
Ijot 3Deyoi9nB	840	04 0C		d g\$		, C	v0 - 820

Lab Sample ID: LCSD 705-5859/3-A
Matrix: Water
Analysis Batch: 5987

Client Sample ID: Lab Control Sample Dup
Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Ajynt a3Deyoi9nB	0400	040v, 8		d g\$		v,	v0 - 820	8	20
Ijot 3Deyoi9nB	840	04 12		d g\$		, 1	v0 - 820	8	20

Eajof y AGPt Q

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1206-2

Client Sample ID: HAM-PT-13-07-40-F 5 8-PM
Date Collecte/ : 0724023 17:30
Date v ecei9e/ : 0724123 0y:37

Lab Sample ID: 70x-4103-1
MatriW d ater

Prep TBpe	s atch TBpe	s atch Metho/	v z n	Dilz tion 8 actor	s atch 5 z mber	AnalBut	Lab	Prepare/ or AnalBNe/
Total/v B	PreA	1020B			5310	SB	EET BTL	07/12/46 24:23
Total/v B	Bnalysis	9020D		2	5p95	DS	EET BTL	07/12/46 25:66
Total NecoRerable	PreA	1005B			534p	SB	EET BTL	07/12/46 24:23
Total NecoRerable	Bnalysis	90408		2	5p39	BD	EET BTL	07/12/46 29:23

Client Sample ID: HAM-PT-13-07-40-8IL-PM
Date Collecte/ : 0724023 17:30
Date v ecei9e/ : 0724123 0y:37

Lab Sample ID: 70x-4103-R
MatriW d ater

Prep TBpe	s atch TBpe	s atch Metho/	v z n	Dilz tion 8 actor	s atch 5 z mber	AnalBut	Lab	Prepare/ or AnalBNe/
DissolRed	Bnalysis	9020D		2	5p95	DS	EET BTL	07/12/46 25:14
DissolRed	Bnalysis	90408		2	5p37	BD	EET BTL	07/12/46 26:4p

Client Sample ID: HAM-PT-0U-07-40-F 5 8-PM
Date Collecte/ : 0724023 17:x0
Date v ecei9e/ : 0724123 0y:37

Lab Sample ID: 70x-4103-4
MatriW d ater

Prep TBpe	s atch TBpe	s atch Metho/	v z n	Dilz tion 8 actor	s atch 5 z mber	AnalBut	Lab	Prepare/ or AnalBNe/
Total/v B	PreA	1020B			5310	SB	EET BTL	07/12/46 24:23
Total/v B	Bnalysis	9020D		2	5p95	DS	EET BTL	07/12/46 25:67
Total NecoRerable	PreA	1005B			534p	SB	EET BTL	07/12/46 24:23
Total NecoRerable	Bnalysis	90408		2	5p39	BD	EET BTL	07/12/46 29:40

Client Sample ID: HAM-PT-0U-07-40-8IL-PM
Date Collecte/ : 0724023 17:x0
Date v ecei9e/ : 0724123 0y:37

Lab Sample ID: 70x-4103-3
MatriW d ater

Prep TBpe	s atch TBpe	s atch Metho/	v z n	Dilz tion 8 actor	s atch 5 z mber	AnalBut	Lab	Prepare/ or AnalBNe/
DissolRed	Bnalysis	9020D		2	5p95	DS	EET BTL	07/12/46 25:15
DissolRed	Bnalysis	90408		2	5p37	BD	EET BTL	07/12/46 26:12

Client Sample ID: HAM-PT-07-07-40-F 5 8-PM
Date Collecte/ : 0724023 1U:00
Date v ecei9e/ : 0724123 0y:37

Lab Sample ID: 70x-4103-x
MatriW d ater

Prep TBpe	s atch TBpe	s atch Metho/	v z n	Dilz tion 8 actor	s atch 5 z mber	AnalBut	Lab	Prepare/ or AnalBNe/
Total/v B	PreA	1020B			5310	SB	EET BTL	07/12/46 24:23
Total/v B	Bnalysis	9020D		2	5p95	DS	EET BTL	07/12/46 25:52
Total NecoRerable	PreA	1005B			534p	SB	EET BTL	07/12/46 24:23
Total NecoRerable	Bnalysis	90408		2	5p39	BD	EET BTL	07/12/46 29:41
Total NecoRerable	PreA	1005B			534p	SB	EET BTL	07/12/46 24:23
Total NecoRerable	Bnalysis	90408		20	5p39	BD	EET BTL	07/12/46 29:69

Client Sample ID: HAM-PT-07-07-40-8IL-PM
Date Collecte/ : 07/24/23 1U:00
Date v ecei9e/ : 07/24/23 0y:37

Lab Sample ID: 70x-4103-6
MatriW d ater

Prep TBpe	s atch TBpe	s atch Metho/	v z n	Dilz tion 8 actor	s atch 5 z mber	AnalBut	Lab	Prepare/ or AnalBne/
DissolRed	Bnalysis	9020D		2	5p95	DS	EET BTL	07/12/46 25:13
DissolRed	Bnalysis	90408		2	5p37	BD	EET BTL	07/12/46 26:16
DissolRed	Bnalysis	90408		20	5p37	BD	EET BTL	07/12/46 29:66

Client Sample ID: HAM-PT-14-07-40-F 5 8-PM
Date Collecte/ : 07/24/23 1U:10
Date v ecei9e/ : 07/24/23 0y:37

Lab Sample ID: 70x-4103-7
MatriW d ater

Prep TBpe	s atch TBpe	s atch Metho/	v z n	Dilz tion 8 actor	s atch 5 z mber	AnalBut	Lab	Prepare/ or AnalBne/
Total/v B	PreA	1020B			5310	SB	EET BTL	07/12/46 24:23
Total/v B	Bnalysis	9020D		2	5p95	DS	EET BTL	07/12/46 29:00
Total NecoFerale	PreA	1005B			534p	SB	EET BTL	07/12/46 24:23
Total NecoFerale	Bnalysis	90408		2	5p39	BD	EET BTL	07/12/46 29:45

Client Sample ID: HAM-PT-14-07-40-8IL-PM
Date Collecte/ : 07/24/23 1U:10
Date v ecei9e/ : 07/24/23 0y:37

Lab Sample ID: 70x-4103-U
MatriW d ater

Prep TBpe	s atch TBpe	s atch Metho/	v z n	Dilz tion 8 actor	s atch 5 z mber	AnalBut	Lab	Prepare/ or AnalBne/
DissolRed	Bnalysis	9020D		2	5p95	DS	EET BTL	07/12/46 25:62
DissolRed	Bnalysis	90408		2	5p37	BD	EET BTL	07/12/46 26:19

LaboratorB v eferenceu:
EET BTL = Eurofins Btlanta, 1030 Presidential Dr, Btlanta, GB 10160, TEL (770)657-3277

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-3104-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13

Method Summary

2025-01-20 10:00 AM
aPbri ynj/ lri : aQenSuHHoem

Job ID: 705-1309-3

Method	Method Description	Protocol	Laboratory
8030D	4 i ruG82aM	/ d V08	(() E) T
80A0L	4 i ruG82aj4 / M	/ d V08	(() E) T
1005E	aR BuRurloep)onuG, i yoR RubC oPDIGbGR m4 i ruG	/ d V08	(() E) T
1030E	aR BuRurloep)onuG4 i ruG	/ d V08	(() E) T

Protocol References:

/ d V08 v =>i G4 i r' onGhoP(RuGurleF / oQnd uGi pa"sGyuG2"i HlyuG4 i r' onGp) "IRn(mtrloepg oR Hbi P3N0 EemlrGUBmuri G

Laboratory References:

(() E) T v (cRfleGEnQerup10V0 aR Gmi erluCDPEnQerupt E 10190p) (T 6770N957-V877



Sample Summary

Client: Geosyntec Consultants Inc
Project: Site remediation

Job ID: 705-180P-8

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-180P-8	mMT-r 3-8P-07-10-4 FL-r T	Water	07/30/2024 8:50:00	07/30/2024 09:07:00
705-180P-2	mMT-r 3-8P-07-10-LIU-r T	Water	07/30/2024 8:50:00	07/30/2024 09:07:00
705-180P-1	mMT-r 3-0N-07-10-4 FL-r T	Water	07/30/2024 8:50:00	07/30/2024 09:07:00
705-180P-P	mMT-r 3-0N-07-10-LIU-r T	Water	07/30/2024 8:50:00	07/30/2024 09:07:00
705-180P-5	mMT-r 3-07-07-10-4 FL-r T	Water	07/30/2024 8:50:00	07/30/2024 09:07:00
705-180P-6	mMT-r 3-07-07-10-LIU-r T	Water	07/30/2024 8:50:00	07/30/2024 09:07:00
705-180P-7	mMT-r 3-81-07-10-4 FL-r T	Water	07/30/2024 8:50:00	07/30/2024 09:07:00
705-180P-N	mMT-r 3-81-07-10-LIU-r T	Water	07/30/2024 8:50:00	07/30/2024 09:07:00

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-3104-1

Login Number: 3104

List Source: Eurofins Atlanta

List Number: 1

Creator: Pomuti, Carmen

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	N/A	
Sample custody seals, if present, are intact.	N/A	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	False	Limited volume received.
Sample Preservation Verified.	True	Refer to Job Narrative for details.
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	N/A	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT



ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 8/2/2024 7:13:52 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-3342-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
8/2/2024 7:13:52 PM

Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	17
Lab Chronicle	19
Certification Summary	21
Method Summary	22
Sample Summary	23
Receipt Checklists	24
End Of Report	25



Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-3342-1

Qualifiers

Metals

Qualifier	Qualifier Description
4	MS, MSD: The analyte present in the original sample is greater than 4 times the matrix spike concentration; therefore, control limits are not applicable.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

3000 Piedmont Dr
Atlanta, GA 30340
Phone (770) 457-8177

Chain of Custody Record



Environmental Testing

Client Information		Sample ID: 7-21-24		Lab No: 404-434-2074		Date of Receipt: 8-1-24		Time of Receipt: 15:11		Company: Geosyntec		Project: 7-21-24		Date of Sample: 8-1-24		Time of Sample: 15:11		Company: Geosyntec	
Client Name: Geosyntec Consultants Inc		Address: 1255 Roberts Blvd, NW Suite 200		City: Atlanta, GA 30144		State: GA		Zip: 30144		Phone: (770) 457-8177		Fax: (770) 457-8177		Email: info@geosyntec.com		Project Name: Point Harwood		Test Code: 7-21-24	
Due Date Requested: 8-1-24		VAT Requested (days): RUSH 1 Day TAT		Compliance Program: A TIA 3 No		Lab Project #: 70502911 (DO NOT REMOVE)		PO #: 10001103		Project #: GW05810		Test Code: 7-21-24		Total Number of Containers: 1		Special Instructions/Notes: See 7047 CDD		Signature: [Signature]	
Sample Identification		Sample Date		Sample Time		Sample Type (C-Cross, P-Push, etc.)		Matrix (Soil, Water, etc.)		Field Filtered (Yes or No)		Permitted MSWSD (Yes or No)		60100 - Total Boron		60206 - Total Arsenic and Iron		60208 - Total Iron and Molybdenum	
HAM-PT-14-07-31-UNF-AM		7-21-24		0910		C		W		X		X		X		X		X	
HAM-PT-14-07-31-FIL-AM		7-31-24		0910		C		W		X		X		X		X		X	
HAM-PT-07-07-31-UNF-AM		7-31-24		0940		C		W		X		X		X		X		X	
HAM-PT-07-07-31-FIL-AM		7-31-24		0940		C		W		X		X		X		X		X	
HAM-PT-08-07-31-UNF-AM		7-31-24		1000		C		W		X		X		X		X		X	
HAM-PT-08-07-31-FIL-AM		7-31-24		1000		C		W		X		X		X		X		X	
HAM-PT-13-07-31-UNF-AM		7-31-24		0950		C		W		X		X		X		X		X	
HAM-PT-13-07-31-FIL-AM		7-31-24		1050		C		W		X		X		X		X		X	
HAM-PT-14-07-31-UNF-PIN		7-31-24		1540		C		W		X		X		X		X		X	
HAM-PT-14-07-31-FIL-PIN		7-31-24		1540		C		W		X		X		X		X		X	
Possible Hazard Identification		Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☒ Unknown ☐ Radiological ☐		Date: 8-1-24		Time: 15:11		Company: Geosyntec		Project: 7-21-24		Date of Sample: 8-1-24		Time of Sample: 15:11		Company: Geosyntec		Project: 7-21-24	
Emergency Kit Being Used By: 7-21-24		Date: 8-1-24		Time: 15:11		Company: Geosyntec		Project: 7-21-24		Date of Sample: 8-1-24		Time of Sample: 15:11		Company: Geosyntec		Project: 7-21-24		Date of Sample: 8-1-24	
Custody Seal Intact: Yes		Custody Seal No: No		Date: 8-1-24		Time: 15:11		Company: Geosyntec		Project: 7-21-24		Date of Sample: 8-1-24		Time of Sample: 15:11		Company: Geosyntec		Project: 7-21-24	
Signature: [Signature]		Signature: [Signature]		Signature: [Signature]		Signature: [Signature]		Signature: [Signature]		Signature: [Signature]		Signature: [Signature]		Signature: [Signature]		Signature: [Signature]		Signature: [Signature]	

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-3342-1

Job ID: 705-3342-1

Eurofins Atlanta

Job Narrative 705- 4 -1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers and/or narrative comments are included to explain any exceptions, if applicable.

- Matrix QC may not be reported if insufficient sample is provided or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 8/1/2024 4: 0 PM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 0. °C.

Receipt Exceptions

The reference method requires samples to be preserved to a p of less than 2. The following samples were received with a p of 2, 2, , 2, and 2, respectively: AM-PT-14-07- 1-UN -AM (705- 42-1), AM-PT-07-07- 1-UN -AM (705- 42-), AM-PT-08-07- 1-UN -AM (705- 42-5), AM-PT-1 -07- 1-UN -AM (705- 42-7) and AM-PT-14-07- 1-UN -PM (705- 42-9). The samples were preserved to the appropriate p in the laboratory.

Metals

Method 020 - Total recoverable: The matrix spi e / matrix spi e duplicate (MS/MSD) recoveries for preparation batch 705- 210 and analytical batch 705- 52 was outside control limits. Sample matrix interference is suspected. The post digestion spi e passed.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1139-2

Client Sample ID: MPT -34-A8-07-1A-Fr x-PT

Lab Sample ID: 705-118H-A

Date Cdille/ te2: 07/11/18 09:40

T atWb: c ateW

Date Re/ eihe2: 06/01/18 A :10

T et) d2: Sc 68((0A0D - T etals .IC3y

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUQ2	Dil xa/
, dWIn	0.4 A		0.030	0.094	m6/g		0L/09/93 07:54	0L/09/93 21:2L	2

T et) d2: Sc 68((0H0, - T etals .IC3v Sy- 4dtal Re/ dheWble

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUQ2	Dil xa/
PVeni/	0.2A6		0.0050	0.0021	m6/g		0L/09/93 0L:01	0L/09/93 25:32	2
IWIn	18		0.030	0.02L	m6/g		0L/09/93 0L:01	0L/09/93 25:32	2

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1139-2

Client Sample ID: MPT -34-A8-07-1A-xIL-PT

Lab Sample ID: 705-118H-H

Date Cdlle/ te2: 07/11/18 09:40

T at Wb: c ate W

Date Re/ eihe2: 06/01/18 A :10

T et) d2: Sc 68((0A0D - T etals .IC3y - Dissdlhe2

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUQ2	Dil xa/
, dWnNDissdlhe2	0z5(		0.030	0.094	m6/g			0L/09/93 21:5A	2

T et) d2: Sc 68((0H0, - T etals .IC3v Sy - Dissdlhe2

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUQ2	Dil xa/
PWeni/ NDissdlhe2	0zAA		0.0050	0.0021	m6/g			0L/09/93 23:17	2
IWnNDissdlhe2	A6		0.030	0.02L	m6/g			0L/09/93 23:17	2

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1139-2

Client Sample ID: MPT -34-07-07-1A-Fr x-PT

Lab Sample ID: 705-118H-1

Date Cdille/ te2: 07/11/18 09:80

T atWb: c ateW

Date Re/ eihe2: 06/01/18 A :10

T et) d2: Sc 68((0A0D - T etals .IC3y

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUQ2	Dil xa/
, dWIn	0.4 A		0.030	0.094	m6/g		0L/09/93 07:54	0L/09/93 21:1L	2

T et) d2: Sc 68((0H0, - T etals .IC3v Sy- 4dtal Re/ dheWble

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUQ2	Dil xa/
PWeni/	0.28		0.0050	0.0021	m6/g		0L/09/93 0L:01	0L/09/93 25:33	2
IWIn	AA0		0.30	0.2L	m6/g		0L/09/93 0L:01	0L/09/93 24:24	20

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1139-2

Client Sample ID: MPT -34-07-07-1A-xIL-PT

Lab Sample ID: 705-118H-8

Date Cdille/ te2: 07/11/18 09:80

T atWb: c ateW

Date Re/ eihe2: 06/01/18 A :10

T et) d2: Sc 68((0A0D - T etals .IC3y- Dissdlhe2

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUte2	Dil xa/
, dWnNDissdlhe2	0.5A		0.030	0.094	m6/g			0L/09/93 23:07	2

T et) d2: Sc 68((0H0, - T etals .IC3v Sy- Dissdlhe2

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUte2	Dil xa/
PWeni/ NDissdlhe2	0.010		0.0050	0.0021	m6/g			0L/09/93 23:1A	2
IWnNDissdlhe2	H6		0.30	0.2L	m6/g			0L/09/93 24:2A	20

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1139-2

Client Sample ID: MPT -34-06-07-1A-Fr x-PT

Lab Sample ID: 705-118H-5

Date Cdlle/ te2: 07/11/18 A0:00

T atWb: c ateW

Date Re/ eihe2: 06/01/18 A :10

T et) d2: Sc 68((0A0D - T etals .IC3y

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUe2	Dil xa/
, dWIn	0.5		0.030	0.094	m6/g		0L/09/93 07:54	0L/09/93 21:32	2

T et) d2: Sc 68((0H0, - T etals .IC3v Sy- 4dtal Re/ dheWble

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUe2	Dil xa/
PVeni/	0.31		0.0050	0.0021	m6/g		0L/09/93 0L:01	0L/09/93 25:34	2
IWIn	18		0.030	0.02L	m6/g		0L/09/93 0L:01	0L/09/93 25:34	2

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1139-2

Client Sample ID: MPT -34-06-07-1A-xIL-PT

Lab Sample ID: 705-118H-

Date Cdlle/ te2: 07/11/18 A0:00

T atWb: c ateW

Date Re/ eihe2: 06/01/18 A :10

T et) d2: Sc 68((0A0D - T etals .IC3y- Dissdlhe2

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUQ2	Dil xa/
, dWnNDissdlhe2	0z A		0.030	0.094	m6/g			0L/09/93 23:20	2

T et) d2: Sc 68((0H0, - T etals .IC3v Sy- Dissdlhe2

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUQ2	Dil xa/
PWeni/ NDissdlhe2	0zA		0.0050	0.0021	m6/g			0L/09/93 23:32	2
IWnNDissdlhe2	A1		0.030	0.02L	m6/g			0L/09/93 23:32	2

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1139-2

Client Sample ID: MPT -34-A1-07-1A-Fr x-PT

Lab Sample ID: 705-118H-7

Date Cdlle/ te2: 07/11/18 09:50

T at Wb: c ateW

Date Re/ eihe2: 06/01/18 A :10

T et) d2: Sc 68((0A0D - T etals .IC3y

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUe2	Dil xa/
, dWln	0.5(		0.030	0.094	m6/g		0L/09/93 07:54	0L/09/93 21:33	2

T et) d2: Sc 68((0H0, - T etals .IC3v Sy- 4dtal Re/ dheWble

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUe2	Dil xa/
PVeni/	0.2H		0.0050	0.0021	m6/g		0L/09/93 0L:01	0L/09/93 24:22	2
IWln	1(		0.030	0.02L	m6/g		0L/09/93 0L:01	0L/09/93 24:22	2

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1139-2

Client Sample ID: MPT -34-A1-07-1A-xIL-PT

Lab Sample ID: 705-118H-6

Date Cdille/ te2: 07/11/18 09:50

T atWb: c ateW

Date Re/ eihe2: 06/01/18 A :10

T et) d2: Sc 68((0A0D - T etals .IC3y - Dissdlhe2

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUe2	Dil xa/
, dWnNDissdlhe2	0z58		0.030	0.094	m6/g			0L/09/93 23:21	2

T et) d2: Sc 68((0H0, - T etals .IC3v Sy - Dissdlhe2

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUe2	Dil xa/
PWeni/ NDissdlhe2	0zA1		0.0050	0.0021	m6/g			0L/09/93 23:33	2
IWnNDissdlhe2	H1		0.030	0.02L	m6/g			0L/09/93 23:33	2

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1139-2

Client Sample ID: MPT -34-A8-07-1A-Fr x-3T

Lab Sample ID: 705-118H-9

Date Cdille/ te2: 07/11/18 A5:80

T atWb: c ateW

Date Re/ eihe2: 06/01/18 A :10

T et) d2: Sc 68((0A0D - T etals .IC3y

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUQ2	Dil xa/
, dWIn	0z1A		0.030	0.094	m6/g		0L/09/93 07:54	0L/09/93 21:37	2

T et) d2: Sc 68((0H0, - T etals .IC3v Sy- 4dtal Re/ dheWble

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUQ2	Dil xa/
PVeni/	0z05A		0.0050	0.0021	m6/g		0L/09/93 0L:01	0L/09/93 25:10	2
IWIn	A7		0.030	0.02L	m6/g		0L/09/93 0L:01	0L/09/93 25:10	2

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1139-2

Client Sample ID: MPT -34-A8-07-1A-xIL-3T

Lab Sample ID: 705-118H-A0

Date Cdille/ te2: 07/11/18 A5:80

T atWb: c ateW

Date Re/ eihe2: 06/01/18 A :10

T et) d2: Sc 68((0A0D - T etals .IC3y- Dissdlhe2

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUQ2	Dil xa/
, dWnNDissdlhe2	0zIH		0.030	0.094	m6/g			0L/09/93 23:24	2

T et) d2: Sc 68((0H0, - T etals .IC3v Sy- Dissdlhe2

PnalUte	Result	f ualiBeW	RL	T DL	F nit	D	3 WpaW2	PnalUQ2	Dil xa/
PWeni/ NDissdlhe2	0zA8		0.0050	0.0021	m6/g			0L/09/93 23:34	2
IWnNDissdlhe2	8zi		0.030	0.02L	m6/g			0L/09/93 23:34	2

QC Sample Results

i a G y t o c u G t a i o G P e G c I G a
j / o S a s h n : j e G d r B B o G N

Job ID: 705-118C-I

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-630/ A-r
MatxiW T atex
r nalNsis Bat8h: 6F17

Client Sample ID: Method Blank
Pæp yNpe: yotalA r
Pæp Bat8h: 630/

r nalNte	MB Result	MB QualiZex	RL	MDL	f nit	D	Pæpaxed	r nalNled	Dil za8
. o/oG	4 D		02080	020C6	B gHL		0, H0C08 07:56	0, H0C08 1 1:1 C	I

Lab Sample ID: LCS 705-630/ A-r
MatxiW T atex
r nalNsis Bat8h: 6F17

Client Sample ID: Lab Contxol Sample
Pæp yNpe: yotalA r
Pæp Bat8h: 630/

r nalNte	Spike r dded	LCS Result	LCS QualiZex	f nit	D	%Re8	%Re8 Limits
. o/oG	I 200	02/, v		B gHL		vv	, 0 - I C0

Lab Sample ID: 705-FF93-1 MS
MatxiW T atex
r nalNsis Bat8h: 6F17

Client Sample ID: Hr M-Py-19-07-F1-f c z-r M
Pæp yNpe: yotalA r
Pæp Bat8h: 630/

r nalNte	Sample Result	Sample QualiZex	Spike r dded	MS Result	MS QualiZex	f nit	D	%Re8	%Re8 Limits
. o/oG	026i		I 200	I 25v		B gHL		v,	75 - I C5

Lab Sample ID: 705-FF93-1 MSD
MatxiW T atex
r nalNsis Bat8h: 6F17

Client Sample ID: Hr M-Py-19-07-F1-f c z-r M
Pæp yNpe: yotalA r
Pæp Bat8h: 630/

r nalNte	Sample Result	Sample QualiZex	Spike r dded	MSD Result	MSD QualiZex	f nit	D	%Re8	%Re8 Limits	RPD Limit
. o/oG	026i		I 200	I 260		B gHL		vv	75 - I C5	I C0

Lab Sample ID: MB 705-63/ 6A-r
MatxiW T atex
r nalNsis Bat8h: 6F17

Client Sample ID: Method Blank
Pæp yNpe: Dissolved

r nalNte	MB Result	MB QualiZex	RL	MDL	f nit	D	Pæpaxed	r nalNled	Dil za8
. o/oG3Dreco0t N	4 D		02080	020C6	B gHL			0, H0C08 1 1:50	I

Lab Sample ID: LCS 705-63/ 6A-r
MatxiW T atex
r nalNsis Bat8h: 6F17

Client Sample ID: Lab Contxol Sample
Pæp yNpe: Dissolved

r nalNte	Spike r dded	LCS Result	LCS QualiZex	f nit	D	%Re8	%Re8 Limits
. o/oG3Dreco0t N	I 200	02/, 6		B gHL		vv	, 0 - I C0

Lab Sample ID: LCSD 705-63/ 6A-r
MatxiW T atex
r nalNsis Bat8h: 6F17

Client Sample ID: Lab Contxol Sample Dup
Pæp yNpe: Dissolved

r nalNte	Spike r dded	LCSD Result	LCSD QualiZex	f nit	D	%Re8	%Re8 Limits	RPD Limit
. o/oG3Dreco0t N	I 200	02/7,		B gHL		v,	, 0 - I C0	I C0

EP/ofrGc Ass Gr

QC Sample Results

i a G y t o c u G t a i o G P e G c I G a
j / o S a s h t : j e G d r B B o G N

Job ID: 705-118C-I

Method: 6030B - Metals (ICP/MS)

Lab Sample ID: MB 705-6310A-r
Matix W T atex
r nalNsis Bat8h: 6F53

Client Sample ID: Method Blank
P x e p y N p e: y o t a l R e 8 o v e x a b l e
P x e p Bat8h: 6310

r nalNte	MB Result	MB Qualizex	RL	MDL	f nit	D	P x e p a x e d	r nalNted	Dil za8
A/ct Ga	4 D		02050	0201 1	B g H L		0, H 0 C 0 8 0, : 01	0, H 0 C 0 8 1 5: C 5	I
I/oG	4 D		02080	0201 ,	B g H L		0, H 0 C 0 8 0, : 01	0, H 0 C 0 8 1 5: C 5	I

Lab Sample ID: LCS 705-6310A-r
Matix W T atex
r nalNsis Bat8h: 6F53

Client Sample ID: Lab Control Sample
P x e p y N p e: y o t a l R e 8 o v e x a b l e
P x e p Bat8h: 6310

r nalNte	Spike r dded	LCS Result	LCS Qualizex	f nit	D	%Re8	%Re8 Limits
A/ct Ga	02 00	02071		B g H L		v7	, 0 - I C 0
I/oG	1 20	02/51		B g H L		v5	, 0 - I C 0

Lab Sample ID: 705-FF93-4 MS
Matix W T atex
r nalNsis Bat8h: 6F53

Client Sample ID: Hr M-Py-19-07-F1-f c z-PM
P x e p y N p e: y o t a l R e 8 o v e x a b l e
P x e p Bat8h: 6310

r nalNte	Sample Result	Sample Qualizex	Spike r dded	MS Result	MS Qualizex	f nit	D	%Re8	%Re8 Limits
A/ct Ga	0251		02 00	02 5C		B g H L		1 01	75 - I C 5
I/oG	1 7		1 20	1 , 2/ 8		B g H L		1 61	75 - I C 5

Lab Sample ID: 705-FF93-4 MSD
Matix W T atex
r nalNsis Bat8h: 6F53

Client Sample ID: Hr M-Py-19-07-F1-f c z-PM
P x e p y N p e: y o t a l R e 8 o v e x a b l e
P x e p Bat8h: 6310

r nalNte	Sample Result	Sample Qualizex	Spike r dded	MSD Result	MSD Qualizex	f nit	D	%Re8	%Re8 Limits	RPD	Limit
A/ct Ga	0251		02 00	02 8,		B g H L		v7	75 - I C 5	1	C 0
I/oG	1 7		1 20	1 , 2/ 8		B g H L		1 61	75 - I C 5	0	C 0

Lab Sample ID: MB 705-63/ 5A-r
Matix W T atex
r nalNsis Bat8h: 6F51

Client Sample ID: Method Blank
P x e p y N p e: D i s s o l v e d

r nalNte	MB Result	MB Qualizex	RL	MDL	f nit	D	P x e p a x e d	r nalNted	Dil za8
A/ct Ga3Drecoet N	4 D		02050	0201 1	B g H L			0, H 0 C 0 8 1 8: C 1	I
I/oG3Drecoet N	4 D		02080	0201 ,	B g H L			0, H 0 C 0 8 1 8: C 1	I

Lab Sample ID: LCS 705-63/ 5A-r
Matix W T atex
r nalNsis Bat8h: 6F51

Client Sample ID: Lab Control Sample
P x e p y N p e: D i s s o l v e d

r nalNte	Spike r dded	LCS Result	LCS Qualizex	f nit	D	%Re8	%Re8 Limits
A/ct Ga3Drecoet N	02 00	020, 8C		B g H L		, 8	, 0 - I C 0
I/oG3Drecoet N	1 20	1 208		B g H L		1 08	, 0 - I C 0

Lab Sample ID: LCSD 705-63/ 5A-r
Matix W T atex
r nalNsis Bat8h: 6F51

Client Sample ID: Lab Control Sample Dup
P x e p y N p e: D i s s o l v e d

r nalNte	Spike r dded	LCSD Result	LCSD Qualizex	f nit	D	%Re8	%Re8 Limits	RPD	Limit
A/ct Ga3Drecoet N	02 00	020, 61		B g H L		, 6	, 0 - I C 0	1	C 0
I/oG3Drecoet N	1 20	1 206		B g H L		1 06	, 0 - I C 0	1	C 0

EP/ofrGc Ass Gr

Lab Chronicle

Client: Geosyntec Consultants Inc
r jo/ect\$lite: r lant mad d onA

Job ID: 705-1126-P

Client Sample ID: HAM-PT-13-07-41-F 5 8-AM
Date Collecte2: 07/11/18 0v:10
Date 9 eceiye2: 08/01/18 1s:40

Lab Sample ID: 70x-443W1
Matrid: / ater

Prep Tupe	z atch Tupe	z atch Metho2	9 Un	DilUtion 8actor	z atch 5 Umber	Analun	Lab	Prepare2 or Analu6e2
9otal\$ 3	r jeB	10P03			L60v	ET	449 39T	0v\$6\$2 07:5L
9otal\$ 3	3nalysis	L0P0D		P	L1P7	D3E	449 39T	0v\$6\$2 P1:Pv
9otal NecoRejable	r jeB	10053			L6P0	ET	449 39T	0v\$6\$2 0v:01
9otal NecoRejable	3nalysis	L060E		P	L156	3D	449 39T	0v\$6\$2 P5:2P

Client Sample ID: HAM-PT-13-07-41-8IL-AM
Date Collecte2: 07/11/18 0v:10
Date 9 eceiye2: 08/01/18 1s:40

Lab Sample ID: 70x-443WW
Matrid: / ater

Prep Tupe	z atch Tupe	z atch Metho2	9 Un	DilUtion 8actor	z atch 5 Umber	Analun	Lab	Prepare2 or Analu6e2
DissolReA	3nalysis	L0P0D		P	L1P7	D3E	449 39T	0v\$6\$2 P1:58
DissolReA	3nalysis	L060E		P	L15P	3D	449 39T	0v\$6\$2 P2:17

Client Sample ID: HAM-PT-07-07-41-F 5 8-AM
Date Collecte2: 07/11/18 0v:30
Date 9 eceiye2: 08/01/18 1s:40

Lab Sample ID: 70x-443W4
Matrid: / ater

Prep Tupe	z atch Tupe	z atch Metho2	9 Un	DilUtion 8actor	z atch 5 Umber	Analun	Lab	Prepare2 or Analu6e2
9otal\$ 3	r jeB	10P03			L60v	ET	449 39T	0v\$6\$2 07:5L
9otal\$ 3	3nalysis	L0P0D		P	L1P7	D3E	449 39T	0v\$6\$2 P1:1v
9otal NecoRejable	r jeB	10053			L6P0	ET	449 39T	0v\$6\$2 0v:01
9otal NecoRejable	3nalysis	L060E		P	L156	3D	449 39T	0v\$6\$2 P5:22
9otal NecoRejable	r jeB	10053			L6P0	ET	449 39T	0v\$6\$2 0v:01
9otal NecoRejable	3nalysis	L060E		P0	L156	3D	449 39T	0v\$6\$2 PL:PL

Client Sample ID: HAM-PT-07-07-41-8IL-AM
Date Collecte2: 07/11/18 0v:30
Date 9 eceiye2: 08/01/18 1s:40

Lab Sample ID: 70x-443W3
Matrid: / ater

Prep Tupe	z atch Tupe	z atch Metho2	9 Un	DilUtion 8actor	z atch 5 Umber	Analun	Lab	Prepare2 or Analu6e2
DissolReA	3nalysis	L0P0D		P	L1P7	D3E	449 39T	0v\$6\$2 P2:07
DissolReA	3nalysis	L060E		P	L15P	3D	449 39T	0v\$6\$2 P2:18
DissolReA	3nalysis	L060E		P0	L15P	3D	449 39T	0v\$6\$2 PL:P8

Client Sample ID: HAM-PT-0B-07-41-F 5 8-AM
Date Collecte2: 07/11/18 10:00
Date 9 eceiye2: 08/01/18 1s:40

Lab Sample ID: 70x-443Wx
Matrid: / ater

Prep Tupe	z atch Tupe	z atch Metho2	9 Un	DilUtion 8actor	z atch 5 Umber	Analun	Lab	Prepare2 or Analu6e2
9otal\$ 3	r jeB	10P03			L60v	ET	449 39T	0v\$6\$2 07:5L
9otal\$ 3	3nalysis	L0P0D		P	L1P7	D3E	449 39T	0v\$6\$2 P1:2P
9otal NecoRejable	r jeB	10053			L6P0	ET	449 39T	0v\$6\$2 0v:01
9otal NecoRejable	3nalysis	L060E		P	L156	3D	449 39T	0v\$6\$2 P5:2L

Lab Chronicle

Client: Geosyntec Consultants Inc

Job ID: 705-1126-P

Project: r j o l e c t S l i t e : r l a n t m a d d o n A

Client Sample ID: HAM-PT-0B-07-41-8IL-AM

Lab Sample ID: 70x-443Ww

Date Collecte2: 07/11/2018 10:00

Matrid: / ater

Date 9 eceiye2: 08/01/2018 1s:40

Prep Tupe	z atch Tupe	z atch Metho2	9 Un	DilUtion 8actor	z atch 5 Umber	Analun	Lab	Prepare2 or Analu6e2
DissolReA	3nalysis	L0P0D		P	L1P7	D3E	449 39T	0v\$6\$2 P2:P0
DissolReA	3nalysis	L060E		P	L15P	3D	449 39T	0v\$6\$2 P2:2P

Client Sample ID: HAM-PT-14-07-41-F 5 8-AM

Lab Sample ID: 70x-443W7

Date Collecte2: 07/11/2018 0v:x0

Matrid: / ater

Date 9 eceiye2: 08/01/2018 1s:40

Prep Tupe	z atch Tupe	z atch Metho2	9 Un	DilUtion 8actor	z atch 5 Umber	Analun	Lab	Prepare2 or Analu6e2
9otal\$ 3	r jeB	10P03			L60v	ET	449 39T	0v\$6\$2 07:5L
9otal\$ 3	3nalysis	L0P0D		P	L1P7	D3E	449 39T	0v\$6\$2 P1:22
9otal NecoRejable	r jeB	10053			L6P0	ET	449 39T	0v\$6\$2 0v:01
9otal NecoRejable	3nalysis	L060E		P	L156	3D	449 39T	0v\$6\$2 PL:PP

Client Sample ID: HAM-PT-14-07-41-8IL-AM

Lab Sample ID: 70x-443WB

Date Collecte2: 07/11/2018 0v:x0

Matrid: / ater

Date 9 eceiye2: 08/01/2018 1s:40

Prep Tupe	z atch Tupe	z atch Metho2	9 Un	DilUtion 8actor	z atch 5 Umber	Analun	Lab	Prepare2 or Analu6e2
DissolReA	3nalysis	L0P0D		P	L1P7	D3E	449 39T	0v\$6\$2 P2:P1
DissolReA	3nalysis	L060E		P	L15P	3D	449 39T	0v\$6\$2 P2:22

Client Sample ID: HAM-PT-13-07-41-F 5 8-PM

Lab Sample ID: 70x-443Ww

Date Collecte2: 07/11/2018 1x:30

Matrid: / ater

Date 9 eceiye2: 08/01/2018 1s:40

Prep Tupe	z atch Tupe	z atch Metho2	9 Un	DilUtion 8actor	z atch 5 Umber	Analun	Lab	Prepare2 or Analu6e2
9otal\$ 3	r jeB	10P03			L60v	ET	449 39T	0v\$6\$2 07:5L
9otal\$ 3	3nalysis	L0P0D		P	L1P7	D3E	449 39T	0v\$6\$2 P1:27
9otal NecoRejable	r jeB	10053			L6P0	ET	449 39T	0v\$6\$2 0v:01
9otal NecoRejable	3nalysis	L060E		P	L156	3D	449 39T	0v\$6\$2 P5:10

Client Sample ID: HAM-PT-13-07-41-8IL-PM

Lab Sample ID: 70x-443W10

Date Collecte2: 07/11/2018 1x:30

Matrid: / ater

Date 9 eceiye2: 08/01/2018 1s:40

Prep Tupe	z atch Tupe	z atch Metho2	9 Un	DilUtion 8actor	z atch 5 Umber	Analun	Lab	Prepare2 or Analu6e2
DissolReA	3nalysis	L0P0D		P	L1P7	D3E	449 39T	0v\$6\$2 P2:PL
DissolReA	3nalysis	L060E		P	L15P	3D	449 39T	0v\$6\$2 P2:2L

Laboratoru 9 eferenceNt

449 39T = 4 u j o f i n s 3 t l a n t a , 10v0 r j e s i A e n t i a l D j , 3 t l a n t a , G3 10120, 94 T (770)257-vP77

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-3342-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13

Method Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-1139-2

Method	Method Description	Protocol	Laboratory
4020D	6 etals MCP(	SW834	)) E TEA
4090L	6 etals MCP/6 S(	SW834	)) E TEA
1005T	PreBarationpEotal , ecoRerable or DissolFed 6 etals	SW834	)) E TEA
1020T	PreBarationp Eotal 6 etals	SW834	)) E TEA

Protocol References:

SW834 v "Est 6 et" ods hor) Baluatinf Solid WastepP" yscal/C" emical 6 et" ods=pE" ird) ditionpg oFember 2N84 Tnd Its UBdates.

Laboratory References:

)) E TEA v) urofins Ttlantap1080 Presidential DrpTtlantapGT 10130pE) AM70(357-8277

Sample Summary

Client: Geosyntec Consultants Inc
j / o s c h n i t e : j l a n t d a A A o n M

Job ID: 705-118P-r

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-118P-r	d T3 -j 4-r 8-07-1r -FL WT3	2 ate/	07Hr HP8 09:r 0	0U0r HP8 r N:10
705-118P-P	d T3 -j 4-r 8-07-1r -W6-T3	2 ate/	07Hr HP8 09:r 0	0U0r HP8 r N:10
705-118P-1	d T3 -j 4-07-07-1r -FL WT3	2 ate/	07Hr HP8 09:80	0U0r HP8 r N:10
705-118P-8	d T3 -j 4-07-07-1r -W6-T3	2 ate/	07Hr HP8 09:80	0U0r HP8 r N:10
705-118P-5	d T3 -j 4-0U-07-1r -FL WT3	2 ate/	07Hr HP8 r 0:00	0U0r HP8 r N:10
705-118P-N	d T3 -j 4-0U-07-1r -W6-T3	2 ate/	07Hr HP8 r 0:00	0U0r HP8 r N:10
705-118P-7	d T3 -j 4-r 1-07-1r -FL WT3	2 ate/	07Hr HP8 09:50	0U0r HP8 r N:10
705-118P-U	d T3 -j 4-r 1-07-1r -W6-T3	2 ate/	07Hr HP8 09:50	0U0r HP8 r N:10
705-118P-9	d T3 -j 4-r 8-07-1r -FL Wj 3	2 ate/	07Hr HP8 r 5:80	0U0r HP8 r N:10
705-118P-r 0	d T3 -j 4-r 8-07-1r -W6-j 3	2 ate/	07Hr HP8 r 5:80	0U0r HP8 r N:10

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-3342-1

Login Number: 3342

List Source: Eurofins Atlanta

List Number: 1


Creator: Maguire, Parris

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	N/A	
Sample custody seals, if present, are intact.	N/A	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	Limited volume received.
Sample Preservation Verified.	True	UNF samples slightly above 2. adjusted in lab
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	N/A	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT

APPENDIX B

Slug Test Graphical Solutions and Model Parameters



INW-03 TEST 1

Data Set: N:\...\INW-03_Test 1_BR.aqt

Date: 05/31/24

Time: 15:09:55

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: INW-03

Test Date: 5/15/2024

AQUIFER DATA

Saturated Thickness: 15.1 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (INW-03)

Initial Displacement: 8.94 ft

Static Water Column Height: 15.1 ft

Total Well Penetration Depth: 14.85 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Bouwer-Rice

$K = 3.39$ ft/day

$y_0 = 9.984$ ft



INW-03 TEST 1

Data Set: N:\...\INW-03_Test 1_HV.aqt

Date: 05/31/24

Time: 15:08:57

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: INW-03

Test Date: 5/15/2024

AQUIFER DATA

Saturated Thickness: 15.1 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (INW-03)

Initial Displacement: 8.94 ft

Static Water Column Height: 15.1 ft

Total Well Penetration Depth: 14.85 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Hvorslev

$K = 4.342$ ft/day

$y_0 = 10.5$ ft



INW-03 TEST 2

Data Set: N:\...\INW-03_Test 2_BR.aqt

Date: 05/31/24

Time: 15:08:13

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: INW-03

Test Date: 5/15/2024

AQUIFER DATA

Saturated Thickness: 15.1 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (INW-03)

Initial Displacement: 8.48 ft

Static Water Column Height: 15.1 ft

Total Well Penetration Depth: 14.85 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Bouwer-Rice

$K = 1.971$ ft/day

$y_0 = 8.774$ ft



INW-03 TEST 2

Data Set: N:\...\INW-03_Test 2_HV.aqt

Date: 05/31/24

Time: 15:07:21

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: INW-03

Test Date: 5/15/2024

AQUIFER DATA

Saturated Thickness: 15.1 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (INW-03)

Initial Displacement: 8.48 ft

Static Water Column Height: 15.1 ft

Total Well Penetration Depth: 14.85 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Hvorslev

$K = 2.575$ ft/day

$y_0 = 9.496$ ft



INW-04 TEST 2

Data Set: N:\...\INW-04_Test 1_BR.aqt

Date: 05/31/24

Time: 14:07:34

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: INW-04

Test Date: 5/14/2024

AQUIFER DATA

Saturated Thickness: 20.4 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (INW-04)

Initial Displacement: 8.7 ft

Static Water Column Height: 20.4 ft

Total Well Penetration Depth: 20.15 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Bouwer-Rice

$K = 2.309$ ft/day

$y_0 = 8.668$ ft



INW-04 TEST 2

Data Set: N:\...\INW-04_Test 1_HV.aqt

Date: 05/31/24

Time: 14:08:24

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: INW-04

Test Date: 5/14/2024

AQUIFER DATA

Saturated Thickness: 20.4 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (INW-04)

Initial Displacement: 8.7 ft

Static Water Column Height: 20.4 ft

Total Well Penetration Depth: 20.15 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Hvorslev

$K = 3.019$ ft/day

$y_0 = 10.$ ft



INW-04 TEST 3

Data Set: N:\...\INW-04_Test 3_BR.aqt

Date: 05/31/24

Time: 14:28:49

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: INW-04

Test Date: 5/14/2024

AQUIFER DATA

Saturated Thickness: 20.4 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (INW-04)

Initial Displacement: 8.65 ft

Static Water Column Height: 20.4 ft

Total Well Penetration Depth: 20.15 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Bouwer-Rice

$K = 2.774$ ft/day

$y_0 = 10.54$ ft



INW-04 TEST 3

Data Set: N:\...\INW-04_Test 3_HV.aqt

Date: 05/31/24

Time: 14:28:01

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: INW-04

Test Date: 5/14/2024

AQUIFER DATA

Saturated Thickness: 20.4 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (INW-04)

Initial Displacement: 8.65 ft

Static Water Column Height: 20.4 ft

Total Well Penetration Depth: 20.15 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Hvorslev

$K = 3.323$ ft/day

$y_0 = 10.79$ ft



INW-05 TEST 1

Data Set: N:\...\INW-05_Test 1_BR.aqt
 Date: 05/31/24

Time: 14:39:36

PROJECT INFORMATION

Company: Geosyntec
 Client: Georgia Power
 Project: GW6581G
 Location: Plant Hammond
 Test Well: INW-05
 Test Date: 5/14/2024

AQUIFER DATA

Saturated Thickness: 20.54 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (INW-05)


Initial Displacement: 8.84 ft
 Total Well Penetration Depth: 20.29 ft
 Casing Radius: 0.083 ft

Static Water Column Height: 20.54 ft
 Screen Length: 10. ft
 Well Radius: 0.25 ft

SOLUTION

Aquifer Model: Unconfined
 $K = 1.947$ ft/day

Solution Method: Bouwer-Rice
 $y_0 = 9.487$ ft



INW-05 TEST 1

Data Set: N:\...\INW-05_Test 1_HV.aqt

Date: 05/31/24

Time: 14:40:29

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: INW-05

Test Date: 5/14/2024

AQUIFER DATA

Saturated Thickness: 20.54 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (INW-05)

Initial Displacement: 8.84 ft

Static Water Column Height: 20.54 ft

Total Well Penetration Depth: 20.29 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Hvorslev

$K = 2.373$ ft/day

$y_0 = 9.883$ ft



INW-05 TEST 2

Data Set: N:\...\INW-05_Test 2_BR.aqt

Date: 05/31/24

Time: 14:45:08

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: INW-05

Test Date: 5/14/2024

AQUIFER DATA

Saturated Thickness: 20.54 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (INW-05)

Initial Displacement: 10.06 ft

Static Water Column Height: 20.54 ft

Total Well Penetration Depth: 20.29 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Bouwer-Rice

$K = 1.84$ ft/day

$y_0 = 10.14$ ft



INW-05 TEST 2

Data Set: N:\...\INW-05_Test 2_HV.aqt

Date: 05/31/24

Time: 14:43:35

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: INW-05

Test Date: 5/14/2024

AQUIFER DATA

Saturated Thickness: 20.54 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (INW-05)

Initial Displacement: 10.06 ft

Static Water Column Height: 20.54 ft

Total Well Penetration Depth: 20.29 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Hvorslev

$K = 2.354$ ft/day

$y_0 = 11.4$ ft



PT-07

Data Set: \\...\PT-07_T1_BR.aqt

Date: 07/13/23

Time: 15:30:50

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: PT-07

Test Date: 7/5/2023

AQUIFER DATA

Saturated Thickness: 22.99 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (PT-07)

Initial Displacement: 9.24 ft

Static Water Column Height: 22.99 ft

Total Well Penetration Depth: 22.74 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Bouwer-Rice

$K = 10.25$ ft/day

$y_0 = 10.37$ ft



PT-07

Data Set: N:\...\PT-07_T1_HSV.aqt

Date: 07/13/23

Time: 15:31:05

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: PT-07

Test Date: 7/5/2023

AQUIFER DATA

Saturated Thickness: 22.99 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (PT-07)

Initial Displacement: 9.24 ft

Static Water Column Height: 22.99 ft

Total Well Penetration Depth: 22.74 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Hvorslev

$K = 11.99$ ft/day

$y_0 = 10.53$ ft



PT-07 TEST 2

Data Set: \\...\PT-07_T2_BR.aqt

Date: 07/13/23

Time: 15:35:08

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: PT-07

Test Date: 7/5/2023

AQUIFER DATA

Saturated Thickness: 22.99 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (PT-07)

Initial Displacement: 9.23 ft

Static Water Column Height: 22.99 ft

Total Well Penetration Depth: 22.74 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Bouwer-Rice

K = 11.34 ft/day

y_0 = 10.81 ft



PT-07 TEST 2

Data Set: N:\...\PT-07_T2_HSV.aqt

Date: 07/13/23

Time: 15:34:50

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: PT-07

Test Date: 7/5/2023

AQUIFER DATA

Saturated Thickness: 22.99 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (PT-07)

Initial Displacement: 9.23 ft

Static Water Column Height: 22.99 ft

Total Well Penetration Depth: 22.74 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Hvorslev

$K = 13.5$ ft/day

$y_0 = 11.2$ ft



PT-08 TEST 1

Data Set: \\...\PT-08_T1_BR.aqt
 Date: 07/13/23

Time: 15:50:49

PROJECT INFORMATION

Company: Geosyntec
 Client: Georgia Power
 Project: GW6581G
 Location: Plant Hammond
 Test Well: PT-08
 Test Date: 7/5/2023

AQUIFER DATA

Saturated Thickness: 19.41 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (PT-08)


Initial Displacement: 10.19 ft
 Total Well Penetration Depth: 19.16 ft
 Casing Radius: 0.083 ft

Static Water Column Height: 19.41 ft
 Screen Length: 10. ft
 Well Radius: 0.25 ft

SOLUTION

Aquifer Model: Unconfined
 $K = 3.582$ ft/day

Solution Method: Bouwer-Rice
 $y_0 = 12.84$ ft



PT-08 TEST 1

Data Set: \\...\PT-08_T1_HSV.aqt

Date: 07/13/23

Time: 15:50:17

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: PT-08

Test Date: 7/5/2023

AQUIFER DATA

Saturated Thickness: 19.41 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (PT-08)

Initial Displacement: 10.19 ft

Static Water Column Height: 19.41 ft

Total Well Penetration Depth: 19.16 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Hvorslev

$K = 4.125$ ft/day

$y_0 = 11.91$ ft



PT-08 TEST 2

Data Set: N:\...\PT-08_T2_BR.aqt

Date: 07/13/23

Time: 15:48:31

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: PT-08

Test Date: 7/5/2023

AQUIFER DATA

Saturated Thickness: 19.41 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (PT-08)

Initial Displacement: 10.44 ft

Static Water Column Height: 19.41 ft

Total Well Penetration Depth: 19.16 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Bouwer-Rice

$K = 3.26$ ft/day

$y_0 = 13.57$ ft



PT-08 TEST 2

Data Set: N:\...\PT-08_T2_HSV.aqt

Date: 07/13/23

Time: 15:49:18

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: PT-08

Test Date: 7/5/2023

AQUIFER DATA

Saturated Thickness: 19.41 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (PT-08)

Initial Displacement: 10.44 ft

Static Water Column Height: 19.41 ft

Total Well Penetration Depth: 19.16 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Hvorslev

$K = 3.83$ ft/day

$y_0 = 13.$ ft



PT-09 TEST 1

Data Set: \\...\PT-09 T1_BR.aqt
 Date: 07/13/23

Time: 16:37:07

PROJECT INFORMATION

Company: Geosyntec
 Client: Georgia Power
 Project: GW6581G
 Location: Plant Hammond
 Test Well: PT-09
 Test Date: 6/28/2023

AQUIFER DATA

Saturated Thickness: 16.21 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (PT-09)


Initial Displacement: 2.911 ft
 Total Well Penetration Depth: 15.96 ft
 Casing Radius: 0.083 ft

Static Water Column Height: 16.21 ft
 Screen Length: 10. ft
 Well Radius: 0.25 ft

SOLUTION

Aquifer Model: Unconfined
 $K = 7.618$ ft/day

Solution Method: Bouwer-Rice
 $y_0 = 1.478$ ft



PT-09 TEST 1

Data Set: \\...\PT-09_T1_HSV.aqt
 Date: 07/13/23

Time: 16:37:35

PROJECT INFORMATION

Company: Geosyntec
 Client: Georgia Power
 Project: GW6581G
 Location: Plant Hammond
 Test Well: PT-09
 Test Date: 6/28/2023

AQUIFER DATA

Saturated Thickness: 16.21 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (PT-09)


Initial Displacement: 2.911 ft
 Total Well Penetration Depth: 15.96 ft
 Casing Radius: 0.083 ft

Static Water Column Height: 16.21 ft
 Screen Length: 10. ft
 Well Radius: 0.25 ft

SOLUTION

Aquifer Model: Unconfined
 $K = 7.709$ ft/day

Solution Method: Hvorslev
 $y_0 = 1.284$ ft



PT-09 TEST 2

Data Set: \\...\PT-09_T2_BR.aqt
 Date: 07/13/23

Time: 16:33:45

PROJECT INFORMATION

Company: Geosyntec
 Client: Georgia Power
 Project: GW6581G
 Location: Plant Hammond
 Test Well: PT-09
 Test Date: 6/28/2023

AQUIFER DATA

Saturated Thickness: 16.21 ft

Anisotropy Ratio (Kz/Kr): 0.1

WELL DATA (PT-09)


Initial Displacement: 3.101 ft
 Total Well Penetration Depth: 15.91 ft
 Casing Radius: 0.083 ft

Static Water Column Height: 16.21 ft
 Screen Length: 10. ft
 Well Radius: 0.25 ft

SOLUTION

Aquifer Model: Unconfined
 K = 7.906 ft/day

Solution Method: Bouwer-Rice
 y0 = 1.575 ft



PT-09 TEST 2

Data Set: N:\...\PT-09_T2_HSV.aqt
 Date: 07/13/23

Time: 16:33:56

PROJECT INFORMATION

Company: Geosyntec
 Client: Georgia Power
 Project: GW6581G
 Location: Plant Hammond
 Test Well: PT-09
 Test Date: 6/28/2023

AQUIFER DATA

Saturated Thickness: 16.21 ft

Anisotropy Ratio (Kz/Kr): 0.1

WELL DATA (PT-09)


Initial Displacement: 3.101 ft
 Total Well Penetration Depth: 15.91 ft
 Casing Radius: 0.083 ft

Static Water Column Height: 16.21 ft
 Screen Length: 10. ft
 Well Radius: 0.25 ft

SOLUTION

Aquifer Model: Unconfined
 K = 7.937 ft/day

Solution Method: Hvorslev
 y0 = 1.388 ft



PT-10 TEST 1

Data Set: N:\...\PT-10_T1_BR.aqt
 Date: 07/13/23

Time: 16:55:55

PROJECT INFORMATION

Company: Geosyntec
 Client: Georgia Power
 Project: GW6581G
 Location: Plant Hammond
 Test Well: PT-10
 Test Date: 6/28/2023

AQUIFER DATA

Saturated Thickness: 15.86 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (PT-10)


Initial Displacement: 9.52 ft
 Total Well Penetration Depth: 15.61 ft
 Casing Radius: 0.083 ft

Static Water Column Height: 15.86 ft
 Screen Length: 10. ft
 Well Radius: 0.25 ft

SOLUTION

Aquifer Model: Unconfined
 $K = 1.631$ ft/day

Solution Method: Bouwer-Rice
 $y_0 = 17.02$ ft



PT-10 TEST 1

Data Set: N:\...\PT-10_T1_HSV.aqt
 Date: 07/13/23

Time: 16:56:36

PROJECT INFORMATION

Company: Geosyntec
 Client: Georgia Power
 Project: GW6581G
 Location: Plant Hammond
 Test Well: PT-10
 Test Date: 6/28/2023

AQUIFER DATA

Saturated Thickness: 15.86 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (PT-10)


Initial Displacement: 9.52 ft
 Total Well Penetration Depth: 15.61 ft
 Casing Radius: 0.083 ft

Static Water Column Height: 15.86 ft
 Screen Length: 10. ft
 Well Radius: 0.25 ft

SOLUTION

Aquifer Model: Unconfined
 $K = 2.037$ ft/day

Solution Method: Hvorslev
 $y_0 = 17.42$ ft



PT-10 TEST 2

Data Set: N:\...\PT-10_T2_BR.aqt

Date: 07/13/23

Time: 16:58:45

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: PT-10

Test Date: 6/28/2023

AQUIFER DATA

Saturated Thickness: 15.86 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (PT-10)

Initial Displacement: 8.314 ft

Static Water Column Height: 15.86 ft

Total Well Penetration Depth: 15.61 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft


SOLUTION

Aquifer Model: Unconfined

Solution Method: Bouwer-Rice

$K = 1.71$ ft/day

$y_0 = 14.32$ ft



PT-10 TEST 2

Data Set: N:\...\PT-10_T2_HSV.aqt

Date: 07/13/23

Time: 16:59:18

PROJECT INFORMATION

Company: Geosyntec

Client: Georgia Power

Project: GW6581G

Location: Plant Hammond

Test Well: PT-10

Test Date: 6/28/2023

AQUIFER DATA

Saturated Thickness: 15.86 ft

Anisotropy Ratio (K_z/K_r): 0.1

WELL DATA (PT-10)

Initial Displacement: 8.314 ft

Static Water Column Height: 15.86 ft

Total Well Penetration Depth: 15.61 ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.25 ft

SOLUTION

Aquifer Model: Unconfined

Solution Method: Hvorslev

$K = 2.027$ ft/day

$y_0 = 13.3$ ft

APPENDIX C

Baseline Groundwater Analytical Laboratory Results and Field Sampling Forms

Laboratory Analytical Reports



July 28, 2023

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1
Pace Project No.: 92677694

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on July 17, 2023. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Charlotte
- Pace Analytical Services - Peachtree Corners, GA

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
(704)875-9092
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1

Pace Project No.: 92677694

Pace Analytical Services Charlotte

South Carolina Laboratory ID: 99006
9800 Kinsey Ave. Ste 100, Huntersville, NC 28078
North Carolina Drinking Water Certification #: 37706
North Carolina Field Services Certification #: 5342
North Carolina Wastewater Certification #: 12
South Carolina Laboratory ID: 99006

South Carolina Certification #: 99006001
South Carolina Drinking Water Cert. #: 99006003
Florida/NELAP Certification #: E87627
Kentucky UST Certification #: 84
Louisiana DoH Drinking Water #: LA029
Virginia/VELAP Certification #: 460221

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804
Florida/NELAP Certification #: E87648
North Carolina Drinking Water Certification #: 37712
North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030
South Carolina Certification #: 99030001
Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092
Florida DOH Certification #: E87315
Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381
South Carolina Certification #: 98011001
Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1

Pace Project No.: 92677694

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92677694001	HAM-HGWC-8	Water	07/13/23 10:35	07/17/23 12:30
92677694002	HAM-PT-09	Water	07/13/23 12:47	07/17/23 12:30
92677694003	HAM-PT-10	Water	07/13/23 14:15	07/17/23 12:30
92677694004	HAM-PT-07	Water	07/13/23 16:22	07/17/23 12:30
92677694005	HAM-PT-08	Water	07/13/23 17:51	07/17/23 12:30
92677694006	HAM-AP1-FD-01	Water	07/13/23 00:00	07/17/23 12:30
92677694007	HAM-AP1-FB-01	Water	07/17/23 08:40	07/17/23 12:30
92677694008	HAM-HGWC-13	Water	07/17/23 11:47	07/17/23 12:30

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92677694

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92677694001	HAM-HGWC-8	EPA 6010D	MS	6
		EPA 6020B	CW1	12
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92677694002	HAM-PT-09	EPA 6010D	MS	6
		EPA 6020B	CW1	12
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92677694003	HAM-PT-10	EPA 6010D	MS	6
		EPA 6020B	CW1	12
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92677694004	HAM-PT-07	EPA 6010D	MS	6
		EPA 6020B	CW1	12
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92677694005	HAM-PT-08	EPA 6010D	MS	6
		EPA 6020B	CW1	12
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92677694006	HAM-AP1-FD-01	EPA 6010D	MS	6
		EPA 6020B	CW1	12

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92677694

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92677694007	HAM-AP1-FB-01	EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	MS	6
		EPA 6020B	CW1	12
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	MS	6
		EPA 6020B	CW1	12
92677694008	HAM-HGWC-13	EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	MS	6
		EPA 6020B	CW1	12

PASI-A = Pace Analytical Services - Asheville

PASI-C = Pace Analytical Services - Charlotte

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92677694

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92677694001	HAM-HGWC-8					
	Performed by	CUSTOMER			07/17/23 17:16	
	pH	6.65	Std. Units		07/17/23 17:16	
EPA 6010D	Manganese	0.28	mg/L	0.040	07/20/23 15:39	
EPA 6010D	Potassium	6.9	mg/L	0.50	07/20/23 15:39	
EPA 6010D	Sodium	8.8	mg/L	1.0	07/20/23 15:39	M1
EPA 6010D	Calcium	107	mg/L	1.0	07/20/23 15:39	M1
EPA 6010D	Magnesium	14.9	mg/L	0.050	07/20/23 15:39	M1
EPA 6010D	Iron	0.27	mg/L	0.040	07/25/23 15:53	
EPA 6020B	Barium	0.047	mg/L	0.0050	07/19/23 17:55	
EPA 6020B	Beryllium	0.000073J	mg/L	0.00050	07/19/23 17:55	
EPA 6020B	Boron	2.0	mg/L	0.20	07/21/23 16:37	
EPA 6020B	Cadmium	0.00031J	mg/L	0.00050	07/19/23 17:55	
EPA 6020B	Cobalt	0.0015J	mg/L	0.0050	07/19/23 17:55	
EPA 6020B	Lithium	0.0015J	mg/L	0.030	07/19/23 17:55	
EPA 6020B	Molybdenum	0.30	mg/L	0.010	07/19/23 17:55	
EPA 6020B	Thallium	0.00026J	mg/L	0.0010	07/19/23 17:55	
SM 2540C-2015	Total Dissolved Solids	513	mg/L	25.0	07/18/23 15:24	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	136	mg/L	5.0	07/19/23 19:16	
SM 2320B-2011	Alkalinity, Total as CaCO3	136	mg/L	5.0	07/19/23 19:16	
EPA 300.0 Rev 2.1 1993	Chloride	47.9	mg/L	1.0	07/19/23 03:12	
EPA 300.0 Rev 2.1 1993	Fluoride	0.49	mg/L	0.10	07/19/23 03:12	
EPA 300.0 Rev 2.1 1993	Sulfate	163	mg/L	3.0	07/19/23 09:10	
92677694002	HAM-PT-09					
	Performed by	CUSTOMER			07/17/23 17:16	
	pH	6.57	Std. Units		07/17/23 17:16	
EPA 6010D	Iron	0.33	mg/L	0.040	07/25/23 16:08	
EPA 6010D	Manganese	0.79	mg/L	0.040	07/20/23 15:59	
EPA 6010D	Potassium	6.8	mg/L	0.50	07/20/23 15:59	
EPA 6010D	Sodium	10.6	mg/L	1.0	07/20/23 15:59	
EPA 6010D	Calcium	110	mg/L	1.0	07/20/23 15:59	
EPA 6010D	Magnesium	15.6	mg/L	0.050	07/20/23 15:59	
EPA 6020B	Antimony	0.0027J	mg/L	0.0030	07/19/23 18:19	
EPA 6020B	Barium	0.053	mg/L	0.0050	07/19/23 18:19	
EPA 6020B	Beryllium	0.000077J	mg/L	0.00050	07/19/23 18:19	
EPA 6020B	Boron	2.1	mg/L	0.20	07/21/23 16:55	
EPA 6020B	Cobalt	0.0045J	mg/L	0.0050	07/19/23 18:19	
EPA 6020B	Lithium	0.0013J	mg/L	0.030	07/19/23 18:19	
EPA 6020B	Molybdenum	0.065	mg/L	0.010	07/19/23 18:19	
SM 2540C-2015	Total Dissolved Solids	534	mg/L	25.0	07/18/23 15:24	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	144	mg/L	5.0	07/19/23 19:26	
SM 2320B-2011	Alkalinity, Total as CaCO3	144	mg/L	5.0	07/19/23 19:26	
EPA 300.0 Rev 2.1 1993	Chloride	55.3	mg/L	1.0	07/19/23 03:27	
EPA 300.0 Rev 2.1 1993	Fluoride	0.24	mg/L	0.10	07/19/23 03:27	
EPA 300.0 Rev 2.1 1993	Sulfate	160	mg/L	3.0	07/19/23 09:53	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92677694

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92677694003	HAM-PT-10					
	Performed by	CUSTOMER			07/17/23 17:16	
	pH	7.01	Std. Units		07/17/23 17:16	
EPA 6010D	Manganese	3.5	mg/L	0.040	07/20/23 16:14	
EPA 6010D	Potassium	7.1	mg/L	0.50	07/20/23 16:14	
EPA 6010D	Sodium	10.5	mg/L	1.0	07/20/23 16:14	
EPA 6010D	Calcium	127	mg/L	1.0	07/20/23 16:14	
EPA 6010D	Magnesium	16.8	mg/L	0.050	07/20/23 16:14	
EPA 6010D	Iron	3.1	mg/L	0.040	07/25/23 16:12	
EPA 6020B	Barium	0.074	mg/L	0.0050	07/19/23 18:25	
EPA 6020B	Boron	2.2	mg/L	0.20	07/21/23 17:01	
EPA 6020B	Cobalt	0.0026J	mg/L	0.0050	07/19/23 18:25	
EPA 6020B	Lithium	0.0014J	mg/L	0.030	07/19/23 18:25	
EPA 6020B	Molybdenum	0.10	mg/L	0.010	07/19/23 18:25	
SM 2540C-2015	Total Dissolved Solids	557	mg/L	25.0	07/18/23 15:24	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	185	mg/L	5.0	07/20/23 16:41	
SM 2320B-2011	Alkalinity, Total as CaCO3	185	mg/L	5.0	07/20/23 16:41	
EPA 300.0 Rev 2.1 1993	Chloride	67.2	mg/L	1.0	07/19/23 04:10	
EPA 300.0 Rev 2.1 1993	Fluoride	0.33	mg/L	0.10	07/19/23 04:10	
EPA 300.0 Rev 2.1 1993	Sulfate	145	mg/L	3.0	07/19/23 10:07	
92677694004	HAM-PT-07					
	Performed by	CUSTOMER			07/17/23 17:16	
	pH	6.76	Std. Units		07/17/23 17:16	
EPA 6010D	Manganese	8.2	mg/L	0.040	07/20/23 16:19	
EPA 6010D	Potassium	6.0	mg/L	0.50	07/20/23 16:19	
EPA 6010D	Sodium	6.1	mg/L	1.0	07/20/23 16:19	
EPA 6010D	Calcium	168	mg/L	1.0	07/20/23 16:19	
EPA 6010D	Magnesium	18.5	mg/L	0.050	07/20/23 16:19	
EPA 6010D	Iron	23.8	mg/L	0.040	07/25/23 16:17	
EPA 6020B	Arsenic	0.34	mg/L	0.010	07/19/23 18:30	
EPA 6020B	Barium	0.056	mg/L	0.0050	07/19/23 18:30	
EPA 6020B	Beryllium	0.00012J	mg/L	0.00050	07/19/23 18:30	
EPA 6020B	Boron	1.0	mg/L	0.20	07/21/23 17:07	
EPA 6020B	Cobalt	0.13	mg/L	0.0050	07/19/23 18:30	
EPA 6020B	Lithium	0.060	mg/L	0.030	07/19/23 18:30	
EPA 6020B	Molybdenum	0.017	mg/L	0.010	07/19/23 18:30	
EPA 6020B	Thallium	0.00024J	mg/L	0.0010	07/19/23 18:30	
SM 2540C-2015	Total Dissolved Solids	808	mg/L	25.0	07/18/23 15:24	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	102	mg/L	5.0	07/20/23 16:53	
SM 2320B-2011	Alkalinity, Total as CaCO3	102	mg/L	5.0	07/20/23 16:53	
EPA 300.0 Rev 2.1 1993	Chloride	15.7	mg/L	1.0	07/19/23 04:24	
EPA 300.0 Rev 2.1 1993	Fluoride	0.36	mg/L	0.10	07/19/23 04:24	
EPA 300.0 Rev 2.1 1993	Sulfate	411	mg/L	9.0	07/19/23 10:21	
92677694005	HAM-PT-08					
	Performed by	CUSTOMER			07/17/23 17:17	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92677694

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92677694005	HAM-PT-08					
	pH	6.66	Std. Units		07/17/23 17:17	
EPA 6010D	Manganese	8.7	mg/L	0.040	07/20/23 16:24	
EPA 6010D	Potassium	6.0	mg/L	0.50	07/20/23 16:24	
EPA 6010D	Sodium	6.9	mg/L	1.0	07/20/23 16:24	
EPA 6010D	Calcium	161	mg/L	1.0	07/20/23 16:24	
EPA 6010D	Magnesium	18.9	mg/L	0.050	07/20/23 16:24	
EPA 6010D	Iron	24.2	mg/L	0.040	07/25/23 16:38	
EPA 6020B	Arsenic	0.33	mg/L	0.010	07/19/23 18:36	
EPA 6020B	Barium	0.051	mg/L	0.0050	07/19/23 18:36	
EPA 6020B	Beryllium	0.00011J	mg/L	0.00050	07/19/23 18:36	
EPA 6020B	Boron	1.0	mg/L	0.20	07/21/23 17:13	
EPA 6020B	Cobalt	0.031	mg/L	0.0050	07/19/23 18:36	
EPA 6020B	Lithium	0.065	mg/L	0.030	07/19/23 18:36	
EPA 6020B	Molybdenum	0.0079J	mg/L	0.010	07/19/23 18:36	
SM 2540C-2015	Total Dissolved Solids	734	mg/L	25.0	07/18/23 15:25	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	107	mg/L	5.0	07/20/23 17:03	
SM 2320B-2011	Alkalinity, Total as CaCO3	107	mg/L	5.0	07/20/23 17:03	
SM 4500-S2D-2011	Sulfide	0.036J	mg/L	0.10	07/20/23 03:42	
EPA 300.0 Rev 2.1 1993	Chloride	17.0	mg/L	1.0	07/19/23 04:38	
EPA 300.0 Rev 2.1 1993	Fluoride	0.36	mg/L	0.10	07/19/23 04:38	
EPA 300.0 Rev 2.1 1993	Sulfate	417	mg/L	8.0	07/19/23 12:00	
92677694006	HAM-AP1-FD-01					
EPA 6010D	Iron	24.6	mg/L	0.040	07/25/23 16:48	
EPA 6010D	Manganese	8.6	mg/L	0.040	07/20/23 16:29	
EPA 6010D	Potassium	6.4	mg/L	0.50	07/20/23 16:29	
EPA 6010D	Sodium	6.6	mg/L	1.0	07/20/23 16:29	
EPA 6010D	Calcium	180	mg/L	1.0	07/20/23 16:29	
EPA 6010D	Magnesium	19.6	mg/L	0.050	07/20/23 16:29	
EPA 6020B	Arsenic	0.34	mg/L	0.010	07/19/23 18:54	
EPA 6020B	Barium	0.057	mg/L	0.0050	07/19/23 18:54	
EPA 6020B	Beryllium	0.00011J	mg/L	0.00050	07/19/23 18:54	
EPA 6020B	Boron	0.99	mg/L	0.20	07/21/23 17:19	
EPA 6020B	Cobalt	0.14	mg/L	0.0050	07/19/23 18:54	
EPA 6020B	Lithium	0.060	mg/L	0.030	07/19/23 18:54	
EPA 6020B	Molybdenum	0.018	mg/L	0.010	07/19/23 18:54	
EPA 6020B	Thallium	0.00025J	mg/L	0.0010	07/19/23 18:54	
SM 2540C-2015	Total Dissolved Solids	804	mg/L	25.0	07/18/23 15:25	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	102	mg/L	5.0	07/20/23 17:12	
SM 2320B-2011	Alkalinity, Total as CaCO3	102	mg/L	5.0	07/20/23 17:12	
EPA 300.0 Rev 2.1 1993	Chloride	15.6	mg/L	1.0	07/19/23 04:53	
EPA 300.0 Rev 2.1 1993	Fluoride	0.31	mg/L	0.10	07/19/23 04:53	
EPA 300.0 Rev 2.1 1993	Sulfate	428	mg/L	9.0	07/19/23 12:56	
92677694008	HAM-HGWC-13					
	Performed by	CUSTOMER			07/17/23 17:17	
	pH	6.67	Std. Units		07/17/23 17:17	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92677694

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92677694008	HAM-HGWC-13					
EPA 6010D	Iron	7.2	mg/L	0.040	07/20/23 16:39	
EPA 6010D	Manganese	8.9	mg/L	0.040	07/20/23 16:39	
EPA 6010D	Potassium	6.0	mg/L	0.50	07/20/23 16:39	
EPA 6010D	Sodium	6.8	mg/L	1.0	07/20/23 16:39	
EPA 6010D	Calcium	179	mg/L	1.0	07/20/23 16:39	
EPA 6010D	Magnesium	19.5	mg/L	0.050	07/20/23 16:39	
EPA 6020B	Arsenic	0.63	mg/L	0.010	07/19/23 19:06	
EPA 6020B	Barium	0.056	mg/L	0.0050	07/19/23 19:06	
EPA 6020B	Beryllium	0.00012J	mg/L	0.00050	07/19/23 19:06	
EPA 6020B	Boron	1.0	mg/L	0.20	07/21/23 17:43	
EPA 6020B	Cobalt	0.018	mg/L	0.0050	07/19/23 19:06	
EPA 6020B	Lithium	0.048	mg/L	0.030	07/19/23 19:06	
EPA 6020B	Molybdenum	0.017	mg/L	0.010	07/19/23 19:06	
EPA 6020B	Thallium	0.00030J	mg/L	0.0010	07/19/23 19:06	
SM 2540C-2015	Total Dissolved Solids	817	mg/L	25.0	07/18/23 15:31	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	140	mg/L	5.0	07/20/23 17:26	
SM 2320B-2011	Alkalinity, Total as CaCO3	140	mg/L	5.0	07/20/23 17:26	
EPA 300.0 Rev 2.1 1993	Chloride	17.8	mg/L	1.0	07/19/23 05:50	
EPA 300.0 Rev 2.1 1993	Fluoride	0.32	mg/L	0.10	07/19/23 05:50	
EPA 300.0 Rev 2.1 1993	Sulfate	393	mg/L	8.0	07/19/23 13:10	M1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-HGWC-8		Lab ID: 92677694001		Collected: 07/13/23 10:35		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Field Data		Analytical Method: Pace Analytical Services - Charlotte							
Performed by	CUSTOMER				1		07/17/23 17:16		
pH	6.65	Std. Units			1		07/17/23 17:16		
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Manganese	0.28	mg/L	0.040	0.011	1	07/20/23 09:50	07/20/23 15:39	7439-96-5	
Potassium	6.9	mg/L	0.50	0.15	1	07/20/23 09:50	07/20/23 15:39	7440-09-7	
Sodium	8.8	mg/L	1.0	0.58	1	07/20/23 09:50	07/20/23 15:39	7440-23-5	M1
Calcium	107	mg/L	1.0	0.12	1	07/20/23 09:50	07/20/23 15:39	7440-70-2	M1
Magnesium	14.9	mg/L	0.050	0.012	1	07/20/23 09:50	07/20/23 15:39	7439-95-4	M1
Iron	0.27	mg/L	0.040	0.025	1	07/20/23 09:50	07/25/23 15:53	7439-89-6	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.0012	1	07/18/23 13:46	07/19/23 17:55	7440-36-0	
Arsenic	ND	mg/L	0.010	0.0037	1	07/18/23 13:46	07/19/23 17:55	7440-38-2	
Barium	0.047	mg/L	0.0050	0.00067	1	07/18/23 13:46	07/19/23 17:55	7440-39-3	
Beryllium	0.000073J	mg/L	0.00050	0.000054	1	07/18/23 13:46	07/19/23 17:55	7440-41-7	
Boron	2.0	mg/L	0.20	0.043	5	07/18/23 13:46	07/21/23 16:37	7440-42-8	
Cadmium	0.00031J	mg/L	0.00050	0.00011	1	07/18/23 13:46	07/19/23 17:55	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	07/18/23 13:46	07/19/23 17:55	7440-47-3	
Cobalt	0.0015J	mg/L	0.0050	0.00039	1	07/18/23 13:46	07/19/23 17:55	7440-48-4	
Lithium	0.0015J	mg/L	0.030	0.00073	1	07/18/23 13:46	07/19/23 17:55	7439-93-2	
Molybdenum	0.30	mg/L	0.010	0.00074	1	07/18/23 13:46	07/19/23 17:55	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	07/18/23 13:46	07/19/23 17:55	7782-49-2	
Thallium	0.00026J	mg/L	0.0010	0.00018	1	07/18/23 13:46	07/19/23 17:55	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	07/27/23 12:00	07/27/23 14:51	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	513	mg/L	25.0	25.0	1		07/18/23 15:24		
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO3)	136	mg/L	5.0	5.0	1		07/19/23 19:16		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		07/19/23 19:16		
Alkalinity, Total as CaCO3	136	mg/L	5.0	5.0	1		07/19/23 19:16		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-HGWC-8		Lab ID: 92677694001		Collected: 07/13/23 10:35		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		07/20/23 03:39	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	47.9	mg/L	1.0	0.60	1		07/19/23 03:12	16887-00-6	
Fluoride	0.49	mg/L	0.10	0.050	1		07/19/23 03:12	16984-48-8	
Sulfate	163	mg/L	3.0	1.5	3		07/19/23 09:10	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92677694

Sample: HAM-PT-09		Lab ID: 92677694002		Collected: 07/13/23 12:47		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Field Data		Analytical Method: Pace Analytical Services - Charlotte							
Performed by	CUSTOMER				1		07/17/23 17:16		
pH	6.57	Std. Units			1		07/17/23 17:16		
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	0.33	mg/L	0.040	0.025	1	07/20/23 09:50	07/25/23 16:08	7439-89-6	
Manganese	0.79	mg/L	0.040	0.011	1	07/20/23 09:50	07/20/23 15:59	7439-96-5	
Potassium	6.8	mg/L	0.50	0.15	1	07/20/23 09:50	07/20/23 15:59	7440-09-7	
Sodium	10.6	mg/L	1.0	0.58	1	07/20/23 09:50	07/20/23 15:59	7440-23-5	
Calcium	110	mg/L	1.0	0.12	1	07/20/23 09:50	07/20/23 15:59	7440-70-2	
Magnesium	15.6	mg/L	0.050	0.012	1	07/20/23 09:50	07/20/23 15:59	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	0.0027J	mg/L	0.0030	0.0012	1	07/18/23 13:46	07/19/23 18:19	7440-36-0	
Arsenic	ND	mg/L	0.010	0.0037	1	07/18/23 13:46	07/19/23 18:19	7440-38-2	
Barium	0.053	mg/L	0.0050	0.00067	1	07/18/23 13:46	07/19/23 18:19	7440-39-3	
Beryllium	0.000077J	mg/L	0.00050	0.000054	1	07/18/23 13:46	07/19/23 18:19	7440-41-7	
Boron	2.1	mg/L	0.20	0.043	5	07/18/23 13:46	07/21/23 16:55	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	07/18/23 13:46	07/19/23 18:19	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	07/18/23 13:46	07/19/23 18:19	7440-47-3	
Cobalt	0.0045J	mg/L	0.0050	0.00039	1	07/18/23 13:46	07/19/23 18:19	7440-48-4	
Lithium	0.0013J	mg/L	0.030	0.00073	1	07/18/23 13:46	07/19/23 18:19	7439-93-2	
Molybdenum	0.065	mg/L	0.010	0.00074	1	07/18/23 13:46	07/19/23 18:19	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	07/18/23 13:46	07/19/23 18:19	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00018	1	07/18/23 13:46	07/19/23 18:19	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	07/27/23 12:00	07/27/23 14:53	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	534	mg/L	25.0	25.0	1		07/18/23 15:24		
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO3)	144	mg/L	5.0	5.0	1		07/19/23 19:26		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		07/19/23 19:26		
Alkalinity, Total as CaCO3	144	mg/L	5.0	5.0	1		07/19/23 19:26		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-PT-09		Lab ID: 92677694002		Collected: 07/13/23 12:47		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		07/20/23 03:41	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	55.3	mg/L	1.0	0.60	1		07/19/23 03:27	16887-00-6	
Fluoride	0.24	mg/L	0.10	0.050	1		07/19/23 03:27	16984-48-8	
Sulfate	160	mg/L	3.0	1.5	3		07/19/23 09:53	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92677694

Sample: HAM-PT-10		Lab ID: 92677694003		Collected: 07/13/23 14:15		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Field Data		Analytical Method: Pace Analytical Services - Charlotte							
Performed by	CUSTOMER				1		07/17/23 17:16		
pH	7.01	Std. Units			1		07/17/23 17:16		
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Manganese	3.5	mg/L	0.040	0.011	1	07/20/23 09:50	07/20/23 16:14	7439-96-5	
Potassium	7.1	mg/L	0.50	0.15	1	07/20/23 09:50	07/20/23 16:14	7440-09-7	
Sodium	10.5	mg/L	1.0	0.58	1	07/20/23 09:50	07/20/23 16:14	7440-23-5	
Calcium	127	mg/L	1.0	0.12	1	07/20/23 09:50	07/20/23 16:14	7440-70-2	
Magnesium	16.8	mg/L	0.050	0.012	1	07/20/23 09:50	07/20/23 16:14	7439-95-4	
Iron	3.1	mg/L	0.040	0.025	1	07/20/23 09:50	07/25/23 16:12	7439-89-6	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.0012	1	07/18/23 13:46	07/19/23 18:25	7440-36-0	
Arsenic	ND	mg/L	0.010	0.0037	1	07/18/23 13:46	07/19/23 18:25	7440-38-2	
Barium	0.074	mg/L	0.0050	0.00067	1	07/18/23 13:46	07/19/23 18:25	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000054	1	07/18/23 13:46	07/19/23 18:25	7440-41-7	
Boron	2.2	mg/L	0.20	0.043	5	07/18/23 13:46	07/21/23 17:01	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	07/18/23 13:46	07/19/23 18:25	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	07/18/23 13:46	07/19/23 18:25	7440-47-3	
Cobalt	0.0026J	mg/L	0.0050	0.00039	1	07/18/23 13:46	07/19/23 18:25	7440-48-4	
Lithium	0.0014J	mg/L	0.030	0.00073	1	07/18/23 13:46	07/19/23 18:25	7439-93-2	
Molybdenum	0.10	mg/L	0.010	0.00074	1	07/18/23 13:46	07/19/23 18:25	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	07/18/23 13:46	07/19/23 18:25	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00018	1	07/18/23 13:46	07/19/23 18:25	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	07/27/23 12:00	07/27/23 15:09	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	557	mg/L	25.0	25.0	1		07/18/23 15:24		
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO3)	185	mg/L	5.0	5.0	1		07/20/23 16:41		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		07/20/23 16:41		
Alkalinity, Total as CaCO3	185	mg/L	5.0	5.0	1		07/20/23 16:41		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-PT-10		Lab ID: 92677694003		Collected: 07/13/23 14:15		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		07/20/23 03:41	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	67.2	mg/L	1.0	0.60	1		07/19/23 04:10	16887-00-6	
Fluoride	0.33	mg/L	0.10	0.050	1		07/19/23 04:10	16984-48-8	
Sulfate	145	mg/L	3.0	1.5	3		07/19/23 10:07	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92677694

Sample: HAM-PT-07		Lab ID: 92677694004		Collected: 07/13/23 16:22		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Field Data									
Analytical Method: Pace Analytical Services - Charlotte									
Performed by	CUSTOMER				1		07/17/23 17:16		
pH	6.76	Std. Units			1		07/17/23 17:16		
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Manganese	8.2	mg/L	0.040	0.011	1	07/20/23 09:50	07/20/23 16:19	7439-96-5	
Potassium	6.0	mg/L	0.50	0.15	1	07/20/23 09:50	07/20/23 16:19	7440-09-7	
Sodium	6.1	mg/L	1.0	0.58	1	07/20/23 09:50	07/20/23 16:19	7440-23-5	
Calcium	168	mg/L	1.0	0.12	1	07/20/23 09:50	07/20/23 16:19	7440-70-2	
Magnesium	18.5	mg/L	0.050	0.012	1	07/20/23 09:50	07/20/23 16:19	7439-95-4	
Iron	23.8	mg/L	0.040	0.025	1	07/20/23 09:50	07/25/23 16:17	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	07/18/23 13:46	07/19/23 18:30	7440-36-0	
Arsenic	0.34	mg/L	0.010	0.0037	1	07/18/23 13:46	07/19/23 18:30	7440-38-2	
Barium	0.056	mg/L	0.0050	0.00067	1	07/18/23 13:46	07/19/23 18:30	7440-39-3	
Beryllium	0.00012J	mg/L	0.00050	0.000054	1	07/18/23 13:46	07/19/23 18:30	7440-41-7	
Boron	1.0	mg/L	0.20	0.043	5	07/18/23 13:46	07/21/23 17:07	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	07/18/23 13:46	07/19/23 18:30	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	07/18/23 13:46	07/19/23 18:30	7440-47-3	
Cobalt	0.13	mg/L	0.0050	0.00039	1	07/18/23 13:46	07/19/23 18:30	7440-48-4	
Lithium	0.060	mg/L	0.030	0.00073	1	07/18/23 13:46	07/19/23 18:30	7439-93-2	
Molybdenum	0.017	mg/L	0.010	0.00074	1	07/18/23 13:46	07/19/23 18:30	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	07/18/23 13:46	07/19/23 18:30	7782-49-2	
Thallium	0.00024J	mg/L	0.0010	0.00018	1	07/18/23 13:46	07/19/23 18:30	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	07/27/23 12:00	07/27/23 15:12	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	808	mg/L	25.0	25.0	1		07/18/23 15:24		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	102	mg/L	5.0	5.0	1		07/20/23 16:53		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		07/20/23 16:53		
Alkalinity, Total as CaCO3	102	mg/L	5.0	5.0	1		07/20/23 16:53		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-PT-07		Lab ID: 92677694004		Collected: 07/13/23 16:22		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		07/20/23 03:42	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	15.7	mg/L	1.0	0.60	1		07/19/23 04:24	16887-00-6	
Fluoride	0.36	mg/L	0.10	0.050	1		07/19/23 04:24	16984-48-8	
Sulfate	411	mg/L	9.0	4.5	9		07/19/23 10:21	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-PT-08		Lab ID: 92677694005		Collected: 07/13/23 17:51		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Field Data		Analytical Method: Pace Analytical Services - Charlotte							
Performed by	CUSTOMER				1		07/17/23 17:17		
pH	6.66	Std. Units			1		07/17/23 17:17		
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Manganese	8.7	mg/L	0.040	0.011	1	07/20/23 09:50	07/20/23 16:24	7439-96-5	
Potassium	6.0	mg/L	0.50	0.15	1	07/20/23 09:50	07/20/23 16:24	7440-09-7	
Sodium	6.9	mg/L	1.0	0.58	1	07/20/23 09:50	07/20/23 16:24	7440-23-5	
Calcium	161	mg/L	1.0	0.12	1	07/20/23 09:50	07/20/23 16:24	7440-70-2	
Magnesium	18.9	mg/L	0.050	0.012	1	07/20/23 09:50	07/20/23 16:24	7439-95-4	
Iron	24.2	mg/L	0.040	0.025	1	07/20/23 09:50	07/25/23 16:38	7439-89-6	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.0012	1	07/18/23 13:46	07/19/23 18:36	7440-36-0	
Arsenic	0.33	mg/L	0.010	0.0037	1	07/18/23 13:46	07/19/23 18:36	7440-38-2	
Barium	0.051	mg/L	0.0050	0.00067	1	07/18/23 13:46	07/19/23 18:36	7440-39-3	
Beryllium	0.00011J	mg/L	0.00050	0.000054	1	07/18/23 13:46	07/19/23 18:36	7440-41-7	
Boron	1.0	mg/L	0.20	0.043	5	07/18/23 13:46	07/21/23 17:13	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	07/18/23 13:46	07/19/23 18:36	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	07/18/23 13:46	07/19/23 18:36	7440-47-3	
Cobalt	0.031	mg/L	0.0050	0.00039	1	07/18/23 13:46	07/19/23 18:36	7440-48-4	
Lithium	0.065	mg/L	0.030	0.00073	1	07/18/23 13:46	07/19/23 18:36	7439-93-2	
Molybdenum	0.0079J	mg/L	0.010	0.00074	1	07/18/23 13:46	07/19/23 18:36	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	07/18/23 13:46	07/19/23 18:36	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00018	1	07/18/23 13:46	07/19/23 18:36	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	07/27/23 12:00	07/27/23 15:14	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	734	mg/L	25.0	25.0	1		07/18/23 15:25		
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO3)	107	mg/L	5.0	5.0	1		07/20/23 17:03		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		07/20/23 17:03		
Alkalinity, Total as CaCO3	107	mg/L	5.0	5.0	1		07/20/23 17:03		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-PT-08		Lab ID: 92677694005		Collected: 07/13/23 17:51		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	0.036J	mg/L	0.10	0.022	1		07/20/23 03:42	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	17.0	mg/L	1.0	0.60	1		07/19/23 04:38	16887-00-6	
Fluoride	0.36	mg/L	0.10	0.050	1		07/19/23 04:38	16984-48-8	
Sulfate	417	mg/L	8.0	4.0	8		07/19/23 12:00	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-AP1-FD-01		Lab ID: 92677694006		Collected: 07/13/23 00:00		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	24.6	mg/L	0.040	0.025	1	07/20/23 09:50	07/25/23 16:48	7439-89-6	
Manganese	8.6	mg/L	0.040	0.011	1	07/20/23 09:50	07/20/23 16:29	7439-96-5	
Potassium	6.4	mg/L	0.50	0.15	1	07/20/23 09:50	07/20/23 16:29	7440-09-7	
Sodium	6.6	mg/L	1.0	0.58	1	07/20/23 09:50	07/20/23 16:29	7440-23-5	
Calcium	180	mg/L	1.0	0.12	1	07/20/23 09:50	07/20/23 16:29	7440-70-2	
Magnesium	19.6	mg/L	0.050	0.012	1	07/20/23 09:50	07/20/23 16:29	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	07/18/23 13:46	07/19/23 18:54	7440-36-0	
Arsenic	0.34	mg/L	0.010	0.0037	1	07/18/23 13:46	07/19/23 18:54	7440-38-2	
Barium	0.057	mg/L	0.0050	0.00067	1	07/18/23 13:46	07/19/23 18:54	7440-39-3	
Beryllium	0.00011J	mg/L	0.00050	0.000054	1	07/18/23 13:46	07/19/23 18:54	7440-41-7	
Boron	0.99	mg/L	0.20	0.043	5	07/18/23 13:46	07/21/23 17:19	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	07/18/23 13:46	07/19/23 18:54	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	07/18/23 13:46	07/19/23 18:54	7440-47-3	
Cobalt	0.14	mg/L	0.0050	0.00039	1	07/18/23 13:46	07/19/23 18:54	7440-48-4	
Lithium	0.060	mg/L	0.030	0.00073	1	07/18/23 13:46	07/19/23 18:54	7439-93-2	
Molybdenum	0.018	mg/L	0.010	0.00074	1	07/18/23 13:46	07/19/23 18:54	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	07/18/23 13:46	07/19/23 18:54	7782-49-2	
Thallium	0.00025J	mg/L	0.0010	0.00018	1	07/18/23 13:46	07/19/23 18:54	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	07/27/23 12:00	07/27/23 15:17	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	804	mg/L	25.0	25.0	1		07/18/23 15:25		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	102	mg/L	5.0	5.0	1		07/20/23 17:12		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		07/20/23 17:12		
Alkalinity, Total as CaCO ₃	102	mg/L	5.0	5.0	1		07/20/23 17:12		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		07/20/23 03:42	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	15.6	mg/L	1.0	0.60	1		07/19/23 04:53	16887-00-6	
Fluoride	0.31	mg/L	0.10	0.050	1		07/19/23 04:53	16984-48-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-AP1-FD-01		Lab ID: 92677694006		Collected: 07/13/23 00:00		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Sulfate	428	mg/L	9.0	4.5	9		07/19/23 12:56	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-AP1-FB-01		Lab ID: 92677694007		Collected: 07/17/23 08:40		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Manganese	ND	mg/L	0.040	0.011	1	07/20/23 09:50	07/20/23 16:34	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	07/20/23 09:50	07/20/23 16:34	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	07/20/23 09:50	07/20/23 16:34	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	07/20/23 09:50	07/20/23 16:34	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	07/20/23 09:50	07/20/23 16:34	7439-95-4	
Iron	ND	mg/L	0.040	0.025	1	07/20/23 09:50	07/25/23 16:53	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	07/18/23 13:46	07/19/23 19:00	7440-36-0	
Arsenic	ND	mg/L	0.010	0.0037	1	07/18/23 13:46	07/19/23 19:00	7440-38-2	
Barium	ND	mg/L	0.0050	0.00067	1	07/18/23 13:46	07/19/23 19:00	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000054	1	07/18/23 13:46	07/19/23 19:00	7440-41-7	
Boron	ND	mg/L	0.040	0.0086	1	07/18/23 13:46	07/21/23 17:37	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	07/18/23 13:46	07/19/23 19:00	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	07/18/23 13:46	07/19/23 19:00	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00039	1	07/18/23 13:46	07/19/23 19:00	7440-48-4	
Lithium	ND	mg/L	0.030	0.00073	1	07/18/23 13:46	07/19/23 19:00	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00074	1	07/18/23 13:46	07/19/23 19:00	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	07/18/23 13:46	07/19/23 19:00	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00018	1	07/18/23 13:46	07/19/23 19:00	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	07/27/23 12:00	07/27/23 15:19	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		07/18/23 15:30		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		07/20/23 17:22		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		07/20/23 17:22		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		07/20/23 17:22		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		07/20/23 04:00	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		07/19/23 05:07	16887-00-6	
Fluoride	ND	mg/L	0.10	0.050	1		07/19/23 05:07	16984-48-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-AP1-FB-01		Lab ID: 92677694007		Collected: 07/17/23 08:40		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Sulfate	ND	mg/L	1.0	0.50	1		07/19/23 05:07	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-HGWC-13		Lab ID: 92677694008		Collected: 07/17/23 11:47		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Field Data									
Analytical Method: Pace Analytical Services - Charlotte									
Performed by	CUSTOMER				1		07/17/23 17:17		
pH	6.67	Std. Units			1		07/17/23 17:17		
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	7.2	mg/L	0.040	0.025	1	07/20/23 09:50	07/20/23 16:39	7439-89-6	
Manganese	8.9	mg/L	0.040	0.011	1	07/20/23 09:50	07/20/23 16:39	7439-96-5	
Potassium	6.0	mg/L	0.50	0.15	1	07/20/23 09:50	07/20/23 16:39	7440-09-7	
Sodium	6.8	mg/L	1.0	0.58	1	07/20/23 09:50	07/20/23 16:39	7440-23-5	
Calcium	179	mg/L	1.0	0.12	1	07/20/23 09:50	07/20/23 16:39	7440-70-2	
Magnesium	19.5	mg/L	0.050	0.012	1	07/20/23 09:50	07/20/23 16:39	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	07/18/23 13:46	07/19/23 19:06	7440-36-0	
Arsenic	0.63	mg/L	0.010	0.0037	1	07/18/23 13:46	07/19/23 19:06	7440-38-2	
Barium	0.056	mg/L	0.0050	0.00067	1	07/18/23 13:46	07/19/23 19:06	7440-39-3	
Beryllium	0.00012J	mg/L	0.00050	0.000054	1	07/18/23 13:46	07/19/23 19:06	7440-41-7	
Boron	1.0	mg/L	0.20	0.043	5	07/18/23 13:46	07/21/23 17:43	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	07/18/23 13:46	07/19/23 19:06	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	07/18/23 13:46	07/19/23 19:06	7440-47-3	
Cobalt	0.018	mg/L	0.0050	0.00039	1	07/18/23 13:46	07/19/23 19:06	7440-48-4	
Lithium	0.048	mg/L	0.030	0.00073	1	07/18/23 13:46	07/19/23 19:06	7439-93-2	
Molybdenum	0.017	mg/L	0.010	0.00074	1	07/18/23 13:46	07/19/23 19:06	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	07/18/23 13:46	07/19/23 19:06	7782-49-2	
Thallium	0.00030J	mg/L	0.0010	0.00018	1	07/18/23 13:46	07/19/23 19:06	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	07/27/23 12:00	07/27/23 15:22	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	817	mg/L	25.0	25.0	1		07/18/23 15:31		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	140	mg/L	5.0	5.0	1		07/20/23 17:26		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		07/20/23 17:26		
Alkalinity, Total as CaCO3	140	mg/L	5.0	5.0	1		07/20/23 17:26		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92677694

Sample: HAM-HGWC-13		Lab ID: 92677694008		Collected: 07/17/23 11:47		Received: 07/17/23 12:30		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		07/20/23 04:00	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	17.8	mg/L	1.0	0.60	1		07/19/23 05:50	16887-00-6	
Fluoride	0.32	mg/L	0.10	0.050	1		07/19/23 05:50	16984-48-8	
Sulfate	393	mg/L	8.0	4.0	8		07/19/23 13:10	14808-79-8	M1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch: 787863

Analysis Method: EPA 6010D

QC Batch Method: EPA 3010A

Analysis Description: 6010D ATL

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008

METHOD BLANK: 4084625

Matrix: Water

Associated Lab Samples: 92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	07/20/23 15:30	
Iron	mg/L	ND	0.040	0.025	07/25/23 15:43	
Magnesium	mg/L	ND	0.050	0.012	07/20/23 15:30	
Manganese	mg/L	ND	0.040	0.011	07/20/23 15:30	
Potassium	mg/L	ND	0.50	0.15	07/20/23 15:30	
Sodium	mg/L	ND	1.0	0.58	07/20/23 15:30	

LABORATORY CONTROL SAMPLE: 4084626

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	0.92J	92	80-120	
Iron	mg/L	1	0.99	99	80-120	
Magnesium	mg/L	1	0.93	93	80-120	
Manganese	mg/L	1	0.94	94	80-120	
Potassium	mg/L	1	0.88	88	80-120	
Sodium	mg/L	1	0.84J	84	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4085060 4085061

Parameter	Units	92677694001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Calcium	mg/L	107	1	1	109	104	196	-279	75-125	4	20	M1
Iron	mg/L	0.27	1	1	1.3	1.3	99	105	75-125	5	20	
Magnesium	mg/L	14.9	1	1	16.2	15.6	128	74	75-125	3	20	M1
Manganese	mg/L	0.28	1	1	1.2	1.3	96	100	75-125	3	20	
Potassium	mg/L	6.9	1	1	8.1	7.8	118	90	75-125	3	20	
Sodium	mg/L	8.8	1	1	9.9	9.5	111	73	75-125	4	20	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch:	787489	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008		

METHOD BLANK: 4082463

Matrix: Water

Associated Lab Samples: 92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.0012	07/19/23 17:43	
Arsenic	mg/L	ND	0.010	0.0037	07/19/23 17:43	
Barium	mg/L	ND	0.0050	0.00067	07/19/23 17:43	
Beryllium	mg/L	ND	0.00050	0.000054	07/19/23 17:43	
Boron	mg/L	ND	0.040	0.0086	07/21/23 16:25	
Cadmium	mg/L	ND	0.00050	0.00011	07/19/23 17:43	
Chromium	mg/L	ND	0.0050	0.0011	07/19/23 17:43	
Cobalt	mg/L	ND	0.0050	0.00039	07/19/23 17:43	
Lithium	mg/L	ND	0.030	0.00073	07/19/23 17:43	
Molybdenum	mg/L	ND	0.010	0.00074	07/19/23 17:43	
Selenium	mg/L	ND	0.0050	0.0014	07/19/23 17:43	
Thallium	mg/L	ND	0.0010	0.00018	07/19/23 17:43	

LABORATORY CONTROL SAMPLE: 4082464

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.11	107	80-120	
Arsenic	mg/L	0.1	0.099	99	80-120	
Barium	mg/L	0.1	0.096	96	80-120	
Beryllium	mg/L	0.1	0.10	102	80-120	
Boron	mg/L	1	1.1	110	80-120	
Cadmium	mg/L	0.1	0.10	103	80-120	
Chromium	mg/L	0.1	0.10	102	80-120	
Cobalt	mg/L	0.1	0.10	101	80-120	
Lithium	mg/L	0.1	0.10	103	80-120	
Molybdenum	mg/L	0.1	0.10	102	80-120	
Selenium	mg/L	0.1	0.10	101	80-120	
Thallium	mg/L	0.1	0.097	97	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4082465 4082466

Parameter	Units	MS		MSD		MS		MSD		% Rec Limits	Max	
		92677694001	Spike Conc.	Spike Conc.	Result	Result	% Rec	% Rec	Result		RPD	RPD
Antimony	mg/L	ND	0.1	0.1	0.11	0.11	109	110	75-125	1	20	
Arsenic	mg/L	ND	0.1	0.1	0.10	0.11	104	106	75-125	2	20	
Barium	mg/L	0.047	0.1	0.1	0.16	0.16	114	113	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4082465 4082466												
Parameter	Units	92677694001	MS	MSD	MS	MSD	MS	MSD	% Rec	Max		
		Result	Spike	Spike								
Beryllium	mg/L	0.000073J	0.1	0.1	0.095	0.096	95	96	75-125	1	20	
Boron	mg/L	2.0	1	1	3.1	2.9	108	94	75-125	5	20	
Cadmium	mg/L	0.00031J	0.1	0.1	0.10	0.10	102	104	75-125	1	20	
Chromium	mg/L	ND	0.1	0.1	0.10	0.099	101	99	75-125	2	20	
Cobalt	mg/L	0.0015J	0.1	0.1	0.10	0.099	99	97	75-125	1	20	
Lithium	mg/L	0.0015J	0.1	0.1	0.099	0.099	97	98	75-125	0	20	
Molybdenum	mg/L	0.30	0.1	0.1	0.42	0.42	121	123	75-125	1	20	
Selenium	mg/L	ND	0.1	0.1	0.11	0.11	106	106	75-125	0	20	
Thallium	mg/L	0.00026J	0.1	0.1	0.097	0.096	97	96	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch:	789561	Analysis Method:	EPA 7470A
QC Batch Method:	EPA 7470A	Analysis Description:	7470 Mercury
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008		

METHOD BLANK:	4092350	Matrix:	Water
Associated Lab Samples:	92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	07/27/23 14:41	

LABORATORY CONTROL SAMPLE: 4092351						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0023	92	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:					4092352								4092353			
Parameter	Units	92677694002 Result	MS	MSD	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual				
			Spike Conc.	Spike Conc.												
Mercury	mg/L	ND	0.0025	0.0025	0.0021	0.0021	83	85	75-125	2	20					

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch:	787441	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008		

METHOD BLANK:	4082157	Matrix:	Water
Associated Lab Samples:	92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	07/18/23 15:23	

LABORATORY CONTROL SAMPLE: 4082158						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	409	102	80-120	

SAMPLE DUPLICATE: 4082159						
Parameter	Units	92677694001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	513	511	0	10	

SAMPLE DUPLICATE: 4082160						
Parameter	Units	92677696005 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	1460	1570	8	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch: 787723

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92677694001, 92677694002

METHOD BLANK: 4083535

Matrix: Water

Associated Lab Samples: 92677694001, 92677694002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	07/19/23 16:09	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	07/19/23 16:09	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	07/19/23 16:09	

LABORATORY CONTROL SAMPLE: 4083536

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.8	106	80-120	

LABORATORY CONTROL SAMPLE: 4083537

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	49.5	99	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4083538 4083539

Parameter	Units	92677420019 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	48.7	50	50	102	103	106	108	80-120	1	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4083540 4083541

Parameter	Units	92677318002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	330	50	50	390	394	120	129	80-120	1	25 M1	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch: 788121

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008

METHOD BLANK: 4085797

Matrix: Water

Associated Lab Samples: 92677694003, 92677694004, 92677694005, 92677694006, 92677694007, 92677694008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	07/20/23 16:09	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	07/20/23 16:09	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	07/20/23 16:09	

LABORATORY CONTROL SAMPLE: 4085798

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.4	103	80-120	

LABORATORY CONTROL SAMPLE: 4085799

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	50.7	101	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4085800 4085801

Parameter	Units	92677753005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	121	50	50	180	180	118	118	80-120	0	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4085802 4085803

Parameter	Units	92677753006 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	76.8	50	50	129	131	103	108	80-120	2	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch: 787902

Analysis Method: SM 4500-S2D-2011

QC Batch Method: SM 4500-S2D-2011

Analysis Description: 4500S2D Sulfide Water

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006

METHOD BLANK: 4084741

Matrix: Water

Associated Lab Samples: 92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	07/20/23 03:38	

LABORATORY CONTROL SAMPLE: 4084742

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.49	98	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4084743 4084744

Parameter	Units	92677694001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.47	0.47	93	93	80-120	0	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4084745 4084746

Parameter	Units	92677696005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.48	0.46	94	90	80-120	5	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch: 787903

Analysis Method: SM 4500-S2D-2011

QC Batch Method: SM 4500-S2D-2011

Analysis Description: 4500S2D Sulfide Water

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92677694007, 92677694008

METHOD BLANK: 4084747

Matrix: Water

Associated Lab Samples: 92677694007, 92677694008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	07/20/23 03:57	

LABORATORY CONTROL SAMPLE: 4084748

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.49	97	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4084749 4084750

Parameter	Units	92678161006 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.53	0.54	105	108	80-120	3	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4084751 4084752

Parameter	Units	92677696012 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.43	0.47	84	93	80-120	10	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch:	787373	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007		

METHOD BLANK:	4081842	Matrix:	Water
Associated Lab Samples:	92677694001, 92677694002, 92677694003, 92677694004, 92677694005, 92677694006, 92677694007		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	07/18/23 12:46	
Fluoride	mg/L	ND	0.10	0.050	07/18/23 12:46	
Sulfate	mg/L	ND	1.0	0.50	07/18/23 12:46	

LABORATORY CONTROL SAMPLE: 4081843						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	50.3	101	90-110	
Fluoride	mg/L	2.5	2.5	101	90-110	
Sulfate	mg/L	50	49.5	99	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4081844 4081845												
Parameter	Units	92677589002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	2.9	50	50	54.1	54.7	102	104	90-110	1	10	
Fluoride	mg/L	ND	2.5	2.5	2.7	2.7	107	107	90-110	0	10	
Sulfate	mg/L	25.2	50	50	75.9	76.5	101	103	90-110	1	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4081846 4081847												
Parameter	Units	92677589020 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	21.6	50	50	60.3	60.3	78	77	90-110	0	10	M1
Fluoride	mg/L	0.37J	2.5	2.5	2.8J	3.2J	96	113	90-110		10	M1
Sulfate	mg/L	3080	50	50	3000	2940	-145	-278	90-110	2	10	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92677694

QC Batch:	787377	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville

Associated Lab Samples: 92677694008

METHOD BLANK: 4081859

Matrix: Water

Associated Lab Samples: 92677694008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	07/19/23 05:21	
Fluoride	mg/L	ND	0.10	0.050	07/19/23 05:21	
Sulfate	mg/L	ND	1.0	0.50	07/19/23 05:21	

LABORATORY CONTROL SAMPLE: 4081860

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	50.4	101	90-110	
Fluoride	mg/L	2.5	2.4	98	90-110	
Sulfate	mg/L	50	49.8	100	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4081861 4081862

Parameter	Units	92677694008 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	17.8	50	50	69.7	70.1	104	105	90-110	1	10	
Fluoride	mg/L	0.32	2.5	2.5	2.8	2.8	98	99	90-110	1	10	
Sulfate	mg/L	393	50	50	422	418	58	49	90-110	1	10 M1	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1
Pace Project No.: 92677694

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92677694

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92677694001	HAM-HGWC-8				
92677694002	HAM-PT-09				
92677694003	HAM-PT-10				
92677694004	HAM-PT-07				
92677694005	HAM-PT-08				
92677694008	HAM-HGWC-13				
92677694001	HAM-HGWC-8	EPA 3010A	787863	EPA 6010D	788067
92677694002	HAM-PT-09	EPA 3010A	787863	EPA 6010D	788067
92677694003	HAM-PT-10	EPA 3010A	787863	EPA 6010D	788067
92677694004	HAM-PT-07	EPA 3010A	787863	EPA 6010D	788067
92677694005	HAM-PT-08	EPA 3010A	787863	EPA 6010D	788067
92677694006	HAM-AP1-FD-01	EPA 3010A	787863	EPA 6010D	788067
92677694007	HAM-AP1-FB-01	EPA 3010A	787863	EPA 6010D	788067
92677694008	HAM-HGWC-13	EPA 3010A	787863	EPA 6010D	788067
92677694001	HAM-HGWC-8	EPA 3005A	787489	EPA 6020B	787561
92677694002	HAM-PT-09	EPA 3005A	787489	EPA 6020B	787561
92677694003	HAM-PT-10	EPA 3005A	787489	EPA 6020B	787561
92677694004	HAM-PT-07	EPA 3005A	787489	EPA 6020B	787561
92677694005	HAM-PT-08	EPA 3005A	787489	EPA 6020B	787561
92677694006	HAM-AP1-FD-01	EPA 3005A	787489	EPA 6020B	787561
92677694007	HAM-AP1-FB-01	EPA 3005A	787489	EPA 6020B	787561
92677694008	HAM-HGWC-13	EPA 3005A	787489	EPA 6020B	787561
92677694001	HAM-HGWC-8	EPA 7470A	789561	EPA 7470A	789666
92677694002	HAM-PT-09	EPA 7470A	789561	EPA 7470A	789666
92677694003	HAM-PT-10	EPA 7470A	789561	EPA 7470A	789666
92677694004	HAM-PT-07	EPA 7470A	789561	EPA 7470A	789666
92677694005	HAM-PT-08	EPA 7470A	789561	EPA 7470A	789666
92677694006	HAM-AP1-FD-01	EPA 7470A	789561	EPA 7470A	789666
92677694007	HAM-AP1-FB-01	EPA 7470A	789561	EPA 7470A	789666
92677694008	HAM-HGWC-13	EPA 7470A	789561	EPA 7470A	789666
92677694001	HAM-HGWC-8	SM 2540C-2015	787441		
92677694002	HAM-PT-09	SM 2540C-2015	787441		
92677694003	HAM-PT-10	SM 2540C-2015	787441		
92677694004	HAM-PT-07	SM 2540C-2015	787441		
92677694005	HAM-PT-08	SM 2540C-2015	787441		
92677694006	HAM-AP1-FD-01	SM 2540C-2015	787441		
92677694007	HAM-AP1-FB-01	SM 2540C-2015	787441		
92677694008	HAM-HGWC-13	SM 2540C-2015	787441		
92677694001	HAM-HGWC-8	SM 2320B-2011	787723		
92677694002	HAM-PT-09	SM 2320B-2011	787723		
92677694003	HAM-PT-10	SM 2320B-2011	788121		
92677694004	HAM-PT-07	SM 2320B-2011	788121		
92677694005	HAM-PT-08	SM 2320B-2011	788121		
92677694006	HAM-AP1-FD-01	SM 2320B-2011	788121		
92677694007	HAM-AP1-FB-01	SM 2320B-2011	788121		
92677694008	HAM-HGWC-13	SM 2320B-2011	788121		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92677694

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92677694001	HAM-HGWC-8	SM 4500-S2D-2011	787902		
92677694002	HAM-PT-09	SM 4500-S2D-2011	787902		
92677694003	HAM-PT-10	SM 4500-S2D-2011	787902		
92677694004	HAM-PT-07	SM 4500-S2D-2011	787902		
92677694005	HAM-PT-08	SM 4500-S2D-2011	787902		
92677694006	HAM-AP1-FD-01	SM 4500-S2D-2011	787902		
92677694007	HAM-AP1-FB-01	SM 4500-S2D-2011	787903		
92677694008	HAM-HGWC-13	SM 4500-S2D-2011	787903		
92677694001	HAM-HGWC-8	EPA 300.0 Rev 2.1 1993	787373		
92677694002	HAM-PT-09	EPA 300.0 Rev 2.1 1993	787373		
92677694003	HAM-PT-10	EPA 300.0 Rev 2.1 1993	787373		
92677694004	HAM-PT-07	EPA 300.0 Rev 2.1 1993	787373		
92677694005	HAM-PT-08	EPA 300.0 Rev 2.1 1993	787373		
92677694006	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	787373		
92677694007	HAM-AP1-FB-01	EPA 300.0 Rev 2.1 1993	787373		
92677694008	HAM-HGWC-13	EPA 300.0 Rev 2.1 1993	787377		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



DC#_Title: ENV-FRM-HUN1-0083 v02_Sample Condition Upon Receipt

Effective Date: 11/14/2022

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

GAPower

Project #:

WO#: 92677694



Courier:

☐ Commercial☒ Fed Ex☐ UPS☐ USPS☐ Client☒ Pace☐ Other:

Custody Seal Present?

☒ Yes☐ No

Seals Intact?

☒ Yes☐ No

Packing Material:

☐ Bubble Wrap☒ Bubble Bags☐ None☐ Other

Thermometer:

☒ IR Gun ID:

214

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

6.5

Correction Factor:

Add/Subtract (°C)

0.0

Cooler Temp Corrected (°C):

6.5

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

Comments/Discrepancy:

Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.
Rush Turn Around Time Requested?	☐ Yes ☐ No ☐ N/A	4.
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A	
Containers Intact?	☒ Yes ☐ No ☐ N/A	7.
Dissolved analysis: Samples Field Filtered?	☐ Yes ☒ No ☐ N/A	8.
Sample Labels Match COC?	☒ Yes ☐ No ☐ N/A	9.
-Includes Date/Time/ID/Analysis Matrix:	WG	
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10.
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A	

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_Title: ENV-FRM-HUN1-0083 v02_Sample Condition Upon Receipt

Effective Date: 11/14/2022

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

W0#: 92677694

PM: BV

Due Date: 07/31/23

CLIENT: 92- GP-HAM

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic ZN Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGFU-Wide-mouthed Glass jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG94-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit)-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A – lab)	SP2T-250 mL Sterile Plastic (N/A – lab)	BP3R-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	V5GU-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)
1		21																									
2		21																									
3		21																									
4		21																									
5		21																									
6		21																									
7		21																									
8		21																									
9																											
10																											
11																											
12																											

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers.

CHAIN-OF-CUSTODY / Analytical Request Document
The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Section A Client Information:		Section B Required Project Information:		Section C Invoice Information:		REGULATORY AGENCY		
Client:	GA Power	Report To:	SCS Contacts	Company Name:	Southern Co.	☐ NPDES	☐ GROUND WATER	☐ DRINKING WATER
Address:	Atlanta, GA	Copy To:	Geosyntec Contacts	Address:		☐ UST	☐ RCRA	☒ OTHER
File To:	SCS Contacts	Task Code:	HAM-CCR-CA-20230713	Reference:	Bonnie Vang			
File:	SCS Contacts	Purchase Order No.:		Pace Project Manager:	Bonnie Vang			
Requested Due Date/AT:	10 Day	Project Name:	Hammond AP-2	Pace Profile #:	10839-16463-20	Site Location STATE:	GA	
Section D Required Client Information		Valid Matrix Codes		Requested Analysis Filtered (Y/N)		Residual Chlorine (Y/N)		
MATRIX CODE (see valid codes to left)		SAMPLE TYPE (G=GRAB C=COMP)		DATE		TIME		
SAMPLE ID (A-Z, 0-9 / .) Sample IDs MUST BE UNIQUE		COMPOSITE		COMPOSITE		COMPOSITE		
MATRIX CODE		DATE		TIME		DATE		TIME
SAMPLE TEMP AT COLLECTION		# OF CONTAINERS		Unpreserved		H ₂ SO ₄		HNO ₃
H ₂ SO ₄		HNO ₃		HCl		NaOH		Na ₂ S ₂ O ₃
Methanol		Other		Analysis Test		Full App. III and IV metals		Major Ions (10839-2)
Boron and Cobalt		Y		N		N		N
Pace Project No./ Lab I.D.		92677694		Temp in °C		Received on ice (Y/N)		Custody Sealed Cooler (Y/N)
Samples Intact (Y/N)								

Section D Additional Comments	RELINQUISHED BY / AFFILIATION	DATE	TIME	ACCEPTED BY / AFFILIATION	DATE	TIME	SAMPLE CONDITIONS
HAM-HGNC-8	Alana Wally Geosyntec	7/17/23	1230	Ben Williams / Pac	7/17/23	1230	
HAM-PT-09	Alana Wally Geosyntec	7/17/23	1425	Ben Williams / Pac	7/17/23	1425	
HAM-PT-10	Alana Wally Geosyntec	7/17/23	1425	Ben Williams / Pac	7/17/23	1425	
HAM-PT-D7	Alana Wally Geosyntec	7/17/23	1425	Ben Williams / Pac	7/17/23	1425	
HAM-PT-08	Alana Wally Geosyntec	7/17/23	1425	Ben Williams / Pac	7/17/23	1425	
HAM-AP1-ED-01	Alana Wally Geosyntec	7/17/23	1425	Ben Williams / Pac	7/17/23	1425	
HAM-AP1-FB-01	Alana Wally Geosyntec	7/17/23	1425	Ben Williams / Pac	7/17/23	1425	
HAM-AP1-HGNC-13	Alana Wally Geosyntec	7/17/23	1425	Ben Williams / Pac	7/17/23	1425	



August 25, 2023

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1 (CCR-CA)
Pace Project No.: 92682397

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on August 11, 2023. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Peachtree Corners, GA

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Angela M. Baioni

Angela Baioni for
Bonnie Vang
bonnie.vang@pacelabs.com
(704)875-9092
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92682397001	HAM-PT-07	Water	08/09/23 17:59	08/11/23 13:12
92682397002	HAM-PT-08	Water	08/09/23 10:50	08/11/23 13:12
92682397003	HAM-PT-09	Water	08/09/23 14:42	08/11/23 13:12
92682397004	HAM-PT-10	Water	08/09/23 13:05	08/11/23 13:12
92682397005	HAM-MW-53	Water	08/09/23 16:40	08/11/23 13:12
92682397006	HAM-MW-54	Water	08/09/23 16:51	08/11/23 13:12
92682397007	HAM-AP1-FD-06	Water	08/09/23 00:00	08/11/23 13:12
92682397008	HAM-AP1-FB-06	Water	08/09/23 16:50	08/11/23 13:12

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92682397001	HAM-PT-07	EPA 6010D	MS	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92682397002	HAM-PT-08	EPA 6010D	DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92682397003	HAM-PT-09	EPA 6010D	DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92682397004	HAM-PT-10	EPA 6010D	MS	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92682397005	HAM-MW-53	EPA 6020B	CW1	2
92682397006	HAM-MW-54	EPA 6020B	CW1	2
92682397007	HAM-AP1-FD-06	EPA 6010D	MS	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92682397008	HAM-AP1-FB-06	EPA 6010D	MS	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3

PASI-A = Pace Analytical Services - Asheville

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92682397001	HAM-PT-07					
EPA 6010D	Iron	27.1	mg/L	0.040	08/18/23 21:03	
EPA 6010D	Manganese	7.6	mg/L	0.040	08/18/23 21:03	
EPA 6010D	Potassium	6.8	mg/L	0.50	08/18/23 21:03	
EPA 6010D	Sodium	7.2	mg/L	1.0	08/18/23 21:03	
EPA 6010D	Calcium	173	mg/L	1.0	08/18/23 21:03	
EPA 6010D	Magnesium	19.4	mg/L	0.050	08/18/23 21:03	
EPA 6020B	Arsenic	0.27	mg/L	0.010	08/22/23 16:32	
EPA 6020B	Barium	0.053	mg/L	0.0050	08/22/23 16:32	
EPA 6020B	Beryllium	0.000095J	mg/L	0.00050	08/22/23 16:32	
EPA 6020B	Boron	0.93	mg/L	0.040	08/23/23 13:17	
EPA 6020B	Cobalt	0.090	mg/L	0.0050	08/23/23 13:17	
EPA 6020B	Lithium	0.069	mg/L	0.030	08/23/23 13:17	
EPA 6020B	Molybdenum	0.012	mg/L	0.010	08/22/23 16:32	
EPA 6020B	Thallium	0.00022J	mg/L	0.0010	08/22/23 16:32	
SM 2540C-2015	Total Dissolved Solids	771	mg/L	25.0	08/15/23 16:56	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	116	mg/L	5.0	08/16/23 15:20	
SM 2320B-2011	Alkalinity, Total as CaCO3	116	mg/L	5.0	08/16/23 15:20	
EPA 300.0 Rev 2.1 1993	Chloride	13.5	mg/L	1.0	08/15/23 21:32	
EPA 300.0 Rev 2.1 1993	Fluoride	0.28	mg/L	0.10	08/15/23 21:32	
EPA 300.0 Rev 2.1 1993	Sulfate	339	mg/L	7.0	08/16/23 08:19	
92682397002	HAM-PT-08					
EPA 6010D	Iron	22.0	mg/L	0.040	08/18/23 21:13	
EPA 6010D	Manganese	6.8	mg/L	0.040	08/18/23 21:13	
EPA 6010D	Potassium	6.3	mg/L	0.50	08/18/23 21:13	
EPA 6010D	Sodium	6.8	mg/L	1.0	08/18/23 21:13	
EPA 6010D	Calcium	146	mg/L	1.0	08/18/23 21:13	
EPA 6010D	Magnesium	17.3	mg/L	0.050	08/18/23 21:13	
EPA 6020B	Arsenic	0.32	mg/L	0.010	08/22/23 16:39	
EPA 6020B	Barium	0.050	mg/L	0.0050	08/22/23 16:39	
EPA 6020B	Beryllium	0.000073J	mg/L	0.00050	08/22/23 16:39	
EPA 6020B	Boron	0.99	mg/L	0.040	08/23/23 13:23	
EPA 6020B	Cobalt	0.032	mg/L	0.0050	08/22/23 16:39	
EPA 6020B	Lithium	0.073	mg/L	0.030	08/23/23 13:23	
EPA 6020B	Molybdenum	0.0071J	mg/L	0.010	08/22/23 16:39	
SM 2540C-2015	Total Dissolved Solids	682	mg/L	25.0	08/15/23 16:57	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	118	mg/L	5.0	08/16/23 15:40	
SM 2320B-2011	Alkalinity, Total as CaCO3	118	mg/L	5.0	08/16/23 15:40	
EPA 300.0 Rev 2.1 1993	Chloride	14.5	mg/L	1.0	08/15/23 22:30	
EPA 300.0 Rev 2.1 1993	Fluoride	0.27	mg/L	0.10	08/15/23 22:30	
EPA 300.0 Rev 2.1 1993	Sulfate	290	mg/L	6.0	08/16/23 09:16	M1
92682397003	HAM-PT-09					
EPA 6010D	Iron	0.10	mg/L	0.040	08/18/23 21:18	
EPA 6010D	Manganese	0.51	mg/L	0.040	08/18/23 21:18	
EPA 6010D	Potassium	7.7	mg/L	0.50	08/18/23 21:18	
EPA 6010D	Sodium	10.3	mg/L	1.0	08/18/23 21:18	
EPA 6010D	Calcium	136	mg/L	1.0	08/18/23 21:18	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92682397003	HAM-PT-09					
EPA 6010D	Magnesium	18.2	mg/L	0.050	08/18/23 21:18	
EPA 6020B	Barium	0.057	mg/L	0.0050	08/22/23 16:43	
EPA 6020B	Boron	1.6	mg/L	0.40	08/23/23 19:25	
EPA 6020B	Cobalt	0.0028J	mg/L	0.0050	08/22/23 16:43	
EPA 6020B	Lithium	0.0017J	mg/L	0.030	08/22/23 16:43	
EPA 6020B	Molybdenum	0.21	mg/L	0.010	08/22/23 16:43	
SM 2540C-2015	Total Dissolved Solids	594	mg/L	25.0	08/15/23 16:57	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	150	mg/L	5.0	08/16/23 15:50	
SM 2320B-2011	Alkalinity, Total as CaCO3	150	mg/L	5.0	08/16/23 15:50	
EPA 300.0 Rev 2.1 1993	Chloride	47.5	mg/L	1.0	08/15/23 23:14	
EPA 300.0 Rev 2.1 1993	Fluoride	0.26	mg/L	0.10	08/15/23 23:14	
EPA 300.0 Rev 2.1 1993	Sulfate	188	mg/L	4.0	08/16/23 09:59	
92682397004	HAM-PT-10					
EPA 6010D	Iron	2.9	mg/L	0.040	08/23/23 21:33	
EPA 6010D	Manganese	3.1	mg/L	0.040	08/23/23 21:33	
EPA 6010D	Potassium	6.7	mg/L	0.50	08/23/23 21:33	M1
EPA 6010D	Sodium	9.4	mg/L	1.0	08/23/23 21:33	M1
EPA 6010D	Calcium	116	mg/L	1.0	08/23/23 21:33	M1
EPA 6010D	Magnesium	16.8	mg/L	0.050	08/23/23 21:33	M1
EPA 6020B	Barium	0.070	mg/L	0.0050	08/22/23 16:51	
EPA 6020B	Boron	2.1	mg/L	0.40	08/23/23 19:48	
EPA 6020B	Cobalt	0.0019J	mg/L	0.0050	08/22/23 16:51	
EPA 6020B	Lithium	0.0012J	mg/L	0.030	08/22/23 16:51	
EPA 6020B	Molybdenum	0.096	mg/L	0.010	08/22/23 16:51	
SM 2540C-2015	Total Dissolved Solids	553	mg/L	25.0	08/15/23 16:57	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	199	mg/L	5.0	08/16/23 16:00	
SM 2320B-2011	Alkalinity, Total as CaCO3	199	mg/L	5.0	08/16/23 16:00	
SM 4500-S2D-2011	Sulfide	0.045J	mg/L	0.10	08/15/23 06:30	
EPA 300.0 Rev 2.1 1993	Chloride	62.5	mg/L	1.0	08/15/23 23:42	
EPA 300.0 Rev 2.1 1993	Fluoride	0.27	mg/L	0.10	08/15/23 23:42	
EPA 300.0 Rev 2.1 1993	Sulfate	123	mg/L	3.0	08/16/23 10:27	
92682397005	HAM-MW-53					
EPA 6020B	Boron	1.5	mg/L	0.040	08/22/23 20:17	
EPA 6020B	Molybdenum	0.14	mg/L	0.010	08/22/23 20:17	
92682397006	HAM-MW-54					
EPA 6020B	Arsenic	0.085	mg/L	0.010	08/22/23 20:23	
EPA 6020B	Boron	0.45	mg/L	0.040	08/22/23 20:23	
92682397007	HAM-AP1-FD-06					
EPA 6010D	Iron	21.3	mg/L	0.040	08/23/23 21:54	
EPA 6010D	Manganese	6.8	mg/L	0.040	08/23/23 21:54	
EPA 6010D	Potassium	5.6	mg/L	0.50	08/23/23 21:54	
EPA 6010D	Sodium	6.3	mg/L	1.0	08/23/23 21:54	
EPA 6010D	Calcium	128	mg/L	1.0	08/23/23 21:54	
EPA 6010D	Magnesium	16.7	mg/L	0.050	08/23/23 21:54	
EPA 6020B	Arsenic	0.36	mg/L	0.010	08/22/23 20:29	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92682397007	HAM-AP1-FD-06					
EPA 6020B	Barium	0.047	mg/L	0.0050	08/22/23 20:29	
EPA 6020B	Beryllium	0.000065J	mg/L	0.00050	08/22/23 20:29	
EPA 6020B	Boron	0.90	mg/L	0.040	08/22/23 20:29	
EPA 6020B	Cobalt	0.034	mg/L	0.0050	08/22/23 20:29	
EPA 6020B	Lithium	0.066	mg/L	0.030	08/22/23 20:29	
EPA 6020B	Molybdenum	0.0068J	mg/L	0.010	08/22/23 20:29	
SM 2540C-2015	Total Dissolved Solids	699	mg/L	25.0	08/15/23 16:57	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	111	mg/L	5.0	08/16/23 16:12	
SM 2320B-2011	Alkalinity, Total as CaCO3	111	mg/L	5.0	08/16/23 16:12	
EPA 300.0 Rev 2.1 1993	Chloride	14.6	mg/L	1.0	08/16/23 03:19	
EPA 300.0 Rev 2.1 1993	Fluoride	0.29	mg/L	0.10	08/16/23 03:19	
EPA 300.0 Rev 2.1 1993	Sulfate	293	mg/L	6.0	08/16/23 12:22	
92682397008	HAM-AP1-FB-06					
EPA 6020B	Boron	0.012J	mg/L	0.040	08/22/23 20:35	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-PT-07		Lab ID: 92682397001		Collected: 08/09/23 17:59		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	27.1	mg/L	0.040	0.025	1	08/18/23 10:36	08/18/23 21:03	7439-89-6	
Manganese	7.6	mg/L	0.040	0.011	1	08/18/23 10:36	08/18/23 21:03	7439-96-5	
Potassium	6.8	mg/L	0.50	0.15	1	08/18/23 10:36	08/18/23 21:03	7440-09-7	
Sodium	7.2	mg/L	1.0	0.58	1	08/18/23 10:36	08/18/23 21:03	7440-23-5	
Calcium	173	mg/L	1.0	0.12	1	08/18/23 10:36	08/18/23 21:03	7440-70-2	
Magnesium	19.4	mg/L	0.050	0.012	1	08/18/23 10:36	08/18/23 21:03	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	08/16/23 14:27	08/22/23 16:32	7440-36-0	
Arsenic	0.27	mg/L	0.010	0.0037	1	08/16/23 14:27	08/22/23 16:32	7440-38-2	
Barium	0.053	mg/L	0.0050	0.00067	1	08/16/23 14:27	08/22/23 16:32	7440-39-3	
Beryllium	0.000095J	mg/L	0.00050	0.000054	1	08/16/23 14:27	08/22/23 16:32	7440-41-7	
Boron	0.93	mg/L	0.040	0.0086	1	08/16/23 14:27	08/23/23 13:17	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	08/16/23 14:27	08/22/23 16:32	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	08/16/23 14:27	08/23/23 13:17	7440-47-3	
Cobalt	0.090	mg/L	0.0050	0.00039	1	08/16/23 14:27	08/23/23 13:17	7440-48-4	
Lead	ND	mg/L	0.0010	0.00012	1	08/16/23 14:27	08/22/23 16:32	7439-92-1	
Lithium	0.069	mg/L	0.030	0.00073	1	08/16/23 14:27	08/23/23 13:17	7439-93-2	
Molybdenum	0.012	mg/L	0.010	0.00074	1	08/16/23 14:27	08/22/23 16:32	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	08/16/23 14:27	08/22/23 16:32	7782-49-2	
Thallium	0.00022J	mg/L	0.0010	0.00018	1	08/16/23 14:27	08/22/23 16:32	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/17/23 12:00	08/17/23 15:18	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	771	mg/L	25.0	25.0	1		08/15/23 16:56		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	116	mg/L	5.0	5.0	1		08/16/23 15:20		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/16/23 15:20		
Alkalinity, Total as CaCO3	116	mg/L	5.0	5.0	1		08/16/23 15:20		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/15/23 06:29	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	13.5	mg/L	1.0	0.60	1		08/15/23 21:32	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-PT-07		Lab ID: 92682397001		Collected: 08/09/23 17:59		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.28	mg/L	0.10	0.050	1		08/15/23 21:32	16984-48-8	
Sulfate	339	mg/L	7.0	3.5	7		08/16/23 08:19	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-PT-08		Lab ID: 92682397002		Collected: 08/09/23 10:50		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	22.0	mg/L	0.040	0.025	1	08/18/23 10:36	08/18/23 21:13	7439-89-6	
Manganese	6.8	mg/L	0.040	0.011	1	08/18/23 10:36	08/18/23 21:13	7439-96-5	
Potassium	6.3	mg/L	0.50	0.15	1	08/18/23 10:36	08/18/23 21:13	7440-09-7	
Sodium	6.8	mg/L	1.0	0.58	1	08/18/23 10:36	08/18/23 21:13	7440-23-5	
Calcium	146	mg/L	1.0	0.12	1	08/18/23 10:36	08/18/23 21:13	7440-70-2	
Magnesium	17.3	mg/L	0.050	0.012	1	08/18/23 10:36	08/18/23 21:13	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	08/16/23 14:27	08/22/23 16:39	7440-36-0	
Arsenic	0.32	mg/L	0.010	0.0037	1	08/16/23 14:27	08/22/23 16:39	7440-38-2	
Barium	0.050	mg/L	0.0050	0.00067	1	08/16/23 14:27	08/22/23 16:39	7440-39-3	
Beryllium	0.000073J	mg/L	0.00050	0.000054	1	08/16/23 14:27	08/22/23 16:39	7440-41-7	
Boron	0.99	mg/L	0.040	0.0086	1	08/16/23 14:27	08/23/23 13:23	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	08/16/23 14:27	08/22/23 16:39	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	08/16/23 14:27	08/22/23 16:39	7440-47-3	
Cobalt	0.032	mg/L	0.0050	0.00039	1	08/16/23 14:27	08/22/23 16:39	7440-48-4	
Lead	ND	mg/L	0.0010	0.00012	1	08/16/23 14:27	08/22/23 16:39	7439-92-1	
Lithium	0.073	mg/L	0.030	0.00073	1	08/16/23 14:27	08/23/23 13:23	7439-93-2	
Molybdenum	0.0071J	mg/L	0.010	0.00074	1	08/16/23 14:27	08/22/23 16:39	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	08/16/23 14:27	08/22/23 16:39	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00018	1	08/16/23 14:27	08/22/23 16:39	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/17/23 12:00	08/17/23 15:34	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	682	mg/L	25.0	25.0	1		08/15/23 16:57		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	118	mg/L	5.0	5.0	1		08/16/23 15:40		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/16/23 15:40		
Alkalinity, Total as CaCO3	118	mg/L	5.0	5.0	1		08/16/23 15:40		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/15/23 06:29	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	14.5	mg/L	1.0	0.60	1		08/15/23 22:30	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-PT-08		Lab ID: 92682397002		Collected: 08/09/23 10:50		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.27	mg/L	0.10	0.050	1		08/15/23 22:30	16984-48-8	
Sulfate	290	mg/L	6.0	3.0	6		08/16/23 09:16	14808-79-8	M1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-PT-09		Lab ID: 92682397003		Collected: 08/09/23 14:42		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.10	mg/L	0.040	0.025	1	08/18/23 10:36	08/18/23 21:18	7439-89-6	
Manganese	0.51	mg/L	0.040	0.011	1	08/18/23 10:36	08/18/23 21:18	7439-96-5	
Potassium	7.7	mg/L	0.50	0.15	1	08/18/23 10:36	08/18/23 21:18	7440-09-7	
Sodium	10.3	mg/L	1.0	0.58	1	08/18/23 10:36	08/18/23 21:18	7440-23-5	
Calcium	136	mg/L	1.0	0.12	1	08/18/23 10:36	08/18/23 21:18	7440-70-2	
Magnesium	18.2	mg/L	0.050	0.012	1	08/18/23 10:36	08/18/23 21:18	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	08/16/23 14:27	08/22/23 16:43	7440-36-0	
Arsenic	ND	mg/L	0.010	0.0037	1	08/16/23 14:27	08/22/23 16:43	7440-38-2	
Barium	0.057	mg/L	0.0050	0.00067	1	08/16/23 14:27	08/22/23 16:43	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000054	1	08/16/23 14:27	08/22/23 16:43	7440-41-7	
Boron	1.6	mg/L	0.40	0.086	10	08/16/23 14:27	08/23/23 19:25	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	08/16/23 14:27	08/22/23 16:43	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	08/16/23 14:27	08/22/23 16:43	7440-47-3	
Cobalt	0.0028J	mg/L	0.0050	0.00039	1	08/16/23 14:27	08/22/23 16:43	7440-48-4	
Lead	ND	mg/L	0.0010	0.00012	1	08/16/23 14:27	08/22/23 16:43	7439-92-1	
Lithium	0.0017J	mg/L	0.030	0.00073	1	08/16/23 14:27	08/22/23 16:43	7439-93-2	
Molybdenum	0.21	mg/L	0.010	0.00074	1	08/16/23 14:27	08/22/23 16:43	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	08/16/23 14:27	08/22/23 16:43	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00018	1	08/16/23 14:27	08/22/23 16:43	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/17/23 12:00	08/17/23 15:37	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	594	mg/L	25.0	25.0	1		08/15/23 16:57		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	150	mg/L	5.0	5.0	1		08/16/23 15:50		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/16/23 15:50		
Alkalinity, Total as CaCO ₃	150	mg/L	5.0	5.0	1		08/16/23 15:50		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/15/23 06:30	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	47.5	mg/L	1.0	0.60	1		08/15/23 23:14	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-PT-09		Lab ID: 92682397003		Collected: 08/09/23 14:42		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.26	mg/L	0.10	0.050	1		08/15/23 23:14	16984-48-8	
Sulfate	188	mg/L	4.0	2.0	4		08/16/23 09:59	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-PT-10		Lab ID: 92682397004		Collected: 08/09/23 13:05		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	2.9	mg/L	0.040	0.025	1	08/23/23 12:06	08/23/23 21:33	7439-89-6	
Manganese	3.1	mg/L	0.040	0.011	1	08/23/23 12:06	08/23/23 21:33	7439-96-5	
Potassium	6.7	mg/L	0.50	0.15	1	08/23/23 12:06	08/23/23 21:33	7440-09-7	M1
Sodium	9.4	mg/L	1.0	0.58	1	08/23/23 12:06	08/23/23 21:33	7440-23-5	M1
Calcium	116	mg/L	1.0	0.12	1	08/23/23 12:06	08/23/23 21:33	7440-70-2	M1
Magnesium	16.8	mg/L	0.050	0.012	1	08/23/23 12:06	08/23/23 21:33	7439-95-4	M1
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	08/16/23 14:27	08/22/23 16:51	7440-36-0	
Arsenic	ND	mg/L	0.010	0.0037	1	08/16/23 14:27	08/22/23 16:51	7440-38-2	
Barium	0.070	mg/L	0.0050	0.00067	1	08/16/23 14:27	08/22/23 16:51	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000054	1	08/16/23 14:27	08/22/23 16:51	7440-41-7	
Boron	2.1	mg/L	0.40	0.086	10	08/16/23 14:27	08/23/23 19:48	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	08/16/23 14:27	08/22/23 16:51	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	08/16/23 14:27	08/22/23 16:51	7440-47-3	
Cobalt	0.0019J	mg/L	0.0050	0.00039	1	08/16/23 14:27	08/22/23 16:51	7440-48-4	
Lead	ND	mg/L	0.0010	0.00012	1	08/16/23 14:27	08/22/23 16:51	7439-92-1	
Lithium	0.0012J	mg/L	0.030	0.00073	1	08/16/23 14:27	08/22/23 16:51	7439-93-2	
Molybdenum	0.096	mg/L	0.010	0.00074	1	08/16/23 14:27	08/22/23 16:51	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	08/16/23 14:27	08/22/23 16:51	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00018	1	08/16/23 14:27	08/22/23 16:51	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/17/23 12:00	08/17/23 15:39	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	553	mg/L	25.0	25.0	1		08/15/23 16:57		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	199	mg/L	5.0	5.0	1		08/16/23 16:00		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/16/23 16:00		
Alkalinity, Total as CaCO3	199	mg/L	5.0	5.0	1		08/16/23 16:00		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	0.045J	mg/L	0.10	0.022	1		08/15/23 06:30	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	62.5	mg/L	1.0	0.60	1		08/15/23 23:42	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-PT-10		Lab ID: 92682397004		Collected: 08/09/23 13:05		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.27	mg/L	0.10	0.050	1		08/15/23 23:42	16984-48-8	
Sulfate	123	mg/L	3.0	1.5	3		08/16/23 10:27	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-MW-53		Lab ID: 92682397005		Collected: 08/09/23 16:40		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.5	mg/L	0.040	0.0086	1	08/17/23 10:25	08/22/23 20:17	7440-42-8	
Molybdenum	0.14	mg/L	0.010	0.00074	1	08/17/23 10:25	08/22/23 20:17	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-MW-54		Lab ID: 92682397006		Collected: 08/09/23 16:51		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.085	mg/L	0.010	0.0037	1	08/17/23 10:25	08/22/23 20:23	7440-38-2	
Boron	0.45	mg/L	0.040	0.0086	1	08/17/23 10:25	08/22/23 20:23	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-AP1-FD-06		Lab ID: 92682397007		Collected: 08/09/23 00:00		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	21.3	mg/L	0.040	0.025	1	08/23/23 12:06	08/23/23 21:54	7439-89-6	
Manganese	6.8	mg/L	0.040	0.011	1	08/23/23 12:06	08/23/23 21:54	7439-96-5	
Potassium	5.6	mg/L	0.50	0.15	1	08/23/23 12:06	08/23/23 21:54	7440-09-7	
Sodium	6.3	mg/L	1.0	0.58	1	08/23/23 12:06	08/23/23 21:54	7440-23-5	
Calcium	128	mg/L	1.0	0.12	1	08/23/23 12:06	08/23/23 21:54	7440-70-2	
Magnesium	16.7	mg/L	0.050	0.012	1	08/23/23 12:06	08/23/23 21:54	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	08/17/23 10:25	08/22/23 20:29	7440-36-0	
Arsenic	0.36	mg/L	0.010	0.0037	1	08/17/23 10:25	08/22/23 20:29	7440-38-2	
Barium	0.047	mg/L	0.0050	0.00067	1	08/17/23 10:25	08/22/23 20:29	7440-39-3	
Beryllium	0.000065J	mg/L	0.00050	0.000054	1	08/17/23 10:25	08/22/23 20:29	7440-41-7	
Boron	0.90	mg/L	0.040	0.0086	1	08/17/23 10:25	08/22/23 20:29	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	08/17/23 10:25	08/22/23 20:29	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	08/17/23 10:25	08/23/23 17:24	7440-47-3	
Cobalt	0.034	mg/L	0.0050	0.00039	1	08/17/23 10:25	08/22/23 20:29	7440-48-4	
Lead	ND	mg/L	0.0010	0.00012	1	08/17/23 10:25	08/22/23 20:29	7439-92-1	
Lithium	0.066	mg/L	0.030	0.00073	1	08/17/23 10:25	08/22/23 20:29	7439-93-2	
Molybdenum	0.0068J	mg/L	0.010	0.00074	1	08/17/23 10:25	08/22/23 20:29	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	08/17/23 10:25	08/22/23 20:29	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00018	1	08/17/23 10:25	08/22/23 20:29	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/17/23 12:00	08/17/23 15:42	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	699	mg/L	25.0	25.0	1		08/15/23 16:57		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	111	mg/L	5.0	5.0	1		08/16/23 16:12		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/16/23 16:12		
Alkalinity, Total as CaCO ₃	111	mg/L	5.0	5.0	1		08/16/23 16:12		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/15/23 06:31	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	14.6	mg/L	1.0	0.60	1		08/16/23 03:19	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-AP1-FD-06		Lab ID: 92682397007		Collected: 08/09/23 00:00		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.29	mg/L	0.10	0.050	1		08/16/23 03:19	16984-48-8	
Sulfate	293	mg/L	6.0	3.0	6		08/16/23 12:22	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-AP1-FB-06		Lab ID: 92682397008		Collected: 08/09/23 16:50		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	08/23/23 12:06	08/23/23 21:59	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	08/23/23 12:06	08/23/23 21:59	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	08/23/23 12:06	08/23/23 21:59	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	08/23/23 12:06	08/23/23 21:59	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	08/23/23 12:06	08/23/23 21:59	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	08/23/23 12:06	08/23/23 21:59	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.0012	1	08/17/23 10:25	08/22/23 20:35	7440-36-0	
Arsenic	ND	mg/L	0.010	0.0037	1	08/17/23 10:25	08/22/23 20:35	7440-38-2	
Barium	ND	mg/L	0.0050	0.00067	1	08/17/23 10:25	08/22/23 20:35	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000054	1	08/17/23 10:25	08/22/23 20:35	7440-41-7	
Boron	0.012J	mg/L	0.040	0.0086	1	08/17/23 10:25	08/22/23 20:35	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00011	1	08/17/23 10:25	08/22/23 20:35	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0011	1	08/17/23 10:25	08/23/23 17:28	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00039	1	08/17/23 10:25	08/22/23 20:35	7440-48-4	
Lead	ND	mg/L	0.0010	0.00012	1	08/17/23 10:25	08/22/23 20:35	7439-92-1	
Lithium	ND	mg/L	0.030	0.00073	1	08/17/23 10:25	08/22/23 20:35	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00074	1	08/17/23 10:25	08/22/23 20:35	7439-98-7	
Selenium	ND	mg/L	0.0050	0.0014	1	08/17/23 10:25	08/22/23 20:35	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00018	1	08/17/23 10:25	08/22/23 20:35	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/17/23 12:00	08/17/23 15:44	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		08/15/23 16:57		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/16/23 16:22		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/16/23 16:22		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		08/16/23 16:22		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/15/23 06:32	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		08/16/23 03:33	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Sample: HAM-AP1-FB-06		Lab ID: 92682397008		Collected: 08/09/23 16:50		Received: 08/11/23 13:12		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		08/16/23 03:33	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		08/16/23 03:33	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

QC Batch: 793618

Analysis Method: EPA 6010D

QC Batch Method: EPA 3010A

Analysis Description: 6010D ATL

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92682397001, 92682397002, 92682397003

METHOD BLANK: 4112489

Matrix: Water

Associated Lab Samples: 92682397001, 92682397002, 92682397003

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	08/18/23 19:00	
Iron	mg/L	ND	0.040	0.025	08/18/23 19:00	
Magnesium	mg/L	ND	0.050	0.012	08/18/23 19:00	
Manganese	mg/L	ND	0.040	0.011	08/18/23 19:00	
Potassium	mg/L	ND	0.50	0.15	08/18/23 19:00	
Sodium	mg/L	ND	1.0	0.58	08/18/23 19:00	

LABORATORY CONTROL SAMPLE: 4112490

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	1.1	108	80-120	
Iron	mg/L	1	1.0	102	80-120	
Magnesium	mg/L	1	1.0	101	80-120	
Manganese	mg/L	1	0.99	99	80-120	
Potassium	mg/L	1	1.1	106	80-120	
Sodium	mg/L	1	1.1	106	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4112491 4112492

Parameter	Units	92682392001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Calcium	mg/L	8.4	1	1	8.8	9.3	35	92	75-125	6	20	M1
Iron	mg/L	ND	1	1	1.0	1.0	100	100	75-125	0	20	
Magnesium	mg/L	3.4	1	1	4.1	4.3	72	92	75-125	5	20	M1
Manganese	mg/L	ND	1	1	0.98	0.99	97	98	75-125	1	20	
Potassium	mg/L	0.32J	1	1	1.3	1.5	102	113	75-125	8	20	
Sodium	mg/L	9.5	1	1	10	10.5	44	103	75-125	6	20	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

QC Batch: 795409

Analysis Method: EPA 6010D

QC Batch Method: EPA 3010A

Analysis Description: 6010D ATL

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92682397004, 92682397007, 92682397008

METHOD BLANK: 4121384

Matrix: Water

Associated Lab Samples: 92682397004, 92682397007, 92682397008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	08/23/23 21:12	
Iron	mg/L	ND	0.040	0.025	08/23/23 21:12	
Magnesium	mg/L	ND	0.050	0.012	08/23/23 21:12	
Manganese	mg/L	ND	0.040	0.011	08/23/23 21:12	
Potassium	mg/L	ND	0.50	0.15	08/23/23 21:12	
Sodium	mg/L	ND	1.0	0.58	08/23/23 21:12	

LABORATORY CONTROL SAMPLE: 4121385

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	0.93J	93	80-120	
Iron	mg/L	1	1.0	102	80-120	
Magnesium	mg/L	1	1.1	109	80-120	
Manganese	mg/L	1	1.0	105	80-120	
Potassium	mg/L	1	1.0	100	80-120	
Sodium	mg/L	1	1.1	105	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4121386 4121387

Parameter	Units	92682397004 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Calcium	mg/L	116	1	1	112	116	-370	-33	75-125	3	20	M1
Iron	mg/L	2.9	1	1	3.7	3.8	84	95	75-125	3	20	
Magnesium	mg/L	16.8	1	1	17.0	17.5	22	63	75-125	2	20	M1
Manganese	mg/L	3.1	1	1	4.0	4.0	83	90	75-125	2	20	
Potassium	mg/L	6.7	1	1	7.5	7.7	73	98	75-125	3	20	M1
Sodium	mg/L	9.4	1	1	9.9	10.3	54	92	75-125	4	20	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

QC Batch:	794002	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004

METHOD BLANK: 4114214

Matrix: Water

Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	0.0043	0.0030	0.0012	08/22/23 15:04	
Arsenic	mg/L	ND	0.010	0.0037	08/22/23 15:04	
Barium	mg/L	ND	0.0050	0.00067	08/22/23 15:04	
Beryllium	mg/L	ND	0.00050	0.000054	08/22/23 15:04	
Boron	mg/L	ND	0.040	0.0086	08/22/23 15:04	
Cadmium	mg/L	ND	0.00050	0.00011	08/22/23 15:04	
Chromium	mg/L	ND	0.0050	0.0011	08/22/23 15:04	
Cobalt	mg/L	ND	0.0050	0.00039	08/22/23 15:04	
Lead	mg/L	ND	0.0010	0.00012	08/22/23 15:04	
Lithium	mg/L	ND	0.030	0.00073	08/22/23 15:04	
Molybdenum	mg/L	ND	0.010	0.00074	08/22/23 15:04	
Selenium	mg/L	ND	0.0050	0.0014	08/22/23 15:04	
Thallium	mg/L	ND	0.0010	0.00018	08/22/23 15:04	

LABORATORY CONTROL SAMPLE: 4114215

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.11	112	80-120	
Arsenic	mg/L	0.1	0.10	102	80-120	
Barium	mg/L	0.1	0.10	100	80-120	
Beryllium	mg/L	0.1	0.11	110	80-120	
Boron	mg/L	1	1.1	110	80-120	
Cadmium	mg/L	0.1	0.10	102	80-120	
Chromium	mg/L	0.1	0.11	106	80-120	
Cobalt	mg/L	0.1	0.10	104	80-120	
Lead	mg/L	0.1	0.10	105	80-120	
Lithium	mg/L	0.1	0.11	110	80-120	
Molybdenum	mg/L	0.1	0.11	107	80-120	
Selenium	mg/L	0.1	0.11	105	80-120	
Thallium	mg/L	0.1	0.11	105	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4114216

4114217

Parameter	Units	92682396010 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	0.0014J	0.1	0.1	0.11	0.10	107	101	75-125	6	20	
Arsenic	mg/L	0.0040J	0.1	0.1	0.12	0.11	112	104	75-125	7	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4114216 4114217											
Parameter	Units	92682396010		MS		MSD		MS		MSD	
		Result	Conc.	Spike	Conc.	Result	Conc.	% Rec	% Rec	% Rec	Max
								Limits	RPD	RPD	Qual
Barium	mg/L	0.042	0.1	0.1	0.1	0.16	0.15	118	108	75-125	6 20
Beryllium	mg/L	0.00071	0.1	0.1	0.1	0.090	0.085	89	84	75-125	6 20
Boron	mg/L	10.1	1	1	1	10.9	10.7	77	57	75-125	2 20 M1
Cadmium	mg/L	0.00059	0.1	0.1	0.1	0.099	0.094	98	94	75-125	5 20
Chromium	mg/L	ND	0.1	0.1	0.1	0.10	0.097	104	97	75-125	7 20
Cobalt	mg/L	0.21	0.1	0.1	0.1	0.31	0.29	102	83	75-125	6 20
Lead	mg/L	0.00013J	0.1	0.1	0.1	0.067	0.064	67	64	75-125	5 20 M1
Lithium	mg/L	0.0024J	0.1	0.1	0.1	0.097	0.092	95	89	75-125	6 20
Molybdenum	mg/L	ND	0.1	0.1	0.1	0.11	0.10	109	104	75-125	5 20
Selenium	mg/L	0.013	0.1	0.1	0.1	0.13	0.13	122	113	75-125	8 20
Thallium	mg/L	0.00021J	0.1	0.1	0.1	0.069	0.066	68	65	75-125	5 20 M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

QC Batch: 794177 Analysis Method: EPA 6020B
QC Batch Method: EPA 3005A Analysis Description: 6020 MET
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92682397005, 92682397006, 92682397007, 92682397008

METHOD BLANK: 4115107 Matrix: Water
Associated Lab Samples: 92682397005, 92682397006, 92682397007, 92682397008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.0012	08/22/23 18:42	
Arsenic	mg/L	ND	0.010	0.0037	08/22/23 18:42	
Barium	mg/L	ND	0.0050	0.00067	08/22/23 18:42	
Beryllium	mg/L	ND	0.00050	0.000054	08/22/23 18:42	
Boron	mg/L	ND	0.040	0.0086	08/22/23 18:42	
Cadmium	mg/L	ND	0.00050	0.00011	08/22/23 18:42	
Chromium	mg/L	ND	0.0050	0.0011	08/23/23 16:28	
Cobalt	mg/L	ND	0.0050	0.00039	08/22/23 18:42	
Lead	mg/L	ND	0.0010	0.00012	08/22/23 18:42	
Lithium	mg/L	ND	0.030	0.00073	08/22/23 18:42	
Molybdenum	mg/L	ND	0.010	0.00074	08/22/23 18:42	
Selenium	mg/L	ND	0.0050	0.0014	08/22/23 18:42	
Thallium	mg/L	ND	0.0010	0.00018	08/22/23 18:42	

LABORATORY CONTROL SAMPLE: 4115108

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.10	104	80-120	
Arsenic	mg/L	0.1	0.094	94	80-120	
Barium	mg/L	0.1	0.096	96	80-120	
Beryllium	mg/L	0.1	0.093	93	80-120	
Boron	mg/L	1	0.94	94	80-120	
Cadmium	mg/L	0.1	0.096	96	80-120	
Chromium	mg/L	0.1	0.10	100	80-120	
Cobalt	mg/L	0.1	0.090	90	80-120	
Lead	mg/L	0.1	0.094	94	80-120	
Lithium	mg/L	0.1	0.098	98	80-120	
Molybdenum	mg/L	0.1	0.095	95	80-120	
Selenium	mg/L	0.1	0.097	97	80-120	
Thallium	mg/L	0.1	0.093	93	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4115109 4115110

Parameter	Units	92681886001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	ND	0.1	0.1	0.10	0.10	104	103	75-125	1	20	
Arsenic	mg/L	ND	0.1	0.1	0.099	0.098	99	98	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:			4115109	4115110								
Parameter	Units	92681886001	MS	MSD	MS	MSD	MS	MSD	% Rec	RPD	Max	Qual
		Result	Spike	Spike								
Barium	mg/L	0.039	0.1	0.1	0.14	0.14	103	103	75-125	1	20	
Beryllium	mg/L	0.000067J	0.1	0.1	0.094	0.091	94	91	75-125	4	20	
Boron	mg/L	0.029J	1	1	0.97	0.94	94	91	75-125	3	20	
Cadmium	mg/L	ND	0.1	0.1	0.098	0.099	98	99	75-125	1	20	
Chromium	mg/L	ND	0.1	0.1	0.10	0.10	102	101	75-125	1	20	
Cobalt	mg/L	0.00041J	0.1	0.1	0.092	0.091	91	91	75-125	0	20	
Lead	mg/L	ND	0.1	0.1	0.093	0.092	93	92	75-125	1	20	
Lithium	mg/L	ND	0.1	0.1	0.095	0.094	95	93	75-125	2	20	
Molybdenum	mg/L	ND	0.1	0.1	0.096	0.096	96	95	75-125	0	20	
Selenium	mg/L	ND	0.1	0.1	0.10	0.099	100	99	75-125	1	20	
Thallium	mg/L	ND	0.1	0.1	0.092	0.092	92	92	75-125	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

QC Batch: 794154

Analysis Method: EPA 7470A

QC Batch Method: EPA 7470A

Analysis Description: 7470 Mercury

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

METHOD BLANK: 4115033

Matrix: Water

Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	08/17/23 15:13	

LABORATORY CONTROL SAMPLE: 4115034

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0023	93	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4115035 4115036

Parameter	Units	92682397001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.0025	0.0025	0.0024	0.0024	94	94	75-125	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

QC Batch:	793700	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

METHOD BLANK: 4112841 Matrix: Water

Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	08/15/23 16:52	

LABORATORY CONTROL SAMPLE: 4112842

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	446	112	80-120	

SAMPLE DUPLICATE: 4112843

Parameter	Units	92682396001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	1890	1910	1	10	

SAMPLE DUPLICATE: 4112844

Parameter	Units	92682397001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	771	760	1	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)
Pace Project No.: 92682397

QC Batch: 793896 Analysis Method: SM 2320B-2011
QC Batch Method: SM 2320B-2011 Analysis Description: 2320B Alkalinity
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

METHOD BLANK: 4113632 Matrix: Water
Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	08/16/23 13:58	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	08/16/23 13:58	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	08/16/23 13:58	

LABORATORY CONTROL SAMPLE: 4113633

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.1	104	80-120	

LABORATORY CONTROL SAMPLE: 4113634

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	55.0	110	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4113635 4113636

Parameter	Units	92682175001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	464	50	50	487	487	47	46	80-120	0	25	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4113637 4113638

Parameter	Units	92682175002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	12.5	50	50	65.7	65.4	106	106	80-120	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)
Pace Project No.: 92682397

QC Batch: 793500 Analysis Method: SM 4500-S2D-2011
QC Batch Method: SM 4500-S2D-2011 Analysis Description: 4500S2D Sulfide Water
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

METHOD BLANK: 4111958 Matrix: Water
Associated Lab Samples: 92682397001, 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	08/15/23 06:24	

LABORATORY CONTROL SAMPLE: 4111959

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.50	100	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4111960 4111961

Parameter	Units	92682396005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.50	0.45	99	89	80-120	11	10	R1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4111962 4111963

Parameter	Units	92682397007 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.53	0.55	104	108	80-120	4	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)
Pace Project No.: 92682397

QC Batch: 793550 Analysis Method: EPA 300.0 Rev 2.1 1993
QC Batch Method: EPA 300.0 Rev 2.1 1993 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92682397001

METHOD BLANK: 4112126 Matrix: Water
Associated Lab Samples: 92682397001

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	08/15/23 12:46	
Fluoride	mg/L	ND	0.10	0.050	08/15/23 12:46	
Sulfate	mg/L	ND	1.0	0.50	08/15/23 12:46	

LABORATORY CONTROL SAMPLE: 4112127

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	48.4	97	90-110	
Fluoride	mg/L	2.5	2.5	98	90-110	
Sulfate	mg/L	50	47.4	95	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4112128 4112129

Parameter	Units	92682198001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	ND	50	50	48.0	48.3	95	96	90-110	1	10	
Fluoride	mg/L	ND	2.5	2.5	2.4	2.4	94	95	90-110	1	10	
Sulfate	mg/L	ND	50	50	47.3	47.6	93	94	90-110	1	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4112130 4112131

Parameter	Units	92682396003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	141	50	50	179	180	77	78	90-110	0	10	M1
Fluoride	mg/L	0.56	2.5	2.5	3.1	3.2	102	104	90-110	2	10	
Sulfate	mg/L	762	50	50	787	789	50	53	90-110	0	10	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

QC Batch: 793553 Analysis Method: EPA 300.0 Rev 2.1 1993
QC Batch Method: EPA 300.0 Rev 2.1 1993 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

METHOD BLANK: 4112135 Matrix: Water
Associated Lab Samples: 92682397002, 92682397003, 92682397004, 92682397007, 92682397008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	08/15/23 22:01	
Fluoride	mg/L	ND	0.10	0.050	08/15/23 22:01	
Sulfate	mg/L	ND	1.0	0.50	08/15/23 22:01	

LABORATORY CONTROL SAMPLE: 4112136

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	49.5	99	90-110	
Fluoride	mg/L	2.5	2.5	100	90-110	
Sulfate	mg/L	50	48.3	97	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4112137 4112138

Parameter	Units	92682397002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	14.5	50	50	62.4	63.0	96	97	90-110	1	10	
Fluoride	mg/L	0.27	2.5	2.5	2.6	2.6	92	93	90-110	2	10	
Sulfate	mg/L	290	50	50	327	328	73	75	90-110	0	10 M1	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4112139 4112140

Parameter	Units	92682398009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	13.6	50	50	61.8	62.0	96	97	90-110	0	10	
Fluoride	mg/L	1.5	2.5	2.5	3.8	3.9	95	96	90-110	1	10	
Sulfate	mg/L	0.62J	50	50	47.3	47.5	93	94	90-110	1	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1 (CCR-CA)
Pace Project No.: 92682397

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.
R1 RPD value was outside control limits.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1 (CCR-CA)

Pace Project No.: 92682397

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92682397001	HAM-PT-07	EPA 3010A	793618	EPA 6010D	794582
92682397002	HAM-PT-08	EPA 3010A	793618	EPA 6010D	794582
92682397003	HAM-PT-09	EPA 3010A	793618	EPA 6010D	794582
92682397004	HAM-PT-10	EPA 3010A	795409	EPA 6010D	795455
92682397007	HAM-AP1-FD-06	EPA 3010A	795409	EPA 6010D	795455
92682397008	HAM-AP1-FB-06	EPA 3010A	795409	EPA 6010D	795455
92682397001	HAM-PT-07	EPA 3005A	794002	EPA 6020B	794064
92682397002	HAM-PT-08	EPA 3005A	794002	EPA 6020B	794064
92682397003	HAM-PT-09	EPA 3005A	794002	EPA 6020B	794064
92682397004	HAM-PT-10	EPA 3005A	794002	EPA 6020B	794064
92682397005	HAM-MW-53	EPA 3005A	794177	EPA 6020B	794304
92682397006	HAM-MW-54	EPA 3005A	794177	EPA 6020B	794304
92682397007	HAM-AP1-FD-06	EPA 3005A	794177	EPA 6020B	794304
92682397008	HAM-AP1-FB-06	EPA 3005A	794177	EPA 6020B	794304
92682397001	HAM-PT-07	EPA 7470A	794154	EPA 7470A	794256
92682397002	HAM-PT-08	EPA 7470A	794154	EPA 7470A	794256
92682397003	HAM-PT-09	EPA 7470A	794154	EPA 7470A	794256
92682397004	HAM-PT-10	EPA 7470A	794154	EPA 7470A	794256
92682397007	HAM-AP1-FD-06	EPA 7470A	794154	EPA 7470A	794256
92682397008	HAM-AP1-FB-06	EPA 7470A	794154	EPA 7470A	794256
92682397001	HAM-PT-07	SM 2540C-2015	793700		
92682397002	HAM-PT-08	SM 2540C-2015	793700		
92682397003	HAM-PT-09	SM 2540C-2015	793700		
92682397004	HAM-PT-10	SM 2540C-2015	793700		
92682397007	HAM-AP1-FD-06	SM 2540C-2015	793700		
92682397008	HAM-AP1-FB-06	SM 2540C-2015	793700		
92682397001	HAM-PT-07	SM 2320B-2011	793896		
92682397002	HAM-PT-08	SM 2320B-2011	793896		
92682397003	HAM-PT-09	SM 2320B-2011	793896		
92682397004	HAM-PT-10	SM 2320B-2011	793896		
92682397007	HAM-AP1-FD-06	SM 2320B-2011	793896		
92682397008	HAM-AP1-FB-06	SM 2320B-2011	793896		
92682397001	HAM-PT-07	SM 4500-S2D-2011	793500		
92682397002	HAM-PT-08	SM 4500-S2D-2011	793500		
92682397003	HAM-PT-09	SM 4500-S2D-2011	793500		
92682397004	HAM-PT-10	SM 4500-S2D-2011	793500		
92682397007	HAM-AP1-FD-06	SM 4500-S2D-2011	793500		
92682397008	HAM-AP1-FB-06	SM 4500-S2D-2011	793500		
92682397001	HAM-PT-07	EPA 300.0 Rev 2.1 1993	793550		
92682397002	HAM-PT-08	EPA 300.0 Rev 2.1 1993	793553		
92682397003	HAM-PT-09	EPA 300.0 Rev 2.1 1993	793553		
92682397004	HAM-PT-10	EPA 300.0 Rev 2.1 1993	793553		
92682397007	HAM-AP1-FD-06	EPA 300.0 Rev 2.1 1993	793553		
92682397008	HAM-AP1-FB-06	EPA 300.0 Rev 2.1 1993	793553		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



DC#_Title: ENV-FRM-HUN1-0083 v02_Sample Condition Upon Receipt

Effective Date: 11/14/2022

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

GA Power

Project #

WO# 92682397

Courier:

☐ Commercial☐ Fed Ex☐ UPS☐ USPS☐ Client☒ Pace☐ Other:

Custody Seal Present?

☐ Yes☒ No

Seals Intact?

☐ Yes☐ No

Packing Material:

☐ Bubble Wrap☐ Bubble Bags☒ None☐ Other

Thermometer:

☒ IR Gun ID:

230

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

3.1

Correction Factor:

Add/Subtract (°C)

0.0

Cooler Temp Corrected (°C):

3.1

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☒ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☒ No

Chain of Custody Present?

☒ Yes☐ No☐ N/A

Samples Arrived within Hold Time?

☒ Yes☐ No☐ N/A

Short Hold Time Analysis (<72 hr.)?

☒ Yes☐ No☐ N/A

Rush Turn Around Time Requested?

☐ Yes☒ No☐ N/A

Sufficient Volume?

☐ Yes☒ No☐ N/A

Correct Containers Used?

☒ Yes☐ No☐ N/A

-Pace Containers Used?

☒ Yes☐ No☐ N/A

Containers Intact?

☒ Yes☐ No☐ N/A

Dissolved analysis: Samples Field Filtered?

☐ Yes☐ No☒ N/A

Sample Labels Match COC?

☒ Yes☐ No☐ N/A

-Includes Date/Time/ID/Analysis Matrix:

W

Headspace in VOA Vials (>5-6mm)?

☐ Yes☐ No☒ N/A

Trip Blank Present?

☐ Yes☐ No☒ N/A

Trip Blank Custody Seals Present?

☐ Yes☐ No☒ N/A

Comments/Discrepancy:

Field Data Required? ☐ Yes ☒ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_Title: ENV-FRM-HUN1-0083 v02_Sample Condition Upon Receipt

Effective Date: 11/14/2022

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

WO# 92682397

PM: BV

Due Date: 08/28/23

CLIENT: 92- GRHAM

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic ZN Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGFU-Wide-mouthed Glass jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG94-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit)-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A – lab)	SP2T-250 mL Sterile Plastic (N/A – lab)		BP3R-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	VSGU-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)
1		2	1																									
2		2	1																									
3		2	1																									
4		2	1																									
5																												
6																												
7		2	1																									
8		2	1																									
9																												
10																												
11																												
12																												

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers.



May 10, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1
Pace Project No.: 92728841

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on May 03, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Peachtree Corners, GA

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Tyriek Hooks for
Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Anthony Szwast, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1

Pace Project No.: 92728841

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1

Pace Project No.: 92728841

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92728841001	HAM-INW-04	Water	05/02/24 14:18	05/03/24 13:20
92728841002	HAM-INW-05	Water	05/02/24 09:55	05/03/24 13:20
92728841003	HAM-PT-08	Water	05/02/24 12:35	05/03/24 13:20
92728841004	HAM-PT-14	Water	05/02/24 12:06	05/03/24 13:20
92728841005	HAM-PT-15	Water	05/02/24 15:40	05/03/24 13:20
92728841006	HAM-AP1-EB-01	Water	05/02/24 15:20	05/03/24 13:20
92728841007	HAM-AP1-FB-01	Water	05/02/24 15:15	05/03/24 13:20
92728841008	HAM-AP1-FD-01	Water	05/02/24 00:00	05/03/24 13:20

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92728841

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92728841001	HAM-INW-04	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2320B-2011	YEG	3
		SM 2540C-2015	CMW1	1
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92728841002	HAM-INW-05	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2320B-2011	YEG	3
		SM 2540C-2015	CMW1	1
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92728841003	HAM-PT-08	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2320B-2011	YEG	3
		SM 2540C-2015	CMW1	1
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92728841004	HAM-PT-14	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2320B-2011	YEG	3
		SM 2540C-2015	CMW1	1
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92728841005	HAM-PT-15	EPA 6010D	AJM, DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2320B-2011	YEG	3
		SM 2540C-2015	CMW1	1
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92728841006	HAM-AP1-EB-01	EPA 6010D	AJM	6
		EPA 6020B	CW1	13

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92728841

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92728841007	HAM-AP1-FB-01	EPA 7470A	VB	1
		SM 2320B-2011	YEG	3
		SM 2540C-2015	CMW1	1
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2320B-2011	YEG	3
		SM 2540C-2015	CMW1	1
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
92728841008	HAM-AP1-FD-01	SM 2320B-2011	YEG	3
		SM 2540C-2015	CMW1	1
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13

PASI-A = Pace Analytical Services - Asheville

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92728841

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92728841001	HAM-INW-04					
EPA 6010D	Iron	10.3	mg/L	0.040	05/06/24 22:08	
EPA 6010D	Manganese	4.2	mg/L	0.040	05/06/24 22:08	
EPA 6010D	Potassium	5.4	mg/L	0.50	05/06/24 22:08	
EPA 6010D	Sodium	6.9	mg/L	1.0	05/06/24 22:08	
EPA 6010D	Calcium	110	mg/L	1.0	05/06/24 22:08	
EPA 6010D	Magnesium	13.5	mg/L	0.050	05/06/24 22:08	
EPA 6020B	Arsenic	0.21	mg/L	0.0050	05/06/24 14:29	
EPA 6020B	Barium	0.042	mg/L	0.0050	05/06/24 14:29	
EPA 6020B	Boron	0.61	mg/L	0.040	05/06/24 14:29	
EPA 6020B	Cobalt	0.029	mg/L	0.0050	05/06/24 14:29	
EPA 6020B	Lithium	0.048	mg/L	0.030	05/06/24 14:29	
EPA 6020B	Molybdenum	0.016	mg/L	0.010	05/06/24 14:29	
EPA 6020B	Selenium	0.0016J	mg/L	0.0050	05/06/24 14:29	B
EPA 6020B	Thallium	0.00048J	mg/L	0.0010	05/06/24 14:29	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	128	mg/L	5.0	05/07/24 16:02	
SM 2320B-2011	Alkalinity, Total as CaCO3	128	mg/L	5.0	05/07/24 16:02	
SM 2540C-2015	Total Dissolved Solids	482	mg/L	25.0	05/07/24 15:51	
EPA 300.0 Rev 2.1 1993	Chloride	8.0	mg/L	1.0	05/07/24 13:54	
EPA 300.0 Rev 2.1 1993	Fluoride	0.47	mg/L	0.10	05/07/24 13:54	M1
EPA 300.0 Rev 2.1 1993	Sulfate	180	mg/L	4.0	05/08/24 00:06	M1
92728841002	HAM-INW-05					
EPA 6010D	Iron	17.3	mg/L	0.040	05/06/24 22:13	M1
EPA 6010D	Manganese	3.6	mg/L	0.040	05/06/24 22:13	
EPA 6010D	Potassium	5.2	mg/L	0.50	05/06/24 22:13	M1
EPA 6010D	Sodium	6.5	mg/L	1.0	05/06/24 22:13	M1
EPA 6010D	Calcium	108	mg/L	1.0	05/06/24 22:13	M1
EPA 6010D	Magnesium	12.6	mg/L	0.050	05/06/24 22:13	M1
EPA 6020B	Antimony	0.00098J	mg/L	0.0030	05/06/24 14:44	
EPA 6020B	Arsenic	0.24	mg/L	0.0050	05/06/24 14:44	
EPA 6020B	Barium	0.032	mg/L	0.0050	05/06/24 14:44	
EPA 6020B	Beryllium	0.000099J	mg/L	0.00050	05/06/24 14:44	
EPA 6020B	Boron	0.54	mg/L	0.040	05/06/24 14:44	
EPA 6020B	Cobalt	0.028	mg/L	0.0050	05/06/24 14:44	
EPA 6020B	Lithium	0.060	mg/L	0.030	05/06/24 14:44	
EPA 6020B	Molybdenum	0.0094J	mg/L	0.010	05/06/24 14:44	
EPA 6020B	Selenium	0.0015J	mg/L	0.0050	05/06/24 14:44	B
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	109	mg/L	5.0	05/07/24 16:12	
SM 2320B-2011	Alkalinity, Total as CaCO3	109	mg/L	5.0	05/07/24 16:12	
SM 2540C-2015	Total Dissolved Solids	526	mg/L	25.0	05/07/24 15:51	
EPA 300.0 Rev 2.1 1993	Chloride	6.0	mg/L	1.0	05/07/24 14:38	
EPA 300.0 Rev 2.1 1993	Fluoride	0.59	mg/L	0.10	05/07/24 14:38	
EPA 300.0 Rev 2.1 1993	Sulfate	206	mg/L	5.0	05/08/24 01:37	
92728841003	HAM-PT-08					
EPA 6010D	Iron	8.5	mg/L	0.040	05/06/24 22:32	
EPA 6010D	Manganese	3.9	mg/L	0.040	05/06/24 22:32	
EPA 6010D	Potassium	5.3	mg/L	0.50	05/06/24 22:32	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92728841

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92728841003	HAM-PT-08					
EPA 6010D	Sodium	7.2	mg/L	1.0	05/06/24 22:32	
EPA 6010D	Calcium	98.2	mg/L	1.0	05/06/24 22:32	
EPA 6010D	Magnesium	12.0	mg/L	0.050	05/06/24 22:32	
EPA 6020B	Arsenic	0.26	mg/L	0.0050	05/06/24 14:48	
EPA 6020B	Barium	0.045	mg/L	0.0050	05/06/24 14:48	
EPA 6020B	Boron	0.83	mg/L	0.040	05/06/24 14:48	
EPA 6020B	Cobalt	0.054	mg/L	0.0050	05/06/24 14:48	
EPA 6020B	Lithium	0.016J	mg/L	0.030	05/06/24 14:48	
EPA 6020B	Molybdenum	0.017	mg/L	0.010	05/06/24 14:48	
EPA 6020B	Selenium	0.0012J	mg/L	0.0050	05/06/24 14:48	B
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	108	mg/L	5.0	05/07/24 16:29	
SM 2320B-2011	Alkalinity, Total as CaCO3	108	mg/L	5.0	05/07/24 16:29	
SM 2540C-2015	Total Dissolved Solids	477	mg/L	25.0	05/07/24 15:58	
EPA 300.0 Rev 2.1 1993	Chloride	15.4	mg/L	1.0	05/07/24 14:53	
EPA 300.0 Rev 2.1 1993	Fluoride	0.36	mg/L	0.10	05/07/24 14:53	
EPA 300.0 Rev 2.1 1993	Sulfate	176	mg/L	4.0	05/08/24 01:51	
92728841004	HAM-PT-14					
EPA 6010D	Iron	13.7	mg/L	0.040	05/06/24 22:37	
EPA 6010D	Manganese	3.1	mg/L	0.040	05/06/24 22:37	
EPA 6010D	Potassium	5.4	mg/L	0.50	05/06/24 22:37	
EPA 6010D	Sodium	6.7	mg/L	1.0	05/06/24 22:37	
EPA 6010D	Calcium	101	mg/L	1.0	05/06/24 22:37	
EPA 6010D	Magnesium	12.7	mg/L	0.050	05/06/24 22:37	
EPA 6020B	Arsenic	0.22	mg/L	0.0050	05/06/24 14:51	
EPA 6020B	Barium	0.037	mg/L	0.0050	05/06/24 14:51	
EPA 6020B	Boron	0.51	mg/L	0.040	05/06/24 14:51	
EPA 6020B	Cobalt	0.021	mg/L	0.0050	05/06/24 14:51	
EPA 6020B	Lithium	0.055	mg/L	0.030	05/06/24 14:51	
EPA 6020B	Molybdenum	0.011	mg/L	0.010	05/06/24 14:51	
EPA 6020B	Selenium	0.0014J	mg/L	0.0050	05/06/24 14:51	B
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	121	mg/L	5.0	05/07/24 16:38	
SM 2320B-2011	Alkalinity, Total as CaCO3	121	mg/L	5.0	05/07/24 16:38	
SM 2540C-2015	Total Dissolved Solids	462	mg/L	25.0	05/07/24 15:58	
EPA 300.0 Rev 2.1 1993	Chloride	7.9	mg/L	1.0	05/07/24 15:08	
EPA 300.0 Rev 2.1 1993	Fluoride	0.43	mg/L	0.10	05/07/24 15:08	
EPA 300.0 Rev 2.1 1993	Sulfate	169	mg/L	4.0	05/08/24 02:06	
92728841005	HAM-PT-15					
EPA 6010D	Manganese	5.6	mg/L	0.040	05/07/24 15:31	
EPA 6010D	Iron	9.7	mg/L	0.040	05/06/24 22:41	
EPA 6010D	Potassium	5.2	mg/L	0.50	05/06/24 22:41	
EPA 6010D	Sodium	6.8	mg/L	1.0	05/06/24 22:41	
EPA 6010D	Calcium	141	mg/L	1.0	05/06/24 22:41	
EPA 6010D	Magnesium	15.6	mg/L	0.050	05/06/24 22:41	
EPA 6020B	Arsenic	0.41	mg/L	0.0050	05/06/24 14:55	
EPA 6020B	Barium	0.044	mg/L	0.0050	05/06/24 14:55	
EPA 6020B	Boron	0.75	mg/L	0.040	05/06/24 14:55	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92728841

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92728841005	HAM-PT-15					
EPA 6020B	Cobalt	0.052	mg/L	0.0050	05/06/24 14:55	
EPA 6020B	Lithium	0.051	mg/L	0.030	05/06/24 14:55	
EPA 6020B	Molybdenum	0.017	mg/L	0.010	05/06/24 14:55	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	124	mg/L	5.0	05/07/24 16:47	
SM 2320B-2011	Alkalinity, Total as CaCO3	124	mg/L	5.0	05/07/24 16:47	
SM 2540C-2015	Total Dissolved Solids	638	mg/L	25.0	05/07/24 15:58	
EPA 300.0 Rev 2.1 1993	Chloride	11.8	mg/L	1.0	05/07/24 15:53	
EPA 300.0 Rev 2.1 1993	Fluoride	0.55	mg/L	0.10	05/07/24 15:53	
EPA 300.0 Rev 2.1 1993	Sulfate	278	mg/L	7.0	05/08/24 02:21	
92728841008	HAM-AP1-FD-01					
EPA 6010D	Iron	13.6	mg/L	0.040	05/06/24 23:05	
EPA 6010D	Manganese	3.1	mg/L	0.040	05/06/24 23:05	
EPA 6010D	Potassium	5.4	mg/L	0.50	05/06/24 23:05	
EPA 6010D	Sodium	6.7	mg/L	1.0	05/06/24 23:05	
EPA 6010D	Calcium	99.4	mg/L	1.0	05/06/24 23:05	
EPA 6010D	Magnesium	12.6	mg/L	0.050	05/06/24 23:05	
EPA 6020B	Arsenic	0.20	mg/L	0.0050	05/06/24 15:15	
EPA 6020B	Barium	0.036	mg/L	0.0050	05/06/24 15:15	
EPA 6020B	Boron	0.47	mg/L	0.040	05/06/24 15:15	
EPA 6020B	Cobalt	0.020	mg/L	0.0050	05/06/24 15:15	
EPA 6020B	Lithium	0.052	mg/L	0.030	05/06/24 15:15	
EPA 6020B	Molybdenum	0.010	mg/L	0.010	05/06/24 15:15	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	122	mg/L	5.0	05/07/24 17:38	
SM 2320B-2011	Alkalinity, Total as CaCO3	122	mg/L	5.0	05/07/24 17:38	
SM 2540C-2015	Total Dissolved Solids	442	mg/L	25.0	05/07/24 15:59	
EPA 300.0 Rev 2.1 1993	Chloride	7.9	mg/L	1.0	05/07/24 16:08	
EPA 300.0 Rev 2.1 1993	Fluoride	0.42	mg/L	0.10	05/07/24 16:08	
EPA 300.0 Rev 2.1 1993	Sulfate	167	mg/L	4.0	05/08/24 02:35	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-INW-04 Lab ID: 92728841001 Collected: 05/02/24 14:18 Received: 05/03/24 13:20 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	10.3	mg/L	0.040	0.025	1	05/04/24 10:00	05/06/24 22:08	7439-89-6	
Manganese	4.2	mg/L	0.040	0.011	1	05/04/24 10:00	05/06/24 22:08	7439-96-5	
Potassium	5.4	mg/L	0.50	0.15	1	05/04/24 10:00	05/06/24 22:08	7440-09-7	
Sodium	6.9	mg/L	1.0	0.58	1	05/04/24 10:00	05/06/24 22:08	7440-23-5	
Calcium	110	mg/L	1.0	0.12	1	05/04/24 10:00	05/06/24 22:08	7440-70-2	
Magnesium	13.5	mg/L	0.050	0.012	1	05/04/24 10:00	05/06/24 22:08	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/04/24 09:50	05/06/24 14:29	7440-36-0	
Arsenic	0.21	mg/L	0.0050	0.00084	1	05/04/24 09:50	05/06/24 14:29	7440-38-2	
Barium	0.042	mg/L	0.0050	0.00047	1	05/04/24 09:50	05/06/24 14:29	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/04/24 09:50	05/06/24 14:29	7440-41-7	
Boron	0.61	mg/L	0.040	0.012	1	05/04/24 09:50	05/06/24 14:29	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/04/24 09:50	05/06/24 14:29	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/04/24 09:50	05/06/24 14:29	7440-47-3	
Cobalt	0.029	mg/L	0.0050	0.00032	1	05/04/24 09:50	05/06/24 14:29	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/04/24 09:50	05/06/24 14:29	7439-92-1	
Lithium	0.048	mg/L	0.030	0.0016	1	05/04/24 09:50	05/06/24 14:29	7439-93-2	
Molybdenum	0.016	mg/L	0.010	0.00062	1	05/04/24 09:50	05/06/24 14:29	7439-98-7	
Selenium	0.0016J	mg/L	0.0050	0.00096	1	05/04/24 09:50	05/06/24 14:29	7782-49-2	B
Thallium	0.00048J	mg/L	0.0010	0.00038	1	05/04/24 09:50	05/06/24 14:29	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/06/24 12:30	05/06/24 16:54	7439-97-6	
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	128	mg/L	5.0	5.0	1		05/07/24 16:02		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/07/24 16:02		
Alkalinity, Total as CaCO3	128	mg/L	5.0	5.0	1		05/07/24 16:02		
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	482	mg/L	25.0	25.0	1		05/07/24 15:51		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/09/24 04:42	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	8.0	mg/L	1.0	0.60	1		05/07/24 13:54	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-INW-04		Lab ID: 92728841001		Collected: 05/02/24 14:18		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.47	mg/L	0.10	0.050	1		05/07/24 13:54	16984-48-8	M1
Sulfate	180	mg/L	4.0	2.0	4		05/08/24 00:06	14808-79-8	M1

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-INW-05 Lab ID: 92728841002 Collected: 05/02/24 09:55 Received: 05/03/24 13:20 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	17.3	mg/L	0.040	0.025	1	05/04/24 10:00	05/06/24 22:13	7439-89-6	M1
Manganese	3.6	mg/L	0.040	0.011	1	05/04/24 10:00	05/06/24 22:13	7439-96-5	
Potassium	5.2	mg/L	0.50	0.15	1	05/04/24 10:00	05/06/24 22:13	7440-09-7	M1
Sodium	6.5	mg/L	1.0	0.58	1	05/04/24 10:00	05/06/24 22:13	7440-23-5	M1
Calcium	108	mg/L	1.0	0.12	1	05/04/24 10:00	05/06/24 22:13	7440-70-2	M1
Magnesium	12.6	mg/L	0.050	0.012	1	05/04/24 10:00	05/06/24 22:13	7439-95-4	M1
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	0.00098J	mg/L	0.0030	0.00054	1	05/04/24 09:50	05/06/24 14:44	7440-36-0	
Arsenic	0.24	mg/L	0.0050	0.00084	1	05/04/24 09:50	05/06/24 14:44	7440-38-2	
Barium	0.032	mg/L	0.0050	0.00047	1	05/04/24 09:50	05/06/24 14:44	7440-39-3	
Beryllium	0.000099J	mg/L	0.00050	0.000094	1	05/04/24 09:50	05/06/24 14:44	7440-41-7	
Boron	0.54	mg/L	0.040	0.012	1	05/04/24 09:50	05/06/24 14:44	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/04/24 09:50	05/06/24 14:44	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/04/24 09:50	05/06/24 14:44	7440-47-3	
Cobalt	0.028	mg/L	0.0050	0.00032	1	05/04/24 09:50	05/06/24 14:44	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/04/24 09:50	05/06/24 14:44	7439-92-1	
Lithium	0.060	mg/L	0.030	0.0016	1	05/04/24 09:50	05/06/24 14:44	7439-93-2	
Molybdenum	0.0094J	mg/L	0.010	0.00062	1	05/04/24 09:50	05/06/24 14:44	7439-98-7	
Selenium	0.0015J	mg/L	0.0050	0.00096	1	05/04/24 09:50	05/06/24 14:44	7782-49-2	B
Thallium	ND	mg/L	0.0010	0.00038	1	05/04/24 09:50	05/06/24 14:44	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/06/24 12:30	05/06/24 16:57	7439-97-6	
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	109	mg/L	5.0	5.0	1		05/07/24 16:12		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/07/24 16:12		
Alkalinity, Total as CaCO3	109	mg/L	5.0	5.0	1		05/07/24 16:12		
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	526	mg/L	25.0	25.0	1		05/07/24 15:51		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/09/24 04:42	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	6.0	mg/L	1.0	0.60	1		05/07/24 14:38	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-INW-05		Lab ID: 92728841002		Collected: 05/02/24 09:55		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.59	mg/L	0.10	0.050	1		05/07/24 14:38	16984-48-8	
Sulfate	206	mg/L	5.0	2.5	5		05/08/24 01:37	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-PT-08 Lab ID: 92728841003 Collected: 05/02/24 12:35 Received: 05/03/24 13:20 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	8.5	mg/L	0.040	0.025	1	05/04/24 10:00	05/06/24 22:32	7439-89-6	
Manganese	3.9	mg/L	0.040	0.011	1	05/04/24 10:00	05/06/24 22:32	7439-96-5	
Potassium	5.3	mg/L	0.50	0.15	1	05/04/24 10:00	05/06/24 22:32	7440-09-7	
Sodium	7.2	mg/L	1.0	0.58	1	05/04/24 10:00	05/06/24 22:32	7440-23-5	
Calcium	98.2	mg/L	1.0	0.12	1	05/04/24 10:00	05/06/24 22:32	7440-70-2	
Magnesium	12.0	mg/L	0.050	0.012	1	05/04/24 10:00	05/06/24 22:32	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/04/24 09:50	05/06/24 14:48	7440-36-0	
Arsenic	0.26	mg/L	0.0050	0.00084	1	05/04/24 09:50	05/06/24 14:48	7440-38-2	
Barium	0.045	mg/L	0.0050	0.00047	1	05/04/24 09:50	05/06/24 14:48	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/04/24 09:50	05/06/24 14:48	7440-41-7	
Boron	0.83	mg/L	0.040	0.012	1	05/04/24 09:50	05/06/24 14:48	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/04/24 09:50	05/06/24 14:48	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/04/24 09:50	05/06/24 14:48	7440-47-3	
Cobalt	0.054	mg/L	0.0050	0.00032	1	05/04/24 09:50	05/06/24 14:48	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/04/24 09:50	05/06/24 14:48	7439-92-1	
Lithium	0.016J	mg/L	0.030	0.0016	1	05/04/24 09:50	05/06/24 14:48	7439-93-2	
Molybdenum	0.017	mg/L	0.010	0.00062	1	05/04/24 09:50	05/06/24 14:48	7439-98-7	
Selenium	0.0012J	mg/L	0.0050	0.00096	1	05/04/24 09:50	05/06/24 14:48	7782-49-2	B
Thallium	ND	mg/L	0.0010	0.00038	1	05/04/24 09:50	05/06/24 14:48	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/06/24 12:30	05/06/24 16:59	7439-97-6	
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	108	mg/L	5.0	5.0	1		05/07/24 16:29		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/07/24 16:29		
Alkalinity, Total as CaCO3	108	mg/L	5.0	5.0	1		05/07/24 16:29		
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	477	mg/L	25.0	25.0	1		05/07/24 15:58		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/09/24 04:42	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	15.4	mg/L	1.0	0.60	1		05/07/24 14:53	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-PT-08		Lab ID: 92728841003		Collected: 05/02/24 12:35		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.36	mg/L	0.10	0.050	1		05/07/24 14:53	16984-48-8	
Sulfate	176	mg/L	4.0	2.0	4		05/08/24 01:51	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-PT-14		Lab ID: 92728841004		Collected: 05/02/24 12:06		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	13.7	mg/L	0.040	0.025	1	05/04/24 10:00	05/06/24 22:37	7439-89-6	
Manganese	3.1	mg/L	0.040	0.011	1	05/04/24 10:00	05/06/24 22:37	7439-96-5	
Potassium	5.4	mg/L	0.50	0.15	1	05/04/24 10:00	05/06/24 22:37	7440-09-7	
Sodium	6.7	mg/L	1.0	0.58	1	05/04/24 10:00	05/06/24 22:37	7440-23-5	
Calcium	101	mg/L	1.0	0.12	1	05/04/24 10:00	05/06/24 22:37	7440-70-2	
Magnesium	12.7	mg/L	0.050	0.012	1	05/04/24 10:00	05/06/24 22:37	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/04/24 09:50	05/06/24 14:51	7440-36-0	
Arsenic	0.22	mg/L	0.0050	0.00084	1	05/04/24 09:50	05/06/24 14:51	7440-38-2	
Barium	0.037	mg/L	0.0050	0.00047	1	05/04/24 09:50	05/06/24 14:51	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/04/24 09:50	05/06/24 14:51	7440-41-7	
Boron	0.51	mg/L	0.040	0.012	1	05/04/24 09:50	05/06/24 14:51	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/04/24 09:50	05/06/24 14:51	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/04/24 09:50	05/06/24 14:51	7440-47-3	
Cobalt	0.021	mg/L	0.0050	0.00032	1	05/04/24 09:50	05/06/24 14:51	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/04/24 09:50	05/06/24 14:51	7439-92-1	
Lithium	0.055	mg/L	0.030	0.0016	1	05/04/24 09:50	05/06/24 14:51	7439-93-2	
Molybdenum	0.011	mg/L	0.010	0.00062	1	05/04/24 09:50	05/06/24 14:51	7439-98-7	
Selenium	0.0014J	mg/L	0.0050	0.00096	1	05/04/24 09:50	05/06/24 14:51	7782-49-2	B
Thallium	ND	mg/L	0.0010	0.00038	1	05/04/24 09:50	05/06/24 14:51	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/06/24 12:30	05/06/24 17:15	7439-97-6	
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	121	mg/L	5.0	5.0	1		05/07/24 16:38		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/07/24 16:38		
Alkalinity, Total as CaCO ₃	121	mg/L	5.0	5.0	1		05/07/24 16:38		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	462	mg/L	25.0	25.0	1		05/07/24 15:58		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/09/24 04:43	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	7.9	mg/L	1.0	0.60	1		05/07/24 15:08	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-PT-14		Lab ID: 92728841004		Collected: 05/02/24 12:06		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.43	mg/L	0.10	0.050	1		05/07/24 15:08	16984-48-8	
Sulfate	169	mg/L	4.0	2.0	4		05/08/24 02:06	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-PT-15		Lab ID: 92728841005		Collected: 05/02/24 15:40		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Manganese	5.6	mg/L	0.040	0.011	1	05/04/24 10:00	05/07/24 15:31	7439-96-5	
Iron	9.7	mg/L	0.040	0.025	1	05/04/24 10:00	05/06/24 22:41	7439-89-6	
Potassium	5.2	mg/L	0.50	0.15	1	05/04/24 10:00	05/06/24 22:41	7440-09-7	
Sodium	6.8	mg/L	1.0	0.58	1	05/04/24 10:00	05/06/24 22:41	7440-23-5	
Calcium	141	mg/L	1.0	0.12	1	05/04/24 10:00	05/06/24 22:41	7440-70-2	
Magnesium	15.6	mg/L	0.050	0.012	1	05/04/24 10:00	05/06/24 22:41	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/04/24 09:50	05/06/24 14:55	7440-36-0	
Arsenic	0.41	mg/L	0.0050	0.00084	1	05/04/24 09:50	05/06/24 14:55	7440-38-2	
Barium	0.044	mg/L	0.0050	0.00047	1	05/04/24 09:50	05/06/24 14:55	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/04/24 09:50	05/06/24 14:55	7440-41-7	
Boron	0.75	mg/L	0.040	0.012	1	05/04/24 09:50	05/06/24 14:55	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/04/24 09:50	05/06/24 14:55	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/04/24 09:50	05/06/24 14:55	7440-47-3	
Cobalt	0.052	mg/L	0.0050	0.00032	1	05/04/24 09:50	05/06/24 14:55	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/04/24 09:50	05/06/24 14:55	7439-92-1	
Lithium	0.051	mg/L	0.030	0.0016	1	05/04/24 09:50	05/06/24 14:55	7439-93-2	
Molybdenum	0.017	mg/L	0.010	0.00062	1	05/04/24 09:50	05/06/24 14:55	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/04/24 09:50	05/06/24 14:55	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/04/24 09:50	05/06/24 14:55	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/06/24 12:30	05/06/24 17:18	7439-97-6	
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	124	mg/L	5.0	5.0	1		05/07/24 16:47		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/07/24 16:47		
Alkalinity, Total as CaCO ₃	124	mg/L	5.0	5.0	1		05/07/24 16:47		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	638	mg/L	25.0	25.0	1		05/07/24 15:58		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/09/24 04:43	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	11.8	mg/L	1.0	0.60	1		05/07/24 15:53	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-PT-15		Lab ID: 92728841005		Collected: 05/02/24 15:40		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.55	mg/L	0.10	0.050	1		05/07/24 15:53	16984-48-8	
Sulfate	278	mg/L	7.0	3.5	7		05/08/24 02:21	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-AP1-EB-01 Lab ID: 92728841006 Collected: 05/02/24 15:20 Received: 05/03/24 13:20 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	05/04/24 10:00	05/06/24 22:56	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	05/04/24 10:00	05/06/24 22:56	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	05/04/24 10:00	05/06/24 22:56	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	05/04/24 10:00	05/06/24 22:56	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	05/04/24 10:00	05/06/24 22:56	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	05/04/24 10:00	05/06/24 22:56	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/04/24 09:50	05/06/24 15:07	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/04/24 09:50	05/06/24 15:07	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	05/04/24 09:50	05/06/24 15:07	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/04/24 09:50	05/06/24 15:07	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	05/04/24 09:50	05/06/24 15:07	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/04/24 09:50	05/06/24 15:07	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/04/24 09:50	05/06/24 15:07	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	05/04/24 09:50	05/06/24 15:07	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/04/24 09:50	05/06/24 15:07	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/04/24 09:50	05/06/24 15:07	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	05/04/24 09:50	05/06/24 15:07	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/04/24 09:50	05/06/24 15:07	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/04/24 09:50	05/06/24 15:07	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/06/24 12:30	05/06/24 17:20	7439-97-6	
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/07/24 16:57		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/07/24 16:57		
Alkalinity, Total as CaCO3	ND	mg/L	5.0	5.0	1		05/07/24 16:57		
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		05/07/24 15:59		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/09/24 04:43	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		05/07/24 13:24	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-AP1-EB-01		Lab ID: 92728841006		Collected: 05/02/24 15:20		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		05/07/24 13:24	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		05/07/24 13:24	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-AP1-FB-01 Lab ID: 92728841007 Collected: 05/02/24 15:15 Received: 05/03/24 13:20 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	05/04/24 10:00	05/06/24 23:01	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	05/04/24 10:00	05/06/24 23:01	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	05/04/24 10:00	05/06/24 23:01	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	05/04/24 10:00	05/06/24 23:01	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	05/04/24 10:00	05/06/24 23:01	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	05/04/24 10:00	05/06/24 23:01	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/04/24 09:50	05/06/24 15:11	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/04/24 09:50	05/06/24 15:11	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	05/04/24 09:50	05/06/24 15:11	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/04/24 09:50	05/06/24 15:11	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	05/04/24 09:50	05/06/24 15:11	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/04/24 09:50	05/06/24 15:11	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/04/24 09:50	05/06/24 15:11	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	05/04/24 09:50	05/06/24 15:11	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/04/24 09:50	05/06/24 15:11	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/04/24 09:50	05/06/24 15:11	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	05/04/24 09:50	05/06/24 15:11	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/04/24 09:50	05/06/24 15:11	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/04/24 09:50	05/06/24 15:11	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/06/24 12:30	05/06/24 17:23	7439-97-6	
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/07/24 17:00		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/07/24 17:00		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		05/07/24 17:00		
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		05/07/24 15:59		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/09/24 04:44	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		05/07/24 13:39	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-AP1-FB-01		Lab ID: 92728841007		Collected: 05/02/24 15:15		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		05/07/24 13:39	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		05/07/24 13:39	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-AP1-FD-01 Lab ID: 92728841008 Collected: 05/02/24 00:00 Received: 05/03/24 13:20 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	13.6	mg/L	0.040	0.025	1	05/04/24 10:00	05/06/24 23:05	7439-89-6	
Manganese	3.1	mg/L	0.040	0.011	1	05/04/24 10:00	05/06/24 23:05	7439-96-5	
Potassium	5.4	mg/L	0.50	0.15	1	05/04/24 10:00	05/06/24 23:05	7440-09-7	
Sodium	6.7	mg/L	1.0	0.58	1	05/04/24 10:00	05/06/24 23:05	7440-23-5	
Calcium	99.4	mg/L	1.0	0.12	1	05/04/24 10:00	05/06/24 23:05	7440-70-2	
Magnesium	12.6	mg/L	0.050	0.012	1	05/04/24 10:00	05/06/24 23:05	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/04/24 09:50	05/06/24 15:15	7440-36-0	
Arsenic	0.20	mg/L	0.0050	0.00084	1	05/04/24 09:50	05/06/24 15:15	7440-38-2	
Barium	0.036	mg/L	0.0050	0.00047	1	05/04/24 09:50	05/06/24 15:15	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/04/24 09:50	05/06/24 15:15	7440-41-7	
Boron	0.47	mg/L	0.040	0.012	1	05/04/24 09:50	05/06/24 15:15	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/04/24 09:50	05/06/24 15:15	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/04/24 09:50	05/06/24 15:15	7440-47-3	
Cobalt	0.020	mg/L	0.0050	0.00032	1	05/04/24 09:50	05/06/24 15:15	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/04/24 09:50	05/06/24 15:15	7439-92-1	
Lithium	0.052	mg/L	0.030	0.0016	1	05/04/24 09:50	05/06/24 15:15	7439-93-2	
Molybdenum	0.010	mg/L	0.010	0.00062	1	05/04/24 09:50	05/06/24 15:15	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/04/24 09:50	05/06/24 15:15	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/04/24 09:50	05/06/24 15:15	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/06/24 12:30	05/06/24 17:26	7439-97-6	
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	122	mg/L	5.0	5.0	1		05/07/24 17:38		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/07/24 17:38		
Alkalinity, Total as CaCO ₃	122	mg/L	5.0	5.0	1		05/07/24 17:38		
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	442	mg/L	25.0	25.0	1		05/07/24 15:59		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/09/24 04:45	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	7.9	mg/L	1.0	0.60	1		05/07/24 16:08	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92728841

Sample: HAM-AP1-FD-01		Lab ID: 92728841008		Collected: 05/02/24 00:00		Received: 05/03/24 13:20		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.42	mg/L	0.10	0.050	1		05/07/24 16:08	16984-48-8	
Sulfate	167	mg/L	4.0	2.0	4		05/08/24 02:35	14808-79-8	

REPORT OF LABORATORY ANALYSIS



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

QC Batch: 852144

Analysis Method: EPA 6010D

QC Batch Method: EPA 3010A

Analysis Description: 6010D ATL

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008

METHOD BLANK: 4398182

Matrix: Water

Associated Lab Samples: 92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	05/06/24 21:58	
Iron	mg/L	ND	0.040	0.025	05/06/24 21:58	
Magnesium	mg/L	ND	0.050	0.012	05/06/24 21:58	
Manganese	mg/L	ND	0.040	0.011	05/06/24 21:58	
Potassium	mg/L	ND	0.50	0.15	05/06/24 21:58	
Sodium	mg/L	ND	1.0	0.58	05/06/24 21:58	

LABORATORY CONTROL SAMPLE: 4398183

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	1.0	105	80-120	
Iron	mg/L	1	1.0	104	80-120	
Magnesium	mg/L	1	1.0	105	80-120	
Manganese	mg/L	1	1.0	103	80-120	
Potassium	mg/L	1	1.2	115	80-120	
Sodium	mg/L	1	1.1	114	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4398184 4398185

Parameter	Units	92728841002	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		Result										
Calcium	mg/L	108	1	1	118	115	975	695	75-125	2	20	M1
Iron	mg/L	17.3	1	1	19.5	19.1	217	174	75-125	2	20	M1
Magnesium	mg/L	12.6	1	1	14.5	14.2	189	162	75-125	2	20	M1
Manganese	mg/L	3.6	1	1	4.8	4.7	123	111	75-125	2	20	
Potassium	mg/L	5.2	1	1	6.7	6.6	152	138	75-125	2	20	M1
Sodium	mg/L	6.5	1	1	8.1	7.9	154	135	75-125	2	20	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

QC Batch:	852143	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008		

METHOD BLANK: 4398178

Matrix: Water

Associated Lab Samples: 92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00054	05/06/24 14:22	
Arsenic	mg/L	0.0039J	0.0050	0.00084	05/06/24 14:22	
Barium	mg/L	ND	0.0050	0.00047	05/06/24 14:22	
Beryllium	mg/L	ND	0.00050	0.000094	05/06/24 14:22	
Boron	mg/L	ND	0.040	0.012	05/06/24 14:22	
Cadmium	mg/L	ND	0.00050	0.00010	05/06/24 14:22	
Chromium	mg/L	ND	0.0050	0.0019	05/06/24 14:22	
Cobalt	mg/L	ND	0.0050	0.00032	05/06/24 14:22	
Lead	mg/L	ND	0.0010	0.00016	05/06/24 14:22	
Lithium	mg/L	ND	0.030	0.0016	05/06/24 14:22	
Molybdenum	mg/L	ND	0.010	0.00062	05/06/24 14:22	
Selenium	mg/L	0.0021J	0.0050	0.00096	05/06/24 14:22	
Thallium	mg/L	ND	0.0010	0.00038	05/06/24 14:22	

LABORATORY CONTROL SAMPLE: 4398179

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.097	97	80-120	
Arsenic	mg/L	0.1	0.10	102	80-120	
Barium	mg/L	0.1	0.093	93	80-120	
Beryllium	mg/L	0.1	0.099	99	80-120	
Boron	mg/L	1	1.0	100	80-120	
Cadmium	mg/L	0.1	0.094	94	80-120	
Chromium	mg/L	0.1	0.096	96	80-120	
Cobalt	mg/L	0.1	0.093	93	80-120	
Lead	mg/L	0.1	0.098	98	80-120	
Lithium	mg/L	0.1	0.10	102	80-120	
Molybdenum	mg/L	0.1	0.095	95	80-120	
Selenium	mg/L	0.1	0.10	101	80-120	
Thallium	mg/L	0.1	0.097	97	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4398180 4398181

Parameter	Units	92728841001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	ND	0.1	0.1	0.10	0.10	102	101	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4398180 4398181											
Parameter	Units	92728841001		MS	MSD	MS		MS	MSD	% Rec	Max
		Result	Conc.	Spike	Spike	Result	Result	% Rec	% Rec	Limits	RPD
Arsenic	mg/L	0.21	0.1	0.1	0.1	0.31	0.32	93	104	75-125	3
Barium	mg/L	0.042	0.1	0.1	0.1	0.14	0.13	94	92	75-125	1
Beryllium	mg/L	ND	0.1	0.1	0.1	0.093	0.093	93	93	75-125	0
Boron	mg/L	0.61	1	1	1	1.6	1.6	95	100	75-125	3
Cadmium	mg/L	ND	0.1	0.1	0.1	0.094	0.095	94	95	75-125	1
Chromium	mg/L	ND	0.1	0.1	0.1	0.092	0.094	92	94	75-125	2
Cobalt	mg/L	0.029	0.1	0.1	0.1	0.12	0.12	90	91	75-125	1
Lead	mg/L	ND	0.1	0.1	0.1	0.097	0.10	97	100	75-125	2
Lithium	mg/L	0.048	0.1	0.1	0.1	0.14	0.14	97	96	75-125	0
Molybdenum	mg/L	0.016	0.1	0.1	0.1	0.11	0.11	98	97	75-125	1
Selenium	mg/L	0.0016J	0.1	0.1	0.1	0.10	0.10	99	102	75-125	3
Thallium	mg/L	0.00048J	0.1	0.1	0.1	0.098	0.098	97	98	75-125	1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

QC Batch: 852339

Analysis Method: EPA 7470A

QC Batch Method: EPA 7470A

Analysis Description: 7470 Mercury

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008

METHOD BLANK: 4398727

Matrix: Water

Associated Lab Samples: 92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	05/06/24 16:49	

LABORATORY CONTROL SAMPLE: 4398728

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0025	101	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4398729 4398730

Parameter	Units	92728841003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.0025	0.0025	0.0024	0.0024	97	97	75-125	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

QC Batch: 852662

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007

METHOD BLANK: 4400154

Matrix: Water

Associated Lab Samples: 92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	05/07/24 14:10	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/07/24 14:10	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/07/24 14:10	

LABORATORY CONTROL SAMPLE: 4400155

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.8	104	80-120	

LABORATORY CONTROL SAMPLE: 4400156

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.3	105	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4400157 4400158

Parameter	Units	92727753001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	7.4	50	50	58.7	58.5	103	102	80-120	0	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4400159 4400160

Parameter	Units	92727753002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	ND	50	50	52.8	52.6	103	103	80-120	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

QC Batch: 852668

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92728841008

METHOD BLANK: 4400185

Matrix: Water

Associated Lab Samples: 92728841008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	05/07/24 17:22	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/07/24 17:22	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/07/24 17:22	

LABORATORY CONTROL SAMPLE: 4400186

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	50.4	101	80-120	

LABORATORY CONTROL SAMPLE: 4400187

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.3	103	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4400188 4400189

Parameter	Units	92727828002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	270	50	50	318	305	96	71	80-120	4	25	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4400190 4400191

Parameter	Units	92727828003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	284	50	50	335	326	103	84	80-120	3	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

QC Batch: 852725

Analysis Method: SM 2540C-2015

QC Batch Method: SM 2540C-2015

Analysis Description: 2540C Total Dissolved Solids

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92728841001, 92728841002

METHOD BLANK: 4400519

Matrix: Water

Associated Lab Samples: 92728841001, 92728841002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	05/07/24 15:47	

LABORATORY CONTROL SAMPLE: 4400520

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	250	254	102	90-110	

SAMPLE DUPLICATE: 4400521

Parameter	Units	92728666001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	84.0	89.0	6	25	

SAMPLE DUPLICATE: 4400522

Parameter	Units	92728671010 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	109	107	2	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

QC Batch: 852726

Analysis Method: SM 2540C-2015

QC Batch Method: SM 2540C-2015

Analysis Description: 2540C Total Dissolved Solids

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008

METHOD BLANK: 4400526

Matrix: Water

Associated Lab Samples: 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	05/07/24 15:58	

LABORATORY CONTROL SAMPLE: 4400527

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	250	256	102	90-110	

SAMPLE DUPLICATE: 4400528

Parameter	Units	92728841003 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	477	460	4	25	

SAMPLE DUPLICATE: 4400529

Parameter	Units	92728786001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	1370	1360	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

QC Batch:	853221	Analysis Method:	SM 4500-S2D-2011
QC Batch Method:	SM 4500-S2D-2011	Analysis Description:	4500S2D Sulfide Water
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008		

METHOD BLANK:	4403056	Matrix:	Water
Associated Lab Samples:	92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	05/09/24 04:40	

LABORATORY CONTROL SAMPLE: 4403057						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.54	109	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4403058 4403059												
Parameter	Units	92728841007 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.55	0.56	109	113	80-120	3	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4403060 4403061												
Parameter	Units	92728860002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.46	0.52	92	104	80-120	12	10 R1	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92728841

QC Batch:	852564	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008		

METHOD BLANK:	4399708	Matrix:	Water
Associated Lab Samples:	92728841001, 92728841002, 92728841003, 92728841004, 92728841005, 92728841006, 92728841007, 92728841008		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	05/07/24 12:54	
Fluoride	mg/L	ND	0.10	0.050	05/07/24 12:54	
Sulfate	mg/L	ND	1.0	0.50	05/07/24 12:54	

LABORATORY CONTROL SAMPLE: 4399709						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	48.7	97	90-110	
Fluoride	mg/L	2.5	2.5	101	90-110	
Sulfate	mg/L	50	47.6	95	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4399710 4399711												
Parameter	Units	92728841001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	8.0	50	50	58.4	58.9	101	102	90-110	1	10	
Fluoride	mg/L	0.47	2.5	2.5	4.1	4.1	146	145	90-110	0	10	M1
Sulfate	mg/L	180	50	50	231	223	101	86	90-110	3	10	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4399712 4399713												
Parameter	Units	92728877001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	1.5	50	50	58.2	53.1	113	103	90-110	9	10	M1
Fluoride	mg/L	0.47	2.5	2.5	4.1	3.7	145	129	90-110	10	10	M1
Sulfate	mg/L	37.7	50	50	84.1	86.7	93	98	90-110	3	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1
Pace Project No.: 92728841

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

B Analyte was detected in the associated method blank.
M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.
R1 RPD value was outside control limits.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92728841

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92728841001	HAM-INW-04	EPA 3010A	852144	EPA 6010D	852161
92728841002	HAM-INW-05	EPA 3010A	852144	EPA 6010D	852161
92728841003	HAM-PT-08	EPA 3010A	852144	EPA 6010D	852161
92728841004	HAM-PT-14	EPA 3010A	852144	EPA 6010D	852161
92728841005	HAM-PT-15	EPA 3010A	852144	EPA 6010D	852161
92728841006	HAM-AP1-EB-01	EPA 3010A	852144	EPA 6010D	852161
92728841007	HAM-AP1-FB-01	EPA 3010A	852144	EPA 6010D	852161
92728841008	HAM-AP1-FD-01	EPA 3010A	852144	EPA 6010D	852161
92728841001	HAM-INW-04	EPA 3005A	852143	EPA 6020B	852177
92728841002	HAM-INW-05	EPA 3005A	852143	EPA 6020B	852177
92728841003	HAM-PT-08	EPA 3005A	852143	EPA 6020B	852177
92728841004	HAM-PT-14	EPA 3005A	852143	EPA 6020B	852177
92728841005	HAM-PT-15	EPA 3005A	852143	EPA 6020B	852177
92728841006	HAM-AP1-EB-01	EPA 3005A	852143	EPA 6020B	852177
92728841007	HAM-AP1-FB-01	EPA 3005A	852143	EPA 6020B	852177
92728841008	HAM-AP1-FD-01	EPA 3005A	852143	EPA 6020B	852177
92728841001	HAM-INW-04	EPA 7470A	852339	EPA 7470A	852477
92728841002	HAM-INW-05	EPA 7470A	852339	EPA 7470A	852477
92728841003	HAM-PT-08	EPA 7470A	852339	EPA 7470A	852477
92728841004	HAM-PT-14	EPA 7470A	852339	EPA 7470A	852477
92728841005	HAM-PT-15	EPA 7470A	852339	EPA 7470A	852477
92728841006	HAM-AP1-EB-01	EPA 7470A	852339	EPA 7470A	852477
92728841007	HAM-AP1-FB-01	EPA 7470A	852339	EPA 7470A	852477
92728841008	HAM-AP1-FD-01	EPA 7470A	852339	EPA 7470A	852477
92728841001	HAM-INW-04	SM 2320B-2011	852662		
92728841002	HAM-INW-05	SM 2320B-2011	852662		
92728841003	HAM-PT-08	SM 2320B-2011	852662		
92728841004	HAM-PT-14	SM 2320B-2011	852662		
92728841005	HAM-PT-15	SM 2320B-2011	852662		
92728841006	HAM-AP1-EB-01	SM 2320B-2011	852662		
92728841007	HAM-AP1-FB-01	SM 2320B-2011	852662		
92728841008	HAM-AP1-FD-01	SM 2320B-2011	852668		
92728841001	HAM-INW-04	SM 2540C-2015	852725		
92728841002	HAM-INW-05	SM 2540C-2015	852725		
92728841003	HAM-PT-08	SM 2540C-2015	852726		
92728841004	HAM-PT-14	SM 2540C-2015	852726		
92728841005	HAM-PT-15	SM 2540C-2015	852726		
92728841006	HAM-AP1-EB-01	SM 2540C-2015	852726		
92728841007	HAM-AP1-FB-01	SM 2540C-2015	852726		
92728841008	HAM-AP1-FD-01	SM 2540C-2015	852726		
92728841001	HAM-INW-04	SM 4500-S2D-2011	853221		
92728841002	HAM-INW-05	SM 4500-S2D-2011	853221		
92728841003	HAM-PT-08	SM 4500-S2D-2011	853221		
92728841004	HAM-PT-14	SM 4500-S2D-2011	853221		
92728841005	HAM-PT-15	SM 4500-S2D-2011	853221		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1
Pace Project No.: 92728841

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92728841006	HAM-AP1-EB-01	SM 4500-S2D-2011	853221		
92728841007	HAM-AP1-FB-01	SM 4500-S2D-2011	853221		
92728841008	HAM-AP1-FD-01	SM 4500-S2D-2011	853221		
92728841001	HAM-INW-04	EPA 300.0 Rev 2.1 1993	852564		
92728841002	HAM-INW-05	EPA 300.0 Rev 2.1 1993	852564		
92728841003	HAM-PT-08	EPA 300.0 Rev 2.1 1993	852564		
92728841004	HAM-PT-14	EPA 300.0 Rev 2.1 1993	852564		
92728841005	HAM-PT-15	EPA 300.0 Rev 2.1 1993	852564		
92728841006	HAM-AP1-EB-01	EPA 300.0 Rev 2.1 1993	852564		
92728841007	HAM-AP1-FB-01	EPA 300.0 Rev 2.1 1993	852564		
92728841008	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	852564		

REPORT OF LABORATORY ANALYSIS



DC#_Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

Project

WO#: 92728841

Courier:

☐ Commercial☐ Fed Ex☒ Pace☐ UPS☐ USPS☐ Other:☐ Client

Custody Seal Present?

☒ Yes☐ No

Seals Intact?

☒ Yes☐ No☐ N/A

Date/Initials Person Examining Contents: 5/13/24 SJC

Packing Material:

☒ Bubble Wrap☐ Bubble Bags☐ None☐ Other

Thermometer:

☒ IR Gun ID: 232

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

2.3

Correction Factor:

Add/Subtract (°C)

6.0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

2.3

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☒ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☒ No

			Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.	
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.	
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.	
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4.	
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.	
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.	
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A		
Containers Intact?	☒ Yes ☐ No ☐ N/A	7.	
Dissolved analysis: Samples Field Filtered?	☐ Yes ☐ No ☒ N/A	8.	
Sample Labels Match COC?	☐ Yes ☒ No ☐ N/A	9.	
-Includes Date/Time/ID/Analysis Matrix: 5/13/24 SJC			
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☒ No ☐ N/A	10.	
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.	
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A		

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☒ No

Chain of custody not 2 signatures but still received 20
 SPAD from ALCO HAM-API-FD-01 is not present
 but HAM-API-FD-02 is

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, BOD/8015 (water) DOC, LPHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

WO#: 92728841

PM: BV

Due Date: 05/10/24

CLIENT: 92- GP-HAM

Item #	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic Zn Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WG9U-Wide-mouthed Glass Jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DD94-40 mL Amber NH4Cl (N/A)(Cl-)	DD9H-40 mL VOA HCl (N/A)	VG8T-40 mL VOA Na2SO3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DD9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	VJGX (3 vials per kit)-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)		BP3R-250 mL Plastic (NH4)2SO4 (9.3-9.7)	AG6U-100 mL Amber Unpreserved (N/A) (Cl-)	VSGU-20 mL Scintillation vials (N/A)	DD9U-40 mL Amber Unpreserved vials (N/A)	
1		2																											
2		2																											
3		2																											
4		2																											
5		2																											
6		2																											
7		2																											
8		2																											
9		2																											
10		2																											
11																													
12																													

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers).

Insurance Note: By signing this form you are accepting Pacific NCT 20 day treatment limit and agreeing to pay charges of 15% per month for any services not paid within 30 days.



May 20, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1
Pace Project No.: 92730250

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on May 10, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Peachtree Corners, GA

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Anthony Szwast, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1

Pace Project No.: 92730250

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1
Pace Project No.: 92730250

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92730250001	HAM-PT-07	Water	05/09/24 14:58	05/10/24 13:40
92730250002	HAM-PT-13	Water	05/09/24 16:45	05/10/24 13:40

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92730250

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92730250001	HAM-PT-07	EPA 6010D	DRB	6
		EPA 6020B	MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92730250002	HAM-PT-13	EPA 6010D	DRB	6
		EPA 6020B	MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3

PASI-A = Pace Analytical Services - Asheville

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92730250

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92730250001	HAM-PT-07					
EPA 6010D	Sodium	6.8	mg/L	1.0	05/15/24 22:05	
EPA 6010D	Iron	16.9	mg/L	0.040	05/14/24 17:10	
EPA 6010D	Manganese	3.2	mg/L	0.040	05/14/24 17:10	
EPA 6010D	Potassium	5.6	mg/L	0.50	05/14/24 17:10	
EPA 6010D	Calcium	98.0	mg/L	1.0	05/14/24 17:10	
EPA 6010D	Magnesium	12.5	mg/L	0.050	05/14/24 17:10	
EPA 6020B	Antimony	0.00059J	mg/L	0.0030	05/15/24 14:25	
EPA 6020B	Arsenic	0.30	mg/L	0.0050	05/15/24 14:25	
EPA 6020B	Barium	0.037	mg/L	0.0050	05/15/24 14:25	
EPA 6020B	Beryllium	0.00010J	mg/L	0.00050	05/15/24 14:25	
EPA 6020B	Boron	0.55	mg/L	0.040	05/15/24 14:25	
EPA 6020B	Cobalt	0.041	mg/L	0.0050	05/15/24 14:25	
EPA 6020B	Lithium	0.064	mg/L	0.030	05/15/24 14:25	
EPA 6020B	Molybdenum	0.010	mg/L	0.010	05/15/24 14:25	
SM 2540C-2015	Total Dissolved Solids	463	mg/L	25.0	05/14/24 12:37	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	117	mg/L	5.0	05/17/24 19:33	
SM 2320B-2011	Alkalinity, Total as CaCO3	117	mg/L	5.0	05/17/24 19:33	
EPA 300.0 Rev 2.1 1993	Chloride	9.2	mg/L	1.0	05/14/24 00:00	
EPA 300.0 Rev 2.1 1993	Fluoride	0.33	mg/L	0.10	05/14/24 00:00	
EPA 300.0 Rev 2.1 1993	Sulfate	177	mg/L	4.0	05/14/24 03:34	
92730250002	HAM-PT-13					
EPA 6010D	Iron	15.5	mg/L	0.040	05/14/24 17:13	
EPA 6010D	Manganese	3.5	mg/L	0.040	05/14/24 17:13	
EPA 6010D	Potassium	5.0	mg/L	0.50	05/14/24 17:13	
EPA 6010D	Calcium	94.4	mg/L	1.0	05/14/24 17:13	
EPA 6010D	Magnesium	11.4	mg/L	0.050	05/14/24 17:13	
EPA 6010D	Sodium	6.9	mg/L	1.0	05/15/24 22:10	
EPA 6020B	Arsenic	0.30	mg/L	0.0050	05/15/24 14:29	
EPA 6020B	Barium	0.036	mg/L	0.0050	05/15/24 14:29	
EPA 6020B	Boron	0.54	mg/L	0.040	05/15/24 14:29	
EPA 6020B	Cobalt	0.026	mg/L	0.0050	05/15/24 14:29	
EPA 6020B	Lithium	0.061	mg/L	0.030	05/15/24 14:29	
EPA 6020B	Molybdenum	0.0095J	mg/L	0.010	05/15/24 14:29	
SM 2540C-2015	Total Dissolved Solids	472	mg/L	25.0	05/14/24 12:37	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	106	mg/L	5.0	05/17/24 19:42	
SM 2320B-2011	Alkalinity, Total as CaCO3	106	mg/L	5.0	05/17/24 19:42	
EPA 300.0 Rev 2.1 1993	Chloride	9.0	mg/L	1.0	05/14/24 00:14	
EPA 300.0 Rev 2.1 1993	Fluoride	0.35	mg/L	0.10	05/14/24 00:14	
EPA 300.0 Rev 2.1 1993	Sulfate	195	mg/L	4.0	05/14/24 03:48	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92730250

Sample: HAM-PT-07		Lab ID: 92730250001		Collected: 05/09/24 14:58		Received: 05/10/24 13:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Sodium	6.8	mg/L	1.0	0.58	1	05/10/24 17:49	05/15/24 22:05	7440-23-5	
Iron	16.9	mg/L	0.040	0.025	1	05/10/24 17:49	05/14/24 17:10	7439-89-6	
Manganese	3.2	mg/L	0.040	0.011	1	05/10/24 17:49	05/14/24 17:10	7439-96-5	
Potassium	5.6	mg/L	0.50	0.15	1	05/10/24 17:49	05/14/24 17:10	7440-09-7	
Calcium	98.0	mg/L	1.0	0.12	1	05/10/24 17:49	05/14/24 17:10	7440-70-2	
Magnesium	12.5	mg/L	0.050	0.012	1	05/10/24 17:49	05/14/24 17:10	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	0.00059J	mg/L	0.0030	0.00054	1	05/11/24 13:00	05/15/24 14:25	7440-36-0	
Arsenic	0.30	mg/L	0.0050	0.00084	1	05/11/24 13:00	05/15/24 14:25	7440-38-2	
Barium	0.037	mg/L	0.0050	0.00047	1	05/11/24 13:00	05/15/24 14:25	7440-39-3	
Beryllium	0.00010J	mg/L	0.00050	0.000094	1	05/11/24 13:00	05/15/24 14:25	7440-41-7	
Boron	0.55	mg/L	0.040	0.012	1	05/11/24 13:00	05/15/24 14:25	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/11/24 13:00	05/15/24 14:25	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/11/24 13:00	05/15/24 14:25	7440-47-3	
Cobalt	0.041	mg/L	0.0050	0.00032	1	05/11/24 13:00	05/15/24 14:25	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/11/24 13:00	05/15/24 14:25	7439-92-1	
Lithium	0.064	mg/L	0.030	0.0016	1	05/11/24 13:00	05/15/24 14:25	7439-93-2	
Molybdenum	0.010	mg/L	0.010	0.00062	1	05/11/24 13:00	05/15/24 14:25	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/11/24 13:00	05/15/24 14:25	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/11/24 13:00	05/15/24 14:25	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/16/24 17:00	05/17/24 09:15	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	463	mg/L	25.0	25.0	1		05/14/24 12:37		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	117	mg/L	5.0	5.0	1		05/17/24 19:33		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/17/24 19:33		
Alkalinity, Total as CaCO3	117	mg/L	5.0	5.0	1		05/17/24 19:33		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/11/24 02:08	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	9.2	mg/L	1.0	0.60	1		05/14/24 00:00	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92730250

Sample: HAM-PT-07		Lab ID: 92730250001		Collected: 05/09/24 14:58		Received: 05/10/24 13:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.33	mg/L	0.10	0.050	1		05/14/24 00:00	16984-48-8	
Sulfate	177	mg/L	4.0	2.0	4		05/14/24 03:34	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92730250

Sample: HAM-PT-13		Lab ID: 92730250002		Collected: 05/09/24 16:45		Received: 05/10/24 13:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	15.5	mg/L	0.040	0.025	1	05/10/24 17:49	05/14/24 17:13	7439-89-6	
Manganese	3.5	mg/L	0.040	0.011	1	05/10/24 17:49	05/14/24 17:13	7439-96-5	
Potassium	5.0	mg/L	0.50	0.15	1	05/10/24 17:49	05/14/24 17:13	7440-09-7	
Calcium	94.4	mg/L	1.0	0.12	1	05/10/24 17:49	05/14/24 17:13	7440-70-2	
Magnesium	11.4	mg/L	0.050	0.012	1	05/10/24 17:49	05/14/24 17:13	7439-95-4	
Sodium	6.9	mg/L	1.0	0.58	1	05/10/24 17:49	05/15/24 22:10	7440-23-5	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/11/24 13:00	05/15/24 14:29	7440-36-0	
Arsenic	0.30	mg/L	0.0050	0.00084	1	05/11/24 13:00	05/15/24 14:29	7440-38-2	
Barium	0.036	mg/L	0.0050	0.00047	1	05/11/24 13:00	05/15/24 14:29	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/11/24 13:00	05/15/24 14:29	7440-41-7	
Boron	0.54	mg/L	0.040	0.012	1	05/11/24 13:00	05/15/24 14:29	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/11/24 13:00	05/15/24 14:29	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/11/24 13:00	05/15/24 14:29	7440-47-3	
Cobalt	0.026	mg/L	0.0050	0.00032	1	05/11/24 13:00	05/15/24 14:29	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/11/24 13:00	05/15/24 14:29	7439-92-1	
Lithium	0.061	mg/L	0.030	0.0016	1	05/11/24 13:00	05/15/24 14:29	7439-93-2	
Molybdenum	0.0095J	mg/L	0.010	0.00062	1	05/11/24 13:00	05/15/24 14:29	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/11/24 13:00	05/15/24 14:29	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/11/24 13:00	05/15/24 14:29	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/16/24 17:00	05/17/24 09:17	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	472	mg/L	25.0	25.0	1		05/14/24 12:37		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	106	mg/L	5.0	5.0	1		05/17/24 19:42		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/17/24 19:42		
Alkalinity, Total as CaCO3	106	mg/L	5.0	5.0	1		05/17/24 19:42		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/11/24 02:10	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	9.0	mg/L	1.0	0.60	1		05/14/24 00:14	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92730250

Sample: HAM-PT-13		Lab ID: 92730250002		Collected: 05/09/24 16:45		Received: 05/10/24 13:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.35	mg/L	0.10	0.050	1		05/14/24 00:14	16984-48-8	
Sulfate	195	mg/L	4.0	2.0	4		05/14/24 03:48	14808-79-8	

REPORT OF LABORATORY ANALYSIS



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92730250

QC Batch: 853813

Analysis Method: EPA 6010D

QC Batch Method: EPA 3010A

Analysis Description: 6010D ATL

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92730250001, 92730250002

METHOD BLANK: 4406154

Matrix: Water

Associated Lab Samples: 92730250001, 92730250002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	05/14/24 14:43	
Iron	mg/L	ND	0.040	0.025	05/14/24 14:43	
Magnesium	mg/L	ND	0.050	0.012	05/14/24 14:43	
Manganese	mg/L	ND	0.040	0.011	05/14/24 14:43	
Potassium	mg/L	ND	0.50	0.15	05/15/24 21:55	
Sodium	mg/L	ND	1.0	0.58	05/15/24 21:55	

LABORATORY CONTROL SAMPLE: 4406155

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	0.95J	95	80-120	
Iron	mg/L	1	0.97	97	80-120	
Magnesium	mg/L	1	0.98	98	80-120	
Manganese	mg/L	1	0.96	96	80-120	
Potassium	mg/L	1	0.89	89	80-120	
Sodium	mg/L	1	0.94J	94	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4406156 4406157

Parameter	Units	92729900005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Calcium	mg/L	ND	1	1	1.3J	1.3J	94	98	75-125		20	
Iron	mg/L	ND	1	1	0.96	0.98	96	98	75-125	2	20	
Magnesium	mg/L	ND	1	1	1.0	1.0	95	98	75-125	2	20	
Manganese	mg/L	ND	1	1	1.1	1.1	101	99	75-125	2	20	
Potassium	mg/L	3370 ug/L	1	1	3.6	5.6	19	224	75-125	45	20 M1, R1	
Sodium	mg/L	3680000 ug/L	1	1	3540	3590	-13800	-8670	75-125	1	20 M1	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92730250

QC Batch: 853920

Analysis Method: EPA 6020B

QC Batch Method: EPA 3005A

Analysis Description: 6020 MET

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92730250001, 92730250002

METHOD BLANK: 4406560

Matrix: Water

Associated Lab Samples: 92730250001, 92730250002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00054	05/15/24 13:55	
Arsenic	mg/L	ND	0.0050	0.00084	05/15/24 13:55	
Barium	mg/L	ND	0.0050	0.00047	05/15/24 13:55	
Beryllium	mg/L	ND	0.00050	0.000094	05/15/24 13:55	
Boron	mg/L	ND	0.040	0.012	05/15/24 13:55	
Cadmium	mg/L	ND	0.00050	0.00010	05/15/24 13:55	
Chromium	mg/L	ND	0.0050	0.0019	05/15/24 13:55	
Cobalt	mg/L	ND	0.0050	0.00032	05/15/24 13:55	
Lead	mg/L	ND	0.0010	0.00016	05/15/24 13:55	
Lithium	mg/L	ND	0.030	0.0016	05/15/24 13:55	
Molybdenum	mg/L	ND	0.010	0.00062	05/15/24 13:55	
Selenium	mg/L	ND	0.0050	0.00096	05/15/24 13:55	
Thallium	mg/L	ND	0.0010	0.00038	05/15/24 13:55	

LABORATORY CONTROL SAMPLE: 4406561

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.11	106	80-120	
Arsenic	mg/L	0.1	0.10	103	80-120	
Barium	mg/L	0.1	0.10	102	80-120	
Beryllium	mg/L	0.1	0.11	109	80-120	
Boron	mg/L	1	1.1	105	80-120	
Cadmium	mg/L	0.1	0.10	103	80-120	
Chromium	mg/L	0.1	0.10	103	80-120	
Cobalt	mg/L	0.1	0.10	102	80-120	
Lead	mg/L	0.1	0.10	105	80-120	
Lithium	mg/L	0.1	0.11	110	80-120	
Molybdenum	mg/L	0.1	0.11	106	80-120	
Selenium	mg/L	0.1	0.10	104	80-120	
Thallium	mg/L	0.1	0.10	101	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4406562

4406563

Parameter	Units	92730292001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	0.78J ug/L	0.1	0.1	0.11	0.11	107	105	75-125	2	20	
Arsenic	mg/L	1.9J ug/L	0.1	0.1	0.11	0.11	107	104	75-125	3	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92730250

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:			4406562	4406563								
Parameter	Units	92730292001	MS	MSD	MS	MSD	MS	MSD	% Rec	RPD	Max	Qual
		Result	Spike	Spike								
Barium	mg/L	82.1J ug/L	0.1	0.1	0.19	0.19	108	103	75-125	2	20	
Beryllium	mg/L	ND	0.1	0.1	0.10	0.10	103	102	75-125	1	20	
Boron	mg/L	19.1J ug/L	1	1	1.0	1.0	101	99	75-125	1	20	
Cadmium	mg/L	ND	0.1	0.1	0.10	0.10	104	103	75-125	1	20	
Chromium	mg/L	4.3J ug/L	0.1	0.1	0.11	0.11	106	104	75-125	2	20	
Cobalt	mg/L	ND	0.1	0.1	0.10	0.10	103	103	75-125	0	20	
Lead	mg/L	0.19J ug/L	0.1	0.1	0.10	0.10	103	102	75-125	1	20	
Lithium	mg/L	ND	0.1	0.1	0.10	0.10	103	101	75-125	2	20	
Molybdenum	mg/L	ND	0.1	0.1	0.11	0.11	107	107	75-125	0	20	
Selenium	mg/L	ND	0.1	0.1	0.11	0.10	106	103	75-125	3	20	
Thallium	mg/L	ND	0.1	0.1	0.10	0.099	101	99	75-125	2	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92730250

QC Batch: 855047

Analysis Method: EPA 7470A

QC Batch Method: EPA 7470A

Analysis Description: 7470 Mercury

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92730250001, 92730250002

METHOD BLANK: 4411728

Matrix: Water

Associated Lab Samples: 92730250001, 92730250002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	05/17/24 08:16	

LABORATORY CONTROL SAMPLE: 4411729

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0023	92	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4411730 4411731

Parameter	Units	92729900001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.0025	0.0025	0.0022	0.0023	88	92	75-125	4	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92730250

QC Batch: 854348

Analysis Method: SM 2540C-2015

QC Batch Method: SM 2540C-2015

Analysis Description: 2540C Total Dissolved Solids

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92730250001, 92730250002

METHOD BLANK: 4408261

Matrix: Water

Associated Lab Samples: 92730250001, 92730250002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	05/14/24 12:36	

LABORATORY CONTROL SAMPLE: 4408262

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	399	100	80-120	

SAMPLE DUPLICATE: 4408263

Parameter	Units	92730149001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	125	125	0	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92730250

QC Batch: 855114

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92730250001, 92730250002

METHOD BLANK: 4412185

Matrix: Water

Associated Lab Samples: 92730250001, 92730250002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	05/17/24 16:58	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/17/24 16:58	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/17/24 16:58	

LABORATORY CONTROL SAMPLE: 4412186

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	50.3	101	80-120	

LABORATORY CONTROL SAMPLE: 4412187

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	49.5	99	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4412190 4412191

Parameter	Units	92731061002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	71.7	50	50	124	122	104	101	80-120	1	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4414712 4414713

Parameter	Units	92729999001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	52.3	50	50	88.4	86.8	72	69	80-120	2	25	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92730250

QC Batch: 853854

Analysis Method: SM 4500-S2D-2011

QC Batch Method: SM 4500-S2D-2011

Analysis Description: 4500S2D Sulfide Water

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92730250001, 92730250002

METHOD BLANK: 4406359

Matrix: Water

Associated Lab Samples: 92730250001, 92730250002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	05/11/24 01:56	

LABORATORY CONTROL SAMPLE: 4406360

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.49	98	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4406361 4406362

Parameter	Units	92729816001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.57	0.58	106	109	80-120	3	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4406363 4406364

Parameter	Units	92729816003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.54	0.54	106	107	80-120	1	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92730250

QC Batch: 854169

Analysis Method: EPA 300.0 Rev 2.1 1993

QC Batch Method: EPA 300.0 Rev 2.1 1993

Analysis Description: 300.0 IC Anions

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92730250001, 92730250002

METHOD BLANK: 4407338

Matrix: Water

Associated Lab Samples: 92730250001, 92730250002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	05/13/24 18:31	
Fluoride	mg/L	ND	0.10	0.050	05/13/24 18:31	
Sulfate	mg/L	ND	1.0	0.50	05/13/24 18:31	

LABORATORY CONTROL SAMPLE: 4407339

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	49.5	99	90-110	
Fluoride	mg/L	2.5	2.4	95	90-110	
Sulfate	mg/L	50	49.6	99	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4407340

4407341

Parameter	Units	92730282001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	907	50	50	942	940	71	66	90-110	0	10	M1
Fluoride	mg/L	ND	2.5	2.5	ND	ND	0	0	90-110		10	D3,M1
Sulfate	mg/L	171	50	50	211	211	81	81	90-110	0	10	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1
Pace Project No.: 92730250

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

D3	Sample was diluted due to the presence of high levels of non-target analytes or other matrix interference.
M1	Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.
R1	RPD value was outside control limits.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92730250

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92730250001	HAM-PT-07	EPA 3010A	853813	EPA 6010D	853829
92730250002	HAM-PT-13	EPA 3010A	853813	EPA 6010D	853829
92730250001	HAM-PT-07	EPA 3005A	853920	EPA 6020B	853946
92730250002	HAM-PT-13	EPA 3005A	853920	EPA 6020B	853946
92730250001	HAM-PT-07	EPA 7470A	855047	EPA 7470A	855155
92730250002	HAM-PT-13	EPA 7470A	855047	EPA 7470A	855155
92730250001	HAM-PT-07	SM 2540C-2015	854348		
92730250002	HAM-PT-13	SM 2540C-2015	854348		
92730250001	HAM-PT-07	SM 2320B-2011	855114		
92730250002	HAM-PT-13	SM 2320B-2011	855114		
92730250001	HAM-PT-07	SM 4500-S2D-2011	853854		
92730250002	HAM-PT-13	SM 4500-S2D-2011	853854		
92730250001	HAM-PT-07	EPA 300.0 Rev 2.1 1993	854169		
92730250002	HAM-PT-13	EPA 300.0 Rev 2.1 1993	854169		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



DC#_Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

Georgia Power

Project #:

WO#: 92730250



92730250

Courier: ☐ Fed Ex ☐ UPS ☐ USPS ☐ Client
☐ Commercial ☒ Pace ☐ Other:Custody Seal Present? ☐ Yes ☒ No Seals Intact? ☐ Yes ☐ No ☒ N/A

Date/Initials Person Examining Contents: 5/10/24

Packing Material: ☐ Bubble Wrap ☐ Bubble Bags ☒ None ☐ Other

Biological Tissue Frozen?

☐ Yes ☐ No ☒ N/A

Thermometer:

☒ IR Gun ID:

083

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

2.1

Correction Factor:

Add/Subtract (°C)

-10.1

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

2.2

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

			Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.	
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.	
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.	
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4.	
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.	
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.	
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A		
Containers Intact?	☒ Yes ☐ No ☐ N/A	7.	
Dissolved analysis: Samples Field Filtered?	☐ Yes ☐ No ☐ N/A	8.	
Sample Labels Match COC?	☒ Yes ☐ No ☐ N/A	9.	
-Includes Date/Time/ID/Analysis Matrix:	WT		
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10.	
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.	
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A		

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted: _____ Date/Time: _____

Project Manager SCURF Review: _____

Date: _____

Project Manager SRF Review: _____

Date: _____



DC#_Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

WO#: 92730250

PM: BV

Due Date: 05/24/24

CLIENT: 92- GP-HAM

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic 2N Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGFU-Wide-mouthed Glass Jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG94-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2SO3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9W-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit)-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)	BP9R-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AGOU-100 mL Amber Unpreserved (N/A) (Cl-)	VSGU-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)
1		2	1																								
2		2	1																								
3																											
4																											
5																											
6																											
7																											
8																											
9																											
10																											
11																											
12																											

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers).



CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Section A Required Client Information:		Section B Required Project Information:		Section C Invoice Information:	
Company:	GA Power	Region To:	SCS Contacts	Client:	Southern Co.
Address:	Atlanta, GA	Copy To:	Geosyntec Contacts	Company Name:	
Email To:	SCS Contacts	Purchase Order No.:	GPCR2474-0001	Address:	
Phone:		Project Name:	Hammond AP-1	Facility Code:	
Requested Due Date/TAT:	3 day	Project Number:		Person Project Manager:	Bonnie Vang
				Person Invoice #:	10839
				State:	GA
				REGULATORY AGENCY	
				NPDES ☐ GROUND WATER ☐ DRINKING WATER ☐	
				UST ☐ RCRA ☐ OTHER ☒	

Section D Required Client Information		Valid Matrix Codes		COLLECTED		SAMPLE TYPE (S=SWAB C=COMP)		MATRIX CODE (See valid codes in list)		DATE		TIME		SAMPLE TEMP AT COLLECTION		# OF CONTAINERS		PRESERVATIVES		ANALYSIS TEST		REQUESTED ANALYSIS FILTERED (Y/N)		Residual Chlorine (Y/N)		Pace Project No./ Lab I.D.	
ITEM #	SAMPLE ID (A-Z, 0-9 / - /) Sample IDs MUST BE UNIQUE	SW	WW	SL	OL	CL	WL	AL	OT	TS	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	
1	HAM-PT-07										5/9/2024	1458															
2	HAM-PT-13										5/9/2024	1645															
3																											
4																											
5																											
6																											
7																											
8																											
9																											
10																											
11																											
12																											

ADDITIONAL COMMENTS		RELINQUISHED BY / AFFILIATION		DATE		TIME		ACCEPTED BY / AFFILIATION		DATE		TIME		SAMPLE CONDITIONS	
Anthony Shaw / Geosyntec		Geosyntec		5/10/24		1340		Ryan Williams / Pace		5/10/24		1340			
Ryan Williams / Pace		Pace		5/10/24		1552		Charles Hewitt		5/10/24		1552			

SAMPLER NAME AND SIGNATURE		PRINT Name of SAMPLER:		Anthony Schwarz		Geosyntec Consultants, Inc.	
SIGNATURE of SAMPLER:		DATE Signed		05/09/24		AM/PM/DOY/YY:	



June 17, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1
Pace Project No.: 92731696

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on May 17, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Peachtree Corners, GA

Revision 1: Client requested that the lab re-check anions for HAM-AP1-FB-01 (Lab ID 92731696003) and HAM-AP1-FD-01 (lab ID 92731696005). The lab did a re-run for both samples and the results did not confirm the original. A revised report was issued.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc

Anthony Szwast, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1

Pace Project No.: 92731696

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1

Pace Project No.: 92731696

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92731696001	HAM-AP1-EB-01	Water	05/15/24 16:02	05/17/24 12:55
92731696002	HAM-AP1-EB-02	Water	05/15/24 16:20	05/17/24 12:55
92731696003	HAM-AP1-FB-01	Water	05/15/24 15:56	05/17/24 12:55
92731696004	HAM-AP1-FB-02	Water	05/15/24 17:19	05/17/24 12:55
92731696005	HAM-AP1-FD-01	Water	05/15/24 00:00	05/17/24 12:55
92731696006	HAM-AP1-FD-02	Water	05/15/24 00:00	05/17/24 12:55
92731696007	HAM-INW-03	Water	05/14/24 14:08	05/17/24 12:55
92731696008	HAM-INW-04	Water	05/15/24 14:20	05/17/24 12:55
92731696009	HAM-INW-05	Water	05/15/24 11:18	05/17/24 12:55
92731696010	HAM-PT-07	Water	05/16/24 12:16	05/17/24 12:55
92731696011	HAM-PT-08	Water	05/16/24 10:37	05/17/24 12:55
92731696012	HAM-PT-09	Water	05/14/24 10:40	05/17/24 12:55
92731696013	HAM-PT-10	Water	05/15/24 11:52	05/17/24 12:55
92731696014	HAM-PT-11	Water	05/14/24 15:20	05/17/24 12:55
92731696015	HAM-PT-12	Water	05/14/24 12:05	05/17/24 12:55
92731696016	HAM-PT-13	Water	05/15/24 18:45	05/17/24 12:55
92731696017	HAM-PT-14	Water	05/15/24 18:27	05/17/24 12:55
92731696018	HAM-PT-15	Water	05/15/24 16:10	05/17/24 12:55

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92731696

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92731696001	HAM-AP1-EB-01	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92731696002	HAM-AP1-EB-02	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92731696003	HAM-AP1-FB-01	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92731696004	HAM-AP1-FB-02	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92731696005	HAM-AP1-FD-01	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92731696006	HAM-AP1-FD-02	EPA 6010D	AJM	6
		EPA 6020B	CW1	13

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92731696

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92731696007	HAM-INW-03	EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM, DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
92731696008	HAM-INW-04	SM 4500-S2D-2011	MDW	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
92731696009	HAM-INW-05	EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
92731696010	HAM-PT-07	SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92731696011	HAM-PT-08	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92731696

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92731696012	HAM-PT-09	SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
92731696013	HAM-PT-10	SM 4500-S2D-2011	MDW	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
92731696014	HAM-PT-11	EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	MDW	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92731696015	HAM-PT-12	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	MDW	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
92731696016	HAM-PT-13	EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92731696

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92731696017	HAM-PT-14	EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
92731696018	HAM-PT-15	EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	AJM, DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3

PASI-A = Pace Analytical Services - Asheville

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92731696

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92731696002	HAM-AP1-EB-02					
EPA 6020B	Antimony	0.0013J	mg/L	0.0030	05/22/24 15:20	
92731696005	HAM-AP1-FD-01					
EPA 6010D	Iron	0.20	mg/L	0.040	05/23/24 01:21	
EPA 6010D	Manganese	0.70	mg/L	0.040	05/23/24 01:21	
EPA 6010D	Potassium	6.5	mg/L	0.50	05/23/24 01:21	
EPA 6010D	Sodium	8.9	mg/L	1.0	05/23/24 01:21	
EPA 6010D	Calcium	103	mg/L	1.0	05/23/24 01:21	
EPA 6010D	Magnesium	13.8	mg/L	0.050	05/23/24 01:21	
EPA 6020B	Barium	0.053	mg/L	0.0050	05/22/24 15:31	
EPA 6020B	Boron	1.5	mg/L	0.040	05/22/24 15:31	
EPA 6020B	Cobalt	0.0016J	mg/L	0.0050	05/22/24 15:31	
EPA 6020B	Molybdenum	0.090	mg/L	0.010	05/22/24 15:31	
EPA 6020B	Selenium	0.0011J	mg/L	0.0050	05/22/24 15:31	
SM 2540C-2015	Total Dissolved Solids	528	mg/L	25.0	05/20/24 12:18	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	131	mg/L	5.0	05/21/24 18:48	
SM 2320B-2011	Alkalinity, Total as CaCO3	131	mg/L	5.0	05/21/24 18:48	
EPA 300.0 Rev 2.1 1993	Chloride	49.1	mg/L	1.0	06/12/24 13:41	
EPA 300.0 Rev 2.1 1993	Fluoride	0.19	mg/L	0.10	06/12/24 13:41	
EPA 300.0 Rev 2.1 1993	Sulfate	149	mg/L	3.0	06/12/24 14:39	
92731696006	HAM-AP1-FD-02					
EPA 6010D	Iron	7.9	mg/L	0.040	05/23/24 01:24	
EPA 6010D	Manganese	4.6	mg/L	0.040	05/23/24 01:24	
EPA 6010D	Potassium	4.8	mg/L	0.50	05/23/24 01:24	
EPA 6010D	Sodium	6.9	mg/L	1.0	05/23/24 01:24	
EPA 6010D	Calcium	103	mg/L	1.0	05/23/24 01:24	
EPA 6010D	Magnesium	12.8	mg/L	0.050	05/23/24 01:24	
EPA 6020B	Arsenic	0.19	mg/L	0.0050	05/22/24 15:45	
EPA 6020B	Barium	0.042	mg/L	0.0050	05/22/24 15:45	
EPA 6020B	Boron	0.59	mg/L	0.040	05/22/24 15:45	
EPA 6020B	Cobalt	0.031	mg/L	0.0050	05/22/24 15:45	
EPA 6020B	Lithium	0.044	mg/L	0.030	05/22/24 15:45	
EPA 6020B	Molybdenum	0.014	mg/L	0.010	05/22/24 15:45	
SM 2540C-2015	Total Dissolved Solids	491	mg/L	25.0	05/20/24 12:18	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	138	mg/L	5.0	05/21/24 19:06	
SM 2320B-2011	Alkalinity, Total as CaCO3	138	mg/L	5.0	05/21/24 19:06	
EPA 300.0 Rev 2.1 1993	Chloride	10.1	mg/L	1.0	05/20/24 10:17	
EPA 300.0 Rev 2.1 1993	Fluoride	0.26	mg/L	0.10	05/20/24 10:17	
EPA 300.0 Rev 2.1 1993	Sulfate	189	mg/L	4.0	05/20/24 20:43	
92731696007	HAM-INW-03					
EPA 6010D	Sodium	12.4	mg/L	1.0	05/24/24 11:34	
EPA 6010D	Iron	0.11	mg/L	0.040	05/23/24 02:19	
EPA 6010D	Manganese	0.45	mg/L	0.040	05/23/24 02:19	
EPA 6010D	Potassium	13.8	mg/L	0.50	05/23/24 02:19	
EPA 6010D	Calcium	127	mg/L	1.0	05/23/24 02:19	
EPA 6010D	Magnesium	17.1	mg/L	0.050	05/23/24 02:19	
EPA 6020B	Barium	0.075	mg/L	0.0050	05/22/24 16:41	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92731696

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92731696007	HAM-INW-03					
EPA 6020B	Boron	1.5	mg/L	0.040	05/22/24 16:41	
EPA 6020B	Cobalt	0.00070J	mg/L	0.0050	05/22/24 16:41	
EPA 6020B	Lithium	0.0050J	mg/L	0.030	05/22/24 16:41	
EPA 6020B	Molybdenum	0.082	mg/L	0.010	05/22/24 16:41	
SM 2540C-2015	Total Dissolved Solids	564	mg/L	25.0	05/20/24 12:16	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	175	mg/L	5.0	05/21/24 16:31	
SM 2320B-2011	Alkalinity, Total as CaCO3	175	mg/L	5.0	05/21/24 16:31	M1
EPA 300.0 Rev 2.1 1993	Chloride	56.9	mg/L	1.0	05/21/24 00:39	M1
EPA 300.0 Rev 2.1 1993	Fluoride	0.20	mg/L	0.10	05/21/24 00:39	
EPA 300.0 Rev 2.1 1993	Sulfate	178	mg/L	4.0	05/21/24 08:01	
92731696008	HAM-INW-04					
EPA 6010D	Iron	8.4	mg/L	0.040	05/23/24 01:35	
EPA 6010D	Manganese	4.4	mg/L	0.040	05/23/24 01:35	
EPA 6010D	Potassium	4.8	mg/L	0.50	05/23/24 01:35	
EPA 6010D	Sodium	7.0	mg/L	1.0	05/23/24 01:35	
EPA 6010D	Calcium	107	mg/L	1.0	05/23/24 01:35	
EPA 6010D	Magnesium	13.1	mg/L	0.050	05/23/24 01:35	
EPA 6020B	Arsenic	0.19	mg/L	0.0050	05/22/24 15:49	
EPA 6020B	Barium	0.043	mg/L	0.0050	05/22/24 15:49	
EPA 6020B	Boron	0.59	mg/L	0.040	05/22/24 15:49	
EPA 6020B	Cobalt	0.031	mg/L	0.0050	05/22/24 15:49	
EPA 6020B	Lithium	0.043	mg/L	0.030	05/22/24 15:49	
EPA 6020B	Molybdenum	0.015	mg/L	0.010	05/22/24 15:49	
SM 2540C-2015	Total Dissolved Solids	483	mg/L	25.0	05/20/24 12:19	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	133	mg/L	5.0	05/21/24 19:16	
SM 2320B-2011	Alkalinity, Total as CaCO3	133	mg/L	5.0	05/21/24 19:16	
EPA 300.0 Rev 2.1 1993	Chloride	9.9	mg/L	1.0	05/21/24 01:48	
EPA 300.0 Rev 2.1 1993	Fluoride	0.28	mg/L	0.10	05/21/24 01:48	
EPA 300.0 Rev 2.1 1993	Sulfate	187	mg/L	4.0	05/21/24 08:42	
92731696009	HAM-INW-05					
EPA 6010D	Iron	16.9	mg/L	0.040	05/23/24 01:38	
EPA 6010D	Manganese	3.3	mg/L	0.040	05/23/24 01:38	
EPA 6010D	Potassium	4.7	mg/L	0.50	05/23/24 01:38	
EPA 6010D	Sodium	6.7	mg/L	1.0	05/23/24 01:38	
EPA 6010D	Calcium	101	mg/L	1.0	05/23/24 01:38	
EPA 6010D	Magnesium	11.8	mg/L	0.050	05/23/24 01:38	
EPA 6020B	Arsenic	0.23	mg/L	0.0050	05/22/24 15:53	
EPA 6020B	Barium	0.033	mg/L	0.0050	05/22/24 15:53	
EPA 6020B	Beryllium	0.00012J	mg/L	0.00050	05/22/24 15:53	
EPA 6020B	Boron	0.51	mg/L	0.040	05/22/24 15:53	
EPA 6020B	Cobalt	0.026	mg/L	0.0050	05/22/24 15:53	
EPA 6020B	Lithium	0.057	mg/L	0.030	05/22/24 15:53	
EPA 6020B	Molybdenum	0.0096J	mg/L	0.010	05/22/24 15:53	
SM 2540C-2015	Total Dissolved Solids	456	mg/L	25.0	05/20/24 12:20	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	123	mg/L	5.0	05/21/24 19:25	
SM 2320B-2011	Alkalinity, Total as CaCO3	123	mg/L	5.0	05/21/24 19:25	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92731696

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92731696009	HAM-INW-05					
EPA 300.0 Rev 2.1 1993	Chloride	6.9	mg/L	1.0	05/21/24 02:02	
EPA 300.0 Rev 2.1 1993	Fluoride	0.37	mg/L	0.10	05/21/24 02:02	
EPA 300.0 Rev 2.1 1993	Sulfate	181	mg/L	4.0	05/21/24 08:56	
92731696010	HAM-PT-07					
EPA 6010D	Iron	15.7	mg/L	0.040	05/23/24 01:41	
EPA 6010D	Manganese	3.4	mg/L	0.040	05/23/24 01:41	
EPA 6010D	Potassium	4.9	mg/L	0.50	05/23/24 01:41	
EPA 6010D	Sodium	7.0	mg/L	1.0	05/23/24 01:41	
EPA 6010D	Calcium	96.0	mg/L	1.0	05/23/24 01:41	
EPA 6010D	Magnesium	12.1	mg/L	0.050	05/23/24 01:41	
EPA 6020B	Arsenic	0.27	mg/L	0.0050	05/22/24 15:56	
EPA 6020B	Barium	0.034	mg/L	0.0050	05/22/24 15:56	
EPA 6020B	Boron	0.50	mg/L	0.040	05/22/24 15:56	
EPA 6020B	Cobalt	0.052	mg/L	0.0050	05/22/24 15:56	
EPA 6020B	Lithium	0.056	mg/L	0.030	05/22/24 15:56	
EPA 6020B	Molybdenum	0.0093J	mg/L	0.010	05/22/24 15:56	
SM 2540C-2015	Total Dissolved Solids	450	mg/L	25.0	05/20/24 12:22	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	116	mg/L	5.0	05/28/24 17:56	
SM 2320B-2011	Alkalinity, Total as CaCO3	116	mg/L	5.0	05/28/24 17:56	
EPA 300.0 Rev 2.1 1993	Chloride	10	mg/L	1.0	05/21/24 02:16	
EPA 300.0 Rev 2.1 1993	Fluoride	0.31	mg/L	0.10	05/21/24 02:16	
EPA 300.0 Rev 2.1 1993	Sulfate	171	mg/L	4.0	05/21/24 09:10	
92731696011	HAM-PT-08					
EPA 6010D	Iron	8.0	mg/L	0.040	05/23/24 01:45	
EPA 6010D	Manganese	3.3	mg/L	0.040	05/23/24 01:45	
EPA 6010D	Potassium	4.8	mg/L	0.50	05/23/24 01:45	
EPA 6010D	Sodium	7.2	mg/L	1.0	05/23/24 01:45	
EPA 6010D	Calcium	89.4	mg/L	1.0	05/23/24 01:45	
EPA 6010D	Magnesium	11.5	mg/L	0.050	05/23/24 01:45	
EPA 6020B	Arsenic	0.23	mg/L	0.0050	05/22/24 16:00	
EPA 6020B	Barium	0.041	mg/L	0.0050	05/22/24 16:00	
EPA 6020B	Boron	0.73	mg/L	0.040	05/22/24 16:00	
EPA 6020B	Cobalt	0.046	mg/L	0.0050	05/22/24 16:00	
EPA 6020B	Lead	0.0079	mg/L	0.0010	05/22/24 16:00	
EPA 6020B	Lithium	0.010J	mg/L	0.030	05/22/24 16:00	
EPA 6020B	Molybdenum	0.017	mg/L	0.010	05/22/24 16:00	
SM 2540C-2015	Total Dissolved Solids	410	mg/L	25.0	05/20/24 12:22	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	104	mg/L	5.0	05/28/24 18:06	
SM 2320B-2011	Alkalinity, Total as CaCO3	104	mg/L	5.0	05/28/24 18:06	
EPA 300.0 Rev 2.1 1993	Chloride	16.7	mg/L	1.0	05/21/24 20:59	
EPA 300.0 Rev 2.1 1993	Fluoride	0.19	mg/L	0.10	05/21/24 20:59	
EPA 300.0 Rev 2.1 1993	Sulfate	159	mg/L	4.0	05/22/24 07:35	
92731696012	HAM-PT-09					
EPA 6010D	Iron	0.42	mg/L	0.040	05/23/24 01:48	
EPA 6010D	Manganese	0.19	mg/L	0.040	05/23/24 01:48	
EPA 6010D	Potassium	6.1	mg/L	0.50	05/23/24 01:48	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92731696

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92731696012	HAM-PT-09					
EPA 6010D	Sodium	9.3	mg/L	1.0	05/23/24 01:48	
EPA 6010D	Calcium	82.8	mg/L	1.0	05/23/24 01:48	
EPA 6010D	Magnesium	23.7	mg/L	0.050	05/23/24 01:48	
EPA 6020B	Barium	0.058	mg/L	0.0050	05/22/24 16:04	
EPA 6020B	Boron	1.4	mg/L	0.040	05/22/24 16:04	
EPA 6020B	Cadmium	0.00015J	mg/L	0.00050	05/22/24 16:04	
EPA 6020B	Cobalt	0.0012J	mg/L	0.0050	05/22/24 16:04	
EPA 6020B	Lead	0.00017J	mg/L	0.0010	05/22/24 16:04	
EPA 6020B	Molybdenum	0.27	mg/L	0.010	05/22/24 16:04	
SM 2540C-2015	Total Dissolved Solids	436	mg/L	25.0	05/20/24 12:17	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	139	mg/L	5.0	05/21/24 17:10	
SM 2320B-2011	Alkalinity, Total as CaCO3	139	mg/L	5.0	05/21/24 17:10	M1
EPA 300.0 Rev 2.1 1993	Chloride	44.4	mg/L	1.0	05/21/24 02:29	
EPA 300.0 Rev 2.1 1993	Fluoride	0.37	mg/L	0.10	05/21/24 02:29	
EPA 300.0 Rev 2.1 1993	Sulfate	130	mg/L	3.0	05/21/24 10:07	M1
92731696013	HAM-PT-10					
EPA 6010D	Iron	0.24	mg/L	0.040	05/23/24 01:51	
EPA 6010D	Manganese	0.74	mg/L	0.040	05/23/24 01:51	
EPA 6010D	Potassium	6.7	mg/L	0.50	05/23/24 01:51	
EPA 6010D	Sodium	9.2	mg/L	1.0	05/23/24 01:51	
EPA 6010D	Calcium	108	mg/L	1.0	05/23/24 01:51	
EPA 6010D	Magnesium	14.3	mg/L	0.050	05/23/24 01:51	
EPA 6020B	Barium	0.054	mg/L	0.0050	05/22/24 16:07	
EPA 6020B	Boron	1.5	mg/L	0.040	05/22/24 16:07	
EPA 6020B	Cobalt	0.0016J	mg/L	0.0050	05/22/24 16:07	
EPA 6020B	Molybdenum	0.092	mg/L	0.010	05/22/24 16:07	
SM 2540C-2015	Total Dissolved Solids	503	mg/L	25.0	05/20/24 12:20	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	132	mg/L	5.0	05/21/24 19:35	
SM 2320B-2011	Alkalinity, Total as CaCO3	132	mg/L	5.0	05/21/24 19:35	
EPA 300.0 Rev 2.1 1993	Chloride	50.1	mg/L	1.0	05/21/24 03:11	
EPA 300.0 Rev 2.1 1993	Fluoride	0.22	mg/L	0.10	05/21/24 03:11	
EPA 300.0 Rev 2.1 1993	Sulfate	146	mg/L	3.0	05/21/24 10:48	
92731696014	HAM-PT-11					
EPA 6010D	Manganese	0.28	mg/L	0.040	05/23/24 01:55	
EPA 6010D	Potassium	6.0	mg/L	0.50	05/23/24 01:55	
EPA 6010D	Sodium	8.8	mg/L	1.0	05/23/24 01:55	
EPA 6010D	Calcium	90.9	mg/L	1.0	05/23/24 01:55	
EPA 6010D	Magnesium	16.2	mg/L	0.050	05/23/24 01:55	
EPA 6020B	Barium	0.057	mg/L	0.0050	05/22/24 16:11	
EPA 6020B	Boron	1.6	mg/L	0.040	05/22/24 16:11	
EPA 6020B	Cadmium	0.00013J	mg/L	0.00050	05/22/24 16:11	
EPA 6020B	Cobalt	0.0016J	mg/L	0.0050	05/22/24 16:11	
EPA 6020B	Molybdenum	0.24	mg/L	0.010	05/22/24 16:11	
SM 2540C-2015	Total Dissolved Solids	441	mg/L	25.0	05/20/24 12:17	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	125	mg/L	5.0	05/21/24 17:33	
SM 2320B-2011	Alkalinity, Total as CaCO3	125	mg/L	5.0	05/21/24 17:33	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92731696

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92731696014	HAM-PT-11					
EPA 300.0 Rev 2.1 1993	Chloride	41.4	mg/L	1.0	05/21/24 03:25	
EPA 300.0 Rev 2.1 1993	Fluoride	0.34	mg/L	0.10	05/21/24 03:25	
EPA 300.0 Rev 2.1 1993	Sulfate	122	mg/L	3.0	05/21/24 11:03	
92731696015	HAM-PT-12					
EPA 6010D	Iron	0.33	mg/L	0.040	05/23/24 01:59	
EPA 6010D	Manganese	1.0	mg/L	0.040	05/23/24 01:59	
EPA 6010D	Potassium	6.8	mg/L	0.50	05/23/24 01:59	
EPA 6010D	Sodium	11.8	mg/L	1.0	05/23/24 01:59	
EPA 6010D	Calcium	99.7	mg/L	1.0	05/23/24 01:59	
EPA 6010D	Magnesium	16.6	mg/L	0.050	05/23/24 01:59	
EPA 6020B	Barium	0.069	mg/L	0.0050	05/22/24 16:15	
EPA 6020B	Boron	1.6	mg/L	0.040	05/22/24 16:15	
EPA 6020B	Cadmium	0.00014J	mg/L	0.00050	05/22/24 16:15	
EPA 6020B	Cobalt	0.0044J	mg/L	0.0050	05/22/24 16:15	
EPA 6020B	Lead	0.00017J	mg/L	0.0010	05/22/24 16:15	
EPA 6020B	Molybdenum	0.085	mg/L	0.010	05/22/24 16:15	
SM 2540C-2015	Total Dissolved Solids	523	mg/L	25.0	05/20/24 12:17	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	129	mg/L	5.0	05/21/24 17:51	
SM 2320B-2011	Alkalinity, Total as CaCO3	129	mg/L	5.0	05/21/24 17:51	
EPA 300.0 Rev 2.1 1993	Chloride	50.3	mg/L	1.0	05/21/24 03:38	
EPA 300.0 Rev 2.1 1993	Fluoride	0.20	mg/L	0.10	05/21/24 03:38	
EPA 300.0 Rev 2.1 1993	Sulfate	125	mg/L	3.0	05/21/24 11:17	
92731696016	HAM-PT-13					
EPA 6010D	Iron	15.0	mg/L	0.040	05/23/24 02:02	
EPA 6010D	Manganese	3.6	mg/L	0.040	05/23/24 02:02	
EPA 6010D	Potassium	5.0	mg/L	0.50	05/23/24 02:02	
EPA 6010D	Sodium	7.8	mg/L	1.0	05/23/24 02:02	
EPA 6010D	Calcium	99.2	mg/L	1.0	05/23/24 02:02	
EPA 6010D	Magnesium	12.0	mg/L	0.050	05/23/24 02:02	
EPA 6020B	Arsenic	0.29	mg/L	0.0050	05/22/24 16:19	
EPA 6020B	Barium	0.033	mg/L	0.0050	05/22/24 16:19	
EPA 6020B	Boron	0.52	mg/L	0.040	05/22/24 16:19	
EPA 6020B	Cobalt	0.024	mg/L	0.0050	05/22/24 16:19	
EPA 6020B	Lithium	0.058	mg/L	0.030	05/22/24 16:19	
EPA 6020B	Molybdenum	0.0087J	mg/L	0.010	05/22/24 16:19	
SM 2540C-2015	Total Dissolved Solids	459	mg/L	25.0	05/20/24 12:21	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	111	mg/L	5.0	05/21/24 19:44	
SM 2320B-2011	Alkalinity, Total as CaCO3	111	mg/L	5.0	05/21/24 19:44	
EPA 300.0 Rev 2.1 1993	Chloride	9.5	mg/L	1.0	05/21/24 04:20	
EPA 300.0 Rev 2.1 1993	Fluoride	0.34	mg/L	0.10	05/21/24 04:20	
EPA 300.0 Rev 2.1 1993	Sulfate	190	mg/L	4.0	05/21/24 11:31	
92731696017	HAM-PT-14					
EPA 6010D	Iron	14.9	mg/L	0.040	05/23/24 02:05	
EPA 6010D	Manganese	3.1	mg/L	0.040	05/23/24 02:05	
EPA 6010D	Potassium	5.0	mg/L	0.50	05/23/24 02:05	
EPA 6010D	Sodium	6.7	mg/L	1.0	05/23/24 02:05	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92731696

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92731696017	HAM-PT-14					
EPA 6010D	Calcium	97.4	mg/L	1.0	05/23/24 02:05	
EPA 6010D	Magnesium	12.7	mg/L	0.050	05/23/24 02:05	
EPA 6020B	Arsenic	0.21	mg/L	0.0050	05/22/24 16:33	
EPA 6020B	Barium	0.038	mg/L	0.0050	05/22/24 16:33	
EPA 6020B	Beryllium	0.00016J	mg/L	0.00050	05/22/24 16:33	
EPA 6020B	Boron	0.51	mg/L	0.040	05/22/24 16:33	
EPA 6020B	Cobalt	0.020	mg/L	0.0050	05/22/24 16:33	
EPA 6020B	Lead	0.00046J	mg/L	0.0010	05/22/24 16:33	
EPA 6020B	Lithium	0.051	mg/L	0.030	05/22/24 16:33	
EPA 6020B	Molybdenum	0.011	mg/L	0.010	05/22/24 16:33	
SM 2540C-2015	Total Dissolved Solids	461	mg/L	25.0	05/20/24 12:21	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	121	mg/L	5.0	05/21/24 19:53	
SM 2320B-2011	Alkalinity, Total as CaCO3	121	mg/L	5.0	05/21/24 19:53	
EPA 300.0 Rev 2.1 1993	Chloride	10.5	mg/L	1.0	05/21/24 04:34	
EPA 300.0 Rev 2.1 1993	Fluoride	0.26	mg/L	0.10	05/21/24 04:34	
EPA 300.0 Rev 2.1 1993	Sulfate	175	mg/L	4.0	05/21/24 11:44	
92731696018	HAM-PT-15					
EPA 6010D	Sodium	8.1	mg/L	1.0	05/24/24 11:31	
EPA 6010D	Iron	9.2	mg/L	0.040	05/23/24 02:16	
EPA 6010D	Manganese	5.7	mg/L	0.040	05/23/24 02:16	
EPA 6010D	Potassium	5.3	mg/L	0.50	05/23/24 02:16	
EPA 6010D	Calcium	141	mg/L	1.0	05/23/24 02:16	
EPA 6010D	Magnesium	16.1	mg/L	0.050	05/23/24 02:16	
EPA 6020B	Arsenic	0.39	mg/L	0.0050	05/22/24 16:37	
EPA 6020B	Barium	0.043	mg/L	0.0050	05/22/24 16:37	
EPA 6020B	Boron	0.76	mg/L	0.040	05/22/24 16:37	
EPA 6020B	Cobalt	0.059	mg/L	0.0050	05/22/24 16:37	
EPA 6020B	Lithium	0.047	mg/L	0.030	05/22/24 16:37	
EPA 6020B	Molybdenum	0.021	mg/L	0.010	05/22/24 16:37	
SM 2540C-2015	Total Dissolved Solids	639	mg/L	25.0	05/20/24 12:22	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	134	mg/L	5.0	05/21/24 20:02	
SM 2320B-2011	Alkalinity, Total as CaCO3	134	mg/L	5.0	05/21/24 20:02	
EPA 300.0 Rev 2.1 1993	Chloride	12.6	mg/L	1.0	05/21/24 04:48	
EPA 300.0 Rev 2.1 1993	Fluoride	0.35	mg/L	0.10	05/21/24 04:48	
EPA 300.0 Rev 2.1 1993	Sulfate	271	mg/L	6.0	05/21/24 11:58	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-AP1-EB-01 Lab ID: 92731696001 Collected: 05/15/24 16:02 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 00:56	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 00:56	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 00:56	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 00:56	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 00:56	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 00:56	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 15:05	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 15:05	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 15:05	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 15:05	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 15:05	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 15:05	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 15:05	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 15:05	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 15:05	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 15:05	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 15:05	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 15:05	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 15:05	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 12:35	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		05/20/24 12:17		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 18:33		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 18:33		
Alkalinity, Total as CaCO3	ND	mg/L	5.0	5.0	1		05/21/24 18:33		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:09	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		05/20/24 01:22	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-AP1-EB-01		Lab ID: 92731696001		Collected: 05/15/24 16:02		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		05/20/24 01:22	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		05/20/24 01:22	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-AP1-EB-02 Lab ID: 92731696002 Collected: 05/15/24 16:20 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:09	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:09	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:09	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:09	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:09	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:09	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	0.0013J	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 15:20	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 15:20	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 15:20	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 15:20	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 15:20	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 15:20	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 15:20	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 15:20	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 15:20	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 15:20	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 15:20	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 15:20	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 15:20	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 12:38	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		05/20/24 12:18		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 18:37		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 18:37		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		05/21/24 18:37		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:19	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		05/20/24 01:37	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-AP1-EB-02		Lab ID: 92731696002		Collected: 05/15/24 16:20		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		05/20/24 01:37	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		05/20/24 01:37	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-AP1-FB-01 Lab ID: 92731696003 Collected: 05/15/24 15:56 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:13	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:13	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:13	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:13	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:13	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:13	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 15:24	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 15:24	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 15:24	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 15:24	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 15:24	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 15:24	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 15:24	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 15:24	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 15:24	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 15:24	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 15:24	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 15:24	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 15:24	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 12:48	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		05/20/24 12:18		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 18:41		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 18:41		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		05/21/24 18:41		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:10	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		06/12/24 13:26	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-AP1-FB-01		Lab ID: 92731696003		Collected: 05/15/24 15:56		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		06/12/24 13:26	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		06/12/24 13:26	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-AP1-FB-02 Lab ID: 92731696004 Collected: 05/15/24 17:19 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:17	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:17	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:17	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:17	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:17	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:17	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 15:28	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 15:28	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 15:28	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 15:28	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 15:28	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 15:28	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 15:28	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 15:28	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 15:28	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 15:28	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 15:28	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 15:28	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 15:28	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 12:56	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		05/20/24 12:18		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 18:44		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 18:44		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		05/21/24 18:44		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:11	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		05/20/24 02:56	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-AP1-FB-02		Lab ID: 92731696004		Collected: 05/15/24 17:19		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		05/20/24 02:56	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		05/20/24 02:56	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-AP1-FD-01 Lab ID: 92731696005 Collected: 05/15/24 00:00 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.20	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:21	7439-89-6	
Manganese	0.70	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:21	7439-96-5	
Potassium	6.5	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:21	7440-09-7	
Sodium	8.9	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:21	7440-23-5	
Calcium	103	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:21	7440-70-2	
Magnesium	13.8	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:21	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 15:31	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 15:31	7440-38-2	
Barium	0.053	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 15:31	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 15:31	7440-41-7	
Boron	1.5	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 15:31	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 15:31	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 15:31	7440-47-3	
Cobalt	0.0016J	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 15:31	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 15:31	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 15:31	7439-93-2	
Molybdenum	0.090	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 15:31	7439-98-7	
Selenium	0.0011J	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 15:31	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 15:31	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 12:59	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	528	mg/L	25.0	25.0	1		05/20/24 12:18		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	131	mg/L	5.0	5.0	1		05/21/24 18:48		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 18:48		
Alkalinity, Total as CaCO ₃	131	mg/L	5.0	5.0	1		05/21/24 18:48		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:12	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	49.1	mg/L	1.0	0.60	1		06/12/24 13:41	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-AP1-FD-01		Lab ID: 92731696005		Collected: 05/15/24 00:00		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.19	mg/L	0.10	0.050	1		06/12/24 13:41	16984-48-8	
Sulfate	149	mg/L	3.0	1.5	3		06/12/24 14:39	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92731696

Sample: HAM-AP1-FD-02 Lab ID: 92731696006 Collected: 05/15/24 00:00 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	7.9	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:24	7439-89-6	
Manganese	4.6	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:24	7439-96-5	
Potassium	4.8	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:24	7440-09-7	
Sodium	6.9	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:24	7440-23-5	
Calcium	103	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:24	7440-70-2	
Magnesium	12.8	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:24	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 15:45	7440-36-0	
Arsenic	0.19	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 15:45	7440-38-2	
Barium	0.042	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 15:45	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 15:45	7440-41-7	
Boron	0.59	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 15:45	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 15:45	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 15:45	7440-47-3	
Cobalt	0.031	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 15:45	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 15:45	7439-92-1	
Lithium	0.044	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 15:45	7439-93-2	
Molybdenum	0.014	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 15:45	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 15:45	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 15:45	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:01	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	491	mg/L	25.0	25.0	1		05/20/24 12:18		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	138	mg/L	5.0	5.0	1		05/21/24 19:06		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 19:06		
Alkalinity, Total as CaCO3	138	mg/L	5.0	5.0	1		05/21/24 19:06		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:12	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	10.1	mg/L	1.0	0.60	1		05/20/24 10:17	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-AP1-FD-02		Lab ID: 92731696006		Collected: 05/15/24 00:00		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.26	mg/L	0.10	0.050	1		05/20/24 10:17	16984-48-8	
Sulfate	189	mg/L	4.0	2.0	4		05/20/24 20:43	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-INW-03 Lab ID: 92731696007 Collected: 05/14/24 14:08 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Sodium	12.4	mg/L	1.0	0.58	1	05/18/24 14:09	05/24/24 11:34	7440-23-5	
Iron	0.11	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 02:19	7439-89-6	
Manganese	0.45	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 02:19	7439-96-5	
Potassium	13.8	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 02:19	7440-09-7	
Calcium	127	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 02:19	7440-70-2	
Magnesium	17.1	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 02:19	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 16:41	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 16:41	7440-38-2	
Barium	0.075	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 16:41	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 16:41	7440-41-7	
Boron	1.5	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 16:41	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 16:41	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 16:41	7440-47-3	
Cobalt	0.00070J	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 16:41	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 16:41	7439-92-1	
Lithium	0.0050J	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 16:41	7439-93-2	
Molybdenum	0.082	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 16:41	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 16:41	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 16:41	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:04	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	564	mg/L	25.0	25.0	1		05/20/24 12:16		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	175	mg/L	5.0	5.0	1		05/21/24 16:31		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 16:31		
Alkalinity, Total as CaCO3	175	mg/L	5.0	5.0	1		05/21/24 16:31		M1
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/20/24 23:45	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	56.9	mg/L	1.0	0.60	1		05/21/24 00:39	16887-00-6	M1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-INW-03		Lab ID: 92731696007		Collected: 05/14/24 14:08		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.20	mg/L	0.10	0.050	1		05/21/24 00:39	16984-48-8	
Sulfate	178	mg/L	4.0	2.0	4		05/21/24 08:01	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-INW-04 Lab ID: 92731696008 Collected: 05/15/24 14:20 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	8.4	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:35	7439-89-6	
Manganese	4.4	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:35	7439-96-5	
Potassium	4.8	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:35	7440-09-7	
Sodium	7.0	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:35	7440-23-5	
Calcium	107	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:35	7440-70-2	
Magnesium	13.1	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:35	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 15:49	7440-36-0	
Arsenic	0.19	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 15:49	7440-38-2	
Barium	0.043	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 15:49	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 15:49	7440-41-7	
Boron	0.59	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 15:49	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 15:49	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 15:49	7440-47-3	
Cobalt	0.031	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 15:49	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 15:49	7439-92-1	
Lithium	0.043	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 15:49	7439-93-2	
Molybdenum	0.015	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 15:49	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 15:49	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 15:49	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:07	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	483	mg/L	25.0	25.0	1		05/20/24 12:19		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	133	mg/L	5.0	5.0	1		05/21/24 19:16		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		05/21/24 19:16		
Alkalinity, Total as CaCO ₃	133	mg/L	5.0	5.0	1		05/21/24 19:16		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:13	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	9.9	mg/L	1.0	0.60	1		05/21/24 01:48	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-INW-04		Lab ID: 92731696008		Collected: 05/15/24 14:20		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.28	mg/L	0.10	0.050	1		05/21/24 01:48	16984-48-8	
Sulfate	187	mg/L	4.0	2.0	4		05/21/24 08:42	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-INW-05		Lab ID: 92731696009		Collected: 05/15/24 11:18		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	16.9	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:38	7439-89-6	
Manganese	3.3	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:38	7439-96-5	
Potassium	4.7	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:38	7440-09-7	
Sodium	6.7	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:38	7440-23-5	
Calcium	101	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:38	7440-70-2	
Magnesium	11.8	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:38	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 15:53	7440-36-0	
Arsenic	0.23	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 15:53	7440-38-2	
Barium	0.033	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 15:53	7440-39-3	
Beryllium	0.00012J	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 15:53	7440-41-7	
Boron	0.51	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 15:53	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 15:53	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 15:53	7440-47-3	
Cobalt	0.026	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 15:53	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 15:53	7439-92-1	
Lithium	0.057	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 15:53	7439-93-2	
Molybdenum	0.0096J	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 15:53	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 15:53	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 15:53	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:09	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	456	mg/L	25.0	25.0	1		05/20/24 12:20		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	123	mg/L	5.0	5.0	1		05/21/24 19:25		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 19:25		
Alkalinity, Total as CaCO3	123	mg/L	5.0	5.0	1		05/21/24 19:25		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:13	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	6.9	mg/L	1.0	0.60	1		05/21/24 02:02	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-INW-05		Lab ID: 92731696009		Collected: 05/15/24 11:18		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.37	mg/L	0.10	0.050	1		05/21/24 02:02	16984-48-8	
Sulfate	181	mg/L	4.0	2.0	4		05/21/24 08:56	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-07 Lab ID: 92731696010 Collected: 05/16/24 12:16 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	15.7	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:41	7439-89-6	
Manganese	3.4	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:41	7439-96-5	
Potassium	4.9	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:41	7440-09-7	
Sodium	7.0	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:41	7440-23-5	
Calcium	96.0	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:41	7440-70-2	
Magnesium	12.1	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:41	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 15:56	7440-36-0	
Arsenic	0.27	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 15:56	7440-38-2	
Barium	0.034	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 15:56	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 15:56	7440-41-7	
Boron	0.50	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 15:56	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 15:56	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 15:56	7440-47-3	
Cobalt	0.052	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 15:56	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 15:56	7439-92-1	
Lithium	0.056	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 15:56	7439-93-2	
Molybdenum	0.0093J	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 15:56	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 15:56	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 15:56	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:12	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	450	mg/L	25.0	25.0	1		05/20/24 12:22		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	116	mg/L	5.0	5.0	1		05/28/24 17:56		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/28/24 17:56		
Alkalinity, Total as CaCO3	116	mg/L	5.0	5.0	1		05/28/24 17:56		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:16	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	10	mg/L	1.0	0.60	1		05/21/24 02:16	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-07		Lab ID: 92731696010		Collected: 05/16/24 12:16		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.31	mg/L	0.10	0.050	1		05/21/24 02:16	16984-48-8	
Sulfate	171	mg/L	4.0	2.0	4		05/21/24 09:10	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-08		Lab ID: 92731696011		Collected: 05/16/24 10:37		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	8.0	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:45	7439-89-6	
Manganese	3.3	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:45	7439-96-5	
Potassium	4.8	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:45	7440-09-7	
Sodium	7.2	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:45	7440-23-5	
Calcium	89.4	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:45	7440-70-2	
Magnesium	11.5	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:45	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 16:00	7440-36-0	
Arsenic	0.23	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 16:00	7440-38-2	
Barium	0.041	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 16:00	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 16:00	7440-41-7	
Boron	0.73	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 16:00	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 16:00	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 16:00	7440-47-3	
Cobalt	0.046	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 16:00	7440-48-4	
Lead	0.0079	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 16:00	7439-92-1	
Lithium	0.010J	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 16:00	7439-93-2	
Molybdenum	0.017	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 16:00	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 16:00	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 16:00	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:14	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	410	mg/L	25.0	25.0	1		05/20/24 12:22		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	104	mg/L	5.0	5.0	1		05/28/24 18:06		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/28/24 18:06		
Alkalinity, Total as CaCO3	104	mg/L	5.0	5.0	1		05/28/24 18:06		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:17	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	16.7	mg/L	1.0	0.60	1		05/21/24 20:59	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-08		Lab ID: 92731696011		Collected: 05/16/24 10:37		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.19	mg/L	0.10	0.050	1		05/21/24 20:59	16984-48-8	
Sulfate	159	mg/L	4.0	2.0	4		05/22/24 07:35	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-09 Lab ID: 92731696012 Collected: 05/14/24 10:40 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.42	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:48	7439-89-6	
Manganese	0.19	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:48	7439-96-5	
Potassium	6.1	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:48	7440-09-7	
Sodium	9.3	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:48	7440-23-5	
Calcium	82.8	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:48	7440-70-2	
Magnesium	23.7	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:48	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 16:04	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 16:04	7440-38-2	
Barium	0.058	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 16:04	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 16:04	7440-41-7	
Boron	1.4	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 16:04	7440-42-8	
Cadmium	0.00015J	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 16:04	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 16:04	7440-47-3	
Cobalt	0.0012J	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 16:04	7440-48-4	
Lead	0.00017J	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 16:04	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 16:04	7439-93-2	
Molybdenum	0.27	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 16:04	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 16:04	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 16:04	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:17	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	436	mg/L	25.0	25.0	1		05/20/24 12:17		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	139	mg/L	5.0	5.0	1		05/21/24 17:10		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 17:10		
Alkalinity, Total as CaCO3	139	mg/L	5.0	5.0	1		05/21/24 17:10		M1
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/20/24 23:46	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	44.4	mg/L	1.0	0.60	1		05/21/24 02:29	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-09		Lab ID: 92731696012		Collected: 05/14/24 10:40		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.37	mg/L	0.10	0.050	1		05/21/24 02:29	16984-48-8	
Sulfate	130	mg/L	3.0	1.5	3		05/21/24 10:07	14808-79-8	M1

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-10 Lab ID: 92731696013 Collected: 05/15/24 11:52 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.24	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:51	7439-89-6	
Manganese	0.74	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:51	7439-96-5	
Potassium	6.7	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:51	7440-09-7	
Sodium	9.2	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:51	7440-23-5	
Calcium	108	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:51	7440-70-2	
Magnesium	14.3	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:51	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 16:07	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 16:07	7440-38-2	
Barium	0.054	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 16:07	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 16:07	7440-41-7	
Boron	1.5	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 16:07	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 16:07	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 16:07	7440-47-3	
Cobalt	0.0016J	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 16:07	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 16:07	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 16:07	7439-93-2	
Molybdenum	0.092	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 16:07	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 16:07	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 16:07	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:25	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	503	mg/L	25.0	25.0	1		05/20/24 12:20		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	132	mg/L	5.0	5.0	1		05/21/24 19:35		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 19:35		
Alkalinity, Total as CaCO3	132	mg/L	5.0	5.0	1		05/21/24 19:35		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:13	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	50.1	mg/L	1.0	0.60	1		05/21/24 03:11	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-10		Lab ID: 92731696013		Collected: 05/15/24 11:52		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.22	mg/L	0.10	0.050	1		05/21/24 03:11	16984-48-8	
Sulfate	146	mg/L	3.0	1.5	3		05/21/24 10:48	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-11 Lab ID: 92731696014 Collected: 05/14/24 15:20 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:55	7439-89-6	
Manganese	0.28	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:55	7439-96-5	
Potassium	6.0	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:55	7440-09-7	
Sodium	8.8	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:55	7440-23-5	
Calcium	90.9	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:55	7440-70-2	
Magnesium	16.2	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:55	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 16:11	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 16:11	7440-38-2	
Barium	0.057	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 16:11	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 16:11	7440-41-7	
Boron	1.6	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 16:11	7440-42-8	
Cadmium	0.00013J	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 16:11	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 16:11	7440-47-3	
Cobalt	0.0016J	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 16:11	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 16:11	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 16:11	7439-93-2	
Molybdenum	0.24	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 16:11	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 16:11	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 16:11	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:28	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	441	mg/L	25.0	25.0	1		05/20/24 12:17		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	125	mg/L	5.0	5.0	1		05/21/24 17:33		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 17:33		
Alkalinity, Total as CaCO3	125	mg/L	5.0	5.0	1		05/21/24 17:33		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/20/24 23:46	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	41.4	mg/L	1.0	0.60	1		05/21/24 03:25	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-11		Lab ID: 92731696014		Collected: 05/14/24 15:20		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.34	mg/L	0.10	0.050	1		05/21/24 03:25	16984-48-8	
Sulfate	122	mg/L	3.0	1.5	3		05/21/24 11:03	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-12 Lab ID: 92731696015 Collected: 05/14/24 12:05 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.33	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 01:59	7439-89-6	
Manganese	1.0	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 01:59	7439-96-5	
Potassium	6.8	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 01:59	7440-09-7	
Sodium	11.8	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 01:59	7440-23-5	
Calcium	99.7	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 01:59	7440-70-2	
Magnesium	16.6	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 01:59	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 16:15	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 16:15	7440-38-2	
Barium	0.069	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 16:15	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 16:15	7440-41-7	
Boron	1.6	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 16:15	7440-42-8	
Cadmium	0.00014J	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 16:15	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 16:15	7440-47-3	
Cobalt	0.0044J	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 16:15	7440-48-4	
Lead	0.00017J	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 16:15	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 16:15	7439-93-2	
Molybdenum	0.085	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 16:15	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 16:15	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 16:15	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:30	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	523	mg/L	25.0	25.0	1		05/20/24 12:17		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	129	mg/L	5.0	5.0	1		05/21/24 17:51		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 17:51		
Alkalinity, Total as CaCO3	129	mg/L	5.0	5.0	1		05/21/24 17:51		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/20/24 23:47	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	50.3	mg/L	1.0	0.60	1		05/21/24 03:38	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-12		Lab ID: 92731696015		Collected: 05/14/24 12:05		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.20	mg/L	0.10	0.050	1		05/21/24 03:38	16984-48-8	
Sulfate	125	mg/L	3.0	1.5	3		05/21/24 11:17	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-13 Lab ID: 92731696016 Collected: 05/15/24 18:45 Received: 05/17/24 12:55 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	15.0	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 02:02	7439-89-6	
Manganese	3.6	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 02:02	7439-96-5	
Potassium	5.0	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 02:02	7440-09-7	
Sodium	7.8	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 02:02	7440-23-5	
Calcium	99.2	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 02:02	7440-70-2	
Magnesium	12.0	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 02:02	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 16:19	7440-36-0	
Arsenic	0.29	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 16:19	7440-38-2	
Barium	0.033	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 16:19	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 16:19	7440-41-7	
Boron	0.52	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 16:19	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 16:19	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 16:19	7440-47-3	
Cobalt	0.024	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 16:19	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 16:19	7439-92-1	
Lithium	0.058	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 16:19	7439-93-2	
Molybdenum	0.0087J	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 16:19	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 16:19	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 16:19	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:33	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	459	mg/L	25.0	25.0	1		05/20/24 12:21		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	111	mg/L	5.0	5.0	1		05/21/24 19:44		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 19:44		
Alkalinity, Total as CaCO3	111	mg/L	5.0	5.0	1		05/21/24 19:44		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:14	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	9.5	mg/L	1.0	0.60	1		05/21/24 04:20	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-13		Lab ID: 92731696016		Collected: 05/15/24 18:45		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.34	mg/L	0.10	0.050	1		05/21/24 04:20	16984-48-8	
Sulfate	190	mg/L	4.0	2.0	4		05/21/24 11:31	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-14		Lab ID: 92731696017		Collected: 05/15/24 18:27		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	14.9	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 02:05	7439-89-6	
Manganese	3.1	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 02:05	7439-96-5	
Potassium	5.0	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 02:05	7440-09-7	
Sodium	6.7	mg/L	1.0	0.58	1	05/18/24 14:09	05/23/24 02:05	7440-23-5	
Calcium	97.4	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 02:05	7440-70-2	
Magnesium	12.7	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 02:05	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 16:33	7440-36-0	
Arsenic	0.21	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 16:33	7440-38-2	
Barium	0.038	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 16:33	7440-39-3	
Beryllium	0.00016J	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 16:33	7440-41-7	
Boron	0.51	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 16:33	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 16:33	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 16:33	7440-47-3	
Cobalt	0.020	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 16:33	7440-48-4	
Lead	0.00046J	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 16:33	7439-92-1	
Lithium	0.051	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 16:33	7439-93-2	
Molybdenum	0.011	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 16:33	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 16:33	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 16:33	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:35	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	461	mg/L	25.0	25.0	1		05/20/24 12:21		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	121	mg/L	5.0	5.0	1		05/21/24 19:53		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 19:53		
Alkalinity, Total as CaCO3	121	mg/L	5.0	5.0	1		05/21/24 19:53		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:14	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	10.5	mg/L	1.0	0.60	1		05/21/24 04:34	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-14		Lab ID: 92731696017		Collected: 05/15/24 18:27		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.26	mg/L	0.10	0.050	1		05/21/24 04:34	16984-48-8	
Sulfate	175	mg/L	4.0	2.0	4		05/21/24 11:44	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-15		Lab ID: 92731696018		Collected: 05/15/24 16:10		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Sodium	8.1	mg/L	1.0	0.58	1	05/18/24 14:09	05/24/24 11:31	7440-23-5	
Iron	9.2	mg/L	0.040	0.025	1	05/18/24 14:09	05/23/24 02:16	7439-89-6	
Manganese	5.7	mg/L	0.040	0.011	1	05/18/24 14:09	05/23/24 02:16	7439-96-5	
Potassium	5.3	mg/L	0.50	0.15	1	05/18/24 14:09	05/23/24 02:16	7440-09-7	
Calcium	141	mg/L	1.0	0.12	1	05/18/24 14:09	05/23/24 02:16	7440-70-2	
Magnesium	16.1	mg/L	0.050	0.012	1	05/18/24 14:09	05/23/24 02:16	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/18/24 14:00	05/22/24 16:37	7440-36-0	
Arsenic	0.39	mg/L	0.0050	0.00084	1	05/18/24 14:00	05/22/24 16:37	7440-38-2	
Barium	0.043	mg/L	0.0050	0.00047	1	05/18/24 14:00	05/22/24 16:37	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/18/24 14:00	05/22/24 16:37	7440-41-7	
Boron	0.76	mg/L	0.040	0.012	1	05/18/24 14:00	05/22/24 16:37	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/18/24 14:00	05/22/24 16:37	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/18/24 14:00	05/22/24 16:37	7440-47-3	
Cobalt	0.059	mg/L	0.0050	0.00032	1	05/18/24 14:00	05/22/24 16:37	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/18/24 14:00	05/22/24 16:37	7439-92-1	
Lithium	0.047	mg/L	0.030	0.0016	1	05/18/24 14:00	05/22/24 16:37	7439-93-2	
Molybdenum	0.021	mg/L	0.010	0.00062	1	05/18/24 14:00	05/22/24 16:37	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/18/24 14:00	05/22/24 16:37	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/18/24 14:00	05/22/24 16:37	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	05/24/24 08:30	05/24/24 13:38	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	639	mg/L	25.0	25.0	1		05/20/24 12:22		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	134	mg/L	5.0	5.0	1		05/21/24 20:02		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		05/21/24 20:02		
Alkalinity, Total as CaCO3	134	mg/L	5.0	5.0	1		05/21/24 20:02		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		05/22/24 05:15	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	12.6	mg/L	1.0	0.60	1		05/21/24 04:48	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92731696

Sample: HAM-PT-15		Lab ID: 92731696018		Collected: 05/15/24 16:10		Received: 05/17/24 12:55		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.35	mg/L	0.10	0.050	1		05/21/24 04:48	16984-48-8	
Sulfate	271	mg/L	6.0	3.0	6		05/21/24 11:58	14808-79-8	

REPORT OF LABORATORY ANALYSIS



QUALITY CONTROL DATA

Project: Hammond AP-1
Pace Project No.: 92731696

QC Batch:	855608	Analysis Method:	EPA 6010D
QC Batch Method:	EPA 3010A	Analysis Description:	6010D ATL
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696010, 92731696011, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018		

METHOD BLANK:	4414794	Matrix:	Water
Associated Lab Samples:	92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696010, 92731696011, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	05/23/24 00:42	
Iron	mg/L	ND	0.040	0.025	05/23/24 00:42	
Magnesium	mg/L	ND	0.050	0.012	05/23/24 00:42	
Manganese	mg/L	ND	0.040	0.011	05/23/24 00:42	
Potassium	mg/L	ND	0.50	0.15	05/23/24 00:42	
Sodium	mg/L	ND	1.0	0.58	05/23/24 00:42	

LABORATORY CONTROL SAMPLE: 4414795

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	1.0	101	80-120	
Iron	mg/L	1	1.0	101	80-120	
Magnesium	mg/L	1	1.0	103	80-120	
Manganese	mg/L	1	0.99	99	80-120	
Potassium	mg/L	1	1.0	103	80-120	
Sodium	mg/L	1	1.0	100	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4414796 4414797

Parameter	Units	92731696001		MSD		MS		MSD		% Rec Limits	Max	
		Result	Spike Conc.	Spike Conc.	Result	Result	% Rec	% Rec			RPD	RPD
Calcium	mg/L	ND	1	1	1.0J	1.0	99	100	75-125			20
Iron	mg/L	ND	1	1	0.99	1.0	99	100	75-125		1	20
Magnesium	mg/L	ND	1	1	1.0	1.0	103	103	75-125		0	20
Manganese	mg/L	ND	1	1	0.99	0.99	99	99	75-125		1	20
Potassium	mg/L	ND	1	1	0.98	1.0	97	99	75-125		2	20
Sodium	mg/L	ND	1	1	1.3	1.3	103	100	75-125		2	20

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1
Pace Project No.: 92731696

QC Batch: 855534 Analysis Method: EPA 6020B
QC Batch Method: EPA 3005A Analysis Description: 6020 MET
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696010, 92731696011, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018

METHOD BLANK: 4414417 Matrix: Water
Associated Lab Samples: 92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696010, 92731696011, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00054	05/22/24 14:58	
Arsenic	mg/L	ND	0.0050	0.00084	05/22/24 14:58	
Barium	mg/L	ND	0.0050	0.00047	05/22/24 14:58	
Beryllium	mg/L	ND	0.00050	0.000094	05/22/24 14:58	
Boron	mg/L	ND	0.040	0.012	05/22/24 14:58	
Cadmium	mg/L	ND	0.00050	0.00010	05/22/24 14:58	
Chromium	mg/L	ND	0.0050	0.0019	05/22/24 14:58	
Cobalt	mg/L	ND	0.0050	0.00032	05/22/24 14:58	
Lead	mg/L	ND	0.0010	0.00016	05/22/24 14:58	
Lithium	mg/L	ND	0.030	0.0016	05/22/24 14:58	
Molybdenum	mg/L	ND	0.010	0.00062	05/22/24 14:58	
Selenium	mg/L	ND	0.0050	0.00096	05/22/24 14:58	
Thallium	mg/L	ND	0.0010	0.00038	05/22/24 14:58	

LABORATORY CONTROL SAMPLE: 4414418

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.11	106	80-120	
Arsenic	mg/L	0.1	0.10	101	80-120	
Barium	mg/L	0.1	0.10	101	80-120	
Beryllium	mg/L	0.1	0.10	104	80-120	
Boron	mg/L	1	1.0	103	80-120	
Cadmium	mg/L	0.1	0.10	103	80-120	
Chromium	mg/L	0.1	0.10	103	80-120	
Cobalt	mg/L	0.1	0.10	101	80-120	
Lead	mg/L	0.1	0.10	104	80-120	
Lithium	mg/L	0.1	0.11	106	80-120	
Molybdenum	mg/L	0.1	0.10	105	80-120	
Selenium	mg/L	0.1	0.10	101	80-120	
Thallium	mg/L	0.1	0.10	100	80-120	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4414419 4414420												
Parameter	Units	92731696001 Result	MS	MSD	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
			Spike Conc.	Spike Conc.								
Antimony	mg/L	ND	0.1	0.1	0.10	0.10	105	103	75-125	1	20	
Arsenic	mg/L	ND	0.1	0.1	0.098	0.099	98	99	75-125	1	20	
Barium	mg/L	ND	0.1	0.1	0.10	0.098	100	98	75-125	2	20	
Beryllium	mg/L	ND	0.1	0.1	0.10	0.10	102	102	75-125	0	20	
Boron	mg/L	ND	1	1	1.0	1.0	101	100	75-125	1	20	
Cadmium	mg/L	ND	0.1	0.1	0.10	0.10	100	100	75-125	0	20	
Chromium	mg/L	ND	0.1	0.1	0.099	0.098	99	98	75-125	1	20	
Cobalt	mg/L	ND	0.1	0.1	0.098	0.099	98	99	75-125	1	20	
Lead	mg/L	ND	0.1	0.1	0.10	0.10	100	101	75-125	1	20	
Lithium	mg/L	ND	0.1	0.1	0.10	0.10	104	104	75-125	0	20	
Molybdenum	mg/L	ND	0.1	0.1	0.10	0.10	102	101	75-125	1	20	
Selenium	mg/L	ND	0.1	0.1	0.097	0.098	97	98	75-125	1	20	
Thallium	mg/L	ND	0.1	0.1	0.097	0.099	97	98	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch:	856966	Analysis Method:	EPA 7470A
QC Batch Method:	EPA 7470A	Analysis Description:	7470 Mercury
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696010, 92731696011, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018		

METHOD BLANK:	4421300	Matrix:	Water
Associated Lab Samples:	92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696010, 92731696011, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	05/24/24 12:26	

LABORATORY CONTROL SAMPLE:	4421301					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0024	97	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:	4421302	4421303										
Parameter	Units	92731696002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.0025	0.0025	0.0024	0.0024	95	95	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch: 855801 Analysis Method: SM 2540C-2015
QC Batch Method: SM 2540C-2015 Analysis Description: 2540C Total Dissolved Solids
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696010, 92731696011, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018

METHOD BLANK: 4415457 Matrix: Water
Associated Lab Samples: 92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696010, 92731696011, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	05/20/24 12:16	

LABORATORY CONTROL SAMPLE: 4415458

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	396	99	80-120	

SAMPLE DUPLICATE: 4415459

Parameter	Units	92731696007 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	564	575	2	10	

SAMPLE DUPLICATE: 4415460

Parameter	Units	92731696008 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	483	478	1	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch:	856180	Analysis Method:	SM 2320B-2011
QC Batch Method:	SM 2320B-2011	Analysis Description:	2320B Alkalinity
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018		

METHOD BLANK:	4417200	Matrix:	Water
Associated Lab Samples:	92731696001, 92731696002, 92731696003, 92731696004, 92731696005, 92731696006, 92731696007, 92731696008, 92731696009, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	05/21/24 16:14	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/21/24 16:14	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/21/24 16:14	

LABORATORY CONTROL SAMPLE:		4417201				
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.4	103	80-120	

LABORATORY CONTROL SAMPLE:		4417202				
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	49.9	100	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:		4417203		4417204								
Parameter	Units	92731696007 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	175	50	50	214	211	79	72	80-120	2	25	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:		4417205		4417206								
Parameter	Units	92731696012 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	139	50	50	181	177	83	77	80-120	2	25	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch: 857348

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92731696010, 92731696011

METHOD BLANK: 4422747

Matrix: Water

Associated Lab Samples: 92731696010, 92731696011

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	05/28/24 16:34	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/28/24 16:34	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	05/28/24 16:34	

LABORATORY CONTROL SAMPLE: 4422748

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	50.4	101	80-120	

LABORATORY CONTROL SAMPLE: 4422749

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	50.0	100	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4422750 4422751

Parameter	Units	92731615001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	75300 ug/L	50	50	124	125	98	99	80-120	0	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4422752 4422753

Parameter	Units	92732006003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	766	50	50	804	820	76	109	80-120	2	25 M1	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch: 855942

Analysis Method: SM 4500-S2D-2011

QC Batch Method: SM 4500-S2D-2011

Analysis Description: 4500S2D Sulfide Water

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92731696007, 92731696012, 92731696014, 92731696015

METHOD BLANK: 4416179

Matrix: Water

Associated Lab Samples: 92731696007, 92731696012, 92731696014, 92731696015

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	05/20/24 23:35	

LABORATORY CONTROL SAMPLE: 4416180

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.53	105	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4416181 4416182

Parameter	Units	92731245002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.55	0.55	106	106	80-120	0	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch:	856274	Analysis Method:	SM 4500-S2D-2011
QC Batch Method:	SM 4500-S2D-2011	Analysis Description:	4500S2D Sulfide Water
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92731696001, 92731696003, 92731696004, 92731696005, 92731696006, 92731696008, 92731696009, 92731696010, 92731696011, 92731696013, 92731696016, 92731696017, 92731696018		

METHOD BLANK:	4417824	Matrix:	Water
Associated Lab Samples:	92731696001, 92731696003, 92731696004, 92731696005, 92731696006, 92731696008, 92731696009, 92731696010, 92731696011, 92731696013, 92731696016, 92731696017, 92731696018		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	05/22/24 05:06	

LABORATORY CONTROL SAMPLE: 4417825						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.45	89	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:													4417826	4417827			
Parameter	Units	92731245003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual					
Sulfide	mg/L	ND	0.5	0.5	0.49	0.49	94	95	80-120	1	10						

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:												
4417828					4417829							
		92731696001	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Parameter	Units	Result										
Sulfide	mg/L	ND	0.5	0.5	0.48	0.50	96	100	80-120	4	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch: 856275

Analysis Method: SM 4500-S2D-2011

QC Batch Method: SM 4500-S2D-2011

Analysis Description: 4500S2D Sulfide Water

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92731696002

METHOD BLANK: 4417830

Matrix: Water

Associated Lab Samples: 92731696002

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	05/22/24 05:18	

LABORATORY CONTROL SAMPLE: 4417831

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.49	98	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4417832 4417833

Parameter	Units	92731696002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.49	0.48	99	97	80-120	2	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch: 855697 Analysis Method: EPA 300.0 Rev 2.1 1993
QC Batch Method: EPA 300.0 Rev 2.1 1993 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92731696001, 92731696002, 92731696004, 92731696006

METHOD BLANK: 4415009 Matrix: Water
Associated Lab Samples: 92731696001, 92731696002, 92731696004, 92731696006

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	05/20/24 00:22	
Fluoride	mg/L	ND	0.10	0.050	05/20/24 00:22	
Sulfate	mg/L	ND	1.0	0.50	05/20/24 00:22	

LABORATORY CONTROL SAMPLE: 4415010

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	49.3	99	90-110	
Fluoride	mg/L	2.5	2.4	97	90-110	
Sulfate	mg/L	50	49.1	98	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4415011 4415012

Parameter	Units	92731542009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	151	50	50	199	199	95	96	90-110	0	10	
Fluoride	mg/L	0.081J	2.5	2.5	2.7	2.7	104	103	90-110	1	10	
Sulfate	mg/L	3.0	50	50	55.7	55.2	105	104	90-110	1	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4415013 4415014

Parameter	Units	92731735001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	492	50	50	530	529	75	74	90-110	0	10	M1
Fluoride	mg/L	ND	2.5	2.5	ND	ND	0	0	90-110		10	M1
Sulfate	mg/L	16.9	50	50	70.8	69.6	108	105	90-110	2	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch:	855920	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92731696007, 92731696008, 92731696009, 92731696010, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018		

METHOD BLANK:	4416092	Matrix:	Water
Associated Lab Samples:	92731696007, 92731696008, 92731696009, 92731696010, 92731696012, 92731696013, 92731696014, 92731696015, 92731696016, 92731696017, 92731696018		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	05/20/24 20:15	
Fluoride	mg/L	ND	0.10	0.050	05/20/24 20:15	
Sulfate	mg/L	ND	1.0	0.50	05/20/24 20:15	

LABORATORY CONTROL SAMPLE: 4416093						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	53.3	107	90-110	
Fluoride	mg/L	2.5	2.6	103	90-110	
Sulfate	mg/L	50	53.5	107	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4416094 4416095												
Parameter	Units	92731696007 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	56.9	50	50	97.8	98.5	82	83	90-110	1	10	M1
Fluoride	mg/L	0.20	2.5	2.5	2.7	2.7	99	102	90-110	2	10	
Sulfate	mg/L	178	50	50	224	225	93	93	90-110	0	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4416096 4416097												
Parameter	Units	92731696012 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	44.4	50	50	96.7	97.9	105	107	90-110	1	10	
Fluoride	mg/L	0.37	2.5	2.5	2.9	2.9	100	103	90-110	2	10	
Sulfate	mg/L	130	50	50	175	177	89	94	90-110	1	10	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch: 856238

Analysis Method: EPA 300.0 Rev 2.1 1993

QC Batch Method: EPA 300.0 Rev 2.1 1993

Analysis Description: 300.0 IC Anions

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92731696011

METHOD BLANK: 4417658

Matrix: Water

Associated Lab Samples: 92731696011

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	05/21/24 20:18	
Fluoride	mg/L	ND	0.10	0.050	05/21/24 20:18	
Sulfate	mg/L	ND	1.0	0.50	05/21/24 20:18	

LABORATORY CONTROL SAMPLE: 4417659

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	52.0	104	90-110	
Fluoride	mg/L	2.5	2.6	102	90-110	
Sulfate	mg/L	50	52.1	104	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4417660 4417661

Parameter	Units	92732137001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	533	50	50	569	579	73	92	90-110	2	10	M1
Fluoride	mg/L	0.74	2.5	2.5	2.3	2.4	64	66	90-110	2	10	M1
Sulfate	mg/L	357	50	50	398	404	81	95	90-110	2	10	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4417662 4417663

Parameter	Units	92732121002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	4.5	50	50	58.4	60.2	108	111	90-110	3	10	M1
Fluoride	mg/L	0.061J	2.5	2.5	2.6	2.7	101	106	90-110	5	10	
Sulfate	mg/L	88.0	50	50	125	128	74	79	90-110	2	10	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92731696

QC Batch: 860766 Analysis Method: EPA 300.0 Rev 2.1 1993
QC Batch Method: EPA 300.0 Rev 2.1 1993 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92731696003, 92731696005

METHOD BLANK: 4439360 Matrix: Water

Associated Lab Samples: 92731696003, 92731696005

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	06/12/24 12:57	
Fluoride	mg/L	ND	0.10	0.050	06/12/24 12:57	
Sulfate	mg/L	ND	1.0	0.50	06/12/24 12:57	

LABORATORY CONTROL SAMPLE: 4439361

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	51.5	103	90-110	
Fluoride	mg/L	2.5	2.6	105	90-110	
Sulfate	mg/L	50	51.5	103	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4439362 4439363

Parameter	Units	92735940001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	14.2	50	50	64.9	65.3	101	102	90-110	1	10	
Fluoride	mg/L	0.056J	2.5	2.5	2.7	2.7	104	105	90-110	1	10	
Sulfate	mg/L	11.5	50	50	62.8	63.0	103	103	90-110	0	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1
Pace Project No.: 92731696

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92731696

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92731696001	HAM-AP1-EB-01	EPA 3010A	855608	EPA 6010D	855649
92731696002	HAM-AP1-EB-02	EPA 3010A	855608	EPA 6010D	855649
92731696003	HAM-AP1-FB-01	EPA 3010A	855608	EPA 6010D	855649
92731696004	HAM-AP1-FB-02	EPA 3010A	855608	EPA 6010D	855649
92731696005	HAM-AP1-FD-01	EPA 3010A	855608	EPA 6010D	855649
92731696006	HAM-AP1-FD-02	EPA 3010A	855608	EPA 6010D	855649
92731696007	HAM-INW-03	EPA 3010A	855608	EPA 6010D	855649
92731696008	HAM-INW-04	EPA 3010A	855608	EPA 6010D	855649
92731696009	HAM-INW-05	EPA 3010A	855608	EPA 6010D	855649
92731696010	HAM-PT-07	EPA 3010A	855608	EPA 6010D	855649
92731696011	HAM-PT-08	EPA 3010A	855608	EPA 6010D	855649
92731696012	HAM-PT-09	EPA 3010A	855608	EPA 6010D	855649
92731696013	HAM-PT-10	EPA 3010A	855608	EPA 6010D	855649
92731696014	HAM-PT-11	EPA 3010A	855608	EPA 6010D	855649
92731696015	HAM-PT-12	EPA 3010A	855608	EPA 6010D	855649
92731696016	HAM-PT-13	EPA 3010A	855608	EPA 6010D	855649
92731696017	HAM-PT-14	EPA 3010A	855608	EPA 6010D	855649
92731696018	HAM-PT-15	EPA 3010A	855608	EPA 6010D	855649
92731696001	HAM-AP1-EB-01	EPA 3005A	855534	EPA 6020B	855663
92731696002	HAM-AP1-EB-02	EPA 3005A	855534	EPA 6020B	855663
92731696003	HAM-AP1-FB-01	EPA 3005A	855534	EPA 6020B	855663
92731696004	HAM-AP1-FB-02	EPA 3005A	855534	EPA 6020B	855663
92731696005	HAM-AP1-FD-01	EPA 3005A	855534	EPA 6020B	855663
92731696006	HAM-AP1-FD-02	EPA 3005A	855534	EPA 6020B	855663
92731696007	HAM-INW-03	EPA 3005A	855534	EPA 6020B	855663
92731696008	HAM-INW-04	EPA 3005A	855534	EPA 6020B	855663
92731696009	HAM-INW-05	EPA 3005A	855534	EPA 6020B	855663
92731696010	HAM-PT-07	EPA 3005A	855534	EPA 6020B	855663
92731696011	HAM-PT-08	EPA 3005A	855534	EPA 6020B	855663
92731696012	HAM-PT-09	EPA 3005A	855534	EPA 6020B	855663
92731696013	HAM-PT-10	EPA 3005A	855534	EPA 6020B	855663
92731696014	HAM-PT-11	EPA 3005A	855534	EPA 6020B	855663
92731696015	HAM-PT-12	EPA 3005A	855534	EPA 6020B	855663
92731696016	HAM-PT-13	EPA 3005A	855534	EPA 6020B	855663
92731696017	HAM-PT-14	EPA 3005A	855534	EPA 6020B	855663
92731696018	HAM-PT-15	EPA 3005A	855534	EPA 6020B	855663
92731696001	HAM-AP1-EB-01	EPA 7470A	856966	EPA 7470A	856985
92731696002	HAM-AP1-EB-02	EPA 7470A	856966	EPA 7470A	856985
92731696003	HAM-AP1-FB-01	EPA 7470A	856966	EPA 7470A	856985
92731696004	HAM-AP1-FB-02	EPA 7470A	856966	EPA 7470A	856985
92731696005	HAM-AP1-FD-01	EPA 7470A	856966	EPA 7470A	856985
92731696006	HAM-AP1-FD-02	EPA 7470A	856966	EPA 7470A	856985
92731696007	HAM-INW-03	EPA 7470A	856966	EPA 7470A	856985
92731696008	HAM-INW-04	EPA 7470A	856966	EPA 7470A	856985
92731696009	HAM-INW-05	EPA 7470A	856966	EPA 7470A	856985
92731696010	HAM-PT-07	EPA 7470A	856966	EPA 7470A	856985
92731696011	HAM-PT-08	EPA 7470A	856966	EPA 7470A	856985
92731696012	HAM-PT-09	EPA 7470A	856966	EPA 7470A	856985

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92731696

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92731696013	HAM-PT-10	EPA 7470A	856966	EPA 7470A	856985
92731696014	HAM-PT-11	EPA 7470A	856966	EPA 7470A	856985
92731696015	HAM-PT-12	EPA 7470A	856966	EPA 7470A	856985
92731696016	HAM-PT-13	EPA 7470A	856966	EPA 7470A	856985
92731696017	HAM-PT-14	EPA 7470A	856966	EPA 7470A	856985
92731696018	HAM-PT-15	EPA 7470A	856966	EPA 7470A	856985
92731696001	HAM-AP1-EB-01	SM 2540C-2015	855801		
92731696002	HAM-AP1-EB-02	SM 2540C-2015	855801		
92731696003	HAM-AP1-FB-01	SM 2540C-2015	855801		
92731696004	HAM-AP1-FB-02	SM 2540C-2015	855801		
92731696005	HAM-AP1-FD-01	SM 2540C-2015	855801		
92731696006	HAM-AP1-FD-02	SM 2540C-2015	855801		
92731696007	HAM-INW-03	SM 2540C-2015	855801		
92731696008	HAM-INW-04	SM 2540C-2015	855801		
92731696009	HAM-INW-05	SM 2540C-2015	855801		
92731696010	HAM-PT-07	SM 2540C-2015	855801		
92731696011	HAM-PT-08	SM 2540C-2015	855801		
92731696012	HAM-PT-09	SM 2540C-2015	855801		
92731696013	HAM-PT-10	SM 2540C-2015	855801		
92731696014	HAM-PT-11	SM 2540C-2015	855801		
92731696015	HAM-PT-12	SM 2540C-2015	855801		
92731696016	HAM-PT-13	SM 2540C-2015	855801		
92731696017	HAM-PT-14	SM 2540C-2015	855801		
92731696018	HAM-PT-15	SM 2540C-2015	855801		
92731696001	HAM-AP1-EB-01	SM 2320B-2011	856180		
92731696002	HAM-AP1-EB-02	SM 2320B-2011	856180		
92731696003	HAM-AP1-FB-01	SM 2320B-2011	856180		
92731696004	HAM-AP1-FB-02	SM 2320B-2011	856180		
92731696005	HAM-AP1-FD-01	SM 2320B-2011	856180		
92731696006	HAM-AP1-FD-02	SM 2320B-2011	856180		
92731696007	HAM-INW-03	SM 2320B-2011	856180		
92731696008	HAM-INW-04	SM 2320B-2011	856180		
92731696009	HAM-INW-05	SM 2320B-2011	856180		
92731696010	HAM-PT-07	SM 2320B-2011	857348		
92731696011	HAM-PT-08	SM 2320B-2011	857348		
92731696012	HAM-PT-09	SM 2320B-2011	856180		
92731696013	HAM-PT-10	SM 2320B-2011	856180		
92731696014	HAM-PT-11	SM 2320B-2011	856180		
92731696015	HAM-PT-12	SM 2320B-2011	856180		
92731696016	HAM-PT-13	SM 2320B-2011	856180		
92731696017	HAM-PT-14	SM 2320B-2011	856180		
92731696018	HAM-PT-15	SM 2320B-2011	856180		
92731696001	HAM-AP1-EB-01	SM 4500-S2D-2011	856274		
92731696002	HAM-AP1-EB-02	SM 4500-S2D-2011	856275		
92731696003	HAM-AP1-FB-01	SM 4500-S2D-2011	856274		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92731696

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92731696004	HAM-AP1-FB-02	SM 4500-S2D-2011	856274		
92731696005	HAM-AP1-FD-01	SM 4500-S2D-2011	856274		
92731696006	HAM-AP1-FD-02	SM 4500-S2D-2011	856274		
92731696007	HAM-INW-03	SM 4500-S2D-2011	855942		
92731696008	HAM-INW-04	SM 4500-S2D-2011	856274		
92731696009	HAM-INW-05	SM 4500-S2D-2011	856274		
92731696010	HAM-PT-07	SM 4500-S2D-2011	856274		
92731696011	HAM-PT-08	SM 4500-S2D-2011	856274		
92731696012	HAM-PT-09	SM 4500-S2D-2011	855942		
92731696013	HAM-PT-10	SM 4500-S2D-2011	856274		
92731696014	HAM-PT-11	SM 4500-S2D-2011	855942		
92731696015	HAM-PT-12	SM 4500-S2D-2011	855942		
92731696016	HAM-PT-13	SM 4500-S2D-2011	856274		
92731696017	HAM-PT-14	SM 4500-S2D-2011	856274		
92731696018	HAM-PT-15	SM 4500-S2D-2011	856274		
92731696001	HAM-AP1-EB-01	EPA 300.0 Rev 2.1 1993	855697		
92731696002	HAM-AP1-EB-02	EPA 300.0 Rev 2.1 1993	855697		
92731696003	HAM-AP1-FB-01	EPA 300.0 Rev 2.1 1993	860766		
92731696004	HAM-AP1-FB-02	EPA 300.0 Rev 2.1 1993	855697		
92731696005	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	860766		
92731696006	HAM-AP1-FD-02	EPA 300.0 Rev 2.1 1993	855697		
92731696007	HAM-INW-03	EPA 300.0 Rev 2.1 1993	855920		
92731696008	HAM-INW-04	EPA 300.0 Rev 2.1 1993	855920		
92731696009	HAM-INW-05	EPA 300.0 Rev 2.1 1993	855920		
92731696010	HAM-PT-07	EPA 300.0 Rev 2.1 1993	855920		
92731696011	HAM-PT-08	EPA 300.0 Rev 2.1 1993	856238		
92731696012	HAM-PT-09	EPA 300.0 Rev 2.1 1993	855920		
92731696013	HAM-PT-10	EPA 300.0 Rev 2.1 1993	855920		
92731696014	HAM-PT-11	EPA 300.0 Rev 2.1 1993	855920		
92731696015	HAM-PT-12	EPA 300.0 Rev 2.1 1993	855920		
92731696016	HAM-PT-13	EPA 300.0 Rev 2.1 1993	855920		
92731696017	HAM-PT-14	EPA 300.0 Rev 2.1 1993	855920		
92731696018	HAM-PT-15	EPA 300.0 Rev 2.1 1993	855920		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



DC#_Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

Project #

WO#: 92731696



Courier:

☐ Commercial☐ Fed Ex☐ UPS☐ USPS☐ Other:☐ Client

Custody Seal Present?

☒ Yes☐ No

Seals Intact?

☒ Yes☐ No☐ N/A

Date/Initials Person Examining Contents: 3/17/24 MC

Packing Material:

☒ Bubble Wrap☐ Bubble Bags☐ None☐ Other

Biological Tissue Frozen?

☐ Yes☐ No☒ N/A

Thermometer:

☒ IR Gun ID:

734

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

3.1

Correction Factor:

Add/Subtract (°C)

0.0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

3.1

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

Comments/Discrepancy:

Chain of Custody Present?

☒ Yes☐ No☐ N/A

1.

Samples Arrived within Hold Time?

☒ Yes☐ No☐ N/A

2.

Short Hold Time Analysis (<72 hr.)?

☐ Yes☒ No☐ N/A

3.

Rush Turn Around Time Requested?

☐ Yes☒ No☐ N/A

4.

Sufficient Volume?

☒ Yes☐ No☐ N/A

5.

Correct Containers Used?

☒ Yes☐ No☐ N/A

6.

-Pace Containers Used?

☒ Yes☐ No☐ N/A

7.

Containers Intact?

☒ Yes☐ No☐ N/A

8.

Dissolved analysis: Samples Field Filtered?

☐ Yes☒ No☐ N/A

9.

Sample Labels Match COC?

☒ Yes☐ No☐ N/A

-Includes Date/Time/ID/Analysis Matrix: 4

Headspace in VOA Vials (>5-6mm)?

☐ Yes☐ No☒ N/A

10.

Trip Blank Present?

☐ Yes☐ No☒ N/A

11.

Trip Blank Custody Seals Present?

☐ Yes☐ No☒ N/AField Data Required? ☐ Yes ☐ No

COMMENTS/SAMPLE DISCREPANCY

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:

Qualtrax ID: 69614

Page 1 of 2



DC#_Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.
 (exceptions: VOA, Coliform, TOC, Oil and Grease, DRB/BD15 (water) DOC, UHg)

Project #

**Bottom half of box is to list number of bottles


***Check all unpreserved Nitrates for chlorine

Item #	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP4U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic 2N Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WG9U-Wide-mouthed Glass Jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG94-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KG7U-50 mL Plastic Unpreserved (N/A)	V/DK 13 vials per Kit-VPM/Gas kit (N/A)	SP3T-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)		BP3R-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AG6U-100 mL Amber Unpreserved (N/A) (Cl-)	VS9U-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)	
1		2	1																										
2		2	1																										
3		2	1																										
4		2	1																										
5		2	1																										
6		2	1																										
7																													
8																													
9																													
10																													
11																													
12																													

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers).

Section C
Extra Information


REGULATORY AGENCY

TEST	UNIONED WALLS	CHIMNEY WALL
1ST	2000	2000

STATE	_____
-------	-------

[illegible]

SAMPLE NAME AND SOLVENTS				
PRINT NAME of SAMPLE:	Anthony Soward, Jamo Nevegerne	1	Goodman Consultants, Inc.	
SIGNATURE of SAMPLE:	<i>Anthony Soward</i>	DATE SIGNED	05/16/24	
		TEMPERATURE (°C)		
		RECEIVED ON (YY)		
		CUSTODY SEALED COVER (YY)		
		BARCODE INFO (YY)		



CHAIN-OF-CUSTODY / Analytical Request Document

the water-purification is a slow, continuous, and steady-state process on a continuous basis.

[illegible]



DC#_Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐

Sample Condition
Upon Receipt

Client Name:

Project #:

Courier:
☐ Commercial

☐ Fed Ex
☒ Pace

☐ UPS

☐ USPS
☐ Other:

☐ Client

Custody Seal Present?

☒ Yes

☐ No

Seals Intact?

☒ Yes

☐ No

☐ N/A

Date/Initials Person Examining Contents: 5/17/24 JAC

Packing Material:

☒ Bubble Wrap

☐ Bubble Bags

☐ None

☐ Other

Biological Tissue Frozen?

☐ Yes

☐ No

☒ N/A

Thermometer:

☐ IR Gun ID: 732

Type of Ice:

☒ Wet

☐ Blue

☐ None

Cooler Temp:

3.1

Correction Factor:

Add/Subtract (°C)

0.6

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

3.1

USDA Regulated Soil (☐ N/A, water sample)

Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ No

Did samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

		Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4.
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A	7.
Containers Intact?	☒ Yes ☐ No ☐ N/A	8.
Dissolved analysis: Samples Field Filtered?	☐ Yes ☒ No ☐ N/A	9.
Sample Labels Match COC?	☒ Yes ☐ No ☐ N/A	
-Includes Date/Time/ID/Analysis Matrix:		
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☐ N/A	10.
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☐ N/A	

Field Data Required? ☐ Yes ☐ No

COMMENTS/SAMPLE DISCREPANCY

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:

Qualtrax ID: 69614

Page 1 of 2



DC#_Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Project #

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/BOD5 (water) DOC, LUH

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Item #	BP4U-125 mL Plastic Unpreserved (N/A) (CI-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP65-125 mL Plastic H2SO4 (pH < 2) (CI-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP42-125 mL Plastic Zn Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (CI-)	WG7U-Wide-mouthed Glass jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (CI-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (CI-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG94-40 mL Amber NH4Cl (N/A)(CI-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KD7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit)-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)		BP3R-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AG9U-100 mL Amber Unpreserved (N/A) (CI-)	VS6U-20 mL Solubilization vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)	
1		2	1																										
2		2	1																										
3		2	1																										
4		2	1																										
5		2	1																										
6		2	1																										
7		2	1																										
8		2	1																										
9		2	1																										
10		2	1																										
11		2	1																										
12		2	1																										

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DEAR Certification Office (Out of hold, incorrect preservative, out of temp, incorrect containers).



June 17, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1
Pace Project No.: 92733822

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on May 31, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Peachtree Corners, GA

Revision 1: EB/FB/FD sample ID's amended.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Anthony Szwast, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1

Pace Project No.: 92733822

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1

Pace Project No.: 92733822

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92733822001	HAM-INW-03	Water	05/29/24 14:14	05/31/24 12:05
92733822002	HAM-PT-09	Water	05/30/24 11:52	05/31/24 12:05
92733822003	HAM-PT-10	Water	05/30/24 14:40	05/31/24 12:05
92733822004	HAM-PT-11	Water	05/29/24 16:43	05/31/24 12:05
92733822005	HAM-PT-12	Water	05/29/24 12:08	05/31/24 12:05
92733822006	HAM-AP1-EB-01	Water	05/30/24 16:59	05/31/24 12:05
92733822007	HAM-AP1-FB-01	Water	05/30/24 16:52	05/31/24 12:05
92733822008	HAM-AP1-FD-01	Water	05/30/24 00:00	05/31/24 12:05

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92733822

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92733822001	HAM-INW-03	EPA 6010D	AJM	6
		EPA 6020B	MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92733822002	HAM-PT-09	EPA 6010D	AJM	6
		EPA 6020B	MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92733822003	HAM-PT-10	EPA 6010D	AJM	6
		EPA 6020B	MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92733822004	HAM-PT-11	EPA 6010D	AJM	6
		EPA 6020B	MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92733822005	HAM-PT-12	EPA 6010D	AJM	6
		EPA 6020B	MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92733822006	HAM-AP1-EB-01	EPA 6010D	AJM	6
		EPA 6020B	MT1	13

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92733822

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92733822007	HAM-AP1-FB-01	EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	AJM	6
		EPA 6020B	MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	AJM	6
		EPA 6020B	MT1	13
92733822008	HAM-AP1-FD-01	EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	AJM	6
		EPA 6020B	MT1	13

PASI-A = Pace Analytical Services - Asheville

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92733822

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92733822001	HAM-INW-03					
EPA 6010D	Iron	0.14	mg/L	0.040	06/03/24 20:27	
EPA 6010D	Manganese	1.2	mg/L	0.040	06/03/24 20:27	
EPA 6010D	Potassium	6.1	mg/L	0.50	06/03/24 20:27	
EPA 6010D	Sodium	11.1	mg/L	1.0	06/03/24 20:27	
EPA 6010D	Calcium	144	mg/L	1.0	06/03/24 20:27	
EPA 6010D	Magnesium	16.5	mg/L	0.050	06/03/24 20:27	
EPA 6020B	Arsenic	0.0022J	mg/L	0.0050	06/04/24 16:51	
EPA 6020B	Barium	0.12	mg/L	0.0050	06/04/24 16:51	
EPA 6020B	Boron	1.5	mg/L	0.040	06/04/24 16:51	
EPA 6020B	Cobalt	0.00087J	mg/L	0.0050	06/04/24 16:51	
EPA 6020B	Lithium	0.0048J	mg/L	0.030	06/04/24 16:51	
EPA 6020B	Molybdenum	0.060	mg/L	0.010	06/04/24 16:51	
EPA 6020B	Selenium	0.0016J	mg/L	0.0050	06/04/24 16:51	
SM 2540C-2015	Total Dissolved Solids	610	mg/L	25.0	06/03/24 12:08	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	176	mg/L	5.0	06/05/24 17:10	
SM 2320B-2011	Alkalinity, Total as CaCO3	176	mg/L	5.0	06/05/24 17:10	
EPA 300.0 Rev 2.1 1993	Chloride	61.6	mg/L	1.0	06/01/24 22:59	
EPA 300.0 Rev 2.1 1993	Fluoride	0.13	mg/L	0.10	06/01/24 22:59	
EPA 300.0 Rev 2.1 1993	Sulfate	187	mg/L	4.0	06/02/24 04:57	
92733822002	HAM-PT-09					
EPA 6010D	Iron	0.24	mg/L	0.040	06/03/24 20:31	
EPA 6010D	Manganese	0.28	mg/L	0.040	06/03/24 20:31	
EPA 6010D	Potassium	6.2	mg/L	0.50	06/03/24 20:31	
EPA 6010D	Sodium	11.5	mg/L	1.0	06/03/24 20:31	
EPA 6010D	Calcium	94.9	mg/L	1.0	06/03/24 20:31	
EPA 6010D	Magnesium	19.9	mg/L	0.050	06/03/24 20:31	
EPA 6020B	Arsenic	0.0022J	mg/L	0.0050	06/04/24 16:55	
EPA 6020B	Barium	0.062	mg/L	0.0050	06/04/24 16:55	
EPA 6020B	Boron	1.5	mg/L	0.040	06/04/24 16:55	
EPA 6020B	Cadmium	0.00010J	mg/L	0.00050	06/04/24 16:55	
EPA 6020B	Cobalt	0.0010J	mg/L	0.0050	06/04/24 16:55	
EPA 6020B	Molybdenum	0.24	mg/L	0.010	06/04/24 16:55	
SM 2540C-2015	Total Dissolved Solids	532	mg/L	25.0	06/03/24 12:09	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	138	mg/L	5.0	06/07/24 15:22	
SM 2320B-2011	Alkalinity, Total as CaCO3	138	mg/L	5.0	06/07/24 15:22	
EPA 300.0 Rev 2.1 1993	Chloride	52.4	mg/L	1.0	06/01/24 23:14	
EPA 300.0 Rev 2.1 1993	Fluoride	0.33	mg/L	0.10	06/01/24 23:14	
EPA 300.0 Rev 2.1 1993	Sulfate	133	mg/L	3.0	06/02/24 05:41	
92733822003	HAM-PT-10					
EPA 6010D	Iron	0.21	mg/L	0.040	06/03/24 20:35	
EPA 6010D	Manganese	0.52	mg/L	0.040	06/03/24 20:35	
EPA 6010D	Potassium	6.6	mg/L	0.50	06/03/24 20:35	
EPA 6010D	Sodium	9.5	mg/L	1.0	06/03/24 20:35	
EPA 6010D	Calcium	95.9	mg/L	1.0	06/03/24 20:35	
EPA 6010D	Magnesium	13.1	mg/L	0.050	06/03/24 20:35	
EPA 6020B	Arsenic	0.0018J	mg/L	0.0050	06/04/24 16:59	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92733822

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92733822003	HAM-PT-10					
EPA 6020B	Barium	0.052	mg/L	0.0050	06/04/24 16:59	
EPA 6020B	Boron	1.4	mg/L	0.040	06/04/24 16:59	
EPA 6020B	Cobalt	0.0014J	mg/L	0.0050	06/04/24 16:59	
EPA 6020B	Molybdenum	0.053	mg/L	0.010	06/04/24 16:59	
SM 2540C-2015	Total Dissolved Solids	495	mg/L	25.0	06/03/24 12:10	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	116	mg/L	5.0	06/07/24 15:31	
SM 2320B-2011	Alkalinity, Total as CaCO3	116	mg/L	5.0	06/07/24 15:31	
EPA 300.0 Rev 2.1 1993	Chloride	53.0	mg/L	1.0	06/01/24 23:57	
EPA 300.0 Rev 2.1 1993	Fluoride	0.17	mg/L	0.10	06/01/24 23:57	
EPA 300.0 Rev 2.1 1993	Sulfate	124	mg/L	3.0	06/02/24 05:55	
92733822004	HAM-PT-11					
EPA 6010D	Iron	0.10	mg/L	0.040	06/03/24 20:39	
EPA 6010D	Manganese	0.27	mg/L	0.040	06/03/24 20:39	
EPA 6010D	Potassium	6.5	mg/L	0.50	06/03/24 20:39	
EPA 6010D	Sodium	9.2	mg/L	1.0	06/03/24 20:39	
EPA 6010D	Calcium	95.7	mg/L	1.0	06/03/24 20:39	
EPA 6010D	Magnesium	16.7	mg/L	0.050	06/03/24 20:39	
EPA 6020B	Arsenic	0.0021J	mg/L	0.0050	06/04/24 17:03	
EPA 6020B	Barium	0.072	mg/L	0.0050	06/04/24 17:03	
EPA 6020B	Boron	1.4	mg/L	0.040	06/04/24 17:03	
EPA 6020B	Cadmium	0.00013J	mg/L	0.00050	06/04/24 17:03	
EPA 6020B	Cobalt	0.0013J	mg/L	0.0050	06/04/24 17:03	
EPA 6020B	Molybdenum	0.17	mg/L	0.010	06/04/24 17:03	
SM 2540C-2015	Total Dissolved Solids	474	mg/L	25.0	06/03/24 12:08	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	143	mg/L	5.0	06/05/24 17:35	
SM 2320B-2011	Alkalinity, Total as CaCO3	143	mg/L	5.0	06/05/24 17:35	
EPA 300.0 Rev 2.1 1993	Chloride	39.4	mg/L	1.0	06/02/24 00:11	
EPA 300.0 Rev 2.1 1993	Fluoride	0.31	mg/L	0.10	06/02/24 00:11	
EPA 300.0 Rev 2.1 1993	Sulfate	118	mg/L	3.0	06/02/24 06:09	
92733822005	HAM-PT-12					
EPA 6010D	Iron	0.032J	mg/L	0.040	06/03/24 20:43	
EPA 6010D	Manganese	0.75	mg/L	0.040	06/03/24 20:43	
EPA 6010D	Potassium	5.7	mg/L	0.50	06/03/24 20:43	
EPA 6010D	Sodium	9.6	mg/L	1.0	06/03/24 20:43	
EPA 6010D	Calcium	91.0	mg/L	1.0	06/03/24 20:43	
EPA 6010D	Magnesium	18.6	mg/L	0.050	06/03/24 20:43	
EPA 6020B	Arsenic	0.0026J	mg/L	0.0050	06/04/24 17:07	
EPA 6020B	Barium	0.069	mg/L	0.0050	06/04/24 17:07	
EPA 6020B	Boron	1.5	mg/L	0.040	06/04/24 17:07	
EPA 6020B	Cadmium	0.00011J	mg/L	0.00050	06/04/24 17:07	
EPA 6020B	Cobalt	0.0021J	mg/L	0.0050	06/04/24 17:07	
EPA 6020B	Molybdenum	0.22	mg/L	0.010	06/04/24 17:07	
EPA 6020B	Selenium	0.0015J	mg/L	0.0050	06/04/24 17:07	
SM 2540C-2015	Total Dissolved Solids	488	mg/L	25.0	06/03/24 12:08	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	136	mg/L	5.0	06/07/24 13:55	
SM 2320B-2011	Alkalinity, Total as CaCO3	136	mg/L	5.0	06/07/24 13:55	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92733822

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92733822005	HAM-PT-12					
EPA 300.0 Rev 2.1 1993	Chloride	48.0	mg/L	1.0	06/03/24 00:51	
EPA 300.0 Rev 2.1 1993	Fluoride	0.31	mg/L	0.10	06/03/24 00:51	
EPA 300.0 Rev 2.1 1993	Sulfate	131	mg/L	3.0	06/03/24 03:15	
92733822006	HAM-AP1-EB-01					
EPA 6010D	Calcium	0.13J	mg/L	1.0	06/03/24 20:47	
EPA 6010D	Magnesium	0.030J	mg/L	0.050	06/03/24 20:47	
EPA 6020B	Arsenic	0.0044J	mg/L	0.0050	06/04/24 17:16	
92733822007	HAM-AP1-FB-01					
EPA 6020B	Arsenic	0.0040J	mg/L	0.0050	06/04/24 17:20	
EPA 6020B	Selenium	0.0011J	mg/L	0.0050	06/04/24 17:20	
92733822008	HAM-AP1-FD-01					
EPA 6010D	Iron	0.26	mg/L	0.040	06/03/24 21:41	
EPA 6010D	Manganese	0.27	mg/L	0.040	06/03/24 21:41	
EPA 6010D	Calcium	97.3	mg/L	1.0	06/03/24 21:41	
EPA 6010D	Magnesium	20.9	mg/L	0.050	06/03/24 21:41	
EPA 6010D	Potassium	6.4	mg/L	0.50	06/04/24 14:10	
EPA 6010D	Sodium	12.0	mg/L	1.0	06/04/24 14:10	
EPA 6020B	Arsenic	0.0025J	mg/L	0.0050	06/04/24 17:24	
EPA 6020B	Barium	0.062	mg/L	0.0050	06/04/24 17:24	
EPA 6020B	Boron	1.4	mg/L	0.040	06/04/24 17:24	
EPA 6020B	Cadmium	0.00014J	mg/L	0.00050	06/04/24 17:24	
EPA 6020B	Cobalt	0.0010J	mg/L	0.0050	06/04/24 17:24	
EPA 6020B	Molybdenum	0.24	mg/L	0.010	06/04/24 17:24	
EPA 6020B	Selenium	0.0012J	mg/L	0.0050	06/04/24 17:24	
SM 2540C-2015	Total Dissolved Solids	500	mg/L	25.0	06/03/24 12:10	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	140	mg/L	5.0	06/07/24 15:48	
SM 2320B-2011	Alkalinity, Total as CaCO3	140	mg/L	5.0	06/07/24 15:48	
EPA 300.0 Rev 2.1 1993	Chloride	51.3	mg/L	1.0	06/03/24 01:06	
EPA 300.0 Rev 2.1 1993	Fluoride	0.32	mg/L	0.10	06/03/24 01:06	
EPA 300.0 Rev 2.1 1993	Sulfate	129	mg/L	3.0	06/03/24 03:29	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-INW-03 Lab ID: 92733822001 Collected: 05/29/24 14:14 Received: 05/31/24 12:05 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.14	mg/L	0.040	0.025	1	05/31/24 17:19	06/03/24 20:27	7439-89-6	
Manganese	1.2	mg/L	0.040	0.011	1	05/31/24 17:19	06/03/24 20:27	7439-96-5	
Potassium	6.1	mg/L	0.50	0.15	1	05/31/24 17:19	06/03/24 20:27	7440-09-7	
Sodium	11.1	mg/L	1.0	0.58	1	05/31/24 17:19	06/03/24 20:27	7440-23-5	
Calcium	144	mg/L	1.0	0.12	1	05/31/24 17:19	06/03/24 20:27	7440-70-2	
Magnesium	16.5	mg/L	0.050	0.012	1	05/31/24 17:19	06/03/24 20:27	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/31/24 16:57	06/04/24 16:51	7440-36-0	
Arsenic	0.0022J	mg/L	0.0050	0.00084	1	05/31/24 16:57	06/04/24 16:51	7440-38-2	
Barium	0.12	mg/L	0.0050	0.00047	1	05/31/24 16:57	06/04/24 16:51	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/31/24 16:57	06/04/24 16:51	7440-41-7	
Boron	1.5	mg/L	0.040	0.012	1	05/31/24 16:57	06/04/24 16:51	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/31/24 16:57	06/04/24 16:51	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/31/24 16:57	06/04/24 16:51	7440-47-3	
Cobalt	0.00087J	mg/L	0.0050	0.00032	1	05/31/24 16:57	06/04/24 16:51	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/31/24 16:57	06/04/24 16:51	7439-92-1	
Lithium	0.0048J	mg/L	0.030	0.0016	1	05/31/24 16:57	06/04/24 16:51	7439-93-2	
Molybdenum	0.060	mg/L	0.010	0.00062	1	05/31/24 16:57	06/04/24 16:51	7439-98-7	
Selenium	0.0016J	mg/L	0.0050	0.00096	1	05/31/24 16:57	06/04/24 16:51	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/31/24 16:57	06/04/24 16:51	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	06/10/24 17:00	06/11/24 09:10	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	610	mg/L	25.0	25.0	1		06/03/24 12:08		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	176	mg/L	5.0	5.0	1		06/05/24 17:10		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		06/05/24 17:10		
Alkalinity, Total as CaCO3	176	mg/L	5.0	5.0	1		06/05/24 17:10		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		06/02/24 02:01	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	61.6	mg/L	1.0	0.60	1		06/01/24 22:59	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-INW-03		Lab ID: 92733822001		Collected: 05/29/24 14:14		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.13	mg/L	0.10	0.050	1		06/01/24 22:59	16984-48-8	
Sulfate	187	mg/L	4.0	2.0	4		06/02/24 04:57	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-PT-09 Lab ID: 92733822002 Collected: 05/30/24 11:52 Received: 05/31/24 12:05 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.24	mg/L	0.040	0.025	1	05/31/24 17:19	06/03/24 20:31	7439-89-6	
Manganese	0.28	mg/L	0.040	0.011	1	05/31/24 17:19	06/03/24 20:31	7439-96-5	
Potassium	6.2	mg/L	0.50	0.15	1	05/31/24 17:19	06/03/24 20:31	7440-09-7	
Sodium	11.5	mg/L	1.0	0.58	1	05/31/24 17:19	06/03/24 20:31	7440-23-5	
Calcium	94.9	mg/L	1.0	0.12	1	05/31/24 17:19	06/03/24 20:31	7440-70-2	
Magnesium	19.9	mg/L	0.050	0.012	1	05/31/24 17:19	06/03/24 20:31	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/31/24 16:57	06/04/24 16:55	7440-36-0	
Arsenic	0.0022J	mg/L	0.0050	0.00084	1	05/31/24 16:57	06/04/24 16:55	7440-38-2	
Barium	0.062	mg/L	0.0050	0.00047	1	05/31/24 16:57	06/04/24 16:55	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/31/24 16:57	06/04/24 16:55	7440-41-7	
Boron	1.5	mg/L	0.040	0.012	1	05/31/24 16:57	06/04/24 16:55	7440-42-8	
Cadmium	0.00010J	mg/L	0.00050	0.00010	1	05/31/24 16:57	06/04/24 16:55	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/31/24 16:57	06/04/24 16:55	7440-47-3	
Cobalt	0.0010J	mg/L	0.0050	0.00032	1	05/31/24 16:57	06/04/24 16:55	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/31/24 16:57	06/04/24 16:55	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/31/24 16:57	06/04/24 16:55	7439-93-2	
Molybdenum	0.24	mg/L	0.010	0.00062	1	05/31/24 16:57	06/04/24 16:55	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/31/24 16:57	06/04/24 16:55	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/31/24 16:57	06/04/24 16:55	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	06/10/24 17:00	06/11/24 09:32	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	532	mg/L	25.0	25.0	1		06/03/24 12:09		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	138	mg/L	5.0	5.0	1		06/07/24 15:22		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		06/07/24 15:22		
Alkalinity, Total as CaCO3	138	mg/L	5.0	5.0	1		06/07/24 15:22		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		06/02/24 02:05	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	52.4	mg/L	1.0	0.60	1		06/01/24 23:14	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-PT-09		Lab ID: 92733822002		Collected: 05/30/24 11:52		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.33	mg/L	0.10	0.050	1		06/01/24 23:14	16984-48-8	
Sulfate	133	mg/L	3.0	1.5	3		06/02/24 05:41	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-PT-10 Lab ID: 92733822003 Collected: 05/30/24 14:40 Received: 05/31/24 12:05 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.21	mg/L	0.040	0.025	1	05/31/24 17:19	06/03/24 20:35	7439-89-6	
Manganese	0.52	mg/L	0.040	0.011	1	05/31/24 17:19	06/03/24 20:35	7439-96-5	
Potassium	6.6	mg/L	0.50	0.15	1	05/31/24 17:19	06/03/24 20:35	7440-09-7	
Sodium	9.5	mg/L	1.0	0.58	1	05/31/24 17:19	06/03/24 20:35	7440-23-5	
Calcium	95.9	mg/L	1.0	0.12	1	05/31/24 17:19	06/03/24 20:35	7440-70-2	
Magnesium	13.1	mg/L	0.050	0.012	1	05/31/24 17:19	06/03/24 20:35	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/31/24 16:57	06/04/24 16:59	7440-36-0	
Arsenic	0.0018J	mg/L	0.0050	0.00084	1	05/31/24 16:57	06/04/24 16:59	7440-38-2	
Barium	0.052	mg/L	0.0050	0.00047	1	05/31/24 16:57	06/04/24 16:59	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/31/24 16:57	06/04/24 16:59	7440-41-7	
Boron	1.4	mg/L	0.040	0.012	1	05/31/24 16:57	06/04/24 16:59	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/31/24 16:57	06/04/24 16:59	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/31/24 16:57	06/04/24 16:59	7440-47-3	
Cobalt	0.0014J	mg/L	0.0050	0.00032	1	05/31/24 16:57	06/04/24 16:59	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/31/24 16:57	06/04/24 16:59	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/31/24 16:57	06/04/24 16:59	7439-93-2	
Molybdenum	0.053	mg/L	0.010	0.00062	1	05/31/24 16:57	06/04/24 16:59	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/31/24 16:57	06/04/24 16:59	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/31/24 16:57	06/04/24 16:59	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	06/10/24 17:00	06/11/24 09:35	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	495	mg/L	25.0	25.0	1		06/03/24 12:10		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	116	mg/L	5.0	5.0	1		06/07/24 15:31		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		06/07/24 15:31		
Alkalinity, Total as CaCO3	116	mg/L	5.0	5.0	1		06/07/24 15:31		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		06/02/24 02:05	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	53.0	mg/L	1.0	0.60	1		06/01/24 23:57	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-PT-10		Lab ID: 92733822003		Collected: 05/30/24 14:40		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.17	mg/L	0.10	0.050	1		06/01/24 23:57	16984-48-8	
Sulfate	124	mg/L	3.0	1.5	3		06/02/24 05:55	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92733822

Sample: HAM-PT-11 Lab ID: 92733822004 Collected: 05/29/24 16:43 Received: 05/31/24 12:05 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.10	mg/L	0.040	0.025	1	05/31/24 17:19	06/03/24 20:39	7439-89-6	
Manganese	0.27	mg/L	0.040	0.011	1	05/31/24 17:19	06/03/24 20:39	7439-96-5	
Potassium	6.5	mg/L	0.50	0.15	1	05/31/24 17:19	06/03/24 20:39	7440-09-7	
Sodium	9.2	mg/L	1.0	0.58	1	05/31/24 17:19	06/03/24 20:39	7440-23-5	
Calcium	95.7	mg/L	1.0	0.12	1	05/31/24 17:19	06/03/24 20:39	7440-70-2	
Magnesium	16.7	mg/L	0.050	0.012	1	05/31/24 17:19	06/03/24 20:39	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/31/24 16:57	06/04/24 17:03	7440-36-0	
Arsenic	0.0021J	mg/L	0.0050	0.00084	1	05/31/24 16:57	06/04/24 17:03	7440-38-2	
Barium	0.072	mg/L	0.0050	0.00047	1	05/31/24 16:57	06/04/24 17:03	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/31/24 16:57	06/04/24 17:03	7440-41-7	
Boron	1.4	mg/L	0.040	0.012	1	05/31/24 16:57	06/04/24 17:03	7440-42-8	
Cadmium	0.00013J	mg/L	0.00050	0.00010	1	05/31/24 16:57	06/04/24 17:03	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/31/24 16:57	06/04/24 17:03	7440-47-3	
Cobalt	0.0013J	mg/L	0.0050	0.00032	1	05/31/24 16:57	06/04/24 17:03	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/31/24 16:57	06/04/24 17:03	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/31/24 16:57	06/04/24 17:03	7439-93-2	
Molybdenum	0.17	mg/L	0.010	0.00062	1	05/31/24 16:57	06/04/24 17:03	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/31/24 16:57	06/04/24 17:03	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/31/24 16:57	06/04/24 17:03	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	06/10/24 17:00	06/11/24 09:37	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	474	mg/L	25.0	25.0	1		06/03/24 12:08		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	143	mg/L	5.0	5.0	1		06/05/24 17:35		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		06/05/24 17:35		
Alkalinity, Total as CaCO3	143	mg/L	5.0	5.0	1		06/05/24 17:35		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		06/02/24 02:01	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	39.4	mg/L	1.0	0.60	1		06/02/24 00:11	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-PT-11		Lab ID: 92733822004		Collected: 05/29/24 16:43		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.31	mg/L	0.10	0.050	1		06/02/24 00:11	16984-48-8	
Sulfate	118	mg/L	3.0	1.5	3		06/02/24 06:09	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-PT-12		Lab ID: 92733822005		Collected: 05/29/24 12:08		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.032J	mg/L	0.040	0.025	1	05/31/24 17:19	06/03/24 20:43	7439-89-6	
Manganese	0.75	mg/L	0.040	0.011	1	05/31/24 17:19	06/03/24 20:43	7439-96-5	
Potassium	5.7	mg/L	0.50	0.15	1	05/31/24 17:19	06/03/24 20:43	7440-09-7	
Sodium	9.6	mg/L	1.0	0.58	1	05/31/24 17:19	06/03/24 20:43	7440-23-5	
Calcium	91.0	mg/L	1.0	0.12	1	05/31/24 17:19	06/03/24 20:43	7440-70-2	
Magnesium	18.6	mg/L	0.050	0.012	1	05/31/24 17:19	06/03/24 20:43	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/31/24 16:57	06/04/24 17:07	7440-36-0	
Arsenic	0.0026J	mg/L	0.0050	0.00084	1	05/31/24 16:57	06/04/24 17:07	7440-38-2	
Barium	0.069	mg/L	0.0050	0.00047	1	05/31/24 16:57	06/04/24 17:07	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/31/24 16:57	06/04/24 17:07	7440-41-7	
Boron	1.5	mg/L	0.040	0.012	1	05/31/24 16:57	06/04/24 17:07	7440-42-8	
Cadmium	0.00011J	mg/L	0.00050	0.00010	1	05/31/24 16:57	06/04/24 17:07	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/31/24 16:57	06/04/24 17:07	7440-47-3	
Cobalt	0.0021J	mg/L	0.0050	0.00032	1	05/31/24 16:57	06/04/24 17:07	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/31/24 16:57	06/04/24 17:07	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/31/24 16:57	06/04/24 17:07	7439-93-2	
Molybdenum	0.22	mg/L	0.010	0.00062	1	05/31/24 16:57	06/04/24 17:07	7439-98-7	
Selenium	0.0015J	mg/L	0.0050	0.00096	1	05/31/24 16:57	06/04/24 17:07	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/31/24 16:57	06/04/24 17:07	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	06/10/24 17:00	06/11/24 09:40	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	488	mg/L	25.0	25.0	1		06/03/24 12:08		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	136	mg/L	5.0	5.0	1		06/07/24 13:55		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		06/07/24 13:55		
Alkalinity, Total as CaCO3	136	mg/L	5.0	5.0	1		06/07/24 13:55		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		06/02/24 02:01	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	48.0	mg/L	1.0	0.60	1		06/03/24 00:51	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-PT-12		Lab ID: 92733822005		Collected: 05/29/24 12:08		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.31	mg/L	0.10	0.050	1		06/03/24 00:51	16984-48-8	
Sulfate	131	mg/L	3.0	1.5	3		06/03/24 03:15	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92733822

Sample: HAM-AP1-EB-01 Lab ID: 92733822006 Collected: 05/30/24 16:59 Received: 05/31/24 12:05 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	05/31/24 17:19	06/03/24 20:47	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	05/31/24 17:19	06/03/24 20:47	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	05/31/24 17:19	06/03/24 20:47	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	05/31/24 17:19	06/03/24 20:47	7440-23-5	
Calcium	0.13J	mg/L	1.0	0.12	1	05/31/24 17:19	06/03/24 20:47	7440-70-2	
Magnesium	0.030J	mg/L	0.050	0.012	1	05/31/24 17:19	06/03/24 20:47	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/31/24 16:57	06/04/24 17:16	7440-36-0	
Arsenic	0.0044J	mg/L	0.0050	0.00084	1	05/31/24 16:57	06/04/24 17:16	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	05/31/24 16:57	06/04/24 17:16	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/31/24 16:57	06/04/24 17:16	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	05/31/24 16:57	06/04/24 17:16	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/31/24 16:57	06/04/24 17:16	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/31/24 16:57	06/04/24 17:16	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	05/31/24 16:57	06/04/24 17:16	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/31/24 16:57	06/04/24 17:16	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/31/24 16:57	06/04/24 17:16	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	05/31/24 16:57	06/04/24 17:16	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	05/31/24 16:57	06/04/24 17:16	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/31/24 16:57	06/04/24 17:16	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	06/10/24 17:00	06/11/24 09:43	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		06/03/24 12:10		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		06/07/24 15:40		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		06/07/24 15:40		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		06/07/24 15:40		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		06/02/24 02:06	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		06/02/24 22:00	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-AP1-EB-01		Lab ID: 92733822006		Collected: 05/30/24 16:59		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		06/02/24 22:00	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		06/02/24 22:00	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92733822

Sample: HAM-AP1-FB-01 Lab ID: 92733822007 Collected: 05/30/24 16:52 Received: 05/31/24 12:05 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	05/31/24 17:19	06/03/24 20:51	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	05/31/24 17:19	06/03/24 20:51	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	05/31/24 17:19	06/03/24 20:51	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	05/31/24 17:19	06/03/24 20:51	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	05/31/24 17:19	06/03/24 20:51	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	05/31/24 17:19	06/03/24 20:51	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/31/24 16:57	06/04/24 17:20	7440-36-0	
Arsenic	0.0040J	mg/L	0.0050	0.00084	1	05/31/24 16:57	06/04/24 17:20	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	05/31/24 16:57	06/04/24 17:20	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/31/24 16:57	06/04/24 17:20	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	05/31/24 16:57	06/04/24 17:20	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	05/31/24 16:57	06/04/24 17:20	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/31/24 16:57	06/04/24 17:20	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	05/31/24 16:57	06/04/24 17:20	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/31/24 16:57	06/04/24 17:20	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/31/24 16:57	06/04/24 17:20	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	05/31/24 16:57	06/04/24 17:20	7439-98-7	
Selenium	0.0011J	mg/L	0.0050	0.00096	1	05/31/24 16:57	06/04/24 17:20	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/31/24 16:57	06/04/24 17:20	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	06/10/24 17:00	06/11/24 09:45	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		06/03/24 12:10		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	ND	mg/L	5.0	5.0	1		06/07/24 15:44		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		06/07/24 15:44		
Alkalinity, Total as CaCO3	ND	mg/L	5.0	5.0	1		06/07/24 15:44		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		06/02/24 02:06	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		06/02/24 22:14	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-AP1-FB-01		Lab ID: 92733822007		Collected: 05/30/24 16:52		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		06/02/24 22:14	16984-48-8	M1
Sulfate	ND	mg/L	1.0	0.50	1		06/02/24 22:14	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92733822

Sample: HAM-AP1-FD-01 Lab ID: 92733822008 Collected: 05/30/24 00:00 Received: 05/31/24 12:05 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.26	mg/L	0.040	0.025	1	05/31/24 17:19	06/03/24 21:41	7439-89-6	
Manganese	0.27	mg/L	0.040	0.011	1	05/31/24 17:19	06/03/24 21:41	7439-96-5	
Calcium	97.3	mg/L	1.0	0.12	1	05/31/24 17:19	06/03/24 21:41	7440-70-2	
Magnesium	20.9	mg/L	0.050	0.012	1	05/31/24 17:19	06/03/24 21:41	7439-95-4	
Potassium	6.4	mg/L	0.50	0.15	1	05/31/24 17:19	06/04/24 14:10	7440-09-7	
Sodium	12.0	mg/L	1.0	0.58	1	05/31/24 17:19	06/04/24 14:10	7440-23-5	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	05/31/24 16:57	06/04/24 17:24	7440-36-0	
Arsenic	0.0025J	mg/L	0.0050	0.00084	1	05/31/24 16:57	06/04/24 17:24	7440-38-2	
Barium	0.062	mg/L	0.0050	0.00047	1	05/31/24 16:57	06/04/24 17:24	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	05/31/24 16:57	06/04/24 17:24	7440-41-7	
Boron	1.4	mg/L	0.040	0.012	1	05/31/24 16:57	06/04/24 17:24	7440-42-8	
Cadmium	0.00014J	mg/L	0.00050	0.00010	1	05/31/24 16:57	06/04/24 17:24	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	05/31/24 16:57	06/04/24 17:24	7440-47-3	
Cobalt	0.0010J	mg/L	0.0050	0.00032	1	05/31/24 16:57	06/04/24 17:24	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	05/31/24 16:57	06/04/24 17:24	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	05/31/24 16:57	06/04/24 17:24	7439-93-2	
Molybdenum	0.24	mg/L	0.010	0.00062	1	05/31/24 16:57	06/04/24 17:24	7439-98-7	
Selenium	0.0012J	mg/L	0.0050	0.00096	1	05/31/24 16:57	06/04/24 17:24	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	05/31/24 16:57	06/04/24 17:24	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	06/10/24 17:00	06/11/24 09:48	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	500	mg/L	25.0	25.0	1		06/03/24 12:10		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	140	mg/L	5.0	5.0	1		06/07/24 15:48		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		06/07/24 15:48		
Alkalinity, Total as CaCO3	140	mg/L	5.0	5.0	1		06/07/24 15:48		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		06/02/24 02:06	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	51.3	mg/L	1.0	0.60	1		06/03/24 01:06	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92733822

Sample: HAM-AP1-FD-01		Lab ID: 92733822008		Collected: 05/30/24 00:00		Received: 05/31/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.32	mg/L	0.10	0.050	1		06/03/24 01:06	16984-48-8	
Sulfate	129	mg/L	3.0	1.5	3		06/03/24 03:29	14808-79-8	

REPORT OF LABORATORY ANALYSIS



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

QC Batch:	858318	Analysis Method:	EPA 6010D
QC Batch Method:	EPA 3010A	Analysis Description:	6010D ATL
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008		

METHOD BLANK:	4427514	Matrix:	Water
Associated Lab Samples:	92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	06/03/24 19:29	
Iron	mg/L	ND	0.040	0.025	06/03/24 19:29	
Magnesium	mg/L	ND	0.050	0.012	06/03/24 19:29	
Manganese	mg/L	ND	0.040	0.011	06/03/24 19:29	
Potassium	mg/L	ND	0.50	0.15	06/03/24 19:29	
Sodium	mg/L	ND	1.0	0.58	06/03/24 19:29	

LABORATORY CONTROL SAMPLE: 4427515

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	1.0	102	80-120	
Iron	mg/L	1	1.0	103	80-120	
Magnesium	mg/L	1	1.0	104	80-120	
Manganese	mg/L	1	1.0	102	80-120	
Potassium	mg/L	1	1.0	102	80-120	
Sodium	mg/L	1	1.1	110	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4427516 4427517

Parameter	Units	92733547001	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		Result										
Calcium	mg/L	37.2	1	1	38.6	39.0	141	186	75-125	1	20	M1
Iron	mg/L	0.21	1	1	1.2	1.2	100	100	75-125	0	20	
Magnesium	mg/L	8.5	1	1	9.5	9.6	101	112	75-125	1	20	
Manganese	mg/L	ND	1	1	0.99	1.0	97	98	75-125	1	20	
Potassium	mg/L	2580 ug/L	1	1	3.4	3.5	85	88	75-125	1	20	
Sodium	mg/L	67.1	1	1	68.5	69.1	139	197	75-125	1	20	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

QC Batch: 858301 Analysis Method: EPA 6020B
QC Batch Method: EPA 3005A Analysis Description: 6020 MET
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008

METHOD BLANK: 4427464 Matrix: Water
Associated Lab Samples: 92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	0.0010J	0.0030	0.00054	06/04/24 15:49	
Arsenic	mg/L	ND	0.0050	0.00084	06/04/24 15:49	
Barium	mg/L	ND	0.0050	0.00047	06/04/24 15:49	
Beryllium	mg/L	ND	0.00050	0.000094	06/04/24 15:49	
Boron	mg/L	ND	0.040	0.012	06/04/24 15:49	
Cadmium	mg/L	ND	0.00050	0.00010	06/04/24 15:49	
Chromium	mg/L	ND	0.0050	0.0019	06/04/24 15:49	
Cobalt	mg/L	ND	0.0050	0.00032	06/04/24 15:49	
Lead	mg/L	ND	0.0010	0.00016	06/04/24 15:49	
Lithium	mg/L	ND	0.030	0.0016	06/04/24 15:49	
Molybdenum	mg/L	ND	0.010	0.00062	06/04/24 15:49	
Selenium	mg/L	ND	0.0050	0.00096	06/04/24 15:49	
Thallium	mg/L	ND	0.0010	0.00038	06/04/24 15:49	

LABORATORY CONTROL SAMPLE: 4427465

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.11	111	80-120	
Arsenic	mg/L	0.1	0.11	106	80-120	
Barium	mg/L	0.1	0.11	105	80-120	
Beryllium	mg/L	0.1	0.10	103	80-120	
Boron	mg/L	1	0.98	98	80-120	
Cadmium	mg/L	0.1	0.10	101	80-120	
Chromium	mg/L	0.1	0.096	96	80-120	
Cobalt	mg/L	0.1	0.096	96	80-120	
Lead	mg/L	0.1	0.10	102	80-120	
Lithium	mg/L	0.1	0.10	104	80-120	
Molybdenum	mg/L	0.1	0.10	104	80-120	
Selenium	mg/L	0.1	0.11	107	80-120	
Thallium	mg/L	0.1	0.10	100	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4427466 4427467

Parameter	Units	92732634001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	ND	0.1	0.1	0.10	0.11	104	108	75-125	4	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4427466 4427467											
Parameter	Units	92732634001		MS		MSD		MS		MSD	
		Result	Conc.	Spike	Conc.	Result	Conc.	% Rec	% Rec	% Rec	Max
								Limits	RPD	RPD	Qual
Arsenic	mg/L	6.5 ug/L	0.1	0.1	0.12	0.13	118	120	75-125	1	20
Barium	mg/L	73.4 ug/L	0.1	0.1	0.19	0.20	120	123	75-125	2	20
Beryllium	mg/L	ND	0.1	0.1	0.080	0.081	80	81	75-125	1	20
Boron	mg/L	16.1	1	1	17.8	17.4	179	137	75-125	2	20 M1
Cadmium	mg/L	0.16J ug/L	0.1	0.1	0.097	0.098	97	97	75-125	1	20
Chromium	mg/L	ND	0.1	0.1	0.10	0.10	103	100	75-125	3	20
Cobalt	mg/L	0.011	0.1	0.1	0.11	0.11	103	99	75-125	3	20
Lead	mg/L	ND	0.1	0.1	0.080	0.083	80	83	75-125	4	20
Lithium	mg/L	16.2J ug/L	0.1	0.1	0.10	0.11	88	89	75-125	1	20
Molybdenum	mg/L	41.5 ug/L	0.1	0.1	0.15	0.15	104	109	75-125	4	20
Selenium	mg/L	2.9J ug/L	0.1	0.1	0.12	0.12	115	120	75-125	5	20
Thallium	mg/L	0.75J ug/L	0.1	0.1	0.086	0.090	85	89	75-125	5	20

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

QC Batch:	860215	Analysis Method:	EPA 7470A
QC Batch Method:	EPA 7470A	Analysis Description:	7470 Mercury
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008		

METHOD BLANK:	4436712	Matrix:	Water
Associated Lab Samples:	92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	06/11/24 09:02	

LABORATORY CONTROL SAMPLE:		4436713				
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0026	106	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:		4436714				4436715						
Parameter	Units	92733822001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.0025	0.0025	0.0027	0.0026	106	105	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

QC Batch:	858596	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008		

METHOD BLANK:	4428622	Matrix:	Water
Associated Lab Samples:	92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	06/03/24 12:07	

LABORATORY CONTROL SAMPLE:	4428623					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	394	98	80-120	

SAMPLE DUPLICATE:	4428624					
Parameter	Units	92733822001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	610	630	3	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

QC Batch: 859203

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92733822001, 92733822004

METHOD BLANK: 4431658

Matrix: Water

Associated Lab Samples: 92733822001, 92733822004

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	06/05/24 14:59	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	06/05/24 14:59	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	06/05/24 14:59	

LABORATORY CONTROL SAMPLE: 4431659

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	50.6	101	80-120	

LABORATORY CONTROL SAMPLE: 4431660

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.5	105	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4431661 4431662

Parameter	Units	92733822001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	176	50	50	221	222	90	90	80-120	0	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4431663 4431664

Parameter	Units	92733822004 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	143	50	50	190	190	94	93	80-120	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

QC Batch: 859504

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92733822002, 92733822003, 92733822005, 92733822006, 92733822007, 92733822008

METHOD BLANK: 4433372

Matrix: Water

Associated Lab Samples: 92733822002, 92733822003, 92733822005, 92733822006, 92733822007, 92733822008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	06/07/24 13:37	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	06/07/24 13:37	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	06/07/24 13:37	

LABORATORY CONTROL SAMPLE: 4433373

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	49.9	100	80-120	

LABORATORY CONTROL SAMPLE: 4433374

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	49.7	99	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4433375 4433376

Parameter	Units	92733822005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	136	50	50	184	183	97	96	80-120	0	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4433377 4433378

Parameter	Units	92734198001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	67.0	50	50	114	115	95	96	80-120	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

QC Batch:	858390	Analysis Method:	SM 4500-S2D-2011
QC Batch Method:	SM 4500-S2D-2011	Analysis Description:	4500S2D Sulfide Water
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008		

METHOD BLANK:	4428023	Matrix:	Water
Associated Lab Samples:	92733822001, 92733822002, 92733822003, 92733822004, 92733822005, 92733822006, 92733822007, 92733822008		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	06/02/24 01:56	

LABORATORY CONTROL SAMPLE: 4428024						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.52	105	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:												
4428025					4428026							
		92733542001	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Parameter	Units	Result										
Sulfide	mg/L	ND	0.5	0.5	0.53	0.54	104	107	80-120	3	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:													4428027	4428028			
Parameter	Units	92733542003	MS	MSD	MS	MSD	MS	MSD	% Rec	RPD	Max	Qual					
		Result	Spike Conc.	Spike Conc.									Result	Result	% Rec	% Rec	Limits
Sulfide	mg/L	ND	0.5	0.5	0.52	0.56	102	110	80-120	8	10						

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

QC Batch: 858418 Analysis Method: EPA 300.0 Rev 2.1 1993
QC Batch Method: EPA 300.0 Rev 2.1 1993 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92733822001, 92733822002, 92733822003, 92733822004

METHOD BLANK: 4428096 Matrix: Water
Associated Lab Samples: 92733822001, 92733822002, 92733822003, 92733822004

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	06/01/24 16:46	
Fluoride	mg/L	ND	0.10	0.050	06/01/24 16:46	
Sulfate	mg/L	ND	1.0	0.50	06/01/24 16:46	

LABORATORY CONTROL SAMPLE: 4428097

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	51.1	102	90-110	
Fluoride	mg/L	2.5	2.6	104	90-110	
Sulfate	mg/L	50	51.1	102	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4428098 4428099

Parameter	Units	92733871001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	11.7	50	50	66.7	63.3	110	103	90-110	5	10	
Fluoride	mg/L	0.33	2.5	2.5	3.2	2.9	113	104	90-110	7	10	M1
Sulfate	mg/L	3.5	50	50	58.5	55.1	110	103	90-110	6	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4428102 4428103

Parameter	Units	92733765025 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	3.2	50	50	56.9	57.5	107	109	90-110	1	10	
Fluoride	mg/L	0.30	2.5	2.5	3.1	3.1	110	111	90-110	1	10	M1
Sulfate	mg/L	43.6	50	50	96.9	97.5	107	108	90-110	1	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92733822

QC Batch: 858511 Analysis Method: EPA 300.0 Rev 2.1 1993
QC Batch Method: EPA 300.0 Rev 2.1 1993 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92733822005, 92733822006, 92733822007, 92733822008

METHOD BLANK: 4428289 Matrix: Water
Associated Lab Samples: 92733822005, 92733822006, 92733822007, 92733822008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	06/02/24 21:31	
Fluoride	mg/L	ND	0.10	0.050	06/02/24 21:31	
Sulfate	mg/L	ND	1.0	0.50	06/02/24 21:31	

LABORATORY CONTROL SAMPLE: 4428290

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	51.0	102	90-110	
Fluoride	mg/L	2.5	2.7	107	90-110	
Sulfate	mg/L	50	51.1	102	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4428291 4428292

Parameter	Units	92733788001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	70.2	50	50	108	109	75	78	90-110	1	10	M1
Fluoride	mg/L	ND	2.5	2.5	2.6	2.8	105	110	90-110	5	10	
Sulfate	mg/L	22.8	50	50	73.4	75.8	101	106	90-110	3	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4428293 4428294

Parameter	Units	92733822007 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	ND	50	50	49.3	53.2	99	106	90-110	7	10	
Fluoride	mg/L	ND	2.5	2.5	2.6	2.8	105	112	90-110	6	10	M1
Sulfate	mg/L	ND	50	50	49.3	53.1	99	106	90-110	7	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1
Pace Project No.: 92733822

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92733822

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92733822001	HAM-INW-03	EPA 3010A	858318	EPA 6010D	858334
92733822002	HAM-PT-09	EPA 3010A	858318	EPA 6010D	858334
92733822003	HAM-PT-10	EPA 3010A	858318	EPA 6010D	858334
92733822004	HAM-PT-11	EPA 3010A	858318	EPA 6010D	858334
92733822005	HAM-PT-12	EPA 3010A	858318	EPA 6010D	858334
92733822006	HAM-AP1-EB-01	EPA 3010A	858318	EPA 6010D	858334
92733822007	HAM-AP1-FB-01	EPA 3010A	858318	EPA 6010D	858334
92733822008	HAM-AP1-FD-01	EPA 3010A	858318	EPA 6010D	858334
92733822001	HAM-INW-03	EPA 3005A	858301	EPA 6020B	858345
92733822002	HAM-PT-09	EPA 3005A	858301	EPA 6020B	858345
92733822003	HAM-PT-10	EPA 3005A	858301	EPA 6020B	858345
92733822004	HAM-PT-11	EPA 3005A	858301	EPA 6020B	858345
92733822005	HAM-PT-12	EPA 3005A	858301	EPA 6020B	858345
92733822006	HAM-AP1-EB-01	EPA 3005A	858301	EPA 6020B	858345
92733822007	HAM-AP1-FB-01	EPA 3005A	858301	EPA 6020B	858345
92733822008	HAM-AP1-FD-01	EPA 3005A	858301	EPA 6020B	858345
92733822001	HAM-INW-03	EPA 7470A	860215	EPA 7470A	860356
92733822002	HAM-PT-09	EPA 7470A	860215	EPA 7470A	860356
92733822003	HAM-PT-10	EPA 7470A	860215	EPA 7470A	860356
92733822004	HAM-PT-11	EPA 7470A	860215	EPA 7470A	860356
92733822005	HAM-PT-12	EPA 7470A	860215	EPA 7470A	860356
92733822006	HAM-AP1-EB-01	EPA 7470A	860215	EPA 7470A	860356
92733822007	HAM-AP1-FB-01	EPA 7470A	860215	EPA 7470A	860356
92733822008	HAM-AP1-FD-01	EPA 7470A	860215	EPA 7470A	860356
92733822001	HAM-INW-03	SM 2540C-2015	858596		
92733822002	HAM-PT-09	SM 2540C-2015	858596		
92733822003	HAM-PT-10	SM 2540C-2015	858596		
92733822004	HAM-PT-11	SM 2540C-2015	858596		
92733822005	HAM-PT-12	SM 2540C-2015	858596		
92733822006	HAM-AP1-EB-01	SM 2540C-2015	858596		
92733822007	HAM-AP1-FB-01	SM 2540C-2015	858596		
92733822008	HAM-AP1-FD-01	SM 2540C-2015	858596		
92733822001	HAM-INW-03	SM 2320B-2011	859203		
92733822002	HAM-PT-09	SM 2320B-2011	859504		
92733822003	HAM-PT-10	SM 2320B-2011	859504		
92733822004	HAM-PT-11	SM 2320B-2011	859203		
92733822005	HAM-PT-12	SM 2320B-2011	859504		
92733822006	HAM-AP1-EB-01	SM 2320B-2011	859504		
92733822007	HAM-AP1-FB-01	SM 2320B-2011	859504		
92733822008	HAM-AP1-FD-01	SM 2320B-2011	859504		
92733822001	HAM-INW-03	SM 4500-S2D-2011	858390		
92733822002	HAM-PT-09	SM 4500-S2D-2011	858390		
92733822003	HAM-PT-10	SM 4500-S2D-2011	858390		
92733822004	HAM-PT-11	SM 4500-S2D-2011	858390		
92733822005	HAM-PT-12	SM 4500-S2D-2011	858390		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1
Pace Project No.: 92733822

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92733822006	HAM-AP1-EB-01	SM 4500-S2D-2011	858390		
92733822007	HAM-AP1-FB-01	SM 4500-S2D-2011	858390		
92733822008	HAM-AP1-FD-01	SM 4500-S2D-2011	858390		
92733822001	HAM-INW-03	EPA 300.0 Rev 2.1 1993	858418		
92733822002	HAM-PT-09	EPA 300.0 Rev 2.1 1993	858418		
92733822003	HAM-PT-10	EPA 300.0 Rev 2.1 1993	858418		
92733822004	HAM-PT-11	EPA 300.0 Rev 2.1 1993	858418		
92733822005	HAM-PT-12	EPA 300.0 Rev 2.1 1993	858511		
92733822006	HAM-AP1-EB-01	EPA 300.0 Rev 2.1 1993	858511		
92733822007	HAM-AP1-FB-01	EPA 300.0 Rev 2.1 1993	858511		
92733822008	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	858511		

REPORT OF LABORATORY ANALYSIS



DC#_Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

Project #:

WO#: 92733822

Courier:

☐ Commercial☐ Fed Ex☐ UPS☐ USPS☐ Client☒ Pace☐ Other: _____

Custody Seal Present?

☒ Yes☐ No

Seals Intact?

☒ Yes☐ No☐ N/A

Date/Initials Person Examining Contents: 5/21/24 DW

Packing Material:

☒ Bubble Wrap☐ Bubble Bags☐ None☐ Other

Biological Tissue Frozen?

☐ Yes☐ No☒ N/A

Thermometer:

☐ IR Gun ID:

230

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

2.6

Correction Factor:

Add/Subtract (°C)

0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

2.6

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☒ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☒ No

			Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.	
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.	
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.	
Rush Turn Around Time Requested?	☒ Yes ☐ No ☐ N/A	4.	5 DAY TAT
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.	
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.	
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A		
Containers Intact?	☒ Yes ☐ No ☐ N/A	7.	
Dissolved analysis: Samples Field Filtered?	☐ Yes ☒ No ☐ N/A	8.	
Sample Labels Match COC?	☒ Yes ☐ No ☐ N/A	9.	
-Includes Date/Time/ID/Analysis Matrix: W 6, W 12			
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10.	
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.	
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A		

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☒ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_Title: ENV-FRM-HUN1-0083 v03_Sample Condition Upon Receipt

Effective Date: 12/01/2023

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/BD15 (water) DOC, UHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

WO#: 92733822

PM: BV

Due Date: 06/14/24

CLIENT: 92- GP-HAM

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic ZN Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGFU-Wide-mouthed Glass Jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG94-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2SO3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per Nit-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)		BP3H-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AG6U-100 mL Amber Unpreserved (N/A) (Cl-)	VSGU-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)
1		2	1																									
2		2	1																									
3		2	1																									
4		2	1																									
5		2	1																									
6		2	1																									
7		2	1																									
8		2	1																									
9																												
10																												
11																												
12																												

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers.



CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Important Note: The standard list items and any associated Price's list 1-800 have standard terms and conditions to list changes of 1-800, not month to any visitors per paid within 30 days.

Field Sampling Forms

Low-Flow Test Report:

Test Date / Time: 7/13/2023 9:51:13 AM
Project: GW6581
Operator Name: Alana Neely

Location Name: HGWC-8 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 15.5 ft Total Depth: 25.51 ft Initial Depth to Water: 13.41 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 20.5 ft Estimated Total Volume Pumped: 11.25 L Flow Cell Volume: 90 ml Final Flow Rate: 250 ml/min Final Draw Down: 0.06 ft	Instrument Used: Aqua TROLL 400 Serial Number: 884187
---	--	--

Test Notes:
Five bottles: Full App III and IV and Geochem

Weather Conditions:
73-91 deg F; sunny

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
7/13/2023 9:51 AM	00:00	6.54 pH	20.67 °C	704.35 µS/cm	0.12 mg/L	108.00 NTU	75.0 mV	13.40 ft	250.00 ml/min
7/13/2023 9:51 AM	00:29	6.56 pH	20.65 °C	700.23 µS/cm	0.12 mg/L		65.9 mV	13.40 ft	250.00 ml/min
7/13/2023 9:56 AM	05:29	6.60 pH	20.41 °C	716.26 µS/cm	0.08 mg/L	50.40 NTU	60.7 mV	13.45 ft	250.00 ml/min
7/13/2023 10:01 AM	10:29	6.63 pH	21.14 °C	714.09 µS/cm	0.07 mg/L	27.90 NTU	45.7 mV	13.47 ft	250.00 ml/min
7/13/2023 10:06 AM	15:29	6.64 pH	21.51 °C	723.67 µS/cm	0.06 mg/L	16.20 NTU	41.8 mV	13.47 ft	250.00 ml/min
7/13/2023 10:11 AM	20:29	6.65 pH	21.74 °C	717.17 µS/cm	0.05 mg/L	12.10 NTU	45.9 mV	13.47 ft	250.00 ml/min
7/13/2023 10:16 AM	25:29	6.65 pH	21.08 °C	721.11 µS/cm	0.04 mg/L	8.93 NTU	41.5 mV	13.47 ft	250.00 ml/min
7/13/2023 10:21 AM	30:29	6.65 pH	21.43 °C	721.10 µS/cm	0.04 mg/L	8.41 NTU	47.0 mV	13.47 ft	250.00 ml/min
7/13/2023 10:26 AM	35:29	6.56 pH	21.58 °C	702.26 µS/cm	0.14 mg/L	5.41 NTU	51.1 mV	13.47 ft	250.00 ml/min
7/13/2023 10:31 AM	40:29	6.65 pH	21.38 °C	723.48 µS/cm	0.08 mg/L	4.50 NTU	48.4 mV	13.47 ft	250.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

HAM-HGWC-8	Grab.
------------	-------

Low-Flow Test Report:

Test Date / Time: 7/17/2023 10:12:40 AM
Project: GW6581
Operator Name: Alana Neely

Location Name: HGWC-13 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 32 ft Total Depth: 42 ft Initial Depth to Water: 26.4 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 37 ft Estimated Total Volume Pumped: 19 L Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.4 ft	Instrument Used: Aqua TROLL 400 Serial Number: 884187
--	---	--

Test Notes:
Five bottles: Full App III and IV and Geochem

Weather Conditions:
66-93 deg F Sunny

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
7/17/2023 10:12 AM	00:00	6.59 pH	20.94 °C	1,029.2 µS/cm	0.23 mg/L	37.60 NTU	-74.7 mV	26.80 ft	200.00 ml/min
7/17/2023 10:17 AM	05:00	6.64 pH	20.94 °C	1,029.0 µS/cm	0.16 mg/L	41.90 NTU	-80.9 mV	26.80 ft	200.00 ml/min
7/17/2023 10:22 AM	10:00	6.64 pH	21.07 °C	1,020.4 µS/cm	0.17 mg/L	61.80 NTU	-61.9 mV	26.80 ft	200.00 ml/min
7/17/2023 10:27 AM	15:00	6.66 pH	22.28 °C	1,002.2 µS/cm	1.80 mg/L	40.00 NTU	-2.6 mV	26.80 ft	200.00 ml/min
7/17/2023 10:32 AM	20:00	6.61 pH	21.57 °C	993.49 µS/cm	0.35 mg/L	42.20 NTU	-15.2 mV	26.80 ft	200.00 ml/min
7/17/2023 10:37 AM	25:00	6.61 pH	22.19 °C	1,005.4 µS/cm	0.35 mg/L	49.20 NTU	-32.1 mV	26.80 ft	200.00 ml/min
7/17/2023 10:42 AM	30:00	6.62 pH	22.55 °C	1,016.7 µS/cm	0.28 mg/L	58.00 NTU	-52.3 mV	26.80 ft	200.00 ml/min
7/17/2023 10:47 AM	35:00	6.63 pH	23.25 °C	1,027.9 µS/cm	0.28 mg/L	64.50 NTU	-68.7 mV	26.80 ft	200.00 ml/min
7/17/2023 10:52 AM	40:00	6.64 pH	22.88 °C	1,017.4 µS/cm	0.25 mg/L	43.20 NTU	-58.0 mV	26.80 ft	200.00 ml/min
7/17/2023 10:57 AM	45:00	6.65 pH	22.54 °C	1,021.8 µS/cm	0.18 mg/L	34.80 NTU	-69.7 mV	26.80 ft	200.00 ml/min
7/17/2023 11:02 AM	50:00	6.65 pH	22.65 °C	1,023.7 µS/cm	0.15 mg/L	29.60 NTU	-72.4 mV	26.80 ft	200.00 ml/min
7/17/2023 11:07 AM	55:00	6.66 pH	22.73 °C	1,024.7 µS/cm	0.14 mg/L	24.00 NTU	-74.1 mV	26.80 ft	200.00 ml/min
7/17/2023 11:12 AM	01:00:00	6.65 pH	22.81 °C	1,024.2 µS/cm	0.12 mg/L	18.20 NTU	-68.2 mV	26.80 ft	200.00 ml/min

7/17/2023 11:17 AM	01:05:00	6.66 pH	22.81 °C	1,020.8 μS/cm	0.11 mg/L	14.60 NTU	-75.5 mV	26.80 ft	200.00 ml/min
7/17/2023 11:22 AM	01:10:00	6.66 pH	22.84 °C	1,022.9 μS/cm	0.10 mg/L	13.70 NTU	-69.1 mV	26.80 ft	200.00 ml/min
7/17/2023 11:27 AM	01:15:00	6.66 pH	22.81 °C	1,024.0 μS/cm	0.09 mg/L	12.50 NTU	-69.6 mV	26.80 ft	200.00 ml/min
7/17/2023 11:32 AM	01:20:00	6.66 pH	22.92 °C	1,024.1 μS/cm	0.09 mg/L	9.80 NTU	-76.8 mV	26.80 ft	200.00 ml/min
7/17/2023 11:37 AM	01:25:00	6.66 pH	23.08 °C	1,025.7 μS/cm	0.09 mg/L	6.70 NTU	-70.1 mV	26.80 ft	200.00 ml/min
7/17/2023 11:42 AM	01:30:00	6.67 pH	23.26 °C	1,024.5 μS/cm	0.08 mg/L	4.26 NTU	-77.2 mV	26.80 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-HGWC-13	Grab.

Low-Flow Test Report:

Test Date / Time: 7/13/2023 3:37:26 PM
Project: GW6581
Operator Name: Alana Neely

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 38.6 ft Total Depth: 48.6 ft Initial Depth to Water: 25.3 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 43.6 ft Estimated Total Volume Pumped: 9 L Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 884187
--	---	--

Test Notes:
Five bottles: Full App III and IV and Geochem

Weather Conditions:
73-91 deg F sunny

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
7/13/2023 3:37 PM	00:00	6.80 pH	28.25 °C	1,056.0 µS/cm	1.39 mg/L	21.70 NTU	-108.6 mV	25.30 ft	200.00 ml/min
7/13/2023 3:42 PM	05:00	6.81 pH	26.88 °C	1,079.0 µS/cm	0.68 mg/L	21.30 NTU	-111.1 mV	25.30 ft	200.00 ml/min
7/13/2023 3:47 PM	10:00	6.82 pH	26.52 °C	1,072.1 µS/cm	0.49 mg/L	18.70 NTU	-127.0 mV	25.30 ft	200.00 ml/min
7/13/2023 3:52 PM	15:00	6.80 pH	27.35 °C	1,080.9 µS/cm	0.48 mg/L	16.00 NTU	-128.2 mV	25.30 ft	200.00 ml/min
7/13/2023 3:57 PM	20:00	6.77 pH	27.44 °C	979.74 µS/cm	0.41 mg/L	9.81 NTU	-113.5 mV	25.30 ft	200.00 ml/min
7/13/2023 4:02 PM	25:00	6.76 pH	27.85 °C	1,068.5 µS/cm	0.35 mg/L	9.08 NTU	-126.8 mV	25.30 ft	200.00 ml/min
7/13/2023 4:07 PM	30:00	6.76 pH	27.68 °C	1,061.0 µS/cm	0.32 mg/L	6.69 NTU	-111.9 mV	25.30 ft	200.00 ml/min
7/13/2023 4:12 PM	35:00	6.75 pH	27.81 °C	1,069.4 µS/cm	0.29 mg/L	6.01 NTU	-125.6 mV	25.30 ft	200.00 ml/min
7/13/2023 4:17 PM	40:00	6.76 pH	27.26 °C	1,064.5 µS/cm	0.30 mg/L	4.91 NTU	-111.0 mV	25.30 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-07	Grab.

HAM-AP1-FD-01	Grab.
---------------	-------

Low-Flow Test Report:

Test Date / Time: 7/13/2023 5:11:34 PM
Project: GW6581
Operator Name: Alana Neely

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 33 ft Total Depth: 43 ft Initial Depth to Water: 22.2 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 38 ft Estimated Total Volume Pumped: 8 L Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.1 ft	Instrument Used: Aqua TROLL 400 Serial Number: 884187
--	---	--

Test Notes:
Five bottles: Full App III and IV and Geochem
Weather Conditions:
73-91 deg F sunny
Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
7/13/2023 5:11 PM	00:00	6.70 pH	26.09 °C	930.24 µS/cm	0.88 mg/L	20.20 NTU	-77.5 mV	22.30 ft	200.00 ml/min
7/13/2023 5:16 PM	05:00	6.68 pH	24.72 °C	960.77 µS/cm	1.07 mg/L	19.70 NTU	-81.4 mV	22.30 ft	200.00 ml/min
7/13/2023 5:21 PM	10:00	6.67 pH	24.21 °C	962.53 µS/cm	0.13 mg/L	24.30 NTU	-101.1 mV	22.30 ft	200.00 ml/min
7/13/2023 5:26 PM	15:00	6.66 pH	24.14 °C	972.51 µS/cm	0.11 mg/L	22.50 NTU	-107.9 mV	22.30 ft	200.00 ml/min
7/13/2023 5:31 PM	20:00	6.67 pH	24.49 °C	1,002.9 µS/cm	0.10 mg/L	8.59 NTU	-124.8 mV	22.30 ft	200.00 ml/min
7/13/2023 5:36 PM	25:00	6.68 pH	24.12 °C	999.67 µS/cm	0.08 mg/L	6.25 NTU	-115.1 mV	22.30 ft	200.00 ml/min
7/13/2023 5:41 PM	30:00	6.66 pH	24.79 °C	1,007.2 µS/cm	0.09 mg/L	7.11 NTU	-116.7 mV	22.30 ft	200.00 ml/min
7/13/2023 5:46 PM	35:00	6.66 pH	24.53 °C	1,007.1 µS/cm	0.09 mg/L	4.41 NTU	-124.9 mV	22.30 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.

Low-Flow Test Report:

Test Date / Time: 7/13/2023 11:06:04 AM
Project: GW6581
Operator Name: Alana Neely

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 18.5 ft Total Depth: 28.5 ft Initial Depth to Water: 14 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 23.5 ft Estimated Total Volume Pumped: 25.25 L Flow Cell Volume: 90 ml Final Flow Rate: 250 ml/min Final Draw Down: 0.1 ft	Instrument Used: Aqua TROLL 400 Serial Number: 884187
--	---	--

Test Notes:
Five bottles: Full App III and IV and Geochem

Weather Conditions:
73-91 deg F sunny

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
7/13/2023 11:06 AM	00:00	6.47 pH	23.91 °C	730.32 µS/cm	0.18 mg/L	3.55 NTU	32.8 mV	14.10 ft	250.00 ml/min
7/13/2023 11:07 AM	01:07	6.52 pH	23.22 °C	743.74 µS/cm	0.15 mg/L	-	11.4 mV	14.10 ft	250.00 ml/min
7/13/2023 11:12 AM	06:07	6.56 pH	22.23 °C	753.03 µS/cm	0.09 mg/L	2.51 NTU	6.0 mV	14.10 ft	250.00 ml/min
7/13/2023 11:17 AM	11:07	6.57 pH	22.47 °C	754.10 µS/cm	0.06 mg/L	2.49 NTU	3.4 mV	14.10 ft	250.00 ml/min
7/13/2023 11:22 AM	16:07	6.57 pH	22.10 °C	764.27 µS/cm	0.05 mg/L	4.55 NTU	-9.5 mV	14.10 ft	250.00 ml/min
7/13/2023 11:27 AM	21:07	6.58 pH	22.12 °C	768.51 µS/cm	0.04 mg/L	3.98 NTU	-12.2 mV	14.10 ft	250.00 ml/min
7/13/2023 11:32 AM	26:08	6.42 pH	22.27 °C	729.76 µS/cm	0.04 mg/L	4.56 NTU	4.1 mV	14.10 ft	250.00 ml/min
7/13/2023 11:37 AM	31:08	6.57 pH	22.45 °C	763.33 µS/cm	0.03 mg/L	10.50 NTU	3.6 mV	14.10 ft	250.00 ml/min
7/13/2023 11:42 AM	36:08	6.56 pH	22.99 °C	768.69 µS/cm	0.03 mg/L	16.20 NTU	-19.3 mV	14.10 ft	250.00 ml/min
7/13/2023 11:47 AM	41:08	6.45 pH	23.29 °C	723.65 µS/cm	0.03 mg/L	16.60 NTU	6.2 mV	14.10 ft	250.00 ml/min
7/13/2023 11:52 AM	46:08	6.54 pH	23.37 °C	768.73 µS/cm	0.04 mg/L	16.00 NTU	14.3 mV	14.10 ft	250.00 ml/min
7/13/2023 11:57 AM	51:08	6.56 pH	23.35 °C	767.51 µS/cm	0.03 mg/L	18.00 NTU	12.2 mV	14.10 ft	250.00 ml/min
7/13/2023 12:02 PM	56:08	6.56 pH	23.59 °C	770.87 µS/cm	0.02 mg/L	16.30 NTU	3.5 mV	14.10 ft	250.00 ml/min

7/13/2023 12:07 PM	01:01:08	6.56 pH	23.26 °C	771.12 µS/cm	0.02 mg/L	20.10 NTU	5.6 mV	14.10 ft	250.00 ml/min
7/13/2023 12:12 PM	01:06:08	6.56 pH	23.45 °C	773.37 µS/cm	0.02 mg/L	16.70 NTU	7.1 mV	14.10 ft	250.00 ml/min
7/13/2023 12:17 PM	01:11:08	6.56 pH	23.36 °C	775.77 µS/cm	0.02 mg/L	13.30 NTU	9.8 mV	14.10 ft	250.00 ml/min
7/13/2023 12:22 PM	01:16:08	6.57 pH	24.10 °C	773.97 µS/cm	0.02 mg/L	11.81 NTU	14.8 mV	14.10 ft	250.00 ml/min
7/13/2023 12:26 PM	01:20:29	6.57 pH	23.62 °C	771.90 µS/cm	0.02 mg/L	10.18 NTU	15.0 mV	14.10 ft	250.00 ml/min
7/13/2023 12:31 PM	01:25:29	6.57 pH	23.66 °C	776.24 µS/cm	0.02 mg/L	9.43 NTU	18.2 mV	14.10 ft	250.00 ml/min
7/13/2023 12:36 PM	01:30:29	6.57 pH	24.30 °C	779.12 µS/cm	0.02 mg/L	7.91 NTU	16.2 mV	14.10 ft	250.00 ml/min
7/13/2023 12:41 PM	01:35:29	6.57 pH	24.48 °C	779.77 µS/cm	0.02 mg/L	4.95 NTU	18.4 mV	14.10 ft	250.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.

Low-Flow Test Report:

Test Date / Time: 7/13/2023 1:16:15 PM
Project: GW6581
Operator Name: Alana Neely

Location Name: PT-10 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 18 ft Total Depth: 28 ft Initial Depth to Water: 14 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 23 ft Estimated Total Volume Pumped: 12 L Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.3 ft	Instrument Used: Aqua TROLL 400 Serial Number: 884187
--	--	--

Test Notes:
Five bottles: Full App III and IV and Geochem

Weather Conditions:
73-91 deg F; sunny

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
7/13/2023 1:16 PM	00:00	7.05 pH	24.25 °C	808.38 µS/cm	0.31 mg/L	11.60 NTU	-135.4 mV	14.30 ft	200.00 ml/min
7/13/2023 1:21 PM	04:45	7.04 pH	22.90 °C	832.12 µS/cm	0.49 mg/L	20.60 NTU	-134.8 mV	14.30 ft	200.00 ml/min
7/13/2023 1:25 PM	09:02	7.05 pH	22.36 °C	827.40 µS/cm	0.12 mg/L	18.10 NTU	-142.1 mV	14.30 ft	200.00 ml/min
7/13/2023 1:30 PM	14:02	7.04 pH	21.87 °C	835.53 µS/cm	0.10 mg/L	13.20 NTU	-136.6 mV	14.30 ft	200.00 ml/min
7/13/2023 1:35 PM	19:02	7.03 pH	22.00 °C	831.33 µS/cm	0.08 mg/L	12.47 NTU	-182.4 mV	14.30 ft	200.00 ml/min
7/13/2023 1:40 PM	24:02	7.03 pH	22.23 °C	834.62 µS/cm	0.06 mg/L	10.64 NTU	-179.2 mV	14.30 ft	200.00 ml/min
7/13/2023 1:45 PM	29:02	7.02 pH	21.83 °C	837.40 µS/cm	0.05 mg/L	9.54 NTU	-126.6 mV	14.30 ft	200.00 ml/min
7/13/2023 1:50 PM	34:02	7.02 pH	22.13 °C	840.48 µS/cm	0.05 mg/L	8.72 NTU	-173.7 mV	14.30 ft	200.00 ml/min
7/13/2023 1:55 PM	39:02	7.02 pH	21.98 °C	834.18 µS/cm	0.04 mg/L	7.59 NTU	-122.1 mV	14.30 ft	200.00 ml/min
7/13/2023 2:00 PM	44:02	7.01 pH	21.89 °C	840.03 µS/cm	0.04 mg/L	6.56 NTU	-118.7 mV	14.30 ft	200.00 ml/min
7/13/2023 2:05 PM	49:02	7.01 pH	22.10 °C	840.92 µS/cm	0.03 mg/L	5.64 NTU	-163.8 mV	14.30 ft	200.00 ml/min
7/13/2023 2:10 PM	54:02	7.01 pH	21.95 °C	842.15 µS/cm	0.03 mg/L	4.94 NTU	-161.5 mV	14.30 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.

Low-Flow Test Report:

Test Date / Time: 8/9/2023 3:28:27 PM
Project: GP-Plant Hammond
Operator Name: Elisabeth McDonnell

Location Name: MW-53 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 26.6 ft Total Depth: 36.35 ft Initial Depth to Water: 16.0 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 31.6 ft Estimated Total Volume Pumped: 15 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.08 ft	Instrument Used: Aqua TROLL 400 Serial Number: 989630
---	--	--

Test Notes:
One bottle: Boron and Molybdenum

Weather Conditions:
Sunny, 72 Degrees F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/9/2023 3:28 PM	00:00	6.58 pH	21.50 °C	811.88 µS/cm	1.19 mg/L	4.93 NTU	46.9 mV	16.07 ft	200.00 ml/min
8/9/2023 3:33 PM	05:00	6.63 pH	21.32 °C	834.15 µS/cm	0.84 mg/L	3.37 NTU	46.6 mV	16.08 ft	200.00 ml/min
8/9/2023 3:38 PM	10:00	6.63 pH	21.42 °C	836.69 µS/cm	1.03 mg/L	1.67 NTU	47.1 mV	16.06 ft	200.00 ml/min
8/9/2023 3:43 PM	15:00	6.64 pH	21.24 °C	839.10 µS/cm	0.93 mg/L	1.01 NTU	58.2 mV	16.07 ft	200.00 ml/min
8/9/2023 3:48 PM	20:00	6.63 pH	21.28 °C	836.21 µS/cm	0.84 mg/L	0.45 NTU	47.3 mV	16.07 ft	200.00 ml/min
8/9/2023 3:53 PM	25:00	6.63 pH	20.90 °C	837.24 µS/cm	0.54 mg/L	0.78 NTU	59.3 mV	16.07 ft	200.00 ml/min
8/9/2023 3:58 PM	30:00	6.63 pH	21.19 °C	835.68 µS/cm	1.45 mg/L	0.29 NTU	60.3 mV	16.08 ft	200.00 ml/min
8/9/2023 4:03 PM	35:00	6.64 pH	21.06 °C	833.61 µS/cm	0.78 mg/L	0.04 NTU	60.1 mV	16.08 ft	200.00 ml/min
8/9/2023 4:08 PM	40:00	6.63 pH	21.03 °C	828.43 µS/cm	1.29 mg/L	0.00 NTU	60.7 mV	16.08 ft	200.00 ml/min
8/9/2023 4:13 PM	45:00	6.63 pH	20.94 °C	827.95 µS/cm	0.65 mg/L	0.04 NTU	60.6 mV	16.08 ft	200.00 ml/min
8/9/2023 4:18 PM	50:00	6.63 pH	20.17 °C	756.61 µS/cm	2.48 mg/L	0.00 NTU	49.0 mV	16.07 ft	200.00 ml/min
8/9/2023 4:23 PM	55:00	6.65 pH	19.90 °C	754.42 µS/cm	1.81 mg/L	0.00 NTU	48.3 mV	16.08 ft	200.00 ml/min
8/9/2023 4:28 PM	01:00:00	6.63 pH	19.72 °C	846.76 µS/cm	0.35 mg/L	0.00 NTU	59.5 mV	16.08 ft	200.00 ml/min
8/9/2023 4:33 PM	01:05:00	6.63 pH	19.64 °C	847.37 µS/cm	0.29 mg/L	0.01 NTU	47.3 mV	16.07 ft	200.00 ml/min
8/9/2023 4:38 PM	01:10:00	6.63 pH	19.60 °C	848.27 µS/cm	0.24 mg/L		57.3 mV	16.08 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-MW-53	Grab.

Low-Flow Test Report:

Test Date / Time: 8/9/2023 3:26:03 PM
Project: GP-Plant Hammond
Operator Name: Thomas Kessler

Location Name: MW-54 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 28.3 ft Total Depth: 38.30 ft Initial Depth to Water: 24.15 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 33.3 ft Estimated Total Volume Pumped: 9 liter Flow Cell Volume: 90 ml Final Flow Rate: 100 ml/min Final Draw Down: 0.1ft	Instrument Used: Aqua TROLL 400 Serial Number: 850724
--	---	--

Test Notes:
One bottle: Boron and Arsenic

Weather Conditions:
Sunny, 85 Degrees F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/9/2023 3:26 PM	00:00	5.01 pH	26.69 °C	329.38 µS/cm	1.73 mg/L	5.12 NTU	171.8 mV	24.25 ft	100.00 ml/min
8/9/2023 3:31 PM	05:00	4.98 pH	25.95 °C	330.64 µS/cm	1.70 mg/L	6.87 NTU	149.1 mV	24.25 ft	100.00 ml/min
8/9/2023 3:36 PM	10:00	4.99 pH	25.33 °C	330.08 µS/cm	1.65 mg/L	6.29 NTU	185.3 mV	24.25 ft	100.00 ml/min
8/9/2023 3:41 PM	15:00	5.02 pH	24.97 °C	332.29 µS/cm	1.57 mg/L	5.76 NTU	180.6 mV	24.25 ft	100.00 ml/min
8/9/2023 3:46 PM	20:00	5.03 pH	24.61 °C	330.02 µS/cm	1.53 mg/L	6.69 NTU	176.5 mV	24.25 ft	100.00 ml/min
8/9/2023 3:51 PM	25:00	5.10 pH	23.90 °C	331.08 µS/cm	1.45 mg/L	4.98 NTU	172.1 mV	24.25 ft	100.00 ml/min
8/9/2023 3:56 PM	30:00	5.18 pH	23.88 °C	334.85 µS/cm	1.41 mg/L	4.23 NTU	132.1 mV	24.25 ft	100.00 ml/min
8/9/2023 4:01 PM	35:00	5.31 pH	23.56 °C	342.94 µS/cm	1.32 mg/L	4.00 NTU	158.5 mV	24.25 ft	100.00 ml/min
8/9/2023 4:06 PM	40:00	5.50 pH	23.74 °C	361.26 µS/cm	1.20 mg/L	3.98 NTU	152.1 mV	24.25 ft	100.00 ml/min
8/9/2023 4:11 PM	45:00	5.67 pH	23.43 °C	382.99 µS/cm	1.07 mg/L	3.50 NTU	112.1 mV	24.25 ft	100.00 ml/min
8/9/2023 4:16 PM	50:00	5.80 pH	23.60 °C	406.33 µS/cm	0.95 mg/L	3.57 NTU	136.0 mV	24.25 ft	100.00 ml/min
8/9/2023 4:21 PM	55:00	5.89 pH	23.28 °C	422.58 µS/cm	0.86 mg/L	1.33 NTU	132.8 mV	24.25 ft	100.00 ml/min
8/9/2023 4:26 PM	01:00:00	5.98 pH	23.21 °C	439.54 µS/cm	0.78 mg/L	1.25 NTU	99.6 mV	24.25 ft	100.00 ml/min

8/9/2023 4:31 PM	01:05:00	6.04 pH	23.07 °C	456.26 µS/cm	0.73 mg/L	1.31 NTU	124.2 mV	24.25 ft	100.00 ml/min
8/9/2023 4:36 PM	01:10:00	6.10 pH	23.02 °C	466.92 µS/cm	0.68 mg/L	1.12 NTU	95.3 mV	24.25 ft	100.00 ml/min
8/9/2023 4:41 PM	01:15:00	6.15 pH	22.89 °C	476.56 µS/cm	0.63 mg/L	0.86 NTU	118.0 mV	24.25 ft	100.00 ml/min
8/9/2023 4:46 PM	01:20:00	6.18 pH	22.86 °C	488.16 µS/cm	0.60 mg/L	0.36 NTU	117.5 mV	24.25 ft	100.00 ml/min

Samples

Sample ID:	Description:
HAM-MW-54	Grab.

Low-Flow Test Report:

Test Date / Time: 8/9/2023 5:24:44 PM
Project: GP-Plant Hammond
Operator Name: Thomas Kessler

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 38.6 ft Total Depth: 47.94 ft Initial Depth to Water: 25.05 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 43.8 ft Estimated Total Volume Pumped: 8 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 850724
--	---	--

Test Notes:
Five bottles: Baseline Sampling and Major Ions

Weather Conditions:
Cloudy, 80 Degrees F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/9/2023 5:24 PM	00:00	6.69 pH	22.70 °C	979.72 µS/cm	0.65 mg/L	6.30 NTU	-88.9 mV	25.10 ft	200.00 ml/min
8/9/2023 5:29 PM	05:00	6.73 pH	21.85 °C	986.58 µS/cm	0.43 mg/L	4.87 NTU	-89.0 mV	25.10 ft	200.00 ml/min
8/9/2023 5:34 PM	10:00	6.76 pH	21.55 °C	992.34 µS/cm	0.48 mg/L	4.83 NTU	-89.8 mV	25.10 ft	200.00 ml/min
8/9/2023 5:39 PM	15:00	6.78 pH	21.44 °C	993.38 µS/cm	0.33 mg/L	5.08 NTU	-107.7 mV	25.10 ft	200.00 ml/min
8/9/2023 5:44 PM	20:00	6.79 pH	21.42 °C	1,008.3 µS/cm	0.41 mg/L	1.91 NTU	-90.6 mV	25.10 ft	200.00 ml/min
8/9/2023 5:49 PM	25:00	6.80 pH	21.36 °C	1,010.3 µS/cm	0.30 mg/L	0.80 NTU	-90.8 mV	25.10 ft	200.00 ml/min
8/9/2023 5:54 PM	30:00	6.82 pH	21.19 °C	1,012.4 µS/cm	0.40 mg/L	0.18 NTU	-90.9 mV	25.10 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-07	Grab.

Low-Flow Test Report:

Test Date / Time: 8/9/2023 10:03:54 AM
Project: GP-Plant Hammond
Operator Name: Elisabeth McDonnell

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 28.8 ft Total Depth: 42.0 ft Initial Depth to Water: 23.6 ft	Pump Type: Bladder pump Tubing Type: Peri Pump Intake From TOC: 37.3 ft Estimated Total Volume Pumped: 8 liter Flow Cell Volume: 90 ml Final Flow Rate: 160 ml/min Final Draw Down: 0.04 ft	Instrument Used: Aqua TROLL 400 Serial Number: 989630
---	--	--

Test Notes:
Five bottles: Baseline Sampling and Major Ions

Weather Conditions:
Cloudy, 80 Degrees F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/9/2023 10:03 AM	00:00	6.80 pH	20.72 °C	943.04 µS/cm	2.15 mg/L	15.50 NTU	-57.8 mV	23.64 ft	160.00 ml/min
8/9/2023 10:08 AM	05:00	6.81 pH	20.71 °C	915.43 µS/cm	1.51 mg/L	10.90 NTU	-60.5 mV	23.63 ft	160.00 ml/min
8/9/2023 10:13 AM	10:00	6.81 pH	20.73 °C	905.45 µS/cm	1.62 mg/L	7.91 NTU	-61.7 mV	23.65 ft	160.00 ml/min
8/9/2023 10:18 AM	15:00	6.82 pH	20.59 °C	908.95 µS/cm	2.77 mg/L	4.08 NTU	-82.5 mV	23.64 ft	160.00 ml/min
8/9/2023 10:23 AM	20:00	6.82 pH	20.63 °C	911.77 µS/cm	1.38 mg/L	4.45 NTU	-84.8 mV	23.64 ft	160.00 ml/min
8/9/2023 10:28 AM	25:00	6.82 pH	20.57 °C	907.31 µS/cm	1.20 mg/L	4.04 NTU	-64.7 mV	23.63 ft	160.00 ml/min
8/9/2023 10:33 AM	30:00	6.83 pH	20.52 °C	905.19 µS/cm	0.97 mg/L	2.96 NTU	-85.5 mV	23.63 ft	160.00 ml/min
8/9/2023 10:38 AM	35:00	6.83 pH	20.58 °C	911.05 µS/cm	0.84 mg/L	3.40 NTU	-64.5 mV	23.63 ft	160.00 ml/min
8/9/2023 10:43 AM	40:00	6.82 pH	20.60 °C	909.15 µS/cm	0.94 mg/L	3.98 NTU	-84.4 mV	23.64 ft	160.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.
HAM-AP1-FD-06	Grab.

Low-Flow Test Report:

Test Date / Time: 8/9/2023 1:27:10 PM
Project: GP-Plant Hammond
Operator Name: Elisabeth McDonnell

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 28.8 ft Total Depth: 30.75 ft Initial Depth to Water: 14.99 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 26 ft Estimated Total Volume Pumped: 1.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 989630
--	--	--

Test Notes:
Five bottles: Baseline Sampling and Major Ions

Weather Conditions:
Cloudy, 80 Degrees F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/9/2023 1:27 PM	00:00	6.76 pH	21.93 °C	745.27 µS/cm	4.47 mg/L	2.02 NTU	56.2 mV	14.99 ft	200.00 ml/min
8/9/2023 1:32 PM	05:00	6.81 pH	21.68 °C	771.52 µS/cm	3.35 mg/L	1.11 NTU	52.3 mV	14.99 ft	200.00 ml/min
8/9/2023 1:37 PM	10:00	6.85 pH	21.44 °C	786.50 µS/cm	2.58 mg/L	1.46 NTU	28.7 mV	14.99 ft	200.00 ml/min
8/9/2023 1:42 PM	15:00	6.86 pH	21.30 °C	797.33 µS/cm	6.17 mg/L	2.12 NTU	16.0 mV	14.99 ft	200.00 ml/min
8/9/2023 1:47 PM	20:00	6.87 pH	21.28 °C	797.79 µS/cm	2.58 mg/L	2.86 NTU	19.9 mV	14.99 ft	200.00 ml/min
8/9/2023 1:52 PM	25:00	6.88 pH	21.32 °C	806.94 µS/cm	3.88 mg/L	3.70 NTU	15.9 mV	14.99 ft	200.00 ml/min
8/9/2023 1:57 PM	30:00	6.88 pH	21.25 °C	797.98 µS/cm	0.84 mg/L	3.86 NTU	11.7 mV	14.99 ft	200.00 ml/min
8/9/2023 2:02 PM	35:00	6.88 pH	21.20 °C	794.19 µS/cm	0.80 mg/L	3.31 NTU	10.9 mV	14.99 ft	200.00 ml/min
8/9/2023 2:07 PM	40:00	6.88 pH	21.03 °C	791.25 µS/cm	1.44 mg/L	2.06 NTU	10.4 mV	14.99 ft	200.00 ml/min
8/9/2023 2:12 PM	45:00	6.89 pH	20.96 °C	770.10 µS/cm	0.72 mg/L	1.72 NTU	9.1 mV	14.99 ft	200.00 ml/min
8/9/2023 2:17 PM	50:00	6.88 pH	20.97 °C	792.63 µS/cm	0.55 mg/L	0.98 NTU	9.9 mV	14.99 ft	200.00 ml/min
8/9/2023 2:22 PM	55:00	6.89 pH	21.06 °C	791.96 µS/cm	1.03 mg/L	1.51 NTU	1.0 mV	14.99 ft	200.00 ml/min
8/9/2023 2:27 PM	01:00:00	6.89 pH	21.29 °C	791.26 µS/cm	0.63 mg/L	0.62 NTU	12.2 mV	14.99 ft	200.00 ml/min
8/9/2023 2:32 PM	01:05:00	6.89 pH	21.71 °C	825.29 µS/cm	0.44 mg/L	0.44 NTU	14.1 mV	14.99 ft	200.00 ml/min
8/9/2023 2:37 PM	01:10:00	6.89 pH	21.59 °C	826.86 µS/cm	0.58 mg/L	0.56 NTU	14.4 mV	14.99 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.

Low-Flow Test Report:

Test Date / Time: 8/9/2023 12:22:52 PM
Project: GP-Plant Hammond
Operator Name: Elisabeth McDonnell

Location Name: PT-10 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20 ft Total Depth: 31.75 ft Initial Depth to Water: 15.05 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 25 ft Estimated Total Volume Pumped: 5.8 liter Flow Cell Volume: 90 ml Final Flow Rate: 160 ml/min Final Draw Down: 0.13 ft	Instrument Used: Aqua TROLL 400 Serial Number: 989630
--	---	--

Test Notes:
Five bottles: Baseline Sampling and Major Ions

Weather Conditions:
Cloudy, 80 Degrees F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/9/2023 12:22 PM	00:00	7.14 pH	22.18 °C	811.17 µS/cm	1.15 mg/L	24.10 NTU	-75.4 mV	15.18 ft	160.00 ml/min
8/9/2023 12:27 PM	05:00	7.15 pH	22.04 °C	798.04 µS/cm	0.38 mg/L	16.60 NTU	-75.5 mV	15.18 ft	160.00 ml/min
8/9/2023 12:32 PM	10:00	7.16 pH	21.96 °C	800.28 µS/cm	0.37 mg/L	11.80 NTU	-99.1 mV	15.18 ft	160.00 ml/min
8/9/2023 12:37 PM	15:00	7.16 pH	22.00 °C	793.73 µS/cm	0.33 mg/L	4.09 NTU	-78.0 mV	15.18 ft	160.00 ml/min
8/9/2023 12:42 PM	20:00	7.17 pH	21.46 °C	790.02 µS/cm	0.24 mg/L	4.11 NTU	-101.9 mV	15.18 ft	160.00 ml/min
8/9/2023 12:47 PM	25:00	7.18 pH	21.86 °C	782.36 µS/cm	0.16 mg/L	2.36 NTU	-81.4 mV	15.18 ft	160.00 ml/min
8/9/2023 12:52 PM	30:00	7.18 pH	21.79 °C	770.46 µS/cm	0.12 mg/L	4.55 NTU	-80.9 mV	15.18 ft	160.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.

Low-Flow Test Report:

Test Date / Time: 5/2/2024 1:35:02 PM
Project: Plant Hammond
Operator Name: Zain Webb

Location Name: INW-04 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 34.95 ft Total Depth: 44.95 ft Initial Depth to Water: 24.73 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 39.95 ft Estimated Total Volume Pumped: 9 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.67 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
---	--	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).
Fe2+ = 6 mg/L.

Weather Conditions:
Clear, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/2/2024 1:35 PM	00:00	6.74 pH	20.32 °C	671.78 µS/cm	0.54 mg/L	23.40 NTU	-103.0 mV	25.40 ft	200.00 ml/min
5/2/2024 1:40 PM	05:00	6.75 pH	20.43 °C	671.91 µS/cm	0.62 mg/L	11.80 NTU	-101.3 mV	25.40 ft	200.00 ml/min
5/2/2024 1:45 PM	10:00	6.76 pH	20.48 °C	673.75 µS/cm	0.65 mg/L	9.63 NTU	-101.9 mV	25.40 ft	200.00 ml/min
5/2/2024 1:50 PM	15:00	6.76 pH	20.45 °C	673.00 µS/cm	0.69 mg/L	8.21 NTU	-99.9 mV	25.40 ft	200.00 ml/min
5/2/2024 1:55 PM	20:00	6.77 pH	20.61 °C	672.37 µS/cm	0.67 mg/L	8.39 NTU	-99.5 mV	25.40 ft	200.00 ml/min
5/2/2024 2:00 PM	25:00	6.77 pH	20.66 °C	673.40 µS/cm	0.82 mg/L	5.71 NTU	-95.5 mV	25.40 ft	200.00 ml/min
5/2/2024 2:05 PM	30:00	6.78 pH	20.70 °C	674.20 µS/cm	0.76 mg/L	5.80 NTU	-97.4 mV	25.40 ft	200.00 ml/min
5/2/2024 2:10 PM	35:00	6.78 pH	20.39 °C	673.60 µS/cm	0.73 mg/L	5.17 NTU	-96.2 mV	25.40 ft	200.00 ml/min
5/2/2024 2:15 PM	40:00	6.78 pH	20.57 °C	674.04 µS/cm	0.72 mg/L	4.11 NTU	-96.1 mV	25.40 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-INW-04	Grab.

Low-Flow Test Report:

Test Date / Time: 5/2/2024 9:20:40 AM
Project: Plant Hammond
Operator Name: Zain Webb

Location Name: INW-05 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 34.65 ft Total Depth: 44.65 ft Initial Depth to Water: 24.81 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 39.65 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.04 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
--	---	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).
Fe2+ > 10 mg/L.

Weather Conditions:
Clear, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/2/2024 9:20 AM	00:00	6.82 pH	18.40 °C	705.59 µS/cm	0.18 mg/L	30.80 NTU	-112.4 mV	24.85 ft	200.00 ml/min
5/2/2024 9:25 AM	05:00	6.85 pH	18.26 °C	706.64 µS/cm	0.15 mg/L	17.10 NTU	-123.7 mV	24.85 ft	200.00 ml/min
5/2/2024 9:30 AM	10:00	6.87 pH	18.25 °C	708.86 µS/cm	0.12 mg/L	11.10 NTU	-125.7 mV	24.85 ft	200.00 ml/min
5/2/2024 9:35 AM	15:00	6.88 pH	18.26 °C	707.77 µS/cm	0.10 mg/L	7.39 NTU	-120.8 mV	24.85 ft	200.00 ml/min
5/2/2024 9:40 AM	20:00	6.88 pH	18.25 °C	706.48 µS/cm	0.09 mg/L	5.67 NTU	-126.4 mV	24.85 ft	200.00 ml/min
5/2/2024 9:45 AM	25:00	6.87 pH	18.16 °C	708.47 µS/cm	0.07 mg/L	4.21 NTU	-126.6 mV	24.85 ft	200.00 ml/min
5/2/2024 9:50 AM	30:00	6.87 pH	18.17 °C	706.51 µS/cm	0.06 mg/L	4.15 NTU	-120.9 mV	24.85 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-INW-05	Grab.

Low-Flow Test Report:

Test Date / Time: 5/2/2024 9:29:36 AM
Project: Plant Hammond
Operator Name: Elisabeth Russell

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 31.93 ft Total Depth: 41.93 ft Initial Depth to Water: 25.45 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 36 ft Estimated Total Volume Pumped: 38 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.01 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883546
---	---	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).
Fe2+ = 6 mg/L.

Weather Conditions:
Clear, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/2/2024 9:29 AM	00:00	6.35 pH	24.56 °C	582.44 µS/cm	1.54 mg/L	24.60 NTU	134.4 mV	25.45 ft	200.00 ml/min
5/2/2024 9:34 AM	05:00	6.44 pH	22.45 °C	606.19 µS/cm	2.15 mg/L	22.00 NTU	137.5 mV	25.46 ft	200.00 ml/min
5/2/2024 9:39 AM	10:00	6.48 pH	21.66 °C	613.75 µS/cm	2.38 mg/L	19.20 NTU	139.2 mV	25.46 ft	200.00 ml/min
5/2/2024 9:44 AM	15:00	6.51 pH	21.55 °C	618.36 µS/cm	2.47 mg/L	17.20 NTU	145.2 mV	25.46 ft	200.00 ml/min
5/2/2024 9:49 AM	20:00	6.53 pH	21.04 °C	637.76 µS/cm	2.53 mg/L	11.90 NTU	148.4 mV	25.46 ft	200.00 ml/min
5/2/2024 9:54 AM	25:00	6.54 pH	20.95 °C	632.45 µS/cm	2.73 mg/L	10.86 NTU	152.0 mV	25.46 ft	200.00 ml/min
5/2/2024 9:59 AM	30:00	6.52 pH	20.55 °C	644.03 µS/cm	2.33 mg/L	11.83 NTU	154.4 mV	25.46 ft	200.00 ml/min
5/2/2024 10:04 AM	35:00	6.51 pH	20.60 °C	646.21 µS/cm	2.05 mg/L	10.99 NTU	157.7 mV	25.46 ft	200.00 ml/min
5/2/2024 10:09 AM	40:00	6.50 pH	20.67 °C	656.01 µS/cm	1.48 mg/L	11.17 NTU	161.7 mV	25.46 ft	200.00 ml/min
5/2/2024 10:14 AM	45:00	6.51 pH	20.73 °C	662.60 µS/cm	1.68 mg/L	8.91 NTU	164.0 mV	25.46 ft	200.00 ml/min
5/2/2024 10:19 AM	50:00	6.53 pH	20.77 °C	662.47 µS/cm	2.04 mg/L	9.98 NTU	160.1 mV	25.46 ft	200.00 ml/min
5/2/2024 10:24 AM	55:00	6.54 pH	20.83 °C	664.54 µS/cm	2.24 mg/L	9.44 NTU	159.7 mV	25.46 ft	200.00 ml/min
5/2/2024 10:29 AM	01:00:00	6.55 pH	20.90 °C	664.65 µS/cm	2.35 mg/L	9.50 NTU	155.9 mV	25.46 ft	200.00 ml/min
5/2/2024 10:34 AM	01:05:00	6.55 pH	20.93 °C	668.54 µS/cm	2.35 mg/L	9.41 NTU	159.4 mV	25.46 ft	200.00 ml/min
5/2/2024 10:39 AM	01:10:00	6.56 pH	20.99 °C	669.88 µS/cm	2.36 mg/L	9.23 NTU	158.5 mV	25.46 ft	200.00 ml/min

5/2/2024 10:44 AM	01:15:00	6.56 pH	20.99 °C	671.50 µS/cm	2.38 mg/L	7.89 NTU	158.0 mV	25.46 ft	200.00 ml/min
5/2/2024 10:49 AM	01:20:00	6.56 pH	21.02 °C	675.48 µS/cm	2.38 mg/L	8.83 NTU	157.0 mV	25.46 ft	200.00 ml/min
5/2/2024 10:54 AM	01:25:00	6.56 pH	21.08 °C	672.45 µS/cm	2.44 mg/L	8.09 NTU	156.4 mV	25.46 ft	200.00 ml/min
5/2/2024 10:59 AM	01:30:00	6.57 pH	21.08 °C	676.50 µS/cm	2.41 mg/L	8.17 NTU	161.1 mV	25.46 ft	200.00 ml/min
5/2/2024 11:02 AM	01:32:52	6.57 pH	21.23 °C	675.23 µS/cm	2.42 mg/L	8.20 NTU	153.9 mV	25.46 ft	200.00 ml/min
5/2/2024 11:07 AM	01:37:52	6.57 pH	21.16 °C	677.88 µS/cm	2.45 mg/L	8.05 NTU	156.3 mV	25.46 ft	200.00 ml/min
5/2/2024 11:12 AM	01:42:52	6.58 pH	21.20 °C	679.81 µS/cm	2.45 mg/L	7.99 NTU	151.9 mV	25.46 ft	200.00 ml/min
5/2/2024 11:17 AM	01:47:52	6.56 pH	21.26 °C	675.06 µS/cm	2.45 mg/L	7.87 NTU	157.4 mV	25.46 ft	200.00 ml/min
5/2/2024 11:22 AM	01:52:52	6.55 pH	21.23 °C	675.85 µS/cm	2.14 mg/L	7.41 NTU	157.0 mV	25.46 ft	200.00 ml/min
5/2/2024 11:27 AM	01:57:52	6.53 pH	21.26 °C	675.02 µS/cm	1.84 mg/L	7.03 NTU	156.1 mV	25.46 ft	200.00 ml/min
5/2/2024 11:32 AM	02:02:52	6.53 pH	21.22 °C	677.94 µS/cm	1.62 mg/L	6.98 NTU	156.0 mV	25.46 ft	200.00 ml/min
5/2/2024 11:37 AM	02:07:52	6.52 pH	21.23 °C	678.86 µS/cm	1.38 mg/L	6.76 NTU	156.6 mV	25.46 ft	200.00 ml/min
5/2/2024 11:42 AM	02:12:52	6.53 pH	21.24 °C	681.47 µS/cm	1.32 mg/L	7.27 NTU	158.1 mV	25.46 ft	200.00 ml/min
5/2/2024 11:47 AM	02:17:52	6.53 pH	21.25 °C	680.18 µS/cm	1.22 mg/L	6.49 NTU	152.3 mV	25.46 ft	200.00 ml/min
5/2/2024 11:52 AM	02:22:52	6.53 pH	21.26 °C	683.39 µS/cm	1.12 mg/L	6.78 NTU	150.0 mV	25.46 ft	200.00 ml/min
5/2/2024 11:57 AM	02:27:52	6.53 pH	21.33 °C	684.53 µS/cm	0.97 mg/L	7.09 NTU	150.6 mV	25.46 ft	200.00 ml/min
5/2/2024 12:01 PM	02:31:27	6.52 pH	21.44 °C	683.50 µS/cm	0.93 mg/L	6.89 NTU	153.2 mV	25.46 ft	200.00 ml/min
5/2/2024 12:06 PM	02:36:27	6.53 pH	21.37 °C	686.70 µS/cm	0.89 mg/L	7.03 NTU	154.3 mV	25.46 ft	200.00 ml/min
5/2/2024 12:11 PM	02:41:27	6.53 pH	21.44 °C	686.68 µS/cm	0.84 mg/L	7.99 NTU	157.8 mV	25.46 ft	200.00 ml/min
5/2/2024 12:16 PM	02:46:27	6.53 pH	21.42 °C	687.58 µS/cm	0.80 mg/L	6.26 NTU	155.5 mV	25.46 ft	200.00 ml/min
5/2/2024 12:21 PM	02:51:27	6.52 pH	21.36 °C	686.79 µS/cm	0.83 mg/L	6.77 NTU	158.3 mV	25.46 ft	200.00 ml/min
5/2/2024 12:26 PM	02:56:27	6.53 pH	21.35 °C	687.71 µS/cm	0.96 mg/L	7.03 NTU	151.0 mV	25.46 ft	200.00 ml/min
5/2/2024 12:31 PM	03:01:27	6.53 pH	21.27 °C	691.07 µS/cm	1.01 mg/L	8.60 NTU	154.4 mV	25.46 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.

Low-Flow Test Report:

Test Date / Time: 5/2/2024 11:06:29 AM
Project: Plant Hammond
Operator Name: Zain Webb

Location Name: PT-14 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 34.65 ft Total Depth: 44.65 ft Initial Depth to Water: 25.1 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 39.65 ft Estimated Total Volume Pumped: 12 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
--	---	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).
Fe2+ = 6 mg/L.

Weather Conditions:
Clear, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/2/2024 11:06 AM	00:00	6.71 pH	22.40 °C	594.65 µS/cm	0.45 mg/L	49.50 NTU	-88.9 mV	25.10 ft	200.00 ml/min
5/2/2024 11:11 AM	05:00	6.76 pH	19.29 °C	630.14 µS/cm	0.19 mg/L	41.80 NTU	-99.5 mV	25.10 ft	200.00 ml/min
5/2/2024 11:16 AM	10:00	6.79 pH	19.21 °C	631.68 µS/cm	0.16 mg/L	31.20 NTU	-108.1 mV	25.10 ft	200.00 ml/min
5/2/2024 11:21 AM	15:00	6.81 pH	19.12 °C	633.14 µS/cm	0.13 mg/L	14.60 NTU	-109.5 mV	25.10 ft	200.00 ml/min
5/2/2024 11:26 AM	20:00	6.82 pH	19.06 °C	633.47 µS/cm	0.11 mg/L	11.80 NTU	-111.6 mV	25.10 ft	200.00 ml/min
5/2/2024 11:31 AM	25:00	6.82 pH	19.03 °C	632.62 µS/cm	0.08 mg/L	8.39 NTU	-112.2 mV	25.10 ft	200.00 ml/min
5/2/2024 11:36 AM	30:00	6.83 pH	19.02 °C	634.27 µS/cm	0.08 mg/L	7.05 NTU	-113.7 mV	25.10 ft	200.00 ml/min
5/2/2024 11:41 AM	35:00	6.83 pH	19.01 °C	635.47 µS/cm	0.07 mg/L	9.44 NTU	-114.8 mV	25.10 ft	200.00 ml/min
5/2/2024 11:46 AM	40:00	6.83 pH	19.01 °C	635.06 µS/cm	0.06 mg/L	6.59 NTU	-115.5 mV	25.10 ft	200.00 ml/min
5/2/2024 11:51 AM	45:00	6.83 pH	19.13 °C	634.75 µS/cm	0.07 mg/L	8.16 NTU	-116.0 mV	25.10 ft	200.00 ml/min
5/2/2024 11:56 AM	50:00	6.83 pH	19.10 °C	636.34 µS/cm	0.05 mg/L	5.51 NTU	-116.3 mV	25.10 ft	200.00 ml/min
5/2/2024 12:01 PM	55:00	6.83 pH	19.09 °C	636.04 µS/cm	0.05 mg/L	4.27 NTU	-116.5 mV	25.10 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-14	Grab.
HAM-AP1-FD-01	Grab.

Low-Flow Test Report:

Test Date / Time: 5/2/2024 2:09:59 PM
Project: Plant Hammond
Operator Name: Elisabeth Russell

Location Name: PT-15 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 34.54 ft Total Depth: 44.54 ft Initial Depth to Water: 25.05 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 35 ft Estimated Total Volume Pumped: 19.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 250 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883546
--	--	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).
Fe2+ = 3 mg/L.

Weather Conditions:
Clear, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/2/2024 2:09 PM	00:00	6.94 pH	24.23 °C	853.70 µS/cm	0.24 mg/L	32.40 NTU	85.0 mV	25.05 ft	200.00 ml/min
5/2/2024 2:14 PM	05:00	6.93 pH	22.42 °C	874.49 µS/cm	0.15 mg/L	17.40 NTU	98.0 mV	25.07 ft	200.00 ml/min
5/2/2024 2:19 PM	10:00	6.94 pH	22.11 °C	874.61 µS/cm	0.12 mg/L	12.18 NTU	106.1 mV	25.10 ft	200.00 ml/min
5/2/2024 2:24 PM	15:00	6.95 pH	22.02 °C	874.12 µS/cm	0.09 mg/L	12.24 NTU	109.4 mV	25.10 ft	200.00 ml/min
5/2/2024 2:29 PM	20:00	6.95 pH	22.09 °C	875.98 µS/cm	0.07 mg/L	10.40 NTU	108.5 mV	25.10 ft	200.00 ml/min
5/2/2024 2:34 PM	25:00	6.95 pH	22.18 °C	872.33 µS/cm	0.06 mg/L	10.34 NTU	108.1 mV	25.10 ft	200.00 ml/min
5/2/2024 2:39 PM	30:00	6.95 pH	22.40 °C	870.02 µS/cm	0.05 mg/L	9.37 NTU	104.0 mV	25.10 ft	200.00 ml/min
5/2/2024 2:44 PM	35:00	6.95 pH	22.51 °C	864.36 µS/cm	0.04 mg/L	8.99 NTU	102.7 mV	25.10 ft	200.00 ml/min
5/2/2024 2:49 PM	40:00	6.95 pH	22.46 °C	862.10 µS/cm	0.03 mg/L	9.39 NTU	103.2 mV	25.10 ft	200.00 ml/min
5/2/2024 2:54 PM	45:00	6.95 pH	22.50 °C	860.83 µS/cm	0.01 mg/L	9.03 NTU	99.8 mV	25.10 ft	200.00 ml/min
5/2/2024 2:59 PM	50:00	6.95 pH	22.27 °C	864.40 µS/cm	0.01 mg/L	8.88 NTU	99.3 mV	25.10 ft	200.00 ml/min
5/2/2024 3:04 PM	55:00	6.95 pH	22.21 °C	865.32 µS/cm	0.01 mg/L	8.36 NTU	98.5 mV	25.10 ft	200.00 ml/min
5/2/2024 3:09 PM	01:00:00	6.96 pH	21.94 °C	864.66 µS/cm	0.00 mg/L	8.70 NTU	94.2 mV	25.10 ft	250.00 ml/min
5/2/2024 3:14 PM	01:05:00	6.95 pH	21.49 °C	869.85 µS/cm	-0.02 mg/L	6.73 NTU	96.4 mV	25.10 ft	250.00 ml/min
5/2/2024 3:19 PM	01:10:00	6.95 pH	21.74 °C	869.26 µS/cm	-0.02 mg/L	5.29 NTU	90.9 mV	25.10 ft	250.00 ml/min

5/2/2024 3:24 PM	01:15:00	6.95 pH	21.80 °C	868.16 µS/cm	-0.03 mg/L	4.37 NTU	93.6 mV	25.10 ft	250.00 ml/min
5/2/2024 3:29 PM	01:20:00	6.95 pH	21.84 °C	866.31 µS/cm	-0.03 mg/L	3.78 NTU	93.8 mV	25.10 ft	250.00 ml/min
5/2/2024 3:34 PM	01:25:00	6.95 pH	21.71 °C	868.60 µS/cm	-0.03 mg/L	2.99 NTU	93.8 mV	25.10 ft	250.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-15	Grab

Low-Flow Test Report:

Test Date / Time: 5/9/2024 2:23:35 PM
Project: Plant Hammond
Operator Name: Anthony Szwast

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 37.75 ft Total Depth: 47.75 ft Initial Depth to Water: 25.32 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 42.75 ft Estimated Total Volume Pumped: 4 liter Flow Cell Volume: 90 ml Final Flow Rate: 100 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 850751
---	---	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).
Total Fe > 10 mg/L.
Fe2+ = 3.5 mg/L.

Weather Conditions:
Cloudy, 70 deg. F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/9/2024 2:23 PM	00:00	6.75 pH	20.49 °C	666.44 µS/cm	2.66 mg/L	30.60 NTU	-78.1 mV	25.26 ft	100.00 ml/min
5/9/2024 2:28 PM	05:00	6.76 pH	20.66 °C	661.58 µS/cm	3.13 mg/L	25.00 NTU	-81.9 mV	25.34 ft	100.00 ml/min
5/9/2024 2:33 PM	10:00	6.77 pH	20.43 °C	663.91 µS/cm	2.04 mg/L	8.90 NTU	-89.2 mV	25.35 ft	100.00 ml/min
5/9/2024 2:38 PM	15:00	6.82 pH	20.28 °C	664.46 µS/cm	0.56 mg/L	1.83 NTU	-100.2 mV	25.35 ft	100.00 ml/min
5/9/2024 2:43 PM	20:00	6.85 pH	19.99 °C	665.10 µS/cm	0.38 mg/L	0.87 NTU	-108.4 mV	25.35 ft	100.00 ml/min
5/9/2024 2:48 PM	25:00	6.86 pH	20.06 °C	665.95 µS/cm	0.35 mg/L	1.04 NTU	-100.8 mV	25.35 ft	100.00 ml/min
5/9/2024 2:53 PM	30:00	6.86 pH	20.53 °C	665.99 µS/cm	0.37 mg/L	1.06 NTU	-100.6 mV	25.35 ft	100.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-07	Grab.

Low-Flow Test Report:

Test Date / Time: 5/9/2024 4:10:09 PM
Project: Plant Hammond
Operator Name: Anthony Szwast

Location Name: PT-13 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35 ft Total Depth: 45 ft Initial Depth to Water: 24.85 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 3.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 100 ml/min Final Draw Down: 0.01 ft	Instrument Used: Aqua TROLL 400 Serial Number: 850751
---	--	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).
Total Fe > 10 mg/L.
Fe2+ = 4.0 mg/L.

Weather Conditions:
Partly cloudy, 75 deg. F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/9/2024 4:10 PM	00:00	6.76 pH	25.40 °C	658.97 µS/cm	0.92 mg/L	62.20 NTU	-109.5 mV	24.84 ft	100.00 ml/min
5/9/2024 4:15 PM	05:00	6.81 pH	22.00 °C	665.97 µS/cm	0.50 mg/L	21.30 NTU	-106.4 mV	24.87 ft	100.00 ml/min
5/9/2024 4:20 PM	10:00	6.83 pH	21.25 °C	672.24 µS/cm	0.34 mg/L	11.00 NTU	-113.2 mV	24.84 ft	100.00 ml/min
5/9/2024 4:25 PM	15:00	6.84 pH	21.06 °C	669.58 µS/cm	0.28 mg/L	8.58 NTU	-112.5 mV	24.84 ft	100.00 ml/min
5/9/2024 4:30 PM	20:00	6.84 pH	20.87 °C	670.23 µS/cm	0.22 mg/L	2.95 NTU	-105.5 mV	24.85 ft	100.00 ml/min
5/9/2024 4:35 PM	25:00	6.84 pH	20.77 °C	668.65 µS/cm	0.18 mg/L	2.98 NTU	-104.6 mV	24.86 ft	100.00 ml/min
5/9/2024 4:40 PM	30:00	6.84 pH	20.75 °C	670.23 µS/cm	0.16 mg/L	2.27 NTU	-104.0 mV	24.86 ft	100.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-13	Grab.

Low-Flow Test Report:

Test Date / Time: 5/14/2024 1:18:17 PM
Project: Plant Hammond
Operator Name: Jamie Newsome

Location Name: AS-01 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17 ft Total Depth: 27 ft Initial Depth to Water: 11.52 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 22 ft Estimated Total Volume Pumped: 10 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
---	---	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).

Weather Conditions:
Light rain, 70F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 3 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/14/2024 1:18 PM	00:00	7.66 pH	18.05 °C	863.23 µS/cm	0.18 mg/L	11.20 NTU	52.6 mV	11.52 ft	200.00 ml/min
5/14/2024 1:23 PM	05:00	7.78 pH	18.12 °C	805.31 µS/cm	0.23 mg/L	11.40 NTU	36.3 mV	11.52 ft	200.00 ml/min
5/14/2024 1:28 PM	10:00	7.88 pH	18.26 °C	798.68 µS/cm	0.26 mg/L	18.70 NTU	37.4 mV	11.52 ft	200.00 ml/min
5/14/2024 1:33 PM	15:00	7.83 pH	18.39 °C	795.31 µS/cm	0.24 mg/L	18.60 NTU	37.6 mV	11.52 ft	200.00 ml/min
5/14/2024 1:38 PM	20:00	8.01 pH	18.47 °C	798.28 µS/cm	0.39 mg/L	25.40 NTU	31.3 mV	11.52 ft	200.00 ml/min
5/14/2024 1:43 PM	25:00	8.04 pH	18.55 °C	802.11 µS/cm	0.43 mg/L	16.50 NTU	31.1 mV	11.52 ft	200.00 ml/min
5/14/2024 1:48 PM	30:00	7.85 pH	18.88 °C	801.55 µS/cm	0.30 mg/L	17.70 NTU	38.0 mV	11.52 ft	200.00 ml/min
5/14/2024 1:53 PM	35:00	7.77 pH	19.24 °C	812.68 µS/cm	0.24 mg/L	11.30 NTU	41.2 mV	11.52 ft	200.00 ml/min
5/14/2024 1:58 PM	40:00	7.72 pH	19.05 °C	816.72 µS/cm	0.23 mg/L	8.73 NTU	42.0 mV	11.52 ft	200.00 ml/min
5/14/2024 2:03 PM	45:00	7.68 pH	18.77 °C	835.04 µS/cm	0.25 mg/L	4.98 NTU	43.0 mV	11.52 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-AS-01	Grab.

Low-Flow Test Report:

Test Date / Time: 5/15/2024 12:20:04 PM
Project: Plant Hammond
Operator Name: Jamie Newsome

Location Name: INW-04 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35 ft Total Depth: 45 ft Initial Depth to Water: 24.75 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 12.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 100 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
--	--	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).
Fe2+ = 2.5 mg/L.

Weather Conditions:
Partly cloudy, 75F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 3 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/15/2024 12:20 PM	00:00	6.94 pH	20.68 °C	691.70 µS/cm	0.65 mg/L	7.97 NTU	-90.5 mV	24.75 ft	100.00 ml/min
5/15/2024 12:25 PM	05:00	6.94 pH	20.71 °C	692.40 µS/cm	0.53 mg/L	9.88 NTU	-92.0 mV	24.75 ft	100.00 ml/min
5/15/2024 12:30 PM	10:00	6.94 pH	20.48 °C	695.78 µS/cm	0.49 mg/L	22.80 NTU	-95.6 mV	24.75 ft	100.00 ml/min
5/15/2024 12:35 PM	15:00	6.96 pH	20.38 °C	719.95 µS/cm	0.43 mg/L	92.90 NTU	-97.0 mV	24.75 ft	100.00 ml/min
5/15/2024 12:40 PM	20:00	6.97 pH	20.48 °C	721.53 µS/cm	0.31 mg/L	91.00 NTU	-98.8 mV	24.75 ft	100.00 ml/min
5/15/2024 12:45 PM	25:00	6.97 pH	19.90 °C	718.94 µS/cm	0.26 mg/L	72.20 NTU	-99.3 mV	24.75 ft	100.00 ml/min
5/15/2024 12:50 PM	30:00	6.96 pH	19.99 °C	717.86 µS/cm	0.21 mg/L	56.00 NTU	-100.6 mV	24.75 ft	100.00 ml/min
5/15/2024 12:55 PM	35:00	6.95 pH	20.69 °C	712.72 µS/cm	0.19 mg/L	42.90 NTU	-103.1 mV	24.75 ft	100.00 ml/min
5/15/2024 1:00 PM	40:00	6.96 pH	20.37 °C	705.43 µS/cm	0.17 mg/L	32.10 NTU	-104.2 mV	24.75 ft	100.00 ml/min
5/15/2024 1:05 PM	45:00	6.95 pH	20.21 °C	703.72 µS/cm	0.14 mg/L	23.80 NTU	-105.1 mV	24.75 ft	100.00 ml/min
5/15/2024 1:10 PM	50:00	6.95 pH	19.95 °C	702.71 µS/cm	0.14 mg/L	19.30 NTU	-105.3 mV	24.75 ft	100.00 ml/min
5/15/2024 1:15 PM	55:00	6.95 pH	20.15 °C	702.02 µS/cm	0.13 mg/L	14.80 NTU	-105.9 mV	24.75 ft	100.00 ml/min
5/15/2024 1:20 PM	01:00:00	6.94 pH	20.64 °C	698.75 µS/cm	0.13 mg/L	13.50 NTU	-107.2 mV	24.75 ft	100.00 ml/min

5/15/2024 1:25 PM	01:05:00	6.94 pH	20.04 °C	698.46 µS/cm	0.12 mg/L	11.20 NTU	-104.7 mV	24.75 ft	100.00 ml/min
5/15/2024 1:30 PM	01:10:00	6.95 pH	19.74 °C	698.67 µS/cm	0.12 mg/L	12.80 NTU	-103.9 mV	24.75 ft	100.00 ml/min
5/15/2024 1:35 PM	01:15:00	6.94 pH	19.74 °C	697.18 µS/cm	0.14 mg/L	9.88 NTU	-103.4 mV	24.75 ft	100.00 ml/min
5/15/2024 1:40 PM	01:20:00	6.94 pH	20.21 °C	699.40 µS/cm	0.20 mg/L	9.75 NTU	-103.7 mV	24.75 ft	100.00 ml/min
5/15/2024 1:45 PM	01:25:00	6.94 pH	20.16 °C	696.60 µS/cm	0.30 mg/L	8.87 NTU	-102.2 mV	24.75 ft	100.00 ml/min
5/15/2024 1:50 PM	01:30:00	6.93 pH	20.48 °C	695.91 µS/cm	0.38 mg/L	8.23 NTU	-100.0 mV	24.75 ft	100.00 ml/min
5/15/2024 1:55 PM	01:35:00	6.94 pH	19.87 °C	693.32 µS/cm	0.45 mg/L	7.28 NTU	-99.9 mV	24.75 ft	100.00 ml/min
5/15/2024 2:00 PM	01:40:00	6.94 pH	20.08 °C	696.43 µS/cm	0.51 mg/L	7.16 NTU	-98.7 mV	24.75 ft	100.00 ml/min
5/15/2024 2:05 PM	01:45:00	6.94 pH	20.13 °C	694.50 µS/cm	0.48 mg/L	6.23 NTU	-98.5 mV	24.75 ft	100.00 ml/min
5/15/2024 2:10 PM	01:50:00	6.94 pH	20.33 °C	694.16 µS/cm	0.46 mg/L	5.46 NTU	-98.5 mV	24.75 ft	100.00 ml/min
5/15/2024 2:15 PM	01:55:00	6.94 pH	19.86 °C	693.25 µS/cm	0.48 mg/L	4.92 NTU	-97.4 mV	24.75 ft	100.00 ml/min

Samples

Sample ID:	Description:
HAM-INW-04	Grab.
HAM-AP1-FD-02	Grab.

Low-Flow Test Report:

Test Date / Time: 5/15/2024 10:00:05 AM
Project: Plant Hammond
Operator Name: Jamie Newsome

Location Name: INW-05 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35 ft Total Depth: 45 ft Initial Depth to Water: 24.48 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 8 liter Flow Cell Volume: 90 ml Final Flow Rate: 100 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
--	---	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).

Weather Conditions:
Cloudy, 70F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 3 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/15/2024 10:00 AM	00:00	6.98 pH	18.46 °C	689.27 µS/cm	0.33 mg/L	11.60 NTU	-132.4 mV	24.48 ft	100.00 ml/min
5/15/2024 10:05 AM	05:00	7.00 pH	18.48 °C	697.86 µS/cm	0.32 mg/L	43.30 NTU	-131.6 mV	24.48 ft	100.00 ml/min
5/15/2024 10:10 AM	10:00	7.01 pH	18.45 °C	695.52 µS/cm	0.25 mg/L	107.50 NTU	-137.8 mV	24.48 ft	100.00 ml/min
5/15/2024 10:15 AM	15:00	7.02 pH	18.47 °C	692.19 µS/cm	0.28 mg/L	88.60 NTU	-137.3 mV	24.48 ft	100.00 ml/min
5/15/2024 10:20 AM	20:00	7.02 pH	18.49 °C	689.46 µS/cm	0.27 mg/L	67.00 NTU	-131.7 mV	24.48 ft	100.00 ml/min
5/15/2024 10:25 AM	25:00	7.02 pH	18.46 °C	687.15 µS/cm	0.25 mg/L	50.10 NTU	-131.2 mV	24.48 ft	100.00 ml/min
5/15/2024 10:30 AM	30:00	7.02 pH	18.54 °C	685.31 µS/cm	0.27 mg/L	35.40 NTU	-129.5 mV	24.48 ft	100.00 ml/min
5/15/2024 10:35 AM	35:00	7.01 pH	18.56 °C	682.72 µS/cm	0.34 mg/L	21.40 NTU	-129.9 mV	24.48 ft	100.00 ml/min
5/15/2024 10:40 AM	40:00	7.01 pH	18.70 °C	681.19 µS/cm	0.36 mg/L	16.40 NTU	-127.8 mV	24.48 ft	100.00 ml/min
5/15/2024 10:45 AM	45:00	7.01 pH	18.66 °C	680.55 µS/cm	0.37 mg/L	13.30 NTU	-126.5 mV	24.48 ft	100.00 ml/min
5/15/2024 10:50 AM	50:00	7.01 pH	18.73 °C	679.58 µS/cm	0.36 mg/L	11.50 NTU	-126.1 mV	24.48 ft	100.00 ml/min
5/15/2024 10:55 AM	55:00	7.01 pH	18.74 °C	679.78 µS/cm	0.38 mg/L	11.77 NTU	-125.5 mV	24.48 ft	100.00 ml/min
5/15/2024 11:00 AM	01:00:00	7.01 pH	18.97 °C	676.34 µS/cm	0.37 mg/L	9.57 NTU	-121.8 mV	24.48 ft	100.00 ml/min

5/15/2024 11:05 AM	01:05:00	7.01 pH	18.82 °C	676.61 µS/cm	0.39 mg/L	8.42 NTU	-124.0 mV	24.48 ft	100.00 ml/min
5/15/2024 11:10 AM	01:10:00	7.01 pH	19.09 °C	677.40 µS/cm	0.37 mg/L	6.83 NTU	-124.4 mV	24.48 ft	100.00 ml/min
5/15/2024 11:15 AM	01:15:00	7.01 pH	19.19 °C	675.78 µS/cm	0.36 mg/L	4.97 NTU	-124.3 mV	24.48 ft	100.00 ml/min

Samples

Sample ID:	Description:
HAM-INW-05	Grab.

Low-Flow Test Report:

Test Date / Time: 5/16/2024 9:12:40 AM
Project: Plant Hammond
Operator Name: Jamie Newsome

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 37.6 ft Total Depth: 47.6 ft Initial Depth to Water: 25.1 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 42.6 ft Estimated Total Volume Pumped: 32 liter Flow Cell Volume: 90 ml Final Flow Rate: 100 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
--	---	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).
Fe2+ = 2.0 mg/L.

Weather Conditions:
Sunny, 70F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 3 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/16/2024 9:12 AM	00:00	6.95 pH	18.01 °C	667.33 µS/cm	4.16 mg/L	10.89 NTU	-80.3 mV	25.10 ft	200.00 ml/min
5/16/2024 9:17 AM	05:00	6.97 pH	17.99 °C	668.59 µS/cm	4.23 mg/L	8.81 NTU	-80.6 mV	25.15 ft	200.00 ml/min
5/16/2024 9:22 AM	10:00	6.98 pH	17.99 °C	670.91 µS/cm	4.11 mg/L	8.09 NTU	-82.0 mV	25.15 ft	200.00 ml/min
5/16/2024 9:27 AM	15:00	7.00 pH	18.03 °C	671.58 µS/cm	4.06 mg/L	7.64 NTU	-83.3 mV	25.15 ft	200.00 ml/min
5/16/2024 9:32 AM	20:00	7.01 pH	18.03 °C	673.36 µS/cm	4.08 mg/L	8.05 NTU	-84.4 mV	25.15 ft	200.00 ml/min
5/16/2024 9:37 AM	25:00	7.01 pH	17.99 °C	675.11 µS/cm	3.95 mg/L	7.74 NTU	-85.5 mV	25.15 ft	200.00 ml/min
5/16/2024 9:42 AM	30:00	7.01 pH	18.03 °C	675.27 µS/cm	3.87 mg/L	8.09 NTU	-86.3 mV	25.15 ft	200.00 ml/min
5/16/2024 9:47 AM	35:00	7.01 pH	18.07 °C	674.61 µS/cm	3.86 mg/L	7.14 NTU	-86.8 mV	25.15 ft	200.00 ml/min
5/16/2024 9:52 AM	40:00	7.01 pH	18.08 °C	675.60 µS/cm	3.95 mg/L	7.99 NTU	-89.0 mV	25.15 ft	200.00 ml/min
5/16/2024 9:57 AM	45:00	7.01 pH	18.08 °C	676.64 µS/cm	3.80 mg/L	8.51 NTU	-89.9 mV	25.15 ft	200.00 ml/min
5/16/2024 10:02 AM	50:00	7.01 pH	18.21 °C	673.83 µS/cm	3.80 mg/L	10.10 NTU	-87.7 mV	25.15 ft	200.00 ml/min
5/16/2024 10:07 AM	55:00	7.01 pH	18.27 °C	675.26 µS/cm	3.76 mg/L	10.34 NTU	-88.6 mV	25.15 ft	200.00 ml/min
5/16/2024 10:12 AM	01:00:00	7.01 pH	18.27 °C	674.83 µS/cm	3.88 mg/L	9.86 NTU	-88.6 mV	25.15 ft	200.00 ml/min

5/16/2024 10:17 AM	01:05:00	7.01 pH	18.52 °C	671.23 µS/cm	3.83 mg/L	13.27 NTU	-88.0 mV	25.15 ft	200.00 ml/min
5/16/2024 10:22 AM	01:10:00	7.01 pH	18.44 °C	675.80 µS/cm	3.67 mg/L	11.80 NTU	-89.1 mV	25.15 ft	200.00 ml/min
5/16/2024 10:27 AM	01:15:00	7.00 pH	18.34 °C	672.95 µS/cm	3.69 mg/L	11.10 NTU	-88.6 mV	25.15 ft	200.00 ml/min
5/16/2024 10:32 AM	01:20:00	7.01 pH	18.19 °C	672.92 µS/cm	3.81 mg/L	11.30 NTU	-88.5 mV	25.15 ft	200.00 ml/min
5/16/2024 10:37 AM	01:25:00	7.01 pH	18.34 °C	673.83 µS/cm	3.81 mg/L	11.50 NTU	-88.7 mV	25.15 ft	200.00 ml/min
5/16/2024 10:42 AM	01:30:00	7.01 pH	18.47 °C	674.23 µS/cm	3.91 mg/L	11.80 NTU	-88.9 mV	25.15 ft	200.00 ml/min
5/16/2024 10:47 AM	01:35:00	7.01 pH	18.52 °C	673.88 µS/cm	3.74 mg/L	12.10 NTU	-89.0 mV	25.15 ft	200.00 ml/min
5/16/2024 10:52 AM	01:40:00	7.01 pH	18.49 °C	672.98 µS/cm	3.88 mg/L	11.50 NTU	-89.1 mV	25.15 ft	200.00 ml/min
5/16/2024 10:57 AM	01:45:00	7.01 pH	18.40 °C	674.82 µS/cm	3.77 mg/L	11.10 NTU	-89.3 mV	25.15 ft	200.00 ml/min
5/16/2024 11:02 AM	01:50:00	7.00 pH	18.57 °C	673.12 µS/cm	3.87 mg/L	11.50 NTU	-90.4 mV	25.15 ft	200.00 ml/min
5/16/2024 11:07 AM	01:55:00	7.01 pH	18.52 °C	674.19 µS/cm	3.78 mg/L	11.30 NTU	-90.7 mV	25.15 ft	200.00 ml/min
5/16/2024 11:12 AM	02:00:00	7.00 pH	18.52 °C	673.98 µS/cm	3.75 mg/L	11.10 NTU	-90.7 mV	25.15 ft	200.00 ml/min
5/16/2024 11:17 AM	02:05:00	7.00 pH	18.57 °C	674.73 µS/cm	3.95 mg/L	11.20 NTU	-88.9 mV	25.15 ft	200.00 ml/min
5/16/2024 11:22 AM	02:10:00	7.00 pH	18.52 °C	673.25 µS/cm	3.84 mg/L	11.40 NTU	-88.8 mV	25.15 ft	200.00 ml/min
5/16/2024 11:27 AM	02:15:00	6.99 pH	19.07 °C	676.19 µS/cm	3.35 mg/L	11.50 NTU	-90.3 mV	25.15 ft	100.00 ml/min
5/16/2024 11:32 AM	02:20:00	6.99 pH	19.17 °C	676.75 µS/cm	2.38 mg/L	10.89 NTU	-95.8 mV	25.15 ft	100.00 ml/min
5/16/2024 11:37 AM	02:25:00	7.00 pH	19.24 °C	677.74 µS/cm	2.42 mg/L	12.30 NTU	-96.1 mV	25.15 ft	100.00 ml/min
5/16/2024 11:42 AM	02:30:00	6.99 pH	19.35 °C	673.31 µS/cm	2.26 mg/L	13.42 NTU	-93.9 mV	25.15 ft	100.00 ml/min
5/16/2024 11:47 AM	02:35:00	6.98 pH	19.50 °C	674.30 µS/cm	2.41 mg/L	12.50 NTU	-92.9 mV	25.15 ft	100.00 ml/min
5/16/2024 11:52 AM	02:40:00	6.98 pH	19.29 °C	671.44 µS/cm	2.39 mg/L		-92.2 mV	25.15 ft	100.00 ml/min
5/16/2024 11:57 AM	02:45:00	6.98 pH	19.34 °C	669.89 µS/cm	2.70 mg/L	13.20 NTU	-90.9 mV	25.15 ft	100.00 ml/min
5/16/2024 12:02 PM	02:50:00	6.98 pH	19.28 °C	670.02 µS/cm	2.34 mg/L	13.70 NTU	-92.0 mV	25.15 ft	100.00 ml/min
5/16/2024 12:07 PM	02:55:00	6.98 pH	19.28 °C	670.24 µS/cm	2.41 mg/L	14.20 NTU	-91.6 mV	25.15 ft	100.00 ml/min
5/16/2024 12:12 PM	03:00:00	6.98 pH	19.39 °C	671.25 µS/cm	2.33 mg/L	13.80 NTU	-91.9 mV	25.15 ft	100.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-07	Grab.
HAM-PT-07-TS-WG-05162024	Grab.

Low-Flow Test Report:

Test Date / Time: 5/16/2024 9:17:05 AM
Project: Plant Hammond
Operator Name: Anthony Szwast

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 31.93 ft Total Depth: 41.93 ft Initial Depth to Water: 24.91 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 36.93 ft Estimated Total Volume Pumped: 16 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 850751
---	---	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).
Total Fe > 7 mg/L.
Fe2+ = 5.6 mg/L.

Weather Conditions:
Sunny, 70 deg. F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/16/2024 9:17 AM	00:00	6.41 pH	19.46 °C	607.47 µS/cm	0.66 mg/L	54.40 NTU	-29.9 mV	24.90 ft	200.00 ml/min
5/16/2024 9:22 AM	05:00	6.40 pH	19.10 °C	610.29 µS/cm	0.90 mg/L	44.50 NTU	-27.9 mV	24.91 ft	200.00 ml/min
5/16/2024 9:27 AM	10:00	6.41 pH	19.07 °C	613.25 µS/cm	0.91 mg/L	28.20 NTU	-26.9 mV	24.93 ft	200.00 ml/min
5/16/2024 9:32 AM	15:00	6.41 pH	19.06 °C	611.66 µS/cm	1.18 mg/L	20.20 NTU	-23.7 mV	24.91 ft	200.00 ml/min
5/16/2024 9:37 AM	20:00	6.42 pH	18.97 °C	613.21 µS/cm	1.22 mg/L	16.10 NTU	-23.0 mV	24.91 ft	200.00 ml/min
5/16/2024 9:42 AM	25:00	6.42 pH	19.10 °C	612.36 µS/cm	1.15 mg/L	14.60 NTU	-23.7 mV	24.91 ft	200.00 ml/min
5/16/2024 9:47 AM	30:00	6.42 pH	19.10 °C	614.95 µS/cm	1.03 mg/L	13.00 NTU	-22.8 mV	24.91 ft	200.00 ml/min
5/16/2024 9:52 AM	35:00	6.43 pH	19.15 °C	616.67 µS/cm	0.97 mg/L	12.70 NTU	-23.4 mV	24.91 ft	200.00 ml/min
5/16/2024 9:57 AM	40:00	6.44 pH	19.12 °C	617.80 µS/cm	0.96 mg/L	7.13 NTU	-25.5 mV	24.91 ft	200.00 ml/min
5/16/2024 10:02 AM	45:00	6.44 pH	19.09 °C	618.77 µS/cm	0.93 mg/L	6.82 NTU	-24.1 mV	24.91 ft	200.00 ml/min
5/16/2024 10:07 AM	50:00	6.45 pH	19.15 °C	618.51 µS/cm	0.94 mg/L	5.84 NTU	-23.8 mV	24.91 ft	200.00 ml/min
5/16/2024 10:12 AM	55:00	6.45 pH	19.26 °C	620.25 µS/cm	0.93 mg/L	5.45 NTU	-24.1 mV	24.91 ft	200.00 ml/min
5/16/2024 10:17 AM	01:00:00	6.46 pH	19.29 °C	621.61 µS/cm	0.81 mg/L	5.28 NTU	-25.1 mV	24.91 ft	200.00 ml/min

5/16/2024 10:22 AM	01:05:00	6.47 pH	19.30 °C	622.51 µS/cm	0.70 mg/L	4.66 NTU	-26.0 mV	24.91 ft	200.00 ml/min
5/16/2024 10:27 AM	01:10:00	6.47 pH	19.10 °C	625.69 µS/cm	0.54 mg/L	4.58 NTU	-29.4 mV	24.91 ft	200.00 ml/min
5/16/2024 10:32 AM	01:15:00	6.49 pH	19.16 °C	626.30 µS/cm	0.51 mg/L	4.10 NTU	-29.0 mV	24.91 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.
HAM-PT-08-TS-WG-05162024	Grab.

Low-Flow Test Report:

Test Date / Time: 5/14/2024 9:20:06 AM
Project: Plant Hammond
Operator Name: Jamie Newsome

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.15 ft Total Depth: 27.15 ft Initial Depth to Water: 14.82 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 19.15 ft Estimated Total Volume Pumped: 16 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
---	---	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).

Weather Conditions:
Cloudy, 64F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 3 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/14/2024 9:20 AM	00:00	6.99 pH	17.49 °C	706.91 µS/cm	0.18 mg/L	823.00 NTU	105.6 mV	14.82 ft	200.00 ml/min
5/14/2024 9:25 AM	05:00	7.06 pH	17.45 °C	716.68 µS/cm	0.43 mg/L	40.60 NTU	85.0 mV	14.82 ft	200.00 ml/min
5/14/2024 9:30 AM	10:00	7.16 pH	17.54 °C	711.82 µS/cm	0.09 mg/L	634.00 NTU	65.8 mV	14.82 ft	200.00 ml/min
5/14/2024 9:35 AM	15:00	7.18 pH	17.61 °C	705.63 µS/cm	0.07 mg/L	147.00 NTU	48.7 mV	14.82 ft	200.00 ml/min
5/14/2024 9:40 AM	20:00	7.17 pH	17.63 °C	700.13 µS/cm	0.06 mg/L	150.00 NTU	46.3 mV	14.82 ft	200.00 ml/min
5/14/2024 9:45 AM	25:00	7.17 pH	17.67 °C	693.99 µS/cm	0.05 mg/L	85.90 NTU	54.4 mV	14.82 ft	200.00 ml/min
5/14/2024 9:50 AM	30:00	7.17 pH	17.67 °C	691.39 µS/cm	0.05 mg/L	66.80 NTU	54.7 mV	14.85 ft	200.00 ml/min
5/14/2024 9:55 AM	35:00	7.16 pH	17.69 °C	689.18 µS/cm	0.05 mg/L	39.40 NTU	54.3 mV	14.85 ft	200.00 ml/min
5/14/2024 10:00 AM	40:00	7.16 pH	17.75 °C	686.92 µS/cm	0.05 mg/L	28.50 NTU	54.0 mV	14.85 ft	200.00 ml/min
5/14/2024 10:05 AM	45:00	7.15 pH	17.76 °C	685.36 µS/cm	0.06 mg/L	21.00 NTU	53.5 mV	14.85 ft	200.00 ml/min
5/14/2024 10:10 AM	50:00	7.15 pH	17.76 °C	685.00 µS/cm	0.06 mg/L	12.60 NTU	53.1 mV	14.85 ft	200.00 ml/min
5/14/2024 10:15 AM	55:00	7.15 pH	17.77 °C	684.26 µS/cm	0.06 mg/L	11.50 NTU	52.3 mV	14.85 ft	200.00 ml/min
5/14/2024 10:20 AM	01:00:00	7.15 pH	17.76 °C	683.86 µS/cm	0.07 mg/L	11.60 NTU	51.6 mV	14.85 ft	200.00 ml/min

5/14/2024 10:25 AM	01:05:00	7.16 pH	17.77 °C	684.36 µS/cm	0.05 mg/L	7.81 NTU	51.0 mV	14.85 ft	200.00 ml/min
5/14/2024 10:30 AM	01:10:00	7.16 pH	17.75 °C	682.89 µS/cm	0.05 mg/L	6.15 NTU	50.4 mV	14.85 ft	200.00 ml/min
5/14/2024 10:35 AM	01:15:00	7.16 pH	17.76 °C	681.69 µS/cm	0.04 mg/L	4.98 NTU	49.9 mV	14.85 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.

Low-Flow Test Report:

Test Date / Time: 5/15/2024 10:12:45 AM
Project: Plant Hammond
Operator Name: Anthony Szwast

Location Name: PT-10 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.45 ft Total Depth: 30.45 ft Initial Depth to Water: 15.11 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 25.45 ft Estimated Total Volume Pumped: 20 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 850751
---	---	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).
Total Fe = 0 mg/L.
Fe2+ = 0 mg/L.

Weather Conditions:
Cloudy, 67 deg. F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/15/2024 10:12 AM	00:00	6.88 pH	19.14 °C	744.43 µS/cm	0.41 mg/L	65.60 NTU	-23.7 mV	15.14 ft	200.00 ml/min
5/15/2024 10:17 AM	05:00	6.90 pH	18.86 °C	738.89 µS/cm	0.38 mg/L	72.30 NTU	-12.8 mV	15.14 ft	200.00 ml/min
5/15/2024 10:22 AM	10:00	6.86 pH	18.82 °C	728.49 µS/cm	0.38 mg/L	55.40 NTU	-5.8 mV	15.14 ft	200.00 ml/min
5/15/2024 10:27 AM	15:00	6.89 pH	18.79 °C	713.40 µS/cm	0.34 mg/L	50.40 NTU	4.9 mV	15.14 ft	200.00 ml/min
5/15/2024 10:32 AM	20:00	6.87 pH	18.76 °C	716.36 µS/cm	0.35 mg/L	35.20 NTU	6.4 mV	15.14 ft	200.00 ml/min
5/15/2024 10:37 AM	25:00	6.92 pH	18.98 °C	714.92 µS/cm	0.36 mg/L	32.00 NTU	10.5 mV	15.14 ft	200.00 ml/min
5/15/2024 10:42 AM	30:00	6.91 pH	18.99 °C	721.19 µS/cm	0.34 mg/L	25.70 NTU	8.1 mV	15.15 ft	200.00 ml/min
5/15/2024 10:47 AM	35:00	6.88 pH	19.08 °C	719.67 µS/cm	0.31 mg/L	22.90 NTU	9.9 mV	15.15 ft	200.00 ml/min
5/15/2024 10:52 AM	40:00	6.92 pH	19.06 °C	716.50 µS/cm	0.34 mg/L	19.30 NTU	11.9 mV	15.15 ft	200.00 ml/min
5/15/2024 10:57 AM	45:00	6.89 pH	19.05 °C	716.11 µS/cm	0.33 mg/L	16.00 NTU	12.2 mV	15.15 ft	200.00 ml/min
5/15/2024 11:02 AM	50:00	6.92 pH	19.51 °C	719.47 µS/cm	0.33 mg/L	12.70 NTU	10.8 mV	15.15 ft	200.00 ml/min
5/15/2024 11:07 AM	55:00	6.92 pH	19.28 °C	715.52 µS/cm	0.37 mg/L	12.84 NTU	12.5 mV	15.15 ft	200.00 ml/min
5/15/2024 11:12 AM	01:00:00	6.91 pH	19.68 °C	713.72 µS/cm	0.33 mg/L	10.77 NTU	14.3 mV	15.15 ft	200.00 ml/min

5/15/2024 11:17 AM	01:05:00	6.90 pH	19.82 °C	716.90 µS/cm	0.32 mg/L	9.98 NTU	11.8 mV	15.15 ft	200.00 ml/min
5/15/2024 11:22 AM	01:10:00	6.91 pH	19.77 °C	709.96 µS/cm	0.30 mg/L	8.56 NTU	16.1 mV	15.16 ft	200.00 ml/min
5/15/2024 11:27 AM	01:15:00	6.91 pH	20.03 °C	712.22 µS/cm	0.28 mg/L	7.72 NTU	16.1 mV	15.16 ft	200.00 ml/min
5/15/2024 11:32 AM	01:20:00	6.92 pH	20.09 °C	712.26 µS/cm	0.28 mg/L	6.32 NTU	14.0 mV	15.16 ft	200.00 ml/min
5/15/2024 11:37 AM	01:25:00	6.93 pH	19.90 °C	717.20 µS/cm	0.28 mg/L	6.86 NTU	14.2 mV	15.16 ft	200.00 ml/min
5/15/2024 11:42 AM	01:30:00	6.92 pH	20.22 °C	709.75 µS/cm	0.25 mg/L	3.57 NTU	17.3 mV	15.16 ft	200.00 ml/min
5/15/2024 11:47 AM	01:35:00	6.92 pH	20.00 °C	707.36 µS/cm	0.25 mg/L	4.92 NTU	20.1 mV	15.16 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.
HAM-AP1-FD-01	Grab.

Low-Flow Test Report:

Test Date / Time: 5/14/2024 2:45:08 PM
Project: Plant Hammond
Operator Name: Jamie Newsome

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17 ft Total Depth: 27 ft Initial Depth to Water: 11.37 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 22 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
---	---	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).

Weather Conditions:
Light rain, 70F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 3 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/14/2024 2:45 PM	00:00	7.02 pH	18.01 °C	675.49 µS/cm	0.18 mg/L	4.88 NTU	45.5 mV	11.37 ft	200.00 ml/min
5/14/2024 2:50 PM	05:00	6.98 pH	17.98 °C	675.33 µS/cm	0.12 mg/L	1.54 NTU	35.9 mV	11.37 ft	200.00 ml/min
5/14/2024 2:55 PM	10:00	6.97 pH	17.96 °C	678.01 µS/cm	0.10 mg/L	1.27 NTU	32.2 mV	11.37 ft	200.00 ml/min
5/14/2024 3:00 PM	15:00	6.97 pH	17.85 °C	677.20 µS/cm	0.09 mg/L	1.10 NTU	30.6 mV	11.37 ft	200.00 ml/min
5/14/2024 3:05 PM	20:00	6.97 pH	17.94 °C	676.22 µS/cm	0.08 mg/L	1.02 NTU	29.6 mV	11.40 ft	200.00 ml/min
5/14/2024 3:10 PM	25:00	6.98 pH	18.00 °C	673.82 µS/cm	0.09 mg/L	1.15 NTU	27.1 mV	11.40 ft	200.00 ml/min
5/14/2024 3:15 PM	30:00	6.98 pH	18.11 °C	676.01 µS/cm	0.07 mg/L	1.43 NTU	28.7 mV	11.40 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-11	Grab.

Low-Flow Test Report:

Test Date / Time: 5/14/2024 11:30:05 AM
Project: Plant Hammond
Operator Name: Jamie Newsome

Location Name: PT-12 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17 ft Total Depth: 27 ft Initial Depth to Water: 11.25 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 22 ft Estimated Total Volume Pumped: 5.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 100 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
---	--	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).

Weather Conditions:
Cloudy, 65F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 3 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/14/2024 11:30 AM	00:00	6.58 pH	17.76 °C	679.33 µS/cm	0.20 mg/L	6.24 NTU	61.4 mV	11.25 ft	200.00 ml/min
5/14/2024 11:35 AM	05:00	6.57 pH	17.95 °C	689.70 µS/cm	0.21 mg/L	6.40 NTU	49.5 mV	11.25 ft	200.00 ml/min
5/14/2024 11:40 AM	10:00	6.57 pH	18.08 °C	689.22 µS/cm	0.19 mg/L	5.87 NTU	59.3 mV	11.25 ft	200.00 ml/min
5/14/2024 11:45 AM	15:00	6.57 pH	18.30 °C	688.05 µS/cm	0.22 mg/L	4.72 NTU	59.4 mV	11.25 ft	200.00 ml/min
5/14/2024 11:50 AM	20:00	6.57 pH	18.43 °C	688.65 µS/cm	0.22 mg/L	5.20 NTU	59.0 mV	11.25 ft	100.00 ml/min
5/14/2024 11:55 AM	25:00	6.58 pH	18.66 °C	687.32 µS/cm	0.27 mg/L	4.84 NTU	58.7 mV	11.25 ft	100.00 ml/min
5/14/2024 12:00 PM	30:00	6.58 pH	18.81 °C	685.68 µS/cm	0.32 mg/L	4.71 NTU	58.8 mV	11.25 ft	100.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-12	Grab.

Low-Flow Test Report:

Test Date / Time: 5/15/2024 5:25:06 PM
Project: Plant Hammond
Operator Name: Jamie Newsome

Location Name: PT-13 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35 ft Total Depth: 45 ft Initial Depth to Water: 24.57 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 8.2 liter Flow Cell Volume: 90 ml Final Flow Rate: 100 ml/min Final Draw Down: 0.04 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
---	--	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).
Fe2+ = 2.5 mg/L.

Weather Conditions:
Partly cloudy, 75F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 3 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/15/2024 5:25 PM	00:00	6.90 pH	19.68 °C	677.73 µS/cm	0.88 mg/L	11.20 NTU	-90.6 mV	24.57 ft	100.00 ml/min
5/15/2024 5:30 PM	05:00	6.93 pH	19.23 °C	680.71 µS/cm	1.02 mg/L	9.34 NTU	-99.0 mV	24.57 ft	100.00 ml/min
5/15/2024 5:35 PM	10:00	6.94 pH	19.10 °C	681.15 µS/cm	1.21 mg/L	7.75 NTU	-97.5 mV	24.57 ft	100.00 ml/min
5/15/2024 5:40 PM	15:00	6.93 pH	19.10 °C	681.34 µS/cm	1.20 mg/L	7.13 NTU	-99.3 mV	24.57 ft	100.00 ml/min
5/15/2024 5:45 PM	20:00	6.93 pH	18.94 °C	681.37 µS/cm	1.35 mg/L	13.62 NTU	-95.9 mV	24.57 ft	100.00 ml/min
5/15/2024 5:50 PM	25:00	6.93 pH	18.83 °C	683.12 µS/cm	1.15 mg/L	12.36 NTU	-96.7 mV	24.57 ft	100.00 ml/min
5/15/2024 5:55 PM	30:00	6.94 pH	18.78 °C	682.89 µS/cm	1.01 mg/L	9.89 NTU	-100.1 mV	24.57 ft	100.00 ml/min
5/15/2024 6:00 PM	35:00	6.94 pH	18.79 °C	682.69 µS/cm	1.10 mg/L	8.97 NTU	-99.3 mV	24.57 ft	100.00 ml/min
5/15/2024 6:05 PM	40:00	6.93 pH	18.97 °C	682.73 µS/cm	1.12 mg/L	8.12 NTU	-99.2 mV	24.57 ft	100.00 ml/min
5/15/2024 6:10 PM	45:00	6.93 pH	19.07 °C	682.16 µS/cm	1.04 mg/L	7.17 NTU	-99.9 mV	24.61 ft	100.00 ml/min
5/15/2024 6:15 PM	50:00	6.93 pH	19.12 °C	681.98 µS/cm	1.08 mg/L	6.67 NTU	-99.6 mV	24.61 ft	100.00 ml/min
5/15/2024 6:20 PM	55:00	6.93 pH	18.91 °C	682.48 µS/cm	1.10 mg/L	6.27 NTU	-96.8 mV	24.61 ft	100.00 ml/min
5/15/2024 6:25 PM	01:00:00	6.93 pH	18.74 °C	682.62 µS/cm	1.29 mg/L	6.95 NTU	-95.4 mV	24.61 ft	100.00 ml/min

5/15/2024 6:30 PM	01:05:00	6.93 pH	18.74 °C	682.98 µS/cm	1.03 mg/L	6.16 NTU	-96.6 mV	24.61 ft	100.00 ml/min
5/15/2024 6:35 PM	01:10:00	6.93 pH	18.65 °C	683.56 µS/cm	0.97 mg/L	5.40 NTU	-99.2 mV	24.61 ft	100.00 ml/min
5/15/2024 6:40 PM	01:15:00	6.93 pH	18.64 °C	683.83 µS/cm	1.10 mg/L	4.82 NTU	-98.3 mV	24.61 ft	100.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-13	Grab.

Low-Flow Test Report:

Test Date / Time: 5/15/2024 5:02:23 PM
Project: Plant Hammond
Operator Name: Anthony Szwast

Location Name: PT-14 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35 ft Total Depth: 45 ft Initial Depth to Water: 24.48 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 15.4 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 850751
---	---	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).
Fe2+ = 3.0 mg/L.

Weather Conditions:
Sunny, 70 deg. F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/15/2024 5:02 PM	00:00	6.63 pH	21.21 °C	654.87 µS/cm	0.86 mg/L	93.20 NTU	-126.0 mV	24.49 ft	100.00 ml/min
5/15/2024 5:07 PM	05:00	6.71 pH	19.85 °C	665.04 µS/cm	0.48 mg/L	89.10 NTU	-127.2 mV	24.49 ft	100.00 ml/min
5/15/2024 5:12 PM	10:00	6.73 pH	19.06 °C	667.24 µS/cm	0.33 mg/L	69.30 NTU	-126.1 mV	24.51 ft	200.00 ml/min
5/15/2024 5:17 PM	15:00	6.75 pH	19.28 °C	664.55 µS/cm	0.23 mg/L	44.50 NTU	-120.4 mV	24.51 ft	200.00 ml/min
5/15/2024 5:22 PM	20:00	6.75 pH	19.00 °C	667.67 µS/cm	0.18 mg/L	30.90 NTU	-119.3 mV	24.51 ft	200.00 ml/min
5/15/2024 5:27 PM	25:00	6.76 pH	18.88 °C	668.74 µS/cm	0.15 mg/L	20.40 NTU	-118.2 mV	24.52 ft	200.00 ml/min
5/15/2024 5:32 PM	30:00	6.85 pH	19.53 °C	0.72 µS/cm	5.30 mg/L	16.20 NTU	-62.3 mV	24.52 ft	200.00 ml/min
5/15/2024 5:37 PM	35:00	6.74 pH	18.97 °C	670.06 µS/cm	0.30 mg/L	96.20 NTU	-106.1 mV	24.52 ft	200.00 ml/min
5/15/2024 5:42 PM	40:00	6.76 pH	18.88 °C	671.64 µS/cm	0.15 mg/L	57.80 NTU	-109.6 mV	24.52 ft	200.00 ml/min
5/15/2024 5:47 PM	45:00	6.76 pH	18.84 °C	670.94 µS/cm	0.12 mg/L	35.70 NTU	-111.0 mV	24.52 ft	200.00 ml/min
5/15/2024 5:52 PM	50:00	6.77 pH	18.78 °C	671.50 µS/cm	0.10 mg/L	21.40 NTU	-111.7 mV	24.53 ft	200.00 ml/min
5/15/2024 5:57 PM	55:00	6.77 pH	18.72 °C	671.66 µS/cm	0.09 mg/L	18.90 NTU	-111.6 mV	24.51 ft	200.00 ml/min
5/15/2024 6:02 PM	01:00:00	6.77 pH	18.77 °C	671.48 µS/cm	0.08 mg/L	11.90 NTU	-111.5 mV	24.53 ft	200.00 ml/min

5/15/2024 6:07 PM	01:05:00	6.78 pH	18.88 °C	670.46 µS/cm	0.07 mg/L	9.45 NTU	-111.1 mV	24.53 ft	200.00 ml/min
5/15/2024 6:12 PM	01:10:00	6.78 pH	19.10 °C	668.71 µS/cm	0.06 mg/L	7.68 NTU	-110.7 mV	24.53 ft	200.00 ml/min
5/15/2024 6:17 PM	01:15:00	6.78 pH	18.88 °C	671.20 µS/cm	0.06 mg/L	5.68 NTU	-110.1 mV	24.53 ft	200.00 ml/min
5/15/2024 6:22 PM	01:20:00	6.78 pH	18.75 °C	671.71 µS/cm	0.05 mg/L	4.99 NTU	-110.0 mV	24.53 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-14	Grab.

Low-Flow Test Report:

Test Date / Time: 5/15/2024 3:35:08 PM
Project: Plant Hammond
Operator Name: Jamie Newsome

Location Name: PT-15 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35 ft Total Depth: 45 ft Initial Depth to Water: 24.42 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 4 liter Flow Cell Volume: 90 ml Final Flow Rate: 100 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 966105
---	--	--

Test Notes:
Full App. III and IV and Major Ions (no RADs).
Fe 2+ = 2.5 mg/L.

Weather Conditions:
Partly cloudy, 75F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 3 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/15/2024 3:35 PM	00:00	7.00 pH	19.78 °C	776.12 µS/cm	0.19 mg/L	1.38 NTU	-123.5 mV	24.42 ft	100.00 ml/min
5/15/2024 3:40 PM	05:00	7.00 pH	19.63 °C	779.55 µS/cm	0.18 mg/L	0.69 NTU	-125.7 mV	24.42 ft	100.00 ml/min
5/15/2024 3:45 PM	10:00	6.99 pH	20.21 °C	789.34 µS/cm	0.17 mg/L	0.28 NTU	-125.6 mV	24.42 ft	100.00 ml/min
5/15/2024 3:50 PM	15:00	7.00 pH	20.44 °C	839.74 µS/cm	0.14 mg/L	1.61 NTU	-122.9 mV	24.42 ft	100.00 ml/min
5/15/2024 3:55 PM	20:00	7.01 pH	20.04 °C	849.30 µS/cm	0.12 mg/L	1.83 NTU	-120.1 mV	24.42 ft	100.00 ml/min
5/15/2024 4:00 PM	25:00	7.01 pH	20.21 °C	859.17 µS/cm	0.11 mg/L	0.93 NTU	-118.7 mV	24.45 ft	100.00 ml/min
5/15/2024 4:05 PM	30:00	7.01 pH	20.45 °C	863.09 µS/cm	0.10 mg/L	0.77 NTU	-118.3 mV	24.45 ft	100.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-15	Grab.

Low-Flow Test Report:

Test Date / Time: 5/29/2024 12:44:33 PM
Project: Plant Hammond
Operator Name: Zain Webb

Location Name: AS-01 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17 ft Total Depth: 27 ft Initial Depth to Water: 11.38 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22 ft Estimated Total Volume Pumped: 14.25 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.11 ft	Instrument Used: Aqua TROLL 400 Serial Number: 965586
--	---	--

Test Notes:
Appendix III and IV and Major Ions (no RADs).
Fe2+ = 0 mg/L.
Fe = 0 mg/L.

Weather Conditions:
Sunny, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/29/2024 12:44 PM	00:00	7.53 pH	20.88 °C	840.04 µS/cm	2.98 mg/L	2.99 NTU	-77.5 mV	11.38 ft	150.00 ml/min
5/29/2024 12:49 PM	05:00	7.54 pH	19.80 °C	863.27 µS/cm	0.91 mg/L	2.57 NTU	-57.4 mV	11.47 ft	150.00 ml/min
5/29/2024 12:54 PM	10:00	7.52 pH	19.85 °C	854.17 µS/cm	1.57 mg/L	2.12 NTU	-59.5 mV	11.48 ft	150.00 ml/min
5/29/2024 12:59 PM	15:00	7.49 pH	19.76 °C	865.61 µS/cm	1.23 mg/L	1.73 NTU	-83.2 mV	11.49 ft	150.00 ml/min
5/29/2024 1:04 PM	20:00	7.46 pH	19.86 °C	872.27 µS/cm	1.14 mg/L	1.07 NTU	-49.7 mV	11.49 ft	150.00 ml/min
5/29/2024 1:09 PM	25:00	7.45 pH	19.91 °C	872.76 µS/cm	2.09 mg/L	0.99 NTU	-76.1 mV	11.49 ft	150.00 ml/min
5/29/2024 1:14 PM	30:00	7.42 pH	19.99 °C	870.17 µS/cm	0.44 mg/L	0.76 NTU	-44.0 mV	11.49 ft	150.00 ml/min
5/29/2024 1:19 PM	35:00	7.41 pH	20.03 °C	884.25 µS/cm	0.47 mg/L	0.40 NTU	-44.2 mV	11.49 ft	150.00 ml/min
5/29/2024 1:24 PM	40:00	7.40 pH	19.96 °C	866.45 µS/cm	2.21 mg/L	0.43 NTU	-41.6 mV	11.49 ft	150.00 ml/min
5/29/2024 1:29 PM	45:00	7.40 pH	20.01 °C	880.70 µS/cm	0.57 mg/L	0.50 NTU	-39.8 mV	11.49 ft	150.00 ml/min
5/29/2024 1:34 PM	50:00	7.38 pH	20.13 °C	875.48 µS/cm	1.63 mg/L	0.87 NTU	-37.9 mV	11.49 ft	150.00 ml/min
5/29/2024 1:39 PM	55:00	7.37 pH	20.21 °C	865.85 µS/cm	0.38 mg/L	0.44 NTU	-35.9 mV	11.49 ft	150.00 ml/min
5/29/2024 1:44 PM	01:00:00	7.37 pH	19.90 °C	868.81 µS/cm	0.48 mg/L	0.48 NTU	-33.5 mV	11.49 ft	150.00 ml/min

5/29/2024 1:47 PM	01:02:29	7.37 pH	20.03 °C	818.62 µS/cm	0.50 mg/L	0.48 NTU	-32.7 mV	11.49 ft	150.00 ml/min
5/29/2024 1:52 PM	01:07:29	7.36 pH	20.03 °C	875.39 µS/cm	0.53 mg/L	0.17 NTU	-30.6 mV	11.49 ft	150.00 ml/min
5/29/2024 1:54 PM	01:10:21	7.35 pH	20.21 °C	795.78 µS/cm	0.49 mg/L	0.28 NTU	-29.2 mV	11.49 ft	150.00 ml/min
5/29/2024 1:59 PM	01:15:21	7.35 pH	20.22 °C	833.20 µS/cm	0.54 mg/L	0.30 NTU	-29.8 mV	11.49 ft	150.00 ml/min
5/29/2024 2:04 PM	01:20:21	7.35 pH	20.11 °C	848.09 µS/cm	0.68 mg/L	0.11 NTU	-28.7 mV	11.49 ft	150.00 ml/min
5/29/2024 2:09 PM	01:25:21	7.36 pH	20.17 °C	864.90 µS/cm	0.61 mg/L	0.56 NTU	-26.7 mV	11.49 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-AS-01	Grab.

Low-Flow Test Report:

Test Date / Time: 5/30/2024 9:07:43 AM
Project: Plant Hammond
Operator Name: Zain Webb

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.47 ft Total Depth: 30.47 ft Initial Depth to Water: 14.94 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 25.47 ft Estimated Total Volume Pumped: 24.75 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.01 ft	Instrument Used: Aqua TROLL 400 Serial Number: 965586
---	---	--

Test Notes:
Appendix III and IV, Major Ions, and Treatability Study Sample (no RADs).
Fe2+ = 0 mg/L.
Fe = 0 mg/L.

Weather Conditions:
Sunny, 75 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/30/2024 9:07 AM	00:00	6.83 pH	18.39 °C	688.12 µS/cm	0.22 mg/L	++++	47.0 mV	14.94 ft	150.00 ml/min
5/30/2024 9:12 AM	05:00	6.84 pH	18.47 °C	760.88 µS/cm	0.14 mg/L	++++	66.3 mV	14.95 ft	150.00 ml/min
5/30/2024 9:17 AM	10:00	6.86 pH	18.61 °C	742.55 µS/cm	0.12 mg/L	++++	60.1 mV	14.95 ft	150.00 ml/min
5/30/2024 9:22 AM	15:00	6.87 pH	18.72 °C	747.90 µS/cm	0.10 mg/L	++++	76.1 mV	14.95 ft	150.00 ml/min
5/30/2024 9:27 AM	20:00	6.88 pH	18.78 °C	730.72 µS/cm	0.09 mg/L	++++	65.2 mV	14.95 ft	150.00 ml/min
5/30/2024 9:32 AM	25:00	6.89 pH	18.88 °C	735.76 µS/cm	0.09 mg/L	++++	82.7 mV	14.95 ft	150.00 ml/min
5/30/2024 9:37 AM	30:00	6.91 pH	18.99 °C	727.93 µS/cm	0.08 mg/L	++++	70.3 mV	14.95 ft	150.00 ml/min
5/30/2024 9:42 AM	35:00	6.91 pH	19.14 °C	729.82 µS/cm	0.07 mg/L	++++	91.2 mV	14.95 ft	150.00 ml/min
5/30/2024 9:47 AM	40:00	6.91 pH	19.23 °C	716.96 µS/cm	0.07 mg/L	99.40 NTU	77.0 mV	14.95 ft	150.00 ml/min
5/30/2024 9:52 AM	45:00	6.92 pH	19.19 °C	722.21 µS/cm	0.07 mg/L	82.60 NTU	99.4 mV	14.95 ft	150.00 ml/min
5/30/2024 9:57 AM	50:00	6.92 pH	19.23 °C	723.97 µS/cm	0.07 mg/L	80.60 NTU	80.6 mV	14.95 ft	150.00 ml/min
5/30/2024 10:02 AM	55:00	6.93 pH	19.25 °C	723.61 µS/cm	0.07 mg/L	68.90 NTU	102.3 mV	14.95 ft	150.00 ml/min
5/30/2024 10:07 AM	01:00:00	6.94 pH	19.44 °C	719.47 µS/cm	0.08 mg/L	66.00 NTU	82.5 mV	14.95 ft	150.00 ml/min

5/30/2024 10:12 AM	01:05:00	6.95 pH	19.41 °C	717.41 µS/cm	0.08 mg/L	54.90 NTU	105.8 mV	14.95 ft	150.00 ml/min
5/30/2024 10:17 AM	01:10:00	6.97 pH	19.41 °C	712.56 µS/cm	0.08 mg/L	43.60 NTU	83.8 mV	14.95 ft	150.00 ml/min
5/30/2024 10:22 AM	01:15:00	6.97 pH	19.35 °C	716.02 µS/cm	0.07 mg/L	37.50 NTU	79.8 mV	14.95 ft	150.00 ml/min
5/30/2024 10:27 AM	01:20:00	6.99 pH	19.41 °C	715.33 µS/cm	0.07 mg/L	31.30 NTU	103.2 mV	14.95 ft	150.00 ml/min
5/30/2024 10:32 AM	01:25:00	6.97 pH	19.46 °C	712.25 µS/cm	0.07 mg/L	28.20 NTU	82.3 mV	14.95 ft	150.00 ml/min
5/30/2024 10:37 AM	01:30:00	6.97 pH	19.39 °C	718.79 µS/cm	0.07 mg/L	25.50 NTU	102.1 mV	14.95 ft	150.00 ml/min
5/30/2024 10:42 AM	01:35:00	6.99 pH	19.45 °C	715.90 µS/cm	0.06 mg/L	22.50 NTU	105.8 mV	14.95 ft	150.00 ml/min
5/30/2024 10:47 AM	01:40:00	6.98 pH	19.46 °C	711.90 µS/cm	0.06 mg/L	20.60 NTU	80.9 mV	14.95 ft	150.00 ml/min
5/30/2024 10:52 AM	01:45:00	7.00 pH	19.44 °C	712.95 µS/cm	0.06 mg/L	19.30 NTU	101.1 mV	14.95 ft	150.00 ml/min
5/30/2024 10:57 AM	01:50:00	7.02 pH	19.46 °C	707.88 µS/cm	0.06 mg/L	16.70 NTU	79.5 mV	14.95 ft	150.00 ml/min
5/30/2024 11:02 AM	01:55:00	7.02 pH	19.35 °C	713.67 µS/cm	0.06 mg/L	13.40 NTU	76.7 mV	14.95 ft	150.00 ml/min
5/30/2024 11:07 AM	02:00:00	7.04 pH	19.45 °C	712.10 µS/cm	0.06 mg/L	12.90 NTU	100.6 mV	14.95 ft	150.00 ml/min
5/30/2024 11:12 AM	02:05:00	7.04 pH	19.43 °C	705.54 µS/cm	0.05 mg/L	10.33 NTU	81.4 mV	14.95 ft	150.00 ml/min
5/30/2024 11:17 AM	02:10:00	7.05 pH	19.48 °C	708.45 µS/cm	0.05 mg/L	9.76 NTU	78.9 mV	14.95 ft	150.00 ml/min
5/30/2024 11:22 AM	02:15:00	7.04 pH	19.50 °C	711.64 µS/cm	0.05 mg/L	7.94 NTU	102.9 mV	14.95 ft	150.00 ml/min
5/30/2024 11:27 AM	02:20:00	7.06 pH	19.50 °C	705.54 µS/cm	0.05 mg/L	6.92 NTU	81.5 mV	14.95 ft	150.00 ml/min
5/30/2024 11:32 AM	02:25:00	7.07 pH	19.47 °C	706.63 µS/cm	0.05 mg/L	6.48 NTU	103.6 mV	14.95 ft	150.00 ml/min
5/30/2024 11:37 AM	02:30:00	7.05 pH	19.49 °C	702.56 µS/cm	0.05 mg/L	6.24 NTU	82.7 mV	14.95 ft	150.00 ml/min
5/30/2024 11:42 AM	02:35:00	7.05 pH	19.58 °C	707.31 µS/cm	0.05 mg/L	5.41 NTU	106.4 mV	14.95 ft	150.00 ml/min
5/30/2024 11:47 AM	02:40:00	7.06 pH	19.69 °C	703.83 µS/cm	0.05 mg/L	4.71 NTU	83.4 mV	14.95 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.
HAM-AP1-FD-01	Grab.
HAM-PT-09-TS-WG-05302024	Grab.

Low-Flow Test Report:

Test Date / Time: 5/30/2024 2:05:29 PM
Project: Plant Hammond
Operator Name: Zain Webb

Location Name: PT-10 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.45 ft Total Depth: 30.45 ft Initial Depth to Water: 14.98 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 25.45 ft Estimated Total Volume Pumped: 5.25 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.1 ft	Instrument Used: Aqua TROLL 400 Serial Number: 965586
---	---	--

Test Notes:
Appendix III and IV, Major Ions, and Treatability Study Sample (no RADs).
Fe2+ = 0 mg/L.
Fe = 0 mg/L.

Weather Conditions:
Sunny, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/30/2024 2:05 PM	00:00	6.75 pH	20.31 °C	641.23 µS/cm	0.51 mg/L	16.10 NTU	33.4 mV	14.98 ft	150.00 ml/min
5/30/2024 2:10 PM	05:00	6.87 pH	20.03 °C	691.81 µS/cm	0.51 mg/L	8.38 NTU	15.2 mV	15.08 ft	150.00 ml/min
5/30/2024 2:15 PM	10:00	6.96 pH	20.24 °C	710.77 µS/cm	0.53 mg/L	6.54 NTU	21.4 mV	15.08 ft	150.00 ml/min
5/30/2024 2:20 PM	15:00	6.86 pH	20.12 °C	701.76 µS/cm	0.46 mg/L	4.46 NTU	30.0 mV	15.08 ft	150.00 ml/min
5/30/2024 2:25 PM	20:00	6.85 pH	20.21 °C	695.18 µS/cm	0.43 mg/L	3.92 NTU	34.9 mV	15.08 ft	150.00 ml/min
5/30/2024 2:30 PM	25:00	6.83 pH	20.17 °C	672.75 µS/cm	0.46 mg/L	3.28 NTU	40.0 mV	15.08 ft	150.00 ml/min
5/30/2024 2:35 PM	30:00	6.81 pH	20.16 °C	664.75 µS/cm	0.43 mg/L	3.01 NTU	52.5 mV	15.08 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.
HAM-PT-10-TS-WG-05302024	Grab.

Low-Flow Test Report:

Test Date / Time: 5/29/2024 3:32:11 PM
Project: Plant Hammond
Operator Name: Zain Webb

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17 ft Total Depth: 27 ft Initial Depth to Water: 11.3 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22 ft Estimated Total Volume Pumped: 10.65 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.04 ft	Instrument Used: Aqua TROLL 400 Serial Number: 965586
--	--	--

Test Notes:
Appendix III and IV and Major Ions (no RADs).
Fe2+ = 0 mg/L.
Fe = 0 mg/L.

Weather Conditions:
Sunny, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/29/2024 3:32 PM	00:00	7.18 pH	25.73 °C	609.75 µS/cm	0.72 mg/L	21.20 NTU	76.3 mV	11.30 ft	150.00 ml/min
5/29/2024 3:37 PM	05:00	6.96 pH	19.68 °C	728.70 µS/cm	0.41 mg/L	20.60 NTU	100.5 mV	11.32 ft	150.00 ml/min
5/29/2024 3:42 PM	10:00	6.94 pH	19.36 °C	726.23 µS/cm	0.40 mg/L	18.10 NTU	143.3 mV	11.33 ft	150.00 ml/min
5/29/2024 3:47 PM	15:00	6.97 pH	19.48 °C	727.51 µS/cm	0.37 mg/L	13.60 NTU	160.6 mV	11.33 ft	150.00 ml/min
5/29/2024 3:52 PM	20:00	6.97 pH	19.52 °C	726.39 µS/cm	0.36 mg/L	10.41 NTU	172.6 mV	11.34 ft	150.00 ml/min
5/29/2024 3:57 PM	25:00	6.98 pH	19.47 °C	706.81 µS/cm	0.44 mg/L	9.50 NTU	181.0 mV	11.34 ft	150.00 ml/min
5/29/2024 4:02 PM	30:00	6.99 pH	19.62 °C	722.22 µS/cm	0.39 mg/L	9.07 NTU	142.9 mV	11.34 ft	150.00 ml/min
5/29/2024 4:07 PM	35:00	7.00 pH	19.52 °C	713.02 µS/cm	0.39 mg/L	8.97 NTU	138.6 mV	11.34 ft	150.00 ml/min
5/29/2024 4:12 PM	40:00	6.99 pH	19.45 °C	642.62 µS/cm	0.38 mg/L	9.32 NTU	137.8 mV	11.34 ft	150.00 ml/min
5/29/2024 4:17 PM	45:00	7.00 pH	19.27 °C	724.99 µS/cm	0.39 mg/L	8.07 NTU	135.3 mV	11.34 ft	150.00 ml/min
5/29/2024 4:22 PM	50:00	7.00 pH	19.37 °C	693.70 µS/cm	0.42 mg/L	---	129.9 mV	11.34 ft	150.00 ml/min
5/29/2024 4:22 PM	50:48	7.01 pH	19.31 °C	640.95 µS/cm	0.40 mg/L	6.80 NTU	112.9 mV	11.34 ft	150.00 ml/min
5/29/2024 4:27 PM	55:48	7.01 pH	19.41 °C	713.33 µS/cm	0.49 mg/L	5.95 NTU	122.6 mV	11.34 ft	150.00 ml/min

5/29/2024 4:32 PM	01:00:48	7.00 pH	19.23 °C	707.15 µS/cm	0.43 mg/L	4.70 NTU	158.4 mV	11.34 ft	150.00 ml/min
5/29/2024 4:37 PM	01:05:48	7.00 pH	19.15 °C	708.73 µS/cm	0.42 mg/L	3.84 NTU	161.9 mV	11.34 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-11	Grab.

Low-Flow Test Report:

Test Date / Time: 5/29/2024 10:52:59 AM
Project: Plant Hammond
Operator Name: Zain Webb

Location Name: PT-12 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17 ft Total Depth: 27 ft Initial Depth to Water: 11.14 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22 ft Estimated Total Volume Pumped: 10.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 965586
---	---	--

Test Notes:
Appendix III and IV and Major Ions (No RADs).
Fe2+ = 0 mg/L.
Fe = 0 mg/L.

Weather Conditions:
Sunny, 75 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
5/29/2024 10:52 AM	00:00	6.61 pH	19.85 °C	675.59 µS/cm	0.52 mg/L	12.30 NTU	75.5 mV	11.14 ft	150.00 ml/min
5/29/2024 10:57 AM	05:00	6.64 pH	19.25 °C	659.00 µS/cm	0.45 mg/L	8.33 NTU	81.4 mV	11.16 ft	150.00 ml/min
5/29/2024 11:02 AM	10:00	6.66 pH	19.32 °C	687.80 µS/cm	0.55 mg/L	9.76 NTU	102.1 mV	11.16 ft	150.00 ml/min
5/29/2024 11:07 AM	15:00	6.67 pH	19.27 °C	683.39 µS/cm	1.16 mg/L	8.75 NTU	86.7 mV	11.16 ft	150.00 ml/min
5/29/2024 11:12 AM	20:00	6.69 pH	19.31 °C	683.56 µS/cm	0.83 mg/L	5.99 NTU	87.0 mV	11.17 ft	150.00 ml/min
5/29/2024 11:17 AM	25:00	6.71 pH	19.40 °C	678.81 µS/cm	0.26 mg/L	4.57 NTU	85.5 mV	11.17 ft	150.00 ml/min
5/29/2024 11:22 AM	30:00	6.71 pH	19.44 °C	678.62 µS/cm	1.58 mg/L	4.49 NTU	85.5 mV	11.17 ft	150.00 ml/min
5/29/2024 11:27 AM	35:00	6.76 pH	19.38 °C	673.69 µS/cm	0.52 mg/L	2.84 NTU	84.0 mV	11.17 ft	150.00 ml/min
5/29/2024 11:32 AM	40:00	6.76 pH	19.44 °C	669.07 µS/cm	0.29 mg/L	2.40 NTU	85.5 mV	11.17 ft	150.00 ml/min
5/29/2024 11:37 AM	45:00	6.76 pH	19.32 °C	676.74 µS/cm	0.79 mg/L	1.56 NTU	82.6 mV	11.17 ft	150.00 ml/min
5/29/2024 11:42 AM	50:00	6.79 pH	19.38 °C	676.53 µS/cm	1.37 mg/L	1.35 NTU	81.5 mV	11.17 ft	150.00 ml/min
5/29/2024 11:47 AM	55:00	6.81 pH	19.38 °C	673.08 µS/cm	0.88 mg/L	1.26 NTU	102.2 mV	11.17 ft	150.00 ml/min
5/29/2024 11:52 AM	01:00:00	6.81 pH	19.32 °C	669.80 µS/cm	0.80 mg/L	1.28 NTU	84.9 mV	11.17 ft	150.00 ml/min

5/29/2024 11:57 AM	01:05:00	6.82 pH	19.36 °C	678.21 µS/cm	0.71 mg/L	0.73 NTU	81.4 mV	11.17 ft	150.00 ml/min
-----------------------	----------	---------	----------	--------------	-----------	----------	---------	----------	---------------

Samples

Sample ID:	Description:
HAM-PT-12	Grab.

Calibration Forms

EQUIPMENT CALIBRATION LOG

Field Technician: Amanda Neely

Date: 2/13/23

Time (start): 0850

Time (finish): 0910

smarTroll SN: 884187

Turbidity Meter Type: LaMotte 2020we

SN: 7009-1416

Weather Conditions: 73-91, sunny

Facility and Unit: Piant+Hammond

Project No.: GW6581

Calibration log

	Standard Lot # / Date of Expiration	Temp of Standard (°C)	Value of Standard	Initial Reading	Post-Cal Reading	Acceptable Range	Pass?	Comments
Specific Conductance (µS/cm)	22250153 11/23	25.72	4490	4122.4	4487.6	+/- 5 %	☒ Yes No	
pH (4)			4.00	4.02	4.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (4) check	-	-	4.00	-	-	+/- 0.1 SU	Yes No	
pH (7)	2216893 11/23	25.7	7.00	7.35	7.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (7) check	-	-	7.00	-	-	+/- 0.1 SU	Yes No	
pH (10)	21320202 12/23	25.5	10.00	10.3	10.0	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (10) check	-	-	10.00	-	-	+/- 0.1 SU	Yes No	
ORP (mV)	21390144 11/23	24.72	228	215.4	227.7	+/- 20mV	☒ Yes No	
DO (%) (1pt, 100% water saturated air cal)			100	101.11%	100.00%	+/- 6 % saturation	☒ Yes No	
Turbidity 0 NTU			0	0.20	0.00	+/- 0.5 NTU	☒ Yes No	
Turbidity 1 NTU			1.00	0.71	0.81	+/- 0.5 NTU	☒ Yes No	
Turbidity 10 NTU			10.00	11.30	9.99	+/- 0.5 NTU	☒ Yes No	

EQUIPMENT CALIBRATION LOG

Field Technician: Alana Neely

Date: 7/14/23

Time (start): 0730

Time (finish): 0745

smarTroll SN: 884187

Turbidity Meter Type: LaMotte 2020we

SN: 7009-1416

Weather Conditions: 73-93°, Cloudy

Facility and Unit: Plant Hammond

Project No.: GW6581

Calibration log

	Standard Lot # / Date of Expiration	Temp of Standard (°C)	Value of Standard	Initial Reading	Post-Cal Reading	Acceptable Range	Pass?	Comments
Specific Conductance (µS/cm)	22250153	27.25	4490	4508.8	4486.0	+/- 5 %	☒ Yes No	
pH (4)	11/23		4.00	4.03	4.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (4) check	-	-	4.00	-	-	+/- 0.1 SU	Yes No	
pH (7)	2216893	27.01	7.00	7.36	6.99	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (7) check	-		7.00	-	-	+/- 0.1 SU	Yes No	
pH (10)	21320202	26.31	10.00	9.73	10.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (10) check	-		10.00	-	-	+/- 0.1 SU	Yes No	
ORP (mV)	21390144	25.73	228	222.6	228.1	+/- 20mV	☒ Yes No	
DO (%) (1pt, 100% water saturated air cal)			100	98.43%	100.54%	+/- 6 % saturation	☒ Yes No	
Turbidity 0 NTU			0	0.21	0.01	+/- 0.5 NTU	☒ Yes No	
Turbidity 1 NTU			1.00	0.55	0.70	+/- 0.5 NTU	☒ Yes No	
Turbidity 10 NTU			10.00	11.53	10.01	+/- 0.5 NTU	☒ Yes No	

EQUIPMENT CALIBRATION LOG

Field Technician: Alana Neely

Date: 7/17/23

Time (start): 0855

Time (finish): 0915

SmartTroll SN: 884187

Turbidity Meter Type: LaMotte 2020we

SN: 7009-1416

Weather Conditions: 66-93°, sunny

Facility and Unit: Plant Hammond

Project No.: GW6581

Calibration log

	Standard Lot # / Date of Expiration	Temp of Standard (°C)	Value of Standard	Initial Reading	Post-Cal Reading	Acceptable Range	Pass?	Comments
Specific Conductance (µS/cm)	22250153 11/23	25.52	4490	4440.8	4492.1	+/- 5 %	☒ Yes No	
pH (4)			4.00	4.05	4.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (4) check	-	-	4.00	-	-	+/- 0.1 SU	Yes No	
pH (7)	2216893 11/23	25.45	7.00	7.32	7.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (7) check	-	-	7.00	-	-	+/- 0.1 SU	Yes No	
pH (10)	21320202 12/23	24.03	10.00	9.03	10.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (10) check	-	-	10.00	-	-	+/- 0.1 SU	Yes No	
ORP (mV)	21390144 11/23	23.02	228	227.0	228.0	+/- 20mV	☒ Yes No	
DO (%) (1pt, 100% water saturated air cal)			100	100.42	100.25	+/- 6 % saturation	☒ Yes No	
Turbidity 0 NTU			0	0.14	0.01	+/- 0.5 NTU	☒ Yes No	
Turbidity 1 NTU			1.00	0.70	0.95	+/- 0.5 NTU	☒ Yes No	
Turbidity 10 NTU			10.00	11.51	10.01	+/- 0.5 NTU	☒ Yes No	

EQUIPMENT CALIBRATION LOG

Field Technician: Alana Neely

Date: 7/18/23

Time (start): 0755

Time (finish): 0810

smarTroll SN: 884187

Turbidity Meter Type: LaMotte 2020we

SN: 7009-1416

Weather Conditions: 67-93° sunny

Facility and Unit: Plant Hammond

Project No.: GW6581

Calibration log

	Standard Lot # / Date of Expiration	Temp of Standard (°C)	Value of Standard	Initial Reading	Post-Cal Reading	Acceptable Range	Pass?	Comments
Specific Conductance (µS/cm)	22250153 11/23	23.95	4490	4490.7	4490.8	+/- 5 %	☒ Yes No	
pH (4)			4.00	4.04	4.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (4) check	—	—	4.00	—	—	+/- 0.1 SU	Yes No	
pH (7)	2216893 11/23	23.68	7.00	7.35	7.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (7) check			7.00	—	—	+/- 0.1 SU	Yes No	
pH (10)	2132002 12/23	23.28	10.00	9.68	10.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (10) check			10.00	—	—	+/- 0.1 SU	Yes No	
ORP (mV)	21390144 11/23	22.72	228	226.3	228.1	+/- 20mV	☒ Yes No	
DO (%) (1pt, 100% water saturated air cal)			100	100.00%	100.00%	+/- 6 % saturation	☒ Yes No	
Turbidity 0 NTU			0	0.22	0.06	+/- 0.5 NTU	☒ Yes No	
Turbidity 1 NTU			1.00	0.40	0.96	+/- 0.5 NTU	☒ Yes No	
Turbidity 10 NTU			10.00	11.38	9.96	+/- 0.5 NTU	☒ Yes No	

EQUIPMENT CALIBRATION LOG

Field Technician: Alana Nelly

Date: 7/19/23

Time (start): 0745

Time (finish): 0800

smarTroll SN: 884187

Turbidity Meter Type: LaMotte 2020we

SN: 7009-1416

Weather Conditions: 68-93° cloudy

Facility and Unit: Plant Hammond Project No.: GW6581

Calibration log

	Standard Lot # / Date of Expiration	Temp of Standard (°C)	Value of Standard	Initial Reading	Post-Cal Reading	Acceptable Range	Pass?	Comments
Specific Conductance (µS/cm)	22250153 11/23	24.77	4490	4479.0	4485.6	+/- 5 %	☒ Yes No	
pH (4)			4.00	4.03	3.99	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (4) check	-	-	4.00	-	-	+/- 0.1 SU	Yes No	
pH (7)	22140893 11/23	24.65	7.00	7.38	7.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (7) check	-	-	7.00	-	-	+/- 0.1 SU	Yes No	
pH (10)	21320702 12/23	24.27	10.00	9.64	10.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (10) check	-	-	10.00	-	-	+/- 0.1 SU	Yes No	
ORP (mV)	21390144 11/23	23.89	228	222.5	228.1	+/- 20mV	☒ Yes No	
DO (%) (1pt, 100% water saturated air cal)			100	98.7	100.017	+/- 6 % saturation	☒ Yes No	
Turbidity 0 NTU			0	0.44	0.00	+/- 0.5 NTU	☒ Yes No	
Turbidity 1 NTU			1.00	0.69	0.94	+/- 0.5 NTU	☒ Yes No	
Turbidity 10 NTU			10.00	11.08	9.99	+/- 0.5 NTU	☒ Yes No	

EQUIPMENT CALIBRATION LOG

Field Technician: C-CAIN Date: 8/9/23 Time (start): 0815 Time (finish): 0845
 smarTroll SN: 883553 Turbidity Meter Type: Laette 2001 SN: 4121-7623
 Weather Conditions: Fog 68 Facility and Unit: Plant Hammond Project No.: GW6581

Calibration log

	Standard Lot # / Date of Expiration	Temp of Standard (°C)	Value of Standard	Initial Reading	Post-Cal Reading	Acceptable Range	Pass?	Comments
Specific Conductance (µS/cm)	22250153 11/23	22.78	4573.5 4490	4573.5	4490	+/- 5 %	☒ Yes No	
pH (4)			4.0	4.07	4.0	+/- 0.1 SU	Yes No	
Mid-Day pH (4) check	// //		4.0	4.02		+/- 0.1 SU	Yes No	
pH (7)	2216893 11/29	23.43	7.0	7.05	7.0	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (7) check	// //		7.0	7.0		+/- 0.1 SU	Yes No	
pH (10)	22110130 8/23	23.75	10.0	10.05	10	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (10) check	// //		10.0	10.03		+/- 0.1 SU	Yes No	
ORP (mV)	21390144 11/23	23.81	228	227.1	228	+/- 20mV	☒ Yes No	
DO (%) (1pt, 100% water saturated air cal)			100	95.23	100	+/- 6 % saturation	☒ Yes No	
Turbidity 0 NTU			0	0.00	0.00	+/- 0.5 NTU	☒ Yes No	
Turbidity 1 NTU			1	1.43	1.13	+/- 0.5 NTU	☒ Yes No	
Turbidity 10 NTU			10	10.75	10	+/- 0.5 NTU	☒ Yes No	

EQUIPMENT CALIBRATION LOG

Field Technician: A. Szewast

Date: 8/9/2023

Time (start): 1145

Time (finish): 1205

smarTroll SN: 883530

Turbidity Meter Type: LaMotte 2020t

SN: 4739-2623

Weather Conditions: Partly cloudy, 73°F

Facility and Unit: Plant Hammond

Project No.: GW6581

Calibration log

	Standard Lot # / Date of Expiration	Temp of Standard (°C)	Value of Standard	Initial Reading	Post-Cal Reading	Acceptable Range	Pass?	Comments
Specific Conductance (µS/cm)	22250153	24.50	4490	4250.9	4490.0	+/- 5 %	☒ Yes No	
pH (4)	11/2023		4.00	4.45	4.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (4) check						+/- 0.1 SU	Yes No	
pH (7)	2216893 11/2023	24.85	7.00	7.32	7.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (7) check						+/- 0.1 SU	Yes No	
pH (10)	21320202 12/2023	25.05	10.00	10.54	10.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (10) check						+/- 0.1 SU	Yes No	
ORP (mV)	21390144 11/2023	25.06	228.0	225.9	228.0	+/- 20mV	☒ Yes No	
DO (%) (1pt, 100% water saturated air cal)			100.00 101.24 8-4-2023	101.24	100.0	+/- 6 % saturation	☒ Yes No	
Turbidity 0 NTU			0.00	0.00	—	+/- 0.5 NTU	☒ Yes No	
Turbidity 1 NTU			1.00	1.08	—	+/- 0.5 NTU	☒ Yes No	
Turbidity 10 NTU			10.00	10.7	9.59	+/- 0.5 NTU	☒ Yes No	

EQUIPMENT CALIBRATION LOG

Field Technician: Elisabeth McDonnell

Date: 8/9/23

Time (start): 830

Time (finish): 850

smarTroll SN: 989630

Turbidity Meter Type: La Motte 2020t

SN: 4109-2623

Weather Conditions: 70, cloudy

Facility and Unit: Plant Hammond

Project No.: GW6581

Calibration log

	Standard Lot # / Date of Expiration	Temp of Standard (°C)	Value of Standard	Initial Reading	Post-Cal Reading	Acceptable Range	Pass?	Comments
Specific Conductance (µS/cm)	22250153 11/23 ↓	23.18				+/- 5 %	Yes No	
pH (4)			4.00	3.94	4.00	+/- 0.1 SU	☒ Yes ☐ No	
Mid-Day pH (4) check						+/- 0.1 SU	Yes No	
pH (7)	2216893 11/23 ↓	23.48	7.0	6.85	7.0	+/- 0.1 SU	☒ Yes ☐ No	
Mid-Day pH (7) check						+/- 0.1 SU	Yes No	
pH (10)	21320202 12/23 ↓	23.70	10.0	10.0	10.0	+/- 0.1 SU	☒ Yes ☐ No	
Mid-Day pH (10) check						+/- 0.1 SU	Yes No	
ORP (mV)	21390149 11/23	23.85	228	230.90	228	+/- 20mV	☒ Yes ☐ No	
DO (%) (1pt, 100% water saturated air cal)			100%	102.36%	100%	+/- 6 % saturation	☒ Yes ☐ No	
Turbidity 0 NTU			0.0	0.0	0.0	+/- 0.5 NTU	☒ Yes ☐ No	
Turbidity 1 NTU			1.0	1.0	1.0	+/- 0.5 NTU	☒ Yes ☐ No	
Turbidity 10 NTU			10.0	11.1	10.4	+/- 0.5 NTU	☒ Yes ☐ No	

EQUIPMENT CALIBRATION LOG

Field Technician: Thomas Kessler

Date: 8/14/23

Time (start): 0800

Time (finish): 0825

smarTroll SN: 850729

Turbidity Meter Type: Lemotte 2020me

SN: 1475-2101

Weather Conditions: Seagun 75°

Facility and Unit: Plant Hammond

Project No.: GLCS881

Calibration log

	Standard Lot # / Date of Expiration	Temp of Standard (°C)	Value of Standard	Initial Reading	Post-Cal Reading	Acceptable Range	Pass?	Comments
Specific Conductance (µS/cm)	2225053	21.91	4490	41562	4490	+/- 5 %	☒ Yes No	
pH (4)	11/23		4	4.04	4.0	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (4) check	↓	29	4	4.03	—	+/- 0.1 SU	☒ Yes No	
pH (7)	2226893 11/23	22.77	7.06 7.00	7.05	7.00	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (7) check	↓	29	7	6.98	—	+/- 0.1 SU	☒ Yes No	
pH (10)	21380202 12/23	22.62	10.00	10.01	10.0	+/- 0.1 SU	☒ Yes No	
Mid-Day pH (10) check	↓	22	10	9.91	—	+/- 0.1 SU	☒ Yes No	
ORP (mV)	22260085 8/23		228	227.7	228	+/- 20mV	☒ Yes No	
DO (%) (1pt, 100% water saturated air cal)			100	99.08	100	+/- 6 % saturation	☒ Yes No	
Turbidity 0 NTU			0	.53	0	+/- 0.5 NTU	☒ Yes No	
Turbidity 1 NTU			1	.56	.93	+/- 0.5 NTU	☒ Yes No	
Turbidity 10 NTU			10	10.35	10.1	+/- 0.5 NTU	☒ Yes No	

Site Name: Hammond

Field Instrumentation Calibration Form

Date: 5/2/23Calibrated By: ERField Conditions: 60-80 sunny

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aqua Troll 400	183546
Turbidity Meter	12mflite 2022	1511-4811

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (uS/cm)	4,490	24005593	12/29	AN
pH (SU)	4.00	24004012	12/29	AN
pH (SU)	7.00	24004517	12/29	AN
pH (SU)	10.00	24000083	12/29	AN
D.O. (%)	N/A	—	12/29	AN
ORP (mV)	228.0	24006805	12/29	AN

Calibration					
Time Start	8:15		Time Finish	8:17	
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (uS/cm)	4,490	4490	19.86	± 10% of standard	EPA 2023
pH (SU)	4.00	4.00	27.25	± 0.1	GWMP
pH (SU)	7.00	7.00	27.26	± 0.1	GWMP
pH (SU)	10.00	10.00	26.99	± 0.1	GWMP
D.O. (%)	N/A	100.1	27.22	± 10%	NA
ORP (mV)	228.0	228	26.52	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	1		
	10	9.91		
	—	—		

Calibration Check					
Time Start	13:15		Time Finish	2:40	
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (uS/cm)	4,490	2490	36.04	± 10% of standard	EPA 2023
pH (SU)	4.00	4	34.13	± 0.1	GWMP
pH (SU)	7.00	7	33.21	± 0.1	GWMP
pH (SU)	10.00	10	31.94	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	0.92		
	10	9.71		
	—	—		

Notes:

Site Name: Pond Hammad

Field Instrumentation Calibration Form

Date: 6-2-24Calibrated By: Zain W.Field Conditions: Clear, 70°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	AquaTide 400	966105
Turbidity Meter	LAOM-100	7009-1416

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (uS/cm)	4,490	74005593	12/24	ATR
pH (SU)	4.00	74005593	12/24	
pH (SU)	7.00	24004511	12/24	
pH (SU)	10.00	24000085	12/24	
D.O. (%)	N/A	-	-	
ORP (mV)	228.0	24006903	12/24	

Calibration					
Time Start <u>0828</u>		Time Finish <u>0848</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (uS/cm)	4,490	4490	22.01	± 10% of standard	EPA 2023
pH (SU)	4.00	4.0	22.17	± 0.1	GWMP
pH (SU)	7.00	7.0	22.33	± 0.1	GWMP
pH (SU)	10.00	10.0	22.55	± 0.1	GWMP
D.O. (%)	N/A	-	97.56	± 10%	NA
ORP (mV)	228.0	228.0	22.19	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	1		
	10	10		

Calibration Check					
Time Start <u>1510</u>		Time Finish <u>1523</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (uS/cm)	4,490	4490	26.05	± 10% of standard	EPA 2023
pH (SU)	4.00	4.0	26.33	± 0.1	GWMP
pH (SU)	7.00	7.0	25.26	± 0.1	GWMP
pH (SU)	10.00	10.0	24.38	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	1		
	10	10		

Notes:

Had problem w/ conductivity; solved by restoring factory calibration

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 5-9-2024Calibrated By: A. SwestField Conditions: Thunderstorms, 66°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>AquaTronics 400</u>	<u>850751</u>
Turbidity Meter	<u>La Motte 2720T</u>	<u>7009-1416</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	<u>24000093</u>	<u>12/2024</u>	<u>AIR</u>
pH (SU)	4.00	<u>240015593</u>	<u>12/2024</u>	<u>AIR</u>
pH (SU)	7.00	<u>24003397</u>	<u>11/2024</u>	<u>AIR</u>
pH (SU)	10.00	<u>24004996</u>	<u>11/2024</u>	<u>AIR</u>
D.O. (%)	N/A	<u>-</u>	<u>-</u>	<u>-</u>
ORP (mV)	228.0	<u>24006903</u>	<u>11/2024</u>	<u>AIR</u>

Calibration					
Time Start	<u>1020</u>	Time Finish	<u>1040</u>		
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4490.0</u>	<u>23.34</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>23.54</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>23.52</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>23.57</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>23.04</u>	± 10%	NA
ORP (mV)	228.0	<u>228.0</u>	<u>23.45</u>	± 10	EPA 2023

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)	<u>0</u>	<u>0.00</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>0.70</u>		
	<u>10</u>	<u>10.12</u>		
	<u>-</u>	<u>-</u>		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)			± 10% of standard	EPA 2023

Notes:

Site Name: GP Plant Hammond

Field Instrumentation Calibration Form

Date: 5/13/24Calibrated By: J. NewsonField Conditions: Cloudy, 60°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Hantronic	966105
Turbidity Meter	Lamotte 2020 WC	1511-4111

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	24005593	12/2024	AIR
pH (SU)	4.00	24005593	12/2024	AIR
pH (SU)	7.00	24004517	12/2024	AIR
pH (SU)	10.00	24011080	12/2024	AIR
D.O. (%)	N/A			
ORP (mV)	228.0	24000903	12/2024	AIR

Calibration					
Time Start	0750	Time Finish	820		
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	4891.4	19.05	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.04	19.14	± 0.1	GWMP
pH (SU)	7.00	7.04	19.24	± 0.1	GWMP
pH (SU)	10.00	10.13	19.33	± 0.1	GWMP
D.O. (%)	N/A	99.75	19.24	$\pm 10\%$	NA
ORP (mV)	228.0	228.5	19.32	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0.01	$\pm 10\%$ of standard	EPA 2023
	1	1.01		
	10	9.98		

Calibration Check					
Time Start	1230	Time Finish	1245		
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	4460.91	20.12	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.03	20.12	± 0.1	GWMP
pH (SU)	7.00	7.02	19.13	± 0.1	GWMP
pH (SU)	10.00	10.04	20.05	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	$\pm 10\%$ of standard	EPA 2023
	1	1.01		
	10	10		

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 5-15-2024Calibrated By: A. SwastField Conditions: Cloudy, 70°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Amatrol 400</u>	<u>850751</u>
Turbidity Meter	<u>10/10/4 2020</u>	<u>3009-1816</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4.490	<u>2400593</u>	<u>12/2024</u>	<u>AIR</u>
pH (SU)	4.00	<u>2400593</u>	<u>12/2024</u>	<u>AIR</u>
pH (SU)	7.00	<u>2400593</u>	<u>11/2024</u>	<u>AIR</u>
pH (SU)	10.00	<u>24004996</u>	<u>11/2024</u>	<u>AIR</u>
D.O. (%)	N/A			
ORP (mV)	228.0	<u>24006903</u>	<u>11/2024</u>	<u>AIR</u>

Calibration					
Time Start	<u>7:45</u>	Time Finish	<u>8:10</u>		
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490	<u>4490.0</u>	<u>18.97</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>19.15</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>19.33</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>19.47</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100.00</u>	<u>18.62</u>	± 10%	NA
ORP (mV)	228.0	<u>228.0</u>	<u>19.46</u>	± 10	EPA 2023

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)	<u>0</u>	<u>0.00</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>0.73</u>		
	<u>10</u>	<u>9.87</u>		
	<u>—</u>	<u>—</u>		

Calibration Check					
Time Start	<u>1:30</u>	Time Finish	<u>1:40</u>		
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490	<u>4490.0</u>	<u>20.19</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>7.00</u>	<u>29.82</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>28.04</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>27.03</u>	± 0.1	GWMP

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)	<u>0</u>	<u>0.02</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>0.83</u>		
	<u>10</u>	<u>10.08</u>		
	<u>—</u>	<u>—</u>		

Notes:

Site Name: Alan's Hammond

Field Instrumentation Calibration Form

Date: 6/15/24Calibrated By: J. NewsomeField Conditions: cloudy, 60°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aqua Troll	966105
Turbidity Meter	LaMotte 7020T	1711-411

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	74 (X55 89 3)	12/2024	A1V2
pH (SU)	4.00	71 (X55 43)	12/2024	A1V2
pH (SU)	7.00	7400 4517	12/2024	A1V2
pH (SU)	10.00	740000 05	12/2024	A1V2
D.O. (%)	N/A	—	—	—
ORP (mV)	228.0	24 (X) 6905	12/2024	A1V2

Calibration					
Time Start	03:50		Time Finish	08:10	
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	4034.9	20.20	± 10% of standard	EPA 2023
pH (SU)	4.00	4.02	20.35	± 0.1	GWMP
pH (SU)	7.00	7.03	20.30	± 0.1	GWMP
pH (SU)	10.00	10.05	21.01	± 0.1	GWMP
D.O. (%)	N/A	100.11	20.23	± 10%	NA
ORP (mV)	228.0	232.8	20.97	± 10	EPA 2023

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)	0	0	± 10% of standard	EPA 2023
	1	0.98		
	10	10.01		

Calibration Check					
Time Start	14:45		Time Finish	14:55	
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	4109.7	22.4	± 10% of standard	EPA 2023
pH (SU)	4.00	4.02	22.4	± 0.1	GWMP
pH (SU)	7.00	7.03	21.6	± 0.1	GWMP
pH (SU)	10.00	10.0	22.7	± 0.1	GWMP

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)	0	0	± 10% of standard	EPA 2023
	1	1.01		
	10	10.01		

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 5-16-2024Calibrated By: A. S. WestField Conditions: Sunny 70°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Hanna HI 400	8501751
Turbidity Meter	La Motte 2004	7001-1466

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4.490	24005593	12/2024	AIR
pH (SU)	4.00	24005593	12/2024	AIR
pH (SU)	7.00	24005593	11/2024	AIR
pH (SU)	10.00	24004996	11/2024	AIR
D.O. (%)	N/A	~	~	~
ORP (mV)	228.0	24006903	11/2024	AIR

Calibration					
Time Start	800	Time Finish	830		
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490	4480.0	20.04	± 10% of standard	EPA 2023
pH (SU)	4.00	4.00	20.02	± 0.1	GWMP
pH (SU)	7.00	7.00	20.13	± 0.1	GWMP
pH (SU)	10.00	10.00	20.20	± 0.1	GWMP
D.O. (%)	N/A	100.00	20.04	± 10%	NA
ORP (mV)	228.0	228.0	20.04	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0.00	± 10% of standard	EPA 2023
	1	0.81		
	10	10.10		

Calibration Check					
Time Start	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			± 10% of standard	EPA 2023

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 5/14/24Calibrated By: J. NewsomeField Conditions: Sunny, 100°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aqua-trail	16012106
Turbidity Meter	1.1 Mottle 2024	1511-7111

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	24005593	12/2024	AIR
pH (SU)	4.00	24005593	12/2024	AIR
pH (SU)	7.00	24004517	12/2024	AIR
pH (SU)	10.00	24000086	12/2024	AIR
D.O. (%)	N/A	—	—	—
ORP (mV)	228.0	24006903	12/2024	AIR

Calibration					
Time Start		Time Finish			
740		0800			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	4435.9	19.9	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.00	20.17	± 0.1	GWMP
pH (SU)	7.00	6.97	20.25	± 0.1	GWMP
pH (SU)	10.00	10.02	20.29	± 0.1	GWMP
D.O. (%)	N/A	100.53	20.3	$\pm 10\%$	NA
ORP (mV)	228.0	234.7	20.52	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0.00	$\pm 10\%$ of standard	EPA 2023
	1	0.13		
	10	4.98		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 5-29-24Calibrated By: Jason WebbField Conditions: Sunny 75°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>ANALOG</u> <u>Ameco TROLL 4M</u>	<u>965586</u>
Turbidity Meter	<u>VERMOREL</u> <u>90907</u>	<u>-</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4.490	<u>2400595</u>	<u>12/24</u>	<u>ATR</u>
pH (SU)	4.00	<u>2400593</u>	<u>12/24</u>	<u>ATR</u>
pH (SU)	7.00	<u>2400597</u>	<u>11/24</u>	<u>ATR</u>
pH (SU)	10.00	<u>2400085</u>	<u>12/24</u>	<u>ATR</u>
D.O. (%)	N/A	<u>-</u>	<u>-</u>	<u>ATR</u>
ORP (mV)	228.0	<u>24006203</u>	<u>12/25</u>	<u>ATR</u>

Calibration					
Time Start	<u>0937</u>	Time Finish	<u>0959</u>		
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490	<u>4490</u>	<u>73.69</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>23.87</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>24.17</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>24.35</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>-</u>	<u>24.51</u>	± 10%	NA
ORP (mV)	228.0	<u>228.0</u>	<u>24.51</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		

Calibration Check					
Time Start	<u>1500</u>	Time Finish	<u>1515</u>		
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490	<u>4490</u>	<u>29.03</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>28.59</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>26.87</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>25.93</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		

Notes:

Site Name Plant Hammond

Field Instrumentation Calibration Form

Date 5-30-24Calibrated By Zain W.Field Conditions Sunny 70°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>dr. son Aqua Controller</u>	<u>965586</u>
Turbidity Meter	<u>La Motte 90207</u>	<u>—</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>24005593</u>	<u>12/24</u>	<u>ATR</u> ↓
pH (SU)	4.00	<u>24005593</u>	<u>12/24</u>	
pH (SU)	7.00	<u>24003599</u>	<u>11/24</u>	
pH (SU)	10.00	<u>24000085</u>	<u>12/24</u>	
D.O. (%)	N/A	<u>—</u>	<u>—</u>	
ORP (mV)	228.0	<u>24006903</u>	<u>12/24</u>	↓

Calibration					
Time Start <u>0819</u>		Time Finish <u>0844</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>4.490</u>	<u>20.32</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>20.75</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>21.90</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>22.55</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>22.21</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>229.0</u>	<u>22.68</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	1	<u>1</u>		
	10	<u>10</u>		

Calibration Check					
Time Start <u>—</u>		Time Finish <u>—</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>—</u>	<u>—</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	7.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	10.00	<u>—</u>	<u>—</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>—</u>	<u>—</u>	$\pm 10\%$ of standard	EPA 2023
	<u>—</u>	<u>—</u>		
	<u>—</u>	<u>—</u>		

Notes:

APPENDIX D

Screening Level Groundwater Analytical Laboratory Results and Field Sampling Forms

Laboratory Analytical Reports

ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 9/12/2024 6:52:08 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-6691-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
9/12/2024 6:52:08 PM

Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	13
Lab Chronicle	15
Certification Summary	17
Method Summary	18
Sample Summary	19
Receipt Checklists	20
End Of Report	21



Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6691-1

Qualifiers

Metals

Qualifier	Qualifier Description
^2	Calibration Blank (ICB and/or CCB) is outside acceptance limits.
B	Compound was found in the blank and sample.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Eurofins Atlanta

3080 Presidential Dr

Atlanta, GA 30340

Phone: 770-457-8177 Fax: 770-457-8188

Chain of Custody Record



Environment Testing

Client Information		Sampler: <u>A. Akbari</u>		Lab PM: Fuller, David		Carrier Tracking No(s):		COC No: 705-3725-1686.2					
Client Contact: Kip Gray		Phone: <u>6269222765</u>		E-Mail: David.Fuller@et.eurofinsus.com		State of Origin:		Page: Page 2 of 3					
Company: Geosyntec Consultants Inc		PWSID:		Analysis Requested						Job #:			
Address: 1255 Roberts Blvd. NW Suite 200		Due Date Requested:		Field Filtered Sample (Yes or No) Perform MS/MSD (Yes or No) 6010 D - Total boron 6020 B - Total Arsenic / Iron 6010 B - Dissolve Arsenic / Iron Total Number of containers						Preservation Codes:			
City: Kennesaw		TAT Requested (days):								Other:			
State, Zip: GA, 30144		Compliance Project: ☐ Yes ☐ No								705-6691 COC			
Phone:		PO #: 100061163											
Email: Kip.Gray@Geosyntec.com		WO #: Project# GW6581G											
Project Name: Plant Hammond		Project #: 70500911											
Site:		SSOW#:											
Sample Identification		Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)							Special Instructions/Note:	
HAM-PT7-09-10-(i)-UNF		9-10-24	1045	G	Water								
HAM-PT7-09-10-(i)-FIL		9-10-24	1045	G	Water								
HAM-PT7-09-10-(ii)-UNF		9-10-24	1235	G	Water								
HAM-PT7-09-10-(ii)-FIL		9-10-24	1235	G	Water								
HAM-PT13-09-10-UNF		9-10-24	1245	G	Water								
HAM-PT13-09-10-FIL		9-10-24	1245	G	Water								
					Water								
					Water								
					Water								
					Water								
					Water								
Possible Hazard Identification ☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☐ Unknown ☐ Radiological						Sample Disposal (A fee may be assessed if samples are retained longer than 1 month) ☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months							
Deliverable Requested: I, II, III, IV, Other (specify)						Special Instructions/QC Requirements:							
Empty Kit Relinquished by:				Date:		Time:		Method of Shipment:					
Relinquished by:		Date/Time: 9/10/2024 1530		Company: Geosyntec		Received by:		Date/Time: 9-10-24 5:00		Company:			
Relinquished by:		Date/Time: 9-10-24 6:15		Company:		Received by:		Date/Time: 9/11/24 805		Company: EUN			
Relinquished by:		Date/Time:		Company:		Received by:		Date/Time:		Company:			
Custody Seals Intact: ☐ Yes ☐ No		Custody Seal No.:		Cooler Temperature(s) °C and Other Remarks: 0.2 2665									

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-6691-1

Job ID: 705-6691-1

Eurofins Atlanta

Job Narrative 705-6691-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers and/or narrative comments are included to explain any exceptions, if applicable.

- Matrix QC may not be reported if insufficient sample is provided or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 9/11/2024 8:05 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 0.2°C.

Receipt Exceptions

For the PT13 samples, it was determined that the Unfiltered water was placed in the bottle labeled Filtered, while the Filtered water for this sample was put in the bottle labeled Unfiltered. For this reason, the Client Sample IDs were swapped for the fifth & sixth samples on this submittal so analytical results are more accurately presented.

Metals

Method 6010D: The method blank for preparation batch 705-11351 and analytical batch 705-11414 contained Boron above the method reporting limit (RL). Associated sample(s) were not re-extracted and/or re-analyzed because results were greater than 10X the value found in the method blank.

Method 6010D: A deviation from the Standard Operating Procedure (SOP) was authorized by client request. Samples were not processed by prep method 3010 and analyzed straight from the bottle.

Method 6010D: The method blank for preparation batch 705-11351 and analytical batch 705-11617 contained Boron above the reporting limit (RL). Associated sample(s) were not re-extracted and/or re-analyzed because results were greater than 10X the value found in the method blank.

Method 6020B - Total Recoverable: A deviation from the Standard Operating Procedure (SOP) was authorized by client request: Samples with a prep date & time of 9/11/24 @ 11:38 and 9/11/24 @ 16:06 were not processed by prep method 3005 and analyzed straight from the bottle.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6691-1

Client Sample ID: HAM-PT7-09-10-(i)-UNF

Lab Sample ID: 705-6691-1

Date Collected: 09/10/24 10:45

Matrix: Water

Date Received: 09/11/24 08:05

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.60	B	0.040	0.026	mg/L		09/11/24 12:10	09/11/24 14:39	1
Iron	6.9		0.10	0.035	mg/L		09/11/24 12:10	09/11/24 14:39	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.16		0.0050	0.0013	mg/L		09/11/24 11:38	09/11/24 16:36	1
Arsenic	0.11		0.0050	0.0013	mg/L		09/11/24 16:06	09/11/24 16:57	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6691-1

Client Sample ID: HAM-PT7-09-10-(i)-FIL
Date Collected: 09/10/24 10:45
Date Received: 09/11/24 08:05

Lab Sample ID: 705-6691-2
Matrix: Water

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.016		0.0050	0.0013	mg/L			09/11/24 14:02	1
Iron, Dissolved	ND		0.040	0.018	mg/L			09/11/24 14:02	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6691-1

Client Sample ID: HAM-PT7-09-10-(ii)-UNF

Lab Sample ID: 705-6691-3

Date Collected: 09/10/24 12:35

Matrix: Water

Date Received: 09/11/24 08:05

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.60	B	0.040	0.026	mg/L		09/11/24 12:10	09/11/24 14:42	1
Iron	1.0		0.10	0.035	mg/L		09/11/24 12:10	09/11/24 14:42	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.055		0.0050	0.0013	mg/L		09/11/24 11:38	09/11/24 16:54	1
Arsenic	0.060		0.0050	0.0013	mg/L		09/12/24 07:01	09/12/24 13:39	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6691-1

Client Sample ID: HAM-PT7-09-10-(ii)-FIL
Date Collected: 09/10/24 12:35
Date Received: 09/11/24 08:05

Lab Sample ID: 705-6691-4
Matrix: Water

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.032		0.0050	0.0013	mg/L			09/11/24 14:04	1
Iron, Dissolved	ND		0.040	0.018	mg/L			09/11/24 14:04	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6691-1

Client Sample ID: HAM-PT13-09-10-FIL
Date Collected: 09/10/24 12:45
Date Received: 09/11/24 08:05

Lab Sample ID: 705-6691-5
Matrix: Water

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.038		0.0050	0.0013	mg/L			09/11/24 16:52	1
Iron, Dissolved	1.2		0.040	0.018	mg/L			09/11/24 16:52	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6691-1

Client Sample ID: HAM-PT13-09-10-UNF

Lab Sample ID: 705-6691-6

Date Collected: 09/10/24 12:45

Matrix: Water

Date Received: 09/11/24 08:05

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.72	B ^2	0.040	0.026	mg/L		09/12/24 07:15	09/12/24 13:55	1
Iron	15		0.10	0.035	mg/L		09/12/24 07:15	09/12/24 13:55	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.059		0.0050	0.0013	mg/L		09/11/24 16:06	09/11/24 13:51	1
Arsenic	0.073		0.0050	0.0013	mg/L		09/12/24 07:15	09/12/24 13:41	1

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6691-1

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-11351/1-A
Matrix: Water
Analysis Batch: 11414

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 11351

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.0549		0.040	0.026	mg/L		09/11/24 12:10	09/11/24 14:30	1
Iron	ND		0.10	0.035	mg/L		09/11/24 12:10	09/11/24 14:30	1

Lab Sample ID: LCS 705-11351/2-A
Matrix: Water
Analysis Batch: 11414

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 11351

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	1.00	0.997		mg/L		100	80 - 120
Iron	10.0	9.23		mg/L		92	80 - 120

Lab Sample ID: LCSD 705-11351/3-A
Matrix: Water
Analysis Batch: 11414

Client Sample ID: Lab Control Sample Dup
Prep Type: Total/NA
Prep Batch: 11351

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron	1.00	0.984		mg/L		98	80 - 120	1	20
Iron	10.0	9.11		mg/L		91	80 - 120	1	20

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-11348/1-A
Matrix: Water
Analysis Batch: 11459

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 11348

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	ND		0.0050	0.0013	mg/L		09/11/24 11:38	09/11/24 16:25	1

Lab Sample ID: LCS 705-11348/2-A
Matrix: Water
Analysis Batch: 11459

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 11348

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.100	0.0941		mg/L		94	80 - 120

Lab Sample ID: 705-6691-A-5-E MS
Matrix: Water
Analysis Batch: 11459

Client Sample ID: Matrix Spike
Prep Type: Total Recoverable
Prep Batch: 11348

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.038		0.100	0.131		mg/L		93	75 - 125

Lab Sample ID: 705-6691-A-5-F MSD
Matrix: Water
Analysis Batch: 11459

Client Sample ID: Matrix Spike Duplicate
Prep Type: Total Recoverable
Prep Batch: 11348

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic	0.038		0.100	0.134		mg/L		96	75 - 125	2	20

Eurofins Atlanta

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6691-1

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: MB 705-11357/1-A

Matrix: Water

Analysis Batch: 11410

Client Sample ID: Method Blank

Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	ND		0.0050	0.0013	mg/L			09/11/24 13:46	1
Iron, Dissolved	ND		0.040	0.018	mg/L			09/11/24 13:46	1

Lab Sample ID: LCS 705-11357/2-A

Matrix: Water

Analysis Batch: 11410

Client Sample ID: Lab Control Sample

Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic, Dissolved	0.100	0.0843		mg/L		84	80 - 120
Iron, Dissolved	1.00	0.813		mg/L		81	80 - 120

Lab Sample ID: 705-6691-A-6 MS

Matrix: Water

Analysis Batch: 11410

Client Sample ID: Matrix Spike

Prep Type: Dissolved

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic, Dissolved	0.059		0.100	0.145		mg/L		86	75 - 125
Iron, Dissolved	3.1		1.00	4.09		mg/L		95	75 - 125

Lab Sample ID: 705-6691-A-6 MSD

Matrix: Water

Analysis Batch: 11410

Client Sample ID: Matrix Spike Duplicate

Prep Type: Dissolved

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic, Dissolved	0.059		0.100	0.146		mg/L		88	75 - 125	1	20
Iron, Dissolved	3.1		1.00	4.07		mg/L		93	75 - 125	1	20

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6691-1

Client Sample ID: HAM-PT7-09-10-(i)-UNF

Date Collected: 09/10/24 10:45

Date Received: 09/11/24 08:05

Lab Sample ID: 705-6691-1

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			11351	SA	EET ATL	09/11/24 12:10
Total/NA	Analysis	6010D		1	11414	DS	EET ATL	09/11/24 14:39
Total Recoverable	Prep	3005A			11348	SA	EET ATL	09/11/24 11:38
Total Recoverable	Analysis	6020B		1	11459	AD	EET ATL	09/11/24 16:36
Total Recoverable	Prep	3005A			11348	SA	EET ATL	09/11/24 16:06
Total Recoverable	Analysis	6020B		1	11459	AD	EET ATL	09/11/24 16:57

Client Sample ID: HAM-PT7-09-10-(i)-FIL

Date Collected: 09/10/24 10:45

Date Received: 09/11/24 08:05

Lab Sample ID: 705-6691-2

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6020B		1	11410	AD	EET ATL	09/11/24 14:02

Client Sample ID: HAM-PT7-09-10-(ii)-UNF

Date Collected: 09/10/24 12:35

Date Received: 09/11/24 08:05

Lab Sample ID: 705-6691-3

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			11351	SA	EET ATL	09/11/24 12:10
Total/NA	Analysis	6010D		1	11414	DS	EET ATL	09/11/24 14:42
Total Recoverable	Prep	3005A			11348	SA	EET ATL	09/11/24 11:38
Total Recoverable	Analysis	6020B		1	11459	AD	EET ATL	09/11/24 16:54
Total Recoverable	Prep	3005A			11348	SA	EET ATL	09/12/24 07:01
Total Recoverable	Analysis	6020B		1	11614	AD	EET ATL	09/12/24 13:39

Client Sample ID: HAM-PT7-09-10-(ii)-FIL

Date Collected: 09/10/24 12:35

Date Received: 09/11/24 08:05

Lab Sample ID: 705-6691-4

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6020B		1	11410	AD	EET ATL	09/11/24 14:04

Client Sample ID: HAM-PT13-09-10-FIL

Date Collected: 09/10/24 12:45

Date Received: 09/11/24 08:05

Lab Sample ID: 705-6691-5

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6020B		1	11688	TA	EET ATL	09/11/24 16:52

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6691-1

Client Sample ID: HAM-PT13-09-10-UNF
Date Collected: 09/10/24 12:45
Date Received: 09/11/24 08:05

Lab Sample ID: 705-6691-6
Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			11351	SA	EET ATL	09/12/24 07:15
Total/NA	Analysis	6010D		1	11617	DS	EET ATL	09/12/24 13:55
Total Recoverable	Analysis	6020B		1	11682	TA	EET ATL	09/11/24 13:51
Total Recoverable	Prep	3005A			11348	SA	EET ATL	09/11/24 16:06
Total Recoverable	Prep	3005A			11348	SA	EET ATL	09/12/24 07:15
Total Recoverable	Analysis	6020B		1	11614	AD	EET ATL	09/12/24 13:41

Laboratory References:
EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6691-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

1
2
3
4
5
6
7
8
9
10
11
12
13

Method Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6691-1

Method	Method Description	Protocol	Laboratory
6010D	Metals (ICP)	SW846	EET ATL
6020B	Metals (ICP/MS)	SW846	EET ATL
3005A	Preparation, Total Recoverable or Dissolved Metals	SW846	EET ATL
3010A	Preparation, Total Metals	SW846	EET ATL

Protocol References:

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Sample Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6691-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-6691-1	HAM-PT7-09-10-(i)-UNF	Water	09/10/24 10:45	09/11/24 08:05
705-6691-2	HAM-PT7-09-10-(i)-FIL	Water	09/10/24 10:45	09/11/24 08:05
705-6691-3	HAM-PT7-09-10-(ii)-UNF	Water	09/10/24 12:35	09/11/24 08:05
705-6691-4	HAM-PT7-09-10-(ii)-FIL	Water	09/10/24 12:35	09/11/24 08:05
705-6691-5	HAM-PT13-09-10-FIL	Water	09/10/24 12:45	09/11/24 08:05
705-6691-6	HAM-PT13-09-10-UNF	Water	09/10/24 12:45	09/11/24 08:05

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-6691-1

Login Number: 6691

List Source: Eurofins Atlanta

List Number: 1

Creator: Stephens, Andrena

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT

ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 9/12/2024 7:07:48 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-6851-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
9/12/2024 7:07:48 PM

Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	11
Lab Chronicle	12
Certification Summary	13
Method Summary	14
Sample Summary	15
Receipt Checklists	16
End Of Report	17



Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6851-1

Qualifiers

Metals

Qualifier	Qualifier Description
^2	Calibration Blank (ICB and/or CCB) is outside acceptance limits.
B	Compound was found in the blank and sample.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Eurofins Atlanta

3080 Presidential Dr
Atlanta, GA 30340
Phone: 770-457-8177 Fax: 770-457-8188

Chain of Custody Record



Environment Testing

Client Information		Sampler: <u>Ali Akbari</u>		Lab PM: Fuller, David		Carrier Tracking No(s):		COC No: 705-3932-1820.1					
Client Contact: Kip Gray		Phone: <u>626922 2765</u>		E-Mail: David.Fuller@et.eurofinsus.com		State of Origin:		Page: Page 1 of 2					
Company: Geosyntec Consultants Inc		PWSID:		Analysis Requested						Job #:			
Address: 1255 Roberts Blvd. NW Suite 200		Due Date Requested:		Field Filtered Sample (Yes or No) Perform: MS/MSD (Yes or No) Total Botton total Arsenic/iron dissolved arsenic/iron						Preservation Codes:			
City: Kennesaw		TAT Requested (days): <u>Sameday</u>								Other:			
State, Zip: GA, 30144		Compliance Project: ☐ Yes ☐ No								705-6851 COC			
Phone:		PO #: 100061163											
Email: Kip.Gray@Geosyntec.com		WO #: Project# GW6581G											
Project Name: Plant Hammond		Project #: 70500911											
Site:		SSOW#:											
Sample Identification		Sample Date		Sample Time		Sample Type (C=comp, G=grab)		Matrix (W=water, S=solid, O=waste/oli, BT=Tissue, A=Air)		Total Number of containers		Special Instructions/Note:	
HAM-PT7-09-12-i-UNF		9/12/24		950		G		Water					
HAM-PT7-09-12-i-FIL		↓		950		↓		Water					
HAM-PT7-09-12-ii-UNF		↓		1045		↓		Water					
HAM-PT7-09-12-ii-FIL		↓		1045				Water					
								Water					
								Water					
								Water					
								Water					
								Water					
								Water					
Possible Hazard Identification ☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☐ Unknown ☐ Radiological										Sample Disposal (A fee may be assessed if samples are retained longer than 1 month) ☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months			
Deliverable Requested: I, II, III, IV, Other (specify)										Special Instructions/QC Requirements:			
Empty Kit Relinquished by:				Date:		Time:		Method of Shipment: <u>Courier</u>					
Relinquished by: <u>[Signature]</u>		Date/Time: <u>09-12-24 700</u>		Company: <u>Geosyntec</u>		Received by: <u>[Signature]</u>		Date/Time: <u>9-12-24 7:15</u>		Company:			
Relinquished by: <u>[Signature]</u>		Date/Time: <u>9-12-24 9:26</u>		Company:		Received by: <u>Anna Neal</u>		Date/Time: <u>9-12-24 920</u>		Company:			
Relinquished by: <u>[Signature]</u>		Date/Time:		Company:		Received by:		Date/Time:		Company:			
Custody Seals Intact: ☐ Yes ☐ No		Custody Seal No.:		Cooler Temperature(s) °C and Other Remarks: <u>1.2°C #2927</u>									

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-6851-1

Job ID: 705-6851-1

Eurofins Atlanta

Job Narrative 705-6851-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers and/or narrative comments are included to explain any exceptions, if applicable.

- Matrix QC may not be reported if insufficient sample is provided or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 9/12/2024 9:26 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 1.2°C.

Receipt Exceptions

The date of collection on the container labels did not match the date on the Chain-of-Custody (COC). Laboratory used 9/11/2024.

Metals

Method 6010D: A deviation from the Standard Operating Procedure (SOP) was authorized by client request. Samples were not processed by prep method 3010A and analyzed straight from the bottle.

Method 6010D: The method blank for preparation batch 705-11351 and analytical batch 705-11414 contained Boron above the method reporting limit (RL). Associated sample(s) were not re-extracted and/or re-analyzed because results were greater than 10X the value found in the method blank.

Method 6020B - Total Recoverable: A deviation from the Standard Operating Procedure (SOP) was authorized by client request: Samples with an analysis time earlier than 14:00 were not processed by prep method 3005A and analyzed straight from the bottle.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6851-1

Client Sample ID: HAM-PT7-09-11-i-UNF

Lab Sample ID: 705-6851-1

Date Collected: 09/11/24 09:50

Matrix: Water

Date Received: 09/12/24 09:26

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.63	B ^2	0.040	0.026	mg/L		09/12/24 10:41	09/12/24 13:58	1
Iron	1.9		0.10	0.035	mg/L		09/12/24 10:41	09/12/24 13:58	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.045		0.0050	0.0013	mg/L		09/12/24 10:50	09/12/24 13:55	1
Arsenic	0.071		0.0050	0.0013	mg/L		09/12/24 10:50	09/12/24 16:39	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6851-1

Client Sample ID: HAM-PT7-09-11-i-FIL
Date Collected: 09/11/24 09:50
Date Received: 09/12/24 09:26

Lab Sample ID: 705-6851-2
Matrix: Water

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.0065		0.0050	0.0013	mg/L			09/12/24 13:34	1
Iron, Dissolved	ND		0.040	0.018	mg/L			09/12/24 13:34	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6851-1

Client Sample ID: HAM-PT7-09-11-ii-UNF

Lab Sample ID: 705-6851-3

Date Collected: 09/11/24 10:45

Matrix: Water

Date Received: 09/12/24 09:26

Method: SW846 6010D - Metals (ICP)										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Boron	0.65	B ^2	0.040	0.026	mg/L		09/12/24 10:41	09/12/24 14:01	1	
Iron	6.6		0.10	0.035	mg/L		09/12/24 10:41	09/12/24 14:01	1	

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable										
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac	
Arsenic	0.031		0.0050	0.0013	mg/L		09/12/24 10:50	09/12/24 13:57	1	
Arsenic	0.035		0.0050	0.0013	mg/L		09/12/24 10:50	09/12/24 16:41	1	

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6851-1

Client Sample ID: HAM-PT7-09-11-ii-FIL
Date Collected: 09/11/24 10:45
Date Received: 09/12/24 09:26

Lab Sample ID: 705-6851-4
Matrix: Water

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.019		0.0050	0.0013	mg/L			09/12/24 13:37	1
Iron, Dissolved	ND		0.040	0.018	mg/L			09/12/24 13:37	1

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6851-1

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-11351/1-A
Matrix: Water
Analysis Batch: 11414

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 11351

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.0549		0.040	0.026	mg/L		09/11/24 12:10	09/11/24 14:30	1
Iron	ND		0.10	0.035	mg/L		09/11/24 12:10	09/11/24 14:30	1

Lab Sample ID: LCS 705-11351/2-A
Matrix: Water
Analysis Batch: 11414

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 11351

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	1.00	0.997		mg/L		100	80 - 120
Iron	10.0	9.23		mg/L		92	80 - 120

Lab Sample ID: LCSD 705-11351/3-A
Matrix: Water
Analysis Batch: 11414

Client Sample ID: Lab Control Sample Dup
Prep Type: Total/NA
Prep Batch: 11351

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron	1.00	0.984		mg/L		98	80 - 120	1	20
Iron	10.0	9.11		mg/L		91	80 - 120	1	20

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-11348/1-A
Matrix: Water
Analysis Batch: 11459

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 11348

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	ND		0.0050	0.0013	mg/L		09/11/24 11:38	09/11/24 16:25	1

Lab Sample ID: LCS 705-11348/2-A
Matrix: Water
Analysis Batch: 11459

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 11348

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.100	0.0941		mg/L		94	80 - 120

Lab Sample ID: 705-6691-A-5-E MS
Matrix: Water
Analysis Batch: 11459

Client Sample ID: Matrix Spike
Prep Type: Total Recoverable
Prep Batch: 11348

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.038		0.100	0.131		mg/L		93	75 - 125

Lab Sample ID: 705-6691-A-5-F MSD
Matrix: Water
Analysis Batch: 11459

Client Sample ID: Matrix Spike Duplicate
Prep Type: Total Recoverable
Prep Batch: 11348

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic	0.038		0.100	0.134		mg/L		96	75 - 125	2	20

Eurofins Atlanta

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6851-1

Client Sample ID: HAM-PT7-09-11-i-UNF

Date Collected: 09/11/24 09:50

Date Received: 09/12/24 09:26

Lab Sample ID: 705-6851-1

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			11351	SA	EET ATL	09/12/24 10:41
Total/NA	Analysis	6010D		1	11617	DS	EET ATL	09/12/24 13:58
Total Recoverable	Prep	3005A			11348	SA	EET ATL	09/12/24 10:50
Total Recoverable	Analysis	6020B		1	11614	AD	EET ATL	09/12/24 13:55
Total Recoverable	Prep	3005A			11348	SA	EET ATL	09/12/24 10:50
Total Recoverable	Analysis	6020B		1	11667	AD	EET ATL	09/12/24 16:39

Client Sample ID: HAM-PT7-09-11-i-FIL

Date Collected: 09/11/24 09:50

Date Received: 09/12/24 09:26

Lab Sample ID: 705-6851-2

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6020B		1	11644	AD	EET ATL	09/12/24 13:34

Client Sample ID: HAM-PT7-09-11-ii-UNF

Date Collected: 09/11/24 10:45

Date Received: 09/12/24 09:26

Lab Sample ID: 705-6851-3

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			11351	SA	EET ATL	09/12/24 10:41
Total/NA	Analysis	6010D		1	11617	DS	EET ATL	09/12/24 14:01
Total Recoverable	Prep	3005A			11348	SA	EET ATL	09/12/24 10:50
Total Recoverable	Analysis	6020B		1	11614	AD	EET ATL	09/12/24 13:57
Total Recoverable	Prep	3005A			11348	SA	EET ATL	09/12/24 10:50
Total Recoverable	Analysis	6020B		1	11667	AD	EET ATL	09/12/24 16:41

Client Sample ID: HAM-PT7-09-11-ii-FIL

Date Collected: 09/11/24 10:45

Date Received: 09/12/24 09:26

Lab Sample ID: 705-6851-4

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6020B		1	11644	AD	EET ATL	09/12/24 13:37

Laboratory References:

EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6851-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

1
2
3
4
5
6
7
8
9
10
11
12
13

Method Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6851-1

Method	Method Description	Protocol	Laboratory
6010D	Metals (ICP)	SW846	EET ATL
6020B	Metals (ICP/MS)	SW846	EET ATL
3005A	Preparation, Total Recoverable or Dissolved Metals	SW846	EET ATL
3010A	Preparation, Total Metals	SW846	EET ATL

Protocol References:

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Sample Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-6851-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-6851-1	HAM-PT7-09-11-i-UNF	Water	09/11/24 09:50	09/12/24 09:26
705-6851-2	HAM-PT7-09-11-i-FIL	Water	09/11/24 09:50	09/12/24 09:26
705-6851-3	HAM-PT7-09-11-ii-UNF	Water	09/11/24 10:45	09/12/24 09:26
705-6851-4	HAM-PT7-09-11-ii-FIL	Water	09/11/24 10:45	09/12/24 09:26

1

2

3

4

5

6

7

8

9

10

11

12

13

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-6851-1

Login Number: 6851

List Number: 1

Creator: Ince, Sadie-Jane

List Source: Eurofins Atlanta

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	N/A	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	False	changed sample date references to 9/11
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	False	Limited volume received for dissolved metals
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	N/A	
Multiphasic samples are not present.	N/A	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT

ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 9/13/2024 5:16:29 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-7006-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
9/13/2024 5:16:29 PM

Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	11
Lab Chronicle	13
Certification Summary	14
Method Summary	15
Sample Summary	16
Receipt Checklists	17
End Of Report	18



Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7006-1

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
□	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

 eurofins | Environment Testing

Verifed 9/13/2024

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-7006-1

Job ID: 705-7006-1

Eurofins Atlanta

Job Narrative 705-7006-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers and/or narrative comments are included to explain any exceptions, if applicable.

- Matrix QC may not be reported if insufficient sample is provided or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 9/13/2024 10:02 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 0.3°C.

Metals

Method 6010D: A deviation from the Standard Operating Procedure (SOP) was authorized by client request. Samples were not processed by prep method 3010A and analyzed straight from the bottle.

Method 6020B - Total Recoverable: A deviation from the Standard Operating Procedure (SOP) was authorized by client request: Samples with a Prepared date & time of 9/13/24 @ 10:25 were not processed by prep method 3005A and analyzed straight from the bottle.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7006-1

Client Sample ID: HAM-PT7-09-12-FIL

Lab Sample ID: 705-7006-1

Date Collected: 09/12/24 10:50

Matrix: Water

Date Received: 09/13/24 10:02

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.010		0.0050	0.0013	mg/L			09/13/24 12:35	1
Iron, Dissolved	ND		0.040	0.018	mg/L			09/13/24 12:35	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7006-1

Client Sample ID: HAM-PT7-09-12-UNF

Lab Sample ID: 705-7006-2

Date Collected: 09/12/24 10:50

Matrix: Water

Date Received: 09/13/24 10:02

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.61		0.040	0.026	mg/L		09/13/24 11:07	09/13/24 12:21	1
Iron	1.8		0.10	0.035	mg/L		09/13/24 11:07	09/13/24 12:21	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.018		0.0050	0.0013	mg/L		09/13/24 10:25	09/13/24 12:47	1
Arsenic	0.022		0.0050	0.0013	mg/L		09/13/24 10:49	09/13/24 16:05	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7006-1

Client Sample ID: HAM-PT14-09-12-FIL
Date Collected: 09/12/24 11:45
Date Received: 09/13/24 10:02

Lab Sample ID: 705-7006-3
Matrix: Water

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.037		0.0050	0.0013	mg/L			09/13/24 12:38	1
Iron, Dissolved	4.4		0.040	0.018	mg/L			09/13/24 12:38	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7006-1

Client Sample ID: HAM-PT14-09-12-UNF

Lab Sample ID: 705-7006-4

Date Collected: 09/12/24 11:45

Matrix: Water

Date Received: 09/13/24 10:02

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.74		0.040	0.026	mg/L		09/13/24 11:07	09/13/24 12:24	1
Iron	6.5		0.10	0.035	mg/L		09/13/24 11:07	09/13/24 12:24	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.043		0.0050	0.0013	mg/L		09/13/24 10:25	09/13/24 12:49	1
Arsenic	0.041		0.0050	0.0013	mg/L		09/13/24 10:49	09/13/24 16:17	1

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7006-1

Method: 6010D - Metals (ICP)

Lab Sample ID: MB 705-11749/1-A
Matrix: Water
Analysis Batch: 11792

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 11749

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	ND		0.040	0.026	mg/L		09/13/24 11:07	09/13/24 12:05	1
Iron	ND		0.10	0.035	mg/L		09/13/24 11:07	09/13/24 12:05	1

Lab Sample ID: LCS 705-11749/2-A
Matrix: Water
Analysis Batch: 11792

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 11749

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Boron	1.00	1.03		mg/L		103	80 - 120
Iron	10.0	10.3		mg/L		103	80 - 120

Lab Sample ID: LCSD 705-11749/3-A
Matrix: Water
Analysis Batch: 11792

Client Sample ID: Lab Control Sample Dup
Prep Type: Total/NA
Prep Batch: 11749

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Boron	1.00	1.02		mg/L		102	80 - 120	0	20
Iron	10.0	10.3		mg/L		103	80 - 120	0	20

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-11740/1-A
Matrix: Water
Analysis Batch: 11873

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 11740

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	ND		0.0050	0.0013	mg/L		09/13/24 10:49	09/13/24 16:01	1

Lab Sample ID: LCS 705-11740/2-A
Matrix: Water
Analysis Batch: 11873

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 11740

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.100	0.0884		mg/L		88	80 - 120

Lab Sample ID: 705-7006-2 MS
Matrix: Water
Analysis Batch: 11873

Client Sample ID: HAM-PT7-09-12-UNF
Prep Type: Total Recoverable
Prep Batch: 11740

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.022		0.100	0.107		mg/L		85	75 - 125

Lab Sample ID: 705-7006-2 MSD
Matrix: Water
Analysis Batch: 11873

Client Sample ID: HAM-PT7-09-12-UNF
Prep Type: Total Recoverable
Prep Batch: 11740

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic	0.022		0.100	0.106		mg/L		84	75 - 125	2	20

Eurofins Atlanta

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7006-1

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: MB 705-11600/1-A

Matrix: Water

Analysis Batch: 11804

Client Sample ID: Method Blank

Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	ND		0.0050	0.0013	mg/L			09/13/24 12:28	1
Iron, Dissolved	ND		0.040	0.018	mg/L			09/13/24 12:28	1

Lab Sample ID: LCS 705-11600/2-A

Matrix: Water

Analysis Batch: 11804

Client Sample ID: Lab Control Sample

Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic, Dissolved	0.100	0.0815		mg/L		81	80 - 120
Iron, Dissolved	1.00	0.885		mg/L		88	80 - 120

Lab Sample ID: LCSD 705-11600/3-A

Matrix: Water

Analysis Batch: 11804

Client Sample ID: Lab Control Sample Dup

Prep Type: Dissolved

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic, Dissolved	0.100	0.0828		mg/L		83	80 - 120	2	20
Iron, Dissolved	1.00	0.889		mg/L		89	80 - 120	0	20

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7006-1

Client Sample ID: HAM-PT7-09-12-FIL

Date Collected: 09/12/24 10:50

Date Received: 09/13/24 10:02

Lab Sample ID: 705-7006-1

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6020B		1	11804	AD	EET ATL	09/13/24 12:35

Client Sample ID: HAM-PT7-09-12-UNF

Date Collected: 09/12/24 10:50

Date Received: 09/13/24 10:02

Lab Sample ID: 705-7006-2

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			11749	SA	EET ATL	09/13/24 11:07
Total/NA	Analysis	6010D		1	11792	DS	EET ATL	09/13/24 12:21
Total Recoverable	Prep	3005A			11739	BL	EET ATL	09/13/24 10:25
Total Recoverable	Analysis	6020B		1	11805	AD	EET ATL	09/13/24 12:47
Total Recoverable	Prep	3005A			11740	BL	EET ATL	09/13/24 10:49
Total Recoverable	Analysis	6020B		1	11873	AD	EET ATL	09/13/24 16:05

Client Sample ID: HAM-PT14-09-12-FIL

Date Collected: 09/12/24 11:45

Date Received: 09/13/24 10:02

Lab Sample ID: 705-7006-3

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6020B		1	11804	AD	EET ATL	09/13/24 12:38

Client Sample ID: HAM-PT14-09-12-UNF

Date Collected: 09/12/24 11:45

Date Received: 09/13/24 10:02

Lab Sample ID: 705-7006-4

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			11749	SA	EET ATL	09/13/24 11:07
Total/NA	Analysis	6010D		1	11792	DS	EET ATL	09/13/24 12:24
Total Recoverable	Prep	3005A			11739	BL	EET ATL	09/13/24 10:25
Total Recoverable	Analysis	6020B		1	11805	AD	EET ATL	09/13/24 12:49
Total Recoverable	Prep	3005A			11740	BL	EET ATL	09/13/24 10:49
Total Recoverable	Analysis	6020B		1	11873	AD	EET ATL	09/13/24 16:17

Laboratory References:

EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7006-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13

Method Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7006-1

Method	Method Description	Protocol	Laboratory
6010D	Metals (ICP)	SW846	EET ATL
6020B	Metals (ICP/MS)	SW846	EET ATL
3005A	Preparation, Total Recoverable or Dissolved Metals	SW846	EET ATL
3010A	Preparation, Total Metals	SW846	EET ATL

Protocol References:

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Sample Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7006-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-7006-1	HAM-PT7-09-12-FIL	Water	09/12/24 10:50	09/13/24 10:02
705-7006-2	HAM-PT7-09-12-UNF	Water	09/12/24 10:50	09/13/24 10:02
705-7006-3	HAM-PT14-09-12-FIL	Water	09/12/24 11:45	09/13/24 10:02
705-7006-4	HAM-PT14-09-12-UNF	Water	09/12/24 11:45	09/13/24 10:02

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-7006-1

Login Number: 7006

List Source: Eurofins Atlanta

List Number: 1

Creator: Ince, Sadie-Jane

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	N/A	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	False	Limited volume received for dissolved metals
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	N/A	
Multiphasic samples are not present.	N/A	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT

ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 9/24/2024 2:51:16 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-7790-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
9/24/2024 2:51:16 PM

Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	9
Lab Chronicle	11
Certification Summary	12
Method Summary	13
Sample Summary	14
Receipt Checklists	15
End Of Report	16



Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7790-1

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
□	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

3080 Presidential Dr
Atlanta, GA 30340
Phone: 770-457-8177 Fax: 770-457-8188

• Hypothesis Testing

Page 5 of 16

9/24/2024

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-7790-1

Job ID: 705-7790-1

Eurofins Atlanta

Job Narrative 705-7790-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers and/or narrative comments are included to explain any exceptions, if applicable.

- Matrix QC may not be reported if insufficient sample is provided or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 9/20/2024 4:23 PM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 2.4°C.

Metals

Method 6010D: A deviation from the Standard Operating Procedure (SOP) was authorized by client request. Samples were not processed by prep method 3010A and analyzed straight from the bottle.

Method 6020B - Total Recoverable: A deviation from the Standard Operating Procedure (SOP) was authorized by client request: Samples with a prep date & time of 9/23/24 @ 10:19 were not processed by prep method 3005A and analyzed straight from the bottle.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7790-1

Client Sample ID: HAM-PT14-09-20-FIL

Lab Sample ID: 705-7790-1

Date Collected: 09/20/24 10:05

Matrix: Water

Date Received: 09/20/24 16:23

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.0067		0.0050	0.0013	mg/L			09/23/24 15:59	1
Iron, Dissolved	1.5		0.040	0.018	mg/L			09/23/24 15:59	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7790-1

Client Sample ID: HAM-PT14-09-20-UNF

Lab Sample ID: 705-7790-2

Date Collected: 09/20/24 10:05

Matrix: Water

Date Received: 09/20/24 16:23

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.58		0.040	0.026	mg/L		09/23/24 10:11	09/23/24 11:39	1
Iron	1.8		0.10	0.035	mg/L		09/23/24 10:11	09/23/24 11:39	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.0069		0.0050	0.0013	mg/L		09/23/24 10:19	09/23/24 14:07	1
Arsenic	0.0078		0.0050	0.0013	mg/L		09/23/24 10:40	09/23/24 17:50	1

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7790-1

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-13058/1-A

Matrix: Water

Analysis Batch: 13250

Client Sample ID: Method Blank

Prep Type: Total Recoverable

Prep Batch: 13058

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	ND		0.0050	0.0013	mg/L		09/23/24 10:40	09/23/24 17:43	1

Lab Sample ID: LCS 705-13058/2-A

Matrix: Water

Analysis Batch: 13250

Client Sample ID: Lab Control Sample

Prep Type: Total Recoverable

Prep Batch: 13058

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.100	0.0979		mg/L		98	80 - 120

Lab Sample ID: 705-7847-A-5-D MS

Matrix: Water

Analysis Batch: 13250

Client Sample ID: Matrix Spike

Prep Type: Total Recoverable

Prep Batch: 13058

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.0078		0.100	0.104		mg/L		96	75 - 125

Lab Sample ID: 705-7847-A-5-E MSD

Matrix: Water

Analysis Batch: 13250

Client Sample ID: Matrix Spike Duplicate

Prep Type: Total Recoverable

Prep Batch: 13058

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic	0.0078		0.100	0.104		mg/L		97	75 - 125	0	20

Lab Sample ID: MB 705-13047/1-A

Matrix: Water

Analysis Batch: 13192

Client Sample ID: Method Blank

Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	ND		0.0050	0.0013	mg/L			09/23/24 15:39	1
Iron, Dissolved	ND		0.040	0.018	mg/L			09/23/24 15:39	1

Lab Sample ID: LCS 705-13047/2-A

Matrix: Water

Analysis Batch: 13192

Client Sample ID: Lab Control Sample

Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic, Dissolved	0.100	0.0946		mg/L		95	80 - 120
Iron, Dissolved	1.00	0.966		mg/L		97	80 - 120

Lab Sample ID: 705-7582-A-5 MS

Matrix: Water

Analysis Batch: 13192

Client Sample ID: Matrix Spike

Prep Type: Dissolved

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic, Dissolved	ND		0.100	0.0927		mg/L		93	75 - 125
Iron, Dissolved	ND		1.00	0.959		mg/L		96	75 - 125

Eurofins Atlanta

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7790-1

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: 705-7582-A-5 MSD				Client Sample ID: Matrix Spike Duplicate								
Matrix: Water				Prep Type: Dissolved								
Analysis Batch: 13192												
Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit	
Arsenic, Dissolved	ND		0.100	0.0899		mg/L		90	75 - 125	3	20	
Iron, Dissolved	ND		1.00	0.908		mg/L		91	75 - 125	5	20	

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7790-1

Client Sample ID: HAM-PT14-09-20-FIL
Date Collected: 09/20/24 10:05
Date Received: 09/20/24 16:23

Lab Sample ID: 705-7790-1
Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6020B		1	13192	IF	EET ATL	09/23/24 15:59

Client Sample ID: HAM-PT14-09-20-UNF
Date Collected: 09/20/24 10:05
Date Received: 09/20/24 16:23

Lab Sample ID: 705-7790-2
Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			13055	SA	EET ATL	09/23/24 10:11
Total/NA	Analysis	6010D		1	13095	DAB	EET ATL	09/23/24 11:39
Total Recoverable	Prep	3005A			13057	SA	EET ATL	09/23/24 10:19
Total Recoverable	Analysis	6020B		1	13154	AD	EET ATL	09/23/24 14:07
Total Recoverable	Prep	3005A			13058	BR	EET ATL	09/23/24 10:40
Total Recoverable	Analysis	6020B		1	13250	AD	EET ATL	09/23/24 17:50

Laboratory References:
EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7790-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

1
2
3
4
5
6
7
8
9
10
11
12
13

Method Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7790-1

Method	Method Description	Protocol	Laboratory
6010D	Metals (ICP)	SW846	EET ATL
6020B	Metals (ICP/MS)	SW846	EET ATL
3005A	Preparation, Total Recoverable or Dissolved Metals	SW846	EET ATL
3010A	Preparation, Total Metals	SW846	EET ATL

Protocol References:

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Sample Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7790-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-7790-1	HAM-PT14-09-20-FIL	Water	09/20/24 10:05	09/20/24 16:23
705-7790-2	HAM-PT14-09-20-UNF	Water	09/20/24 10:05	09/20/24 16:23

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-7790-1

Login Number: 7790

List Source: Eurofins Atlanta

List Number: 1

Creator: Ince, Sadie-Jane

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	N/A	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	False	Limited volume received.
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	N/A	
Multiphasic samples are not present.	N/A	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT

ANALYTICAL REPORT

PREPARED FOR

Attn: Kip Gray
Geosyntec Consultants Inc
1255 Roberts Blvd. NW
Suite 200
Kennesaw, Georgia 30144

Generated 9/24/2024 3:15:01 PM

JOB DESCRIPTION

Plant Hammond

JOB NUMBER

705-7847-1

Eurofins Atlanta

Job Notes

The test results in this report relate only to the samples as received by the laboratory and will meet all requirements of the methodology, with any exceptions noted. This report shall not be reproduced except in full, without the express written approval of the laboratory. All questions should be directed to the Eurofins Environment Testing Southeast, LLC Project Manager.

Authorization



Authorized for release by
David Fuller, Project Manager
David.Fuller@et.eurofinsus.com
(770)344-8986

Generated
9/24/2024 3:15:01 PM

Table of Contents

Cover Page	1
Table of Contents	3
Definitions/Glossary	4
Chain of Custody	5
Case Narrative	6
Client Sample Results	7
QC Sample Results	17
Lab Chronicle	19
Certification Summary	21
Method Summary	22
Sample Summary	23
Receipt Checklists	24
End Of Report	25



Definitions/Glossary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7847-1

Qualifiers

Metals

Qualifier	Qualifier Description
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Chain of Custody Record

Client Information		Sampler: <u>Ali Akbari</u>		Lab PM: Fuller, David		Carrier Tracking No(s):		COC No: 705-4071-1881.4			
Client Contact: Kip Gray		Phone: <u>6209222765</u>		E-Mail: David.Fuller@eurolabs.com		State of Origin:		Page: Page 4 of 8			
Company: Geosyntec Consultants Inc		PWSID:		Analysis Requested Boron, Iron, Gluc / No Prep Arsenic, 60206 / Nomenclature Arsenic (total) - 60206 Arsenic / Iron (dissolved) 60206		Job #:		Preservation Codes:			
Address: 1255 Roberts Blvd. NW Suite 200		Due Date Requested:				705-7847 COC		Other:			
City: Kennesaw		TAT Requested (days):									
State, Zip: GA, 30144		Compliance Project: ☐ Yes ☐ No									
Phone:		PO #: 100061163									
Email: Kip.Gray@Geosyntec.com		WO #: Project# GW6581G									
Project Name: Plant Hammond		Project #: 70500911									
Site:		SSOW#:									
Sample Identification		Sample Date		Sample Time		Sample Type (C=comp, G=grab)		Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)		Field Filtered Sample (Yes or No)	
										Perform MS/MSD (Yes or No)	
										Total Number of containers	
										Special Instructions/Note:	
HAM-PT7-09-21-UNF		09-21-24		1145		G		Water		XX X	
HAM-PT7-09-21-FIL		↓		1145		↓		Water		X	
HAM-PT8-09-21-UNF		↓		1430		↓		Water		XX X	
HAM-PT8-09-21-FIL		↓		1430		↓		Water		X	
HAM-PT13-09-21-UNF		↓		1600		↓		Water		XX X	
HAM-PT13-09-21-FIL		↓		1600		↓		Water		X	
HAM-PT14-09-21-UNF		↓		1845		↓		Water		XX X	
HAM-PT14-09-21-FIL		↓		1845		↓		Water		X	
HAM-PT15-09-21-FIL		↓		1015		↓		Water		X	
HAM-PT15-09-21-UNF		↓		1015		↓		Water		XX X	
								Water			
Possible Hazard Identification										Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)	
☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☐ Unknown ☐ Radiological										☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months	
Deliverable Requested: I, II, III, IV, Other (specify)										Special Instructions/QC Requirements:	
Empty Kit Relinquished by:				Date:		Time:		Method of Shipment: <u>Courier</u>			
Relinquished by: <u>[Signature]</u>				Date/Time: <u>7/23/2024 4:10</u>		Company: <u>Geosyntec</u>		Received by: <u>[Signature]</u>			
Relinquished by: <u>[Signature]</u>				Date/Time: <u>9-23-24 11:55</u>		Company: <u>eurolabs</u>		Received by: <u>Anna Neal</u>			
Relinquished by: <u>[Signature]</u>				Date/Time: <u>9-23-24 11:55</u>		Company: <u>eurolabs</u>		Received by: <u>[Signature]</u>			
Custody Seals Intact: ☐ Yes ☐ No		Custody Seal No.:		Cooler Temperature(s) °C and Other Remarks: <u>2.2° ± 26.65</u>							

Case Narrative

Client: Geosyntec Consultants Inc
Project: Plant Hammond

Job ID: 705-7847-1

Job ID: 705-7847-1

Eurofins Atlanta

Job Narrative 705-7847-1

Analytical test results meet all requirements of the associated regulatory program listed on the Accreditation/Certification Summary Page unless otherwise noted under the individual analysis. Data qualifiers and/or narrative comments are included to explain any exceptions, if applicable.

- Matrix QC may not be reported if insufficient sample is provided or site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD may be performed, unless otherwise specified in the method.
- Surrogate and/or isotope dilution analyte recoveries (if applicable) which are outside of the QC window are confirmed unless attributed to a dilution or otherwise noted in the narrative.

Receipt

The samples were received on 9/23/2024 11:55 AM. Unless otherwise noted below, the samples arrived in good condition, and, where required, properly preserved and on ice. The temperature of the cooler at receipt time was 2.2°C.

Metals

Method 6010D: A deviation from the Standard Operating Procedure (SOP) was authorized by client request. Samples were not processed by prep method 3010A and analyzed straight from the bottle.

Method 6020B - Total Recoverable: A deviation from the Standard Operating Procedure (SOP) was authorized by client request: Samples with a prep date & time of 9/23/24 @ 12:52 were not processed by prep method 3005A and analyzed straight from the bottle.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/ Glossary page.

Eurofins Atlanta

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7847-1

Client Sample ID: HAM-PT7-09-21-UNF

Lab Sample ID: 705-7847-1

Date Collected: 09/21/24 11:45

Matrix: Water

Date Received: 09/23/24 11:55

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.46		0.040	0.026	mg/L		09/23/24 12:38	09/23/24 16:08	1
Iron	0.13		0.10	0.035	mg/L		09/23/24 12:38	09/23/24 16:08	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.010		0.0050	0.0013	mg/L		09/23/24 13:10	09/23/24 17:59	1
Arsenic	0.0092		0.0050	0.0013	mg/L		09/23/24 12:52	09/23/24 14:09	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7847-1

Client Sample ID: HAM-PT7-09-21-FIL
Date Collected: 09/21/24 11:45
Date Received: 09/23/24 11:55

Lab Sample ID: 705-7847-2
Matrix: Water

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.0073		0.0050	0.0013	mg/L			09/23/24 16:03	1
Iron, Dissolved	ND		0.040	0.018	mg/L			09/23/24 16:03	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7847-1

Client Sample ID: HAM-PT8-09-21-UNF

Lab Sample ID: 705-7847-3

Date Collected: 09/21/24 14:30

Matrix: Water

Date Received: 09/23/24 11:55

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.64		0.040	0.026	mg/L		09/23/24 12:38	09/23/24 16:11	1
Iron	0.46		0.10	0.035	mg/L		09/23/24 12:38	09/23/24 16:11	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.019		0.0050	0.0013	mg/L		09/23/24 13:10	09/23/24 18:02	1
Arsenic	0.020		0.0050	0.0013	mg/L		09/23/24 12:52	09/23/24 14:11	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7847-1

Client Sample ID: HAM-PT8-09-21-FIL
Date Collected: 09/21/24 14:30
Date Received: 09/23/24 11:55

Lab Sample ID: 705-7847-4
Matrix: Water

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.0055		0.0050	0.0013	mg/L			09/23/24 16:43	1
Iron, Dissolved	0.056		0.040	0.018	mg/L			09/23/24 16:43	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7847-1

Client Sample ID: HAM-PT13-09-21-UNF

Lab Sample ID: 705-7847-5

Date Collected: 09/21/24 16:00

Matrix: Water

Date Received: 09/23/24 11:55

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.50		0.040	0.026	mg/L		09/23/24 12:38	09/23/24 16:19	1
Iron	1.7		0.10	0.035	mg/L		09/23/24 12:38	09/23/24 16:19	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.0078		0.0050	0.0013	mg/L		09/23/24 13:10	09/23/24 17:57	1
Arsenic	0.0069		0.0050	0.0013	mg/L		09/23/24 12:52	09/23/24 14:14	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7847-1

Client Sample ID: HAM-PT13-09-21-FIL
Date Collected: 09/21/24 16:00
Date Received: 09/23/24 11:55

Lab Sample ID: 705-7847-6
Matrix: Water

Method: SW846 6020B - Metals (ICP/MS) - Dissolved

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.0028	J	0.0050	0.0013	mg/L			09/23/24 16:39	1
Iron, Dissolved	0.74		0.040	0.018	mg/L			09/23/24 16:39	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7847-1

Client Sample ID: HAM-PT14-09-21-UNF

Lab Sample ID: 705-7847-7

Date Collected: 09/21/24 15:45

Matrix: Water

Date Received: 09/23/24 11:55

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.58		0.040	0.026	mg/L		09/23/24 12:38	09/23/24 16:22	1
Iron	3.3		0.10	0.035	mg/L		09/23/24 12:38	09/23/24 16:22	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.0087		0.0050	0.0013	mg/L		09/23/24 13:10	09/23/24 18:04	1
Arsenic	0.0090		0.0050	0.0013	mg/L		09/23/24 12:52	09/23/24 14:16	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7847-1

Client Sample ID: HAM-PT14-09-21-FIL
Date Collected: 09/21/24 15:45
Date Received: 09/23/24 11:55

Lab Sample ID: 705-7847-8
Matrix: Water

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.0078		0.0050	0.0013	mg/L			09/23/24 16:07	1
Iron, Dissolved	2.8		0.040	0.018	mg/L			09/23/24 16:07	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7847-1

Client Sample ID: HAM-PT15-09-21-FIL
Date Collected: 09/21/24 10:15
Date Received: 09/23/24 11:55

Lab Sample ID: 705-7847-9
Matrix: Water

Method: SW846 6020B - Metals (ICP/MS) - Dissolved									
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	0.0052		0.0050	0.0013	mg/L			09/23/24 16:11	1
Iron, Dissolved	0.031	J	0.040	0.018	mg/L			09/23/24 16:11	1

Client Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7847-1

Client Sample ID: HAM-PT15-09-21-UNF

Lab Sample ID: 705-7847-10

Date Collected: 09/21/24 10:15

Matrix: Water

Date Received: 09/23/24 11:55

Method: SW846 6010D - Metals (ICP)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Boron	0.63		0.040	0.026	mg/L		09/23/24 12:38	09/23/24 16:25	1
Iron	0.090	J	0.10	0.035	mg/L		09/23/24 12:38	09/23/24 16:25	1

Method: SW846 6020B - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	0.0062		0.0050	0.0013	mg/L		09/23/24 13:10	09/23/24 18:06	1
Arsenic	0.0066		0.0050	0.0013	mg/L		09/23/24 12:52	09/23/24 14:18	1

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7847-1

Method: 6020B - Metals (ICP/MS)

Lab Sample ID: MB 705-13058/1-A

Matrix: Water

Analysis Batch: 13250

Client Sample ID: Method Blank

Prep Type: Total Recoverable

Prep Batch: 13058

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	ND		0.0050	0.0013	mg/L		09/23/24 10:40	09/23/24 17:43	1

Lab Sample ID: LCS 705-13058/2-A

Matrix: Water

Analysis Batch: 13250

Client Sample ID: Lab Control Sample

Prep Type: Total Recoverable

Prep Batch: 13058

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.100	0.0979		mg/L		98	80 - 120

Lab Sample ID: 705-7847-5 MS

Matrix: Water

Analysis Batch: 13250

Client Sample ID: HAM-PT13-09-21-UNF

Prep Type: Total Recoverable

Prep Batch: 13058

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic	0.0078		0.100	0.104		mg/L		96	75 - 125

Lab Sample ID: 705-7847-5 MSD

Matrix: Water

Analysis Batch: 13250

Client Sample ID: HAM-PT13-09-21-UNF

Prep Type: Total Recoverable

Prep Batch: 13058

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit
Arsenic	0.0078		0.100	0.104		mg/L		97	75 - 125	0	20

Lab Sample ID: MB 705-13047/1-A

Matrix: Water

Analysis Batch: 13192

Client Sample ID: Method Blank

Prep Type: Dissolved

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic, Dissolved	ND		0.0050	0.0013	mg/L			09/23/24 15:39	1
Iron, Dissolved	ND		0.040	0.018	mg/L			09/23/24 15:39	1

Lab Sample ID: LCS 705-13047/2-A

Matrix: Water

Analysis Batch: 13192

Client Sample ID: Lab Control Sample

Prep Type: Dissolved

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic, Dissolved	0.100	0.0946		mg/L		95	80 - 120
Iron, Dissolved	1.00	0.966		mg/L		97	80 - 120

Lab Sample ID: 705-7582-A-5 MS

Matrix: Water

Analysis Batch: 13192

Client Sample ID: Matrix Spike

Prep Type: Dissolved

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec Limits
Arsenic, Dissolved	ND		0.100	0.0927		mg/L		93	75 - 125
Iron, Dissolved	ND		1.00	0.959		mg/L		96	75 - 125

Eurofins Atlanta

QC Sample Results

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7847-1

Method: 6020B - Metals (ICP/MS) (Continued)

Lab Sample ID: 705-7582-A-5 MSD				Client Sample ID: Matrix Spike Duplicate								
Matrix: Water				Prep Type: Dissolved								
Analysis Batch: 13192												
Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec Limits	RPD	RPD Limit	
Arsenic, Dissolved	ND		0.100	0.0899		mg/L		90	75 - 125	3	20	
Iron, Dissolved	ND		1.00	0.908		mg/L		91	75 - 125	5	20	

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7847-1

Client Sample ID: HAM-PT7-09-21-UNF

Date Collected: 09/21/24 11:45

Date Received: 09/23/24 11:55

Lab Sample ID: 705-7847-1

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			13055	SA	EET ATL	09/23/24 12:38
Total/NA	Analysis	6010D		1	13168	DAB	EET ATL	09/23/24 16:08
Total Recoverable	Prep	3005A			13057	SA	EET ATL	09/23/24 12:52
Total Recoverable	Analysis	6020B		1	13154	AD	EET ATL	09/23/24 14:09
Total Recoverable	Prep	3005A			13058	BR	EET ATL	09/23/24 13:10
Total Recoverable	Analysis	6020B		1	13250	AD	EET ATL	09/23/24 17:59

Client Sample ID: HAM-PT7-09-21-FIL

Date Collected: 09/21/24 11:45

Date Received: 09/23/24 11:55

Lab Sample ID: 705-7847-2

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6020B		1	13192	IF	EET ATL	09/23/24 16:03

Client Sample ID: HAM-PT8-09-21-UNF

Date Collected: 09/21/24 14:30

Date Received: 09/23/24 11:55

Lab Sample ID: 705-7847-3

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			13055	SA	EET ATL	09/23/24 12:38
Total/NA	Analysis	6010D		1	13168	DAB	EET ATL	09/23/24 16:11
Total Recoverable	Prep	3005A			13057	SA	EET ATL	09/23/24 12:52
Total Recoverable	Analysis	6020B		1	13154	AD	EET ATL	09/23/24 14:11
Total Recoverable	Prep	3005A			13058	BR	EET ATL	09/23/24 13:10
Total Recoverable	Analysis	6020B		1	13250	AD	EET ATL	09/23/24 18:02

Client Sample ID: HAM-PT8-09-21-FIL

Date Collected: 09/21/24 14:30

Date Received: 09/23/24 11:55

Lab Sample ID: 705-7847-4

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6020B		1	13192	IF	EET ATL	09/23/24 16:43

Client Sample ID: HAM-PT13-09-21-UNF

Date Collected: 09/21/24 16:00

Date Received: 09/23/24 11:55

Lab Sample ID: 705-7847-5

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			13055	SA	EET ATL	09/23/24 12:38
Total/NA	Analysis	6010D		1	13168	DAB	EET ATL	09/23/24 16:19
Total Recoverable	Prep	3005A			13057	SA	EET ATL	09/23/24 12:52
Total Recoverable	Analysis	6020B		1	13154	AD	EET ATL	09/23/24 14:14
Total Recoverable	Prep	3005A			13058	BR	EET ATL	09/23/24 13:10
Total Recoverable	Analysis	6020B		1	13250	AD	EET ATL	09/23/24 17:57

Eurofins Atlanta

Lab Chronicle

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7847-1

Client Sample ID: HAM-PT13-09-21-FIL

Date Collected: 09/21/24 16:00

Date Received: 09/23/24 11:55

Lab Sample ID: 705-7847-6

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6020B		1	13192	IF	EET ATL	09/23/24 16:39

Client Sample ID: HAM-PT14-09-21-UNF

Date Collected: 09/21/24 15:45

Date Received: 09/23/24 11:55

Lab Sample ID: 705-7847-7

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			13055	SA	EET ATL	09/23/24 12:38
Total/NA	Analysis	6010D		1	13168	DAB	EET ATL	09/23/24 16:22
Total Recoverable	Prep	3005A			13057	SA	EET ATL	09/23/24 12:52
Total Recoverable	Analysis	6020B		1	13154	AD	EET ATL	09/23/24 14:16
Total Recoverable	Prep	3005A			13058	BR	EET ATL	09/23/24 13:10
Total Recoverable	Analysis	6020B		1	13250	AD	EET ATL	09/23/24 18:04

Client Sample ID: HAM-PT14-09-21-FIL

Date Collected: 09/21/24 15:45

Date Received: 09/23/24 11:55

Lab Sample ID: 705-7847-8

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6020B		1	13192	IF	EET ATL	09/23/24 16:07

Client Sample ID: HAM-PT15-09-21-FIL

Date Collected: 09/21/24 10:15

Date Received: 09/23/24 11:55

Lab Sample ID: 705-7847-9

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Dissolved	Analysis	6020B		1	13192	IF	EET ATL	09/23/24 16:11

Client Sample ID: HAM-PT15-09-21-UNF

Date Collected: 09/21/24 10:15

Date Received: 09/23/24 11:55

Lab Sample ID: 705-7847-10

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Analyst	Lab	Prepared or Analyzed
Total/NA	Prep	3010A			13055	SA	EET ATL	09/23/24 12:38
Total/NA	Analysis	6010D		1	13168	DAB	EET ATL	09/23/24 16:25
Total Recoverable	Prep	3005A			13057	SA	EET ATL	09/23/24 12:52
Total Recoverable	Analysis	6020B		1	13154	AD	EET ATL	09/23/24 14:18
Total Recoverable	Prep	3005A			13058	BR	EET ATL	09/23/24 13:10
Total Recoverable	Analysis	6020B		1	13250	AD	EET ATL	09/23/24 18:06

Laboratory References:

EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Eurofins Atlanta

Accreditation/Certification Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7847-1

Laboratory: Eurofins Atlanta

The accreditations/certifications listed below are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Florida	NELAP	E87582	06-30-25

1
2
3
4
5
6
7
8
9
10
11
12
13

Method Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7847-1

Method	Method Description	Protocol	Laboratory
6010D	Metals (ICP)	SW846	EET ATL
6020B	Metals (ICP/MS)	SW846	EET ATL
3005A	Preparation, Total Recoverable or Dissolved Metals	SW846	EET ATL
3010A	Preparation, Total Metals	SW846	EET ATL

Protocol References:

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

EET ATL = Eurofins Atlanta, 3080 Presidential Dr, Atlanta, GA 30340, TEL (770)457-8177

Sample Summary

Client: Geosyntec Consultants Inc
Project/Site: Plant Hammond

Job ID: 705-7847-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
705-7847-1	HAM-PT7-09-21-UNF	Water	09/21/24 11:45	09/23/24 11:55
705-7847-2	HAM-PT7-09-21-FIL	Water	09/21/24 11:45	09/23/24 11:55
705-7847-3	HAM-PT8-09-21-UNF	Water	09/21/24 14:30	09/23/24 11:55
705-7847-4	HAM-PT8-09-21-FIL	Water	09/21/24 14:30	09/23/24 11:55
705-7847-5	HAM-PT13-09-21-UNF	Water	09/21/24 16:00	09/23/24 11:55
705-7847-6	HAM-PT13-09-21-FIL	Water	09/21/24 16:00	09/23/24 11:55
705-7847-7	HAM-PT14-09-21-UNF	Water	09/21/24 15:45	09/23/24 11:55
705-7847-8	HAM-PT14-09-21-FIL	Water	09/21/24 15:45	09/23/24 11:55
705-7847-9	HAM-PT15-09-21-FIL	Water	09/21/24 10:15	09/23/24 11:55
705-7847-10	HAM-PT15-09-21-UNF	Water	09/21/24 10:15	09/23/24 11:55

Login Sample Receipt Checklist

Client: Geosyntec Consultants Inc

Job Number: 705-7847-1

Login Number: 7847

List Source: Eurofins Atlanta

List Number: 1

Creator: Pomuti, Carmen

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	N/A	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	N/A	
Multiphasic samples are not present.	N/A	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

END OF REPORT

Field Sampling Forms

GROUNDWATER SAMPLING LOG SHEET

Client: GP

Site: Plant Hammond

Well ID: PT-13

Total Depth (ft): 45

Depth to Water (ft): 28.70

Well Diameter (in): 2

Well Volume (gal) = $0.041d^2h$: 267 g

Well Volume (L) = $\text{gal} * 3.785$:

Project No.: _____

Location: _____

Pump Type/Model: Bladder

Tubing Material: Poly

Pump Intake Depth (ft): 40

Start/Stop Purge Time: 0950 / 1300

Purge Rate (mL/min): 300

Total Purge Volume (L): _____

Sampling Date:	9/10/24
Sampler's Name:	A. Akhram
Sample Collection Time:	1245
Sample Purge Rate (mL/min):	300
Sample ID:	HAM-PT-13-09-10
Laboratory Analyses:	Total Boron Total As / Fe Dissolved As / Fe
QA/QC Collected?	NO
QA/QC I.D.	

d = well diameter (inches); h = length of water column (feet)

Well Type:	Flush	Stick Up
Well Lock:	Yes	No
Well Cap Condition:	Good	Replace
Well Tag Present:	Yes	No

Purge Method: Low-Flow Well Volume Other: _____
Sampling Method: Pump Discharge Other: _____

QA/QC Cclected?
QA/QC I.D.

All sample containers requiring chemical preservation properly preserved prior to demob from well?	Yes	No

Time	pH (SU)	Spec. Cond. (µS/cm)	ORP (mV)	DO (mg/L)	Temp. (°C)	Turbidity (NTUs)	DTW (ft btoc)	Purge Rate (mL/min)	Purged Volume (L)	Notes (Purge method, water clarity, odor, purge rate, issues with pump/well/weather/etc.)
0958	6.77	0.00	64.8	6.85	30.75	1600+		300		
1003	6.90	751.62	53.4	8.09	20.58	1000+		300		
1033	6.65	772.10	43.8	4.18	19.98	1000+		300		
1103	6.62	772.78	37.8	3.94	20.12	1000+		300		
1133	6.58	776.34	29.1	3.50	20.20	1000+		300		
1203	6.59	778.42	22.1	3.18	20.30	1000+		300		
1233	6.56	779.86	16.3	2.64	20.38	1000+		300		
1248	6.56	781.46	12.3	2.69	20.48	212		300		
										Unfiltered Fe: 4x 3 mg/L Fe ²⁺ : 4x 0-0.5 mg/L
										Low Range As: 6 mg/L (10x)
										High Range As: 50 mg/L
										Filtered
										Fe: 2 mg/L, Fe ²⁺ : 1.8 mg/L
										Low Range As: 4x 10 mg/L
										High Range As: 40 mg/L
Stabilizing Criteria	+/- 0.1 SU	+/- 5%		0.2 mg/L or 10% for DO > 0.5 mg/L (whichever is greater)		< 5 NTUs	< 0.3 ft	> 100 mL < 250 mL	> 3L	

All sample containers requiring chemical preservation properly preserved prior to demob from well?	Yes	No
--	-----	----

Time	pH (SU)	Spec. Cond. (µS/cm)	ORP (mV)	DO (mg/L)	Temp. (°C)	Turbidity (NTUs)	DTW (ft btoc)	Purge Rate (mL/min)	Purged Volume (L)	Notes (Purge method, water clarity, odor, purge rate, issues with pump/well/weather/etc.)
0914	7.04	779.73	61.1	7.02	19.109	1000 +		300		(#1) → 1245 Sample
0919	7.06	766.22	57.6	6.101	20.35	1000 +		300		Unfiltered
0949	7.09	744.29	57.9	6.04	21.16	1000+		300		Fe: 1.25 mg/L, Fe ²⁺ : 0 mg/L
1019	7.08	750.14	59.4	6.37	20.99	1000+		300		Low Range AS: 6 mg/L (10x)
1045	7.03	722.53	58.9	5.94	22.83	1000+		300		High Range AS: 50 mg/L
1235	6.78	692.55 762.41	29.5	5.56	20.24	101		300		Filtered
										Fe: 2 mg/L, Fe ²⁺ : 0 mg/L
										Low Range AS: not run
										High Range AS: 10 mg/L
Stabilizing Criteria	+/- 0.1 SU	+/- 5%		0.2 mg/L or 10% for DO > 0.5 mg/L (whichever is greater)		< 5 NTUs	< 0.3 ft	> 100 mL < 250 mL	> 3L	

GROUNDWATER SAMPLING LOG SHEET

Client: GP
Site: Plant Hammond
Well ID: PT-07
Total Depth (ft): 47.6
Depth to Water (ft): 30.18
Well Diameter (in): 2
Well Volume (gal) = $0.041d^2h$: 2.87
Well Volume (L) = gal * 3.785:

Project No.:
Location:
Pump Type/Model: Bladder
Tubing Material: Pony
Pump Intake Depth (ft): 42.60
Start/Stop Purge Time: 0747 /
Purge Rate (mL/min): 300
Total Purge Volume (L):

Sampling Date: 9/11/2024
Sampler's Name:
Sample Collection Time: 0950(i) 1045(ii)
Sample Purge Rate (mL/min): 300
Sample ID: HAM-PT-07-09-11
Laboratory Analyses:

d = well diameter (inches); h = length of water column (feet)

Well Type: Flush Stick Up
Well Lock: Yes No
Well Cap Condition: Good Replace
Well Tag Present: Yes No

Purge Method: Low-Flow Well Volume Other:
Sampling Method: Pump Discharge Other:

QA/QC Collected? NO
QA/QC I.D.:

All sample containers requiring chemical preservation properly preserved prior to demob from well? Yes No

Time	pH (SU)	Spec. Cond. (µS/cm)	ORP (mV)	DO (mg/L)	Temp. (°C)	Turbidity (NTUs)	DTW (ft btoc)	Purge Rate (mL/min)	Purged Volume (L)	Notes (Purge method, water clarity, odor, purge rate, issues with pump/well/weather/etc.)
0747	6.74	769.42	82.7	9.60	20.83	1000+		300		(i) Unfiltered
0752	7.27	672.14	55.6	9.23	18.65	1000+		200		High Range As: 40 µg/L
0817	7.28	713.75	37.8	9.53	18.60	540		300		Total Fe: 4 mg/L (2x)
0847	7.22	785.28	37.3	8.43	18.78	248		300		Ferrus Fe: 0 mg/L (2x)
0917	7.22	713.75	39.6	8.29	19.07	511		300		
0947	7.22	763.62	40.1	8.03	19.24	392		300		(i) Filtered
1017	7.23	733.87	40.5	8.58	19.36	181		300		High Range As: 10 µg/L
1047	7.24	720.05	41.1	8.76	19.30	80.1		300		Total Fe: 0 mg/L
										Ferrus Fe: 0 mg/L
										(ii) Unfiltered
										High Range As: 40 µg/L
										Total Fe: 1.5 mg/L (2x)
										Ferrus Fe: 0 mg/L (2x)
										(ii) Filtered
										High Range As: 30 µg/L
										Total Fe: 0 mg/L
										Ferrus Fe: 0 mg/L
Stabilizing Criteria	+/- 0.1 SU	+/- 5%		0.2 mg/L or 10% for DO > 0.5 mg/L (whichever is greater)		< 5 NTUs	< 0.3 ft	> 100 mL < 250 mL	> 3L	

GROUNDWATER SAMPLING LOG SHEET

Client: <u>GP</u>	Project No.: _____	Sampling Date: <u>9/12/2024</u>
Site: <u>Hammond</u>	Location: _____	Sampler's Name: <u>A. Akbari</u>
Well ID: <u>PT-14</u>	Pump Type/Model: <u>Bladder</u>	Sample Collection Time: <u>1145</u>
Total Depth (ft): <u>45</u>	Tubing Material: <u>Poly</u>	Sample Purge Rate (mL/min): <u>HA 300</u>
Depth to Water (ft): _____	Pump Intake Depth (ft): <u>40</u>	Sample ID: <u>ITAM-PT-14-09-12</u>
Well Diameter (in): <u>2</u>	Start/Stop Purge Time: <u>1118</u>	Laboratory Analyses: _____
Well Volume (gal) = 0.041d ² h: _____	Purge Rate (mL/min): _____	
Well Volume (L) = gal * 3.785: _____	Total Purge Volume (L): _____	
d = well diameter (inches); h = length of water column (feet)		
Well Type: <u>Flush</u> <u>Stick Up</u>	Purge Method: Low-Flow Well Volume Other: _____	QA/QC Collected? <u>NO</u>
Well Lock: <u>Yes</u> <u>No</u>	Sampling Method: Pump Discharge Other: _____	QA/QC I.D. _____
Well Cap Condition: <u>Good</u> <u>Replace</u>		
Well Tag Present: <u>Yes</u> <u>No</u>		

All sample containers requiring chemical preservation properly preserved prior to demob from well? Yes No

Time	pH (SU)	Spec. Cond. (µS/cm)	ORP (mV)	DO (mg/L)	Temp. (°C)	Turbidity (NTUs)	DTW (ft btoc)	Purge Rate (mL/min)	Purged Volume (L)	Notes (Purge method, water clarity, odor, purge rate, issues with pump/well/weather/etc.)
1120	6.91	817.72	-58.7	1.30	20.07			300		unfiltered
1125	6.72	839.73	-62.9	0.40	18.71			300		Purges: 2-2.5 mg/L (2x)
1130	6.68	841.49	-63.9	0.31	18.62			300		Total: 2.5-3 mg/L (2x)
1135	6.70	836.59	-65.1	0.30	18.84			300		
1140	6.68	842.17	-65.6	0.14	18.68			300		Filtered
1145	6.69	843.56	-64.8	0.14	18.60	14.3		300		Purges: 3 mg/L (1x)
										Total: 5.5 mg/L (1x)
										Purges: 1.5 mg/L (2x)
										Total: 1.5 mg/L (2x)
Stabilizing Criteria	+/- 0.1 SU	+/- 5%		0.2 mg/L or 10% for DO > 0.5 mg/L (whichever is greater)		< 5 NTUs	< 0.3 ft	> 100 mL < 250 mL	> 3L	

Sampling Date:	9/12/2024
Sampler's Name:	A. Akbari
Sample Collection Time:	1050
Sample Purge Rate (mL/min):	300
Sample ID:	HAM-PT-07-09-12
Laboratory Analyses:	

QA/QC Collected? *NO*

QA/OC I.D.

All sample containers requiring chemical preservation properly preserved prior to demob from well?	Yes	No
--	-----	----

Time	pH (SU)	Spec. Cond. (µS/cm)	ORP (mV)	DO (mg/L)	Temp. (°C)	Turbidity (NTUs)	DTW (ft btoc)	Purge Rate (mL/min)	Purged Volume (L)	Notes (Purge method, water clarity, odor, purge rate, issues with pump/well/weather/etc.)
0916	7.44	725.19	65.9	10.79	20.87			300		Unfiltered
0921	7.46	694.83	54.9	11.24	18.46			300		Ferrous: 0 mg/L
0946	7.49	727.93	50.2	11.58	18.26			300		Total: 1 mg/L
1016	7.44	737.12	49.4	11.16	18.30	131		300		
1046	7.41	733.66	49.7	10.90	18.31	46.8		300		Filtered
										Ferrous: 0 mg/L
										Total: 0 mg/L
Stabilizing Criteria	+/- 0.1 SU	+/- 5%		0.2 mg/L or 10% for DO > 0.5 mg/L (whichever is greater)		< 5 NTUs	< 0.3 ft	> 100 mL < 250 mL	> 3L	

GROUNDWATER SAMPLING LOG SHEET

Client: GP
Site: Hammond
Well ID: PT-15
Total Depth (ft): 45
Depth to Water (ft):
Well Diameter (in): 2
Well Volume (gal) = $0.041d^2h$:
Well Volume (L) = gal * 3.785:

Project No.: _____

Location: _____

Pump Type/Model: Bladder

Tubing Material: poly

Pump Intake Depth (ft): 40

Start/Stop Purge Time: 1056/1130

Purge Rate (mL/min): 300

Total Purge Volume (L): _____

Sampling Date:	9/13/2024
Sampler's Name:	A. Akbari
Sample Collection Time:	1130
Sample Purge Rate (mL/min):	300
Sample ID:	HAM-PT-15-09-13
Laboratory Analyses:	

d = well diameter (inches); h = length of water column (feet)

Well Type: ☒ Flush ☐ Stick Up

Well Lock:	Yes	No
------------	-----	----

Well Cap Condition:	Good	Replace
---------------------	------	---------

Well Tag Present:	Yes	No
-------------------	-----	----

Purge Method: ☐ Low-Flow ☐ Well Volume ☐ Other: _____

Sampling Method: ☒ Pump Discharge ☐ Other: _____

QA/OC Collected? NO

QA/QC I.D.

All sample containers requiring chemical preservation properly preserved prior to demob from well?	Yes	No

[illegible]

GROUNDWATER SAMPLING LOG SHEET

Client:	GP	
Site:	Haymond	
Well ID:	PT-08	
Total Depth (ft):	42.2	
Depth to Water (ft):		
Well Diameter (in):		
Well Volume (gal) = $0.041d^2h$:		
Well Volume (L) = gal * 3.785:		
<i>d = well diameter (inches); h = length of water column (feet)</i>		
Well Type:	Flush	Stick Up
Well Lock:	Yes	No
Well Cap Condition:	Good	Replace
Well Tag Present:	Yes	No

Project No.: _____

Location: _____

Pump Type/Model: Bladder

Tubing Material: PVC

Pump Intake Depth (ft): 37.2

Start/Stop Purge Time: 0945 / 1050

Purge Rate (mL/min): 300

Total Purge Volume (L): _____

Sampling Date:	9/13/2024
Sampler's Name:	A. Akbari
Sample Collection Time:	1050
Sample Purge Rate (π L/min):	300
Sample ID:	HAM-PT-08-09-13
Laboratory Analyses:	
QA/QC Collected?	NO
QA/QC I.D.	

All sample containers requiring chemical preservation properly preserved prior to demob from well?	Yes	No
--	-----	----

Time	pH (SU)	Spec. Cond. (µS/cm)	ORP (mV)	DO (mg/L)	Temp. (°C)	Turbidity (NTUs)	DTW (ft btoc)	Purge Rate (mL/min)	Purged Volume (L)	Notes (Purge method, water clarity, odor, purge rate, issues with pump/well/weather/etc.)
0947	6.90	686.11	17.6	7.09	20.81			300		Filtered
0952	6.66	705.25	75.9	4.32	19.04	421		300		Ferrus: 0.25 mg/L
1017	6.58	719.46	49.2	2.34	18.81	48.7		300		Total Fe: 0.5 mg/L
1042	6.59	78.70	40.2	2.67	18.66	25.9		300		High range AS: 30
										Unfiltered
										Ferrus: 0.05 mg/L #
										Total Fe: 0.05 mg/L #
										High range AS: 40
										# Iron testing done
										2 hours after sampling
										due to lightning.
Stabilizing Criteria	+/- 0.1 SU	+/- 5%		0.2 mg/L or 10% for DO > 0.5 mg/L (whichever is greater)		< 5 NTUs	< 0.3 ft	> 100 mL < 250 mL	> 3L	

All sample containers requiring chemical preservation properly preserved prior to demob from well?	Yes	No
---	------------	-----------

[illegible]

GROUNDWATER SAMPLING LOG SHEET

Client: GP
Site: Hammond
Well ID: PT-13
Total Depth (ft): 45
Depth to Water (ft):
Well Diameter (in):
Well Volume (gal) = $0.041d^2h$:
Well Volume (L) = gal * 3.785:

Project No.: _____
 Location: _____
 Pump Type/Model: Bladder
 Tubing Material: poly
 Pump Intake Depth (ft): 40
 Start/Stop Purge Time: 09/21 / 1615
 Purge Rate (mL/min): 300
 Total Purge Volume (L): _____

Sampling Date: 9/13/2024
Sampler's Name: A. Akbari
Sample Collection Time: 1615
Sample Purge Rate (nL/min): 300
Sample ID: HAM-PT-13-09-13
Laboratory Analysis:

d = well diameter (inches); h = length of water column (feet)

Well Type:	Flush	Stick Up
------------	-------	----------

Well Lock:	Yes	No
------------	-----	----

Well Cap Condition:	Good	Replace
---------------------	------	---------

Well Tag Present:	Yes	No
-------------------	-----	----

Purge Method: ☐ Low-Flow ☐ Well Volume ☐ Other: _____

Sampling Method: Pump Discharge Other: _____

QA/QC Cclected? Ne

QA/QC I.D. _____

All sample containers requiring chemical preservation properly preserved prior to demob from well?	Yes	No
--	-----	----

Time	pH (SU)	Spec. Cond. (µS/cm)	ORP (mV)	DO (mg/L)	Temp. (°C)	Turbidity (NTUs)	DTW (ft btoc)	Purge Rate (mL/min)	Purged Volume (L)	Notes (Purge method, water clarity, odor, purge rate, issues with pump/well/weather/etc.)
0922	6.94	787.15	51.5	7.72	20.52	over range		300		Filtered
0952	6.63	780.62	41.7	5.79	18.98	over range		300		Total: 2 mg/L
1022	6.62	777.48	34.1	5.50	18.99			300		Ferrus 1.75 mg/L
1122	6.58	768.29	28.9	4.84	19.07	48.6		300		High Range As: 5-10
1222	6.57	760.86	30.8	3.94	19.18	41.3		300		
1322	no	reading	as	ipad	died	231				
1421	6.55	761.36	25.9	2.97	19.28	18.5		300		Unfiltered
1524	6.54	763.61	21.8	2.66	19.69	14.1		300		Total: 2.5 mg/L
1615	6.55	765.18	28.6	2.69	19.85	44.3		300		Ferrus 1.5 mg/L
										High Range As: 10-20
Stabilizing Criteria	+/- 0.1 SU	+/- 5%		0.2 mg/L or 10% for DO > 0.5 mg/L (whichever is greater)		< 5 NTUs	< 0.3 ft	> 100 mL < 250 mL	> 3L	

GROUNDWATER SAMPLING LOG SHEET

d = well diameter (inches); h = length of water column (feet)

Well Cap Condition: Good ReplacePurge Method: Low-Flow Well Volume Other:

Sampling Method: Pump Discharge Other: _____

OA/OC Collected? No

QA/QC I.D. _____

All sample containers requiring chemical preservation properly preserved prior to demob from well? ☒ Yes ☐ No

[illegible]

GROUNDWATER SAMPLING LOG SHEET

Client:	SCS
Site:	AP-1
Well ID:	PF-07
Total Depth (ft):	45.72
Depth to Water (ft):	
Well Diameter (in):	2
Well Volume (gal) = $0.041d^2h$:	
Well Volume (L) = gal * 3.785:	

d = well diameter (inches); h = length of water column (feet)

Well Type:	Flush	Stick Up
Well Lock:	Yes	No
Well Cap Condition:	Good	Replace
Well Tag Present:	Yes	No

Project No.: GWW45816
Location: Plant Hammond
Pump Type/Model: Bladder
Tubing Material: poly
Pump Intake Depth (ft): 40
Start/Stop Purge Time: 1029/1145
Purge Rate (mL/min): 200
Total Purge Volume (L): 12

Purge Method: Low-Flow Well Volume Other: _____
Sampling Method: Pump Discharge Other: _____

Sampling Date: 9/21/24
 Sampler's Name: J. Newsome
 Sample Collection Time: 1145
 Sample Purge Rate (mL/min): 200
 Sample ID: HAM-PT-07-FIL HAM-PT-07-UNF
 Laboratory Analyses: Metals
 QA/QC Collected? No
 QA/QC I.D. _____

All sample containers requiring chemical preservation properly preserved prior to demob from well? Yes No

[illegible]

GROUNDWATER SAMPLING LOG SHEET

Client:	SCS	
Site:	LP-1	
Well ID:	PT-08	
Total Depth (ft):	45	
Depth to Water (ft):		
Well Diameter (in):	2	
Well Volume (gal) = $0.041d^2h$:		
Well Volume (L) = gal * 3.785:		
<i>d = well diameter (inches); h = length of water column (feet)</i>		
Well Type:	Flush	Stock Up
Well Lock:	Yes	No
Well Cap Condition:	Good	Replace
Well Tag Present:	Yes	No

Project No.: AUG581G
Location: GPO Plant Hammond
Pump Type/Model: Bladder
Tubing Material: poly
Pump Intake Depth (ft): 40
Start/Stop Purge Time: 1155/
Purge Rate (mL/min): 300
Total Purge Volume (L): _____

Sampling Date: 9/21/24

Sampler's Name: J. Newson

Sample Collection Time: 1430

Sample Purge Rate (mL/min): 700

Sample ID: HAM-PT-08-FIL

Laboratory Analyses: Metals

QA/QC Collected? No

QA/QC I.D. _____

All sample containers requiring chemical preservation properly preserved prior to demob from well? Yes No

Time	pH (SU)	Spec. Cond. (µS/cm)	ORP (mV)	DO (mg/L)	Temp. (°C)	Turbidity (NTUs)	DTW (ft btoc)	Purge Rate (mL/min)	Purged Volume (L)	Notes (Purge method, water clarity, odor, purge rate, issues with pump/well/weather/etc.)
1155										
1200	6.75	595.02	69.1	1.97	22.48	++ +		300	1	pre purge
1210	6.44	598.23	99.5	1.45	21.55	7.51			3	
1220	6.40	408.33	100.1	5.53	21.73	350			5	
1230	6.59	670.08	97.0	4.71	21.60	180			7	
1240 50	6.56	631.48	99.6	2.2	21.84	145			11	
1300	6.58	637.36	83.6	3.55	22.04	123			13	
1310	6.56	637.39	45.4	3.26	22.10	917			15	
1320	6.56	644.73	70.9	3.15	21.05	58.6				FIL ONE
1330	6.56	649.04	63.0	2.98	22.13	30.1				Fe 0.25 mg/L
1340	6.56	648.45	58.2	2.99	22.35	28.0				Fe ²⁺ 0.01 mg/L
1350	6.56	650.64	45.1	2.92	22.40	25.9				AS 2x6=20 m 4x6=24
1400	6.56	652.13	42.3	2.77	22.56	15.1				
1410	6.56	654.15	38.0	2.69	22.55	10.4				
1420	6.57	652.53	35.3	2.45	22.35					
1430		Sampled								
Stabilizing Criteria	+/- 0.1 SU	+/- 5%		0.2 mg/L or 10% for DO > 0.5 mg/L (whichever is greater)		< 5 NTUs	< 0.3 ft	> 100 mL < 250 mL	> 3L	

GROUNDWATER SAMPLING LOG SHEET

Client: Hammond
Site: AP-1
Well ID: PT-13
Total Depth (ft): 45
Depth to Water (ft): 26.50 (APT) 26.50 ft
Well Diameter (in): 2
Well Volume (gal) = $0.041d^2h$:
Well Volume (L) = gal * 3.785:

Project No.:
Location: AP-1
Pump Type/Model: Bladder
Tubing Material: Poly
Pump Intake Depth (ft): 40
Start/Stop Purge Time: 0845/
Purge Rate (mL/min): 300
Total Purge Volume (L):

Sampling Date: 9/21/2024
Sampler's Name: A. Thompson
Sample Collection Time: 1600
Sample Purge Rate (mL/min): 200
Sample ID: HAM-PT-13-09-24
Laboratory Analyses:

d = well diameter (inches); h = length of water column (feet)

Well Type: ☒ Flush ☐ Stick Up
Well Lock: ☒ Yes ☐ No
Well Cap Condition: ☒ Good ☐ Replace
Well Tag Present: ☒ Yes ☐ No

Purge Method: Low-Flow Well Volume Other: NO
Sampling Method: Pump Discharge Other: —
QA/QC I.D. —

All sample containers requiring chemical preservation properly preserved prior to demob from well? Yes No

Time	pH (SU)	Spec. Cond. (µS/cm)	ORP (mV)	DO (mg/L)	Temp. (°C)	Turbidity (NTUs)	DTW (ft btoc)	Purge Rate (mL/min)	Purged Volume (L)	Notes (Purge method, water clarity, odor, purge rate, issues with pump/well/weather/etc.)
0855	6.54	692.71	52.4	6.99	20.91	1114		300		
0900	6.54	693.43	71.6	7.16	20.96	1117		300		
0927	6.55	660.57	40.9	7.68	20.67	1114		300		result stabilizing during
0957	6.54	653.60	23.0	7.75	20.78	804		300		
1027	6.55	649.39	15.7	7.86	20.92	325		300		
1057	6.56	648.64	12.2	7.70	21.01	237		300		
1127	6.57	651.98	12.7	7.52	21.09	203		300		
1157	6.51	654.60	12.7	6.45	21.27	427		300		
1227	6.50	654.60	11.1	6.60	21.27	188		300		
1257	6.52	658.17	12.7	6.13	21.40	391		300		
1327	6.51	658.10	13.4	6.19	21.45	576		300		
1357	6.53	658.36	11.8	6.33	21.45	235		300		UNE
1427	6.53	659.88	6.3	5.80	21.44	108		300		Fe 2x1=2 mL
1457	6.54	658.87	3.3	5.42	21.54	91.1		300		Fe ²⁺ 1x1=1
1527	6.50	691.00	3.2	4.88	21.49	10.0		300		AS 2x4.5=9.0
1557						23.7		300		
1600						saturated				
Stabilizing Criteria	+/- 0.1 SU	+/- 5%		0.2 mg/L or 10% for DO > 0.5 mg/L (whichever is greater)		< 5 NTUs	< 0.3 ft	> 100 mL < 250 mL	> 3L	

$\geq 3L$

GROUNDWATER SAMPLING LOG SHEET

Client:	ICS
Site:	# AP-1
Well ID:	PT-15
Total Depth (ft):	45
Depth to Water (ft):	38 27.14
Well Diameter (in):	2
Well Volume (gal) = $0.041d^2h$:	2.93
Well Volume (L) = gal * 3.785:	11.09

d = well diameter (inches); h = length of water column (feet)

Well Type: ☒ Flush ☐ Stick UpWell Lock: Yes ☒ No ☐Well Cap Condition: Good Replace

Well Tag Present: Yes No

Project No.: AWW651G
Location: Plant Hammond
Type/Model: Bladder
Lining Material: poly
Take Depth (ft): 400
Purge Time: 935/1010
Rate (mL/min): 200
Sample Volume (L): 4

Purge Method: Low-Flow Well Volume Other: _____

Sampling Method: Pump Discharge Other: _____

Sampling Date: 9/21/24

Sampler's Name: J. Newsome

Sample Collection Time: 1015

Sample Purge Rate (mL/min): 700

Sample ID: HAM-F#-PT-15-DNF

Laboratory Analyses: Metals

QA/QC Collected? NC

QA/QC I.D. _____

All sample containers requiring chemical preservation properly preserved prior to demob from well? Yes No

[illegible]

Calibration Forms

Site Name: Plant Hammond Field Instrumentation Calibration Form

Date: 9/9/2024

Calibrated By: A. Akbari

Field Conditions: 74°F, Sunny

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Agila TRILL 400</u>	<u>850791</u>
Turbidity Meter		

118075

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (μS/cm)	4,490	<u>24010943</u>	<u>5/2025</u>	<u>AIR ANAL CAL</u>
pH (SU)	4.00	<u>24010943</u>	<u>5/2025</u>	<u>AIR ANAL CAL</u>
pH (SU)	7.00	<u>24004517</u>	<u>12/2024</u>	<u>AIR</u>
pH (SU)	10.00	<u>24000085</u>	<u>12/2024</u>	<u>AIR</u>
D.O. (%)	N/A			
ORP (mV)	228.0	<u>24000905</u>	<u>12/2024</u>	<u>AIR</u>

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (μS/cm)	4,490	<u>4291.7</u>	<u>23.93</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.04</u>	<u>24.06</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.02</u>	<u>23.93</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.01</u>	<u>23.104</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100.52%</u>	<u>23.21</u>	± 10%	NA
ORP (mV)	228.0	<u>227.0</u>	<u>23.25</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			± 10% of standard	EPA 2023

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (μS/cm)	4,490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			± 10% of standard	EPA 2023

Notes:

Site Name: Plant Hammond Field Instrumentation Calibration FormDate: 9/9/2024Calibrated By: A. TammisonField Conditions: 72°F, sunny

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	AquaTRAIL 400	10791634
Turbidity Meter		

1119364 → 1080307

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (μS/cm)	4,490	24010943	5/2025	AIR AUTOCAL
pH (SU)	4.00	24010943	5/2025	AIR AUTOCAL
pH (SU)	7.00	24054517	12/2024	AIR
pH (SU)	10.00	24000085	12/2024	AIR
D.O. (%)	N/A			
ORP (mV)	228.0	24006903	12/2024	AIR

Calibration					
Time Start <u>1055</u>		Time Finish <u>1110</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (μS/cm)	4,490	<u>4486.6</u>	<u>23.51</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.04</u>	<u>23.75</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.05</u>	<u>23.80</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.01</u>	<u>23.44</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>108.74%</u>	<u>24.33</u>	± 10%	NA
ORP (mV)	228.0	<u>227.1</u>	<u>23.88</u>	± 10	EPA 2023

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)			± 10% of standard	EPA 2023

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (μS/cm)	4,490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)			± 10% of standard	EPA 2023

Notes:

Site Name: _____

Field Instrumentation Calibration Form

Date: 9/10/24Calibrated By: A. TanlinsenField Conditions: 64°F, sunny

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter		
Turbidity Meter	Hach 2100Q	234013000344

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490			
pH (SU)	4.00			
pH (SU)	7.00			
pH (SU)	10.00			
D.O. (%)	N/A			
ORP (mV)	228.0			

Calibration					
Time Start <u>0915</u>		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP
D.O. (%)	N/A			± 10%	NA
ORP (mV)	228.0			± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>20</u>	<u>19.6</u>	± 10% of standard	EPA 2023
	<u>100</u>	<u>111</u>		
	<u>500</u>	<u>823</u>		
	<u>10</u>	<u>10.35</u>		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			± 10% of standard	EPA 2023

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 9/16/24

Calibrated By: J. Newberry

Field Conditions: Sunny, 80°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	AquaTron 1	168037
Turbidity Meter		

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	24010943	6/20/25	A/R
pH (SU)	4.00	4	"	
pH (SU)	7.00	24004812	12/2024	
pH (SU)	10.00	24000005	12/2024	
D.O. (%)	N/A			
ORP (mV)	228.0	24004900	12/2024	A/R

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	4490	29.81	± 10% of standard	EPA 2023
pH (SU)	4.00	4.00	29.76	± 0.1	GWMP
pH (SU)	7.00	7.00	29.21	± 0.1	GWMP
pH (SU)	10.00	10.01	27.44	± 0.1	GWMP
D.O. (%)	N/A	100	28.75	± 10%	NA
ORP (mV)	228.0	228.0	28.74	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			± 10% of standard	EPA 2023

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			± 10% of standard	EPA 2023

Notes:

Site Name: Gr Plant Hammond

Field Instrumentation Calibration Form

Date: 9/19/24Calibrated By: J. NewsonField Conditions: Clear, 70F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Aquatroll</u>	<u>966105</u>
Turbidity Meter		

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>24610943</u>	<u>09/2025</u>	<u>AIR</u>
pH (SU)	4.00	"	"	"
pH (SU)	7.00	<u>24004517</u>	<u>12/2024</u>	"
pH (SU)	10.00	<u>24000085</u>	<u>12/2024</u>	"
D.O. (%)	N/A			
ORP (mV)	228.0	<u>24006403</u>	<u>12/2024</u>	<u>AIR</u>

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>4490</u>	<u>21.55</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.06</u>	<u>21.73</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>22.13</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>22.15</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100</u>	<u>21.41</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228.0</u>	<u>21.54</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

Site Name: GP Plant Hammond

Field Instrumentation Calibration Form

Date: 9/19/24Calibrated By: J. NewcomeField Conditions: Sunny, 90F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>AquaTron</u>	<u>1080307</u>
Turbidity Meter		

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>24010943</u>	<u>05/2025</u>	<u>AIR</u>
pH (SU)	4.00			
pH (SU)	7.00	<u>24004517</u>	<u>12/2024</u>	
pH (SU)	10.00	<u>24000685</u>	<u>12/2024</u>	
D.O. (%)	N/A			
ORP (mV)	228.0	<u>24000903</u>	<u>12/2024</u>	<u>AIR</u>

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>4490</u>	<u>21.54</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>21.84</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>21.13</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>22.20</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100</u>	<u>20.15</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228.0</u>	<u>21.89</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

APPENDIX E

Post-injection Performance Monitoring Groundwater Analytical Laboratory Results and Field Sampling Forms

Laboratory Analytical Reports



August 19, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1 (CA)
Pace Project No.: 92745452

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on August 02, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Peachtree Corners, GA

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Jamie Newsome, Geosyntec Consultants
Zain Webb, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92745452001	HAM-PT-07	Water	08/01/24 13:43	08/02/24 14:00
92745452002	HAM-PT-08	Water	08/01/24 14:55	08/02/24 14:00
92745452003	HAM-PT-09	Water	07/31/24 13:33	08/02/24 14:00
92745452004	HAM-PT-10	Water	07/31/24 10:07	08/02/24 14:00
92745452005	HAM-PT-11	Water	07/31/24 16:46	08/02/24 14:00
92745452006	HAM-PT-12	Water	07/31/24 18:05	08/02/24 14:00
92745452007	HAM-PT-13	Water	08/01/24 12:47	08/02/24 14:00
92745452008	HAM-PT-14	Water	08/01/24 16:45	08/02/24 14:00
92745452009	HAM-PT-15	Water	08/01/24 10:47	08/02/24 14:00
92745452010	HAM-AP1-FD-01	Water	07/31/24 00:00	08/02/24 14:00
92745452011	HAM-AP1-FB-01	Water	08/01/24 12:00	08/02/24 14:00
92745452012	HAM-AP1-EB-01	Water	08/01/24 12:00	08/02/24 14:00

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92745452001	HAM-PT-07	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92745452002	HAM-PT-08	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92745452003	HAM-PT-09	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92745452004	HAM-PT-10	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92745452005	HAM-PT-11	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92745452006	HAM-PT-12	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92745452007	HAM-PT-13	EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
92745452008	HAM-PT-14	SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	MJS2	6
92745452009	HAM-PT-15	EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
92745452010	HAM-AP1-FD-01	SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92745452011	HAM-AP1-FB-01	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92745452012	HAM-AP1-EB-01	SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3

PASI-A = Pace Analytical Services - Asheville

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92745452001	HAM-PT-07					
EPA 6010D	Iron	13.2	mg/L	0.040	08/07/24 17:06	M1
EPA 6010D	Manganese	4.2	mg/L	0.040	08/07/24 17:06	
EPA 6010D	Potassium	5.7	mg/L	0.50	08/07/24 17:06	
EPA 6010D	Sodium	8.6	mg/L	1.0	08/07/24 17:06	
EPA 6010D	Calcium	123	mg/L	1.0	08/07/24 17:06	M1
EPA 6010D	Magnesium	17.8	mg/L	0.050	08/07/24 17:06	M1
EPA 6020B	Arsenic	0.11	mg/L	0.025	08/08/24 10:28	
EPA 6020B	Barium	0.049	mg/L	0.0050	08/07/24 17:20	
EPA 6020B	Beryllium	0.00019J	mg/L	0.00050	08/07/24 17:20	
EPA 6020B	Boron	0.57	mg/L	0.20	08/08/24 10:28	
EPA 6020B	Cobalt	0.056	mg/L	0.0050	08/07/24 17:20	
EPA 6020B	Lithium	0.056	mg/L	0.030	08/07/24 17:20	
EPA 6020B	Molybdenum	0.0047J	mg/L	0.010	08/07/24 17:20	
EPA 6020B	Thallium	0.00050J	mg/L	0.0010	08/07/24 17:20	
SM 2540C-2015	Total Dissolved Solids	578	mg/L	25.0	08/05/24 16:28	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	119	mg/L	5.0	08/06/24 13:15	
SM 2320B-2011	Alkalinity, Total as CaCO3	119	mg/L	5.0	08/06/24 13:15	
EPA 300.0 Rev 2.1 1993	Chloride	16.7	mg/L	1.0	08/03/24 12:38	
EPA 300.0 Rev 2.1 1993	Fluoride	0.22	mg/L	0.10	08/03/24 12:38	
EPA 300.0 Rev 2.1 1993	Sulfate	223	mg/L	5.0	08/03/24 23:50	M1
92745452002	HAM-PT-08					
EPA 6010D	Iron	14.5	mg/L	0.040	08/07/24 17:26	
EPA 6010D	Manganese	4.1	mg/L	0.040	08/07/24 17:26	
EPA 6010D	Potassium	5.0	mg/L	0.50	08/07/24 17:26	
EPA 6010D	Sodium	6.8	mg/L	1.0	08/07/24 17:26	
EPA 6010D	Calcium	85.2	mg/L	1.0	08/07/24 17:26	
EPA 6010D	Magnesium	11.9	mg/L	0.050	08/07/24 17:26	
EPA 6020B	Arsenic	0.26	mg/L	0.025	08/08/24 10:32	
EPA 6020B	Barium	0.044	mg/L	0.0050	08/07/24 17:23	
EPA 6020B	Beryllium	0.000098J	mg/L	0.00050	08/07/24 17:23	
EPA 6020B	Boron	0.63	mg/L	0.20	08/08/24 10:32	
EPA 6020B	Cobalt	0.073	mg/L	0.0050	08/07/24 17:23	
EPA 6020B	Lithium	0.022J	mg/L	0.030	08/07/24 17:23	
EPA 6020B	Molybdenum	0.012	mg/L	0.010	08/07/24 17:23	
SM 2540C-2015	Total Dissolved Solids	443	mg/L	25.0	08/05/24 16:29	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	76.4	mg/L	5.0	08/06/24 13:38	
SM 2320B-2011	Alkalinity, Total as CaCO3	76.4	mg/L	5.0	08/06/24 13:38	
EPA 300.0 Rev 2.1 1993	Chloride	14.0	mg/L	1.0	08/03/24 13:18	
EPA 300.0 Rev 2.1 1993	Fluoride	0.16	mg/L	0.10	08/03/24 13:18	
EPA 300.0 Rev 2.1 1993	Sulfate	176	mg/L	4.0	08/04/24 00:31	
92745452003	HAM-PT-09					
EPA 6010D	Iron	0.13	mg/L	0.040	08/07/24 17:30	
EPA 6010D	Manganese	0.47	mg/L	0.040	08/07/24 17:30	
EPA 6010D	Potassium	6.1	mg/L	0.50	08/07/24 17:30	
EPA 6010D	Sodium	6.6	mg/L	1.0	08/07/24 17:30	
EPA 6010D	Calcium	96.9	mg/L	1.0	08/07/24 17:30	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92745452003	HAM-PT-09					
EPA 6010D	Magnesium	24.5	mg/L	0.050	08/07/24 17:30	
EPA 6020B	Antimony	0.0010J	mg/L	0.0030	08/07/24 17:38	
EPA 6020B	Barium	0.072	mg/L	0.0050	08/07/24 17:38	
EPA 6020B	Beryllium	0.00013J	mg/L	0.00050	08/07/24 17:38	
EPA 6020B	Boron	1.1	mg/L	0.040	08/08/24 11:09	
EPA 6020B	Cadmium	0.00028J	mg/L	0.00050	08/07/24 17:38	
EPA 6020B	Cobalt	0.0037J	mg/L	0.0050	08/07/24 17:38	
EPA 6020B	Lithium	0.0019J	mg/L	0.030	08/07/24 17:38	
EPA 6020B	Molybdenum	0.24	mg/L	0.010	08/07/24 17:38	
SM 2540C-2015	Total Dissolved Solids	500	mg/L	25.0	08/05/24 12:42	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	119	mg/L	5.0	08/06/24 13:59	
SM 2320B-2011	Alkalinity, Total as CaCO3	119	mg/L	5.0	08/06/24 13:59	
EPA 300.0 Rev 2.1 1993	Chloride	29.3	mg/L	1.0	08/03/24 13:32	
EPA 300.0 Rev 2.1 1993	Fluoride	0.33	mg/L	0.10	08/03/24 13:32	
EPA 300.0 Rev 2.1 1993	Sulfate	172	mg/L	4.0	08/04/24 00:45	
92745452004	HAM-PT-10					
EPA 6010D	Manganese	0.48	mg/L	0.040	08/07/24 17:34	
EPA 6010D	Potassium	6.7	mg/L	0.50	08/07/24 17:34	
EPA 6010D	Sodium	8.8	mg/L	1.0	08/07/24 17:34	
EPA 6010D	Calcium	102	mg/L	1.0	08/07/24 17:34	
EPA 6010D	Magnesium	13.7	mg/L	0.050	08/07/24 17:34	
EPA 6020B	Barium	0.046	mg/L	0.0050	08/07/24 17:42	
EPA 6020B	Boron	1.6	mg/L	0.040	08/08/24 11:13	
EPA 6020B	Cadmium	0.00012J	mg/L	0.00050	08/07/24 17:42	
EPA 6020B	Cobalt	0.0015J	mg/L	0.0050	08/07/24 17:42	
EPA 6020B	Molybdenum	0.15	mg/L	0.010	08/07/24 17:42	
SM 2540C-2015	Total Dissolved Solids	535	mg/L	25.0	08/05/24 12:42	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	133	mg/L	5.0	08/06/24 14:17	
SM 2320B-2011	Alkalinity, Total as CaCO3	133	mg/L	5.0	08/06/24 14:17	
EPA 300.0 Rev 2.1 1993	Chloride	46.4	mg/L	1.0	08/03/24 13:45	
EPA 300.0 Rev 2.1 1993	Fluoride	0.22	mg/L	0.10	08/03/24 13:45	
EPA 300.0 Rev 2.1 1993	Sulfate	117	mg/L	3.0	08/04/24 00:59	
92745452005	HAM-PT-11					
EPA 6010D	Iron	0.66	mg/L	0.040	08/07/24 17:38	
EPA 6010D	Manganese	1.3	mg/L	0.040	08/07/24 17:38	
EPA 6010D	Potassium	5.6	mg/L	0.50	08/07/24 17:38	
EPA 6010D	Sodium	7.5	mg/L	1.0	08/07/24 17:38	
EPA 6010D	Calcium	90.6	mg/L	1.0	08/07/24 17:38	
EPA 6010D	Magnesium	19.0	mg/L	0.050	08/07/24 17:38	
EPA 6020B	Antimony	0.00086J	mg/L	0.0030	08/07/24 17:45	
EPA 6020B	Barium	0.068	mg/L	0.0050	08/07/24 17:45	
EPA 6020B	Boron	1.4	mg/L	0.040	08/08/24 11:17	
EPA 6020B	Cadmium	0.00027J	mg/L	0.00050	08/07/24 17:45	
EPA 6020B	Cobalt	0.019	mg/L	0.0050	08/07/24 17:45	
EPA 6020B	Lithium	0.0060J	mg/L	0.030	08/07/24 17:45	
EPA 6020B	Molybdenum	0.074	mg/L	0.010	08/07/24 17:45	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92745452005	HAM-PT-11					
SM 2540C-2015	Total Dissolved Solids	464	mg/L	25.0	08/05/24 12:42	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	112	mg/L	5.0	08/06/24 14:27	
SM 2320B-2011	Alkalinity, Total as CaCO3	112	mg/L	5.0	08/06/24 14:27	
EPA 300.0 Rev 2.1 1993	Chloride	33.6	mg/L	1.0	08/03/24 13:58	
EPA 300.0 Rev 2.1 1993	Fluoride	0.26	mg/L	0.10	08/03/24 13:58	
EPA 300.0 Rev 2.1 1993	Sulfate	141	mg/L	3.0	08/04/24 01:14	
92745452006	HAM-PT-12					
EPA 6010D	Iron	0.16	mg/L	0.040	08/07/24 17:42	
EPA 6010D	Manganese	0.77	mg/L	0.040	08/07/24 17:42	
EPA 6010D	Potassium	6.0	mg/L	0.50	08/07/24 17:42	
EPA 6010D	Sodium	7.9	mg/L	1.0	08/07/24 17:42	
EPA 6010D	Calcium	94.9	mg/L	1.0	08/07/24 17:42	
EPA 6010D	Magnesium	21.8	mg/L	0.050	08/07/24 17:42	
EPA 6020B	Barium	0.064	mg/L	0.0050	08/07/24 18:13	
EPA 6020B	Boron	1.3	mg/L	0.040	08/08/24 11:21	
EPA 6020B	Cadmium	0.00022J	mg/L	0.00050	08/07/24 18:13	
EPA 6020B	Cobalt	0.0032J	mg/L	0.0050	08/07/24 18:13	
EPA 6020B	Molybdenum	0.16	mg/L	0.010	08/07/24 18:13	
SM 2540C-2015	Total Dissolved Solids	470	mg/L	25.0	08/05/24 12:42	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	124	mg/L	5.0	08/06/24 14:36	
SM 2320B-2011	Alkalinity, Total as CaCO3	124	mg/L	5.0	08/06/24 14:36	
EPA 300.0 Rev 2.1 1993	Chloride	30.2	mg/L	1.0	08/03/24 14:12	
EPA 300.0 Rev 2.1 1993	Fluoride	0.26	mg/L	0.10	08/03/24 14:12	
EPA 300.0 Rev 2.1 1993	Sulfate	157	mg/L	4.0	08/04/24 01:28	
92745452007	HAM-PT-13					
EPA 6010D	Iron	25.6	mg/L	0.040	08/07/24 17:46	
EPA 6010D	Manganese	4.3	mg/L	0.040	08/07/24 17:46	
EPA 6010D	Potassium	5.3	mg/L	0.50	08/07/24 17:46	
EPA 6010D	Sodium	8.2	mg/L	1.0	08/07/24 17:46	
EPA 6010D	Calcium	111	mg/L	1.0	08/07/24 17:46	
EPA 6010D	Magnesium	15.5	mg/L	0.050	08/07/24 17:46	
EPA 6020B	Arsenic	0.20	mg/L	0.025	08/08/24 10:44	
EPA 6020B	Barium	0.043	mg/L	0.0050	08/07/24 18:16	
EPA 6020B	Boron	0.51	mg/L	0.20	08/08/24 10:44	
EPA 6020B	Cobalt	0.040	mg/L	0.0050	08/07/24 18:16	
EPA 6020B	Lithium	0.058	mg/L	0.030	08/07/24 18:16	
EPA 6020B	Molybdenum	0.0052J	mg/L	0.010	08/07/24 18:16	
SM 2540C-2015	Total Dissolved Solids	549	mg/L	25.0	08/05/24 16:29	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	115	mg/L	5.0	08/06/24 14:45	
SM 2320B-2011	Alkalinity, Total as CaCO3	115	mg/L	5.0	08/06/24 14:45	
EPA 300.0 Rev 2.1 1993	Chloride	15.5	mg/L	1.0	08/03/24 14:25	
EPA 300.0 Rev 2.1 1993	Fluoride	0.26	mg/L	0.10	08/03/24 14:25	
EPA 300.0 Rev 2.1 1993	Sulfate	229	mg/L	5.0	08/04/24 02:09	
92745452008	HAM-PT-14					
EPA 6010D	Iron	17.5	mg/L	0.040	08/07/24 17:50	
EPA 6010D	Manganese	3.4	mg/L	0.040	08/07/24 17:50	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92745452008	HAM-PT-14					
EPA 6010D	Potassium	5.9	mg/L	0.50	08/07/24 17:50	
EPA 6010D	Sodium	8.8	mg/L	1.0	08/07/24 17:50	
EPA 6010D	Calcium	123	mg/L	1.0	08/07/24 17:50	
EPA 6010D	Magnesium	18.7	mg/L	0.050	08/07/24 17:50	
EPA 6020B	Arsenic	0.15	mg/L	0.025	08/08/24 10:48	
EPA 6020B	Barium	0.045	mg/L	0.0050	08/07/24 18:20	
EPA 6020B	Boron	0.55	mg/L	0.20	08/08/24 10:48	
EPA 6020B	Cobalt	0.025	mg/L	0.0050	08/07/24 18:20	
EPA 6020B	Lithium	0.049	mg/L	0.030	08/07/24 18:20	
EPA 6020B	Molybdenum	0.011	mg/L	0.010	08/07/24 18:20	
SM 2540C-2015	Total Dissolved Solids	599	mg/L	25.0	08/05/24 16:29	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	153	mg/L	5.0	08/06/24 14:55	
SM 2320B-2011	Alkalinity, Total as CaCO3	153	mg/L	5.0	08/06/24 14:55	
EPA 300.0 Rev 2.1 1993	Chloride	17.8	mg/L	1.0	08/03/24 14:39	
EPA 300.0 Rev 2.1 1993	Fluoride	0.22	mg/L	0.10	08/03/24 14:39	
EPA 300.0 Rev 2.1 1993	Sulfate	224	mg/L	5.0	08/04/24 02:23	
92745452009	HAM-PT-15					
EPA 6010D	Iron	13.4	mg/L	0.040	08/07/24 17:53	
EPA 6010D	Manganese	5.4	mg/L	0.040	08/07/24 17:53	
EPA 6010D	Potassium	5.4	mg/L	0.50	08/07/24 17:53	
EPA 6010D	Sodium	7.7	mg/L	1.0	08/07/24 17:53	
EPA 6010D	Calcium	117	mg/L	1.0	08/07/24 17:53	
EPA 6010D	Magnesium	14.5	mg/L	0.050	08/07/24 17:53	
EPA 6020B	Arsenic	0.42	mg/L	0.025	08/08/24 10:53	
EPA 6020B	Barium	0.042	mg/L	0.0050	08/07/24 18:24	
EPA 6020B	Boron	0.63	mg/L	0.20	08/08/24 10:53	
EPA 6020B	Cobalt	0.056	mg/L	0.0050	08/07/24 18:24	
EPA 6020B	Lithium	0.050	mg/L	0.030	08/07/24 18:24	
EPA 6020B	Molybdenum	0.013	mg/L	0.010	08/07/24 18:24	
SM 2540C-2015	Total Dissolved Solids	544	mg/L	25.0	08/05/24 16:29	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	129	mg/L	5.0	08/06/24 15:06	
SM 2320B-2011	Alkalinity, Total as CaCO3	129	mg/L	5.0	08/06/24 15:06	
EPA 300.0 Rev 2.1 1993	Chloride	14.4	mg/L	1.0	08/03/24 15:19	
EPA 300.0 Rev 2.1 1993	Fluoride	0.29	mg/L	0.10	08/03/24 15:19	
EPA 300.0 Rev 2.1 1993	Sulfate	206	mg/L	5.0	08/04/24 02:36	
92745452010	HAM-AP1-FD-01					
EPA 6010D	Iron	0.20	mg/L	0.040	08/07/24 18:56	
EPA 6010D	Manganese	0.81	mg/L	0.040	08/07/24 18:56	
EPA 6010D	Potassium	6.0	mg/L	0.50	08/07/24 18:56	
EPA 6010D	Sodium	8.1	mg/L	1.0	08/07/24 18:56	
EPA 6010D	Calcium	94.9	mg/L	1.0	08/07/24 18:56	
EPA 6010D	Magnesium	21.9	mg/L	0.050	08/07/24 18:56	
EPA 6020B	Barium	0.064	mg/L	0.0050	08/07/24 18:31	
EPA 6020B	Boron	1.2	mg/L	0.040	08/08/24 11:25	
EPA 6020B	Cadmium	0.00023J	mg/L	0.00050	08/07/24 18:31	
EPA 6020B	Cobalt	0.0032J	mg/L	0.0050	08/07/24 18:31	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92745452010	HAM-AP1-FD-01					
EPA 6020B	Molybdenum	0.15	mg/L	0.010	08/07/24 18:31	
SM 2540C-2015	Total Dissolved Solids	462	mg/L	25.0	08/05/24 12:45	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	124	mg/L	5.0	08/06/24 15:16	
SM 2320B-2011	Alkalinity, Total as CaCO3	124	mg/L	5.0	08/06/24 15:16	
EPA 300.0 Rev 2.1 1993	Chloride	30.6	mg/L	1.0	08/03/24 15:33	
EPA 300.0 Rev 2.1 1993	Fluoride	0.26	mg/L	0.10	08/03/24 15:33	
EPA 300.0 Rev 2.1 1993	Sulfate	155	mg/L	4.0	08/04/24 02:50	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Sample: HAM-PT-07		Lab ID: 92745452001		Collected: 08/01/24 13:43		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	13.2	mg/L	0.040	0.025	1	08/07/24 11:36	08/07/24 17:06	7439-89-6	M1
Manganese	4.2	mg/L	0.040	0.011	1	08/07/24 11:36	08/07/24 17:06	7439-96-5	
Potassium	5.7	mg/L	0.50	0.15	1	08/07/24 11:36	08/07/24 17:06	7440-09-7	
Sodium	8.6	mg/L	1.0	0.58	1	08/07/24 11:36	08/07/24 17:06	7440-23-5	
Calcium	123	mg/L	1.0	0.12	1	08/07/24 11:36	08/07/24 17:06	7440-70-2	M1
Magnesium	17.8	mg/L	0.050	0.012	1	08/07/24 11:36	08/07/24 17:06	7439-95-4	M1
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/07/24 11:55	08/07/24 17:20	7440-36-0	
Arsenic	0.11	mg/L	0.025	0.0042	5	08/07/24 11:55	08/08/24 10:28	7440-38-2	
Barium	0.049	mg/L	0.0050	0.00047	1	08/07/24 11:55	08/07/24 17:20	7440-39-3	
Beryllium	0.00019J	mg/L	0.00050	0.000094	1	08/07/24 11:55	08/07/24 17:20	7440-41-7	
Boron	0.57	mg/L	0.20	0.060	5	08/07/24 11:55	08/08/24 10:28	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	08/07/24 11:55	08/07/24 17:20	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/07/24 11:55	08/07/24 17:20	7440-47-3	
Cobalt	0.056	mg/L	0.0050	0.00032	1	08/07/24 11:55	08/07/24 17:20	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/07/24 11:55	08/07/24 17:20	7439-92-1	
Lithium	0.056	mg/L	0.030	0.0016	1	08/07/24 11:55	08/07/24 17:20	7439-93-2	
Molybdenum	0.0047J	mg/L	0.010	0.00062	1	08/07/24 11:55	08/07/24 17:20	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/07/24 11:55	08/07/24 17:20	7782-49-2	
Thallium	0.00050J	mg/L	0.0010	0.00038	1	08/07/24 11:55	08/07/24 17:20	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/14/24 10:30	08/14/24 14:50	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	578	mg/L	25.0	25.0	1		08/05/24 16:28		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	119	mg/L	5.0	5.0	1		08/06/24 13:15		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/06/24 13:15		
Alkalinity, Total as CaCO3	119	mg/L	5.0	5.0	1		08/06/24 13:15		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/03/24 03:16	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	16.7	mg/L	1.0	0.60	1		08/03/24 12:38	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Sample: HAM-PT-07		Lab ID: 92745452001		Collected: 08/01/24 13:43		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.22	mg/L	0.10	0.050	1		08/03/24 12:38	16984-48-8	
Sulfate	223	mg/L	5.0	2.5	5		08/03/24 23:50	14808-79-8	M1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Sample: HAM-PT-08		Lab ID: 92745452002		Collected: 08/01/24 14:55		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	14.5	mg/L	0.040	0.025	1	08/07/24 11:36	08/07/24 17:26	7439-89-6	
Manganese	4.1	mg/L	0.040	0.011	1	08/07/24 11:36	08/07/24 17:26	7439-96-5	
Potassium	5.0	mg/L	0.50	0.15	1	08/07/24 11:36	08/07/24 17:26	7440-09-7	
Sodium	6.8	mg/L	1.0	0.58	1	08/07/24 11:36	08/07/24 17:26	7440-23-5	
Calcium	85.2	mg/L	1.0	0.12	1	08/07/24 11:36	08/07/24 17:26	7440-70-2	
Magnesium	11.9	mg/L	0.050	0.012	1	08/07/24 11:36	08/07/24 17:26	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/07/24 11:55	08/07/24 17:23	7440-36-0	
Arsenic	0.26	mg/L	0.025	0.0042	5	08/07/24 11:55	08/08/24 10:32	7440-38-2	
Barium	0.044	mg/L	0.0050	0.00047	1	08/07/24 11:55	08/07/24 17:23	7440-39-3	
Beryllium	0.000098J	mg/L	0.00050	0.000094	1	08/07/24 11:55	08/07/24 17:23	7440-41-7	
Boron	0.63	mg/L	0.20	0.060	5	08/07/24 11:55	08/08/24 10:32	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	08/07/24 11:55	08/07/24 17:23	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/07/24 11:55	08/07/24 17:23	7440-47-3	
Cobalt	0.073	mg/L	0.0050	0.00032	1	08/07/24 11:55	08/07/24 17:23	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/07/24 11:55	08/07/24 17:23	7439-92-1	
Lithium	0.022J	mg/L	0.030	0.0016	1	08/07/24 11:55	08/07/24 17:23	7439-93-2	
Molybdenum	0.012	mg/L	0.010	0.00062	1	08/07/24 11:55	08/07/24 17:23	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/07/24 11:55	08/07/24 17:23	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/07/24 11:55	08/07/24 17:23	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/14/24 10:30	08/14/24 15:06	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	443	mg/L	25.0	25.0	1		08/05/24 16:29		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	76.4	mg/L	5.0	5.0	1		08/06/24 13:38		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/06/24 13:38		
Alkalinity, Total as CaCO3	76.4	mg/L	5.0	5.0	1		08/06/24 13:38		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/03/24 03:17	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	14.0	mg/L	1.0	0.60	1		08/03/24 13:18	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Sample: HAM-PT-08		Lab ID: 92745452002		Collected: 08/01/24 14:55		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.16	mg/L	0.10	0.050	1		08/03/24 13:18	16984-48-8	
Sulfate	176	mg/L	4.0	2.0	4		08/04/24 00:31	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Sample: HAM-PT-09		Lab ID: 92745452003		Collected: 07/31/24 13:33		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.13	mg/L	0.040	0.025	1	08/07/24 11:36	08/07/24 17:30	7439-89-6	
Manganese	0.47	mg/L	0.040	0.011	1	08/07/24 11:36	08/07/24 17:30	7439-96-5	
Potassium	6.1	mg/L	0.50	0.15	1	08/07/24 11:36	08/07/24 17:30	7440-09-7	
Sodium	6.6	mg/L	1.0	0.58	1	08/07/24 11:36	08/07/24 17:30	7440-23-5	
Calcium	96.9	mg/L	1.0	0.12	1	08/07/24 11:36	08/07/24 17:30	7440-70-2	
Magnesium	24.5	mg/L	0.050	0.012	1	08/07/24 11:36	08/07/24 17:30	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	0.0010J	mg/L	0.0030	0.00054	1	08/07/24 11:55	08/07/24 17:38	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	08/07/24 11:55	08/08/24 11:09	7440-38-2	
Barium	0.072	mg/L	0.0050	0.00047	1	08/07/24 11:55	08/07/24 17:38	7440-39-3	
Beryllium	0.00013J	mg/L	0.00050	0.000094	1	08/07/24 11:55	08/07/24 17:38	7440-41-7	
Boron	1.1	mg/L	0.040	0.012	1	08/07/24 11:55	08/08/24 11:09	7440-42-8	
Cadmium	0.00028J	mg/L	0.00050	0.00010	1	08/07/24 11:55	08/07/24 17:38	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/07/24 11:55	08/07/24 17:38	7440-47-3	
Cobalt	0.0037J	mg/L	0.0050	0.00032	1	08/07/24 11:55	08/07/24 17:38	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/07/24 11:55	08/07/24 17:38	7439-92-1	
Lithium	0.0019J	mg/L	0.030	0.0016	1	08/07/24 11:55	08/07/24 17:38	7439-93-2	
Molybdenum	0.24	mg/L	0.010	0.00062	1	08/07/24 11:55	08/07/24 17:38	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/07/24 11:55	08/07/24 17:38	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/07/24 11:55	08/07/24 17:38	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/14/24 10:30	08/14/24 15:09	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	500	mg/L	25.0	25.0	1		08/05/24 12:42		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	119	mg/L	5.0	5.0	1		08/06/24 13:59		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/06/24 13:59		
Alkalinity, Total as CaCO3	119	mg/L	5.0	5.0	1		08/06/24 13:59		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/03/24 03:11	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	29.3	mg/L	1.0	0.60	1		08/03/24 13:32	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)
Pace Project No.: 92745452

Sample: HAM-PT-09		Lab ID: 92745452003		Collected: 07/31/24 13:33		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.33	mg/L	0.10	0.050	1		08/03/24 13:32	16984-48-8	
Sulfate	172	mg/L	4.0	2.0	4		08/04/24 00:45	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Sample: HAM-PT-10		Lab ID: 92745452004		Collected: 07/31/24 10:07		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	08/07/24 11:36	08/07/24 17:34	7439-89-6	
Manganese	0.48	mg/L	0.040	0.011	1	08/07/24 11:36	08/07/24 17:34	7439-96-5	
Potassium	6.7	mg/L	0.50	0.15	1	08/07/24 11:36	08/07/24 17:34	7440-09-7	
Sodium	8.8	mg/L	1.0	0.58	1	08/07/24 11:36	08/07/24 17:34	7440-23-5	
Calcium	102	mg/L	1.0	0.12	1	08/07/24 11:36	08/07/24 17:34	7440-70-2	
Magnesium	13.7	mg/L	0.050	0.012	1	08/07/24 11:36	08/07/24 17:34	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/07/24 11:55	08/07/24 17:42	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	08/07/24 11:55	08/08/24 11:13	7440-38-2	
Barium	0.046	mg/L	0.0050	0.00047	1	08/07/24 11:55	08/07/24 17:42	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/07/24 11:55	08/07/24 17:42	7440-41-7	
Boron	1.6	mg/L	0.040	0.012	1	08/07/24 11:55	08/08/24 11:13	7440-42-8	
Cadmium	0.00012J	mg/L	0.00050	0.00010	1	08/07/24 11:55	08/07/24 17:42	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/07/24 11:55	08/07/24 17:42	7440-47-3	
Cobalt	0.0015J	mg/L	0.0050	0.00032	1	08/07/24 11:55	08/07/24 17:42	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/07/24 11:55	08/07/24 17:42	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	08/07/24 11:55	08/07/24 17:42	7439-93-2	
Molybdenum	0.15	mg/L	0.010	0.00062	1	08/07/24 11:55	08/07/24 17:42	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/07/24 11:55	08/07/24 17:42	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/07/24 11:55	08/07/24 17:42	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/14/24 10:30	08/14/24 15:11	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	535	mg/L	25.0	25.0	1		08/05/24 12:42		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	133	mg/L	5.0	5.0	1		08/06/24 14:17		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/06/24 14:17		
Alkalinity, Total as CaCO3	133	mg/L	5.0	5.0	1		08/06/24 14:17		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/03/24 03:12	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	46.4	mg/L	1.0	0.60	1		08/03/24 13:45	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Sample: HAM-PT-10		Lab ID: 92745452004		Collected: 07/31/24 10:07		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.22	mg/L	0.10	0.050	1		08/03/24 13:45	16984-48-8	
Sulfate	117	mg/L	3.0	1.5	3		08/04/24 00:59	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Sample: HAM-PT-11 Lab ID: 92745452005 Collected: 07/31/24 16:46 Received: 08/02/24 14:00 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.66	mg/L	0.040	0.025	1	08/07/24 11:36	08/07/24 17:38	7439-89-6	
Manganese	1.3	mg/L	0.040	0.011	1	08/07/24 11:36	08/07/24 17:38	7439-96-5	
Potassium	5.6	mg/L	0.50	0.15	1	08/07/24 11:36	08/07/24 17:38	7440-09-7	
Sodium	7.5	mg/L	1.0	0.58	1	08/07/24 11:36	08/07/24 17:38	7440-23-5	
Calcium	90.6	mg/L	1.0	0.12	1	08/07/24 11:36	08/07/24 17:38	7440-70-2	
Magnesium	19.0	mg/L	0.050	0.012	1	08/07/24 11:36	08/07/24 17:38	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	0.00086J	mg/L	0.0030	0.00054	1	08/07/24 11:55	08/07/24 17:45	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	08/07/24 11:55	08/08/24 11:17	7440-38-2	
Barium	0.068	mg/L	0.0050	0.00047	1	08/07/24 11:55	08/07/24 17:45	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/07/24 11:55	08/07/24 17:45	7440-41-7	
Boron	1.4	mg/L	0.040	0.012	1	08/07/24 11:55	08/08/24 11:17	7440-42-8	
Cadmium	0.00027J	mg/L	0.00050	0.00010	1	08/07/24 11:55	08/07/24 17:45	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/07/24 11:55	08/07/24 17:45	7440-47-3	
Cobalt	0.019	mg/L	0.0050	0.00032	1	08/07/24 11:55	08/07/24 17:45	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/07/24 11:55	08/07/24 17:45	7439-92-1	
Lithium	0.0060J	mg/L	0.030	0.0016	1	08/07/24 11:55	08/07/24 17:45	7439-93-2	
Molybdenum	0.074	mg/L	0.010	0.00062	1	08/07/24 11:55	08/07/24 17:45	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/07/24 11:55	08/07/24 17:45	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/07/24 11:55	08/07/24 17:45	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/14/24 10:30	08/14/24 15:14	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	464	mg/L	25.0	25.0	1		08/05/24 12:42		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	112	mg/L	5.0	5.0	1		08/06/24 14:27		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/06/24 14:27		
Alkalinity, Total as CaCO3	112	mg/L	5.0	5.0	1		08/06/24 14:27		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/03/24 03:13	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	33.6	mg/L	1.0	0.60	1		08/03/24 13:58	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)
Pace Project No.: 92745452

Sample: HAM-PT-11		Lab ID: 92745452005		Collected: 07/31/24 16:46		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.26	mg/L	0.10	0.050	1		08/03/24 13:58	16984-48-8	
Sulfate	141	mg/L	3.0	1.5	3		08/04/24 01:14	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Sample: HAM-PT-12 Lab ID: 92745452006 Collected: 07/31/24 18:05 Received: 08/02/24 14:00 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.16	mg/L	0.040	0.025	1	08/07/24 11:36	08/07/24 17:42	7439-89-6	
Manganese	0.77	mg/L	0.040	0.011	1	08/07/24 11:36	08/07/24 17:42	7439-96-5	
Potassium	6.0	mg/L	0.50	0.15	1	08/07/24 11:36	08/07/24 17:42	7440-09-7	
Sodium	7.9	mg/L	1.0	0.58	1	08/07/24 11:36	08/07/24 17:42	7440-23-5	
Calcium	94.9	mg/L	1.0	0.12	1	08/07/24 11:36	08/07/24 17:42	7440-70-2	
Magnesium	21.8	mg/L	0.050	0.012	1	08/07/24 11:36	08/07/24 17:42	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/07/24 11:55	08/07/24 18:13	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	08/07/24 11:55	08/08/24 11:21	7440-38-2	
Barium	0.064	mg/L	0.0050	0.00047	1	08/07/24 11:55	08/07/24 18:13	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/07/24 11:55	08/07/24 18:13	7440-41-7	
Boron	1.3	mg/L	0.040	0.012	1	08/07/24 11:55	08/08/24 11:21	7440-42-8	
Cadmium	0.00022J	mg/L	0.00050	0.00010	1	08/07/24 11:55	08/07/24 18:13	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/07/24 11:55	08/07/24 18:13	7440-47-3	
Cobalt	0.0032J	mg/L	0.0050	0.00032	1	08/07/24 11:55	08/07/24 18:13	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/07/24 11:55	08/07/24 18:13	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	08/07/24 11:55	08/07/24 18:13	7439-93-2	
Molybdenum	0.16	mg/L	0.010	0.00062	1	08/07/24 11:55	08/07/24 18:13	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/07/24 11:55	08/07/24 18:13	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/07/24 11:55	08/07/24 18:13	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/14/24 10:30	08/14/24 15:17	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	470	mg/L	25.0	25.0	1		08/05/24 12:42		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	124	mg/L	5.0	5.0	1		08/06/24 14:36		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/06/24 14:36		
Alkalinity, Total as CaCO3	124	mg/L	5.0	5.0	1		08/06/24 14:36		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/03/24 03:13	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	30.2	mg/L	1.0	0.60	1		08/03/24 14:12	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Sample: HAM-PT-12		Lab ID: 92745452006		Collected: 07/31/24 18:05		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.26	mg/L	0.10	0.050	1		08/03/24 14:12	16984-48-8	
Sulfate	157	mg/L	4.0	2.0	4		08/04/24 01:28	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Sample: HAM-PT-13		Lab ID: 92745452007		Collected: 08/01/24 12:47		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	25.6	mg/L	0.040	0.025	1	08/07/24 11:36	08/07/24 17:46	7439-89-6	
Manganese	4.3	mg/L	0.040	0.011	1	08/07/24 11:36	08/07/24 17:46	7439-96-5	
Potassium	5.3	mg/L	0.50	0.15	1	08/07/24 11:36	08/07/24 17:46	7440-09-7	
Sodium	8.2	mg/L	1.0	0.58	1	08/07/24 11:36	08/07/24 17:46	7440-23-5	
Calcium	111	mg/L	1.0	0.12	1	08/07/24 11:36	08/07/24 17:46	7440-70-2	
Magnesium	15.5	mg/L	0.050	0.012	1	08/07/24 11:36	08/07/24 17:46	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/07/24 11:55	08/07/24 18:16	7440-36-0	
Arsenic	0.20	mg/L	0.025	0.0042	5	08/07/24 11:55	08/08/24 10:44	7440-38-2	
Barium	0.043	mg/L	0.0050	0.00047	1	08/07/24 11:55	08/07/24 18:16	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/07/24 11:55	08/07/24 18:16	7440-41-7	
Boron	0.51	mg/L	0.20	0.060	5	08/07/24 11:55	08/08/24 10:44	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	08/07/24 11:55	08/07/24 18:16	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/07/24 11:55	08/07/24 18:16	7440-47-3	
Cobalt	0.040	mg/L	0.0050	0.00032	1	08/07/24 11:55	08/07/24 18:16	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/07/24 11:55	08/07/24 18:16	7439-92-1	
Lithium	0.058	mg/L	0.030	0.0016	1	08/07/24 11:55	08/07/24 18:16	7439-93-2	
Molybdenum	0.0052	mg/L	0.010	0.00062	1	08/07/24 11:55	08/07/24 18:16	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/07/24 11:55	08/07/24 18:16	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/07/24 11:55	08/07/24 18:16	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/14/24 10:30	08/14/24 15:19	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	549	mg/L	25.0	25.0	1		08/05/24 16:29		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	115	mg/L	5.0	5.0	1		08/06/24 14:45		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/06/24 14:45		
Alkalinity, Total as CaCO3	115	mg/L	5.0	5.0	1		08/06/24 14:45		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/03/24 03:18	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	15.5	mg/L	1.0	0.60	1		08/03/24 14:25	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)
Pace Project No.: 92745452

Sample: HAM-PT-13		Lab ID: 92745452007		Collected: 08/01/24 12:47		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.26	mg/L	0.10	0.050	1		08/03/24 14:25	16984-48-8	
Sulfate	229	mg/L	5.0	2.5	5		08/04/24 02:09	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Sample: HAM-PT-14		Lab ID: 92745452008		Collected: 08/01/24 16:45		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	17.5	mg/L	0.040	0.025	1	08/07/24 11:36	08/07/24 17:50	7439-89-6	
Manganese	3.4	mg/L	0.040	0.011	1	08/07/24 11:36	08/07/24 17:50	7439-96-5	
Potassium	5.9	mg/L	0.50	0.15	1	08/07/24 11:36	08/07/24 17:50	7440-09-7	
Sodium	8.8	mg/L	1.0	0.58	1	08/07/24 11:36	08/07/24 17:50	7440-23-5	
Calcium	123	mg/L	1.0	0.12	1	08/07/24 11:36	08/07/24 17:50	7440-70-2	
Magnesium	18.7	mg/L	0.050	0.012	1	08/07/24 11:36	08/07/24 17:50	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/07/24 11:55	08/07/24 18:20	7440-36-0	
Arsenic	0.15	mg/L	0.025	0.0042	5	08/07/24 11:55	08/08/24 10:48	7440-38-2	
Barium	0.045	mg/L	0.0050	0.00047	1	08/07/24 11:55	08/07/24 18:20	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/07/24 11:55	08/07/24 18:20	7440-41-7	
Boron	0.55	mg/L	0.20	0.060	5	08/07/24 11:55	08/08/24 10:48	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	08/07/24 11:55	08/07/24 18:20	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/07/24 11:55	08/07/24 18:20	7440-47-3	
Cobalt	0.025	mg/L	0.0050	0.00032	1	08/07/24 11:55	08/07/24 18:20	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/07/24 11:55	08/07/24 18:20	7439-92-1	
Lithium	0.049	mg/L	0.030	0.0016	1	08/07/24 11:55	08/07/24 18:20	7439-93-2	
Molybdenum	0.011	mg/L	0.010	0.00062	1	08/07/24 11:55	08/07/24 18:20	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/07/24 11:55	08/07/24 18:20	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/07/24 11:55	08/07/24 18:20	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/14/24 10:30	08/14/24 15:22	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	599	mg/L	25.0	25.0	1		08/05/24 16:29		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	153	mg/L	5.0	5.0	1		08/06/24 14:55		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/06/24 14:55		
Alkalinity, Total as CaCO3	153	mg/L	5.0	5.0	1		08/06/24 14:55		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/03/24 03:18	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	17.8	mg/L	1.0	0.60	1		08/03/24 14:39	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)
Pace Project No.: 92745452

Sample: HAM-PT-14		Lab ID: 92745452008		Collected: 08/01/24 16:45		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.22	mg/L	0.10	0.050	1		08/03/24 14:39	16984-48-8	
Sulfate	224	mg/L	5.0	2.5	5		08/04/24 02:23	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Sample: HAM-PT-15		Lab ID: 92745452009		Collected: 08/01/24 10:47		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	13.4	mg/L	0.040	0.025	1	08/07/24 11:36	08/07/24 17:53	7439-89-6	
Manganese	5.4	mg/L	0.040	0.011	1	08/07/24 11:36	08/07/24 17:53	7439-96-5	
Potassium	5.4	mg/L	0.50	0.15	1	08/07/24 11:36	08/07/24 17:53	7440-09-7	
Sodium	7.7	mg/L	1.0	0.58	1	08/07/24 11:36	08/07/24 17:53	7440-23-5	
Calcium	117	mg/L	1.0	0.12	1	08/07/24 11:36	08/07/24 17:53	7440-70-2	
Magnesium	14.5	mg/L	0.050	0.012	1	08/07/24 11:36	08/07/24 17:53	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/07/24 11:55	08/07/24 18:24	7440-36-0	
Arsenic	0.42	mg/L	0.025	0.0042	5	08/07/24 11:55	08/08/24 10:53	7440-38-2	
Barium	0.042	mg/L	0.0050	0.00047	1	08/07/24 11:55	08/07/24 18:24	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/07/24 11:55	08/07/24 18:24	7440-41-7	
Boron	0.63	mg/L	0.20	0.060	5	08/07/24 11:55	08/08/24 10:53	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	08/07/24 11:55	08/07/24 18:24	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/07/24 11:55	08/07/24 18:24	7440-47-3	
Cobalt	0.056	mg/L	0.0050	0.00032	1	08/07/24 11:55	08/07/24 18:24	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/07/24 11:55	08/07/24 18:24	7439-92-1	
Lithium	0.050	mg/L	0.030	0.0016	1	08/07/24 11:55	08/07/24 18:24	7439-93-2	
Molybdenum	0.013	mg/L	0.010	0.00062	1	08/07/24 11:55	08/07/24 18:24	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/07/24 11:55	08/07/24 18:24	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/07/24 11:55	08/07/24 18:24	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/14/24 10:30	08/14/24 15:25	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	544	mg/L	25.0	25.0	1		08/05/24 16:29		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	129	mg/L	5.0	5.0	1		08/06/24 15:06		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/06/24 15:06		
Alkalinity, Total as CaCO3	129	mg/L	5.0	5.0	1		08/06/24 15:06		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/03/24 03:19	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	14.4	mg/L	1.0	0.60	1		08/03/24 15:19	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Sample: HAM-PT-15		Lab ID: 92745452009		Collected: 08/01/24 10:47		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.29	mg/L	0.10	0.050	1		08/03/24 15:19	16984-48-8	
Sulfate	206	mg/L	5.0	2.5	5		08/04/24 02:36	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Sample: HAM-AP1-FD-01 Lab ID: 92745452010 Collected: 07/31/24 00:00 Received: 08/02/24 14:00 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.20	mg/L	0.040	0.025	1	08/07/24 11:36	08/07/24 18:56	7439-89-6	
Manganese	0.81	mg/L	0.040	0.011	1	08/07/24 11:36	08/07/24 18:56	7439-96-5	
Potassium	6.0	mg/L	0.50	0.15	1	08/07/24 11:36	08/07/24 18:56	7440-09-7	
Sodium	8.1	mg/L	1.0	0.58	1	08/07/24 11:36	08/07/24 18:56	7440-23-5	
Calcium	94.9	mg/L	1.0	0.12	1	08/07/24 11:36	08/07/24 18:56	7440-70-2	
Magnesium	21.9	mg/L	0.050	0.012	1	08/07/24 11:36	08/07/24 18:56	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/07/24 11:55	08/07/24 18:31	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	08/07/24 11:55	08/08/24 11:25	7440-38-2	
Barium	0.064	mg/L	0.0050	0.00047	1	08/07/24 11:55	08/07/24 18:31	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/07/24 11:55	08/07/24 18:31	7440-41-7	
Boron	1.2	mg/L	0.040	0.012	1	08/07/24 11:55	08/08/24 11:25	7440-42-8	
Cadmium	0.00023J	mg/L	0.00050	0.00010	1	08/07/24 11:55	08/07/24 18:31	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/07/24 11:55	08/07/24 18:31	7440-47-3	
Cobalt	0.0032J	mg/L	0.0050	0.00032	1	08/07/24 11:55	08/07/24 18:31	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/07/24 11:55	08/07/24 18:31	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	08/07/24 11:55	08/07/24 18:31	7439-93-2	
Molybdenum	0.15	mg/L	0.010	0.00062	1	08/07/24 11:55	08/07/24 18:31	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/07/24 11:55	08/07/24 18:31	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/07/24 11:55	08/07/24 18:31	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/14/24 10:30	08/14/24 15:32	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	462	mg/L	25.0	25.0	1		08/05/24 12:45		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	124	mg/L	5.0	5.0	1		08/06/24 15:16		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/06/24 15:16		
Alkalinity, Total as CaCO3	124	mg/L	5.0	5.0	1		08/06/24 15:16		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/03/24 03:15	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	30.6	mg/L	1.0	0.60	1		08/03/24 15:33	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)
Pace Project No.: 92745452

Sample: HAM-AP1-FD-01		Lab ID: 92745452010		Collected: 07/31/24 00:00		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.26	mg/L	0.10	0.050	1		08/03/24 15:33	16984-48-8	
Sulfate	155	mg/L	4.0	2.0	4		08/04/24 02:50	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Sample: HAM-AP1-FB-01		Lab ID: 92745452011		Collected: 08/01/24 12:00		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	08/07/24 11:36	08/07/24 19:00	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	08/07/24 11:36	08/07/24 19:00	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	08/07/24 11:36	08/07/24 19:00	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	08/07/24 11:36	08/07/24 19:00	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	08/07/24 11:36	08/07/24 19:00	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	08/07/24 11:36	08/07/24 19:00	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/07/24 11:55	08/07/24 18:35	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	08/07/24 11:55	08/08/24 10:09	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	08/07/24 11:55	08/07/24 18:35	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/07/24 11:55	08/07/24 18:35	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	08/07/24 11:55	08/08/24 10:09	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	08/07/24 11:55	08/07/24 18:35	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/07/24 11:55	08/07/24 18:35	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	08/07/24 11:55	08/07/24 18:35	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/07/24 11:55	08/07/24 18:35	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	08/07/24 11:55	08/07/24 18:35	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	08/07/24 11:55	08/07/24 18:35	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/07/24 11:55	08/07/24 18:35	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/07/24 11:55	08/07/24 18:35	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/14/24 10:30	08/14/24 15:35	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		08/05/24 16:29		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/06/24 15:25		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/06/24 15:25		
Alkalinity, Total as CaCO3	ND	mg/L	5.0	5.0	1		08/06/24 15:25		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/03/24 03:19	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		08/03/24 10:23	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)
Pace Project No.: 92745452

Sample: HAM-AP1-FB-01		Lab ID: 92745452011		Collected: 08/01/24 12:00		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		08/03/24 10:23	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		08/03/24 10:23	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Sample: HAM-AP1-EB-01		Lab ID: 92745452012		Collected: 08/01/24 12:00		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	08/07/24 11:36	08/07/24 19:04	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	08/07/24 11:36	08/07/24 19:04	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	08/07/24 11:36	08/07/24 19:04	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	08/07/24 11:36	08/07/24 19:04	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	08/07/24 11:36	08/07/24 19:04	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	08/07/24 11:36	08/07/24 19:04	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/07/24 11:55	08/07/24 18:38	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	08/07/24 11:55	08/08/24 10:13	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	08/07/24 11:55	08/07/24 18:38	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/07/24 11:55	08/07/24 18:38	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	08/07/24 11:55	08/08/24 10:13	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	08/07/24 11:55	08/07/24 18:38	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/07/24 11:55	08/07/24 18:38	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	08/07/24 11:55	08/07/24 18:38	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/07/24 11:55	08/07/24 18:38	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	08/07/24 11:55	08/07/24 18:38	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	08/07/24 11:55	08/07/24 18:38	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/07/24 11:55	08/07/24 18:38	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/07/24 11:55	08/07/24 18:38	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/14/24 10:30	08/14/24 15:38	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		08/05/24 16:30		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/06/24 15:29		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/06/24 15:29		
Alkalinity, Total as CaCO3	ND	mg/L	5.0	5.0	1		08/06/24 15:29		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/03/24 03:20	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		08/03/24 11:04	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)
Pace Project No.: 92745452

Sample: HAM-AP1-EB-01		Lab ID: 92745452012		Collected: 08/01/24 12:00		Received: 08/02/24 14:00		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		08/03/24 11:04	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		08/03/24 11:04	14808-79-8	

REPORT OF LABORATORY ANALYSIS



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

QC Batch:	873657	Analysis Method:	EPA 6010D
QC Batch Method:	EPA 3010A	Analysis Description:	6010D ATL
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92745452001, 92745452002, 92745452003, 92745452004, 92745452005, 92745452006, 92745452007, 92745452008, 92745452009, 92745452010, 92745452011, 92745452012		

METHOD BLANK:	4500486	Matrix:	Water
Associated Lab Samples:	92745452001, 92745452002, 92745452003, 92745452004, 92745452005, 92745452006, 92745452007, 92745452008, 92745452009, 92745452010, 92745452011, 92745452012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	08/07/24 17:00	
Iron	mg/L	ND	0.040	0.025	08/07/24 17:00	
Magnesium	mg/L	ND	0.050	0.012	08/07/24 17:00	
Manganese	mg/L	ND	0.040	0.011	08/07/24 17:00	
Potassium	mg/L	ND	0.50	0.15	08/07/24 17:00	
Sodium	mg/L	ND	1.0	0.58	08/07/24 17:00	

LABORATORY CONTROL SAMPLE: 4500487

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	1.0	103	80-120	
Iron	mg/L	1	1.0	104	80-120	
Magnesium	mg/L	1	1.0	103	80-120	
Manganese	mg/L	1	1.1	105	80-120	
Potassium	mg/L	1	1.0	101	80-120	
Sodium	mg/L	1	1.1	109	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4500488 4500489

Parameter	Units	92745452001	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		Result										
Calcium	mg/L	123	1	1	122	122	-90	-79	75-125	0	20	M1
Iron	mg/L	13.2	1	1	13.9	14.0	73	86	75-125	1	20	M1
Magnesium	mg/L	17.8	1	1	18.6	18.6	74	78	75-125	0	20	M1
Manganese	mg/L	4.2	1	1	5.1	5.1	91	96	75-125	1	20	
Potassium	mg/L	5.7	1	1	6.5	6.5	76	81	75-125	1	20	
Sodium	mg/L	8.6	1	1	9.4	9.4	79	83	75-125	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

QC Batch:	873910	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92745452001, 92745452002, 92745452003, 92745452004, 92745452005, 92745452006, 92745452007, 92745452008, 92745452009, 92745452010, 92745452011, 92745452012		

METHOD BLANK: 4501702

Matrix: Water

Associated Lab Samples: 92745452001, 92745452002, 92745452003, 92745452004, 92745452005, 92745452006, 92745452007, 92745452008, 92745452009, 92745452010, 92745452011, 92745452012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00054	08/07/24 17:12	
Arsenic	mg/L	ND	0.0050	0.00084	08/08/24 10:01	
Barium	mg/L	ND	0.0050	0.00047	08/07/24 17:12	
Beryllium	mg/L	ND	0.00050	0.000094	08/07/24 17:12	
Boron	mg/L	ND	0.040	0.012	08/08/24 10:01	
Cadmium	mg/L	ND	0.00050	0.00010	08/07/24 17:12	
Chromium	mg/L	ND	0.0050	0.0019	08/07/24 17:12	
Cobalt	mg/L	ND	0.0050	0.00032	08/07/24 17:12	
Lead	mg/L	ND	0.0010	0.00016	08/07/24 17:12	
Lithium	mg/L	ND	0.030	0.0016	08/07/24 17:12	
Molybdenum	mg/L	ND	0.010	0.00062	08/07/24 17:12	
Selenium	mg/L	ND	0.0050	0.00096	08/07/24 17:12	
Thallium	mg/L	ND	0.0010	0.00038	08/07/24 17:12	

LABORATORY CONTROL SAMPLE: 4501703

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.10	103	80-120	
Arsenic	mg/L	0.1	0.10	102	80-120	
Barium	mg/L	0.1	0.098	98	80-120	
Beryllium	mg/L	0.1	0.10	101	80-120	
Boron	mg/L	1	1.0	101	80-120	
Cadmium	mg/L	0.1	0.098	98	80-120	
Chromium	mg/L	0.1	0.10	100	80-120	
Cobalt	mg/L	0.1	0.097	97	80-120	
Lead	mg/L	0.1	0.10	101	80-120	
Lithium	mg/L	0.1	0.10	103	80-120	
Molybdenum	mg/L	0.1	0.10	105	80-120	
Selenium	mg/L	0.1	0.10	102	80-120	
Thallium	mg/L	0.1	0.10	100	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4501704 4501705

Parameter	Units	92745452002		MS		MSD		MS	MSD	% Rec	% Rec	% Rec	Limits	RPD	Max RPD	Qual
		Result	Conc.	Spike Conc.	Conc.	Result	Conc.	Result	Conc.							
Antimony	mg/L	ND	0.1	0.1	0.1	0.10	0.10	101	100	75-125	1	20				

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4501704 4501705											
Parameter	Units	92745452002		MS		MSD		MS		MSD	
		Result	Conc.	Spike	Conc.	Result	Conc.	% Rec	% Rec	Limits	Max
Arsenic	mg/L	0.26	0.1	0.1	0.1	0.35	0.35	97	93	75-125	1 20
Barium	mg/L	0.044	0.1	0.1	0.1	0.14	0.14	101	100	75-125	1 20
Beryllium	mg/L	0.000098J	0.1	0.1	0.1	0.092	0.089	92	89	75-125	3 20
Boron	mg/L	0.63	1	1	1	1.6	1.6	97	93	75-125	3 20
Cadmium	mg/L	ND	0.1	0.1	0.1	0.098	0.098	98	98	75-125	0 20
Chromium	mg/L	ND	0.1	0.1	0.1	0.094	0.091	94	91	75-125	3 20
Cobalt	mg/L	0.073	0.1	0.1	0.1	0.17	0.16	92	90	75-125	1 20
Lead	mg/L	ND	0.1	0.1	0.1	0.095	0.096	95	96	75-125	1 20
Lithium	mg/L	0.022J	0.1	0.1	0.1	0.11	0.11	93	93	75-125	0 20
Molybdenum	mg/L	0.012	0.1	0.1	0.1	0.11	0.11	100	97	75-125	3 20
Selenium	mg/L	ND	0.1	0.1	0.1	0.10	0.10	101	99	75-125	1 20
Thallium	mg/L	ND	0.1	0.1	0.1	0.095	0.097	95	97	75-125	2 20

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

QC Batch:	875505	Analysis Method:	EPA 7470A
QC Batch Method:	EPA 7470A	Analysis Description:	7470 Mercury
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92745452001, 92745452002, 92745452003, 92745452004, 92745452005, 92745452006, 92745452007, 92745452008, 92745452009, 92745452010, 92745452011, 92745452012		

METHOD BLANK:	4509737	Matrix:	Water
Associated Lab Samples:	92745452001, 92745452002, 92745452003, 92745452004, 92745452005, 92745452006, 92745452007, 92745452008, 92745452009, 92745452010, 92745452011, 92745452012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	08/14/24 14:45	

LABORATORY CONTROL SAMPLE: 4509738						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0025	100	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:			4509739		4509740							
Parameter	Units	92745452001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.0025	0.0025	0.0025	0.0025	100	100	75-125	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

QC Batch:	873350	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92745452003, 92745452004, 92745452005, 92745452006, 92745452010

METHOD BLANK: 4498843 Matrix: Water

Associated Lab Samples: 92745452003, 92745452004, 92745452005, 92745452006, 92745452010

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	08/05/24 12:39	

LABORATORY CONTROL SAMPLE: 4498844

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	479	120	80-120	

SAMPLE DUPLICATE: 4498845

Parameter	Units	92745459001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	239	232	3	10	

SAMPLE DUPLICATE: 4498846

Parameter	Units	92745452006 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	470	489	4	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

QC Batch:	873411	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92745452001, 92745452002, 92745452007, 92745452008, 92745452009, 92745452011, 92745452012

METHOD BLANK: 4499128 Matrix: Water

Associated Lab Samples: 92745452001, 92745452002, 92745452007, 92745452008, 92745452009, 92745452011, 92745452012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	08/05/24 16:11	

LABORATORY CONTROL SAMPLE: 4499129

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	407	102	80-120	

SAMPLE DUPLICATE: 4499130

Parameter	Units	92745459017 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	166	166	0	10	

SAMPLE DUPLICATE: 4499131

Parameter	Units	92745452011 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	ND	ND		10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

QC Batch:	873172	Analysis Method:	SM 2320B-2011
QC Batch Method:	SM 2320B-2011	Analysis Description:	2320B Alkalinity
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92745452001, 92745452002, 92745452003, 92745452004, 92745452005, 92745452006, 92745452007, 92745452008, 92745452009, 92745452010, 92745452011, 92745452012		

METHOD BLANK:	4498414	Matrix:	Water
Associated Lab Samples:	92745452001, 92745452002, 92745452003, 92745452004, 92745452005, 92745452006, 92745452007, 92745452008, 92745452009, 92745452010, 92745452011, 92745452012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	08/06/24 12:56	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	08/06/24 12:56	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	08/06/24 12:56	

LABORATORY CONTROL SAMPLE:	4498415					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.8	106	80-120	

LABORATORY CONTROL SAMPLE:	4498416					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.1	104	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:	4498417			4498418								
Parameter	Units	92745452001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	119	50	50	165	168	93	98	80-120	1	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:	4498419			4498420								
Parameter	Units	92745452002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	76.4	50	50	127	126	101	100	80-120	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

QC Batch:	873142	Analysis Method:	SM 4500-S2D-2011
QC Batch Method:	SM 4500-S2D-2011	Analysis Description:	4500S2D Sulfide Water
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92745452001, 92745452002, 92745452003, 92745452004, 92745452005, 92745452006, 92745452007, 92745452008, 92745452009, 92745452010, 92745452011, 92745452012		

METHOD BLANK:	4498333	Matrix:	Water
Associated Lab Samples:	92745452001, 92745452002, 92745452003, 92745452004, 92745452005, 92745452006, 92745452007, 92745452008, 92745452009, 92745452010, 92745452011, 92745452012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	08/03/24 03:06	

LABORATORY CONTROL SAMPLE: 4498334						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.53	107	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:					4498335	4498336							
Parameter	Units	92745068001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual	
Sulfide	mg/L	ND	0.5	0.5	0.48	0.50	94	98	80-120	4	10		

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:													4498337	4498338			
Parameter	Units	92745452006 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual					
Sulfide	mg/L	ND	0.5	0.5	0.49	0.51	98	102	80-120	4	10						

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

QC Batch:	873156	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92745452001, 92745452002, 92745452003, 92745452004, 92745452005, 92745452006, 92745452007, 92745452008, 92745452009, 92745452010, 92745452011, 92745452012		

METHOD BLANK:	4498354	Matrix:	Water
Associated Lab Samples:	92745452001, 92745452002, 92745452003, 92745452004, 92745452005, 92745452006, 92745452007, 92745452008, 92745452009, 92745452010, 92745452011, 92745452012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	08/03/24 09:56	
Fluoride	mg/L	ND	0.10	0.050	08/03/24 09:56	
Sulfate	mg/L	ND	1.0	0.50	08/03/24 09:56	

LABORATORY CONTROL SAMPLE: 4498355						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	49.4	99	90-110	
Fluoride	mg/L	2.5	2.5	101	90-110	
Sulfate	mg/L	50	48.8	98	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4498356 4498357												
Parameter	Units	92745452001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	16.7	50	50	65.1	65.7	97	98	90-110	1	10	
Fluoride	mg/L	0.22	2.5	2.5	2.6	2.6	95	96	90-110	1	10	
Sulfate	mg/L	223	50	50	265	266	83	84	90-110	0	10 M1	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4498358 4498359												
Parameter	Units	92745452011 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	ND	50	50	48.6	48.3	97	96	90-110	1	10	
Fluoride	mg/L	ND	2.5	2.5	2.4	2.4	96	95	90-110	2	10	
Sulfate	mg/L	ND	50	50	47.9	47.6	96	95	90-110	1	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1 (CA)
Pace Project No.: 92745452

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92745452001	HAM-PT-07	EPA 3010A	873657	EPA 6010D	873965
92745452002	HAM-PT-08	EPA 3010A	873657	EPA 6010D	873965
92745452003	HAM-PT-09	EPA 3010A	873657	EPA 6010D	873965
92745452004	HAM-PT-10	EPA 3010A	873657	EPA 6010D	873965
92745452005	HAM-PT-11	EPA 3010A	873657	EPA 6010D	873965
92745452006	HAM-PT-12	EPA 3010A	873657	EPA 6010D	873965
92745452007	HAM-PT-13	EPA 3010A	873657	EPA 6010D	873965
92745452008	HAM-PT-14	EPA 3010A	873657	EPA 6010D	873965
92745452009	HAM-PT-15	EPA 3010A	873657	EPA 6010D	873965
92745452010	HAM-AP1-FD-01	EPA 3010A	873657	EPA 6010D	873965
92745452011	HAM-AP1-FB-01	EPA 3010A	873657	EPA 6010D	873965
92745452012	HAM-AP1-EB-01	EPA 3010A	873657	EPA 6010D	873965
92745452001	HAM-PT-07	EPA 3005A	873910	EPA 6020B	874022
92745452002	HAM-PT-08	EPA 3005A	873910	EPA 6020B	874022
92745452003	HAM-PT-09	EPA 3005A	873910	EPA 6020B	874022
92745452004	HAM-PT-10	EPA 3005A	873910	EPA 6020B	874022
92745452005	HAM-PT-11	EPA 3005A	873910	EPA 6020B	874022
92745452006	HAM-PT-12	EPA 3005A	873910	EPA 6020B	874022
92745452007	HAM-PT-13	EPA 3005A	873910	EPA 6020B	874022
92745452008	HAM-PT-14	EPA 3005A	873910	EPA 6020B	874022
92745452009	HAM-PT-15	EPA 3005A	873910	EPA 6020B	874022
92745452010	HAM-AP1-FD-01	EPA 3005A	873910	EPA 6020B	874022
92745452011	HAM-AP1-FB-01	EPA 3005A	873910	EPA 6020B	874022
92745452012	HAM-AP1-EB-01	EPA 3005A	873910	EPA 6020B	874022
92745452001	HAM-PT-07	EPA 7470A	875505	EPA 7470A	875591
92745452002	HAM-PT-08	EPA 7470A	875505	EPA 7470A	875591
92745452003	HAM-PT-09	EPA 7470A	875505	EPA 7470A	875591
92745452004	HAM-PT-10	EPA 7470A	875505	EPA 7470A	875591
92745452005	HAM-PT-11	EPA 7470A	875505	EPA 7470A	875591
92745452006	HAM-PT-12	EPA 7470A	875505	EPA 7470A	875591
92745452007	HAM-PT-13	EPA 7470A	875505	EPA 7470A	875591
92745452008	HAM-PT-14	EPA 7470A	875505	EPA 7470A	875591
92745452009	HAM-PT-15	EPA 7470A	875505	EPA 7470A	875591
92745452010	HAM-AP1-FD-01	EPA 7470A	875505	EPA 7470A	875591
92745452011	HAM-AP1-FB-01	EPA 7470A	875505	EPA 7470A	875591
92745452012	HAM-AP1-EB-01	EPA 7470A	875505	EPA 7470A	875591
92745452001	HAM-PT-07	SM 2540C-2015	873411		
92745452002	HAM-PT-08	SM 2540C-2015	873411		
92745452003	HAM-PT-09	SM 2540C-2015	873350		
92745452004	HAM-PT-10	SM 2540C-2015	873350		
92745452005	HAM-PT-11	SM 2540C-2015	873350		
92745452006	HAM-PT-12	SM 2540C-2015	873350		
92745452007	HAM-PT-13	SM 2540C-2015	873411		
92745452008	HAM-PT-14	SM 2540C-2015	873411		
92745452009	HAM-PT-15	SM 2540C-2015	873411		
92745452010	HAM-AP1-FD-01	SM 2540C-2015	873350		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1 (CA)

Pace Project No.: 92745452

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92745452011	HAM-AP1-FB-01	SM 2540C-2015	873411		
92745452012	HAM-AP1-EB-01	SM 2540C-2015	873411		
92745452001	HAM-PT-07	SM 2320B-2011	873172		
92745452002	HAM-PT-08	SM 2320B-2011	873172		
92745452003	HAM-PT-09	SM 2320B-2011	873172		
92745452004	HAM-PT-10	SM 2320B-2011	873172		
92745452005	HAM-PT-11	SM 2320B-2011	873172		
92745452006	HAM-PT-12	SM 2320B-2011	873172		
92745452007	HAM-PT-13	SM 2320B-2011	873172		
92745452008	HAM-PT-14	SM 2320B-2011	873172		
92745452009	HAM-PT-15	SM 2320B-2011	873172		
92745452010	HAM-AP1-FD-01	SM 2320B-2011	873172		
92745452011	HAM-AP1-FB-01	SM 2320B-2011	873172		
92745452012	HAM-AP1-EB-01	SM 2320B-2011	873172		
92745452001	HAM-PT-07	SM 4500-S2D-2011	873142		
92745452002	HAM-PT-08	SM 4500-S2D-2011	873142		
92745452003	HAM-PT-09	SM 4500-S2D-2011	873142		
92745452004	HAM-PT-10	SM 4500-S2D-2011	873142		
92745452005	HAM-PT-11	SM 4500-S2D-2011	873142		
92745452006	HAM-PT-12	SM 4500-S2D-2011	873142		
92745452007	HAM-PT-13	SM 4500-S2D-2011	873142		
92745452008	HAM-PT-14	SM 4500-S2D-2011	873142		
92745452009	HAM-PT-15	SM 4500-S2D-2011	873142		
92745452010	HAM-AP1-FD-01	SM 4500-S2D-2011	873142		
92745452011	HAM-AP1-FB-01	SM 4500-S2D-2011	873142		
92745452012	HAM-AP1-EB-01	SM 4500-S2D-2011	873142		
92745452001	HAM-PT-07	EPA 300.0 Rev 2.1 1993	873156		
92745452002	HAM-PT-08	EPA 300.0 Rev 2.1 1993	873156		
92745452003	HAM-PT-09	EPA 300.0 Rev 2.1 1993	873156		
92745452004	HAM-PT-10	EPA 300.0 Rev 2.1 1993	873156		
92745452005	HAM-PT-11	EPA 300.0 Rev 2.1 1993	873156		
92745452006	HAM-PT-12	EPA 300.0 Rev 2.1 1993	873156		
92745452007	HAM-PT-13	EPA 300.0 Rev 2.1 1993	873156		
92745452008	HAM-PT-14	EPA 300.0 Rev 2.1 1993	873156		
92745452009	HAM-PT-15	EPA 300.0 Rev 2.1 1993	873156		
92745452010	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	873156		
92745452011	HAM-AP1-FB-01	EPA 300.0 Rev 2.1 1993	873156		
92745452012	HAM-AP1-EB-01	EPA 300.0 Rev 2.1 1993	873156		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



 **DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt**
Effective Date: 05/24/2024

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐

Sample Condition Upon Receipt

Client Name:

Project #:

WO#: 92745452

Courier:
☐ Commercial

☐ Fed Ex
☒ Pace

☐ UPS

☐ USPS
☐ Other:

☐ Client

PM: BV

Due Date: 08/09/24

CLIENT: 92- GP-HAM

Custody Seal Present? ☐ Yes ☒ No

Seals Intact? ☐ Yes ☐ No ☒ N/A

Date/Initials Person Examining Contents: 12/01/24

Packing Material: ☒ Bubble Wrap ☐ Bubble Bags ☐ None ☐ Other

Biological Tissue Frozen?

☐ Yes ☐ No ☒ N/A

Thermometer:

☒ IR Gun ID: 214

Type of Ice: ☒ Wet ☐ Blue ☐ None

Cooler Temp: 5.6

Correction Factor: 0.0

Add/Subtract (°C) 0.0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C): 5.6

USDA Regulated Soil (☐ N/A, water sample)

Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ No

Did samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

			Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.	
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.	
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☐ No ☐ N/A	3.	
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4.	
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.	
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.	
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A		
Containers Intact?	☒ Yes ☐ No ☐ N/A	7.	
Dissolved analysis: Samples Field Filtered?	☐ Yes ☐ No ☒ N/A	8.	
Sample Labels Match COC?	☒ Yes ☐ No ☐ N/A	9.	
-Includes Date/Time/ID/Analysis Matrix: <u>WT</u>			
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10.	
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.	
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A		

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, L.Hg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐

Client _____ Profile/EZ (Circle one) _____ Notes _____

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic ZN Acetate & NaOH (pH > 9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	W6FU-Wide-mouthed Glass jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG9H-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KPTU-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit) VP-4/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)	BP3R-250 mL Plastic (NH4)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	VSGU-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)	
CC																												
1	2	1																										
2	2	1																										
3	2	1																										
4	2	1																										
5	2	1																										
6	2	1																										
7	2	1																										
8	2	1																										
9	2	1																										
10	2	1																										
11	2	1																										
12	2	1																										

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers.



August 26, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1 (CA)-20240807
Pace Project No.: 92746280

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory between August 07, 2024 and August 14, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Peachtree Corners, GA

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Jamie Newsome, Geosyntec Consultants
Zain Webb, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1 (CA)-20240807
Pace Project No.: 92746280

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804
Florida/NELAP Certification #: E87648
North Carolina Drinking Water Certification #: 37712
North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030
South Carolina Certification #: 99030001
Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092
Florida DOH Certification #: E87315
Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381
South Carolina Certification #: 98011001
Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92746280001	HAM-PT-09	Water	08/06/24 11:10	08/07/24 12:25
92746280002	HAM-PT-12	Water	08/06/24 16:20	08/07/24 12:25
92746280003	HAM-AP1-FD-01	Water	08/06/24 00:00	08/07/24 12:25
92746280004	HAM-PT-08	Water	08/08/24 18:10	08/09/24 14:15
92746280005	HAM-PT-11	Water	08/07/24 10:30	08/09/24 14:15
92746280006	HAM-PT-14	Water	08/08/24 13:21	08/09/24 14:15
92746280007	HAM-PT-15	Water	08/09/24 10:10	08/12/24 12:10
92746280008	HAM-PT-07	Water	08/09/24 12:15	08/12/24 12:10
92746280009	HAM-PT-13	Water	08/09/24 14:05	08/12/24 12:10
92746280010	HAM-AP1-EB-01	Water	08/09/24 14:40	08/12/24 12:10
92746280011	HAM-AP1-FB-01	Water	08/09/24 14:50	08/12/24 12:10
92746280012	HAM-MW-53	Water	08/12/24 14:45	08/14/24 16:35
92746280013	HAM-MW-54	Water	08/12/24 12:35	08/14/24 14:40
92746282001	HAM-PT-10	Water	08/05/24 17:02	08/07/24 12:25

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92746280001	HAM-PT-09	EPA 6010D	MJS2	1
		EPA 6020B	CW1	2
92746280002	HAM-PT-12	EPA 6010D	MJS2	1
		EPA 6020B	CW1	2
92746280003	HAM-AP1-FD-01	EPA 6010D	MJS2	1
		EPA 6020B	CW1	3
92746280004	HAM-PT-08	EPA 6010D	MT1	1
		EPA 6020B	CW1	2
92746280005	HAM-PT-11	EPA 6010D	MT1	1
		EPA 6020B	CW1	2
92746280006	HAM-PT-14	EPA 6010D	MT1	1
		EPA 6020B	CW1	2
92746280007	HAM-PT-15	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92746280008	HAM-PT-07	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92746280009	HAM-PT-13	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92746280010	HAM-AP1-EB-01	EPA 6010D	AJM	1
		EPA 6020B	CW1	3
92746280011	HAM-AP1-FB-01	EPA 6010D	MJS2	1
		EPA 6020B	CW1	3
92746280012	HAM-MW-53	EPA 6010D	MJS2	5
		EPA 6020B	CW1	2
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
92746280013	HAM-MW-54	EPA 6010D	MJS2	5
		EPA 6020B	CW1	2
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
92746282001	HAM-PT-10	EPA 6010D	MJS2	1
		EPA 6020B	CW1	2

PASI-A = Pace Analytical Services - Asheville

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)-20240807
Pace Project No.: 92746280

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92746280001	HAM-PT-09					
EPA 6010D	Iron	0.31	mg/L	0.040	08/15/24 22:36	
EPA 6020B	Boron	1.1	mg/L	0.040	08/13/24 19:02	
EPA 6020B	Molybdenum	0.24	mg/L	0.010	08/13/24 19:02	
92746280002	HAM-PT-12					
EPA 6010D	Iron	0.33	mg/L	0.040	08/15/24 22:40	
EPA 6020B	Boron	1.1	mg/L	0.040	08/13/24 19:05	
EPA 6020B	Molybdenum	0.20	mg/L	0.010	08/13/24 19:05	
92746280003	HAM-AP1-FD-01					
EPA 6010D	Iron	0.28	mg/L	0.040	08/15/24 22:43	
EPA 6020B	Boron	0.052	mg/L	0.040	08/13/24 19:09	
EPA 6020B	Molybdenum	0.00067J	mg/L	0.010	08/13/24 19:09	
92746280004	HAM-PT-08					
EPA 6010D	Iron	16.7	mg/L	0.040	08/16/24 17:23	
EPA 6020B	Arsenic	0.32	mg/L	0.0050	08/15/24 18:43	
EPA 6020B	Boron	0.55	mg/L	0.040	08/15/24 18:43	
92746280005	HAM-PT-11					
EPA 6010D	Iron	0.36	mg/L	0.040	08/16/24 17:26	
EPA 6020B	Boron	1.3	mg/L	0.040	08/15/24 18:47	
EPA 6020B	Molybdenum	0.086	mg/L	0.010	08/15/24 18:47	
92746280006	HAM-PT-14					
EPA 6010D	Iron	17.3	mg/L	0.040	08/16/24 17:30	
EPA 6020B	Arsenic	0.22	mg/L	0.0050	08/15/24 18:51	
EPA 6020B	Boron	0.55	mg/L	0.040	08/15/24 18:51	
92746280007	HAM-PT-15					
EPA 6010D	Iron	14.5	mg/L	0.040	08/18/24 19:52	
EPA 6020B	Arsenic	0.43	mg/L	0.0050	08/19/24 16:56	
EPA 6020B	Boron	0.60	mg/L	0.040	08/19/24 16:56	
92746280008	HAM-PT-07					
EPA 6010D	Iron	18.3	mg/L	0.040	08/18/24 20:02	
EPA 6020B	Arsenic	0.21	mg/L	0.0050	08/19/24 17:00	
EPA 6020B	Boron	0.54	mg/L	0.040	08/19/24 17:00	
92746280009	HAM-PT-13					
EPA 6010D	Iron	24.0	mg/L	0.040	08/18/24 20:05	
EPA 6020B	Arsenic	0.26	mg/L	0.0050	08/19/24 17:04	
EPA 6020B	Boron	0.52	mg/L	0.040	08/19/24 17:04	
92746280012	HAM-MW-53					
EPA 6010D	Iron	0.13	mg/L	0.040	08/22/24 17:42	
EPA 6010D	Manganese	8.8	mg/L	0.040	08/22/24 17:42	
EPA 6010D	Potassium	6.9	mg/L	0.50	08/22/24 17:42	
EPA 6010D	Sodium	17.1	mg/L	1.0	08/22/24 17:42	
EPA 6010D	Magnesium	40.2	mg/L	0.050	08/22/24 17:42	
EPA 6020B	Boron	8.8	mg/L	0.040	08/21/24 17:19	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92746280013	HAM-MW-54					
EPA 6010D	Iron	0.11	mg/L	0.040	08/22/24 17:53	
EPA 6010D	Manganese	8.6	mg/L	0.040	08/22/24 17:53	
EPA 6010D	Potassium	6.4	mg/L	0.50	08/22/24 17:53	
EPA 6010D	Sodium	15.8	mg/L	1.0	08/22/24 17:53	
EPA 6010D	Magnesium	37.8	mg/L	0.050	08/22/24 17:53	
EPA 6020B	Arsenic	0.0077	mg/L	0.0050	08/21/24 17:30	
EPA 6020B	Boron	8.8	mg/L	0.040	08/21/24 17:30	
92746282001	HAM-PT-10					
EPA 6010D	Iron	0.11	mg/L	0.040	08/15/24 22:47	
EPA 6020B	Boron	0.015J	mg/L	0.040	08/13/24 19:20	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

Sample: HAM-PT-09		Lab ID: 92746280001		Collected: 08/06/24 11:10		Received: 08/07/24 12:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.31	mg/L	0.040	0.025	1	08/09/24 11:23	08/15/24 22:36	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.1	mg/L	0.040	0.012	1	08/08/24 10:02	08/13/24 19:02	7440-42-8	
Molybdenum	0.24	mg/L	0.010	0.00062	1	08/08/24 10:02	08/13/24 19:02	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

Sample: HAM-PT-12		Lab ID: 92746280002		Collected: 08/06/24 16:20		Received: 08/07/24 12:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.33	mg/L	0.040	0.025	1	08/09/24 11:23	08/15/24 22:40	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.1	mg/L	0.040	0.012	1	08/08/24 10:02	08/13/24 19:05	7440-42-8	
Molybdenum	0.20	mg/L	0.010	0.00062	1	08/08/24 10:02	08/13/24 19:05	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

Sample: HAM-AP1-FD-01		Lab ID: 92746280003		Collected: 08/06/24 00:00		Received: 08/07/24 12:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.28	mg/L	0.040	0.025	1	08/09/24 11:23	08/15/24 22:43	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	ND	mg/L	0.0050	0.00084	1	08/08/24 10:02	08/13/24 19:09	7440-38-2	
Boron	0.052	mg/L	0.040	0.012	1	08/08/24 10:02	08/13/24 19:09	7440-42-8	
Molybdenum	0.00067J	mg/L	0.010	0.00062	1	08/08/24 10:02	08/13/24 19:09	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

Sample: HAM-PT-08		Lab ID: 92746280004		Collected: 08/08/24 18:10		Received: 08/09/24 14:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	16.7	mg/L	0.040	0.025	1	08/15/24 17:37	08/16/24 17:23	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.32	mg/L	0.0050	0.00084	1	08/15/24 12:41	08/15/24 18:43	7440-38-2	
Boron	0.55	mg/L	0.040	0.012	1	08/15/24 12:41	08/15/24 18:43	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

Sample: HAM-PT-11		Lab ID: 92746280005		Collected: 08/07/24 10:30		Received: 08/09/24 14:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.36	mg/L	0.040	0.025	1	08/15/24 17:37	08/16/24 17:26	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.3	mg/L	0.040	0.012	1	08/15/24 12:41	08/15/24 18:47	7440-42-8	
Molybdenum	0.086	mg/L	0.010	0.00062	1	08/15/24 12:41	08/15/24 18:47	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

Sample: HAM-PT-14		Lab ID: 92746280006		Collected: 08/08/24 13:21		Received: 08/09/24 14:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	17.3	mg/L	0.040	0.025	1	08/15/24 17:37	08/16/24 17:30	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.22	mg/L	0.0050	0.00084	1	08/15/24 12:41	08/15/24 18:51	7440-38-2	
Boron	0.55	mg/L	0.040	0.012	1	08/15/24 12:41	08/15/24 18:51	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

Sample: HAM-PT-15		Lab ID: 92746280007		Collected: 08/09/24 10:10		Received: 08/12/24 12:10		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	14.5	mg/L	0.040	0.025	1	08/16/24 15:57	08/18/24 19:52	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.43	mg/L	0.0050	0.00084	1	08/15/24 13:30	08/19/24 16:56	7440-38-2	
Boron	0.60	mg/L	0.040	0.012	1	08/15/24 13:30	08/19/24 16:56	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

Sample: HAM-PT-07		Lab ID: 92746280008		Collected: 08/09/24 12:15		Received: 08/12/24 12:10		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	18.3	mg/L	0.040	0.025	1	08/16/24 15:57	08/18/24 20:02	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.21	mg/L	0.0050	0.00084	1	08/15/24 13:30	08/19/24 17:00	7440-38-2	
Boron	0.54	mg/L	0.040	0.012	1	08/15/24 13:30	08/19/24 17:00	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

Sample: HAM-PT-13		Lab ID: 92746280009		Collected: 08/09/24 14:05		Received: 08/12/24 12:10		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	24.0	mg/L	0.040	0.025	1	08/16/24 15:57	08/18/24 20:05	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.26	mg/L	0.0050	0.00084	1	08/15/24 13:30	08/19/24 17:04	7440-38-2	
Boron	0.52	mg/L	0.040	0.012	1	08/15/24 13:30	08/19/24 17:04	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

Sample: HAM-AP1-EB-01		Lab ID: 92746280010		Collected: 08/09/24 14:40		Received: 08/12/24 12:10		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	08/16/24 15:57	08/18/24 20:11	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	ND	mg/L	0.0050	0.00084	1	08/15/24 13:30	08/19/24 17:08	7440-38-2	
Boron	ND	mg/L	0.040	0.012	1	08/15/24 13:30	08/19/24 17:08	7440-42-8	
Molybdenum	ND	mg/L	0.010	0.00062	1	08/15/24 13:30	08/19/24 17:08	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

Sample: HAM-AP1-FB-01		Lab ID: 92746280011		Collected: 08/09/24 14:50		Received: 08/12/24 12:10		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	08/21/24 13:18	08/22/24 14:21	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	ND	mg/L	0.0050	0.00084	1	08/15/24 13:30	08/19/24 17:22	7440-38-2	
Boron	ND	mg/L	0.040	0.012	1	08/15/24 13:30	08/19/24 17:22	7440-42-8	
Molybdenum	ND	mg/L	0.010	0.00062	1	08/15/24 13:30	08/19/24 17:22	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

Sample: HAM-MW-53		Lab ID: 92746280012		Collected: 08/12/24 14:45		Received: 08/14/24 16:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	0.13	mg/L	0.040	0.025	1	08/21/24 13:41	08/22/24 17:42	7439-89-6	
Manganese	8.8	mg/L	0.040	0.011	1	08/21/24 13:41	08/22/24 17:42	7439-96-5	
Potassium	6.9	mg/L	0.50	0.15	1	08/21/24 13:41	08/22/24 17:42	7440-09-7	
Sodium	17.1	mg/L	1.0	0.58	1	08/21/24 13:41	08/22/24 17:42	7440-23-5	
Magnesium	40.2	mg/L	0.050	0.012	1	08/21/24 13:41	08/22/24 17:42	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Boron	8.8	mg/L	0.040	0.012	1	08/17/24 10:09	08/21/24 17:19	7440-42-8	
Molybdenum	ND	mg/L	0.010	0.00062	1	08/17/24 10:09	08/21/24 17:19	7439-98-7	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/15/24 20:52		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/15/24 20:52		
Alkalinity, Total as CaCO3	ND	mg/L	5.0	5.0	1		08/15/24 20:52		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		08/17/24 04:13	18496-25-8	M1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

Sample: HAM-MW-54		Lab ID: 92746280013		Collected: 08/12/24 12:35		Received: 08/14/24 14:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	0.11	mg/L	0.040	0.025	1	08/21/24 13:41	08/22/24 17:53	7439-89-6	
Manganese	8.6	mg/L	0.040	0.011	1	08/21/24 13:41	08/22/24 17:53	7439-96-5	
Potassium	6.4	mg/L	0.50	0.15	1	08/21/24 13:41	08/22/24 17:53	7440-09-7	
Sodium	15.8	mg/L	1.0	0.58	1	08/21/24 13:41	08/22/24 17:53	7440-23-5	
Magnesium	37.8	mg/L	0.050	0.012	1	08/21/24 13:41	08/22/24 17:53	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Arsenic	0.0077	mg/L	0.0050	0.00084	1	08/17/24 10:09	08/21/24 17:30	7440-38-2	
Boron	8.8	mg/L	0.040	0.012	1	08/17/24 10:09	08/21/24 17:30	7440-42-8	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/15/24 20:55		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/15/24 20:55		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		08/15/24 20:55		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		08/17/24 04:15	18496-25-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

Sample: HAM-PT-10		Lab ID: 92746282001		Collected: 08/05/24 17:02		Received: 08/07/24 12:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.11	mg/L	0.040	0.025	1	08/09/24 11:23	08/15/24 22:47	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	0.015J	mg/L	0.040	0.012	1	08/08/24 10:02	08/13/24 19:20	7440-42-8	
Molybdenum	ND	mg/L	0.010	0.00062	1	08/08/24 10:02	08/13/24 19:20	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

QC Batch: 874538

Analysis Method: EPA 6010D

QC Batch Method: EPA 3010A

Analysis Description: 6010D ATL

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92746280001, 92746280002, 92746280003, 92746282001

METHOD BLANK: 4505177

Matrix: Water

Associated Lab Samples: 92746280001, 92746280002, 92746280003, 92746282001

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Iron	mg/L	ND	0.040	0.025	08/15/24 21:56	

LABORATORY CONTROL SAMPLE: 4505178

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Iron	mg/L	1	1.0	105	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4505179 4505180

Parameter	Units	92746435001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Iron	mg/L	242 ug/L	1	1	1.3	1.2	101	100	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240807
Pace Project No.: 92746280

QC Batch: 875958 Analysis Method: EPA 6010D
QC Batch Method: EPA 3010A Analysis Description: 6010D ATL
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92746280004, 92746280005, 92746280006

METHOD BLANK: 4512108 Matrix: Water
Associated Lab Samples: 92746280004, 92746280005, 92746280006

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Iron	mg/L	ND	0.040	0.025	08/16/24 15:49	

LABORATORY CONTROL SAMPLE: 4512109

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Iron	mg/L	1	0.98	98	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4512110 4512111

Parameter	Units	92746891009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Iron	mg/L	2.7	1	1	3.6	3.5	98	83	75-125	4	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

QC Batch: 876300

Analysis Method: EPA 6010D

QC Batch Method: EPA 3010A

Analysis Description: 6010D ATL

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92746280007, 92746280008, 92746280009, 92746280010

METHOD BLANK: 4514148

Matrix: Water

Associated Lab Samples: 92746280007, 92746280008, 92746280009, 92746280010

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Iron	mg/L	ND	0.040	0.025	08/18/24 18:19	

LABORATORY CONTROL SAMPLE: 4514149

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Iron	mg/L	1	1.1	106	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4514150 4514151

Parameter	Units	92746288005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Iron	mg/L	2.8	1	1	3.8	3.9	99	112	75-125	3	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

QC Batch: 877200

Analysis Method: EPA 6010D

QC Batch Method: EPA 3010A

Analysis Description: 6010D ATL

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92746280011

METHOD BLANK: 4518173

Matrix: Water

Associated Lab Samples: 92746280011

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Iron	mg/L	ND	0.040	0.025	08/22/24 14:14	

LABORATORY CONTROL SAMPLE: 4518174

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Iron	mg/L	1	1.2	115	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4518175 4518176

Parameter	Units	92747047001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Iron	mg/L	2.1	1	1	3.1	3.1	107	105	75-125	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240807
Pace Project No.: 92746280

QC Batch:	877202	Analysis Method:	EPA 6010D
QC Batch Method:	EPA 3010A	Analysis Description:	6010D ATL
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92746280012, 92746280013

METHOD BLANK: 4518182 Matrix: Water
Associated Lab Samples: 92746280012, 92746280013

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Iron	mg/L	ND	0.040	0.025	08/22/24 16:05	
Magnesium	mg/L	ND	0.050	0.012	08/22/24 16:05	
Manganese	mg/L	ND	0.040	0.011	08/22/24 16:05	
Potassium	mg/L	ND	0.50	0.15	08/22/24 16:05	
Sodium	mg/L	ND	1.0	0.58	08/22/24 16:05	

LABORATORY CONTROL SAMPLE: 4518183

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Iron	mg/L	1	1.2	119	80-120	
Magnesium	mg/L	1	1.2	118	80-120	
Manganese	mg/L	1	1.1	110	80-120	
Potassium	mg/L	1	1.1	113	80-120	
Sodium	mg/L	1	1.2	116	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4518184 4518185

Parameter	Units	92746783017 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Iron	mg/L	ND	1	1	1.1	1.1	111	110	75-125	2	20	
Magnesium	mg/L	7.0	1	1	8.1	8.1	107	110	75-125	0	20	
Manganese	mg/L	ND	1	1	1.1	1.1	107	108	75-125	0	20	
Potassium	mg/L	1.8	1	1	2.8	2.8	104	103	75-125	0	20	
Sodium	mg/L	1.9	1	1	2.9	3.0	105	112	75-125	3	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240807
Pace Project No.: 92746280

QC Batch:	874191	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92746280001, 92746280002, 92746280003, 92746282001

METHOD BLANK: 4503331 Matrix: Water
Associated Lab Samples: 92746280001, 92746280002, 92746280003, 92746282001

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Arsenic	mg/L	ND	0.0050	0.00084	08/13/24 17:51	
Boron	mg/L	ND	0.040	0.012	08/13/24 17:51	
Molybdenum	mg/L	ND	0.010	0.00062	08/13/24 17:51	

LABORATORY CONTROL SAMPLE: 4503332

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Arsenic	mg/L	0.1	0.095	95	80-120	
Boron	mg/L	1	0.92	92	80-120	
Molybdenum	mg/L	0.1	0.099	99	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4503333 4503334

Parameter	Units	92745465009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Arsenic	mg/L	ND	0.1	0.1	0.098	0.097	98	97	75-125	1	20	
Boron	mg/L	ND	1	1	0.95	0.96	95	96	75-125	1	20	
Molybdenum	mg/L	ND	0.1	0.1	0.099	0.10	99	99	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240807
Pace Project No.: 92746280

QC Batch:	875890	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92746280004, 92746280005, 92746280006

METHOD BLANK: 4511665 Matrix: Water
Associated Lab Samples: 92746280004, 92746280005, 92746280006

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Arsenic	mg/L	ND	0.0050	0.00084	08/15/24 17:33	
Boron	mg/L	ND	0.040	0.012	08/15/24 17:33	
Molybdenum	mg/L	ND	0.010	0.00062	08/15/24 17:33	

LABORATORY CONTROL SAMPLE: 4511666

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Arsenic	mg/L	0.1	0.098	98	80-120	
Boron	mg/L	1	0.95	95	80-120	
Molybdenum	mg/L	0.1	0.10	100	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4511667 4511668

Parameter	Units	92746891014 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Arsenic	mg/L	ND	0.1	0.1	0.098	0.10	98	100	75-125	2	20	
Boron	mg/L	0.61	1	1	1.6	1.6	99	100	75-125	1	20	
Molybdenum	mg/L	0.046	0.1	0.1	0.14	0.14	99	99	75-125	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

QC Batch:	875892	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92746280007, 92746280008, 92746280009, 92746280010, 92746280011

METHOD BLANK: 4511675

Matrix: Water

Associated Lab Samples: 92746280007, 92746280008, 92746280009, 92746280010, 92746280011

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Arsenic	mg/L	ND	0.0050	0.00084	08/19/24 15:35	
Boron	mg/L	ND	0.040	0.012	08/19/24 15:35	
Molybdenum	mg/L	ND	0.010	0.00062	08/19/24 15:35	

LABORATORY CONTROL SAMPLE: 4511676

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Arsenic	mg/L	0.1	0.099	99	80-120	
Boron	mg/L	1	0.96	96	80-120	
Molybdenum	mg/L	0.1	0.10	103	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4511677

4511678

Parameter	Units	92746288009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Arsenic	mg/L	ND	0.1	0.1	0.10	0.10	101	103	75-125	2	20	
Boron	mg/L	0.59	1	1	1.6	1.6	101	105	75-125	2	20	
Molybdenum	mg/L	ND	0.1	0.1	0.10	0.10	104	102	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240807
Pace Project No.: 92746280

QC Batch:	876406	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92746280012, 92746280013

METHOD BLANK: 4514719 Matrix: Water
Associated Lab Samples: 92746280012, 92746280013

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Arsenic	mg/L	ND	0.0050	0.00084	08/21/24 16:00	
Boron	mg/L	ND	0.040	0.012	08/21/24 16:00	
Molybdenum	mg/L	ND	0.010	0.00062	08/21/24 16:00	

LABORATORY CONTROL SAMPLE: 4514720

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Arsenic	mg/L	0.1	0.099	99	80-120	
Boron	mg/L	1	0.98	98	80-120	
Molybdenum	mg/L	0.1	0.10	101	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4514743 4514744

Parameter	Units	92747503015 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Arsenic	mg/L	ND	0.1	0.1	0.099	0.099	99	99	75-125	0	20	
Boron	mg/L	ND	1	1	0.87	0.86	87	86	75-125	1	20	
Molybdenum	mg/L	ND	0.1	0.1	0.10	0.10	101	101	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240807
Pace Project No.: 92746280

QC Batch: 875982 Analysis Method: SM 2320B-2011
QC Batch Method: SM 2320B-2011 Analysis Description: 2320B Alkalinity
Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92746280012, 92746280013

METHOD BLANK: 4512446 Matrix: Water

Associated Lab Samples: 92746280012, 92746280013

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	08/15/24 19:45	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	08/15/24 19:45	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	08/15/24 19:45	

LABORATORY CONTROL SAMPLE: 4512447

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.5	105	80-120	

LABORATORY CONTROL SAMPLE: 4512448

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	53.1	106	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4512449 4512450

Parameter	Units	92747221005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	62.0	50	50	107	112	91	101	80-120	5	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4512451 4512452

Parameter	Units	92747221006 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	ND	50	50	41.0	39.5	82	79	80-120	4	25	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240807
Pace Project No.: 92746280

QC Batch: 876099 Analysis Method: SM 4500-S2D-2011
QC Batch Method: SM 4500-S2D-2011 Analysis Description: 4500S2D Sulfide Water
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92746280012, 92746280013

METHOD BLANK: 4513327 Matrix: Water
Associated Lab Samples: 92746280012, 92746280013

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	08/17/24 04:12	

LABORATORY CONTROL SAMPLE: 4513328

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.52	104	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4513329 4513330

Parameter	Units	92746280012 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.41	0.39	82	77	80-120	6	10	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4513331 4513332

Parameter	Units	92747679002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.52	0.54	103	108	80-120	5	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1 (CA)-20240807
Pace Project No.: 92746280

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1 (CA)-20240807

Pace Project No.: 92746280

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92746280001	HAM-PT-09	EPA 3010A	874538	EPA 6010D	874645
92746280002	HAM-PT-12	EPA 3010A	874538	EPA 6010D	874645
92746280003	HAM-AP1-FD-01	EPA 3010A	874538	EPA 6010D	874645
92746282001	HAM-PT-10	EPA 3010A	874538	EPA 6010D	874645
92746280004	HAM-PT-08	EPA 3010A	875958	EPA 6010D	876036
92746280005	HAM-PT-11	EPA 3010A	875958	EPA 6010D	876036
92746280006	HAM-PT-14	EPA 3010A	875958	EPA 6010D	876036
92746280007	HAM-PT-15	EPA 3010A	876300	EPA 6010D	876355
92746280008	HAM-PT-07	EPA 3010A	876300	EPA 6010D	876355
92746280009	HAM-PT-13	EPA 3010A	876300	EPA 6010D	876355
92746280010	HAM-AP1-EB-01	EPA 3010A	876300	EPA 6010D	876355
92746280011	HAM-AP1-FB-01	EPA 3010A	877200	EPA 6010D	877281
92746280012	HAM-MW-53	EPA 3010A	877202	EPA 6010D	877299
92746280013	HAM-MW-54	EPA 3010A	877202	EPA 6010D	877299
92746280001	HAM-PT-09	EPA 3005A	874191	EPA 6020B	874323
92746280002	HAM-PT-12	EPA 3005A	874191	EPA 6020B	874323
92746280003	HAM-AP1-FD-01	EPA 3005A	874191	EPA 6020B	874323
92746282001	HAM-PT-10	EPA 3005A	874191	EPA 6020B	874323
92746280004	HAM-PT-08	EPA 3005A	875890	EPA 6020B	876009
92746280005	HAM-PT-11	EPA 3005A	875890	EPA 6020B	876009
92746280006	HAM-PT-14	EPA 3005A	875890	EPA 6020B	876009
92746280007	HAM-PT-15	EPA 3005A	875892	EPA 6020B	876017
92746280008	HAM-PT-07	EPA 3005A	875892	EPA 6020B	876017
92746280009	HAM-PT-13	EPA 3005A	875892	EPA 6020B	876017
92746280010	HAM-AP1-EB-01	EPA 3005A	875892	EPA 6020B	876017
92746280011	HAM-AP1-FB-01	EPA 3005A	875892	EPA 6020B	876017
92746280012	HAM-MW-53	EPA 3005A	876406	EPA 6020B	876456
92746280013	HAM-MW-54	EPA 3005A	876406	EPA 6020B	876456
92746280012	HAM-MW-53	SM 2320B-2011	875982		
92746280013	HAM-MW-54	SM 2320B-2011	875982		
92746280012	HAM-MW-53	SM 4500-S2D-2011	876099		
92746280013	HAM-MW-54	SM 4500-S2D-2011	876099		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



DC#_TITLE: ENV-FRM-HUNT-0083 v03_Sample Condition Upon Receipt

Effective Date: 05/24/2024

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐

Client Name:

G.A. Power

Project #

WO#: 92746280

Courier:

☐ Commercial☒ Pace☐ UPS☐ USPS☐ Client☐ Other:

Custody Seal Present?

☐ Yes☒ No

Seals Intact?

☐ Yes☐ No☒ N/A

Date/Initials Person Examining Contents: 5/17/24 CS4

Packing Material:

☐ Bubble Wrap☐ Bubble Bags☒ None☐ Other

Biological Tissue Frozen?

☐ Yes☐ No☒ N/A

Thermometer:

☐ IR Gun ID:

230

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

2.3

Correction Factor:

Add/Subtract (°C)

2.3

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

2.3

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☒ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☒ No

				Comments/Discrepancy:
Chain of Custody Present?	☒ Yes	☐ No	☐ N/A	1.
Samples Arrived within Hold Time?	☒ Yes	☐ No	☐ N/A	2.
Short Hold Time Analysis (<72 hr.)?	☐ Yes	☒ No	☐ N/A	3.
Rush Turn Around Time Requested?	☐ Yes	☒ No	☐ N/A	4.
Sufficient Volume?	☒ Yes	☐ No	☐ N/A	5.
Correct Containers Used?	☒ Yes	☐ No	☐ N/A	6.
-Pace Containers Used?	☒ Yes	☐ No	☐ N/A	
Containers Intact?	☒ Yes	☐ No	☐ N/A	7.
Dissolved analysis: Samples Field Filtered?	☐ Yes	☐ No	☒ N/A	8.
Sample Labels Match COC?	☒ Yes	☐ No	☐ N/A	9.
-Includes Date/Time/ID/Analysis Matrix: W				
Headspace in VOA Vials (>5-Gmm)?	☐ Yes	☐ No	☒ N/A	10.
Trip Blank Present?	☐ Yes	☐ No	☒ N/A	11.
Trip Blank Custody Seals Present?	☐ Yes	☐ No	☒ N/A	

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☒ No

HAM-PT-10 is listed twice on 2 different COC's

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

WO#: 92746280

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

PM: BV

Due Date: 08/21/24

CLIENT: 92- GP-HAM

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐

Client _____ Profile/EZ (Circle one) _____ Notes _____

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic 2N Acetate & NaOH (pH > 9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGFU-Wide-mouthed Glass jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG9H-40 mL Amber Nitric (N/A) (Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit) VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)	BP3N-250 mL Plastic (N/A) (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	VSGU-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)	
CC																												
1																												
2																												
3																												
4																												
5																												
6																												
7																												
8																												
9																												
10																												
11																												
12																												

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers).



CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Section A Required Client Information:		Section B Required Project Information:		Section C Invoice Information:		Page: 1 of 1	
Company: GA Power		Report To: SCS Contacts		Attention: Southern Co.		REGULATORY AGENCY NPDES GROUND WATER DRINKING WATER UST RCRA OTHER <u>CR</u>	
Address: Atlanta, GA		Copy To: Geosyntec Contacts		Company Name:			
Email To: SCS Contacts		Purchase Order No.: GPC82474-0001		Address:		Site Location STATE: <u>GA</u>	
Phone: Fax:		Project Name: Hammond AP-1		Pace Quote Reference:			
Requested Due Date/TAT: 5 day		Project Number: GW6581G/109/12		Pace Project Manager: Sonam Vang			
				Pace Protocol: 10483			

ITEM #	Section D Required Client Information SAMPLE ID (A-Z, 0-9 / -) Sample IDs MUST BE UNIQUE	Valid Matrix Codes MATRIX CODE DRINKING WATER WATER WASTE WATER PRODUCT OTHER (Specify) OTHER (Specify) OTHER (Specify)	Valid Matrix Codes CODE WQ WQ WQ WQ WQ WQ WQ	MATRIX CODE (See Section D)	SAMPLE TYPE (G-ORAB) (See Section D)	COLLECTED				SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives										Requested Analysis Filtered (Y/N)										Residual Chlorine (Y/N)	Pace Project No./ Lab I.D.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
						COMPOSITE		IMMEDIATE				Unpreserved	H ₂ SO ₄	HNO ₃	HCl	NaOH	Na ₂ S ₂ O ₈	Methanol	Other	Analysis Test	Y/N	N	N	N	N	N	N	N	N	N	N			N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N

ADDITIONAL COMMENTS	RELINQUISHED BY / AFFILIATION	DATE	TIME	ACCEPTED BY / AFFILIATION	DATE	TIME	SAMPLE CONDITIONS
Task Code: HAM-CCN-GA-20240805	Elisabeth Russell / Geosyntec	8/6/24	12:00	Thomas W. Smith / Geosyntec	8/6/24	12:00	
	Thomas W. Smith / Geosyntec	8/6/24	12:05	Kyle Williams / Pace	8/6/24	12:05	
	Kyle Williams / Pace	8/7/24	15:05	Corbin Hester / Pace	8/7/24	15:05	

SAMPLER NAME AND SIGNATURE		Temp (°C)	Revised for (Y/N)	Custody Sealed (Y/N)	Samples (Y/N)
PRINT Name of SAMPLER: Elisabeth Russell / Geosyntec Consultants, Inc.					
SIGNATURE of SAMPLER:					
DATE Signed (MM/DD/YYYY): 08/06/2024					



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

GA Power

Project #:

Courier: ☐ Fed Ex ☐ UPS ☐ USPS ☐ Client
☐ Commercial ☒ Pace ☐ Other: _____Custody Seal Present? ☐ Yes ☒ No Seals Intact? ☐ Yes ☐ No ☒ N/A

Date/Initials Person Examining Contents:

8/9/24
CoutPacking Material: ☐ Bubble Wrap ☐ Bubble Bags ☒ None ☐ Other

Thermometer:

☒ IR Gun ID:

230

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

2.1

Correction Factor:

Add/Subtract (°C)

0.0

Cooler Temp Corrected (°C):

2.1

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC
(check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally,
including Hawaii and Puerto Rico)? ☐ Yes ☐ No

			Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.	
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.	
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.	
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4.	
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.	
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.	
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A		
Containers Intact?	☒ Yes ☐ No ☐ N/A	7.	
Dissolved analysis: Samples Field Filtered?	☐ Yes ☐ No ☒ N/A	8.	
Sample Labels Match COC?	☒ Yes ☐ No ☐ N/A	9.	
-Includes Date/Time/ID/Analysis Matrix:	W		
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10.	
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.	
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A		

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted: _____ Date/Time: _____

Project Manager SCURF Review: _____

Date: _____

Project Manager SRF Review: _____

Date: _____



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐

Client _____ Profile/EZ (Circle one) _____ Notes _____

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)		BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic 2N Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGFU-Wide-mouthed Glass jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG94-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit)-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A – lab)	SP2T-250 mL Sterile Plastic (N/A – lab)		BP3R-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	V6GU-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)	
CC																														
1																														
2																														
3																														
4																														
5																														
6																														
7																														
8																														
9																														
10																														
11																														
12																														

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers.



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒Sample Condition
Upon Receipt

Client Name:

Project #:

WO#: 92746280

PM: BV

Due Date: 08/21/24

CLIENT: 92- GP-HAM

Courier:

☐ Commercial☐ Fed-Ex
☒ Pace☐ UPS☐ USPS☐ Other: _____☐ Client

Custody Seal Present?

☐ Yes☐ No

Seals Intact?

☐ Yes☐ No☒ N/A

Date/Initials Person Examining Contents: 8/12/24

CJH

Packing Material:

☐ Bubble Wrap☐ Bubble Bags☒ None☐ Other

Biological Tissue Frozen?

☐ Yes☐ No☐ N/A

Thermometer:

☐ IR Gun ID:

230

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

2.1

Correction Factor:

Add/Subtract (°C)

0.0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

2.1

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

				Comments/Discrepancy:
Chain of Custody Present?	☒ Yes	☐ No	☐ N/A	1.
Samples Arrived within Hold Time?	☐ Yes	☐ No	☐ N/A	2.
Short Hold Time Analysis (<72 hr.)?	☐ Yes	☒ No	☐ N/A	3.
Rush Turn Around Time Requested?	☐ Yes	☒ No	☐ N/A	4.
Sufficient Volume?	☒ Yes	☐ No	☐ N/A	5.
Correct Containers Used?	☒ Yes	☐ No	☐ N/A	6.
-Pace Containers Used?	☒ Yes	☐ No	☐ N/A	
Containers Intact?	☒ Yes	☐ No	☐ N/A	7.
Dissolved analysis: Samples Field Filtered?	☐ Yes	☐ No	☒ N/A	8.
Sample Labels Match COC?	☒ Yes	☐ No	☐ N/A	9.
-Includes Date/Time/ID/Analysis Matrix: W				
Headspace in VOA Vials (>5-6mm)?	☐ Yes	☐ No	☒ N/A	10.
Trip Blank Present?	☐ Yes	☐ No	☒ N/A	11.
Trip Blank Custody Seals Present?	☐ Yes	☐ No	☒ N/A	

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted: _____

Date/Time: _____

Project Manager SCURF Review: _____

Date: _____

Project Manager SRF Review: _____

Date: _____



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

W0#: 92746280

PM: BV

Due Date: 08/21/24

CLIENT: 92- GP-HAM

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐

Client _____ Profile/EZ (Circle one) _____ Notes _____

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)		BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic Zn Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGFU-Wide-mouthed Glass Jar Unpreserved		AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)		AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG94-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)		VG9T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit)-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A – lab)	SP2T-250 mL Sterile Plastic (N/A – lab)		BP3R-250 mL Plastic (NH4)2SO4 (9.3-9.7)		AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	V5GU-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)			
CC																																				
1																																				
2																																				
3																																				
4																																				
5																																				
6																																				
7																																				
8																																				
9																																				
10																																				
11																																				
12																																				

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers.



CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Section A Required Client Information:		Section B Required Project Information:		Section C Invoice Information:		Page: 1 of 1	
Company: GA Power		Report To: SCS Contacts		Attention: Southern Co.		REGULATORY AGENCY NPDES GROUND WATER DRINKING WATER UST RCRA OTHER CCR	
Address: Atlanta, GA		Copy To: Geosyntec Contacts		Company Name:			
Email To: SCS Contacts		Purchase Order No.: GPC82474-0001		Address:		Site Location	
Phone:		Project Name: Hammond AP-1		Pace Quote Reference:		STATE: GA	
Requested Due Date/TAT: 10 day		Project Number: GW6581G		Pace Project Manager: Bonnie Vang			
				Pace Profile #: 16483			

ITEM #	Section D Required Client Information		Valid Matrix Codes MATRIX CODE DRINKING WATER DW WT WATER WW WASTE WATER P PRODUCT SL SOIL/SOLID OL OIL WP WIPE AR AIR UT OTHER TS TISSUE TS		MATRIX CODE	(see valid codes to left)	SAMPLE TYPE (G=GRAB C=COMP)	COLLECTED				SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives								Analysis Test	Requested Analysis Filtered (Y/N)												Residual Chlorine (Y/N)	Pace Project No./ Lab I.D.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
								COMPOSITE		COMPOSITE END/GRAB				Unpreserved	H ₂ SO ₄	HNO ₃	HCl	NaOH	Na ₂ S ₂ O ₃	Methanol	Other		Total 601/6022-B, As, Mo, Fe	Z	N	N	N																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											

ADDITIONAL COMMENTS	RELINQUISHED BY / AFFILIATION	DATE	TIME	ACCEPTED BY / AFFILIATION	DATE	TIME	SAMPLE CONDITIONS
Task Code: HAM-CCR CA 20240807	Elisabeth Russell / Geosyntec	08/09/2024	1010	Thomas Kessler / Geosyntec	08/09/2024	1200	
	Thomas Kessler / Geosyntec	08/11/2024	0745	Jacob Tracy / Geosyntec	08/11/2024	0745	
	Jacob Tracy / Geosyntec	08/12/2024	1210	Kyan Williams / Pace	08/12/24	1210	
	Kyan Williams / Pace	8/12/2024	1352	Elisabeth Russell / Geosyntec	8/12/24	1352	

SAMPLER NAME AND SIGNATURE		Temp in °C	Received on ice (Y/N)	Custody Sealed Coder (Y/N)	Samples Inset (Y/N)
PRINT Name of SAMPLER: Elisabeth Russell / Geosyntec Consultants, Inc.					
SIGNATURE of SAMPLER:					
DATE Signed (MM/DD/YY): 08/09/2024					



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

Project #:

Courier:

☐ Commercial☐ Fed Ex☐ UPS☐ USPS☐ Client☒ Pace☐ Other: _____

Custody Seal Present?

☒ Yes☐ No

Seals Intact?

☒ Yes☐ No☐ N/ADate/Initials Person Examining Contents: MA

Packing Material:

☒ Bubble Wrap☐ Bubble Bags☐ None☐ Other

Biological Tissue Frozen?

☐ Yes☐ No☒ N/A

Thermometer:

☐ IR Gun ID:214

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

3.0

Correction Factor:

Add/Subtract (°C)

0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

3.0USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

			Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.	
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.	
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.	
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4.	
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.	
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.	
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A		
Containers Intact?	☒ Yes ☐ No ☐ N/A	7.	
Dissolved analysis: Samples Field Filtered?	☐ Yes ☐ No ☒ N/A	8.	
Sample Labels Match COC?	☒ Yes ☐ No ☐ N/A	9.	
-Includes Date/Time/ID/Analysis Matrix: <u>W</u>			
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10.	
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.	
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A		

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted: _____

Date/Time: _____

Project Manager SCURF Review: _____

Date: _____

Project Manager SRF Review: _____

Date: _____



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐

Client _____ Profile/EZ (Circle one) _____ Notes _____

Client	Item#	CC	1	2	3	4	5	6	7	8	9	10	11	12
	BP4U-125 mL Plastic Unpreserved (N/A) (Cl ⁻)			2										
	BP3U-250 mL Plastic Unpreserved (N/A)			2										
	BP2U-500 mL Plastic Unpreserved (N/A)													
	BP1U-1 liter Plastic Unpreserved (N/A)													
	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl ⁻)													
	BP3N-250 mL plastic HNO3 (pH < 2)													
	BP4Z-125 mL Plastic Zn Acetate & NaOH (pH > 9)													
	BP4B-125 mL Plastic NaOH (pH > 12) (Cl ⁻)													
	WGFU-Wide-mouthed Glass Jar Unpreserved													
	AG1U-1 liter Amber Unpreserved (N/A) (Cl ⁻)													
	AG1H-1 liter Amber HCl (pH < 2)													
	AG3U-250 mL Amber Unpreserved (N/A) (Cl ⁻)													
	AG1S-1 liter Amber H2SO4 (pH < 2)													
	AG3S-250 mL Amber H2SO4 (pH < 2)													
	DG9H-40 mL Amber H4C2O4 (N/A) (Cl ⁻)													
	DG9H-40 mL VOA HCl (N/A)													
	VG9T-40 mL VOA Na2S2O3 (N/A)													
	VG9U-40 mL VOA Unpreserved (N/A)													
	DG9V-40 mL VOA H3PO4 (N/A)													
	KP7U-50 mL Plastic Unpreserved (N/A)													
	V/GK (3 vials per kit) VPH/Gas kit (N/A)													
	SP5T-125 mL Sterile Plastic (N/A - lab)													
	SP2T-250 mL Sterile Plastic (N/A - lab)													
	BP3R-250 mL Plastic (NH2)2SO4 (9.3-9.7)													
	AGGU-100 mL Amber Unpreserved (N/A) (Cl ⁻)													
	VSGU-20 mL Scintillation vials (N/A)													
	DG9U-40 mL Amber Unpreserved vials (N/A)													

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers).



CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Section A Required Client Information:		Section B Required Project Information:		Section C Invoice Information:		Page: 1 of 1	
Company: GA Power		Report To: SCS Contacts		Attention: Southern Co.		REGULATORY AGENCY	
Address: Atlanta, GA		Copy To: Geosynlec Contacts		Company Name:			
Email To: SCS Contacts		Purchase Order No.: GPC82474-0001		Address:		NPDES GROUND WATER DRINKING WATER	
Phone:		Project Name: Hammond AP-1		Pace Quote Reference:		UST RCRA OTHER CCR	
Requested Due Date/TAT: 10 day		Project Number: GW6581G		Pace Project Manager: Bonnie Vang		Site Location	
				Pace Profile #: 16483		STATE: GA	

ITEM #	Section D Required Client Information	Valid Matrix Codes MATRIX CODE DRINKING WATER DW WT WATER WW WASTE WATER W PRODUCT SL SOLID/SOILS DL OIL WP WIFE AK AIR DT OTHER TS	MATRIX CODE used with collect ID	SAMPLE TYPE (G=GRAB C=COMP)	COLLECTED				SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives										Analysis Test Y/N	Requested Analysis Filtered (Y/N)										Residual Chlorine (Y/N)	Pace Project No./ Lab I.D.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
					COMPOSITE		COMPOSITE END-GRAB				Unpreserved	H ₂ SO ₄	HNO ₃	HCl	NaOH	Na ₂ S ₂ O ₃	Methanol	Other	Total 601/6022-B, Fe, Mn	Total 601/6022-As, B, Fe		Major Ions (Profile 10639-2):																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
					DATE	TIME	DATE	TIME														Sulfate	Nitrate	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Nitrite	Phosphate			Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Chlorate	Perchlorate	Nitrate	Nitrite	Ammonium	Calcium	Magnesium	Sodium + Potassium	Chloride	Fluoride	Sulfate	Phosphate	Silica	Cyanide	Zinc	Copper	Lead	Cadmium	Chromium	Manganese	Nickel	Selenium	Vanadium	Molybdenum	Barium	Strontium	Boron	Lithium	Sulfide	Oxide	Hydroxide	Carbonate	Bicarbonate	Silicate	Aluminate	Ch

ADDITIONAL COMMENTS	RELINQUISHED BY / AFFILIATION	DATE	TIME	ACCEPTED BY / AFFILIATION	DATE	TIME	SAMPLE CONDITIONS			
Task Code: HAM-CCR-CA-20240807	Elizabeth Russell / Geosynlec	08/12/24	14:00	Jacob Tracy / Geosynlec	08/12/24	14:00				
	Jacob Tracy / Geosynlec	08/14/24	12:05	Ryan Williams / Pace	08/14/24	12:05				
	Ryan Williams / Pace	8/14/2024	1440	ng / Pace	8/14/24	1440				

SAMPLER NAME AND SIGNATURE		Temp in °C	Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)	Sampled in Heat (Y/N)
PRINT Name of SAMPLER: Elisabeth Russell / Geosynlec Consultants, Inc.					
SIGNATURE of SAMPLER:	DATE Signed (MM/DD/YY):				



DC#_Title: ENV-FRM-HUNT-0083 V05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

Project #:

WO#: 92746280

PM: BV

Due Date: 08/21/24

CLIENT: 92- GP-HAM

Courier:

☐ Commercial☐ FedEx☐ UPS☐ USPS☐ Client☒ Pace☐ Other: _____

Custody Seal Present?

☐ Yes☒ No

Seals Intact?

☐ Yes☐ No☒ N/A

Date/Initials Person Examining Contents:

8/17/24
CJ

Packing Material:

☐ Bubble Wrap☐ Bubble Bags☒ None☐ Other

Biological Tissue Frozen?

☐ Yes☐ No☒ N/A

Thermometer:

☐ IR Gun ID:

230

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

2.3

Correction Factor:

Add/Subtract (°C)

2.3

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

2.3

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

Comments/Discrepancy:

Chain of Custody Present?

☒ Yes☐ No☐ N/A

1.

Samples Arrived within Hold Time?

☒ Yes☐ No☐ N/A

2.

Short Hold Time Analysis (<72 hr.)?

☐ Yes☒ No☐ N/A

3.

Rush Turn Around Time Requested?

☐ Yes☒ No☐ N/A

4.

Sufficient Volume?

☒ Yes☐ No☐ N/A

5.

Correct Containers Used?

☒ Yes☐ No☐ N/A

6.

-Pace Containers Used?

☒ Yes☐ No☐ N/A

Containers Intact?

☒ Yes☐ No☐ N/A

7.

Dissolved analysis: Samples Field Filtered?

☐ Yes☐ No☒ N/A

8.

Sample Labels Match COC?

☒ Yes☐ No☐ N/A

9.

-Includes Date/Time/ID/Analysis Matrix:

W

Headspace in VOA Vials (>5-6mm)?

☐ Yes☐ No☒ N/A

10.

Trip Blank Present?

☐ Yes☐ No☒ N/A

11.

Trip Blank Custody Seals Present?

☐ Yes☐ No☒ N/A

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

HAM-PT-10 is listed twice on 2 different COC's

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project

WO#: 92746282

PM: BV

Due Date: 08/21/24

CLIENT: 92- GP-HAM

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐

Client _____ Profile/EZ (Circle one) _____ Notes _____

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)		BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic ZN Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGFU-Wide-mouthed Glass Jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG94-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit)-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)		BP3R-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	VSGU-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)	
CC																														
1																														
2																														
3																														
4																														
5																														
6																														
7																														
8																														
9																														
10																														
11																														
12																														

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers.

Page 48 of 48



August 27, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92747679

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on August 14, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Peachtree Corners, GA

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Jamie Newsome, Geosyntec Consultants
Zain Webb, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92747679

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92747679

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92747679001	HAM-PT-09	Water	08/12/24 15:30	08/14/24 12:05
92747679002	HAM-PT-10	Water	08/13/24 14:10	08/14/24 12:05
92747679003	HAM-PT-11	Water	08/12/24 17:25	08/14/24 12:05
92747679004	HAM-PT-12	Water	08/13/24 12:05	08/14/24 12:05
92747679005	HAM-PT-14	Water	08/13/24 17:00	08/14/24 12:05

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92747679

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92747679001	HAM-PT-09	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92747679002	HAM-PT-10	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92747679003	HAM-PT-11	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92747679004	HAM-PT-12	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92747679005	HAM-PT-14	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3

PASI-A = Pace Analytical Services - Asheville

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92747679

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92747679001	HAM-PT-09					
EPA 6010D	Iron	0.34	mg/L	0.040	08/22/24 17:17	
EPA 6010D	Manganese	0.36	mg/L	0.040	08/22/24 17:17	
EPA 6010D	Potassium	6.1	mg/L	0.50	08/22/24 17:17	
EPA 6010D	Sodium	7.8	mg/L	1.0	08/22/24 17:17	
EPA 6010D	Calcium	92.5	mg/L	1.0	08/22/24 17:17	
EPA 6010D	Magnesium	23.9	mg/L	0.050	08/22/24 17:17	
EPA 6020B	Barium	0.066	mg/L	0.0050	08/20/24 15:20	
EPA 6020B	Boron	1.2	mg/L	0.040	08/20/24 15:20	
EPA 6020B	Cadmium	0.00021J	mg/L	0.00050	08/20/24 15:20	
EPA 6020B	Cobalt	0.0033J	mg/L	0.0050	08/20/24 15:20	
EPA 6020B	Lithium	0.0019J	mg/L	0.030	08/20/24 15:20	
EPA 6020B	Molybdenum	0.25	mg/L	0.010	08/20/24 15:20	
SM 2540C-2015	Total Dissolved Solids	521	mg/L	25.0	08/16/24 14:18	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	120	mg/L	5.0	08/15/24 20:59	
SM 2320B-2011	Alkalinity, Total as CaCO3	120	mg/L	5.0	08/15/24 20:59	
EPA 300.0 Rev 2.1 1993	Chloride	42.3	mg/L	1.0	08/16/24 02:04	
EPA 300.0 Rev 2.1 1993	Fluoride	0.35	mg/L	0.10	08/16/24 02:04	
EPA 300.0 Rev 2.1 1993	Sulfate	157	mg/L	4.0	08/16/24 13:35	M1
92747679002	HAM-PT-10					
EPA 6010D	Iron	0.31	mg/L	0.040	08/22/24 17:20	
EPA 6010D	Manganese	0.50	mg/L	0.040	08/22/24 17:20	
EPA 6010D	Potassium	7.2	mg/L	0.50	08/22/24 17:20	
EPA 6010D	Sodium	9.1	mg/L	1.0	08/22/24 17:20	
EPA 6010D	Calcium	107	mg/L	1.0	08/22/24 17:20	
EPA 6010D	Magnesium	14.4	mg/L	0.050	08/22/24 17:20	
EPA 6020B	Antimony	0.0010J	mg/L	0.0030	08/20/24 15:35	
EPA 6020B	Barium	0.049	mg/L	0.0050	08/20/24 15:35	
EPA 6020B	Boron	1.7	mg/L	0.040	08/20/24 15:35	
EPA 6020B	Cadmium	0.00013J	mg/L	0.00050	08/20/24 15:35	
EPA 6020B	Cobalt	0.0016J	mg/L	0.0050	08/20/24 15:35	
EPA 6020B	Molybdenum	0.17	mg/L	0.010	08/20/24 15:35	
SM 2540C-2015	Total Dissolved Solids	449	mg/L	25.0	08/19/24 17:59	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	133	mg/L	5.0	08/16/24 16:35	
SM 2320B-2011	Alkalinity, Total as CaCO3	133	mg/L	5.0	08/16/24 16:35	
EPA 300.0 Rev 2.1 1993	Chloride	47.5	mg/L	1.0	08/16/24 03:14	
EPA 300.0 Rev 2.1 1993	Fluoride	0.25	mg/L	0.10	08/16/24 03:14	
EPA 300.0 Rev 2.1 1993	Sulfate	122	mg/L	3.0	08/16/24 14:47	
92747679003	HAM-PT-11					
EPA 6010D	Iron	0.25	mg/L	0.040	08/22/24 17:24	
EPA 6010D	Manganese	1.0	mg/L	0.040	08/22/24 17:24	
EPA 6010D	Potassium	6.1	mg/L	0.50	08/22/24 17:24	
EPA 6010D	Sodium	8.5	mg/L	1.0	08/22/24 17:24	
EPA 6010D	Calcium	96.7	mg/L	1.0	08/22/24 17:24	
EPA 6010D	Magnesium	20.6	mg/L	0.050	08/22/24 17:24	
EPA 6020B	Barium	0.072	mg/L	0.0050	08/20/24 15:39	
EPA 6020B	Boron	1.5	mg/L	0.040	08/20/24 15:39	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92747679

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92747679003	HAM-PT-11					
EPA 6020B	Cadmium	0.00022J	mg/L	0.00050	08/20/24 15:39	
EPA 6020B	Cobalt	0.015	mg/L	0.0050	08/20/24 15:39	
EPA 6020B	Lithium	0.0059J	mg/L	0.030	08/20/24 15:39	
EPA 6020B	Molybdenum	0.10	mg/L	0.010	08/20/24 15:39	
SM 2540C-2015	Total Dissolved Solids	456	mg/L	25.0	08/16/24 14:19	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	126	mg/L	5.0	08/15/24 21:08	
SM 2320B-2011	Alkalinity, Total as CaCO3	126	mg/L	5.0	08/15/24 21:08	
EPA 300.0 Rev 2.1 1993	Chloride	41.7	mg/L	1.0	08/16/24 03:28	
EPA 300.0 Rev 2.1 1993	Fluoride	0.32	mg/L	0.10	08/16/24 03:28	
EPA 300.0 Rev 2.1 1993	Sulfate	139	mg/L	3.0	08/16/24 15:01	
92747679004	HAM-PT-12					
EPA 6010D	Iron	0.082	mg/L	0.040	08/22/24 17:28	
EPA 6010D	Manganese	0.62	mg/L	0.040	08/22/24 17:28	
EPA 6010D	Potassium	5.8	mg/L	0.50	08/22/24 17:28	
EPA 6010D	Sodium	6.6	mg/L	1.0	08/22/24 17:28	
EPA 6010D	Calcium	98.4	mg/L	1.0	08/22/24 17:28	
EPA 6010D	Magnesium	24.5	mg/L	0.050	08/22/24 17:28	
EPA 6020B	Arsenic	0.00089J	mg/L	0.0050	08/20/24 15:54	
EPA 6020B	Barium	0.070	mg/L	0.0050	08/20/24 15:54	
EPA 6020B	Boron	1.1	mg/L	0.040	08/20/24 15:54	
EPA 6020B	Cadmium	0.00024J	mg/L	0.00050	08/20/24 15:54	
EPA 6020B	Cobalt	0.0022J	mg/L	0.0050	08/20/24 15:54	
EPA 6020B	Lithium	0.0025J	mg/L	0.030	08/20/24 15:54	
EPA 6020B	Molybdenum	0.23	mg/L	0.010	08/20/24 15:54	
SM 2540C-2015	Total Dissolved Solids	546	mg/L	25.0	08/19/24 18:00	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	128	mg/L	5.0	08/16/24 16:53	
SM 2320B-2011	Alkalinity, Total as CaCO3	128	mg/L	5.0	08/16/24 16:53	
EPA 300.0 Rev 2.1 1993	Chloride	31.7	mg/L	1.0	08/16/24 03:42	
EPA 300.0 Rev 2.1 1993	Fluoride	0.32	mg/L	0.10	08/16/24 03:42	
EPA 300.0 Rev 2.1 1993	Sulfate	178	mg/L	4.0	08/16/24 15:15	
92747679005	HAM-PT-14					
EPA 6010D	Iron	18.9	mg/L	0.040	08/22/24 17:32	
EPA 6010D	Manganese	3.6	mg/L	0.040	08/22/24 17:32	
EPA 6010D	Potassium	6.4	mg/L	0.50	08/22/24 17:32	
EPA 6010D	Sodium	9.7	mg/L	1.0	08/22/24 17:32	
EPA 6010D	Calcium	136	mg/L	1.0	08/22/24 17:32	
EPA 6010D	Magnesium	21.0	mg/L	0.050	08/22/24 17:32	
EPA 6020B	Arsenic	0.24	mg/L	0.0050	08/20/24 15:58	
EPA 6020B	Barium	0.048	mg/L	0.0050	08/20/24 15:58	
EPA 6020B	Boron	0.60	mg/L	0.040	08/20/24 15:58	
EPA 6020B	Cobalt	0.028	mg/L	0.0050	08/20/24 15:58	
EPA 6020B	Lithium	0.053	mg/L	0.030	08/20/24 15:58	
EPA 6020B	Molybdenum	0.014	mg/L	0.010	08/20/24 15:58	
SM 2540C-2015	Total Dissolved Solids	621	mg/L	25.0	08/19/24 18:00	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	153	mg/L	5.0	08/16/24 17:02	
SM 2320B-2011	Alkalinity, Total as CaCO3	153	mg/L	5.0	08/16/24 17:02	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92747679

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92747679005	HAM-PT-14					
EPA 300.0 Rev 2.1 1993	Chloride	19.6	mg/L	1.0	08/16/24 03:56	
EPA 300.0 Rev 2.1 1993	Fluoride	0.21	mg/L	0.10	08/16/24 03:56	
EPA 300.0 Rev 2.1 1993	Sulfate	239	mg/L	6.0	08/16/24 15:29	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92747679

Sample: HAM-PT-09		Lab ID: 92747679001		Collected: 08/12/24 15:30		Received: 08/14/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.34	mg/L	0.040	0.025	1	08/21/24 13:41	08/22/24 17:17	7439-89-6	
Manganese	0.36	mg/L	0.040	0.011	1	08/21/24 13:41	08/22/24 17:17	7439-96-5	
Potassium	6.1	mg/L	0.50	0.15	1	08/21/24 13:41	08/22/24 17:17	7440-09-7	
Sodium	7.8	mg/L	1.0	0.58	1	08/21/24 13:41	08/22/24 17:17	7440-23-5	
Calcium	92.5	mg/L	1.0	0.12	1	08/21/24 13:41	08/22/24 17:17	7440-70-2	
Magnesium	23.9	mg/L	0.050	0.012	1	08/21/24 13:41	08/22/24 17:17	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/16/24 12:09	08/20/24 15:20	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	08/16/24 12:09	08/20/24 15:20	7440-38-2	
Barium	0.066	mg/L	0.0050	0.00047	1	08/16/24 12:09	08/20/24 15:20	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/16/24 12:09	08/20/24 15:20	7440-41-7	
Boron	1.2	mg/L	0.040	0.012	1	08/16/24 12:09	08/20/24 15:20	7440-42-8	
Cadmium	0.00021J	mg/L	0.00050	0.00010	1	08/16/24 12:09	08/20/24 15:20	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/16/24 12:09	08/20/24 15:20	7440-47-3	
Cobalt	0.0033J	mg/L	0.0050	0.00032	1	08/16/24 12:09	08/20/24 15:20	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/16/24 12:09	08/20/24 15:20	7439-92-1	
Lithium	0.0019J	mg/L	0.030	0.0016	1	08/16/24 12:09	08/20/24 15:20	7439-93-2	
Molybdenum	0.25	mg/L	0.010	0.00062	1	08/16/24 12:09	08/20/24 15:20	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/16/24 12:09	08/20/24 15:20	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/16/24 12:09	08/20/24 15:20	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/26/24 09:00	08/26/24 13:00	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	521	mg/L	25.0	25.0	1		08/16/24 14:18		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	120	mg/L	5.0	5.0	1		08/15/24 20:59		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/15/24 20:59		
Alkalinity, Total as CaCO3	120	mg/L	5.0	5.0	1		08/15/24 20:59		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/17/24 04:16	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	42.3	mg/L	1.0	0.60	1		08/16/24 02:04	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92747679

Sample: HAM-PT-09		Lab ID: 92747679001		Collected: 08/12/24 15:30		Received: 08/14/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.35	mg/L	0.10	0.050	1		08/16/24 02:04	16984-48-8	
Sulfate	157	mg/L	4.0	2.0	4		08/16/24 13:35	14808-79-8	M1

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92747679

Sample: HAM-PT-10		Lab ID: 92747679002		Collected: 08/13/24 14:10		Received: 08/14/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	0.31	mg/L	0.040	0.025	1	08/21/24 13:41	08/22/24 17:20	7439-89-6	
Manganese	0.50	mg/L	0.040	0.011	1	08/21/24 13:41	08/22/24 17:20	7439-96-5	
Potassium	7.2	mg/L	0.50	0.15	1	08/21/24 13:41	08/22/24 17:20	7440-09-7	
Sodium	9.1	mg/L	1.0	0.58	1	08/21/24 13:41	08/22/24 17:20	7440-23-5	
Calcium	107	mg/L	1.0	0.12	1	08/21/24 13:41	08/22/24 17:20	7440-70-2	
Magnesium	14.4	mg/L	0.050	0.012	1	08/21/24 13:41	08/22/24 17:20	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	0.0010J	mg/L	0.0030	0.00054	1	08/16/24 12:09	08/20/24 15:35	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	08/16/24 12:09	08/20/24 15:35	7440-38-2	
Barium	0.049	mg/L	0.0050	0.00047	1	08/16/24 12:09	08/20/24 15:35	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/16/24 12:09	08/20/24 15:35	7440-41-7	
Boron	1.7	mg/L	0.040	0.012	1	08/16/24 12:09	08/20/24 15:35	7440-42-8	
Cadmium	0.00013J	mg/L	0.00050	0.00010	1	08/16/24 12:09	08/20/24 15:35	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/16/24 12:09	08/20/24 15:35	7440-47-3	
Cobalt	0.0016J	mg/L	0.0050	0.00032	1	08/16/24 12:09	08/20/24 15:35	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/16/24 12:09	08/20/24 15:35	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	08/16/24 12:09	08/20/24 15:35	7439-93-2	
Molybdenum	0.17	mg/L	0.010	0.00062	1	08/16/24 12:09	08/20/24 15:35	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/16/24 12:09	08/20/24 15:35	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/16/24 12:09	08/20/24 15:35	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	08/26/24 09:00	08/26/24 13:03	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	449	mg/L	25.0	25.0	1		08/19/24 17:59		
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO3)	133	mg/L	5.0	5.0	1		08/16/24 16:35		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/16/24 16:35		
Alkalinity, Total as CaCO3	133	mg/L	5.0	5.0	1		08/16/24 16:35		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		08/17/24 04:19	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	47.5	mg/L	1.0	0.60	1		08/16/24 03:14	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92747679

Sample: HAM-PT-10		Lab ID: 92747679002		Collected: 08/13/24 14:10		Received: 08/14/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.25	mg/L	0.10	0.050	1		08/16/24 03:14	16984-48-8	
Sulfate	122	mg/L	3.0	1.5	3		08/16/24 14:47	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92747679

Sample: HAM-PT-11		Lab ID: 92747679003		Collected: 08/12/24 17:25		Received: 08/14/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.25	mg/L	0.040	0.025	1	08/21/24 13:41	08/22/24 17:24	7439-89-6	
Manganese	1.0	mg/L	0.040	0.011	1	08/21/24 13:41	08/22/24 17:24	7439-96-5	
Potassium	6.1	mg/L	0.50	0.15	1	08/21/24 13:41	08/22/24 17:24	7440-09-7	
Sodium	8.5	mg/L	1.0	0.58	1	08/21/24 13:41	08/22/24 17:24	7440-23-5	
Calcium	96.7	mg/L	1.0	0.12	1	08/21/24 13:41	08/22/24 17:24	7440-70-2	
Magnesium	20.6	mg/L	0.050	0.012	1	08/21/24 13:41	08/22/24 17:24	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/16/24 12:09	08/20/24 15:39	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	08/16/24 12:09	08/20/24 15:39	7440-38-2	
Barium	0.072	mg/L	0.0050	0.00047	1	08/16/24 12:09	08/20/24 15:39	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/16/24 12:09	08/20/24 15:39	7440-41-7	
Boron	1.5	mg/L	0.040	0.012	1	08/16/24 12:09	08/20/24 15:39	7440-42-8	
Cadmium	0.00022J	mg/L	0.00050	0.00010	1	08/16/24 12:09	08/20/24 15:39	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/16/24 12:09	08/20/24 15:39	7440-47-3	
Cobalt	0.015	mg/L	0.0050	0.00032	1	08/16/24 12:09	08/20/24 15:39	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/16/24 12:09	08/20/24 15:39	7439-92-1	
Lithium	0.0059J	mg/L	0.030	0.0016	1	08/16/24 12:09	08/20/24 15:39	7439-93-2	
Molybdenum	0.10	mg/L	0.010	0.00062	1	08/16/24 12:09	08/20/24 15:39	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/16/24 12:09	08/20/24 15:39	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/16/24 12:09	08/20/24 15:39	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/26/24 09:00	08/26/24 13:06	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	456	mg/L	25.0	25.0	1		08/16/24 14:19		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	126	mg/L	5.0	5.0	1		08/15/24 21:08		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/15/24 21:08		
Alkalinity, Total as CaCO3	126	mg/L	5.0	5.0	1		08/15/24 21:08		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/17/24 04:16	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	41.7	mg/L	1.0	0.60	1		08/16/24 03:28	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92747679

Sample: HAM-PT-11		Lab ID: 92747679003		Collected: 08/12/24 17:25		Received: 08/14/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.32	mg/L	0.10	0.050	1		08/16/24 03:28	16984-48-8	
Sulfate	139	mg/L	3.0	1.5	3		08/16/24 15:01	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92747679

Sample: HAM-PT-12		Lab ID: 92747679004		Collected: 08/13/24 12:05		Received: 08/14/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	0.082	mg/L	0.040	0.025	1	08/21/24 13:41	08/22/24 17:28	7439-89-6	
Manganese	0.62	mg/L	0.040	0.011	1	08/21/24 13:41	08/22/24 17:28	7439-96-5	
Potassium	5.8	mg/L	0.50	0.15	1	08/21/24 13:41	08/22/24 17:28	7440-09-7	
Sodium	6.6	mg/L	1.0	0.58	1	08/21/24 13:41	08/22/24 17:28	7440-23-5	
Calcium	98.4	mg/L	1.0	0.12	1	08/21/24 13:41	08/22/24 17:28	7440-70-2	
Magnesium	24.5	mg/L	0.050	0.012	1	08/21/24 13:41	08/22/24 17:28	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.00054	1	08/16/24 12:09	08/20/24 15:54	7440-36-0	
Arsenic	0.00089J	mg/L	0.0050	0.00084	1	08/16/24 12:09	08/20/24 15:54	7440-38-2	
Barium	0.070	mg/L	0.0050	0.00047	1	08/16/24 12:09	08/20/24 15:54	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/16/24 12:09	08/20/24 15:54	7440-41-7	
Boron	1.1	mg/L	0.040	0.012	1	08/16/24 12:09	08/20/24 15:54	7440-42-8	
Cadmium	0.00024J	mg/L	0.00050	0.00010	1	08/16/24 12:09	08/20/24 15:54	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/16/24 12:09	08/20/24 15:54	7440-47-3	
Cobalt	0.0022J	mg/L	0.0050	0.00032	1	08/16/24 12:09	08/20/24 15:54	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/16/24 12:09	08/20/24 15:54	7439-92-1	
Lithium	0.0025J	mg/L	0.030	0.0016	1	08/16/24 12:09	08/20/24 15:54	7439-93-2	
Molybdenum	0.23	mg/L	0.010	0.00062	1	08/16/24 12:09	08/20/24 15:54	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/16/24 12:09	08/20/24 15:54	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/16/24 12:09	08/20/24 15:54	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	08/26/24 09:00	08/26/24 13:08	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	546	mg/L	25.0	25.0	1		08/19/24 18:00		
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO3)	128	mg/L	5.0	5.0	1		08/16/24 16:53		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/16/24 16:53		
Alkalinity, Total as CaCO3	128	mg/L	5.0	5.0	1		08/16/24 16:53		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		08/17/24 04:21	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	31.7	mg/L	1.0	0.60	1		08/16/24 03:42	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92747679

Sample: HAM-PT-12		Lab ID: 92747679004		Collected: 08/13/24 12:05		Received: 08/14/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.32	mg/L	0.10	0.050	1		08/16/24 03:42	16984-48-8	
Sulfate	178	mg/L	4.0	2.0	4		08/16/24 15:15	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92747679

Sample: HAM-PT-14		Lab ID: 92747679005		Collected: 08/13/24 17:00		Received: 08/14/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	18.9	mg/L	0.040	0.025	1	08/21/24 13:41	08/22/24 17:32	7439-89-6	
Manganese	3.6	mg/L	0.040	0.011	1	08/21/24 13:41	08/22/24 17:32	7439-96-5	
Potassium	6.4	mg/L	0.50	0.15	1	08/21/24 13:41	08/22/24 17:32	7440-09-7	
Sodium	9.7	mg/L	1.0	0.58	1	08/21/24 13:41	08/22/24 17:32	7440-23-5	
Calcium	136	mg/L	1.0	0.12	1	08/21/24 13:41	08/22/24 17:32	7440-70-2	
Magnesium	21.0	mg/L	0.050	0.012	1	08/21/24 13:41	08/22/24 17:32	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/16/24 12:09	08/20/24 15:58	7440-36-0	
Arsenic	0.24	mg/L	0.0050	0.00084	1	08/16/24 12:09	08/20/24 15:58	7440-38-2	
Barium	0.048	mg/L	0.0050	0.00047	1	08/16/24 12:09	08/20/24 15:58	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/16/24 12:09	08/20/24 15:58	7440-41-7	
Boron	0.60	mg/L	0.040	0.012	1	08/16/24 12:09	08/20/24 15:58	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	08/16/24 12:09	08/20/24 15:58	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/16/24 12:09	08/20/24 15:58	7440-47-3	
Cobalt	0.028	mg/L	0.0050	0.00032	1	08/16/24 12:09	08/20/24 15:58	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/16/24 12:09	08/20/24 15:58	7439-92-1	
Lithium	0.053	mg/L	0.030	0.0016	1	08/16/24 12:09	08/20/24 15:58	7439-93-2	
Molybdenum	0.014	mg/L	0.010	0.00062	1	08/16/24 12:09	08/20/24 15:58	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/16/24 12:09	08/20/24 15:58	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/16/24 12:09	08/20/24 15:58	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/26/24 09:00	08/26/24 13:11	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	621	mg/L	25.0	25.0	1		08/19/24 18:00		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	153	mg/L	5.0	5.0	1		08/16/24 17:02		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/16/24 17:02		
Alkalinity, Total as CaCO3	153	mg/L	5.0	5.0	1		08/16/24 17:02		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/17/24 04:22	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	19.6	mg/L	1.0	0.60	1		08/16/24 03:56	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92747679

Sample: HAM-PT-14		Lab ID: 92747679005		Collected: 08/13/24 17:00		Received: 08/14/24 12:05		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.21	mg/L	0.10	0.050	1		08/16/24 03:56	16984-48-8	
Sulfate	239	mg/L	6.0	3.0	6		08/16/24 15:29	14808-79-8	

REPORT OF LABORATORY ANALYSIS



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92747679

QC Batch:	877202	Analysis Method:	EPA 6010D
QC Batch Method:	EPA 3010A	Analysis Description:	6010D ATL
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92747679001, 92747679002, 92747679003, 92747679004, 92747679005

METHOD BLANK: 4518182 Matrix: Water
Associated Lab Samples: 92747679001, 92747679002, 92747679003, 92747679004, 92747679005

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	08/22/24 16:05	
Iron	mg/L	ND	0.040	0.025	08/22/24 16:05	
Magnesium	mg/L	ND	0.050	0.012	08/22/24 16:05	
Manganese	mg/L	ND	0.040	0.011	08/22/24 16:05	
Potassium	mg/L	ND	0.50	0.15	08/22/24 16:05	
Sodium	mg/L	ND	1.0	0.58	08/22/24 16:05	

LABORATORY CONTROL SAMPLE: 4518183

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	1.2	119	80-120	
Iron	mg/L	1	1.2	119	80-120	
Magnesium	mg/L	1	1.2	118	80-120	
Manganese	mg/L	1	1.1	110	80-120	
Potassium	mg/L	1	1.1	113	80-120	
Sodium	mg/L	1	1.2	116	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4518184 4518185

Parameter	Units	92746783017 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Calcium	mg/L	20.9	1	1	22.0	21.8	106	87	75-125	1	20	
Iron	mg/L	ND	1	1	1.1	1.1	111	110	75-125	2	20	
Magnesium	mg/L	7.0	1	1	8.1	8.1	107	110	75-125	0	20	
Manganese	mg/L	ND	1	1	1.1	1.1	107	108	75-125	0	20	
Potassium	mg/L	1.8	1	1	2.8	2.8	104	103	75-125	0	20	
Sodium	mg/L	1.9	1	1	2.9	3.0	105	112	75-125	3	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92747679

QC Batch: 876140 Analysis Method: EPA 6020B
QC Batch Method: EPA 3005A Analysis Description: 6020 MET
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92747679001, 92747679002, 92747679003, 92747679004, 92747679005

METHOD BLANK: 4513433 Matrix: Water
Associated Lab Samples: 92747679001, 92747679002, 92747679003, 92747679004, 92747679005

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00054	08/20/24 15:05	
Arsenic	mg/L	ND	0.0050	0.00084	08/20/24 15:05	
Barium	mg/L	ND	0.0050	0.00047	08/20/24 15:05	
Beryllium	mg/L	ND	0.00050	0.000094	08/20/24 15:05	
Boron	mg/L	ND	0.040	0.012	08/20/24 15:05	
Cadmium	mg/L	ND	0.00050	0.00010	08/20/24 15:05	
Chromium	mg/L	ND	0.0050	0.0019	08/20/24 15:05	
Cobalt	mg/L	ND	0.0050	0.00032	08/20/24 15:05	
Lead	mg/L	ND	0.0010	0.00016	08/20/24 15:05	
Lithium	mg/L	ND	0.030	0.0016	08/20/24 15:05	
Molybdenum	mg/L	ND	0.010	0.00062	08/20/24 15:05	
Selenium	mg/L	ND	0.0050	0.00096	08/20/24 15:05	
Thallium	mg/L	ND	0.0010	0.00038	08/20/24 15:05	

LABORATORY CONTROL SAMPLE: 4513434

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.11	105	80-120	
Arsenic	mg/L	0.1	0.10	102	80-120	
Barium	mg/L	0.1	0.10	101	80-120	
Beryllium	mg/L	0.1	0.11	107	80-120	
Boron	mg/L	1	1.0	100	80-120	
Cadmium	mg/L	0.1	0.10	105	80-120	
Chromium	mg/L	0.1	0.10	104	80-120	
Cobalt	mg/L	0.1	0.10	103	80-120	
Lead	mg/L	0.1	0.10	102	80-120	
Lithium	mg/L	0.1	0.11	108	80-120	
Molybdenum	mg/L	0.1	0.11	106	80-120	
Selenium	mg/L	0.1	0.10	103	80-120	
Thallium	mg/L	0.1	0.10	102	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4513435 4513436

Parameter	Units	92747679001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	ND	0.1	0.1	0.10	0.10	103	103	75-125	0	20	
Arsenic	mg/L	ND	0.1	0.1	0.10	0.10	101	102	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92747679

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:			4513435		4513436							
Parameter	Units	92747679001	MS	MSD	MS	MSD	MS	MSD	% Rec	RPD	Max	Qual
		Result	Spike	Spike								
Barium	mg/L	0.066	0.1	0.1	0.17	0.17	107	107	75-125	0	20	
Beryllium	mg/L	ND	0.1	0.1	0.10	0.10	100	100	75-125	0	20	
Boron	mg/L	1.2	1	1	2.3	2.4	112	114	75-125	1	20	
Cadmium	mg/L	0.00021J	0.1	0.1	0.10	0.10	102	102	75-125	0	20	
Chromium	mg/L	ND	0.1	0.1	0.10	0.10	103	102	75-125	1	20	
Cobalt	mg/L	0.0033J	0.1	0.1	0.10	0.10	100	101	75-125	1	20	
Lead	mg/L	ND	0.1	0.1	0.095	0.097	95	97	75-125	2	20	
Lithium	mg/L	0.0019J	0.1	0.1	0.10	0.10	101	100	75-125	1	20	
Molybdenum	mg/L	0.25	0.1	0.1	0.35	0.36	108	111	75-125	1	20	
Selenium	mg/L	ND	0.1	0.1	0.10	0.10	101	102	75-125	1	20	
Thallium	mg/L	ND	0.1	0.1	0.095	0.097	95	97	75-125	2	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92747679

QC Batch:	877185	Analysis Method:	EPA 7470A
QC Batch Method:	EPA 7470A	Analysis Description:	7470 Mercury
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92747679001, 92747679002, 92747679003, 92747679004, 92747679005

METHOD BLANK: 4518051 Matrix: Water
Associated Lab Samples: 92747679001, 92747679002, 92747679003, 92747679004, 92747679005

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	08/26/24 12:25	

LABORATORY CONTROL SAMPLE: 4518052

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0024	97	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4518053 4518054

Parameter	Units	92746891021 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.0025	0.0025	0.0023	0.0024	93	94	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92747679

QC Batch: 876190 Analysis Method: SM 2540C-2015
QC Batch Method: SM 2540C-2015 Analysis Description: 2540C Total Dissolved Solids
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92747679001, 92747679003

METHOD BLANK: 4513596 Matrix: Water
Associated Lab Samples: 92747679001, 92747679003

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	08/16/24 14:10	

LABORATORY CONTROL SAMPLE: 4513597

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	415	104	80-120	

SAMPLE DUPLICATE: 4513598

Parameter	Units	92747267003 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	141	141	0	10	

SAMPLE DUPLICATE: 4513599

Parameter	Units	92747305002 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	93.0	87.0	7	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92747679

QC Batch: 876599 Analysis Method: SM 2540C-2015
QC Batch Method: SM 2540C-2015 Analysis Description: 2540C Total Dissolved Solids
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92747679002, 92747679004, 92747679005

METHOD BLANK: 4515256 Matrix: Water
Associated Lab Samples: 92747679002, 92747679004, 92747679005

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	08/19/24 17:58	

LABORATORY CONTROL SAMPLE: 4515257

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	410	102	80-120	

SAMPLE DUPLICATE: 4515259

Parameter	Units	92747679002 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	449	493	9	10	

SAMPLE DUPLICATE: 4515287

Parameter	Units	92746783032 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	25.0	25.0	0	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92747679

QC Batch: 875982 Analysis Method: SM 2320B-2011
QC Batch Method: SM 2320B-2011 Analysis Description: 2320B Alkalinity
Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92747679001, 92747679003

METHOD BLANK: 4512446 Matrix: Water

Associated Lab Samples: 92747679001, 92747679003

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	08/15/24 19:45	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	08/15/24 19:45	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	08/15/24 19:45	

LABORATORY CONTROL SAMPLE: 4512447

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.5	105	80-120	

LABORATORY CONTROL SAMPLE: 4512448

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	53.1	106	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4512449 4512450

Parameter	Units	92747221005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	62.0	50	50	107	112	91	101	80-120	5	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4512451 4512452

Parameter	Units	92747221006 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	ND	50	50	41.0	39.5	82	79	80-120	4	25	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92747679

QC Batch: 876126 Analysis Method: SM 2320B-2011
QC Batch Method: SM 2320B-2011 Analysis Description: 2320B Alkalinity
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92747679002, 92747679004, 92747679005

METHOD BLANK: 4513382 Matrix: Water
Associated Lab Samples: 92747679002, 92747679004, 92747679005

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	08/16/24 14:26	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	08/16/24 14:26	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	08/16/24 14:26	

LABORATORY CONTROL SAMPLE: 4513383

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.5	105	80-120	

LABORATORY CONTROL SAMPLE: 4513384

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.2	104	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4513385 4513386

Parameter	Units	92747429001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	8.4	50	50	59.6	59.3	102	102	80-120	0	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4513387 4513388

Parameter	Units	92748004001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	226	50	50	277	269	101	86	80-120	3	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92747679

QC Batch: 876099 Analysis Method: SM 4500-S2D-2011
QC Batch Method: SM 4500-S2D-2011 Analysis Description: 4500S2D Sulfide Water
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92747679001, 92747679002, 92747679003, 92747679004, 92747679005

METHOD BLANK: 4513327 Matrix: Water
Associated Lab Samples: 92747679001, 92747679002, 92747679003, 92747679004, 92747679005

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	08/17/24 04:12	

LABORATORY CONTROL SAMPLE: 4513328

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.52	104	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4513329 4513330

Parameter	Units	92746280012 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.41	0.39	82	77	80-120	6	10	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4513331 4513332

Parameter	Units	92747679002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.52	0.54	103	108	80-120	5	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92747679

QC Batch: 876002 Analysis Method: EPA 300.0 Rev 2.1 1993
QC Batch Method: EPA 300.0 Rev 2.1 1993 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92747679001, 92747679002, 92747679003, 92747679004, 92747679005

METHOD BLANK: 4512588 Matrix: Water
Associated Lab Samples: 92747679001, 92747679002, 92747679003, 92747679004, 92747679005

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	08/15/24 21:36	
Fluoride	mg/L	ND	0.10	0.050	08/15/24 21:36	
Sulfate	mg/L	ND	1.0	0.50	08/15/24 21:36	

LABORATORY CONTROL SAMPLE: 4512589

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	50.4	101	90-110	
Fluoride	mg/L	2.5	2.6	102	90-110	
Sulfate	mg/L	50	51.1	102	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4512590 4512591

Parameter	Units	92747679001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	42.3	50	50	90.1	93.2	96	102	90-110	3	10	
Fluoride	mg/L	0.35	2.5	2.5	2.8	2.9	97	103	90-110	5	10	
Sulfate	mg/L	157	50	50	198	208	82	101	90-110	5	10 M1	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4512592 4512593

Parameter	Units	92747803004 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	1.6	50	50	52.4	53.1	102	103	90-110	1	10	
Fluoride	mg/L	0.12	2.5	2.5	2.6	2.7	100	102	90-110	2	10	
Sulfate	mg/L	34.8	50	50	85.2	86.0	101	102	90-110	1	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92747679

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92747679

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92747679001	HAM-PT-09	EPA 3010A	877202	EPA 6010D	877299
92747679002	HAM-PT-10	EPA 3010A	877202	EPA 6010D	877299
92747679003	HAM-PT-11	EPA 3010A	877202	EPA 6010D	877299
92747679004	HAM-PT-12	EPA 3010A	877202	EPA 6010D	877299
92747679005	HAM-PT-14	EPA 3010A	877202	EPA 6010D	877299
92747679001	HAM-PT-09	EPA 3005A	876140	EPA 6020B	876308
92747679002	HAM-PT-10	EPA 3005A	876140	EPA 6020B	876308
92747679003	HAM-PT-11	EPA 3005A	876140	EPA 6020B	876308
92747679004	HAM-PT-12	EPA 3005A	876140	EPA 6020B	876308
92747679005	HAM-PT-14	EPA 3005A	876140	EPA 6020B	876308
92747679001	HAM-PT-09	EPA 7470A	877185	EPA 7470A	878170
92747679002	HAM-PT-10	EPA 7470A	877185	EPA 7470A	878170
92747679003	HAM-PT-11	EPA 7470A	877185	EPA 7470A	878170
92747679004	HAM-PT-12	EPA 7470A	877185	EPA 7470A	878170
92747679005	HAM-PT-14	EPA 7470A	877185	EPA 7470A	878170
92747679001	HAM-PT-09	SM 2540C-2015	876190		
92747679002	HAM-PT-10	SM 2540C-2015	876599		
92747679003	HAM-PT-11	SM 2540C-2015	876190		
92747679004	HAM-PT-12	SM 2540C-2015	876599		
92747679005	HAM-PT-14	SM 2540C-2015	876599		
92747679001	HAM-PT-09	SM 2320B-2011	875982		
92747679002	HAM-PT-10	SM 2320B-2011	876126		
92747679003	HAM-PT-11	SM 2320B-2011	875982		
92747679004	HAM-PT-12	SM 2320B-2011	876126		
92747679005	HAM-PT-14	SM 2320B-2011	876126		
92747679001	HAM-PT-09	SM 4500-S2D-2011	876099		
92747679002	HAM-PT-10	SM 4500-S2D-2011	876099		
92747679003	HAM-PT-11	SM 4500-S2D-2011	876099		
92747679004	HAM-PT-12	SM 4500-S2D-2011	876099		
92747679005	HAM-PT-14	SM 4500-S2D-2011	876099		
92747679001	HAM-PT-09	EPA 300.0 Rev 2.1 1993	876002		
92747679002	HAM-PT-10	EPA 300.0 Rev 2.1 1993	876002		
92747679003	HAM-PT-11	EPA 300.0 Rev 2.1 1993	876002		
92747679004	HAM-PT-12	EPA 300.0 Rev 2.1 1993	876002		
92747679005	HAM-PT-14	EPA 300.0 Rev 2.1 1993	876002		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

Project #:

W0#: 92747679

Courier:

☐ Commercial☐ Fed Ex☐ UPS☐ USPS☐ Client☐ Other:

Custody Seal Present?

☒ Yes☐ No

Seals Intact?

☒ Yes☐ No☐ N/ADate/Initials Person Examining Contents: Man

Packing Material:

☒ Bubble Wrap☐ Bubble Bags☐ None☐ Other

Biological Tissue Frozen?

☐ Yes☐ No☒ N/A

Thermometer:

☐ IR Gun ID:214

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

3.0

Correction Factor:

Add/Subtract (°C)

0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

3.0USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

			Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.	
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.	
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.	
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4.	
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.	
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.	
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A	7.	
Containers Intact?	☒ Yes ☐ No ☐ N/A	8.	
Dissolved analysis: Samples Field Filtered?	☐ Yes ☐ No ☒ N/A	9.	
Sample Labels Match COC?	☒ Yes ☐ No ☐ N/A		
-Includes Date/Time/ID/Analysis Matrix: <u>W</u>			
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10.	
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.	
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A		

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_ Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

WO#: 92747679

Project #

PM: BV

Due Date: 08/29/24

CLIENT: 92- GP-HAM

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐

Client: GA Power Profile/EZ (Circle one) Notes

Item#	CC	1	2	3	4	5	6	7	8	9	10	11	12
BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)													
BP3U-250 mL Plastic Unpreserved (N/A)		2	2	2	2	2							
BP2U-500 mL Plastic Unpreserved (N/A)		1	1	1	1	1							
BP1U-1 liter Plastic Unpreserved (N/A)													
BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)													
BP3N-250 mL plastic HNO3 (pH < 2)													
BP4Z-125 mL Plastic Zn Acetate & NaOH (>9)													
BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)													
WGfU-Wide-mouthed Glass Jar Unpreserved													
AG1U-1 liter Amber Unpreserved (N/A) (Cl-)													
AG1H-1 liter Amber HCl (pH < 2)													
AG3U-250 mL Amber Unpreserved (N/A) (Cl-)													
AG1S-1 liter Amber H2SO4 (pH < 2)													
AG3S-250 mL Amber H2SO4 (pH < 2)													
DG5U-40 mL Amber NH4Cl (N/A)(Cl-)													
DG9H-40 mL VOA HCl (N/A)													
VG9T-40 mL VOA Na2S2O3 (N/A)													
VG9U-40 mL VOA Unpreserved (N/A)													
DG9V-40 mL VOA H3PO4 (N/A)													
KP7U-50 mL Plastic Unpreserved (N/A)													
V/GK (3 vials per kit) VPH/Gas kit (N/A)													
SP5T-125 mL Sterile Plastic (N/A - lab)													
SP2T-250 mL Sterile Plastic (N/A - lab)													
BP3R-250 mL Plastic (NH4)2SO4 (9.3-9.7)													
AGOU-100 mL Amber Unpreserved (N/A) (Cl-)													
VSGU-20 mL Scintillation vials (N/A)													
DG9U-40 mL Amber Unpreserved vials (N/A)													

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers).



September 17, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92748254

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on August 16, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Peachtree Corners, GA

Revision 1: Collected date for FD-01 updated to 8/14/24.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Jamie Newsome, Geosyntec Consultants
Zain Webb, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92748254

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92748254001	HAM-PT-07	Water	08/14/24 15:07	08/16/24 12:50
92748254002	HAM-PT-08	Water	08/14/24 11:41	08/16/24 12:50
92748254003	HAM-PT-13	Water	08/14/24 16:55	08/16/24 12:50
92748254004	HAM-PT-15	Water	08/14/24 13:30	08/16/24 12:50
92748254005	HAM-AP1-FB-01	Water	08/15/24 14:45	08/16/24 12:50
92748254006	HAM-AP1-EB-01	Water	08/15/24 14:45	08/16/24 12:50
92748254007	HAM-AP1-FD-01	Water	08/14/24 00:00	08/16/24 12:50

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92748254001	HAM-PT-07	EPA 6010D	AJM, MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92748254002	HAM-PT-08	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92748254003	HAM-PT-13	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92748254004	HAM-PT-15	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92748254005	HAM-AP1-FB-01	EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92748254006	HAM-AP1-EB-01	EPA 6010D	AJM	6
		EPA 6020B	CW1	13

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92748254007	HAM-AP1-FD-01	EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	AJM	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3

PASI-A = Pace Analytical Services - Asheville

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92748254001	HAM-PT-07					
EPA 6010D	Iron	18.4	mg/L	0.040	08/23/24 03:10	
EPA 6010D	Manganese	4.3	mg/L	0.040	08/23/24 03:10	
EPA 6010D	Calcium	127	mg/L	1.0	08/23/24 03:10	
EPA 6010D	Magnesium	18.7	mg/L	0.050	08/23/24 03:10	
EPA 6010D	Potassium	5.7	mg/L	0.50	08/25/24 18:02	
EPA 6010D	Sodium	9.5	mg/L	1.0	08/25/24 18:02	
EPA 6020B	Arsenic	0.24	mg/L	0.0050	08/26/24 22:08	
EPA 6020B	Barium	0.047	mg/L	0.0050	08/26/24 22:08	
EPA 6020B	Beryllium	0.00010J	mg/L	0.00050	08/26/24 22:08	
EPA 6020B	Boron	0.55	mg/L	0.040	08/26/24 22:08	
EPA 6020B	Cobalt	0.059	mg/L	0.0050	08/26/24 22:08	
EPA 6020B	Lithium	0.058	mg/L	0.030	08/26/24 22:08	
EPA 6020B	Molybdenum	0.0079J	mg/L	0.010	08/26/24 22:08	
SM 2540C-2015	Total Dissolved Solids	574	mg/L	25.0	08/21/24 16:27	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	134	mg/L	5.0	08/19/24 14:38	
SM 2320B-2011	Alkalinity, Total as CaCO3	134	mg/L	5.0	08/19/24 14:38	
EPA 300.0 Rev 2.1 1993	Chloride	18.6	mg/L	1.0	08/17/24 18:41	
EPA 300.0 Rev 2.1 1993	Fluoride	0.29	mg/L	0.10	08/17/24 18:41	
EPA 300.0 Rev 2.1 1993	Sulfate	231	mg/L	5.0	08/18/24 01:23	
92748254002	HAM-PT-08					
EPA 6010D	Iron	15.5	mg/L	0.040	08/25/24 18:16	
EPA 6010D	Manganese	4.2	mg/L	0.040	08/25/24 18:16	
EPA 6010D	Potassium	4.9	mg/L	0.50	08/25/24 18:16	
EPA 6010D	Sodium	7.2	mg/L	1.0	08/25/24 18:16	
EPA 6010D	Calcium	99.1	mg/L	1.0	08/25/24 18:16	
EPA 6010D	Magnesium	13.6	mg/L	0.050	08/25/24 18:16	
EPA 6020B	Arsenic	0.29	mg/L	0.0050	08/26/24 22:12	
EPA 6020B	Barium	0.048	mg/L	0.0050	08/26/24 22:12	
EPA 6020B	Boron	0.62	mg/L	0.040	08/26/24 22:12	
EPA 6020B	Cobalt	0.084	mg/L	0.0050	08/26/24 22:12	
EPA 6020B	Lithium	0.025J	mg/L	0.030	08/26/24 22:12	
EPA 6020B	Molybdenum	0.011	mg/L	0.010	08/26/24 22:12	
SM 2540C-2015	Total Dissolved Solids	474	mg/L	25.0	08/21/24 16:27	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	89.7	mg/L	5.0	08/19/24 14:48	
SM 2320B-2011	Alkalinity, Total as CaCO3	89.7	mg/L	5.0	08/19/24 14:48	
EPA 300.0 Rev 2.1 1993	Chloride	17.0	mg/L	1.0	08/17/24 18:55	
EPA 300.0 Rev 2.1 1993	Sulfate	203	mg/L	5.0	08/18/24 01:37	
92748254003	HAM-PT-13					
EPA 6010D	Iron	22.8	mg/L	0.040	08/25/24 18:19	
EPA 6010D	Manganese	4.0	mg/L	0.040	08/25/24 18:19	
EPA 6010D	Potassium	5.4	mg/L	0.50	08/25/24 18:19	
EPA 6010D	Sodium	9.2	mg/L	1.0	08/25/24 18:19	
EPA 6010D	Calcium	124	mg/L	1.0	08/25/24 18:19	
EPA 6010D	Magnesium	16.9	mg/L	0.050	08/25/24 18:19	
EPA 6020B	Arsenic	0.26	mg/L	0.0050	08/26/24 22:16	
EPA 6020B	Barium	0.043	mg/L	0.0050	08/26/24 22:16	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92748254003	HAM-PT-13					
EPA 6020B	Boron	0.52	mg/L	0.040	08/26/24 22:16	
EPA 6020B	Cobalt	0.036	mg/L	0.0050	08/26/24 22:16	
EPA 6020B	Lithium	0.058	mg/L	0.030	08/26/24 22:16	
EPA 6020B	Molybdenum	0.0072J	mg/L	0.010	08/26/24 22:16	
SM 2540C-2015	Total Dissolved Solids	564	mg/L	25.0	08/21/24 16:27	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	118	mg/L	5.0	08/19/24 14:56	
SM 2320B-2011	Alkalinity, Total as CaCO3	118	mg/L	5.0	08/19/24 14:56	
EPA 300.0 Rev 2.1 1993	Chloride	17.7	mg/L	1.0	08/17/24 19:10	
EPA 300.0 Rev 2.1 1993	Fluoride	0.28	mg/L	0.10	08/17/24 19:10	
EPA 300.0 Rev 2.1 1993	Sulfate	232	mg/L	6.0	08/18/24 01:51	
92748254004	HAM-PT-15					
EPA 6010D	Iron	12.8	mg/L	0.040	08/25/24 18:22	
EPA 6010D	Manganese	5.5	mg/L	0.040	08/25/24 18:22	
EPA 6010D	Potassium	5.3	mg/L	0.50	08/25/24 18:22	
EPA 6010D	Sodium	8.1	mg/L	1.0	08/25/24 18:22	
EPA 6010D	Calcium	123	mg/L	1.0	08/25/24 18:22	
EPA 6010D	Magnesium	15.3	mg/L	0.050	08/25/24 18:22	
EPA 6020B	Arsenic	0.42	mg/L	0.0050	08/26/24 22:27	
EPA 6020B	Barium	0.044	mg/L	0.0050	08/26/24 22:27	
EPA 6020B	Beryllium	0.000096J	mg/L	0.00050	08/26/24 22:27	
EPA 6020B	Boron	0.63	mg/L	0.040	08/26/24 22:27	
EPA 6020B	Cobalt	0.061	mg/L	0.0050	08/26/24 22:27	
EPA 6020B	Lithium	0.052	mg/L	0.030	08/26/24 22:27	
EPA 6020B	Molybdenum	0.013	mg/L	0.010	08/26/24 22:27	
SM 2540C-2015	Total Dissolved Solids	548	mg/L	25.0	08/21/24 16:27	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	128	mg/L	5.0	08/19/24 15:05	
SM 2320B-2011	Alkalinity, Total as CaCO3	128	mg/L	5.0	08/19/24 15:05	
EPA 300.0 Rev 2.1 1993	Chloride	15.7	mg/L	1.0	08/17/24 19:24	
EPA 300.0 Rev 2.1 1993	Fluoride	0.29	mg/L	0.10	08/17/24 19:24	
EPA 300.0 Rev 2.1 1993	Sulfate	212	mg/L	5.0	08/18/24 02:05	
92748254006	HAM-AP1-EB-01					
SM 2540C-2015	Total Dissolved Solids	111	mg/L	25.0	08/22/24 16:16	
92748254007	HAM-AP1-FD-01					
EPA 6010D	Iron	15.4	mg/L	0.040	08/25/24 18:40	
EPA 6010D	Manganese	4.2	mg/L	0.040	08/25/24 18:40	
EPA 6010D	Potassium	4.9	mg/L	0.50	08/25/24 18:40	
EPA 6010D	Sodium	7.4	mg/L	1.0	08/25/24 18:40	
EPA 6010D	Calcium	99.4	mg/L	1.0	08/25/24 18:40	
EPA 6010D	Magnesium	13.8	mg/L	0.050	08/25/24 18:40	
EPA 6020B	Arsenic	0.29	mg/L	0.0050	08/26/24 22:42	
EPA 6020B	Barium	0.048	mg/L	0.0050	08/26/24 22:42	
EPA 6020B	Boron	0.63	mg/L	0.040	08/26/24 22:42	
EPA 6020B	Cobalt	0.082	mg/L	0.0050	08/26/24 22:42	
EPA 6020B	Lithium	0.024J	mg/L	0.030	08/26/24 22:42	
EPA 6020B	Molybdenum	0.011	mg/L	0.010	08/26/24 22:42	
SM 2540C-2015	Total Dissolved Solids	469	mg/L	25.0	08/22/24 16:16	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92748254007	HAM-AP1-FD-01					
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	101	mg/L	5.0	08/21/24 19:41	
SM 2320B-2011	Alkalinity, Total as CaCO3	101	mg/L	5.0	08/21/24 19:41	
EPA 300.0 Rev 2.1 1993	Chloride	16.7	mg/L	1.0	08/17/24 19:39	
EPA 300.0 Rev 2.1 1993	Fluoride	0.14	mg/L	0.10	08/17/24 19:39	
EPA 300.0 Rev 2.1 1993	Sulfate	201	mg/L	5.0	08/18/24 02:19	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

Sample: HAM-PT-07		Lab ID: 92748254001		Collected: 08/14/24 15:07		Received: 08/16/24 12:50		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	18.4	mg/L	0.040	0.025	1	08/22/24 13:55	08/23/24 03:10	7439-89-6	
Manganese	4.3	mg/L	0.040	0.011	1	08/22/24 13:55	08/23/24 03:10	7439-96-5	
Calcium	127	mg/L	1.0	0.12	1	08/22/24 13:55	08/23/24 03:10	7440-70-2	
Magnesium	18.7	mg/L	0.050	0.012	1	08/22/24 13:55	08/23/24 03:10	7439-95-4	
Potassium	5.7	mg/L	0.50	0.15	1	08/22/24 13:55	08/25/24 18:02	7440-09-7	
Sodium	9.5	mg/L	1.0	0.58	1	08/22/24 13:55	08/25/24 18:02	7440-23-5	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/23/24 10:30	08/26/24 22:08	7440-36-0	
Arsenic	0.24	mg/L	0.0050	0.00084	1	08/23/24 10:30	08/26/24 22:08	7440-38-2	
Barium	0.047	mg/L	0.0050	0.00047	1	08/23/24 10:30	08/26/24 22:08	7440-39-3	
Beryllium	0.00010J	mg/L	0.00050	0.000094	1	08/23/24 10:30	08/26/24 22:08	7440-41-7	
Boron	0.55	mg/L	0.040	0.012	1	08/23/24 10:30	08/26/24 22:08	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	08/23/24 10:30	08/26/24 22:08	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/23/24 10:30	08/26/24 22:08	7440-47-3	
Cobalt	0.059	mg/L	0.0050	0.00032	1	08/23/24 10:30	08/26/24 22:08	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/23/24 10:30	08/26/24 22:08	7439-92-1	
Lithium	0.058	mg/L	0.030	0.0016	1	08/23/24 10:30	08/26/24 22:08	7439-93-2	
Molybdenum	0.0079J	mg/L	0.010	0.00062	1	08/23/24 10:30	08/26/24 22:08	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/23/24 10:30	08/26/24 22:08	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/23/24 10:30	08/26/24 22:08	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/27/24 10:00	08/27/24 14:20	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	574	mg/L	25.0	25.0	1		08/21/24 16:27		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	134	mg/L	5.0	5.0	1		08/19/24 14:38		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/19/24 14:38		
Alkalinity, Total as CaCO ₃	134	mg/L	5.0	5.0	1		08/19/24 14:38		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/17/24 04:26	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	18.6	mg/L	1.0	0.60	1		08/17/24 18:41	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92748254

Sample: HAM-PT-07		Lab ID: 92748254001		Collected: 08/14/24 15:07		Received: 08/16/24 12:50		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.29	mg/L	0.10	0.050	1		08/17/24 18:41	16984-48-8	
Sulfate	231	mg/L	5.0	2.5	5		08/18/24 01:23	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92748254

Sample: HAM-PT-08		Lab ID: 92748254002		Collected: 08/14/24 11:41		Received: 08/16/24 12:50		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	15.5	mg/L	0.040	0.025	1	08/24/24 09:57	08/25/24 18:16	7439-89-6	
Manganese	4.2	mg/L	0.040	0.011	1	08/24/24 09:57	08/25/24 18:16	7439-96-5	
Potassium	4.9	mg/L	0.50	0.15	1	08/24/24 09:57	08/25/24 18:16	7440-09-7	
Sodium	7.2	mg/L	1.0	0.58	1	08/24/24 09:57	08/25/24 18:16	7440-23-5	
Calcium	99.1	mg/L	1.0	0.12	1	08/24/24 09:57	08/25/24 18:16	7440-70-2	
Magnesium	13.6	mg/L	0.050	0.012	1	08/24/24 09:57	08/25/24 18:16	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/23/24 10:30	08/26/24 22:12	7440-36-0	
Arsenic	0.29	mg/L	0.0050	0.00084	1	08/23/24 10:30	08/26/24 22:12	7440-38-2	
Barium	0.048	mg/L	0.0050	0.00047	1	08/23/24 10:30	08/26/24 22:12	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/23/24 10:30	08/26/24 22:12	7440-41-7	
Boron	0.62	mg/L	0.040	0.012	1	08/23/24 10:30	08/26/24 22:12	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	08/23/24 10:30	08/26/24 22:12	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/23/24 10:30	08/26/24 22:12	7440-47-3	
Cobalt	0.084	mg/L	0.0050	0.00032	1	08/23/24 10:30	08/26/24 22:12	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/23/24 10:30	08/26/24 22:12	7439-92-1	
Lithium	0.025J	mg/L	0.030	0.0016	1	08/23/24 10:30	08/26/24 22:12	7439-93-2	
Molybdenum	0.011	mg/L	0.010	0.00062	1	08/23/24 10:30	08/26/24 22:12	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/23/24 10:30	08/26/24 22:12	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/23/24 10:30	08/26/24 22:12	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/27/24 10:00	08/27/24 14:23	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	474	mg/L	25.0	25.0	1		08/21/24 16:27		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	89.7	mg/L	5.0	5.0	1		08/19/24 14:48		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/19/24 14:48		
Alkalinity, Total as CaCO3	89.7	mg/L	5.0	5.0	1		08/19/24 14:48		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/17/24 04:27	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	17.0	mg/L	1.0	0.60	1		08/17/24 18:55	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92748254

Sample: HAM-PT-08		Lab ID: 92748254002		Collected: 08/14/24 11:41		Received: 08/16/24 12:50		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		08/17/24 18:55	16984-48-8	
Sulfate	203	mg/L	5.0	2.5	5		08/18/24 01:37	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

Sample: HAM-PT-13		Lab ID: 92748254003		Collected: 08/14/24 16:55		Received: 08/16/24 12:50		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	22.8	mg/L	0.040	0.025	1	08/24/24 09:57	08/25/24 18:19	7439-89-6	
Manganese	4.0	mg/L	0.040	0.011	1	08/24/24 09:57	08/25/24 18:19	7439-96-5	
Potassium	5.4	mg/L	0.50	0.15	1	08/24/24 09:57	08/25/24 18:19	7440-09-7	
Sodium	9.2	mg/L	1.0	0.58	1	08/24/24 09:57	08/25/24 18:19	7440-23-5	
Calcium	124	mg/L	1.0	0.12	1	08/24/24 09:57	08/25/24 18:19	7440-70-2	
Magnesium	16.9	mg/L	0.050	0.012	1	08/24/24 09:57	08/25/24 18:19	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/23/24 10:30	08/26/24 22:16	7440-36-0	
Arsenic	0.26	mg/L	0.0050	0.00084	1	08/23/24 10:30	08/26/24 22:16	7440-38-2	
Barium	0.043	mg/L	0.0050	0.00047	1	08/23/24 10:30	08/26/24 22:16	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/23/24 10:30	08/26/24 22:16	7440-41-7	
Boron	0.52	mg/L	0.040	0.012	1	08/23/24 10:30	08/26/24 22:16	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	08/23/24 10:30	08/26/24 22:16	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/23/24 10:30	08/26/24 22:16	7440-47-3	
Cobalt	0.036	mg/L	0.0050	0.00032	1	08/23/24 10:30	08/26/24 22:16	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/23/24 10:30	08/26/24 22:16	7439-92-1	
Lithium	0.058	mg/L	0.030	0.0016	1	08/23/24 10:30	08/26/24 22:16	7439-93-2	
Molybdenum	0.00723	mg/L	0.010	0.00062	1	08/23/24 10:30	08/26/24 22:16	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/23/24 10:30	08/26/24 22:16	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/23/24 10:30	08/26/24 22:16	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/27/24 10:00	08/27/24 14:25	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	564	mg/L	25.0	25.0	1		08/21/24 16:27		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	118	mg/L	5.0	5.0	1		08/19/24 14:56		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/19/24 14:56		
Alkalinity, Total as CaCO ₃	118	mg/L	5.0	5.0	1		08/19/24 14:56		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/17/24 04:28	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	17.7	mg/L	1.0	0.60	1		08/17/24 19:10	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

Sample: HAM-PT-13		Lab ID: 92748254003		Collected: 08/14/24 16:55		Received: 08/16/24 12:50		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.28	mg/L	0.10	0.050	1		08/17/24 19:10	16984-48-8	
Sulfate	232	mg/L	6.0	3.0	6		08/18/24 01:51	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

Sample: HAM-PT-15		Lab ID: 92748254004		Collected: 08/14/24 13:30		Received: 08/16/24 12:50		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	12.8	mg/L	0.040	0.025	1	08/24/24 09:57	08/25/24 18:22	7439-89-6	
Manganese	5.5	mg/L	0.040	0.011	1	08/24/24 09:57	08/25/24 18:22	7439-96-5	
Potassium	5.3	mg/L	0.50	0.15	1	08/24/24 09:57	08/25/24 18:22	7440-09-7	
Sodium	8.1	mg/L	1.0	0.58	1	08/24/24 09:57	08/25/24 18:22	7440-23-5	
Calcium	123	mg/L	1.0	0.12	1	08/24/24 09:57	08/25/24 18:22	7440-70-2	
Magnesium	15.3	mg/L	0.050	0.012	1	08/24/24 09:57	08/25/24 18:22	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/23/24 10:30	08/26/24 22:27	7440-36-0	
Arsenic	0.42	mg/L	0.0050	0.00084	1	08/23/24 10:30	08/26/24 22:27	7440-38-2	
Barium	0.044	mg/L	0.0050	0.00047	1	08/23/24 10:30	08/26/24 22:27	7440-39-3	
Beryllium	0.000096J	mg/L	0.00050	0.000094	1	08/23/24 10:30	08/26/24 22:27	7440-41-7	
Boron	0.63	mg/L	0.040	0.012	1	08/23/24 10:30	08/26/24 22:27	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	08/23/24 10:30	08/26/24 22:27	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/23/24 10:30	08/26/24 22:27	7440-47-3	
Cobalt	0.061	mg/L	0.0050	0.00032	1	08/23/24 10:30	08/26/24 22:27	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/23/24 10:30	08/26/24 22:27	7439-92-1	
Lithium	0.052	mg/L	0.030	0.0016	1	08/23/24 10:30	08/26/24 22:27	7439-93-2	
Molybdenum	0.013	mg/L	0.010	0.00062	1	08/23/24 10:30	08/26/24 22:27	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/23/24 10:30	08/26/24 22:27	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/23/24 10:30	08/26/24 22:27	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/27/24 10:00	08/27/24 14:28	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	548	mg/L	25.0	25.0	1		08/21/24 16:27		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	128	mg/L	5.0	5.0	1		08/19/24 15:05		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/19/24 15:05		
Alkalinity, Total as CaCO3	128	mg/L	5.0	5.0	1		08/19/24 15:05		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/17/24 04:29	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	15.7	mg/L	1.0	0.60	1		08/17/24 19:24	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

Sample: HAM-PT-15		Lab ID: 92748254004		Collected: 08/14/24 13:30		Received: 08/16/24 12:50		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.29	mg/L	0.10	0.050	1		08/17/24 19:24	16984-48-8	
Sulfate	212	mg/L	5.0	2.5	5		08/18/24 02:05	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

Sample: HAM-AP1-FB-01 Lab ID: 92748254005 Collected: 08/15/24 14:45 Received: 08/16/24 12:50 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	08/24/24 09:57	08/25/24 18:25	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	08/24/24 09:57	08/25/24 18:25	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	08/24/24 09:57	08/25/24 18:25	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	08/24/24 09:57	08/25/24 18:25	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	08/24/24 09:57	08/25/24 18:25	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	08/24/24 09:57	08/25/24 18:25	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/28/24 09:51	08/28/24 16:21	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	08/28/24 09:51	08/28/24 16:21	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	08/28/24 09:51	08/28/24 16:21	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/28/24 09:51	08/28/24 16:21	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	08/28/24 09:51	08/28/24 16:21	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	08/28/24 09:51	08/28/24 16:21	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/28/24 09:51	08/28/24 16:21	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	08/28/24 09:51	08/28/24 16:21	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/28/24 09:51	08/28/24 16:21	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	08/28/24 09:51	08/28/24 16:21	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	08/28/24 09:51	08/28/24 16:21	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/28/24 09:51	08/28/24 16:21	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/28/24 09:51	08/28/24 16:21	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/27/24 10:00	08/27/24 14:31	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		08/22/24 16:15		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/21/24 19:33		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/21/24 19:33		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		08/21/24 19:33		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/17/24 04:39	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		08/17/24 14:50	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92748254

Sample: HAM-AP1-FB-01		Lab ID: 92748254005		Collected: 08/15/24 14:45		Received: 08/16/24 12:50		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		08/17/24 14:50	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		08/17/24 14:50	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

Sample: HAM-AP1-EB-01		Lab ID: 92748254006		Collected: 08/15/24 14:45		Received: 08/16/24 12:50		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	08/24/24 09:57	08/25/24 18:36	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	08/24/24 09:57	08/25/24 18:36	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	08/24/24 09:57	08/25/24 18:36	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	08/24/24 09:57	08/25/24 18:36	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	08/24/24 09:57	08/25/24 18:36	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	08/24/24 09:57	08/25/24 18:36	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/28/24 09:51	08/28/24 16:25	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	08/28/24 09:51	08/28/24 16:25	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	08/28/24 09:51	08/28/24 16:25	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/28/24 09:51	08/28/24 16:25	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	08/28/24 09:51	08/28/24 16:25	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	08/28/24 09:51	08/28/24 16:25	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/28/24 09:51	08/28/24 16:25	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	08/28/24 09:51	08/28/24 16:25	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/28/24 09:51	08/28/24 16:25	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	08/28/24 09:51	08/28/24 16:25	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	08/28/24 09:51	08/28/24 16:25	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/28/24 09:51	08/28/24 16:25	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/28/24 09:51	08/28/24 16:25	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/27/24 10:00	08/27/24 14:33	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	111	mg/L	25.0	25.0	1		08/22/24 16:16		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/21/24 19:37		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		08/21/24 19:37		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		08/21/24 19:37		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/17/24 04:39	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		08/17/24 15:04	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92748254

Sample: HAM-AP1-EB-01		Lab ID: 92748254006		Collected: 08/15/24 14:45		Received: 08/16/24 12:50		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		08/17/24 15:04	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		08/17/24 15:04	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

Sample: HAM-AP1-FD-01 Lab ID: 92748254007 Collected: 08/14/24 00:00 Received: 08/16/24 12:50 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	15.4	mg/L	0.040	0.025	1	08/24/24 09:57	08/25/24 18:40	7439-89-6	
Manganese	4.2	mg/L	0.040	0.011	1	08/24/24 09:57	08/25/24 18:40	7439-96-5	
Potassium	4.9	mg/L	0.50	0.15	1	08/24/24 09:57	08/25/24 18:40	7440-09-7	
Sodium	7.4	mg/L	1.0	0.58	1	08/24/24 09:57	08/25/24 18:40	7440-23-5	
Calcium	99.4	mg/L	1.0	0.12	1	08/24/24 09:57	08/25/24 18:40	7440-70-2	
Magnesium	13.8	mg/L	0.050	0.012	1	08/24/24 09:57	08/25/24 18:40	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	08/23/24 10:30	08/26/24 22:42	7440-36-0	
Arsenic	0.29	mg/L	0.0050	0.00084	1	08/23/24 10:30	08/26/24 22:42	7440-38-2	
Barium	0.048	mg/L	0.0050	0.00047	1	08/23/24 10:30	08/26/24 22:42	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	08/23/24 10:30	08/26/24 22:42	7440-41-7	
Boron	0.63	mg/L	0.040	0.012	1	08/23/24 10:30	08/26/24 22:42	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	08/23/24 10:30	08/26/24 22:42	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	08/23/24 10:30	08/26/24 22:42	7440-47-3	
Cobalt	0.082	mg/L	0.0050	0.00032	1	08/23/24 10:30	08/26/24 22:42	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	08/23/24 10:30	08/26/24 22:42	7439-92-1	
Lithium	0.024J	mg/L	0.030	0.0016	1	08/23/24 10:30	08/26/24 22:42	7439-93-2	
Molybdenum	0.011	mg/L	0.010	0.00062	1	08/23/24 10:30	08/26/24 22:42	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	08/23/24 10:30	08/26/24 22:42	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	08/23/24 10:30	08/26/24 22:42	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	08/27/24 10:00	08/27/24 14:36	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	469	mg/L	25.0	25.0	1		08/22/24 16:16		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	101	mg/L	5.0	5.0	1		08/21/24 19:41		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		08/21/24 19:41		
Alkalinity, Total as CaCO3	101	mg/L	5.0	5.0	1		08/21/24 19:41		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		08/17/24 04:40	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	16.7	mg/L	1.0	0.60	1		08/17/24 19:39	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

Sample: HAM-AP1-FD-01		Lab ID: 92748254007		Collected: 08/14/24 00:00		Received: 08/16/24 12:50		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.14	mg/L	0.10	0.050	1		08/17/24 19:39	16984-48-8	
Sulfate	201	mg/L	5.0	2.5	5		08/18/24 02:19	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92748254

QC Batch:	877559	Analysis Method:	EPA 6010D
QC Batch Method:	EPA 3010A	Analysis Description:	6010D ATL
Associated Lab Samples:	92748254001	Laboratory:	Pace Analytical Services - Peachtree Corners, GA

METHOD BLANK: 4520288 Matrix: Water
Associated Lab Samples: 92748254001

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	08/23/24 01:31	
Iron	mg/L	ND	0.040	0.025	08/23/24 01:31	
Magnesium	mg/L	ND	0.050	0.012	08/23/24 01:31	
Manganese	mg/L	ND	0.040	0.011	08/23/24 01:31	
Potassium	mg/L	ND	0.50	0.15	08/25/24 16:35	
Sodium	mg/L	ND	1.0	0.58	08/25/24 16:35	

LABORATORY CONTROL SAMPLE: 4520289

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	1.2	116	80-120	
Iron	mg/L	1	1.1	115	80-120	
Magnesium	mg/L	1	1.2	118	80-120	
Manganese	mg/L	1	1.1	112	80-120	
Potassium	mg/L	1	1.1	111	80-120	
Sodium	mg/L	1	1.1	113	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4520290 4520291

Parameter	Units	92746783026 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Calcium	mg/L	9.2	1	1	10.3	10.4	103	119	75-125	1	20	
Iron	mg/L	0.45	1	1	1.1	1.1	68	68	75-125	0	20	M1
Magnesium	mg/L	4.8	1	1	6.0	6.2	116	131	75-125	3	20	M1
Manganese	mg/L	0.016J	1	1	1.1	1.2	106	114	75-125	7	20	
Potassium	mg/L	0.67	1	1	1.8	1.8	111	111	75-125	0	20	
Sodium	mg/L	3.3	1	1	4.5	4.6	118	126	75-125	2	20	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

QC Batch: 878059 Analysis Method: EPA 6010D
QC Batch Method: EPA 3010A Analysis Description: 6010D ATL
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92748254002, 92748254003, 92748254004, 92748254005, 92748254006, 92748254007

METHOD BLANK: 4522961 Matrix: Water
Associated Lab Samples: 92748254002, 92748254003, 92748254004, 92748254005, 92748254006, 92748254007

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	08/25/24 18:09	
Iron	mg/L	ND	0.040	0.025	08/25/24 18:09	
Magnesium	mg/L	ND	0.050	0.012	08/25/24 18:09	
Manganese	mg/L	ND	0.040	0.011	08/25/24 18:09	
Potassium	mg/L	ND	0.50	0.15	08/25/24 18:09	
Sodium	mg/L	ND	1.0	0.58	08/25/24 18:09	

LABORATORY CONTROL SAMPLE: 4522962

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	1.1	108	80-120	
Iron	mg/L	1	1.1	107	80-120	
Magnesium	mg/L	1	1.1	107	80-120	
Manganese	mg/L	1	1.0	102	80-120	
Potassium	mg/L	1	0.96	96	80-120	
Sodium	mg/L	1	1.1	112	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4522980 4522981

Parameter	Units	92748919006 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Calcium	mg/L	ND	1	1	1.6	1.6	107	103	75-125	3	20	
Iron	mg/L	221 ug/L	1	1	1.3	1.3	109	106	75-125	3	20	
Magnesium	mg/L	412 ug/L	1	1	1.5	1.5	107	105	75-125	2	20	
Manganese	mg/L	ND	1	1	1.0	1.0	103	100	75-125	3	20	
Potassium	mg/L	1590 ug/L	1	1	2.6	2.6	104	100	75-125	2	20	
Sodium	mg/L	6150 ug/L	1	1	7.4	7.3	128	117	75-125	2	20 M1	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92748254

QC Batch: 877798 Analysis Method: EPA 6020B
QC Batch Method: EPA 3005A Analysis Description: 6020 MET
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92748254001, 92748254002, 92748254003, 92748254004, 92748254007

METHOD BLANK: 4521510 Matrix: Water
Associated Lab Samples: 92748254001, 92748254002, 92748254003, 92748254004, 92748254007

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00054	08/26/24 20:58	
Arsenic	mg/L	ND	0.0050	0.00084	08/26/24 20:58	
Barium	mg/L	ND	0.0050	0.00047	08/26/24 20:58	
Beryllium	mg/L	ND	0.00050	0.000094	08/26/24 20:58	
Boron	mg/L	ND	0.040	0.012	08/26/24 20:58	
Cadmium	mg/L	ND	0.00050	0.00010	08/26/24 20:58	
Chromium	mg/L	ND	0.0050	0.0019	08/26/24 20:58	
Cobalt	mg/L	ND	0.0050	0.00032	08/26/24 20:58	
Lead	mg/L	ND	0.0010	0.00016	08/26/24 20:58	
Lithium	mg/L	ND	0.030	0.0016	08/26/24 20:58	
Molybdenum	mg/L	ND	0.010	0.00062	08/26/24 20:58	
Selenium	mg/L	ND	0.0050	0.00096	08/26/24 20:58	
Thallium	mg/L	ND	0.0010	0.00038	08/26/24 20:58	

LABORATORY CONTROL SAMPLE: 4521511

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.10	102	80-120	
Arsenic	mg/L	0.1	0.098	98	80-120	
Barium	mg/L	0.1	0.096	96	80-120	
Beryllium	mg/L	0.1	0.10	102	80-120	
Boron	mg/L	1	1.0	102	80-120	
Cadmium	mg/L	0.1	0.097	97	80-120	
Chromium	mg/L	0.1	0.098	98	80-120	
Cobalt	mg/L	0.1	0.097	97	80-120	
Lead	mg/L	0.1	0.10	100	80-120	
Lithium	mg/L	0.1	0.11	105	80-120	
Molybdenum	mg/L	0.1	0.10	101	80-120	
Selenium	mg/L	0.1	0.098	98	80-120	
Thallium	mg/L	0.1	0.096	96	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4521512 4521513

Parameter	Units	92748119003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	ND	0.1	0.1	0.097	0.098	97	98	75-125	1	20	
Arsenic	mg/L	0.0013J	0.1	0.1	0.099	0.099	97	98	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:			4521512		4521513							
Parameter	Units	92748119003	MS	MSD	MS	MSD	MS	MSD	% Rec	RPD	Max	Qual
		Result	Spike	Spike								
Barium	mg/L	0.041	0.1	0.1	0.13	0.13	93	93	75-125	0	20	
Beryllium	mg/L	ND	0.1	0.1	0.10	0.10	100	100	75-125	0	20	
Boron	mg/L	0.35	1	1	1.3	1.3	99	97	75-125	1	20	
Cadmium	mg/L	ND	0.1	0.1	0.094	0.095	94	95	75-125	2	20	
Chromium	mg/L	ND	0.1	0.1	0.098	0.098	97	98	75-125	0	20	
Cobalt	mg/L	ND	0.1	0.1	0.093	0.095	93	95	75-125	2	20	
Lead	mg/L	ND	0.1	0.1	0.094	0.096	94	96	75-125	2	20	
Lithium	mg/L	ND	0.1	0.1	0.10	0.10	103	104	75-125	2	20	
Molybdenum	mg/L	ND	0.1	0.1	0.098	0.098	98	98	75-125	0	20	
Selenium	mg/L	ND	0.1	0.1	0.096	0.097	95	96	75-125	1	20	
Thallium	mg/L	ND	0.1	0.1	0.092	0.093	91	93	75-125	2	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92748254

QC Batch: 878757 Analysis Method: EPA 6020B
QC Batch Method: EPA 3005A Analysis Description: 6020 MET
Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92748254005, 92748254006

METHOD BLANK: 4526083 Matrix: Water

Associated Lab Samples: 92748254005, 92748254006

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00054	08/28/24 16:12	
Arsenic	mg/L	ND	0.0050	0.00084	08/28/24 16:12	
Barium	mg/L	ND	0.0050	0.00047	08/28/24 16:12	
Beryllium	mg/L	ND	0.00050	0.000094	08/28/24 16:12	
Boron	mg/L	ND	0.040	0.012	08/28/24 16:12	
Cadmium	mg/L	ND	0.00050	0.00010	08/28/24 16:12	
Chromium	mg/L	ND	0.0050	0.0019	08/28/24 16:12	
Cobalt	mg/L	ND	0.0050	0.00032	08/28/24 16:12	
Lead	mg/L	ND	0.0010	0.00016	08/28/24 16:12	
Lithium	mg/L	ND	0.030	0.0016	08/28/24 16:12	
Molybdenum	mg/L	ND	0.010	0.00062	08/28/24 16:12	
Selenium	mg/L	ND	0.0050	0.00096	08/28/24 16:12	
Thallium	mg/L	ND	0.0010	0.00038	08/28/24 16:12	

LABORATORY CONTROL SAMPLE: 4526084

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.11	106	80-120	
Arsenic	mg/L	0.1	0.099	99	80-120	
Barium	mg/L	0.1	0.11	107	80-120	
Beryllium	mg/L	0.1	0.10	101	80-120	
Boron	mg/L	1	1.1	111	80-120	
Cadmium	mg/L	0.1	0.10	102	80-120	
Chromium	mg/L	0.1	0.10	102	80-120	
Cobalt	mg/L	0.1	0.098	98	80-120	
Lead	mg/L	0.1	0.10	103	80-120	
Lithium	mg/L	0.1	0.11	107	80-120	
Molybdenum	mg/L	0.1	0.11	110	80-120	
Selenium	mg/L	0.1	0.10	102	80-120	
Thallium	mg/L	0.1	0.099	99	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4526085 4526086

Parameter	Units	92749319036 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	ND	0.1	0.1	0.11	0.10	109	104	75-125	4	20	
Arsenic	mg/L	ND	0.1	0.1	0.10	0.10	101	101	75-125	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:			4526085		4526086							
Parameter	Units	92749319036	MS	MSD	MS	MSD	MS	MSD	% Rec	RPD	Max	Qual
		Result	Spike	Spike								
Barium	mg/L	25.1 ug/L	0.1	0.1	0.14	0.13	110	108	75-125	2	20	
Beryllium	mg/L	ND	0.1	0.1	0.11	0.099	105	99	75-125	6	20	
Boron	mg/L	ND	1	1	1.1	1.1	105	105	75-125	0	20	
Cadmium	mg/L	ND	0.1	0.1	0.10	0.10	104	100	75-125	5	20	
Chromium	mg/L	ND	0.1	0.1	0.10	0.10	101	102	75-125	1	20	
Cobalt	mg/L	ND	0.1	0.1	0.10	0.10	100	101	75-125	1	20	
Lead	mg/L	ND	0.1	0.1	0.10	0.10	100	100	75-125	1	20	
Lithium	mg/L	ND	0.1	0.1	0.10	0.10	104	100	75-125	4	20	
Molybdenum	mg/L	ND	0.1	0.1	0.11	0.11	109	107	75-125	3	20	
Selenium	mg/L	ND	0.1	0.1	0.10	0.099	103	98	75-125	5	20	
Thallium	mg/L	ND	0.1	0.1	0.095	0.096	95	96	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92748254

QC Batch:	878334	Analysis Method:	EPA 7470A
QC Batch Method:	EPA 7470A	Analysis Description:	7470 Mercury
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92748254001, 92748254002, 92748254003, 92748254004, 92748254005, 92748254006, 92748254007

METHOD BLANK: 4524107 Matrix: Water
Associated Lab Samples: 92748254001, 92748254002, 92748254003, 92748254004, 92748254005, 92748254006, 92748254007

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	08/27/24 13:22	

LABORATORY CONTROL SAMPLE: 4524108

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0027	109	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4524109 4524110

Parameter	Units	92748048013 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.0025	0.0025	0.0024	0.0023	93	91	75-125	2	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

QC Batch:	877174	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92748254001, 92748254002, 92748254003, 92748254004

METHOD BLANK: 4518022 Matrix: Water

Associated Lab Samples: 92748254001, 92748254002, 92748254003, 92748254004

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	08/21/24 16:23	

LABORATORY CONTROL SAMPLE: 4518023

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	392	98	80-120	

SAMPLE DUPLICATE: 4518024

Parameter	Units	92748019001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	373	350	6	10	

SAMPLE DUPLICATE: 4518025

Parameter	Units	92748119002 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	245	255	4	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92748254

QC Batch: 877482 Analysis Method: SM 2540C-2015
QC Batch Method: SM 2540C-2015 Analysis Description: 2540C Total Dissolved Solids
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92748254005, 92748254006, 92748254007

METHOD BLANK: 4519828 Matrix: Water
Associated Lab Samples: 92748254005, 92748254006, 92748254007

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	08/22/24 16:13	

LABORATORY CONTROL SAMPLE: 4519829

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	343	86	80-120	

SAMPLE DUPLICATE: 4519830

Parameter	Units	92748251006 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	1290	1270	1	10	

SAMPLE DUPLICATE: 4519831

Parameter	Units	92748515001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	160	176	10	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92748254

QC Batch: 876583 Analysis Method: SM 2320B-2011
QC Batch Method: SM 2320B-2011 Analysis Description: 2320B Alkalinity
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92748254001, 92748254002, 92748254003, 92748254004

METHOD BLANK: 4515214 Matrix: Water
Associated Lab Samples: 92748254001, 92748254002, 92748254003, 92748254004

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	08/19/24 12:19	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	08/19/24 12:19	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	08/19/24 12:19	

LABORATORY CONTROL SAMPLE: 4515215

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.1	104	80-120	

LABORATORY CONTROL SAMPLE: 4515216

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	53.1	106	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4515217 4515218

Parameter	Units	92748115002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	25.9	50	50	75.6	75.2	99	99	80-120	0	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4515219 4515220

Parameter	Units	92748115004 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	25.4	50	50	71.8	79.2	93	108	80-120	10	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92748254

QC Batch: 877163 Analysis Method: SM 2320B-2011
QC Batch Method: SM 2320B-2011 Analysis Description: 2320B Alkalinity
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92748254005, 92748254006, 92748254007

METHOD BLANK: 4517979 Matrix: Water
Associated Lab Samples: 92748254005, 92748254006, 92748254007

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	08/21/24 17:18	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	08/21/24 17:18	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	08/21/24 17:18	

LABORATORY CONTROL SAMPLE: 4517980

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.6	103	80-120	

LABORATORY CONTROL SAMPLE: 4517981

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.6	105	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4517982 4517983

Parameter	Units	92748629001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	ND	50	50	ND	ND	7	9	80-120		25	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4517984 4517985

Parameter	Units	92748455001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	22.5	50	50	71.9	71.9	99	99	80-120	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92748254

QC Batch:	876390	Analysis Method:	SM 4500-S2D-2011
QC Batch Method:	SM 4500-S2D-2011	Analysis Description:	4500S2D Sulfide Water
		Laboratory:	Pace Analytical Services - Asheville

Associated Lab Samples: 92748254001, 92748254002, 92748254003, 92748254004, 92748254005, 92748254006, 92748254007

METHOD BLANK: 4514671 Matrix: Water
Associated Lab Samples: 92748254001, 92748254002, 92748254003, 92748254004, 92748254005, 92748254006, 92748254007

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	08/17/24 04:24	

LABORATORY CONTROL SAMPLE: 4514672

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.51	102	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4514673 4514674

Parameter	Units	92748254001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.49	0.50	98	100	80-120	3	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4514675 4514676

Parameter	Units	92748251006 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.48	0.51	95	102	80-120	6	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92748254

QC Batch: 876425 Analysis Method: EPA 300.0 Rev 2.1 1993
QC Batch Method: EPA 300.0 Rev 2.1 1993 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92748254001, 92748254002, 92748254003, 92748254004, 92748254005, 92748254006, 92748254007

METHOD BLANK: 4514777 Matrix: Water
Associated Lab Samples: 92748254001, 92748254002, 92748254003, 92748254004, 92748254005, 92748254006, 92748254007

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	08/17/24 12:54	
Fluoride	mg/L	ND	0.10	0.050	08/17/24 12:54	
Sulfate	mg/L	ND	1.0	0.50	08/17/24 12:54	

LABORATORY CONTROL SAMPLE: 4514778

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	50.2	100	90-110	
Fluoride	mg/L	2.5	2.5	101	90-110	
Sulfate	mg/L	50	50.2	100	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4514779 4514780

Parameter	Units	92746783031 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	3.6	50	50	51.8	57.7	96	108	90-110	11	10	R1
Fluoride	mg/L	ND	2.5	2.5	2.3	2.6	93	105	90-110	13	10	R1
Sulfate	mg/L	7.5	50	50	55.7	61.7	96	109	90-110	10	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4514781 4514782

Parameter	Units	92748251008 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	ND	50	50	49.4	51.7	99	103	90-110	5	10	
Fluoride	mg/L	ND	2.5	2.5	2.5	2.6	100	103	90-110	2	10	
Sulfate	mg/L	ND	50	50	49.3	51.5	99	103	90-110	4	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92748254

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.
R1 RPD value was outside control limits.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1 (CA)-20240812

Pace Project No.: 92748254

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92748254001	HAM-PT-07	EPA 3010A	877559	EPA 6010D	877624
92748254002	HAM-PT-08	EPA 3010A	878059	EPA 6010D	878092
92748254003	HAM-PT-13	EPA 3010A	878059	EPA 6010D	878092
92748254004	HAM-PT-15	EPA 3010A	878059	EPA 6010D	878092
92748254005	HAM-AP1-FB-01	EPA 3010A	878059	EPA 6010D	878092
92748254006	HAM-AP1-EB-01	EPA 3010A	878059	EPA 6010D	878092
92748254007	HAM-AP1-FD-01	EPA 3010A	878059	EPA 6010D	878092
92748254001	HAM-PT-07	EPA 3005A	877798	EPA 6020B	877921
92748254002	HAM-PT-08	EPA 3005A	877798	EPA 6020B	877921
92748254003	HAM-PT-13	EPA 3005A	877798	EPA 6020B	877921
92748254004	HAM-PT-15	EPA 3005A	877798	EPA 6020B	877921
92748254005	HAM-AP1-FB-01	EPA 3005A	878757	EPA 6020B	878909
92748254006	HAM-AP1-EB-01	EPA 3005A	878757	EPA 6020B	878909
92748254007	HAM-AP1-FD-01	EPA 3005A	877798	EPA 6020B	877921
92748254001	HAM-PT-07	EPA 7470A	878334	EPA 7470A	878506
92748254002	HAM-PT-08	EPA 7470A	878334	EPA 7470A	878506
92748254003	HAM-PT-13	EPA 7470A	878334	EPA 7470A	878506
92748254004	HAM-PT-15	EPA 7470A	878334	EPA 7470A	878506
92748254005	HAM-AP1-FB-01	EPA 7470A	878334	EPA 7470A	878506
92748254006	HAM-AP1-EB-01	EPA 7470A	878334	EPA 7470A	878506
92748254007	HAM-AP1-FD-01	EPA 7470A	878334	EPA 7470A	878506
92748254001	HAM-PT-07	SM 2540C-2015	877174		
92748254002	HAM-PT-08	SM 2540C-2015	877174		
92748254003	HAM-PT-13	SM 2540C-2015	877174		
92748254004	HAM-PT-15	SM 2540C-2015	877174		
92748254005	HAM-AP1-FB-01	SM 2540C-2015	877482		
92748254006	HAM-AP1-EB-01	SM 2540C-2015	877482		
92748254007	HAM-AP1-FD-01	SM 2540C-2015	877482		
92748254001	HAM-PT-07	SM 2320B-2011	876583		
92748254002	HAM-PT-08	SM 2320B-2011	876583		
92748254003	HAM-PT-13	SM 2320B-2011	876583		
92748254004	HAM-PT-15	SM 2320B-2011	876583		
92748254005	HAM-AP1-FB-01	SM 2320B-2011	877163		
92748254006	HAM-AP1-EB-01	SM 2320B-2011	877163		
92748254007	HAM-AP1-FD-01	SM 2320B-2011	877163		
92748254001	HAM-PT-07	SM 4500-S2D-2011	876390		
92748254002	HAM-PT-08	SM 4500-S2D-2011	876390		
92748254003	HAM-PT-13	SM 4500-S2D-2011	876390		
92748254004	HAM-PT-15	SM 4500-S2D-2011	876390		
92748254005	HAM-AP1-FB-01	SM 4500-S2D-2011	876390		
92748254006	HAM-AP1-EB-01	SM 4500-S2D-2011	876390		
92748254007	HAM-AP1-FD-01	SM 4500-S2D-2011	876390		
92748254001	HAM-PT-07	EPA 300.0 Rev 2.1 1993	876425		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1 (CA)-20240812
Pace Project No.: 92748254

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92748254002	HAM-PT-08	EPA 300.0 Rev 2.1 1993	876425		
92748254003	HAM-PT-13	EPA 300.0 Rev 2.1 1993	876425		
92748254004	HAM-PT-15	EPA 300.0 Rev 2.1 1993	876425		
92748254005	HAM-AP1-FB-01	EPA 300.0 Rev 2.1 1993	876425		
92748254006	HAM-AP1-EB-01	EPA 300.0 Rev 2.1 1993	876425		
92748254007	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	876425		


REPORT OF LABORATORY ANALYSIS



Effective Date: 05/24/2024

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐



Client Name:

GA Power Geosynthetic

Project #:

WO#: 92748254



Courier:

☐ Commercial

☐ Fed Ex

☐ UPS

☐ USPS

☐ Client

☐ Pace

☐ Other:

Custody Seal Present?

☒ Yes

☐ No

Seals Intact?

☐ Yes

☐ No

☐ N/A

Date/Initials Person Examining Contents: 5/16/24 DW

Packing Material:

☒ Bubble Wrap

☐ Bubble Bags

☐ None

☐ Other

Biological Tissue Frozen?

☐ Yes

☐ No

☒ N/A

Thermometer:

☐ IR Gun ID:

230

Type of Ice:

☒ Wet

☐ Blue

☐ None

Cooler Temp:

4.0

Correction Factor:

Add/Subtract (°C)

0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

4.0

USDA Regulated Soil (☐ N/A, water sample)

Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ No

Did samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

				Comments/Discrepancy:
Chain of Custody Present?	☒ Yes	☐ No	☐ N/A	1.
Samples Arrived within Hold Time?	☒ Yes	☐ No	☐ N/A	2.
Short Hold Time Analysis (<72 hr.)?	☒ Yes	☐ No	☐ N/A	3.
Rush Turn Around Time Requested?	☐ Yes	☒ No	☐ N/A	4.
Sufficient Volume?	☒ Yes	☐ No	☐ N/A	5.
Correct Containers Used?	☒ Yes	☐ No	☐ N/A	6.
-Pace Containers Used?	☒ Yes	☐ No	☐ N/A	
Containers Intact?	☒ Yes	☐ No	☐ N/A	7.
Dissolved analysis: Samples Field Filtered?	☐ Yes	☒ No	☐ N/A	8.
Sample Labels Match COC?	☒ Yes	☐ No	☐ N/A	9.
-Includes Date/Time/ID/Analysis Matrix: WGWQ				
Headspace in VOA Vials (>5-6mm)?	☐ Yes	☐ No	☒ N/A	10.
Trip Blank Present?	☐ Yes	☐ No	☒ N/A	11.
Trip Blank Custody Seals Present?	☐ Yes	☐ No	☒ N/A	

Field Data Required? ☐ Yes ☐ No

COMMENTS/SAMPLE DISCREPANCY

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:

Qualtrax ID: 69614

Page 1 of 2



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

WO#: 92748254

Project #

PM: BV

Due Date: 08/30/24

CLIENT: 92- GP-HAM

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐

Client: GA Power Profile/EZ (Circle one) 10539 Notes


Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)		BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic 2N Acetate & NaOH (.99)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGFU-Wide-mouthed Glass Jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG94-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit)-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)		BP3R-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	VSGU-20 mL Scintillation vials (N/A)	
CC																													
1		2	1																										
2		2	1																										
3		2	1																										
4		2	1																										
5		2	1																										
6		2	1																										
7		2	1																										
8																													
9																													
10																													
11																													
12																													

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers).

PM: BV Due Date: 08/30/24
CLIENT: 92- GP-HAM

Page 41 of 41



September 05, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1 (CA)-20240820
Pace Project No.: 92749180

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on August 22, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Peachtree Corners, GA

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Jamie Newsome, Geosyntec Consultants
Zain Webb, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1 (CA)-20240820

Pace Project No.: 92749180

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1 (CA)-20240820

Pace Project No.: 92749180

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92749180001	HAM-PT-07	Water	08/20/24 15:55	08/22/24 12:15
92749180002	HAM-PT-08	Water	08/20/24 13:24	08/22/24 12:15
92749180003	HAM-PT-09	Water	08/21/24 16:04	08/22/24 12:15
92749180004	HAM-PT-10	Water	08/20/24 16:44	08/22/24 12:15
92749180005	HAM-PT-11	Water	08/21/24 12:43	08/22/24 12:15
92749180006	HAM-PT-12	Water	08/21/24 12:55	08/22/24 12:15
92749180007	HAM-PT-13	Water	08/20/24 11:54	08/22/24 12:15
92749180008	HAM-PT-14	Water	08/20/24 12:03	08/22/24 12:15
92749180009	HAM-PT-15	Water	08/20/24 13:25	08/22/24 12:15
92749180010	HAM-AP1-EB-01	Water	08/21/24 14:20	08/22/24 12:15
92749180011	HAM-AP1-FB-01	Water	08/21/24 14:27	08/22/24 12:15
92749180012	HAM-AP1-FD-01	Water	08/20/24 00:00	08/22/24 12:15

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1 (CA)-20240820

Pace Project No.: 92749180

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92749180001	HAM-PT-07	EPA 6010D	DRB	1
		EPA 6020B	CW1	2
92749180002	HAM-PT-08	EPA 6010D	DRB	1
		EPA 6020B	CW1	2
92749180003	HAM-PT-09	EPA 6010D	DRB	1
		EPA 6020B	CW1	2
92749180004	HAM-PT-10	EPA 6010D	DRB	1
		EPA 6020B	CW1	2
92749180005	HAM-PT-11	EPA 6010D	DRB	1
		EPA 6020B	CW1	2
92749180006	HAM-PT-12	EPA 6010D	DRB	1
		EPA 6020B	CW1	2
92749180007	HAM-PT-13	EPA 6010D	DRB	1
		EPA 6020B	CW1	2
92749180008	HAM-PT-14	EPA 6010D	DRB	1
		EPA 6020B	CW1	2
92749180009	HAM-PT-15	EPA 6010D	DRB	1
		EPA 6020B	CW1	2
92749180010	HAM-AP1-EB-01	EPA 6010D	DRB	1
		EPA 6020B	CW1	3
92749180011	HAM-AP1-FB-01	EPA 6010D	DRB	1
		EPA 6020B	CW1	3
92749180012	HAM-AP1-FD-01	EPA 6010D	DRB	1
		EPA 6020B	CW1	3

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)-20240820
Pace Project No.: 92749180

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92749180001	HAM-PT-07					
EPA 6010D	Iron	17.9	mg/L	0.040	08/26/24 08:45	
EPA 6020B	Arsenic	0.26	mg/L	0.0050	08/30/24 19:16	
EPA 6020B	Boron	0.57	mg/L	0.040	08/30/24 19:16	
92749180002	HAM-PT-08					
EPA 6010D	Iron	14.8	mg/L	0.040	08/26/24 08:55	
EPA 6020B	Arsenic	0.29	mg/L	0.0050	08/30/24 19:27	
EPA 6020B	Boron	0.63	mg/L	0.040	08/30/24 19:27	
92749180003	HAM-PT-09					
EPA 6010D	Iron	0.23	mg/L	0.040	08/26/24 08:58	
EPA 6020B	Boron	1.3	mg/L	0.040	08/30/24 19:31	
EPA 6020B	Molybdenum	0.24	mg/L	0.010	08/30/24 19:31	
92749180004	HAM-PT-10					
EPA 6010D	Iron	0.18	mg/L	0.040	08/26/24 09:01	
EPA 6020B	Boron	1.7	mg/L	0.040	08/30/24 19:34	
EPA 6020B	Molybdenum	0.16	mg/L	0.010	08/30/24 19:34	
92749180005	HAM-PT-11					
EPA 6010D	Iron	0.10	mg/L	0.040	08/26/24 09:05	
EPA 6020B	Boron	1.5	mg/L	0.040	08/30/24 19:38	
EPA 6020B	Molybdenum	0.12	mg/L	0.010	08/30/24 19:38	
92749180006	HAM-PT-12					
EPA 6010D	Iron	0.078	mg/L	0.040	08/26/24 09:09	
EPA 6020B	Boron	1.2	mg/L	0.040	08/30/24 19:42	
EPA 6020B	Molybdenum	0.21	mg/L	0.010	08/30/24 19:42	
92749180007	HAM-PT-13					
EPA 6010D	Iron	21.6	mg/L	0.040	08/26/24 09:13	
EPA 6020B	Arsenic	0.25	mg/L	0.0050	08/30/24 19:46	
EPA 6020B	Boron	0.54	mg/L	0.040	08/30/24 19:46	
92749180008	HAM-PT-14					
EPA 6010D	Iron	17.7	mg/L	0.040	08/26/24 09:16	
EPA 6020B	Arsenic	0.23	mg/L	0.0050	08/30/24 19:49	
EPA 6020B	Boron	0.59	mg/L	0.040	08/30/24 19:49	
92749180009	HAM-PT-15					
EPA 6010D	Iron	13.3	mg/L	0.040	08/26/24 09:19	
EPA 6020B	Arsenic	0.42	mg/L	0.0050	08/30/24 19:53	
EPA 6020B	Boron	0.63	mg/L	0.040	08/30/24 19:53	
92749180010	HAM-AP1-EB-01					
EPA 6020B	Boron	0.013J	mg/L	0.040	08/30/24 19:57	
92749180012	HAM-AP1-FD-01					
EPA 6010D	Iron	13.0	mg/L	0.040	08/26/24 09:37	
EPA 6020B	Arsenic	0.42	mg/L	0.0050	08/30/24 20:11	
EPA 6020B	Boron	0.62	mg/L	0.040	08/30/24 20:11	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)-20240820
Pace Project No.: 92749180

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92749180012	HAM-AP1-FD-01					
EPA 6020B	Molybdenum	0.013	mg/L	0.010	08/30/24 20:11	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240820

Pace Project No.: 92749180

Sample: HAM-PT-07		Lab ID: 92749180001		Collected: 08/20/24 15:55		Received: 08/22/24 12:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	17.9	mg/L	0.040	0.025	1	08/24/24 12:03	08/26/24 08:45	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.26	mg/L	0.0050	0.00084	1	08/24/24 14:01	08/30/24 19:16	7440-38-2	
Boron	0.57	mg/L	0.040	0.012	1	08/24/24 14:01	08/30/24 19:16	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240820

Pace Project No.: 92749180

Sample: HAM-PT-08		Lab ID: 92749180002		Collected: 08/20/24 13:24		Received: 08/22/24 12:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	14.8	mg/L	0.040	0.025	1	08/24/24 12:03	08/26/24 08:55	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.29	mg/L	0.0050	0.00084	1	08/24/24 14:01	08/30/24 19:27	7440-38-2	
Boron	0.63	mg/L	0.040	0.012	1	08/24/24 14:01	08/30/24 19:27	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240820

Pace Project No.: 92749180

Sample: HAM-PT-09		Lab ID: 92749180003		Collected: 08/21/24 16:04		Received: 08/22/24 12:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.23	mg/L	0.040	0.025	1	08/24/24 12:03	08/26/24 08:58	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.3	mg/L	0.040	0.012	1	08/24/24 14:01	08/30/24 19:31	7440-42-8	
Molybdenum	0.24	mg/L	0.010	0.00062	1	08/24/24 14:01	08/30/24 19:31	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240820

Pace Project No.: 92749180

Sample: HAM-PT-10		Lab ID: 92749180004		Collected: 08/20/24 16:44		Received: 08/22/24 12:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.18	mg/L	0.040	0.025	1	08/24/24 12:03	08/26/24 09:01	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.7	mg/L	0.040	0.012	1	08/24/24 14:01	08/30/24 19:34	7440-42-8	
Molybdenum	0.16	mg/L	0.010	0.00062	1	08/24/24 14:01	08/30/24 19:34	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240820

Pace Project No.: 92749180

Sample: HAM-PT-11		Lab ID: 92749180005		Collected: 08/21/24 12:43		Received: 08/22/24 12:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.10	mg/L	0.040	0.025	1	08/24/24 12:03	08/26/24 09:05	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.5	mg/L	0.040	0.012	1	08/24/24 14:01	08/30/24 19:38	7440-42-8	
Molybdenum	0.12	mg/L	0.010	0.00062	1	08/24/24 14:01	08/30/24 19:38	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240820

Pace Project No.: 92749180

Sample: HAM-PT-12		Lab ID: 92749180006		Collected: 08/21/24 12:55		Received: 08/22/24 12:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.078	mg/L	0.040	0.025	1	08/24/24 12:03	08/26/24 09:09	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.2	mg/L	0.040	0.012	1	08/24/24 14:01	08/30/24 19:42	7440-42-8	
Molybdenum	0.21	mg/L	0.010	0.00062	1	08/24/24 14:01	08/30/24 19:42	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240820

Pace Project No.: 92749180

Sample: HAM-PT-13		Lab ID: 92749180007		Collected: 08/20/24 11:54		Received: 08/22/24 12:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	21.6	mg/L	0.040	0.025	1	08/24/24 12:03	08/26/24 09:13	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.25	mg/L	0.0050	0.00084	1	08/24/24 14:01	08/30/24 19:46	7440-38-2	
Boron	0.54	mg/L	0.040	0.012	1	08/24/24 14:01	08/30/24 19:46	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240820

Pace Project No.: 92749180

Sample: HAM-PT-14		Lab ID: 92749180008		Collected: 08/20/24 12:03		Received: 08/22/24 12:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	17.7	mg/L	0.040	0.025	1	08/24/24 12:03	08/26/24 09:16	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.23	mg/L	0.0050	0.00084	1	08/24/24 14:01	08/30/24 19:49	7440-38-2	
Boron	0.59	mg/L	0.040	0.012	1	08/24/24 14:01	08/30/24 19:49	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240820

Pace Project No.: 92749180

Sample: HAM-PT-15		Lab ID: 92749180009		Collected: 08/20/24 13:25		Received: 08/22/24 12:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	13.3	mg/L	0.040	0.025	1	08/24/24 12:03	08/26/24 09:19	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.42	mg/L	0.0050	0.00084	1	08/24/24 14:01	08/30/24 19:53	7440-38-2	
Boron	0.63	mg/L	0.040	0.012	1	08/24/24 14:01	08/30/24 19:53	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240820

Pace Project No.: 92749180

Sample: HAM-AP1-EB-01		Lab ID: 92749180010		Collected: 08/21/24 14:20		Received: 08/22/24 12:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	08/24/24 12:03	08/26/24 09:22	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	ND	mg/L	0.0050	0.00084	1	08/24/24 14:01	08/30/24 19:57	7440-38-2	
Boron	0.013J	mg/L	0.040	0.012	1	08/24/24 14:01	08/30/24 19:57	7440-42-8	
Molybdenum	ND	mg/L	0.010	0.00062	1	08/24/24 14:01	08/30/24 19:57	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240820

Pace Project No.: 92749180

Sample: HAM-AP1-FB-01		Lab ID: 92749180011		Collected: 08/21/24 14:27		Received: 08/22/24 12:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	08/24/24 12:03	08/26/24 09:26	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	ND	mg/L	0.0050	0.00084	1	08/24/24 14:01	08/30/24 20:00	7440-38-2	
Boron	ND	mg/L	0.040	0.012	1	08/24/24 14:01	08/30/24 20:00	7440-42-8	
Molybdenum	ND	mg/L	0.010	0.00062	1	08/24/24 14:01	08/30/24 20:00	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240820

Pace Project No.: 92749180

Sample: HAM-AP1-FD-01		Lab ID: 92749180012		Collected: 08/20/24 00:00		Received: 08/22/24 12:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	13.0	mg/L	0.040	0.025	1	08/24/24 12:03	08/26/24 09:37	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.42	mg/L	0.0050	0.00084	1	08/24/24 14:01	08/30/24 20:11	7440-38-2	
Boron	0.62	mg/L	0.040	0.012	1	08/24/24 14:01	08/30/24 20:11	7440-42-8	
Molybdenum	0.013	mg/L	0.010	0.00062	1	08/24/24 14:01	08/30/24 20:11	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240820
Pace Project No.: 92749180

QC Batch:	878070	Analysis Method:	EPA 6010D
QC Batch Method:	EPA 3010A	Analysis Description:	6010D ATL
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92749180001, 92749180002, 92749180003, 92749180004, 92749180005, 92749180006, 92749180007, 92749180008, 92749180009, 92749180010, 92749180011, 92749180012

METHOD BLANK:	4523022	Matrix:	Water
---------------	---------	---------	-------

Associated Lab Samples: 92749180001, 92749180002, 92749180003, 92749180004, 92749180005, 92749180006, 92749180007, 92749180008, 92749180009, 92749180010, 92749180011, 92749180012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Iron	mg/L	ND	0.040	0.025	08/26/24 09:50	

LABORATORY CONTROL SAMPLE: 4523023						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Iron	mg/L	1	1.1	109	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:		4523024	4523025									
Parameter	Units	92749173004 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Iron	mg/L	0.13	1	1	1.2	1.1	106	101	75-125	4	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240820
Pace Project No.: 92749180

QC Batch:	878079	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92749180001, 92749180002, 92749180003, 92749180004, 92749180005, 92749180006, 92749180007, 92749180008, 92749180009, 92749180010, 92749180011, 92749180012

METHOD BLANK: 4523054 Matrix: Water

Associated Lab Samples: 92749180001, 92749180002, 92749180003, 92749180004, 92749180005, 92749180006, 92749180007, 92749180008, 92749180009, 92749180010, 92749180011, 92749180012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Arsenic	mg/L	ND	0.0050	0.00084	08/30/24 18:43	
Boron	mg/L	ND	0.040	0.012	08/30/24 18:43	
Molybdenum	mg/L	ND	0.010	0.00062	08/30/24 18:43	

LABORATORY CONTROL SAMPLE: 4523055

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Arsenic	mg/L	0.1	0.098	98	80-120	
Boron	mg/L	1	0.97	97	80-120	
Molybdenum	mg/L	0.1	0.10	103	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4523056 4523057

Parameter	Units	92749173004 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Arsenic	mg/L	0.0037J	0.1	0.1	0.11	0.11	103	103	75-125	0	20	
Boron	mg/L	7.6	1	1	9.0	9.0	137	133	75-125	0	20	M1
Molybdenum	mg/L	ND	0.1	0.1	0.10	0.10	102	102	75-125	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1 (CA)-20240820
Pace Project No.: 92749180

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1 (CA)-20240820
Pace Project No.: 92749180

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92749180001	HAM-PT-07	EPA 3010A	878070	EPA 6010D	878096
92749180002	HAM-PT-08	EPA 3010A	878070	EPA 6010D	878096
92749180003	HAM-PT-09	EPA 3010A	878070	EPA 6010D	878096
92749180004	HAM-PT-10	EPA 3010A	878070	EPA 6010D	878096
92749180005	HAM-PT-11	EPA 3010A	878070	EPA 6010D	878096
92749180006	HAM-PT-12	EPA 3010A	878070	EPA 6010D	878096
92749180007	HAM-PT-13	EPA 3010A	878070	EPA 6010D	878096
92749180008	HAM-PT-14	EPA 3010A	878070	EPA 6010D	878096
92749180009	HAM-PT-15	EPA 3010A	878070	EPA 6010D	878096
92749180010	HAM-AP1-EB-01	EPA 3010A	878070	EPA 6010D	878096
92749180011	HAM-AP1-FB-01	EPA 3010A	878070	EPA 6010D	878096
92749180012	HAM-AP1-FD-01	EPA 3010A	878070	EPA 6010D	878096
92749180001	HAM-PT-07	EPA 3005A	878079	EPA 6020B	878101
92749180002	HAM-PT-08	EPA 3005A	878079	EPA 6020B	878101
92749180003	HAM-PT-09	EPA 3005A	878079	EPA 6020B	878101
92749180004	HAM-PT-10	EPA 3005A	878079	EPA 6020B	878101
92749180005	HAM-PT-11	EPA 3005A	878079	EPA 6020B	878101
92749180006	HAM-PT-12	EPA 3005A	878079	EPA 6020B	878101
92749180007	HAM-PT-13	EPA 3005A	878079	EPA 6020B	878101
92749180008	HAM-PT-14	EPA 3005A	878079	EPA 6020B	878101
92749180009	HAM-PT-15	EPA 3005A	878079	EPA 6020B	878101
92749180010	HAM-AP1-EB-01	EPA 3005A	878079	EPA 6020B	878101
92749180011	HAM-AP1-FB-01	EPA 3005A	878079	EPA 6020B	878101
92749180012	HAM-AP1-FD-01	EPA 3005A	878079	EPA 6020B	878101

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



DO#_TRC: ENVIRONMENTAL 0000 VOS-sample
Effective Date: 05/24/2024

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mech ☐ Asheville ☐ Atlanta ☐ Kernersville ☐



Client Name:

GA Power

Project #:

Courier:

☐ Commercial

☐ Fed Ex

☒ Pace

☐ UPS

☐ USPS

☐ Other:

☐ Client

Custody Seal Present?

☐ Yes

☒ No

Seals Intact?

☐ Yes

☐ No

☒ N/A

Date/Initials Person Examining Contents:

8/15/24

Packing Material:

☐ Bubble Wrap

☐ Bubble Bags

☒ None

☐ Other

Biological Tissue Frozen?

☐ Yes

☐ No

☐ N/A

Thermometer:

☐ IR Gun ID:

230

Type of Ice:

☒ Wet

☐ Blue

☐ None

Cooler Temp:

4.9

Correction Factor:
Add/Subtract (°C)

0.0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

4.9

USDA Regulated Soil (☐ N/A, water sample)

Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ No

Did samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

			Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.	
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.	
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.	
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4.	
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.	
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.	
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A	7.	
Containers Intact?	☒ Yes ☐ No ☐ N/A	8.	
Dissolved analysis: Samples Field Filtered?	☐ Yes ☐ No ☒ N/A	9.	
Sample Labels Match COC?	☒ Yes ☐ No ☐ N/A		
-Includes Date/Time/ID/Analysis Matrix:	W		
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10.	
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.	
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A		

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐

Client _____ Profile/EZ (Circle one) _____ Notes _____

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)		BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic ZN Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGFU-Wide-mouthed Glass jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG9H-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit)-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A -lab)	SP2T-250 mL Sterile Plastic (N/A -lab)		BP3R-250 mL Plastic (NH4)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	VSGU-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)	
CC							GA																							
1																														
2																														
3																														
4																														
5																														
6																														
7																														
8																														
9																														
10																														
11																														
12																														

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers).



The Criminal Justice Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

[illegible]



September 18, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on September 06, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Peachtree Corners, GA

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Jamie Newsome, Geosyntec Consultants
Zain Webb, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92752167001	HAM-PT-07	Water	09/04/24 15:38	09/06/24 11:54
92752167002	HAM-PT-08	Water	09/05/24 12:47	09/06/24 11:54
92752167003	HAM-PT-09	Water	09/04/24 13:20	09/06/24 11:54
92752167004	HAM-PT-10	Water	09/04/24 11:35	09/06/24 11:54
92752167005	HAM-PT-11	Water	09/04/24 11:25	09/06/24 11:54
92752167006	HAM-PT-12	Water	09/04/24 15:25	09/06/24 11:54
92752167007	HAM-PT-13	Water	09/04/24 14:00	09/06/24 11:54
92752167008	HAM-PT-14	Water	09/05/24 11:35	09/06/24 11:54
92752167009	HAM-PT-15	Water	09/04/24 16:10	09/06/24 11:54
92752167010	HAM-AP1-EB-01	Water	09/05/24 14:35	09/06/24 11:54
92752167011	HAM-AP1-FB-01	Water	09/05/24 14:30	09/06/24 11:54
92752167012	HAM-AP1-FD-01	Water	09/05/24 00:00	09/06/24 11:54

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92752167001	HAM-PT-07	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92752167002	HAM-PT-08	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92752167003	HAM-PT-09	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92752167004	HAM-PT-10	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92752167005	HAM-PT-11	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92752167006	HAM-PT-12	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92752167007	HAM-PT-13	EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
92752167008	HAM-PT-14	SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	MJS2	6
92752167009	HAM-PT-15	EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
92752167010	HAM-AP1-EB-01	SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
92752167011	HAM-AP1-FB-01	EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92752167012	HAM-AP1-FD-01	SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	MJS2	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3

PASI-A = Pace Analytical Services - Asheville

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92752167001	HAM-PT-07					
EPA 6010D	Iron	15.6	mg/L	0.040	09/13/24 20:42	M1
EPA 6010D	Manganese	4.4	mg/L	0.040	09/13/24 20:42	M1
EPA 6010D	Potassium	5.8	mg/L	0.50	09/13/24 20:42	
EPA 6010D	Sodium	9.8	mg/L	1.0	09/13/24 20:42	M1
EPA 6010D	Calcium	117	mg/L	1.0	09/13/24 20:42	M1
EPA 6010D	Magnesium	16.4	mg/L	0.050	09/13/24 20:42	M1
EPA 6020B	Antimony	0.0014J	mg/L	0.0030	09/13/24 16:47	
EPA 6020B	Arsenic	0.30	mg/L	0.0050	09/13/24 16:47	
EPA 6020B	Barium	0.050	mg/L	0.0050	09/13/24 16:47	
EPA 6020B	Boron	0.56	mg/L	0.040	09/13/24 16:47	
EPA 6020B	Cobalt	0.12	mg/L	0.0050	09/13/24 16:47	
EPA 6020B	Lithium	0.053	mg/L	0.030	09/13/24 16:47	
EPA 6020B	Molybdenum	0.010	mg/L	0.010	09/13/24 16:47	
SM 2540C-2015	Total Dissolved Solids	561	mg/L	25.0	09/10/24 12:56	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	143	mg/L	5.0	09/11/24 14:27	
SM 2320B-2011	Alkalinity, Total as CaCO3	143	mg/L	5.0	09/11/24 14:27	
EPA 300.0 Rev 2.1 1993	Chloride	17.4	mg/L	1.0	09/10/24 06:53	
EPA 300.0 Rev 2.1 1993	Fluoride	0.37	mg/L	0.10	09/10/24 06:53	
EPA 300.0 Rev 2.1 1993	Sulfate	221	mg/L	5.0	09/10/24 16:52	
92752167002	HAM-PT-08					
EPA 6010D	Iron	9.8	mg/L	0.040	09/13/24 21:12	
EPA 6010D	Manganese	3.0	mg/L	0.040	09/13/24 21:12	
EPA 6010D	Potassium	5.3	mg/L	0.50	09/13/24 21:12	
EPA 6010D	Sodium	8.2	mg/L	1.0	09/13/24 21:12	
EPA 6010D	Calcium	94.4	mg/L	1.0	09/13/24 21:12	
EPA 6010D	Magnesium	13.2	mg/L	0.050	09/13/24 21:12	
EPA 6020B	Antimony	0.0013J	mg/L	0.0030	09/13/24 17:01	
EPA 6020B	Arsenic	0.23	mg/L	0.0050	09/13/24 17:01	
EPA 6020B	Barium	0.048	mg/L	0.0050	09/13/24 17:01	
EPA 6020B	Boron	0.70	mg/L	0.040	09/13/24 17:01	
EPA 6020B	Cobalt	0.084	mg/L	0.0050	09/13/24 17:01	
EPA 6020B	Lithium	0.015J	mg/L	0.030	09/13/24 17:01	
EPA 6020B	Molybdenum	0.010	mg/L	0.010	09/13/24 17:01	
SM 2540C-2015	Total Dissolved Solids	466	mg/L	25.0	09/11/24 13:47	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	77.7	mg/L	5.0	09/11/24 17:31	
SM 2320B-2011	Alkalinity, Total as CaCO3	77.7	mg/L	5.0	09/11/24 17:31	
EPA 300.0 Rev 2.1 1993	Chloride	19.3	mg/L	1.0	09/10/24 07:09	
EPA 300.0 Rev 2.1 1993	Fluoride	0.16	mg/L	0.10	09/10/24 07:09	M1
EPA 300.0 Rev 2.1 1993	Sulfate	193	mg/L	4.0	09/10/24 17:07	M1
92752167003	HAM-PT-09					
EPA 6010D	Iron	0.31	mg/L	0.040	09/13/24 21:17	
EPA 6010D	Manganese	0.28	mg/L	0.040	09/13/24 21:17	
EPA 6010D	Potassium	6.1	mg/L	0.50	09/13/24 21:17	
EPA 6010D	Sodium	8.9	mg/L	1.0	09/13/24 21:17	
EPA 6010D	Calcium	87.9	mg/L	1.0	09/13/24 21:17	
EPA 6010D	Magnesium	24.9	mg/L	0.050	09/13/24 21:17	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92752167003	HAM-PT-09					
EPA 6020B	Barium	0.068	mg/L	0.0050	09/13/24 17:05	
EPA 6020B	Boron	1.4	mg/L	0.040	09/13/24 17:05	
EPA 6020B	Cadmium	0.00021J	mg/L	0.00050	09/13/24 17:05	
EPA 6020B	Cobalt	0.0027J	mg/L	0.0050	09/13/24 17:05	
EPA 6020B	Lithium	0.0022J	mg/L	0.030	09/13/24 17:05	
EPA 6020B	Molybdenum	0.26	mg/L	0.010	09/13/24 17:05	
SM 2540C-2015	Total Dissolved Solids	486	mg/L	25.0	09/10/24 12:56	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	121	mg/L	5.0	09/11/24 14:38	
SM 2320B-2011	Alkalinity, Total as CaCO3	121	mg/L	5.0	09/11/24 14:38	
EPA 300.0 Rev 2.1 1993	Chloride	45.3	mg/L	1.0	09/10/24 07:56	
EPA 300.0 Rev 2.1 1993	Fluoride	0.43	mg/L	0.10	09/10/24 07:56	
EPA 300.0 Rev 2.1 1993	Sulfate	149	mg/L	3.0	09/10/24 17:54	
92752167004	HAM-PT-10					
EPA 6010D	Iron	0.077	mg/L	0.040	09/13/24 21:22	
EPA 6010D	Manganese	0.42	mg/L	0.040	09/13/24 21:22	
EPA 6010D	Potassium	6.8	mg/L	0.50	09/13/24 21:22	
EPA 6010D	Sodium	8.7	mg/L	1.0	09/13/24 21:22	
EPA 6010D	Calcium	99.0	mg/L	1.0	09/13/24 21:22	
EPA 6010D	Magnesium	13.1	mg/L	0.050	09/13/24 21:22	
EPA 6020B	Barium	0.047	mg/L	0.0050	09/13/24 17:09	
EPA 6020B	Boron	1.6	mg/L	0.040	09/13/24 17:09	
EPA 6020B	Cadmium	0.00011J	mg/L	0.00050	09/13/24 17:09	
EPA 6020B	Cobalt	0.0015J	mg/L	0.0050	09/13/24 17:09	
EPA 6020B	Molybdenum	0.18	mg/L	0.010	09/13/24 17:09	
SM 2540C-2015	Total Dissolved Solids	473	mg/L	25.0	09/10/24 12:56	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	130	mg/L	5.0	09/11/24 14:47	
SM 2320B-2011	Alkalinity, Total as CaCO3	130	mg/L	5.0	09/11/24 14:47	
EPA 300.0 Rev 2.1 1993	Chloride	46.2	mg/L	1.0	09/10/24 16:35	
EPA 300.0 Rev 2.1 1993	Fluoride	0.28	mg/L	0.10	09/10/24 16:35	
EPA 300.0 Rev 2.1 1993	Sulfate	118	mg/L	3.0	09/10/24 18:49	
92752167005	HAM-PT-11					
EPA 6010D	Iron	0.41	mg/L	0.040	09/13/24 21:27	
EPA 6010D	Manganese	0.59	mg/L	0.040	09/13/24 21:27	
EPA 6010D	Potassium	6.1	mg/L	0.50	09/13/24 21:27	
EPA 6010D	Sodium	8.6	mg/L	1.0	09/13/24 21:27	
EPA 6010D	Calcium	94.9	mg/L	1.0	09/13/24 21:27	
EPA 6010D	Magnesium	17.8	mg/L	0.050	09/13/24 21:27	
EPA 6020B	Arsenic	0.00087J	mg/L	0.0050	09/13/24 17:12	
EPA 6020B	Barium	0.070	mg/L	0.0050	09/13/24 17:12	
EPA 6020B	Boron	1.4	mg/L	0.040	09/13/24 17:12	
EPA 6020B	Cadmium	0.00017J	mg/L	0.00050	09/13/24 17:12	
EPA 6020B	Cobalt	0.0066	mg/L	0.0050	09/13/24 17:12	
EPA 6020B	Lithium	0.0039J	mg/L	0.030	09/13/24 17:12	
EPA 6020B	Molybdenum	0.14	mg/L	0.010	09/13/24 17:12	
SM 2540C-2015	Total Dissolved Solids	483	mg/L	25.0	09/10/24 13:01	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	133	mg/L	5.0	09/11/24 15:04	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92752167005	HAM-PT-11					
SM 2320B-2011	Alkalinity, Total as CaCO ₃	133	mg/L	5.0	09/11/24 15:04	
EPA 300.0 Rev 2.1 1993	Chloride	46.1	mg/L	1.0	09/10/24 08:12	
EPA 300.0 Rev 2.1 1993	Fluoride	0.43	mg/L	0.10	09/10/24 08:12	
EPA 300.0 Rev 2.1 1993	Sulfate	139	mg/L	3.0	09/10/24 18:10	
92752167006	HAM-PT-12					
EPA 6010D	Iron	0.14	mg/L	0.040	09/13/24 21:32	
EPA 6010D	Manganese	0.77	mg/L	0.040	09/13/24 21:32	
EPA 6010D	Potassium	5.5	mg/L	0.50	09/13/24 21:32	
EPA 6010D	Sodium	6.7	mg/L	1.0	09/13/24 21:32	
EPA 6010D	Calcium	90.2	mg/L	1.0	09/13/24 21:32	
EPA 6010D	Magnesium	26.4	mg/L	0.050	09/13/24 21:32	
EPA 6020B	Arsenic	0.0017J	mg/L	0.0050	09/13/24 17:32	
EPA 6020B	Barium	0.068	mg/L	0.0050	09/13/24 17:32	
EPA 6020B	Boron	1.0	mg/L	0.040	09/13/24 17:32	
EPA 6020B	Cadmium	0.00024J	mg/L	0.00050	09/13/24 17:32	
EPA 6020B	Cobalt	0.0028J	mg/L	0.0050	09/13/24 17:32	
EPA 6020B	Lithium	0.0020J	mg/L	0.030	09/13/24 17:32	
EPA 6020B	Molybdenum	0.19	mg/L	0.010	09/13/24 17:32	
SM 2540C-2015	Total Dissolved Solids	500	mg/L	25.0	09/10/24 13:02	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO ₃)	124	mg/L	5.0	09/11/24 15:14	
SM 2320B-2011	Alkalinity, Total as CaCO ₃	124	mg/L	5.0	09/11/24 15:14	
EPA 300.0 Rev 2.1 1993	Chloride	28.7	mg/L	1.0	09/10/24 08:28	
EPA 300.0 Rev 2.1 1993	Fluoride	0.38	mg/L	0.10	09/10/24 08:28	
EPA 300.0 Rev 2.1 1993	Sulfate	187	mg/L	4.0	09/10/24 18:25	
92752167007	HAM-PT-13					
EPA 6010D	Iron	17.2	mg/L	0.040	09/13/24 21:37	
EPA 6010D	Manganese	4.1	mg/L	0.040	09/13/24 21:37	
EPA 6010D	Potassium	5.9	mg/L	0.50	09/13/24 21:37	
EPA 6010D	Sodium	10.6	mg/L	1.0	09/13/24 21:37	
EPA 6010D	Calcium	120	mg/L	1.0	09/13/24 21:37	
EPA 6010D	Magnesium	16.1	mg/L	0.050	09/13/24 21:37	
EPA 6020B	Arsenic	0.31	mg/L	0.0050	09/13/24 17:36	
EPA 6020B	Barium	0.050	mg/L	0.0050	09/13/24 17:36	
EPA 6020B	Boron	0.53	mg/L	0.040	09/13/24 17:36	
EPA 6020B	Cobalt	0.038	mg/L	0.0050	09/13/24 17:36	
EPA 6020B	Lithium	0.059	mg/L	0.030	09/13/24 17:36	
EPA 6020B	Molybdenum	0.0088J	mg/L	0.010	09/13/24 17:36	
SM 2540C-2015	Total Dissolved Solids	570	mg/L	25.0	09/11/24 13:45	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO ₃)	134	mg/L	5.0	09/11/24 15:23	
SM 2320B-2011	Alkalinity, Total as CaCO ₃	134	mg/L	5.0	09/11/24 15:23	
EPA 300.0 Rev 2.1 1993	Chloride	17.4	mg/L	1.0	09/10/24 08:44	
EPA 300.0 Rev 2.1 1993	Fluoride	0.40	mg/L	0.10	09/10/24 08:44	
EPA 300.0 Rev 2.1 1993	Sulfate	241	mg/L	5.0	09/10/24 19:12	
92752167008	HAM-PT-14					
EPA 6010D	Iron	14.9	mg/L	0.040	09/13/24 21:41	
EPA 6010D	Manganese	3.0	mg/L	0.040	09/13/24 21:41	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92752167008	HAM-PT-14					
EPA 6010D	Potassium	6.1	mg/L	0.50	09/13/24 21:41	
EPA 6010D	Sodium	9.6	mg/L	1.0	09/13/24 21:41	
EPA 6010D	Calcium	121	mg/L	1.0	09/13/24 21:41	
EPA 6010D	Magnesium	18.6	mg/L	0.050	09/13/24 21:41	
EPA 6020B	Arsenic	0.23	mg/L	0.0050	09/13/24 17:40	
EPA 6020B	Barium	0.048	mg/L	0.0050	09/13/24 17:40	
EPA 6020B	Boron	0.62	mg/L	0.040	09/13/24 17:40	
EPA 6020B	Cobalt	0.025	mg/L	0.0050	09/13/24 17:40	
EPA 6020B	Lithium	0.049	mg/L	0.030	09/13/24 17:40	
EPA 6020B	Molybdenum	0.015	mg/L	0.010	09/13/24 17:40	
SM 2540C-2015	Total Dissolved Solids	586	mg/L	25.0	09/11/24 13:47	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	156	mg/L	5.0	09/11/24 17:39	
SM 2320B-2011	Alkalinity, Total as CaCO3	156	mg/L	5.0	09/11/24 17:39	
EPA 300.0 Rev 2.1 1993	Chloride	19.1	mg/L	1.0	09/10/24 09:00	
EPA 300.0 Rev 2.1 1993	Fluoride	0.27	mg/L	0.10	09/10/24 09:00	
EPA 300.0 Rev 2.1 1993	Sulfate	236	mg/L	5.0	09/10/24 19:28	
92752167009	HAM-PT-15					
EPA 6010D	Iron	7.4	mg/L	0.040	09/13/24 21:46	
EPA 6010D	Manganese	4.9	mg/L	0.040	09/13/24 21:46	
EPA 6010D	Potassium	5.0	mg/L	0.50	09/13/24 21:46	
EPA 6010D	Sodium	7.9	mg/L	1.0	09/13/24 21:46	
EPA 6010D	Calcium	107	mg/L	1.0	09/13/24 21:46	
EPA 6010D	Magnesium	13.1	mg/L	0.050	09/13/24 21:46	
EPA 6020B	Arsenic	0.43	mg/L	0.0050	09/13/24 17:43	
EPA 6020B	Barium	0.048	mg/L	0.0050	09/13/24 17:43	
EPA 6020B	Beryllium	0.000099J	mg/L	0.00050	09/13/24 17:43	
EPA 6020B	Boron	0.69	mg/L	0.040	09/13/24 17:43	
EPA 6020B	Cobalt	0.079	mg/L	0.0050	09/13/24 17:43	
EPA 6020B	Lithium	0.042	mg/L	0.030	09/13/24 17:43	
EPA 6020B	Molybdenum	0.017	mg/L	0.010	09/13/24 17:43	
SM 2540C-2015	Total Dissolved Solids	521	mg/L	25.0	09/11/24 13:46	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	149	mg/L	5.0	09/11/24 15:33	
SM 2320B-2011	Alkalinity, Total as CaCO3	149	mg/L	5.0	09/11/24 15:33	
EPA 300.0 Rev 2.1 1993	Chloride	15.2	mg/L	1.0	09/10/24 09:47	
EPA 300.0 Rev 2.1 1993	Fluoride	0.36	mg/L	0.10	09/10/24 09:47	
EPA 300.0 Rev 2.1 1993	Sulfate	204	mg/L	5.0	09/10/24 19:44	
92752167010	HAM-AP1-EB-01					
SM 2540C-2015	Total Dissolved Solids	66.0	mg/L	25.0	09/11/24 13:48	
92752167011	HAM-AP1-FB-01					
EPA 6020B	Molybdenum	0.00063J	mg/L	0.010	09/13/24 17:51	
SM 2540C-2015	Total Dissolved Solids	43.0	mg/L	25.0	09/11/24 13:48	
92752167012	HAM-AP1-FD-01					
EPA 6010D	Iron	10.1	mg/L	0.040	09/13/24 22:11	
EPA 6010D	Manganese	3.0	mg/L	0.040	09/13/24 22:11	
EPA 6010D	Potassium	5.4	mg/L	0.50	09/13/24 22:11	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92752167012	HAM-AP1-FD-01					
EPA 6010D	Sodium	9.3	mg/L	1.0	09/13/24 22:11	
EPA 6010D	Calcium	92.4	mg/L	1.0	09/13/24 22:11	
EPA 6010D	Magnesium	13.1	mg/L	0.050	09/13/24 22:11	
EPA 6020B	Arsenic	0.21	mg/L	0.0050	09/13/24 17:54	
EPA 6020B	Barium	0.049	mg/L	0.0050	09/13/24 17:54	
EPA 6020B	Boron	0.71	mg/L	0.040	09/13/24 17:54	
EPA 6020B	Cobalt	0.084	mg/L	0.0050	09/13/24 17:54	
EPA 6020B	Lithium	0.016J	mg/L	0.030	09/13/24 17:54	
EPA 6020B	Molybdenum	0.010	mg/L	0.010	09/13/24 17:54	
SM 2540C-2015	Total Dissolved Solids	492	mg/L	25.0	09/11/24 13:48	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	81.3	mg/L	5.0	09/11/24 17:55	
SM 2320B-2011	Alkalinity, Total as CaCO3	81.3	mg/L	5.0	09/11/24 17:55	
EPA 300.0 Rev 2.1 1993	Chloride	19.5	mg/L	1.0	09/10/24 10:03	
EPA 300.0 Rev 2.1 1993	Fluoride	0.17	mg/L	0.10	09/10/24 10:03	
EPA 300.0 Rev 2.1 1993	Sulfate	195	mg/L	4.0	09/10/24 19:59	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Sample: HAM-PT-07		Lab ID: 92752167001		Collected: 09/04/24 15:38		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	15.6	mg/L	0.040	0.025	1	09/12/24 13:03	09/13/24 20:42	7439-89-6	M1
Manganese	4.4	mg/L	0.040	0.011	1	09/12/24 13:03	09/13/24 20:42	7439-96-5	M1
Potassium	5.8	mg/L	0.50	0.15	1	09/12/24 13:03	09/13/24 20:42	7440-09-7	
Sodium	9.8	mg/L	1.0	0.58	1	09/12/24 13:03	09/13/24 20:42	7440-23-5	M1
Calcium	117	mg/L	1.0	0.12	1	09/12/24 13:03	09/13/24 20:42	7440-70-2	M1
Magnesium	16.4	mg/L	0.050	0.012	1	09/12/24 13:03	09/13/24 20:42	7439-95-4	M1
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	0.0014J	mg/L	0.0030	0.00054	1	09/11/24 13:55	09/13/24 16:47	7440-36-0	
Arsenic	0.30	mg/L	0.0050	0.00084	1	09/11/24 13:55	09/13/24 16:47	7440-38-2	
Barium	0.050	mg/L	0.0050	0.00047	1	09/11/24 13:55	09/13/24 16:47	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	09/11/24 13:55	09/13/24 16:47	7440-41-7	
Boron	0.56	mg/L	0.040	0.012	1	09/11/24 13:55	09/13/24 16:47	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	09/11/24 13:55	09/13/24 16:47	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	09/11/24 13:55	09/13/24 16:47	7440-47-3	
Cobalt	0.12	mg/L	0.0050	0.00032	1	09/11/24 13:55	09/13/24 16:47	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	09/11/24 13:55	09/13/24 16:47	7439-92-1	
Lithium	0.053	mg/L	0.030	0.0016	1	09/11/24 13:55	09/13/24 16:47	7439-93-2	
Molybdenum	0.010	mg/L	0.010	0.00062	1	09/11/24 13:55	09/13/24 16:47	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	09/11/24 13:55	09/13/24 16:47	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	09/11/24 13:55	09/13/24 16:47	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	09/17/24 07:00	09/17/24 10:34	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	561	mg/L	25.0	25.0	1		09/10/24 12:56		
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO3)	143	mg/L	5.0	5.0	1		09/11/24 14:27		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		09/11/24 14:27		
Alkalinity, Total as CaCO3	143	mg/L	5.0	5.0	1		09/11/24 14:27		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		09/10/24 04:23	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	17.4	mg/L	1.0	0.60	1		09/10/24 06:53	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Sample: HAM-PT-07		Lab ID: 92752167001		Collected: 09/04/24 15:38		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.37	mg/L	0.10	0.050	1		09/10/24 06:53	16984-48-8	
Sulfate	221	mg/L	5.0	2.5	5		09/10/24 16:52	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Sample: HAM-PT-08		Lab ID: 92752167002		Collected: 09/05/24 12:47		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	9.8	mg/L	0.040	0.025	1	09/12/24 13:03	09/13/24 21:12	7439-89-6	
Manganese	3.0	mg/L	0.040	0.011	1	09/12/24 13:03	09/13/24 21:12	7439-96-5	
Potassium	5.3	mg/L	0.50	0.15	1	09/12/24 13:03	09/13/24 21:12	7440-09-7	
Sodium	8.2	mg/L	1.0	0.58	1	09/12/24 13:03	09/13/24 21:12	7440-23-5	
Calcium	94.4	mg/L	1.0	0.12	1	09/12/24 13:03	09/13/24 21:12	7440-70-2	
Magnesium	13.2	mg/L	0.050	0.012	1	09/12/24 13:03	09/13/24 21:12	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	0.0013J	mg/L	0.0030	0.00054	1	09/11/24 13:55	09/13/24 17:01	7440-36-0	
Arsenic	0.23	mg/L	0.0050	0.00084	1	09/11/24 13:55	09/13/24 17:01	7440-38-2	
Barium	0.048	mg/L	0.0050	0.00047	1	09/11/24 13:55	09/13/24 17:01	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	09/11/24 13:55	09/13/24 17:01	7440-41-7	
Boron	0.70	mg/L	0.040	0.012	1	09/11/24 13:55	09/13/24 17:01	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	09/11/24 13:55	09/13/24 17:01	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	09/11/24 13:55	09/13/24 17:01	7440-47-3	
Cobalt	0.084	mg/L	0.0050	0.00032	1	09/11/24 13:55	09/13/24 17:01	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	09/11/24 13:55	09/13/24 17:01	7439-92-1	
Lithium	0.015J	mg/L	0.030	0.0016	1	09/11/24 13:55	09/13/24 17:01	7439-93-2	
Molybdenum	0.010	mg/L	0.010	0.00062	1	09/11/24 13:55	09/13/24 17:01	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	09/11/24 13:55	09/13/24 17:01	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	09/11/24 13:55	09/13/24 17:01	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	09/17/24 07:00	09/17/24 10:37	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	466	mg/L	25.0	25.0	1		09/11/24 13:47		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	77.7	mg/L	5.0	5.0	1		09/11/24 17:31		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		09/11/24 17:31		
Alkalinity, Total as CaCO3	77.7	mg/L	5.0	5.0	1		09/11/24 17:31		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		09/10/24 04:31	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	19.3	mg/L	1.0	0.60	1		09/10/24 07:09	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Sample: HAM-PT-08		Lab ID: 92752167002		Collected: 09/05/24 12:47		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.16	mg/L	0.10	0.050	1		09/10/24 07:09	16984-48-8	M1
Sulfate	193	mg/L	4.0	2.0	4		09/10/24 17:07	14808-79-8	M1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Sample: HAM-PT-09		Lab ID: 92752167003		Collected: 09/04/24 13:20		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.31	mg/L	0.040	0.025	1	09/12/24 13:03	09/13/24 21:17	7439-89-6	
Manganese	0.28	mg/L	0.040	0.011	1	09/12/24 13:03	09/13/24 21:17	7439-96-5	
Potassium	6.1	mg/L	0.50	0.15	1	09/12/24 13:03	09/13/24 21:17	7440-09-7	
Sodium	8.9	mg/L	1.0	0.58	1	09/12/24 13:03	09/13/24 21:17	7440-23-5	
Calcium	87.9	mg/L	1.0	0.12	1	09/12/24 13:03	09/13/24 21:17	7440-70-2	
Magnesium	24.9	mg/L	0.050	0.012	1	09/12/24 13:03	09/13/24 21:17	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	09/11/24 13:55	09/13/24 17:05	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	09/11/24 13:55	09/13/24 17:05	7440-38-2	
Barium	0.068	mg/L	0.0050	0.00047	1	09/11/24 13:55	09/13/24 17:05	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	09/11/24 13:55	09/13/24 17:05	7440-41-7	
Boron	1.4	mg/L	0.040	0.012	1	09/11/24 13:55	09/13/24 17:05	7440-42-8	
Cadmium	0.00021J	mg/L	0.00050	0.00010	1	09/11/24 13:55	09/13/24 17:05	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	09/11/24 13:55	09/13/24 17:05	7440-47-3	
Cobalt	0.0027J	mg/L	0.0050	0.00032	1	09/11/24 13:55	09/13/24 17:05	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	09/11/24 13:55	09/13/24 17:05	7439-92-1	
Lithium	0.0022J	mg/L	0.030	0.0016	1	09/11/24 13:55	09/13/24 17:05	7439-93-2	
Molybdenum	0.26	mg/L	0.010	0.00062	1	09/11/24 13:55	09/13/24 17:05	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	09/11/24 13:55	09/13/24 17:05	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	09/11/24 13:55	09/13/24 17:05	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	09/17/24 07:00	09/17/24 10:39	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	486	mg/L	25.0	25.0	1		09/10/24 12:56		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	121	mg/L	5.0	5.0	1		09/11/24 14:38		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		09/11/24 14:38		
Alkalinity, Total as CaCO3	121	mg/L	5.0	5.0	1		09/11/24 14:38		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		09/10/24 04:25	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	45.3	mg/L	1.0	0.60	1		09/10/24 07:56	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Sample: HAM-PT-09		Lab ID: 92752167003		Collected: 09/04/24 13:20		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.43	mg/L	0.10	0.050	1		09/10/24 07:56	16984-48-8	
Sulfate	149	mg/L	3.0	1.5	3		09/10/24 17:54	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

Sample: HAM-PT-10		Lab ID: 92752167004		Collected: 09/04/24 11:35		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.077	mg/L	0.040	0.025	1	09/12/24 13:03	09/13/24 21:22	7439-89-6	
Manganese	0.42	mg/L	0.040	0.011	1	09/12/24 13:03	09/13/24 21:22	7439-96-5	
Potassium	6.8	mg/L	0.50	0.15	1	09/12/24 13:03	09/13/24 21:22	7440-09-7	
Sodium	8.7	mg/L	1.0	0.58	1	09/12/24 13:03	09/13/24 21:22	7440-23-5	
Calcium	99.0	mg/L	1.0	0.12	1	09/12/24 13:03	09/13/24 21:22	7440-70-2	
Magnesium	13.1	mg/L	0.050	0.012	1	09/12/24 13:03	09/13/24 21:22	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	09/11/24 13:55	09/13/24 17:09	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	09/11/24 13:55	09/13/24 17:09	7440-38-2	
Barium	0.047	mg/L	0.0050	0.00047	1	09/11/24 13:55	09/13/24 17:09	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	09/11/24 13:55	09/13/24 17:09	7440-41-7	
Boron	1.6	mg/L	0.040	0.012	1	09/11/24 13:55	09/13/24 17:09	7440-42-8	
Cadmium	0.00011J	mg/L	0.00050	0.00010	1	09/11/24 13:55	09/13/24 17:09	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	09/11/24 13:55	09/13/24 17:09	7440-47-3	
Cobalt	0.0015J	mg/L	0.0050	0.00032	1	09/11/24 13:55	09/13/24 17:09	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	09/11/24 13:55	09/13/24 17:09	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	09/11/24 13:55	09/13/24 17:09	7439-93-2	
Molybdenum	0.18	mg/L	0.010	0.00062	1	09/11/24 13:55	09/13/24 17:09	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	09/11/24 13:55	09/13/24 17:09	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	09/11/24 13:55	09/13/24 17:09	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	09/17/24 07:00	09/17/24 10:55	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	473	mg/L	25.0	25.0	1		09/10/24 12:56		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	130	mg/L	5.0	5.0	1		09/11/24 14:47		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		09/11/24 14:47		
Alkalinity, Total as CaCO3	130	mg/L	5.0	5.0	1		09/11/24 14:47		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		09/10/24 04:25	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	46.2	mg/L	1.0	0.60	1		09/10/24 16:35	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Sample: HAM-PT-10		Lab ID: 92752167004		Collected: 09/04/24 11:35		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.28	mg/L	0.10	0.050	1		09/10/24 16:35	16984-48-8	
Sulfate	118	mg/L	3.0	1.5	3		09/10/24 18:49	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Sample: HAM-PT-11		Lab ID: 92752167005		Collected: 09/04/24 11:25		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.41	mg/L	0.040	0.025	1	09/12/24 13:03	09/13/24 21:27	7439-89-6	
Manganese	0.59	mg/L	0.040	0.011	1	09/12/24 13:03	09/13/24 21:27	7439-96-5	
Potassium	6.1	mg/L	0.50	0.15	1	09/12/24 13:03	09/13/24 21:27	7440-09-7	
Sodium	8.6	mg/L	1.0	0.58	1	09/12/24 13:03	09/13/24 21:27	7440-23-5	
Calcium	94.9	mg/L	1.0	0.12	1	09/12/24 13:03	09/13/24 21:27	7440-70-2	
Magnesium	17.8	mg/L	0.050	0.012	1	09/12/24 13:03	09/13/24 21:27	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	09/11/24 13:55	09/13/24 17:12	7440-36-0	
Arsenic	0.00087J	mg/L	0.0050	0.00084	1	09/11/24 13:55	09/13/24 17:12	7440-38-2	
Barium	0.070	mg/L	0.0050	0.00047	1	09/11/24 13:55	09/13/24 17:12	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	09/11/24 13:55	09/13/24 17:12	7440-41-7	
Boron	1.4	mg/L	0.040	0.012	1	09/11/24 13:55	09/13/24 17:12	7440-42-8	
Cadmium	0.00017J	mg/L	0.00050	0.00010	1	09/11/24 13:55	09/13/24 17:12	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	09/11/24 13:55	09/13/24 17:12	7440-47-3	
Cobalt	0.0066	mg/L	0.0050	0.00032	1	09/11/24 13:55	09/13/24 17:12	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	09/11/24 13:55	09/13/24 17:12	7439-92-1	
Lithium	0.0039J	mg/L	0.030	0.0016	1	09/11/24 13:55	09/13/24 17:12	7439-93-2	
Molybdenum	0.14	mg/L	0.010	0.00062	1	09/11/24 13:55	09/13/24 17:12	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	09/11/24 13:55	09/13/24 17:12	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	09/11/24 13:55	09/13/24 17:12	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	09/17/24 07:00	09/17/24 10:58	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	483	mg/L	25.0	25.0	1		09/10/24 13:01		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	133	mg/L	5.0	5.0	1		09/11/24 15:04		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		09/11/24 15:04		
Alkalinity, Total as CaCO3	133	mg/L	5.0	5.0	1		09/11/24 15:04		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		09/10/24 04:26	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	46.1	mg/L	1.0	0.60	1		09/10/24 08:12	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Sample: HAM-PT-11		Lab ID: 92752167005		Collected: 09/04/24 11:25		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.43	mg/L	0.10	0.050	1		09/10/24 08:12	16984-48-8	
Sulfate	139	mg/L	3.0	1.5	3		09/10/24 18:10	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Sample: HAM-PT-12		Lab ID: 92752167006		Collected: 09/04/24 15:25		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.14	mg/L	0.040	0.025	1	09/12/24 13:03	09/13/24 21:32	7439-89-6	
Manganese	0.77	mg/L	0.040	0.011	1	09/12/24 13:03	09/13/24 21:32	7439-96-5	
Potassium	5.5	mg/L	0.50	0.15	1	09/12/24 13:03	09/13/24 21:32	7440-09-7	
Sodium	6.7	mg/L	1.0	0.58	1	09/12/24 13:03	09/13/24 21:32	7440-23-5	
Calcium	90.2	mg/L	1.0	0.12	1	09/12/24 13:03	09/13/24 21:32	7440-70-2	
Magnesium	26.4	mg/L	0.050	0.012	1	09/12/24 13:03	09/13/24 21:32	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	09/11/24 13:55	09/13/24 17:32	7440-36-0	
Arsenic	0.0017J	mg/L	0.0050	0.00084	1	09/11/24 13:55	09/13/24 17:32	7440-38-2	
Barium	0.068	mg/L	0.0050	0.00047	1	09/11/24 13:55	09/13/24 17:32	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	09/11/24 13:55	09/13/24 17:32	7440-41-7	
Boron	1.0	mg/L	0.040	0.012	1	09/11/24 13:55	09/13/24 17:32	7440-42-8	
Cadmium	0.00024J	mg/L	0.00050	0.00010	1	09/11/24 13:55	09/13/24 17:32	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	09/11/24 13:55	09/13/24 17:32	7440-47-3	
Cobalt	0.0028J	mg/L	0.0050	0.00032	1	09/11/24 13:55	09/13/24 17:32	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	09/11/24 13:55	09/13/24 17:32	7439-92-1	
Lithium	0.0020J	mg/L	0.030	0.0016	1	09/11/24 13:55	09/13/24 17:32	7439-93-2	
Molybdenum	0.19	mg/L	0.010	0.00062	1	09/11/24 13:55	09/13/24 17:32	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	09/11/24 13:55	09/13/24 17:32	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	09/11/24 13:55	09/13/24 17:32	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	09/17/24 07:00	09/17/24 11:00	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	500	mg/L	25.0	25.0	1		09/10/24 13:02		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	124	mg/L	5.0	5.0	1		09/11/24 15:14		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		09/11/24 15:14		
Alkalinity, Total as CaCO3	124	mg/L	5.0	5.0	1		09/11/24 15:14		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		09/10/24 04:27	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	28.7	mg/L	1.0	0.60	1		09/10/24 08:28	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Sample: HAM-PT-12		Lab ID: 92752167006		Collected: 09/04/24 15:25		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.38	mg/L	0.10	0.050	1		09/10/24 08:28	16984-48-8	
Sulfate	187	mg/L	4.0	2.0	4		09/10/24 18:25	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

Sample: HAM-PT-13		Lab ID: 92752167007		Collected: 09/04/24 14:00		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	17.2	mg/L	0.040	0.025	1	09/12/24 13:03	09/13/24 21:37	7439-89-6	
Manganese	4.1	mg/L	0.040	0.011	1	09/12/24 13:03	09/13/24 21:37	7439-96-5	
Potassium	5.9	mg/L	0.50	0.15	1	09/12/24 13:03	09/13/24 21:37	7440-09-7	
Sodium	10.6	mg/L	1.0	0.58	1	09/12/24 13:03	09/13/24 21:37	7440-23-5	
Calcium	120	mg/L	1.0	0.12	1	09/12/24 13:03	09/13/24 21:37	7440-70-2	
Magnesium	16.1	mg/L	0.050	0.012	1	09/12/24 13:03	09/13/24 21:37	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	09/11/24 13:55	09/13/24 17:36	7440-36-0	
Arsenic	0.31	mg/L	0.0050	0.00084	1	09/11/24 13:55	09/13/24 17:36	7440-38-2	
Barium	0.050	mg/L	0.0050	0.00047	1	09/11/24 13:55	09/13/24 17:36	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	09/11/24 13:55	09/13/24 17:36	7440-41-7	
Boron	0.53	mg/L	0.040	0.012	1	09/11/24 13:55	09/13/24 17:36	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	09/11/24 13:55	09/13/24 17:36	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	09/11/24 13:55	09/13/24 17:36	7440-47-3	
Cobalt	0.038	mg/L	0.0050	0.00032	1	09/11/24 13:55	09/13/24 17:36	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	09/11/24 13:55	09/13/24 17:36	7439-92-1	
Lithium	0.059	mg/L	0.030	0.0016	1	09/11/24 13:55	09/13/24 17:36	7439-93-2	
Molybdenum	0.0088J	mg/L	0.010	0.00062	1	09/11/24 13:55	09/13/24 17:36	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	09/11/24 13:55	09/13/24 17:36	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	09/11/24 13:55	09/13/24 17:36	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	09/17/24 07:00	09/17/24 11:03	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	570	mg/L	25.0	25.0	1		09/11/24 13:45		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	134	mg/L	5.0	5.0	1		09/11/24 15:23		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		09/11/24 15:23		
Alkalinity, Total as CaCO3	134	mg/L	5.0	5.0	1		09/11/24 15:23		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		09/10/24 04:27	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	17.4	mg/L	1.0	0.60	1		09/10/24 08:44	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

Sample: HAM-PT-13		Lab ID: 92752167007		Collected: 09/04/24 14:00		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.40	mg/L	0.10	0.050	1		09/10/24 08:44	16984-48-8	
Sulfate	241	mg/L	5.0	2.5	5		09/10/24 19:12	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Sample: HAM-PT-14		Lab ID: 92752167008		Collected: 09/05/24 11:35		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	14.9	mg/L	0.040	0.025	1	09/12/24 13:03	09/13/24 21:41	7439-89-6	
Manganese	3.0	mg/L	0.040	0.011	1	09/12/24 13:03	09/13/24 21:41	7439-96-5	
Potassium	6.1	mg/L	0.50	0.15	1	09/12/24 13:03	09/13/24 21:41	7440-09-7	
Sodium	9.6	mg/L	1.0	0.58	1	09/12/24 13:03	09/13/24 21:41	7440-23-5	
Calcium	121	mg/L	1.0	0.12	1	09/12/24 13:03	09/13/24 21:41	7440-70-2	
Magnesium	18.6	mg/L	0.050	0.012	1	09/12/24 13:03	09/13/24 21:41	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	09/11/24 13:55	09/13/24 17:40	7440-36-0	
Arsenic	0.23	mg/L	0.0050	0.00084	1	09/11/24 13:55	09/13/24 17:40	7440-38-2	
Barium	0.048	mg/L	0.0050	0.00047	1	09/11/24 13:55	09/13/24 17:40	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	09/11/24 13:55	09/13/24 17:40	7440-41-7	
Boron	0.62	mg/L	0.040	0.012	1	09/11/24 13:55	09/13/24 17:40	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	09/11/24 13:55	09/13/24 17:40	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	09/11/24 13:55	09/13/24 17:40	7440-47-3	
Cobalt	0.025	mg/L	0.0050	0.00032	1	09/11/24 13:55	09/13/24 17:40	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	09/11/24 13:55	09/13/24 17:40	7439-92-1	
Lithium	0.049	mg/L	0.030	0.0016	1	09/11/24 13:55	09/13/24 17:40	7439-93-2	
Molybdenum	0.015	mg/L	0.010	0.00062	1	09/11/24 13:55	09/13/24 17:40	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	09/11/24 13:55	09/13/24 17:40	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	09/11/24 13:55	09/13/24 17:40	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	09/17/24 07:00	09/17/24 11:05	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	586	mg/L	25.0	25.0	1		09/11/24 13:47		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	156	mg/L	5.0	5.0	1		09/11/24 17:39		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		09/11/24 17:39		
Alkalinity, Total as CaCO3	156	mg/L	5.0	5.0	1		09/11/24 17:39		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		09/10/24 04:32	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	19.1	mg/L	1.0	0.60	1		09/10/24 09:00	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

Sample: HAM-PT-14		Lab ID: 92752167008		Collected: 09/05/24 11:35		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.27	mg/L	0.10	0.050	1		09/10/24 09:00	16984-48-8	
Sulfate	236	mg/L	5.0	2.5	5		09/10/24 19:28	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Sample: HAM-PT-15		Lab ID: 92752167009		Collected: 09/04/24 16:10		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	7.4	mg/L	0.040	0.025	1	09/12/24 13:03	09/13/24 21:46	7439-89-6	
Manganese	4.9	mg/L	0.040	0.011	1	09/12/24 13:03	09/13/24 21:46	7439-96-5	
Potassium	5.0	mg/L	0.50	0.15	1	09/12/24 13:03	09/13/24 21:46	7440-09-7	
Sodium	7.9	mg/L	1.0	0.58	1	09/12/24 13:03	09/13/24 21:46	7440-23-5	
Calcium	107	mg/L	1.0	0.12	1	09/12/24 13:03	09/13/24 21:46	7440-70-2	
Magnesium	13.1	mg/L	0.050	0.012	1	09/12/24 13:03	09/13/24 21:46	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	09/11/24 13:55	09/13/24 17:43	7440-36-0	
Arsenic	0.43	mg/L	0.0050	0.00084	1	09/11/24 13:55	09/13/24 17:43	7440-38-2	
Barium	0.048	mg/L	0.0050	0.00047	1	09/11/24 13:55	09/13/24 17:43	7440-39-3	
Beryllium	0.000099J	mg/L	0.00050	0.000094	1	09/11/24 13:55	09/13/24 17:43	7440-41-7	
Boron	0.69	mg/L	0.040	0.012	1	09/11/24 13:55	09/13/24 17:43	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	09/11/24 13:55	09/13/24 17:43	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	09/11/24 13:55	09/13/24 17:43	7440-47-3	
Cobalt	0.079	mg/L	0.0050	0.00032	1	09/11/24 13:55	09/13/24 17:43	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	09/11/24 13:55	09/13/24 17:43	7439-92-1	
Lithium	0.042	mg/L	0.030	0.0016	1	09/11/24 13:55	09/13/24 17:43	7439-93-2	
Molybdenum	0.017	mg/L	0.010	0.00062	1	09/11/24 13:55	09/13/24 17:43	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	09/11/24 13:55	09/13/24 17:43	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	09/11/24 13:55	09/13/24 17:43	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	09/17/24 07:00	09/17/24 11:08	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	521	mg/L	25.0	25.0	1		09/11/24 13:46		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	149	mg/L	5.0	5.0	1		09/11/24 15:33		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		09/11/24 15:33		
Alkalinity, Total as CaCO3	149	mg/L	5.0	5.0	1		09/11/24 15:33		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		09/10/24 04:27	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	15.2	mg/L	1.0	0.60	1		09/10/24 09:47	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Sample: HAM-PT-15		Lab ID: 92752167009		Collected: 09/04/24 16:10		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.36	mg/L	0.10	0.050	1		09/10/24 09:47	16984-48-8	
Sulfate	204	mg/L	5.0	2.5	5		09/10/24 19:44	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Sample: HAM-AP1-EB-01		Lab ID: 92752167010		Collected: 09/05/24 14:35		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	09/12/24 13:03	09/13/24 21:51	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	09/12/24 13:03	09/13/24 21:51	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	09/12/24 13:03	09/13/24 21:51	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	09/12/24 13:03	09/13/24 21:51	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	09/12/24 13:03	09/13/24 21:51	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	09/12/24 13:03	09/13/24 21:51	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	09/11/24 13:55	09/13/24 17:47	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	09/11/24 13:55	09/13/24 17:47	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	09/11/24 13:55	09/13/24 17:47	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	09/11/24 13:55	09/13/24 17:47	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	09/11/24 13:55	09/13/24 17:47	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	09/11/24 13:55	09/13/24 17:47	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	09/11/24 13:55	09/13/24 17:47	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	09/11/24 13:55	09/13/24 17:47	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	09/11/24 13:55	09/13/24 17:47	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	09/11/24 13:55	09/13/24 17:47	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	09/11/24 13:55	09/13/24 17:47	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	09/11/24 13:55	09/13/24 17:47	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	09/11/24 13:55	09/13/24 17:47	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	09/17/24 07:00	09/17/24 11:11	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	66.0	mg/L	25.0	25.0	1		09/11/24 13:48		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	ND	mg/L	5.0	5.0	1		09/11/24 17:47		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		09/11/24 17:47		
Alkalinity, Total as CaCO3	ND	mg/L	5.0	5.0	1		09/11/24 17:47		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		09/10/24 04:33	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		09/09/24 22:26	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

Sample: HAM-AP1-EB-01		Lab ID: 92752167010		Collected: 09/05/24 14:35		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		09/09/24 22:26	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		09/09/24 22:26	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

Sample: HAM-AP1-FB-01		Lab ID: 92752167011		Collected: 09/05/24 14:30		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	09/12/24 13:03	09/13/24 22:06	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	09/12/24 13:03	09/13/24 22:06	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	09/12/24 13:03	09/13/24 22:06	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	09/12/24 13:03	09/13/24 22:06	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	09/12/24 13:03	09/13/24 22:06	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	09/12/24 13:03	09/13/24 22:06	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	09/11/24 13:55	09/13/24 17:51	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	09/11/24 13:55	09/13/24 17:51	7440-38-2	
Barium	ND	mg/L	0.0050	0.00047	1	09/11/24 13:55	09/13/24 17:51	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	09/11/24 13:55	09/13/24 17:51	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	09/11/24 13:55	09/13/24 17:51	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	09/11/24 13:55	09/13/24 17:51	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	09/11/24 13:55	09/13/24 17:51	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	09/11/24 13:55	09/13/24 17:51	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	09/11/24 13:55	09/13/24 17:51	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	09/11/24 13:55	09/13/24 17:51	7439-93-2	
Molybdenum	0.00063J	mg/L	0.010	0.00062	1	09/11/24 13:55	09/13/24 17:51	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	09/11/24 13:55	09/13/24 17:51	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	09/11/24 13:55	09/13/24 17:51	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	09/17/24 07:00	09/17/24 11:19	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	43.0	mg/L	25.0	25.0	1		09/11/24 13:48		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	ND	mg/L	5.0	5.0	1		09/11/24 17:51		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		09/11/24 17:51		
Alkalinity, Total as CaCO3	ND	mg/L	5.0	5.0	1		09/11/24 17:51		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		09/10/24 04:33	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		09/09/24 22:42	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Sample: HAM-AP1-FB-01		Lab ID: 92752167011		Collected: 09/05/24 14:30		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		09/09/24 22:42	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		09/09/24 22:42	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Sample: HAM-AP1-FD-01		Lab ID: 92752167012		Collected: 09/05/24 00:00		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	10.1	mg/L	0.040	0.025	1	09/12/24 13:03	09/13/24 22:11	7439-89-6	
Manganese	3.0	mg/L	0.040	0.011	1	09/12/24 13:03	09/13/24 22:11	7439-96-5	
Potassium	5.4	mg/L	0.50	0.15	1	09/12/24 13:03	09/13/24 22:11	7440-09-7	
Sodium	9.3	mg/L	1.0	0.58	1	09/12/24 13:03	09/13/24 22:11	7440-23-5	
Calcium	92.4	mg/L	1.0	0.12	1	09/12/24 13:03	09/13/24 22:11	7440-70-2	
Magnesium	13.1	mg/L	0.050	0.012	1	09/12/24 13:03	09/13/24 22:11	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	09/11/24 13:55	09/13/24 17:54	7440-36-0	
Arsenic	0.21	mg/L	0.0050	0.00084	1	09/11/24 13:55	09/13/24 17:54	7440-38-2	
Barium	0.049	mg/L	0.0050	0.00047	1	09/11/24 13:55	09/13/24 17:54	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	09/11/24 13:55	09/13/24 17:54	7440-41-7	
Boron	0.71	mg/L	0.040	0.012	1	09/11/24 13:55	09/13/24 17:54	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	09/11/24 13:55	09/13/24 17:54	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	09/11/24 13:55	09/13/24 17:54	7440-47-3	
Cobalt	0.084	mg/L	0.0050	0.00032	1	09/11/24 13:55	09/13/24 17:54	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	09/11/24 13:55	09/13/24 17:54	7439-92-1	
Lithium	0.016J	mg/L	0.030	0.0016	1	09/11/24 13:55	09/13/24 17:54	7439-93-2	
Molybdenum	0.010	mg/L	0.010	0.00062	1	09/11/24 13:55	09/13/24 17:54	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	09/11/24 13:55	09/13/24 17:54	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	09/11/24 13:55	09/13/24 17:54	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	09/17/24 07:00	09/17/24 11:21	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	492	mg/L	25.0	25.0	1		09/11/24 13:48		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	81.3	mg/L	5.0	5.0	1		09/11/24 17:55		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		09/11/24 17:55		
Alkalinity, Total as CaCO3	81.3	mg/L	5.0	5.0	1		09/11/24 17:55		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		09/10/24 04:34	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	19.5	mg/L	1.0	0.60	1		09/10/24 10:03	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

Sample: HAM-AP1-FD-01		Lab ID: 92752167012		Collected: 09/05/24 00:00		Received: 09/06/24 11:54		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.17	mg/L	0.10	0.050	1		09/10/24 10:03	16984-48-8	
Sulfate	195	mg/L	4.0	2.0	4		09/10/24 19:59	14808-79-8	

REPORT OF LABORATORY ANALYSIS



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

QC Batch: 881937 Analysis Method: EPA 6010D
QC Batch Method: EPA 3010A Analysis Description: 6010D ATL
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92752167001, 92752167002, 92752167003, 92752167004, 92752167005, 92752167006, 92752167007, 92752167008, 92752167009, 92752167010, 92752167011, 92752167012

METHOD BLANK: 4542011 Matrix: Water
Associated Lab Samples: 92752167001, 92752167002, 92752167003, 92752167004, 92752167005, 92752167006, 92752167007, 92752167008, 92752167009, 92752167010, 92752167011, 92752167012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	09/13/24 20:33	
Iron	mg/L	ND	0.040	0.025	09/13/24 20:33	
Magnesium	mg/L	ND	0.050	0.012	09/13/24 20:33	
Manganese	mg/L	ND	0.040	0.011	09/13/24 20:33	
Potassium	mg/L	ND	0.50	0.15	09/13/24 20:33	
Sodium	mg/L	ND	1.0	0.58	09/13/24 20:33	

LABORATORY CONTROL SAMPLE: 4542012

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	0.93J	93	80-120	
Iron	mg/L	1	0.93	93	80-120	
Magnesium	mg/L	1	0.92	92	80-120	
Manganese	mg/L	1	0.95	95	80-120	
Potassium	mg/L	1	0.94	94	80-120	
Sodium	mg/L	1	0.98J	98	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4542013 4542014

Parameter	Units	92752167001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Calcium	mg/L	117	1	1	114	118	-272	108	75-125	3	20	M1
Iron	mg/L	15.6	1	1	16.0	16.5	41	90	75-125	3	20	M1
Magnesium	mg/L	16.4	1	1	16.8	17.3	42	92	75-125	3	20	M1
Manganese	mg/L	4.4	1	1	5.1	5.3	73	86	75-125	2	20	M1
Potassium	mg/L	5.8	1	1	6.5	6.8	77	104	75-125	4	20	
Sodium	mg/L	9.8	1	1	10.5	10.9	69	108	75-125	4	20	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

QC Batch:	881820	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92752167001, 92752167002, 92752167003, 92752167004, 92752167005, 92752167006, 92752167007, 92752167008, 92752167009, 92752167010, 92752167011, 92752167012		

METHOD BLANK: 4541044 Matrix: Water
Associated Lab Samples: 92752167001, 92752167002, 92752167003, 92752167004, 92752167005, 92752167006, 92752167007, 92752167008, 92752167009, 92752167010, 92752167011, 92752167012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00054	09/13/24 16:39	
Arsenic	mg/L	ND	0.0050	0.00084	09/13/24 16:39	
Barium	mg/L	ND	0.0050	0.00047	09/13/24 16:39	
Beryllium	mg/L	ND	0.00050	0.000094	09/13/24 16:39	
Boron	mg/L	ND	0.040	0.012	09/13/24 16:39	
Cadmium	mg/L	ND	0.00050	0.00010	09/13/24 16:39	
Chromium	mg/L	ND	0.0050	0.0019	09/13/24 16:39	
Cobalt	mg/L	ND	0.0050	0.00032	09/13/24 16:39	
Lead	mg/L	ND	0.0010	0.00016	09/13/24 16:39	
Lithium	mg/L	ND	0.030	0.0016	09/13/24 16:39	
Molybdenum	mg/L	ND	0.010	0.00062	09/13/24 16:39	
Selenium	mg/L	ND	0.0050	0.00096	09/13/24 16:39	
Thallium	mg/L	ND	0.0010	0.00038	09/13/24 16:39	

LABORATORY CONTROL SAMPLE: 4541045

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.098	98	80-120	
Arsenic	mg/L	0.1	0.096	96	80-120	
Barium	mg/L	0.1	0.10	100	80-120	
Beryllium	mg/L	0.1	0.097	97	80-120	
Boron	mg/L	1	0.98	98	80-120	
Cadmium	mg/L	0.1	0.098	98	80-120	
Chromium	mg/L	0.1	0.10	100	80-120	
Cobalt	mg/L	0.1	0.097	97	80-120	
Lead	mg/L	0.1	0.098	98	80-120	
Lithium	mg/L	0.1	0.098	98	80-120	
Molybdenum	mg/L	0.1	0.098	98	80-120	
Selenium	mg/L	0.1	0.097	97	80-120	
Thallium	mg/L	0.1	0.098	98	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4541046 4541047

Parameter	Units	92752167001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	0.0014J	0.1	0.1	0.10	0.099	98	97	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4541046 4541047											
Parameter	Units	92752167001		MS	MSD	4541047		MS	MSD	% Rec	Max
		Result	Conc.	Spike	Spike	Result	Result	% Rec	% Rec	Limits	RPD
Arsenic	mg/L	0.30	0.1	0.1	0.1	0.40	0.40	95	95	75-125	0
Barium	mg/L	0.050	0.1	0.1	0.1	0.15	0.15	99	99	75-125	0
Beryllium	mg/L	ND	0.1	0.1	0.1	0.090	0.089	90	89	75-125	1
Boron	mg/L	0.56	1	1	1	1.5	1.5	91	90	75-125	1
Cadmium	mg/L	ND	0.1	0.1	0.1	0.097	0.097	97	97	75-125	0
Chromium	mg/L	ND	0.1	0.1	0.1	0.095	0.094	95	94	75-125	1
Cobalt	mg/L	0.12	0.1	0.1	0.1	0.21	0.21	89	91	75-125	1
Lead	mg/L	ND	0.1	0.1	0.1	0.095	0.094	95	94	75-125	1
Lithium	mg/L	0.053	0.1	0.1	0.1	0.14	0.14	89	89	75-125	0
Molybdenum	mg/L	0.010	0.1	0.1	0.1	0.11	0.11	99	99	75-125	1
Selenium	mg/L	ND	0.1	0.1	0.1	0.097	0.096	97	96	75-125	1
Thallium	mg/L	ND	0.1	0.1	0.1	0.094	0.095	94	94	75-125	0

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

QC Batch:	882891	Analysis Method:	EPA 7470A
QC Batch Method:	EPA 7470A	Analysis Description:	7470 Mercury
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92752167001, 92752167002, 92752167003, 92752167004, 92752167005, 92752167006, 92752167007, 92752167008, 92752167009, 92752167010, 92752167011, 92752167012		

METHOD BLANK:	4546909	Matrix:	Water
Associated Lab Samples:	92752167001, 92752167002, 92752167003, 92752167004, 92752167005, 92752167006, 92752167007, 92752167008, 92752167009, 92752167010, 92752167011, 92752167012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	09/17/24 10:11	

LABORATORY CONTROL SAMPLE: 4546910						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0024	94	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:					4546911								4546912			
Parameter	Units	92752167003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual				
Mercury	mg/L	ND	0.0025	0.0025	0.0028	0.0025	110	99	75-125	11	20					

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

QC Batch: 881518 Analysis Method: SM 2540C-2015
QC Batch Method: SM 2540C-2015 Analysis Description: 2540C Total Dissolved Solids
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92752167001, 92752167003, 92752167004, 92752167005, 92752167006

METHOD BLANK: 4539487 Matrix: Water
Associated Lab Samples: 92752167001, 92752167003, 92752167004, 92752167005, 92752167006

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	09/10/24 12:49	

LABORATORY CONTROL SAMPLE: 4539488

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	393	98	80-120	

SAMPLE DUPLICATE: 4539489

Parameter	Units	92745448001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	9160	9160	0	10	H1

SAMPLE DUPLICATE: 4539490

Parameter	Units	92751692003 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	1320	1310	0	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

QC Batch: 881821 Analysis Method: SM 2540C-2015
QC Batch Method: SM 2540C-2015 Analysis Description: 2540C Total Dissolved Solids
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92752167002, 92752167007, 92752167008, 92752167009, 92752167010, 92752167011, 92752167012

METHOD BLANK: 4541049 Matrix: Water
Associated Lab Samples: 92752167002, 92752167007, 92752167008, 92752167009, 92752167010, 92752167011, 92752167012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	09/11/24 13:43	

LABORATORY CONTROL SAMPLE: 4541050

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	425	106	80-120	

SAMPLE DUPLICATE: 4541051

Parameter	Units	92752167007 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	570	598	5	10	

SAMPLE DUPLICATE: 4541052

Parameter	Units	92751700009 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	1220	1220	0	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

QC Batch: 881613 Analysis Method: SM 2320B-2011
QC Batch Method: SM 2320B-2011 Analysis Description: 2320B Alkalinity
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92752167001, 92752167003, 92752167004, 92752167005, 92752167006, 92752167007, 92752167009

METHOD BLANK: 4540209 Matrix: Water
Associated Lab Samples: 92752167001, 92752167003, 92752167004, 92752167005, 92752167006, 92752167007, 92752167009

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	09/11/24 12:15	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	09/11/24 12:15	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	09/11/24 12:15	

LABORATORY CONTROL SAMPLE: 4540210

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.0	104	80-120	

LABORATORY CONTROL SAMPLE: 4540211

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.4	103	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4540212 4540213

Parameter	Units	92752097001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	43.2	50	50	91.4	92.4	97	98	80-120	1	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4540214 4540215

Parameter	Units	92752097002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	60.7	50	50	112	112	102	102	80-120	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

QC Batch: 881617 Analysis Method: SM 2320B-2011
QC Batch Method: SM 2320B-2011 Analysis Description: 2320B Alkalinity
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92752167002, 92752167008, 92752167010, 92752167011, 92752167012

METHOD BLANK: 4540224 Matrix: Water
Associated Lab Samples: 92752167002, 92752167008, 92752167010, 92752167011, 92752167012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	09/11/24 16:20	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	09/11/24 16:20	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	09/11/24 16:20	

LABORATORY CONTROL SAMPLE: 4540225

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.3	105	80-120	

LABORATORY CONTROL SAMPLE: 4540226

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.1	104	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4540227 4540228

Parameter	Units	92752128010 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	68.8	50	50	84.8	84.3	32	31	80-120	1	25	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4540229 4540230

Parameter	Units	92752128011 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	37.0	50	50	71.7	72.0	69	70	80-120	0	25	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

QC Batch: 881394 Analysis Method: SM 4500-S2D-2011
QC Batch Method: SM 4500-S2D-2011 Analysis Description: 4500S2D Sulfide Water
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92752167001, 92752167002, 92752167003, 92752167004, 92752167005, 92752167006, 92752167007, 92752167008, 92752167009, 92752167010, 92752167011, 92752167012

METHOD BLANK: 4539194 Matrix: Water
Associated Lab Samples: 92752167001, 92752167002, 92752167003, 92752167004, 92752167005, 92752167006, 92752167007, 92752167008, 92752167009, 92752167010, 92752167011, 92752167012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	09/10/24 04:20	

LABORATORY CONTROL SAMPLE: 4539195						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.45	90	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4539196 4539197												
Parameter	Units	92751700001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.49	0.54	97	108	80-120	10	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4539198 4539199												
Parameter	Units	92752167009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.51	0.54	101	107	80-120	5	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

QC Batch: 881368 Analysis Method: EPA 300.0 Rev 2.1 1993
QC Batch Method: EPA 300.0 Rev 2.1 1993 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92752167001

METHOD BLANK: 4539005 Matrix: Water
Associated Lab Samples: 92752167001

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	09/09/24 21:06	
Fluoride	mg/L	ND	0.10	0.050	09/09/24 21:06	
Sulfate	mg/L	ND	1.0	0.50	09/09/24 21:06	

LABORATORY CONTROL SAMPLE: 4539006

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	51.6	103	90-110	
Fluoride	mg/L	2.5	2.7	108	90-110	
Sulfate	mg/L	50	52.1	104	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4539007 4539008

Parameter	Units	92751585003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	61.8	50	50	96.7	101	70	78	90-110	4	10	M1
Fluoride	mg/L		2.5	2.5	3.4	3.6	109	116	90-110	5	10	M1
Sulfate	mg/L	47.9	50	50	97.0	88.0	98	80	90-110	10	10	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4539009 4539010

Parameter	Units	92752128005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	13.0	50	50	62.5	66.4	99	107	90-110	6	10	
Fluoride	mg/L	0.60	2.5	2.5	4.2	4.6	146	159	90-110	7	10	M1
Sulfate	mg/L	2770	50	50	2810	2900	86	272	90-110	3	10	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

QC Batch:	881369	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92752167002, 92752167003, 92752167005, 92752167006, 92752167007, 92752167008, 92752167009, 92752167010, 92752167011, 92752167012		

METHOD BLANK: 4539017 Matrix: Water
Associated Lab Samples: 92752167002, 92752167003, 92752167005, 92752167006, 92752167007, 92752167008, 92752167009, 92752167010, 92752167011, 92752167012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	09/09/24 21:38	
Fluoride	mg/L	ND	0.10	0.050	09/09/24 21:38	
Sulfate	mg/L	ND	1.0	0.50	09/09/24 21:38	

LABORATORY CONTROL SAMPLE: 4539018

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	51.6	103	90-110	
Fluoride	mg/L	2.5	2.7	107	90-110	
Sulfate	mg/L	50	52.0	104	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4539019 4539020

Parameter	Units	92752167002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	19.3	50	50	69.0	73.0	99	107	90-110	6	10	
Fluoride	mg/L	0.16	2.5	2.5	2.7	3.0	103	112	90-110	8	10 M1	
Sulfate	mg/L	193	50	50	237	237	89	89	90-110	0	10 M1	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4539021 4539022

Parameter	Units	92751692006 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	5.4	50	50	55.1	59.2	99	108	90-110	7	10	
Fluoride	mg/L	0.12	2.5	2.5	2.8	3.0	106	116	90-110	9	10 M1	
Sulfate	mg/L	155	50	50	195	195	80	80	90-110	0	10 M1	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

QC Batch:	881544	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville

Associated Lab Samples: 92752167004

METHOD BLANK: 4539722 Matrix: Water
Associated Lab Samples: 92752167004

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	09/10/24 14:58	
Fluoride	mg/L	ND	0.10	0.050	09/10/24 14:58	
Sulfate	mg/L	ND	1.0	0.50	09/10/24 14:58	

LABORATORY CONTROL SAMPLE: 4539723

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	50.9	102	90-110	
Fluoride	mg/L	2.5	2.6	102	90-110	
Sulfate	mg/L	50	50.8	102	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4539724 4539725

Parameter	Units	92751585001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	54.2	50	50	83.3	77.1	58	46	90-110	8	10	M1
Fluoride	mg/L		2.5	2.5	2.4	2.6	97	102	90-110	5	10	
Sulfate	mg/L	30.4	50	50	79.4	81.7	98	103	90-110	3	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1 (CA)-20240904
Pace Project No.: 92752167

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

H1 Analysis conducted outside the EPA method holding time.
M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92752167001	HAM-PT-07	EPA 3010A	881937	EPA 6010D	882242
92752167002	HAM-PT-08	EPA 3010A	881937	EPA 6010D	882242
92752167003	HAM-PT-09	EPA 3010A	881937	EPA 6010D	882242
92752167004	HAM-PT-10	EPA 3010A	881937	EPA 6010D	882242
92752167005	HAM-PT-11	EPA 3010A	881937	EPA 6010D	882242
92752167006	HAM-PT-12	EPA 3010A	881937	EPA 6010D	882242
92752167007	HAM-PT-13	EPA 3010A	881937	EPA 6010D	882242
92752167008	HAM-PT-14	EPA 3010A	881937	EPA 6010D	882242
92752167009	HAM-PT-15	EPA 3010A	881937	EPA 6010D	882242
92752167010	HAM-AP1-EB-01	EPA 3010A	881937	EPA 6010D	882242
92752167011	HAM-AP1-FB-01	EPA 3010A	881937	EPA 6010D	882242
92752167012	HAM-AP1-FD-01	EPA 3010A	881937	EPA 6010D	882242
92752167001	HAM-PT-07	EPA 3005A	881820	EPA 6020B	881940
92752167002	HAM-PT-08	EPA 3005A	881820	EPA 6020B	881940
92752167003	HAM-PT-09	EPA 3005A	881820	EPA 6020B	881940
92752167004	HAM-PT-10	EPA 3005A	881820	EPA 6020B	881940
92752167005	HAM-PT-11	EPA 3005A	881820	EPA 6020B	881940
92752167006	HAM-PT-12	EPA 3005A	881820	EPA 6020B	881940
92752167007	HAM-PT-13	EPA 3005A	881820	EPA 6020B	881940
92752167008	HAM-PT-14	EPA 3005A	881820	EPA 6020B	881940
92752167009	HAM-PT-15	EPA 3005A	881820	EPA 6020B	881940
92752167010	HAM-AP1-EB-01	EPA 3005A	881820	EPA 6020B	881940
92752167011	HAM-AP1-FB-01	EPA 3005A	881820	EPA 6020B	881940
92752167012	HAM-AP1-FD-01	EPA 3005A	881820	EPA 6020B	881940
92752167001	HAM-PT-07	EPA 7470A	882891	EPA 7470A	883081
92752167002	HAM-PT-08	EPA 7470A	882891	EPA 7470A	883081
92752167003	HAM-PT-09	EPA 7470A	882891	EPA 7470A	883081
92752167004	HAM-PT-10	EPA 7470A	882891	EPA 7470A	883081
92752167005	HAM-PT-11	EPA 7470A	882891	EPA 7470A	883081
92752167006	HAM-PT-12	EPA 7470A	882891	EPA 7470A	883081
92752167007	HAM-PT-13	EPA 7470A	882891	EPA 7470A	883081
92752167008	HAM-PT-14	EPA 7470A	882891	EPA 7470A	883081
92752167009	HAM-PT-15	EPA 7470A	882891	EPA 7470A	883081
92752167010	HAM-AP1-EB-01	EPA 7470A	882891	EPA 7470A	883081
92752167011	HAM-AP1-FB-01	EPA 7470A	882891	EPA 7470A	883081
92752167012	HAM-AP1-FD-01	EPA 7470A	882891	EPA 7470A	883081
92752167001	HAM-PT-07	SM 2540C-2015	881518		
92752167002	HAM-PT-08	SM 2540C-2015	881821		
92752167003	HAM-PT-09	SM 2540C-2015	881518		
92752167004	HAM-PT-10	SM 2540C-2015	881518		
92752167005	HAM-PT-11	SM 2540C-2015	881518		
92752167006	HAM-PT-12	SM 2540C-2015	881518		
92752167007	HAM-PT-13	SM 2540C-2015	881821		
92752167008	HAM-PT-14	SM 2540C-2015	881821		
92752167009	HAM-PT-15	SM 2540C-2015	881821		
92752167010	HAM-AP1-EB-01	SM 2540C-2015	881821		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1 (CA)-20240904

Pace Project No.: 92752167

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92752167011	HAM-AP1-FB-01	SM 2540C-2015	881821		
92752167012	HAM-AP1-FD-01	SM 2540C-2015	881821		
92752167001	HAM-PT-07	SM 2320B-2011	881613		
92752167002	HAM-PT-08	SM 2320B-2011	881617		
92752167003	HAM-PT-09	SM 2320B-2011	881613		
92752167004	HAM-PT-10	SM 2320B-2011	881613		
92752167005	HAM-PT-11	SM 2320B-2011	881613		
92752167006	HAM-PT-12	SM 2320B-2011	881613		
92752167007	HAM-PT-13	SM 2320B-2011	881613		
92752167008	HAM-PT-14	SM 2320B-2011	881617		
92752167009	HAM-PT-15	SM 2320B-2011	881613		
92752167010	HAM-AP1-EB-01	SM 2320B-2011	881617		
92752167011	HAM-AP1-FB-01	SM 2320B-2011	881617		
92752167012	HAM-AP1-FD-01	SM 2320B-2011	881617		
92752167001	HAM-PT-07	SM 4500-S2D-2011	881394		
92752167002	HAM-PT-08	SM 4500-S2D-2011	881394		
92752167003	HAM-PT-09	SM 4500-S2D-2011	881394		
92752167004	HAM-PT-10	SM 4500-S2D-2011	881394		
92752167005	HAM-PT-11	SM 4500-S2D-2011	881394		
92752167006	HAM-PT-12	SM 4500-S2D-2011	881394		
92752167007	HAM-PT-13	SM 4500-S2D-2011	881394		
92752167008	HAM-PT-14	SM 4500-S2D-2011	881394		
92752167009	HAM-PT-15	SM 4500-S2D-2011	881394		
92752167010	HAM-AP1-EB-01	SM 4500-S2D-2011	881394		
92752167011	HAM-AP1-FB-01	SM 4500-S2D-2011	881394		
92752167012	HAM-AP1-FD-01	SM 4500-S2D-2011	881394		
92752167001	HAM-PT-07	EPA 300.0 Rev 2.1 1993	881368		
92752167002	HAM-PT-08	EPA 300.0 Rev 2.1 1993	881369		
92752167003	HAM-PT-09	EPA 300.0 Rev 2.1 1993	881369		
92752167004	HAM-PT-10	EPA 300.0 Rev 2.1 1993	881544		
92752167005	HAM-PT-11	EPA 300.0 Rev 2.1 1993	881369		
92752167006	HAM-PT-12	EPA 300.0 Rev 2.1 1993	881369		
92752167007	HAM-PT-13	EPA 300.0 Rev 2.1 1993	881369		
92752167008	HAM-PT-14	EPA 300.0 Rev 2.1 1993	881369		
92752167009	HAM-PT-15	EPA 300.0 Rev 2.1 1993	881369		
92752167010	HAM-AP1-EB-01	EPA 300.0 Rev 2.1 1993	881369		
92752167011	HAM-AP1-FB-01	EPA 300.0 Rev 2.1 1993	881369		
92752167012	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	881369		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CHAIN-OF-CUSTODY / Analytical Request D

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be complete

W0#: 92752167



92752167

Section A Required Client Information:		Section B Required Project Information:		Section C Invoice Information:		Page: 1 of 1	
Company: GA Power		Report To: SCS Contacts		Attention: Southern Co.		REGULATORY AGENCY ☐ NPDES ☐ GROUND WATER ☐ DRINKING WATER ☐ UST ☐ RCRA ☒ OTHER CCE	
Address: Atlanta, GA		Copy To: Geosyntec Contacts		Company Name:			
Email To: SCS Contacts		Purchase Order No.: GPC82474-0001		Address:		Site Location	
Phone: Fax:		Project Name: Hammond AP-1		Pace Quote Reference:		STATE: GA	
Requested Due Date/TAT: 10 Day		Project Number:		Pace Project Manager: Bonnie Vang			
				Pace Profile #: 10839			

ITEM #	Section D Required Client Information	Valid Matrix Codes MATRIX CODE DRINKING WATER DW WATER WT WASTE WATER WW PRODUCT P SOIL/SOLID SL OIL OL WIPE WP AIR AR OTHER OT TISSUE TS	MATRIX CODE (see valid codes to left)	SAMPLE TYPE (G=GRAB C=COMP)	COLLECTED				SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives								Analysis Test	Requested Analysis Filtered (Y/N)												Residual Chlorine (Y/N)	Pace Project No./ Lab I.D.				
					COMPOSITE		COMPOSITE				Unpreserved	H ₂ SO ₄	HNO ₃	HCl	NaOH	Na ₂ S ₂ O ₃	Methanol	Other		Chloride, Fluoride, Sulfate	Full App. III and IV metals	Major Ions (Profile 10839-2)	TDS														
					DATE	TIME	DATE	TIME																													
1	HAM-PT-07		WG	G	9/4/2024	1538			20	5	3		1						1	X	X	X	X									N	001				
2	HAM-PT-08		WG	G	9/5/2024	1247			20	5	3		1						1	X	X	X	X									N	002				
3	HAM-PT-09		WG	G	9/4/2024	1320			22	5	3		1						1	X	X	X	X									N	003				
4	HAM-PT-10		WG	G	9/4/2024	1135			22	5	3		1						1	X	X	X	X									N	004				
5	HAM-PT-11		WG	G	9/4/2024	1125			22	5	3		1						1	X	X	X	X									N	005				
6	HAM-PT-12		WG	G	9/4/2024	1525			22	5	3		1						1	X	X	X	X									N	006				
7	HAM-PT-13		WG	G	9/4/2024	1400			21	5	3		1						1	X	X	X	X									N	007				
8	HAM-PT-14		WG	G	9/5/2024	1135			21	5	3		1						1	X	X	X	X									N	008				
9	HAM-PT-15		WG	G	9/4/2024	1610			20	5	3		1						1	X	X	X	X									N	009				
10	HAM-AP1-EB-01		WQ	G	9/5/2024	1435			20	5	3		1						1	X	X	X	X									N	010				
11	HAM-AP1-FB-01		WQ	G	9/5/2024	1430			20	5	3		1						1	X	X	X	X									N	011				
12	HAM-AP1-FD-01		WG	G	9/5/2024	0000			20	5	3		1						1	X	X	X	X									N	012				

ADDITIONAL COMMENTS		RELINQUISHED BY / AFFILIATION		DATE	TIME	ACCEPTED BY / AFFILIATION		DATE	TIME	SAMPLE CONDITIONS	
Task Code: HAM-CCR-CA-20240904		Jamie Newsome / Geosyntec		9/6/24	1154	Ryan Williams / Pace		9/6/24	1154		
		Ryan Williams / Pace		9/6/24	1245			9/6/24	1245		

SAMPLER NAME AND SIGNATURE		Temp in °C	Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)	Samples Intact (Y/N)
PRINT Name of SAMPLER: Jamie Newsome / Geosyntec Consultants, Inc.					
SIGNATURE OF SAMPLER:					
DATE Signed (MM/DD/YY): 9/5/24					

Important Note: By signing this form you are accepting Pace's NET 30 day payment terms and agreeing to late charges of 1.5% per month for any invoices not paid within 30 days.


F-ALL-Q-020rev.07, 15-Feb-2007



DO#_FILE: ENV-FRM-NON-0003 V03 Sample Collection Upon Receipt

Effective Date: 05/24/2024

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ N

Client Name:

GM

PWC

Project #

Courier:

☐ Commercial☐ Fed Ex☒ Pace☐ UPS☐ USPS☐ Other:☐ Client

Custody Seal Present?

☒ Yes☐ No

Seals Intact?

☒ Yes☐ No☐ N/A

Packing Material:

☒ Bubble Wrap☐ Bubble Bags☐ None☐ Other

Thermometer:

☒ IR Gun ID:

230

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

31

Correction Factor:

Add/Subtract (°C)

0.0

Cooler Temp Corrected (°C):

3.1

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

			Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.	
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.	
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.	
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4.	
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.	
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.	
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A	7.	
Containers Intact?	☒ Yes ☐ No ☐ N/A	8.	
Dissolved analysis: Samples Field Filtered?	☐ Yes ☐ No ☒ N/A	9.	
Sample Labels Match COC?	☐ Yes ☐ No ☐ N/A		
-Includes Date/Time/ID/Analysis Matrix: <u>W</u>			
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10.	
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.	
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A		

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

AGENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐

Client _____ Profile/EZ (Circle one) _____ Notes _____

Item#	CC	BP4U-125 mL Plastic Unpreserved (N/A) (C-)	BP4U-250 mL Plastic Unpreserved (N/A)	BP7U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (C-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic 2N Acetate & NaOH (S)	BP4B-125 mL Plastic NaOH (pH > 12) (C-)	WGTU-Wide-mouthed Glass Jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (C-)	AG1N-1 liter Amber HCl (pH < 2)	AGBU-250 mL Amber Unpreserved (N/A) (C-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG84-40 mL Amber NH4Cl (N/A) (C-)	DG8H-40 mL VOA HCl (N/A)	VG87-40 mL VOA Na2S2O3 (N/A)	VG8U-40 mL VOA Unpreserved (N/A)	DC9V-40 mL VOA H3PO4 (N/A)	KPTU-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit) VPH/Gas kit (N/A)	SP9T-125 mL Sterile Plastic (N/A - lab)	SP9T-250 mL Sterile Plastic (N/A - lab)	BP3B-250 mL Plastic (NH2)2CO4 (D.3.9.7)	AGBU-100 mL Amber Unpreserved (N/A) (C-)	VSBU-20 mL Scintillation vial (N/A)	
1			✓	✓			✓	✓	✓																			
2			✓	✓			✓	✓	✓																			
3			✓	✓			✓	✓	✓																			
4			✓	✓			✓	✓	✓																			
5			✓	✓			✓	✓	✓																			
6			✓	✓			✓	✓	✓																			
7			✓	✓			✓	✓	✓																			
8			✓	✓			✓	✓	✓																			
9			✓	✓			✓	✓	✓																			
10			✓	✓			✓	✓	✓																			
11			✓	✓			✓	✓	✓																			
12			✓	✓			✓	✓	✓																			

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers.



October 21, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1_Week 1
Pace Project No.: 92756037

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on September 26, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Duluth, MN
- Pace Analytical Services - Peachtree Corners, GA
- Pace Analytical Services - Minneapolis

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Jamie Newsome, Geosyntec Consultants
Zain Webb, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Pace Analytical Services, LLC - Minneapolis MN

1700 Elm Street SE, Minneapolis, MN 55414

Alabama Certification #: 40770

Alaska Contaminated Sites Certification #: 17-009

Alaska DW Certification #: MN00064

Arizona Certification #: AZ0014

Arkansas DW Certification #: MN00064

Arkansas WW Certification #: 88-0680

California Certification #: 2929

Colorado Certification #: MN00064

Connecticut Certification #: PH-0256

DoD Certification via A2LA #: 2926.01

EPA Region 8 Tribal Water Systems+Wyoming DW
Certification #: via MN 027-053-137

Florida Certification #: E87605

Georgia Certification #: 959

GMP+ Certification #: GMP050884

Hawaii Certification #: MN00064

Idaho Certification #: MN00064

Illinois Certification #: 200011

Indiana Certification #: C-MN-01

Iowa Certification #: 368

ISO/IEC 17025 Certification via A2LA #: 2926.01

Kansas Certification #: E-10167

Kentucky DW Certification #: 90062

Kentucky WW Certification #: 90062

Louisiana DEQ Certification #: AI-03086

Louisiana DW Certification #: MN00064

Maine Certification #: MN00064

Maryland Certification #: 322

Michigan Certification #: 9909

Minnesota Certification #: 027-053-137

Minnesota Dept of Ag Approval: via MN 027-053-137

Minnesota Petrofund Registration #: 1240

Mississippi Certification #: MN00064

Missouri Certification #: 10100

Montana Certification #: CERT0092

Nebraska Certification #: NE-OS-18-06

Nevada Certification #: MN00064

New Hampshire Certification #: 2081

New Jersey Certification #: MN002

New York Certification #: 11647

North Carolina DW Certification #: 27700

North Carolina WW Certification #: 530

North Dakota Certification (A2LA) #: R-036

North Dakota Certification (MN) #: R-036

Ohio DW Certification #: 41244

Ohio VAP Certification (1700) #: CL101

Oklahoma Certification #: 9507

Oregon Primary Certification #: MN300001

Oregon Secondary Certification #: MN200001

Pennsylvania Certification #: 68-00563

Puerto Rico Certification #: MN00064

South Carolina Certification #: 74003001

Tennessee Certification #: TN02818

Texas Certification #: T104704192

Utah Certification #: MN00064

Vermont Certification #: VT-027053137

Virginia Certification #: 460163

Washington Certification #: C486

West Virginia DEP Certification #: 382

West Virginia DW Certification #: 9952 C

Wisconsin Certification #: 999407970

Wyoming UST Certification via A2LA #: 2926.01

USDA Permit #: P330-19-00208

Pace Analytical Services, LLC - Duluth MN

4730 Oneota Street, Duluth, MN 55807

Minnesota Certification #: 027-137-152

Minnesota Dept of Ag Approval: via Minnesota 027-137-
152

Minnesota Petrofund Registration #: 1240

North Dakota Certification #: R-105

Wisconsin Certification #: 999446800

Wisconsin Dept of Ag Certification #: 480341

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92756037001	HAM-PT-07	Water	09/24/24 16:20	09/26/24 11:40
92756037002	HAM-PT-08	Water	09/24/24 14:31	09/26/24 11:40
92756037003	HAM-PT-09	Water	09/25/24 12:30	09/26/24 11:40
92756037004	HAM-PT-10	Water	09/25/24 10:00	09/26/24 11:40
92756037005	HAM-PT-11	Water	09/25/24 14:54	09/26/24 11:40
92756037006	HAM-PT-12	Water	09/25/24 16:50	09/26/24 11:40
92756037007	HAM-PT-13	Water	09/24/24 12:25	09/26/24 11:40
92756037008	HAM-PT-14	Water	09/24/24 14:40	09/26/24 11:40
92756037009	HAM-PT-15	Water	09/24/24 11:03	09/26/24 11:40
92756037010	HAM-AP1-FD-01	Water	09/24/24 00:00	09/26/24 11:40
92756037011	HAM-AP1-FB-01	Water	09/25/24 17:40	09/26/24 11:40
92756037012	HAM-AP1-EB-01	Water	09/25/24 17:45	09/26/24 11:40

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
92756037001	HAM-PT-07	EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	DRB	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
92756037002	HAM-PT-08	EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	DRB	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
92756037003	HAM-PT-09	EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	DRB	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
92756037004	HAM-PT-10	EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	DRB	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
92756037005	HAM-PT-11	EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	DRB	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
92756037006	HAM-PT-12	EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
92756037007	HAM-PT-13	EPA 6010D	DRB	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
		EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	DRB	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
92756037008	HAM-PT-14	SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
		EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	DRB	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
		EPA 300.0	JA2	3	PASI-DU
92756037009	HAM-PT-15	SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	DRB	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
		EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	DRB	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
92756037010	HAM-AP1-FD-01	EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
		EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	DRB	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
92756037011	HAM-AP1-FB-01	EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	DRB	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
92756037012	HAM-AP1-EB-01	EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
		EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	DRB	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M

PASI-DU = Pace Analytical Services - Duluth, MN

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

PASI-M = Pace Analytical Services - Minneapolis

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92756037001	HAM-PT-07					
EPA 300.0	Chloride	17.5	mg/L	1.0	10/16/24 10:35	
EPA 300.0	Fluoride	0.26	mg/L	0.050	10/16/24 10:35	
EPA 300.0	Sulfate	249	mg/L	1.0	10/16/24 10:35	
EPA 6010D	Iron	0.54	mg/L	0.040	10/02/24 11:58	
EPA 6010D	Manganese	2.4	mg/L	0.040	10/02/24 11:58	
EPA 6010D	Potassium	5.9	mg/L	0.50	10/02/24 11:58	
EPA 6010D	Sodium	10.2	mg/L	1.0	10/02/24 11:58	
EPA 6010D	Calcium	128	mg/L	1.0	10/02/24 11:58	
EPA 6010D	Magnesium	18.7	mg/L	0.050	10/02/24 11:58	
EPA 6020B	Antimony	0.00056J	mg/L	0.0030	10/01/24 17:44	
EPA 6020B	Arsenic	0.016	mg/L	0.0050	10/01/24 17:44	B
EPA 6020B	Barium	0.056	mg/L	0.0050	10/01/24 17:44	
EPA 6020B	Beryllium	0.00012J	mg/L	0.00050	10/01/24 17:44	
EPA 6020B	Boron	0.54	mg/L	0.040	10/01/24 17:44	
EPA 6020B	Cadmium	0.00015J	mg/L	0.00050	10/01/24 17:44	
EPA 6020B	Cobalt	0.031	mg/L	0.0050	10/01/24 17:44	
EPA 6020B	Lithium	0.048	mg/L	0.030	10/01/24 17:44	
EPA 6020B	Molybdenum	0.0054J	mg/L	0.010	10/01/24 17:44	
EPA 6020B	Selenium	0.0011J	mg/L	0.0050	10/01/24 17:44	
EPA 6020B	Thallium	0.00067J	mg/L	0.0010	10/01/24 17:44	
SM 2540C-2015	Total Dissolved Solids	559	mg/L	25.0	10/01/24 15:58	
SM 2320B	Alkalinity, Total as CaCO3	136	mg/L	5.0	10/07/24 09:09	
SM 2320B	Alkalinity,Bicarbonate (CaCO3)	136	mg/L	5.0	10/07/24 09:09	
92756037002	HAM-PT-08					
EPA 300.0	Chloride	17.1	mg/L	1.0	10/16/24 11:20	
EPA 300.0	Fluoride	0.25	mg/L	0.050	10/16/24 11:20	
EPA 300.0	Sulfate	239	mg/L	1.0	10/16/24 11:20	
EPA 6010D	Iron	1.1	mg/L	0.040	10/02/24 12:03	
EPA 6010D	Manganese	2.5	mg/L	0.040	10/02/24 12:03	
EPA 6010D	Potassium	5.3	mg/L	0.50	10/02/24 12:03	
EPA 6010D	Sodium	9.1	mg/L	1.0	10/02/24 12:03	
EPA 6010D	Calcium	112	mg/L	1.0	10/02/24 12:03	M1
EPA 6010D	Magnesium	14.3	mg/L	0.050	10/02/24 12:03	M1
EPA 6020B	Antimony	0.0012J	mg/L	0.0030	10/01/24 17:59	
EPA 6020B	Arsenic	0.021	mg/L	0.0050	10/01/24 17:59	
EPA 6020B	Barium	0.050	mg/L	0.0050	10/01/24 17:59	
EPA 6020B	Beryllium	0.00013J	mg/L	0.00050	10/01/24 17:59	
EPA 6020B	Boron	0.61	mg/L	0.040	10/01/24 17:59	
EPA 6020B	Cadmium	0.00018J	mg/L	0.00050	10/01/24 17:59	
EPA 6020B	Cobalt	0.022	mg/L	0.0050	10/01/24 17:59	
EPA 6020B	Lithium	0.035	mg/L	0.030	10/01/24 17:59	
EPA 6020B	Molybdenum	0.0098J	mg/L	0.010	10/01/24 17:59	
EPA 6020B	Selenium	0.0013J	mg/L	0.0050	10/01/24 17:59	
EPA 6020B	Thallium	0.00050J	mg/L	0.0010	10/01/24 17:59	
SM 2540C-2015	Total Dissolved Solids	490	mg/L	25.0	10/01/24 15:58	
SM 2320B	Alkalinity, Total as CaCO3	91.8	mg/L	5.0	10/07/24 09:27	
SM 2320B	Alkalinity,Bicarbonate (CaCO3)	91.8	mg/L	5.0	10/07/24 09:27	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92756037003	HAM-PT-09					
EPA 300.0	Chloride	39.4	mg/L	1.0	10/16/24 12:05	
EPA 300.0	Fluoride	0.33	mg/L	0.050	10/16/24 12:05	
EPA 300.0	Sulfate	236	mg/L	1.0	10/16/24 12:05	
EPA 6010D	Iron	0.24	mg/L	0.040	10/02/24 12:22	
EPA 6010D	Manganese	0.73	mg/L	0.040	10/02/24 12:22	
EPA 6010D	Potassium	5.8	mg/L	0.50	10/02/24 12:22	
EPA 6010D	Sodium	7.0	mg/L	1.0	10/02/24 12:22	
EPA 6010D	Calcium	111	mg/L	1.0	10/02/24 12:22	
EPA 6010D	Magnesium	27.2	mg/L	0.050	10/02/24 12:22	
EPA 6020B	Arsenic	0.0034J	mg/L	0.0050	10/01/24 18:03	B
EPA 6020B	Barium	0.089	mg/L	0.0050	10/01/24 18:03	
EPA 6020B	Boron	1.2	mg/L	0.040	10/01/24 18:03	
EPA 6020B	Cadmium	0.00030J	mg/L	0.00050	10/01/24 18:03	
EPA 6020B	Cobalt	0.0066	mg/L	0.0050	10/01/24 18:03	
EPA 6020B	Lithium	0.0035J	mg/L	0.030	10/01/24 18:03	
EPA 6020B	Molybdenum	0.14	mg/L	0.010	10/01/24 18:03	
SM 2540C-2015	Total Dissolved Solids	547	mg/L	25.0	10/01/24 16:01	
SM 2320B	Alkalinity, Total as CaCO3	112	mg/L	5.0	10/07/24 09:31	
SM 2320B	Alkalinity,Bicarbonate (CaCO3)	112	mg/L	5.0	10/07/24 09:31	
92756037004	HAM-PT-10					
EPA 300.0	Chloride	49.6	mg/L	1.0	10/16/24 12:20	
EPA 300.0	Fluoride	0.32	mg/L	0.050	10/16/24 12:20	
EPA 300.0	Sulfate	158	mg/L	1.0	10/16/24 12:20	
EPA 6010D	Iron	0.060	mg/L	0.040	10/02/24 12:27	
EPA 6010D	Manganese	0.43	mg/L	0.040	10/02/24 12:27	
EPA 6010D	Potassium	6.6	mg/L	0.50	10/02/24 12:27	
EPA 6010D	Sodium	9.0	mg/L	1.0	10/02/24 12:27	
EPA 6010D	Calcium	113	mg/L	1.0	10/02/24 12:27	
EPA 6010D	Magnesium	14.2	mg/L	0.050	10/02/24 12:27	
EPA 6020B	Arsenic	0.0024J	mg/L	0.0050	10/01/24 18:07	B
EPA 6020B	Barium	0.053	mg/L	0.0050	10/01/24 18:07	
EPA 6020B	Boron	1.6	mg/L	0.040	10/01/24 18:07	
EPA 6020B	Cadmium	0.00017J	mg/L	0.00050	10/01/24 18:07	
EPA 6020B	Chromium	0.0039J	mg/L	0.0050	10/01/24 18:07	
EPA 6020B	Cobalt	0.0019J	mg/L	0.0050	10/01/24 18:07	
EPA 6020B	Molybdenum	0.23	mg/L	0.010	10/01/24 18:07	
SM 2540C-2015	Total Dissolved Solids	521	mg/L	25.0	10/01/24 16:01	
SM 2320B	Alkalinity, Total as CaCO3	131	mg/L	5.0	10/07/24 09:36	
SM 2320B	Alkalinity,Bicarbonate (CaCO3)	131	mg/L	5.0	10/07/24 09:36	
92756037005	HAM-PT-11					
EPA 300.0	Chloride	48.3	mg/L	1.0	10/16/24 13:05	
EPA 300.0	Fluoride	0.33	mg/L	0.050	10/16/24 13:05	
EPA 300.0	Sulfate	200	mg/L	1.0	10/16/24 13:05	
EPA 6010D	Iron	3.7	mg/L	0.040	10/02/24 12:32	
EPA 6010D	Manganese	1.4	mg/L	0.040	10/02/24 12:32	
EPA 6010D	Potassium	5.6	mg/L	0.50	10/02/24 12:32	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92756037005	HAM-PT-11					
EPA 6010D	Sodium	8.1	mg/L	1.0	10/02/24 12:32	
EPA 6010D	Calcium	109	mg/L	1.0	10/02/24 12:32	
EPA 6010D	Magnesium	20.3	mg/L	0.050	10/02/24 12:32	
EPA 6020B	Arsenic	0.0031J	mg/L	0.0050	10/01/24 18:10	B
EPA 6020B	Barium	0.078	mg/L	0.0050	10/01/24 18:10	
EPA 6020B	Boron	1.5	mg/L	0.040	10/01/24 18:10	
EPA 6020B	Cadmium	0.00030J	mg/L	0.00050	10/01/24 18:10	
EPA 6020B	Cobalt	0.025	mg/L	0.0050	10/01/24 18:10	
EPA 6020B	Lithium	0.0067J	mg/L	0.030	10/01/24 18:10	
EPA 6020B	Molybdenum	0.074	mg/L	0.010	10/01/24 18:10	
SM 2540C-2015	Total Dissolved Solids	546	mg/L	25.0	10/01/24 16:02	
SM 2320B	Alkalinity, Total as CaCO ₃	98.0	mg/L	5.0	10/07/24 09:41	
SM 2320B	Alkalinity,Bicarbonate (CaCO ₃)	98.0	mg/L	5.0	10/07/24 09:41	
92756037006	HAM-PT-12					
EPA 300.0	Chloride	22.9	mg/L	1.0	10/16/24 13:20	
EPA 300.0	Fluoride	0.27	mg/L	0.050	10/16/24 13:20	
EPA 300.0	Sulfate	266	mg/L	1.0	10/16/24 13:20	
EPA 6010D	Iron	0.21	mg/L	0.040	10/02/24 12:50	
EPA 6010D	Manganese	2.6	mg/L	0.040	10/02/24 12:50	
EPA 6010D	Potassium	5.1	mg/L	0.50	10/02/24 12:50	
EPA 6010D	Sodium	6.1	mg/L	1.0	10/02/24 12:50	
EPA 6010D	Calcium	106	mg/L	1.0	10/02/24 12:50	
EPA 6010D	Magnesium	30.0	mg/L	0.050	10/02/24 12:50	
EPA 6020B	Arsenic	0.0031J	mg/L	0.0050	10/01/24 18:21	B
EPA 6020B	Barium	0.087	mg/L	0.0050	10/01/24 18:21	
EPA 6020B	Boron	0.81	mg/L	0.040	10/01/24 18:21	
EPA 6020B	Cadmium	0.00055	mg/L	0.00050	10/01/24 18:21	
EPA 6020B	Cobalt	0.011	mg/L	0.0050	10/01/24 18:21	
EPA 6020B	Lithium	0.0044J	mg/L	0.030	10/01/24 18:21	
EPA 6020B	Molybdenum	0.088	mg/L	0.010	10/01/24 18:21	
SM 2540C-2015	Total Dissolved Solids	573	mg/L	25.0	10/01/24 16:02	
SM 2320B	Alkalinity, Total as CaCO ₃	90.2	mg/L	5.0	10/07/24 10:03	
SM 2320B	Alkalinity,Bicarbonate (CaCO ₃)	90.2	mg/L	5.0	10/07/24 10:03	
92756037007	HAM-PT-13					
EPA 300.0	Chloride	16.9	mg/L	1.0	10/16/24 13:35	
EPA 300.0	Fluoride	0.36	mg/L	0.050	10/16/24 13:35	
EPA 300.0	Sulfate	261	mg/L	1.0	10/16/24 13:35	
EPA 6010D	Iron	5.3	mg/L	0.040	10/02/24 12:55	
EPA 6010D	Manganese	3.2	mg/L	0.040	10/02/24 12:55	
EPA 6010D	Potassium	5.4	mg/L	0.50	10/02/24 12:55	
EPA 6010D	Sodium	9.2	mg/L	1.0	10/02/24 12:55	
EPA 6010D	Calcium	122	mg/L	1.0	10/02/24 12:55	
EPA 6010D	Magnesium	16.1	mg/L	0.050	10/02/24 12:55	
EPA 6020B	Arsenic	0.021	mg/L	0.0050	10/01/24 18:25	
EPA 6020B	Barium	0.050	mg/L	0.0050	10/01/24 18:25	
EPA 6020B	Boron	0.49	mg/L	0.040	10/01/24 18:25	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92756037007	HAM-PT-13					
EPA 6020B	Cadmium	0.00011J	mg/L	0.00050	10/01/24 18:25	
EPA 6020B	Cobalt	0.022	mg/L	0.0050	10/01/24 18:25	
EPA 6020B	Lead	0.00057J	mg/L	0.0010	10/01/24 18:25	
EPA 6020B	Lithium	0.052	mg/L	0.030	10/01/24 18:25	
EPA 6020B	Molybdenum	0.0031J	mg/L	0.010	10/01/24 18:25	
EPA 6020B	Selenium	0.0013J	mg/L	0.0050	10/01/24 18:25	
SM 2540C-2015	Total Dissolved Solids	518	mg/L	25.0	10/01/24 15:59	
SM 2320B	Alkalinity, Total as CaCO3	105	mg/L	5.0	10/07/24 10:08	
SM 2320B	Alkalinity,Bicarbonate (CaCO3)	105	mg/L	5.0	10/07/24 10:08	
92756037008	HAM-PT-14					
EPA 300.0	Chloride	19.6	mg/L	1.0	10/16/24 13:50	
EPA 300.0	Fluoride	0.28	mg/L	0.050	10/16/24 13:50	
EPA 300.0	Sulfate	259	mg/L	1.0	10/16/24 13:50	
EPA 6010D	Iron	9.9	mg/L	0.040	10/02/24 13:00	
EPA 6010D	Manganese	3.4	mg/L	0.040	10/02/24 13:00	
EPA 6010D	Potassium	5.8	mg/L	0.50	10/02/24 13:00	
EPA 6010D	Sodium	10.3	mg/L	1.0	10/02/24 13:00	
EPA 6010D	Calcium	135	mg/L	1.0	10/02/24 13:00	
EPA 6010D	Magnesium	19.5	mg/L	0.050	10/02/24 13:00	
EPA 6020B	Arsenic	0.058	mg/L	0.0050	10/01/24 18:29	
EPA 6020B	Barium	0.050	mg/L	0.0050	10/01/24 18:29	
EPA 6020B	Boron	0.59	mg/L	0.040	10/01/24 18:29	
EPA 6020B	Cobalt	0.022	mg/L	0.0050	10/01/24 18:29	
EPA 6020B	Lead	0.00038J	mg/L	0.0010	10/01/24 18:29	
EPA 6020B	Lithium	0.049	mg/L	0.030	10/01/24 18:29	
EPA 6020B	Molybdenum	0.010	mg/L	0.010	10/01/24 18:29	
SM 2540C-2015	Total Dissolved Solids	588	mg/L	25.0	10/01/24 15:59	
SM 2320B	Alkalinity, Total as CaCO3	142	mg/L	5.0	10/07/24 10:12	
SM 2320B	Alkalinity,Bicarbonate (CaCO3)	142	mg/L	5.0	10/07/24 10:12	
92756037009	HAM-PT-15					
EPA 300.0	Chloride	14.5	mg/L	1.0	10/16/24 14:05	
EPA 300.0	Fluoride	0.31	mg/L	0.050	10/16/24 14:05	
EPA 300.0	Sulfate	242	mg/L	1.0	10/16/24 14:05	
EPA 6010D	Iron	0.15	mg/L	0.040	10/02/24 13:05	
EPA 6010D	Manganese	2.3	mg/L	0.040	10/02/24 13:05	
EPA 6010D	Potassium	5.1	mg/L	0.50	10/02/24 13:05	
EPA 6010D	Sodium	7.7	mg/L	1.0	10/02/24 13:05	
EPA 6010D	Calcium	118	mg/L	1.0	10/02/24 13:05	
EPA 6010D	Magnesium	12.3	mg/L	0.050	10/02/24 13:05	
EPA 6020B	Antimony	0.00065J	mg/L	0.0030	10/01/24 18:32	
EPA 6020B	Arsenic	0.0097	mg/L	0.0050	10/01/24 18:32	B
EPA 6020B	Barium	0.049	mg/L	0.0050	10/01/24 18:32	
EPA 6020B	Boron	0.64	mg/L	0.040	10/01/24 18:32	
EPA 6020B	Cadmium	0.00029J	mg/L	0.00050	10/01/24 18:32	
EPA 6020B	Cobalt	0.012	mg/L	0.0050	10/01/24 18:32	
EPA 6020B	Lithium	0.040	mg/L	0.030	10/01/24 18:32	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92756037009	HAM-PT-15					
EPA 6020B	Molybdenum	0.010	mg/L	0.010	10/01/24 18:32	
EPA 6020B	Selenium	0.0038J	mg/L	0.0050	10/01/24 18:32	
EPA 6020B	Thallium	0.00044J	mg/L	0.0010	10/01/24 18:32	
SM 2540C-2015	Total Dissolved Solids	473	mg/L	25.0	10/01/24 16:00	
SM 2320B	Alkalinity, Total as CaCO3	81.7	mg/L	5.0	10/07/24 10:17	
SM 2320B	Alkalinity,Bicarbonate (CaCO3)	81.7	mg/L	5.0	10/07/24 10:17	
92756037010	HAM-AP1-FD-01					
EPA 300.0	Chloride	17.5	mg/L	1.0	10/16/24 14:20	
EPA 300.0	Fluoride	0.25	mg/L	0.050	10/16/24 14:20	
EPA 300.0	Sulfate	244	mg/L	1.0	10/16/24 14:20	
EPA 6010D	Iron	1.1	mg/L	0.040	10/02/24 13:14	
EPA 6010D	Manganese	2.6	mg/L	0.040	10/02/24 13:14	
EPA 6010D	Potassium	5.3	mg/L	0.50	10/02/24 13:14	
EPA 6010D	Sodium	9.0	mg/L	1.0	10/02/24 13:14	
EPA 6010D	Calcium	120	mg/L	1.0	10/02/24 13:14	
EPA 6010D	Magnesium	14.7	mg/L	0.050	10/02/24 13:14	
EPA 6020B	Arsenic	0.021	mg/L	0.0050	10/01/24 18:40	
EPA 6020B	Barium	0.052	mg/L	0.0050	10/01/24 18:40	
EPA 6020B	Boron	0.61	mg/L	0.040	10/01/24 18:40	
EPA 6020B	Cadmium	0.00015J	mg/L	0.00050	10/01/24 18:40	
EPA 6020B	Cobalt	0.023	mg/L	0.0050	10/01/24 18:40	
EPA 6020B	Lithium	0.035	mg/L	0.030	10/01/24 18:40	
EPA 6020B	Molybdenum	0.0099J	mg/L	0.010	10/01/24 18:40	
EPA 6020B	Selenium	0.0014J	mg/L	0.0050	10/01/24 18:40	
EPA 6020B	Thallium	0.00041J	mg/L	0.0010	10/01/24 18:40	
SM 2540C-2015	Total Dissolved Solids	520	mg/L	25.0	10/01/24 16:00	
SM 2320B	Alkalinity, Total as CaCO3	91.8	mg/L	5.0	10/07/24 10:21	
SM 2320B	Alkalinity,Bicarbonate (CaCO3)	91.8	mg/L	5.0	10/07/24 10:21	
92756037011	HAM-AP1-FB-01					
EPA 6020B	Arsenic	0.0014J	mg/L	0.0050	10/01/24 18:43	B
92756037012	HAM-AP1-EB-01					
EPA 6010D	Sodium	0.62J	mg/L	1.0	10/02/24 13:24	
EPA 6010D	Calcium	0.44J	mg/L	1.0	10/02/24 13:24	
EPA 6010D	Magnesium	0.097	mg/L	0.050	10/02/24 13:24	
EPA 6020B	Arsenic	0.00093J	mg/L	0.0050	10/01/24 18:47	B
EPA 6020B	Barium	0.0021J	mg/L	0.0050	10/01/24 18:47	
SM 2320B	Alkalinity, Total as CaCO3	5.8	mg/L	5.0	10/07/24 10:29	
SM 2320B	Alkalinity,Bicarbonate (CaCO3)	5.8	mg/L	5.0	10/07/24 10:29	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Sample: HAM-PT-07		Lab ID: 92756037001		Collected: 09/24/24 16:20		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	17.5	mg/L	1.0	0.34	1		10/16/24 10:35	16887-00-6	
Fluoride	0.26	mg/L	0.050	0.0057	1		10/16/24 10:35	16984-48-8	
Sulfate	249	mg/L	1.0	0.086	1		10/16/24 10:35	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/11/24 18:04	18496-25-8	H3
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	0.54	mg/L	0.040	0.025	1	10/01/24 11:11	10/02/24 11:58	7439-89-6	
Manganese	2.4	mg/L	0.040	0.011	1	10/01/24 11:11	10/02/24 11:58	7439-96-5	
Potassium	5.9	mg/L	0.50	0.15	1	10/01/24 11:11	10/02/24 11:58	7440-09-7	
Sodium	10.2	mg/L	1.0	0.58	1	10/01/24 11:11	10/02/24 11:58	7440-23-5	
Calcium	128	mg/L	1.0	0.12	1	10/01/24 11:11	10/02/24 11:58	7440-70-2	
Magnesium	18.7	mg/L	0.050	0.012	1	10/01/24 11:11	10/02/24 11:58	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	0.00056J	mg/L	0.0030	0.00054	1	10/01/24 11:00	10/01/24 17:44	7440-36-0	
Arsenic	0.016	mg/L	0.0050	0.00084	1	10/01/24 11:00	10/01/24 17:44	7440-38-2	B
Barium	0.056	mg/L	0.0050	0.00047	1	10/01/24 11:00	10/01/24 17:44	7440-39-3	
Beryllium	0.00012J	mg/L	0.00050	0.000094	1	10/01/24 11:00	10/01/24 17:44	7440-41-7	
Boron	0.54	mg/L	0.040	0.012	1	10/01/24 11:00	10/01/24 17:44	7440-42-8	
Cadmium	0.00015J	mg/L	0.00050	0.00010	1	10/01/24 11:00	10/01/24 17:44	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/01/24 11:00	10/01/24 17:44	7440-47-3	
Cobalt	0.031	mg/L	0.0050	0.00032	1	10/01/24 11:00	10/01/24 17:44	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	10/01/24 11:00	10/01/24 17:44	7439-92-1	
Lithium	0.048	mg/L	0.030	0.0016	1	10/01/24 11:00	10/01/24 17:44	7439-93-2	
Molybdenum	0.0054J	mg/L	0.010	0.00062	1	10/01/24 11:00	10/01/24 17:44	7439-98-7	
Selenium	0.0011J	mg/L	0.0050	0.00096	1	10/01/24 11:00	10/01/24 17:44	7782-49-2	
Thallium	0.00067J	mg/L	0.0010	0.00038	1	10/01/24 11:00	10/01/24 17:44	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/01/24 16:00	10/02/24 10:28	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	559	mg/L	25.0	25.0	1		10/01/24 15:58		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO ₃	136	mg/L	5.0	1.9	1		10/07/24 09:09		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1
Pace Project No.: 92756037

Sample: HAM-PT-07		Lab ID: 92756037001		Collected: 09/24/24 16:20		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO3)	136	mg/L	5.0	1.9	1		10/07/24 09:09		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/07/24 09:09		

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Sample: HAM-PT-08		Lab ID: 92756037002		Collected: 09/24/24 14:31		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	17.1	mg/L	1.0	0.34	1		10/16/24 11:20	16887-00-6	
Fluoride	0.25	mg/L	0.050	0.0057	1		10/16/24 11:20	16984-48-8	
Sulfate	239	mg/L	1.0	0.086	1		10/16/24 11:20	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/11/24 18:04	18496-25-8	H3
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	1.1	mg/L	0.040	0.025	1	10/01/24 11:11	10/02/24 12:03	7439-89-6	
Manganese	2.5	mg/L	0.040	0.011	1	10/01/24 11:11	10/02/24 12:03	7439-96-5	
Potassium	5.3	mg/L	0.50	0.15	1	10/01/24 11:11	10/02/24 12:03	7440-09-7	
Sodium	9.1	mg/L	1.0	0.58	1	10/01/24 11:11	10/02/24 12:03	7440-23-5	
Calcium	112	mg/L	1.0	0.12	1	10/01/24 11:11	10/02/24 12:03	7440-70-2	M1
Magnesium	14.3	mg/L	0.050	0.012	1	10/01/24 11:11	10/02/24 12:03	7439-95-4	M1
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	0.0012J	mg/L	0.0030	0.00054	1	10/01/24 11:00	10/01/24 17:59	7440-36-0	
Arsenic	0.021	mg/L	0.0050	0.00084	1	10/01/24 11:00	10/01/24 17:59	7440-38-2	
Barium	0.050	mg/L	0.0050	0.00047	1	10/01/24 11:00	10/01/24 17:59	7440-39-3	
Beryllium	0.00013J	mg/L	0.00050	0.000094	1	10/01/24 11:00	10/01/24 17:59	7440-41-7	
Boron	0.61	mg/L	0.040	0.012	1	10/01/24 11:00	10/01/24 17:59	7440-42-8	
Cadmium	0.00018J	mg/L	0.00050	0.00010	1	10/01/24 11:00	10/01/24 17:59	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/01/24 11:00	10/01/24 17:59	7440-47-3	
Cobalt	0.022	mg/L	0.0050	0.00032	1	10/01/24 11:00	10/01/24 17:59	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	10/01/24 11:00	10/01/24 17:59	7439-92-1	
Lithium	0.035	mg/L	0.030	0.0016	1	10/01/24 11:00	10/01/24 17:59	7439-93-2	
Molybdenum	0.0098J	mg/L	0.010	0.00062	1	10/01/24 11:00	10/01/24 17:59	7439-98-7	
Selenium	0.0013J	mg/L	0.0050	0.00096	1	10/01/24 11:00	10/01/24 17:59	7782-49-2	
Thallium	0.00050J	mg/L	0.0010	0.00038	1	10/01/24 11:00	10/01/24 17:59	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/01/24 16:00	10/02/24 10:39	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	490	mg/L	25.0	25.0	1		10/01/24 15:58		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO ₃	91.8	mg/L	5.0	1.9	1		10/07/24 09:27		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1
Pace Project No.: 92756037

Sample: HAM-PT-08		Lab ID: 92756037002		Collected: 09/24/24 14:31		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO3)	91.8	mg/L	5.0	1.9	1		10/07/24 09:27		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/07/24 09:27		

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Sample: HAM-PT-09		Lab ID: 92756037003		Collected: 09/25/24 12:30		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	39.4	mg/L	1.0	0.34	1		10/16/24 12:05	16887-00-6	
Fluoride	0.33	mg/L	0.050	0.0057	1		10/16/24 12:05	16984-48-8	
Sulfate	236	mg/L	1.0	0.086	1		10/16/24 12:05	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/11/24 18:04	18496-25-8	H3
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	0.24	mg/L	0.040	0.025	1	10/01/24 11:11	10/02/24 12:22	7439-89-6	
Manganese	0.73	mg/L	0.040	0.011	1	10/01/24 11:11	10/02/24 12:22	7439-96-5	
Potassium	5.8	mg/L	0.50	0.15	1	10/01/24 11:11	10/02/24 12:22	7440-09-7	
Sodium	7.0	mg/L	1.0	0.58	1	10/01/24 11:11	10/02/24 12:22	7440-23-5	
Calcium	111	mg/L	1.0	0.12	1	10/01/24 11:11	10/02/24 12:22	7440-70-2	
Magnesium	27.2	mg/L	0.050	0.012	1	10/01/24 11:11	10/02/24 12:22	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.00054	1	10/01/24 11:00	10/01/24 18:03	7440-36-0	
Arsenic	0.0034J	mg/L	0.0050	0.00084	1	10/01/24 11:00	10/01/24 18:03	7440-38-2	B
Barium	0.089	mg/L	0.0050	0.00047	1	10/01/24 11:00	10/01/24 18:03	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	10/01/24 11:00	10/01/24 18:03	7440-41-7	
Boron	1.2	mg/L	0.040	0.012	1	10/01/24 11:00	10/01/24 18:03	7440-42-8	
Cadmium	0.00030J	mg/L	0.00050	0.00010	1	10/01/24 11:00	10/01/24 18:03	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/01/24 11:00	10/01/24 18:03	7440-47-3	
Cobalt	0.0066	mg/L	0.0050	0.00032	1	10/01/24 11:00	10/01/24 18:03	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	10/01/24 11:00	10/01/24 18:03	7439-92-1	
Lithium	0.0035J	mg/L	0.030	0.0016	1	10/01/24 11:00	10/01/24 18:03	7439-93-2	
Molybdenum	0.14	mg/L	0.010	0.00062	1	10/01/24 11:00	10/01/24 18:03	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	10/01/24 11:00	10/01/24 18:03	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/01/24 11:00	10/01/24 18:03	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/01/24 16:00	10/02/24 10:42	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	547	mg/L	25.0	25.0	1		10/01/24 16:01		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO ₃	112	mg/L	5.0	1.9	1		10/07/24 09:31		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1
Pace Project No.: 92756037

Sample: HAM-PT-09		Lab ID: 92756037003		Collected: 09/25/24 12:30		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO3)	112	mg/L	5.0	1.9	1		10/07/24 09:31		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/07/24 09:31		

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Sample: HAM-PT-10		Lab ID: 92756037004		Collected: 09/25/24 10:00		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	49.6	mg/L	1.0	0.34	1		10/16/24 12:20	16887-00-6	
Fluoride	0.32	mg/L	0.050	0.0057	1		10/16/24 12:20	16984-48-8	
Sulfate	158	mg/L	1.0	0.086	1		10/16/24 12:20	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/11/24 18:04	18496-25-8	H3
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	0.060	mg/L	0.040	0.025	1	10/01/24 11:11	10/02/24 12:27	7439-89-6	
Manganese	0.43	mg/L	0.040	0.011	1	10/01/24 11:11	10/02/24 12:27	7439-96-5	
Potassium	6.6	mg/L	0.50	0.15	1	10/01/24 11:11	10/02/24 12:27	7440-09-7	
Sodium	9.0	mg/L	1.0	0.58	1	10/01/24 11:11	10/02/24 12:27	7440-23-5	
Calcium	113	mg/L	1.0	0.12	1	10/01/24 11:11	10/02/24 12:27	7440-70-2	
Magnesium	14.2	mg/L	0.050	0.012	1	10/01/24 11:11	10/02/24 12:27	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.00054	1	10/01/24 11:00	10/01/24 18:07	7440-36-0	
Arsenic	0.0024J	mg/L	0.0050	0.00084	1	10/01/24 11:00	10/01/24 18:07	7440-38-2	B
Barium	0.053	mg/L	0.0050	0.00047	1	10/01/24 11:00	10/01/24 18:07	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	10/01/24 11:00	10/01/24 18:07	7440-41-7	
Boron	1.6	mg/L	0.040	0.012	1	10/01/24 11:00	10/01/24 18:07	7440-42-8	
Cadmium	0.00017J	mg/L	0.00050	0.00010	1	10/01/24 11:00	10/01/24 18:07	7440-43-9	
Chromium	0.0039J	mg/L	0.0050	0.0019	1	10/01/24 11:00	10/01/24 18:07	7440-47-3	
Cobalt	0.0019J	mg/L	0.0050	0.00032	1	10/01/24 11:00	10/01/24 18:07	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	10/01/24 11:00	10/01/24 18:07	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	10/01/24 11:00	10/01/24 18:07	7439-93-2	
Molybdenum	0.23	mg/L	0.010	0.00062	1	10/01/24 11:00	10/01/24 18:07	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	10/01/24 11:00	10/01/24 18:07	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/01/24 11:00	10/01/24 18:07	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/01/24 16:00	10/02/24 10:50	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	521	mg/L	25.0	25.0	1		10/01/24 16:01		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO3	131	mg/L	5.0	1.9	1		10/07/24 09:36		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1
Pace Project No.: 92756037

Sample: HAM-PT-10		Lab ID: 92756037004		Collected: 09/25/24 10:00		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO3)	131	mg/L	5.0	1.9	1		10/07/24 09:36		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/07/24 09:36		

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Sample: HAM-PT-11		Lab ID: 92756037005		Collected: 09/25/24 14:54		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	48.3	mg/L	1.0	0.34	1		10/16/24 13:05	16887-00-6	
Fluoride	0.33	mg/L	0.050	0.0057	1		10/16/24 13:05	16984-48-8	
Sulfate	200	mg/L	1.0	0.086	1		10/16/24 13:05	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/11/24 18:05	18496-25-8	H3
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	3.7	mg/L	0.040	0.025	1	10/01/24 11:11	10/02/24 12:32	7439-89-6	
Manganese	1.4	mg/L	0.040	0.011	1	10/01/24 11:11	10/02/24 12:32	7439-96-5	
Potassium	5.6	mg/L	0.50	0.15	1	10/01/24 11:11	10/02/24 12:32	7440-09-7	
Sodium	8.1	mg/L	1.0	0.58	1	10/01/24 11:11	10/02/24 12:32	7440-23-5	
Calcium	109	mg/L	1.0	0.12	1	10/01/24 11:11	10/02/24 12:32	7440-70-2	
Magnesium	20.3	mg/L	0.050	0.012	1	10/01/24 11:11	10/02/24 12:32	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.00054	1	10/01/24 11:00	10/01/24 18:10	7440-36-0	
Arsenic	0.0031J	mg/L	0.0050	0.00084	1	10/01/24 11:00	10/01/24 18:10	7440-38-2	B
Barium	0.078	mg/L	0.0050	0.00047	1	10/01/24 11:00	10/01/24 18:10	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	10/01/24 11:00	10/01/24 18:10	7440-41-7	
Boron	1.5	mg/L	0.040	0.012	1	10/01/24 11:00	10/01/24 18:10	7440-42-8	
Cadmium	0.00030J	mg/L	0.00050	0.00010	1	10/01/24 11:00	10/01/24 18:10	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/01/24 11:00	10/01/24 18:10	7440-47-3	
Cobalt	0.025	mg/L	0.0050	0.00032	1	10/01/24 11:00	10/01/24 18:10	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	10/01/24 11:00	10/01/24 18:10	7439-92-1	
Lithium	0.0067J	mg/L	0.030	0.0016	1	10/01/24 11:00	10/01/24 18:10	7439-93-2	
Molybdenum	0.074	mg/L	0.010	0.00062	1	10/01/24 11:00	10/01/24 18:10	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	10/01/24 11:00	10/01/24 18:10	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/01/24 11:00	10/01/24 18:10	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/01/24 16:00	10/02/24 10:52	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	546	mg/L	25.0	25.0	1		10/01/24 16:02		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO3	98.0	mg/L	5.0	1.9	1		10/07/24 09:41		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Sample: HAM-PT-11		Lab ID: 92756037005		Collected: 09/25/24 14:54		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO ₃)	98.0	mg/L	5.0	1.9	1		10/07/24 09:41		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	1.9	1		10/07/24 09:41		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Sample: HAM-PT-12		Lab ID: 92756037006		Collected: 09/25/24 16:50		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	22.9	mg/L	1.0	0.34	1		10/16/24 13:20	16887-00-6	
Fluoride	0.27	mg/L	0.050	0.0057	1		10/16/24 13:20	16984-48-8	
Sulfate	266	mg/L	1.0	0.086	1		10/16/24 13:20	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/11/24 18:05	18496-25-8	H3
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	0.21	mg/L	0.040	0.025	1	10/01/24 11:11	10/02/24 12:50	7439-89-6	
Manganese	2.6	mg/L	0.040	0.011	1	10/01/24 11:11	10/02/24 12:50	7439-96-5	
Potassium	5.1	mg/L	0.50	0.15	1	10/01/24 11:11	10/02/24 12:50	7440-09-7	
Sodium	6.1	mg/L	1.0	0.58	1	10/01/24 11:11	10/02/24 12:50	7440-23-5	
Calcium	106	mg/L	1.0	0.12	1	10/01/24 11:11	10/02/24 12:50	7440-70-2	
Magnesium	30.0	mg/L	0.050	0.012	1	10/01/24 11:11	10/02/24 12:50	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.00054	1	10/01/24 11:00	10/01/24 18:21	7440-36-0	
Arsenic	0.0031J	mg/L	0.0050	0.00084	1	10/01/24 11:00	10/01/24 18:21	7440-38-2	B
Barium	0.087	mg/L	0.0050	0.00047	1	10/01/24 11:00	10/01/24 18:21	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	10/01/24 11:00	10/01/24 18:21	7440-41-7	
Boron	0.81	mg/L	0.040	0.012	1	10/01/24 11:00	10/01/24 18:21	7440-42-8	
Cadmium	0.00055	mg/L	0.00050	0.00010	1	10/01/24 11:00	10/01/24 18:21	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/01/24 11:00	10/01/24 18:21	7440-47-3	
Cobalt	0.011	mg/L	0.0050	0.00032	1	10/01/24 11:00	10/01/24 18:21	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	10/01/24 11:00	10/01/24 18:21	7439-92-1	
Lithium	0.0044J	mg/L	0.030	0.0016	1	10/01/24 11:00	10/01/24 18:21	7439-93-2	
Molybdenum	0.088	mg/L	0.010	0.00062	1	10/01/24 11:00	10/01/24 18:21	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	10/01/24 11:00	10/01/24 18:21	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/01/24 11:00	10/01/24 18:21	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/01/24 16:00	10/02/24 10:56	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	573	mg/L	25.0	25.0	1		10/01/24 16:02		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO ₃	90.2	mg/L	5.0	1.9	1		10/07/24 10:03		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1
Pace Project No.: 92756037

Sample: HAM-PT-12		Lab ID: 92756037006		Collected: 09/25/24 16:50		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO3)	90.2	mg/L	5.0	1.9	1		10/07/24 10:03		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/07/24 10:03		

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Sample: HAM-PT-13		Lab ID: 92756037007		Collected: 09/24/24 12:25		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	16.9	mg/L	1.0	0.34	1		10/16/24 13:35	16887-00-6	
Fluoride	0.36	mg/L	0.050	0.0057	1		10/16/24 13:35	16984-48-8	
Sulfate	261	mg/L	1.0	0.086	1		10/16/24 13:35	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/11/24 18:03	18496-25-8	H3
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	5.3	mg/L	0.040	0.025	1	10/01/24 11:11	10/02/24 12:55	7439-89-6	
Manganese	3.2	mg/L	0.040	0.011	1	10/01/24 11:11	10/02/24 12:55	7439-96-5	
Potassium	5.4	mg/L	0.50	0.15	1	10/01/24 11:11	10/02/24 12:55	7440-09-7	
Sodium	9.2	mg/L	1.0	0.58	1	10/01/24 11:11	10/02/24 12:55	7440-23-5	
Calcium	122	mg/L	1.0	0.12	1	10/01/24 11:11	10/02/24 12:55	7440-70-2	
Magnesium	16.1	mg/L	0.050	0.012	1	10/01/24 11:11	10/02/24 12:55	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.00054	1	10/01/24 11:00	10/01/24 18:25	7440-36-0	
Arsenic	0.021	mg/L	0.0050	0.00084	1	10/01/24 11:00	10/01/24 18:25	7440-38-2	
Barium	0.050	mg/L	0.0050	0.00047	1	10/01/24 11:00	10/01/24 18:25	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	10/01/24 11:00	10/01/24 18:25	7440-41-7	
Boron	0.49	mg/L	0.040	0.012	1	10/01/24 11:00	10/01/24 18:25	7440-42-8	
Cadmium	0.00011J	mg/L	0.00050	0.00010	1	10/01/24 11:00	10/01/24 18:25	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/01/24 11:00	10/01/24 18:25	7440-47-3	
Cobalt	0.022	mg/L	0.0050	0.00032	1	10/01/24 11:00	10/01/24 18:25	7440-48-4	
Lead	0.00057J	mg/L	0.0010	0.00016	1	10/01/24 11:00	10/01/24 18:25	7439-92-1	
Lithium	0.052	mg/L	0.030	0.0016	1	10/01/24 11:00	10/01/24 18:25	7439-93-2	
Molybdenum	0.0031J	mg/L	0.010	0.00062	1	10/01/24 11:00	10/01/24 18:25	7439-98-7	
Selenium	0.0013J	mg/L	0.0050	0.00096	1	10/01/24 11:00	10/01/24 18:25	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/01/24 11:00	10/01/24 18:25	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/01/24 16:00	10/02/24 10:58	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	518	mg/L	25.0	25.0	1		10/01/24 15:59		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO3	105	mg/L	5.0	1.9	1		10/07/24 10:08		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1
Pace Project No.: 92756037

Sample: HAM-PT-13		Lab ID: 92756037007		Collected: 09/24/24 12:25		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO3)	105	mg/L	5.0	1.9	1		10/07/24 10:08		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/07/24 10:08		

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Sample: HAM-PT-14		Lab ID: 92756037008		Collected: 09/24/24 14:40		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	19.6	mg/L	1.0	0.34	1		10/16/24 13:50	16887-00-6	
Fluoride	0.28	mg/L	0.050	0.0057	1		10/16/24 13:50	16984-48-8	
Sulfate	259	mg/L	1.0	0.086	1		10/16/24 13:50	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/11/24 18:04	18496-25-8	H3
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	9.9	mg/L	0.040	0.025	1	10/01/24 11:11	10/02/24 13:00	7439-89-6	
Manganese	3.4	mg/L	0.040	0.011	1	10/01/24 11:11	10/02/24 13:00	7439-96-5	
Potassium	5.8	mg/L	0.50	0.15	1	10/01/24 11:11	10/02/24 13:00	7440-09-7	
Sodium	10.3	mg/L	1.0	0.58	1	10/01/24 11:11	10/02/24 13:00	7440-23-5	
Calcium	135	mg/L	1.0	0.12	1	10/01/24 11:11	10/02/24 13:00	7440-70-2	
Magnesium	19.5	mg/L	0.050	0.012	1	10/01/24 11:11	10/02/24 13:00	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.00054	1	10/01/24 11:00	10/01/24 18:29	7440-36-0	
Arsenic	0.058	mg/L	0.0050	0.00084	1	10/01/24 11:00	10/01/24 18:29	7440-38-2	
Barium	0.050	mg/L	0.0050	0.00047	1	10/01/24 11:00	10/01/24 18:29	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	10/01/24 11:00	10/01/24 18:29	7440-41-7	
Boron	0.59	mg/L	0.040	0.012	1	10/01/24 11:00	10/01/24 18:29	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	10/01/24 11:00	10/01/24 18:29	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/01/24 11:00	10/01/24 18:29	7440-47-3	
Cobalt	0.022	mg/L	0.0050	0.00032	1	10/01/24 11:00	10/01/24 18:29	7440-48-4	
Lead	0.00038J	mg/L	0.0010	0.00016	1	10/01/24 11:00	10/01/24 18:29	7439-92-1	
Lithium	0.049	mg/L	0.030	0.0016	1	10/01/24 11:00	10/01/24 18:29	7439-93-2	
Molybdenum	0.010	mg/L	0.010	0.00062	1	10/01/24 11:00	10/01/24 18:29	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	10/01/24 11:00	10/01/24 18:29	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/01/24 11:00	10/01/24 18:29	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/01/24 16:00	10/02/24 11:01	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	588	mg/L	25.0	25.0	1		10/01/24 15:59		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO3	142	mg/L	5.0	1.9	1		10/07/24 10:12		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Sample: HAM-PT-14		Lab ID: 92756037008		Collected: 09/24/24 14:40		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO ₃)	142	mg/L	5.0	1.9	1		10/07/24 10:12		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	1.9	1		10/07/24 10:12		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Sample: HAM-PT-15		Lab ID: 92756037009		Collected: 09/24/24 11:03		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	14.5	mg/L	1.0	0.34	1		10/16/24 14:05	16887-00-6	
Fluoride	0.31	mg/L	0.050	0.0057	1		10/16/24 14:05	16984-48-8	
Sulfate	242	mg/L	1.0	0.086	1		10/16/24 14:05	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/11/24 18:03	18496-25-8	H3
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	0.15	mg/L	0.040	0.025	1	10/01/24 11:11	10/02/24 13:05	7439-89-6	
Manganese	2.3	mg/L	0.040	0.011	1	10/01/24 11:11	10/02/24 13:05	7439-96-5	
Potassium	5.1	mg/L	0.50	0.15	1	10/01/24 11:11	10/02/24 13:05	7440-09-7	
Sodium	7.7	mg/L	1.0	0.58	1	10/01/24 11:11	10/02/24 13:05	7440-23-5	
Calcium	118	mg/L	1.0	0.12	1	10/01/24 11:11	10/02/24 13:05	7440-70-2	
Magnesium	12.3	mg/L	0.050	0.012	1	10/01/24 11:11	10/02/24 13:05	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	0.00065J	mg/L	0.0030	0.00054	1	10/01/24 11:00	10/01/24 18:32	7440-36-0	
Arsenic	0.0097	mg/L	0.0050	0.00084	1	10/01/24 11:00	10/01/24 18:32	7440-38-2	B
Barium	0.049	mg/L	0.0050	0.00047	1	10/01/24 11:00	10/01/24 18:32	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	10/01/24 11:00	10/01/24 18:32	7440-41-7	
Boron	0.64	mg/L	0.040	0.012	1	10/01/24 11:00	10/01/24 18:32	7440-42-8	
Cadmium	0.00029J	mg/L	0.00050	0.00010	1	10/01/24 11:00	10/01/24 18:32	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/01/24 11:00	10/01/24 18:32	7440-47-3	
Cobalt	0.012	mg/L	0.0050	0.00032	1	10/01/24 11:00	10/01/24 18:32	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	10/01/24 11:00	10/01/24 18:32	7439-92-1	
Lithium	0.040	mg/L	0.030	0.0016	1	10/01/24 11:00	10/01/24 18:32	7439-93-2	
Molybdenum	0.010	mg/L	0.010	0.00062	1	10/01/24 11:00	10/01/24 18:32	7439-98-7	
Selenium	0.0038J	mg/L	0.0050	0.00096	1	10/01/24 11:00	10/01/24 18:32	7782-49-2	
Thallium	0.00044J	mg/L	0.0010	0.00038	1	10/01/24 11:00	10/01/24 18:32	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/01/24 16:00	10/02/24 11:03	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	473	mg/L	25.0	25.0	1		10/01/24 16:00		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO3	81.7	mg/L	5.0	1.9	1		10/07/24 10:17		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Sample: HAM-PT-15		Lab ID: 92756037009		Collected: 09/24/24 11:03		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity									
Analytical Method: SM 2320B									
Pace Analytical Services - Minneapolis									
Alkalinity,Bicarbonate (CaCO3)	81.7	mg/L	5.0	1.9	1		10/07/24 10:17		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/07/24 10:17		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Sample: HAM-AP1-FD-01		Lab ID: 92756037010		Collected: 09/24/24 00:00		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	17.5	mg/L	1.0	0.34	1		10/16/24 14:20	16887-00-6	
Fluoride	0.25	mg/L	0.050	0.0057	1		10/16/24 14:20	16984-48-8	
Sulfate	244	mg/L	1.0	0.086	1		10/16/24 14:20	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/11/24 18:02	18496-25-8	H3
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	1.1	mg/L	0.040	0.025	1	10/01/24 11:11	10/02/24 13:14	7439-89-6	
Manganese	2.6	mg/L	0.040	0.011	1	10/01/24 11:11	10/02/24 13:14	7439-96-5	
Potassium	5.3	mg/L	0.50	0.15	1	10/01/24 11:11	10/02/24 13:14	7440-09-7	
Sodium	9.0	mg/L	1.0	0.58	1	10/01/24 11:11	10/02/24 13:14	7440-23-5	
Calcium	120	mg/L	1.0	0.12	1	10/01/24 11:11	10/02/24 13:14	7440-70-2	
Magnesium	14.7	mg/L	0.050	0.012	1	10/01/24 11:11	10/02/24 13:14	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.00054	1	10/01/24 11:00	10/01/24 18:40	7440-36-0	
Arsenic	0.021	mg/L	0.0050	0.00084	1	10/01/24 11:00	10/01/24 18:40	7440-38-2	
Barium	0.052	mg/L	0.0050	0.00047	1	10/01/24 11:00	10/01/24 18:40	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	10/01/24 11:00	10/01/24 18:40	7440-41-7	
Boron	0.61	mg/L	0.040	0.012	1	10/01/24 11:00	10/01/24 18:40	7440-42-8	
Cadmium	0.00015J	mg/L	0.00050	0.00010	1	10/01/24 11:00	10/01/24 18:40	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/01/24 11:00	10/01/24 18:40	7440-47-3	
Cobalt	0.023	mg/L	0.0050	0.00032	1	10/01/24 11:00	10/01/24 18:40	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	10/01/24 11:00	10/01/24 18:40	7439-92-1	
Lithium	0.035	mg/L	0.030	0.0016	1	10/01/24 11:00	10/01/24 18:40	7439-93-2	
Molybdenum	0.0099J	mg/L	0.010	0.00062	1	10/01/24 11:00	10/01/24 18:40	7439-98-7	
Selenium	0.0014J	mg/L	0.0050	0.00096	1	10/01/24 11:00	10/01/24 18:40	7782-49-2	
Thallium	0.00041J	mg/L	0.0010	0.00038	1	10/01/24 11:00	10/01/24 18:40	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/01/24 16:00	10/02/24 11:06	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	520	mg/L	25.0	25.0	1		10/01/24 16:00		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO ₃	91.8	mg/L	5.0	1.9	1		10/07/24 10:21		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1
Pace Project No.: 92756037

Sample: HAM-AP1-FD-01		Lab ID: 92756037010		Collected: 09/24/24 00:00		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO3)	91.8	mg/L	5.0	1.9	1		10/07/24 10:21		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/07/24 10:21		

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Sample: HAM-AP1-FB-01		Lab ID: 92756037011		Collected: 09/25/24 17:40		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	ND	mg/L	1.0	0.34	1		10/16/24 14:35	16887-00-6	
Fluoride	ND	mg/L	0.050	0.0057	1		10/16/24 14:35	16984-48-8	
Sulfate	ND	mg/L	1.0	0.086	1		10/16/24 14:35	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/11/24 18:05	18496-25-8	H3
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	ND	mg/L	0.040	0.025	1	10/01/24 11:11	10/02/24 13:19	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	10/01/24 11:11	10/02/24 13:19	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	10/01/24 11:11	10/02/24 13:19	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	10/01/24 11:11	10/02/24 13:19	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	10/01/24 11:11	10/02/24 13:19	7440-70-2	
Magnesium	ND	mg/L	0.050	0.012	1	10/01/24 11:11	10/02/24 13:19	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.00054	1	10/01/24 11:00	10/01/24 18:43	7440-36-0	
Arsenic	0.0014J	mg/L	0.0050	0.00084	1	10/01/24 11:00	10/01/24 18:43	7440-38-2	B
Barium	ND	mg/L	0.0050	0.00047	1	10/01/24 11:00	10/01/24 18:43	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	10/01/24 11:00	10/01/24 18:43	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	10/01/24 11:00	10/01/24 18:43	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	10/01/24 11:00	10/01/24 18:43	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/01/24 11:00	10/01/24 18:43	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	10/01/24 11:00	10/01/24 18:43	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	10/01/24 11:00	10/01/24 18:43	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	10/01/24 11:00	10/01/24 18:43	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	10/01/24 11:00	10/01/24 18:43	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	10/01/24 11:00	10/01/24 18:43	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/01/24 11:00	10/01/24 18:43	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/01/24 16:00	10/02/24 11:09	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		10/01/24 16:02		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	1.9	1		10/07/24 10:26		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1
Pace Project No.: 92756037

Sample: HAM-AP1-FB-01		Lab ID: 92756037011		Collected: 09/25/24 17:40		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/07/24 10:26		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/07/24 10:26		

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Sample: HAM-AP1-EB-01		Lab ID: 92756037012		Collected: 09/25/24 17:45		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	ND	mg/L	1.0	0.34	1		10/16/24 14:50	16887-00-6	
Fluoride	ND	mg/L	0.050	0.0057	1		10/16/24 14:50	16984-48-8	
Sulfate	ND	mg/L	1.0	0.086	1		10/16/24 14:50	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/11/24 18:05	18496-25-8	H3
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	ND	mg/L	0.040	0.025	1	10/01/24 11:11	10/02/24 13:24	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	10/01/24 11:11	10/02/24 13:24	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	10/01/24 11:11	10/02/24 13:24	7440-09-7	
Sodium	0.62J	mg/L	1.0	0.58	1	10/01/24 11:11	10/02/24 13:24	7440-23-5	
Calcium	0.44J	mg/L	1.0	0.12	1	10/01/24 11:11	10/02/24 13:24	7440-70-2	
Magnesium	0.097	mg/L	0.050	0.012	1	10/01/24 11:11	10/02/24 13:24	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.00054	1	10/01/24 11:00	10/01/24 18:47	7440-36-0	
Arsenic	0.00093J	mg/L	0.0050	0.00084	1	10/01/24 11:00	10/01/24 18:47	7440-38-2	B
Barium	0.0021J	mg/L	0.0050	0.00047	1	10/01/24 11:00	10/01/24 18:47	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	10/01/24 11:00	10/01/24 18:47	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	10/01/24 11:00	10/01/24 18:47	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	10/01/24 11:00	10/01/24 18:47	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/01/24 11:00	10/01/24 18:47	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	10/01/24 11:00	10/01/24 18:47	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	10/01/24 11:00	10/01/24 18:47	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	10/01/24 11:00	10/01/24 18:47	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	10/01/24 11:00	10/01/24 18:47	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	10/01/24 11:00	10/01/24 18:47	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/01/24 11:00	10/01/24 18:47	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/01/24 16:00	10/02/24 11:11	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		10/01/24 16:03		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO ₃	5.8	mg/L	5.0	1.9	1		10/07/24 10:29		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 1
Pace Project No.: 92756037

Sample: HAM-AP1-EB-01		Lab ID: 92756037012		Collected: 09/25/24 17:45		Received: 09/26/24 11:40		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO3)	5.8	mg/L	5.0	1.9	1		10/07/24 10:29		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/07/24 10:29		

REPORT OF LABORATORY ANALYSIS



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 1
Pace Project No.: 92756037

QC Batch:	973742	Analysis Method:	EPA 300.0
QC Batch Method:	EPA 300.0	Analysis Description:	300.0 IC Anions WW 28 Day DU
		Laboratory:	Pace Analytical Services - Duluth, MN
Associated Lab Samples:	92756037001, 92756037002, 92756037003, 92756037004, 92756037005, 92756037006, 92756037007, 92756037008, 92756037009, 92756037010, 92756037011, 92756037012		

METHOD BLANK: 5089258 Matrix: Water
Associated Lab Samples: 92756037001, 92756037002, 92756037003, 92756037004, 92756037005, 92756037006, 92756037007, 92756037008, 92756037009, 92756037010, 92756037011, 92756037012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.34	10/16/24 10:05	
Fluoride	mg/L	ND	0.050	0.0057	10/16/24 10:05	
Sulfate	mg/L	ND	1.0	0.086	10/16/24 10:05	

LABORATORY CONTROL SAMPLE: 5089259

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	100	98.8	99	90-110	
Fluoride	mg/L	5	5.2	103	90-110	
Sulfate	mg/L	100	99.1	99	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 5089260 5089261

Parameter	Units	92756037001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	17.5	100	100	119	120	102	103	90-110	1	20	
Fluoride	mg/L	0.26	5	5	5.6	5.6	107	107	90-110	0	20	
Sulfate	mg/L	249	100	100	341	342	92	93	90-110	0	20	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 5089262 5089263

Parameter	Units	92756037002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	17.1	100	100	119	119	102	102	90-110	0	20	
Fluoride	mg/L	0.25	5	5	5.6	5.6	106	107	90-110	0	20	
Sulfate	mg/L	239	100	100	331	332	92	93	90-110	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 1
Pace Project No.: 92756037

QC Batch: 973160 Analysis Method: SM 4500-S2 D-2011
QC Batch Method: SM 4500-S2 D-2011 Analysis Description: 4500S2D Sulfide LL Water DU
Laboratory: Pace Analytical Services - Duluth, MN
Associated Lab Samples: 92756037001, 92756037002, 92756037003, 92756037004, 92756037005, 92756037006, 92756037007, 92756037008, 92756037009, 92756037010, 92756037011, 92756037012

METHOD BLANK: 5086234 Matrix: Water
Associated Lab Samples: 92756037001, 92756037002, 92756037003, 92756037004, 92756037005, 92756037006, 92756037007, 92756037008, 92756037009, 92756037010, 92756037011, 92756037012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.011	10/11/24 18:01	

LABORATORY CONTROL SAMPLE: 5086235		Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Parameter	Units					
Sulfide	mg/L	0.19	0.20	106	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 5086236					5086237							
Parameter	Units	92756037010	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		Result										
Sulfide	mg/L	ND	0.2	0.2	0.21	0.21	104	107	90-110	3	10	H3

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 5086238					5086239							
Parameter	Units	10710729001	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		Result										
Sulfide	mg/L	ND	0.2	0.2	0.24	0.24	106	108	90-110	2	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

QC Batch:	886167	Analysis Method:	EPA 6010D
QC Batch Method:	EPA 3010A	Analysis Description:	6010D ATL
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92756037001, 92756037002, 92756037003, 92756037004, 92756037005, 92756037006, 92756037007, 92756037008, 92756037009, 92756037010, 92756037011, 92756037012		

METHOD BLANK:	4563116	Matrix:	Water
Associated Lab Samples:	92756037001, 92756037002, 92756037003, 92756037004, 92756037005, 92756037006, 92756037007, 92756037008, 92756037009, 92756037010, 92756037011, 92756037012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	10/02/24 11:48	
Iron	mg/L	ND	0.040	0.025	10/02/24 11:48	
Magnesium	mg/L	ND	0.050	0.012	10/02/24 11:48	
Manganese	mg/L	ND	0.040	0.011	10/02/24 11:48	
Potassium	mg/L	ND	0.50	0.15	10/02/24 11:48	
Sodium	mg/L	ND	1.0	0.58	10/02/24 11:48	

LABORATORY CONTROL SAMPLE: 4563117

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	1.0	103	80-120	
Iron	mg/L	1	1.0	102	80-120	
Magnesium	mg/L	1	1.0	104	80-120	
Manganese	mg/L	1	1.0	101	80-120	
Potassium	mg/L	1	0.99	99	80-120	
Sodium	mg/L	1	1.0	103	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4563118 4563119

Parameter	Units	92756037002	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		Result										
Calcium	mg/L	112	1	1	117	115	546	364	75-125	2	20	M1
Iron	mg/L	1.1	1	1	2.2	2.2	110	107	75-125	1	20	
Magnesium	mg/L	14.3	1	1	15.8	15.3	147	102	75-125	3	20	M1
Manganese	mg/L	2.5	1	1	3.6	3.5	109	96	75-125	4	20	
Potassium	mg/L	5.3	1	1	6.4	6.2	109	90	75-125	3	20	
Sodium	mg/L	9.1	1	1	10.3	9.9	116	84	75-125	3	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

QC Batch:	886154	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92756037001, 92756037002, 92756037003, 92756037004, 92756037005, 92756037006, 92756037007, 92756037008, 92756037009, 92756037010, 92756037011, 92756037012		

METHOD BLANK: 4563064

Matrix: Water

Associated Lab Samples: 92756037001, 92756037002, 92756037003, 92756037004, 92756037005, 92756037006, 92756037007, 92756037008, 92756037009, 92756037010, 92756037011, 92756037012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00054	10/01/24 17:37	
Arsenic	mg/L	0.0019J	0.0050	0.00084	10/01/24 17:37	
Barium	mg/L	ND	0.0050	0.00047	10/01/24 17:37	
Beryllium	mg/L	ND	0.00050	0.000094	10/01/24 17:37	
Boron	mg/L	ND	0.040	0.012	10/01/24 17:37	
Cadmium	mg/L	ND	0.00050	0.00010	10/01/24 17:37	
Chromium	mg/L	ND	0.0050	0.0019	10/01/24 17:37	
Cobalt	mg/L	ND	0.0050	0.00032	10/01/24 17:37	
Lead	mg/L	ND	0.0010	0.00016	10/01/24 17:37	
Lithium	mg/L	ND	0.030	0.0016	10/01/24 17:37	
Molybdenum	mg/L	ND	0.010	0.00062	10/01/24 17:37	
Selenium	mg/L	ND	0.0050	0.00096	10/01/24 17:37	
Thallium	mg/L	ND	0.0010	0.00038	10/01/24 17:37	

LABORATORY CONTROL SAMPLE: 4563065

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.10	100	80-120	
Arsenic	mg/L	0.1	0.096	96	80-120	
Barium	mg/L	0.1	0.10	100	80-120	
Beryllium	mg/L	0.1	0.094	94	80-120	
Boron	mg/L	1	0.93	93	80-120	
Cadmium	mg/L	0.1	0.097	97	80-120	
Chromium	mg/L	0.1	0.097	97	80-120	
Cobalt	mg/L	0.1	0.096	96	80-120	
Lead	mg/L	0.1	0.10	100	80-120	
Lithium	mg/L	0.1	0.096	96	80-120	
Molybdenum	mg/L	0.1	0.099	99	80-120	
Selenium	mg/L	0.1	0.097	97	80-120	
Thallium	mg/L	0.1	0.097	97	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4563066

4563067

Parameter	Units	92756037001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	0.00056J	0.1	0.1	0.10	0.097	102	97	75-125	5	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4563066 4563067											
Parameter	Units	92756037001	MS	MSD	MS	MSD	MS	MSD	% Rec	Limits	Max
		Result	Spike	Spike							
			Conc.	Conc.	Result	Result	% Rec	% Rec			RPD
Arsenic	mg/L	0.016	0.1	0.1	0.12	0.11	100	98	75-125	2	20
Barium	mg/L	0.056	0.1	0.1	0.16	0.16	107	101	75-125	4	20
Beryllium	mg/L	0.00012J	0.1	0.1	0.093	0.089	93	89	75-125	4	20
Boron	mg/L	0.54	1	1	1.5	1.5	98	93	75-125	4	20
Cadmium	mg/L	0.00015J	0.1	0.1	0.099	0.097	99	96	75-125	3	20
Chromium	mg/L	ND	0.1	0.1	0.098	0.093	97	93	75-125	5	20
Cobalt	mg/L	0.031	0.1	0.1	0.13	0.12	97	91	75-125	5	20
Lead	mg/L	ND	0.1	0.1	0.099	0.095	99	95	75-125	4	20
Lithium	mg/L	0.048	0.1	0.1	0.15	0.14	97	90	75-125	5	20
Molybdenum	mg/L	0.0054J	0.1	0.1	0.11	0.10	102	97	75-125	5	20
Selenium	mg/L	0.0011J	0.1	0.1	0.098	0.098	97	97	75-125	0	20
Thallium	mg/L	0.00067J	0.1	0.1	0.098	0.095	97	94	75-125	3	20

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

QC Batch:	886196	Analysis Method:	EPA 7470A
QC Batch Method:	EPA 7470A	Analysis Description:	7470 Mercury
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92756037001, 92756037002, 92756037003, 92756037004, 92756037005, 92756037006, 92756037007, 92756037008, 92756037009, 92756037010, 92756037011, 92756037012		

METHOD BLANK:	4563527	Matrix:	Water
Associated Lab Samples:	92756037001, 92756037002, 92756037003, 92756037004, 92756037005, 92756037006, 92756037007, 92756037008, 92756037009, 92756037010, 92756037011, 92756037012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	10/02/24 10:23	

LABORATORY CONTROL SAMPLE: 4563528						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0023	94	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:													
					4563529	4563530							
		92756037001	MS	MSD									
Parameter	Units	Result	Spike Conc.	Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual	
Mercury	mg/L	ND	0.0025	0.0025	0.0023	0.0022	90	90	75-125	1	20		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

QC Batch:	886204	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92756037001, 92756037002, 92756037003, 92756037004, 92756037005, 92756037006, 92756037007, 92756037008, 92756037009, 92756037010, 92756037011, 92756037012		

METHOD BLANK:	4563594	Matrix:	Water
Associated Lab Samples:	92756037001, 92756037002, 92756037003, 92756037004, 92756037005, 92756037006, 92756037007, 92756037008, 92756037009, 92756037010, 92756037011, 92756037012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	10/01/24 15:55	

LABORATORY CONTROL SAMPLE:	4563595					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	387	97	80-120	

SAMPLE DUPLICATE:	4563596					
Parameter	Units	92756037001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	559	574	3	10	

SAMPLE DUPLICATE:	4563597					
Parameter	Units	92756037011 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	ND	ND		10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 1
Pace Project No.: 92756037

QC Batch: 972071 Analysis Method: SM 2320B
QC Batch Method: SM 2320B Analysis Description: 2320B Alkalinity
Laboratory: Pace Analytical Services - Minneapolis
Associated Lab Samples: 92756037001, 92756037002, 92756037003, 92756037004, 92756037005, 92756037006, 92756037007, 92756037008, 92756037009, 92756037010, 92756037011, 92756037012

METHOD BLANK: 5080271 Matrix: Water
Associated Lab Samples: 92756037001, 92756037002, 92756037003, 92756037004, 92756037005, 92756037006, 92756037007, 92756037008, 92756037009, 92756037010, 92756037011, 92756037012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	1.9	10/07/24 08:59	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	1.9	10/07/24 08:59	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	1.9	10/07/24 08:59	

LABORATORY CONTROL SAMPLE & LCSD: 5080272			5080273							
Parameter	Units	Spike Conc.	LCS Result	LCSD Result	LCS % Rec	LCSD % Rec	% Rec Limits	RPD	Max RPD	Qualifiers
Alkalinity, Total as CaCO3	mg/L	40	43.9	43.7	110	109	90-110	0	20	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 5080274		5080275										
Parameter	Units	92756037001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	136	40	40	173	173	92	93	80-120	0	20	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 5080276		5080277										
Parameter	Units	10709658001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	72.9	40	40	113	113	102	99	80-120	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1_Week 1
Pace Project No.: 92756037

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

B Analyte was detected in the associated method blank.
H3 Sample was received or analysis requested beyond the recognized method holding time.
M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92756037001	HAM-PT-07	EPA 300.0	973742		
92756037002	HAM-PT-08	EPA 300.0	973742		
92756037003	HAM-PT-09	EPA 300.0	973742		
92756037004	HAM-PT-10	EPA 300.0	973742		
92756037005	HAM-PT-11	EPA 300.0	973742		
92756037006	HAM-PT-12	EPA 300.0	973742		
92756037007	HAM-PT-13	EPA 300.0	973742		
92756037008	HAM-PT-14	EPA 300.0	973742		
92756037009	HAM-PT-15	EPA 300.0	973742		
92756037010	HAM-AP1-FD-01	EPA 300.0	973742		
92756037011	HAM-AP1-FB-01	EPA 300.0	973742		
92756037012	HAM-AP1-EB-01	EPA 300.0	973742		
92756037001	HAM-PT-07	SM 4500-S2 D-2011	973160		
92756037002	HAM-PT-08	SM 4500-S2 D-2011	973160		
92756037003	HAM-PT-09	SM 4500-S2 D-2011	973160		
92756037004	HAM-PT-10	SM 4500-S2 D-2011	973160		
92756037005	HAM-PT-11	SM 4500-S2 D-2011	973160		
92756037006	HAM-PT-12	SM 4500-S2 D-2011	973160		
92756037007	HAM-PT-13	SM 4500-S2 D-2011	973160		
92756037008	HAM-PT-14	SM 4500-S2 D-2011	973160		
92756037009	HAM-PT-15	SM 4500-S2 D-2011	973160		
92756037010	HAM-AP1-FD-01	SM 4500-S2 D-2011	973160		
92756037011	HAM-AP1-FB-01	SM 4500-S2 D-2011	973160		
92756037012	HAM-AP1-EB-01	SM 4500-S2 D-2011	973160		
92756037001	HAM-PT-07	EPA 3010A	886167	EPA 6010D	886202
92756037002	HAM-PT-08	EPA 3010A	886167	EPA 6010D	886202
92756037003	HAM-PT-09	EPA 3010A	886167	EPA 6010D	886202
92756037004	HAM-PT-10	EPA 3010A	886167	EPA 6010D	886202
92756037005	HAM-PT-11	EPA 3010A	886167	EPA 6010D	886202
92756037006	HAM-PT-12	EPA 3010A	886167	EPA 6010D	886202
92756037007	HAM-PT-13	EPA 3010A	886167	EPA 6010D	886202
92756037008	HAM-PT-14	EPA 3010A	886167	EPA 6010D	886202
92756037009	HAM-PT-15	EPA 3010A	886167	EPA 6010D	886202
92756037010	HAM-AP1-FD-01	EPA 3010A	886167	EPA 6010D	886202
92756037011	HAM-AP1-FB-01	EPA 3010A	886167	EPA 6010D	886202
92756037012	HAM-AP1-EB-01	EPA 3010A	886167	EPA 6010D	886202
92756037001	HAM-PT-07	EPA 3005A	886154	EPA 6020B	886216
92756037002	HAM-PT-08	EPA 3005A	886154	EPA 6020B	886216
92756037003	HAM-PT-09	EPA 3005A	886154	EPA 6020B	886216
92756037004	HAM-PT-10	EPA 3005A	886154	EPA 6020B	886216
92756037005	HAM-PT-11	EPA 3005A	886154	EPA 6020B	886216
92756037006	HAM-PT-12	EPA 3005A	886154	EPA 6020B	886216
92756037007	HAM-PT-13	EPA 3005A	886154	EPA 6020B	886216
92756037008	HAM-PT-14	EPA 3005A	886154	EPA 6020B	886216
92756037009	HAM-PT-15	EPA 3005A	886154	EPA 6020B	886216
92756037010	HAM-AP1-FD-01	EPA 3005A	886154	EPA 6020B	886216
92756037011	HAM-AP1-FB-01	EPA 3005A	886154	EPA 6020B	886216

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1_Week 1

Pace Project No.: 92756037

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92756037012	HAM-AP1-EB-01	EPA 3005A	886154	EPA 6020B	886216
92756037001	HAM-PT-07	EPA 7470A	886196	EPA 7470A	886290
92756037002	HAM-PT-08	EPA 7470A	886196	EPA 7470A	886290
92756037003	HAM-PT-09	EPA 7470A	886196	EPA 7470A	886290
92756037004	HAM-PT-10	EPA 7470A	886196	EPA 7470A	886290
92756037005	HAM-PT-11	EPA 7470A	886196	EPA 7470A	886290
92756037006	HAM-PT-12	EPA 7470A	886196	EPA 7470A	886290
92756037007	HAM-PT-13	EPA 7470A	886196	EPA 7470A	886290
92756037008	HAM-PT-14	EPA 7470A	886196	EPA 7470A	886290
92756037009	HAM-PT-15	EPA 7470A	886196	EPA 7470A	886290
92756037010	HAM-AP1-FD-01	EPA 7470A	886196	EPA 7470A	886290
92756037011	HAM-AP1-FB-01	EPA 7470A	886196	EPA 7470A	886290
92756037012	HAM-AP1-EB-01	EPA 7470A	886196	EPA 7470A	886290
92756037001	HAM-PT-07	SM 2540C-2015	886204		
92756037002	HAM-PT-08	SM 2540C-2015	886204		
92756037003	HAM-PT-09	SM 2540C-2015	886204		
92756037004	HAM-PT-10	SM 2540C-2015	886204		
92756037005	HAM-PT-11	SM 2540C-2015	886204		
92756037006	HAM-PT-12	SM 2540C-2015	886204		
92756037007	HAM-PT-13	SM 2540C-2015	886204		
92756037008	HAM-PT-14	SM 2540C-2015	886204		
92756037009	HAM-PT-15	SM 2540C-2015	886204		
92756037010	HAM-AP1-FD-01	SM 2540C-2015	886204		
92756037011	HAM-AP1-FB-01	SM 2540C-2015	886204		
92756037012	HAM-AP1-EB-01	SM 2540C-2015	886204		
92756037001	HAM-PT-07	SM 2320B	972071		
92756037002	HAM-PT-08	SM 2320B	972071		
92756037003	HAM-PT-09	SM 2320B	972071		
92756037004	HAM-PT-10	SM 2320B	972071		
92756037005	HAM-PT-11	SM 2320B	972071		
92756037006	HAM-PT-12	SM 2320B	972071		
92756037007	HAM-PT-13	SM 2320B	972071		
92756037008	HAM-PT-14	SM 2320B	972071		
92756037009	HAM-PT-15	SM 2320B	972071		
92756037010	HAM-AP1-FD-01	SM 2320B	972071		
92756037011	HAM-AP1-FB-01	SM 2320B	972071		
92756037012	HAM-AP1-EB-01	SM 2320B	972071		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

WO#: 92756037

PM: BV Due Date: 10/03/24
CLIENT: 92- GP-HAM

CHAIN-OF-CUSTODY Analytical Request Document

Chain-of-Custody is a LEGAL DOCUMENT - Complete all relevant fields

Pace* Location Requested (City/State):

Pace Analytical Charlotte
9800 Kinsey Ave, Suite 130, Huntersville, NC 28078

Company Name: Georgia Power - Hammond
Street Address: 241 Ralph McGill Blvd NE
Bldg 10160
Atlanta, GA 30308

Customer Project #:

Hammond AP-1_Week 1

Project Name:

Site Collection Info/Facility ID (as applicable):

Contact/Report To: Kristen Jurinko
Phone #: 470-217-0008
E-Mail: knjurink@southernco.com
Cc E-Mail:

Invoice To: Account Payable
Invoice E-Mail: georgiapowerinvoices@southernco.com
Purchase Order # (if applicable): GPCE2474-0001

Quote #:

County / State origin of sample(s): Georgia

Regulatory Program (DWR, RCRA, etc.) as applicable: Reportable [] Yes [] No

Date Results Requested:

[] Same Day [] 1 Day [] 2 Day [] 3 Day [] Other:

Field Filtered (if applicable): [] Yes [] No

Analysis:

DW PW-20 # or VAW Permit # as applicable:

Matrix Codes (Insert in Matrix box below): Drinking Water (DW), Waste Water (WW), Product (P), Soil/Solid (SS), Oil (OL), Wipe (WP), Tissue (TS), Blood/Serum (B), Vapor (V), Surface Water (SW), Sediment (SD), Sludge (SL), Caulk (CX), Leachate (LL), Biosolid (BS), Other (OT)

Customer Sample ID

Matrix #

Comp / Grab

Date

Time

Collected or Composite End

Time

Cont.

Res. Chlorine

Results

Units

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

WT

Additional Instructions from Pace*:

Collected By:

(Printed Name)

Signature:

7-26-24 11:40

7-26-24 11:40

7-26-24 11:40

7-26-24 11:40

7-26-24 11:40

7-26-24 11:40

7-26-24 11:40

7-26-24 11:40

7-26-24 11:40

7-26-24 11:40

7-26-24 11:40

7-26-24 11:40

7-26-24 11:40

7-26-24 11:40

7-26-24 11:40

7-26-24 11:40

7-26-24 11:40

7-26-24 11:40

Specify Container Size **

Identify Container Preservative Type ***

Analyte Requested

Preservation non-compliance identified for

Lab Use Only

Proj. Mgr:

Bonnie Vang

Acct/Hldg / Client ID:

Table #:

Profile / Template:

16483

Priority / Bottle Ord. ID:

ET 3157518

Sample Comment

011

012

013

014

015

016

017

018

019

020

021

022

023

024

025

026

027

028

029

030

031

032

033

034

035

036

037

038

039

040

041

042

043

044

045

046

047

048

049

050

051

052

Customer Remarks / Special Conditions / Possible Hazards:

Thermometer (U):

Corrected Temp (°C):

On-Cor:

0 8/26/24 11:40

0 8/26/24 11:40

0 8/26/24 11:40

0 8/26/24 11:40

0 8/26/24 11:40

0 8/26/24 11:40

0 8/26/24 11:40

0 8/26/24 11:40

0 8/26/24 11:40

0 8/26/24 11:40

0 8/26/24 11:40

0 8/26/24 11:40

0 8/26/24 11:40

0 8/26/24 11:40

0 8/26/24 11:40

0 8/26/24 11:40

0 8/26/24 11:40

0 8/26/24 11:40

Yard # Number:

Delivered by: [] In Person [] Courier

[] FedEx [] UPS [] Other

Page: 2 of 2

ENV-FRM-CORC-0019_V02_10123 ©

ample via this chain of custody constitutes acknowledgment and acceptance of the Pace* Terms and Conditions found at <https://www.pacelabs.com/resource-library/resource/pace-terms-and-conditions/>

Page 48 of 50



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐

Client Name:

Project #:

WO#: 92756037

PM: BV

Due Date: 10/03/24

CLIENT: 92- GP-HAM

Courier:

☐ Commercial☐ Fed Ex☐ UPS☐ USPS☒ Client☐ Pace☐ Other:

Custody Seal Present?

☒ Yes☐ No

Seals Intact?

☒ Yes☐ No☐ N/A

Date/Initials Person Examining Contents: 4-16-24 SK

Packing Material:

☒ Bubble Wrap☐ Bubble Bags☐ None☐ Other

Biological Tissue Frozen?

☐ Yes☐ No☒ N/A

Thermometer:

☒ IR Gun ID:

730

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

1.1

Correction Factor:

Add/Subtract (°C) 0.0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

1.1

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

			Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.	
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.	
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.	
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4.	
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.	
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.	
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A		
Containers Intact?	☒ Yes ☐ No ☐ N/A	7.	
Dissolved analysis: Samples Field Filtered?	☐ Yes ☐ No ☒ N/A	8.	
Sample Labels Match COC?	☒ Yes ☐ No ☐ N/A	9.	
-Includes Date/Time/ID/Analysis Matrix: 2			
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10.	
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.	
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A		

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐

Client _____ Profile/EZ (Circle one) _____ Notes _____

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic 2N Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	W6FU-Wide-mouthed Glass jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG9A-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit)-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)	BP3R-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	VSGU-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)	
CC																												
1		✓	✓																									
2		✓	✓																									
3		✓	✓																									
4		✓	✓																									
5		✓	✓																									
6		✓	✓																									
7		✓	✓																									
8		✓	✓																									
9		✓	✓																									
10		✓	✓																									
11		✓	✓																									
12		✓	✓																									

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. out of hold, incorrect preservative, out of temp, incorrect containers).



October 14, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1_Week 2
Pace Project No.: 92756894

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on October 03, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Peachtree Corners, GA

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Jamie Newsome, Geosyntec Consultants
Zain Webb, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92756894001	HAM-PT-07	Water	10/01/24 14:31	10/03/24 15:25
92756894002	HAM-PT-08	Water	10/01/24 14:40	10/03/24 15:25
92756894003	HAM-PT-09	Water	10/02/24 12:21	10/03/24 15:25
92756894004	HAM-PT-10	Water	10/02/24 12:10	10/03/24 15:25
92756894005	HAM-PT-11	Water	10/02/24 10:06	10/03/24 15:25
92756894006	HAM-PT-12	Water	10/02/24 10:30	10/03/24 15:25
92756894007	HAM-PT-13	Water	10/01/24 12:15	10/03/24 15:25
92756894008	HAM-PT-14	Water	10/01/24 11:20	10/03/24 15:25
92756894009	HAM-PT-15	Water	10/01/24 17:25	10/03/24 15:25
92756894010	HAM-AP1-EB-01	Water	10/02/24 13:45	10/03/24 15:25
92756894011	HAM-AP1-FB-01	Water	10/02/24 13:40	10/03/24 15:25
92756894012	HAM-AP1-FD-01	Water	10/02/24 00:00	10/03/24 15:25

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92756894001	HAM-PT-07	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92756894002	HAM-PT-08	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92756894003	HAM-PT-09	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92756894004	HAM-PT-10	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92756894005	HAM-PT-11	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92756894006	HAM-PT-12	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92756894007	HAM-PT-13	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92756894008	HAM-PT-14	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92756894009	HAM-PT-15	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92756894010	HAM-AP1-EB-01	EPA 6010D	AJM	1
		EPA 6020B	CW1	3
92756894011	HAM-AP1-FB-01	EPA 6010D	AJM	1
		EPA 6020B	CW1	3
92756894012	HAM-AP1-FD-01	EPA 6010D	AJM	1
		EPA 6020B	CW1	3

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1_Week 2
Pace Project No.: 92756894

Lab Sample ID Method	Client Sample ID Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92756894001	HAM-PT-07					
EPA 6010D	Iron	0.23	mg/L	0.050	10/07/24 17:40	
EPA 6020B	Arsenic	0.0062	mg/L	0.0050	10/11/24 13:29	
EPA 6020B	Boron	0.61	mg/L	0.040	10/09/24 17:54	
92756894002	HAM-PT-08					
EPA 6010D	Iron	3.7	mg/L	0.050	10/07/24 17:44	
EPA 6020B	Arsenic	0.085	mg/L	0.0050	10/09/24 18:08	
EPA 6020B	Boron	0.56	mg/L	0.040	10/09/24 18:08	
92756894003	HAM-PT-09					
EPA 6010D	Iron	0.12	mg/L	0.050	10/07/24 18:04	
EPA 6020B	Boron	1.4	mg/L	0.040	10/09/24 18:12	
EPA 6020B	Molybdenum	0.14	mg/L	0.010	10/09/24 18:12	
92756894004	HAM-PT-10					
EPA 6010D	Iron	0.17	mg/L	0.050	10/07/24 18:09	
EPA 6020B	Boron	1.7	mg/L	0.040	10/09/24 18:16	
EPA 6020B	Molybdenum	0.16	mg/L	0.010	10/09/24 18:16	
92756894005	HAM-PT-11					
EPA 6010D	Iron	1.8	mg/L	0.050	10/07/24 18:23	
EPA 6020B	Boron	1.3	mg/L	0.040	10/09/24 18:19	
EPA 6020B	Molybdenum	0.069	mg/L	0.010	10/09/24 18:19	
92756894006	HAM-PT-12					
EPA 6010D	Iron	0.043J	mg/L	0.050	10/07/24 18:28	
EPA 6020B	Boron	1.3	mg/L	0.040	10/09/24 18:30	
EPA 6020B	Molybdenum	0.14	mg/L	0.010	10/09/24 18:30	
92756894007	HAM-PT-13					
EPA 6010D	Iron	1.3	mg/L	0.050	10/07/24 18:33	
EPA 6020B	Arsenic	0.0026J	mg/L	0.0050	10/11/24 13:33	
EPA 6020B	Boron	0.56	mg/L	0.040	10/09/24 18:34	
92756894008	HAM-PT-14					
EPA 6010D	Iron	6.7	mg/L	0.050	10/07/24 18:38	
EPA 6020B	Arsenic	0.040	mg/L	0.0050	10/11/24 13:37	
EPA 6020B	Boron	0.56	mg/L	0.040	10/09/24 18:38	
92756894009	HAM-PT-15					
EPA 6010D	Iron	0.12	mg/L	0.050	10/07/24 18:43	
EPA 6020B	Arsenic	0.0034J	mg/L	0.0050	10/11/24 13:41	
EPA 6020B	Boron	0.63	mg/L	0.040	10/09/24 18:41	
92756894010	HAM-AP1-EB-01					
EPA 6020B	Arsenic	0.0021J	mg/L	0.0050	10/09/24 18:49	B
92756894011	HAM-AP1-FB-01					
EPA 6020B	Arsenic	0.0020J	mg/L	0.0050	10/09/24 18:52	B

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Lab Sample ID Method	Client Sample ID Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92756894012	HAM-AP1-FD-01					
EPA 6010D	Iron	0.10	mg/L	0.050	10/07/24 19:02	
EPA 6020B	Arsenic	0.0036J	mg/L	0.0050	10/09/24 18:56	B
EPA 6020B	Boron	1.3	mg/L	0.040	10/09/24 18:56	
EPA 6020B	Molybdenum	0.15	mg/L	0.010	10/09/24 18:56	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-PT-07		Lab ID: 92756894001		Collected: 10/01/24 14:31		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.23	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 17:40	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.0062	mg/L	0.0050	0.00084	1	10/05/24 13:24	10/11/24 13:29	7440-38-2	
Boron	0.61	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 17:54	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-PT-08		Lab ID: 92756894002		Collected: 10/01/24 14:40		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	3.7	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 17:44	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.085	mg/L	0.0050	0.00084	1	10/05/24 13:24	10/09/24 18:08	7440-38-2	
Boron	0.56	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:08	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-PT-09		Lab ID: 92756894003		Collected: 10/02/24 12:21		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.12	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 18:04	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.4	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:12	7440-42-8	
Molybdenum	0.14	mg/L	0.010	0.00062	1	10/05/24 13:24	10/09/24 18:12	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-PT-10		Lab ID: 92756894004		Collected: 10/02/24 12:10		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.17	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 18:09	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.7	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:16	7440-42-8	
Molybdenum	0.16	mg/L	0.010	0.00062	1	10/05/24 13:24	10/09/24 18:16	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-PT-11		Lab ID: 92756894005		Collected: 10/02/24 10:06		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	1.8	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 18:23	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.3	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:19	7440-42-8	
Molybdenum	0.069	mg/L	0.010	0.00062	1	10/05/24 13:24	10/09/24 18:19	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-PT-12		Lab ID: 92756894006		Collected: 10/02/24 10:30		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.043J	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 18:28	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.3	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:30	7440-42-8	
Molybdenum	0.14	mg/L	0.010	0.00062	1	10/05/24 13:24	10/09/24 18:30	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-PT-13		Lab ID: 92756894007		Collected: 10/01/24 12:15		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	1.3	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 18:33	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.0026J	mg/L	0.0050	0.00084	1	10/05/24 13:24	10/11/24 13:33	7440-38-2	
Boron	0.56	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:34	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-PT-14		Lab ID: 92756894008		Collected: 10/01/24 11:20		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	6.7	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 18:38	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.040	mg/L	0.0050	0.00084	1	10/05/24 13:24	10/11/24 13:37	7440-38-2	
Boron	0.56	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:38	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-PT-15		Lab ID: 92756894009		Collected: 10/01/24 17:25		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.12	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 18:43	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.0034J	mg/L	0.0050	0.00084	1	10/05/24 13:24	10/11/24 13:41	7440-38-2	
Boron	0.63	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:41	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-AP1-EB-01		Lab ID: 92756894010		Collected: 10/02/24 13:45		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 18:53	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.0021J	mg/L	0.0050	0.00084	1	10/05/24 13:24	10/09/24 18:49	7440-38-2	B
Boron	ND	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:49	7440-42-8	
Molybdenum	ND	mg/L	0.010	0.00062	1	10/05/24 13:24	10/09/24 18:49	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-AP1-FB-01		Lab ID: 92756894011		Collected: 10/02/24 13:40		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 18:57	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.0020J	mg/L	0.0050	0.00084	1	10/05/24 13:24	10/09/24 18:52	7440-38-2	B
Boron	ND	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:52	7440-42-8	
Molybdenum	ND	mg/L	0.010	0.00062	1	10/05/24 13:24	10/09/24 18:52	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-AP1-FD-01		Lab ID: 92756894012		Collected: 10/02/24 00:00		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.10	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 19:02	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.0036J	mg/L	0.0050	0.00084	1	10/05/24 13:24	10/09/24 18:56	7440-38-2	B
Boron	1.3	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:56	7440-42-8	
Molybdenum	0.15	mg/L	0.010	0.00062	1	10/05/24 13:24	10/09/24 18:56	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

QC Batch:	886934	Analysis Method:	EPA 6010D
QC Batch Method:	EPA 3010A	Analysis Description:	6010D ATL
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92756894001, 92756894002, 92756894003, 92756894004, 92756894005, 92756894006, 92756894007, 92756894008, 92756894009, 92756894010, 92756894011, 92756894012		

METHOD BLANK:	4568098	Matrix:	Water
Associated Lab Samples:	92756894001, 92756894002, 92756894003, 92756894004, 92756894005, 92756894006, 92756894007, 92756894008, 92756894009, 92756894010, 92756894011, 92756894012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Iron	mg/L	ND	0.050	0.025	10/07/24 17:30	

LABORATORY CONTROL SAMPLE: 4568099						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Iron	mg/L	1	0.92	92	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:												
4568100					4568101							
		92756894002	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Parameter	Units	Result										
Iron	mg/L	3.7	1	1	4.8	4.7	108	97	75-125	2	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 2
Pace Project No.: 92756894

QC Batch:	886933	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92756894001, 92756894002, 92756894003, 92756894004, 92756894005, 92756894006, 92756894007, 92756894008, 92756894009, 92756894010, 92756894011, 92756894012		

METHOD BLANK:	4568094	Matrix:	Water
Associated Lab Samples:	92756894001, 92756894002, 92756894003, 92756894004, 92756894005, 92756894006, 92756894007, 92756894008, 92756894009, 92756894010, 92756894011, 92756894012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Arsenic	mg/L	ND	0.0050	0.00084	10/11/24 13:25	
Boron	mg/L	ND	0.040	0.012	10/09/24 17:46	
Molybdenum	mg/L	ND	0.010	0.00062	10/09/24 17:46	

LABORATORY CONTROL SAMPLE:	4568095					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Arsenic	mg/L	0.1	0.099	99	80-120	
Boron	mg/L	1	1.0	103	80-120	
Molybdenum	mg/L	0.1	0.098	98	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:	4568096			4568097								
Parameter	Units	92756894001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Arsenic	mg/L	0.0062	0.1	0.1	0.11	0.11	102	103	75-125	1	20	
Boron	mg/L	0.61	1	1	1.6	1.7	102	106	75-125	2	20	
Molybdenum	mg/L	5.2J ug/L	0.1	0.1	0.098	0.098	92	93	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1_Week 2
Pace Project No.: 92756894

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

B Analyte was detected in the associated method blank.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92756894001	HAM-PT-07	EPA 3010A	886934	EPA 6010D	886973
92756894002	HAM-PT-08	EPA 3010A	886934	EPA 6010D	886973
92756894003	HAM-PT-09	EPA 3010A	886934	EPA 6010D	886973
92756894004	HAM-PT-10	EPA 3010A	886934	EPA 6010D	886973
92756894005	HAM-PT-11	EPA 3010A	886934	EPA 6010D	886973
92756894006	HAM-PT-12	EPA 3010A	886934	EPA 6010D	886973
92756894007	HAM-PT-13	EPA 3010A	886934	EPA 6010D	886973
92756894008	HAM-PT-14	EPA 3010A	886934	EPA 6010D	886973
92756894009	HAM-PT-15	EPA 3010A	886934	EPA 6010D	886973
92756894010	HAM-AP1-EB-01	EPA 3010A	886934	EPA 6010D	886973
92756894011	HAM-AP1-FB-01	EPA 3010A	886934	EPA 6010D	886973
92756894012	HAM-AP1-FD-01	EPA 3010A	886934	EPA 6010D	886973
92756894001	HAM-PT-07	EPA 3005A	886933	EPA 6020B	886977
92756894002	HAM-PT-08	EPA 3005A	886933	EPA 6020B	886977
92756894003	HAM-PT-09	EPA 3005A	886933	EPA 6020B	886977
92756894004	HAM-PT-10	EPA 3005A	886933	EPA 6020B	886977
92756894005	HAM-PT-11	EPA 3005A	886933	EPA 6020B	886977
92756894006	HAM-PT-12	EPA 3005A	886933	EPA 6020B	886977
92756894007	HAM-PT-13	EPA 3005A	886933	EPA 6020B	886977
92756894008	HAM-PT-14	EPA 3005A	886933	EPA 6020B	886977
92756894009	HAM-PT-15	EPA 3005A	886933	EPA 6020B	886977
92756894010	HAM-AP1-EB-01	EPA 3005A	886933	EPA 6020B	886977
92756894011	HAM-AP1-FB-01	EPA 3005A	886933	EPA 6020B	886977
92756894012	HAM-AP1-FD-01	EPA 3005A	886933	EPA 6020B	886977

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

WO#: 92756894

The Chain of Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

www.guestbooks.com

[illegible]

92756894

Section A Required Client Information:		Section B Required Project Information:		Section C Invoice Information:	
Company:	GA Power	Report To:	SCS Contacts	Attention:	Southern Co.
Address:	Atlanta, GA	Copy To:	Geosyntec Contacts	Company Name:	
Email To:	SCS Contacts	Purchase Order No.:	GPC82474-0001	Address:	
Phone:		Project Name:	Hammond AP-1_Week 2	Pick Quote Reference:	
Fax:		Project Number:		Pick Project Manager:	Bonnie Vang
Requested Due Date/TAT:		10 Day		Place Profile #: 16483	

Section D Required Client Information		Valid Matrix Codes		COLLECTED		# OF CONTAINERS		Preservatives		Analysis Test		Requested Analysis Filtered (Y/N)		Pace Project No. / Lab I.D.				
ITEM #	MATRIX CODE	SAMPLE TYPE (G=GRAB Q=COMP)	DATE	TIME	DATE	TIME	UNPRESERVED	Other					Y/N	Total 601/6022 B As, Mo, Fe	Total 601/6022 B As, Mo, Fe	Total 601/6022 B As, Mo, Fe	Residual Chlorine (Y/N)	Pace Project No. / Lab I.D.
1	HAM-PT-07	WG G	10/12/2024	1431														
2	HAM-PT-08	WG G	10/12/2024	1440														
3	HAM-PT-09	WG G	10/22/2024	1221														
4	HAM-PT-10	WG G	10/22/2024	1210														
5	HAM-PT-11	WG G	10/22/2024	1006														
6	HAM-PT-12	WG G	10/22/2024	1030														
7	HAM-PT-13	WG G	10/12/2024	1215														
8	HAM-PT-14	WG G	10/12/2024	1120														
9	HAM-PT-15	WG G	10/12/2024	1725														
10	HAM-API-EB-01	WG G	10/22/2024	1345														
11	HAM-API-FB-01	WG G	10/22/2024	1340														
12	HAM-API-FD-01	WG G	10/22/2024	2000														

Section E Additional Comments		RELINQUISHED BY / AFFILIATION		DATE		TIME		ACCEPTED BY / AFFILIATION		DATE		TIME		SAMPLE CONDITIONS	
		Zain Webb / Geosyntec		10-3-24		1050		Ryan Williams / Pace		10/3/2024		1050			
		Ryan Williams / Pace		10/3/2024		1525		N/A		10/3/2024		1525			

Section F SAMPLER NAME AND SIGNATURE	
PRINT Name of SAMPLER: Zain Webb, Elisabeth Russell / Geosyntec Consultants, Inc.	
SIGNATURE of SAMPLER: Zain Webb / Elisabeth Russell / Geosyntec Consultants, Inc. DATE Signed: 10/3/24	

Important Note: By signing this form you are accepting Pace's NET 30 day payment terms and agreeing to late charges of 1.5% per month for any invoices not paid within 30 days.

F-ALL-Q-020rev 07. 15-Feb-2007



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

Gut Power

Project #:

WO#: 92756894

Courier:

☐ Commercial☐ Fed Ex☒ Pace☐ UPS☐ USPS☐ Other:☐ Client

PM: BV

Due Date: 10/18/24

CLIENT: 92- GP-HAM

Custody Seal Present?

☐ Yes☐ No

Seals Intact?

☐ Yes☐ No☒ N/ADate/Initials Person Examining Contents: Man

Packing Material:

☒ Bubble Wrap☐ Bubble Bags☐ None☐ Other

Biological Tissue Frozen?

☐ Yes☐ No☒ N/A

Thermometer:

☐ IR Gun ID:

214

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

5.3

Correction Factor:

Add/Subtract (°C)

0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

5.3

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

			Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.	
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.	
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.	
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4.	
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.	
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.	
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A		
Containers Intact?	☒ Yes ☐ No ☐ N/A	7.	
Dissolved analysis: Samples Field Filtered?	☐ Yes ☐ No ☒ N/A	8.	
Sample Labels Match COC?	☒ Yes ☐ No ☐ N/A	9.	
-Includes Date/Time/ID/Analysis Matrix: <u>W6</u>			
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10.	
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.	
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A		

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_ Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

WO#: 92756894

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

PM: BV

Due Date: 10/18/24

CLIENT: 92- GP-HAM

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐Client GA Power Profile/EZ (Circle one) 16483 Notes

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4S-125 mL Plastic ZN Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGU-Wide-mouthed Glass jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG94-40 mL Amber NH4Cl (N/A) (Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2SO3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KPTU-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit) VPH/Gas kit (N/A)	SPST-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)	BP2R-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	VSGU-20 mL Schillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)
CC																											
1																											
2																											
3																											
4																											
5																											
6																											
7																											
8																											
9																											
10																											
11																											
12																											

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers.



October 14, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1_Week 2
Pace Project No.: 92756894

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on October 03, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Peachtree Corners, GA

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Jamie Newsome, Geosyntec Consultants
Zain Webb, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92756894001	HAM-PT-07	Water	10/01/24 14:31	10/03/24 15:25
92756894002	HAM-PT-08	Water	10/01/24 14:40	10/03/24 15:25
92756894003	HAM-PT-09	Water	10/02/24 12:21	10/03/24 15:25
92756894004	HAM-PT-10	Water	10/02/24 12:10	10/03/24 15:25
92756894005	HAM-PT-11	Water	10/02/24 10:06	10/03/24 15:25
92756894006	HAM-PT-12	Water	10/02/24 10:30	10/03/24 15:25
92756894007	HAM-PT-13	Water	10/01/24 12:15	10/03/24 15:25
92756894008	HAM-PT-14	Water	10/01/24 11:20	10/03/24 15:25
92756894009	HAM-PT-15	Water	10/01/24 17:25	10/03/24 15:25
92756894010	HAM-AP1-EB-01	Water	10/02/24 13:45	10/03/24 15:25
92756894011	HAM-AP1-FB-01	Water	10/02/24 13:40	10/03/24 15:25
92756894012	HAM-AP1-FD-01	Water	10/02/24 00:00	10/03/24 15:25

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92756894001	HAM-PT-07	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92756894002	HAM-PT-08	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92756894003	HAM-PT-09	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92756894004	HAM-PT-10	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92756894005	HAM-PT-11	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92756894006	HAM-PT-12	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92756894007	HAM-PT-13	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92756894008	HAM-PT-14	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92756894009	HAM-PT-15	EPA 6010D	AJM	1
		EPA 6020B	CW1	2
92756894010	HAM-AP1-EB-01	EPA 6010D	AJM	1
		EPA 6020B	CW1	3
92756894011	HAM-AP1-FB-01	EPA 6010D	AJM	1
		EPA 6020B	CW1	3
92756894012	HAM-AP1-FD-01	EPA 6010D	AJM	1
		EPA 6020B	CW1	3

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1_Week 2
Pace Project No.: 92756894

Lab Sample ID Method	Client Sample ID Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92756894001	HAM-PT-07					
EPA 6010D	Iron	0.23	mg/L	0.050	10/07/24 17:40	
EPA 6020B	Arsenic	0.0062	mg/L	0.0050	10/11/24 13:29	
EPA 6020B	Boron	0.61	mg/L	0.040	10/09/24 17:54	
92756894002	HAM-PT-08					
EPA 6010D	Iron	3.7	mg/L	0.050	10/07/24 17:44	
EPA 6020B	Arsenic	0.085	mg/L	0.0050	10/09/24 18:08	
EPA 6020B	Boron	0.56	mg/L	0.040	10/09/24 18:08	
92756894003	HAM-PT-09					
EPA 6010D	Iron	0.12	mg/L	0.050	10/07/24 18:04	
EPA 6020B	Boron	1.4	mg/L	0.040	10/09/24 18:12	
EPA 6020B	Molybdenum	0.14	mg/L	0.010	10/09/24 18:12	
92756894004	HAM-PT-10					
EPA 6010D	Iron	0.17	mg/L	0.050	10/07/24 18:09	
EPA 6020B	Boron	1.7	mg/L	0.040	10/09/24 18:16	
EPA 6020B	Molybdenum	0.16	mg/L	0.010	10/09/24 18:16	
92756894005	HAM-PT-11					
EPA 6010D	Iron	1.8	mg/L	0.050	10/07/24 18:23	
EPA 6020B	Boron	1.3	mg/L	0.040	10/09/24 18:19	
EPA 6020B	Molybdenum	0.069	mg/L	0.010	10/09/24 18:19	
92756894006	HAM-PT-12					
EPA 6010D	Iron	0.043J	mg/L	0.050	10/07/24 18:28	
EPA 6020B	Boron	1.3	mg/L	0.040	10/09/24 18:30	
EPA 6020B	Molybdenum	0.14	mg/L	0.010	10/09/24 18:30	
92756894007	HAM-PT-13					
EPA 6010D	Iron	1.3	mg/L	0.050	10/07/24 18:33	
EPA 6020B	Arsenic	0.0026J	mg/L	0.0050	10/11/24 13:33	
EPA 6020B	Boron	0.56	mg/L	0.040	10/09/24 18:34	
92756894008	HAM-PT-14					
EPA 6010D	Iron	6.7	mg/L	0.050	10/07/24 18:38	
EPA 6020B	Arsenic	0.040	mg/L	0.0050	10/11/24 13:37	
EPA 6020B	Boron	0.56	mg/L	0.040	10/09/24 18:38	
92756894009	HAM-PT-15					
EPA 6010D	Iron	0.12	mg/L	0.050	10/07/24 18:43	
EPA 6020B	Arsenic	0.0034J	mg/L	0.0050	10/11/24 13:41	
EPA 6020B	Boron	0.63	mg/L	0.040	10/09/24 18:41	
92756894010	HAM-AP1-EB-01					
EPA 6020B	Arsenic	0.0021J	mg/L	0.0050	10/09/24 18:49	B
92756894011	HAM-AP1-FB-01					
EPA 6020B	Arsenic	0.0020J	mg/L	0.0050	10/09/24 18:52	B

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Lab Sample ID Method	Client Sample ID Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92756894012	HAM-AP1-FD-01					
EPA 6010D	Iron	0.10	mg/L	0.050	10/07/24 19:02	
EPA 6020B	Arsenic	0.0036J	mg/L	0.0050	10/09/24 18:56	B
EPA 6020B	Boron	1.3	mg/L	0.040	10/09/24 18:56	
EPA 6020B	Molybdenum	0.15	mg/L	0.010	10/09/24 18:56	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-PT-07		Lab ID: 92756894001		Collected: 10/01/24 14:31		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.23	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 17:40	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.0062	mg/L	0.0050	0.00084	1	10/05/24 13:24	10/11/24 13:29	7440-38-2	
Boron	0.61	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 17:54	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-PT-08		Lab ID: 92756894002		Collected: 10/01/24 14:40		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	3.7	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 17:44	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.085	mg/L	0.0050	0.00084	1	10/05/24 13:24	10/09/24 18:08	7440-38-2	
Boron	0.56	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:08	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-PT-09		Lab ID: 92756894003		Collected: 10/02/24 12:21		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.12	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 18:04	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.4	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:12	7440-42-8	
Molybdenum	0.14	mg/L	0.010	0.00062	1	10/05/24 13:24	10/09/24 18:12	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-PT-10		Lab ID: 92756894004		Collected: 10/02/24 12:10		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.17	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 18:09	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.7	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:16	7440-42-8	
Molybdenum	0.16	mg/L	0.010	0.00062	1	10/05/24 13:24	10/09/24 18:16	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-PT-11		Lab ID: 92756894005		Collected: 10/02/24 10:06		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	1.8	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 18:23	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.3	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:19	7440-42-8	
Molybdenum	0.069	mg/L	0.010	0.00062	1	10/05/24 13:24	10/09/24 18:19	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-PT-12		Lab ID: 92756894006		Collected: 10/02/24 10:30		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.043J	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 18:28	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.3	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:30	7440-42-8	
Molybdenum	0.14	mg/L	0.010	0.00062	1	10/05/24 13:24	10/09/24 18:30	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-PT-13		Lab ID: 92756894007		Collected: 10/01/24 12:15		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	1.3	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 18:33	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.0026J	mg/L	0.0050	0.00084	1	10/05/24 13:24	10/11/24 13:33	7440-38-2	
Boron	0.56	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:34	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-PT-14		Lab ID: 92756894008		Collected: 10/01/24 11:20		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	6.7	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 18:38	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.040	mg/L	0.0050	0.00084	1	10/05/24 13:24	10/11/24 13:37	7440-38-2	
Boron	0.56	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:38	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-PT-15		Lab ID: 92756894009		Collected: 10/01/24 17:25		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.12	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 18:43	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.0034J	mg/L	0.0050	0.00084	1	10/05/24 13:24	10/11/24 13:41	7440-38-2	
Boron	0.63	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:41	7440-42-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-AP1-EB-01		Lab ID: 92756894010		Collected: 10/02/24 13:45		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 18:53	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.0021J	mg/L	0.0050	0.00084	1	10/05/24 13:24	10/09/24 18:49	7440-38-2	B
Boron	ND	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:49	7440-42-8	
Molybdenum	ND	mg/L	0.010	0.00062	1	10/05/24 13:24	10/09/24 18:49	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-AP1-FB-01		Lab ID: 92756894011		Collected: 10/02/24 13:40		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 18:57	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.0020J	mg/L	0.0050	0.00084	1	10/05/24 13:24	10/09/24 18:52	7440-38-2	B
Boron	ND	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:52	7440-42-8	
Molybdenum	ND	mg/L	0.010	0.00062	1	10/05/24 13:24	10/09/24 18:52	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Sample: HAM-AP1-FD-01		Lab ID: 92756894012		Collected: 10/02/24 00:00		Received: 10/03/24 15:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.10	mg/L	0.050	0.025	1	10/05/24 13:24	10/07/24 19:02	7439-89-6	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.0036J	mg/L	0.0050	0.00084	1	10/05/24 13:24	10/09/24 18:56	7440-38-2	B
Boron	1.3	mg/L	0.040	0.012	1	10/05/24 13:24	10/09/24 18:56	7440-42-8	
Molybdenum	0.15	mg/L	0.010	0.00062	1	10/05/24 13:24	10/09/24 18:56	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

QC Batch:	886934	Analysis Method:	EPA 6010D
QC Batch Method:	EPA 3010A	Analysis Description:	6010D ATL
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92756894001, 92756894002, 92756894003, 92756894004, 92756894005, 92756894006, 92756894007, 92756894008, 92756894009, 92756894010, 92756894011, 92756894012		

METHOD BLANK:	4568098	Matrix:	Water
Associated Lab Samples:	92756894001, 92756894002, 92756894003, 92756894004, 92756894005, 92756894006, 92756894007, 92756894008, 92756894009, 92756894010, 92756894011, 92756894012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Iron	mg/L	ND	0.050	0.025	10/07/24 17:30	

LABORATORY CONTROL SAMPLE: 4568099						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Iron	mg/L	1	0.92	92	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:												
4568100					4568101							
		92756894002	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Parameter	Units	Result										
Iron	mg/L	3.7	1	1	4.8	4.7	108	97	75-125	2	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

QC Batch:	886933	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92756894001, 92756894002, 92756894003, 92756894004, 92756894005, 92756894006, 92756894007, 92756894008, 92756894009, 92756894010, 92756894011, 92756894012		

METHOD BLANK:	4568094	Matrix:	Water
Associated Lab Samples:	92756894001, 92756894002, 92756894003, 92756894004, 92756894005, 92756894006, 92756894007, 92756894008, 92756894009, 92756894010, 92756894011, 92756894012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Arsenic	mg/L	ND	0.0050	0.00084	10/11/24 13:25	
Boron	mg/L	ND	0.040	0.012	10/09/24 17:46	
Molybdenum	mg/L	ND	0.010	0.00062	10/09/24 17:46	

LABORATORY CONTROL SAMPLE:	4568095					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Arsenic	mg/L	0.1	0.099	99	80-120	
Boron	mg/L	1	1.0	103	80-120	
Molybdenum	mg/L	0.1	0.098	98	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:			4568096		4568097							
Parameter	Units	92756894001	MS	MSD	MS	MSD	MS	MSD	% Rec	RPD	Max	Qual
		Result	Spike Conc.	Spike Conc.								
Arsenic	mg/L	0.0062	0.1	0.1	0.11	0.11	102	103	75-125	1	20	
Boron	mg/L	0.61	1	1	1.6	1.7	102	106	75-125	2	20	
Molybdenum	mg/L	5.2J ug/L	0.1	0.1	0.098	0.098	92	93	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1_Week 2
Pace Project No.: 92756894

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

B Analyte was detected in the associated method blank.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1_Week 2

Pace Project No.: 92756894

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92756894001	HAM-PT-07	EPA 3010A	886934	EPA 6010D	886973
92756894002	HAM-PT-08	EPA 3010A	886934	EPA 6010D	886973
92756894003	HAM-PT-09	EPA 3010A	886934	EPA 6010D	886973
92756894004	HAM-PT-10	EPA 3010A	886934	EPA 6010D	886973
92756894005	HAM-PT-11	EPA 3010A	886934	EPA 6010D	886973
92756894006	HAM-PT-12	EPA 3010A	886934	EPA 6010D	886973
92756894007	HAM-PT-13	EPA 3010A	886934	EPA 6010D	886973
92756894008	HAM-PT-14	EPA 3010A	886934	EPA 6010D	886973
92756894009	HAM-PT-15	EPA 3010A	886934	EPA 6010D	886973
92756894010	HAM-AP1-EB-01	EPA 3010A	886934	EPA 6010D	886973
92756894011	HAM-AP1-FB-01	EPA 3010A	886934	EPA 6010D	886973
92756894012	HAM-AP1-FD-01	EPA 3010A	886934	EPA 6010D	886973
92756894001	HAM-PT-07	EPA 3005A	886933	EPA 6020B	886977
92756894002	HAM-PT-08	EPA 3005A	886933	EPA 6020B	886977
92756894003	HAM-PT-09	EPA 3005A	886933	EPA 6020B	886977
92756894004	HAM-PT-10	EPA 3005A	886933	EPA 6020B	886977
92756894005	HAM-PT-11	EPA 3005A	886933	EPA 6020B	886977
92756894006	HAM-PT-12	EPA 3005A	886933	EPA 6020B	886977
92756894007	HAM-PT-13	EPA 3005A	886933	EPA 6020B	886977
92756894008	HAM-PT-14	EPA 3005A	886933	EPA 6020B	886977
92756894009	HAM-PT-15	EPA 3005A	886933	EPA 6020B	886977
92756894010	HAM-AP1-EB-01	EPA 3005A	886933	EPA 6020B	886977
92756894011	HAM-AP1-FB-01	EPA 3005A	886933	EPA 6020B	886977
92756894012	HAM-AP1-FD-01	EPA 3005A	886933	EPA 6020B	886977

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

WO#: 92756894

The Chain of Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

www.garcilaso.com

[illegible]

92756894

Section A Required Client Information:		Section B Required Project Information:		Section C Invoice Information:	
Company:	GA Power	Report To:	SCS Contacts	Attention:	Southern Co.
Address:	Atlanta, GA	Copy To:	Geosyntec Contacts	Company Name:	
Email To:	SCS Contacts	Purchase Order No.:	GPC82474-0001	Address:	
Phone:		Project Name:	Hammond AP-1_Week 2	Pick Quote Reference:	
Fax:		Project Number:		Pick Project Manager:	Bonnie Vang
Requested Due Date/TAT:		10 Day		Place Profile #: 16483	

Section D Required Client Information		Valid Matrix Codes		COLLECTED		# OF CONTAINERS		Preservatives		Analysis Test		Requested Analysis Filtered (Y/N)		Pace Project No. / Lab I.D.					
ITEM #		MATRIX CODE	SAMPLE TYPE (G=GRAB Q=COMP)	COMPOSITE		COMPOSITE		UNPRESERVED	H ₂ SO ₄ HNO ₃ HCl NaOH Na ₂ S ₂ O ₃ Methanol Other				Y/N	Total 601/6022 B As, Mo, Fe	Total 601/6022 B As, Mo, Fe	Total 601/6022 B As, Mo, Fe	Residual Chlorine (Y/N)		
				DATE	TIME	DATE	TIME		DATE	TIME									
1	HAM-PT-07	WG G	G	10/12/2024	1431			1											
2	HAM-PT-08	WG G	G	10/12/2024	1440			1											
3	HAM-PT-09	WG G	G	10/22/2024	1221			1											
4	HAM-PT-10	WG G	G	10/22/2024	1210			1											
5	HAM-PT-11	WG G	G	10/22/2024	1006			1											
6	HAM-PT-12	WG G	G	10/22/2024	1030			1											
7	HAM-PT-13	WG G	G	10/12/2024	1215			1											
8	HAM-PT-14	WG G	G	10/12/2024	1120			1											
9	HAM-PT-15	WG G	G	10/12/2024	1725			1											
10	HAM-API-EB-01	WG G	G	10/22/2024	1345			1											
11	HAM-API-FB-01	WG G	G	10/22/2024	1340			1											
12	HAM-API-FD-01	WG G	G	10/22/2024	3000			1											

ADDITIONAL COMMENTS	RELINQUISHED BY / AFFILIATION		DATE		TIME		ACCEPTED BY / AFFILIATION		DATE		TIME		SAMPLE CONDITIONS	
Task Code: HAM-GOR-CA-20241001	Zain Webb / Geosyntec		10-3-24		1050		Ryan Williams / Pace		10/3/2024		1050			
	Ryan Williams / Pace		10/3/2024		1525		N/A		10/3/2024		1525			

SAMPLER NAME AND SIGNATURE			
PRINT Name of SAMPLER: Zain Webb, Elisabeth Russell / Geosyntec Consultants, Inc.			
SIGNATURE of SAMPLER: Zain Webb / Elisabeth Russell / Geosyntec Consultants, Inc. DATE Signed: 10/3/24			

Important Note: By signing this form you are accepting Pace's NET 30 day payment terms and agreeing to late charges of 1.5% per month for any invoices not paid within 30 days.

F-ALL-Q-020 rev 07 15-Feb-2007



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

Gut Power

Project #:

WO#: 92756894

Courier:

☐ Commercial☐ Fed Ex☒ Pace☐ UPS☐ USPS☐ Other:☐ Client

PM: BV

Due Date: 10/18/24

CLIENT: 92- GP-HAM

Custody Seal Present?

☐ Yes☐ No

Seals Intact?

☐ Yes☐ No☒ N/ADate/Initials Person Examining Contents: Man

Packing Material:

☒ Bubble Wrap☐ Bubble Bags☐ None☐ Other

Biological Tissue Frozen?

☐ Yes☐ No☒ N/A

Thermometer:

☐ IR Gun ID:

214

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

5.3

Correction Factor:

Add/Subtract (°C)

0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

5.3

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

			Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.	
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.	
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.	
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4.	
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.	
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.	
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A		
Containers Intact?	☒ Yes ☐ No ☐ N/A	7.	
Dissolved analysis: Samples Field Filtered?	☐ Yes ☐ No ☒ N/A	8.	
Sample Labels Match COC?	☒ Yes ☐ No ☐ N/A	9.	
-Includes Date/Time/ID/Analysis Matrix: <u>W6</u>			
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10.	
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.	
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A		

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_ Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

WO#: 92756894

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

PM: BV

Due Date: 10/18/24

CLIENT: 92- GP-HAM

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐Client GA Power Profile/EZ (Circle one) 16483 Notes

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4S-125 mL Plastic ZN Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGU-Wide-mouthed Glass jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG94-40 mL Amber NH4Cl (N/A) (Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2SO3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KPTU-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit) VPH/Gas kit (N/A)	SPST-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)	BP2R-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	VSGU-20 mL Schillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)
CC																											
1																											
2																											
3																											
4																											
5																											
6																											
7																											
8																											
9																											
10																											
11																											
12																											

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers.



October 29, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1_Week 3
Pace Project No.: 92757972

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on October 10, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Duluth, MN
- Pace Analytical Services - Peachtree Corners, GA
- Pace Analytical Services - Minneapolis

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Jamie Newsome, Geosyntec Consultants
Zain Webb, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Pace Analytical Services, LLC - Minneapolis MN

1700 Elm Street SE, Minneapolis, MN 55414

Alabama Certification #: 40770

Alaska Contaminated Sites Certification #: 17-009

Alaska DW Certification #: MN00064

Arizona Certification #: AZ0014

Arkansas DW Certification #: MN00064

Arkansas WW Certification #: 88-0680

California Certification #: 2929

Colorado Certification #: MN00064

Connecticut Certification #: PH-0256

DoD Certification via A2LA #: 2926.01

EPA Region 8 Tribal Water Systems+Wyoming DW
Certification #: via MN 027-053-137

Florida Certification #: E87605

Georgia Certification #: 959

GMP+ Certification #: GMP050884

Hawaii Certification #: MN00064

Idaho Certification #: MN00064

Illinois Certification #: 200011

Indiana Certification #: C-MN-01

Iowa Certification #: 368

ISO/IEC 17025 Certification via A2LA #: 2926.01

Kansas Certification #: E-10167

Kentucky DW Certification #: 90062

Kentucky WW Certification #: 90062

Louisiana DEQ Certification #: AI-03086

Louisiana DW Certification #: MN00064

Maine Certification #: MN00064

Maryland Certification #: 322

Michigan Certification #: 9909

Minnesota Certification #: 027-053-137

Minnesota Dept of Ag Approval: via MN 027-053-137

Minnesota Petrofund Registration #: 1240

Mississippi Certification #: MN00064

Missouri Certification #: 10100

Montana Certification #: CERT0092

Nebraska Certification #: NE-OS-18-06

Nevada Certification #: MN00064

New Hampshire Certification #: 2081

New Jersey Certification #: MN002

New York Certification #: 11647

North Carolina DW Certification #: 27700

North Carolina WW Certification #: 530

North Dakota Certification (A2LA) #: R-036

North Dakota Certification (MN) #: R-036

Ohio DW Certification #: 41244

Ohio VAP Certification (1700) #: CL101

Oklahoma Certification #: 9507

Oregon Primary Certification #: MN300001

Oregon Secondary Certification #: MN200001

Pennsylvania Certification #: 68-00563

Puerto Rico Certification #: MN00064

South Carolina Certification #: 74003001

Tennessee Certification #: TN02818

Texas Certification #: T104704192

Utah Certification #: MN00064

Vermont Certification #: VT-027053137

Virginia Certification #: 460163

Washington Certification #: C486

West Virginia DEP Certification #: 382

West Virginia DW Certification #: 9952 C

Wisconsin Certification #: 999407970

Wyoming UST Certification via A2LA #: 2926.01

USDA Permit #: P330-19-00208

Pace Analytical Services, LLC - Duluth MN

4730 Oneota Street, Duluth, MN 55807

Minnesota Certification #: 027-137-152

Minnesota Dept of Ag Approval: via Minnesota 027-137-
152

Minnesota Petrofund Registration #: 1240

North Dakota Certification #: R-105

Wisconsin Certification #: 999446800

Wisconsin Dept of Ag Certification #: 480341

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92757972001	HAM-PT-07	Water	10/08/24 15:13	10/10/24 11:15
92757972002	HAM-PT-08	Water	10/08/24 12:45	10/10/24 11:15
92757972003	HAM-PT-09	Water	10/09/24 12:40	10/10/24 11:15
92757972004	HAM-PT-10	Water	10/09/24 13:44	10/10/24 11:15
92757972005	HAM-PT-11	Water	10/09/24 10:07	10/10/24 11:15
92757972006	HAM-PT-12	Water	10/09/24 10:40	10/10/24 11:15
92757972007	HAM-PT-13	Water	10/08/24 13:00	10/10/24 11:15
92757972008	HAM-PT-14	Water	10/08/24 15:30	10/10/24 11:15
92757972009	HAM-PT-15	Water	10/08/24 17:04	10/10/24 11:15
92757972010	HAM-AP1-EB-01	Water	10/09/24 15:00	10/10/24 11:15
92757972011	HAM-AP1-FB-01	Water	10/09/24 15:05	10/10/24 11:15
92757972012	HAM-AP1-FD-01	Water	10/08/24 00:00	10/10/24 11:15

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
92757972001	HAM-PT-07	EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	MJS2	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
92757972002	HAM-PT-08	EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	MJS2	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
92757972003	HAM-PT-09	EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	MJS2	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
92757972004	HAM-PT-10	EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	MJS2	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
92757972005	HAM-PT-11	EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	MJS2	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
92757972006	HAM-PT-12	EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
92757972007	HAM-PT-13	EPA 6010D	MJS2	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
		EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	MJS2	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
92757972008	HAM-PT-14	SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
		EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	MJS2	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
		EPA 300.0	JA2	3	PASI-DU
92757972009	HAM-PT-15	SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	MJS2	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
		EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	MJS2	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
92757972010	HAM-AP1-EB-01	EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
		EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	MJS2	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
92757972011	HAM-AP1-FB-01	EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	MJS2	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
92757972012	HAM-AP1-FD-01	EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M
		EPA 300.0	JA2	3	PASI-DU
		SM 4500-S2 D-2011	DW3	1	PASI-DU
		EPA 6010D	MJS2	6	PASI-GA
		EPA 6020B	CW1	13	PASI-GA
		EPA 7470A	VB	1	PASI-GA
		SM 2540C-2015	DL1	1	PASI-GA
		SM 2320B	KEO	3	PASI-M

PASI-DU = Pace Analytical Services - Duluth, MN

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

PASI-M = Pace Analytical Services - Minneapolis

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92757972001	HAM-PT-07					
EPA 300.0	Chloride	18.6	mg/L	1.0	10/26/24 08:26	
EPA 300.0	Fluoride	0.30	mg/L	0.050	10/26/24 08:26	
EPA 300.0	Sulfate	238	mg/L	1.0	10/26/24 08:26	
EPA 6010D	Iron	3.2	mg/L	0.040	10/12/24 13:51	
EPA 6010D	Manganese	2.8	mg/L	0.040	10/12/24 13:51	
EPA 6010D	Potassium	5.6	mg/L	0.50	10/12/24 13:51	
EPA 6010D	Sodium	10.5	mg/L	1.0	10/13/24 13:15	
EPA 6010D	Calcium	108	mg/L	1.0	10/12/24 13:51	
EPA 6010D	Magnesium	17.0	mg/L	0.050	10/12/24 13:51	
EPA 6020B	Arsenic	0.025	mg/L	0.0050	10/14/24 20:32	
EPA 6020B	Barium	0.051	mg/L	0.0050	10/14/24 20:32	
EPA 6020B	Beryllium	0.00014J	mg/L	0.00050	10/14/24 20:32	
EPA 6020B	Boron	0.54	mg/L	0.040	10/14/24 20:32	
EPA 6020B	Cadmium	0.00016J	mg/L	0.00050	10/14/24 20:32	
EPA 6020B	Cobalt	0.033	mg/L	0.0050	10/15/24 19:56	
EPA 6020B	Lithium	0.051	mg/L	0.030	10/14/24 20:32	
EPA 6020B	Molybdenum	0.0045J	mg/L	0.010	10/14/24 20:32	
EPA 7470A	Mercury	0.00018J	mg/L	0.00020	10/16/24 13:37	
SM 2540C-2015	Total Dissolved Solids	548	mg/L	25.0	10/14/24 12:28	
SM 2320B	Alkalinity, Total as CaCO3	149	mg/L	5.0	10/17/24 13:07	
SM 2320B	Alkalinity,Bicarbonate (CaCO3)	149	mg/L	5.0	10/17/24 13:07	
92757972002	HAM-PT-08					
EPA 300.0	Chloride	18.1	mg/L	1.0	10/26/24 09:11	
EPA 300.0	Fluoride	0.23	mg/L	0.050	10/26/24 09:11	
EPA 300.0	Sulfate	242	mg/L	1.0	10/26/24 09:11	
EPA 6010D	Iron	2.8	mg/L	0.040	10/12/24 13:54	
EPA 6010D	Manganese	2.2	mg/L	0.040	10/12/24 13:54	
EPA 6010D	Potassium	5.7	mg/L	0.50	10/12/24 13:54	
EPA 6010D	Sodium	9.9	mg/L	1.0	10/13/24 13:19	
EPA 6010D	Calcium	106	mg/L	1.0	10/12/24 13:54	
EPA 6010D	Magnesium	15.4	mg/L	0.050	10/12/24 13:54	
EPA 6020B	Arsenic	0.066	mg/L	0.0050	10/14/24 20:36	
EPA 6020B	Barium	0.051	mg/L	0.0050	10/14/24 20:36	
EPA 6020B	Boron	0.58	mg/L	0.040	10/14/24 20:36	
EPA 6020B	Cadmium	0.00011J	mg/L	0.00050	10/14/24 20:36	
EPA 6020B	Cobalt	0.021	mg/L	0.0050	10/15/24 20:00	
EPA 6020B	Lithium	0.035	mg/L	0.030	10/14/24 20:36	
EPA 6020B	Molybdenum	0.0086J	mg/L	0.010	10/14/24 20:36	
SM 2540C-2015	Total Dissolved Solids	524	mg/L	25.0	10/14/24 12:29	
SM 2320B	Alkalinity, Total as CaCO3	114	mg/L	5.0	10/17/24 12:43	
SM 2320B	Alkalinity,Bicarbonate (CaCO3)	114	mg/L	5.0	10/17/24 12:43	
92757972003	HAM-PT-09					
EPA 300.0	Chloride	45.9	mg/L	1.0	10/26/24 10:27	
EPA 300.0	Fluoride	0.39	mg/L	0.050	10/26/24 10:27	
EPA 300.0	Sulfate	200	mg/L	1.0	10/26/24 10:27	
EPA 6010D	Iron	0.073	mg/L	0.040	10/12/24 13:57	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92757972003	HAM-PT-09					
EPA 6010D	Manganese	0.58	mg/L	0.040	10/12/24 13:57	
EPA 6010D	Potassium	6.0	mg/L	0.50	10/12/24 13:57	
EPA 6010D	Sodium	9.5	mg/L	1.0	10/13/24 13:22	
EPA 6010D	Calcium	92.4	mg/L	1.0	10/12/24 13:57	
EPA 6010D	Magnesium	25.3	mg/L	0.050	10/12/24 13:57	
EPA 6020B	Barium	0.073	mg/L	0.0050	10/14/24 20:40	
EPA 6020B	Boron	1.4	mg/L	0.040	10/14/24 20:40	
EPA 6020B	Cadmium	0.00018J	mg/L	0.00050	10/14/24 20:40	
EPA 6020B	Cobalt	0.0040J	mg/L	0.0050	10/15/24 20:11	
EPA 6020B	Lithium	0.0021J	mg/L	0.030	10/14/24 20:40	
EPA 6020B	Molybdenum	0.18	mg/L	0.010	10/14/24 20:40	
SM 2540C-2015	Total Dissolved Solids	493	mg/L	25.0	10/14/24 12:35	
SM 2320B	Alkalinity, Total as CaCO3	123	mg/L	5.0	10/17/24 13:42	
SM 2320B	Alkalinity,Bicarbonate (CaCO3)	123	mg/L	5.0	10/17/24 13:42	
92757972004	HAM-PT-10					
EPA 300.0	Chloride	50.0	mg/L	1.0	10/26/24 10:42	
EPA 300.0	Fluoride	0.29	mg/L	0.050	10/26/24 10:42	
EPA 300.0	Sulfate	165	mg/L	1.0	10/26/24 10:42	
EPA 6010D	Iron	0.12	mg/L	0.040	10/12/24 14:02	
EPA 6010D	Manganese	0.60	mg/L	0.040	10/12/24 14:02	
EPA 6010D	Potassium	7.0	mg/L	0.50	10/12/24 14:02	
EPA 6010D	Sodium	9.1	mg/L	1.0	10/13/24 13:26	
EPA 6010D	Calcium	109	mg/L	1.0	10/12/24 14:02	
EPA 6010D	Magnesium	14.1	mg/L	0.050	10/12/24 14:02	
EPA 6020B	Barium	0.054	mg/L	0.0050	10/14/24 20:45	
EPA 6020B	Boron	1.6	mg/L	0.040	10/14/24 20:45	
EPA 6020B	Cobalt	0.0013J	mg/L	0.0050	10/15/24 20:15	
EPA 6020B	Molybdenum	0.18	mg/L	0.010	10/14/24 20:45	
SM 2540C-2015	Total Dissolved Solids	484	mg/L	25.0	10/14/24 12:36	
SM 2320B	Alkalinity, Total as CaCO3	141	mg/L	5.0	10/17/24 13:47	
SM 2320B	Alkalinity,Bicarbonate (CaCO3)	141	mg/L	5.0	10/17/24 13:47	
92757972005	HAM-PT-11					
EPA 300.0	Chloride	37.6	mg/L	1.0	10/26/24 10:57	
EPA 300.0	Fluoride	0.32	mg/L	0.050	10/26/24 10:57	
EPA 300.0	Sulfate	211	mg/L	1.0	10/26/24 10:57	
EPA 6010D	Iron	0.24	mg/L	0.040	10/12/24 14:06	
EPA 6010D	Manganese	1.1	mg/L	0.040	10/12/24 14:06	
EPA 6010D	Potassium	5.7	mg/L	0.50	10/12/24 14:06	
EPA 6010D	Sodium	7.8	mg/L	1.0	10/13/24 13:30	
EPA 6010D	Calcium	91.9	mg/L	1.0	10/12/24 14:06	
EPA 6010D	Magnesium	21.6	mg/L	0.050	10/12/24 14:06	
EPA 6020B	Arsenic	0.0014J	mg/L	0.0050	10/24/24 12:53	
EPA 6020B	Barium	0.067	mg/L	0.0050	10/24/24 12:53	
EPA 6020B	Boron	1.5	mg/L	0.040	10/24/24 12:53	
EPA 6020B	Cadmium	0.00017J	mg/L	0.00050	10/24/24 12:53	
EPA 6020B	Cobalt	0.015	mg/L	0.0050	10/24/24 12:53	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92757972005	HAM-PT-11					
EPA 6020B	Lithium	0.0057J	mg/L	0.030	10/24/24 12:53	
EPA 6020B	Molybdenum	0.066	mg/L	0.010	10/24/24 12:53	
SM 2540C-2015	Total Dissolved Solids	496	mg/L	25.0	10/14/24 12:36	
SM 2320B	Alkalinity, Total as CaCO3	108	mg/L	5.0	10/17/24 13:32	
SM 2320B	Alkalinity,Bicarbonate (CaCO3)	108	mg/L	5.0	10/17/24 13:32	
92757972006	HAM-PT-12					
EPA 300.0	Chloride	41.9	mg/L	1.0	10/26/24 11:12	
EPA 300.0	Fluoride	0.32	mg/L	0.050	10/26/24 11:12	
EPA 300.0	Sulfate	203	mg/L	1.0	10/26/24 11:12	
EPA 6010D	Iron	0.091	mg/L	0.040	10/12/24 14:10	
EPA 6010D	Manganese	1.1	mg/L	0.040	10/12/24 14:10	
EPA 6010D	Potassium	5.6	mg/L	0.50	10/12/24 14:10	
EPA 6010D	Sodium	7.8	mg/L	1.0	10/13/24 13:35	
EPA 6010D	Calcium	87.3	mg/L	1.0	10/12/24 14:10	
EPA 6010D	Magnesium	24.8	mg/L	0.050	10/12/24 14:10	
EPA 6020B	Antimony	0.0022J	mg/L	0.0030	10/24/24 13:10	B
EPA 6020B	Arsenic	0.0015J	mg/L	0.0050	10/24/24 13:10	
EPA 6020B	Barium	0.071	mg/L	0.0050	10/24/24 13:10	
EPA 6020B	Boron	1.3	mg/L	0.040	10/24/24 13:10	
EPA 6020B	Cadmium	0.00031J	mg/L	0.00050	10/24/24 13:10	
EPA 6020B	Cobalt	0.0044J	mg/L	0.0050	10/24/24 13:10	
EPA 6020B	Lead	0.00074J	mg/L	0.0010	10/24/24 13:10	
EPA 6020B	Lithium	0.0029J	mg/L	0.030	10/24/24 13:10	
EPA 6020B	Molybdenum	0.18	mg/L	0.010	10/24/24 13:10	
SM 2540C-2015	Total Dissolved Solids	485	mg/L	25.0	10/14/24 12:36	
SM 2320B	Alkalinity, Total as CaCO3	113	mg/L	5.0	10/17/24 13:37	
SM 2320B	Alkalinity,Bicarbonate (CaCO3)	113	mg/L	5.0	10/17/24 13:37	
92757972007	HAM-PT-13					
EPA 300.0	Chloride	18.8	mg/L	1.0	10/26/24 11:27	
EPA 300.0	Fluoride	0.35	mg/L	0.050	10/26/24 11:27	
EPA 300.0	Sulfate	254	mg/L	1.0	10/26/24 11:27	
EPA 6010D	Iron	6.6	mg/L	0.040	10/13/24 20:41	
EPA 6010D	Manganese	3.2	mg/L	0.040	10/13/24 20:41	
EPA 6010D	Potassium	5.7	mg/L	0.50	10/13/24 20:41	
EPA 6010D	Sodium	10.7	mg/L	1.0	10/13/24 20:41	
EPA 6010D	Calcium	114	mg/L	1.0	10/13/24 20:41	M1
EPA 6010D	Magnesium	16.2	mg/L	0.050	10/13/24 20:41	M1
EPA 6020B	Antimony	0.00066J	mg/L	0.0030	10/24/24 13:14	B
EPA 6020B	Arsenic	0.033	mg/L	0.0050	10/24/24 13:14	
EPA 6020B	Barium	0.050	mg/L	0.0050	10/24/24 13:14	
EPA 6020B	Boron	0.54	mg/L	0.040	10/24/24 13:14	
EPA 6020B	Cobalt	0.025	mg/L	0.0050	10/24/24 13:14	
EPA 6020B	Lithium	0.053	mg/L	0.030	10/24/24 13:14	
EPA 6020B	Molybdenum	0.0043J	mg/L	0.010	10/24/24 13:14	
SM 2540C-2015	Total Dissolved Solids	562	mg/L	25.0	10/14/24 12:29	
SM 2320B	Alkalinity, Total as CaCO3	132	mg/L	5.0	10/17/24 13:01	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92757972007	HAM-PT-13					
SM 2320B	Alkalinity,Bicarbonate (CaCO3)	132	mg/L	5.0	10/17/24 13:01	
92757972008	HAM-PT-14					
EPA 300.0	Chloride	20.4	mg/L	1.0	10/26/24 11:42	
EPA 300.0	Fluoride	0.27	mg/L	0.050	10/26/24 11:42	
EPA 300.0	Sulfate	249	mg/L	1.0	10/26/24 11:42	
EPA 6010D	Iron	13.7	mg/L	0.040	10/13/24 20:54	
EPA 6010D	Manganese	2.8	mg/L	0.040	10/13/24 20:54	
EPA 6010D	Potassium	6.1	mg/L	0.50	10/13/24 20:54	
EPA 6010D	Sodium	11.1	mg/L	1.0	10/13/24 20:54	
EPA 6010D	Calcium	116	mg/L	1.0	10/13/24 20:54	
EPA 6010D	Magnesium	18.5	mg/L	0.050	10/13/24 20:54	
EPA 6020B	Arsenic	0.15	mg/L	0.0050	10/24/24 13:18	
EPA 6020B	Barium	0.047	mg/L	0.0050	10/24/24 13:18	
EPA 6020B	Beryllium	0.00011J	mg/L	0.00050	10/24/24 13:18	
EPA 6020B	Boron	0.57	mg/L	0.040	10/24/24 13:18	
EPA 6020B	Cobalt	0.023	mg/L	0.0050	10/24/24 13:18	
EPA 6020B	Lead	0.00026J	mg/L	0.0010	10/24/24 13:18	
EPA 6020B	Lithium	0.046	mg/L	0.030	10/24/24 13:18	
EPA 6020B	Molybdenum	0.015	mg/L	0.010	10/24/24 13:18	
SM 2540C-2015	Total Dissolved Solids	557	mg/L	25.0	10/14/24 12:33	
SM 2320B	Alkalinity, Total as CaCO3	151	mg/L	5.0	10/17/24 13:20	
SM 2320B	Alkalinity,Bicarbonate (CaCO3)	151	mg/L	5.0	10/17/24 13:20	
92757972009	HAM-PT-15					
EPA 300.0	Chloride	17.2	mg/L	1.0	10/26/24 11:57	
EPA 300.0	Fluoride	0.31	mg/L	0.050	10/26/24 11:57	
EPA 300.0	Sulfate	245	mg/L	1.0	10/26/24 11:57	
EPA 6010D	Iron	0.95	mg/L	0.040	10/13/24 20:58	
EPA 6010D	Manganese	2.5	mg/L	0.040	10/13/24 20:58	
EPA 6010D	Potassium	5.3	mg/L	0.50	10/13/24 20:58	
EPA 6010D	Sodium	9.2	mg/L	1.0	10/13/24 20:58	
EPA 6010D	Calcium	109	mg/L	1.0	10/13/24 20:58	
EPA 6010D	Magnesium	13.4	mg/L	0.050	10/13/24 20:58	
EPA 6020B	Antimony	0.00061J	mg/L	0.0030	10/24/24 13:22	B
EPA 6020B	Arsenic	0.013	mg/L	0.0050	10/24/24 13:22	
EPA 6020B	Barium	0.051	mg/L	0.0050	10/24/24 13:22	
EPA 6020B	Beryllium	0.00012J	mg/L	0.00050	10/24/24 13:22	
EPA 6020B	Boron	0.60	mg/L	0.040	10/24/24 13:22	
EPA 6020B	Cadmium	0.00025J	mg/L	0.00050	10/24/24 13:22	
EPA 6020B	Cobalt	0.016	mg/L	0.0050	10/24/24 13:22	
EPA 6020B	Lithium	0.038	mg/L	0.030	10/24/24 13:22	
EPA 6020B	Molybdenum	0.011	mg/L	0.010	10/24/24 13:22	
EPA 6020B	Selenium	0.0029J	mg/L	0.0050	10/24/24 13:22	
EPA 6020B	Thallium	0.00039J	mg/L	0.0010	10/24/24 13:22	
SM 2540C-2015	Total Dissolved Solids	509	mg/L	25.0	10/14/24 12:33	
SM 2320B	Alkalinity, Total as CaCO3	114	mg/L	5.0	10/17/24 13:26	
SM 2320B	Alkalinity,Bicarbonate (CaCO3)	114	mg/L	5.0	10/17/24 13:26	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92757972010	HAM-AP1-EB-01					
EPA 6010D	Sodium	0.98J	mg/L	1.0	10/13/24 21:01	
EPA 6010D	Calcium	0.31J	mg/L	1.0	10/13/24 21:01	
EPA 6010D	Magnesium	0.080	mg/L	0.050	10/13/24 21:01	
EPA 6020B	Antimony	0.00074J	mg/L	0.0030	10/24/24 14:24	B
EPA 6020B	Arsenic	0.00087J	mg/L	0.0050	10/24/24 14:24	
EPA 6020B	Barium	0.0020J	mg/L	0.0050	10/24/24 14:24	
EPA 6020B	Lead	0.00019J	mg/L	0.0010	10/24/24 14:24	
92757972011	HAM-AP1-FB-01					
EPA 6010D	Iron	0.032J	mg/L	0.040	10/13/24 21:05	
EPA 6010D	Sodium	1.1	mg/L	1.0	10/13/24 21:05	
EPA 6010D	Calcium	0.45J	mg/L	1.0	10/13/24 21:05	
EPA 6010D	Magnesium	0.12	mg/L	0.050	10/13/24 21:05	
EPA 6020B	Arsenic	0.00098J	mg/L	0.0050	10/24/24 14:29	
EPA 6020B	Barium	0.0023J	mg/L	0.0050	10/24/24 14:29	
EPA 6020B	Lead	0.00019J	mg/L	0.0010	10/24/24 14:29	
SM 2320B	Alkalinity, Total as CaCO ₃	5.0	mg/L	5.0	10/17/24 13:56	
SM 2320B	Alkalinity,Bicarbonate (CaCO ₃)	5.0	mg/L	5.0	10/17/24 13:56	
92757972012	HAM-AP1-FD-01					
EPA 300.0	Chloride	17.2	mg/L	1.0	10/26/24 13:12	
EPA 300.0	Fluoride	0.32	mg/L	0.050	10/26/24 13:12	
EPA 300.0	Sulfate	247	mg/L	1.0	10/26/24 13:12	
EPA 6010D	Iron	0.78	mg/L	0.040	10/13/24 21:09	
EPA 6010D	Manganese	2.7	mg/L	0.040	10/13/24 21:09	
EPA 6010D	Potassium	5.6	mg/L	0.50	10/13/24 21:09	
EPA 6010D	Sodium	9.6	mg/L	1.0	10/13/24 21:09	
EPA 6010D	Calcium	116	mg/L	1.0	10/13/24 21:09	
EPA 6010D	Magnesium	14.1	mg/L	0.050	10/13/24 21:09	
EPA 6020B	Arsenic	0.012	mg/L	0.0050	10/24/24 14:33	
EPA 6020B	Barium	0.049	mg/L	0.0050	10/24/24 14:33	
EPA 6020B	Beryllium	0.000094J	mg/L	0.00050	10/24/24 14:33	
EPA 6020B	Boron	0.59	mg/L	0.040	10/24/24 14:33	
EPA 6020B	Cadmium	0.00028J	mg/L	0.00050	10/24/24 14:33	
EPA 6020B	Cobalt	0.015	mg/L	0.0050	10/24/24 14:33	
EPA 6020B	Lithium	0.037	mg/L	0.030	10/24/24 14:33	
EPA 6020B	Molybdenum	0.010	mg/L	0.010	10/24/24 14:33	
EPA 6020B	Selenium	0.0031J	mg/L	0.0050	10/24/24 14:33	
SM 2540C-2015	Total Dissolved Solids	521	mg/L	25.0	10/14/24 12:34	
SM 2320B	Alkalinity, Total as CaCO ₃	114	mg/L	5.0	10/17/24 12:37	
SM 2320B	Alkalinity,Bicarbonate (CaCO ₃)	114	mg/L	5.0	10/17/24 12:37	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Sample: HAM-PT-07		Lab ID: 92757972001		Collected: 10/08/24 15:13		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	18.6	mg/L	1.0	0.34	1		10/26/24 08:26	16887-00-6	
Fluoride	0.30	mg/L	0.050	0.0057	1		10/26/24 08:26	16984-48-8	
Sulfate	238	mg/L	1.0	0.086	1		10/26/24 08:26	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/15/24 18:03	18496-25-8	
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	3.2	mg/L	0.040	0.025	1	10/11/24 13:38	10/12/24 13:51	7439-89-6	
Manganese	2.8	mg/L	0.040	0.011	1	10/11/24 13:38	10/12/24 13:51	7439-96-5	
Potassium	5.6	mg/L	0.50	0.15	1	10/11/24 13:38	10/12/24 13:51	7440-09-7	
Sodium	10.5	mg/L	1.0	0.58	1	10/11/24 13:38	10/13/24 13:15	7440-23-5	
Calcium	108	mg/L	1.0	0.12	1	10/11/24 13:38	10/12/24 13:51	7440-70-2	
Magnesium	17.0	mg/L	0.050	0.012	1	10/11/24 13:38	10/12/24 13:51	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.00054	1	10/12/24 10:28	10/14/24 20:32	7440-36-0	
Arsenic	0.025	mg/L	0.0050	0.00084	1	10/12/24 10:28	10/14/24 20:32	7440-38-2	
Barium	0.051	mg/L	0.0050	0.00047	1	10/12/24 10:28	10/14/24 20:32	7440-39-3	
Beryllium	0.00014J	mg/L	0.00050	0.000094	1	10/12/24 10:28	10/14/24 20:32	7440-41-7	
Boron	0.54	mg/L	0.040	0.012	1	10/12/24 10:28	10/14/24 20:32	7440-42-8	
Cadmium	0.00016J	mg/L	0.00050	0.00010	1	10/12/24 10:28	10/14/24 20:32	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/12/24 10:28	10/14/24 20:32	7440-47-3	
Cobalt	0.033	mg/L	0.0050	0.00032	1	10/12/24 10:28	10/15/24 19:56	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	10/12/24 10:28	10/14/24 20:32	7439-92-1	
Lithium	0.051	mg/L	0.030	0.0016	1	10/12/24 10:28	10/14/24 20:32	7439-93-2	
Molybdenum	0.0045J	mg/L	0.010	0.00062	1	10/12/24 10:28	10/14/24 20:32	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	10/12/24 10:28	10/14/24 20:32	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/12/24 10:28	10/15/24 19:56	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	0.00018J	mg/L	0.00020	0.00013	1	10/16/24 07:30	10/16/24 13:37	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	548	mg/L	25.0	25.0	1		10/14/24 12:28		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO ₃	149	mg/L	5.0	1.9	1		10/17/24 13:07		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Sample: HAM-PT-07		Lab ID: 92757972001		Collected: 10/08/24 15:13		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO ₃)	149	mg/L	5.0	1.9	1		10/17/24 13:07		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	1.9	1		10/17/24 13:07		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3
Pace Project No.: 92757972

Sample: HAM-PT-08		Lab ID: 92757972002		Collected: 10/08/24 12:45		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	18.1	mg/L	1.0	0.34	1		10/26/24 09:11	16887-00-6	
Fluoride	0.23	mg/L	0.050	0.0057	1		10/26/24 09:11	16984-48-8	
Sulfate	242	mg/L	1.0	0.086	1		10/26/24 09:11	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/15/24 18:03	18496-25-8	
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	2.8	mg/L	0.040	0.025	1	10/11/24 13:38	10/12/24 13:54	7439-89-6	
Manganese	2.2	mg/L	0.040	0.011	1	10/11/24 13:38	10/12/24 13:54	7439-96-5	
Potassium	5.7	mg/L	0.50	0.15	1	10/11/24 13:38	10/12/24 13:54	7440-09-7	
Sodium	9.9	mg/L	1.0	0.58	1	10/11/24 13:38	10/13/24 13:19	7440-23-5	
Calcium	106	mg/L	1.0	0.12	1	10/11/24 13:38	10/12/24 13:54	7440-70-2	
Magnesium	15.4	mg/L	0.050	0.012	1	10/11/24 13:38	10/12/24 13:54	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.00054	1	10/12/24 10:28	10/14/24 20:36	7440-36-0	
Arsenic	0.066	mg/L	0.0050	0.00084	1	10/12/24 10:28	10/14/24 20:36	7440-38-2	
Barium	0.051	mg/L	0.0050	0.00047	1	10/12/24 10:28	10/14/24 20:36	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	10/12/24 10:28	10/14/24 20:36	7440-41-7	
Boron	0.58	mg/L	0.040	0.012	1	10/12/24 10:28	10/14/24 20:36	7440-42-8	
Cadmium	0.00011J	mg/L	0.00050	0.00010	1	10/12/24 10:28	10/14/24 20:36	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/12/24 10:28	10/14/24 20:36	7440-47-3	
Cobalt	0.021	mg/L	0.0050	0.00032	1	10/12/24 10:28	10/15/24 20:00	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	10/12/24 10:28	10/14/24 20:36	7439-92-1	
Lithium	0.035	mg/L	0.030	0.0016	1	10/12/24 10:28	10/14/24 20:36	7439-93-2	
Molybdenum	0.0086J	mg/L	0.010	0.00062	1	10/12/24 10:28	10/14/24 20:36	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	10/12/24 10:28	10/14/24 20:36	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/12/24 10:28	10/15/24 20:00	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/16/24 07:30	10/16/24 13:40	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	524	mg/L	25.0	25.0	1		10/14/24 12:29		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO3	114	mg/L	5.0	1.9	1		10/17/24 12:43		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Sample: HAM-PT-08		Lab ID: 92757972002		Collected: 10/08/24 12:45		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO ₃)	114	mg/L	5.0	1.9	1		10/17/24 12:43		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	1.9	1		10/17/24 12:43		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Sample: HAM-PT-09		Lab ID: 92757972003		Collected: 10/09/24 12:40		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	45.9	mg/L	1.0	0.34	1		10/26/24 10:27	16887-00-6	
Fluoride	0.39	mg/L	0.050	0.0057	1		10/26/24 10:27	16984-48-8	
Sulfate	200	mg/L	1.0	0.086	1		10/26/24 10:27	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/15/24 18:03	18496-25-8	
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	0.073	mg/L	0.040	0.025	1	10/11/24 13:38	10/12/24 13:57	7439-89-6	
Manganese	0.58	mg/L	0.040	0.011	1	10/11/24 13:38	10/12/24 13:57	7439-96-5	
Potassium	6.0	mg/L	0.50	0.15	1	10/11/24 13:38	10/12/24 13:57	7440-09-7	
Sodium	9.5	mg/L	1.0	0.58	1	10/11/24 13:38	10/13/24 13:22	7440-23-5	
Calcium	92.4	mg/L	1.0	0.12	1	10/11/24 13:38	10/12/24 13:57	7440-70-2	
Magnesium	25.3	mg/L	0.050	0.012	1	10/11/24 13:38	10/12/24 13:57	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.00054	1	10/12/24 10:28	10/14/24 20:40	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	10/12/24 10:28	10/14/24 20:40	7440-38-2	
Barium	0.073	mg/L	0.0050	0.00047	1	10/12/24 10:28	10/14/24 20:40	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	10/12/24 10:28	10/14/24 20:40	7440-41-7	
Boron	1.4	mg/L	0.040	0.012	1	10/12/24 10:28	10/14/24 20:40	7440-42-8	
Cadmium	0.00018J	mg/L	0.00050	0.00010	1	10/12/24 10:28	10/14/24 20:40	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/12/24 10:28	10/14/24 20:40	7440-47-3	
Cobalt	0.0040J	mg/L	0.0050	0.00032	1	10/12/24 10:28	10/15/24 20:11	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	10/12/24 10:28	10/14/24 20:40	7439-92-1	
Lithium	0.0021J	mg/L	0.030	0.0016	1	10/12/24 10:28	10/14/24 20:40	7439-93-2	
Molybdenum	0.18	mg/L	0.010	0.00062	1	10/12/24 10:28	10/14/24 20:40	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	10/12/24 10:28	10/14/24 20:40	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/12/24 10:28	10/15/24 20:11	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/16/24 07:30	10/16/24 13:50	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	493	mg/L	25.0	25.0	1		10/14/24 12:35		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO ₃	123	mg/L	5.0	1.9	1		10/17/24 13:42		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Sample: HAM-PT-09		Lab ID: 92757972003		Collected: 10/09/24 12:40		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO ₃)	123	mg/L	5.0	1.9	1		10/17/24 13:42		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	1.9	1		10/17/24 13:42		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3
Pace Project No.: 92757972

Sample: HAM-PT-10		Lab ID: 92757972004		Collected: 10/09/24 13:44		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	50.0	mg/L	1.0	0.34	1		10/26/24 10:42	16887-00-6	
Fluoride	0.29	mg/L	0.050	0.0057	1		10/26/24 10:42	16984-48-8	
Sulfate	165	mg/L	1.0	0.086	1		10/26/24 10:42	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/15/24 18:03	18496-25-8	
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	0.12	mg/L	0.040	0.025	1	10/11/24 13:38	10/12/24 14:02	7439-89-6	
Manganese	0.60	mg/L	0.040	0.011	1	10/11/24 13:38	10/12/24 14:02	7439-96-5	
Potassium	7.0	mg/L	0.50	0.15	1	10/11/24 13:38	10/12/24 14:02	7440-09-7	
Sodium	9.1	mg/L	1.0	0.58	1	10/11/24 13:38	10/13/24 13:26	7440-23-5	
Calcium	109	mg/L	1.0	0.12	1	10/11/24 13:38	10/12/24 14:02	7440-70-2	
Magnesium	14.1	mg/L	0.050	0.012	1	10/11/24 13:38	10/12/24 14:02	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.00054	1	10/12/24 10:28	10/14/24 20:45	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.00084	1	10/12/24 10:28	10/14/24 20:45	7440-38-2	
Barium	0.054	mg/L	0.0050	0.00047	1	10/12/24 10:28	10/14/24 20:45	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	10/12/24 10:28	10/14/24 20:45	7440-41-7	
Boron	1.6	mg/L	0.040	0.012	1	10/12/24 10:28	10/14/24 20:45	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	10/12/24 10:28	10/14/24 20:45	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/12/24 10:28	10/14/24 20:45	7440-47-3	
Cobalt	0.0013J	mg/L	0.0050	0.00032	1	10/12/24 10:28	10/15/24 20:15	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	10/12/24 10:28	10/14/24 20:45	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	10/12/24 10:28	10/14/24 20:45	7439-93-2	
Molybdenum	0.18	mg/L	0.010	0.00062	1	10/12/24 10:28	10/14/24 20:45	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	10/12/24 10:28	10/14/24 20:45	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/12/24 10:28	10/15/24 20:15	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/16/24 07:30	10/16/24 13:53	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	484	mg/L	25.0	25.0	1		10/14/24 12:36		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO3	141	mg/L	5.0	1.9	1		10/17/24 13:47		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3
Pace Project No.: 92757972

Sample: HAM-PT-10		Lab ID: 92757972004		Collected: 10/09/24 13:44		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO3)	141	mg/L	5.0	1.9	1		10/17/24 13:47		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/17/24 13:47		

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Sample: HAM-PT-11		Lab ID: 92757972005		Collected: 10/09/24 10:07		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	37.6	mg/L	1.0	0.34	1		10/26/24 10:57	16887-00-6	
Fluoride	0.32	mg/L	0.050	0.0057	1		10/26/24 10:57	16984-48-8	
Sulfate	211	mg/L	1.0	0.086	1		10/26/24 10:57	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/15/24 18:04	18496-25-8	
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	0.24	mg/L	0.040	0.025	1	10/11/24 13:38	10/12/24 14:06	7439-89-6	
Manganese	1.1	mg/L	0.040	0.011	1	10/11/24 13:38	10/12/24 14:06	7439-96-5	
Potassium	5.7	mg/L	0.50	0.15	1	10/11/24 13:38	10/12/24 14:06	7440-09-7	
Sodium	7.8	mg/L	1.0	0.58	1	10/11/24 13:38	10/13/24 13:30	7440-23-5	
Calcium	91.9	mg/L	1.0	0.12	1	10/11/24 13:38	10/12/24 14:06	7440-70-2	
Magnesium	21.6	mg/L	0.050	0.012	1	10/11/24 13:38	10/12/24 14:06	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.00054	1	10/12/24 10:28	10/24/24 12:53	7440-36-0	
Arsenic	0.0014J	mg/L	0.0050	0.00084	1	10/12/24 10:28	10/24/24 12:53	7440-38-2	
Barium	0.067	mg/L	0.0050	0.00047	1	10/12/24 10:28	10/24/24 12:53	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	10/12/24 10:28	10/24/24 12:53	7440-41-7	
Boron	1.5	mg/L	0.040	0.012	1	10/12/24 10:28	10/24/24 12:53	7440-42-8	
Cadmium	0.00017J	mg/L	0.00050	0.00010	1	10/12/24 10:28	10/24/24 12:53	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/12/24 10:28	10/24/24 12:53	7440-47-3	
Cobalt	0.015	mg/L	0.0050	0.00032	1	10/12/24 10:28	10/24/24 12:53	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	10/12/24 10:28	10/24/24 12:53	7439-92-1	
Lithium	0.0057J	mg/L	0.030	0.0016	1	10/12/24 10:28	10/24/24 12:53	7439-93-2	
Molybdenum	0.066	mg/L	0.010	0.00062	1	10/12/24 10:28	10/24/24 12:53	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	10/12/24 10:28	10/24/24 12:53	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/12/24 10:28	10/24/24 12:53	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/16/24 07:30	10/16/24 13:56	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	496	mg/L	25.0	25.0	1		10/14/24 12:36		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO3	108	mg/L	5.0	1.9	1		10/17/24 13:32		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3
Pace Project No.: 92757972

Sample: HAM-PT-11		Lab ID: 92757972005		Collected: 10/09/24 10:07		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO3)	108	mg/L	5.0	1.9	1		10/17/24 13:32		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/17/24 13:32		

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Sample: HAM-PT-12		Lab ID: 92757972006		Collected: 10/09/24 10:40		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	41.9	mg/L	1.0	0.34	1		10/26/24 11:12	16887-00-6	
Fluoride	0.32	mg/L	0.050	0.0057	1		10/26/24 11:12	16984-48-8	
Sulfate	203	mg/L	1.0	0.086	1		10/26/24 11:12	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/15/24 18:04	18496-25-8	
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	0.091	mg/L	0.040	0.025	1	10/11/24 13:38	10/12/24 14:10	7439-89-6	
Manganese	1.1	mg/L	0.040	0.011	1	10/11/24 13:38	10/12/24 14:10	7439-96-5	
Potassium	5.6	mg/L	0.50	0.15	1	10/11/24 13:38	10/12/24 14:10	7440-09-7	
Sodium	7.8	mg/L	1.0	0.58	1	10/11/24 13:38	10/13/24 13:35	7440-23-5	
Calcium	87.3	mg/L	1.0	0.12	1	10/11/24 13:38	10/12/24 14:10	7440-70-2	
Magnesium	24.8	mg/L	0.050	0.012	1	10/11/24 13:38	10/12/24 14:10	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	0.0022J	mg/L	0.0030	0.00054	1	10/12/24 10:28	10/24/24 13:10	7440-36-0	B
Arsenic	0.0015J	mg/L	0.0050	0.00084	1	10/12/24 10:28	10/24/24 13:10	7440-38-2	
Barium	0.071	mg/L	0.0050	0.00047	1	10/12/24 10:28	10/24/24 13:10	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	10/12/24 10:28	10/24/24 13:10	7440-41-7	
Boron	1.3	mg/L	0.040	0.012	1	10/12/24 10:28	10/24/24 13:10	7440-42-8	
Cadmium	0.00031J	mg/L	0.00050	0.00010	1	10/12/24 10:28	10/24/24 13:10	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/12/24 10:28	10/24/24 13:10	7440-47-3	
Cobalt	0.0044J	mg/L	0.0050	0.00032	1	10/12/24 10:28	10/24/24 13:10	7440-48-4	
Lead	0.00074J	mg/L	0.0010	0.00016	1	10/12/24 10:28	10/24/24 13:10	7439-92-1	
Lithium	0.0029J	mg/L	0.030	0.0016	1	10/12/24 10:28	10/24/24 13:10	7439-93-2	
Molybdenum	0.18	mg/L	0.010	0.00062	1	10/12/24 10:28	10/24/24 13:10	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	10/12/24 10:28	10/24/24 13:10	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/12/24 10:28	10/24/24 13:10	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/16/24 07:30	10/16/24 14:03	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	485	mg/L	25.0	25.0	1		10/14/24 12:36		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO ₃	113	mg/L	5.0	1.9	1		10/17/24 13:37		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3
Pace Project No.: 92757972

Sample: HAM-PT-12		Lab ID: 92757972006		Collected: 10/09/24 10:40		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO3)	113	mg/L	5.0	1.9	1		10/17/24 13:37		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/17/24 13:37		

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Sample: HAM-PT-13		Lab ID: 92757972007		Collected: 10/08/24 13:00		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	18.8	mg/L	1.0	0.34	1		10/26/24 11:27	16887-00-6	
Fluoride	0.35	mg/L	0.050	0.0057	1		10/26/24 11:27	16984-48-8	
Sulfate	254	mg/L	1.0	0.086	1		10/26/24 11:27	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/15/24 18:04	18496-25-8	
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	6.6	mg/L	0.040	0.025	1	10/12/24 13:49	10/13/24 20:41	7439-89-6	
Manganese	3.2	mg/L	0.040	0.011	1	10/12/24 13:49	10/13/24 20:41	7439-96-5	
Potassium	5.7	mg/L	0.50	0.15	1	10/12/24 13:49	10/13/24 20:41	7440-09-7	
Sodium	10.7	mg/L	1.0	0.58	1	10/12/24 13:49	10/13/24 20:41	7440-23-5	
Calcium	114	mg/L	1.0	0.12	1	10/12/24 13:49	10/13/24 20:41	7440-70-2	M1
Magnesium	16.2	mg/L	0.050	0.012	1	10/12/24 13:49	10/13/24 20:41	7439-95-4	M1
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	0.00066J	mg/L	0.0030	0.00054	1	10/12/24 10:28	10/24/24 13:14	7440-36-0	B
Arsenic	0.033	mg/L	0.0050	0.00084	1	10/12/24 10:28	10/24/24 13:14	7440-38-2	
Barium	0.050	mg/L	0.0050	0.00047	1	10/12/24 10:28	10/24/24 13:14	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	10/12/24 10:28	10/24/24 13:14	7440-41-7	
Boron	0.54	mg/L	0.040	0.012	1	10/12/24 10:28	10/24/24 13:14	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	10/12/24 10:28	10/24/24 13:14	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/12/24 10:28	10/24/24 13:14	7440-47-3	
Cobalt	0.025	mg/L	0.0050	0.00032	1	10/12/24 10:28	10/24/24 13:14	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	10/12/24 10:28	10/24/24 13:14	7439-92-1	
Lithium	0.053	mg/L	0.030	0.0016	1	10/12/24 10:28	10/24/24 13:14	7439-93-2	
Molybdenum	0.0043J	mg/L	0.010	0.00062	1	10/12/24 10:28	10/24/24 13:14	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	10/12/24 10:28	10/24/24 13:14	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/12/24 10:28	10/24/24 13:14	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/16/24 07:30	10/16/24 14:06	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	562	mg/L	25.0	25.0	1		10/14/24 12:29		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO3	132	mg/L	5.0	1.9	1		10/17/24 13:01		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3
Pace Project No.: 92757972

Sample: HAM-PT-13		Lab ID: 92757972007		Collected: 10/08/24 13:00		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO3)	132	mg/L	5.0	1.9	1		10/17/24 13:01		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/17/24 13:01		

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Sample: HAM-PT-14		Lab ID: 92757972008		Collected: 10/08/24 15:30		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	20.4	mg/L	1.0	0.34	1		10/26/24 11:42	16887-00-6	
Fluoride	0.27	mg/L	0.050	0.0057	1		10/26/24 11:42	16984-48-8	
Sulfate	249	mg/L	1.0	0.086	1		10/26/24 11:42	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/15/24 18:04	18496-25-8	
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	13.7	mg/L	0.040	0.025	1	10/12/24 13:49	10/13/24 20:54	7439-89-6	
Manganese	2.8	mg/L	0.040	0.011	1	10/12/24 13:49	10/13/24 20:54	7439-96-5	
Potassium	6.1	mg/L	0.50	0.15	1	10/12/24 13:49	10/13/24 20:54	7440-09-7	
Sodium	11.1	mg/L	1.0	0.58	1	10/12/24 13:49	10/13/24 20:54	7440-23-5	
Calcium	116	mg/L	1.0	0.12	1	10/12/24 13:49	10/13/24 20:54	7440-70-2	
Magnesium	18.5	mg/L	0.050	0.012	1	10/12/24 13:49	10/13/24 20:54	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.00054	1	10/12/24 10:28	10/24/24 13:18	7440-36-0	
Arsenic	0.15	mg/L	0.0050	0.00084	1	10/12/24 10:28	10/24/24 13:18	7440-38-2	
Barium	0.047	mg/L	0.0050	0.00047	1	10/12/24 10:28	10/24/24 13:18	7440-39-3	
Beryllium	0.00011J	mg/L	0.00050	0.000094	1	10/12/24 10:28	10/24/24 13:18	7440-41-7	
Boron	0.57	mg/L	0.040	0.012	1	10/12/24 10:28	10/24/24 13:18	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	10/12/24 10:28	10/24/24 13:18	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/12/24 10:28	10/24/24 13:18	7440-47-3	
Cobalt	0.023	mg/L	0.0050	0.00032	1	10/12/24 10:28	10/24/24 13:18	7440-48-4	
Lead	0.00026J	mg/L	0.0010	0.00016	1	10/12/24 10:28	10/24/24 13:18	7439-92-1	
Lithium	0.046	mg/L	0.030	0.0016	1	10/12/24 10:28	10/24/24 13:18	7439-93-2	
Molybdenum	0.015	mg/L	0.010	0.00062	1	10/12/24 10:28	10/24/24 13:18	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	10/12/24 10:28	10/24/24 13:18	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/12/24 10:28	10/24/24 13:18	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/16/24 07:30	10/16/24 14:09	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	557	mg/L	25.0	25.0	1		10/14/24 12:33		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO ₃	151	mg/L	5.0	1.9	1		10/17/24 13:20		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3
Pace Project No.: 92757972

Sample: HAM-PT-14		Lab ID: 92757972008		Collected: 10/08/24 15:30		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO3)	151	mg/L	5.0	1.9	1		10/17/24 13:20		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/17/24 13:20		

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Sample: HAM-PT-15		Lab ID: 92757972009		Collected: 10/08/24 17:04		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	17.2	mg/L	1.0	0.34	1		10/26/24 11:57	16887-00-6	
Fluoride	0.31	mg/L	0.050	0.0057	1		10/26/24 11:57	16984-48-8	
Sulfate	245	mg/L	1.0	0.086	1		10/26/24 11:57	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/15/24 18:04	18496-25-8	
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	0.95	mg/L	0.040	0.025	1	10/12/24 13:49	10/13/24 20:58	7439-89-6	
Manganese	2.5	mg/L	0.040	0.011	1	10/12/24 13:49	10/13/24 20:58	7439-96-5	
Potassium	5.3	mg/L	0.50	0.15	1	10/12/24 13:49	10/13/24 20:58	7440-09-7	
Sodium	9.2	mg/L	1.0	0.58	1	10/12/24 13:49	10/13/24 20:58	7440-23-5	
Calcium	109	mg/L	1.0	0.12	1	10/12/24 13:49	10/13/24 20:58	7440-70-2	
Magnesium	13.4	mg/L	0.050	0.012	1	10/12/24 13:49	10/13/24 20:58	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	0.00061J	mg/L	0.0030	0.00054	1	10/12/24 10:28	10/24/24 13:22	7440-36-0	B
Arsenic	0.013	mg/L	0.0050	0.00084	1	10/12/24 10:28	10/24/24 13:22	7440-38-2	
Barium	0.051	mg/L	0.0050	0.00047	1	10/12/24 10:28	10/24/24 13:22	7440-39-3	
Beryllium	0.00012J	mg/L	0.00050	0.000094	1	10/12/24 10:28	10/24/24 13:22	7440-41-7	
Boron	0.60	mg/L	0.040	0.012	1	10/12/24 10:28	10/24/24 13:22	7440-42-8	
Cadmium	0.00025J	mg/L	0.00050	0.00010	1	10/12/24 10:28	10/24/24 13:22	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/12/24 10:28	10/24/24 13:22	7440-47-3	
Cobalt	0.016	mg/L	0.0050	0.00032	1	10/12/24 10:28	10/24/24 13:22	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	10/12/24 10:28	10/24/24 13:22	7439-92-1	
Lithium	0.038	mg/L	0.030	0.0016	1	10/12/24 10:28	10/24/24 13:22	7439-93-2	
Molybdenum	0.011	mg/L	0.010	0.00062	1	10/12/24 10:28	10/24/24 13:22	7439-98-7	
Selenium	0.0029J	mg/L	0.0050	0.00096	1	10/12/24 10:28	10/24/24 13:22	7782-49-2	
Thallium	0.00039J	mg/L	0.0010	0.00038	1	10/12/24 10:28	10/24/24 13:22	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/16/24 07:30	10/16/24 14:11	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	509	mg/L	25.0	25.0	1		10/14/24 12:33		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO ₃	114	mg/L	5.0	1.9	1		10/17/24 13:26		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Sample: HAM-PT-15		Lab ID: 92757972009		Collected: 10/08/24 17:04		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO ₃)	114	mg/L	5.0	1.9	1		10/17/24 13:26		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	1.9	1		10/17/24 13:26		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Sample: HAM-AP1-EB-01		Lab ID: 92757972010		Collected: 10/09/24 15:00		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	ND	mg/L	1.0	0.34	1		10/26/24 12:12	16887-00-6	
Fluoride	ND	mg/L	0.050	0.0057	1		10/26/24 12:12	16984-48-8	
Sulfate	ND	mg/L	1.0	0.086	1		10/26/24 12:12	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/15/24 18:05	18496-25-8	
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	ND	mg/L	0.040	0.025	1	10/12/24 13:49	10/13/24 21:01	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	10/12/24 13:49	10/13/24 21:01	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	10/12/24 13:49	10/13/24 21:01	7440-09-7	
Sodium	0.98J	mg/L	1.0	0.58	1	10/12/24 13:49	10/13/24 21:01	7440-23-5	
Calcium	0.31J	mg/L	1.0	0.12	1	10/12/24 13:49	10/13/24 21:01	7440-70-2	
Magnesium	0.080	mg/L	0.050	0.012	1	10/12/24 13:49	10/13/24 21:01	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	0.00074J	mg/L	0.0030	0.00054	1	10/12/24 10:28	10/24/24 14:24	7440-36-0	B
Arsenic	0.00087J	mg/L	0.0050	0.00084	1	10/12/24 10:28	10/24/24 14:24	7440-38-2	
Barium	0.0020J	mg/L	0.0050	0.00047	1	10/12/24 10:28	10/24/24 14:24	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	10/12/24 10:28	10/24/24 14:24	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	10/12/24 10:28	10/24/24 14:24	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	10/12/24 10:28	10/24/24 14:24	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/12/24 10:28	10/24/24 14:24	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	10/12/24 10:28	10/24/24 14:24	7440-48-4	
Lead	0.00019J	mg/L	0.0010	0.00016	1	10/12/24 10:28	10/24/24 14:24	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	10/12/24 10:28	10/24/24 14:24	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	10/12/24 10:28	10/24/24 14:24	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	10/12/24 10:28	10/24/24 14:24	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/12/24 10:28	10/24/24 14:24	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/16/24 07:30	10/16/24 14:14	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		10/14/24 12:36		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	1.9	1		10/17/24 13:53		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3
Pace Project No.: 92757972

Sample: HAM-AP1-EB-01		Lab ID: 92757972010		Collected: 10/09/24 15:00		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/17/24 13:53		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/17/24 13:53		

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Sample: HAM-AP1-FB-01		Lab ID: 92757972011		Collected: 10/09/24 15:05		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU		Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN							
Chloride	ND	mg/L	1.0	0.34	1		10/26/24 12:27	16887-00-6	
Fluoride	ND	mg/L	0.050	0.0057	1		10/26/24 12:27	16984-48-8	
Sulfate	ND	mg/L	1.0	0.086	1		10/26/24 12:27	14808-79-8	
4500S2D Sulfide LL Water DU		Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN							
Sulfide	ND	mg/L	0.10	0.011	1		10/15/24 18:05	18496-25-8	
6010D ATL ICP		Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA							
Iron	0.032J	mg/L	0.040	0.025	1	10/12/24 13:49	10/13/24 21:05	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	10/12/24 13:49	10/13/24 21:05	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	10/12/24 13:49	10/13/24 21:05	7440-09-7	
Sodium	1.1	mg/L	1.0	0.58	1	10/12/24 13:49	10/13/24 21:05	7440-23-5	
Calcium	0.45J	mg/L	1.0	0.12	1	10/12/24 13:49	10/13/24 21:05	7440-70-2	
Magnesium	0.12	mg/L	0.050	0.012	1	10/12/24 13:49	10/13/24 21:05	7439-95-4	
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Antimony	ND	mg/L	0.0030	0.00054	1	10/12/24 10:28	10/24/24 14:29	7440-36-0	
Arsenic	0.00098J	mg/L	0.0050	0.00084	1	10/12/24 10:28	10/24/24 14:29	7440-38-2	
Barium	0.0023J	mg/L	0.0050	0.00047	1	10/12/24 10:28	10/24/24 14:29	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	10/12/24 10:28	10/24/24 14:29	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	10/12/24 10:28	10/24/24 14:29	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	10/12/24 10:28	10/24/24 14:29	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/12/24 10:28	10/24/24 14:29	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	10/12/24 10:28	10/24/24 14:29	7440-48-4	
Lead	0.00019J	mg/L	0.0010	0.00016	1	10/12/24 10:28	10/24/24 14:29	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	10/12/24 10:28	10/24/24 14:29	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	10/12/24 10:28	10/24/24 14:29	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	10/12/24 10:28	10/24/24 14:29	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/12/24 10:28	10/24/24 14:29	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA							
Mercury	ND	mg/L	0.00020	0.00013	1	10/16/24 07:30	10/16/24 14:17	7439-97-6	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		10/14/24 12:37		
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity, Total as CaCO ₃	5.0	mg/L	5.0	1.9	1		10/17/24 13:56		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3
Pace Project No.: 92757972

Sample: HAM-AP1-FB-01		Lab ID: 92757972011		Collected: 10/09/24 15:05		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO3)	5.0	mg/L	5.0	1.9	1		10/17/24 13:56		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/17/24 13:56		

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Sample: HAM-AP1-FD-01 Lab ID: 92757972012 Collected: 10/08/24 00:00 Received: 10/10/24 11:15 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions WW 28 Day DU Analytical Method: EPA 300.0 Pace Analytical Services - Duluth, MN									
Chloride	17.2	mg/L	1.0	0.34	1		10/26/24 13:12	16887-00-6	
Fluoride	0.32	mg/L	0.050	0.0057	1		10/26/24 13:12	16984-48-8	
Sulfate	247	mg/L	1.0	0.086	1		10/26/24 13:12	14808-79-8	
4500S2D Sulfide LL Water DU Analytical Method: SM 4500-S2 D-2011 Pace Analytical Services - Duluth, MN									
Sulfide	ND	mg/L	0.10	0.011	1		10/15/24 18:06	18496-25-8	H1
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.78	mg/L	0.040	0.025	1	10/12/24 13:49	10/13/24 21:09	7439-89-6	
Manganese	2.7	mg/L	0.040	0.011	1	10/12/24 13:49	10/13/24 21:09	7439-96-5	
Potassium	5.6	mg/L	0.50	0.15	1	10/12/24 13:49	10/13/24 21:09	7440-09-7	
Sodium	9.6	mg/L	1.0	0.58	1	10/12/24 13:49	10/13/24 21:09	7440-23-5	
Calcium	116	mg/L	1.0	0.12	1	10/12/24 13:49	10/13/24 21:09	7440-70-2	
Magnesium	14.1	mg/L	0.050	0.012	1	10/12/24 13:49	10/13/24 21:09	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	10/12/24 10:28	10/24/24 14:33	7440-36-0	
Arsenic	0.012	mg/L	0.0050	0.00084	1	10/12/24 10:28	10/24/24 14:33	7440-38-2	
Barium	0.049	mg/L	0.0050	0.00047	1	10/12/24 10:28	10/24/24 14:33	7440-39-3	
Beryllium	0.000094J	mg/L	0.00050	0.000094	1	10/12/24 10:28	10/24/24 14:33	7440-41-7	
Boron	0.59	mg/L	0.040	0.012	1	10/12/24 10:28	10/24/24 14:33	7440-42-8	
Cadmium	0.00028J	mg/L	0.00050	0.00010	1	10/12/24 10:28	10/24/24 14:33	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	10/12/24 10:28	10/24/24 14:33	7440-47-3	
Cobalt	0.015	mg/L	0.0050	0.00032	1	10/12/24 10:28	10/24/24 14:33	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	10/12/24 10:28	10/24/24 14:33	7439-92-1	
Lithium	0.037	mg/L	0.030	0.0016	1	10/12/24 10:28	10/24/24 14:33	7439-93-2	
Molybdenum	0.010	mg/L	0.010	0.00062	1	10/12/24 10:28	10/24/24 14:33	7439-98-7	
Selenium	0.0031J	mg/L	0.0050	0.00096	1	10/12/24 10:28	10/24/24 14:33	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	10/12/24 10:28	10/24/24 14:33	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	10/16/24 07:30	10/16/24 14:19	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	521	mg/L	25.0	25.0	1		10/14/24 12:34		
2320B Alkalinity Analytical Method: SM 2320B Pace Analytical Services - Minneapolis									
Alkalinity, Total as CaCO3	114	mg/L	5.0	1.9	1		10/17/24 12:37		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 3
Pace Project No.: 92757972

Sample: HAM-AP1-FD-01		Lab ID: 92757972012		Collected: 10/08/24 00:00		Received: 10/10/24 11:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
2320B Alkalinity		Analytical Method: SM 2320B Pace Analytical Services - Minneapolis							
Alkalinity,Bicarbonate (CaCO3)	114	mg/L	5.0	1.9	1		10/17/24 12:37		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	1.9	1		10/17/24 12:37		

REPORT OF LABORATORY ANALYSIS



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 3
Pace Project No.: 92757972

QC Batch:	976023	Analysis Method:	EPA 300.0
QC Batch Method:	EPA 300.0	Analysis Description:	300.0 IC Anions WW 28 Day DU
		Laboratory:	Pace Analytical Services - Duluth, MN
Associated Lab Samples:	92757972001, 92757972002, 92757972003, 92757972004, 92757972005, 92757972006, 92757972007, 92757972008, 92757972009, 92757972010, 92757972011, 92757972012		

METHOD BLANK: 5101385 Matrix: Water
Associated Lab Samples: 92757972001, 92757972002, 92757972003, 92757972004, 92757972005, 92757972006, 92757972007, 92757972008, 92757972009, 92757972010, 92757972011, 92757972012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.34	10/26/24 07:56	
Fluoride	mg/L	ND	0.050	0.0057	10/26/24 07:56	
Sulfate	mg/L	ND	1.0	0.086	10/26/24 07:56	

LABORATORY CONTROL SAMPLE: 5101386

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	100	99.9	100	90-110	
Fluoride	mg/L	5	5.2	104	90-110	
Sulfate	mg/L	100	99.3	99	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 5101387 5101388

Parameter	Units	92757972001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	18.6	100	100	120	120	101	102	90-110	1	20	
Fluoride	mg/L	0.30	5	5	5.6	5.6	106	106	90-110	0	20	
Sulfate	mg/L	238	100	100	331	332	93	94	90-110	0	20	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 5101389 5101390

Parameter	Units	92757972002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	18.1	100	100	121	122	102	104	90-110	1	20	
Fluoride	mg/L	0.23	5	5	5.6	5.7	107	109	90-110	2	20	
Sulfate	mg/L	242	100	100	337	338	94	96	90-110	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

QC Batch:	973697	Analysis Method:	SM 4500-S2 D-2011
QC Batch Method:	SM 4500-S2 D-2011	Analysis Description:	4500S2D Sulfide LL Water DU
		Laboratory:	Pace Analytical Services - Duluth, MN
Associated Lab Samples:	92757972001, 92757972002, 92757972003, 92757972004, 92757972005, 92757972006, 92757972007, 92757972008, 92757972009, 92757972010		

METHOD BLANK:	5088870	Matrix:	Water
Associated Lab Samples:	92757972001, 92757972002, 92757972003, 92757972004, 92757972005, 92757972006, 92757972007, 92757972008, 92757972009, 92757972010		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.011	10/15/24 17:59	

LABORATORY CONTROL SAMPLE: 5088871						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.2	0.18	93	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:					5088872	5088873							
Parameter	Units	10711326001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual	
Sulfide	mg/L	<0.011	0.2	0.2	0.20	0.20	99	102	90-110	3	10		

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:					5088874								5088875			
Parameter	Units	10711326002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual				
Sulfide	mg/L	<0.011	0.2	0.2	0.19	0.19	97	99	90-110	2	10					

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

QC Batch: 973699

Analysis Method: SM 4500-S2 D-2011

QC Batch Method: SM 4500-S2 D-2011

Analysis Description: 4500S2D Sulfide LL Water DU

Laboratory: Pace Analytical Services - Duluth, MN

Associated Lab Samples: 92757972011, 92757972012

METHOD BLANK: 5088877

Matrix: Water

Associated Lab Samples: 92757972011, 92757972012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.011	10/15/24 18:05	

LABORATORY CONTROL SAMPLE: 5088878

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.2	0.19	98	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 5088879 5088880

Parameter	Units	92757972011 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.2	0.2	0.20	0.21	103	105	90-110	1	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

QC Batch: 888265 Analysis Method: EPA 6010D
QC Batch Method: EPA 3010A Analysis Description: 6010D ATL
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92757972001, 92757972002, 92757972003, 92757972004, 92757972005, 92757972006

METHOD BLANK: 4574207 Matrix: Water
Associated Lab Samples: 92757972001, 92757972002, 92757972003, 92757972004, 92757972005, 92757972006

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	10/12/24 10:03	
Iron	mg/L	ND	0.040	0.025	10/12/24 10:03	
Magnesium	mg/L	ND	0.050	0.012	10/12/24 10:03	
Manganese	mg/L	ND	0.040	0.011	10/12/24 10:03	
Potassium	mg/L	ND	0.50	0.15	10/12/24 10:03	
Sodium	mg/L	ND	1.0	0.58	10/13/24 11:52	

LABORATORY CONTROL SAMPLE: 4574208

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	0.95J	95	80-120	
Iron	mg/L	1	0.94	94	80-120	
Magnesium	mg/L	1	0.99	99	80-120	
Manganese	mg/L	1	0.97	97	80-120	
Potassium	mg/L	1	0.92	92	80-120	
Sodium	mg/L	1	1.1	107	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4574209 4574210

Parameter	Units	92755893003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Calcium	mg/L	90300 ug/L	1	1	87.9	89.2	-238	-116	75-125	1	20	M1
Iron	mg/L	3640 ug/L	1	1	5.5	5.7	186	211	75-125	4	20	M1
Magnesium	mg/L	21400 ug/L	1	1	22.2	22.6	78	119	75-125	2	20	
Manganese	mg/L	2620 ug/L	1	1	3.5	3.6	90	102	75-125	3	20	
Potassium	mg/L	3010 ug/L	1	1	4.8	5.0	179	195	75-125	3	20	M1
Sodium	mg/L	131000 ug/L	1	1	129	132	-242	25	75-125	2	20	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

QC Batch: 888406

Analysis Method: EPA 6010D

QC Batch Method: EPA 3010A

Analysis Description: 6010D ATL

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92757972007, 92757972008, 92757972009, 92757972010, 92757972011, 92757972012

METHOD BLANK: 4575061

Matrix: Water

Associated Lab Samples: 92757972007, 92757972008, 92757972009, 92757972010, 92757972011, 92757972012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	10/15/24 20:47	
Iron	mg/L	ND	0.040	0.025	10/15/24 20:47	
Magnesium	mg/L	ND	0.050	0.012	10/15/24 20:47	
Manganese	mg/L	ND	0.040	0.011	10/15/24 20:47	
Potassium	mg/L	ND	0.50	0.15	10/15/24 20:47	
Sodium	mg/L	ND	1.0	0.58	10/15/24 20:47	

LABORATORY CONTROL SAMPLE: 4575062

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	0.95J	95	80-120	
Iron	mg/L	1	0.99	99	80-120	
Magnesium	mg/L	1	1.0	103	80-120	
Manganese	mg/L	1	1.0	101	80-120	
Potassium	mg/L	1	0.96	96	80-120	
Sodium	mg/L	1	0.94J	94	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4575063 4575064

Parameter	Units	92757972007 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Calcium	mg/L	114	1	1	117	116	376	195	75-125	2	20	M1
Iron	mg/L	6.6	1	1	7.7	7.7	116	108	75-125	1	20	
Magnesium	mg/L	16.2	1	1	17.6	17.4	143	117	75-125	2	20	M1
Manganese	mg/L	3.2	1	1	4.2	4.1	98	96	75-125	0	20	
Potassium	mg/L	5.7	1	1	6.6	6.5	91	86	75-125	1	20	
Sodium	mg/L	10.7	1	1	11.9	11.9	121	115	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 3
Pace Project No.: 92757972

QC Batch: 888402 Analysis Method: EPA 6020B
QC Batch Method: EPA 3005A Analysis Description: 6020 MET
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92757972001, 92757972002, 92757972003, 92757972004

METHOD BLANK: 4575045 Matrix: Water
Associated Lab Samples: 92757972001, 92757972002, 92757972003, 92757972004

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00054	10/14/24 18:48	
Arsenic	mg/L	0.0012J	0.0050	0.00084	10/14/24 18:48	
Barium	mg/L	ND	0.0050	0.00047	10/14/24 18:48	
Beryllium	mg/L	ND	0.00050	0.000094	10/14/24 18:48	
Boron	mg/L	ND	0.040	0.012	10/14/24 18:48	
Cadmium	mg/L	ND	0.00050	0.00010	10/14/24 18:48	
Chromium	mg/L	ND	0.0050	0.0019	10/15/24 18:43	
Cobalt	mg/L	ND	0.0050	0.00032	10/15/24 18:43	
Lead	mg/L	ND	0.0010	0.00016	10/14/24 18:48	
Lithium	mg/L	ND	0.030	0.0016	10/14/24 18:48	
Molybdenum	mg/L	ND	0.010	0.00062	10/14/24 18:48	
Selenium	mg/L	ND	0.0050	0.00096	10/14/24 18:48	
Thallium	mg/L	ND	0.0010	0.00038	10/15/24 18:43	

LABORATORY CONTROL SAMPLE: 4575046

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.099	99	80-120	
Arsenic	mg/L	0.1	0.098	98	80-120	
Barium	mg/L	0.1	0.096	96	80-120	
Beryllium	mg/L	0.1	0.096	96	80-120	
Boron	mg/L	1	0.92	92	80-120	
Cadmium	mg/L	0.1	0.098	98	80-120	
Chromium	mg/L	0.1	0.097	97	80-120	
Cobalt	mg/L	0.1	0.098	98	80-120	
Lead	mg/L	0.1	0.094	94	80-120	
Lithium	mg/L	0.1	0.096	96	80-120	
Molybdenum	mg/L	0.1	0.099	99	80-120	
Selenium	mg/L	0.1	0.095	95	80-120	
Thallium	mg/L	0.1	0.10	100	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4575047 4575048

Parameter	Units	9275772001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	ND	0.1	0.1	0.10	0.095	101	95	75-125	6	20	
Arsenic	mg/L	ND	0.1	0.1	0.098	0.097	96	95	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:			4575047		4575048							
Parameter	Units	92755772001	MS	MSD	MS	MSD	MS	MSD	% Rec	RPD	Max	Qual
		Result	Spike	Spike								
Barium	mg/L	22.3 ug/L	0.1	0.1	0.12	0.12	102	98	75-125	3	20	
Beryllium	mg/L	ND	0.1	0.1	0.10	0.096	99	96	75-125	3	20	
Boron	mg/L	ND	1	1	0.95	0.92	95	92	75-125	3	20	
Cadmium	mg/L	ND	0.1	0.1	0.097	0.096	97	96	75-125	1	20	
Chromium	mg/L	ND	0.1	0.1	0.10	0.10	98	98	75-125	1	20	
Cobalt	mg/L	ND	0.1	0.1	0.099	0.098	98	96	75-125	1	20	
Lead	mg/L	ND	0.1	0.1	0.095	0.092	95	91	75-125	4	20	
Lithium	mg/L	ND	0.1	0.1	0.099	0.095	99	95	75-125	4	20	
Molybdenum	mg/L	ND	0.1	0.1	0.10	0.096	102	94	75-125	8	20	
Selenium	mg/L	ND	0.1	0.1	0.095	0.095	95	95	75-125	0	20	
Thallium	mg/L	ND	0.1	0.1	0.095	0.095	95	95	75-125	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 3
Pace Project No.: 92757972

QC Batch: 888403 Analysis Method: EPA 6020B
QC Batch Method: EPA 3005A Analysis Description: 6020 MET
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92757972005, 92757972006, 92757972007, 92757972008, 92757972009, 92757972010, 92757972011, 92757972012

METHOD BLANK: 4575049 Matrix: Water
Associated Lab Samples: 92757972005, 92757972006, 92757972007, 92757972008, 92757972009, 92757972010, 92757972011, 92757972012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	0.00085J	0.0030	0.00054	10/24/24 12:45	
Arsenic	mg/L	ND	0.0050	0.00084	10/24/24 12:45	
Barium	mg/L	ND	0.0050	0.00047	10/24/24 12:45	
Beryllium	mg/L	ND	0.00050	0.000094	10/24/24 12:45	
Boron	mg/L	ND	0.040	0.012	10/24/24 12:45	
Cadmium	mg/L	ND	0.00050	0.00010	10/24/24 12:45	
Chromium	mg/L	ND	0.0050	0.0019	10/24/24 12:45	
Cobalt	mg/L	ND	0.0050	0.00032	10/24/24 12:45	
Lead	mg/L	ND	0.0010	0.00016	10/24/24 12:45	
Lithium	mg/L	ND	0.030	0.0016	10/24/24 12:45	
Molybdenum	mg/L	ND	0.010	0.00062	10/24/24 12:45	
Selenium	mg/L	ND	0.0050	0.00096	10/24/24 12:45	
Thallium	mg/L	ND	0.0010	0.00038	10/24/24 12:45	

LABORATORY CONTROL SAMPLE: 4575050

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.10	100	80-120	
Arsenic	mg/L	0.1	0.097	97	80-120	
Barium	mg/L	0.1	0.098	98	80-120	
Beryllium	mg/L	0.1	0.11	105	80-120	
Boron	mg/L	1	1.0	100	80-120	
Cadmium	mg/L	0.1	0.099	99	80-120	
Chromium	mg/L	0.1	0.098	98	80-120	
Cobalt	mg/L	0.1	0.096	96	80-120	
Lead	mg/L	0.1	0.096	96	80-120	
Lithium	mg/L	0.1	0.11	109	80-120	
Molybdenum	mg/L	0.1	0.098	98	80-120	
Selenium	mg/L	0.1	0.097	97	80-120	
Thallium	mg/L	0.1	0.094	94	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4575051 4575052

Parameter	Units	92757972005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	ND	0.1	0.1	0.097	0.10	96	100	75-125	4	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:					4575051	4575052							
Parameter	Units	92757972005	MS	MSD	MS	MSD	MS	MSD	% Rec	RPD	Max	Qual	
		Result	Spike Conc.	Spike Conc.									Result
Arsenic	mg/L	0.0014J	0.1	0.1	0.10	0.10	98	100	75-125	2	20		
Barium	mg/L	0.067	0.1	0.1	0.17	0.17	105	103	75-125	1	20		
Beryllium	mg/L	ND	0.1	0.1	0.10	0.10	100	100	75-125	0	20		
Boron	mg/L	1.5	1	1	2.4	2.4	97	92	75-125	2	20		
Cadmium	mg/L	0.00017J	0.1	0.1	0.097	0.097	96	96	75-125	0	20		
Chromium	mg/L	ND	0.1	0.1	0.10	0.10	101	100	75-125	0	20		
Cobalt	mg/L	0.015	0.1	0.1	0.11	0.11	99	96	75-125	3	20		
Lead	mg/L	ND	0.1	0.1	0.093	0.096	93	96	75-125	3	20		
Lithium	mg/L	0.0057J	0.1	0.1	0.11	0.10	99	99	75-125	1	20		
Molybdenum	mg/L	0.066	0.1	0.1	0.17	0.17	101	105	75-125	2	20		
Selenium	mg/L	ND	0.1	0.1	0.098	0.099	97	99	75-125	1	20		
Thallium	mg/L	ND	0.1	0.1	0.093	0.095	93	95	75-125	2	20		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 3
Pace Project No.: 92757972

QC Batch:	888937	Analysis Method:	EPA 7470A
QC Batch Method:	EPA 7470A	Analysis Description:	7470 Mercury
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92757972001, 92757972002, 92757972003, 92757972004, 92757972005, 92757972006, 92757972007, 92757972008, 92757972009, 92757972010, 92757972011, 92757972012		

METHOD BLANK:	4577183	Matrix:	Water
Associated Lab Samples:	92757972001, 92757972002, 92757972003, 92757972004, 92757972005, 92757972006, 92757972007, 92757972008, 92757972009, 92757972010, 92757972011, 92757972012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	10/16/24 12:33	

LABORATORY CONTROL SAMPLE:	4577184					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0024	94	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:	4577185			4577186								
Parameter	Units	92757972002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.0025	0.0025	0.0023	0.0024	93	95	75-125	2	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

QC Batch:	888616	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92757972001, 92757972002, 92757972003, 92757972004, 92757972005, 92757972006, 92757972007, 92757972008, 92757972009, 92757972010, 92757972011, 92757972012		

METHOD BLANK:	4575788	Matrix:	Water
Associated Lab Samples:	92757972001, 92757972002, 92757972003, 92757972004, 92757972005, 92757972006, 92757972007, 92757972008, 92757972009, 92757972010, 92757972011, 92757972012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	10/14/24 12:23	

LABORATORY CONTROL SAMPLE: 4575789						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	396	99	80-120	

SAMPLE DUPLICATE: 4575790						
Parameter	Units	92757767001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	220	217	1	10	

SAMPLE DUPLICATE: 4575791						
Parameter	Units	92757972009 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	509	508	0	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 3
Pace Project No.: 92757972

QC Batch: 974088 Analysis Method: SM 2320B
QC Batch Method: SM 2320B Analysis Description: 2320B Alkalinity
Laboratory: Pace Analytical Services - Minneapolis
Associated Lab Samples: 92757972001, 92757972002, 92757972003, 92757972004, 92757972005, 92757972006, 92757972007, 92757972008, 92757972009, 92757972010, 92757972011, 92757972012

METHOD BLANK: 5091266 Matrix: Water
Associated Lab Samples: 92757972001, 92757972002, 92757972003, 92757972004, 92757972005, 92757972006, 92757972007, 92757972008, 92757972009, 92757972010, 92757972011, 92757972012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	1.9	10/17/24 10:59	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	1.9	10/17/24 10:59	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	1.9	10/17/24 10:59	

LABORATORY CONTROL SAMPLE & LCSD: 5091267			5091268							
Parameter	Units	Spike Conc.	LCS Result	LCSD Result	LCS % Rec	LCSD % Rec	% Rec Limits	RPD	Max RPD	Qualifiers
Alkalinity, Total as CaCO3	mg/L	40	43.3	43.7	108	109	90-110	1	20	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 5091269					5091270							
Parameter	Units	10711077003	MS	MSD	MS	MSD	MS	MSD	% Rec	Max	Qual	
		Result	Spike Conc.	Spike Conc.								Result
Alkalinity, Total as CaCO3	mg/L	173	40	40	223	218	123	112	80-120	2	20	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 5091271					5091272							
Parameter	Units	92757972002	MS	MSD	MS	MSD	MS	MSD	% Rec	Max		
		Result	Spike Conc.	Spike Conc.								
Alkalinity, Total as CaCO3	mg/L	114	40	40	155	155	103	104	80-120	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1_Week 3
Pace Project No.: 92757972

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

B Analyte was detected in the associated method blank.
H1 Analysis conducted outside the recognized method holding time.
M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1_Week 3
Pace Project No.: 92757972

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92757972001	HAM-PT-07	EPA 300.0	976023		
92757972002	HAM-PT-08	EPA 300.0	976023		
92757972003	HAM-PT-09	EPA 300.0	976023		
92757972004	HAM-PT-10	EPA 300.0	976023		
92757972005	HAM-PT-11	EPA 300.0	976023		
92757972006	HAM-PT-12	EPA 300.0	976023		
92757972007	HAM-PT-13	EPA 300.0	976023		
92757972008	HAM-PT-14	EPA 300.0	976023		
92757972009	HAM-PT-15	EPA 300.0	976023		
92757972010	HAM-AP1-EB-01	EPA 300.0	976023		
92757972011	HAM-AP1-FB-01	EPA 300.0	976023		
92757972012	HAM-AP1-FD-01	EPA 300.0	976023		
92757972001	HAM-PT-07	SM 4500-S2 D-2011	973697		
92757972002	HAM-PT-08	SM 4500-S2 D-2011	973697		
92757972003	HAM-PT-09	SM 4500-S2 D-2011	973697		
92757972004	HAM-PT-10	SM 4500-S2 D-2011	973697		
92757972005	HAM-PT-11	SM 4500-S2 D-2011	973697		
92757972006	HAM-PT-12	SM 4500-S2 D-2011	973697		
92757972007	HAM-PT-13	SM 4500-S2 D-2011	973697		
92757972008	HAM-PT-14	SM 4500-S2 D-2011	973697		
92757972009	HAM-PT-15	SM 4500-S2 D-2011	973697		
92757972010	HAM-AP1-EB-01	SM 4500-S2 D-2011	973697		
92757972011	HAM-AP1-FB-01	SM 4500-S2 D-2011	973699		
92757972012	HAM-AP1-FD-01	SM 4500-S2 D-2011	973699		
92757972001	HAM-PT-07	EPA 3010A	888265	EPA 6010D	888393
92757972002	HAM-PT-08	EPA 3010A	888265	EPA 6010D	888393
92757972003	HAM-PT-09	EPA 3010A	888265	EPA 6010D	888393
92757972004	HAM-PT-10	EPA 3010A	888265	EPA 6010D	888393
92757972005	HAM-PT-11	EPA 3010A	888265	EPA 6010D	888393
92757972006	HAM-PT-12	EPA 3010A	888265	EPA 6010D	888393
92757972007	HAM-PT-13	EPA 3010A	888406	EPA 6010D	888486
92757972008	HAM-PT-14	EPA 3010A	888406	EPA 6010D	888486
92757972009	HAM-PT-15	EPA 3010A	888406	EPA 6010D	888486
92757972010	HAM-AP1-EB-01	EPA 3010A	888406	EPA 6010D	888486
92757972011	HAM-AP1-FB-01	EPA 3010A	888406	EPA 6010D	888486
92757972012	HAM-AP1-FD-01	EPA 3010A	888406	EPA 6010D	888486
92757972001	HAM-PT-07	EPA 3005A	888402	EPA 6020B	888488
92757972002	HAM-PT-08	EPA 3005A	888402	EPA 6020B	888488
92757972003	HAM-PT-09	EPA 3005A	888402	EPA 6020B	888488
92757972004	HAM-PT-10	EPA 3005A	888402	EPA 6020B	888488
92757972005	HAM-PT-11	EPA 3005A	888403	EPA 6020B	888489
92757972006	HAM-PT-12	EPA 3005A	888403	EPA 6020B	888489
92757972007	HAM-PT-13	EPA 3005A	888403	EPA 6020B	888489
92757972008	HAM-PT-14	EPA 3005A	888403	EPA 6020B	888489
92757972009	HAM-PT-15	EPA 3005A	888403	EPA 6020B	888489
92757972010	HAM-AP1-EB-01	EPA 3005A	888403	EPA 6020B	888489

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1_Week 3

Pace Project No.: 92757972

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92757972011	HAM-AP1-FB-01	EPA 3005A	888403	EPA 6020B	888489
92757972012	HAM-AP1-FD-01	EPA 3005A	888403	EPA 6020B	888489
92757972001	HAM-PT-07	EPA 7470A	888937	EPA 7470A	889140
92757972002	HAM-PT-08	EPA 7470A	888937	EPA 7470A	889140
92757972003	HAM-PT-09	EPA 7470A	888937	EPA 7470A	889140
92757972004	HAM-PT-10	EPA 7470A	888937	EPA 7470A	889140
92757972005	HAM-PT-11	EPA 7470A	888937	EPA 7470A	889140
92757972006	HAM-PT-12	EPA 7470A	888937	EPA 7470A	889140
92757972007	HAM-PT-13	EPA 7470A	888937	EPA 7470A	889140
92757972008	HAM-PT-14	EPA 7470A	888937	EPA 7470A	889140
92757972009	HAM-PT-15	EPA 7470A	888937	EPA 7470A	889140
92757972010	HAM-AP1-EB-01	EPA 7470A	888937	EPA 7470A	889140
92757972011	HAM-AP1-FB-01	EPA 7470A	888937	EPA 7470A	889140
92757972012	HAM-AP1-FD-01	EPA 7470A	888937	EPA 7470A	889140
92757972001	HAM-PT-07	SM 2540C-2015	888616		
92757972002	HAM-PT-08	SM 2540C-2015	888616		
92757972003	HAM-PT-09	SM 2540C-2015	888616		
92757972004	HAM-PT-10	SM 2540C-2015	888616		
92757972005	HAM-PT-11	SM 2540C-2015	888616		
92757972006	HAM-PT-12	SM 2540C-2015	888616		
92757972007	HAM-PT-13	SM 2540C-2015	888616		
92757972008	HAM-PT-14	SM 2540C-2015	888616		
92757972009	HAM-PT-15	SM 2540C-2015	888616		
92757972010	HAM-AP1-EB-01	SM 2540C-2015	888616		
92757972011	HAM-AP1-FB-01	SM 2540C-2015	888616		
92757972012	HAM-AP1-FD-01	SM 2540C-2015	888616		
92757972001	HAM-PT-07	SM 2320B	974088		
92757972002	HAM-PT-08	SM 2320B	974088		
92757972003	HAM-PT-09	SM 2320B	974088		
92757972004	HAM-PT-10	SM 2320B	974088		
92757972005	HAM-PT-11	SM 2320B	974088		
92757972006	HAM-PT-12	SM 2320B	974088		
92757972007	HAM-PT-13	SM 2320B	974088		
92757972008	HAM-PT-14	SM 2320B	974088		
92757972009	HAM-PT-15	SM 2320B	974088		
92757972010	HAM-AP1-EB-01	SM 2320B	974088		
92757972011	HAM-AP1-FB-01	SM 2320B	974088		
92757972012	HAM-AP1-FD-01	SM 2320B	974088		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Laboratory receiving samples:
Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐

Sample Condition Upon Receipt

Client Name: Go Pure Project #: **WO#: 92757972**

Courier: ☐ Commercial ☐ Fed Ex ☐ UPS ☐ USPS ☐ Client ☐ Other: ☐

Custody Seal Present? ☒ Yes ☐ No Seals Intact? ☒ Yes ☐ No ☐ N/A

Packing Material: ☒ Bubble Wrap ☐ Bubble Bags ☐ None ☐ Other

Thermometer: ☒ IR Gun ID: 730 Type of Ice: ☒ Wet ☐ Blue ☐ None

Cooler Temp: 3.3 Correction Factor: 0.0 Temp should be above freezing to 6°C
☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C): 3.3

USDA Regulated Soil (☐ N/A, water sample)
Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ No

Did samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

Date/Initials Person Examining Contents: 10/24/24 JLA

Biological Tissue Frozen? ☐ Yes ☐ No ☒ N/A

Chain of Custody Present?	☒ Yes ☐ No	☐ N/A	1.	
Samples Arrived within Hold Time?	☒ Yes ☐ No	☐ N/A	2.	
Short Hold Time Analysis (<72 hr.)?	☒ Yes ☐ No	☐ N/A	3.	
Rush Turn Around Time Requested?	☐ Yes ☒ No	☐ N/A	4.	
Sufficient Volume?	☐ Yes ☐ No	☐ N/A	5.	
Correct Containers Used?	☒ Yes ☐ No	☐ N/A	6.	
-Pace Containers Used?	☐ Yes ☐ No	☐ N/A	7.	
Containers Intact?	☐ Yes ☐ No	☐ N/A	8.	
Dissolved analysis: Samples Field Filtered?	☐ Yes ☐ No	☒ N/A		
Sample Labels Match COC?	<u>10/11/24</u> ☒ Yes ☐ No	☐ N/A	9.	Sample 7 & Sample 14 do not have same ID name but do have same time & date
-Includes Date/Time/ID/Analysis Matrix:				
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No	☐ N/A	10.	
Trip Blank Present?	☐ Yes ☐ No	☒ N/A	11.	
Trip Blank Custody Seals Present?	☐ Yes ☐ No	☐ N/A		

Field Data Required? ☐ Yes ☐ No

COMMENTS/SAMPLE DISCREPANCY

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted: _____ Date/Time: _____

Project Manager SCURF Review: _____ Date: _____

Project Manager SRF Review: _____ Date: _____



DC# Title: ENV-FRM-HUN1-0083 v05 Sample Condition Upon Receipt

Effective Date: 05/24/2024

WO#: 92757972

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

PM: BV Due Date: 10/24/24

CLIENT: 92- GP-HAM

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐

Client

Profile/EZ (Circle one)

Notes

CC	Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic 2N Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGFLU-Wide-mouthed Glass jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG3S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG94-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2SO3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit)-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)	BP3R-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	VS6U-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)	
1		/	2			/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/
2		/	2			/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/
3		/	2			/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/
4		/	2			/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/
5		/	2			/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/
6		/	2			/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/
7		/	2			/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/
8		/	2			/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/
9		/	2			/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/
10		/	2			/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/
11		/	2			/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/
12		/	2			/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers.



October 30, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1_Week 4
Pace Project No.: 92759101

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on October 17, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Peachtree Corners, GA

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Jamie Newsome, Geosyntec Consultants
Zain Webb, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1_Week 4

Pace Project No.: 92759101

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1_Week 4

Pace Project No.: 92759101

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92759101001	HAM-PT-07	Water	10/15/24 14:22	10/17/24 11:22
92759101002	HAM-PT-08	Water	10/15/24 14:20	10/17/24 11:22
92759101003	HAM-PT-09	Water	10/16/24 12:27	10/17/24 11:22
92759101004	HAM-PT-10	Water	10/16/24 10:40	10/17/24 11:22
92759101005	HAM-PT-11	Water	10/16/24 10:40	10/17/24 11:22
92759101006	HAM-PT-12	Water	10/16/24 14:20	10/17/24 11:22
92759101007	HAM-PT-13	Water	10/15/24 13:08	10/17/24 11:22
92759101008	HAM-PT-14	Water	10/15/24 11:25	10/17/24 11:22
92759101009	HAM-PT-15	Water	10/15/24 15:20	10/17/24 11:22
92759101010	HAM-AP1-EB-01	Water	10/16/24 14:05	10/17/24 11:22
92759101011	HAM-AP1-FB-01	Water	10/16/24 14:00	10/17/24 11:22
92759101012	HAM-AP1-FD-01	Water	10/16/24 00:00	10/17/24 11:22

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1_Week 4

Pace Project No.: 92759101

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92759101001	HAM-PT-07	EPA 6020B	CW1	3
92759101002	HAM-PT-08	EPA 6020B	CW1	3
92759101003	HAM-PT-09	EPA 6020B	CW1	3
92759101004	HAM-PT-10	EPA 6020B	CW1	3
92759101005	HAM-PT-11	EPA 6020B	CW1	3
92759101006	HAM-PT-12	EPA 6020B	CW1	3
92759101007	HAM-PT-13	EPA 6020B	CW1	3
92759101008	HAM-PT-14	EPA 6020B	CW1	3
92759101009	HAM-PT-15	EPA 6020B	CW1	3
92759101010	HAM-AP1-EB-01	EPA 6020B	CW1	4
92759101011	HAM-AP1-FB-01	EPA 6020B	CW1	4
92759101012	HAM-AP1-FD-01	EPA 6020B	CW1	4

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1_Week 4
Pace Project No.: 92759101

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92759101001	HAM-PT-07					
EPA 6020B	Arsenic	0.044	mg/L	0.0050	10/25/24 18:52	
EPA 6020B	Boron	0.56	mg/L	0.040	10/25/24 18:52	
EPA 6020B	Iron	4.3	mg/L	0.040	10/25/24 18:52	
92759101002	HAM-PT-08					
EPA 6020B	Arsenic	0.052	mg/L	0.0050	10/25/24 19:07	
EPA 6020B	Boron	0.59	mg/L	0.040	10/25/24 19:07	
EPA 6020B	Iron	2.2	mg/L	0.040	10/25/24 19:07	
92759101003	HAM-PT-09					
EPA 6020B	Boron	1.3	mg/L	0.040	10/25/24 19:11	
EPA 6020B	Iron	0.34	mg/L	0.040	10/25/24 19:11	
EPA 6020B	Molybdenum	0.18	mg/L	0.010	10/25/24 19:11	
92759101004	HAM-PT-10					
EPA 6020B	Boron	1.5	mg/L	0.040	10/25/24 19:14	
EPA 6020B	Iron	0.51	mg/L	0.040	10/25/24 19:14	
EPA 6020B	Molybdenum	0.16	mg/L	0.010	10/25/24 19:14	
92759101005	HAM-PT-11					
EPA 6020B	Boron	1.3	mg/L	0.040	10/25/24 19:18	
EPA 6020B	Iron	0.82	mg/L	0.040	10/25/24 19:18	
EPA 6020B	Molybdenum	0.062	mg/L	0.010	10/25/24 19:18	
92759101006	HAM-PT-12					
EPA 6020B	Boron	1.2	mg/L	0.040	10/25/24 19:29	
EPA 6020B	Iron	0.48	mg/L	0.040	10/25/24 19:29	
EPA 6020B	Molybdenum	0.16	mg/L	0.010	10/25/24 19:29	
92759101007	HAM-PT-13					
EPA 6020B	Arsenic	0.064	mg/L	0.0050	10/25/24 19:33	
EPA 6020B	Boron	0.54	mg/L	0.040	10/25/24 19:33	
EPA 6020B	Iron	7.2	mg/L	0.040	10/25/24 19:33	
92759101008	HAM-PT-14					
EPA 6020B	Arsenic	0.20	mg/L	0.0050	10/25/24 19:37	
EPA 6020B	Boron	0.59	mg/L	0.040	10/25/24 19:37	
EPA 6020B	Iron	14.4	mg/L	0.40	10/28/24 19:18	
92759101009	HAM-PT-15					
EPA 6020B	Arsenic	0.022	mg/L	0.0050	10/25/24 19:40	
EPA 6020B	Boron	0.62	mg/L	0.040	10/25/24 19:40	
EPA 6020B	Iron	1.2	mg/L	0.040	10/25/24 19:40	
92759101010	HAM-AP1-EB-01					
EPA 6020B	Iron	0.0089J	mg/L	0.040	10/25/24 19:48	
92759101012	HAM-AP1-FD-01					
EPA 6020B	Boron	1.3	mg/L	0.040	10/25/24 19:55	
EPA 6020B	Iron	0.78	mg/L	0.040	10/25/24 19:55	
EPA 6020B	Molybdenum	0.063	mg/L	0.010	10/25/24 19:55	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 4
Pace Project No.: 92759101

Sample: HAM-PT-07		Lab ID: 92759101001		Collected: 10/15/24 14:22		Received: 10/17/24 11:22		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Arsenic	0.044	mg/L	0.0050	0.00084	1	10/23/24 17:06	10/25/24 18:52	7440-38-2	
Boron	0.56	mg/L	0.040	0.012	1	10/23/24 17:06	10/25/24 18:52	7440-42-8	
Iron	4.3	mg/L	0.040	0.0075	1	10/23/24 17:06	10/25/24 18:52	7439-89-6	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 4
Pace Project No.: 92759101

Sample: HAM-PT-08		Lab ID: 92759101002		Collected: 10/15/24 14:20		Received: 10/17/24 11:22		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Arsenic	0.052	mg/L	0.0050	0.00084	1	10/23/24 17:06	10/25/24 19:07	7440-38-2	
Boron	0.59	mg/L	0.040	0.012	1	10/23/24 17:06	10/25/24 19:07	7440-42-8	
Iron	2.2	mg/L	0.040	0.0075	1	10/23/24 17:06	10/25/24 19:07	7439-89-6	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 4

Pace Project No.: 92759101

Sample: HAM-PT-09		Lab ID: 92759101003		Collected: 10/16/24 12:27		Received: 10/17/24 11:22		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.3	mg/L	0.040	0.012	1	10/23/24 17:06	10/25/24 19:11	7440-42-8	
Iron	0.34	mg/L	0.040	0.0075	1	10/23/24 17:06	10/25/24 19:11	7439-89-6	
Molybdenum	0.18	mg/L	0.010	0.00062	1	10/23/24 17:06	10/25/24 19:11	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 4

Pace Project No.: 92759101

Sample: HAM-PT-10		Lab ID: 92759101004		Collected: 10/16/24 10:40		Received: 10/17/24 11:22		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.5	mg/L	0.040	0.012	1	10/23/24 17:06	10/25/24 19:14	7440-42-8	
Iron	0.51	mg/L	0.040	0.0075	1	10/23/24 17:06	10/25/24 19:14	7439-89-6	
Molybdenum	0.16	mg/L	0.010	0.00062	1	10/23/24 17:06	10/25/24 19:14	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 4

Pace Project No.: 92759101

Sample: HAM-PT-11		Lab ID: 92759101005		Collected: 10/16/24 10:40		Received: 10/17/24 11:22		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.3	mg/L	0.040	0.012	1	10/23/24 17:06	10/25/24 19:18	7440-42-8	
Iron	0.82	mg/L	0.040	0.0075	1	10/23/24 17:06	10/25/24 19:18	7439-89-6	
Molybdenum	0.062	mg/L	0.010	0.00062	1	10/23/24 17:06	10/25/24 19:18	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 4

Pace Project No.: 92759101

Sample: HAM-PT-12		Lab ID: 92759101006		Collected: 10/16/24 14:20		Received: 10/17/24 11:22		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Boron	1.2	mg/L	0.040	0.012	1	10/23/24 17:06	10/25/24 19:29	7440-42-8	
Iron	0.48	mg/L	0.040	0.0075	1	10/23/24 17:06	10/25/24 19:29	7439-89-6	
Molybdenum	0.16	mg/L	0.010	0.00062	1	10/23/24 17:06	10/25/24 19:29	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 4

Pace Project No.: 92759101

Sample: HAM-PT-13		Lab ID: 92759101007		Collected: 10/15/24 13:08		Received: 10/17/24 11:22		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.064	mg/L	0.0050	0.00084	1	10/23/24 17:06	10/25/24 19:33	7440-38-2	
Boron	0.54	mg/L	0.040	0.012	1	10/23/24 17:06	10/25/24 19:33	7440-42-8	
Iron	7.2	mg/L	0.040	0.0075	1	10/23/24 17:06	10/25/24 19:33	7439-89-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 4

Pace Project No.: 92759101

Sample: HAM-PT-14		Lab ID: 92759101008		Collected: 10/15/24 11:25		Received: 10/17/24 11:22		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Arsenic	0.20	mg/L	0.0050	0.00084	1	10/23/24 17:06	10/25/24 19:37	7440-38-2	
Boron	0.59	mg/L	0.040	0.012	1	10/23/24 17:06	10/25/24 19:37	7440-42-8	
Iron	14.4	mg/L	0.40	0.075	10	10/23/24 17:06	10/28/24 19:18	7439-89-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 4

Pace Project No.: 92759101

Sample: HAM-PT-15		Lab ID: 92759101009		Collected: 10/15/24 15:20		Received: 10/17/24 11:22		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	0.022	mg/L	0.0050	0.00084	1	10/23/24 17:06	10/25/24 19:40	7440-38-2	
Boron	0.62	mg/L	0.040	0.012	1	10/23/24 17:06	10/25/24 19:40	7440-42-8	
Iron	1.2	mg/L	0.040	0.0075	1	10/23/24 17:06	10/25/24 19:40	7439-89-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 4
Pace Project No.: 92759101

Sample: HAM-AP1-EB-01		Lab ID: 92759101010		Collected: 10/16/24 14:05		Received: 10/17/24 11:22		Matrix: Water	
Parameters	Results	Units	Report			Prepared	Analyzed	CAS No.	Qual
			Limit	MDL	DF				
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Arsenic	ND	mg/L	0.0050	0.00084	1	10/23/24 17:06	10/25/24 19:48	7440-38-2	
Boron	ND	mg/L	0.040	0.012	1	10/23/24 17:06	10/25/24 19:48	7440-42-8	
Iron	0.0089J	mg/L	0.040	0.0075	1	10/23/24 17:06	10/25/24 19:48	7439-89-6	
Molybdenum	ND	mg/L	0.010	0.00062	1	10/23/24 17:06	10/25/24 19:48	7439-98-7	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 4
Pace Project No.: 92759101

Sample: HAM-AP1-FB-01		Lab ID: 92759101011		Collected: 10/16/24 14:00		Received: 10/17/24 11:22		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Arsenic	ND	mg/L	0.0050	0.00084	1	10/23/24 17:06	10/25/24 19:51	7440-38-2	
Boron	ND	mg/L	0.040	0.012	1	10/23/24 17:06	10/25/24 19:51	7440-42-8	
Iron	ND	mg/L	0.040	0.0075	1	10/23/24 17:06	10/25/24 19:51	7439-89-6	
Molybdenum	ND	mg/L	0.010	0.00062	1	10/23/24 17:06	10/25/24 19:51	7439-98-7	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1_Week 4

Pace Project No.: 92759101

Sample: HAM-AP1-FD-01		Lab ID: 92759101012		Collected: 10/16/24 00:00		Received: 10/17/24 11:22		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Arsenic	ND	mg/L	0.0050	0.00084	1	10/23/24 17:06	10/25/24 19:55	7440-38-2	
Boron	1.3	mg/L	0.040	0.012	1	10/23/24 17:06	10/25/24 19:55	7440-42-8	
Iron	0.78	mg/L	0.040	0.0075	1	10/23/24 17:06	10/25/24 19:55	7439-89-6	
Molybdenum	0.063	mg/L	0.010	0.00062	1	10/23/24 17:06	10/25/24 19:55	7439-98-7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1_Week 4
Pace Project No.: 92759101

QC Batch:	890896	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92759101001, 92759101002, 92759101003, 92759101004, 92759101005, 92759101006, 92759101007, 92759101008, 92759101009, 92759101010, 92759101011, 92759101012		

METHOD BLANK:	4586647	Matrix:	Water
Associated Lab Samples:	92759101001, 92759101002, 92759101003, 92759101004, 92759101005, 92759101006, 92759101007, 92759101008, 92759101009, 92759101010, 92759101011, 92759101012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Arsenic	mg/L	ND	0.0050	0.00084	10/25/24 18:45	
Boron	mg/L	ND	0.040	0.012	10/25/24 18:45	
Iron	mg/L	ND	0.040	0.0075	10/25/24 18:45	
Molybdenum	mg/L	ND	0.010	0.00062	10/25/24 18:45	

LABORATORY CONTROL SAMPLE:		4586648				
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Arsenic	mg/L	0.1	0.094	94	80-120	
Boron	mg/L	1	0.93	93	80-120	
Iron	mg/L	1	1.0	100	80-120	
Molybdenum	mg/L	0.1	0.096	96	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:		4586649		4586650								
Parameter	Units	92759101001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Arsenic	mg/L	0.044	0.1	0.1	0.14	0.14	101	100	75-125	0	20	
Boron	mg/L	0.56	1	1	1.5	1.4	91	89	75-125	1	20	
Iron	mg/L	4.3	1	1	5.4	5.5	103	113	75-125	2	20	
Molybdenum	mg/L	0.0055J	0.1	0.1	0.10	0.10	99	99	75-125	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1_Week 4
Pace Project No.: 92759101

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above adjusted reporting limit.

TNTC - Too Numerous To Count

J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

MDL - Adjusted Method Detection Limit.

PQL - Practical Quantitation Limit.

RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected.

Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.

A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1_Week 4

Pace Project No.: 92759101

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92759101001	HAM-PT-07	EPA 3005A	890896	EPA 6020B	890981
92759101002	HAM-PT-08	EPA 3005A	890896	EPA 6020B	890981
92759101003	HAM-PT-09	EPA 3005A	890896	EPA 6020B	890981
92759101004	HAM-PT-10	EPA 3005A	890896	EPA 6020B	890981
92759101005	HAM-PT-11	EPA 3005A	890896	EPA 6020B	890981
92759101006	HAM-PT-12	EPA 3005A	890896	EPA 6020B	890981
92759101007	HAM-PT-13	EPA 3005A	890896	EPA 6020B	890981
92759101008	HAM-PT-14	EPA 3005A	890896	EPA 6020B	890981
92759101009	HAM-PT-15	EPA 3005A	890896	EPA 6020B	890981
92759101010	HAM-AP1-EB-01	EPA 3005A	890896	EPA 6020B	890981
92759101011	HAM-AP1-FB-01	EPA 3005A	890896	EPA 6020B	890981
92759101012	HAM-AP1-FD-01	EPA 3005A	890896	EPA 6020B	890981

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CHAIN-OF-CUSTODY / Analytical Request Document

The Chain of Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

WO# : 92759101



92759101

Section A Required Client Information:		Section B Required Project Information:		Section C Invoice Information:	
Company:	GA Power	Report To:	SCS Contacts	Attention:	Southern Co.
Address:	Atlanta, GA	Copy To:	Geosyntec Contacts	Company Name:	
				Address:	
Email To:	SCS Contacts	Purchase Order No.:	GPC82474-0001	Pace Custodian Reference:	
Phone:		Project Name:	Hammond AP-1_Week 4	Pace Project Manager:	Bornie Vang
Requested Due Date/TAT:	10 Day	Project Number:		Pace Profile #:	15483

REGULATORY AGENCY		
☐ NPDES	☐ GROUND WATER	☐ DRINKING WATER
☐ UST	☐ RCRA	☒ OTHER CCR
Site Location	STATE:	GA

ITEM #	Section D Required Client Information	Valid Matrix Codes MATRIX CODE DW WT WW P SL OL WP AR OT TS	SAMPLE TYPE (G=GRAB C=COMP)	COLLECTED		SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives										Analysis Test	Y/N	Total 601/6022-B, As, Mo, Fe	Total 601/6022-B, As, Fe	Total 601/6022-B, Mo, Fe	Residual Chlorine (Y/N)	Pace Project No./ Lab I.D.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
				COMPOSITE	COMPOSITE			DATE	TIME	DATE	TIME	Unpreserved	H2SO4	HNO3	HCl	NaOH	Na2O3								Methanol	Other																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
1	SAMPLE ID (A-Z, 0-9 / -) Sample IDs MUST BE UNIQUE	HAM-PT-07	WG	G	10/15/2024	1422																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														

ADDITIONAL COMMENTS		RELINQUISHED BY / AFFILIATION		DATE		TIME		ACCEPTED BY / AFFILIATION		DATE		TIME		SAMPLE CONDITIONS	
Task Code: HAM-COR-CA-20241015		Jannie Newsome / Geo		10/17/24		1122		Ryan Williams / Pace		10/17/24		1122			
		Ryan Williams / Pace		10/17/24		1210		WOW		10/17/24		1210			

SAMPLER NAME AND SIGNATURE		PRINT Name of SAMPLER: Jannie Newsome, Amanda Tomlinson / Geosyntec Consultants, Inc.		DATE Signed (MM/DD/YYYY): 10/17/2024	
		SIGNATURE OF SAMPLER: Jannie Newsome			

*Important Note: By signing this form you are accepting Pace's NET 30 day payment terms and agreeing to file changes of 1.5% per month for all invoices not paid within 30 days.



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

Project #:

WO#: 92759101

PM: BV

Due Date: 10/31/24

CLIENT: 92- GP-HAM

Courier:

☐ Commercial☐ Fed Ex☒ Pace☐ UPS☐ USPS☐ Other:☐ Client

Custody Seal Present?

☒ Yes☐ No

Seals Intact?

☒ Yes☐ No☐ N/A

Date/Initials Person Examining Contents:

10/17/24

Packing Material:

☒ Bubble Wrap☐ Bubble Bags☐ None☐ Other

Thermometer:

☐ IR Gun ID:

214

Type of Ice:

☒ Wet☐ Blue☐ None

Biological Tissue Frozen?

☐ Yes☐ No☒ N/A

Cooler Temp:

5.4

Correction Factor:

Add/Subtract (°C)

0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

5.4

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

				Comments/Discrepancy:
Chain of Custody Present?	☒ Yes	☐ No	☐ N/A	1.
Samples Arrived within Hold Time?	☒ Yes	☐ No	☐ N/A	2.
Short Hold Time Analysis (<72 hr.)?	☐ Yes	☒ No	☐ N/A	3.
Rush Turn Around Time Requested?	☐ Yes	☒ No	☐ N/A	4.
Sufficient Volume?	☒ Yes	☐ No	☐ N/A	5.
Correct Containers Used?	☒ Yes	☐ No	☐ N/A	6.
-Pace Containers Used?	☒ Yes	☐ No	☐ N/A	
Containers Intact?	☒ Yes	☐ No	☐ N/A	7.
Dissolved analysis: Samples Field Filtered?	☐ Yes	☐ No	☒ N/A	8.
Sample Labels Match COC?	☒ Yes	☐ No	☐ N/A	9.
-Includes Date/Time/ID/Analysis Matrix: WG				
Headspace in VOA Vials (>5-6mm)?	☐ Yes	☐ No	☒ N/A	10.
Trip Blank Present?	☐ Yes	☐ No	☒ N/A	11.
Trip Blank Custody Seals Present?	☐ Yes	☐ No	☒ N/A	

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC# Title: ENV-FRM-HUN1-0083 v05 Sample Condition Upon Receipt

Effective Date: 05/24/2024

WO#: 92759101

Project #

PM: BV

Due Date: 10/31/24

CLIENT: 92- GP-HAM

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Client GA Power Profile/EZ (Circle one) 16483 Notes

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)		BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic 2N Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGFU-Wide-mouthed Glass Jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG9H-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit)-VPH/Gas kit (N/A)	SPST-125 mL Sterile Plastic (N/A – lab)	SP2T-250 mL Sterile Plastic (N/A – lab)		BP3K-250 mL Plastic (NH4)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	V5GU-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)	
CC																														
1																														
2																														
3																														
4																														
5																														
6																														
7																														
8																														
9																														
10																														
11																														
12																														

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers.



January 24, 2025

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1
Pace Project No.: 92762188

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on November 06, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Peachtree Corners, GA

Revision 1: Collected date for sample ID HAM-AP1-FD-01 was updated to 11/4/24, per client request.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Jamie Newsome, Geosyntec Consultants
Zain Webb, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1

Pace Project No.: 92762188

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1

Pace Project No.: 92762188

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92762188001	HAM-PT-07	Water	11/04/24 12:34	11/06/24 14:15
92762188002	HAM-PT-08	Water	11/04/24 12:14	11/06/24 14:15
92762188003	HAM-PT-09	Water	11/05/24 11:54	11/06/24 14:15
92762188004	HAM-PT-10	Water	11/05/24 09:29	11/06/24 14:15
92762188005	HAM-PT-11	Water	11/05/24 09:25	11/06/24 14:15
92762188006	HAM-PT-12	Water	11/05/24 11:44	11/06/24 14:15
92762188007	HAM-PT-13	Water	11/04/24 11:05	11/06/24 14:15
92762188008	HAM-PT-14	Water	11/04/24 14:50	11/06/24 14:15
92762188009	HAM-PT-15	Water	11/04/24 14:01	11/06/24 14:15
92762188010	HAM-AP1-EB-01	Water	11/05/24 12:36	11/06/24 14:15
92762188011	HAM-AP1-FB-01	Water	11/05/24 12:32	11/06/24 14:15
92762188012	HAM-AP1-FD-01	Water	11/04/24 00:00	11/06/24 14:15

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92762188

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92762188001	HAM-PT-07	EPA 6010D	DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92762188002	HAM-PT-08	EPA 6010D	DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92762188003	HAM-PT-09	EPA 6010D	DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92762188004	HAM-PT-10	EPA 6010D	DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92762188005	HAM-PT-11	EPA 6010D	DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92762188006	HAM-PT-12	EPA 6010D	DRB	6
		EPA 6020B	CW1	13

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92762188

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92762188007	HAM-PT-13	EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
92762188008	HAM-PT-14	SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	DRB	6
92762188009	HAM-PT-15	EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
92762188010	HAM-AP1-EB-01	SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92762188011	HAM-AP1-FB-01	EPA 6010D	DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92762188

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92762188012	HAM-AP1-FD-01	SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	DRB	6
		EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3

PASI-A = Pace Analytical Services - Asheville

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92762188

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92762188001	HAM-PT-07					
EPA 6010D	Iron	6.6	mg/L	0.040	11/08/24 19:24	
EPA 6010D	Manganese	3.1	mg/L	0.040	11/08/24 19:24	
EPA 6010D	Potassium	5.9	mg/L	0.50	11/08/24 19:24	
EPA 6010D	Sodium	9.8	mg/L	1.0	11/08/24 19:24	M1
EPA 6010D	Calcium	121	mg/L	1.0	11/08/24 19:24	M1
EPA 6010D	Magnesium	17.9	mg/L	0.050	11/08/24 19:24	M1
EPA 6020B	Arsenic	0.11	mg/L	0.0050	11/13/24 17:15	
EPA 6020B	Barium	0.051	mg/L	0.0050	11/13/24 17:15	
EPA 6020B	Boron	0.67	mg/L	0.040	11/13/24 17:15	
EPA 6020B	Cobalt	0.042	mg/L	0.0050	11/13/24 17:15	
EPA 6020B	Lead	0.00019J	mg/L	0.0010	11/13/24 17:15	
EPA 6020B	Lithium	0.051	mg/L	0.030	11/13/24 17:15	
EPA 6020B	Molybdenum	0.0088J	mg/L	0.010	11/13/24 17:15	
SM 2540C-2015	Total Dissolved Solids	542	mg/L	25.0	11/07/24 12:29	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	152	mg/L	5.0	11/12/24 13:55	
SM 2320B-2011	Alkalinity, Total as CaCO3	152	mg/L	5.0	11/12/24 13:55	
EPA 300.0 Rev 2.1 1993	Chloride	16.5	mg/L	1.0	11/07/24 16:25	
EPA 300.0 Rev 2.1 1993	Fluoride	0.29	mg/L	0.10	11/07/24 16:25	
EPA 300.0 Rev 2.1 1993	Sulfate	194	mg/L	4.0	11/08/24 01:54	
92762188002	HAM-PT-08					
EPA 6010D	Iron	0.63	mg/L	0.040	11/08/24 19:44	
EPA 6010D	Manganese	1.4	mg/L	0.040	11/08/24 19:44	
EPA 6010D	Potassium	5.7	mg/L	0.50	11/08/24 19:44	
EPA 6010D	Sodium	8.2	mg/L	1.0	11/08/24 19:44	
EPA 6010D	Calcium	105	mg/L	1.0	11/08/24 19:44	
EPA 6010D	Magnesium	14.4	mg/L	0.050	11/08/24 19:44	
EPA 6020B	Arsenic	0.027	mg/L	0.0050	11/13/24 17:19	
EPA 6020B	Barium	0.053	mg/L	0.0050	11/13/24 17:19	
EPA 6020B	Boron	0.70	mg/L	0.040	11/13/24 17:19	
EPA 6020B	Cobalt	0.032	mg/L	0.0050	11/13/24 17:19	
EPA 6020B	Lithium	0.023J	mg/L	0.030	11/13/24 17:19	
EPA 6020B	Molybdenum	0.0097J	mg/L	0.010	11/13/24 17:19	
EPA 6020B	Selenium	0.0014J	mg/L	0.0050	11/13/24 17:19	
SM 2540C-2015	Total Dissolved Solids	474	mg/L	25.0	11/07/24 12:30	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	98.7	mg/L	5.0	11/12/24 14:05	
SM 2320B-2011	Alkalinity, Total as CaCO3	98.7	mg/L	5.0	11/12/24 14:05	
EPA 300.0 Rev 2.1 1993	Chloride	15.6	mg/L	1.0	11/07/24 16:40	
EPA 300.0 Rev 2.1 1993	Fluoride	0.15	mg/L	0.10	11/07/24 16:40	
EPA 300.0 Rev 2.1 1993	Sulfate	187	mg/L	4.0	11/08/24 02:09	
92762188003	HAM-PT-09					
EPA 6010D	Iron	0.37	mg/L	0.040	11/08/24 19:49	
EPA 6010D	Manganese	0.44	mg/L	0.040	11/08/24 19:49	
EPA 6010D	Potassium	6.4	mg/L	0.50	11/08/24 19:49	
EPA 6010D	Sodium	9.7	mg/L	1.0	11/08/24 19:49	
EPA 6010D	Calcium	106	mg/L	1.0	11/08/24 19:49	
EPA 6010D	Magnesium	25.0	mg/L	0.050	11/08/24 19:49	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92762188

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92762188003	HAM-PT-09					
EPA 6020B	Antimony	0.00060J	mg/L	0.0030	11/13/24 17:35	
EPA 6020B	Arsenic	0.0028J	mg/L	0.0050	11/13/24 17:35	B
EPA 6020B	Barium	0.072	mg/L	0.0050	11/13/24 17:35	
EPA 6020B	Boron	1.6	mg/L	0.040	11/13/24 17:35	
EPA 6020B	Cadmium	0.00023J	mg/L	0.00050	11/13/24 17:35	
EPA 6020B	Cobalt	0.0040J	mg/L	0.0050	11/13/24 17:35	
EPA 6020B	Lithium	0.0029J	mg/L	0.030	11/13/24 17:35	
EPA 6020B	Molybdenum	0.22	mg/L	0.010	11/13/24 17:35	
EPA 6020B	Selenium	0.00099J	mg/L	0.0050	11/13/24 17:35	
SM 2540C-2015	Total Dissolved Solids	563	mg/L	25.0	11/07/24 12:32	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	122	mg/L	5.0	11/12/24 18:00	
SM 2320B-2011	Alkalinity, Total as CaCO3	122	mg/L	5.0	11/12/24 18:00	
EPA 300.0 Rev 2.1 1993	Chloride	48.3	mg/L	1.0	11/07/24 17:26	
EPA 300.0 Rev 2.1 1993	Fluoride	0.37	mg/L	0.10	11/07/24 17:26	
EPA 300.0 Rev 2.1 1993	Sulfate	165	mg/L	4.0	11/08/24 02:54	
92762188004	HAM-PT-10					
EPA 6010D	Iron	0.033J	mg/L	0.040	11/08/24 19:54	
EPA 6010D	Manganese	0.40	mg/L	0.040	11/08/24 19:54	
EPA 6010D	Potassium	6.9	mg/L	0.50	11/08/24 19:54	
EPA 6010D	Sodium	9.2	mg/L	1.0	11/08/24 19:54	
EPA 6010D	Calcium	107	mg/L	1.0	11/08/24 19:54	
EPA 6010D	Magnesium	13.9	mg/L	0.050	11/08/24 19:54	
EPA 6020B	Arsenic	0.0021J	mg/L	0.0050	11/13/24 17:39	B
EPA 6020B	Barium	0.050	mg/L	0.0050	11/13/24 17:39	
EPA 6020B	Boron	1.7	mg/L	0.040	11/13/24 17:39	
EPA 6020B	Cadmium	0.00013J	mg/L	0.00050	11/13/24 17:39	
EPA 6020B	Cobalt	0.0014J	mg/L	0.0050	11/13/24 17:39	
EPA 6020B	Molybdenum	0.21	mg/L	0.010	11/13/24 17:39	
EPA 6020B	Selenium	0.0011J	mg/L	0.0050	11/13/24 17:39	
SM 2540C-2015	Total Dissolved Solids	527	mg/L	25.0	11/07/24 12:32	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	132	mg/L	5.0	11/12/24 18:08	
SM 2320B-2011	Alkalinity, Total as CaCO3	132	mg/L	5.0	11/12/24 18:08	
EPA 300.0 Rev 2.1 1993	Chloride	45.1	mg/L	1.0	11/07/24 17:42	
EPA 300.0 Rev 2.1 1993	Fluoride	0.27	mg/L	0.10	11/07/24 17:42	
EPA 300.0 Rev 2.1 1993	Sulfate	129	mg/L	3.0	11/08/24 03:09	
92762188005	HAM-PT-11					
EPA 6010D	Iron	0.19	mg/L	0.040	11/08/24 19:58	
EPA 6010D	Manganese	0.66	mg/L	0.040	11/08/24 19:58	
EPA 6010D	Potassium	6.3	mg/L	0.50	11/08/24 19:58	
EPA 6010D	Sodium	9.1	mg/L	1.0	11/08/24 19:58	
EPA 6010D	Calcium	112	mg/L	1.0	11/08/24 19:58	
EPA 6010D	Magnesium	19.1	mg/L	0.050	11/08/24 19:58	
EPA 6020B	Arsenic	0.0030J	mg/L	0.0050	11/13/24 17:43	B
EPA 6020B	Barium	0.074	mg/L	0.0050	11/13/24 17:43	
EPA 6020B	Boron	1.6	mg/L	0.040	11/13/24 17:43	
EPA 6020B	Cadmium	0.00018J	mg/L	0.00050	11/13/24 17:43	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92762188

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92762188005	HAM-PT-11					
EPA 6020B	Cobalt	0.0079	mg/L	0.0050	11/13/24 17:43	
EPA 6020B	Lithium	0.0046J	mg/L	0.030	11/13/24 17:43	
EPA 6020B	Molybdenum	0.11	mg/L	0.010	11/13/24 17:43	
SM 2540C-2015	Total Dissolved Solids	563	mg/L	25.0	11/07/24 12:33	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	128	mg/L	5.0	11/12/24 18:17	
SM 2320B-2011	Alkalinity, Total as CaCO3	128	mg/L	5.0	11/12/24 18:17	
EPA 300.0 Rev 2.1 1993	Chloride	46.9	mg/L	1.0	11/07/24 17:57	
EPA 300.0 Rev 2.1 1993	Fluoride	0.31	mg/L	0.10	11/07/24 17:57	
EPA 300.0 Rev 2.1 1993	Sulfate	156	mg/L	4.0	11/08/24 03:25	
92762188006	HAM-PT-12					
EPA 6010D	Iron	0.14	mg/L	0.040	11/08/24 20:13	
EPA 6010D	Manganese	1.4	mg/L	0.040	11/08/24 20:13	
EPA 6010D	Potassium	5.4	mg/L	0.50	11/08/24 20:13	
EPA 6010D	Sodium	7.6	mg/L	1.0	11/08/24 20:13	
EPA 6010D	Calcium	98.0	mg/L	1.0	11/08/24 20:13	
EPA 6010D	Magnesium	31.4	mg/L	0.050	11/08/24 20:13	
EPA 6020B	Arsenic	0.0046J	mg/L	0.0050	11/13/24 18:12	B
EPA 6020B	Barium	0.074	mg/L	0.0050	11/13/24 18:12	
EPA 6020B	Boron	1.1	mg/L	0.040	11/13/24 18:12	
EPA 6020B	Cadmium	0.00037J	mg/L	0.00050	11/13/24 18:12	
EPA 6020B	Cobalt	0.0053	mg/L	0.0050	11/13/24 18:12	
EPA 6020B	Lithium	0.0037J	mg/L	0.030	11/13/24 18:12	
EPA 6020B	Molybdenum	0.12	mg/L	0.010	11/13/24 18:12	
SM 2540C-2015	Total Dissolved Solids	549	mg/L	25.0	11/12/24 15:09	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	107	mg/L	5.0	11/12/24 18:25	
SM 2320B-2011	Alkalinity, Total as CaCO3	107	mg/L	5.0	11/12/24 18:25	
EPA 300.0 Rev 2.1 1993	Chloride	32.2	mg/L	1.0	11/07/24 18:59	
EPA 300.0 Rev 2.1 1993	Fluoride	0.26	mg/L	0.10	11/07/24 18:59	
EPA 300.0 Rev 2.1 1993	Sulfate	204	mg/L	5.0	11/08/24 03:40	
92762188007	HAM-PT-13					
EPA 6010D	Iron	8.6	mg/L	0.040	11/08/24 20:18	
EPA 6010D	Manganese	2.9	mg/L	0.040	11/08/24 20:18	
EPA 6010D	Potassium	5.9	mg/L	0.50	11/08/24 20:18	
EPA 6010D	Sodium	11.3	mg/L	1.0	11/08/24 20:18	
EPA 6010D	Calcium	119	mg/L	1.0	11/08/24 20:18	
EPA 6010D	Magnesium	16.9	mg/L	0.050	11/08/24 20:18	
EPA 6020B	Arsenic	0.14	mg/L	0.0050	11/13/24 18:16	
EPA 6020B	Barium	0.050	mg/L	0.0050	11/13/24 18:16	
EPA 6020B	Beryllium	0.00011J	mg/L	0.00050	11/13/24 18:16	
EPA 6020B	Boron	0.65	mg/L	0.040	11/13/24 18:16	
EPA 6020B	Cobalt	0.024	mg/L	0.0050	11/13/24 18:16	
EPA 6020B	Lithium	0.058	mg/L	0.030	11/13/24 18:16	
EPA 6020B	Molybdenum	0.0072J	mg/L	0.010	11/13/24 18:16	
EPA 6020B	Selenium	0.0011J	mg/L	0.0050	11/13/24 18:16	
SM 2540C-2015	Total Dissolved Solids	550	mg/L	25.0	11/07/24 12:31	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	147	mg/L	5.0	11/12/24 14:13	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92762188

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92762188007	HAM-PT-13					
SM 2320B-2011	Alkalinity, Total as CaCO ₃	147	mg/L	5.0	11/12/24 14:13	
EPA 300.0 Rev 2.1 1993	Chloride	18.5	mg/L	1.0	11/07/24 19:14	
EPA 300.0 Rev 2.1 1993	Fluoride	0.32	mg/L	0.10	11/07/24 19:14	
EPA 300.0 Rev 2.1 1993	Sulfate	199	mg/L	4.0	11/08/24 04:41	
92762188008	HAM-PT-14					
EPA 6010D	Iron	13.5	mg/L	0.040	11/08/24 20:23	
EPA 6010D	Manganese	2.8	mg/L	0.040	11/08/24 20:23	
EPA 6010D	Potassium	5.8	mg/L	0.50	11/08/24 20:23	
EPA 6010D	Sodium	8.7	mg/L	1.0	11/08/24 20:23	
EPA 6010D	Calcium	123	mg/L	1.0	11/08/24 20:23	
EPA 6010D	Magnesium	17.6	mg/L	0.050	11/08/24 20:23	
EPA 6020B	Arsenic	0.26	mg/L	0.0050	11/13/24 18:20	
EPA 6020B	Barium	0.045	mg/L	0.0050	11/13/24 18:20	
EPA 6020B	Boron	0.66	mg/L	0.040	11/13/24 18:20	
EPA 6020B	Cobalt	0.023	mg/L	0.0050	11/13/24 18:20	
EPA 6020B	Lithium	0.051	mg/L	0.030	11/13/24 18:20	
EPA 6020B	Molybdenum	0.016	mg/L	0.010	11/13/24 18:20	
EPA 6020B	Selenium	0.0012J	mg/L	0.0050	11/13/24 18:20	
SM 2540C-2015	Total Dissolved Solids	628	mg/L	25.0	11/07/24 12:31	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO ₃)	148	mg/L	5.0	11/12/24 14:31	
SM 2320B-2011	Alkalinity, Total as CaCO ₃	148	mg/L	5.0	11/12/24 14:31	
EPA 300.0 Rev 2.1 1993	Chloride	15.2	mg/L	1.0	11/07/24 19:30	
EPA 300.0 Rev 2.1 1993	Fluoride	0.25	mg/L	0.10	11/07/24 19:30	
EPA 300.0 Rev 2.1 1993	Sulfate	196	mg/L	4.0	11/08/24 04:56	
92762188009	HAM-PT-15					
EPA 6010D	Iron	1.1	mg/L	0.040	11/08/24 20:28	
EPA 6010D	Manganese	2.9	mg/L	0.040	11/08/24 20:28	
EPA 6010D	Potassium	5.3	mg/L	0.50	11/08/24 20:28	
EPA 6010D	Sodium	8.8	mg/L	1.0	11/08/24 20:28	
EPA 6010D	Calcium	119	mg/L	1.0	11/08/24 20:28	
EPA 6010D	Magnesium	14.2	mg/L	0.050	11/08/24 20:28	
EPA 6020B	Arsenic	0.040	mg/L	0.0050	11/13/24 18:24	
EPA 6020B	Barium	0.051	mg/L	0.0050	11/13/24 18:24	
EPA 6020B	Boron	0.74	mg/L	0.040	11/13/24 18:24	
EPA 6020B	Cadmium	0.00034J	mg/L	0.00050	11/13/24 18:24	
EPA 6020B	Cobalt	0.019	mg/L	0.0050	11/13/24 18:24	
EPA 6020B	Lithium	0.046	mg/L	0.030	11/13/24 18:24	
EPA 6020B	Molybdenum	0.012	mg/L	0.010	11/13/24 18:24	
EPA 6020B	Selenium	0.0020J	mg/L	0.0050	11/13/24 18:24	
EPA 6020B	Thallium	0.00041J	mg/L	0.0010	11/13/24 18:24	
SM 2540C-2015	Total Dissolved Solids	543	mg/L	25.0	11/07/24 12:31	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO ₃)	140	mg/L	5.0	11/12/24 14:41	
SM 2320B-2011	Alkalinity, Total as CaCO ₃	140	mg/L	5.0	11/12/24 14:41	
EPA 300.0 Rev 2.1 1993	Chloride	16.0	mg/L	1.0	11/07/24 19:45	
EPA 300.0 Rev 2.1 1993	Fluoride	0.28	mg/L	0.10	11/07/24 19:45	
EPA 300.0 Rev 2.1 1993	Sulfate	194	mg/L	4.0	11/08/24 05:12	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92762188

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92762188010	HAM-AP1-EB-01					
EPA 6010D	Magnesium	0.019J	mg/L	0.050	11/08/24 20:32	
EPA 6020B	Arsenic	0.0021J	mg/L	0.0050	11/13/24 18:33	B
SM 2540C-2015	Total Dissolved Solids	57.0	mg/L	25.0	11/07/24 12:33	
92762188011	HAM-AP1-FB-01					
EPA 6010D	Sodium	0.74J	mg/L	1.0	11/08/24 20:37	
EPA 6010D	Calcium	0.40J	mg/L	1.0	11/08/24 20:37	
EPA 6010D	Magnesium	0.10	mg/L	0.050	11/08/24 20:37	
EPA 6020B	Arsenic	0.0017J	mg/L	0.0050	11/13/24 18:37	B
EPA 6020B	Barium	0.0022J	mg/L	0.0050	11/13/24 18:37	
92762188012	HAM-AP1-FD-01					
EPA 6010D	Iron	0.66	mg/L	0.040	11/08/24 20:42	
EPA 6010D	Manganese	1.5	mg/L	0.040	11/08/24 20:42	
EPA 6010D	Potassium	5.6	mg/L	0.50	11/08/24 20:42	
EPA 6010D	Sodium	8.2	mg/L	1.0	11/08/24 20:42	
EPA 6010D	Calcium	106	mg/L	1.0	11/08/24 20:42	
EPA 6010D	Magnesium	14.5	mg/L	0.050	11/08/24 20:42	
EPA 6020B	Arsenic	0.028	mg/L	0.0050	11/13/24 18:41	
EPA 6020B	Barium	0.054	mg/L	0.0050	11/13/24 18:41	
EPA 6020B	Boron	0.70	mg/L	0.040	11/13/24 18:41	
EPA 6020B	Cobalt	0.033	mg/L	0.0050	11/13/24 18:41	
EPA 6020B	Lithium	0.025J	mg/L	0.030	11/13/24 18:41	
EPA 6020B	Molybdenum	0.010	mg/L	0.010	11/13/24 18:41	
EPA 6020B	Selenium	0.0014J	mg/L	0.0050	11/13/24 18:41	
SM 2540C-2015	Total Dissolved Solids	497	mg/L	25.0	11/07/24 12:34	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	102	mg/L	5.0	11/14/24 18:40	
SM 2320B-2011	Alkalinity, Total as CaCO3	102	mg/L	5.0	11/14/24 18:40	
EPA 300.0 Rev 2.1 1993	Chloride	15.8	mg/L	1.0	11/07/24 21:02	
EPA 300.0 Rev 2.1 1993	Fluoride	0.16	mg/L	0.10	11/07/24 21:02	
EPA 300.0 Rev 2.1 1993	Sulfate	190	mg/L	4.0	11/08/24 05:27	M1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92762188

Sample: HAM-PT-07 Lab ID: 92762188001 Collected: 11/04/24 12:34 Received: 11/06/24 14:15 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	6.6	mg/L	0.040	0.025	1	11/08/24 12:32	11/08/24 19:24	7439-89-6	
Manganese	3.1	mg/L	0.040	0.011	1	11/08/24 12:32	11/08/24 19:24	7439-96-5	
Potassium	5.9	mg/L	0.50	0.15	1	11/08/24 12:32	11/08/24 19:24	7440-09-7	
Sodium	9.8	mg/L	1.0	0.58	1	11/08/24 12:32	11/08/24 19:24	7440-23-5	M1
Calcium	121	mg/L	1.0	0.12	1	11/08/24 12:32	11/08/24 19:24	7440-70-2	M1
Magnesium	17.9	mg/L	0.050	0.012	1	11/08/24 12:32	11/08/24 19:24	7439-95-4	M1
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	11/08/24 12:13	11/13/24 17:15	7440-36-0	
Arsenic	0.11	mg/L	0.0050	0.00084	1	11/08/24 12:13	11/13/24 17:15	7440-38-2	
Barium	0.051	mg/L	0.0050	0.00047	1	11/08/24 12:13	11/13/24 17:15	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	11/08/24 12:13	11/13/24 17:15	7440-41-7	
Boron	0.67	mg/L	0.040	0.012	1	11/08/24 12:13	11/13/24 17:15	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	11/08/24 12:13	11/13/24 17:15	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	11/08/24 12:13	11/13/24 17:15	7440-47-3	
Cobalt	0.042	mg/L	0.0050	0.00032	1	11/08/24 12:13	11/13/24 17:15	7440-48-4	
Lead	0.00019J	mg/L	0.0010	0.00016	1	11/08/24 12:13	11/13/24 17:15	7439-92-1	
Lithium	0.051	mg/L	0.030	0.0016	1	11/08/24 12:13	11/13/24 17:15	7439-93-2	
Molybdenum	0.0088J	mg/L	0.010	0.00062	1	11/08/24 12:13	11/13/24 17:15	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	11/08/24 12:13	11/13/24 17:15	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	11/08/24 12:13	11/13/24 17:15	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	11/19/24 08:00	11/19/24 12:56	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	542	mg/L	25.0	25.0	1		11/07/24 12:29		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	152	mg/L	5.0	5.0	1		11/12/24 13:55		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		11/12/24 13:55		
Alkalinity, Total as CaCO ₃	152	mg/L	5.0	5.0	1		11/12/24 13:55		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		11/09/24 04:17	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	16.5	mg/L	1.0	0.60	1		11/07/24 16:25	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92762188

Sample: HAM-PT-07		Lab ID: 92762188001		Collected: 11/04/24 12:34		Received: 11/06/24 14:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.29	mg/L	0.10	0.050	1		11/07/24 16:25	16984-48-8	
Sulfate	194	mg/L	4.0	2.0	4		11/08/24 01:54	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92762188

Sample: HAM-PT-08 Lab ID: 92762188002 Collected: 11/04/24 12:14 Received: 11/06/24 14:15 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.63	mg/L	0.040	0.025	1	11/08/24 12:32	11/08/24 19:44	7439-89-6	
Manganese	1.4	mg/L	0.040	0.011	1	11/08/24 12:32	11/08/24 19:44	7439-96-5	
Potassium	5.7	mg/L	0.50	0.15	1	11/08/24 12:32	11/08/24 19:44	7440-09-7	
Sodium	8.2	mg/L	1.0	0.58	1	11/08/24 12:32	11/08/24 19:44	7440-23-5	
Calcium	105	mg/L	1.0	0.12	1	11/08/24 12:32	11/08/24 19:44	7440-70-2	
Magnesium	14.4	mg/L	0.050	0.012	1	11/08/24 12:32	11/08/24 19:44	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	11/08/24 12:13	11/13/24 17:19	7440-36-0	
Arsenic	0.027	mg/L	0.0050	0.00084	1	11/08/24 12:13	11/13/24 17:19	7440-38-2	
Barium	0.053	mg/L	0.0050	0.00047	1	11/08/24 12:13	11/13/24 17:19	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	11/08/24 12:13	11/13/24 17:19	7440-41-7	
Boron	0.70	mg/L	0.040	0.012	1	11/08/24 12:13	11/13/24 17:19	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	11/08/24 12:13	11/13/24 17:19	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	11/08/24 12:13	11/13/24 17:19	7440-47-3	
Cobalt	0.032	mg/L	0.0050	0.00032	1	11/08/24 12:13	11/13/24 17:19	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	11/08/24 12:13	11/13/24 17:19	7439-92-1	
Lithium	0.023J	mg/L	0.030	0.0016	1	11/08/24 12:13	11/13/24 17:19	7439-93-2	
Molybdenum	0.0097J	mg/L	0.010	0.00062	1	11/08/24 12:13	11/13/24 17:19	7439-98-7	
Selenium	0.0014J	mg/L	0.0050	0.00096	1	11/08/24 12:13	11/13/24 17:19	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	11/08/24 12:13	11/13/24 17:19	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	11/19/24 08:00	11/19/24 12:59	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	474	mg/L	25.0	25.0	1		11/07/24 12:30		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	98.7	mg/L	5.0	5.0	1		11/12/24 14:05		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		11/12/24 14:05		
Alkalinity, Total as CaCO ₃	98.7	mg/L	5.0	5.0	1		11/12/24 14:05		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		11/09/24 04:19	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	15.6	mg/L	1.0	0.60	1		11/07/24 16:40	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92762188

Sample: HAM-PT-08		Lab ID: 92762188002		Collected: 11/04/24 12:14		Received: 11/06/24 14:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.15	mg/L	0.10	0.050	1		11/07/24 16:40	16984-48-8	
Sulfate	187	mg/L	4.0	2.0	4		11/08/24 02:09	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92762188

Sample: HAM-PT-09 Lab ID: 92762188003 Collected: 11/05/24 11:54 Received: 11/06/24 14:15 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.37	mg/L	0.040	0.025	1	11/08/24 12:32	11/08/24 19:49	7439-89-6	
Manganese	0.44	mg/L	0.040	0.011	1	11/08/24 12:32	11/08/24 19:49	7439-96-5	
Potassium	6.4	mg/L	0.50	0.15	1	11/08/24 12:32	11/08/24 19:49	7440-09-7	
Sodium	9.7	mg/L	1.0	0.58	1	11/08/24 12:32	11/08/24 19:49	7440-23-5	
Calcium	106	mg/L	1.0	0.12	1	11/08/24 12:32	11/08/24 19:49	7440-70-2	
Magnesium	25.0	mg/L	0.050	0.012	1	11/08/24 12:32	11/08/24 19:49	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	0.00060J	mg/L	0.0030	0.00054	1	11/08/24 12:13	11/13/24 17:35	7440-36-0	
Arsenic	0.0028J	mg/L	0.0050	0.00084	1	11/08/24 12:13	11/13/24 17:35	7440-38-2	B
Barium	0.072	mg/L	0.0050	0.00047	1	11/08/24 12:13	11/13/24 17:35	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	11/08/24 12:13	11/13/24 17:35	7440-41-7	
Boron	1.6	mg/L	0.040	0.012	1	11/08/24 12:13	11/13/24 17:35	7440-42-8	
Cadmium	0.00023J	mg/L	0.00050	0.00010	1	11/08/24 12:13	11/13/24 17:35	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	11/08/24 12:13	11/13/24 17:35	7440-47-3	
Cobalt	0.0040J	mg/L	0.0050	0.00032	1	11/08/24 12:13	11/13/24 17:35	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	11/08/24 12:13	11/13/24 17:35	7439-92-1	
Lithium	0.0029J	mg/L	0.030	0.0016	1	11/08/24 12:13	11/13/24 17:35	7439-93-2	
Molybdenum	0.22	mg/L	0.010	0.00062	1	11/08/24 12:13	11/13/24 17:35	7439-98-7	
Selenium	0.00099J	mg/L	0.0050	0.00096	1	11/08/24 12:13	11/13/24 17:35	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	11/08/24 12:13	11/13/24 17:35	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	11/19/24 08:00	11/19/24 13:10	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	563	mg/L	25.0	25.0	1		11/07/24 12:32		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	122	mg/L	5.0	5.0	1		11/12/24 18:00		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		11/12/24 18:00		
Alkalinity, Total as CaCO3	122	mg/L	5.0	5.0	1		11/12/24 18:00		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		11/09/24 04:21	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	48.3	mg/L	1.0	0.60	1		11/07/24 17:26	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92762188

Sample: HAM-PT-09		Lab ID: 92762188003		Collected: 11/05/24 11:54		Received: 11/06/24 14:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.37	mg/L	0.10	0.050	1		11/07/24 17:26	16984-48-8	
Sulfate	165	mg/L	4.0	2.0	4		11/08/24 02:54	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92762188

Sample: HAM-PT-10 Lab ID: 92762188004 Collected: 11/05/24 09:29 Received: 11/06/24 14:15 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.033J	mg/L	0.040	0.025	1	11/08/24 12:32	11/08/24 19:54	7439-89-6	
Manganese	0.40	mg/L	0.040	0.011	1	11/08/24 12:32	11/08/24 19:54	7439-96-5	
Potassium	6.9	mg/L	0.50	0.15	1	11/08/24 12:32	11/08/24 19:54	7440-09-7	
Sodium	9.2	mg/L	1.0	0.58	1	11/08/24 12:32	11/08/24 19:54	7440-23-5	
Calcium	107	mg/L	1.0	0.12	1	11/08/24 12:32	11/08/24 19:54	7440-70-2	
Magnesium	13.9	mg/L	0.050	0.012	1	11/08/24 12:32	11/08/24 19:54	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	11/08/24 12:13	11/13/24 17:39	7440-36-0	
Arsenic	0.0021J	mg/L	0.0050	0.00084	1	11/08/24 12:13	11/13/24 17:39	7440-38-2	B
Barium	0.050	mg/L	0.0050	0.00047	1	11/08/24 12:13	11/13/24 17:39	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	11/08/24 12:13	11/13/24 17:39	7440-41-7	
Boron	1.7	mg/L	0.040	0.012	1	11/08/24 12:13	11/13/24 17:39	7440-42-8	
Cadmium	0.00013J	mg/L	0.00050	0.00010	1	11/08/24 12:13	11/13/24 17:39	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	11/08/24 12:13	11/13/24 17:39	7440-47-3	
Cobalt	0.0014J	mg/L	0.0050	0.00032	1	11/08/24 12:13	11/13/24 17:39	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	11/08/24 12:13	11/13/24 17:39	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	11/08/24 12:13	11/13/24 17:39	7439-93-2	
Molybdenum	0.21	mg/L	0.010	0.00062	1	11/08/24 12:13	11/13/24 17:39	7439-98-7	
Selenium	0.0011J	mg/L	0.0050	0.00096	1	11/08/24 12:13	11/13/24 17:39	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	11/08/24 12:13	11/13/24 17:39	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	11/19/24 08:00	11/19/24 13:12	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	527	mg/L	25.0	25.0	1		11/07/24 12:32		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	132	mg/L	5.0	5.0	1		11/12/24 18:08		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		11/12/24 18:08		
Alkalinity, Total as CaCO3	132	mg/L	5.0	5.0	1		11/12/24 18:08		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		11/09/24 04:22	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	45.1	mg/L	1.0	0.60	1		11/07/24 17:42	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92762188

Sample: HAM-PT-10		Lab ID: 92762188004		Collected: 11/05/24 09:29		Received: 11/06/24 14:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.27	mg/L	0.10	0.050	1		11/07/24 17:42	16984-48-8	
Sulfate	129	mg/L	3.0	1.5	3		11/08/24 03:09	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92762188

Sample: HAM-PT-11 Lab ID: 92762188005 Collected: 11/05/24 09:25 Received: 11/06/24 14:15 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.19	mg/L	0.040	0.025	1	11/08/24 12:32	11/08/24 19:58	7439-89-6	
Manganese	0.66	mg/L	0.040	0.011	1	11/08/24 12:32	11/08/24 19:58	7439-96-5	
Potassium	6.3	mg/L	0.50	0.15	1	11/08/24 12:32	11/08/24 19:58	7440-09-7	
Sodium	9.1	mg/L	1.0	0.58	1	11/08/24 12:32	11/08/24 19:58	7440-23-5	
Calcium	112	mg/L	1.0	0.12	1	11/08/24 12:32	11/08/24 19:58	7440-70-2	
Magnesium	19.1	mg/L	0.050	0.012	1	11/08/24 12:32	11/08/24 19:58	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	11/08/24 12:13	11/13/24 17:43	7440-36-0	
Arsenic	0.0030J	mg/L	0.0050	0.00084	1	11/08/24 12:13	11/13/24 17:43	7440-38-2	B
Barium	0.074	mg/L	0.0050	0.00047	1	11/08/24 12:13	11/13/24 17:43	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	11/08/24 12:13	11/13/24 17:43	7440-41-7	
Boron	1.6	mg/L	0.040	0.012	1	11/08/24 12:13	11/13/24 17:43	7440-42-8	
Cadmium	0.00018J	mg/L	0.00050	0.00010	1	11/08/24 12:13	11/13/24 17:43	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	11/08/24 12:13	11/13/24 17:43	7440-47-3	
Cobalt	0.0079	mg/L	0.0050	0.00032	1	11/08/24 12:13	11/13/24 17:43	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	11/08/24 12:13	11/13/24 17:43	7439-92-1	
Lithium	0.0046J	mg/L	0.030	0.0016	1	11/08/24 12:13	11/13/24 17:43	7439-93-2	
Molybdenum	0.11	mg/L	0.010	0.00062	1	11/08/24 12:13	11/13/24 17:43	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	11/08/24 12:13	11/13/24 17:43	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	11/08/24 12:13	11/13/24 17:43	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	11/19/24 08:00	11/19/24 13:15	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	563	mg/L	25.0	25.0	1		11/07/24 12:33		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	128	mg/L	5.0	5.0	1		11/12/24 18:17		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		11/12/24 18:17		
Alkalinity, Total as CaCO3	128	mg/L	5.0	5.0	1		11/12/24 18:17		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		11/09/24 04:22	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	46.9	mg/L	1.0	0.60	1		11/07/24 17:57	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92762188

Sample: HAM-PT-11		Lab ID: 92762188005		Collected: 11/05/24 09:25		Received: 11/06/24 14:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.31	mg/L	0.10	0.050	1		11/07/24 17:57	16984-48-8	
Sulfate	156	mg/L	4.0	2.0	4		11/08/24 03:25	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92762188

Sample: HAM-PT-12 Lab ID: 92762188006 Collected: 11/05/24 11:44 Received: 11/06/24 14:15 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.14	mg/L	0.040	0.025	1	11/08/24 12:32	11/08/24 20:13	7439-89-6	
Manganese	1.4	mg/L	0.040	0.011	1	11/08/24 12:32	11/08/24 20:13	7439-96-5	
Potassium	5.4	mg/L	0.50	0.15	1	11/08/24 12:32	11/08/24 20:13	7440-09-7	
Sodium	7.6	mg/L	1.0	0.58	1	11/08/24 12:32	11/08/24 20:13	7440-23-5	
Calcium	98.0	mg/L	1.0	0.12	1	11/08/24 12:32	11/08/24 20:13	7440-70-2	
Magnesium	31.4	mg/L	0.050	0.012	1	11/08/24 12:32	11/08/24 20:13	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	11/08/24 12:13	11/13/24 18:12	7440-36-0	
Arsenic	0.0046J	mg/L	0.0050	0.00084	1	11/08/24 12:13	11/13/24 18:12	7440-38-2	B
Barium	0.074	mg/L	0.0050	0.00047	1	11/08/24 12:13	11/13/24 18:12	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	11/08/24 12:13	11/13/24 18:12	7440-41-7	
Boron	1.1	mg/L	0.040	0.012	1	11/08/24 12:13	11/13/24 18:12	7440-42-8	
Cadmium	0.00037J	mg/L	0.00050	0.00010	1	11/08/24 12:13	11/13/24 18:12	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	11/08/24 12:13	11/13/24 18:12	7440-47-3	
Cobalt	0.0053	mg/L	0.0050	0.00032	1	11/08/24 12:13	11/13/24 18:12	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	11/08/24 12:13	11/13/24 18:12	7439-92-1	
Lithium	0.0037J	mg/L	0.030	0.0016	1	11/08/24 12:13	11/13/24 18:12	7439-93-2	
Molybdenum	0.12	mg/L	0.010	0.00062	1	11/08/24 12:13	11/13/24 18:12	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	11/08/24 12:13	11/13/24 18:12	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	11/08/24 12:13	11/13/24 18:12	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	11/19/24 08:00	11/19/24 13:23	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	549	mg/L	25.0	25.0	1		11/12/24 15:09		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	107	mg/L	5.0	5.0	1		11/12/24 18:25		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		11/12/24 18:25		
Alkalinity, Total as CaCO3	107	mg/L	5.0	5.0	1		11/12/24 18:25		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		11/09/24 04:22	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	32.2	mg/L	1.0	0.60	1		11/07/24 18:59	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92762188

Sample: HAM-PT-12		Lab ID: 92762188006		Collected: 11/05/24 11:44		Received: 11/06/24 14:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.26	mg/L	0.10	0.050	1		11/07/24 18:59	16984-48-8	
Sulfate	204	mg/L	5.0	2.5	5		11/08/24 03:40	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92762188

Sample: HAM-PT-13		Lab ID: 92762188007		Collected: 11/04/24 11:05		Received: 11/06/24 14:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	8.6	mg/L	0.040	0.025	1	11/08/24 12:32	11/08/24 20:18	7439-89-6	
Manganese	2.9	mg/L	0.040	0.011	1	11/08/24 12:32	11/08/24 20:18	7439-96-5	
Potassium	5.9	mg/L	0.50	0.15	1	11/08/24 12:32	11/08/24 20:18	7440-09-7	
Sodium	11.3	mg/L	1.0	0.58	1	11/08/24 12:32	11/08/24 20:18	7440-23-5	
Calcium	119	mg/L	1.0	0.12	1	11/08/24 12:32	11/08/24 20:18	7440-70-2	
Magnesium	16.9	mg/L	0.050	0.012	1	11/08/24 12:32	11/08/24 20:18	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	11/08/24 12:13	11/13/24 18:16	7440-36-0	
Arsenic	0.14	mg/L	0.0050	0.00084	1	11/08/24 12:13	11/13/24 18:16	7440-38-2	
Barium	0.050	mg/L	0.0050	0.00047	1	11/08/24 12:13	11/13/24 18:16	7440-39-3	
Beryllium	0.00011J	mg/L	0.00050	0.000094	1	11/08/24 12:13	11/13/24 18:16	7440-41-7	
Boron	0.65	mg/L	0.040	0.012	1	11/08/24 12:13	11/13/24 18:16	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	11/08/24 12:13	11/13/24 18:16	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	11/08/24 12:13	11/13/24 18:16	7440-47-3	
Cobalt	0.024	mg/L	0.0050	0.00032	1	11/08/24 12:13	11/13/24 18:16	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	11/08/24 12:13	11/13/24 18:16	7439-92-1	
Lithium	0.058	mg/L	0.030	0.0016	1	11/08/24 12:13	11/13/24 18:16	7439-93-2	
Molybdenum	0.0072J	mg/L	0.010	0.00062	1	11/08/24 12:13	11/13/24 18:16	7439-98-7	
Selenium	0.0011J	mg/L	0.0050	0.00096	1	11/08/24 12:13	11/13/24 18:16	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	11/08/24 12:13	11/13/24 18:16	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	11/19/24 08:00	11/19/24 13:25	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	550	mg/L	25.0	25.0	1		11/07/24 12:31		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	147	mg/L	5.0	5.0	1		11/12/24 14:13		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		11/12/24 14:13		
Alkalinity, Total as CaCO3	147	mg/L	5.0	5.0	1		11/12/24 14:13		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		11/09/24 04:20	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	18.5	mg/L	1.0	0.60	1		11/07/24 19:14	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92762188

Sample: HAM-PT-13		Lab ID: 92762188007		Collected: 11/04/24 11:05		Received: 11/06/24 14:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.32	mg/L	0.10	0.050	1		11/07/24 19:14	16984-48-8	
Sulfate	199	mg/L	4.0	2.0	4		11/08/24 04:41	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92762188

Sample: HAM-PT-14 Lab ID: 92762188008 Collected: 11/04/24 14:50 Received: 11/06/24 14:15 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	13.5	mg/L	0.040	0.025	1	11/08/24 12:32	11/08/24 20:23	7439-89-6	
Manganese	2.8	mg/L	0.040	0.011	1	11/08/24 12:32	11/08/24 20:23	7439-96-5	
Potassium	5.8	mg/L	0.50	0.15	1	11/08/24 12:32	11/08/24 20:23	7440-09-7	
Sodium	8.7	mg/L	1.0	0.58	1	11/08/24 12:32	11/08/24 20:23	7440-23-5	
Calcium	123	mg/L	1.0	0.12	1	11/08/24 12:32	11/08/24 20:23	7440-70-2	
Magnesium	17.6	mg/L	0.050	0.012	1	11/08/24 12:32	11/08/24 20:23	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	11/08/24 12:13	11/13/24 18:20	7440-36-0	
Arsenic	0.26	mg/L	0.0050	0.00084	1	11/08/24 12:13	11/13/24 18:20	7440-38-2	
Barium	0.045	mg/L	0.0050	0.00047	1	11/08/24 12:13	11/13/24 18:20	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	11/08/24 12:13	11/13/24 18:20	7440-41-7	
Boron	0.66	mg/L	0.040	0.012	1	11/08/24 12:13	11/13/24 18:20	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	11/08/24 12:13	11/13/24 18:20	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	11/08/24 12:13	11/13/24 18:20	7440-47-3	
Cobalt	0.023	mg/L	0.0050	0.00032	1	11/08/24 12:13	11/13/24 18:20	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	11/08/24 12:13	11/13/24 18:20	7439-92-1	
Lithium	0.051	mg/L	0.030	0.0016	1	11/08/24 12:13	11/13/24 18:20	7439-93-2	
Molybdenum	0.016	mg/L	0.010	0.00062	1	11/08/24 12:13	11/13/24 18:20	7439-98-7	
Selenium	0.00123	mg/L	0.0050	0.00096	1	11/08/24 12:13	11/13/24 18:20	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	11/08/24 12:13	11/13/24 18:20	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	11/19/24 08:00	11/19/24 13:28	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	628	mg/L	25.0	25.0	1		11/07/24 12:31		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	148	mg/L	5.0	5.0	1		11/12/24 14:31		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		11/12/24 14:31		
Alkalinity, Total as CaCO3	148	mg/L	5.0	5.0	1		11/12/24 14:31		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		11/09/24 04:20	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	15.2	mg/L	1.0	0.60	1		11/07/24 19:30	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92762188

Sample: HAM-PT-14		Lab ID: 92762188008		Collected: 11/04/24 14:50		Received: 11/06/24 14:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.25	mg/L	0.10	0.050	1		11/07/24 19:30	16984-48-8	
Sulfate	196	mg/L	4.0	2.0	4		11/08/24 04:56	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92762188

Sample: HAM-PT-15 Lab ID: 92762188009 Collected: 11/04/24 14:01 Received: 11/06/24 14:15 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	1.1	mg/L	0.040	0.025	1	11/08/24 12:32	11/08/24 20:28	7439-89-6	
Manganese	2.9	mg/L	0.040	0.011	1	11/08/24 12:32	11/08/24 20:28	7439-96-5	
Potassium	5.3	mg/L	0.50	0.15	1	11/08/24 12:32	11/08/24 20:28	7440-09-7	
Sodium	8.8	mg/L	1.0	0.58	1	11/08/24 12:32	11/08/24 20:28	7440-23-5	
Calcium	119	mg/L	1.0	0.12	1	11/08/24 12:32	11/08/24 20:28	7440-70-2	
Magnesium	14.2	mg/L	0.050	0.012	1	11/08/24 12:32	11/08/24 20:28	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	11/08/24 12:13	11/13/24 18:24	7440-36-0	
Arsenic	0.040	mg/L	0.0050	0.00084	1	11/08/24 12:13	11/13/24 18:24	7440-38-2	
Barium	0.051	mg/L	0.0050	0.00047	1	11/08/24 12:13	11/13/24 18:24	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	11/08/24 12:13	11/13/24 18:24	7440-41-7	
Boron	0.74	mg/L	0.040	0.012	1	11/08/24 12:13	11/13/24 18:24	7440-42-8	
Cadmium	0.00034J	mg/L	0.00050	0.00010	1	11/08/24 12:13	11/13/24 18:24	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	11/08/24 12:13	11/13/24 18:24	7440-47-3	
Cobalt	0.019	mg/L	0.0050	0.00032	1	11/08/24 12:13	11/13/24 18:24	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	11/08/24 12:13	11/13/24 18:24	7439-92-1	
Lithium	0.046	mg/L	0.030	0.0016	1	11/08/24 12:13	11/13/24 18:24	7439-93-2	
Molybdenum	0.012	mg/L	0.010	0.00062	1	11/08/24 12:13	11/13/24 18:24	7439-98-7	
Selenium	0.0020J	mg/L	0.0050	0.00096	1	11/08/24 12:13	11/13/24 18:24	7782-49-2	
Thallium	0.00041J	mg/L	0.0010	0.00038	1	11/08/24 12:13	11/13/24 18:24	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	11/19/24 08:00	11/19/24 13:31	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	543	mg/L	25.0	25.0	1		11/07/24 12:31		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	140	mg/L	5.0	5.0	1		11/12/24 14:41		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		11/12/24 14:41		
Alkalinity, Total as CaCO3	140	mg/L	5.0	5.0	1		11/12/24 14:41		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		11/09/24 04:20	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	16.0	mg/L	1.0	0.60	1		11/07/24 19:45	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92762188

Sample: HAM-PT-15		Lab ID: 92762188009		Collected: 11/04/24 14:01		Received: 11/06/24 14:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.28	mg/L	0.10	0.050	1		11/07/24 19:45	16984-48-8	
Sulfate	194	mg/L	4.0	2.0	4		11/08/24 05:12	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92762188

Sample: HAM-AP1-EB-01 Lab ID: 92762188010 Collected: 11/05/24 12:36 Received: 11/06/24 14:15 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	11/08/24 12:32	11/08/24 20:32	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	11/08/24 12:32	11/08/24 20:32	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	11/08/24 12:32	11/08/24 20:32	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	11/08/24 12:32	11/08/24 20:32	7440-23-5	
Calcium	ND	mg/L	1.0	0.12	1	11/08/24 12:32	11/08/24 20:32	7440-70-2	
Magnesium	0.019J	mg/L	0.050	0.012	1	11/08/24 12:32	11/08/24 20:32	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	11/08/24 12:13	11/13/24 18:33	7440-36-0	
Arsenic	0.0021J	mg/L	0.0050	0.00084	1	11/08/24 12:13	11/13/24 18:33	7440-38-2	B
Barium	ND	mg/L	0.0050	0.00047	1	11/08/24 12:13	11/13/24 18:33	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	11/08/24 12:13	11/13/24 18:33	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	11/08/24 12:13	11/13/24 18:33	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	11/08/24 12:13	11/13/24 18:33	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	11/08/24 12:13	11/13/24 18:33	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	11/08/24 12:13	11/13/24 18:33	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	11/08/24 12:13	11/13/24 18:33	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	11/08/24 12:13	11/13/24 18:33	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	11/08/24 12:13	11/13/24 18:33	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	11/08/24 12:13	11/13/24 18:33	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	11/08/24 12:13	11/13/24 18:33	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	11/19/24 08:00	11/19/24 13:38	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	57.0	mg/L	25.0	25.0	1		11/07/24 12:33		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	ND	mg/L	5.0	5.0	1		11/12/24 18:33		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		11/12/24 18:33		
Alkalinity, Total as CaCO3	ND	mg/L	5.0	5.0	1		11/12/24 18:33		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		11/09/24 04:23	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		11/07/24 20:01	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92762188

Sample: HAM-AP1-EB-01		Lab ID: 92762188010		Collected: 11/05/24 12:36		Received: 11/06/24 14:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		11/07/24 20:01	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		11/07/24 20:01	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92762188

Sample: HAM-AP1-FB-01 Lab ID: 92762188011 Collected: 11/05/24 12:32 Received: 11/06/24 14:15 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	11/08/24 12:32	11/08/24 20:37	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	11/08/24 12:32	11/08/24 20:37	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	11/08/24 12:32	11/08/24 20:37	7440-09-7	
Sodium	0.74J	mg/L	1.0	0.58	1	11/08/24 12:32	11/08/24 20:37	7440-23-5	
Calcium	0.40J	mg/L	1.0	0.12	1	11/08/24 12:32	11/08/24 20:37	7440-70-2	
Magnesium	0.10	mg/L	0.050	0.012	1	11/08/24 12:32	11/08/24 20:37	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	11/08/24 12:13	11/13/24 18:37	7440-36-0	
Arsenic	0.0017J	mg/L	0.0050	0.00084	1	11/08/24 12:13	11/13/24 18:37	7440-38-2	B
Barium	0.0022J	mg/L	0.0050	0.00047	1	11/08/24 12:13	11/13/24 18:37	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	11/08/24 12:13	11/13/24 18:37	7440-41-7	
Boron	ND	mg/L	0.040	0.012	1	11/08/24 12:13	11/13/24 18:37	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	11/08/24 12:13	11/13/24 18:37	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	11/08/24 12:13	11/13/24 18:37	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.00032	1	11/08/24 12:13	11/13/24 18:37	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	11/08/24 12:13	11/13/24 18:37	7439-92-1	
Lithium	ND	mg/L	0.030	0.0016	1	11/08/24 12:13	11/13/24 18:37	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00062	1	11/08/24 12:13	11/13/24 18:37	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00096	1	11/08/24 12:13	11/13/24 18:37	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	11/08/24 12:13	11/13/24 18:37	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	11/19/24 08:00	11/19/24 13:41	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		11/07/24 12:33		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	ND	mg/L	5.0	5.0	1		11/14/24 18:36		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		11/14/24 18:36		
Alkalinity, Total as CaCO3	ND	mg/L	5.0	5.0	1		11/14/24 18:36		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		11/09/24 04:23	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		11/07/24 20:16	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92762188

Sample: HAM-AP1-FB-01		Lab ID: 92762188011		Collected: 11/05/24 12:32		Received: 11/06/24 14:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		11/07/24 20:16	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		11/07/24 20:16	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92762188

Sample: HAM-AP1-FD-01 Lab ID: 92762188012 Collected: 11/04/24 00:00 Received: 11/06/24 14:15 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.66	mg/L	0.040	0.025	1	11/08/24 12:32	11/08/24 20:42	7439-89-6	
Manganese	1.5	mg/L	0.040	0.011	1	11/08/24 12:32	11/08/24 20:42	7439-96-5	
Potassium	5.6	mg/L	0.50	0.15	1	11/08/24 12:32	11/08/24 20:42	7440-09-7	
Sodium	8.2	mg/L	1.0	0.58	1	11/08/24 12:32	11/08/24 20:42	7440-23-5	
Calcium	106	mg/L	1.0	0.12	1	11/08/24 12:32	11/08/24 20:42	7440-70-2	
Magnesium	14.5	mg/L	0.050	0.012	1	11/08/24 12:32	11/08/24 20:42	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00054	1	11/08/24 12:13	11/13/24 18:41	7440-36-0	
Arsenic	0.028	mg/L	0.0050	0.00084	1	11/08/24 12:13	11/13/24 18:41	7440-38-2	
Barium	0.054	mg/L	0.0050	0.00047	1	11/08/24 12:13	11/13/24 18:41	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000094	1	11/08/24 12:13	11/13/24 18:41	7440-41-7	
Boron	0.70	mg/L	0.040	0.012	1	11/08/24 12:13	11/13/24 18:41	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00010	1	11/08/24 12:13	11/13/24 18:41	7440-43-9	
Chromium	ND	mg/L	0.0050	0.0019	1	11/08/24 12:13	11/13/24 18:41	7440-47-3	
Cobalt	0.033	mg/L	0.0050	0.00032	1	11/08/24 12:13	11/13/24 18:41	7440-48-4	
Lead	ND	mg/L	0.0010	0.00016	1	11/08/24 12:13	11/13/24 18:41	7439-92-1	
Lithium	0.025J	mg/L	0.030	0.0016	1	11/08/24 12:13	11/13/24 18:41	7439-93-2	
Molybdenum	0.010	mg/L	0.010	0.00062	1	11/08/24 12:13	11/13/24 18:41	7439-98-7	
Selenium	0.0014J	mg/L	0.0050	0.00096	1	11/08/24 12:13	11/13/24 18:41	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00038	1	11/08/24 12:13	11/13/24 18:41	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	11/19/24 08:00	11/19/24 13:43	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	497	mg/L	25.0	25.0	1		11/07/24 12:34		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	102	mg/L	5.0	5.0	1		11/14/24 18:40		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		11/14/24 18:40		
Alkalinity, Total as CaCO3	102	mg/L	5.0	5.0	1		11/14/24 18:40		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		11/09/24 04:23	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	15.8	mg/L	1.0	0.60	1		11/07/24 21:02	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92762188

Sample: HAM-AP1-FD-01		Lab ID: 92762188012		Collected: 11/04/24 00:00		Received: 11/06/24 14:15		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.16	mg/L	0.10	0.050	1		11/07/24 21:02	16984-48-8	
Sulfate	190	mg/L	4.0	2.0	4		11/08/24 05:27	14808-79-8	M1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92762188

QC Batch:	894321	Analysis Method:	EPA 6010D
QC Batch Method:	EPA 3010A	Analysis Description:	6010D ATL
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92762188001, 92762188002, 92762188003, 92762188004, 92762188005, 92762188006, 92762188007, 92762188008, 92762188009, 92762188010, 92762188011, 92762188012		

METHOD BLANK:	4604089	Matrix:	Water
Associated Lab Samples:	92762188001, 92762188002, 92762188003, 92762188004, 92762188005, 92762188006, 92762188007, 92762188008, 92762188009, 92762188010, 92762188011, 92762188012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	11/08/24 19:14	
Iron	mg/L	ND	0.040	0.025	11/08/24 19:14	
Magnesium	mg/L	ND	0.050	0.012	11/08/24 19:14	
Manganese	mg/L	ND	0.040	0.011	11/08/24 19:14	
Potassium	mg/L	ND	0.50	0.15	11/08/24 19:14	
Sodium	mg/L	ND	1.0	0.58	11/08/24 19:14	

LABORATORY CONTROL SAMPLE: 4604090

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	0.98J	98	80-120	
Iron	mg/L	1	1.0	103	80-120	
Magnesium	mg/L	1	1.0	103	80-120	
Manganese	mg/L	1	0.97	97	80-120	
Potassium	mg/L	1	0.98	98	80-120	
Sodium	mg/L	1	1.0	105	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4604091 4604092

Parameter	Units	92762188001	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		Result										
Calcium	mg/L	121	1	1	123	122	206	36	75-125	1	20	M1
Iron	mg/L	6.6	1	1	7.8	7.6	120	96	75-125	3	20	
Magnesium	mg/L	17.9	1	1	19.2	18.9	133	101	75-125	2	20	M1
Manganese	mg/L	3.1	1	1	4.1	4.0	92	84	75-125	2	20	
Potassium	mg/L	5.9	1	1	7.0	6.9	113	100	75-125	2	20	
Sodium	mg/L	9.8	1	1	11.1	10.9	132	112	75-125	2	20	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1
Pace Project No.: 92762188

QC Batch:	894324	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92762188001, 92762188002, 92762188003, 92762188004, 92762188005, 92762188006, 92762188007, 92762188008, 92762188009, 92762188010, 92762188011, 92762188012		

METHOD BLANK: 4604104 Matrix: Water
Associated Lab Samples: 92762188001, 92762188002, 92762188003, 92762188004, 92762188005, 92762188006, 92762188007, 92762188008, 92762188009, 92762188010, 92762188011, 92762188012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00054	11/13/24 17:06	
Arsenic	mg/L	0.0016J	0.0050	0.00084	11/13/24 17:06	
Barium	mg/L	ND	0.0050	0.00047	11/13/24 17:06	
Beryllium	mg/L	ND	0.00050	0.000094	11/13/24 17:06	
Boron	mg/L	ND	0.040	0.012	11/13/24 17:06	
Cadmium	mg/L	ND	0.00050	0.00010	11/13/24 17:06	
Chromium	mg/L	ND	0.0050	0.0019	11/13/24 17:06	
Cobalt	mg/L	ND	0.0050	0.00032	11/13/24 17:06	
Lead	mg/L	ND	0.0010	0.00016	11/13/24 17:06	
Lithium	mg/L	ND	0.030	0.0016	11/13/24 17:06	
Molybdenum	mg/L	ND	0.010	0.00062	11/13/24 17:06	
Selenium	mg/L	ND	0.0050	0.00096	11/13/24 17:06	
Thallium	mg/L	ND	0.0010	0.00038	11/13/24 17:06	

LABORATORY CONTROL SAMPLE: 4604105

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.10	100	80-120	
Arsenic	mg/L	0.1	0.099	99	80-120	
Barium	mg/L	0.1	0.097	97	80-120	
Beryllium	mg/L	0.1	0.099	99	80-120	
Boron	mg/L	1	1.0	100	80-120	
Cadmium	mg/L	0.1	0.099	99	80-120	
Chromium	mg/L	0.1	0.097	97	80-120	
Cobalt	mg/L	0.1	0.098	98	80-120	
Lead	mg/L	0.1	0.10	101	80-120	
Lithium	mg/L	0.1	0.10	100	80-120	
Molybdenum	mg/L	0.1	0.10	102	80-120	
Selenium	mg/L	0.1	0.099	99	80-120	
Thallium	mg/L	0.1	0.099	99	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4604106 4604107

Parameter	Units	92762188002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	ND	0.1	0.1	0.11	0.10	107	103	75-125	3	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92762188

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4604106 4604107											
Parameter	Units	92762188002		MS	MSD	MS		MS	MSD	% Rec	Max
		Result	Conc.	Spike	Spike	Result	Result	% Rec	% Rec	Limits	RPD
Arsenic	mg/L	0.027	0.1	0.1	0.1	0.13	0.13	101	98	75-125	2
Barium	mg/L	0.053	0.1	0.1	0.1	0.17	0.16	114	109	75-125	3
Beryllium	mg/L	ND	0.1	0.1	0.1	0.10	0.10	100	99	75-125	0
Boron	mg/L	0.70	1	1	1	1.8	1.7	105	103	75-125	1
Cadmium	mg/L	ND	0.1	0.1	0.1	0.10	0.099	101	99	75-125	3
Chromium	mg/L	ND	0.1	0.1	0.1	0.096	0.094	96	94	75-125	2
Cobalt	mg/L	0.032	0.1	0.1	0.1	0.13	0.13	95	95	75-125	0
Lead	mg/L	ND	0.1	0.1	0.1	0.096	0.095	96	95	75-125	1
Lithium	mg/L	0.023J	0.1	0.1	0.1	0.13	0.12	102	101	75-125	1
Molybdenum	mg/L	0.0097J	0.1	0.1	0.1	0.12	0.11	106	102	75-125	3
Selenium	mg/L	0.0014J	0.1	0.1	0.1	0.10	0.099	101	98	75-125	3
Thallium	mg/L	ND	0.1	0.1	0.1	0.096	0.094	95	94	75-125	2

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92762188

QC Batch:	896849	Analysis Method:	EPA 7470A
QC Batch Method:	EPA 7470A	Analysis Description:	7470 Mercury
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92762188001, 92762188002, 92762188003, 92762188004, 92762188005, 92762188006, 92762188007, 92762188008, 92762188009, 92762188010, 92762188011, 92762188012		

METHOD BLANK:	4616941	Matrix:	Water
Associated Lab Samples:	92762188001, 92762188002, 92762188003, 92762188004, 92762188005, 92762188006, 92762188007, 92762188008, 92762188009, 92762188010, 92762188011, 92762188012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	11/19/24 12:51	

LABORATORY CONTROL SAMPLE: 4616942						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0025	101	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:					4616943	4616944							
Parameter	Units	92762188002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual	
Mercury	mg/L	ND	0.0025	0.0025	0.0026	0.0025	103	100	75-125	3	20		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92762188

QC Batch:	894298	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92762188001, 92762188002, 92762188003, 92762188004, 92762188005, 92762188007, 92762188008, 92762188009, 92762188010, 92762188011, 92762188012		

METHOD BLANK:	4603995	Matrix:	Water
Associated Lab Samples:	92762188001, 92762188002, 92762188003, 92762188004, 92762188005, 92762188007, 92762188008, 92762188009, 92762188010, 92762188011, 92762188012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	11/07/24 12:28	

LABORATORY CONTROL SAMPLE:	4603996					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	407	102	80-120	

SAMPLE DUPLICATE:	4603997					
Parameter	Units	92762188001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	542	568	5	10	

SAMPLE DUPLICATE:	4603998					
Parameter	Units	92762188011 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	ND	ND		10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92762188

QC Batch: 895288

Analysis Method: SM 2540C-2015

QC Batch Method: SM 2540C-2015

Analysis Description: 2540C Total Dissolved Solids

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92762188006

METHOD BLANK: 4608785

Matrix: Water

Associated Lab Samples: 92762188006

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	11/12/24 13:42	

LABORATORY CONTROL SAMPLE: 4608786

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	418	104	80-120	

SAMPLE DUPLICATE: 4608787

Parameter	Units	92762733002 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	1360	1350	1	10	

SAMPLE DUPLICATE: 4608788

Parameter	Units	92762733009 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	362	379	5	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92762188

QC Batch: 895260

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92762188001, 92762188002, 92762188007, 92762188008, 92762188009

METHOD BLANK: 4608680

Matrix: Water

Associated Lab Samples: 92762188001, 92762188002, 92762188007, 92762188008, 92762188009

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	11/14/24 14:11	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	11/14/24 14:11	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	11/14/24 14:11	

LABORATORY CONTROL SAMPLE: 4608681

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	49.5	99	80-120	

LABORATORY CONTROL SAMPLE: 4608682

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	50.0	100	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4608683 4608684

Parameter	Units	92762323004 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	293	50	50	339	341	91	95	80-120	1	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4608685 4608686

Parameter	Units	92762323005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	27.7	50	50	73.5	71.9	92	88	80-120	2	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92762188

QC Batch: 895261

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92762188003, 92762188004, 92762188005, 92762188006, 92762188010

METHOD BLANK: 4608687

Matrix: Water

Associated Lab Samples: 92762188003, 92762188004, 92762188005, 92762188006, 92762188010

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	11/12/24 15:34	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	11/12/24 15:34	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	11/12/24 15:34	

LABORATORY CONTROL SAMPLE: 4608688

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	50.3	101	80-120	

LABORATORY CONTROL SAMPLE: 4608689

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	48.9	98	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4608690 4608691

Parameter	Units	92762023002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	8.9	50	50	60.8	60.7	104	103	80-120	0	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4608692 4608693

Parameter	Units	92762023003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	109	50	50	159	161	102	104	80-120	1	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92762188

QC Batch: 895967

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92762188011, 92762188012

METHOD BLANK: 4611978

Matrix: Water

Associated Lab Samples: 92762188011, 92762188012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	11/14/24 18:11	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	11/14/24 18:11	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	11/14/24 18:11	

LABORATORY CONTROL SAMPLE: 4611979

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	49.5	99	80-120	

LABORATORY CONTROL SAMPLE: 4611980

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	49.8	100	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4611981 4611982

Parameter	Units	92762616004 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	24.3	50	50	74.3	74.0	100	99	80-120	0	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4611983 4611984

Parameter	Units	92762616005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	24.2	50	50	73.6	74.2	99	100	80-120	1	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92762188

QC Batch:	894848	Analysis Method:	SM 4500-S2D-2011
QC Batch Method:	SM 4500-S2D-2011	Analysis Description:	4500S2D Sulfide Water
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92762188001, 92762188002, 92762188003, 92762188004, 92762188005, 92762188006, 92762188007, 92762188008, 92762188009, 92762188010, 92762188011, 92762188012		

METHOD BLANK:	4607175	Matrix:	Water
Associated Lab Samples:	92762188001, 92762188002, 92762188003, 92762188004, 92762188005, 92762188006, 92762188007, 92762188008, 92762188009, 92762188010, 92762188011, 92762188012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	11/09/24 04:16	

LABORATORY CONTROL SAMPLE: 4607176						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.52	104	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:					4607177	4607178							
Parameter	Units	92762188001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual	
Sulfide	mg/L	ND	0.5	0.5	0.54	0.57	106	113	80-120	6	10		

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:													4607179	4607180			
Parameter	Units	92762188012 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual					
Sulfide	mg/L	ND	0.5	0.5	0.51	0.53	101	106	80-120	5	10						

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92762188

QC Batch:	894254	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92762188001, 92762188002, 92762188003, 92762188004, 92762188005, 92762188006, 92762188007, 92762188008, 92762188009, 92762188010, 92762188011		

METHOD BLANK:	4603880	Matrix:	Water
Associated Lab Samples:	92762188001, 92762188002, 92762188003, 92762188004, 92762188005, 92762188006, 92762188007, 92762188008, 92762188009, 92762188010, 92762188011		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	11/07/24 12:33	
Fluoride	mg/L	ND	0.10	0.050	11/07/24 12:33	
Sulfate	mg/L	ND	1.0	0.50	11/07/24 12:33	

LABORATORY CONTROL SAMPLE: 4603881						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	49.8	100	90-110	
Fluoride	mg/L	2.5	2.7	107	90-110	
Sulfate	mg/L	50	51.2	102	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4603882 4603883												
Parameter	Units	92762268002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	55.6	50	50	94.6	96.5	78	82	90-110	2	10	M1
Fluoride	mg/L	0.21	2.5	2.5	3.1	3.4	114	127	90-110	11	10	M1,R1
Sulfate	mg/L	125	50	50	173	176	97	102	90-110	2	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4603884 4603885												
Parameter	Units	92762188002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	15.6	50	50	65.3	65.9	99	101	90-110	1	10	
Fluoride	mg/L	0.15	2.5	2.5	2.4	2.4	90	91	90-110	1	10	
Sulfate	mg/L	187	50	50	232	233	91	92	90-110	0	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92762188

QC Batch: 894256

Analysis Method: EPA 300.0 Rev 2.1 1993

QC Batch Method: EPA 300.0 Rev 2.1 1993

Analysis Description: 300.0 IC Anions

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92762188012

METHOD BLANK: 4603887

Matrix: Water

Associated Lab Samples: 92762188012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	11/07/24 20:32	
Fluoride	mg/L	ND	0.10	0.050	11/07/24 20:32	
Sulfate	mg/L	ND	1.0	0.50	11/07/24 20:32	

LABORATORY CONTROL SAMPLE: 4603888

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	50.7	101	90-110	
Fluoride	mg/L	2.5	2.4	95	90-110	
Sulfate	mg/L	50	51.7	103	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4603889

4603890

Parameter	Units	92762188012 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	15.8	50	50	65.2	65.9	99	100	90-110	1	10	
Fluoride	mg/L	0.16	2.5	2.5	2.4	2.5	90	93	90-110	3	10	
Sulfate	mg/L	190	50	50	231	233	82	86	90-110	1	10 M1	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1
Pace Project No.: 92762188

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

B Analyte was detected in the associated method blank.
M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.
R1 RPD value was outside control limits.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92762188

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92762188001	HAM-PT-07	EPA 3010A	894321	EPA 6010D	894759
92762188002	HAM-PT-08	EPA 3010A	894321	EPA 6010D	894759
92762188003	HAM-PT-09	EPA 3010A	894321	EPA 6010D	894759
92762188004	HAM-PT-10	EPA 3010A	894321	EPA 6010D	894759
92762188005	HAM-PT-11	EPA 3010A	894321	EPA 6010D	894759
92762188006	HAM-PT-12	EPA 3010A	894321	EPA 6010D	894759
92762188007	HAM-PT-13	EPA 3010A	894321	EPA 6010D	894759
92762188008	HAM-PT-14	EPA 3010A	894321	EPA 6010D	894759
92762188009	HAM-PT-15	EPA 3010A	894321	EPA 6010D	894759
92762188010	HAM-AP1-EB-01	EPA 3010A	894321	EPA 6010D	894759
92762188011	HAM-AP1-FB-01	EPA 3010A	894321	EPA 6010D	894759
92762188012	HAM-AP1-FD-01	EPA 3010A	894321	EPA 6010D	894759
92762188001	HAM-PT-07	EPA 3005A	894324	EPA 6020B	894778
92762188002	HAM-PT-08	EPA 3005A	894324	EPA 6020B	894778
92762188003	HAM-PT-09	EPA 3005A	894324	EPA 6020B	894778
92762188004	HAM-PT-10	EPA 3005A	894324	EPA 6020B	894778
92762188005	HAM-PT-11	EPA 3005A	894324	EPA 6020B	894778
92762188006	HAM-PT-12	EPA 3005A	894324	EPA 6020B	894778
92762188007	HAM-PT-13	EPA 3005A	894324	EPA 6020B	894778
92762188008	HAM-PT-14	EPA 3005A	894324	EPA 6020B	894778
92762188009	HAM-PT-15	EPA 3005A	894324	EPA 6020B	894778
92762188010	HAM-AP1-EB-01	EPA 3005A	894324	EPA 6020B	894778
92762188011	HAM-AP1-FB-01	EPA 3005A	894324	EPA 6020B	894778
92762188012	HAM-AP1-FD-01	EPA 3005A	894324	EPA 6020B	894778
92762188001	HAM-PT-07	EPA 7470A	896849	EPA 7470A	896905
92762188002	HAM-PT-08	EPA 7470A	896849	EPA 7470A	896905
92762188003	HAM-PT-09	EPA 7470A	896849	EPA 7470A	896905
92762188004	HAM-PT-10	EPA 7470A	896849	EPA 7470A	896905
92762188005	HAM-PT-11	EPA 7470A	896849	EPA 7470A	896905
92762188006	HAM-PT-12	EPA 7470A	896849	EPA 7470A	896905
92762188007	HAM-PT-13	EPA 7470A	896849	EPA 7470A	896905
92762188008	HAM-PT-14	EPA 7470A	896849	EPA 7470A	896905
92762188009	HAM-PT-15	EPA 7470A	896849	EPA 7470A	896905
92762188010	HAM-AP1-EB-01	EPA 7470A	896849	EPA 7470A	896905
92762188011	HAM-AP1-FB-01	EPA 7470A	896849	EPA 7470A	896905
92762188012	HAM-AP1-FD-01	EPA 7470A	896849	EPA 7470A	896905
92762188001	HAM-PT-07	SM 2540C-2015	894298		
92762188002	HAM-PT-08	SM 2540C-2015	894298		
92762188003	HAM-PT-09	SM 2540C-2015	894298		
92762188004	HAM-PT-10	SM 2540C-2015	894298		
92762188005	HAM-PT-11	SM 2540C-2015	894298		
92762188006	HAM-PT-12	SM 2540C-2015	895288		
92762188007	HAM-PT-13	SM 2540C-2015	894298		
92762188008	HAM-PT-14	SM 2540C-2015	894298		
92762188009	HAM-PT-15	SM 2540C-2015	894298		
92762188010	HAM-AP1-EB-01	SM 2540C-2015	894298		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92762188

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92762188011	HAM-AP1-FB-01	SM 2540C-2015	894298		
92762188012	HAM-AP1-FD-01	SM 2540C-2015	894298		
92762188001	HAM-PT-07	SM 2320B-2011	895260		
92762188002	HAM-PT-08	SM 2320B-2011	895260		
92762188003	HAM-PT-09	SM 2320B-2011	895261		
92762188004	HAM-PT-10	SM 2320B-2011	895261		
92762188005	HAM-PT-11	SM 2320B-2011	895261		
92762188006	HAM-PT-12	SM 2320B-2011	895261		
92762188007	HAM-PT-13	SM 2320B-2011	895260		
92762188008	HAM-PT-14	SM 2320B-2011	895260		
92762188009	HAM-PT-15	SM 2320B-2011	895260		
92762188010	HAM-AP1-EB-01	SM 2320B-2011	895261		
92762188011	HAM-AP1-FB-01	SM 2320B-2011	895967		
92762188012	HAM-AP1-FD-01	SM 2320B-2011	895967		
92762188001	HAM-PT-07	SM 4500-S2D-2011	894848		
92762188002	HAM-PT-08	SM 4500-S2D-2011	894848		
92762188003	HAM-PT-09	SM 4500-S2D-2011	894848		
92762188004	HAM-PT-10	SM 4500-S2D-2011	894848		
92762188005	HAM-PT-11	SM 4500-S2D-2011	894848		
92762188006	HAM-PT-12	SM 4500-S2D-2011	894848		
92762188007	HAM-PT-13	SM 4500-S2D-2011	894848		
92762188008	HAM-PT-14	SM 4500-S2D-2011	894848		
92762188009	HAM-PT-15	SM 4500-S2D-2011	894848		
92762188010	HAM-AP1-EB-01	SM 4500-S2D-2011	894848		
92762188011	HAM-AP1-FB-01	SM 4500-S2D-2011	894848		
92762188012	HAM-AP1-FD-01	SM 4500-S2D-2011	894848		
92762188001	HAM-PT-07	EPA 300.0 Rev 2.1 1993	894254		
92762188002	HAM-PT-08	EPA 300.0 Rev 2.1 1993	894254		
92762188003	HAM-PT-09	EPA 300.0 Rev 2.1 1993	894254		
92762188004	HAM-PT-10	EPA 300.0 Rev 2.1 1993	894254		
92762188005	HAM-PT-11	EPA 300.0 Rev 2.1 1993	894254		
92762188006	HAM-PT-12	EPA 300.0 Rev 2.1 1993	894254		
92762188007	HAM-PT-13	EPA 300.0 Rev 2.1 1993	894254		
92762188008	HAM-PT-14	EPA 300.0 Rev 2.1 1993	894254		
92762188009	HAM-PT-15	EPA 300.0 Rev 2.1 1993	894254		
92762188010	HAM-AP1-EB-01	EPA 300.0 Rev 2.1 1993	894254		
92762188011	HAM-AP1-FB-01	EPA 300.0 Rev 2.1 1993	894254		
92762188012	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	894256		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CHAIN-OF-CUSTODY / Analytical Request Doc

The Chain of Custody is a LEGAL DOCUMENT. All relevant fields must be completed at

WO#: 92762188



92762188

Section C

Invoice Information

Attention: Southern Co

Company Name

Address

Pace Order Reference

Pace Project Manager

Pace Profile #

16483

Section B

Required Project Information

Report To: SCS Contacts

Copy To: Geosyntec Contacts

Purchase Order No: GPC82474-0001

Project Name: Hammond AP-1

Project Number:

Section A

Required Client Information

Company: GA Power

Address: Atlanta, GA

Email To: SCS Contacts

Phone: [Redacted]

Requested Due Date/TAT: 10 Day

REGULATORY AGENCY

NPDES ☐ GROUND WATER ☐ DRINKING WATER ☐

UST ☐ RCRA ☒ OTHER CCR ☐

Site Location

STATE: GA

Requested Analysis Filtered (Y/N)

ITEM #	Valid Matrix Codes MATRIX CODE WATER WASTE WATER PRODUCT SOLID OIL WIRE OTHER TSS	Valid Matrix Codes CODE W1 W2 P S O W O T	COLLECTED DATE TIME	DATE TIME	SAMPLE TYPE (G=GRAB C=COMPO)	RELINQUISHED BY / AFFILIATION	DATE	TIME	ACCEPTED BY / AFFILIATION	DATE	TIME	SAMPLE CONDITIONS	Temp in °C	Received on	Custody Sealed Cooler (Y/N)	Samples Intact (Y/N)
1	HAM-PT-07		11/14/2024	1234	WG G	Geosyntec / Pace	11/14/2024	1330	Y	11/14/2024	1330					
2	HAM-PT-08		11/14/2024	1214	WG G	Geosyntec / Pace	11/14/2024	1330	Y	11/14/2024	1330					
3	HAM-PT-09		11/15/2024	1154	WG G	Geosyntec / Pace	11/15/2024	1415	Y	11/15/2024	1415					
4	HAM-PT-10		11/15/2024	0929	WG G	Geosyntec / Pace	11/15/2024	1415	Y	11/15/2024	1415					
5	HAM-PT-11		11/15/2024	0925	WG G	Geosyntec / Pace	11/15/2024	1415	Y	11/15/2024	1415					
6	HAM-PT-12		11/15/2024	1144	WG G	Geosyntec / Pace	11/15/2024	1415	Y	11/15/2024	1415					
7	HAM-PT-13		11/14/2024	1105	WG G	Geosyntec / Pace	11/14/2024	1415	Y	11/14/2024	1415					
8	HAM-PT-14		11/14/2024	1450	WG G	Geosyntec / Pace	11/14/2024	1415	Y	11/14/2024	1415					
9	HAM-PT-15		11/14/2024	1401	WG G	Geosyntec / Pace	11/14/2024	1415	Y	11/14/2024	1415					
10	HAM-API-EB-01		11/15/2024	1236	WQ G	Geosyntec / Pace	11/15/2024	1415	Y	11/15/2024	1415					
11	HAM-API-FB-01	C.H.	11/15/2024	1232	WQ G	Geosyntec / Pace	11/15/2024	1415	Y	11/15/2024	1415					
12	HAM-API-FD-01	* 11/14/2024	11/14/2024	0900	WQ G	Geosyntec / Pace	11/14/2024	1415	Y	11/14/2024	1415					

SAMPLER NAME AND SIGNATURE

PRINT Name of SAMPLER: Tristan Halterman, Zain Webb / Geosyntec Consultants, Inc.

SIGNATURE of SAMPLER: [Signature]

DATE SIGNED (MM/DD/YYYY): 11/16/24

DATE SIGNED (MM/DD/YYYY): 11/16/24

DATE SIGNED (MM/DD/YYYY): 11/16/24

DATE SIGNED (MM/DD/YYYY): 11/16/24

DATE SIGNED (MM/DD/YYYY): 11/16/24

F-ALL-Q-020rev.07, 15-Feb-2007



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

George Power

Project #:

WO#: 92762188

PM: BV

Due Date: 11/21/24

CLIENT: 92- GP-HAM

Courier:

☐ Commercial☐ Fed Ex☐ UPS☐ USPS☐ Client☒ Pace☐ Other:Custody Seal Present? ☐ Yes☒ No

Seals Intact?

☐ Yes☐ No☒ N/A

Date/Initials Person Examining Contents: 11/8/24

COA

Packing Material:

☐ Bubble Wrap☐ Bubble Bags☒ None☐ Other

Biological Tissue Frozen?

☐ Yes ☐ No ☒ N/A

Thermometer:

☒ IR Gun ID:

083

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

3.9

Correction Factor:

Add/Subtract (°C)

0.0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

3.9

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

				Comments/Discrepancy:
Chain of Custody Present?	☒ Yes	☐ No	☐ N/A	1.
Samples Arrived within Hold Time?	☒ Yes	☐ No	☐ N/A	2.
Short Hold Time Analysis (<72 hr.)?	☐ Yes	☒ No	☐ N/A	3.
Rush Turn Around Time Requested?	☐ Yes	☒ No	☐ N/A	4.
Sufficient Volume?	☒ Yes	☐ No	☐ N/A	5.
Correct Containers Used?	☒ Yes	☐ No	☐ N/A	6.
-Pace Containers Used?	☒ Yes	☐ No	☐ N/A	
Containers Intact?	☒ Yes	☐ No	☐ N/A	7.
Dissolved analysis: Samples Field Filtered?	☐ Yes	☐ No	☒ N/A	8.
Sample Labels Match COC?	☒ Yes	☐ No	☐ N/A	9.
-Includes Date/Time/ID/Analysis Matrix: W				
Headspace in VOA Vials (>5-6mm)?	☐ Yes	☐ No	☒ N/A	10.
Trip Blank Present?	☐ Yes	☐ No	☒ N/A	11.
Trip Blank Custody Seals Present?	☐ Yes	☐ No	☒ N/A	

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

WO#: 92762188

Project # PM: BV Due Date: 11/21/24
CLIENT: 92- GP-HAM

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐

Client _____ Profile/EZ (Circle one) _____ Notes _____

Item#	CC	1	2	3	4	5	6	7	8	9	10	11	12	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic ZN Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGFU-Wide-mouthed Glass jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG9U-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG8T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit)-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)	BP3R-250 mL Plastic (NH4)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	V5GU-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers).



December 18, 2024

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1
Pace Project No.: 92767477

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on December 05, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Peachtree Corners, GA

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Jamie Newsome, Geosyntec Consultants
Zain Webb, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1

Pace Project No.: 92767477

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1

Pace Project No.: 92767477

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92767477001	HAM-PT-07	Water	12/02/24 15:01	12/05/24 11:35
92767477002	HAM-PT-08	Water	12/02/24 12:18	12/05/24 11:35
92767477003	HAM-PT-09	Water	12/03/24 13:20	12/05/24 11:35
92767477004	HAM-PT-10	Water	12/03/24 11:57	12/05/24 11:35
92767477005	HAM-PT-11	Water	12/03/24 14:37	12/05/24 11:35
92767477006	HAM-PT-12	Water	12/03/24 13:57	12/05/24 11:35
92767477007	HAM-PT-13	Water	12/02/24 13:17	12/05/24 11:35
92767477008	HAM-PT-14	Water	12/02/24 14:35	12/05/24 11:35
92767477009	HAM-PT-15	Water	12/02/24 16:25	12/05/24 11:35
92767477010	HAM-AP1-EB-01	Water	12/03/24 15:50	12/05/24 11:35
92767477011	HAM-AP1-FB-01	Water	12/03/24 15:45	12/05/24 11:35
92767477012	HAM-AP1-FD-01	Water	12/03/24 00:00	12/05/24 11:35

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92767477

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92767477001	HAM-PT-07	EPA 6010D	MJS2	6
		EPA 6020B	CW1, MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92767477002	HAM-PT-08	EPA 6010D	MJS2	6
		EPA 6020B	CW1, MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92767477003	HAM-PT-09	EPA 6010D	MJS2	6
		EPA 6020B	CW1, MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92767477004	HAM-PT-10	EPA 6010D	MJS2	6
		EPA 6020B	CW1, MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92767477005	HAM-PT-11	EPA 6010D	MJS2	6
		EPA 6020B	CW1, MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92767477006	HAM-PT-12	EPA 6010D	MJS2	6
		EPA 6020B	CW1, MT1	13

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92767477

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92767477007	HAM-PT-13	EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6010D	MJS2	6
		EPA 6020B	CW1, MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92767477008	HAM-PT-14	EPA 6010D	MJS2	6
		EPA 6020B	CW1, MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	MJS2	6
		EPA 6020B	CW1, MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
92767477009	HAM-PT-15	SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	MJS2	6
		EPA 6020B	CW1, MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	MJS2	6
		EPA 6020B	CW1, MT1	13
		EPA 7470A	VB	1
92767477010	HAM-AP1-EB-01	SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	MJS2	6
		EPA 6020B	CW1, MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	MJS2	6
92767477011	HAM-AP1-FB-01	EPA 6020B	CW1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		EPA 6010D	MJS2	6

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92767477

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92767477012	HAM-AP1-FD-01	SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3
		EPA 6010D	MJS2	6
		EPA 6020B	CW1, MT1	13
		EPA 7470A	VB	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	YEG	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	JCM	3

PASI-A = Pace Analytical Services - Asheville

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92767477

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92767477001	HAM-PT-07					
EPA 6010D	Iron	7.7	mg/L	0.040	12/06/24 03:47	M1
EPA 6010D	Manganese	3.4	mg/L	0.040	12/06/24 03:47	
EPA 6010D	Potassium	6.0	mg/L	0.50	12/06/24 03:47	
EPA 6010D	Sodium	8.5	mg/L	1.0	12/06/24 03:47	
EPA 6010D	Calcium	129	mg/L	1.0	12/06/24 03:47	
EPA 6010D	Magnesium	17.7	mg/L	0.050	12/06/24 03:47	
EPA 6020B	Arsenic	0.15	mg/L	0.0050	12/09/24 20:19	
EPA 6020B	Barium	0.047	mg/L	0.0050	12/09/24 20:19	
EPA 6020B	Beryllium	0.000071J	mg/L	0.00050	12/09/24 20:19	
EPA 6020B	Boron	0.72	mg/L	0.050	12/10/24 16:43	
EPA 6020B	Cadmium	0.00012J	mg/L	0.00050	12/09/24 20:19	
EPA 6020B	Chromium	0.00032J	mg/L	0.0050	12/09/24 20:19	
EPA 6020B	Cobalt	0.048	mg/L	0.0050	12/09/24 20:19	
EPA 6020B	Lithium	0.050	mg/L	0.030	12/09/24 20:19	
EPA 6020B	Molybdenum	0.011	mg/L	0.010	12/09/24 20:19	
EPA 6020B	Selenium	0.00097J	mg/L	0.0050	12/09/24 20:19	
EPA 6020B	Thallium	0.00024J	mg/L	0.0010	12/09/24 20:19	
SM 2540C-2015	Total Dissolved Solids	528	mg/L	25.0	12/06/24 12:08	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	150	mg/L	5.0	12/09/24 17:32	
SM 2320B-2011	Alkalinity, Total as CaCO3	150	mg/L	5.0	12/09/24 17:32	
EPA 300.0 Rev 2.1 1993	Chloride	16.5	mg/L	1.0	12/06/24 12:07	
EPA 300.0 Rev 2.1 1993	Fluoride	0.35	mg/L	0.10	12/06/24 12:07	
EPA 300.0 Rev 2.1 1993	Sulfate	192	mg/L	4.0	12/06/24 18:02	
92767477002	HAM-PT-08					
EPA 6010D	Iron	0.32	mg/L	0.040	12/06/24 04:07	
EPA 6010D	Manganese	1.5	mg/L	0.040	12/06/24 04:07	
EPA 6010D	Potassium	6.0	mg/L	0.50	12/06/24 04:07	
EPA 6010D	Sodium	7.4	mg/L	1.0	12/06/24 04:07	
EPA 6010D	Calcium	111	mg/L	1.0	12/06/24 04:07	
EPA 6010D	Magnesium	14.3	mg/L	0.050	12/06/24 04:07	
EPA 6020B	Arsenic	0.010	mg/L	0.0050	12/09/24 20:31	
EPA 6020B	Barium	0.052	mg/L	0.0050	12/09/24 20:31	
EPA 6020B	Beryllium	0.000070J	mg/L	0.00050	12/09/24 20:31	
EPA 6020B	Boron	0.85	mg/L	0.050	12/10/24 16:47	
EPA 6020B	Chromium	0.00040J	mg/L	0.0050	12/09/24 20:31	
EPA 6020B	Cobalt	0.048	mg/L	0.0050	12/09/24 20:31	
EPA 6020B	Lithium	0.020J	mg/L	0.030	12/09/24 20:31	
EPA 6020B	Molybdenum	0.0068J	mg/L	0.010	12/09/24 20:31	
EPA 6020B	Selenium	0.0012J	mg/L	0.0050	12/09/24 20:31	
SM 2540C-2015	Total Dissolved Solids	451	mg/L	25.0	12/06/24 12:08	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	84.2	mg/L	5.0	12/09/24 17:50	
SM 2320B-2011	Alkalinity, Total as CaCO3	84.2	mg/L	5.0	12/09/24 17:50	
EPA 300.0 Rev 2.1 1993	Chloride	17.5	mg/L	1.0	12/06/24 12:22	
EPA 300.0 Rev 2.1 1993	Fluoride	0.14	mg/L	0.10	12/06/24 12:22	
EPA 300.0 Rev 2.1 1993	Sulfate	187	mg/L	4.0	12/06/24 18:17	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92767477

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92767477003	HAM-PT-09					
EPA 6010D	Iron	0.049	mg/L	0.040	12/06/24 04:12	
EPA 6010D	Manganese	0.37	mg/L	0.040	12/06/24 04:12	
EPA 6010D	Potassium	6.9	mg/L	0.50	12/06/24 04:12	
EPA 6010D	Sodium	10.1	mg/L	1.0	12/06/24 04:12	
EPA 6010D	Calcium	116	mg/L	1.0	12/06/24 04:12	
EPA 6010D	Magnesium	23.1	mg/L	0.050	12/06/24 04:12	
EPA 6020B	Arsenic	0.0020J	mg/L	0.0050	12/09/24 20:35	
EPA 6020B	Barium	0.066	mg/L	0.0050	12/09/24 20:35	
EPA 6020B	Beryllium	0.000030J	mg/L	0.00050	12/09/24 20:35	
EPA 6020B	Boron	1.6	mg/L	0.050	12/10/24 16:51	
EPA 6020B	Cadmium	0.00024J	mg/L	0.00050	12/09/24 20:35	
EPA 6020B	Chromium	0.00037J	mg/L	0.0050	12/09/24 20:35	
EPA 6020B	Cobalt	0.0028J	mg/L	0.0050	12/09/24 20:35	
EPA 6020B	Lithium	0.0025J	mg/L	0.030	12/09/24 20:35	
EPA 6020B	Molybdenum	0.25	mg/L	0.010	12/09/24 20:35	
EPA 6020B	Selenium	0.00096J	mg/L	0.0050	12/09/24 20:35	
SM 2540C-2015	Total Dissolved Solids	521	mg/L	25.0	12/09/24 11:55	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	121	mg/L	5.0	12/09/24 19:21	
SM 2320B-2011	Alkalinity, Total as CaCO3	121	mg/L	5.0	12/09/24 19:21	
EPA 300.0 Rev 2.1 1993	Chloride	48.3	mg/L	1.0	12/06/24 12:37	
EPA 300.0 Rev 2.1 1993	Fluoride	0.40	mg/L	0.10	12/06/24 12:37	
EPA 300.0 Rev 2.1 1993	Sulfate	157	mg/L	3.0	12/06/24 18:31	
92767477004	HAM-PT-10					
EPA 6010D	Manganese	0.37	mg/L	0.040	12/06/24 04:27	
EPA 6010D	Potassium	7.1	mg/L	0.50	12/06/24 04:27	
EPA 6010D	Sodium	8.8	mg/L	1.0	12/06/24 04:27	
EPA 6010D	Calcium	114	mg/L	1.0	12/06/24 04:27	
EPA 6010D	Magnesium	13.8	mg/L	0.050	12/06/24 04:27	
EPA 6020B	Barium	0.047	mg/L	0.0050	12/09/24 20:39	
EPA 6020B	Boron	1.7	mg/L	0.050	12/10/24 16:55	
EPA 6020B	Cadmium	0.00015J	mg/L	0.00050	12/09/24 20:39	
EPA 6020B	Chromium	0.00025J	mg/L	0.0050	12/09/24 20:39	
EPA 6020B	Cobalt	0.0015J	mg/L	0.0050	12/09/24 20:39	
EPA 6020B	Lithium	0.0010J	mg/L	0.030	12/09/24 20:39	
EPA 6020B	Molybdenum	0.18	mg/L	0.010	12/09/24 20:39	
EPA 6020B	Selenium	0.00095J	mg/L	0.0050	12/09/24 20:39	
SM 2540C-2015	Total Dissolved Solids	470	mg/L	25.0	12/09/24 11:55	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	118	mg/L	5.0	12/09/24 19:29	
SM 2320B-2011	Alkalinity, Total as CaCO3	118	mg/L	5.0	12/09/24 19:29	
EPA 300.0 Rev 2.1 1993	Chloride	46.1	mg/L	1.0	12/06/24 12:52	
EPA 300.0 Rev 2.1 1993	Fluoride	0.27	mg/L	0.10	12/06/24 12:52	
EPA 300.0 Rev 2.1 1993	Sulfate	130	mg/L	3.0	12/06/24 18:46	
92767477005	HAM-PT-11					
EPA 6010D	Iron	0.17	mg/L	0.040	12/06/24 04:32	
EPA 6010D	Manganese	0.45	mg/L	0.040	12/06/24 04:32	
EPA 6010D	Potassium	7.2	mg/L	0.50	12/06/24 04:32	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92767477

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92767477005	HAM-PT-11					
EPA 6010D	Sodium	9.5	mg/L	1.0	12/06/24 04:32	
EPA 6010D	Calcium	120	mg/L	1.0	12/06/24 04:32	
EPA 6010D	Magnesium	16.9	mg/L	0.050	12/06/24 04:32	
EPA 6020B	Barium	0.067	mg/L	0.0050	12/09/24 20:43	
EPA 6020B	Boron	1.6	mg/L	0.050	12/10/24 16:59	
EPA 6020B	Cadmium	0.00015J	mg/L	0.00050	12/09/24 20:43	
EPA 6020B	Chromium	0.00045J	mg/L	0.0050	12/09/24 20:43	
EPA 6020B	Cobalt	0.0044J	mg/L	0.0050	12/09/24 20:43	
EPA 6020B	Lithium	0.0027J	mg/L	0.030	12/09/24 20:43	
EPA 6020B	Molybdenum	0.12	mg/L	0.010	12/09/24 20:43	
EPA 6020B	Selenium	0.00092J	mg/L	0.0050	12/09/24 20:43	
SM 2540C-2015	Total Dissolved Solids	486	mg/L	25.0	12/09/24 11:55	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	122	mg/L	5.0	12/09/24 19:38	
SM 2320B-2011	Alkalinity, Total as CaCO3	122	mg/L	5.0	12/09/24 19:38	
EPA 300.0 Rev 2.1 1993	Chloride	44.0	mg/L	1.0	12/06/24 13:07	
EPA 300.0 Rev 2.1 1993	Fluoride	0.31	mg/L	0.10	12/06/24 13:07	
EPA 300.0 Rev 2.1 1993	Sulfate	139	mg/L	3.0	12/06/24 19:01	
92767477006	HAM-PT-12					
EPA 6010D	Iron	0.33	mg/L	0.040	12/06/24 04:37	
EPA 6010D	Manganese	0.86	mg/L	0.040	12/06/24 04:37	
EPA 6010D	Potassium	6.1	mg/L	0.50	12/06/24 04:37	
EPA 6010D	Sodium	10.9	mg/L	1.0	12/06/24 04:37	
EPA 6010D	Calcium	105	mg/L	1.0	12/06/24 04:37	
EPA 6010D	Magnesium	28.7	mg/L	0.050	12/06/24 04:37	
EPA 6020B	Arsenic	0.0027J	mg/L	0.0050	12/09/24 20:47	
EPA 6020B	Barium	0.062	mg/L	0.0050	12/09/24 20:47	
EPA 6020B	Beryllium	0.000057J	mg/L	0.00050	12/09/24 20:47	
EPA 6020B	Boron	1.6	mg/L	0.050	12/10/24 17:03	
EPA 6020B	Cadmium	0.00028J	mg/L	0.00050	12/09/24 20:47	
EPA 6020B	Chromium	0.00067J	mg/L	0.0050	12/09/24 20:47	
EPA 6020B	Cobalt	0.0035J	mg/L	0.0050	12/09/24 20:47	
EPA 6020B	Lead	0.000093J	mg/L	0.0010	12/09/24 20:47	
EPA 6020B	Lithium	0.0023J	mg/L	0.030	12/09/24 20:47	
EPA 6020B	Molybdenum	0.16	mg/L	0.010	12/09/24 20:47	
SM 2540C-2015	Total Dissolved Solids	526	mg/L	25.0	12/09/24 11:55	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	116	mg/L	5.0	12/09/24 19:47	
SM 2320B-2011	Alkalinity, Total as CaCO3	116	mg/L	5.0	12/09/24 19:47	
EPA 300.0 Rev 2.1 1993	Chloride	44.2	mg/L	1.0	12/06/24 13:22	
EPA 300.0 Rev 2.1 1993	Fluoride	0.30	mg/L	0.10	12/06/24 13:22	
EPA 300.0 Rev 2.1 1993	Sulfate	179	mg/L	4.0	12/06/24 19:15	
92767477007	HAM-PT-13					
EPA 6010D	Iron	9.5	mg/L	0.040	12/06/24 04:41	
EPA 6010D	Manganese	3.0	mg/L	0.040	12/06/24 04:41	
EPA 6010D	Potassium	6.1	mg/L	0.50	12/06/24 04:41	
EPA 6010D	Sodium	10.1	mg/L	1.0	12/06/24 04:41	
EPA 6010D	Calcium	129	mg/L	1.0	12/06/24 04:41	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92767477

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92767477007	HAM-PT-13					
EPA 6010D	Magnesium	17.8	mg/L	0.050	12/06/24 04:41	
EPA 6020B	Arsenic	0.19	mg/L	0.0050	12/09/24 20:51	
EPA 6020B	Barium	0.047	mg/L	0.0050	12/09/24 20:51	
EPA 6020B	Beryllium	0.000082J	mg/L	0.00050	12/09/24 20:51	
EPA 6020B	Boron	0.70	mg/L	0.050	12/10/24 17:36	
EPA 6020B	Cadmium	0.000054J	mg/L	0.00050	12/09/24 20:51	
EPA 6020B	Chromium	0.00039J	mg/L	0.0050	12/09/24 20:51	
EPA 6020B	Cobalt	0.023	mg/L	0.0050	12/09/24 20:51	
EPA 6020B	Lead	0.00011J	mg/L	0.0010	12/09/24 20:51	
EPA 6020B	Lithium	0.058	mg/L	0.030	12/09/24 20:51	
EPA 6020B	Molybdenum	0.0085J	mg/L	0.010	12/09/24 20:51	
EPA 6020B	Selenium	0.0011J	mg/L	0.0050	12/09/24 20:51	
EPA 6020B	Thallium	0.00023J	mg/L	0.0010	12/09/24 20:51	
SM 2540C-2015	Total Dissolved Solids	528	mg/L	25.0	12/06/24 12:08	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	145	mg/L	5.0	12/09/24 17:58	
SM 2320B-2011	Alkalinity, Total as CaCO3	145	mg/L	5.0	12/09/24 17:58	
EPA 300.0 Rev 2.1 1993	Chloride	18.6	mg/L	1.0	12/06/24 13:37	
EPA 300.0 Rev 2.1 1993	Fluoride	0.37	mg/L	0.10	12/06/24 13:37	
EPA 300.0 Rev 2.1 1993	Sulfate	200	mg/L	4.0	12/06/24 19:30	
92767477008	HAM-PT-14					
EPA 6010D	Iron	14.2	mg/L	0.040	12/06/24 16:54	
EPA 6010D	Manganese	2.9	mg/L	0.040	12/06/24 16:54	
EPA 6010D	Potassium	6.1	mg/L	0.50	12/06/24 16:54	
EPA 6010D	Sodium	8.0	mg/L	1.0	12/06/24 16:54	
EPA 6010D	Calcium	137	mg/L	1.0	12/06/24 16:54	
EPA 6010D	Magnesium	18.9	mg/L	0.050	12/06/24 16:54	
EPA 6020B	Arsenic	0.27	mg/L	0.0050	12/09/24 20:55	
EPA 6020B	Barium	0.043	mg/L	0.0050	12/09/24 20:55	
EPA 6020B	Beryllium	0.000056J	mg/L	0.00050	12/09/24 20:55	
EPA 6020B	Boron	0.74	mg/L	0.050	12/10/24 17:40	
EPA 6020B	Chromium	0.00036J	mg/L	0.0050	12/09/24 20:55	
EPA 6020B	Cobalt	0.024	mg/L	0.0050	12/09/24 20:55	
EPA 6020B	Lead	0.00015J	mg/L	0.0010	12/09/24 20:55	
EPA 6020B	Lithium	0.054	mg/L	0.030	12/09/24 20:55	
EPA 6020B	Molybdenum	0.016	mg/L	0.010	12/09/24 20:55	
EPA 6020B	Selenium	0.0010J	mg/L	0.0050	12/09/24 20:55	
SM 2540C-2015	Total Dissolved Solids	560	mg/L	25.0	12/06/24 12:09	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	149	mg/L	5.0	12/09/24 18:08	
SM 2320B-2011	Alkalinity, Total as CaCO3	149	mg/L	5.0	12/09/24 18:08	
EPA 300.0 Rev 2.1 1993	Chloride	17.8	mg/L	1.0	12/06/24 19:26	
EPA 300.0 Rev 2.1 1993	Fluoride	0.31	mg/L	0.10	12/06/24 19:26	
EPA 300.0 Rev 2.1 1993	Sulfate	184	mg/L	5.0	12/06/24 20:44	
92767477009	HAM-PT-15					
EPA 6010D	Iron	0.38	mg/L	0.040	12/06/24 04:51	
EPA 6010D	Manganese	2.4	mg/L	0.040	12/06/24 04:51	
EPA 6010D	Potassium	6.1	mg/L	0.50	12/06/24 04:51	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92767477

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92767477009	HAM-PT-15					
EPA 6010D	Sodium	9.3	mg/L	1.0	12/06/24 04:51	
EPA 6010D	Calcium	129	mg/L	1.0	12/06/24 04:51	
EPA 6010D	Magnesium	14.6	mg/L	0.050	12/06/24 04:51	
EPA 6020B	Antimony	0.00063J	mg/L	0.0030	12/09/24 20:59	
EPA 6020B	Arsenic	0.024	mg/L	0.0050	12/09/24 20:59	
EPA 6020B	Barium	0.051	mg/L	0.0050	12/09/24 20:59	
EPA 6020B	Beryllium	0.000062J	mg/L	0.00050	12/09/24 20:59	
EPA 6020B	Boron	0.86	mg/L	0.050	12/10/24 17:44	
EPA 6020B	Cadmium	0.00025J	mg/L	0.00050	12/09/24 20:59	
EPA 6020B	Chromium	0.00026J	mg/L	0.0050	12/09/24 20:59	
EPA 6020B	Cobalt	0.025	mg/L	0.0050	12/09/24 20:59	
EPA 6020B	Lithium	0.041	mg/L	0.030	12/09/24 20:59	
EPA 6020B	Molybdenum	0.015	mg/L	0.010	12/09/24 20:59	
EPA 6020B	Selenium	0.0017J	mg/L	0.0050	12/09/24 20:59	
EPA 6020B	Thallium	0.00044J	mg/L	0.0010	12/09/24 20:59	
SM 2540C-2015	Total Dissolved Solids	497	mg/L	25.0	12/06/24 12:09	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	141	mg/L	5.0	12/09/24 18:18	
SM 2320B-2011	Alkalinity, Total as CaCO3	141	mg/L	5.0	12/09/24 18:18	
EPA 300.0 Rev 2.1 1993	Chloride	17.4	mg/L	1.0	12/06/24 19:42	
EPA 300.0 Rev 2.1 1993	Fluoride	0.37	mg/L	0.10	12/06/24 19:42	
EPA 300.0 Rev 2.1 1993	Sulfate	175	mg/L	4.0	12/06/24 21:31	
92767477010	HAM-AP1-EB-01					
EPA 6010D	Iron	0.037J	mg/L	0.040	12/06/24 05:01	
EPA 6010D	Sodium	1.1	mg/L	1.0	12/06/24 05:01	
EPA 6010D	Calcium	0.62J	mg/L	1.0	12/06/24 05:01	
EPA 6010D	Magnesium	0.14	mg/L	0.050	12/06/24 05:01	
EPA 6020B	Barium	0.0037J	mg/L	0.0050	12/10/24 16:14	
EPA 6020B	Chromium	0.00078J	mg/L	0.0050	12/09/24 21:07	
EPA 6020B	Lead	0.00047J	mg/L	0.0010	12/09/24 21:07	
SM 2540C-2015	Total Dissolved Solids	40.0	mg/L	25.0	12/09/24 11:56	
92767477011	HAM-AP1-FB-01					
EPA 6010D	Calcium	0.18J	mg/L	1.0	12/06/24 05:06	
EPA 6010D	Magnesium	0.027J	mg/L	0.050	12/06/24 05:06	
EPA 6020B	Barium	0.00084J	mg/L	0.0050	12/09/24 21:19	
EPA 6020B	Boron	0.018J	mg/L	0.050	12/09/24 21:19	
EPA 6020B	Chromium	0.00033J	mg/L	0.0050	12/09/24 21:19	
EPA 6020B	Lead	0.00010J	mg/L	0.0010	12/09/24 21:19	
92767477012	HAM-AP1-FD-01					
EPA 6010D	Iron	0.029J	mg/L	0.040	12/06/24 05:11	
EPA 6010D	Manganese	0.37	mg/L	0.040	12/06/24 05:11	
EPA 6010D	Potassium	7.1	mg/L	0.50	12/06/24 05:11	
EPA 6010D	Sodium	8.9	mg/L	1.0	12/06/24 05:11	
EPA 6010D	Calcium	113	mg/L	1.0	12/06/24 05:11	
EPA 6010D	Magnesium	13.8	mg/L	0.050	12/06/24 05:11	
EPA 6020B	Barium	0.047	mg/L	0.0050	12/09/24 21:23	
EPA 6020B	Boron	1.8	mg/L	0.25	12/11/24 13:45	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92767477

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92767477012	HAM-AP1-FD-01					
EPA 6020B	Cadmium	0.00013J	mg/L	0.00050	12/09/24 21:23	
EPA 6020B	Chromium	0.00030J	mg/L	0.0050	12/09/24 21:23	
EPA 6020B	Cobalt	0.0015J	mg/L	0.0050	12/09/24 21:23	
EPA 6020B	Lithium	0.0010J	mg/L	0.030	12/09/24 21:23	
EPA 6020B	Molybdenum	0.17	mg/L	0.010	12/09/24 21:23	
EPA 6020B	Selenium	0.0012J	mg/L	0.0050	12/09/24 21:23	
SM 2540C-2015	Total Dissolved Solids	468	mg/L	25.0	12/09/24 11:57	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	121	mg/L	5.0	12/09/24 20:13	
SM 2320B-2011	Alkalinity, Total as CaCO3	121	mg/L	5.0	12/09/24 20:13	
EPA 300.0 Rev 2.1 1993	Chloride	46.0	mg/L	1.0	12/07/24 18:43	
EPA 300.0 Rev 2.1 1993	Fluoride	0.29	mg/L	0.10	12/07/24 18:43	
EPA 300.0 Rev 2.1 1993	Sulfate	132	mg/L	3.0	12/08/24 04:55	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92767477

Sample: HAM-PT-07 Lab ID: 92767477001 Collected: 12/02/24 15:01 Received: 12/05/24 11:35 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	7.7	mg/L	0.040	0.025	1	12/05/24 17:27	12/06/24 03:47	7439-89-6	M1
Manganese	3.4	mg/L	0.040	0.011	1	12/05/24 17:27	12/06/24 03:47	7439-96-5	
Potassium	6.0	mg/L	0.50	0.15	1	12/05/24 17:27	12/06/24 03:47	7440-09-7	
Sodium	8.5	mg/L	1.0	0.58	1	12/05/24 17:27	12/06/24 03:47	7440-23-5	
Calcium	129	mg/L	1.0	0.12	1	12/05/24 17:27	12/06/24 03:47	7440-70-2	
Magnesium	17.7	mg/L	0.050	0.012	1	12/05/24 17:27	12/06/24 03:47	7439-95-4	
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00038	1	12/05/24 17:00	12/09/24 20:19	7440-36-0	
Arsenic	0.15	mg/L	0.0050	0.0016	1	12/05/24 17:00	12/09/24 20:19	7440-38-2	
Barium	0.047	mg/L	0.0050	0.00019	1	12/05/24 17:00	12/09/24 20:19	7440-39-3	
Beryllium	0.000071J	mg/L	0.00050	0.000026	1	12/05/24 17:00	12/09/24 20:19	7440-41-7	
Boron	0.72	mg/L	0.050	0.014	1	12/05/24 17:00	12/10/24 16:43	7440-42-8	
Cadmium	0.00012J	mg/L	0.00050	0.000041	1	12/05/24 17:00	12/09/24 20:19	7440-43-9	
Chromium	0.00032J	mg/L	0.0050	0.00015	1	12/05/24 17:00	12/09/24 20:19	7440-47-3	
Cobalt	0.048	mg/L	0.0050	0.000098	1	12/05/24 17:00	12/09/24 20:19	7440-48-4	
Lead	ND	mg/L	0.0010	0.000076	1	12/05/24 17:00	12/09/24 20:19	7439-92-1	
Lithium	0.050	mg/L	0.030	0.00028	1	12/05/24 17:00	12/09/24 20:19	7439-93-2	
Molybdenum	0.011	mg/L	0.010	0.00035	1	12/05/24 17:00	12/09/24 20:19	7439-98-7	
Selenium	0.00097J	mg/L	0.0050	0.00092	1	12/05/24 17:00	12/09/24 20:19	7782-49-2	
Thallium	0.00024J	mg/L	0.0010	0.00020	1	12/05/24 17:00	12/09/24 20:19	7440-28-0	
7470 Mercury Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	12/12/24 16:00	12/13/24 09:31	7439-97-6	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	528	mg/L	25.0	25.0	1		12/06/24 12:08		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	150	mg/L	5.0	5.0	1		12/09/24 17:32		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		12/09/24 17:32		
Alkalinity, Total as CaCO ₃	150	mg/L	5.0	5.0	1		12/09/24 17:32		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		12/07/24 03:54	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	16.5	mg/L	1.0	0.60	1		12/06/24 12:07	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92767477

Sample: HAM-PT-07		Lab ID: 92767477001		Collected: 12/02/24 15:01		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.35	mg/L	0.10	0.050	1		12/06/24 12:07	16984-48-8	
Sulfate	192	mg/L	4.0	2.0	4		12/06/24 18:02	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92767477

Sample: HAM-PT-08		Lab ID: 92767477002		Collected: 12/02/24 12:18		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.32	mg/L	0.040	0.025	1	12/05/24 17:27	12/06/24 04:07	7439-89-6	
Manganese	1.5	mg/L	0.040	0.011	1	12/05/24 17:27	12/06/24 04:07	7439-96-5	
Potassium	6.0	mg/L	0.50	0.15	1	12/05/24 17:27	12/06/24 04:07	7440-09-7	
Sodium	7.4	mg/L	1.0	0.58	1	12/05/24 17:27	12/06/24 04:07	7440-23-5	
Calcium	111	mg/L	1.0	0.12	1	12/05/24 17:27	12/06/24 04:07	7440-70-2	
Magnesium	14.3	mg/L	0.050	0.012	1	12/05/24 17:27	12/06/24 04:07	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00038	1	12/05/24 17:00	12/09/24 20:31	7440-36-0	
Arsenic	0.010	mg/L	0.0050	0.0016	1	12/05/24 17:00	12/09/24 20:31	7440-38-2	
Barium	0.052	mg/L	0.0050	0.00019	1	12/05/24 17:00	12/09/24 20:31	7440-39-3	
Beryllium	0.000070J	mg/L	0.00050	0.000026	1	12/05/24 17:00	12/09/24 20:31	7440-41-7	
Boron	0.85	mg/L	0.050	0.014	1	12/05/24 17:00	12/10/24 16:47	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.000041	1	12/05/24 17:00	12/09/24 20:31	7440-43-9	
Chromium	0.00040J	mg/L	0.0050	0.00015	1	12/05/24 17:00	12/09/24 20:31	7440-47-3	
Cobalt	0.048	mg/L	0.0050	0.000098	1	12/05/24 17:00	12/09/24 20:31	7440-48-4	
Lead	ND	mg/L	0.0010	0.000076	1	12/05/24 17:00	12/09/24 20:31	7439-92-1	
Lithium	0.020J	mg/L	0.030	0.00028	1	12/05/24 17:00	12/09/24 20:31	7439-93-2	
Molybdenum	0.0068J	mg/L	0.010	0.00035	1	12/05/24 17:00	12/09/24 20:31	7439-98-7	
Selenium	0.0012J	mg/L	0.0050	0.00092	1	12/05/24 17:00	12/09/24 20:31	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00020	1	12/05/24 17:00	12/09/24 20:31	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	12/12/24 16:00	12/13/24 09:33	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	451	mg/L	25.0	25.0	1		12/06/24 12:08		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	84.2	mg/L	5.0	5.0	1		12/09/24 17:50		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		12/09/24 17:50		
Alkalinity, Total as CaCO3	84.2	mg/L	5.0	5.0	1		12/09/24 17:50		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		12/07/24 03:56	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	17.5	mg/L	1.0	0.60	1		12/06/24 12:22	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92767477

Sample: HAM-PT-08		Lab ID: 92767477002		Collected: 12/02/24 12:18		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.14	mg/L	0.10	0.050	1		12/06/24 12:22	16984-48-8	
Sulfate	187	mg/L	4.0	2.0	4		12/06/24 18:17	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92767477

Sample: HAM-PT-09		Lab ID: 92767477003		Collected: 12/03/24 13:20		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A									
Pace Analytical Services - Peachtree Corners, GA									
Iron	0.049	mg/L	0.040	0.025	1	12/05/24 17:27	12/06/24 04:12	7439-89-6	
Manganese	0.37	mg/L	0.040	0.011	1	12/05/24 17:27	12/06/24 04:12	7439-96-5	
Potassium	6.9	mg/L	0.50	0.15	1	12/05/24 17:27	12/06/24 04:12	7440-09-7	
Sodium	10.1	mg/L	1.0	0.58	1	12/05/24 17:27	12/06/24 04:12	7440-23-5	
Calcium	116	mg/L	1.0	0.12	1	12/05/24 17:27	12/06/24 04:12	7440-70-2	
Magnesium	23.1	mg/L	0.050	0.012	1	12/05/24 17:27	12/06/24 04:12	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00038	1	12/05/24 17:00	12/09/24 20:35	7440-36-0	
Arsenic	0.0020J	mg/L	0.0050	0.0016	1	12/05/24 17:00	12/09/24 20:35	7440-38-2	
Barium	0.066	mg/L	0.0050	0.00019	1	12/05/24 17:00	12/09/24 20:35	7440-39-3	
Beryllium	0.000030J	mg/L	0.00050	0.000026	1	12/05/24 17:00	12/09/24 20:35	7440-41-7	
Boron	1.6	mg/L	0.050	0.014	1	12/05/24 17:00	12/10/24 16:51	7440-42-8	
Cadmium	0.00024J	mg/L	0.00050	0.000041	1	12/05/24 17:00	12/09/24 20:35	7440-43-9	
Chromium	0.00037J	mg/L	0.0050	0.00015	1	12/05/24 17:00	12/09/24 20:35	7440-47-3	
Cobalt	0.0028J	mg/L	0.0050	0.000098	1	12/05/24 17:00	12/09/24 20:35	7440-48-4	
Lead	ND	mg/L	0.0010	0.000076	1	12/05/24 17:00	12/09/24 20:35	7439-92-1	
Lithium	0.0025J	mg/L	0.030	0.00028	1	12/05/24 17:00	12/09/24 20:35	7439-93-2	
Molybdenum	0.25	mg/L	0.010	0.00035	1	12/05/24 17:00	12/09/24 20:35	7439-98-7	
Selenium	0.00096J	mg/L	0.0050	0.00092	1	12/05/24 17:00	12/09/24 20:35	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00020	1	12/05/24 17:00	12/09/24 20:35	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	12/12/24 16:00	12/13/24 09:43	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	521	mg/L	25.0	25.0	1		12/09/24 11:55		
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	121	mg/L	5.0	5.0	1		12/09/24 19:21		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		12/09/24 19:21		
Alkalinity, Total as CaCO3	121	mg/L	5.0	5.0	1		12/09/24 19:21		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		12/07/24 04:00	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	48.3	mg/L	1.0	0.60	1		12/06/24 12:37	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92767477

Sample: HAM-PT-09		Lab ID: 92767477003		Collected: 12/03/24 13:20		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.40	mg/L	0.10	0.050	1		12/06/24 12:37	16984-48-8	
Sulfate	157	mg/L	3.0	1.5	3		12/06/24 18:31	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92767477

Sample: HAM-PT-10		Lab ID: 92767477004		Collected: 12/03/24 11:57		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	12/05/24 17:27	12/06/24 04:27	7439-89-6	
Manganese	0.37	mg/L	0.040	0.011	1	12/05/24 17:27	12/06/24 04:27	7439-96-5	
Potassium	7.1	mg/L	0.50	0.15	1	12/05/24 17:27	12/06/24 04:27	7440-09-7	
Sodium	8.8	mg/L	1.0	0.58	1	12/05/24 17:27	12/06/24 04:27	7440-23-5	
Calcium	114	mg/L	1.0	0.12	1	12/05/24 17:27	12/06/24 04:27	7440-70-2	
Magnesium	13.8	mg/L	0.050	0.012	1	12/05/24 17:27	12/06/24 04:27	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00038	1	12/05/24 17:00	12/09/24 20:39	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0016	1	12/05/24 17:00	12/09/24 20:39	7440-38-2	
Barium	0.047	mg/L	0.0050	0.00019	1	12/05/24 17:00	12/09/24 20:39	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000026	1	12/05/24 17:00	12/09/24 20:39	7440-41-7	
Boron	1.7	mg/L	0.050	0.014	1	12/05/24 17:00	12/10/24 16:55	7440-42-8	
Cadmium	0.00015J	mg/L	0.00050	0.000041	1	12/05/24 17:00	12/09/24 20:39	7440-43-9	
Chromium	0.00025J	mg/L	0.0050	0.00015	1	12/05/24 17:00	12/09/24 20:39	7440-47-3	
Cobalt	0.0015J	mg/L	0.0050	0.000098	1	12/05/24 17:00	12/09/24 20:39	7440-48-4	
Lead	ND	mg/L	0.0010	0.000076	1	12/05/24 17:00	12/09/24 20:39	7439-92-1	
Lithium	0.0010J	mg/L	0.030	0.00028	1	12/05/24 17:00	12/09/24 20:39	7439-93-2	
Molybdenum	0.18	mg/L	0.010	0.00035	1	12/05/24 17:00	12/09/24 20:39	7439-98-7	
Selenium	0.00095J	mg/L	0.0050	0.00092	1	12/05/24 17:00	12/09/24 20:39	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00020	1	12/05/24 17:00	12/09/24 20:39	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	12/12/24 16:00	12/13/24 09:46	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	470	mg/L	25.0	25.0	1		12/09/24 11:55		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	118	mg/L	5.0	5.0	1		12/09/24 19:29		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		12/09/24 19:29		
Alkalinity, Total as CaCO3	118	mg/L	5.0	5.0	1		12/09/24 19:29		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		12/07/24 04:01	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	46.1	mg/L	1.0	0.60	1		12/06/24 12:52	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92767477

Sample: HAM-PT-10		Lab ID: 92767477004		Collected: 12/03/24 11:57		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.27	mg/L	0.10	0.050	1		12/06/24 12:52	16984-48-8	
Sulfate	130	mg/L	3.0	1.5	3		12/06/24 18:46	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92767477

Sample: HAM-PT-11		Lab ID: 92767477005		Collected: 12/03/24 14:37		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.17	mg/L	0.040	0.025	1	12/05/24 17:27	12/06/24 04:32	7439-89-6	
Manganese	0.45	mg/L	0.040	0.011	1	12/05/24 17:27	12/06/24 04:32	7439-96-5	
Potassium	7.2	mg/L	0.50	0.15	1	12/05/24 17:27	12/06/24 04:32	7440-09-7	
Sodium	9.5	mg/L	1.0	0.58	1	12/05/24 17:27	12/06/24 04:32	7440-23-5	
Calcium	120	mg/L	1.0	0.12	1	12/05/24 17:27	12/06/24 04:32	7440-70-2	
Magnesium	16.9	mg/L	0.050	0.012	1	12/05/24 17:27	12/06/24 04:32	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00038	1	12/05/24 17:00	12/09/24 20:43	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0016	1	12/05/24 17:00	12/09/24 20:43	7440-38-2	
Barium	0.067	mg/L	0.0050	0.00019	1	12/05/24 17:00	12/09/24 20:43	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000026	1	12/05/24 17:00	12/09/24 20:43	7440-41-7	
Boron	1.6	mg/L	0.050	0.014	1	12/05/24 17:00	12/10/24 16:59	7440-42-8	
Cadmium	0.00015J	mg/L	0.00050	0.000041	1	12/05/24 17:00	12/09/24 20:43	7440-43-9	
Chromium	0.00045J	mg/L	0.0050	0.00015	1	12/05/24 17:00	12/09/24 20:43	7440-47-3	
Cobalt	0.0044J	mg/L	0.0050	0.000098	1	12/05/24 17:00	12/09/24 20:43	7440-48-4	
Lead	ND	mg/L	0.0010	0.000076	1	12/05/24 17:00	12/09/24 20:43	7439-92-1	
Lithium	0.0027J	mg/L	0.030	0.00028	1	12/05/24 17:00	12/09/24 20:43	7439-93-2	
Molybdenum	0.12	mg/L	0.010	0.00035	1	12/05/24 17:00	12/09/24 20:43	7439-98-7	
Selenium	0.00092J	mg/L	0.0050	0.00092	1	12/05/24 17:00	12/09/24 20:43	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00020	1	12/05/24 17:00	12/09/24 20:43	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	12/12/24 16:00	12/13/24 09:53	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	486	mg/L	25.0	25.0	1		12/09/24 11:55		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	122	mg/L	5.0	5.0	1		12/09/24 19:38		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		12/09/24 19:38		
Alkalinity, Total as CaCO3	122	mg/L	5.0	5.0	1		12/09/24 19:38		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		12/07/24 04:01	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	44.0	mg/L	1.0	0.60	1		12/06/24 13:07	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92767477

Sample: HAM-PT-11		Lab ID: 92767477005		Collected: 12/03/24 14:37		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.31	mg/L	0.10	0.050	1		12/06/24 13:07	16984-48-8	
Sulfate	139	mg/L	3.0	1.5	3		12/06/24 19:01	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92767477

Sample: HAM-PT-12		Lab ID: 92767477006		Collected: 12/03/24 13:57		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.33	mg/L	0.040	0.025	1	12/05/24 17:27	12/06/24 04:37	7439-89-6	
Manganese	0.86	mg/L	0.040	0.011	1	12/05/24 17:27	12/06/24 04:37	7439-96-5	
Potassium	6.1	mg/L	0.50	0.15	1	12/05/24 17:27	12/06/24 04:37	7440-09-7	
Sodium	10.9	mg/L	1.0	0.58	1	12/05/24 17:27	12/06/24 04:37	7440-23-5	
Calcium	105	mg/L	1.0	0.12	1	12/05/24 17:27	12/06/24 04:37	7440-70-2	
Magnesium	28.7	mg/L	0.050	0.012	1	12/05/24 17:27	12/06/24 04:37	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00038	1	12/05/24 17:00	12/09/24 20:47	7440-36-0	
Arsenic	0.0027J	mg/L	0.0050	0.0016	1	12/05/24 17:00	12/09/24 20:47	7440-38-2	
Barium	0.062	mg/L	0.0050	0.00019	1	12/05/24 17:00	12/09/24 20:47	7440-39-3	
Beryllium	0.000057J	mg/L	0.00050	0.000026	1	12/05/24 17:00	12/09/24 20:47	7440-41-7	
Boron	1.6	mg/L	0.050	0.014	1	12/05/24 17:00	12/10/24 17:03	7440-42-8	
Cadmium	0.00028J	mg/L	0.00050	0.000041	1	12/05/24 17:00	12/09/24 20:47	7440-43-9	
Chromium	0.00067J	mg/L	0.0050	0.00015	1	12/05/24 17:00	12/09/24 20:47	7440-47-3	
Cobalt	0.0035J	mg/L	0.0050	0.000098	1	12/05/24 17:00	12/09/24 20:47	7440-48-4	
Lead	0.000093J	mg/L	0.0010	0.000076	1	12/05/24 17:00	12/09/24 20:47	7439-92-1	
Lithium	0.0023J	mg/L	0.030	0.00028	1	12/05/24 17:00	12/09/24 20:47	7439-93-2	
Molybdenum	0.16	mg/L	0.010	0.00035	1	12/05/24 17:00	12/09/24 20:47	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00092	1	12/05/24 17:00	12/09/24 20:47	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00020	1	12/05/24 17:00	12/09/24 20:47	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	12/12/24 16:00	12/13/24 09:56	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	526	mg/L	25.0	25.0	1		12/09/24 11:55		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	116	mg/L	5.0	5.0	1		12/09/24 19:47		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		12/09/24 19:47		
Alkalinity, Total as CaCO ₃	116	mg/L	5.0	5.0	1		12/09/24 19:47		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		12/07/24 04:02	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	44.2	mg/L	1.0	0.60	1		12/06/24 13:22	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92767477

Sample: HAM-PT-12		Lab ID: 92767477006		Collected: 12/03/24 13:57		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.30	mg/L	0.10	0.050	1		12/06/24 13:22	16984-48-8	
Sulfate	179	mg/L	4.0	2.0	4		12/06/24 19:15	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92767477

Sample: HAM-PT-13		Lab ID: 92767477007		Collected: 12/02/24 13:17		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	9.5	mg/L	0.040	0.025	1	12/05/24 17:27	12/06/24 04:41	7439-89-6	
Manganese	3.0	mg/L	0.040	0.011	1	12/05/24 17:27	12/06/24 04:41	7439-96-5	
Potassium	6.1	mg/L	0.50	0.15	1	12/05/24 17:27	12/06/24 04:41	7440-09-7	
Sodium	10.1	mg/L	1.0	0.58	1	12/05/24 17:27	12/06/24 04:41	7440-23-5	
Calcium	129	mg/L	1.0	0.12	1	12/05/24 17:27	12/06/24 04:41	7440-70-2	
Magnesium	17.8	mg/L	0.050	0.012	1	12/05/24 17:27	12/06/24 04:41	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00038	1	12/05/24 17:00	12/09/24 20:51	7440-36-0	
Arsenic	0.19	mg/L	0.0050	0.0016	1	12/05/24 17:00	12/09/24 20:51	7440-38-2	
Barium	0.047	mg/L	0.0050	0.00019	1	12/05/24 17:00	12/09/24 20:51	7440-39-3	
Beryllium	0.000082J	mg/L	0.00050	0.000026	1	12/05/24 17:00	12/09/24 20:51	7440-41-7	
Boron	0.70	mg/L	0.050	0.014	1	12/05/24 17:00	12/10/24 17:36	7440-42-8	
Cadmium	0.000054J	mg/L	0.00050	0.000041	1	12/05/24 17:00	12/09/24 20:51	7440-43-9	
Chromium	0.00039J	mg/L	0.0050	0.00015	1	12/05/24 17:00	12/09/24 20:51	7440-47-3	
Cobalt	0.023	mg/L	0.0050	0.000098	1	12/05/24 17:00	12/09/24 20:51	7440-48-4	
Lead	0.00011J	mg/L	0.0010	0.000076	1	12/05/24 17:00	12/09/24 20:51	7439-92-1	
Lithium	0.058	mg/L	0.030	0.00028	1	12/05/24 17:00	12/09/24 20:51	7439-93-2	
Molybdenum	0.0085J	mg/L	0.010	0.00035	1	12/05/24 17:00	12/09/24 20:51	7439-98-7	
Selenium	0.0011J	mg/L	0.0050	0.00092	1	12/05/24 17:00	12/09/24 20:51	7782-49-2	
Thallium	0.00023J	mg/L	0.0010	0.00020	1	12/05/24 17:00	12/09/24 20:51	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	12/12/24 16:00	12/13/24 09:58	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	528	mg/L	25.0	25.0	1		12/06/24 12:08		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	145	mg/L	5.0	5.0	1		12/09/24 17:58		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		12/09/24 17:58		
Alkalinity, Total as CaCO3	145	mg/L	5.0	5.0	1		12/09/24 17:58		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		12/07/24 03:56	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	18.6	mg/L	1.0	0.60	1		12/06/24 13:37	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92767477

Sample: HAM-PT-13		Lab ID: 92767477007		Collected: 12/02/24 13:17		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.37	mg/L	0.10	0.050	1		12/06/24 13:37	16984-48-8	
Sulfate	200	mg/L	4.0	2.0	4		12/06/24 19:30	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92767477

Sample: HAM-PT-14		Lab ID: 92767477008		Collected: 12/02/24 14:35		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	14.2	mg/L	0.040	0.025	1	12/05/24 17:27	12/06/24 16:54	7439-89-6	
Manganese	2.9	mg/L	0.040	0.011	1	12/05/24 17:27	12/06/24 16:54	7439-96-5	
Potassium	6.1	mg/L	0.50	0.15	1	12/05/24 17:27	12/06/24 16:54	7440-09-7	
Sodium	8.0	mg/L	1.0	0.58	1	12/05/24 17:27	12/06/24 16:54	7440-23-5	
Calcium	137	mg/L	1.0	0.12	1	12/05/24 17:27	12/06/24 16:54	7440-70-2	
Magnesium	18.9	mg/L	0.050	0.012	1	12/05/24 17:27	12/06/24 16:54	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00038	1	12/05/24 17:00	12/09/24 20:55	7440-36-0	
Arsenic	0.27	mg/L	0.0050	0.0016	1	12/05/24 17:00	12/09/24 20:55	7440-38-2	
Barium	0.043	mg/L	0.0050	0.00019	1	12/05/24 17:00	12/09/24 20:55	7440-39-3	
Beryllium	0.000056J	mg/L	0.00050	0.000026	1	12/05/24 17:00	12/09/24 20:55	7440-41-7	
Boron	0.74	mg/L	0.050	0.014	1	12/05/24 17:00	12/10/24 17:40	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.000041	1	12/05/24 17:00	12/09/24 20:55	7440-43-9	
Chromium	0.00036J	mg/L	0.0050	0.00015	1	12/05/24 17:00	12/09/24 20:55	7440-47-3	
Cobalt	0.024	mg/L	0.0050	0.000098	1	12/05/24 17:00	12/09/24 20:55	7440-48-4	
Lead	0.00015J	mg/L	0.0010	0.000076	1	12/05/24 17:00	12/09/24 20:55	7439-92-1	
Lithium	0.054	mg/L	0.030	0.00028	1	12/05/24 17:00	12/09/24 20:55	7439-93-2	
Molybdenum	0.016	mg/L	0.010	0.00035	1	12/05/24 17:00	12/09/24 20:55	7439-98-7	
Selenium	0.0010J	mg/L	0.0050	0.00092	1	12/05/24 17:00	12/09/24 20:55	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00020	1	12/05/24 17:00	12/09/24 20:55	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	12/12/24 16:00	12/13/24 10:01	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	560	mg/L	25.0	25.0	1		12/06/24 12:09		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	149	mg/L	5.0	5.0	1		12/09/24 18:08		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		12/09/24 18:08		
Alkalinity, Total as CaCO ₃	149	mg/L	5.0	5.0	1		12/09/24 18:08		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		12/07/24 03:56	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	17.8	mg/L	1.0	0.60	1		12/06/24 19:26	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92767477

Sample: HAM-PT-14		Lab ID: 92767477008		Collected: 12/02/24 14:35		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.31	mg/L	0.10	0.050	1		12/06/24 19:26	16984-48-8	
Sulfate	184	mg/L	5.0	2.5	5		12/06/24 20:44	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92767477

Sample: HAM-PT-15		Lab ID: 92767477009		Collected: 12/02/24 16:25		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.38	mg/L	0.040	0.025	1	12/05/24 17:27	12/06/24 04:51	7439-89-6	
Manganese	2.4	mg/L	0.040	0.011	1	12/05/24 17:27	12/06/24 04:51	7439-96-5	
Potassium	6.1	mg/L	0.50	0.15	1	12/05/24 17:27	12/06/24 04:51	7440-09-7	
Sodium	9.3	mg/L	1.0	0.58	1	12/05/24 17:27	12/06/24 04:51	7440-23-5	
Calcium	129	mg/L	1.0	0.12	1	12/05/24 17:27	12/06/24 04:51	7440-70-2	
Magnesium	14.6	mg/L	0.050	0.012	1	12/05/24 17:27	12/06/24 04:51	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	0.00063J	mg/L	0.0030	0.00038	1	12/05/24 17:00	12/09/24 20:59	7440-36-0	
Arsenic	0.024	mg/L	0.0050	0.0016	1	12/05/24 17:00	12/09/24 20:59	7440-38-2	
Barium	0.051	mg/L	0.0050	0.00019	1	12/05/24 17:00	12/09/24 20:59	7440-39-3	
Beryllium	0.000062J	mg/L	0.00050	0.000026	1	12/05/24 17:00	12/09/24 20:59	7440-41-7	
Boron	0.86	mg/L	0.050	0.014	1	12/05/24 17:00	12/10/24 17:44	7440-42-8	
Cadmium	0.00025J	mg/L	0.00050	0.000041	1	12/05/24 17:00	12/09/24 20:59	7440-43-9	
Chromium	0.00026J	mg/L	0.0050	0.00015	1	12/05/24 17:00	12/09/24 20:59	7440-47-3	
Cobalt	0.025	mg/L	0.0050	0.000098	1	12/05/24 17:00	12/09/24 20:59	7440-48-4	
Lead	ND	mg/L	0.0010	0.000076	1	12/05/24 17:00	12/09/24 20:59	7439-92-1	
Lithium	0.041	mg/L	0.030	0.00028	1	12/05/24 17:00	12/09/24 20:59	7439-93-2	
Molybdenum	0.015	mg/L	0.010	0.00035	1	12/05/24 17:00	12/09/24 20:59	7439-98-7	
Selenium	0.0017J	mg/L	0.0050	0.00092	1	12/05/24 17:00	12/09/24 20:59	7782-49-2	
Thallium	0.00044J	mg/L	0.0010	0.00020	1	12/05/24 17:00	12/09/24 20:59	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	12/12/24 16:00	12/13/24 10:04	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	497	mg/L	25.0	25.0	1		12/06/24 12:09		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	141	mg/L	5.0	5.0	1		12/09/24 18:18		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		12/09/24 18:18		
Alkalinity, Total as CaCO ₃	141	mg/L	5.0	5.0	1		12/09/24 18:18		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		12/07/24 03:57	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	17.4	mg/L	1.0	0.60	1		12/06/24 19:42	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92767477

Sample: HAM-PT-15		Lab ID: 92767477009		Collected: 12/02/24 16:25		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.37	mg/L	0.10	0.050	1		12/06/24 19:42	16984-48-8	
Sulfate	175	mg/L	4.0	2.0	4		12/06/24 21:31	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92767477

Sample: HAM-AP1-EB-01		Lab ID: 92767477010		Collected: 12/03/24 15:50		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.037J	mg/L	0.040	0.025	1	12/05/24 17:27	12/06/24 05:01	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	12/05/24 17:27	12/06/24 05:01	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	12/05/24 17:27	12/06/24 05:01	7440-09-7	
Sodium	1.1	mg/L	1.0	0.58	1	12/05/24 17:27	12/06/24 05:01	7440-23-5	
Calcium	0.62J	mg/L	1.0	0.12	1	12/05/24 17:27	12/06/24 05:01	7440-70-2	
Magnesium	0.14	mg/L	0.050	0.012	1	12/05/24 17:27	12/06/24 05:01	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00038	1	12/05/24 17:00	12/09/24 21:07	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0016	1	12/05/24 17:00	12/09/24 21:07	7440-38-2	
Barium	0.0037J	mg/L	0.0050	0.00019	1	12/05/24 17:00	12/10/24 16:14	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000026	1	12/05/24 17:00	12/09/24 21:07	7440-41-7	
Boron	ND	mg/L	0.050	0.014	1	12/05/24 17:00	12/10/24 16:14	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.000041	1	12/05/24 17:00	12/09/24 21:07	7440-43-9	
Chromium	0.00078J	mg/L	0.0050	0.00015	1	12/05/24 17:00	12/09/24 21:07	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.000098	1	12/05/24 17:00	12/09/24 21:07	7440-48-4	
Lead	0.00047J	mg/L	0.0010	0.000076	1	12/05/24 17:00	12/09/24 21:07	7439-92-1	
Lithium	ND	mg/L	0.030	0.00028	1	12/05/24 17:00	12/09/24 21:07	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00035	1	12/05/24 17:00	12/09/24 21:07	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00092	1	12/05/24 17:00	12/09/24 21:07	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00020	1	12/05/24 17:00	12/09/24 21:07	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	12/12/24 16:00	12/13/24 10:06	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	40.0	mg/L	25.0	25.0	1		12/09/24 11:56		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		12/09/24 19:55		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		12/09/24 19:55		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		12/09/24 19:55		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		12/07/24 04:03	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		12/06/24 12:34	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92767477

Sample: HAM-AP1-EB-01		Lab ID: 92767477010		Collected: 12/03/24 15:50		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		12/06/24 12:34	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		12/06/24 12:34	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92767477

Sample: HAM-AP1-FB-01		Lab ID: 92767477011		Collected: 12/03/24 15:45		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	ND	mg/L	0.040	0.025	1	12/05/24 17:27	12/06/24 05:06	7439-89-6	
Manganese	ND	mg/L	0.040	0.011	1	12/05/24 17:27	12/06/24 05:06	7439-96-5	
Potassium	ND	mg/L	0.50	0.15	1	12/05/24 17:27	12/06/24 05:06	7440-09-7	
Sodium	ND	mg/L	1.0	0.58	1	12/05/24 17:27	12/06/24 05:06	7440-23-5	
Calcium	0.18J	mg/L	1.0	0.12	1	12/05/24 17:27	12/06/24 05:06	7440-70-2	
Magnesium	0.027J	mg/L	0.050	0.012	1	12/05/24 17:27	12/06/24 05:06	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00038	1	12/05/24 17:00	12/09/24 21:19	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0016	1	12/05/24 17:00	12/09/24 21:19	7440-38-2	
Barium	0.00084J	mg/L	0.0050	0.00019	1	12/05/24 17:00	12/09/24 21:19	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000026	1	12/05/24 17:00	12/09/24 21:19	7440-41-7	
Boron	0.018J	mg/L	0.050	0.014	1	12/05/24 17:00	12/09/24 21:19	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.000041	1	12/05/24 17:00	12/09/24 21:19	7440-43-9	
Chromium	0.00033J	mg/L	0.0050	0.00015	1	12/05/24 17:00	12/09/24 21:19	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.000098	1	12/05/24 17:00	12/09/24 21:19	7440-48-4	
Lead	0.00010J	mg/L	0.0010	0.000076	1	12/05/24 17:00	12/09/24 21:19	7439-92-1	
Lithium	ND	mg/L	0.030	0.00028	1	12/05/24 17:00	12/09/24 21:19	7439-93-2	
Molybdenum	ND	mg/L	0.010	0.00035	1	12/05/24 17:00	12/09/24 21:19	7439-98-7	
Selenium	ND	mg/L	0.0050	0.00092	1	12/05/24 17:00	12/09/24 21:19	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00020	1	12/05/24 17:00	12/09/24 21:19	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	12/12/24 16:00	12/13/24 10:09	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		12/09/24 11:56		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		12/09/24 20:00		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		12/09/24 20:00		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		12/09/24 20:00		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		12/07/24 04:03	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		12/06/24 12:50	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92767477

Sample: HAM-AP1-FB-01		Lab ID: 92767477011		Collected: 12/03/24 15:45		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	ND	mg/L	0.10	0.050	1		12/06/24 12:50	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		12/06/24 12:50	14808-79-8	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92767477

Sample: HAM-AP1-FD-01		Lab ID: 92767477012		Collected: 12/03/24 00:00		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010D ATL ICP									
Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Peachtree Corners, GA									
Iron	0.029J	mg/L	0.040	0.025	1	12/05/24 17:27	12/06/24 05:11	7439-89-6	
Manganese	0.37	mg/L	0.040	0.011	1	12/05/24 17:27	12/06/24 05:11	7439-96-5	
Potassium	7.1	mg/L	0.50	0.15	1	12/05/24 17:27	12/06/24 05:11	7440-09-7	
Sodium	8.9	mg/L	1.0	0.58	1	12/05/24 17:27	12/06/24 05:11	7440-23-5	
Calcium	113	mg/L	1.0	0.12	1	12/05/24 17:27	12/06/24 05:11	7440-70-2	
Magnesium	13.8	mg/L	0.050	0.012	1	12/05/24 17:27	12/06/24 05:11	7439-95-4	
6020 MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Antimony	ND	mg/L	0.0030	0.00038	1	12/05/24 17:00	12/09/24 21:23	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0016	1	12/05/24 17:00	12/09/24 21:23	7440-38-2	
Barium	0.047	mg/L	0.0050	0.00019	1	12/05/24 17:00	12/09/24 21:23	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.000026	1	12/05/24 17:00	12/09/24 21:23	7440-41-7	
Boron	1.8	mg/L	0.25	0.069	5	12/05/24 17:00	12/11/24 13:45	7440-42-8	
Cadmium	0.00013J	mg/L	0.00050	0.000041	1	12/05/24 17:00	12/09/24 21:23	7440-43-9	
Chromium	0.00030J	mg/L	0.0050	0.00015	1	12/05/24 17:00	12/09/24 21:23	7440-47-3	
Cobalt	0.0015J	mg/L	0.0050	0.000098	1	12/05/24 17:00	12/09/24 21:23	7440-48-4	
Lead	ND	mg/L	0.0010	0.000076	1	12/05/24 17:00	12/09/24 21:23	7439-92-1	
Lithium	0.0010J	mg/L	0.030	0.00028	1	12/05/24 17:00	12/09/24 21:23	7439-93-2	
Molybdenum	0.17	mg/L	0.010	0.00035	1	12/05/24 17:00	12/09/24 21:23	7439-98-7	
Selenium	0.0012J	mg/L	0.0050	0.00092	1	12/05/24 17:00	12/09/24 21:23	7782-49-2	
Thallium	ND	mg/L	0.0010	0.00020	1	12/05/24 17:00	12/09/24 21:23	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Peachtree Corners, GA									
Mercury	ND	mg/L	0.00020	0.00013	1	12/12/24 16:00	12/13/24 10:11	7439-97-6	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	468	mg/L	25.0	25.0	1		12/09/24 11:57		
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	121	mg/L	5.0	5.0	1		12/09/24 20:13		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		12/09/24 20:13		
Alkalinity, Total as CaCO3	121	mg/L	5.0	5.0	1		12/09/24 20:13		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		12/07/24 04:04	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	46.0	mg/L	1.0	0.60	1		12/07/24 18:43	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92767477

Sample: HAM-AP1-FD-01		Lab ID: 92767477012		Collected: 12/03/24 00:00		Received: 12/05/24 11:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Fluoride	0.29	mg/L	0.10	0.050	1		12/07/24 18:43	16984-48-8	
Sulfate	132	mg/L	3.0	1.5	3		12/08/24 04:55	14808-79-8	

REPORT OF LABORATORY ANALYSIS



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92767477

QC Batch:	900606	Analysis Method:	EPA 6010D
QC Batch Method:	EPA 3010A	Analysis Description:	6010D ATL
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92767477001, 92767477002, 92767477003, 92767477004, 92767477005, 92767477006, 92767477007, 92767477008, 92767477009, 92767477010, 92767477011, 92767477012		

METHOD BLANK: 4635885

Matrix: Water

Associated Lab Samples: 92767477001, 92767477002, 92767477003, 92767477004, 92767477005, 92767477006, 92767477007, 92767477008, 92767477009, 92767477010, 92767477011, 92767477012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Calcium	mg/L	ND	1.0	0.12	12/06/24 03:38	
Iron	mg/L	ND	0.040	0.025	12/06/24 03:38	
Magnesium	mg/L	ND	0.050	0.012	12/06/24 03:38	
Manganese	mg/L	ND	0.040	0.011	12/06/24 03:38	
Potassium	mg/L	ND	0.50	0.15	12/06/24 03:38	
Sodium	mg/L	ND	1.0	0.58	12/06/24 03:38	

LABORATORY CONTROL SAMPLE: 4635886

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Calcium	mg/L	1	1.1	107	80-120	
Iron	mg/L	1	1.1	107	80-120	
Magnesium	mg/L	1	1.1	106	80-120	
Manganese	mg/L	1	1.1	107	80-120	
Potassium	mg/L	1	1.1	111	80-120	
Sodium	mg/L	1	1.1	110	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4635887 4635888

Parameter	Units	92767477001	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		Result										
Calcium	mg/L	129	1	1	130	128	47	-83	75-125	1	20	M1
Iron	mg/L	7.7	1	1	8.6	8.7	98	99	75-125	0	20	
Magnesium	mg/L	17.7	1	1	18.8	18.5	111	87	75-125	1	20	
Manganese	mg/L	3.4	1	1	4.3	4.3	90	90	75-125	0	20	
Potassium	mg/L	6.0	1	1	7.1	7.1	114	112	75-125	0	20	
Sodium	mg/L	8.5	1	1	9.6	9.5	112	104	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1
Pace Project No.: 92767477

QC Batch:	900605	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92767477001, 92767477002, 92767477003, 92767477004, 92767477005, 92767477006, 92767477007, 92767477008, 92767477009, 92767477010, 92767477011, 92767477012		

METHOD BLANK: 4635874 Matrix: Water
Associated Lab Samples: 92767477001, 92767477002, 92767477003, 92767477004, 92767477005, 92767477006, 92767477007, 92767477008, 92767477009, 92767477010, 92767477011, 92767477012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00038	12/10/24 15:58	
Arsenic	mg/L	ND	0.0050	0.0016	12/10/24 15:58	
Barium	mg/L	ND	0.0050	0.00019	12/10/24 15:58	
Beryllium	mg/L	ND	0.00050	0.000026	12/10/24 15:58	
Boron	mg/L	ND	0.050	0.014	12/10/24 15:58	
Cadmium	mg/L	ND	0.00050	0.000041	12/10/24 15:58	
Chromium	mg/L	ND	0.0050	0.00015	12/10/24 15:58	
Cobalt	mg/L	ND	0.0050	0.000098	12/10/24 15:58	
Lead	mg/L	ND	0.0010	0.000076	12/10/24 15:58	
Lithium	mg/L	ND	0.030	0.00028	12/10/24 15:58	
Molybdenum	mg/L	ND	0.010	0.00035	12/10/24 15:58	
Selenium	mg/L	ND	0.0050	0.00092	12/10/24 15:58	
Thallium	mg/L	ND	0.0010	0.00020	12/10/24 15:58	

LABORATORY CONTROL SAMPLE: 4635875

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.10	101	80-120	
Arsenic	mg/L	0.1	0.10	100	80-120	
Barium	mg/L	0.1	0.10	102	80-120	
Beryllium	mg/L	0.1	0.10	102	80-120	
Boron	mg/L	1	1.1	110	80-120	
Cadmium	mg/L	0.1	0.099	99	80-120	
Chromium	mg/L	0.1	0.10	104	80-120	
Cobalt	mg/L	0.1	0.10	104	80-120	
Lead	mg/L	0.1	0.10	103	80-120	
Lithium	mg/L	0.1	0.10	103	80-120	
Molybdenum	mg/L	0.1	0.10	104	80-120	
Selenium	mg/L	0.1	0.099	99	80-120	
Thallium	mg/L	0.1	0.10	104	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4635876 4635877

Parameter	Units	92766149001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	0.00092J	0.1	0.1	0.097	0.098	96	97	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92767477

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4635876					4635877							
Parameter	Units	92766149001	MS	MSD	MS	MSD	MS	MSD	% Rec	RPD	Max	Qual
		Result	Spike Conc.	Spike Conc.								
Arsenic	mg/L	0.0045J	0.1	0.1	0.11	0.11	106	106	75-125	0	20	
Barium	mg/L	0.019	0.1	0.1	0.12	0.12	105	106	75-125	0	20	
Beryllium	mg/L	0.0037	0.1	0.1	0.097	0.099	94	95	75-125	2	20	
Boron	mg/L	23.8	1	1	24.3	23.6	51	-17	75-125	3	20	M1
Cadmium	mg/L	0.015	0.1	0.1	0.11	0.11	96	97	75-125	1	20	
Chromium	mg/L	0.00041J	0.1	0.1	0.11	0.11	109	109	75-125	0	20	
Cobalt	mg/L	0.0075	0.1	0.1	0.11	0.12	107	109	75-125	1	20	
Lead	mg/L	0.00033J	0.1	0.1	0.088	0.090	88	90	75-125	2	20	
Lithium	mg/L	0.0032J	0.1	0.1	0.10	0.11	101	102	75-125	1	20	
Molybdenum	mg/L	ND	0.1	0.1	0.10	0.11	104	106	75-125	1	20	
Selenium	mg/L	0.0022J	0.1	0.1	0.11	0.11	106	108	75-125	1	20	
Thallium	mg/L	ND	0.1	0.1	0.091	0.093	91	93	75-125	2	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1
Pace Project No.: 92767477

QC Batch:	902280	Analysis Method:	EPA 7470A
QC Batch Method:	EPA 7470A	Analysis Description:	7470 Mercury
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92767477001, 92767477002, 92767477003, 92767477004, 92767477005, 92767477006, 92767477007, 92767477008, 92767477009, 92767477010, 92767477011, 92767477012

METHOD BLANK:	4643843	Matrix:	Water
---------------	---------	---------	-------

Associated Lab Samples: 92767477001, 92767477002, 92767477003, 92767477004, 92767477005, 92767477006, 92767477007, 92767477008, 92767477009, 92767477010, 92767477011, 92767477012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00013	12/13/24 09:25	

LABORATORY CONTROL SAMPLE: 4643844						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0022	89	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:					4643846							
Parameter	Units	92767477002	MS	MSD	MS	MSD	MS	MSD	% Rec	RPD	Max	Qual
		Result	Spike Conc.	Spike Conc.								
Mercury	mg/L	ND	0.0025	0.0025	0.0022	0.0021	86	83	75-125	4	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92767477

QC Batch:	900794	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92767477001, 92767477002, 92767477007, 92767477008, 92767477009

METHOD BLANK: 4636624 Matrix: Water

Associated Lab Samples: 92767477001, 92767477002, 92767477007, 92767477008, 92767477009

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	12/06/24 12:02	

LABORATORY CONTROL SAMPLE: 4636625

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	403	101	80-120	

SAMPLE DUPLICATE: 4636626

Parameter	Units	92767533001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	1150	1220	6	10	

SAMPLE DUPLICATE: 4636627

Parameter	Units	92767550007 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	2760	2720	2	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92767477

QC Batch: 901268 Analysis Method: SM 2540C-2015
QC Batch Method: SM 2540C-2015 Analysis Description: 2540C Total Dissolved Solids
Laboratory: Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples: 92767477003, 92767477004, 92767477005, 92767477006, 92767477010, 92767477011, 92767477012

METHOD BLANK: 4638882 Matrix: Water
Associated Lab Samples: 92767477003, 92767477004, 92767477005, 92767477006, 92767477010, 92767477011, 92767477012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	12/09/24 11:52	

LABORATORY CONTROL SAMPLE: 4638883

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	405	101	80-120	

SAMPLE DUPLICATE: 4638884

Parameter	Units	92766727005 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	87.0	82.0	6	10	

SAMPLE DUPLICATE: 4638885

Parameter	Units	92767477011 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	ND	ND		10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92767477

QC Batch: 901259

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92767477001, 92767477002, 92767477007, 92767477008, 92767477009

METHOD BLANK: 4638849

Matrix: Water

Associated Lab Samples: 92767477001, 92767477002, 92767477007, 92767477008, 92767477009

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	12/09/24 15:34	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	12/09/24 15:34	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	12/09/24 15:34	

LABORATORY CONTROL SAMPLE: 4638850

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.7	103	80-120	

LABORATORY CONTROL SAMPLE: 4638851

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.3	105	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4638852 4638853

Parameter	Units	92766964006 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	22.7	50	50	72.0	71.5	99	98	80-120	1	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4638854 4638855

Parameter	Units	92766964008 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	25.1	50	50	74.0	75.3	98	100	80-120	2	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92767477

QC Batch: 901260

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92767477003, 92767477004, 92767477005, 92767477006, 92767477010, 92767477011, 92767477012

METHOD BLANK: 4638858

Matrix: Water

Associated Lab Samples: 92767477003, 92767477004, 92767477005, 92767477006, 92767477010, 92767477011, 92767477012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	12/09/24 19:00	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	12/09/24 19:00	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	12/09/24 19:00	

LABORATORY CONTROL SAMPLE: 4638859

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.8	104	80-120	

LABORATORY CONTROL SAMPLE: 4638860

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.1	104	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4638861 4638862

Parameter	Units	92767661014 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	42.9	50	50	92.7	91.6	100	97	80-120	1	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4638863 4638864

Parameter	Units	92767674002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	85.9	50	50	132	134	93	97	80-120	1	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92767477

QC Batch: 900997

Analysis Method: SM 4500-S2D-2011

QC Batch Method: SM 4500-S2D-2011

Analysis Description: 4500S2D Sulfide Water

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92767477001, 92767477002, 92767477007, 92767477008, 92767477009

METHOD BLANK: 4638176

Matrix: Water

Associated Lab Samples: 92767477001, 92767477002, 92767477007, 92767477008, 92767477009

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	12/07/24 03:46	

LABORATORY CONTROL SAMPLE: 4638177

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.51	103	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4638178 4638179

Parameter	Units	92767533001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.49	0.50	95	97	80-120	2	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4638180 4638181

Parameter	Units	92767550007 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.44	0.47	86	92	80-120	7	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92767477

QC Batch: 900998

Analysis Method: SM 4500-S2D-2011

QC Batch Method: SM 4500-S2D-2011

Analysis Description: 4500S2D Sulfide Water

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92767477003, 92767477004, 92767477005, 92767477006, 92767477010, 92767477011, 92767477012

METHOD BLANK: 4638182

Matrix: Water

Associated Lab Samples: 92767477003, 92767477004, 92767477005, 92767477006, 92767477010, 92767477011, 92767477012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	12/07/24 03:59	

LABORATORY CONTROL SAMPLE: 4638183

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.51	102	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4638184 4638185

Parameter	Units	92767477003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.52	0.52	101	102	80-120	1	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4638186 4638187

Parameter	Units	92767830002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.51	0.51	99	101	80-120	1	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92767477

QC Batch:	900636	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville

Associated Lab Samples: 92767477001, 92767477002, 92767477003, 92767477004, 92767477005, 92767477006, 92767477007

METHOD BLANK: 4636162

Matrix: Water

Associated Lab Samples: 92767477001, 92767477002, 92767477003, 92767477004, 92767477005, 92767477006, 92767477007

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	12/05/24 22:24	
Fluoride	mg/L	ND	0.10	0.050	12/05/24 22:24	
Sulfate	mg/L	ND	1.0	0.50	12/05/24 22:24	

LABORATORY CONTROL SAMPLE: 4636163

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	50.1	100	90-110	
Fluoride	mg/L	2.5	2.5	101	90-110	
Sulfate	mg/L	50	51.1	102	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4636164 4636165

Parameter	Units	92767407009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	8.0	50	50	59.6	63.5	103	111	90-110	6	10	M1
Fluoride	mg/L	0.074J	2.5	2.5	2.5	2.7	99	106	90-110	7	10	
Sulfate	mg/L	9.9	50	50	61.8	66.0	104	112	90-110	7	10	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4636166 4636167

Parameter	Units	92767407011 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	23.9	50	50	76.1	78.1	104	108	90-110	3	10	
Fluoride	mg/L	0.11	2.5	2.5	2.5	2.6	96	100	90-110	4	10	
Sulfate	mg/L	6.2	50	50	59.2	61.2	106	110	90-110	3	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92767477

QC Batch: 900731 Analysis Method: EPA 300.0 Rev 2.1 1993
QC Batch Method: EPA 300.0 Rev 2.1 1993 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92767477008, 92767477009, 92767477010, 92767477011

METHOD BLANK: 4636419 Matrix: Water
Associated Lab Samples: 92767477008, 92767477009, 92767477010, 92767477011

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	12/06/24 12:03	
Fluoride	mg/L	ND	0.10	0.050	12/06/24 12:03	
Sulfate	mg/L	ND	1.0	0.50	12/06/24 12:03	

LABORATORY CONTROL SAMPLE: 4636420

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	50.5	101	90-110	
Fluoride	mg/L	2.5	2.5	98	90-110	
Sulfate	mg/L	50	50.2	100	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4636421 4636422

Parameter	Units	92767505005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	7.8	50	50	58.2	59.5	101	103	90-110	2	10	
Fluoride	mg/L	0.092J	2.5	2.5	2.6	2.6	99	101	90-110	3	10	
Sulfate	mg/L	5.0	50	50	55.3	56.5	100	103	90-110	2	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4636423 4636424

Parameter	Units	92767477011 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	ND	50	50	50.5	51.1	101	102	90-110	1	10	
Fluoride	mg/L	ND	2.5	2.5	2.4	2.5	98	99	90-110	1	10	
Sulfate	mg/L	ND	50	50	49.7	50.3	99	101	90-110	1	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92767477

QC Batch:	901028	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville

Associated Lab Samples: 92767477012

METHOD BLANK: 4638247 Matrix: Water

Associated Lab Samples: 92767477012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	12/07/24 13:29	
Fluoride	mg/L	ND	0.10	0.050	12/07/24 13:29	
Sulfate	mg/L	ND	1.0	0.50	12/07/24 13:29	

LABORATORY CONTROL SAMPLE: 4638248

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	49.6	99	90-110	
Fluoride	mg/L	2.5	2.5	101	90-110	
Sulfate	mg/L	50	50.4	101	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4638249 4638250

Parameter	Units	92767805006 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	6.2	50	50	52.9	53.6	93	95	90-110	1	10	
Fluoride	mg/L	0.075J	2.5	2.5	2.5	2.5	97	98	90-110	2	10	
Sulfate	mg/L	2.7	50	50	50.1	50.8	95	96	90-110	1	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4638251 4638252

Parameter	Units	92767661002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	5.1	50	50	52.0	52.3	94	94	90-110	1	10	
Fluoride	mg/L	0.21	2.5	2.5	2.7	2.6	100	96	90-110	4	10	
Sulfate	mg/L	293	50	50	336	333	85	80	90-110	1	10 M1	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1
Pace Project No.: 92767477

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92767477

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92767477001	HAM-PT-07	EPA 3010A	900606	EPA 6010D	900663
92767477002	HAM-PT-08	EPA 3010A	900606	EPA 6010D	900663
92767477003	HAM-PT-09	EPA 3010A	900606	EPA 6010D	900663
92767477004	HAM-PT-10	EPA 3010A	900606	EPA 6010D	900663
92767477005	HAM-PT-11	EPA 3010A	900606	EPA 6010D	900663
92767477006	HAM-PT-12	EPA 3010A	900606	EPA 6010D	900663
92767477007	HAM-PT-13	EPA 3010A	900606	EPA 6010D	900663
92767477008	HAM-PT-14	EPA 3010A	900606	EPA 6010D	900663
92767477009	HAM-PT-15	EPA 3010A	900606	EPA 6010D	900663
92767477010	HAM-AP1-EB-01	EPA 3010A	900606	EPA 6010D	900663
92767477011	HAM-AP1-FB-01	EPA 3010A	900606	EPA 6010D	900663
92767477012	HAM-AP1-FD-01	EPA 3010A	900606	EPA 6010D	900663
92767477001	HAM-PT-07	EPA 3005A	900605	EPA 6020B	900671
92767477002	HAM-PT-08	EPA 3005A	900605	EPA 6020B	900671
92767477003	HAM-PT-09	EPA 3005A	900605	EPA 6020B	900671
92767477004	HAM-PT-10	EPA 3005A	900605	EPA 6020B	900671
92767477005	HAM-PT-11	EPA 3005A	900605	EPA 6020B	900671
92767477006	HAM-PT-12	EPA 3005A	900605	EPA 6020B	900671
92767477007	HAM-PT-13	EPA 3005A	900605	EPA 6020B	900671
92767477008	HAM-PT-14	EPA 3005A	900605	EPA 6020B	900671
92767477009	HAM-PT-15	EPA 3005A	900605	EPA 6020B	900671
92767477010	HAM-AP1-EB-01	EPA 3005A	900605	EPA 6020B	900671
92767477011	HAM-AP1-FB-01	EPA 3005A	900605	EPA 6020B	900671
92767477012	HAM-AP1-FD-01	EPA 3005A	900605	EPA 6020B	900671
92767477001	HAM-PT-07	EPA 7470A	902280	EPA 7470A	902462
92767477002	HAM-PT-08	EPA 7470A	902280	EPA 7470A	902462
92767477003	HAM-PT-09	EPA 7470A	902280	EPA 7470A	902462
92767477004	HAM-PT-10	EPA 7470A	902280	EPA 7470A	902462
92767477005	HAM-PT-11	EPA 7470A	902280	EPA 7470A	902462
92767477006	HAM-PT-12	EPA 7470A	902280	EPA 7470A	902462
92767477007	HAM-PT-13	EPA 7470A	902280	EPA 7470A	902462
92767477008	HAM-PT-14	EPA 7470A	902280	EPA 7470A	902462
92767477009	HAM-PT-15	EPA 7470A	902280	EPA 7470A	902462
92767477010	HAM-AP1-EB-01	EPA 7470A	902280	EPA 7470A	902462
92767477011	HAM-AP1-FB-01	EPA 7470A	902280	EPA 7470A	902462
92767477012	HAM-AP1-FD-01	EPA 7470A	902280	EPA 7470A	902462
92767477001	HAM-PT-07	SM 2540C-2015	900794		
92767477002	HAM-PT-08	SM 2540C-2015	900794		
92767477003	HAM-PT-09	SM 2540C-2015	901268		
92767477004	HAM-PT-10	SM 2540C-2015	901268		
92767477005	HAM-PT-11	SM 2540C-2015	901268		
92767477006	HAM-PT-12	SM 2540C-2015	901268		
92767477007	HAM-PT-13	SM 2540C-2015	900794		
92767477008	HAM-PT-14	SM 2540C-2015	900794		
92767477009	HAM-PT-15	SM 2540C-2015	900794		
92767477010	HAM-AP1-EB-01	SM 2540C-2015	901268		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92767477

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92767477011	HAM-AP1-FB-01	SM 2540C-2015	901268		
92767477012	HAM-AP1-FD-01	SM 2540C-2015	901268		
92767477001	HAM-PT-07	SM 2320B-2011	901259		
92767477002	HAM-PT-08	SM 2320B-2011	901259		
92767477003	HAM-PT-09	SM 2320B-2011	901260		
92767477004	HAM-PT-10	SM 2320B-2011	901260		
92767477005	HAM-PT-11	SM 2320B-2011	901260		
92767477006	HAM-PT-12	SM 2320B-2011	901260		
92767477007	HAM-PT-13	SM 2320B-2011	901259		
92767477008	HAM-PT-14	SM 2320B-2011	901259		
92767477009	HAM-PT-15	SM 2320B-2011	901259		
92767477010	HAM-AP1-EB-01	SM 2320B-2011	901260		
92767477011	HAM-AP1-FB-01	SM 2320B-2011	901260		
92767477012	HAM-AP1-FD-01	SM 2320B-2011	901260		
92767477001	HAM-PT-07	SM 4500-S2D-2011	900997		
92767477002	HAM-PT-08	SM 4500-S2D-2011	900997		
92767477003	HAM-PT-09	SM 4500-S2D-2011	900998		
92767477004	HAM-PT-10	SM 4500-S2D-2011	900998		
92767477005	HAM-PT-11	SM 4500-S2D-2011	900998		
92767477006	HAM-PT-12	SM 4500-S2D-2011	900998		
92767477007	HAM-PT-13	SM 4500-S2D-2011	900997		
92767477008	HAM-PT-14	SM 4500-S2D-2011	900997		
92767477009	HAM-PT-15	SM 4500-S2D-2011	900997		
92767477010	HAM-AP1-EB-01	SM 4500-S2D-2011	900998		
92767477011	HAM-AP1-FB-01	SM 4500-S2D-2011	900998		
92767477012	HAM-AP1-FD-01	SM 4500-S2D-2011	900998		
92767477001	HAM-PT-07	EPA 300.0 Rev 2.1 1993	900636		
92767477002	HAM-PT-08	EPA 300.0 Rev 2.1 1993	900636		
92767477003	HAM-PT-09	EPA 300.0 Rev 2.1 1993	900636		
92767477004	HAM-PT-10	EPA 300.0 Rev 2.1 1993	900636		
92767477005	HAM-PT-11	EPA 300.0 Rev 2.1 1993	900636		
92767477006	HAM-PT-12	EPA 300.0 Rev 2.1 1993	900636		
92767477007	HAM-PT-13	EPA 300.0 Rev 2.1 1993	900636		
92767477008	HAM-PT-14	EPA 300.0 Rev 2.1 1993	900731		
92767477009	HAM-PT-15	EPA 300.0 Rev 2.1 1993	900731		
92767477010	HAM-AP1-EB-01	EPA 300.0 Rev 2.1 1993	900731		
92767477011	HAM-AP1-FB-01	EPA 300.0 Rev 2.1 1993	900731		
92767477012	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	901028		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Me ☐Sample Condition
Upon Receipt

Client Name:

G A Power

Project #:

WO#: 92767477



Courier:

☐ Commercial☐ Fed Ex☒ Pace☐ UPS☐ USPS☐ Other: _____☐ ClientCustody Seal Present? ☐ Yes ☒ NoSeals Intact? ☐ Yes ☐ No ☒ N/ADate/Initials Person Examining Contents: 12/3/24
LOH

Packing Material:

☐ Bubble Wrap☐ Bubble Bags☒ None☐ Other

Biological Tissue Frozen?

☐ Yes☐ No☒ N/A

Thermometer:

☒ IR Gun ID:

230

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

3.1

Correction Factor:

Add/Subtract (°C)

0.0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

3.1

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

				Comments/Discrepancy:
Chain of Custody Present?	☒ Yes	☐ No	☐ N/A	1.
Samples Arrived within Hold Time?	☒ Yes	☐ No	☐ N/A	2.
Short Hold Time Analysis (<72 hr.)?	☐ Yes	☒ No	☐ N/A	3.
Rush Turn Around Time Requested?	☐ Yes	☒ No	☐ N/A	4.
Sufficient Volume?	☒ Yes	☐ No	☐ N/A	5.
Correct Containers Used?	☒ Yes	☐ No	☐ N/A	6.
-Pace Containers Used?	☒ Yes	☐ No	☐ N/A	
Containers Intact?	☒ Yes	☐ No	☐ N/A	7.
Dissolved analysis: Samples Field Filtered?	☐ Yes	☐ No	☒ N/A	8.
Sample Labels Match COC?	☒ Yes	☐ No	☐ N/A	9.
-Includes Date/Time/ID/Analysis Matrix: 12/3/24 [Signature]				
Headspace in VOA Vials (>5-6mm)?	☐ Yes	☐ No	☒ N/A	10.
Trip Blank Present?	☐ Yes	☐ No	☒ N/A	11.
Trip Blank Custody Seals Present?	☐ Yes	☐ No	☒ N/A	

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

WO#: 92767477

Project #

PM: BV

Due Date: 12/19/24

CLIENT: 92- GP-HAM

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐

Client _____ Profile/EZ (Circle one) _____ Notes _____

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)		BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic 2N Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGfU-Wide-mouthed Glass jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG9A-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2SO3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit)-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A -lab)	SP2T-250 mL Sterile Plastic (N/A -lab)		BP3R-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	V5GU-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)	
CC																														
1		2	1																											
2		2	1																											
3		2	1																											
4		2	1																											
5		2	1																											
6		2	1																											
7		2	1																											
8		2	1																											
9		2	1																											
10		2	1																											
11		2	1																											
12		2	1																											

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers.



CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Section A
Required Client Information:

Company: GA Power
Address: Atlanta, GA
Email To: SCS Contacts
Phone:
Fax:
Requested Due Date/TAT: 10 Day

Section B
Required Project Information:

Report To: SCS Contacts
Copy To: Geosyntec Contacts
Purchase Order No.: GPC82474-0001
Project Name: Hampton AP-1
Project Number:
Pace Profile #: 16483

Section C
Invoice Information:

Attention: Southern Co.
Company Name:
Address:
Pace Guide Reference:
Pace Project Manager: Bonnie Vang

Page:
of

REGULATORY AGENCY

☐ NPDES ☐ GROUND WATER ☐ DRINKING WATER
☐ UST ☐ RCRA ☐ OTHER CCR

Site Location
STATE: GA

Requested Analysis Filtered (Y/N)

ITEM #	Valid Matrix Codes Required Client Information	MATRIX CODE	SAMPLE TYPE (G=GRAB C=COMP)	DATE	TIME	DATE	TIME	SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives	Analysis Test	Y/N	Residual Chlorine (Y/N)	Pace Project No./ Lab I.D.
1	HAM-PT-07	WG	G	12/2/2024	1501	19	5	3	1	1	Chloride, Fluoride, Sulfate	N	N	021
2	HAM-PT-08	WG	G	12/2/2024	1218	19	5	3	1	1	Full App. III and IV metals	N	N	003
3	HAM-PT-09	WG	G	12/3/2024	1320	17	5	3	1	1	Major Ions (Profile 10839-2)	N	N	004
4	HAM-PT-10	WG	G	12/3/2024	1157	18	5	3	1	1	TDS	N	N	005
5	HAM-PT-11	WG	G	12/3/2024	1437	17	5	3	1	1		N	N	006
6	HAM-PT-12	WG	G	12/3/2024	1357	18	5	3	1	1		N	N	007
7	HAM-PT-13	WG	G	12/2/2024	1317	19	5	3	1	1		N	N	008
8	HAM-PT-14	WG	G	12/2/2024	1435	18	5	3	1	1		N	N	009
9	HAM-PT-15	WG	G	12/2/2024	1625	18	5	3	1	1		N	N	010
10	HAM-AP1-EB-01	WG	G	12/3/2024	1550	18	5	3	1	1		N	N	011
11	HAM-AP1-FB-01	WG	G	12/3/2024	1545	18	5	3	1	1		N	N	012
12	HAM-AP1-FD-01	WG	G	12/3/2024	0000	18	5	3	1	1		N	N	013

Task Code: HAM-CCR-CA-20241202

RELINQUISHED BY / AFFILIATION	DATE	TIME	ACCEPTED BY / AFFILIATION	DATE	TIME	SAMPLE CONDITIONS
Zain Webb / Geosyntec	12/5/24	9:17	Gian Williams / Pace	12/5/24	0917	
Gian Williams / Pace	12/5/24	1135	Charles Hende / Pace	12/5/24	1135	

SAMPLER NAME AND SIGNATURE

PRINT Name of SAMPLER: Zain Webb / Geosyntec Consultants, Inc.
SIGNATURE OF SAMPLER:
DATE Signed (MM/DD/YYYY): 12/3/24

*Important Note: By signing this form you are accepting Pace's NET 30 day payment terms and agreeing to late charges of 1.5% per month for any invoices not paid within 30 days.

F-ALL-Q-020rev.07, 15-Feb-2007



January 28, 2025

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1
Pace Project No.: 92772942

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on January 08, 2025. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Asheville
- Pace Analytical Services - Peachtree Corners, GA
- Pace Analytical Services - West Columbia

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Jamie Newsome, Geosyntec Consultants
Zain Webb, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1

Pace Project No.: 92772942

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services Peachtree Corners

110 Technology Pkwy, Peachtree Corners, GA 30092

Florida DOH Certification #: E87315

Georgia DW Inorganics Certification #: 812

North Carolina Certification #: 381

South Carolina Certification #: 98011001

Virginia Certification #: 460204

Pace Analytical Services West Columbia

106 Vantage Point Drive, West Columbia, SC 29172

Alaska Dept. of Energy Conservation, Cert# 20-002

California ELAP, cert# 3049

DoD, DoD QSM V5.4, cert# I.2224

DOE, DoD/DOE QSM V5.4, cert# I.2224.01

Florida, Dept. of Health, cert# E87653-70

Georgia, Env. Protection Division, cert# E87653

Illinois, EPA NELAP, cert# 2000552024-9

Kansas, Dept. of Health and Environment, cert# E-10417

Kentucky, Dept. for Env. Protection, UST, cert# 103582

Kentucky, Dept. for Env. Protection, cert# 98037

Louisiana, Dept. of Environmental Quality, cert# 5125

North Carolina, DEQ, Water Resources, cert# 329

New Jersey, Dept. of Env. Protection, cert# NLC 240005

Oklahoma, Dept. of Env. Quality, cert# 2023-175

Oregon, ELAP, cert# 4181-006

Pennsylvania, Dept. of Env. Protection, cert# 003

South Carolina, Dept. of Env. Services, cert# 32010001

Texas, Commission on Env. Quality, cert# TX-C24-00083

Virginia, Dept. of General Services, cert# 13080

Wisconsin, Dept. of Natural Resources, cert# 399136100

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1

Pace Project No.: 92772942

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92772942001	HAM-PT-07	Water	01/06/25 15:44	01/08/25 12:45
92772942002	HAM-PT-08	Water	01/06/25 16:50	01/08/25 12:45
92772942003	HAM-PT-09	Water	01/07/25 10:37	01/08/25 12:45
92772942004	HAM-PT-10	Water	01/07/25 12:30	01/08/25 12:45
92772942005	HAM-PT-11	Water	01/07/25 11:37	01/08/25 12:45
92772942006	HAM-PT-12	Water	01/07/25 09:36	01/08/25 12:45
92772942007	HAM-PT-13	Water	01/06/25 12:47	01/08/25 12:45
92772942008	HAM-PT-14	Water	01/06/25 12:40	01/08/25 12:45
92772942009	HAM-PT-15	Water	01/06/25 14:23	01/08/25 12:45
92772942010	HAM-AP1-EB-01	Water	01/07/25 12:55	01/08/25 12:45
92772942011	HAM-AP1-FB-01	Water	01/07/25 12:50	01/08/25 12:45
92772942012	HAM-AP1-FD-01	Water	01/06/25 00:00	01/08/25 12:45

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92772942

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92772942001	HAM-PT-07	EPA 6020B	CW1	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6020B	BK1, BW	18
		EPA 7470A	KAJ1	1
92772942002	HAM-PT-08	EPA 6020B	CW1	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6020B	BK1, BW	18
		EPA 7470A	KAJ1	1
92772942003	HAM-PT-09	EPA 6020B	CW1	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6020B	BK1, BW	18
		EPA 7470A	KAJ1	1
92772942004	HAM-PT-10	EPA 6020B	CW1	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6020B	BK1, BW	18
		EPA 7470A	KAJ1	1
92772942005	HAM-PT-11	EPA 6020B	CW1	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6020B	BK1, BW	18
		EPA 7470A	KAJ1	1
92772942006	HAM-PT-12	EPA 6020B	CW1	1
		SM 2540C-2015	DL1	1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92772942

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92772942007	HAM-PT-13	SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6020B	BK1, BW	18
		EPA 7470A	KAJ1	1
		EPA 6020B	CW1	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
92772942008	HAM-PT-14	EPA 6020B	BK1, BW	18
		EPA 7470A	KAJ1	1
		EPA 6020B	CW1	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6020B	BK1, BW	18
		EPA 7470A	KAJ1	1
		EPA 6020B	CW1	1
92772942009	HAM-PT-15	SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6020B	BK1, BW	18
		EPA 7470A	KAJ1	1
		EPA 6020B	CW1	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
92772942010	HAM-AP1-EB-01	EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6020B	BK1, BW	18
		EPA 7470A	KAJ1	1
		EPA 6020B	CW1	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6020B	BK1	18
		EPA 7470A	KAJ1	1
92772942011	HAM-AP1-FB-01	EPA 6020B	CW1	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92772942

Lab ID	Sample ID	Method	Analysts	Analytes Reported
92772942012	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6020B	BK1	18
		EPA 7470A	KAJ1	1
		EPA 6020B	CW1	1
		SM 2540C-2015	DL1	1
		SM 2320B-2011	SMS	3
		SM 4500-S2D-2011	JP1	1
		EPA 300.0 Rev 2.1 1993	CDC	3
		EPA 6020B	BK1, BW	18
		EPA 7470A	KAJ1	1

PASI-A = Pace Analytical Services - Asheville

PASI-GA = Pace Analytical Services - Peachtree Corners, GA

PASI-WC = Pace Analytical Services - West Columbia

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92772942

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92772942001	HAM-PT-07					
EPA 6020B	Lithium	0.049	mg/L	0.030	01/23/25 14:09	
SM 2540C-2015	Total Dissolved Solids	529	mg/L	25.0	01/09/25 13:49	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	163	mg/L	5.0	01/14/25 13:45	
SM 2320B-2011	Alkalinity, Total as CaCO3	163	mg/L	5.0	01/14/25 13:45	
EPA 300.0 Rev 2.1 1993	Chloride	18.1	mg/L	1.0	01/09/25 08:15	
EPA 300.0 Rev 2.1 1993	Fluoride	0.38	mg/L	0.10	01/09/25 08:15	
EPA 300.0 Rev 2.1 1993	Sulfate	181	mg/L	4.0	01/09/25 18:17	
EPA 6020B	Arsenic	0.18	mg/L	0.0050	01/13/25 18:21	
EPA 6020B	Barium	0.047	mg/L	0.0050	01/13/25 18:21	
EPA 6020B	Boron	0.83J	mg/L	0.80	01/14/25 16:44	
EPA 6020B	Calcium	113	mg/L	20.0	01/14/25 16:44	
EPA 6020B	Cobalt	0.042	mg/L	0.0050	01/13/25 18:21	
EPA 6020B	Iron	7.8	mg/L	0.040	01/13/25 18:21	
EPA 6020B	Magnesium	16.5	mg/L	0.050	01/13/25 18:21	
EPA 6020B	Manganese	3.2	mg/L	0.80	01/14/25 16:44	
EPA 6020B	Molybdenum	0.011	mg/L	0.010	01/13/25 18:21	
EPA 6020B	Potassium	5.8	mg/L	0.50	01/13/25 18:21	
EPA 6020B	Sodium	8.1	mg/L	1.0	01/13/25 18:21	
EPA 6020B	Thallium	0.00027J	mg/L	0.0010	01/14/25 15:42	
92772942002	HAM-PT-08					
EPA 6020B	Lithium	0.028J	mg/L	0.030	01/23/25 14:13	
SM 2540C-2015	Total Dissolved Solids	479	mg/L	25.0	01/09/25 13:49	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	111	mg/L	5.0	01/14/25 13:54	
SM 2320B-2011	Alkalinity, Total as CaCO3	111	mg/L	5.0	01/14/25 13:54	
EPA 300.0 Rev 2.1 1993	Chloride	17.7	mg/L	1.0	01/09/25 08:32	
EPA 300.0 Rev 2.1 1993	Fluoride	0.23	mg/L	0.10	01/09/25 08:32	
EPA 300.0 Rev 2.1 1993	Sulfate	183	mg/L	4.0	01/09/25 18:32	
EPA 6020B	Arsenic	0.062	mg/L	0.0050	01/13/25 18:30	
EPA 6020B	Barium	0.051	mg/L	0.0050	01/13/25 18:30	
EPA 6020B	Boron	0.92J	mg/L	0.80	01/14/25 16:53	
EPA 6020B	Calcium	105	mg/L	20.0	01/14/25 16:53	
EPA 6020B	Cobalt	0.042	mg/L	0.0050	01/13/25 18:30	
EPA 6020B	Iron	1.3	mg/L	0.040	01/13/25 18:30	
EPA 6020B	Magnesium	13.7	mg/L	0.050	01/13/25 18:30	
EPA 6020B	Manganese	2.7	mg/L	0.80	01/14/25 16:53	
EPA 6020B	Molybdenum	0.010J	mg/L	0.010	01/13/25 18:30	
EPA 6020B	Potassium	5.5	mg/L	0.50	01/13/25 18:30	
EPA 6020B	Sodium	7.2	mg/L	1.0	01/13/25 18:30	
EPA 6020B	Thallium	0.00025J	mg/L	0.0010	01/14/25 15:51	
92772942003	HAM-PT-09					
EPA 6020B	Lithium	0.0021J	mg/L	0.030	01/23/25 14:17	
SM 2540C-2015	Total Dissolved Solids	490	mg/L	25.0	01/09/25 13:55	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	131	mg/L	5.0	01/14/25 17:01	
SM 2320B-2011	Alkalinity, Total as CaCO3	131	mg/L	5.0	01/14/25 17:01	
EPA 300.0 Rev 2.1 1993	Chloride	50.2	mg/L	1.0	01/09/25 08:48	
EPA 300.0 Rev 2.1 1993	Fluoride	0.37	mg/L	0.10	01/09/25 08:48	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92772942

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92772942003	HAM-PT-09					
EPA 300.0 Rev 2.1 1993	Sulfate	127	mg/L	3.0	01/09/25 18:47	
EPA 6020B	Barium	0.065	mg/L	0.0050	01/13/25 18:38	
EPA 6020B	Boron	1.8	mg/L	0.80	01/14/25 17:01	
EPA 6020B	Cadmium	0.00013J	mg/L	0.00050	01/13/25 18:38	
EPA 6020B	Calcium	90.2	mg/L	20.0	01/14/25 17:01	
EPA 6020B	Cobalt	0.0023J	mg/L	0.0050	01/13/25 18:38	
EPA 6020B	Iron	0.26	mg/L	0.040	01/13/25 18:38	
EPA 6020B	Magnesium	20.7	mg/L	0.050	01/13/25 18:38	
EPA 6020B	Manganese	0.36J	mg/L	0.80	01/14/25 17:01	
EPA 6020B	Molybdenum	0.19	mg/L	0.010	01/13/25 18:38	
EPA 6020B	Potassium	6.7	mg/L	0.50	01/13/25 18:38	
EPA 6020B	Sodium	14.1	mg/L	1.0	01/13/25 18:38	
EPA 6020B	Thallium	0.00019J	mg/L	0.0010	01/13/25 18:38	BC
92772942004	HAM-PT-10					
EPA 6020B	Lithium	0.00058J	mg/L	0.030	01/23/25 14:21	
SM 2540C-2015	Total Dissolved Solids	414	mg/L	25.0	01/09/25 13:56	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	105	mg/L	5.0	01/15/25 11:47	
SM 2320B-2011	Alkalinity, Total as CaCO3	105	mg/L	5.0	01/15/25 11:47	
EPA 300.0 Rev 2.1 1993	Chloride	50.4	mg/L	1.0	01/09/25 09:04	
EPA 300.0 Rev 2.1 1993	Fluoride	0.20	mg/L	0.10	01/09/25 09:04	
EPA 300.0 Rev 2.1 1993	Sulfate	112	mg/L	3.0	01/09/25 19:02	
EPA 6020B	Barium	0.048	mg/L	0.0050	01/13/25 18:47	
EPA 6020B	Boron	1.6	mg/L	0.80	01/14/25 17:10	
EPA 6020B	Calcium	93.1	mg/L	20.0	01/14/25 17:10	
EPA 6020B	Cobalt	0.0013J	mg/L	0.0050	01/13/25 18:47	
EPA 6020B	Iron	0.19	mg/L	0.040	01/13/25 18:47	
EPA 6020B	Magnesium	12.3	mg/L	0.050	01/13/25 18:47	
EPA 6020B	Manganese	0.42J	mg/L	0.80	01/14/25 17:10	
EPA 6020B	Molybdenum	0.043	mg/L	0.010	01/13/25 18:47	
EPA 6020B	Potassium	7.1	mg/L	0.50	01/13/25 18:47	
EPA 6020B	Sodium	10.3	mg/L	1.0	01/13/25 18:47	
92772942005	HAM-PT-11					
EPA 6020B	Lithium	0.0010J	mg/L	0.030	01/23/25 14:25	
SM 2540C-2015	Total Dissolved Solids	424	mg/L	25.0	01/09/25 13:56	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	121	mg/L	5.0	01/15/25 12:13	
SM 2320B-2011	Alkalinity, Total as CaCO3	121	mg/L	5.0	01/15/25 12:13	
EPA 300.0 Rev 2.1 1993	Chloride	34.5	mg/L	1.0	01/09/25 09:21	
EPA 300.0 Rev 2.1 1993	Fluoride	0.28	mg/L	0.10	01/09/25 09:21	
EPA 300.0 Rev 2.1 1993	Sulfate	103	mg/L	4.0	01/09/25 19:18	
EPA 6020B	Barium	0.060	mg/L	0.0050	01/13/25 18:56	
EPA 6020B	Boron	1.7	mg/L	0.80	01/14/25 17:19	
EPA 6020B	Calcium	88.8	mg/L	20.0	01/14/25 17:19	
EPA 6020B	Cobalt	0.0017J	mg/L	0.0050	01/13/25 18:56	
EPA 6020B	Iron	0.014J	mg/L	0.040	01/13/25 18:56	
EPA 6020B	Magnesium	12.8	mg/L	0.050	01/13/25 18:56	
EPA 6020B	Manganese	0.33J	mg/L	0.80	01/14/25 17:19	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92772942

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92772942005	HAM-PT-11					
EPA 6020B	Molybdenum	0.12	mg/L	0.010	01/13/25 18:56	
EPA 6020B	Potassium	6.7	mg/L	0.50	01/13/25 18:56	
EPA 6020B	Sodium	8.9	mg/L	1.0	01/13/25 18:56	
92772942006	HAM-PT-12					
EPA 6020B	Lithium	0.00095J	mg/L	0.030	01/23/25 14:51	
SM 2540C-2015	Total Dissolved Solids	506	mg/L	25.0	01/09/25 13:56	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	126	mg/L	5.0	01/15/25 12:38	
SM 2320B-2011	Alkalinity, Total as CaCO3	126	mg/L	5.0	01/15/25 12:38	
EPA 300.0 Rev 2.1 1993	Chloride	55.0	mg/L	1.0	01/09/25 09:37	M1
EPA 300.0 Rev 2.1 1993	Fluoride	0.27	mg/L	0.10	01/09/25 09:37	M1
EPA 300.0 Rev 2.1 1993	Sulfate	130	mg/L	3.0	01/09/25 20:03	M1
EPA 6020B	Barium	0.057	mg/L	0.0050	01/13/25 19:05	
EPA 6020B	Boron	1.8	mg/L	0.80	01/14/25 17:28	
EPA 6020B	Cadmium	0.00013J	mg/L	0.00050	01/13/25 19:05	
EPA 6020B	Calcium	90.2	mg/L	20.0	01/14/25 17:28	
EPA 6020B	Cobalt	0.0019J	mg/L	0.0050	01/13/25 19:05	
EPA 6020B	Iron	0.11	mg/L	0.040	01/13/25 19:05	
EPA 6020B	Magnesium	17.8	mg/L	0.050	01/13/25 19:05	
EPA 6020B	Manganese	0.41J	mg/L	0.80	01/14/25 17:28	
EPA 6020B	Molybdenum	0.13	mg/L	0.010	01/13/25 19:05	
EPA 6020B	Potassium	6.5	mg/L	0.50	01/13/25 19:05	
EPA 6020B	Sodium	12.8	mg/L	1.0	01/13/25 19:05	
EPA 6020B	Thallium	0.00017J	mg/L	0.0010	01/13/25 19:05	BC
92772942007	HAM-PT-13					
EPA 6020B	Lithium	0.053	mg/L	0.030	01/23/25 14:55	
SM 2540C-2015	Total Dissolved Solids	540	mg/L	25.0	01/09/25 13:49	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	155	mg/L	5.0	01/14/25 14:03	
SM 2320B-2011	Alkalinity, Total as CaCO3	155	mg/L	5.0	01/14/25 14:03	
EPA 300.0 Rev 2.1 1993	Chloride	19.1	mg/L	1.0	01/09/25 10:59	
EPA 300.0 Rev 2.1 1993	Fluoride	0.42	mg/L	0.10	01/09/25 10:59	
EPA 300.0 Rev 2.1 1993	Sulfate	186	mg/L	4.0	01/09/25 20:48	
EPA 6020B	Arsenic	0.20	mg/L	0.0050	01/13/25 19:14	
EPA 6020B	Barium	0.047	mg/L	0.0050	01/13/25 19:14	
EPA 6020B	Boron	0.79J	mg/L	0.80	01/14/25 17:37	
EPA 6020B	Calcium	113	mg/L	20.0	01/14/25 17:37	
EPA 6020B	Cobalt	0.021	mg/L	0.0050	01/13/25 19:14	
EPA 6020B	Iron	7.7	mg/L	0.040	01/13/25 19:14	
EPA 6020B	Magnesium	16.4	mg/L	0.050	01/13/25 19:14	
EPA 6020B	Manganese	2.8	mg/L	0.80	01/14/25 17:37	
EPA 6020B	Molybdenum	0.0088J	mg/L	0.010	01/13/25 19:14	
EPA 6020B	Potassium	6.0	mg/L	0.50	01/13/25 19:14	
EPA 6020B	Sodium	8.8	mg/L	1.0	01/13/25 19:14	
EPA 6020B	Thallium	0.00030J	mg/L	0.0010	01/14/25 16:00	
92772942008	HAM-PT-14					
EPA 6020B	Lithium	0.054	mg/L	0.030	01/23/25 14:59	
SM 2540C-2015	Total Dissolved Solids	551	mg/L	25.0	01/09/25 13:49	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92772942

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92772942008	HAM-PT-14					
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO ₃)	161	mg/L	5.0	01/14/25 14:35	
SM 2320B-2011	Alkalinity, Total as CaCO ₃	161	mg/L	5.0	01/14/25 14:35	
EPA 300.0 Rev 2.1 1993	Chloride	19.5	mg/L	1.0	01/09/25 11:15	
EPA 300.0 Rev 2.1 1993	Fluoride	0.34	mg/L	0.10	01/09/25 11:15	
EPA 300.0 Rev 2.1 1993	Sulfate	213	mg/L	4.0	01/09/25 21:03	
EPA 6020B	Arsenic	0.26	mg/L	0.0050	01/13/25 19:22	
EPA 6020B	Barium	0.043	mg/L	0.0050	01/13/25 19:22	
EPA 6020B	Boron	0.80J	mg/L	0.80	01/15/25 13:49	
EPA 6020B	Calcium	125	mg/L	20.0	01/15/25 13:49	
EPA 6020B	Cobalt	0.023	mg/L	0.0050	01/13/25 19:22	
EPA 6020B	Iron	10.5	mg/L	0.040	01/13/25 19:22	
EPA 6020B	Magnesium	16.8	mg/L	0.050	01/13/25 19:22	
EPA 6020B	Manganese	3.2	mg/L	0.80	01/15/25 13:49	
EPA 6020B	Molybdenum	0.013	mg/L	0.010	01/13/25 19:22	
EPA 6020B	Potassium	5.7	mg/L	0.50	01/13/25 19:22	
EPA 6020B	Sodium	7.9	mg/L	1.0	01/13/25 19:22	
EPA 6020B	Thallium	0.00015J	mg/L	0.0010	01/13/25 19:22	BC
92772942009	HAM-PT-15					
EPA 6020B	Lithium	0.043	mg/L	0.030	01/23/25 15:03	
SM 2540C-2015	Total Dissolved Solids	519	mg/L	25.0	01/09/25 13:50	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO ₃)	155	mg/L	5.0	01/14/25 14:51	
SM 2320B-2011	Alkalinity, Total as CaCO ₃	155	mg/L	5.0	01/14/25 14:51	
EPA 300.0 Rev 2.1 1993	Chloride	16.1	mg/L	1.0	01/09/25 11:31	
EPA 300.0 Rev 2.1 1993	Fluoride	0.37	mg/L	0.10	01/09/25 11:31	
EPA 300.0 Rev 2.1 1993	Sulfate	187	mg/L	4.0	01/09/25 21:19	
EPA 6020B	Arsenic	0.053	mg/L	0.0050	01/13/25 19:49	
EPA 6020B	Barium	0.049	mg/L	0.0050	01/13/25 19:49	
EPA 6020B	Boron	0.90J	mg/L	0.80	01/15/25 13:58	
EPA 6020B	Cadmium	0.00039J	mg/L	0.00050	01/13/25 19:49	
EPA 6020B	Calcium	121	mg/L	20.0	01/15/25 13:58	
EPA 6020B	Cobalt	0.025	mg/L	0.0050	01/13/25 19:49	
EPA 6020B	Iron	0.90	mg/L	0.040	01/13/25 19:49	
EPA 6020B	Magnesium	14.3	mg/L	0.050	01/13/25 19:49	
EPA 6020B	Manganese	4.0	mg/L	0.80	01/15/25 13:58	
EPA 6020B	Molybdenum	0.014	mg/L	0.010	01/13/25 19:49	
EPA 6020B	Potassium	5.7	mg/L	0.50	01/13/25 19:49	
EPA 6020B	Sodium	7.7	mg/L	1.0	01/13/25 19:49	
EPA 6020B	Thallium	0.00055J	mg/L	0.0010	01/14/25 16:09	
92772942010	HAM-AP1-EB-01					
EPA 6020B	Magnesium	0.022J	mg/L	0.050	01/13/25 19:58	
EPA 6020B	Manganese	0.0050J	mg/L	0.040	01/13/25 19:58	
92772942011	HAM-AP1-FB-01					
EPA 6020B	Manganese	0.0019J	mg/L	0.040	01/13/25 20:06	
92772942012	HAM-AP1-FD-01					
EPA 6020B	Lithium	0.031	mg/L	0.030	01/23/25 15:16	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92772942

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92772942012	HAM-AP1-FD-01					
SM 2540C-2015	Total Dissolved Solids	478	mg/L	25.0	01/09/25 13:51	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	112	mg/L	5.0	01/14/25 15:02	
SM 2320B-2011	Alkalinity, Total as CaCO3	112	mg/L	5.0	01/14/25 15:02	
EPA 300.0 Rev 2.1 1993	Chloride	17.8	mg/L	1.0	01/09/25 11:48	
EPA 300.0 Rev 2.1 1993	Fluoride	0.23	mg/L	0.10	01/09/25 11:48	
EPA 300.0 Rev 2.1 1993	Sulfate	187	mg/L	4.0	01/09/25 21:34	
EPA 6020B	Arsenic	0.063	mg/L	0.0050	01/13/25 20:15	
EPA 6020B	Barium	0.051	mg/L	0.0050	01/13/25 20:15	
EPA 6020B	Boron	0.91J	mg/L	0.80	01/15/25 14:06	
EPA 6020B	Calcium	111	mg/L	20.0	01/15/25 14:06	
EPA 6020B	Cobalt	0.041	mg/L	0.0050	01/13/25 20:15	
EPA 6020B	Iron	1.3	mg/L	0.040	01/13/25 20:15	
EPA 6020B	Magnesium	13.5	mg/L	0.050	01/13/25 20:15	
EPA 6020B	Manganese	2.9	mg/L	0.80	01/15/25 14:06	
EPA 6020B	Molybdenum	0.0095J	mg/L	0.010	01/13/25 20:15	
EPA 6020B	Potassium	5.4	mg/L	0.50	01/13/25 20:15	
EPA 6020B	Sodium	7.0	mg/L	1.0	01/13/25 20:15	
EPA 6020B	Thallium	0.00024J	mg/L	0.0010	01/14/25 16:18	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92772942

Sample: HAM-PT-07 Lab ID: 92772942001 Collected: 01/06/25 15:44 Received: 01/08/25 12:45 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Lithium	0.049	mg/L	0.030	0.00028	1	01/23/25 10:10	01/23/25 14:09	7439-93-2	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	529	mg/L	25.0	25.0	1		01/09/25 13:49		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	163	mg/L	5.0	5.0	1		01/14/25 13:45		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		01/14/25 13:45		
Alkalinity, Total as CaCO ₃	163	mg/L	5.0	5.0	1		01/14/25 13:45		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		01/10/25 03:15	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	18.1	mg/L	1.0	0.60	1		01/09/25 08:15	16887-00-6	
Fluoride	0.38	mg/L	0.10	0.050	1		01/09/25 08:15	16984-48-8	
Sulfate	181	mg/L	4.0	2.0	4		01/09/25 18:17	14808-79-8	
WC 6020B MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	01/13/25 09:30	01/13/25 18:21	7440-36-0	
Arsenic	0.18	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:21	7440-38-2	
Barium	0.047	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:21	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	01/13/25 09:30	01/13/25 18:21	7440-41-7	
Boron	0.83J	mg/L	0.80	0.12	20	01/13/25 09:30	01/14/25 16:44	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	01/13/25 09:30	01/13/25 18:21	7440-43-9	
Calcium	113	mg/L	20.0	2.0	20	01/13/25 09:30	01/14/25 16:44	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:21	7440-47-3	
Cobalt	0.042	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:21	7440-48-4	
Iron	7.8	mg/L	0.040	0.012	1	01/13/25 09:30	01/13/25 18:21	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	01/13/25 09:30	01/13/25 18:21	7439-92-1	
Magnesium	16.5	mg/L	0.050	0.010	1	01/13/25 09:30	01/13/25 18:21	7439-95-4	
Manganese	3.2	mg/L	0.80	0.025	20	01/13/25 09:30	01/14/25 16:44	7439-96-5	
Molybdenum	0.011	mg/L	0.010	0.0025	1	01/13/25 09:30	01/13/25 18:21	7439-98-7	
Potassium	5.8	mg/L	0.50	0.10	1	01/13/25 09:30	01/13/25 18:21	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:21	7782-49-2	
Sodium	8.1	mg/L	1.0	0.15	1	01/13/25 09:30	01/13/25 18:21	7440-23-5	
Thallium	0.00027J	mg/L	0.0010	0.00015	1	01/13/25 09:30	01/14/25 15:42	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92772942

Sample: HAM-PT-07		Lab ID: 92772942001		Collected: 01/06/25 15:44		Received: 01/08/25 12:45		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00080	0.00036	1	01/15/25 07:18	01/25/25 12:06	7439-97-6	P1

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92772942

Sample: HAM-PT-08		Lab ID: 92772942002		Collected: 01/06/25 16:50		Received: 01/08/25 12:45		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Lithium	0.028J	mg/L	0.030	0.00028	1	01/23/25 10:10	01/23/25 14:13	7439-93-2	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	479	mg/L	25.0	25.0	1		01/09/25 13:49		
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	111	mg/L	5.0	5.0	1		01/14/25 13:54		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		01/14/25 13:54		
Alkalinity, Total as CaCO ₃	111	mg/L	5.0	5.0	1		01/14/25 13:54		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		01/10/25 03:17	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	17.7	mg/L	1.0	0.60	1		01/09/25 08:32	16887-00-6	
Fluoride	0.23	mg/L	0.10	0.050	1		01/09/25 08:32	16984-48-8	
Sulfate	183	mg/L	4.0	2.0	4		01/09/25 18:32	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	01/13/25 09:30	01/13/25 18:30	7440-36-0	
Arsenic	0.062	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:30	7440-38-2	
Barium	0.051	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:30	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	01/13/25 09:30	01/13/25 18:30	7440-41-7	
Boron	0.92J	mg/L	0.80	0.12	20	01/13/25 09:30	01/14/25 16:53	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	01/13/25 09:30	01/13/25 18:30	7440-43-9	
Calcium	105	mg/L	20.0	2.0	20	01/13/25 09:30	01/14/25 16:53	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:30	7440-47-3	
Cobalt	0.042	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:30	7440-48-4	
Iron	1.3	mg/L	0.040	0.012	1	01/13/25 09:30	01/13/25 18:30	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	01/13/25 09:30	01/13/25 18:30	7439-92-1	
Magnesium	13.7	mg/L	0.050	0.010	1	01/13/25 09:30	01/13/25 18:30	7439-95-4	
Manganese	2.7	mg/L	0.80	0.025	20	01/13/25 09:30	01/14/25 16:53	7439-96-5	
Molybdenum	0.010J	mg/L	0.010	0.0025	1	01/13/25 09:30	01/13/25 18:30	7439-98-7	
Potassium	5.5	mg/L	0.50	0.10	1	01/13/25 09:30	01/13/25 18:30	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:30	7782-49-2	
Sodium	7.2	mg/L	1.0	0.15	1	01/13/25 09:30	01/13/25 18:30	7440-23-5	
Thallium	0.00025J	mg/L	0.0010	0.00015	1	01/13/25 09:30	01/14/25 15:51	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92772942

Sample: HAM-PT-08		Lab ID: 92772942002		Collected: 01/06/25 16:50		Received: 01/08/25 12:45		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	01/15/25 07:18	01/25/25 12:14	7439-97-6	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92772942

Sample: HAM-PT-09 Lab ID: 92772942003 Collected: 01/07/25 10:37 Received: 01/08/25 12:45 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Lithium	0.0021J	mg/L	0.030	0.00028	1	01/23/25 10:10	01/23/25 14:17	7439-93-2	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	490	mg/L	25.0	25.0	1		01/09/25 13:55		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	131	mg/L	5.0	5.0	1		01/14/25 17:01		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		01/14/25 17:01		
Alkalinity, Total as CaCO ₃	131	mg/L	5.0	5.0	1		01/14/25 17:01		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		01/10/25 03:22	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	50.2	mg/L	1.0	0.60	1		01/09/25 08:48	16887-00-6	
Fluoride	0.37	mg/L	0.10	0.050	1		01/09/25 08:48	16984-48-8	
Sulfate	127	mg/L	3.0	1.5	3		01/09/25 18:47	14808-79-8	
WC 6020B MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	01/13/25 09:30	01/13/25 18:38	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:38	7440-38-2	
Barium	0.065	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:38	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	01/13/25 09:30	01/13/25 18:38	7440-41-7	
Boron	1.8	mg/L	0.80	0.12	20	01/13/25 09:30	01/14/25 17:01	7440-42-8	
Cadmium	0.00013J	mg/L	0.00050	0.00012	1	01/13/25 09:30	01/13/25 18:38	7440-43-9	
Calcium	90.2	mg/L	20.0	2.0	20	01/13/25 09:30	01/14/25 17:01	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:38	7440-47-3	
Cobalt	0.0023J	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:38	7440-48-4	
Iron	0.26	mg/L	0.040	0.012	1	01/13/25 09:30	01/13/25 18:38	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	01/13/25 09:30	01/13/25 18:38	7439-92-1	
Magnesium	20.7	mg/L	0.050	0.010	1	01/13/25 09:30	01/13/25 18:38	7439-95-4	
Manganese	0.36J	mg/L	0.80	0.025	20	01/13/25 09:30	01/14/25 17:01	7439-96-5	
Molybdenum	0.19	mg/L	0.010	0.0025	1	01/13/25 09:30	01/13/25 18:38	7439-98-7	
Potassium	6.7	mg/L	0.50	0.10	1	01/13/25 09:30	01/13/25 18:38	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:38	7782-49-2	
Sodium	14.1	mg/L	1.0	0.15	1	01/13/25 09:30	01/13/25 18:38	7440-23-5	
Thallium	0.00019J	mg/L	0.0010	0.00015	1	01/13/25 09:30	01/13/25 18:38	7440-28-0	BC

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92772942

Sample: HAM-PT-09		Lab ID: 92772942003		Collected: 01/07/25 10:37		Received: 01/08/25 12:45		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	01/15/25 07:18	01/25/25 12:16	7439-97-6	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92772942

Sample: HAM-PT-10 Lab ID: 92772942004 Collected: 01/07/25 12:30 Received: 01/08/25 12:45 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Lithium	0.00058J	mg/L	0.030	0.00028	1	01/23/25 10:10	01/23/25 14:21	7439-93-2	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	414	mg/L	25.0	25.0	1		01/09/25 13:56		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	105	mg/L	5.0	5.0	1		01/15/25 11:47		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		01/15/25 11:47		
Alkalinity, Total as CaCO ₃	105	mg/L	5.0	5.0	1		01/15/25 11:47		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		01/10/25 03:23	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	50.4	mg/L	1.0	0.60	1		01/09/25 09:04	16887-00-6	
Fluoride	0.20	mg/L	0.10	0.050	1		01/09/25 09:04	16984-48-8	
Sulfate	112	mg/L	3.0	1.5	3		01/09/25 19:02	14808-79-8	
WC 6020B MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	01/13/25 09:30	01/13/25 18:47	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:47	7440-38-2	
Barium	0.048	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:47	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	01/13/25 09:30	01/13/25 18:47	7440-41-7	
Boron	1.6	mg/L	0.80	0.12	20	01/13/25 09:30	01/14/25 17:10	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	01/13/25 09:30	01/13/25 18:47	7440-43-9	
Calcium	93.1	mg/L	20.0	2.0	20	01/13/25 09:30	01/14/25 17:10	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:47	7440-47-3	
Cobalt	0.0013J	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:47	7440-48-4	
Iron	0.19	mg/L	0.040	0.012	1	01/13/25 09:30	01/13/25 18:47	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	01/13/25 09:30	01/13/25 18:47	7439-92-1	
Magnesium	12.3	mg/L	0.050	0.010	1	01/13/25 09:30	01/13/25 18:47	7439-95-4	
Manganese	0.42J	mg/L	0.80	0.025	20	01/13/25 09:30	01/14/25 17:10	7439-96-5	
Molybdenum	0.043	mg/L	0.010	0.0025	1	01/13/25 09:30	01/13/25 18:47	7439-98-7	
Potassium	7.1	mg/L	0.50	0.10	1	01/13/25 09:30	01/13/25 18:47	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:47	7782-49-2	
Sodium	10.3	mg/L	1.0	0.15	1	01/13/25 09:30	01/13/25 18:47	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	01/13/25 09:30	01/13/25 18:47	7440-28-0	BC

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92772942

Sample: HAM-PT-10		Lab ID: 92772942004		Collected: 01/07/25 12:30		Received: 01/08/25 12:45		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	01/15/25 07:18	01/25/25 12:19	7439-97-6	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92772942

Sample: HAM-PT-11 Lab ID: 92772942005 Collected: 01/07/25 11:37 Received: 01/08/25 12:45 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Lithium	0.0010J	mg/L	0.030	0.00028	1	01/23/25 10:10	01/23/25 14:25	7439-93-2	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	424	mg/L	25.0	25.0	1		01/09/25 13:56		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	121	mg/L	5.0	5.0	1		01/15/25 12:13		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		01/15/25 12:13		
Alkalinity, Total as CaCO ₃	121	mg/L	5.0	5.0	1		01/15/25 12:13		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		01/10/25 03:24	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	34.5	mg/L	1.0	0.60	1		01/09/25 09:21	16887-00-6	
Fluoride	0.28	mg/L	0.10	0.050	1		01/09/25 09:21	16984-48-8	
Sulfate	103	mg/L	4.0	2.0	4		01/09/25 19:18	14808-79-8	
WC 6020B MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	01/13/25 09:30	01/13/25 18:56	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:56	7440-38-2	
Barium	0.060	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:56	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	01/13/25 09:30	01/13/25 18:56	7440-41-7	
Boron	1.7	mg/L	0.80	0.12	20	01/13/25 09:30	01/14/25 17:19	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	01/13/25 09:30	01/13/25 18:56	7440-43-9	
Calcium	88.8	mg/L	20.0	2.0	20	01/13/25 09:30	01/14/25 17:19	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:56	7440-47-3	
Cobalt	0.0017J	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:56	7440-48-4	
Iron	0.014J	mg/L	0.040	0.012	1	01/13/25 09:30	01/13/25 18:56	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	01/13/25 09:30	01/13/25 18:56	7439-92-1	
Magnesium	12.8	mg/L	0.050	0.010	1	01/13/25 09:30	01/13/25 18:56	7439-95-4	
Manganese	0.33J	mg/L	0.80	0.025	20	01/13/25 09:30	01/14/25 17:19	7439-96-5	
Molybdenum	0.12	mg/L	0.010	0.0025	1	01/13/25 09:30	01/13/25 18:56	7439-98-7	
Potassium	6.7	mg/L	0.50	0.10	1	01/13/25 09:30	01/13/25 18:56	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 18:56	7782-49-2	
Sodium	8.9	mg/L	1.0	0.15	1	01/13/25 09:30	01/13/25 18:56	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	01/13/25 09:30	01/13/25 18:56	7440-28-0	BC

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92772942

Sample: HAM-PT-11		Lab ID: 92772942005		Collected: 01/07/25 11:37		Received: 01/08/25 12:45		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - West Columbia							
Mercury	ND	mg/L	0.00020	0.000091	1	01/15/25 07:18	01/25/25 12:22	7439-97-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92772942

Sample: HAM-PT-12		Lab ID: 92772942006		Collected: 01/07/25 09:36		Received: 01/08/25 12:45		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Lithium	0.00095J	mg/L	0.030	0.00028	1	01/23/25 10:10	01/23/25 14:51	7439-93-2	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	506	mg/L	25.0	25.0	1		01/09/25 13:56		
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	126	mg/L	5.0	5.0	1		01/15/25 12:38		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		01/15/25 12:38		
Alkalinity, Total as CaCO ₃	126	mg/L	5.0	5.0	1		01/15/25 12:38		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		01/10/25 03:24	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	55.0	mg/L	1.0	0.60	1		01/09/25 09:37	16887-00-6	M1
Fluoride	0.27	mg/L	0.10	0.050	1		01/09/25 09:37	16984-48-8	M1
Sulfate	130	mg/L	3.0	1.5	3		01/09/25 20:03	14808-79-8	M1
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	01/13/25 09:30	01/13/25 19:05	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:05	7440-38-2	
Barium	0.057	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:05	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	01/13/25 09:30	01/13/25 19:05	7440-41-7	
Boron	1.8	mg/L	0.80	0.12	20	01/13/25 09:30	01/14/25 17:28	7440-42-8	
Cadmium	0.00013J	mg/L	0.00050	0.00012	1	01/13/25 09:30	01/13/25 19:05	7440-43-9	
Calcium	90.2	mg/L	20.0	2.0	20	01/13/25 09:30	01/14/25 17:28	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:05	7440-47-3	
Cobalt	0.0019J	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:05	7440-48-4	
Iron	0.11	mg/L	0.040	0.012	1	01/13/25 09:30	01/13/25 19:05	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	01/13/25 09:30	01/13/25 19:05	7439-92-1	
Magnesium	17.8	mg/L	0.050	0.010	1	01/13/25 09:30	01/13/25 19:05	7439-95-4	
Manganese	0.41J	mg/L	0.80	0.025	20	01/13/25 09:30	01/14/25 17:28	7439-96-5	
Molybdenum	0.13	mg/L	0.010	0.0025	1	01/13/25 09:30	01/13/25 19:05	7439-98-7	
Potassium	6.5	mg/L	0.50	0.10	1	01/13/25 09:30	01/13/25 19:05	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:05	7782-49-2	
Sodium	12.8	mg/L	1.0	0.15	1	01/13/25 09:30	01/13/25 19:05	7440-23-5	
Thallium	0.00017J	mg/L	0.0010	0.00015	1	01/13/25 09:30	01/13/25 19:05	7440-28-0	BC

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92772942

Sample: HAM-PT-12		Lab ID: 92772942006		Collected: 01/07/25 09:36		Received: 01/08/25 12:45		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	01/15/25 07:18	01/25/25 12:24	7439-97-6	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92772942

Sample: HAM-PT-13 Lab ID: 92772942007 Collected: 01/06/25 12:47 Received: 01/08/25 12:45 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Lithium	0.053	mg/L	0.030	0.00028	1	01/23/25 10:10	01/23/25 14:55	7439-93-2	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	540	mg/L	25.0	25.0	1		01/09/25 13:49		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	155	mg/L	5.0	5.0	1		01/14/25 14:03		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		01/14/25 14:03		
Alkalinity, Total as CaCO ₃	155	mg/L	5.0	5.0	1		01/14/25 14:03		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		01/10/25 03:17	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	19.1	mg/L	1.0	0.60	1		01/09/25 10:59	16887-00-6	
Fluoride	0.42	mg/L	0.10	0.050	1		01/09/25 10:59	16984-48-8	
Sulfate	186	mg/L	4.0	2.0	4		01/09/25 20:48	14808-79-8	
WC 6020B MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	01/13/25 09:30	01/13/25 19:14	7440-36-0	
Arsenic	0.20	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:14	7440-38-2	
Barium	0.047	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:14	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	01/13/25 09:30	01/13/25 19:14	7440-41-7	
Boron	0.79J	mg/L	0.80	0.12	20	01/13/25 09:30	01/14/25 17:37	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	01/13/25 09:30	01/13/25 19:14	7440-43-9	
Calcium	113	mg/L	20.0	2.0	20	01/13/25 09:30	01/14/25 17:37	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:14	7440-47-3	
Cobalt	0.021	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:14	7440-48-4	
Iron	7.7	mg/L	0.040	0.012	1	01/13/25 09:30	01/13/25 19:14	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	01/13/25 09:30	01/13/25 19:14	7439-92-1	
Magnesium	16.4	mg/L	0.050	0.010	1	01/13/25 09:30	01/13/25 19:14	7439-95-4	
Manganese	2.8	mg/L	0.80	0.025	20	01/13/25 09:30	01/14/25 17:37	7439-96-5	
Molybdenum	0.0088J	mg/L	0.010	0.0025	1	01/13/25 09:30	01/13/25 19:14	7439-98-7	
Potassium	6.0	mg/L	0.50	0.10	1	01/13/25 09:30	01/13/25 19:14	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:14	7782-49-2	
Sodium	8.8	mg/L	1.0	0.15	1	01/13/25 09:30	01/13/25 19:14	7440-23-5	
Thallium	0.00030J	mg/L	0.0010	0.00015	1	01/13/25 09:30	01/14/25 16:00	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92772942

Sample: HAM-PT-13		Lab ID: 92772942007		Collected: 01/06/25 12:47		Received: 01/08/25 12:45		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	01/15/25 07:18	01/25/25 12:33	7439-97-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92772942

Sample: HAM-PT-14		Lab ID: 92772942008		Collected: 01/06/25 12:40		Received: 01/08/25 12:45		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Lithium	0.054	mg/L	0.030	0.00028	1	01/23/25 10:10	01/23/25 14:59	7439-93-2	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	551	mg/L	25.0	25.0	1		01/09/25 13:49		
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	161	mg/L	5.0	5.0	1		01/14/25 14:35		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		01/14/25 14:35		
Alkalinity, Total as CaCO ₃	161	mg/L	5.0	5.0	1		01/14/25 14:35		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		01/10/25 03:17	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	19.5	mg/L	1.0	0.60	1		01/09/25 11:15	16887-00-6	
Fluoride	0.34	mg/L	0.10	0.050	1		01/09/25 11:15	16984-48-8	
Sulfate	213	mg/L	4.0	2.0	4		01/09/25 21:03	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	01/13/25 09:30	01/13/25 19:22	7440-36-0	
Arsenic	0.26	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:22	7440-38-2	
Barium	0.043	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:22	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	01/13/25 09:30	01/13/25 19:22	7440-41-7	
Boron	0.80J	mg/L	0.80	0.12	20	01/13/25 09:30	01/15/25 13:49	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	01/13/25 09:30	01/13/25 19:22	7440-43-9	
Calcium	125	mg/L	20.0	2.0	20	01/13/25 09:30	01/15/25 13:49	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:22	7440-47-3	
Cobalt	0.023	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:22	7440-48-4	
Iron	10.5	mg/L	0.040	0.012	1	01/13/25 09:30	01/13/25 19:22	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	01/13/25 09:30	01/13/25 19:22	7439-92-1	
Magnesium	16.8	mg/L	0.050	0.010	1	01/13/25 09:30	01/13/25 19:22	7439-95-4	
Manganese	3.2	mg/L	0.80	0.025	20	01/13/25 09:30	01/15/25 13:49	7439-96-5	
Molybdenum	0.013	mg/L	0.010	0.0025	1	01/13/25 09:30	01/13/25 19:22	7439-98-7	
Potassium	5.7	mg/L	0.50	0.10	1	01/13/25 09:30	01/13/25 19:22	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:22	7782-49-2	
Sodium	7.9	mg/L	1.0	0.15	1	01/13/25 09:30	01/13/25 19:22	7440-23-5	
Thallium	0.00015J	mg/L	0.0010	0.00015	1	01/13/25 09:30	01/13/25 19:22	7440-28-0	BC

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92772942

Sample: HAM-PT-14		Lab ID: 92772942008		Collected: 01/06/25 12:40		Received: 01/08/25 12:45		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	01/15/25 07:18	01/25/25 12:35	7439-97-6	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92772942

Sample: HAM-PT-15		Lab ID: 92772942009		Collected: 01/06/25 14:23		Received: 01/08/25 12:45		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA							
Lithium	0.043	mg/L	0.030	0.00028	1	01/23/25 10:10	01/23/25 15:03	7439-93-2	
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA							
Total Dissolved Solids	519	mg/L	25.0	25.0	1		01/09/25 13:50		
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	155	mg/L	5.0	5.0	1		01/14/25 14:51		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		01/14/25 14:51		
Alkalinity, Total as CaCO ₃	155	mg/L	5.0	5.0	1		01/14/25 14:51		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		01/10/25 03:18	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	16.1	mg/L	1.0	0.60	1		01/09/25 11:31	16887-00-6	
Fluoride	0.37	mg/L	0.10	0.050	1		01/09/25 11:31	16984-48-8	
Sulfate	187	mg/L	4.0	2.0	4		01/09/25 21:19	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	01/13/25 09:30	01/13/25 19:49	7440-36-0	
Arsenic	0.053	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:49	7440-38-2	
Barium	0.049	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:49	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	01/13/25 09:30	01/13/25 19:49	7440-41-7	
Boron	0.90J	mg/L	0.80	0.12	20	01/13/25 09:30	01/15/25 13:58	7440-42-8	
Cadmium	0.00039J	mg/L	0.00050	0.00012	1	01/13/25 09:30	01/13/25 19:49	7440-43-9	
Calcium	121	mg/L	20.0	2.0	20	01/13/25 09:30	01/15/25 13:58	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:49	7440-47-3	
Cobalt	0.025	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:49	7440-48-4	
Iron	0.90	mg/L	0.040	0.012	1	01/13/25 09:30	01/13/25 19:49	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	01/13/25 09:30	01/13/25 19:49	7439-92-1	
Magnesium	14.3	mg/L	0.050	0.010	1	01/13/25 09:30	01/13/25 19:49	7439-95-4	
Manganese	4.0	mg/L	0.80	0.025	20	01/13/25 09:30	01/15/25 13:58	7439-96-5	
Molybdenum	0.014	mg/L	0.010	0.0025	1	01/13/25 09:30	01/13/25 19:49	7439-98-7	
Potassium	5.7	mg/L	0.50	0.10	1	01/13/25 09:30	01/13/25 19:49	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:49	7782-49-2	
Sodium	7.7	mg/L	1.0	0.15	1	01/13/25 09:30	01/13/25 19:49	7440-23-5	
Thallium	0.00055J	mg/L	0.0010	0.00015	1	01/13/25 09:30	01/14/25 16:09	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92772942

Sample: HAM-PT-15		Lab ID: 92772942009		Collected: 01/06/25 14:23		Received: 01/08/25 12:45		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	01/15/25 07:18	01/25/25 12:38	7439-97-6	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92772942

Sample: HAM-AP1-EB-01 Lab ID: 92772942010 Collected: 01/07/25 12:55 Received: 01/08/25 12:45 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Lithium	ND	mg/L	0.030	0.00028	1	01/23/25 10:10	01/23/25 15:07	7439-93-2	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		01/09/25 18:15		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		01/15/25 12:56		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		01/15/25 12:56		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		01/15/25 12:56		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		01/10/25 03:25	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		01/08/25 23:33	16887-00-6	
Fluoride	ND	mg/L	0.10	0.050	1		01/08/25 23:33	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		01/08/25 23:33	14808-79-8	
WC 6020B MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	01/13/25 09:30	01/13/25 19:58	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:58	7440-38-2	
Barium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:58	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	01/13/25 09:30	01/13/25 19:58	7440-41-7	
Boron	ND	mg/L	0.040	0.0062	1	01/13/25 09:30	01/13/25 19:58	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	01/13/25 09:30	01/13/25 19:58	7440-43-9	
Calcium	ND	mg/L	1.0	0.10	1	01/13/25 09:30	01/13/25 19:58	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:58	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:58	7440-48-4	
Iron	ND	mg/L	0.040	0.012	1	01/13/25 09:30	01/13/25 19:58	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	01/13/25 09:30	01/13/25 19:58	7439-92-1	
Magnesium	0.022J	mg/L	0.050	0.010	1	01/13/25 09:30	01/13/25 19:58	7439-95-4	
Manganese	0.0050J	mg/L	0.040	0.0012	1	01/13/25 09:30	01/13/25 19:58	7439-96-5	
Molybdenum	ND	mg/L	0.010	0.0025	1	01/13/25 09:30	01/13/25 19:58	7439-98-7	
Potassium	ND	mg/L	0.50	0.10	1	01/13/25 09:30	01/13/25 19:58	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 19:58	7782-49-2	
Sodium	ND	mg/L	1.0	0.15	1	01/13/25 09:30	01/13/25 19:58	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	01/13/25 09:30	01/13/25 19:58	7440-28-0	BC

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92772942

Sample: HAM-AP1-EB-01		Lab ID: 92772942010		Collected: 01/07/25 12:55		Received: 01/08/25 12:45		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00080	0.00036	1	01/15/25 07:18	01/25/25 12:41	7439-97-6	P1

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92772942

Sample: HAM-AP1-FB-01 Lab ID: 92772942011 Collected: 01/07/25 12:50 Received: 01/08/25 12:45 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Lithium	ND	mg/L	0.030	0.00028	1	01/23/25 10:10	01/23/25 15:12	7439-93-2	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		01/09/25 18:16		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		01/15/25 13:00		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		01/15/25 13:00		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		01/15/25 13:00		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		01/10/25 03:25	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		01/08/25 23:49	16887-00-6	
Fluoride	ND	mg/L	0.10	0.050	1		01/08/25 23:49	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		01/08/25 23:49	14808-79-8	
WC 6020B MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	01/13/25 09:30	01/13/25 20:06	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 20:06	7440-38-2	
Barium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 20:06	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	01/13/25 09:30	01/13/25 20:06	7440-41-7	
Boron	ND	mg/L	0.040	0.0062	1	01/13/25 09:30	01/13/25 20:06	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	01/13/25 09:30	01/13/25 20:06	7440-43-9	
Calcium	ND	mg/L	1.0	0.10	1	01/13/25 09:30	01/13/25 20:06	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 20:06	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 20:06	7440-48-4	
Iron	ND	mg/L	0.040	0.012	1	01/13/25 09:30	01/13/25 20:06	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	01/13/25 09:30	01/13/25 20:06	7439-92-1	
Magnesium	ND	mg/L	0.050	0.010	1	01/13/25 09:30	01/13/25 20:06	7439-95-4	
Manganese	0.0019J	mg/L	0.040	0.0012	1	01/13/25 09:30	01/13/25 20:06	7439-96-5	
Molybdenum	ND	mg/L	0.010	0.0025	1	01/13/25 09:30	01/13/25 20:06	7439-98-7	
Potassium	ND	mg/L	0.50	0.10	1	01/13/25 09:30	01/13/25 20:06	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 20:06	7782-49-2	
Sodium	ND	mg/L	1.0	0.15	1	01/13/25 09:30	01/13/25 20:06	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	01/13/25 09:30	01/13/25 20:06	7440-28-0	BC

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92772942

Sample: HAM-AP1-FB-01		Lab ID: 92772942011		Collected: 01/07/25 12:50		Received: 01/08/25 12:45		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	01/15/25 07:18	01/25/25 12:49	7439-97-6	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92772942

Sample: HAM-AP1-FD-01 Lab ID: 92772942012 Collected: 01/06/25 00:00 Received: 01/08/25 12:45 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - Peachtree Corners, GA									
Lithium	0.031	mg/L	0.030	0.00028	1	01/23/25 10:10	01/23/25 15:16	7439-93-2	
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Peachtree Corners, GA									
Total Dissolved Solids	478	mg/L	25.0	25.0	1		01/09/25 13:51		
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	112	mg/L	5.0	5.0	1		01/14/25 15:02		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		01/14/25 15:02		
Alkalinity, Total as CaCO ₃	112	mg/L	5.0	5.0	1		01/14/25 15:02		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		01/10/25 03:18	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	17.8	mg/L	1.0	0.60	1		01/09/25 11:48	16887-00-6	
Fluoride	0.23	mg/L	0.10	0.050	1		01/09/25 11:48	16984-48-8	
Sulfate	187	mg/L	4.0	2.0	4		01/09/25 21:34	14808-79-8	
WC 6020B MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	01/13/25 09:30	01/13/25 20:15	7440-36-0	
Arsenic	0.063	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 20:15	7440-38-2	
Barium	0.051	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 20:15	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	01/13/25 09:30	01/13/25 20:15	7440-41-7	
Boron	0.91J	mg/L	0.80	0.12	20	01/13/25 09:30	01/15/25 14:06	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	01/13/25 09:30	01/13/25 20:15	7440-43-9	
Calcium	111	mg/L	20.0	2.0	20	01/13/25 09:30	01/15/25 14:06	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 20:15	7440-47-3	
Cobalt	0.041	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 20:15	7440-48-4	
Iron	1.3	mg/L	0.040	0.012	1	01/13/25 09:30	01/13/25 20:15	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	01/13/25 09:30	01/13/25 20:15	7439-92-1	
Magnesium	13.5	mg/L	0.050	0.010	1	01/13/25 09:30	01/13/25 20:15	7439-95-4	
Manganese	2.9	mg/L	0.80	0.025	20	01/13/25 09:30	01/15/25 14:06	7439-96-5	
Molybdenum	0.0095J	mg/L	0.010	0.0025	1	01/13/25 09:30	01/13/25 20:15	7439-98-7	
Potassium	5.4	mg/L	0.50	0.10	1	01/13/25 09:30	01/13/25 20:15	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	01/13/25 09:30	01/13/25 20:15	7782-49-2	
Sodium	7.0	mg/L	1.0	0.15	1	01/13/25 09:30	01/13/25 20:15	7440-23-5	
Thallium	0.00024J	mg/L	0.0010	0.00015	1	01/13/25 09:30	01/14/25 16:18	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92772942

Sample: HAM-AP1-FD-01		Lab ID: 92772942012		Collected: 01/06/25 00:00		Received: 01/08/25 12:45		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	01/15/25 07:18	01/25/25 12:51	7439-97-6	

REPORT OF LABORATORY ANALYSIS



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92772942

QC Batch:	910720	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	6020 MET
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92772942001, 92772942002, 92772942003, 92772942004, 92772942005, 92772942006, 92772942007, 92772942008, 92772942009, 92772942010, 92772942011, 92772942012		

METHOD BLANK:	4683194	Matrix:	Water
Associated Lab Samples:	92772942001, 92772942002, 92772942003, 92772942004, 92772942005, 92772942006, 92772942007, 92772942008, 92772942009, 92772942010, 92772942011, 92772942012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Lithium	mg/L	ND	0.030	0.00028	01/23/25 14:00	

LABORATORY CONTROL SAMPLE:	4683195					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Lithium	mg/L	0.1	0.11	108	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:	4683196			4683197								
Parameter	Units	92772942005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Lithium	mg/L	0.0010J	0.1	0.1	0.10	0.10	102	103	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92772942

QC Batch:	907726	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Peachtree Corners, GA
Associated Lab Samples:	92772942001, 92772942002, 92772942003, 92772942004, 92772942005, 92772942006, 92772942007, 92772942008, 92772942009, 92772942012		

METHOD BLANK:	4669204	Matrix:	Water
Associated Lab Samples:	92772942001, 92772942002, 92772942003, 92772942004, 92772942005, 92772942006, 92772942007, 92772942008, 92772942009, 92772942012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	01/09/25 13:47	

LABORATORY CONTROL SAMPLE:	4669205					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	362	90	80-120	

SAMPLE DUPLICATE:	4669206					
Parameter	Units	92772563001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	248	254	2	10	

SAMPLE DUPLICATE:	4669207					
Parameter	Units	92772479002 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	112	120	7	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92772942

QC Batch: 907875

Analysis Method: SM 2540C-2015

QC Batch Method: SM 2540C-2015

Analysis Description: 2540C Total Dissolved Solids

Laboratory: Pace Analytical Services - Peachtree Corners, GA

Associated Lab Samples: 92772942010, 92772942011

METHOD BLANK: 4670248

Matrix: Water

Associated Lab Samples: 92772942010, 92772942011

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	01/09/25 18:14	

LABORATORY CONTROL SAMPLE: 4670249

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	400	361	90	80-120	

SAMPLE DUPLICATE: 4670250

Parameter	Units	92773113036 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	107	118	10	10	

SAMPLE DUPLICATE: 4670251

Parameter	Units	92773113037 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	43.0	65.0	41	10	D6

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92772942

QC Batch: 907689

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92772942001, 92772942002, 92772942003, 92772942007, 92772942008, 92772942009, 92772942012

METHOD BLANK: 4668970

Matrix: Water

Associated Lab Samples: 92772942001, 92772942002, 92772942003, 92772942007, 92772942008, 92772942009, 92772942012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	01/14/25 12:57	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	01/14/25 12:57	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	01/14/25 12:57	

LABORATORY CONTROL SAMPLE: 4668971

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	50.2	100	80-120	

LABORATORY CONTROL SAMPLE: 4668972

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	50.5	101	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4672574 4672575

Parameter	Units	92772765001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	912	50	50	951	959	77	93	80-120	1	25	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4672576 4672577

Parameter	Units	92772942003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	131	50	50	182	183	103	104	80-120	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92772942

QC Batch: 908504

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92772942004, 92772942005, 92772942006, 92772942010, 92772942011

METHOD BLANK: 4672951

Matrix: Water

Associated Lab Samples: 92772942004, 92772942005, 92772942006, 92772942010, 92772942011

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	01/15/25 11:28	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	01/15/25 11:28	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	01/15/25 11:28	

LABORATORY CONTROL SAMPLE: 4672952

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.8	104	80-120	

LABORATORY CONTROL SAMPLE: 4672953

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.4	103	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4672954 4672955

Parameter	Units	92772942004 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	105	50	50	156	157	103	105	80-120	1	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4672956 4672957

Parameter	Units	92772942005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	121	50	50	167	168	92	93	80-120	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92772942

QC Batch:	907927	Analysis Method:	SM 4500-S2D-2011
QC Batch Method:	SM 4500-S2D-2011	Analysis Description:	4500S2D Sulfide Water
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92772942001, 92772942002, 92772942003, 92772942004, 92772942005, 92772942006, 92772942007, 92772942008, 92772942009, 92772942010, 92772942011, 92772942012		

METHOD BLANK:	4670468	Matrix:	Water
Associated Lab Samples:	92772942001, 92772942002, 92772942003, 92772942004, 92772942005, 92772942006, 92772942007, 92772942008, 92772942009, 92772942010, 92772942011, 92772942012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	01/10/25 03:13	

LABORATORY CONTROL SAMPLE: 4670469						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.53	105	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:												
4670472					4670473							
		92772515002	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Parameter	Units	Result										
Sulfide	mg/L	ND	0.5	0.5	0.48	0.53	95	105	80-120	10	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:													4670499	4670500			
			MS	MSD													
		92772942001	Spike	Spike													
Parameter	Units	Result	Conc.	Conc.	MS	MSD	MS	MSD	% Rec		Max						
					Result	Result	% Rec	% Rec	Limits	RPD	RPD	Qual					
Sulfide	mg/L	ND	0.5	0.5	0.53	0.52	107	104	80-120	2	10						

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92772942

QC Batch:	907517	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92772942001, 92772942002, 92772942003, 92772942004, 92772942005, 92772942006, 92772942007, 92772942008, 92772942009, 92772942010, 92772942011, 92772942012		

METHOD BLANK:	4668315	Matrix:	Water
Associated Lab Samples:	92772942001, 92772942002, 92772942003, 92772942004, 92772942005, 92772942006, 92772942007, 92772942008, 92772942009, 92772942010, 92772942011, 92772942012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	01/08/25 21:52	
Fluoride	mg/L	ND	0.10	0.050	01/08/25 21:52	
Sulfate	mg/L	ND	1.0	0.50	01/08/25 21:52	

LABORATORY CONTROL SAMPLE: 4668316						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	50.6	101	90-110	
Fluoride	mg/L	2.5	2.4	97	90-110	
Sulfate	mg/L	50	50.8	102	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4668317 4668318												
Parameter	Units	92772897001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	2.4	50	50	54.2	55.0	103	105	90-110	2	10	
Fluoride	mg/L	0.059J	2.5	2.5	2.6	2.6	101	102	90-110	1	10	
Sulfate	mg/L	5.2	50	50	57.1	57.9	104	105	90-110	1	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4668319 4668320												
Parameter	Units	92772942006 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	55.0	50	50	92.6	93.1	75	76	90-110	0	10 M1	
Fluoride	mg/L	0.27	2.5	2.5	3.0	3.1	109	111	90-110	2	10 M1	
Sulfate	mg/L	130	50	50	171	171	83	84	90-110	0	10 M1	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92772942

QC Batch:	908184	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	WC 6020B MET
		Laboratory:	Pace Analytical Services - West Columbia
Associated Lab Samples:	92772942001, 92772942002, 92772942003, 92772942004, 92772942005, 92772942006, 92772942007, 92772942008, 92772942009, 92772942010, 92772942011, 92772942012		

METHOD BLANK: 4671543

Matrix: Water

Associated Lab Samples: 92772942001, 92772942002, 92772942003, 92772942004, 92772942005, 92772942006, 92772942007, 92772942008, 92772942009, 92772942010, 92772942011, 92772942012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00050	01/13/25 16:18	
Arsenic	mg/L	ND	0.0050	0.0012	01/13/25 16:18	
Barium	mg/L	ND	0.0050	0.0012	01/13/25 16:18	
Beryllium	mg/L	ND	0.00050	0.00015	01/13/25 16:18	
Boron	mg/L	ND	0.040	0.0062	01/13/25 16:18	
Cadmium	mg/L	ND	0.00050	0.00012	01/13/25 16:18	
Calcium	mg/L	ND	1.0	0.10	01/13/25 16:18	
Chromium	mg/L	ND	0.0050	0.0012	01/13/25 16:18	
Cobalt	mg/L	ND	0.0050	0.0012	01/13/25 16:18	
Iron	mg/L	ND	0.040	0.012	01/13/25 16:18	
Lead	mg/L	ND	0.0010	0.00025	01/13/25 16:18	
Magnesium	mg/L	ND	0.050	0.010	01/13/25 16:18	
Manganese	mg/L	ND	0.040	0.0012	01/13/25 16:18	
Molybdenum	mg/L	ND	0.010	0.0025	01/13/25 16:18	
Potassium	mg/L	ND	0.50	0.10	01/13/25 16:18	
Selenium	mg/L	ND	0.0050	0.0012	01/13/25 16:18	
Sodium	mg/L	ND	1.0	0.15	01/13/25 16:18	
Thallium	mg/L	ND	0.0010	0.00015	01/13/25 16:18	

LABORATORY CONTROL SAMPLE: 4671544

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.098	98	80-120	
Arsenic	mg/L	0.1	0.10	104	80-120	
Barium	mg/L	0.1	0.097	97	80-120	
Beryllium	mg/L	0.1	0.10	102	80-120	
Boron	mg/L	0.1	0.10	102	80-120	
Cadmium	mg/L	0.1	0.099	99	80-120	
Calcium	mg/L	1	1.0	104	80-120	
Chromium	mg/L	0.1	0.10	101	80-120	
Cobalt	mg/L	0.1	0.11	112	80-120	
Iron	mg/L	1	0.99	99	80-120	
Lead	mg/L	0.1	0.11	111	80-120	
Magnesium	mg/L	1	1.0	102	80-120	
Manganese	mg/L	0.1	0.11	107	80-120	
Molybdenum	mg/L	0.1	0.10	100	80-120	
Potassium	mg/L	1	1.1	108	80-120	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92772942

LABORATORY CONTROL SAMPLE: 4671544

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Selenium	mg/L	0.1	0.10	102	80-120	
Sodium	mg/L	1	1.0	102	80-120	
Thallium	mg/L	0.1	0.12	118	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4671545 4671546

Parameter	Units	92772921001	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		Result	Conc.	Conc.	Result	Result	% Rec	% Rec	Limits			
Antimony	mg/L	ND	0.1	0.1	0.089	0.089	88	89	75-125	1	20	
Arsenic	mg/L	ND	0.1	0.1	0.095	0.096	94	95	75-125	1	20	
Barium	mg/L	37.4 ug/L	0.1	0.1	0.14	0.14	104	102	75-125	1	20	
Beryllium	mg/L	0.27J ug/L	0.1	0.1	0.11	0.11	107	106	75-125	1	20	
Boron	mg/L	13.0J ug/L	0.1	0.1	0.12	0.12	110	108	75-125	2	20	
Cadmium	mg/L	ND	0.1	0.1	0.10	0.10	100	101	75-125	0	20	
Calcium	mg/L	5300 ug/L	1	1	6.1	6.0	84	75	75-125	1	20	
Chromium	mg/L	1.9J ug/L	0.1	0.1	0.092	0.093	90	91	75-125	1	20	
Cobalt	mg/L	ND	0.1	0.1	0.11	0.11	109	108	75-125	1	20	
Iron	mg/L	1560 ug/L	1	1	2.8	2.7	119	114	75-125	2	20	
Lead	mg/L	2.2 ug/L	0.1	0.1	0.10	0.10	102	101	75-125	2	20	
Magnesium	mg/L	1350 ug/L	1	1	2.5	2.5	111	114	75-125	1	20	
Manganese	mg/L	66.1 ug/L	0.1	0.1	0.17	0.16	103	97	75-125	3	20	
Molybdenum	mg/L	ND	0.1	0.1	0.090	0.090	89	89	75-125	0	20	
Potassium	mg/L	1740 ug/L	1	1	2.8	2.8	107	107	75-125	0	20	
Selenium	mg/L	ND	0.1	0.1	0.10	0.10	101	102	75-125	1	20	
Sodium	mg/L	11100 ug/L	1	1	11.9	11.8	86	72	75-125	1	20	M1
Thallium	mg/L	ND	0.1	0.1	0.11	0.11	110	107	75-125	3	20	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4671547 4671548

Parameter	Units	92773107001	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		Result	Conc.	Conc.	Result	Result	% Rec	% Rec	Limits			
Antimony	mg/L	ND	0.1	0.1	0.090	0.065	86	61	75-125	33	20	M1,R1
Arsenic	mg/L	ND	0.1	0.1	0.090	0.096	80	86	75-125	6	20	
Barium	mg/L	116 ug/L	0.1	0.1	0.21	0.22	96	104	75-125	3	20	
Beryllium	mg/L	ND	0.1	0.1	0.099	0.098	98	98	75-125	1	20	
Boron	mg/L	ND	0.1	0.1	0.12J	0.12J	100	100	75-125		20	
Cadmium	mg/L	ND	0.1	0.1	0.095	0.094	94	94	75-125	1	20	
Calcium	mg/L	31600 ug/L	1	1	32.4	31.8	80	17	75-125	2	20	M1
Chromium	mg/L	18.8J ug/L	0.1	0.1	0.097	0.11	79	91	75-125	12	20	
Cobalt	mg/L	ND	0.1	0.1	0.097	0.097	95	95	75-125	0	20	
Lead	mg/L	39.9 ug/L	0.1	0.1	0.13	0.14	95	96	75-125	1	20	
Magnesium	mg/L	4030 ug/L	1	1	5.2	5.4	112	139	75-125	5	20	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92772942

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4671547 4671548												
Parameter	Units	92773107001	MS	MSD	MS	MSD	MS	MSD	% Rec	RPD	Max	Qual
		Result	Spike Conc.	Spike Conc.								
Manganese	mg/L	205 ug/L	0.1	0.1	0.31J	0.30J	103	98	75-125	2	20	
Molybdenum	mg/L	ND	0.1	0.1	0.073J	0.064J	69	59	75-125		20	M1
Potassium	mg/L	3430J ug/L	1	1	4.5J	4.9J	106	150	75-125	9	20	M1
Selenium	mg/L	24.2J ug/L	0.1	0.1	0.12	0.12	92	97	75-125	4	20	
Sodium	mg/L	8910 ug/L	1	1	9.8J	9.6J	94	67	75-125	3	20	M1
Thallium	mg/L	ND	0.1	0.1	0.10	0.099	99	99	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92772942

QC Batch:	908632	Analysis Method:	EPA 7470A
QC Batch Method:	EPA 7470A	Analysis Description:	WCOL 7470 Mercury
		Laboratory:	Pace Analytical Services - West Columbia
Associated Lab Samples:	92772942001, 92772942002, 92772942003, 92772942004, 92772942005, 92772942006, 92772942007, 92772942008, 92772942009, 92772942010, 92772942011, 92772942012		

METHOD BLANK:	4673761	Matrix:	Water
Associated Lab Samples:	92772942001, 92772942002, 92772942003, 92772942004, 92772942005, 92772942006, 92772942007, 92772942008, 92772942009, 92772942010, 92772942011, 92772942012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.000091	01/25/25 12:00	

LABORATORY CONTROL SAMPLE: 4673762						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.002	0.0018	91	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:												
4673763					4673764							
		92772942001	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Parameter	Units	Result										
Mercury	mg/L	ND	0.008	0.008	0.0073	0.0072	92	91	80-120	1	20	P1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:													4673765	4673766			
Parameter	Units	92772942010 Result	MS	MSD	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual					
			Spike Conc.	Spike Conc.													
Mercury	mg/L	ND	0.008	0.008	0.0069	0.0070	87	88	80-120	1	20	P1					

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1
Pace Project No.: 92772942

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

BC	The same analyte was detected in an associated blank at a concentration above 1/2 the reporting limit but below the laboratory reporting limit.
D6	The precision between the sample and sample duplicate exceeded laboratory control limits.
M1	Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.
P1	Routine initial sample volume or weight was not used for extraction, resulting in elevated reporting limits.
R1	RPD value was outside control limits.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92772942

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92772942001	HAM-PT-07	EPA 3005A	910720	EPA 6020B	910853
92772942002	HAM-PT-08	EPA 3005A	910720	EPA 6020B	910853
92772942003	HAM-PT-09	EPA 3005A	910720	EPA 6020B	910853
92772942004	HAM-PT-10	EPA 3005A	910720	EPA 6020B	910853
92772942005	HAM-PT-11	EPA 3005A	910720	EPA 6020B	910853
92772942006	HAM-PT-12	EPA 3005A	910720	EPA 6020B	910853
92772942007	HAM-PT-13	EPA 3005A	910720	EPA 6020B	910853
92772942008	HAM-PT-14	EPA 3005A	910720	EPA 6020B	910853
92772942009	HAM-PT-15	EPA 3005A	910720	EPA 6020B	910853
92772942010	HAM-AP1-EB-01	EPA 3005A	910720	EPA 6020B	910853
92772942011	HAM-AP1-FB-01	EPA 3005A	910720	EPA 6020B	910853
92772942012	HAM-AP1-FD-01	EPA 3005A	910720	EPA 6020B	910853
92772942001	HAM-PT-07	SM 2540C-2015	907726		
92772942002	HAM-PT-08	SM 2540C-2015	907726		
92772942003	HAM-PT-09	SM 2540C-2015	907726		
92772942004	HAM-PT-10	SM 2540C-2015	907726		
92772942005	HAM-PT-11	SM 2540C-2015	907726		
92772942006	HAM-PT-12	SM 2540C-2015	907726		
92772942007	HAM-PT-13	SM 2540C-2015	907726		
92772942008	HAM-PT-14	SM 2540C-2015	907726		
92772942009	HAM-PT-15	SM 2540C-2015	907726		
92772942010	HAM-AP1-EB-01	SM 2540C-2015	907875		
92772942011	HAM-AP1-FB-01	SM 2540C-2015	907875		
92772942012	HAM-AP1-FD-01	SM 2540C-2015	907726		
92772942001	HAM-PT-07	SM 2320B-2011	907689		
92772942002	HAM-PT-08	SM 2320B-2011	907689		
92772942003	HAM-PT-09	SM 2320B-2011	907689		
92772942004	HAM-PT-10	SM 2320B-2011	908504		
92772942005	HAM-PT-11	SM 2320B-2011	908504		
92772942006	HAM-PT-12	SM 2320B-2011	908504		
92772942007	HAM-PT-13	SM 2320B-2011	907689		
92772942008	HAM-PT-14	SM 2320B-2011	907689		
92772942009	HAM-PT-15	SM 2320B-2011	907689		
92772942010	HAM-AP1-EB-01	SM 2320B-2011	908504		
92772942011	HAM-AP1-FB-01	SM 2320B-2011	908504		
92772942012	HAM-AP1-FD-01	SM 2320B-2011	907689		
92772942001	HAM-PT-07	SM 4500-S2D-2011	907927		
92772942002	HAM-PT-08	SM 4500-S2D-2011	907927		
92772942003	HAM-PT-09	SM 4500-S2D-2011	907927		
92772942004	HAM-PT-10	SM 4500-S2D-2011	907927		
92772942005	HAM-PT-11	SM 4500-S2D-2011	907927		
92772942006	HAM-PT-12	SM 4500-S2D-2011	907927		
92772942007	HAM-PT-13	SM 4500-S2D-2011	907927		
92772942008	HAM-PT-14	SM 4500-S2D-2011	907927		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92772942

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92772942009	HAM-PT-15	SM 4500-S2D-2011	907927		
92772942010	HAM-AP1-EB-01	SM 4500-S2D-2011	907927		
92772942011	HAM-AP1-FB-01	SM 4500-S2D-2011	907927		
92772942012	HAM-AP1-FD-01	SM 4500-S2D-2011	907927		
92772942001	HAM-PT-07	EPA 300.0 Rev 2.1 1993	907517		
92772942002	HAM-PT-08	EPA 300.0 Rev 2.1 1993	907517		
92772942003	HAM-PT-09	EPA 300.0 Rev 2.1 1993	907517		
92772942004	HAM-PT-10	EPA 300.0 Rev 2.1 1993	907517		
92772942005	HAM-PT-11	EPA 300.0 Rev 2.1 1993	907517		
92772942006	HAM-PT-12	EPA 300.0 Rev 2.1 1993	907517		
92772942007	HAM-PT-13	EPA 300.0 Rev 2.1 1993	907517		
92772942008	HAM-PT-14	EPA 300.0 Rev 2.1 1993	907517		
92772942009	HAM-PT-15	EPA 300.0 Rev 2.1 1993	907517		
92772942010	HAM-AP1-EB-01	EPA 300.0 Rev 2.1 1993	907517		
92772942011	HAM-AP1-FB-01	EPA 300.0 Rev 2.1 1993	907517		
92772942012	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	907517		
92772942001	HAM-PT-07	EPA 3005A	908184	EPA 6020B	908439
92772942002	HAM-PT-08	EPA 3005A	908184	EPA 6020B	908439
92772942003	HAM-PT-09	EPA 3005A	908184	EPA 6020B	908439
92772942004	HAM-PT-10	EPA 3005A	908184	EPA 6020B	908439
92772942005	HAM-PT-11	EPA 3005A	908184	EPA 6020B	908439
92772942006	HAM-PT-12	EPA 3005A	908184	EPA 6020B	908439
92772942007	HAM-PT-13	EPA 3005A	908184	EPA 6020B	908439
92772942008	HAM-PT-14	EPA 3005A	908184	EPA 6020B	908439
92772942009	HAM-PT-15	EPA 3005A	908184	EPA 6020B	908439
92772942010	HAM-AP1-EB-01	EPA 3005A	908184	EPA 6020B	908439
92772942011	HAM-AP1-FB-01	EPA 3005A	908184	EPA 6020B	908439
92772942012	HAM-AP1-FD-01	EPA 3005A	908184	EPA 6020B	908439
92772942001	HAM-PT-07	EPA 7470A	908632	EPA 7470A	911697
92772942002	HAM-PT-08	EPA 7470A	908632	EPA 7470A	911697
92772942003	HAM-PT-09	EPA 7470A	908632	EPA 7470A	911697
92772942004	HAM-PT-10	EPA 7470A	908632	EPA 7470A	911697
92772942005	HAM-PT-11	EPA 7470A	908632	EPA 7470A	911697
92772942006	HAM-PT-12	EPA 7470A	908632	EPA 7470A	911697
92772942007	HAM-PT-13	EPA 7470A	908632	EPA 7470A	911697
92772942008	HAM-PT-14	EPA 7470A	908632	EPA 7470A	911697
92772942009	HAM-PT-15	EPA 7470A	908632	EPA 7470A	911697
92772942010	HAM-AP1-EB-01	EPA 7470A	908632	EPA 7470A	911697
92772942011	HAM-AP1-FB-01	EPA 7470A	908632	EPA 7470A	911697
92772942012	HAM-AP1-FD-01	EPA 7470A	908632	EPA 7470A	911697

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

92772942

CHAIN-OF-CUSTODY / Analytical Request Docu

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.



Section A Required Client Information Company: GA Power Address: Atlanta, GA		Section B Required Project Information Report To: SCS Contacts Copy To: Geosyntec Contacts		Section C Invoice Information Attention: Southern Co. Company Name: Address: Fax: 10 Day	
Email To: SCS Contacts		Purchase Order No.: GPC82474-0001		Site Location STATE: GA	
Phone: 10 Day		Project Name: Hammond AP-1		Project Number:	
Requested Due Date/TAT:		Project Profile #:		15483	

Section D Required Client Information		Valid Matrix Codes		Matrix Code (see valid codes to left)		Sample Type (G-GRAB C-COMP)		COLLECTED		SAMPLE TEMP AT COLLECTION		Preservatives		Analysis Test		Requested Analysis Filtered (Y/N)		Pace Project No./ Lab I.D.	
ITEM #		MATRIX CODE	DW DRINKING WATER	WT WATER	WW WASTE WATER	SW SEWAGE	SL SOLID	SI SOLID	SI SOLID	SI SOLID	SI SOLID	SI SOLID	SI SOLID	SI SOLID	SI SOLID	SI SOLID	SI SOLID	SI SOLID	
1	HAM-PT-07	WG	G	162025	1544													92772942	
2	HAM-PT-08	WG	G	162025	1650														
3	HAM-PT-09	WG	G	172025	1037														
4	HAM-PT-10	WG	G	172025	1230														
5	HAM-PT-11	WG	G	172025	1137														
6	HAM-PT-12	WG	G	172025	0936														
7	HAM-PT-13	WG	G	162025	1247														
8	HAM-PT-14	WG	G	162025	1240														
9	HAM-PT-15	WG	G	162025	1423														
10	HAM-AP1-EB-01	WQ	G	172025	1255														
11	HAM-AP1-FB-01	WQ	G	172025	1250														
12	HAM-AP1-FD-01	WQ	G	162025	0030														

Section E Additional Comments		Relinquished By / Affiliation		Date		Time		Accepted By / Affiliation		Date		Time		Sample Conditions	
Task Code: HAM-COR-CA-20250108		Thomas Kessler / Geosyntec		11/12/25		1700		Thomas Kessler / Geosyntec		11/12/25		1700			
		Thomas Kessler / Geosyntec		11/12/25		1030		Thomas Kessler / Geosyntec		11/12/25		1030			
		Thomas Kessler / Geosyntec		11/12/25		1245		Thomas Kessler / Geosyntec		11/12/25		1245			

Section F Sampler Name and Signature		Print Name of Sampler: Thomas Kessler / Geosyntec Consultants, Inc.		Date Signed (MM/DD/YYYY):	
		Thomas Kessler / Geosyntec Consultants, Inc.		11/12/25	



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

Project #:

WO#: 92772942

Courier:

☐ Commercial☐ FedEx☒ Pace☐ UPS☐ USPS☐ Other:☐ Client

PM: BV

Due Date: 01/22/25

CLIENT: 92- GP-HAM

Custody Seal Present?

☐ Yes☒ No

Seals Intact?

☐ Yes☐ No☒ N/ADate/Initials Person Examining Contents: 1/8/25
GIF

Packing Material:

☐ Bubble Wrap☐ Bubble Bags☒ None☐ Other

Biological Tissue Frozen?

☐ Yes☐ No☒ N/A

Thermometer:

☒ IR Gun ID:

083

Type of Ice:

☒ Wet☐ Blue☐ None

Cooler Temp:

4.1

Correction Factor:

Add/Subtract (°C)

0.0

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C):

4.1

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

			Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1:	
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2:	
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3:	
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4:	
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5:	
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6:	
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A		
Containers Intact?	☒ Yes ☐ No ☐ N/A	7:	
Dissolved analysis: Samples Field Filtered?	☐ Yes ☐ No ☒ N/A	8:	
Sample Labels Match COC?	☒ Yes ☐ No ☐ N/A	9:	
-Includes Date/Time/ID/Analysis Matrix:	W		
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10:	
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11:	
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A		

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

WO#: 92772942

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

PM: BV

Due Date: 01/22/25

CLIENT: 92- GP-HAM

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐

Client _____ Profile/EZ (Circle one) _____ Notes _____

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)		BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic 2N Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGFU-Wide-mouthed Glass jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG84-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG8T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	VJGK (3 vials per kit)-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)		BP3R-250 mL Plastic (NH4)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	V5GU-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)	
CC																														
1	2	1																												
2	2	1																												
3	2	1																												
4	2	1																												
5	2	1																												
6	2	1																												
7	2	1																												
8	2	1																												
9	2	1																												
10	2	1																												
11	2	1																												
12	2	1																												

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers.



April 03, 2025

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1-CA-20250203
Pace Project No.: 92778486

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on February 07, 2025. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace National - Mt. Juliet
- Pace Analytical Services - Asheville
- Pace Analytical Services - West Columbia

Revision 1: Sample ID's for FB-01 and FD-01 were corrected to match COC.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Jamie Newsome, Geosyntec Consultants

Zain Webb, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Pace Analytical Services National

12065 Lebanon Road, Mt. Juliet, TN 37122

Alabama Certification #: 40660

Alaska Certification 17-026

Arizona Certification #: AZ0612

Arkansas Certification #: 88-0469

California Certification #: 2932

Canada Certification #: 1461.01

Colorado Certification #: TN00003

Connecticut Certification #: PH-0197

DOD Certification: #1461.01

EPA# TN00003

Florida Certification #: E87487

Georgia DW Certification #: 923

Georgia Certification: NELAP

Idaho Certification #: TN00003

Illinois Certification #: 200008

Indiana Certification #: C-TN-01

Iowa Certification #: 364

Kansas Certification #: E-10277

Kentucky UST Certification #: 16

Kentucky Certification #: 90010

Louisiana Certification #: AI30792

Louisiana DW Certification #: LA180010

Maine Certification #: TN0002

Maryland Certification #: 324

Massachusetts Certification #: M-TN003

Michigan Certification #: 9958

Minnesota Certification #: 047-999-395

Mississippi Certification #: TN00003

Missouri Certification #: 340

Montana Certification #: CERT0086

Nebraska Certification #: NE-OS-15-05

Nevada Certification #: TN-03-2002-34

New Hampshire Certification #: 2975

New Jersey Certification #: TN002

New Mexico DW Certification

New York Certification #: 11742

North Carolina Aquatic Toxicity Certification #: 41

North Carolina Drinking Water Certification #: 21704

North Carolina Environmental Certificate #: 375

North Dakota Certification #: R-140

Ohio VAP Certification #: CL0069

Oklahoma Certification #: 9915

Oregon Certification #: TN200002

Pennsylvania Certification #: 68-02979

Rhode Island Certification #: LA000356

South Carolina Certification #: 84004

South Dakota Certification

Tennessee DW/Chem/Micro Certification #: 2006

Texas Mold Certification #: LAB0152

Texas Certification #: T 104704245-17-14

USDA Soil Permit #: P330-15-00234

Utah Certification #: TN00003

Virginia Certification #: VT2006

Vermont Dept. of Health: ID# VT-2006

Virginia Certification #: 460132

Washington Certification #: C847

West Virginia Certification #: 233

Wisconsin Certification #: 998093910

Wyoming UST Certification #: via A2LA 2926.01

A2LA-ISO 17025 Certification #: 1461.01

A2LA-ISO 17025 Certification #: 1461.02

AIHA-LAP/LLC EMLAP Certification #:100789

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services West Columbia

106 Vantage Point Drive, West Columbia, SC 29172

Alaska Dept. of Energy Conservation, Cert# 20-002

California ELAP, cert# 3049

DoD, DoD QSM V5.4, cert# I.2224

DOE, DoD/DOE QSM V5.4, cert# I.2224.01

Florida, Dept. of Health, cert# E87653-70

Georgia, Env. Protection Division, cert# E87653

Illinois, EPA NELAP, cert# 2000552024-9

Kansas, Dept. of Health and Environment, cert# E-10417

Kentucky, Dept. for Env. Protection, UST, cert# 103582

Kentucky, Dept. for Env. Protection, cert# 98037

Louisiana, Dept. of Environmental Quality, cert# 5125

North Carolina, DEQ, Water Resources, cert# 329

New Jersey, Dept. of Env. Protection, cert# NLC 240005

Oklahoma, Dept. of Env. Quality, cert# 2023-175

Oregon, ELAP, cert# 4181-006

Pennsylvania, Dept. of Env. Protection, cert# 003

South Carolina, Dept. of Env. Services, cert# 32010001

Texas, Commission on Env. Quality, cert# TX-C24-00083

Virginia, Dept. of General Services, cert# 13080

Wisconsin, Dept. of Natural Resources, cert# 399136100

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92778486001	HAM-PT-07	Water	02/04/25 11:56	02/07/25 14:35
92778486002	HAM-PT-08	Water	02/04/25 13:39	02/07/25 14:35
92778486003	HAM-PT-09	Water	02/05/25 11:21	02/07/25 14:35
92778486004	HAM-PT-10	Water	02/05/25 10:00	02/07/25 14:35
92778486005	HAM-PT-11	Water	02/05/25 10:01	02/07/25 14:35
92778486006	HAM-PT-12	Water	02/05/25 11:41	02/07/25 14:35
92778486007	HAM-PT-13	Water	02/04/25 10:05	02/07/25 14:35
92778486008	HAM-PT-14	Water	02/04/25 10:08	02/07/25 14:35
92778486009	HAM-PT-15	Water	02/04/25 14:55	02/07/25 14:35
92778486010	HAM-AP1-EB-01	Water	02/05/25 12:30	02/07/25 14:35
92778486011	HAM-AP1-FB-01	Water	02/05/25 12:20	02/07/25 14:35
92778486012	HAM-AP1-FD-01	Water	02/05/25 00:00	02/07/25 14:35

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
92778486001	HAM-PT-07	EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	YEG	3	PASI-A
		SM 2540C-2015	CMW1	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
92778486002	HAM-PT-08	EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	YEG	3	PASI-A
		SM 2540C-2015	CMW1	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
92778486003	HAM-PT-09	EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A
92778486004	HAM-PT-10	SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	SMS	3	PASI-A
92778486005	HAM-PT-11	SM 2540C-2015	YEG	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
92778486006	HAM-PT-12	SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
92778486007	HAM-PT-13	SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	YEG	3	PASI-A
		SM 2540C-2015	CMW1	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
92778486008	HAM-PT-14	EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	YEG	3	PASI-A
		SM 2540C-2015	CMW1	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
92778486009	HAM-PT-15	EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	YEG	3	PASI-A
		SM 2540C-2015	CMW1	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	YEG	3	PASI-A
		SM 2540C-2015	CMW1	1	PASI-A
92778486010	HAM-AP1-EB-01	SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
92778486011	HAM-AP1-FB-01	EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
92778486012	HAM-AP1-FD-01	SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC

PAN = Pace National - Mt. Juliet

PASI-A = Pace Analytical Services - Asheville

PASI-WC = Pace Analytical Services - West Columbia

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92778486001	HAM-PT-07					
EPA 6020B	Lithium	0.0461	mg/L	0.0300	03/07/25 02:49	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO ₃)	169	mg/L	5.0	02/10/25 19:38	
SM 2320B-2011	Alkalinity, Total as CaCO ₃	169	mg/L	5.0	02/10/25 19:38	
SM 2540C-2015	Total Dissolved Solids	520	mg/L	25.0	02/08/25 13:02	
EPA 300.0 Rev 2.1 1993	Chloride	19.3	mg/L	1.0	02/09/25 05:28	
EPA 300.0 Rev 2.1 1993	Fluoride	0.40	mg/L	0.10	02/09/25 05:28	
EPA 300.0 Rev 2.1 1993	Sulfate	157	mg/L	4.0	02/09/25 09:38	
EPA 6020B	Arsenic	0.15	mg/L	0.0050	03/20/25 13:01	
EPA 6020B	Barium	0.047	mg/L	0.0050	03/20/25 13:01	
EPA 6020B	Boron	0.74	mg/L	0.40	03/20/25 22:50	
EPA 6020B	Calcium	121	mg/L	10.0	03/20/25 17:21	
EPA 6020B	Cobalt	0.036	mg/L	0.0050	03/20/25 13:01	
EPA 6020B	Iron	7.5	mg/L	0.040	03/20/25 13:01	
EPA 6020B	Magnesium	16.8	mg/L	0.050	03/20/25 13:01	
EPA 6020B	Manganese	3.4	mg/L	0.40	03/20/25 17:21	
EPA 6020B	Molybdenum	0.013	mg/L	0.010	03/20/25 13:01	
EPA 6020B	Potassium	5.5	mg/L	0.50	03/20/25 13:01	
EPA 6020B	Sodium	8.4	mg/L	1.0	03/20/25 13:01	
EPA 6020B	Thallium	0.00019J	mg/L	0.0010	03/20/25 13:01	
92778486002	HAM-PT-08					
EPA 6020B	Lithium	0.0201J	mg/L	0.0300	03/07/25 02:52	J
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO ₃)	113	mg/L	5.0	02/10/25 19:49	
SM 2320B-2011	Alkalinity, Total as CaCO ₃	113	mg/L	5.0	02/10/25 19:49	
SM 2540C-2015	Total Dissolved Solids	483	mg/L	25.0	02/08/25 13:02	
EPA 300.0 Rev 2.1 1993	Chloride	19.6	mg/L	1.0	02/08/25 18:29	
EPA 300.0 Rev 2.1 1993	Fluoride	0.18	mg/L	0.10	02/08/25 18:29	
EPA 300.0 Rev 2.1 1993	Sulfate	170	mg/L	4.0	02/09/25 03:04	M1
EPA 6020B	Arsenic	0.033	mg/L	0.0050	03/20/25 13:06	
EPA 6020B	Barium	0.049	mg/L	0.0050	03/20/25 13:06	
EPA 6020B	Boron	0.82	mg/L	0.40	03/20/25 22:59	
EPA 6020B	Calcium	107	mg/L	10.0	03/20/25 17:25	
EPA 6020B	Cobalt	0.040	mg/L	0.0050	03/20/25 13:06	
EPA 6020B	Iron	1.8	mg/L	0.040	03/20/25 13:06	
EPA 6020B	Magnesium	13.4	mg/L	0.050	03/20/25 13:06	
EPA 6020B	Manganese	2.3	mg/L	0.40	03/20/25 17:25	
EPA 6020B	Molybdenum	0.0096J	mg/L	0.010	03/20/25 13:06	
EPA 6020B	Potassium	5.0	mg/L	0.50	03/20/25 13:06	
EPA 6020B	Sodium	6.8	mg/L	1.0	03/20/25 13:06	
EPA 6020B	Thallium	0.00018J	mg/L	0.0010	03/20/25 13:06	
92778486003	HAM-PT-09					
EPA 6020B	Lithium	0.00155J	mg/L	0.0300	03/07/25 02:55	J
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO ₃)	131	mg/L	5.0	02/12/25 19:10	
SM 2320B-2011	Alkalinity, Total as CaCO ₃	131	mg/L	5.0	02/12/25 19:10	
SM 2540C-2015	Total Dissolved Solids	422	mg/L	25.0	02/11/25 12:06	
EPA 300.0 Rev 2.1 1993	Chloride	50.4	mg/L	1.0	02/08/25 19:10	
EPA 300.0 Rev 2.1 1993	Fluoride	0.37	mg/L	0.10	02/08/25 19:10	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92778486003	HAM-PT-09					
EPA 300.0 Rev 2.1 1993	Sulfate	111	mg/L	3.0	02/09/25 03:46	
EPA 6020B	Barium	0.060	mg/L	0.0050	03/20/25 13:10	
EPA 6020B	Boron	1.6	mg/L	0.40	03/20/25 23:08	
EPA 6020B	Calcium	89.3	mg/L	10.0	03/20/25 17:39	
EPA 6020B	Cobalt	0.0022J	mg/L	0.0050	03/20/25 13:10	
EPA 6020B	Iron	1.0	mg/L	0.040	03/20/25 13:10	
EPA 6020B	Magnesium	20.6	mg/L	0.050	03/20/25 13:10	
EPA 6020B	Manganese	0.33	mg/L	0.040	03/20/25 13:10	
EPA 6020B	Molybdenum	0.23	mg/L	0.010	03/20/25 13:10	
EPA 6020B	Potassium	6.2	mg/L	0.50	03/20/25 13:10	
EPA 6020B	Sodium	12.3	mg/L	1.0	03/20/25 13:10	
92778486004	HAM-PT-10					
EPA 6020B	Lithium	0.000905J	mg/L	0.0300	03/07/25 02:58	J
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	114	mg/L	5.0	02/12/25 19:25	
SM 2320B-2011	Alkalinity, Total as CaCO3	114	mg/L	5.0	02/12/25 19:25	
SM 2540C-2015	Total Dissolved Solids	401	mg/L	25.0	02/11/25 12:07	
EPA 300.0 Rev 2.1 1993	Chloride	46.3	mg/L	1.0	02/08/25 19:24	
EPA 300.0 Rev 2.1 1993	Fluoride	0.19	mg/L	0.10	02/08/25 19:24	
EPA 300.0 Rev 2.1 1993	Sulfate	110	mg/L	3.0	02/09/25 04:00	
EPA 6020B	Barium	0.046	mg/L	0.0050	03/20/25 13:15	
EPA 6020B	Boron	1.5	mg/L	0.40	03/20/25 23:17	
EPA 6020B	Calcium	98.1	mg/L	10.0	03/20/25 17:44	
EPA 6020B	Cobalt	0.0014J	mg/L	0.0050	03/20/25 13:15	
EPA 6020B	Iron	1.0	mg/L	0.040	03/20/25 13:15	
EPA 6020B	Magnesium	12.9	mg/L	0.050	03/20/25 13:15	
EPA 6020B	Manganese	0.43	mg/L	0.040	03/20/25 13:15	
EPA 6020B	Molybdenum	0.079	mg/L	0.010	03/20/25 13:15	
EPA 6020B	Potassium	6.6	mg/L	0.50	03/20/25 13:15	
EPA 6020B	Sodium	9.1	mg/L	1.0	03/20/25 13:15	
92778486005	HAM-PT-11					
EPA 6020B	Lithium	0.00159J	mg/L	0.0300	03/07/25 03:08	J
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	121	mg/L	5.0	02/12/25 19:32	
SM 2320B-2011	Alkalinity, Total as CaCO3	121	mg/L	5.0	02/12/25 19:32	
SM 2540C-2015	Total Dissolved Solids	400	mg/L	25.0	02/11/25 12:07	
EPA 300.0 Rev 2.1 1993	Chloride	37.7	mg/L	1.0	02/08/25 19:38	
EPA 300.0 Rev 2.1 1993	Fluoride	0.27	mg/L	0.10	02/08/25 19:38	
EPA 300.0 Rev 2.1 1993	Sulfate	96.4	mg/L	3.0	02/09/25 04:14	
EPA 6020B	Barium	0.062	mg/L	0.0050	03/20/25 13:20	
EPA 6020B	Boron	1.5	mg/L	0.40	03/20/25 23:26	
EPA 6020B	Calcium	95.8	mg/L	10.0	03/20/25 17:48	
EPA 6020B	Cobalt	0.0024J	mg/L	0.0050	03/20/25 13:20	
EPA 6020B	Iron	0.89	mg/L	0.040	03/20/25 13:20	
EPA 6020B	Magnesium	13.8	mg/L	0.050	03/20/25 13:20	
EPA 6020B	Manganese	0.35	mg/L	0.040	03/20/25 13:20	
EPA 6020B	Molybdenum	0.11	mg/L	0.010	03/20/25 13:20	
EPA 6020B	Potassium	6.3	mg/L	0.50	03/20/25 13:20	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92778486005	HAM-PT-11					
EPA 6020B	Sodium	8.5	mg/L	1.0	03/20/25 13:20	
92778486006	HAM-PT-12					
EPA 6020B	Lithium	0.00122J	mg/L	0.0300	03/07/25 03:11	J
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	120	mg/L	5.0	02/12/25 19:40	
SM 2320B-2011	Alkalinity, Total as CaCO3	120	mg/L	5.0	02/12/25 19:40	
SM 2540C-2015	Total Dissolved Solids	416	mg/L	25.0	02/11/25 12:07	
EPA 300.0 Rev 2.1 1993	Chloride	44.0	mg/L	1.0	02/08/25 19:52	
EPA 300.0 Rev 2.1 1993	Fluoride	0.25	mg/L	0.10	02/08/25 19:52	
EPA 300.0 Rev 2.1 1993	Sulfate	114	mg/L	3.0	02/09/25 04:29	
EPA 6020B	Barium	0.055	mg/L	0.0050	03/20/25 13:24	
EPA 6020B	Boron	1.6	mg/L	0.40	03/20/25 23:35	
EPA 6020B	Cadmium	0.00015J	mg/L	0.00050	03/20/25 13:24	
EPA 6020B	Calcium	91.4	mg/L	10.0	03/20/25 17:53	
EPA 6020B	Cobalt	0.0023J	mg/L	0.0050	03/20/25 13:24	
EPA 6020B	Iron	1.4	mg/L	0.040	03/20/25 13:24	
EPA 6020B	Magnesium	19.1	mg/L	0.050	03/20/25 13:24	
EPA 6020B	Manganese	0.44	mg/L	0.040	03/20/25 13:24	
EPA 6020B	Molybdenum	0.16	mg/L	0.010	03/20/25 13:24	
EPA 6020B	Potassium	6.0	mg/L	0.50	03/20/25 13:24	
EPA 6020B	Sodium	11.0	mg/L	1.0	03/20/25 13:24	
92778486007	HAM-PT-13					
EPA 6020B	Lithium	0.0520	mg/L	0.0300	03/07/25 03:14	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	163	mg/L	5.0	02/10/25 19:58	
SM 2320B-2011	Alkalinity, Total as CaCO3	163	mg/L	5.0	02/10/25 19:58	
SM 2540C-2015	Total Dissolved Solids	527	mg/L	25.0	02/08/25 13:03	
EPA 300.0 Rev 2.1 1993	Chloride	20.2	mg/L	1.0	02/08/25 20:06	
EPA 300.0 Rev 2.1 1993	Fluoride	0.35	mg/L	0.10	02/08/25 20:06	
EPA 300.0 Rev 2.1 1993	Sulfate	161	mg/L	4.0	02/09/25 04:43	
EPA 6020B	Arsenic	0.19	mg/L	0.0050	03/20/25 13:29	
EPA 6020B	Barium	0.046	mg/L	0.0050	03/20/25 13:29	
EPA 6020B	Boron	0.73	mg/L	0.40	03/20/25 23:44	
EPA 6020B	Calcium	114	mg/L	10.0	03/20/25 17:58	
EPA 6020B	Cobalt	0.018	mg/L	0.0050	03/20/25 13:29	
EPA 6020B	Iron	7.6	mg/L	0.040	03/20/25 13:29	
EPA 6020B	Magnesium	16.4	mg/L	0.050	03/20/25 13:29	
EPA 6020B	Manganese	2.9	mg/L	0.40	03/20/25 17:58	
EPA 6020B	Molybdenum	0.0099J	mg/L	0.010	03/20/25 13:29	
EPA 6020B	Potassium	5.4	mg/L	0.50	03/20/25 13:29	
EPA 6020B	Sodium	8.4	mg/L	1.0	03/20/25 13:29	
EPA 6020B	Thallium	0.00021J	mg/L	0.0010	03/20/25 13:29	
92778486008	HAM-PT-14					
EPA 6020B	Lithium	0.0528	mg/L	0.0300	03/07/25 03:17	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	170	mg/L	5.0	02/10/25 20:09	
SM 2320B-2011	Alkalinity, Total as CaCO3	170	mg/L	5.0	02/10/25 20:09	
SM 2540C-2015	Total Dissolved Solids	546	mg/L	25.0	02/08/25 13:03	
EPA 300.0 Rev 2.1 1993	Chloride	20.5	mg/L	1.0	02/08/25 20:20	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92778486008	HAM-PT-14					
EPA 300.0 Rev 2.1 1993	Fluoride	0.30	mg/L	0.10	02/08/25 20:20	
EPA 300.0 Rev 2.1 1993	Sulfate	170	mg/L	4.0	02/09/25 05:25	
EPA 6020B	Arsenic	0.26	mg/L	0.0050	03/20/25 13:34	
EPA 6020B	Barium	0.043	mg/L	0.0050	03/20/25 13:34	
EPA 6020B	Boron	0.75	mg/L	0.40	03/20/25 23:53	
EPA 6020B	Calcium	123	mg/L	10.0	03/20/25 18:02	
EPA 6020B	Cobalt	0.019	mg/L	0.0050	03/20/25 13:34	
EPA 6020B	Iron	11.7	mg/L	0.040	03/20/25 13:34	
EPA 6020B	Magnesium	16.8	mg/L	0.050	03/20/25 13:34	
EPA 6020B	Manganese	3.1	mg/L	0.40	03/20/25 18:02	
EPA 6020B	Molybdenum	0.015	mg/L	0.010	03/20/25 13:34	
EPA 6020B	Potassium	5.6	mg/L	0.50	03/20/25 13:34	
EPA 6020B	Sodium	8.8	mg/L	1.0	03/20/25 13:34	
92778486009	HAM-PT-15					
EPA 6020B	Lithium	0.0421	mg/L	0.0300	03/07/25 03:21	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	146	mg/L	5.0	02/10/25 20:20	
SM 2320B-2011	Alkalinity, Total as CaCO3	146	mg/L	5.0	02/10/25 20:20	
SM 2540C-2015	Total Dissolved Solids	515	mg/L	25.0	02/08/25 13:03	
EPA 300.0 Rev 2.1 1993	Chloride	17.4	mg/L	1.0	02/08/25 21:02	
EPA 300.0 Rev 2.1 1993	Fluoride	0.32	mg/L	0.10	02/08/25 21:02	
EPA 300.0 Rev 2.1 1993	Sulfate	173	mg/L	4.0	02/09/25 05:39	M1
EPA 6020B	Arsenic	0.078	mg/L	0.0050	03/20/25 13:38	
EPA 6020B	Barium	0.052	mg/L	0.0050	03/20/25 13:38	
EPA 6020B	Boron	0.80	mg/L	0.40	03/21/25 00:02	
EPA 6020B	Cadmium	0.00031J	mg/L	0.00050	03/20/25 13:38	
EPA 6020B	Calcium	117	mg/L	10.0	03/20/25 18:07	
EPA 6020B	Cobalt	0.026	mg/L	0.0050	03/20/25 13:38	
EPA 6020B	Iron	2.3	mg/L	0.040	03/20/25 13:38	
EPA 6020B	Magnesium	14.6	mg/L	0.050	03/20/25 13:38	
EPA 6020B	Manganese	4.1	mg/L	0.40	03/20/25 18:07	
EPA 6020B	Molybdenum	0.014	mg/L	0.010	03/20/25 13:38	
EPA 6020B	Potassium	5.4	mg/L	0.50	03/20/25 13:38	
EPA 6020B	Sodium	7.4	mg/L	1.0	03/20/25 13:38	
EPA 6020B	Thallium	0.00050J	mg/L	0.0010	03/20/25 13:38	
92778486010	HAM-AP1-EB-01					
EPA 6020B	Iron	0.050	mg/L	0.040	03/20/25 13:43	
EPA 6020B	Manganese	0.0015J	mg/L	0.040	03/20/25 13:43	
92778486011	HAM-AP1-FB-01					
EPA 6020B	Lithium	0.00809J	mg/L	0.0300	03/07/25 03:27	J
92778486012	HAM-AP1-FD-01					
EPA 6020B	Lithium	0.0538	mg/L	0.0300	03/07/25 03:30	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	172	mg/L	5.0	02/12/25 19:54	
SM 2320B-2011	Alkalinity, Total as CaCO3	172	mg/L	5.0	02/12/25 19:54	
SM 2540C-2015	Total Dissolved Solids	516	mg/L	25.0	02/11/25 12:08	
EPA 300.0 Rev 2.1 1993	Chloride	20.6	mg/L	1.0	02/08/25 21:43	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92778486012	HAM-AP1-FD-01					
EPA 300.0 Rev 2.1 1993	Fluoride	0.30	mg/L	0.10	02/08/25 21:43	
EPA 300.0 Rev 2.1 1993	Sulfate	165	mg/L	4.0	02/09/25 06:20	
EPA 6020B	Arsenic	0.26	mg/L	0.0050	03/20/25 14:01	
EPA 6020B	Barium	0.043	mg/L	0.0050	03/20/25 14:01	
EPA 6020B	Boron	0.77	mg/L	0.40	03/20/25 17:14	
EPA 6020B	Calcium	115	mg/L	10.0	03/20/25 18:21	M1
EPA 6020B	Cobalt	0.019	mg/L	0.0050	03/20/25 14:01	
EPA 6020B	Iron	11.3	mg/L	0.040	03/20/25 14:01	M1
EPA 6020B	Magnesium	16.7	mg/L	0.050	03/20/25 14:01	M1
EPA 6020B	Manganese	2.8	mg/L	0.40	03/20/25 17:14	
EPA 6020B	Molybdenum	0.015	mg/L	0.010	03/20/25 14:01	
EPA 6020B	Potassium	5.5	mg/L	0.50	03/20/25 14:01	
EPA 6020B	Sodium	8.8	mg/L	1.0	03/20/25 14:01	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-07		Lab ID: 92778486001		Collected: 02/04/25 11:56		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B									
Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet									
Lithium	0.0461	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 02:49	7439-93-2	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville									
Mercury	ND	mg/L	0.00020	0.00012	1	02/09/25 17:53	02/11/25 14:43	7439-97-6	
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	169	mg/L	5.0	5.0	1		02/10/25 19:38		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/10/25 19:38		
Alkalinity, Total as CaCO ₃	169	mg/L	5.0	5.0	1		02/10/25 19:38		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	520	mg/L	25.0	25.0	1		02/08/25 13:02		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:47	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	19.3	mg/L	1.0	0.60	1		02/09/25 05:28	16887-00-6	
Fluoride	0.40	mg/L	0.10	0.050	1		02/09/25 05:28	16984-48-8	
Sulfate	157	mg/L	4.0	2.0	4		02/09/25 09:38	14808-79-8	
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:01	7440-36-0	
Arsenic	0.15	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:01	7440-38-2	
Barium	0.047	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:01	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:01	7440-41-7	
Boron	0.74	mg/L	0.40	0.062	10	03/19/25 06:10	03/20/25 22:50	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:01	7440-43-9	
Calcium	121	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 17:21	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:01	7440-47-3	
Cobalt	0.036	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:01	7440-48-4	
Iron	7.5	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:01	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:01	7439-92-1	
Magnesium	16.8	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:01	7439-95-4	
Manganese	3.4	mg/L	0.40	0.012	10	03/19/25 06:10	03/20/25 17:21	7439-96-5	
Molybdenum	0.013	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:01	7439-98-7	
Potassium	5.5	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:01	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:01	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-07		Lab ID: 92778486001		Collected: 02/04/25 11:56		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - West Columbia									
Sodium	8.4	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:01	7440-23-5	
Thallium	0.00019J	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:01	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-08		Lab ID: 92778486002		Collected: 02/04/25 13:39		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	0.0201J	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 02:52	7439-93-2	J
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville							
Mercury	ND	mg/L	0.00020	0.00012	1	02/09/25 17:53	02/11/25 14:45	7439-97-6	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	113	mg/L	5.0	5.0	1		02/10/25 19:49		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/10/25 19:49		
Alkalinity, Total as CaCO ₃	113	mg/L	5.0	5.0	1		02/10/25 19:49		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	483	mg/L	25.0	25.0	1		02/08/25 13:02		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:47	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	19.6	mg/L	1.0	0.60	1		02/08/25 18:29	16887-00-6	
Fluoride	0.18	mg/L	0.10	0.050	1		02/08/25 18:29	16984-48-8	
Sulfate	170	mg/L	4.0	2.0	4		02/09/25 03:04	14808-79-8	M1
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:06	7440-36-0	
Arsenic	0.033	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:06	7440-38-2	
Barium	0.049	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:06	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:06	7440-41-7	
Boron	0.82	mg/L	0.40	0.062	10	03/19/25 06:10	03/20/25 22:59	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:06	7440-43-9	
Calcium	107	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 17:25	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:06	7440-47-3	
Cobalt	0.040	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:06	7440-48-4	
Iron	1.8	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:06	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:06	7439-92-1	
Magnesium	13.4	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:06	7439-95-4	
Manganese	2.3	mg/L	0.40	0.012	10	03/19/25 06:10	03/20/25 17:25	7439-96-5	
Molybdenum	0.0096J	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:06	7439-98-7	
Potassium	5.0	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:06	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:06	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-08		Lab ID: 92778486002		Collected: 02/04/25 13:39		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - West Columbia									
Sodium	6.8	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:06	7440-23-5	
Thallium	0.00018J	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:06	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-09		Lab ID: 92778486003		Collected: 02/05/25 11:21		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B									
Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet									
Lithium	0.00155J	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 02:55	7439-93-2	J
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville									
Mercury	ND	mg/L	0.00020	0.00012	1	02/09/25 17:53	02/11/25 14:47	7439-97-6	
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	131	mg/L	5.0	5.0	1		02/12/25 19:10		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/12/25 19:10		
Alkalinity, Total as CaCO ₃	131	mg/L	5.0	5.0	1		02/12/25 19:10		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	422	mg/L	25.0	25.0	1		02/11/25 12:06		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:56	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	50.4	mg/L	1.0	0.60	1		02/08/25 19:10	16887-00-6	
Fluoride	0.37	mg/L	0.10	0.050	1		02/08/25 19:10	16984-48-8	
Sulfate	111	mg/L	3.0	1.5	3		02/09/25 03:46	14808-79-8	
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:10	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:10	7440-38-2	
Barium	0.060	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:10	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:10	7440-41-7	
Boron	1.6	mg/L	0.40	0.062	10	03/19/25 06:10	03/20/25 23:08	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:10	7440-43-9	
Calcium	89.3	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 17:39	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:10	7440-47-3	
Cobalt	0.0022J	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:10	7440-48-4	
Iron	1.0	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:10	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:10	7439-92-1	
Magnesium	20.6	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:10	7439-95-4	
Manganese	0.33	mg/L	0.040	0.0012	1	03/19/25 06:10	03/20/25 13:10	7439-96-5	
Molybdenum	0.23	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:10	7439-98-7	
Potassium	6.2	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:10	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:10	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-09		Lab ID: 92778486003		Collected: 02/05/25 11:21		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Sodium	12.3	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:10	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:10	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-10		Lab ID: 92778486004		Collected: 02/05/25 10:00		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	0.000905J	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 02:58	7439-93-2	J
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville							
Mercury	ND	mg/L	0.00020	0.00012	1	02/09/25 17:53	02/11/25 14:49	7439-97-6	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	114	mg/L	5.0	5.0	1		02/12/25 19:25		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/12/25 19:25		
Alkalinity, Total as CaCO ₃	114	mg/L	5.0	5.0	1		02/12/25 19:25		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	401	mg/L	25.0	25.0	1		02/11/25 12:07		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:56	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	46.3	mg/L	1.0	0.60	1		02/08/25 19:24	16887-00-6	
Fluoride	0.19	mg/L	0.10	0.050	1		02/08/25 19:24	16984-48-8	
Sulfate	110	mg/L	3.0	1.5	3		02/09/25 04:00	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:15	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:15	7440-38-2	
Barium	0.046	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:15	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:15	7440-41-7	
Boron	1.5	mg/L	0.40	0.062	10	03/19/25 06:10	03/20/25 23:17	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:15	7440-43-9	
Calcium	98.1	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 17:44	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:15	7440-47-3	
Cobalt	0.0014J	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:15	7440-48-4	
Iron	1.0	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:15	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:15	7439-92-1	
Magnesium	12.9	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:15	7439-95-4	
Manganese	0.43	mg/L	0.040	0.0012	1	03/19/25 06:10	03/20/25 13:15	7439-96-5	
Molybdenum	0.079	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:15	7439-98-7	
Potassium	6.6	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:15	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:15	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-10		Lab ID: 92778486004		Collected: 02/05/25 10:00		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - West Columbia									
Sodium	9.1	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:15	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:15	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-11		Lab ID: 92778486005		Collected: 02/05/25 10:01		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	0.00159J	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 03:08	7439-93-2	J
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville							
Mercury	ND	mg/L	0.00020	0.00012	1	02/09/25 17:53	02/11/25 14:51	7439-97-6	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	121	mg/L	5.0	5.0	1		02/12/25 19:32		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/12/25 19:32		
Alkalinity, Total as CaCO ₃	121	mg/L	5.0	5.0	1		02/12/25 19:32		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	400	mg/L	25.0	25.0	1		02/11/25 12:07		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:57	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	37.7	mg/L	1.0	0.60	1		02/08/25 19:38	16887-00-6	
Fluoride	0.27	mg/L	0.10	0.050	1		02/08/25 19:38	16984-48-8	
Sulfate	96.4	mg/L	3.0	1.5	3		02/09/25 04:14	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:20	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:20	7440-38-2	
Barium	0.062	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:20	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:20	7440-41-7	
Boron	1.5	mg/L	0.40	0.062	10	03/19/25 06:10	03/20/25 23:26	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:20	7440-43-9	
Calcium	95.8	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 17:48	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:20	7440-47-3	
Cobalt	0.0024J	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:20	7440-48-4	
Iron	0.89	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:20	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:20	7439-92-1	
Magnesium	13.8	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:20	7439-95-4	
Manganese	0.35	mg/L	0.040	0.0012	1	03/19/25 06:10	03/20/25 13:20	7439-96-5	
Molybdenum	0.11	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:20	7439-98-7	
Potassium	6.3	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:20	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:20	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-11		Lab ID: 92778486005		Collected: 02/05/25 10:01		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Sodium	8.5	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:20	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:20	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-12		Lab ID: 92778486006		Collected: 02/05/25 11:41		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	0.00122J	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 03:11	7439-93-2	J
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville							
Mercury	ND	mg/L	0.00020	0.00012	1	02/09/25 17:53	02/11/25 14:57	7439-97-6	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	120	mg/L	5.0	5.0	1		02/12/25 19:40		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/12/25 19:40		
Alkalinity, Total as CaCO ₃	120	mg/L	5.0	5.0	1		02/12/25 19:40		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	416	mg/L	25.0	25.0	1		02/11/25 12:07		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:57	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	44.0	mg/L	1.0	0.60	1		02/08/25 19:52	16887-00-6	
Fluoride	0.25	mg/L	0.10	0.050	1		02/08/25 19:52	16984-48-8	
Sulfate	114	mg/L	3.0	1.5	3		02/09/25 04:29	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:24	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:24	7440-38-2	
Barium	0.055	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:24	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:24	7440-41-7	
Boron	1.6	mg/L	0.40	0.062	10	03/19/25 06:10	03/20/25 23:35	7440-42-8	
Cadmium	0.00015J	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:24	7440-43-9	
Calcium	91.4	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 17:53	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:24	7440-47-3	
Cobalt	0.0023J	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:24	7440-48-4	
Iron	1.4	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:24	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:24	7439-92-1	
Magnesium	19.1	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:24	7439-95-4	
Manganese	0.44	mg/L	0.040	0.0012	1	03/19/25 06:10	03/20/25 13:24	7439-96-5	
Molybdenum	0.16	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:24	7439-98-7	
Potassium	6.0	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:24	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:24	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-12		Lab ID: 92778486006		Collected: 02/05/25 11:41		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Sodium	11.0	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:24	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:24	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-13		Lab ID: 92778486007		Collected: 02/04/25 10:05		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	0.0520	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 03:14	7439-93-2	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville							
Mercury	ND	mg/L	0.00020	0.00012	1	02/09/25 17:53	02/11/25 15:00	7439-97-6	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	163	mg/L	5.0	5.0	1		02/10/25 19:58		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/10/25 19:58		
Alkalinity, Total as CaCO ₃	163	mg/L	5.0	5.0	1		02/10/25 19:58		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	527	mg/L	25.0	25.0	1		02/08/25 13:03		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:47	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	20.2	mg/L	1.0	0.60	1		02/08/25 20:06	16887-00-6	
Fluoride	0.35	mg/L	0.10	0.050	1		02/08/25 20:06	16984-48-8	
Sulfate	161	mg/L	4.0	2.0	4		02/09/25 04:43	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:29	7440-36-0	
Arsenic	0.19	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:29	7440-38-2	
Barium	0.046	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:29	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:29	7440-41-7	
Boron	0.73	mg/L	0.40	0.062	10	03/19/25 06:10	03/20/25 23:44	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:29	7440-43-9	
Calcium	114	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 17:58	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:29	7440-47-3	
Cobalt	0.018	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:29	7440-48-4	
Iron	7.6	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:29	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:29	7439-92-1	
Magnesium	16.4	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:29	7439-95-4	
Manganese	2.9	mg/L	0.40	0.012	10	03/19/25 06:10	03/20/25 17:58	7439-96-5	
Molybdenum	0.0099J	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:29	7439-98-7	
Potassium	5.4	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:29	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:29	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-13		Lab ID: 92778486007		Collected: 02/04/25 10:05		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Sodium	8.4	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:29	7440-23-5	
Thallium	0.00021J	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:29	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-14		Lab ID: 92778486008		Collected: 02/04/25 10:08		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B									
Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet									
Lithium	0.0528	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 03:17	7439-93-2	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville									
Mercury	ND	mg/L	0.00020	0.00012	1	02/09/25 17:53	02/11/25 15:02	7439-97-6	
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	170	mg/L	5.0	5.0	1		02/10/25 20:09		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/10/25 20:09		
Alkalinity, Total as CaCO ₃	170	mg/L	5.0	5.0	1		02/10/25 20:09		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	546	mg/L	25.0	25.0	1		02/08/25 13:03		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:48	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	20.5	mg/L	1.0	0.60	1		02/08/25 20:20	16887-00-6	
Fluoride	0.30	mg/L	0.10	0.050	1		02/08/25 20:20	16984-48-8	
Sulfate	170	mg/L	4.0	2.0	4		02/09/25 05:25	14808-79-8	
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:34	7440-36-0	
Arsenic	0.26	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:34	7440-38-2	
Barium	0.043	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:34	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:34	7440-41-7	
Boron	0.75	mg/L	0.40	0.062	10	03/19/25 06:10	03/20/25 23:53	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:34	7440-43-9	
Calcium	123	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 18:02	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:34	7440-47-3	
Cobalt	0.019	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:34	7440-48-4	
Iron	11.7	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:34	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:34	7439-92-1	
Magnesium	16.8	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:34	7439-95-4	
Manganese	3.1	mg/L	0.40	0.012	10	03/19/25 06:10	03/20/25 18:02	7439-96-5	
Molybdenum	0.015	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:34	7439-98-7	
Potassium	5.6	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:34	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:34	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-14		Lab ID: 92778486008		Collected: 02/04/25 10:08		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - West Columbia									
Sodium	8.8	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:34	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:34	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-15		Lab ID: 92778486009		Collected: 02/04/25 14:55		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B									
Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet									
Lithium	0.0421	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 03:21	7439-93-2	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville									
Mercury	ND	mg/L	0.00020	0.00012	1	02/09/25 17:53	02/11/25 15:04	7439-97-6	
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	146	mg/L	5.0	5.0	1		02/10/25 20:20		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/10/25 20:20		
Alkalinity, Total as CaCO ₃	146	mg/L	5.0	5.0	1		02/10/25 20:20		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	515	mg/L	25.0	25.0	1		02/08/25 13:03		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:50	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	17.4	mg/L	1.0	0.60	1		02/08/25 21:02	16887-00-6	
Fluoride	0.32	mg/L	0.10	0.050	1		02/08/25 21:02	16984-48-8	
Sulfate	173	mg/L	4.0	2.0	4		02/09/25 05:39	14808-79-8	M1
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:38	7440-36-0	
Arsenic	0.078	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:38	7440-38-2	
Barium	0.052	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:38	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:38	7440-41-7	
Boron	0.80	mg/L	0.40	0.062	10	03/19/25 06:10	03/21/25 00:02	7440-42-8	
Cadmium	0.00031J	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:38	7440-43-9	
Calcium	117	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 18:07	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:38	7440-47-3	
Cobalt	0.026	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:38	7440-48-4	
Iron	2.3	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:38	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:38	7439-92-1	
Magnesium	14.6	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:38	7439-95-4	
Manganese	4.1	mg/L	0.40	0.012	10	03/19/25 06:10	03/20/25 18:07	7439-96-5	
Molybdenum	0.014	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:38	7439-98-7	
Potassium	5.4	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:38	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:38	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-15		Lab ID: 92778486009		Collected: 02/04/25 14:55		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - West Columbia									
Sodium	7.4	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:38	7440-23-5	
Thallium	0.00050J	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:38	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-AP1-EB-01		Lab ID: 92778486010		Collected: 02/05/25 12:30		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	ND	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 03:24	7439-93-2	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville							
Mercury	ND	mg/L	0.00020	0.00012	1	02/10/25 17:03	02/13/25 14:14	7439-97-6	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/12/25 19:47		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/12/25 19:47		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		02/12/25 19:47		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		02/11/25 12:07		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:58	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	ND	mg/L	1.0	0.60	1		02/08/25 15:55	16887-00-6	
Fluoride	ND	mg/L	0.10	0.050	1		02/08/25 15:55	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		02/08/25 15:55	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:43	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:43	7440-38-2	
Barium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:43	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:43	7440-41-7	
Boron	ND	mg/L	0.040	0.0062	1	03/19/25 06:10	03/21/25 00:11	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:43	7440-43-9	
Calcium	ND	mg/L	1.0	0.10	1	03/19/25 06:10	03/20/25 13:43	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:43	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:43	7440-48-4	
Iron	0.050	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:43	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:43	7439-92-1	
Magnesium	ND	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:43	7439-95-4	
Manganese	0.0015J	mg/L	0.040	0.0012	1	03/19/25 06:10	03/20/25 13:43	7439-96-5	
Molybdenum	ND	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:43	7439-98-7	
Potassium	ND	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:43	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:43	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-AP1-EB-01		Lab ID: 92778486010		Collected: 02/05/25 12:30		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - West Columbia									
Sodium	ND	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:43	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:43	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-AP1-FB-01		Lab ID: 92778486011		Collected: 02/05/25 12:20		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	0.00809J	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 03:27	7439-93-2	J
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville							
Mercury	ND	mg/L	0.00020	0.00012	1	02/10/25 17:03	02/13/25 14:18	7439-97-6	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/12/25 19:51		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/12/25 19:51		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		02/12/25 19:51		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		02/11/25 12:07		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:58	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	ND	mg/L	1.0	0.60	1		02/08/25 16:09	16887-00-6	
Fluoride	ND	mg/L	0.10	0.050	1		02/08/25 16:09	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		02/08/25 16:09	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:57	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:57	7440-38-2	
Barium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:57	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:57	7440-41-7	
Boron	ND	mg/L	0.040	0.0062	1	03/19/25 06:10	03/21/25 00:39	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:57	7440-43-9	
Calcium	ND	mg/L	1.0	0.10	1	03/19/25 06:10	03/20/25 13:57	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:57	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:57	7440-48-4	
Iron	ND	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:57	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:57	7439-92-1	
Magnesium	ND	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:57	7439-95-4	
Manganese	ND	mg/L	0.040	0.0012	1	03/19/25 06:10	03/20/25 13:57	7439-96-5	
Molybdenum	ND	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:57	7439-98-7	
Potassium	ND	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:57	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:57	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-AP1-FB-01		Lab ID: 92778486011		Collected: 02/05/25 12:20		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - West Columbia									
Sodium	ND	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:57	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:57	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-AP1-FD-01		Lab ID: 92778486012		Collected: 02/05/25 00:00		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B									
Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet									
Lithium	0.0538	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 03:30	7439-93-2	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville									
Mercury	ND	mg/L	0.00020	0.00012	1	02/10/25 17:03	02/13/25 14:20	7439-97-6	
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	172	mg/L	5.0	5.0	1		02/12/25 19:54		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/12/25 19:54		
Alkalinity, Total as CaCO ₃	172	mg/L	5.0	5.0	1		02/12/25 19:54		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	516	mg/L	25.0	25.0	1		02/11/25 12:08		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:58	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	20.6	mg/L	1.0	0.60	1		02/08/25 21:43	16887-00-6	
Fluoride	0.30	mg/L	0.10	0.050	1		02/08/25 21:43	16984-48-8	
Sulfate	165	mg/L	4.0	2.0	4		02/09/25 06:20	14808-79-8	
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 14:01	7440-36-0	
Arsenic	0.26	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 14:01	7440-38-2	
Barium	0.043	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 14:01	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 14:01	7440-41-7	
Boron	0.77	mg/L	0.40	0.062	10	03/19/25 06:10	03/20/25 17:14	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 14:01	7440-43-9	
Calcium	115	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 18:21	7440-70-2	M1
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 14:01	7440-47-3	
Cobalt	0.019	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 14:01	7440-48-4	
Iron	11.3	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 14:01	7439-89-6	M1
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 14:01	7439-92-1	
Magnesium	16.7	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 14:01	7439-95-4	M1
Manganese	2.8	mg/L	0.40	0.012	10	03/19/25 06:10	03/20/25 17:14	7439-96-5	
Molybdenum	0.015	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 14:01	7439-98-7	
Potassium	5.5	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 14:01	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 14:01	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203
Pace Project No.: 92778486

Sample: HAM-AP1-FD-01		Lab ID: 92778486012		Collected: 02/05/25 00:00		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Sodium	8.8	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 14:01	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 14:01	7440-28-0	

REPORT OF LABORATORY ANALYSIS



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch:	2464154	Analysis Method:	EPA 6020B
QC Batch Method:	3015	Analysis Description:	Metals (ICPMS) 6020B
		Laboratory:	Pace National - Mt. Juliet
Associated Lab Samples:	92778486001, 92778486002, 92778486003, 92778486004, 92778486005, 92778486006, 92778486007, 92778486008, 92778486009, 92778486010, 92778486011, 92778486012		

METHOD BLANK:	R4183615-1	Matrix:	Water
Associated Lab Samples:	92778486001, 92778486002, 92778486003, 92778486004, 92778486005, 92778486006, 92778486007, 92778486008, 92778486009, 92778486010, 92778486011, 92778486012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Lithium	mg/L	ND	0.0300	0.000600	03/07/25 02:29	

LABORATORY CONTROL SAMPLE: R4183615-2						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Lithium	ma/L	0.0500	0.0476	95.2	80.0-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:					R4183615-4								R4183615-5			
Parameter	Units	L1833065-06 Result	MS	MSD	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual				
			Spike Conc.	Spike Conc.												
Lithium	mg/L	0.00370	0.0500	0.0500	0.0494	0.0494	91.4	91.3	75.0-125	0.036	20					

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch:	914889	Analysis Method:	EPA 7470A
QC Batch Method:	EPA 7470A	Analysis Description:	7470 Mercury
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92778486001, 92778486002, 92778486003, 92778486004, 92778486005, 92778486006, 92778486007, 92778486008, 92778486009		

METHOD BLANK:	4702575	Matrix:	Water
Associated Lab Samples:	92778486001, 92778486002, 92778486003, 92778486004, 92778486005, 92778486006, 92778486007, 92778486008, 92778486009		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00012	02/11/25 14:07	

LABORATORY CONTROL SAMPLE: 4702576						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0024	95	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:					4702577								4702578			
Parameter	Units	92777579004 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual				
Mercury	mg/L	ND	0.0025	0.0025	0.0024	0.0023	94	93	75-125	1	25					

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch: 914965

Analysis Method: EPA 7470A

QC Batch Method: EPA 7470A

Analysis Description: 7470 Mercury

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92778486010, 92778486011, 92778486012

METHOD BLANK: 4702822

Matrix: Water

Associated Lab Samples: 92778486010, 92778486011, 92778486012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00012	02/13/25 14:10	

LABORATORY CONTROL SAMPLE: 4702823

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0022	88	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4702824 4702825

Parameter	Units	92778486010 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.0025	0.0025	0.0023	0.0022	93	89	75-125	5	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch: 915023

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92778486001, 92778486002, 92778486007, 92778486008, 92778486009

METHOD BLANK: 4703162

Matrix: Water

Associated Lab Samples: 92778486001, 92778486002, 92778486007, 92778486008, 92778486009

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	02/10/25 16:31	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	02/10/25 16:31	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	02/10/25 16:31	

LABORATORY CONTROL SAMPLE: 4703163

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.6	103	80-120	

LABORATORY CONTROL SAMPLE: 4703164

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.9	106	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4703165 4703166

Parameter	Units	92778494003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	7.1	50	50	53.2	52.2	92	90	80-120	2	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4703167 4703168

Parameter	Units	92778494004 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	246	50	50	290	299	88	106	80-120	3	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch: 915650

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92778486003, 92778486004, 92778486005, 92778486006, 92778486010, 92778486011, 92778486012

METHOD BLANK: 4705927

Matrix: Water

Associated Lab Samples: 92778486003, 92778486004, 92778486005, 92778486006, 92778486010, 92778486011, 92778486012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	02/12/25 16:53	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	02/12/25 16:53	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	02/12/25 16:53	

LABORATORY CONTROL SAMPLE: 4705928

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.7	103	80-120	

LABORATORY CONTROL SAMPLE: 4705929

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.2	104	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4705930 4705931

Parameter	Units	92777634001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	163	50	50	220	223	115	120	80-120	1	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4705932 4705933

Parameter	Units	92777222002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	13.8	50	50	65.4	65.3	103	103	80-120	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch: 914807 Analysis Method: SM 2540C-2015
QC Batch Method: SM 2540C-2015 Analysis Description: 2540C Total Dissolved Solids
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92778486001, 92778486002, 92778486007, 92778486008, 92778486009

METHOD BLANK: 4702382 Matrix: Water
Associated Lab Samples: 92778486001, 92778486002, 92778486007, 92778486008, 92778486009

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	02/08/25 13:01	

LABORATORY CONTROL SAMPLE: 4702383

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	251	252	101	90-110	

SAMPLE DUPLICATE: 4702384

Parameter	Units	92778494001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	386	380	2	25	

SAMPLE DUPLICATE: 4702385

Parameter	Units	92778486002 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	483	482	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch:	915152	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Asheville

Associated Lab Samples: 92778486003, 92778486004, 92778486005, 92778486006, 92778486010, 92778486011, 92778486012

METHOD BLANK: 4703776 Matrix: Water

Associated Lab Samples: 92778486003, 92778486004, 92778486005, 92778486006, 92778486010, 92778486011, 92778486012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	02/11/25 12:03	

LABORATORY CONTROL SAMPLE: 4703777

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	250	246	98	90-110	

SAMPLE DUPLICATE: 4703778

Parameter	Units	92778266001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	124	114	8	25	

SAMPLE DUPLICATE: 4703779

Parameter	Units	92778486005 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	400	400	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch: 914751 Analysis Method: SM 4500-S2D-2011
QC Batch Method: SM 4500-S2D-2011 Analysis Description: 4500S2D Sulfide Water
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92778486001, 92778486002, 92778486007, 92778486008

METHOD BLANK: 4702232 Matrix: Water
Associated Lab Samples: 92778486001, 92778486002, 92778486007, 92778486008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	02/08/25 03:36	

LABORATORY CONTROL SAMPLE: 4702233

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.51	103	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4702234 4702235

Parameter	Units	92778050001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.51	0.54	101	108	80-120	6	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4702236 4702237

Parameter	Units	92778494009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.46	0.47	93	93	80-120	0	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch:	914753	Analysis Method:	SM 4500-S2D-2011
QC Batch Method:	SM 4500-S2D-2011	Analysis Description:	4500S2D Sulfide Water
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92778486003, 92778486004, 92778486005, 92778486006, 92778486009, 92778486010, 92778486011, 92778486012		

METHOD BLANK:	4702242	Matrix:	Water
Associated Lab Samples:	92778486003, 92778486004, 92778486005, 92778486006, 92778486009, 92778486010, 92778486011, 92778486012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	02/08/25 03:49	

LABORATORY CONTROL SAMPLE: 4702243						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	ma/L	0.5	0.52	103	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:					4702244	4702245							
Parameter	Units	92778486009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual	
Sulfide	mg/L	ND	0.5	0.5	0.51	0.48	102	95	80-120	7	10		

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:					4702246	4702247							
Parameter	Units	92777989003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual	
Sulfide	mg/L	ND	0.5	0.5	0.51	0.55	101	110	80-120	9	10		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203
Pace Project No.: 92778486

QC Batch:	914792	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville

Associated Lab Samples: 92778486001

METHOD BLANK: 4702337 Matrix: Water
Associated Lab Samples: 92778486001

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	02/08/25 21:17	
Fluoride	mg/L	ND	0.10	0.050	02/08/25 21:17	
Sulfate	mg/L	ND	1.0	0.50	02/08/25 21:17	

LABORATORY CONTROL SAMPLE: 4702338

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	51.4	103	90-110	
Fluoride	mg/L	2.5	2.6	104	90-110	
Sulfate	mg/L	50	52.2	104	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4702339 4702340

Parameter	Units	92778538006 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	28.7	50	50	79.0	78.0	101	99	90-110	1	10	
Fluoride	mg/L	0.055J	2.5	2.5	2.7	2.6	105	103	90-110	1	10	
Sulfate	mg/L	110	50	50	150	149	80	78	90-110	1	10 M1	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4702341 4702342

Parameter	Units	92778538016 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	1.4	50	50	50.5	52.0	98	101	90-110	3	10	
Fluoride	mg/L	0.073J	2.5	2.5	2.6	2.7	101	104	90-110	3	10	
Sulfate	mg/L	11.6	50	50	61.1	62.5	99	102	90-110	2	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch:	914829	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92778486002, 92778486003, 92778486004, 92778486005, 92778486006, 92778486007, 92778486008, 92778486009, 92778486010, 92778486011, 92778486012		

METHOD BLANK:	4702454	Matrix:	Water
Associated Lab Samples:	92778486002, 92778486003, 92778486004, 92778486005, 92778486006, 92778486007, 92778486008, 92778486009, 92778486010, 92778486011, 92778486012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	02/08/25 15:27	
Fluoride	mg/L	ND	0.10	0.050	02/08/25 15:27	
Sulfate	mg/L	ND	1.0	0.50	02/08/25 15:27	

LABORATORY CONTROL SAMPLE: 4702455						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	51.0	102	90-110	
Fluoride	mg/L	2.5	2.7	108	90-110	
Sulfate	mg/L	50	51.2	102	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4702456 4702457												
Parameter	Units	92778486002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	19.6	50	50	68.9	70.0	99	101	90-110	2	10	
Fluoride	mg/L	0.18	2.5	2.5	2.7	2.7	100	102	90-110	2	10	
Sulfate	mg/L	170	50	50	209	209	77	78	90-110	0	10 M1	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4702458 4702459												
Parameter	Units	92778486009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	17.4	50	50	66.9	66.1	99	97	90-110	1	10	
Fluoride	mg/L	0.32	2.5	2.5	2.8	2.8	100	98	90-110	2	10	
Sulfate	mg/L	173	50	50	213	211	81	77	90-110	1	10 M1	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch:	923197	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	WC 6020B MET
		Laboratory:	Pace Analytical Services - West Columbia
Associated Lab Samples:	92778486001, 92778486002, 92778486003, 92778486004, 92778486005, 92778486006, 92778486007, 92778486008, 92778486009, 92778486010, 92778486011, 92778486012		

METHOD BLANK: 4743181

Matrix: Water

Associated Lab Samples: 92778486001, 92778486002, 92778486003, 92778486004, 92778486005, 92778486006, 92778486007, 92778486008, 92778486009, 92778486010, 92778486011, 92778486012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00050	03/20/25 12:33	
Arsenic	mg/L	ND	0.0050	0.0012	03/20/25 12:33	
Barium	mg/L	ND	0.0050	0.0012	03/20/25 12:33	
Beryllium	mg/L	ND	0.00050	0.00015	03/20/25 12:33	
Boron	mg/L	ND	0.040	0.0062	03/20/25 16:02	
Cadmium	mg/L	ND	0.00050	0.00012	03/20/25 12:33	
Calcium	mg/L	ND	1.0	0.10	03/20/25 12:33	
Chromium	mg/L	ND	0.0050	0.0012	03/20/25 12:33	
Cobalt	mg/L	ND	0.0050	0.0012	03/20/25 12:33	
Iron	mg/L	ND	0.040	0.012	03/20/25 12:33	
Lead	mg/L	ND	0.0010	0.00025	03/20/25 12:33	
Magnesium	mg/L	ND	0.050	0.010	03/20/25 12:33	
Manganese	mg/L	ND	0.040	0.0012	03/20/25 12:33	
Molybdenum	mg/L	ND	0.010	0.0025	03/20/25 12:33	
Potassium	mg/L	ND	0.50	0.10	03/20/25 12:33	
Selenium	mg/L	ND	0.0050	0.0012	03/20/25 12:33	
Sodium	mg/L	ND	1.0	0.15	03/20/25 12:33	
Thallium	mg/L	ND	0.0010	0.00015	03/20/25 12:33	

LABORATORY CONTROL SAMPLE: 4743182

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.093	93	80-120	
Arsenic	mg/L	0.1	0.097	97	80-120	
Barium	mg/L	0.1	0.094	94	80-120	
Beryllium	mg/L	0.1	0.096	96	80-120	
Boron	mg/L	0.1	0.095	95	80-120	
Cadmium	mg/L	0.1	0.095	95	80-120	
Calcium	mg/L	1	0.99J	99	80-120	
Chromium	mg/L	0.1	0.098	98	80-120	
Cobalt	mg/L	0.1	0.10	103	80-120	
Iron	mg/L	1	0.99	99	80-120	
Lead	mg/L	0.1	0.10	102	80-120	
Magnesium	mg/L	1	0.97	97	80-120	
Manganese	mg/L	0.1	0.096	96	80-120	
Molybdenum	mg/L	0.1	0.095	95	80-120	
Potassium	mg/L	1	1.0	103	80-120	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

LABORATORY CONTROL SAMPLE: 4743182

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Selenium	mg/L	0.1	0.096	96	80-120	
Sodium	mg/L	1	1.0	104	80-120	
Thallium	mg/L	0.1	0.099	99	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4743183 4743184

Parameter	Units	92778486012	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		Result	Conc.	Conc.	Result	Result	% Rec	% Rec				
Antimony	mg/L	ND	0.1	0.1	0.096	0.095	96	95	75-125	1	20	
Arsenic	mg/L	0.26	0.1	0.1	0.34	0.34	82	81	75-125	0	20	
Barium	mg/L	0.043	0.1	0.1	0.14	0.14	96	96	75-125	1	20	
Beryllium	mg/L	ND	0.1	0.1	0.092	0.092	92	92	75-125	1	20	
Boron	mg/L	0.77	0.1	0.1	0.88	0.87	103	94	75-125	1	20	
Cadmium	mg/L	ND	0.1	0.1	0.096	0.096	96	96	75-125	0	20	
Calcium	mg/L	115	1	1	117	117	195	232	75-125	0	20	M1
Chromium	mg/L	ND	0.1	0.1	0.098	0.098	98	98	75-125	0	20	
Cobalt	mg/L	0.019	0.1	0.1	0.10	0.10	84	83	75-125	1	20	
Iron	mg/L	11.3	1	1	12.3	12.0	100	67	75-125	3	20	M1
Lead	mg/L	ND	0.1	0.1	0.098	0.098	98	98	75-125	0	20	
Magnesium	mg/L	16.7	1	1	17.4	17.5	68	80	75-125	1	20	M1
Manganese	mg/L	2.8	0.1	0.1	2.9	2.9	106	117	75-125	0	20	
Molybdenum	mg/L	0.015	0.1	0.1	0.11	0.11	96	96	75-125	0	20	
Potassium	mg/L	5.5	1	1	6.6	6.5	106	100	75-125	1	20	
Selenium	mg/L	ND	0.1	0.1	0.081	0.081	81	81	75-125	0	20	
Sodium	mg/L	8.8	1	1	9.7	9.7	92	91	75-125	0	20	
Thallium	mg/L	ND	0.1	0.1	0.095	0.095	95	95	75-125	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above adjusted reporting limit.

TNTC - Too Numerous To Count

J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

MDL - Adjusted Method Detection Limit.

PQL - Practical Quantitation Limit.

RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected.

Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.

A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

ANALYTE QUALIFIERS

J Analyte detected below the reporting limit, therefore result is an estimate. This qualifier is also used for all TICs.

M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92778486001	HAM-PT-07	3015	2464154	EPA 6020B	2464154
92778486002	HAM-PT-08	3015	2464154	EPA 6020B	2464154
92778486003	HAM-PT-09	3015	2464154	EPA 6020B	2464154
92778486004	HAM-PT-10	3015	2464154	EPA 6020B	2464154
92778486005	HAM-PT-11	3015	2464154	EPA 6020B	2464154
92778486006	HAM-PT-12	3015	2464154	EPA 6020B	2464154
92778486007	HAM-PT-13	3015	2464154	EPA 6020B	2464154
92778486008	HAM-PT-14	3015	2464154	EPA 6020B	2464154
92778486009	HAM-PT-15	3015	2464154	EPA 6020B	2464154
92778486010	HAM-AP1-EB-01	3015	2464154	EPA 6020B	2464154
92778486011	HAM-AP1-FB-01	3015	2464154	EPA 6020B	2464154
92778486012	HAM-AP1-FD-01	3015	2464154	EPA 6020B	2464154
92778486001	HAM-PT-07	EPA 7470A	914889	EPA 7470A	915003
92778486002	HAM-PT-08	EPA 7470A	914889	EPA 7470A	915003
92778486003	HAM-PT-09	EPA 7470A	914889	EPA 7470A	915003
92778486004	HAM-PT-10	EPA 7470A	914889	EPA 7470A	915003
92778486005	HAM-PT-11	EPA 7470A	914889	EPA 7470A	915003
92778486006	HAM-PT-12	EPA 7470A	914889	EPA 7470A	915003
92778486007	HAM-PT-13	EPA 7470A	914889	EPA 7470A	915003
92778486008	HAM-PT-14	EPA 7470A	914889	EPA 7470A	915003
92778486009	HAM-PT-15	EPA 7470A	914889	EPA 7470A	915003
92778486010	HAM-AP1-EB-01	EPA 7470A	914965	EPA 7470A	915313
92778486011	HAM-AP1-FB-01	EPA 7470A	914965	EPA 7470A	915313
92778486012	HAM-AP1-FD-01	EPA 7470A	914965	EPA 7470A	915313
92778486001	HAM-PT-07	SM 2320B-2011	915023		
92778486002	HAM-PT-08	SM 2320B-2011	915023		
92778486003	HAM-PT-09	SM 2320B-2011	915650		
92778486004	HAM-PT-10	SM 2320B-2011	915650		
92778486005	HAM-PT-11	SM 2320B-2011	915650		
92778486006	HAM-PT-12	SM 2320B-2011	915650		
92778486007	HAM-PT-13	SM 2320B-2011	915023		
92778486008	HAM-PT-14	SM 2320B-2011	915023		
92778486009	HAM-PT-15	SM 2320B-2011	915023		
92778486010	HAM-AP1-EB-01	SM 2320B-2011	915650		
92778486011	HAM-AP1-FB-01	SM 2320B-2011	915650		
92778486012	HAM-AP1-FD-01	SM 2320B-2011	915650		
92778486001	HAM-PT-07	SM 2540C-2015	914807		
92778486002	HAM-PT-08	SM 2540C-2015	914807		
92778486003	HAM-PT-09	SM 2540C-2015	915152		
92778486004	HAM-PT-10	SM 2540C-2015	915152		
92778486005	HAM-PT-11	SM 2540C-2015	915152		
92778486006	HAM-PT-12	SM 2540C-2015	915152		
92778486007	HAM-PT-13	SM 2540C-2015	914807		
92778486008	HAM-PT-14	SM 2540C-2015	914807		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92778486009	HAM-PT-15	SM 2540C-2015	914807		
92778486010	HAM-AP1-EB-01	SM 2540C-2015	915152		
92778486011	HAM-AP1-FB-01	SM 2540C-2015	915152		
92778486012	HAM-AP1-FD-01	SM 2540C-2015	915152		
92778486001	HAM-PT-07	SM 4500-S2D-2011	914751		
92778486002	HAM-PT-08	SM 4500-S2D-2011	914751		
92778486003	HAM-PT-09	SM 4500-S2D-2011	914753		
92778486004	HAM-PT-10	SM 4500-S2D-2011	914753		
92778486005	HAM-PT-11	SM 4500-S2D-2011	914753		
92778486006	HAM-PT-12	SM 4500-S2D-2011	914753		
92778486007	HAM-PT-13	SM 4500-S2D-2011	914751		
92778486008	HAM-PT-14	SM 4500-S2D-2011	914751		
92778486009	HAM-PT-15	SM 4500-S2D-2011	914753		
92778486010	HAM-AP1-EB-01	SM 4500-S2D-2011	914753		
92778486011	HAM-AP1-FB-01	SM 4500-S2D-2011	914753		
92778486012	HAM-AP1-FD-01	SM 4500-S2D-2011	914753		
92778486001	HAM-PT-07	EPA 300.0 Rev 2.1 1993	914792		
92778486002	HAM-PT-08	EPA 300.0 Rev 2.1 1993	914829		
92778486003	HAM-PT-09	EPA 300.0 Rev 2.1 1993	914829		
92778486004	HAM-PT-10	EPA 300.0 Rev 2.1 1993	914829		
92778486005	HAM-PT-11	EPA 300.0 Rev 2.1 1993	914829		
92778486006	HAM-PT-12	EPA 300.0 Rev 2.1 1993	914829		
92778486007	HAM-PT-13	EPA 300.0 Rev 2.1 1993	914829		
92778486008	HAM-PT-14	EPA 300.0 Rev 2.1 1993	914829		
92778486009	HAM-PT-15	EPA 300.0 Rev 2.1 1993	914829		
92778486010	HAM-AP1-EB-01	EPA 300.0 Rev 2.1 1993	914829		
92778486011	HAM-AP1-FB-01	EPA 300.0 Rev 2.1 1993	914829		
92778486012	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	914829		
92778486001	HAM-PT-07	EPA 3005A	923197	EPA 6020B	923913
92778486002	HAM-PT-08	EPA 3005A	923197	EPA 6020B	923913
92778486003	HAM-PT-09	EPA 3005A	923197	EPA 6020B	923913
92778486004	HAM-PT-10	EPA 3005A	923197	EPA 6020B	923913
92778486005	HAM-PT-11	EPA 3005A	923197	EPA 6020B	923913
92778486006	HAM-PT-12	EPA 3005A	923197	EPA 6020B	923913
92778486007	HAM-PT-13	EPA 3005A	923197	EPA 6020B	923913
92778486008	HAM-PT-14	EPA 3005A	923197	EPA 6020B	923913
92778486009	HAM-PT-15	EPA 3005A	923197	EPA 6020B	923913
92778486010	HAM-AP1-EB-01	EPA 3005A	923197	EPA 6020B	923913
92778486011	HAM-AP1-FB-01	EPA 3005A	923197	EPA 6020B	923913
92778486012	HAM-AP1-FD-01	EPA 3005A	923197	EPA 6020B	923913

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Effective Date: 05/24/2024

Laboratory receiving samples:

heville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐

Sample Condition
Upon Receipt

Client Name:

Project #

WO#: 92778486



Carrier:
Commercial

☐ Fed Ex ☐ UPS ☐ USPS ☐ Client
☒ Pace ☐ Other:

Body Seal Present?

☒ Yes

☐ No

Seals Intact?

☒ Yes

☐ No

☐ N/A

Date/Initials Person Examining Contents: 2/17/25 M.

Shipping Material:

☒ Bubble Wrap

☐ Bubble Bags

☐ None

☐ Other

Biological Tissue Frozen?

☐ Yes ☐ No ☒ N/A

Thermometer:

☒ IR Gun ID:

230

Type of Ice:

☒ Wet

☐ Blue

☐ None

Order Temp:

3.1

Correction Factor:

Add/Subtract (°C) 0.1

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Order Temp Corrected (°C):

3.2

DA Regulated Soil (☐ N/A, water sample)

Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ No

Did samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

		Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.
Short Hold Time Analysis (<72 hr.)?	☒ Yes ☐ No ☐ N/A	3.
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4.
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A	7.
Containers Intact?	☒ Yes ☐ No ☐ N/A	8.
Dissolved analysis: Samples Field Filtered?	1/17/25 ☒ Yes ☐ No ☐ N/A	9.
Sample Labels Match COC?	SA ☒ Yes ☐ No ☐ N/A	
-Includes Date/Time/ID/Analysis Matrix:	W	
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10.
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A	

Field Data Required? ☐ Yes ☐ No

Comments/SAMPLE DISCREPANCY

Lot ID of split containers:

NOTIFICATION/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

WO#: 92778486

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

PM: BV

Due Date: 02/24/25

CLIENT: 92- GP-HAM

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐

Client _____ Profile/EZ (Circle one) _____ Notes _____

Item#	CC	1	2	3	4	5	6	7	8	9	10	11	12	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic ZN Acetate & NaOH (pH > 12) (Cl-)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WG6U-Wide-mouthed Glass Jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG9A-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)	BP3R-250 mL Plastic (NH4)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	VSGU-20 mL Scintillation vials (N/A)	DG3U-40 mL Amber Unpreserved vials (N/A)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								</

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers.

Important Note: By signing this form you are accepting Pac's NET 30 day payment terms and agreeing to late charges of 1.5% per month for any invoices not paid within 30 days.



April 03, 2025

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1-CA-20250203
Pace Project No.: 92778486

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on February 07, 2025. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace National - Mt. Juliet
- Pace Analytical Services - Asheville
- Pace Analytical Services - West Columbia

Revision 1: Sample ID's for FB-01 and FD-01 were corrected to match COC.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Jamie Newsome, Geosyntec Consultants

Zain Webb, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Pace Analytical Services National

12065 Lebanon Road, Mt. Juliet, TN 37122

Alabama Certification #: 40660

Alaska Certification 17-026

Arizona Certification #: AZ0612

Arkansas Certification #: 88-0469

California Certification #: 2932

Canada Certification #: 1461.01

Colorado Certification #: TN00003

Connecticut Certification #: PH-0197

DOD Certification: #1461.01

EPA# TN00003

Florida Certification #: E87487

Georgia DW Certification #: 923

Georgia Certification: NELAP

Idaho Certification #: TN00003

Illinois Certification #: 200008

Indiana Certification #: C-TN-01

Iowa Certification #: 364

Kansas Certification #: E-10277

Kentucky UST Certification #: 16

Kentucky Certification #: 90010

Louisiana Certification #: AI30792

Louisiana DW Certification #: LA180010

Maine Certification #: TN0002

Maryland Certification #: 324

Massachusetts Certification #: M-TN003

Michigan Certification #: 9958

Minnesota Certification #: 047-999-395

Mississippi Certification #: TN00003

Missouri Certification #: 340

Montana Certification #: CERT0086

Nebraska Certification #: NE-OS-15-05

Nevada Certification #: TN-03-2002-34

New Hampshire Certification #: 2975

New Jersey Certification #: TN002

New Mexico DW Certification

New York Certification #: 11742

North Carolina Aquatic Toxicity Certification #: 41

North Carolina Drinking Water Certification #: 21704

North Carolina Environmental Certificate #: 375

North Dakota Certification #: R-140

Ohio VAP Certification #: CL0069

Oklahoma Certification #: 9915

Oregon Certification #: TN200002

Pennsylvania Certification #: 68-02979

Rhode Island Certification #: LA000356

South Carolina Certification #: 84004

South Dakota Certification

Tennessee DW/Chem/Micro Certification #: 2006

Texas Mold Certification #: LAB0152

Texas Certification #: T 104704245-17-14

USDA Soil Permit #: P330-15-00234

Utah Certification #: TN00003

Virginia Certification #: VT2006

Vermont Dept. of Health: ID# VT-2006

Virginia Certification #: 460132

Washington Certification #: C847

West Virginia Certification #: 233

Wisconsin Certification #: 998093910

Wyoming UST Certification #: via A2LA 2926.01

A2LA-ISO 17025 Certification #: 1461.01

A2LA-ISO 17025 Certification #: 1461.02

AIHA-LAP/LLC EMLAP Certification #:100789

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804

Florida/NELAP Certification #: E87648

North Carolina Drinking Water Certification #: 37712

North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030

South Carolina Certification #: 99030001

Virginia/VELAP Certification #: 460222

Pace Analytical Services West Columbia

106 Vantage Point Drive, West Columbia, SC 29172

Alaska Dept. of Energy Conservation, Cert# 20-002

California ELAP, cert# 3049

DoD, DoD QSM V5.4, cert# I.2224

DOE, DoD/DOE QSM V5.4, cert# I.2224.01

Florida, Dept. of Health, cert# E87653-70

Georgia, Env. Protection Division, cert# E87653

Illinois, EPA NELAP, cert# 2000552024-9

Kansas, Dept. of Health and Environment, cert# E-10417

Kentucky, Dept. for Env. Protection, UST, cert# 103582

Kentucky, Dept. for Env. Protection, cert# 98037

Louisiana, Dept. of Environmental Quality, cert# 5125

North Carolina, DEQ, Water Resources, cert# 329

New Jersey, Dept. of Env. Protection, cert# NLC 240005

Oklahoma, Dept. of Env. Quality, cert# 2023-175

Oregon, ELAP, cert# 4181-006

Pennsylvania, Dept. of Env. Protection, cert# 003

South Carolina, Dept. of Env. Services, cert# 32010001

Texas, Commission on Env. Quality, cert# TX-C24-00083

Virginia, Dept. of General Services, cert# 13080

Wisconsin, Dept. of Natural Resources, cert# 399136100

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92778486001	HAM-PT-07	Water	02/04/25 11:56	02/07/25 14:35
92778486002	HAM-PT-08	Water	02/04/25 13:39	02/07/25 14:35
92778486003	HAM-PT-09	Water	02/05/25 11:21	02/07/25 14:35
92778486004	HAM-PT-10	Water	02/05/25 10:00	02/07/25 14:35
92778486005	HAM-PT-11	Water	02/05/25 10:01	02/07/25 14:35
92778486006	HAM-PT-12	Water	02/05/25 11:41	02/07/25 14:35
92778486007	HAM-PT-13	Water	02/04/25 10:05	02/07/25 14:35
92778486008	HAM-PT-14	Water	02/04/25 10:08	02/07/25 14:35
92778486009	HAM-PT-15	Water	02/04/25 14:55	02/07/25 14:35
92778486010	HAM-AP1-EB-01	Water	02/05/25 12:30	02/07/25 14:35
92778486011	HAM-AP1-FB-01	Water	02/05/25 12:20	02/07/25 14:35
92778486012	HAM-AP1-FD-01	Water	02/05/25 00:00	02/07/25 14:35

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
92778486001	HAM-PT-07	EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	YEG	3	PASI-A
		SM 2540C-2015	CMW1	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
92778486002	HAM-PT-08	EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	YEG	3	PASI-A
		SM 2540C-2015	CMW1	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
92778486003	HAM-PT-09	EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A
92778486004	HAM-PT-10	SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	SMS	3	PASI-A
92778486005	HAM-PT-11	SM 2540C-2015	YEG	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
92778486006	HAM-PT-12	SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
92778486007	HAM-PT-13	SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	YEG	3	PASI-A
		SM 2540C-2015	CMW1	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
92778486008	HAM-PT-14	EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	YEG	3	PASI-A
		SM 2540C-2015	CMW1	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
92778486009	HAM-PT-15	EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	YEG	3	PASI-A
		SM 2540C-2015	CMW1	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	YEG	3	PASI-A
		SM 2540C-2015	CMW1	1	PASI-A
92778486010	HAM-AP1-EB-01	SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
92778486011	HAM-AP1-FB-01	EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
92778486012	HAM-AP1-FD-01	SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC
		EPA 6020B	JPD	1	PAN
		EPA 7470A	MAB2	1	PASI-A
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BK1	18	PASI-WC

PAN = Pace National - Mt. Juliet

PASI-A = Pace Analytical Services - Asheville

PASI-WC = Pace Analytical Services - West Columbia

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92778486001	HAM-PT-07					
EPA 6020B	Lithium	0.0461	mg/L	0.0300	03/07/25 02:49	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	169	mg/L	5.0	02/10/25 19:38	
SM 2320B-2011	Alkalinity, Total as CaCO3	169	mg/L	5.0	02/10/25 19:38	
SM 2540C-2015	Total Dissolved Solids	520	mg/L	25.0	02/08/25 13:02	
EPA 300.0 Rev 2.1 1993	Chloride	19.3	mg/L	1.0	02/09/25 05:28	
EPA 300.0 Rev 2.1 1993	Fluoride	0.40	mg/L	0.10	02/09/25 05:28	
EPA 300.0 Rev 2.1 1993	Sulfate	157	mg/L	4.0	02/09/25 09:38	
EPA 6020B	Arsenic	0.15	mg/L	0.0050	03/20/25 13:01	
EPA 6020B	Barium	0.047	mg/L	0.0050	03/20/25 13:01	
EPA 6020B	Boron	0.74	mg/L	0.40	03/20/25 22:50	
EPA 6020B	Calcium	121	mg/L	10.0	03/20/25 17:21	
EPA 6020B	Cobalt	0.036	mg/L	0.0050	03/20/25 13:01	
EPA 6020B	Iron	7.5	mg/L	0.040	03/20/25 13:01	
EPA 6020B	Magnesium	16.8	mg/L	0.050	03/20/25 13:01	
EPA 6020B	Manganese	3.4	mg/L	0.40	03/20/25 17:21	
EPA 6020B	Molybdenum	0.013	mg/L	0.010	03/20/25 13:01	
EPA 6020B	Potassium	5.5	mg/L	0.50	03/20/25 13:01	
EPA 6020B	Sodium	8.4	mg/L	1.0	03/20/25 13:01	
EPA 6020B	Thallium	0.00019J	mg/L	0.0010	03/20/25 13:01	
92778486002	HAM-PT-08					
EPA 6020B	Lithium	0.0201J	mg/L	0.0300	03/07/25 02:52	J
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	113	mg/L	5.0	02/10/25 19:49	
SM 2320B-2011	Alkalinity, Total as CaCO3	113	mg/L	5.0	02/10/25 19:49	
SM 2540C-2015	Total Dissolved Solids	483	mg/L	25.0	02/08/25 13:02	
EPA 300.0 Rev 2.1 1993	Chloride	19.6	mg/L	1.0	02/08/25 18:29	
EPA 300.0 Rev 2.1 1993	Fluoride	0.18	mg/L	0.10	02/08/25 18:29	
EPA 300.0 Rev 2.1 1993	Sulfate	170	mg/L	4.0	02/09/25 03:04	M1
EPA 6020B	Arsenic	0.033	mg/L	0.0050	03/20/25 13:06	
EPA 6020B	Barium	0.049	mg/L	0.0050	03/20/25 13:06	
EPA 6020B	Boron	0.82	mg/L	0.40	03/20/25 22:59	
EPA 6020B	Calcium	107	mg/L	10.0	03/20/25 17:25	
EPA 6020B	Cobalt	0.040	mg/L	0.0050	03/20/25 13:06	
EPA 6020B	Iron	1.8	mg/L	0.040	03/20/25 13:06	
EPA 6020B	Magnesium	13.4	mg/L	0.050	03/20/25 13:06	
EPA 6020B	Manganese	2.3	mg/L	0.40	03/20/25 17:25	
EPA 6020B	Molybdenum	0.0096J	mg/L	0.010	03/20/25 13:06	
EPA 6020B	Potassium	5.0	mg/L	0.50	03/20/25 13:06	
EPA 6020B	Sodium	6.8	mg/L	1.0	03/20/25 13:06	
EPA 6020B	Thallium	0.00018J	mg/L	0.0010	03/20/25 13:06	
92778486003	HAM-PT-09					
EPA 6020B	Lithium	0.00155J	mg/L	0.0300	03/07/25 02:55	J
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	131	mg/L	5.0	02/12/25 19:10	
SM 2320B-2011	Alkalinity, Total as CaCO3	131	mg/L	5.0	02/12/25 19:10	
SM 2540C-2015	Total Dissolved Solids	422	mg/L	25.0	02/11/25 12:06	
EPA 300.0 Rev 2.1 1993	Chloride	50.4	mg/L	1.0	02/08/25 19:10	
EPA 300.0 Rev 2.1 1993	Fluoride	0.37	mg/L	0.10	02/08/25 19:10	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92778486003	HAM-PT-09					
EPA 300.0 Rev 2.1 1993	Sulfate	111	mg/L	3.0	02/09/25 03:46	
EPA 6020B	Barium	0.060	mg/L	0.0050	03/20/25 13:10	
EPA 6020B	Boron	1.6	mg/L	0.40	03/20/25 23:08	
EPA 6020B	Calcium	89.3	mg/L	10.0	03/20/25 17:39	
EPA 6020B	Cobalt	0.0022J	mg/L	0.0050	03/20/25 13:10	
EPA 6020B	Iron	1.0	mg/L	0.040	03/20/25 13:10	
EPA 6020B	Magnesium	20.6	mg/L	0.050	03/20/25 13:10	
EPA 6020B	Manganese	0.33	mg/L	0.040	03/20/25 13:10	
EPA 6020B	Molybdenum	0.23	mg/L	0.010	03/20/25 13:10	
EPA 6020B	Potassium	6.2	mg/L	0.50	03/20/25 13:10	
EPA 6020B	Sodium	12.3	mg/L	1.0	03/20/25 13:10	
92778486004	HAM-PT-10					
EPA 6020B	Lithium	0.000905J	mg/L	0.0300	03/07/25 02:58	J
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	114	mg/L	5.0	02/12/25 19:25	
SM 2320B-2011	Alkalinity, Total as CaCO3	114	mg/L	5.0	02/12/25 19:25	
SM 2540C-2015	Total Dissolved Solids	401	mg/L	25.0	02/11/25 12:07	
EPA 300.0 Rev 2.1 1993	Chloride	46.3	mg/L	1.0	02/08/25 19:24	
EPA 300.0 Rev 2.1 1993	Fluoride	0.19	mg/L	0.10	02/08/25 19:24	
EPA 300.0 Rev 2.1 1993	Sulfate	110	mg/L	3.0	02/09/25 04:00	
EPA 6020B	Barium	0.046	mg/L	0.0050	03/20/25 13:15	
EPA 6020B	Boron	1.5	mg/L	0.40	03/20/25 23:17	
EPA 6020B	Calcium	98.1	mg/L	10.0	03/20/25 17:44	
EPA 6020B	Cobalt	0.0014J	mg/L	0.0050	03/20/25 13:15	
EPA 6020B	Iron	1.0	mg/L	0.040	03/20/25 13:15	
EPA 6020B	Magnesium	12.9	mg/L	0.050	03/20/25 13:15	
EPA 6020B	Manganese	0.43	mg/L	0.040	03/20/25 13:15	
EPA 6020B	Molybdenum	0.079	mg/L	0.010	03/20/25 13:15	
EPA 6020B	Potassium	6.6	mg/L	0.50	03/20/25 13:15	
EPA 6020B	Sodium	9.1	mg/L	1.0	03/20/25 13:15	
92778486005	HAM-PT-11					
EPA 6020B	Lithium	0.00159J	mg/L	0.0300	03/07/25 03:08	J
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	121	mg/L	5.0	02/12/25 19:32	
SM 2320B-2011	Alkalinity, Total as CaCO3	121	mg/L	5.0	02/12/25 19:32	
SM 2540C-2015	Total Dissolved Solids	400	mg/L	25.0	02/11/25 12:07	
EPA 300.0 Rev 2.1 1993	Chloride	37.7	mg/L	1.0	02/08/25 19:38	
EPA 300.0 Rev 2.1 1993	Fluoride	0.27	mg/L	0.10	02/08/25 19:38	
EPA 300.0 Rev 2.1 1993	Sulfate	96.4	mg/L	3.0	02/09/25 04:14	
EPA 6020B	Barium	0.062	mg/L	0.0050	03/20/25 13:20	
EPA 6020B	Boron	1.5	mg/L	0.40	03/20/25 23:26	
EPA 6020B	Calcium	95.8	mg/L	10.0	03/20/25 17:48	
EPA 6020B	Cobalt	0.0024J	mg/L	0.0050	03/20/25 13:20	
EPA 6020B	Iron	0.89	mg/L	0.040	03/20/25 13:20	
EPA 6020B	Magnesium	13.8	mg/L	0.050	03/20/25 13:20	
EPA 6020B	Manganese	0.35	mg/L	0.040	03/20/25 13:20	
EPA 6020B	Molybdenum	0.11	mg/L	0.010	03/20/25 13:20	
EPA 6020B	Potassium	6.3	mg/L	0.50	03/20/25 13:20	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92778486005	HAM-PT-11					
EPA 6020B	Sodium	8.5	mg/L	1.0	03/20/25 13:20	
92778486006	HAM-PT-12					
EPA 6020B	Lithium	0.00122J	mg/L	0.0300	03/07/25 03:11	J
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	120	mg/L	5.0	02/12/25 19:40	
SM 2320B-2011	Alkalinity, Total as CaCO3	120	mg/L	5.0	02/12/25 19:40	
SM 2540C-2015	Total Dissolved Solids	416	mg/L	25.0	02/11/25 12:07	
EPA 300.0 Rev 2.1 1993	Chloride	44.0	mg/L	1.0	02/08/25 19:52	
EPA 300.0 Rev 2.1 1993	Fluoride	0.25	mg/L	0.10	02/08/25 19:52	
EPA 300.0 Rev 2.1 1993	Sulfate	114	mg/L	3.0	02/09/25 04:29	
EPA 6020B	Barium	0.055	mg/L	0.0050	03/20/25 13:24	
EPA 6020B	Boron	1.6	mg/L	0.40	03/20/25 23:35	
EPA 6020B	Cadmium	0.00015J	mg/L	0.00050	03/20/25 13:24	
EPA 6020B	Calcium	91.4	mg/L	10.0	03/20/25 17:53	
EPA 6020B	Cobalt	0.0023J	mg/L	0.0050	03/20/25 13:24	
EPA 6020B	Iron	1.4	mg/L	0.040	03/20/25 13:24	
EPA 6020B	Magnesium	19.1	mg/L	0.050	03/20/25 13:24	
EPA 6020B	Manganese	0.44	mg/L	0.040	03/20/25 13:24	
EPA 6020B	Molybdenum	0.16	mg/L	0.010	03/20/25 13:24	
EPA 6020B	Potassium	6.0	mg/L	0.50	03/20/25 13:24	
EPA 6020B	Sodium	11.0	mg/L	1.0	03/20/25 13:24	
92778486007	HAM-PT-13					
EPA 6020B	Lithium	0.0520	mg/L	0.0300	03/07/25 03:14	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	163	mg/L	5.0	02/10/25 19:58	
SM 2320B-2011	Alkalinity, Total as CaCO3	163	mg/L	5.0	02/10/25 19:58	
SM 2540C-2015	Total Dissolved Solids	527	mg/L	25.0	02/08/25 13:03	
EPA 300.0 Rev 2.1 1993	Chloride	20.2	mg/L	1.0	02/08/25 20:06	
EPA 300.0 Rev 2.1 1993	Fluoride	0.35	mg/L	0.10	02/08/25 20:06	
EPA 300.0 Rev 2.1 1993	Sulfate	161	mg/L	4.0	02/09/25 04:43	
EPA 6020B	Arsenic	0.19	mg/L	0.0050	03/20/25 13:29	
EPA 6020B	Barium	0.046	mg/L	0.0050	03/20/25 13:29	
EPA 6020B	Boron	0.73	mg/L	0.40	03/20/25 23:44	
EPA 6020B	Calcium	114	mg/L	10.0	03/20/25 17:58	
EPA 6020B	Cobalt	0.018	mg/L	0.0050	03/20/25 13:29	
EPA 6020B	Iron	7.6	mg/L	0.040	03/20/25 13:29	
EPA 6020B	Magnesium	16.4	mg/L	0.050	03/20/25 13:29	
EPA 6020B	Manganese	2.9	mg/L	0.40	03/20/25 17:58	
EPA 6020B	Molybdenum	0.0099J	mg/L	0.010	03/20/25 13:29	
EPA 6020B	Potassium	5.4	mg/L	0.50	03/20/25 13:29	
EPA 6020B	Sodium	8.4	mg/L	1.0	03/20/25 13:29	
EPA 6020B	Thallium	0.00021J	mg/L	0.0010	03/20/25 13:29	
92778486008	HAM-PT-14					
EPA 6020B	Lithium	0.0528	mg/L	0.0300	03/07/25 03:17	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	170	mg/L	5.0	02/10/25 20:09	
SM 2320B-2011	Alkalinity, Total as CaCO3	170	mg/L	5.0	02/10/25 20:09	
SM 2540C-2015	Total Dissolved Solids	546	mg/L	25.0	02/08/25 13:03	
EPA 300.0 Rev 2.1 1993	Chloride	20.5	mg/L	1.0	02/08/25 20:20	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92778486008	HAM-PT-14					
EPA 300.0 Rev 2.1 1993	Fluoride	0.30	mg/L	0.10	02/08/25 20:20	
EPA 300.0 Rev 2.1 1993	Sulfate	170	mg/L	4.0	02/09/25 05:25	
EPA 6020B	Arsenic	0.26	mg/L	0.0050	03/20/25 13:34	
EPA 6020B	Barium	0.043	mg/L	0.0050	03/20/25 13:34	
EPA 6020B	Boron	0.75	mg/L	0.40	03/20/25 23:53	
EPA 6020B	Calcium	123	mg/L	10.0	03/20/25 18:02	
EPA 6020B	Cobalt	0.019	mg/L	0.0050	03/20/25 13:34	
EPA 6020B	Iron	11.7	mg/L	0.040	03/20/25 13:34	
EPA 6020B	Magnesium	16.8	mg/L	0.050	03/20/25 13:34	
EPA 6020B	Manganese	3.1	mg/L	0.40	03/20/25 18:02	
EPA 6020B	Molybdenum	0.015	mg/L	0.010	03/20/25 13:34	
EPA 6020B	Potassium	5.6	mg/L	0.50	03/20/25 13:34	
EPA 6020B	Sodium	8.8	mg/L	1.0	03/20/25 13:34	
92778486009	HAM-PT-15					
EPA 6020B	Lithium	0.0421	mg/L	0.0300	03/07/25 03:21	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	146	mg/L	5.0	02/10/25 20:20	
SM 2320B-2011	Alkalinity, Total as CaCO3	146	mg/L	5.0	02/10/25 20:20	
SM 2540C-2015	Total Dissolved Solids	515	mg/L	25.0	02/08/25 13:03	
EPA 300.0 Rev 2.1 1993	Chloride	17.4	mg/L	1.0	02/08/25 21:02	
EPA 300.0 Rev 2.1 1993	Fluoride	0.32	mg/L	0.10	02/08/25 21:02	
EPA 300.0 Rev 2.1 1993	Sulfate	173	mg/L	4.0	02/09/25 05:39	M1
EPA 6020B	Arsenic	0.078	mg/L	0.0050	03/20/25 13:38	
EPA 6020B	Barium	0.052	mg/L	0.0050	03/20/25 13:38	
EPA 6020B	Boron	0.80	mg/L	0.40	03/21/25 00:02	
EPA 6020B	Cadmium	0.00031J	mg/L	0.00050	03/20/25 13:38	
EPA 6020B	Calcium	117	mg/L	10.0	03/20/25 18:07	
EPA 6020B	Cobalt	0.026	mg/L	0.0050	03/20/25 13:38	
EPA 6020B	Iron	2.3	mg/L	0.040	03/20/25 13:38	
EPA 6020B	Magnesium	14.6	mg/L	0.050	03/20/25 13:38	
EPA 6020B	Manganese	4.1	mg/L	0.40	03/20/25 18:07	
EPA 6020B	Molybdenum	0.014	mg/L	0.010	03/20/25 13:38	
EPA 6020B	Potassium	5.4	mg/L	0.50	03/20/25 13:38	
EPA 6020B	Sodium	7.4	mg/L	1.0	03/20/25 13:38	
EPA 6020B	Thallium	0.00050J	mg/L	0.0010	03/20/25 13:38	
92778486010	HAM-AP1-EB-01					
EPA 6020B	Iron	0.050	mg/L	0.040	03/20/25 13:43	
EPA 6020B	Manganese	0.0015J	mg/L	0.040	03/20/25 13:43	
92778486011	HAM-AP1-FB-01					
EPA 6020B	Lithium	0.00809J	mg/L	0.0300	03/07/25 03:27	J
92778486012	HAM-AP1-FD-01					
EPA 6020B	Lithium	0.0538	mg/L	0.0300	03/07/25 03:30	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	172	mg/L	5.0	02/12/25 19:54	
SM 2320B-2011	Alkalinity, Total as CaCO3	172	mg/L	5.0	02/12/25 19:54	
SM 2540C-2015	Total Dissolved Solids	516	mg/L	25.0	02/11/25 12:08	
EPA 300.0 Rev 2.1 1993	Chloride	20.6	mg/L	1.0	02/08/25 21:43	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92778486012	HAM-AP1-FD-01					
EPA 300.0 Rev 2.1 1993	Fluoride	0.30	mg/L	0.10	02/08/25 21:43	
EPA 300.0 Rev 2.1 1993	Sulfate	165	mg/L	4.0	02/09/25 06:20	
EPA 6020B	Arsenic	0.26	mg/L	0.0050	03/20/25 14:01	
EPA 6020B	Barium	0.043	mg/L	0.0050	03/20/25 14:01	
EPA 6020B	Boron	0.77	mg/L	0.40	03/20/25 17:14	
EPA 6020B	Calcium	115	mg/L	10.0	03/20/25 18:21	M1
EPA 6020B	Cobalt	0.019	mg/L	0.0050	03/20/25 14:01	
EPA 6020B	Iron	11.3	mg/L	0.040	03/20/25 14:01	M1
EPA 6020B	Magnesium	16.7	mg/L	0.050	03/20/25 14:01	M1
EPA 6020B	Manganese	2.8	mg/L	0.40	03/20/25 17:14	
EPA 6020B	Molybdenum	0.015	mg/L	0.010	03/20/25 14:01	
EPA 6020B	Potassium	5.5	mg/L	0.50	03/20/25 14:01	
EPA 6020B	Sodium	8.8	mg/L	1.0	03/20/25 14:01	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-07		Lab ID: 92778486001		Collected: 02/04/25 11:56		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B									
Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet									
Lithium	0.0461	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 02:49	7439-93-2	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville									
Mercury	ND	mg/L	0.00020	0.00012	1	02/09/25 17:53	02/11/25 14:43	7439-97-6	
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	169	mg/L	5.0	5.0	1		02/10/25 19:38		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/10/25 19:38		
Alkalinity, Total as CaCO ₃	169	mg/L	5.0	5.0	1		02/10/25 19:38		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	520	mg/L	25.0	25.0	1		02/08/25 13:02		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:47	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	19.3	mg/L	1.0	0.60	1		02/09/25 05:28	16887-00-6	
Fluoride	0.40	mg/L	0.10	0.050	1		02/09/25 05:28	16984-48-8	
Sulfate	157	mg/L	4.0	2.0	4		02/09/25 09:38	14808-79-8	
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:01	7440-36-0	
Arsenic	0.15	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:01	7440-38-2	
Barium	0.047	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:01	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:01	7440-41-7	
Boron	0.74	mg/L	0.40	0.062	10	03/19/25 06:10	03/20/25 22:50	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:01	7440-43-9	
Calcium	121	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 17:21	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:01	7440-47-3	
Cobalt	0.036	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:01	7440-48-4	
Iron	7.5	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:01	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:01	7439-92-1	
Magnesium	16.8	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:01	7439-95-4	
Manganese	3.4	mg/L	0.40	0.012	10	03/19/25 06:10	03/20/25 17:21	7439-96-5	
Molybdenum	0.013	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:01	7439-98-7	
Potassium	5.5	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:01	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:01	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-07		Lab ID: 92778486001		Collected: 02/04/25 11:56		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - West Columbia									
Sodium	8.4	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:01	7440-23-5	
Thallium	0.00019J	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:01	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-08		Lab ID: 92778486002		Collected: 02/04/25 13:39		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	0.0201J	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 02:52	7439-93-2	J
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville							
Mercury	ND	mg/L	0.00020	0.00012	1	02/09/25 17:53	02/11/25 14:45	7439-97-6	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	113	mg/L	5.0	5.0	1		02/10/25 19:49		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/10/25 19:49		
Alkalinity, Total as CaCO ₃	113	mg/L	5.0	5.0	1		02/10/25 19:49		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	483	mg/L	25.0	25.0	1		02/08/25 13:02		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:47	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	19.6	mg/L	1.0	0.60	1		02/08/25 18:29	16887-00-6	
Fluoride	0.18	mg/L	0.10	0.050	1		02/08/25 18:29	16984-48-8	
Sulfate	170	mg/L	4.0	2.0	4		02/09/25 03:04	14808-79-8	M1
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:06	7440-36-0	
Arsenic	0.033	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:06	7440-38-2	
Barium	0.049	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:06	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:06	7440-41-7	
Boron	0.82	mg/L	0.40	0.062	10	03/19/25 06:10	03/20/25 22:59	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:06	7440-43-9	
Calcium	107	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 17:25	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:06	7440-47-3	
Cobalt	0.040	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:06	7440-48-4	
Iron	1.8	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:06	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:06	7439-92-1	
Magnesium	13.4	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:06	7439-95-4	
Manganese	2.3	mg/L	0.40	0.012	10	03/19/25 06:10	03/20/25 17:25	7439-96-5	
Molybdenum	0.0096J	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:06	7439-98-7	
Potassium	5.0	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:06	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:06	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-08		Lab ID: 92778486002		Collected: 02/04/25 13:39		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Sodium	6.8	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:06	7440-23-5	
Thallium	0.00018J	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:06	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-09		Lab ID: 92778486003		Collected: 02/05/25 11:21		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	0.00155J	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 02:55	7439-93-2	J
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville							
Mercury	ND	mg/L	0.00020	0.00012	1	02/09/25 17:53	02/11/25 14:47	7439-97-6	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	131	mg/L	5.0	5.0	1		02/12/25 19:10		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/12/25 19:10		
Alkalinity, Total as CaCO ₃	131	mg/L	5.0	5.0	1		02/12/25 19:10		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	422	mg/L	25.0	25.0	1		02/11/25 12:06		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:56	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	50.4	mg/L	1.0	0.60	1		02/08/25 19:10	16887-00-6	
Fluoride	0.37	mg/L	0.10	0.050	1		02/08/25 19:10	16984-48-8	
Sulfate	111	mg/L	3.0	1.5	3		02/09/25 03:46	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:10	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:10	7440-38-2	
Barium	0.060	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:10	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:10	7440-41-7	
Boron	1.6	mg/L	0.40	0.062	10	03/19/25 06:10	03/20/25 23:08	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:10	7440-43-9	
Calcium	89.3	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 17:39	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:10	7440-47-3	
Cobalt	0.0022J	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:10	7440-48-4	
Iron	1.0	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:10	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:10	7439-92-1	
Magnesium	20.6	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:10	7439-95-4	
Manganese	0.33	mg/L	0.040	0.0012	1	03/19/25 06:10	03/20/25 13:10	7439-96-5	
Molybdenum	0.23	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:10	7439-98-7	
Potassium	6.2	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:10	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:10	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-09		Lab ID: 92778486003		Collected: 02/05/25 11:21		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Sodium	12.3	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:10	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:10	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-10		Lab ID: 92778486004		Collected: 02/05/25 10:00		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B									
Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet									
Lithium	0.000905J	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 02:58	7439-93-2	J
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville									
Mercury	ND	mg/L	0.00020	0.00012	1	02/09/25 17:53	02/11/25 14:49	7439-97-6	
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	114	mg/L	5.0	5.0	1		02/12/25 19:25		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/12/25 19:25		
Alkalinity, Total as CaCO ₃	114	mg/L	5.0	5.0	1		02/12/25 19:25		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	401	mg/L	25.0	25.0	1		02/11/25 12:07		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:56	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	46.3	mg/L	1.0	0.60	1		02/08/25 19:24	16887-00-6	
Fluoride	0.19	mg/L	0.10	0.050	1		02/08/25 19:24	16984-48-8	
Sulfate	110	mg/L	3.0	1.5	3		02/09/25 04:00	14808-79-8	
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:15	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:15	7440-38-2	
Barium	0.046	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:15	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:15	7440-41-7	
Boron	1.5	mg/L	0.40	0.062	10	03/19/25 06:10	03/20/25 23:17	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:15	7440-43-9	
Calcium	98.1	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 17:44	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:15	7440-47-3	
Cobalt	0.0014J	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:15	7440-48-4	
Iron	1.0	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:15	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:15	7439-92-1	
Magnesium	12.9	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:15	7439-95-4	
Manganese	0.43	mg/L	0.040	0.0012	1	03/19/25 06:10	03/20/25 13:15	7439-96-5	
Molybdenum	0.079	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:15	7439-98-7	
Potassium	6.6	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:15	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:15	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-10		Lab ID: 92778486004		Collected: 02/05/25 10:00		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - West Columbia									
Sodium	9.1	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:15	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:15	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-11		Lab ID: 92778486005		Collected: 02/05/25 10:01		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	0.00159J	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 03:08	7439-93-2	J
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville							
Mercury	ND	mg/L	0.00020	0.00012	1	02/09/25 17:53	02/11/25 14:51	7439-97-6	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	121	mg/L	5.0	5.0	1		02/12/25 19:32		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/12/25 19:32		
Alkalinity, Total as CaCO ₃	121	mg/L	5.0	5.0	1		02/12/25 19:32		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	400	mg/L	25.0	25.0	1		02/11/25 12:07		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:57	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	37.7	mg/L	1.0	0.60	1		02/08/25 19:38	16887-00-6	
Fluoride	0.27	mg/L	0.10	0.050	1		02/08/25 19:38	16984-48-8	
Sulfate	96.4	mg/L	3.0	1.5	3		02/09/25 04:14	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:20	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:20	7440-38-2	
Barium	0.062	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:20	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:20	7440-41-7	
Boron	1.5	mg/L	0.40	0.062	10	03/19/25 06:10	03/20/25 23:26	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:20	7440-43-9	
Calcium	95.8	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 17:48	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:20	7440-47-3	
Cobalt	0.0024J	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:20	7440-48-4	
Iron	0.89	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:20	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:20	7439-92-1	
Magnesium	13.8	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:20	7439-95-4	
Manganese	0.35	mg/L	0.040	0.0012	1	03/19/25 06:10	03/20/25 13:20	7439-96-5	
Molybdenum	0.11	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:20	7439-98-7	
Potassium	6.3	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:20	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:20	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-11		Lab ID: 92778486005		Collected: 02/05/25 10:01		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Sodium	8.5	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:20	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:20	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-12		Lab ID: 92778486006		Collected: 02/05/25 11:41		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	0.00122J	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 03:11	7439-93-2	J
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville							
Mercury	ND	mg/L	0.00020	0.00012	1	02/09/25 17:53	02/11/25 14:57	7439-97-6	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	120	mg/L	5.0	5.0	1		02/12/25 19:40		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/12/25 19:40		
Alkalinity, Total as CaCO ₃	120	mg/L	5.0	5.0	1		02/12/25 19:40		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	416	mg/L	25.0	25.0	1		02/11/25 12:07		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:57	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	44.0	mg/L	1.0	0.60	1		02/08/25 19:52	16887-00-6	
Fluoride	0.25	mg/L	0.10	0.050	1		02/08/25 19:52	16984-48-8	
Sulfate	114	mg/L	3.0	1.5	3		02/09/25 04:29	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:24	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:24	7440-38-2	
Barium	0.055	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:24	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:24	7440-41-7	
Boron	1.6	mg/L	0.40	0.062	10	03/19/25 06:10	03/20/25 23:35	7440-42-8	
Cadmium	0.00015J	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:24	7440-43-9	
Calcium	91.4	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 17:53	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:24	7440-47-3	
Cobalt	0.0023J	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:24	7440-48-4	
Iron	1.4	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:24	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:24	7439-92-1	
Magnesium	19.1	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:24	7439-95-4	
Manganese	0.44	mg/L	0.040	0.0012	1	03/19/25 06:10	03/20/25 13:24	7439-96-5	
Molybdenum	0.16	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:24	7439-98-7	
Potassium	6.0	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:24	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:24	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-12		Lab ID: 92778486006		Collected: 02/05/25 11:41		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - West Columbia									
Sodium	11.0	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:24	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:24	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-13		Lab ID: 92778486007		Collected: 02/04/25 10:05		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	0.0520	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 03:14	7439-93-2	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville							
Mercury	ND	mg/L	0.00020	0.00012	1	02/09/25 17:53	02/11/25 15:00	7439-97-6	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	163	mg/L	5.0	5.0	1		02/10/25 19:58		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/10/25 19:58		
Alkalinity, Total as CaCO ₃	163	mg/L	5.0	5.0	1		02/10/25 19:58		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	527	mg/L	25.0	25.0	1		02/08/25 13:03		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:47	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	20.2	mg/L	1.0	0.60	1		02/08/25 20:06	16887-00-6	
Fluoride	0.35	mg/L	0.10	0.050	1		02/08/25 20:06	16984-48-8	
Sulfate	161	mg/L	4.0	2.0	4		02/09/25 04:43	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:29	7440-36-0	
Arsenic	0.19	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:29	7440-38-2	
Barium	0.046	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:29	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:29	7440-41-7	
Boron	0.73	mg/L	0.40	0.062	10	03/19/25 06:10	03/20/25 23:44	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:29	7440-43-9	
Calcium	114	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 17:58	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:29	7440-47-3	
Cobalt	0.018	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:29	7440-48-4	
Iron	7.6	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:29	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:29	7439-92-1	
Magnesium	16.4	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:29	7439-95-4	
Manganese	2.9	mg/L	0.40	0.012	10	03/19/25 06:10	03/20/25 17:58	7439-96-5	
Molybdenum	0.0099J	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:29	7439-98-7	
Potassium	5.4	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:29	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:29	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-13		Lab ID: 92778486007		Collected: 02/04/25 10:05		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Sodium	8.4	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:29	7440-23-5	
Thallium	0.00021J	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:29	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-14		Lab ID: 92778486008		Collected: 02/04/25 10:08		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B									
Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet									
Lithium	0.0528	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 03:17	7439-93-2	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville									
Mercury	ND	mg/L	0.00020	0.00012	1	02/09/25 17:53	02/11/25 15:02	7439-97-6	
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	170	mg/L	5.0	5.0	1		02/10/25 20:09		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/10/25 20:09		
Alkalinity, Total as CaCO ₃	170	mg/L	5.0	5.0	1		02/10/25 20:09		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	546	mg/L	25.0	25.0	1		02/08/25 13:03		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:48	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	20.5	mg/L	1.0	0.60	1		02/08/25 20:20	16887-00-6	
Fluoride	0.30	mg/L	0.10	0.050	1		02/08/25 20:20	16984-48-8	
Sulfate	170	mg/L	4.0	2.0	4		02/09/25 05:25	14808-79-8	
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:34	7440-36-0	
Arsenic	0.26	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:34	7440-38-2	
Barium	0.043	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:34	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:34	7440-41-7	
Boron	0.75	mg/L	0.40	0.062	10	03/19/25 06:10	03/20/25 23:53	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:34	7440-43-9	
Calcium	123	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 18:02	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:34	7440-47-3	
Cobalt	0.019	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:34	7440-48-4	
Iron	11.7	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:34	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:34	7439-92-1	
Magnesium	16.8	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:34	7439-95-4	
Manganese	3.1	mg/L	0.40	0.012	10	03/19/25 06:10	03/20/25 18:02	7439-96-5	
Molybdenum	0.015	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:34	7439-98-7	
Potassium	5.6	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:34	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:34	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-14		Lab ID: 92778486008		Collected: 02/04/25 10:08		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Sodium	8.8	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:34	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:34	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-15		Lab ID: 92778486009		Collected: 02/04/25 14:55		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	0.0421	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 03:21	7439-93-2	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville							
Mercury	ND	mg/L	0.00020	0.00012	1	02/09/25 17:53	02/11/25 15:04	7439-97-6	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	146	mg/L	5.0	5.0	1		02/10/25 20:20		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/10/25 20:20		
Alkalinity, Total as CaCO ₃	146	mg/L	5.0	5.0	1		02/10/25 20:20		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	515	mg/L	25.0	25.0	1		02/08/25 13:03		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:50	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	17.4	mg/L	1.0	0.60	1		02/08/25 21:02	16887-00-6	
Fluoride	0.32	mg/L	0.10	0.050	1		02/08/25 21:02	16984-48-8	
Sulfate	173	mg/L	4.0	2.0	4		02/09/25 05:39	14808-79-8	M1
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:38	7440-36-0	
Arsenic	0.078	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:38	7440-38-2	
Barium	0.052	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:38	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:38	7440-41-7	
Boron	0.80	mg/L	0.40	0.062	10	03/19/25 06:10	03/21/25 00:02	7440-42-8	
Cadmium	0.00031J	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:38	7440-43-9	
Calcium	117	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 18:07	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:38	7440-47-3	
Cobalt	0.026	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:38	7440-48-4	
Iron	2.3	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:38	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:38	7439-92-1	
Magnesium	14.6	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:38	7439-95-4	
Manganese	4.1	mg/L	0.40	0.012	10	03/19/25 06:10	03/20/25 18:07	7439-96-5	
Molybdenum	0.014	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:38	7439-98-7	
Potassium	5.4	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:38	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:38	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-PT-15		Lab ID: 92778486009		Collected: 02/04/25 14:55		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Sodium	7.4	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:38	7440-23-5	
Thallium	0.00050J	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:38	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-AP1-EB-01		Lab ID: 92778486010		Collected: 02/05/25 12:30		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	ND	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 03:24	7439-93-2	
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville							
Mercury	ND	mg/L	0.00020	0.00012	1	02/10/25 17:03	02/13/25 14:14	7439-97-6	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/12/25 19:47		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/12/25 19:47		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		02/12/25 19:47		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		02/11/25 12:07		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:58	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	ND	mg/L	1.0	0.60	1		02/08/25 15:55	16887-00-6	
Fluoride	ND	mg/L	0.10	0.050	1		02/08/25 15:55	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		02/08/25 15:55	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:43	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:43	7440-38-2	
Barium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:43	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:43	7440-41-7	
Boron	ND	mg/L	0.040	0.0062	1	03/19/25 06:10	03/21/25 00:11	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:43	7440-43-9	
Calcium	ND	mg/L	1.0	0.10	1	03/19/25 06:10	03/20/25 13:43	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:43	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:43	7440-48-4	
Iron	0.050	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:43	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:43	7439-92-1	
Magnesium	ND	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:43	7439-95-4	
Manganese	0.0015J	mg/L	0.040	0.0012	1	03/19/25 06:10	03/20/25 13:43	7439-96-5	
Molybdenum	ND	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:43	7439-98-7	
Potassium	ND	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:43	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:43	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-AP1-EB-01		Lab ID: 92778486010		Collected: 02/05/25 12:30		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - West Columbia									
Sodium	ND	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:43	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:43	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-AP1-FB-01		Lab ID: 92778486011		Collected: 02/05/25 12:20		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	0.00809J	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 03:27	7439-93-2	J
7470 Mercury		Analytical Method: EPA 7470A Preparation Method: EPA 7470A Pace Analytical Services - Asheville							
Mercury	ND	mg/L	0.00020	0.00012	1	02/10/25 17:03	02/13/25 14:18	7439-97-6	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/12/25 19:51		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/12/25 19:51		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		02/12/25 19:51		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		02/11/25 12:07		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:58	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	ND	mg/L	1.0	0.60	1		02/08/25 16:09	16887-00-6	
Fluoride	ND	mg/L	0.10	0.050	1		02/08/25 16:09	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		02/08/25 16:09	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 13:57	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:57	7440-38-2	
Barium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:57	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 13:57	7440-41-7	
Boron	ND	mg/L	0.040	0.0062	1	03/19/25 06:10	03/21/25 00:39	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 13:57	7440-43-9	
Calcium	ND	mg/L	1.0	0.10	1	03/19/25 06:10	03/20/25 13:57	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:57	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:57	7440-48-4	
Iron	ND	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 13:57	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 13:57	7439-92-1	
Magnesium	ND	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 13:57	7439-95-4	
Manganese	ND	mg/L	0.040	0.0012	1	03/19/25 06:10	03/20/25 13:57	7439-96-5	
Molybdenum	ND	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 13:57	7439-98-7	
Potassium	ND	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 13:57	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 13:57	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203
Pace Project No.: 92778486

Sample: HAM-AP1-FB-01		Lab ID: 92778486011		Collected: 02/05/25 12:20		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Sodium	ND	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 13:57	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 13:57	7440-28-0	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Sample: HAM-AP1-FD-01		Lab ID: 92778486012		Collected: 02/05/25 00:00		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B									
Analytical Method: EPA 6020B Preparation Method: 3015									
Pace National - Mt. Juliet									
Lithium	0.0538	mg/L	0.0300	0.000600	1	03/06/25 22:51	03/07/25 03:30	7439-93-2	
7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - Asheville									
Mercury	ND	mg/L	0.00020	0.00012	1	02/10/25 17:03	02/13/25 14:20	7439-97-6	
2320B Alkalinity									
Analytical Method: SM 2320B-2011									
Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	172	mg/L	5.0	5.0	1		02/12/25 19:54		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		02/12/25 19:54		
Alkalinity, Total as CaCO ₃	172	mg/L	5.0	5.0	1		02/12/25 19:54		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015									
Pace Analytical Services - Asheville									
Total Dissolved Solids	516	mg/L	25.0	25.0	1		02/11/25 12:08		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011									
Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		02/08/25 03:58	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993									
Pace Analytical Services - Asheville									
Chloride	20.6	mg/L	1.0	0.60	1		02/08/25 21:43	16887-00-6	
Fluoride	0.30	mg/L	0.10	0.050	1		02/08/25 21:43	16984-48-8	
Sulfate	165	mg/L	4.0	2.0	4		02/09/25 06:20	14808-79-8	
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	03/19/25 06:10	03/20/25 14:01	7440-36-0	
Arsenic	0.26	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 14:01	7440-38-2	
Barium	0.043	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 14:01	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	03/19/25 06:10	03/20/25 14:01	7440-41-7	
Boron	0.77	mg/L	0.40	0.062	10	03/19/25 06:10	03/20/25 17:14	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	03/19/25 06:10	03/20/25 14:01	7440-43-9	
Calcium	115	mg/L	10.0	1.0	10	03/19/25 06:10	03/20/25 18:21	7440-70-2	M1
Chromium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 14:01	7440-47-3	
Cobalt	0.019	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 14:01	7440-48-4	
Iron	11.3	mg/L	0.040	0.012	1	03/19/25 06:10	03/20/25 14:01	7439-89-6	M1
Lead	ND	mg/L	0.0010	0.00025	1	03/19/25 06:10	03/20/25 14:01	7439-92-1	
Magnesium	16.7	mg/L	0.050	0.010	1	03/19/25 06:10	03/20/25 14:01	7439-95-4	M1
Manganese	2.8	mg/L	0.40	0.012	10	03/19/25 06:10	03/20/25 17:14	7439-96-5	
Molybdenum	0.015	mg/L	0.010	0.0025	1	03/19/25 06:10	03/20/25 14:01	7439-98-7	
Potassium	5.5	mg/L	0.50	0.10	1	03/19/25 06:10	03/20/25 14:01	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	03/19/25 06:10	03/20/25 14:01	7782-49-2	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1-CA-20250203
Pace Project No.: 92778486

Sample: HAM-AP1-FD-01		Lab ID: 92778486012		Collected: 02/05/25 00:00		Received: 02/07/25 14:35		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A									
Pace Analytical Services - West Columbia									
Sodium	8.8	mg/L	1.0	0.15	1	03/19/25 06:10	03/20/25 14:01	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	03/19/25 06:10	03/20/25 14:01	7440-28-0	

REPORT OF LABORATORY ANALYSIS



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch:	2464154	Analysis Method:	EPA 6020B
QC Batch Method:	3015	Analysis Description:	Metals (ICPMS) 6020B
		Laboratory:	Pace National - Mt. Juliet
Associated Lab Samples:	92778486001, 92778486002, 92778486003, 92778486004, 92778486005, 92778486006, 92778486007, 92778486008, 92778486009, 92778486010, 92778486011, 92778486012		

METHOD BLANK:	R4183615-1	Matrix:	Water
Associated Lab Samples:	92778486001, 92778486002, 92778486003, 92778486004, 92778486005, 92778486006, 92778486007, 92778486008, 92778486009, 92778486010, 92778486011, 92778486012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Lithium	mg/L	ND	0.0300	0.000600	03/07/25 02:29	

LABORATORY CONTROL SAMPLE: R4183615-2						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Lithium	mg/L	0.0500	0.0476	95.2	80.0-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:					R4183615-4								R4183615-5			
Parameter	Units	L1833065-06	MS	MSD	MS	MSD	MS	MSD	% Rec	RPD	Max	Qual				
		Result	Spike Conc.	Spike Conc.												
Lithium	mg/L	0.00370	0.0500	0.0500	0.0494	0.0494	91.4	91.3	75.0-125	0.036	20					

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch:	914889	Analysis Method:	EPA 7470A
QC Batch Method:	EPA 7470A	Analysis Description:	7470 Mercury
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92778486001, 92778486002, 92778486003, 92778486004, 92778486005, 92778486006, 92778486007, 92778486008, 92778486009		

METHOD BLANK:	4702575	Matrix:	Water
Associated Lab Samples:	92778486001, 92778486002, 92778486003, 92778486004, 92778486005, 92778486006, 92778486007, 92778486008, 92778486009		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00012	02/11/25 14:07	

LABORATORY CONTROL SAMPLE: 4702576						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0024	95	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:					4702577								4702578			
Parameter	Units	92777579004	MS	MSD	MS	MSD	MS	MSD	% Rec	RPD	Max	Qual				
		Result	Spike Conc.	Spike Conc.									Result	Result	% Rec	% Rec
Mercury	mg/L	ND	0.0025	0.0025	0.0024	0.0023	94	93	75-125	1	25					

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch: 914965

Analysis Method: EPA 7470A

QC Batch Method: EPA 7470A

Analysis Description: 7470 Mercury

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92778486010, 92778486011, 92778486012

METHOD BLANK: 4702822

Matrix: Water

Associated Lab Samples: 92778486010, 92778486011, 92778486012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.00012	02/13/25 14:10	

LABORATORY CONTROL SAMPLE: 4702823

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.0025	0.0022	88	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4702824 4702825

Parameter	Units	92778486010 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.0025	0.0025	0.0023	0.0022	93	89	75-125	5	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch: 915023

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92778486001, 92778486002, 92778486007, 92778486008, 92778486009

METHOD BLANK: 4703162

Matrix: Water

Associated Lab Samples: 92778486001, 92778486002, 92778486007, 92778486008, 92778486009

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	02/10/25 16:31	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	02/10/25 16:31	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	02/10/25 16:31	

LABORATORY CONTROL SAMPLE: 4703163

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.6	103	80-120	

LABORATORY CONTROL SAMPLE: 4703164

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.9	106	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4703165 4703166

Parameter	Units	92778494003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	7.1	50	50	53.2	52.2	92	90	80-120	2	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4703167 4703168

Parameter	Units	92778494004 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	246	50	50	290	299	88	106	80-120	3	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch: 915650

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92778486003, 92778486004, 92778486005, 92778486006, 92778486010, 92778486011, 92778486012

METHOD BLANK: 4705927

Matrix: Water

Associated Lab Samples: 92778486003, 92778486004, 92778486005, 92778486006, 92778486010, 92778486011, 92778486012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	02/12/25 16:53	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	02/12/25 16:53	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	02/12/25 16:53	

LABORATORY CONTROL SAMPLE: 4705928

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.7	103	80-120	

LABORATORY CONTROL SAMPLE: 4705929

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.2	104	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4705930 4705931

Parameter	Units	92777634001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	163	50	50	220	223	115	120	80-120	1	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4705932 4705933

Parameter	Units	92777222002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	13.8	50	50	65.4	65.3	103	103	80-120	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch: 914807 Analysis Method: SM 2540C-2015
QC Batch Method: SM 2540C-2015 Analysis Description: 2540C Total Dissolved Solids
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92778486001, 92778486002, 92778486007, 92778486008, 92778486009

METHOD BLANK: 4702382 Matrix: Water
Associated Lab Samples: 92778486001, 92778486002, 92778486007, 92778486008, 92778486009

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	02/08/25 13:01	

LABORATORY CONTROL SAMPLE: 4702383

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	251	252	101	90-110	

SAMPLE DUPLICATE: 4702384

Parameter	Units	92778494001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	386	380	2	25	

SAMPLE DUPLICATE: 4702385

Parameter	Units	92778486002 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	483	482	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch:	915152	Analysis Method:	SM 2540C-2015
QC Batch Method:	SM 2540C-2015	Analysis Description:	2540C Total Dissolved Solids
		Laboratory:	Pace Analytical Services - Asheville

Associated Lab Samples: 92778486003, 92778486004, 92778486005, 92778486006, 92778486010, 92778486011, 92778486012

METHOD BLANK: 4703776 Matrix: Water

Associated Lab Samples: 92778486003, 92778486004, 92778486005, 92778486006, 92778486010, 92778486011, 92778486012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	02/11/25 12:03	

LABORATORY CONTROL SAMPLE: 4703777

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	250	246	98	90-110	

SAMPLE DUPLICATE: 4703778

Parameter	Units	92778266001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	124	114	8	25	

SAMPLE DUPLICATE: 4703779

Parameter	Units	92778486005 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	400	400	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch: 914751 Analysis Method: SM 4500-S2D-2011
QC Batch Method: SM 4500-S2D-2011 Analysis Description: 4500S2D Sulfide Water
Laboratory: Pace Analytical Services - Asheville
Associated Lab Samples: 92778486001, 92778486002, 92778486007, 92778486008

METHOD BLANK: 4702232 Matrix: Water
Associated Lab Samples: 92778486001, 92778486002, 92778486007, 92778486008

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	02/08/25 03:36	

LABORATORY CONTROL SAMPLE: 4702233

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.51	103	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4702234 4702235

Parameter	Units	92778050001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.51	0.54	101	108	80-120	6	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4702236 4702237

Parameter	Units	92778494009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.46	0.47	93	93	80-120	0	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch:	914753	Analysis Method:	SM 4500-S2D-2011
QC Batch Method:	SM 4500-S2D-2011	Analysis Description:	4500S2D Sulfide Water
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92778486003, 92778486004, 92778486005, 92778486006, 92778486009, 92778486010, 92778486011, 92778486012		

METHOD BLANK:	4702242	Matrix:	Water
Associated Lab Samples:	92778486003, 92778486004, 92778486005, 92778486006, 92778486009, 92778486010, 92778486011, 92778486012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	02/08/25 03:49	

LABORATORY CONTROL SAMPLE: 4702243						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.52	103	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4702244 4702245												
Parameter	Units	92778486009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.51	0.48	102	95	80-120	7	10	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4702246 4702247												
Parameter	Units	92777989003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfide	mg/L	ND	0.5	0.5	0.51	0.55	101	110	80-120	9	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203
Pace Project No.: 92778486

QC Batch:	914792	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville

Associated Lab Samples: 92778486001

METHOD BLANK: 4702337 Matrix: Water
Associated Lab Samples: 92778486001

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	02/08/25 21:17	
Fluoride	mg/L	ND	0.10	0.050	02/08/25 21:17	
Sulfate	mg/L	ND	1.0	0.50	02/08/25 21:17	

LABORATORY CONTROL SAMPLE: 4702338

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	51.4	103	90-110	
Fluoride	mg/L	2.5	2.6	104	90-110	
Sulfate	mg/L	50	52.2	104	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4702339 4702340

Parameter	Units	92778538006 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	28.7	50	50	79.0	78.0	101	99	90-110	1	10	
Fluoride	mg/L	0.055J	2.5	2.5	2.7	2.6	105	103	90-110	1	10	
Sulfate	mg/L	110	50	50	150	149	80	78	90-110	1	10 M1	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4702341 4702342

Parameter	Units	92778538016 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	1.4	50	50	50.5	52.0	98	101	90-110	3	10	
Fluoride	mg/L	0.073J	2.5	2.5	2.6	2.7	101	104	90-110	3	10	
Sulfate	mg/L	11.6	50	50	61.1	62.5	99	102	90-110	2	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch:	914829	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92778486002, 92778486003, 92778486004, 92778486005, 92778486006, 92778486007, 92778486008, 92778486009, 92778486010, 92778486011, 92778486012		

METHOD BLANK:	4702454	Matrix:	Water
Associated Lab Samples:	92778486002, 92778486003, 92778486004, 92778486005, 92778486006, 92778486007, 92778486008, 92778486009, 92778486010, 92778486011, 92778486012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	02/08/25 15:27	
Fluoride	mg/L	ND	0.10	0.050	02/08/25 15:27	
Sulfate	mg/L	ND	1.0	0.50	02/08/25 15:27	

LABORATORY CONTROL SAMPLE:		4702455				
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	51.0	102	90-110	
Fluoride	mg/L	2.5	2.7	108	90-110	
Sulfate	mg/L	50	51.2	102	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:		4702456		4702457								
Parameter	Units	92778486002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	19.6	50	50	68.9	70.0	99	101	90-110	2	10	
Fluoride	mg/L	0.18	2.5	2.5	2.7	2.7	100	102	90-110	2	10	
Sulfate	mg/L	170	50	50	209	209	77	78	90-110	0	10 M1	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:		4702458		4702459								
Parameter	Units	92778486009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	17.4	50	50	66.9	66.1	99	97	90-110	1	10	
Fluoride	mg/L	0.32	2.5	2.5	2.8	2.8	100	98	90-110	2	10	
Sulfate	mg/L	173	50	50	213	211	81	77	90-110	1	10 M1	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

QC Batch:	923197	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3005A	Analysis Description:	WC 6020B MET
		Laboratory:	Pace Analytical Services - West Columbia
Associated Lab Samples:	92778486001, 92778486002, 92778486003, 92778486004, 92778486005, 92778486006, 92778486007, 92778486008, 92778486009, 92778486010, 92778486011, 92778486012		

METHOD BLANK: 4743181

Matrix: Water

Associated Lab Samples: 92778486001, 92778486002, 92778486003, 92778486004, 92778486005, 92778486006, 92778486007, 92778486008, 92778486009, 92778486010, 92778486011, 92778486012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00050	03/20/25 12:33	
Arsenic	mg/L	ND	0.0050	0.0012	03/20/25 12:33	
Barium	mg/L	ND	0.0050	0.0012	03/20/25 12:33	
Beryllium	mg/L	ND	0.00050	0.00015	03/20/25 12:33	
Boron	mg/L	ND	0.040	0.0062	03/20/25 16:02	
Cadmium	mg/L	ND	0.00050	0.00012	03/20/25 12:33	
Calcium	mg/L	ND	1.0	0.10	03/20/25 12:33	
Chromium	mg/L	ND	0.0050	0.0012	03/20/25 12:33	
Cobalt	mg/L	ND	0.0050	0.0012	03/20/25 12:33	
Iron	mg/L	ND	0.040	0.012	03/20/25 12:33	
Lead	mg/L	ND	0.0010	0.00025	03/20/25 12:33	
Magnesium	mg/L	ND	0.050	0.010	03/20/25 12:33	
Manganese	mg/L	ND	0.040	0.0012	03/20/25 12:33	
Molybdenum	mg/L	ND	0.010	0.0025	03/20/25 12:33	
Potassium	mg/L	ND	0.50	0.10	03/20/25 12:33	
Selenium	mg/L	ND	0.0050	0.0012	03/20/25 12:33	
Sodium	mg/L	ND	1.0	0.15	03/20/25 12:33	
Thallium	mg/L	ND	0.0010	0.00015	03/20/25 12:33	

LABORATORY CONTROL SAMPLE: 4743182

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.093	93	80-120	
Arsenic	mg/L	0.1	0.097	97	80-120	
Barium	mg/L	0.1	0.094	94	80-120	
Beryllium	mg/L	0.1	0.096	96	80-120	
Boron	mg/L	0.1	0.095	95	80-120	
Cadmium	mg/L	0.1	0.095	95	80-120	
Calcium	mg/L	1	0.99J	99	80-120	
Chromium	mg/L	0.1	0.098	98	80-120	
Cobalt	mg/L	0.1	0.10	103	80-120	
Iron	mg/L	1	0.99	99	80-120	
Lead	mg/L	0.1	0.10	102	80-120	
Magnesium	mg/L	1	0.97	97	80-120	
Manganese	mg/L	0.1	0.096	96	80-120	
Molybdenum	mg/L	0.1	0.095	95	80-120	
Potassium	mg/L	1	1.0	103	80-120	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

LABORATORY CONTROL SAMPLE: 4743182

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Selenium	mg/L	0.1	0.096	96	80-120	
Sodium	mg/L	1	1.0	104	80-120	
Thallium	mg/L	0.1	0.099	99	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4743183 4743184

Parameter	Units	92778486012	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		Result	Conc.	Conc.	Result	Result	% Rec	% Rec				
Antimony	mg/L	ND	0.1	0.1	0.096	0.095	96	95	75-125	1	20	
Arsenic	mg/L	0.26	0.1	0.1	0.34	0.34	82	81	75-125	0	20	
Barium	mg/L	0.043	0.1	0.1	0.14	0.14	96	96	75-125	1	20	
Beryllium	mg/L	ND	0.1	0.1	0.092	0.092	92	92	75-125	1	20	
Boron	mg/L	0.77	0.1	0.1	0.88	0.87	103	94	75-125	1	20	
Cadmium	mg/L	ND	0.1	0.1	0.096	0.096	96	96	75-125	0	20	
Calcium	mg/L	115	1	1	117	117	195	232	75-125	0	20	M1
Chromium	mg/L	ND	0.1	0.1	0.098	0.098	98	98	75-125	0	20	
Cobalt	mg/L	0.019	0.1	0.1	0.10	0.10	84	83	75-125	1	20	
Iron	mg/L	11.3	1	1	12.3	12.0	100	67	75-125	3	20	M1
Lead	mg/L	ND	0.1	0.1	0.098	0.098	98	98	75-125	0	20	
Magnesium	mg/L	16.7	1	1	17.4	17.5	68	80	75-125	1	20	M1
Manganese	mg/L	2.8	0.1	0.1	2.9	2.9	106	117	75-125	0	20	
Molybdenum	mg/L	0.015	0.1	0.1	0.11	0.11	96	96	75-125	0	20	
Potassium	mg/L	5.5	1	1	6.6	6.5	106	100	75-125	1	20	
Selenium	mg/L	ND	0.1	0.1	0.081	0.081	81	81	75-125	0	20	
Sodium	mg/L	8.8	1	1	9.7	9.7	92	91	75-125	0	20	
Thallium	mg/L	ND	0.1	0.1	0.095	0.095	95	95	75-125	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1-CA-20250203
Pace Project No.: 92778486

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

J Analyte detected below the reporting limit, therefore result is an estimate. This qualifier is also used for all TICs.
M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92778486001	HAM-PT-07	3015	2464154	EPA 6020B	2464154
92778486002	HAM-PT-08	3015	2464154	EPA 6020B	2464154
92778486003	HAM-PT-09	3015	2464154	EPA 6020B	2464154
92778486004	HAM-PT-10	3015	2464154	EPA 6020B	2464154
92778486005	HAM-PT-11	3015	2464154	EPA 6020B	2464154
92778486006	HAM-PT-12	3015	2464154	EPA 6020B	2464154
92778486007	HAM-PT-13	3015	2464154	EPA 6020B	2464154
92778486008	HAM-PT-14	3015	2464154	EPA 6020B	2464154
92778486009	HAM-PT-15	3015	2464154	EPA 6020B	2464154
92778486010	HAM-AP1-EB-01	3015	2464154	EPA 6020B	2464154
92778486011	HAM-AP1-FB-01	3015	2464154	EPA 6020B	2464154
92778486012	HAM-AP1-FD-01	3015	2464154	EPA 6020B	2464154
92778486001	HAM-PT-07	EPA 7470A	914889	EPA 7470A	915003
92778486002	HAM-PT-08	EPA 7470A	914889	EPA 7470A	915003
92778486003	HAM-PT-09	EPA 7470A	914889	EPA 7470A	915003
92778486004	HAM-PT-10	EPA 7470A	914889	EPA 7470A	915003
92778486005	HAM-PT-11	EPA 7470A	914889	EPA 7470A	915003
92778486006	HAM-PT-12	EPA 7470A	914889	EPA 7470A	915003
92778486007	HAM-PT-13	EPA 7470A	914889	EPA 7470A	915003
92778486008	HAM-PT-14	EPA 7470A	914889	EPA 7470A	915003
92778486009	HAM-PT-15	EPA 7470A	914889	EPA 7470A	915003
92778486010	HAM-AP1-EB-01	EPA 7470A	914965	EPA 7470A	915313
92778486011	HAM-AP1-FB-01	EPA 7470A	914965	EPA 7470A	915313
92778486012	HAM-AP1-FD-01	EPA 7470A	914965	EPA 7470A	915313
92778486001	HAM-PT-07	SM 2320B-2011	915023		
92778486002	HAM-PT-08	SM 2320B-2011	915023		
92778486003	HAM-PT-09	SM 2320B-2011	915650		
92778486004	HAM-PT-10	SM 2320B-2011	915650		
92778486005	HAM-PT-11	SM 2320B-2011	915650		
92778486006	HAM-PT-12	SM 2320B-2011	915650		
92778486007	HAM-PT-13	SM 2320B-2011	915023		
92778486008	HAM-PT-14	SM 2320B-2011	915023		
92778486009	HAM-PT-15	SM 2320B-2011	915023		
92778486010	HAM-AP1-EB-01	SM 2320B-2011	915650		
92778486011	HAM-AP1-FB-01	SM 2320B-2011	915650		
92778486012	HAM-AP1-FD-01	SM 2320B-2011	915650		
92778486001	HAM-PT-07	SM 2540C-2015	914807		
92778486002	HAM-PT-08	SM 2540C-2015	914807		
92778486003	HAM-PT-09	SM 2540C-2015	915152		
92778486004	HAM-PT-10	SM 2540C-2015	915152		
92778486005	HAM-PT-11	SM 2540C-2015	915152		
92778486006	HAM-PT-12	SM 2540C-2015	915152		
92778486007	HAM-PT-13	SM 2540C-2015	914807		
92778486008	HAM-PT-14	SM 2540C-2015	914807		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1-CA-20250203

Pace Project No.: 92778486

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92778486009	HAM-PT-15	SM 2540C-2015	914807		
92778486010	HAM-AP1-EB-01	SM 2540C-2015	915152		
92778486011	HAM-AP1-FB-01	SM 2540C-2015	915152		
92778486012	HAM-AP1-FD-01	SM 2540C-2015	915152		
92778486001	HAM-PT-07	SM 4500-S2D-2011	914751		
92778486002	HAM-PT-08	SM 4500-S2D-2011	914751		
92778486003	HAM-PT-09	SM 4500-S2D-2011	914753		
92778486004	HAM-PT-10	SM 4500-S2D-2011	914753		
92778486005	HAM-PT-11	SM 4500-S2D-2011	914753		
92778486006	HAM-PT-12	SM 4500-S2D-2011	914753		
92778486007	HAM-PT-13	SM 4500-S2D-2011	914751		
92778486008	HAM-PT-14	SM 4500-S2D-2011	914751		
92778486009	HAM-PT-15	SM 4500-S2D-2011	914753		
92778486010	HAM-AP1-EB-01	SM 4500-S2D-2011	914753		
92778486011	HAM-AP1-FB-01	SM 4500-S2D-2011	914753		
92778486012	HAM-AP1-FD-01	SM 4500-S2D-2011	914753		
92778486001	HAM-PT-07	EPA 300.0 Rev 2.1 1993	914792		
92778486002	HAM-PT-08	EPA 300.0 Rev 2.1 1993	914829		
92778486003	HAM-PT-09	EPA 300.0 Rev 2.1 1993	914829		
92778486004	HAM-PT-10	EPA 300.0 Rev 2.1 1993	914829		
92778486005	HAM-PT-11	EPA 300.0 Rev 2.1 1993	914829		
92778486006	HAM-PT-12	EPA 300.0 Rev 2.1 1993	914829		
92778486007	HAM-PT-13	EPA 300.0 Rev 2.1 1993	914829		
92778486008	HAM-PT-14	EPA 300.0 Rev 2.1 1993	914829		
92778486009	HAM-PT-15	EPA 300.0 Rev 2.1 1993	914829		
92778486010	HAM-AP1-EB-01	EPA 300.0 Rev 2.1 1993	914829		
92778486011	HAM-AP1-FB-01	EPA 300.0 Rev 2.1 1993	914829		
92778486012	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	914829		
92778486001	HAM-PT-07	EPA 3005A	923197	EPA 6020B	923913
92778486002	HAM-PT-08	EPA 3005A	923197	EPA 6020B	923913
92778486003	HAM-PT-09	EPA 3005A	923197	EPA 6020B	923913
92778486004	HAM-PT-10	EPA 3005A	923197	EPA 6020B	923913
92778486005	HAM-PT-11	EPA 3005A	923197	EPA 6020B	923913
92778486006	HAM-PT-12	EPA 3005A	923197	EPA 6020B	923913
92778486007	HAM-PT-13	EPA 3005A	923197	EPA 6020B	923913
92778486008	HAM-PT-14	EPA 3005A	923197	EPA 6020B	923913
92778486009	HAM-PT-15	EPA 3005A	923197	EPA 6020B	923913
92778486010	HAM-AP1-EB-01	EPA 3005A	923197	EPA 6020B	923913
92778486011	HAM-AP1-FB-01	EPA 3005A	923197	EPA 6020B	923913
92778486012	HAM-AP1-FD-01	EPA 3005A	923197	EPA 6020B	923913

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Effective Date: 05/24/2024

Laboratory receiving samples:

heville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☒ Kernersville ☐

Sample Condition
Upon Receipt

Client Name:

Project #

WO#: 92778486



Carrier:

Commercial

☐ Fed Ex

☐ Pace

☐ UPS

☐ USPS

☐ Other:

☐ Client

Body Seal Present?

☒ Yes

☐ No

Seals Intact?

☒ Yes

☐ No

☐ N/A

Date/Initials Person Examining Contents: 2/17/25 M.

Shipping Material:

☒ Bubble Wrap

☐ Bubble Bags

☐ None

☐ Other

Thermometer:

☒ IR Gun ID:

230

Type of Ice:

☒ Wet

☐ Blue

☐ None

Order Temp:

3.1

Correction Factor:

Add/Subtract (°C) 0.1

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Order Temp Corrected (°C):

3.2

DA Regulated Soil (☐ N/A, water sample)

Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ No

Did samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

		Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.
Samples Arrived within Hold Time?	☒ Yes ☐ No ☐ N/A	2.
Short Hold Time Analysis (<72 hr.)?	☒ Yes ☐ No ☐ N/A	3.
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4.
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A	7.
Containers Intact?	☒ Yes ☐ No ☐ N/A	8.
Dissolved analysis: Samples Field Filtered?	1/17/25 ☒ Yes ☐ No ☐ N/A	9.
Sample Labels Match COC?	SA ☒ Yes ☐ No ☐ N/A	
-Includes Date/Time/ID/Analysis Matrix:	W	
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10.
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A	

Field Data Required? ☐ Yes ☐ No

Comments/SAMPLE DISCREPANCY

Lot ID of split containers:

Notification/RESOLUTION

Person contacted:

Date/Time:

Project Manager SCURF Review:

Date:

Project Manager SRF Review:

Date:

altrax ID: 69614



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

W0#: 92778486

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Project #

PM: BV

Due Date: 02/24/25

CLIENT: 92- GP-HAM

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐

Client _____ Profile/EZ (Circle one) _____ Notes _____

Item#	CC	1	2	3	4	5	6	7	8	9	10	11	12	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic ZN Acetate & NaOH (pH > 12) (Cl-)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WG6U-Wide-mouthed Glass Jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG9A-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2S2O3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)	BP3R-250 mL Plastic (NH4)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	VSGU-20 mL Scintillation vials (N/A)	DG3U-40 mL Amber Unpreserved vials (N/A)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						</

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers.

Important Note: By signing this form you are accepting Pace's NET 30 day payment terms and agreeing to late charges of 1.5% per month for any invoices not paid within 30 days.



April 23, 2025

Kristen Jurinko
Southern Company
241 Ralph McGill Blvd NE
Bin 10160
Atlanta, GA 30308

RE: Project: Hammond AP-1
Pace Project No.: 92789136

Dear Kristen Jurinko:

Enclosed are the analytical results for sample(s) received by the laboratory on April 04, 2025. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace National - Mt. Juliet
- Pace Analytical Services - Asheville
- Pace Analytical Services - West Columbia

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Bonnie Vang
bonnie.vang@pacelabs.com
704-977-0968
Project Manager

Enclosures

cc: Kip Gray, Geosyntec
Christine Hug, Geosyntec Consultants, Inc.
Thomas Kessler, Geosyntec Consultants
Whitney Law, Geosyntec Consultants
Laura Midkiff, Southern Company
Caroline Nelson, Geosyntec Consultants, Inc
Jamie Newsome, Geosyntec Consultants
Zain Webb, Geosyntec Consultants



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



CERTIFICATIONS

Project: Hammond AP-1
Pace Project No.: 92789136

Pace Analytical Services National

12065 Lebanon Road, Mt. Juliet, TN 37122
Alabama Certification #: 40660
Alaska Certification #: 17-026
Arizona Certification #: AZ0612
Arkansas Certification #: 88-0469
California Certification #: 2932
Canada Certification #: 1461.01
Colorado Certification #: TN00003
Connecticut Certification #: PH-0197
DOD Certification #: 1461.01
EPA# TN00003
Florida Certification #: E87487
Georgia DW Certification #: 923
Georgia Certification: NELAP
Idaho Certification #: TN00003
Illinois Certification #: 200008
Indiana Certification #: C-TN-01
Iowa Certification #: 364
Kansas Certification #: E-10277
Kentucky UST Certification #: 16
Kentucky Certification #: 90010
Louisiana Certification #: AI30792
Louisiana DW Certification #: LA180010
Maine Certification #: TN0002
Maryland Certification #: 324
Massachusetts Certification #: M-TN003
Michigan Certification #: 9958
Minnesota Certification #: 047-999-395
Mississippi Certification #: TN00003
Missouri Certification #: 340
Montana Certification #: CERT0086
Nebraska Certification #: NE-OS-15-05

Nevada Certification #: TN-03-2002-34
New Hampshire Certification #: 2975
New Jersey Certification #: TN002
New Mexico DW Certification
New York Certification #: 11742
North Carolina Aquatic Toxicity Certification #: 41
North Carolina Drinking Water Certification #: 21704
North Carolina Environmental Certificate #: 375
North Dakota Certification #: R-140
Ohio VAP Certification #: CL0069
Oklahoma Certification #: 9915
Oregon Certification #: TN200002
Pennsylvania Certification #: 68-02979
Rhode Island Certification #: LA000356
South Carolina Certification #: 84004
South Dakota Certification
Tennessee DW/Chem/Micro Certification #: 2006
Texas Mold Certification #: LAB0152
Texas Certification #: T 104704245-17-14
USDA Soil Permit #: P330-15-00234
Utah Certification #: TN00003
Virginia Certification #: VT2006
Vermont Dept. of Health: ID# VT-2006
Virginia Certification #: 460132
Washington Certification #: C847
West Virginia Certification #: 233
Wisconsin Certification #: 998093910
Wyoming UST Certification #: via A2LA 2926.01
A2LA-ISO 17025 Certification #: 1461.01
A2LA-ISO 17025 Certification #: 1461.02
AIHA-LAP/LLC EMLAP Certification #: 100789

Pace Analytical Services Asheville

2225 Riverside Drive, Asheville, NC 28804
Florida/NELAP Certification #: E87648
North Carolina Drinking Water Certification #: 37712
North Carolina Wastewater Certification #: 40

South Carolina Laboratory ID: 99030
South Carolina Certification #: 99030001
Virginia/VELAP Certification #: 460222

Pace Analytical Services West Columbia

106 Vantage Point Drive, West Columbia, SC 29172
Alaska Dept. of Energy Conservation, Cert# 20-002
California ELAP, cert# 3049
DoD, DoD QSM V5.4, cert# I.2224
DOE, DoD/DOE QSM V5.4, cert# I.2224.01
Florida, Dept. of Health, cert# E87653-70
Georgia, Env. Protection Division, cert# E87653
Illinois, EPA NELAP, cert# 2000552024-9
Kansas, Dept. of Health and Environment, cert# E-10417
Kentucky, Dept. for Env. Protection, UST, cert# 103582
Kentucky, Dept. for Env. Protection, cert# 98037

Louisiana, Dept. of Environmental Quality, cert# 5125
North Carolina, DEQ, Water Resources, cert# 329
New Jersey, Dept. of Env. Protection, cert# NLC 240005
Oklahoma, Dept. of Env. Quality, cert# 2023-175
Oregon, ELAP, cert# 4181-006
Pennsylvania, Dept. of Env. Protection, cert# 003
South Carolina, Dept. of Env. Services, cert# 32010001
Texas, Commission on Env. Quality, cert# TX-C24-00083
Virginia, Dept. of General Services, cert# 13080
Wisconsin, Dept. of Natural Resources, cert# 399136100

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE SUMMARY

Project: Hammond AP-1

Pace Project No.: 92789136

Lab ID	Sample ID	Matrix	Date Collected	Date Received
92789136001	HAM-PT-07	Water	04/03/25 09:20	04/04/25 14:25
92789136002	HAM-PT-08	Water	04/02/25 16:52	04/04/25 14:25
92789136003	HAM-PT-09	Water	04/03/25 13:57	04/04/25 14:25
92789136004	HAM-PT-10	Water	04/03/25 12:39	04/04/25 14:25
92789136005	HAM-PT-11	Water	04/03/25 12:30	04/04/25 14:25
92789136006	HAM-PT-12	Water	04/03/25 14:23	04/04/25 14:25
92789136007	HAM-PT-13	Water	04/02/25 17:18	04/04/25 14:25
92789136008	HAM-PT-14	Water	04/02/25 13:49	04/04/25 14:25
92789136009	HAM-PT-15	Water	04/02/25 13:04	04/04/25 14:25
92789136010	HAM-AP1-EB-01	Water	04/02/25 18:00	04/04/25 14:25
92789136011	HAM-AP1-FB-01	Water	04/02/25 17:50	04/04/25 14:25
92789136012	HAM-AP1-FD-01	Water	04/02/25 00:00	04/04/25 14:25

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92789136

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
92789136001	HAM-PT-07	EPA 6020B	SJM	1	PAN
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	CDM	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BW	18	PASI-WC
		EPA 7470A	KJW	1	PASI-WC
92789136002	HAM-PT-08	EPA 6020B	SJM	1	PAN
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BW	18	PASI-WC
		EPA 7470A	KJW	1	PASI-WC
92789136003	HAM-PT-09	EPA 6020B	SJM	1	PAN
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	CDM	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BW	18	PASI-WC
		EPA 7470A	KJW	1	PASI-WC
92789136004	HAM-PT-10	EPA 6020B	SJM	1	PAN
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	CDM	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BW	18	PASI-WC
		EPA 7470A	KJW	1	PASI-WC
92789136005	HAM-PT-11	EPA 6020B	SJM	1	PAN
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	CDM	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BW	18	PASI-WC
		EPA 7470A	KJW	1	PASI-WC
92789136006	HAM-PT-12	EPA 6020B	SJM	1	PAN
		SM 2320B-2011	SMS	3	PASI-A

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92789136

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
92789136007	HAM-PT-13	SM 2540C-2015	NSS	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BW	18	PASI-WC
		EPA 7470A	KJW	1	PASI-WC
		EPA 6020B	SJM	1	PAN
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
92789136008	HAM-PT-14	EPA 6020B	BW	18	PASI-WC
		EPA 7470A	KJW	1	PASI-WC
		EPA 6020B	SJM	1	PAN
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BW	18	PASI-WC
		EPA 7470A	KJW	1	PASI-WC
		EPA 6020B	SJM	1	PAN
92789136009	HAM-PT-15	SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BW	18	PASI-WC
		EPA 7470A	KJW	1	PASI-WC
		EPA 6020B	SJM	1	PAN
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
92789136010	HAM-AP1-EB-01	EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BW	18	PASI-WC
		EPA 7470A	KJW	1	PASI-WC
		EPA 6020B	SJM	1	PAN
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BW	18	PASI-WC
		EPA 7470A	KJW	1	PASI-WC
92789136011	HAM-AP1-FB-01	EPA 6020B	SJM	1	PAN
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: Hammond AP-1

Pace Project No.: 92789136

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
92789136012	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BW	18	PASI-WC
		EPA 7470A	KJW	1	PASI-WC
		EPA 6020B	SJM	1	PAN
		SM 2320B-2011	SMS	3	PASI-A
		SM 2540C-2015	YEG	1	PASI-A
		SM 4500-S2D-2011	JP1	1	PASI-A
		EPA 300.0 Rev 2.1 1993	JCM	3	PASI-A
		EPA 6020B	BW	18	PASI-WC
		EPA 7470A	KJW	1	PASI-WC

PAN = Pace National - Mt. Juliet

PASI-A = Pace Analytical Services - Asheville

PASI-WC = Pace Analytical Services - West Columbia

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92789136

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92789136001	HAM-PT-07					
EPA 6020B	Lithium	0.0408	mg/L	0.0300	04/15/25 12:00	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	169	mg/L	5.0	04/08/25 19:19	
SM 2320B-2011	Alkalinity, Total as CaCO3	169	mg/L	5.0	04/08/25 19:19	
SM 2540C-2015	Total Dissolved Solids	512	mg/L	25.0	04/09/25 14:47	
EPA 300.0 Rev 2.1 1993	Chloride	16.6	mg/L	1.0	04/05/25 15:56	
EPA 300.0 Rev 2.1 1993	Fluoride	0.34	mg/L	0.10	04/05/25 15:56	
EPA 300.0 Rev 2.1 1993	Sulfate	159	mg/L	4.0	04/06/25 03:22	
EPA 6020B	Arsenic	0.23	mg/L	0.0050	04/14/25 19:34	
EPA 6020B	Barium	0.044	mg/L	0.0050	04/14/25 19:34	
EPA 6020B	Boron	0.80	mg/L	0.40	04/15/25 15:15	
EPA 6020B	Calcium	116	mg/L	10.0	04/15/25 15:15	
EPA 6020B	Cobalt	0.034	mg/L	0.0050	04/14/25 19:34	
EPA 6020B	Iron	7.6	mg/L	0.040	04/14/25 19:34	
EPA 6020B	Magnesium	14.4	mg/L	0.050	04/14/25 19:34	
EPA 6020B	Manganese	3.0	mg/L	1.0	04/21/25 15:38	
EPA 6020B	Molybdenum	0.011	mg/L	0.010	04/14/25 19:34	
EPA 6020B	Potassium	5.4	mg/L	0.50	04/14/25 19:34	
EPA 6020B	Sodium	7.6	mg/L	1.0	04/14/25 19:34	
EPA 6020B	Thallium	0.00028J	mg/L	0.0010	04/14/25 19:34	
92789136002	HAM-PT-08					
EPA 6020B	Lithium	0.0129J	mg/L	0.0300	04/15/25 12:03	J
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	124	mg/L	5.0	04/08/25 16:26	
SM 2320B-2011	Alkalinity, Total as CaCO3	124	mg/L	5.0	04/08/25 16:26	
SM 2540C-2015	Total Dissolved Solids	491	mg/L	25.0	04/08/25 11:57	
EPA 300.0 Rev 2.1 1993	Chloride	18.8	mg/L	1.0	04/05/25 16:09	
EPA 300.0 Rev 2.1 1993	Fluoride	0.19	mg/L	0.10	04/05/25 16:09	
EPA 300.0 Rev 2.1 1993	Sulfate	175	mg/L	4.0	04/06/25 03:36	
EPA 6020B	Arsenic	0.027	mg/L	0.0050	04/14/25 19:44	
EPA 6020B	Barium	0.045	mg/L	0.0050	04/14/25 19:44	
EPA 6020B	Boron	1.0	mg/L	0.40	04/15/25 15:24	
EPA 6020B	Calcium	119	mg/L	10.0	04/15/25 15:24	
EPA 6020B	Cobalt	0.024	mg/L	0.0050	04/14/25 19:44	
EPA 6020B	Iron	0.37	mg/L	0.040	04/14/25 19:44	
EPA 6020B	Magnesium	12.5	mg/L	0.050	04/14/25 19:44	
EPA 6020B	Manganese	2.0	mg/L	0.40	04/15/25 15:24	
EPA 6020B	Molybdenum	0.012	mg/L	0.010	04/14/25 19:44	
EPA 6020B	Potassium	4.9	mg/L	0.50	04/14/25 19:44	
EPA 6020B	Sodium	6.3	mg/L	1.0	04/14/25 19:44	
EPA 6020B	Thallium	0.00025J	mg/L	0.0010	04/14/25 19:44	
92789136003	HAM-PT-09					
EPA 6020B	Lithium	0.00124J	mg/L	0.0300	04/15/25 12:40	J
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	126	mg/L	5.0	04/08/25 19:38	
SM 2320B-2011	Alkalinity, Total as CaCO3	126	mg/L	5.0	04/08/25 19:38	
SM 2540C-2015	Total Dissolved Solids	516	mg/L	25.0	04/09/25 14:47	
EPA 300.0 Rev 2.1 1993	Chloride	56.9	mg/L	1.0	04/05/25 16:22	
EPA 300.0 Rev 2.1 1993	Fluoride	0.30	mg/L	0.10	04/05/25 16:22	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92789136

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92789136003	HAM-PT-09					
EPA 300.0 Rev 2.1 1993	Sulfate	122	mg/L	3.0	04/06/25 03:51	
EPA 6020B	Barium	0.064	mg/L	0.0050	04/14/25 19:53	
EPA 6020B	Boron	1.8	mg/L	0.40	04/15/25 15:33	
EPA 6020B	Calcium	102	mg/L	10.0	04/15/25 15:33	
EPA 6020B	Cobalt	0.0015J	mg/L	0.0050	04/14/25 19:53	
EPA 6020B	Iron	0.061	mg/L	0.040	04/14/25 19:53	
EPA 6020B	Magnesium	17.1	mg/L	0.050	04/14/25 19:53	
EPA 6020B	Manganese	0.36J	mg/L	0.40	04/15/25 15:33	
EPA 6020B	Molybdenum	0.16	mg/L	0.010	04/14/25 19:53	
EPA 6020B	Potassium	6.3	mg/L	0.50	04/14/25 19:53	
EPA 6020B	Sodium	12.1	mg/L	1.0	04/14/25 19:53	
EPA 6020B	Thallium	0.00017J	mg/L	0.0010	04/14/25 19:53	
92789136004	HAM-PT-10					
EPA 6020B	Lithium	0.00160J	mg/L	0.0300	04/15/25 12:44	J
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	134	mg/L	5.0	04/08/25 19:47	
SM 2320B-2011	Alkalinity, Total as CaCO3	134	mg/L	5.0	04/08/25 19:47	
SM 2540C-2015	Total Dissolved Solids	532	mg/L	25.0	04/09/25 14:47	
EPA 300.0 Rev 2.1 1993	Chloride	54.3	mg/L	1.0	04/05/25 16:34	
EPA 300.0 Rev 2.1 1993	Fluoride	0.15	mg/L	0.10	04/05/25 16:34	
EPA 300.0 Rev 2.1 1993	Sulfate	138	mg/L	3.0	04/06/25 04:05	
EPA 6020B	Barium	0.056	mg/L	0.0050	04/14/25 20:02	
EPA 6020B	Boron	1.7	mg/L	0.40	04/15/25 15:43	
EPA 6020B	Calcium	124	mg/L	10.0	04/15/25 15:43	
EPA 6020B	Iron	0.18	mg/L	0.040	04/14/25 20:02	
EPA 6020B	Magnesium	12.3	mg/L	0.050	04/14/25 20:02	
EPA 6020B	Manganese	0.71	mg/L	0.40	04/15/25 15:43	
EPA 6020B	Molybdenum	0.040	mg/L	0.010	04/14/25 20:02	
EPA 6020B	Potassium	6.8	mg/L	0.50	04/14/25 20:02	
EPA 6020B	Sodium	9.1	mg/L	1.0	04/14/25 20:02	
92789136005	HAM-PT-11					
EPA 6020B	Lithium	0.00125J	mg/L	0.0300	04/15/25 12:47	J
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	121	mg/L	5.0	04/08/25 19:56	
SM 2320B-2011	Alkalinity, Total as CaCO3	121	mg/L	5.0	04/08/25 19:56	
SM 2540C-2015	Total Dissolved Solids	460	mg/L	25.0	04/09/25 14:47	
EPA 300.0 Rev 2.1 1993	Chloride	39.0	mg/L	1.0	04/05/25 16:47	
EPA 300.0 Rev 2.1 1993	Fluoride	0.28	mg/L	0.10	04/05/25 16:47	
EPA 300.0 Rev 2.1 1993	Sulfate	105	mg/L	4.0	04/06/25 04:19	M1
EPA 6020B	Barium	0.063	mg/L	0.0050	04/14/25 20:11	
EPA 6020B	Boron	1.5	mg/L	0.40	04/15/25 16:11	
EPA 6020B	Calcium	97.3	mg/L	10.0	04/15/25 16:11	
EPA 6020B	Cobalt	0.0014J	mg/L	0.0050	04/14/25 20:11	
EPA 6020B	Iron	0.48	mg/L	0.040	04/14/25 20:11	
EPA 6020B	Magnesium	15.0	mg/L	0.050	04/14/25 20:11	
EPA 6020B	Manganese	0.35J	mg/L	0.40	04/15/25 16:11	
EPA 6020B	Molybdenum	0.12	mg/L	0.010	04/14/25 20:11	
EPA 6020B	Potassium	5.9	mg/L	0.50	04/14/25 20:11	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92789136

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92789136005	HAM-PT-11					
EPA 6020B	Sodium	8.3	mg/L	1.0	04/14/25 20:11	
92789136006	HAM-PT-12					
EPA 6020B	Lithium	0.00110J	mg/L	0.0300	04/15/25 12:50	J
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO ₃)	115	mg/L	5.0	04/08/25 20:05	
SM 2320B-2011	Alkalinity, Total as CaCO ₃	115	mg/L	5.0	04/08/25 20:05	
SM 2540C-2015	Total Dissolved Solids	431	mg/L	25.0	04/10/25 06:13	
EPA 300.0 Rev 2.1 1993	Chloride	52.4	mg/L	1.0	04/05/25 17:26	
EPA 300.0 Rev 2.1 1993	Fluoride	0.22	mg/L	0.10	04/05/25 17:26	
EPA 300.0 Rev 2.1 1993	Sulfate	115	mg/L	3.0	04/06/25 05:28	
EPA 6020B	Barium	0.054	mg/L	0.0050	04/14/25 20:20	
EPA 6020B	Boron	1.7	mg/L	0.40	04/15/25 16:21	
EPA 6020B	Cadmium	0.00013J	mg/L	0.00050	04/14/25 20:20	
EPA 6020B	Calcium	100	mg/L	10.0	04/15/25 16:21	
EPA 6020B	Cobalt	0.0017J	mg/L	0.0050	04/14/25 20:20	
EPA 6020B	Iron	0.26	mg/L	0.040	04/14/25 20:20	
EPA 6020B	Magnesium	14.9	mg/L	0.050	04/14/25 20:20	
EPA 6020B	Manganese	0.41	mg/L	0.40	04/15/25 16:21	
EPA 6020B	Molybdenum	0.11	mg/L	0.010	04/14/25 20:20	
EPA 6020B	Potassium	6.0	mg/L	0.50	04/14/25 20:20	
EPA 6020B	Sodium	10.2	mg/L	1.0	04/14/25 20:20	
EPA 6020B	Thallium	0.00016J	mg/L	0.0010	04/14/25 20:20	
92789136007	HAM-PT-13					
EPA 6020B	Lithium	0.0423	mg/L	0.0300	04/15/25 12:53	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO ₃)	166	mg/L	5.0	04/08/25 16:35	
SM 2320B-2011	Alkalinity, Total as CaCO ₃	166	mg/L	5.0	04/08/25 16:35	
SM 2540C-2015	Total Dissolved Solids	517	mg/L	25.0	04/08/25 11:57	
EPA 300.0 Rev 2.1 1993	Chloride	18.5	mg/L	1.0	04/05/25 17:39	
EPA 300.0 Rev 2.1 1993	Fluoride	0.36	mg/L	0.10	04/05/25 17:39	
EPA 300.0 Rev 2.1 1993	Sulfate	166	mg/L	4.0	04/06/25 05:42	
EPA 6020B	Arsenic	0.17	mg/L	0.0050	04/10/25 16:16	
EPA 6020B	Barium	0.047	mg/L	0.0050	04/10/25 16:16	
EPA 6020B	Boron	0.84	mg/L	0.20	04/11/25 14:50	
EPA 6020B	Calcium	127	mg/L	50.0	04/11/25 12:45	
EPA 6020B	Cobalt	0.018	mg/L	0.0050	04/10/25 16:16	
EPA 6020B	Iron	5.8	mg/L	0.040	04/10/25 16:16	
EPA 6020B	Magnesium	15.1	mg/L	0.050	04/10/25 16:16	
EPA 6020B	Manganese	3.2	mg/L	2.0	04/11/25 12:45	
EPA 6020B	Molybdenum	0.0079J	mg/L	0.010	04/10/25 16:16	
EPA 6020B	Potassium	5.8	mg/L	0.50	04/10/25 16:16	
EPA 6020B	Sodium	8.2	mg/L	1.0	04/10/25 16:16	
EPA 6020B	Thallium	0.00036J	mg/L	0.0010	04/10/25 16:16	
92789136008	HAM-PT-14					
EPA 6020B	Lithium	0.0470	mg/L	0.0300	04/15/25 12:56	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO ₃)	163	mg/L	5.0	04/08/25 16:46	
SM 2320B-2011	Alkalinity, Total as CaCO ₃	163	mg/L	5.0	04/08/25 16:46	
SM 2540C-2015	Total Dissolved Solids	515	mg/L	25.0	04/08/25 11:57	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92789136

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92789136008	HAM-PT-14					
EPA 300.0 Rev 2.1 1993	Chloride	15.8	mg/L	1.0	04/05/25 17:52	
EPA 300.0 Rev 2.1 1993	Fluoride	0.32	mg/L	0.10	04/05/25 17:52	
EPA 300.0 Rev 2.1 1993	Sulfate	165	mg/L	4.0	04/06/25 05:56	
EPA 6020B	Arsenic	0.42	mg/L	0.25	04/11/25 12:49	
EPA 6020B	Barium	0.042	mg/L	0.0050	04/10/25 16:25	
EPA 6020B	Boron	0.81	mg/L	0.20	04/11/25 14:59	
EPA 6020B	Calcium	111	mg/L	50.0	04/11/25 12:49	
EPA 6020B	Cobalt	0.022	mg/L	0.0050	04/10/25 16:25	
EPA 6020B	Iron	10.7	mg/L	0.040	04/10/25 16:25	
EPA 6020B	Magnesium	14.8	mg/L	0.050	04/10/25 16:25	
EPA 6020B	Manganese	3.3	mg/L	2.0	04/11/25 12:49	
EPA 6020B	Molybdenum	0.010	mg/L	0.010	04/10/25 16:25	
EPA 6020B	Potassium	5.7	mg/L	0.50	04/10/25 16:25	
EPA 6020B	Sodium	7.3	mg/L	1.0	04/10/25 16:25	
EPA 6020B	Thallium	0.00019J	mg/L	0.0010	04/10/25 16:25	
92789136009	HAM-PT-15					
EPA 6020B	Lithium	0.0355	mg/L	0.0300	04/15/25 13:00	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	157	mg/L	5.0	04/08/25 16:57	
SM 2320B-2011	Alkalinity, Total as CaCO3	157	mg/L	5.0	04/08/25 16:57	
SM 2540C-2015	Total Dissolved Solids	511	mg/L	25.0	04/08/25 11:57	
EPA 300.0 Rev 2.1 1993	Chloride	16.9	mg/L	1.0	04/05/25 18:31	
EPA 300.0 Rev 2.1 1993	Fluoride	0.32	mg/L	0.10	04/05/25 18:31	
EPA 300.0 Rev 2.1 1993	Sulfate	170	mg/L	4.0	04/06/25 06:10	
EPA 6020B	Arsenic	0.088	mg/L	0.0050	04/10/25 16:33	
EPA 6020B	Barium	0.051	mg/L	0.0050	04/10/25 16:33	
EPA 6020B	Boron	0.87	mg/L	0.20	04/11/25 15:07	
EPA 6020B	Cadmium	0.00032J	mg/L	0.00050	04/10/25 16:33	
EPA 6020B	Calcium	122	mg/L	50.0	04/11/25 12:53	
EPA 6020B	Cobalt	0.028	mg/L	0.0050	04/10/25 16:33	
EPA 6020B	Iron	1.1	mg/L	0.040	04/10/25 16:33	
EPA 6020B	Magnesium	13.3	mg/L	0.050	04/10/25 16:33	
EPA 6020B	Manganese	4.1	mg/L	2.0	04/11/25 12:53	
EPA 6020B	Molybdenum	0.012	mg/L	0.010	04/10/25 16:33	
EPA 6020B	Potassium	5.5	mg/L	0.50	04/10/25 16:33	
EPA 6020B	Sodium	7.0	mg/L	1.0	04/10/25 16:33	
EPA 6020B	Thallium	0.00062J	mg/L	0.0010	04/10/25 16:33	
92789136011	HAM-AP1-FB-01					
EPA 6020B	Iron	0.026J	mg/L	0.040	04/10/25 16:50	
EPA 6020B	Magnesium	0.042J	mg/L	0.050	04/10/25 16:50	
EPA 6020B	Manganese	0.0066J	mg/L	0.040	04/10/25 16:50	
92789136012	HAM-AP1-FD-01					
EPA 6020B	Lithium	0.0479	mg/L	0.0300	04/15/25 13:09	
SM 2320B-2011	Alkalinity,Bicarbonate (CaCO3)	162	mg/L	5.0	04/08/25 17:15	
SM 2320B-2011	Alkalinity, Total as CaCO3	162	mg/L	5.0	04/08/25 17:15	
SM 2540C-2015	Total Dissolved Solids	515	mg/L	25.0	04/08/25 11:57	
EPA 300.0 Rev 2.1 1993	Chloride	16.1	mg/L	1.0	04/05/25 19:10	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



SUMMARY OF DETECTION

Project: Hammond AP-1

Pace Project No.: 92789136

Lab Sample ID	Client Sample ID					
Method	Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
92789136012	HAM-AP1-FD-01					
EPA 300.0 Rev 2.1 1993	Fluoride	0.34	mg/L	0.10	04/05/25 19:10	
EPA 300.0 Rev 2.1 1993	Sulfate	166	mg/L	4.0	04/06/25 06:24	
EPA 6020B	Arsenic	0.40	mg/L	0.25	04/11/25 12:57	
EPA 6020B	Barium	0.043	mg/L	0.0050	04/10/25 16:58	
EPA 6020B	Boron	0.79	mg/L	0.20	04/11/25 14:42	
EPA 6020B	Calcium	119	mg/L	50.0	04/11/25 12:57	
EPA 6020B	Cobalt	0.023	mg/L	0.0050	04/10/25 16:58	
EPA 6020B	Iron	10.9	mg/L	0.040	04/10/25 16:58	
EPA 6020B	Magnesium	15.0	mg/L	0.050	04/10/25 16:58	
EPA 6020B	Manganese	3.2	mg/L	2.0	04/11/25 12:57	
EPA 6020B	Molybdenum	0.010	mg/L	0.010	04/10/25 16:58	
EPA 6020B	Potassium	5.6	mg/L	0.50	04/10/25 16:58	
EPA 6020B	Sodium	7.4	mg/L	1.0	04/10/25 16:58	
EPA 6020B	Thallium	0.00017J	mg/L	0.0010	04/10/25 16:58	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92789136

Sample: HAM-PT-07		Lab ID: 92789136001		Collected: 04/03/25 09:20		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B									
Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet									
Lithium	0.0408	mg/L	0.0300	0.000600	1	04/15/25 08:24	04/15/25 12:00	7439-93-2	
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	169	mg/L	5.0	5.0	1		04/08/25 19:19		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		04/08/25 19:19		
Alkalinity, Total as CaCO3	169	mg/L	5.0	5.0	1		04/08/25 19:19		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	512	mg/L	25.0	25.0	1		04/09/25 14:47		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		04/09/25 02:52	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	16.6	mg/L	1.0	0.60	1		04/05/25 15:56	16887-00-6	
Fluoride	0.34	mg/L	0.10	0.050	1		04/05/25 15:56	16984-48-8	
Sulfate	159	mg/L	4.0	2.0	4		04/06/25 03:22	14808-79-8	
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	04/11/25 06:42	04/14/25 19:34	7440-36-0	
Arsenic	0.23	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 19:34	7440-38-2	
Barium	0.044	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 19:34	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	04/11/25 06:42	04/14/25 19:34	7440-41-7	
Boron	0.80	mg/L	0.40	0.062	10	04/11/25 06:42	04/15/25 15:15	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	04/11/25 06:42	04/14/25 19:34	7440-43-9	
Calcium	116	mg/L	10.0	1.0	10	04/11/25 06:42	04/15/25 15:15	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 19:34	7440-47-3	
Cobalt	0.034	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 19:34	7440-48-4	
Iron	7.6	mg/L	0.040	0.012	1	04/11/25 06:42	04/14/25 19:34	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	04/11/25 06:42	04/14/25 19:34	7439-92-1	
Magnesium	14.4	mg/L	0.050	0.010	1	04/11/25 06:42	04/14/25 19:34	7439-95-4	
Manganese	3.0	mg/L	1.0	0.031	25	04/11/25 06:42	04/21/25 15:38	7439-96-5	
Molybdenum	0.011	mg/L	0.010	0.0025	1	04/11/25 06:42	04/14/25 19:34	7439-98-7	
Potassium	5.4	mg/L	0.50	0.10	1	04/11/25 06:42	04/14/25 19:34	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 19:34	7782-49-2	
Sodium	7.6	mg/L	1.0	0.15	1	04/11/25 06:42	04/14/25 19:34	7440-23-5	
Thallium	0.00028J	mg/L	0.0010	0.00015	1	04/11/25 06:42	04/14/25 19:34	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92789136

Sample: HAM-PT-07		Lab ID: 92789136001		Collected: 04/03/25 09:20		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	04/10/25 19:12	04/21/25 21:08	7439-97-6	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92789136

Sample: HAM-PT-08 Lab ID: 92789136002 Collected: 04/02/25 16:52 Received: 04/04/25 14:25 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet									
Lithium	0.0129J	mg/L	0.0300	0.000600	1	04/15/25 08:24	04/15/25 12:03	7439-93-2	J
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	124	mg/L	5.0	5.0	1		04/08/25 16:26		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		04/08/25 16:26		
Alkalinity, Total as CaCO3	124	mg/L	5.0	5.0	1		04/08/25 16:26		
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	491	mg/L	25.0	25.0	1		04/08/25 11:57		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		04/09/25 02:47	18496-25-8	M1
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	18.8	mg/L	1.0	0.60	1		04/05/25 16:09	16887-00-6	
Fluoride	0.19	mg/L	0.10	0.050	1		04/05/25 16:09	16984-48-8	
Sulfate	175	mg/L	4.0	2.0	4		04/06/25 03:36	14808-79-8	
WC 6020B MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	04/11/25 06:42	04/14/25 19:44	7440-36-0	
Arsenic	0.027	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 19:44	7440-38-2	
Barium	0.045	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 19:44	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	04/11/25 06:42	04/14/25 19:44	7440-41-7	
Boron	1.0	mg/L	0.40	0.062	10	04/11/25 06:42	04/15/25 15:24	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	04/11/25 06:42	04/14/25 19:44	7440-43-9	
Calcium	119	mg/L	10.0	1.0	10	04/11/25 06:42	04/15/25 15:24	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 19:44	7440-47-3	
Cobalt	0.024	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 19:44	7440-48-4	
Iron	0.37	mg/L	0.040	0.012	1	04/11/25 06:42	04/14/25 19:44	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	04/11/25 06:42	04/14/25 19:44	7439-92-1	
Magnesium	12.5	mg/L	0.050	0.010	1	04/11/25 06:42	04/14/25 19:44	7439-95-4	
Manganese	2.0	mg/L	0.40	0.012	10	04/11/25 06:42	04/15/25 15:24	7439-96-5	
Molybdenum	0.012	mg/L	0.010	0.0025	1	04/11/25 06:42	04/14/25 19:44	7439-98-7	
Potassium	4.9	mg/L	0.50	0.10	1	04/11/25 06:42	04/14/25 19:44	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 19:44	7782-49-2	
Sodium	6.3	mg/L	1.0	0.15	1	04/11/25 06:42	04/14/25 19:44	7440-23-5	
Thallium	0.00025J	mg/L	0.0010	0.00015	1	04/11/25 06:42	04/14/25 19:44	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92789136

Sample: HAM-PT-08		Lab ID: 92789136002		Collected: 04/02/25 16:52		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	04/10/25 19:12	04/21/25 21:15	7439-97-6	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92789136

Sample: HAM-PT-09		Lab ID: 92789136003		Collected: 04/03/25 13:57		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	0.00124J	mg/L	0.0300	0.000600	1	04/15/25 08:24	04/15/25 12:40	7439-93-2	J
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity, Bicarbonate (CaCO ₃)	126	mg/L	5.0	5.0	1		04/08/25 19:38		
Alkalinity, Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		04/08/25 19:38		
Alkalinity, Total as CaCO ₃	126	mg/L	5.0	5.0	1		04/08/25 19:38		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	516	mg/L	25.0	25.0	1		04/09/25 14:47		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		04/09/25 02:52	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	56.9	mg/L	1.0	0.60	1		04/05/25 16:22	16887-00-6	
Fluoride	0.30	mg/L	0.10	0.050	1		04/05/25 16:22	16984-48-8	
Sulfate	122	mg/L	3.0	1.5	3		04/06/25 03:51	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	04/11/25 06:42	04/14/25 19:53	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 19:53	7440-38-2	
Barium	0.064	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 19:53	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	04/11/25 06:42	04/14/25 19:53	7440-41-7	
Boron	1.8	mg/L	0.40	0.062	10	04/11/25 06:42	04/15/25 15:33	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	04/11/25 06:42	04/14/25 19:53	7440-43-9	
Calcium	102	mg/L	10.0	1.0	10	04/11/25 06:42	04/15/25 15:33	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 19:53	7440-47-3	
Cobalt	0.0015J	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 19:53	7440-48-4	
Iron	0.061	mg/L	0.040	0.012	1	04/11/25 06:42	04/14/25 19:53	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	04/11/25 06:42	04/14/25 19:53	7439-92-1	
Magnesium	17.1	mg/L	0.050	0.010	1	04/11/25 06:42	04/14/25 19:53	7439-95-4	
Manganese	0.36J	mg/L	0.40	0.012	10	04/11/25 06:42	04/15/25 15:33	7439-96-5	
Molybdenum	0.16	mg/L	0.010	0.0025	1	04/11/25 06:42	04/14/25 19:53	7439-98-7	
Potassium	6.3	mg/L	0.50	0.10	1	04/11/25 06:42	04/14/25 19:53	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 19:53	7782-49-2	
Sodium	12.1	mg/L	1.0	0.15	1	04/11/25 06:42	04/14/25 19:53	7440-23-5	
Thallium	0.00017J	mg/L	0.0010	0.00015	1	04/11/25 06:42	04/14/25 19:53	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92789136

Sample: HAM-PT-09		Lab ID: 92789136003		Collected: 04/03/25 13:57		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	04/10/25 19:12	04/21/25 21:18	7439-97-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92789136

Sample: HAM-PT-10		Lab ID: 92789136004		Collected: 04/03/25 12:39		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	0.00160J	mg/L	0.0300	0.000600	1	04/15/25 08:24	04/15/25 12:44	7439-93-2	J
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO3)	134	mg/L	5.0	5.0	1		04/08/25 19:47		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		04/08/25 19:47		
Alkalinity, Total as CaCO3	134	mg/L	5.0	5.0	1		04/08/25 19:47		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	532	mg/L	25.0	25.0	1		04/09/25 14:47		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		04/09/25 02:52	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	54.3	mg/L	1.0	0.60	1		04/05/25 16:34	16887-00-6	
Fluoride	0.15	mg/L	0.10	0.050	1		04/05/25 16:34	16984-48-8	
Sulfate	138	mg/L	3.0	1.5	3		04/06/25 04:05	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	04/11/25 06:42	04/14/25 20:02	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 20:02	7440-38-2	
Barium	0.056	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 20:02	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	04/11/25 06:42	04/14/25 20:02	7440-41-7	
Boron	1.7	mg/L	0.40	0.062	10	04/11/25 06:42	04/15/25 15:43	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	04/11/25 06:42	04/14/25 20:02	7440-43-9	
Calcium	124	mg/L	10.0	1.0	10	04/11/25 06:42	04/15/25 15:43	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 20:02	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 20:02	7440-48-4	
Iron	0.18	mg/L	0.040	0.012	1	04/11/25 06:42	04/14/25 20:02	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	04/11/25 06:42	04/14/25 20:02	7439-92-1	
Magnesium	12.3	mg/L	0.050	0.010	1	04/11/25 06:42	04/14/25 20:02	7439-95-4	
Manganese	0.71	mg/L	0.40	0.012	10	04/11/25 06:42	04/15/25 15:43	7439-96-5	
Molybdenum	0.040	mg/L	0.010	0.0025	1	04/11/25 06:42	04/14/25 20:02	7439-98-7	
Potassium	6.8	mg/L	0.50	0.10	1	04/11/25 06:42	04/14/25 20:02	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 20:02	7782-49-2	
Sodium	9.1	mg/L	1.0	0.15	1	04/11/25 06:42	04/14/25 20:02	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	04/11/25 06:42	04/14/25 20:02	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92789136

Sample: HAM-PT-10		Lab ID: 92789136004		Collected: 04/03/25 12:39		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	04/10/25 19:12	04/21/25 21:20	7439-97-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92789136

Sample: HAM-PT-11		Lab ID: 92789136005		Collected: 04/03/25 12:30		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B									
Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet									
Lithium	0.00125J	mg/L	0.0300	0.000600	1	04/15/25 08:24	04/15/25 12:47	7439-93-2	J
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	121	mg/L	5.0	5.0	1		04/08/25 19:56		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		04/08/25 19:56		
Alkalinity, Total as CaCO3	121	mg/L	5.0	5.0	1		04/08/25 19:56		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	460	mg/L	25.0	25.0	1		04/09/25 14:47		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		04/09/25 02:53	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	39.0	mg/L	1.0	0.60	1		04/05/25 16:47	16887-00-6	
Fluoride	0.28	mg/L	0.10	0.050	1		04/05/25 16:47	16984-48-8	
Sulfate	105	mg/L	4.0	2.0	4		04/06/25 04:19	14808-79-8	M1
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	04/11/25 06:42	04/14/25 20:11	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 20:11	7440-38-2	
Barium	0.063	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 20:11	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	04/11/25 06:42	04/14/25 20:11	7440-41-7	
Boron	1.5	mg/L	0.40	0.062	10	04/11/25 06:42	04/15/25 16:11	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	04/11/25 06:42	04/14/25 20:11	7440-43-9	
Calcium	97.3	mg/L	10.0	1.0	10	04/11/25 06:42	04/15/25 16:11	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 20:11	7440-47-3	
Cobalt	0.0014J	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 20:11	7440-48-4	
Iron	0.48	mg/L	0.040	0.012	1	04/11/25 06:42	04/14/25 20:11	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	04/11/25 06:42	04/14/25 20:11	7439-92-1	
Magnesium	15.0	mg/L	0.050	0.010	1	04/11/25 06:42	04/14/25 20:11	7439-95-4	
Manganese	0.35J	mg/L	0.40	0.012	10	04/11/25 06:42	04/15/25 16:11	7439-96-5	
Molybdenum	0.12	mg/L	0.010	0.0025	1	04/11/25 06:42	04/14/25 20:11	7439-98-7	
Potassium	5.9	mg/L	0.50	0.10	1	04/11/25 06:42	04/14/25 20:11	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 20:11	7782-49-2	
Sodium	8.3	mg/L	1.0	0.15	1	04/11/25 06:42	04/14/25 20:11	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	04/11/25 06:42	04/14/25 20:11	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92789136

Sample: HAM-PT-11		Lab ID: 92789136005		Collected: 04/03/25 12:30		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	04/10/25 19:12	04/21/25 21:23	7439-97-6	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92789136

Sample: HAM-PT-12		Lab ID: 92789136006		Collected: 04/03/25 14:23		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B									
Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet									
Lithium	0.00110J	mg/L	0.0300	0.000600	1	04/15/25 08:24	04/15/25 12:50	7439-93-2	J
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	115	mg/L	5.0	5.0	1		04/08/25 20:05		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		04/08/25 20:05		
Alkalinity, Total as CaCO3	115	mg/L	5.0	5.0	1		04/08/25 20:05		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	431	mg/L	25.0	25.0	1		04/10/25 06:13		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		04/09/25 02:53	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	52.4	mg/L	1.0	0.60	1		04/05/25 17:26	16887-00-6	
Fluoride	0.22	mg/L	0.10	0.050	1		04/05/25 17:26	16984-48-8	
Sulfate	115	mg/L	3.0	1.5	3		04/06/25 05:28	14808-79-8	
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	04/11/25 06:42	04/14/25 20:20	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 20:20	7440-38-2	
Barium	0.054	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 20:20	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	04/11/25 06:42	04/14/25 20:20	7440-41-7	
Boron	1.7	mg/L	0.40	0.062	10	04/11/25 06:42	04/15/25 16:21	7440-42-8	
Cadmium	0.00013J	mg/L	0.00050	0.00012	1	04/11/25 06:42	04/14/25 20:20	7440-43-9	
Calcium	100	mg/L	10.0	1.0	10	04/11/25 06:42	04/15/25 16:21	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 20:20	7440-47-3	
Cobalt	0.0017J	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 20:20	7440-48-4	
Iron	0.26	mg/L	0.040	0.012	1	04/11/25 06:42	04/14/25 20:20	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	04/11/25 06:42	04/14/25 20:20	7439-92-1	
Magnesium	14.9	mg/L	0.050	0.010	1	04/11/25 06:42	04/14/25 20:20	7439-95-4	
Manganese	0.41	mg/L	0.40	0.012	10	04/11/25 06:42	04/15/25 16:21	7439-96-5	
Molybdenum	0.11	mg/L	0.010	0.0025	1	04/11/25 06:42	04/14/25 20:20	7439-98-7	
Potassium	6.0	mg/L	0.50	0.10	1	04/11/25 06:42	04/14/25 20:20	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	04/11/25 06:42	04/14/25 20:20	7782-49-2	
Sodium	10.2	mg/L	1.0	0.15	1	04/11/25 06:42	04/14/25 20:20	7440-23-5	
Thallium	0.00016J	mg/L	0.0010	0.00015	1	04/11/25 06:42	04/14/25 20:20	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92789136

Sample: HAM-PT-12		Lab ID: 92789136006		Collected: 04/03/25 14:23		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	04/10/25 19:12	04/21/25 21:26	7439-97-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92789136

Sample: HAM-PT-13 Lab ID: 92789136007 Collected: 04/02/25 17:18 Received: 04/04/25 14:25 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet									
Lithium	0.0423	mg/L	0.0300	0.000600	1	04/15/25 08:24	04/15/25 12:53	7439-93-2	
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	166	mg/L	5.0	5.0	1		04/08/25 16:35		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		04/08/25 16:35		
Alkalinity, Total as CaCO3	166	mg/L	5.0	5.0	1		04/08/25 16:35		
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	517	mg/L	25.0	25.0	1		04/08/25 11:57		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		04/09/25 02:48	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	18.5	mg/L	1.0	0.60	1		04/05/25 17:39	16887-00-6	
Fluoride	0.36	mg/L	0.10	0.050	1		04/05/25 17:39	16984-48-8	
Sulfate	166	mg/L	4.0	2.0	4		04/06/25 05:42	14808-79-8	
WC 6020B MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	04/10/25 07:00	04/10/25 16:16	7440-36-0	
Arsenic	0.17	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:16	7440-38-2	
Barium	0.047	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:16	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	04/10/25 07:00	04/10/25 16:16	7440-41-7	
Boron	0.84	mg/L	0.20	0.031	5	04/10/25 07:00	04/11/25 14:50	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	04/10/25 07:00	04/10/25 16:16	7440-43-9	
Calcium	127	mg/L	50.0	5.0	50	04/10/25 07:00	04/11/25 12:45	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:16	7440-47-3	
Cobalt	0.018	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:16	7440-48-4	
Iron	5.8	mg/L	0.040	0.012	1	04/10/25 07:00	04/10/25 16:16	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	04/10/25 07:00	04/10/25 16:16	7439-92-1	
Magnesium	15.1	mg/L	0.050	0.010	1	04/10/25 07:00	04/10/25 16:16	7439-95-4	
Manganese	3.2	mg/L	2.0	0.062	50	04/10/25 07:00	04/11/25 12:45	7439-96-5	
Molybdenum	0.0079J	mg/L	0.010	0.0025	1	04/10/25 07:00	04/10/25 16:16	7439-98-7	
Potassium	5.8	mg/L	0.50	0.10	1	04/10/25 07:00	04/10/25 16:16	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:16	7782-49-2	
Sodium	8.2	mg/L	1.0	0.15	1	04/10/25 07:00	04/10/25 16:16	7440-23-5	
Thallium	0.00036J	mg/L	0.0010	0.00015	1	04/10/25 07:00	04/10/25 16:16	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92789136

Sample: HAM-PT-13		Lab ID: 92789136007		Collected: 04/02/25 17:18		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	04/10/25 19:12	04/21/25 21:28	7439-97-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92789136

Sample: HAM-PT-14 Lab ID: 92789136008 Collected: 04/02/25 13:49 Received: 04/04/25 14:25 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet									
Lithium	0.0470	mg/L	0.0300	0.000600	1	04/15/25 08:24	04/15/25 12:56	7439-93-2	
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity, Bicarbonate (CaCO ₃)	163	mg/L	5.0	5.0	1		04/08/25 16:46		
Alkalinity, Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		04/08/25 16:46		
Alkalinity, Total as CaCO ₃	163	mg/L	5.0	5.0	1		04/08/25 16:46		
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	515	mg/L	25.0	25.0	1		04/08/25 11:57		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		04/09/25 02:49	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	15.8	mg/L	1.0	0.60	1		04/05/25 17:52	16887-00-6	
Fluoride	0.32	mg/L	0.10	0.050	1		04/05/25 17:52	16984-48-8	
Sulfate	165	mg/L	4.0	2.0	4		04/06/25 05:56	14808-79-8	
WC 6020B MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	04/10/25 07:00	04/10/25 16:25	7440-36-0	
Arsenic	0.42	mg/L	0.25	0.062	50	04/10/25 07:00	04/11/25 12:49	7440-38-2	
Barium	0.042	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:25	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	04/10/25 07:00	04/10/25 16:25	7440-41-7	
Boron	0.81	mg/L	0.20	0.031	5	04/10/25 07:00	04/11/25 14:59	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	04/10/25 07:00	04/10/25 16:25	7440-43-9	
Calcium	111	mg/L	50.0	5.0	50	04/10/25 07:00	04/11/25 12:49	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:25	7440-47-3	
Cobalt	0.022	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:25	7440-48-4	
Iron	10.7	mg/L	0.040	0.012	1	04/10/25 07:00	04/10/25 16:25	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	04/10/25 07:00	04/10/25 16:25	7439-92-1	
Magnesium	14.8	mg/L	0.050	0.010	1	04/10/25 07:00	04/10/25 16:25	7439-95-4	
Manganese	3.3	mg/L	2.0	0.062	50	04/10/25 07:00	04/11/25 12:49	7439-96-5	
Molybdenum	0.010	mg/L	0.010	0.0025	1	04/10/25 07:00	04/10/25 16:25	7439-98-7	
Potassium	5.7	mg/L	0.50	0.10	1	04/10/25 07:00	04/10/25 16:25	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:25	7782-49-2	
Sodium	7.3	mg/L	1.0	0.15	1	04/10/25 07:00	04/10/25 16:25	7440-23-5	
Thallium	0.00019J	mg/L	0.0010	0.00015	1	04/10/25 07:00	04/10/25 16:25	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92789136

Sample: HAM-PT-14		Lab ID: 92789136008		Collected: 04/02/25 13:49		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	04/10/25 19:12	04/21/25 21:31	7439-97-6	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92789136

Sample: HAM-PT-15		Lab ID: 92789136009		Collected: 04/02/25 13:04		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	0.0355	mg/L	0.0300	0.000600	1	04/15/25 08:24	04/15/25 13:00	7439-93-2	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO3)	157	mg/L	5.0	5.0	1		04/08/25 16:57		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		04/08/25 16:57		
Alkalinity, Total as CaCO3	157	mg/L	5.0	5.0	1		04/08/25 16:57		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	511	mg/L	25.0	25.0	1		04/08/25 11:57		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		04/09/25 02:49	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	16.9	mg/L	1.0	0.60	1		04/05/25 18:31	16887-00-6	
Fluoride	0.32	mg/L	0.10	0.050	1		04/05/25 18:31	16984-48-8	
Sulfate	170	mg/L	4.0	2.0	4		04/06/25 06:10	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	04/10/25 07:00	04/10/25 16:33	7440-36-0	
Arsenic	0.088	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:33	7440-38-2	
Barium	0.051	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:33	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	04/10/25 07:00	04/10/25 16:33	7440-41-7	
Boron	0.87	mg/L	0.20	0.031	5	04/10/25 07:00	04/11/25 15:07	7440-42-8	
Cadmium	0.00032J	mg/L	0.00050	0.00012	1	04/10/25 07:00	04/10/25 16:33	7440-43-9	
Calcium	122	mg/L	50.0	5.0	50	04/10/25 07:00	04/11/25 12:53	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:33	7440-47-3	
Cobalt	0.028	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:33	7440-48-4	
Iron	1.1	mg/L	0.040	0.012	1	04/10/25 07:00	04/10/25 16:33	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	04/10/25 07:00	04/10/25 16:33	7439-92-1	
Magnesium	13.3	mg/L	0.050	0.010	1	04/10/25 07:00	04/10/25 16:33	7439-95-4	
Manganese	4.1	mg/L	2.0	0.062	50	04/10/25 07:00	04/11/25 12:53	7439-96-5	
Molybdenum	0.012	mg/L	0.010	0.0025	1	04/10/25 07:00	04/10/25 16:33	7439-98-7	
Potassium	5.5	mg/L	0.50	0.10	1	04/10/25 07:00	04/10/25 16:33	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:33	7782-49-2	
Sodium	7.0	mg/L	1.0	0.15	1	04/10/25 07:00	04/10/25 16:33	7440-23-5	
Thallium	0.00062J	mg/L	0.0010	0.00015	1	04/10/25 07:00	04/10/25 16:33	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92789136

Sample: HAM-PT-15		Lab ID: 92789136009		Collected: 04/02/25 13:04		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	04/10/25 19:12	04/21/25 21:43	7439-97-6	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92789136

Sample: HAM-AP1-EB-01		Lab ID: 92789136010		Collected: 04/02/25 18:00		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B		Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet							
Lithium	ND	mg/L	0.0300	0.000600	1	04/15/25 08:24	04/15/25 13:03	7439-93-2	
2320B Alkalinity		Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville							
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		04/08/25 17:07		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		04/08/25 17:07		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		04/08/25 17:07		
2540C Total Dissolved Solids		Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville							
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		04/08/25 11:57		
4500S2D Sulfide Water		Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville							
Sulfide	ND	mg/L	0.10	0.022	1		04/09/25 02:49	18496-25-8	
300.0 IC Anions 28 Days		Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville							
Chloride	ND	mg/L	1.0	0.60	1		04/05/25 18:44	16887-00-6	
Fluoride	ND	mg/L	0.10	0.050	1		04/05/25 18:44	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		04/05/25 18:44	14808-79-8	
WC 6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia							
Antimony	ND	mg/L	0.0030	0.00050	1	04/10/25 07:00	04/10/25 16:41	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:41	7440-38-2	
Barium	ND	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:41	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	04/10/25 07:00	04/10/25 16:41	7440-41-7	
Boron	ND	mg/L	0.040	0.0062	1	04/10/25 07:00	04/10/25 16:41	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	04/10/25 07:00	04/10/25 16:41	7440-43-9	
Calcium	ND	mg/L	1.0	0.10	1	04/10/25 07:00	04/10/25 16:41	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:41	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:41	7440-48-4	
Iron	ND	mg/L	0.040	0.012	1	04/10/25 07:00	04/10/25 16:41	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	04/10/25 07:00	04/10/25 16:41	7439-92-1	
Magnesium	ND	mg/L	0.050	0.010	1	04/10/25 07:00	04/10/25 16:41	7439-95-4	
Manganese	ND	mg/L	0.040	0.0012	1	04/10/25 07:00	04/10/25 16:41	7439-96-5	
Molybdenum	ND	mg/L	0.010	0.0025	1	04/10/25 07:00	04/10/25 16:41	7439-98-7	
Potassium	ND	mg/L	0.50	0.10	1	04/10/25 07:00	04/10/25 16:41	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:41	7782-49-2	
Sodium	ND	mg/L	1.0	0.15	1	04/10/25 07:00	04/10/25 16:41	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	04/10/25 07:00	04/10/25 16:41	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92789136

Sample: HAM-AP1-EB-01		Lab ID: 92789136010		Collected: 04/02/25 18:00		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	04/10/25 19:12	04/21/25 21:46	7439-97-6	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92789136

Sample: HAM-AP1-FB-01 Lab ID: 92789136011 Collected: 04/02/25 17:50 Received: 04/04/25 14:25 Matrix: Water									
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet									
Lithium	ND	mg/L	0.0300	0.000600	1	04/15/25 08:24	04/15/25 13:06	7439-93-2	
2320B Alkalinity Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		04/08/25 17:11		
Alkalinity,Carbonate (CaCO ₃)	ND	mg/L	5.0	5.0	1		04/08/25 17:11		
Alkalinity, Total as CaCO ₃	ND	mg/L	5.0	5.0	1		04/08/25 17:11		
2540C Total Dissolved Solids Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	ND	mg/L	25.0	25.0	1		04/08/25 11:57		
4500S2D Sulfide Water Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		04/09/25 02:50	18496-25-8	
300.0 IC Anions 28 Days Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	ND	mg/L	1.0	0.60	1		04/05/25 18:57	16887-00-6	
Fluoride	ND	mg/L	0.10	0.050	1		04/05/25 18:57	16984-48-8	
Sulfate	ND	mg/L	1.0	0.50	1		04/05/25 18:57	14808-79-8	
WC 6020B MET ICPMS Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	04/10/25 07:00	04/10/25 16:50	7440-36-0	
Arsenic	ND	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:50	7440-38-2	
Barium	ND	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:50	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	04/10/25 07:00	04/10/25 16:50	7440-41-7	
Boron	ND	mg/L	0.040	0.0062	1	04/10/25 07:00	04/10/25 16:50	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	04/10/25 07:00	04/10/25 16:50	7440-43-9	
Calcium	ND	mg/L	1.0	0.10	1	04/10/25 07:00	04/10/25 16:50	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:50	7440-47-3	
Cobalt	ND	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:50	7440-48-4	
Iron	0.026J	mg/L	0.040	0.012	1	04/10/25 07:00	04/10/25 16:50	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	04/10/25 07:00	04/10/25 16:50	7439-92-1	
Magnesium	0.042J	mg/L	0.050	0.010	1	04/10/25 07:00	04/10/25 16:50	7439-95-4	
Manganese	0.0066J	mg/L	0.040	0.0012	1	04/10/25 07:00	04/10/25 16:50	7439-96-5	
Molybdenum	ND	mg/L	0.010	0.0025	1	04/10/25 07:00	04/10/25 16:50	7439-98-7	
Potassium	ND	mg/L	0.50	0.10	1	04/10/25 07:00	04/10/25 16:50	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:50	7782-49-2	
Sodium	ND	mg/L	1.0	0.15	1	04/10/25 07:00	04/10/25 16:50	7440-23-5	
Thallium	ND	mg/L	0.0010	0.00015	1	04/10/25 07:00	04/10/25 16:50	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92789136

Sample: HAM-AP1-FB-01		Lab ID: 92789136011		Collected: 04/02/25 17:50		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	04/10/25 19:12	04/21/25 21:48	7439-97-6	

REPORT OF LABORATORY ANALYSIS



ANALYTICAL RESULTS

Project: Hammond AP-1

Pace Project No.: 92789136

Sample: HAM-AP1-FD-01		Lab ID: 92789136012		Collected: 04/02/25 00:00		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
Metals (ICPMS) 6020B									
Analytical Method: EPA 6020B Preparation Method: 3015 Pace National - Mt. Juliet									
Lithium	0.0479	mg/L	0.0300	0.000600	1	04/15/25 08:24	04/15/25 13:09	7439-93-2	
2320B Alkalinity									
Analytical Method: SM 2320B-2011 Pace Analytical Services - Asheville									
Alkalinity,Bicarbonate (CaCO3)	162	mg/L	5.0	5.0	1		04/08/25 17:15		
Alkalinity,Carbonate (CaCO3)	ND	mg/L	5.0	5.0	1		04/08/25 17:15		
Alkalinity, Total as CaCO3	162	mg/L	5.0	5.0	1		04/08/25 17:15		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C-2015 Pace Analytical Services - Asheville									
Total Dissolved Solids	515	mg/L	25.0	25.0	1		04/08/25 11:57		
4500S2D Sulfide Water									
Analytical Method: SM 4500-S2D-2011 Pace Analytical Services - Asheville									
Sulfide	ND	mg/L	0.10	0.022	1		04/09/25 02:51	18496-25-8	
300.0 IC Anions 28 Days									
Analytical Method: EPA 300.0 Rev 2.1 1993 Pace Analytical Services - Asheville									
Chloride	16.1	mg/L	1.0	0.60	1		04/05/25 19:10	16887-00-6	
Fluoride	0.34	mg/L	0.10	0.050	1		04/05/25 19:10	16984-48-8	
Sulfate	166	mg/L	4.0	2.0	4		04/06/25 06:24	14808-79-8	
WC 6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3005A Pace Analytical Services - West Columbia									
Antimony	ND	mg/L	0.0030	0.00050	1	04/10/25 07:00	04/10/25 16:58	7440-36-0	
Arsenic	0.40	mg/L	0.25	0.062	50	04/10/25 07:00	04/11/25 12:57	7440-38-2	
Barium	0.043	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:58	7440-39-3	
Beryllium	ND	mg/L	0.00050	0.00015	1	04/10/25 07:00	04/10/25 16:58	7440-41-7	
Boron	0.79	mg/L	0.20	0.031	5	04/10/25 07:00	04/11/25 14:42	7440-42-8	
Cadmium	ND	mg/L	0.00050	0.00012	1	04/10/25 07:00	04/10/25 16:58	7440-43-9	
Calcium	119	mg/L	50.0	5.0	50	04/10/25 07:00	04/11/25 12:57	7440-70-2	
Chromium	ND	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:58	7440-47-3	
Cobalt	0.023	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:58	7440-48-4	
Iron	10.9	mg/L	0.040	0.012	1	04/10/25 07:00	04/10/25 16:58	7439-89-6	
Lead	ND	mg/L	0.0010	0.00025	1	04/10/25 07:00	04/10/25 16:58	7439-92-1	
Magnesium	15.0	mg/L	0.050	0.010	1	04/10/25 07:00	04/10/25 16:58	7439-95-4	
Manganese	3.2	mg/L	2.0	0.062	50	04/10/25 07:00	04/11/25 12:57	7439-96-5	
Molybdenum	0.010	mg/L	0.010	0.0025	1	04/10/25 07:00	04/10/25 16:58	7439-98-7	
Potassium	5.6	mg/L	0.50	0.10	1	04/10/25 07:00	04/10/25 16:58	7440-09-7	
Selenium	ND	mg/L	0.0050	0.0012	1	04/10/25 07:00	04/10/25 16:58	7782-49-2	
Sodium	7.4	mg/L	1.0	0.15	1	04/10/25 07:00	04/10/25 16:58	7440-23-5	
Thallium	0.00017J	mg/L	0.0010	0.00015	1	04/10/25 07:00	04/10/25 16:58	7440-28-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: Hammond AP-1
Pace Project No.: 92789136

Sample: HAM-AP1-FD-01		Lab ID: 92789136012		Collected: 04/02/25 00:00		Received: 04/04/25 14:25		Matrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
WCOL 7470 Mercury									
Analytical Method: EPA 7470A Preparation Method: EPA 7470A									
Pace Analytical Services - West Columbia									
Mercury	ND	mg/L	0.00020	0.000091	1	04/10/25 19:12	04/21/25 21:51	7439-97-6	

REPORT OF LABORATORY ANALYSIS



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92789136

QC Batch:	2487004	Analysis Method:	EPA 6020B
QC Batch Method:	3015	Analysis Description:	Metals (ICPMS) 6020B
		Laboratory:	Pace National - Mt. Juliet
Associated Lab Samples:	92789136001, 92789136002, 92789136003, 92789136004, 92789136005, 92789136006, 92789136007, 92789136008, 92789136009, 92789136010, 92789136011, 92789136012		

METHOD BLANK:	R4199786-1	Matrix:	Water
Associated Lab Samples:	92789136001, 92789136002, 92789136003, 92789136004, 92789136005, 92789136006, 92789136007, 92789136008, 92789136009, 92789136010, 92789136011, 92789136012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Lithium	mg/L	ND	0.0300	0.000600	04/15/25 11:31	

LABORATORY CONTROL SAMPLE: R4199786-2						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Lithium	ma/L	0.0500	0.0431	86.3	80.0-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:			R4199786-4		R4199786-5							
Parameter	Units	L1844756-01	MS	MSD	MS	MSD	MS	MSD	% Rec	Max	Qual	
		Result	Spike Conc.	Spike Conc.								Result
Lithium	mg/L	0.00302	0.0500	0.0500	0.0467	0.0458	87.3	85.5	75.0-125	1.91	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92789136

QC Batch: 927854

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92789136002, 92789136007, 92789136008, 92789136009, 92789136010, 92789136011, 92789136012

METHOD BLANK: 4766038

Matrix: Water

Associated Lab Samples: 92789136002, 92789136007, 92789136008, 92789136009, 92789136010, 92789136011, 92789136012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	04/08/25 14:52	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	04/08/25 14:52	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	04/08/25 14:52	

LABORATORY CONTROL SAMPLE: 4766039

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.1	102	80-120	

LABORATORY CONTROL SAMPLE: 4766040

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.9	104	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4766041 4766042

Parameter	Units	92788996001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	63.1	50	50	116	117	107	109	80-120	1	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4766043 4766044

Parameter	Units	92789346001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	67.8	50	50	118	117	100	99	80-120	1	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92789136

QC Batch: 927855

Analysis Method: SM 2320B-2011

QC Batch Method: SM 2320B-2011

Analysis Description: 2320B Alkalinity

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92789136001, 92789136003, 92789136004, 92789136005, 92789136006

METHOD BLANK: 4766046

Matrix: Water

Associated Lab Samples: 92789136001, 92789136003, 92789136004, 92789136005, 92789136006

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	ND	5.0	5.0	04/08/25 18:32	
Alkalinity,Bicarbonate (CaCO ₃)	mg/L	ND	5.0	5.0	04/08/25 18:32	
Alkalinity,Carbonate (CaCO ₃)	mg/L	ND	5.0	5.0	04/08/25 18:32	

LABORATORY CONTROL SAMPLE: 4766047

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	51.1	102	80-120	

LABORATORY CONTROL SAMPLE: 4766048

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO ₃	mg/L	50	52.0	104	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4766049 4766050

Parameter	Units	92789065030 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	12.0	50	50	63.5	64.0	103	104	80-120	1	25	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4766051 4766052

Parameter	Units	92789065031 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO ₃	mg/L	46.5	50	50	96.8	97.6	100	102	80-120	1	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92789136

QC Batch: 927864

Analysis Method: SM 2540C-2015

QC Batch Method: SM 2540C-2015

Analysis Description: 2540C Total Dissolved Solids

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92789136002, 92789136007, 92789136008, 92789136009, 92789136010, 92789136011, 92789136012

METHOD BLANK: 4766088

Matrix: Water

Associated Lab Samples: 92789136002, 92789136007, 92789136008, 92789136009, 92789136010, 92789136011, 92789136012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	04/08/25 11:57	

LABORATORY CONTROL SAMPLE: 4766089

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	250	242	97	90-110	

SAMPLE DUPLICATE: 4766090

Parameter	Units	92789136002 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	491	489	0	25	

SAMPLE DUPLICATE: 4766091

Parameter	Units	92788889001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	483	484	0	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92789136

QC Batch: 928218

Analysis Method: SM 2540C-2015

QC Batch Method: SM 2540C-2015

Analysis Description: 2540C Total Dissolved Solids

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92789136001, 92789136003, 92789136004, 92789136005

METHOD BLANK: 4768155

Matrix: Water

Associated Lab Samples: 92789136001, 92789136003, 92789136004, 92789136005

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	04/09/25 14:39	

LABORATORY CONTROL SAMPLE: 4768156

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	250	236	94	90-110	

SAMPLE DUPLICATE: 4768157

Parameter	Units	92789705001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	31.0	27.0	14	25	

SAMPLE DUPLICATE: 4768158

Parameter	Units	92789065027 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	116	112	4	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92789136

QC Batch: 928368

Analysis Method: SM 2540C-2015

QC Batch Method: SM 2540C-2015

Analysis Description: 2540C Total Dissolved Solids

Laboratory: Pace Analytical Services - Asheville

Associated Lab Samples: 92789136006

METHOD BLANK: 4769129

Matrix: Water

Associated Lab Samples: 92789136006

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	ND	25.0	25.0	04/10/25 06:13	

LABORATORY CONTROL SAMPLE: 4769130

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	250	244	98	90-110	

SAMPLE DUPLICATE: 4769131

Parameter	Units	92789136006 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	431	435	1	25	

SAMPLE DUPLICATE: 4769132

Parameter	Units	92789148003 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	119	111	7	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92789136

QC Batch:	928049	Analysis Method:	SM 4500-S2D-2011
QC Batch Method:	SM 4500-S2D-2011	Analysis Description:	4500S2D Sulfide Water
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92789136001, 92789136002, 92789136003, 92789136004, 92789136005, 92789136006, 92789136007, 92789136008, 92789136009, 92789136010, 92789136011, 92789136012		

METHOD BLANK:	4767367	Matrix:	Water
Associated Lab Samples:	92789136001, 92789136002, 92789136003, 92789136004, 92789136005, 92789136006, 92789136007, 92789136008, 92789136009, 92789136010, 92789136011, 92789136012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Sulfide	mg/L	ND	0.10	0.022	04/09/25 02:46	

LABORATORY CONTROL SAMPLE: 4767368						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfide	mg/L	0.5	0.56	113	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:												
4767369					4767370							
		92789136002	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Parameter	Units	Result										
Sulfide	mg/L	ND	0.5	0.5	0.59	0.63	119	125	80-120	5	10	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:					4767372							
Parameter	Units	92789691001	MS	MSD	MS	MSD	MS	MSD	% Rec	RPD	Max	Qual
		Result	Spike Conc.	Spike Conc.								
Sulfide	mg/L	ND	0.5	0.5	0.59	0.62	108	112	80-120	3	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92789136

QC Batch:	927500	Analysis Method:	EPA 300.0 Rev 2.1 1993
QC Batch Method:	EPA 300.0 Rev 2.1 1993	Analysis Description:	300.0 IC Anions
		Laboratory:	Pace Analytical Services - Asheville
Associated Lab Samples:	92789136001, 92789136002, 92789136003, 92789136004, 92789136005, 92789136006, 92789136007, 92789136008, 92789136009, 92789136010, 92789136011, 92789136012		

METHOD BLANK:	4764575	Matrix:	Water
Associated Lab Samples:	92789136001, 92789136002, 92789136003, 92789136004, 92789136005, 92789136006, 92789136007, 92789136008, 92789136009, 92789136010, 92789136011, 92789136012		

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Chloride	mg/L	ND	1.0	0.60	04/05/25 13:20	
Fluoride	mg/L	ND	0.10	0.050	04/05/25 13:20	
Sulfate	mg/L	ND	1.0	0.50	04/05/25 13:20	

LABORATORY CONTROL SAMPLE: 4764576						
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	50	52.4	105	90-110	
Fluoride	mg/L	2.5	2.7	109	90-110	
Sulfate	mg/L	50	52.4	105	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4764577 4764578												
Parameter	Units	92789037001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	916	50	50	944	944	56	56	90-110	0	10	M1
Fluoride	mg/L	ND	2.5	2.5	2.4	2.4	94	96	90-110	2	10	
Sulfate	mg/L	81.5	50	50	110	111	56	59	90-110	1	10	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4764579 4764580												
Parameter	Units	92789136005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	39.0	50	50	86.6	89.1	95	100	90-110	3	10	
Fluoride	mg/L	0.28	2.5	2.5	2.7	2.8	97	102	90-110	4	10	
Sulfate	mg/L	105	50	50	150	147	90	85	90-110	2	10	M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92789136

QC Batch: 928129

Analysis Method: EPA 6020B

QC Batch Method: EPA 3005A

Analysis Description: WC 6020B MET

Laboratory: Pace Analytical Services - West Columbia

Associated Lab Samples: 92789136001, 92789136002, 92789136003, 92789136004, 92789136005, 92789136006

METHOD BLANK: 4767546

Matrix: Water

Associated Lab Samples: 92789136001, 92789136002, 92789136003, 92789136004, 92789136005, 92789136006

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00050	04/14/25 15:56	
Arsenic	mg/L	ND	0.0050	0.0012	04/14/25 15:56	
Barium	mg/L	ND	0.0050	0.0012	04/14/25 15:56	
Beryllium	mg/L	ND	0.00050	0.00015	04/14/25 15:56	
Boron	mg/L	ND	0.040	0.0062	04/14/25 15:56	
Cadmium	mg/L	ND	0.00050	0.00012	04/14/25 15:56	
Calcium	mg/L	ND	1.0	0.10	04/14/25 15:56	
Chromium	mg/L	ND	0.0050	0.0012	04/14/25 15:56	
Cobalt	mg/L	ND	0.0050	0.0012	04/14/25 15:56	
Iron	mg/L	ND	0.040	0.012	04/14/25 15:56	
Lead	mg/L	ND	0.0010	0.00025	04/14/25 15:56	
Magnesium	mg/L	ND	0.050	0.010	04/14/25 15:56	
Manganese	mg/L	ND	0.040	0.0012	04/14/25 15:56	
Molybdenum	mg/L	ND	0.010	0.0025	04/14/25 15:56	
Potassium	mg/L	ND	0.50	0.10	04/14/25 15:56	
Selenium	mg/L	ND	0.0050	0.0012	04/14/25 15:56	
Sodium	mg/L	ND	1.0	0.15	04/14/25 15:56	
Thallium	mg/L	ND	0.0010	0.00015	04/14/25 15:56	

LABORATORY CONTROL SAMPLE: 4767547

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.10	100	80-120	
Arsenic	mg/L	0.1	0.092	92	80-120	
Barium	mg/L	0.1	0.099	99	80-120	
Beryllium	mg/L	0.1	0.096	96	80-120	
Boron	mg/L	0.1	0.10	100	80-120	
Cadmium	mg/L	0.1	0.095	95	80-120	
Calcium	mg/L	1	0.93J	93	80-120	
Chromium	mg/L	0.1	0.10	103	80-120	
Cobalt	mg/L	0.1	0.10	103	80-120	
Iron	mg/L	1	1.0	102	80-120	
Lead	mg/L	0.1	0.097	97	80-120	
Magnesium	mg/L	1	1.0	102	80-120	
Manganese	mg/L	0.1	0.10	101	80-120	
Molybdenum	mg/L	0.1	0.10	101	80-120	
Potassium	mg/L	1	0.98	98	80-120	
Selenium	mg/L	0.1	0.093	93	80-120	
Sodium	mg/L	1	1.0	101	80-120	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92789136

LABORATORY CONTROL SAMPLE: 4767547

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Thallium	mg/L	0.1	0.096	96	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4767548 4767549

Parameter	Units	92789159008	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		Result	Conc.	Conc.	Result	Result	% Rec	% Rec	Limits			
Antimony	mg/L	ND	0.1	0.1	0.10	0.10	101	103	75-125	1	20	
Arsenic	mg/L	11.7 ug/L	0.1	0.1	0.11	0.11	96	98	75-125	1	20	
Barium	mg/L	40.0 ug/L	0.1	0.1	0.14	0.14	96	97	75-125	1	20	
Beryllium	mg/L	ND	0.1	0.1	0.098	0.097	98	96	75-125	1	20	
Boron	mg/L	ND	0.1	0.1	0.10	0.11	97	102	75-125	5	20	
Cadmium	mg/L	ND	0.1	0.1	0.097	0.098	97	98	75-125	1	20	
Calcium	mg/L	22700 ug/L	1	1	23.8	23.6	115	91	75-125	1	20	
Chromium	mg/L	ND	0.1	0.1	0.098	0.099	98	98	75-125	1	20	
Cobalt	mg/L	ND	0.1	0.1	0.098	0.098	94	95	75-125	1	20	
Iron	mg/L	16400 ug/L	1	1	17.5	17.5	106	108	75-125	0	20	
Lead	mg/L	ND	0.1	0.1	0.093	0.095	93	95	75-125	2	20	
Magnesium	mg/L	9660 ug/L	1	1	10.5	10.5	84	88	75-125	0	20	
Manganese	mg/L	4220 ug/L	0.1	0.1	4.3	4.4	120	167	75-125	1	20	M1
Molybdenum	mg/L	ND	0.1	0.1	0.090	0.091	89	90	75-125	1	20	
Potassium	mg/L	1110 ug/L	1	1	2.1	2.1	98	99	75-125	1	20	
Selenium	mg/L	ND	0.1	0.1	0.10	0.10	102	104	75-125	2	20	
Sodium	mg/L	2360 ug/L	1	1	3.3	3.3	94	95	75-125	0	20	
Thallium	mg/L	ND	0.1	0.1	0.094	0.096	94	96	75-125	2	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92789136

QC Batch: 928130

Analysis Method: EPA 6020B

QC Batch Method: EPA 3005A

Analysis Description: WC 6020B MET

Laboratory: Pace Analytical Services - West Columbia

Associated Lab Samples: 92789136007, 92789136008, 92789136009, 92789136010, 92789136011, 92789136012

METHOD BLANK: 4767568

Matrix: Water

Associated Lab Samples: 92789136007, 92789136008, 92789136009, 92789136010, 92789136011, 92789136012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Antimony	mg/L	ND	0.0030	0.00050	04/10/25 15:59	
Arsenic	mg/L	ND	0.0050	0.0012	04/10/25 15:59	
Barium	mg/L	ND	0.0050	0.0012	04/10/25 15:59	
Beryllium	mg/L	ND	0.00050	0.00015	04/10/25 15:59	
Boron	mg/L	ND	0.040	0.0062	04/10/25 15:59	
Cadmium	mg/L	ND	0.00050	0.00012	04/10/25 15:59	
Calcium	mg/L	ND	1.0	0.10	04/10/25 15:59	
Chromium	mg/L	ND	0.0050	0.0012	04/10/25 15:59	
Cobalt	mg/L	ND	0.0050	0.0012	04/10/25 15:59	
Iron	mg/L	ND	0.040	0.012	04/10/25 15:59	
Lead	mg/L	ND	0.0010	0.00025	04/10/25 15:59	
Magnesium	mg/L	ND	0.050	0.010	04/10/25 15:59	
Manganese	mg/L	ND	0.040	0.0012	04/10/25 15:59	
Molybdenum	mg/L	ND	0.010	0.0025	04/10/25 15:59	
Potassium	mg/L	ND	0.50	0.10	04/10/25 15:59	
Selenium	mg/L	ND	0.0050	0.0012	04/10/25 15:59	
Sodium	mg/L	ND	1.0	0.15	04/10/25 15:59	
Thallium	mg/L	ND	0.0010	0.00015	04/10/25 15:59	

LABORATORY CONTROL SAMPLE: 4767569

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	mg/L	0.1	0.093	93	80-120	
Arsenic	mg/L	0.1	0.090	90	80-120	
Barium	mg/L	0.1	0.093	93	80-120	
Beryllium	mg/L	0.1	0.091	91	80-120	
Boron	mg/L	0.1	0.091	91	80-120	
Cadmium	mg/L	0.1	0.093	93	80-120	
Calcium	mg/L	1	1.0J	100	80-120	
Chromium	mg/L	0.1	0.099	99	80-120	
Cobalt	mg/L	0.1	0.099	99	80-120	
Iron	mg/L	1	0.99	99	80-120	
Lead	mg/L	0.1	0.10	102	80-120	
Magnesium	mg/L	1	0.97	97	80-120	
Manganese	mg/L	0.1	0.098	98	80-120	
Molybdenum	mg/L	0.1	0.10	102	80-120	
Potassium	mg/L	1	1.0	101	80-120	
Selenium	mg/L	0.1	0.086	86	80-120	
Sodium	mg/L	1	0.93J	93	80-120	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1

Pace Project No.: 92789136

LABORATORY CONTROL SAMPLE: 4767569

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Thallium	mg/L	0.1	0.10	102	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4767570 4767571

Parameter	Units	92789148002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Antimony	mg/L	ND	0.1	0.1	0.10	0.098	100	98	75-125	2	20	
Arsenic	mg/L	ND	0.1	0.1	0.085	0.084	85	84	75-125	2	20	
Barium	mg/L	146 ug/L	0.1	0.1	0.24	0.23	91	88	75-125	1	20	
Beryllium	mg/L	ND	0.1	0.1	0.097	0.098	97	98	75-125	1	20	
Boron	mg/L	ND	0.1	0.1	0.10	0.10	96	94	75-125	2	20	
Cadmium	mg/L	ND	0.1	0.1	0.10	0.099	100	98	75-125	2	20	
Calcium	mg/L	25600 ug/L	1	1	27.0	25.9	138	35	75-125	4	20	M1
Chromium	mg/L	ND	0.1	0.1	0.10	0.10	100	101	75-125	1	20	
Cobalt	mg/L	ND	0.1	0.1	0.11	0.11	102	104	75-125	2	20	
Iron	mg/L	580 ug/L	1	1	1.5	1.5	90	96	75-125	4	20	
Lead	mg/L	ND	0.1	0.1	0.10	0.10	104	103	75-125	1	20	
Magnesium	mg/L	4670 ug/L	1	1	5.3	5.6	62	91	75-125	5	20	M1
Manganese	mg/L	4800 ug/L	0.1	0.1	4.7	4.8	-117	3	75-125	3	20	M1
Molybdenum	mg/L	ND	0.1	0.1	0.090	0.089	90	89	75-125	1	20	
Potassium	mg/L	633 ug/L	1	1	1.6	1.6	94	96	75-125	1	20	
Selenium	mg/L	ND	0.1	0.1	0.091	0.090	91	90	75-125	1	20	
Sodium	mg/L	5270 ug/L	1	1	6.1	6.3	79	98	75-125	3	20	
Thallium	mg/L	ND	0.1	0.1	0.11	0.11	106	105	75-125	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: Hammond AP-1
Pace Project No.: 92789136

QC Batch: 928649 Analysis Method: EPA 7470A
QC Batch Method: EPA 7470A Analysis Description: WCOL 7470 Mercury
Laboratory: Pace Analytical Services - West Columbia
Associated Lab Samples: 92789136001, 92789136002, 92789136003, 92789136004, 92789136005, 92789136006, 92789136007, 92789136008, 92789136009, 92789136010, 92789136011, 92789136012

METHOD BLANK: 4770650 Matrix: Water
Associated Lab Samples: 92789136001, 92789136002, 92789136003, 92789136004, 92789136005, 92789136006, 92789136007, 92789136008, 92789136009, 92789136010, 92789136011, 92789136012

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Mercury	mg/L	ND	0.00020	0.000091	04/21/25 20:58	

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/L	0.002	0.0020	102	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4770652 4770653												
Parameter	Units	92789136001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.002	0.002	0.0020	0.0020	101	99	80-120	1	20	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 4770654 4770655												
Parameter	Units	92789136008 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mercury	mg/L	ND	0.002	0.002	0.0020	0.0020	101	100	80-120	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: Hammond AP-1
Pace Project No.: 92789136

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.
A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

J Analyte detected below the reporting limit, therefore result is an estimate. This qualifier is also used for all TICs.
M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92789136

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92789136001	HAM-PT-07	3015	2487004	EPA 6020B	2487004
92789136002	HAM-PT-08	3015	2487004	EPA 6020B	2487004
92789136003	HAM-PT-09	3015	2487004	EPA 6020B	2487004
92789136004	HAM-PT-10	3015	2487004	EPA 6020B	2487004
92789136005	HAM-PT-11	3015	2487004	EPA 6020B	2487004
92789136006	HAM-PT-12	3015	2487004	EPA 6020B	2487004
92789136007	HAM-PT-13	3015	2487004	EPA 6020B	2487004
92789136008	HAM-PT-14	3015	2487004	EPA 6020B	2487004
92789136009	HAM-PT-15	3015	2487004	EPA 6020B	2487004
92789136010	HAM-AP1-EB-01	3015	2487004	EPA 6020B	2487004
92789136011	HAM-AP1-FB-01	3015	2487004	EPA 6020B	2487004
92789136012	HAM-AP1-FD-01	3015	2487004	EPA 6020B	2487004
92789136001	HAM-PT-07	SM 2320B-2011	927855		
92789136002	HAM-PT-08	SM 2320B-2011	927854		
92789136003	HAM-PT-09	SM 2320B-2011	927855		
92789136004	HAM-PT-10	SM 2320B-2011	927855		
92789136005	HAM-PT-11	SM 2320B-2011	927855		
92789136006	HAM-PT-12	SM 2320B-2011	927855		
92789136007	HAM-PT-13	SM 2320B-2011	927854		
92789136008	HAM-PT-14	SM 2320B-2011	927854		
92789136009	HAM-PT-15	SM 2320B-2011	927854		
92789136010	HAM-AP1-EB-01	SM 2320B-2011	927854		
92789136011	HAM-AP1-FB-01	SM 2320B-2011	927854		
92789136012	HAM-AP1-FD-01	SM 2320B-2011	927854		
92789136001	HAM-PT-07	SM 2540C-2015	928218		
92789136002	HAM-PT-08	SM 2540C-2015	927864		
92789136003	HAM-PT-09	SM 2540C-2015	928218		
92789136004	HAM-PT-10	SM 2540C-2015	928218		
92789136005	HAM-PT-11	SM 2540C-2015	928218		
92789136006	HAM-PT-12	SM 2540C-2015	928368		
92789136007	HAM-PT-13	SM 2540C-2015	927864		
92789136008	HAM-PT-14	SM 2540C-2015	927864		
92789136009	HAM-PT-15	SM 2540C-2015	927864		
92789136010	HAM-AP1-EB-01	SM 2540C-2015	927864		
92789136011	HAM-AP1-FB-01	SM 2540C-2015	927864		
92789136012	HAM-AP1-FD-01	SM 2540C-2015	927864		
92789136001	HAM-PT-07	SM 4500-S2D-2011	928049		
92789136002	HAM-PT-08	SM 4500-S2D-2011	928049		
92789136003	HAM-PT-09	SM 4500-S2D-2011	928049		
92789136004	HAM-PT-10	SM 4500-S2D-2011	928049		
92789136005	HAM-PT-11	SM 4500-S2D-2011	928049		
92789136006	HAM-PT-12	SM 4500-S2D-2011	928049		
92789136007	HAM-PT-13	SM 4500-S2D-2011	928049		
92789136008	HAM-PT-14	SM 4500-S2D-2011	928049		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Hammond AP-1

Pace Project No.: 92789136

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92789136009	HAM-PT-15	SM 4500-S2D-2011	928049		
92789136010	HAM-AP1-EB-01	SM 4500-S2D-2011	928049		
92789136011	HAM-AP1-FB-01	SM 4500-S2D-2011	928049		
92789136012	HAM-AP1-FD-01	SM 4500-S2D-2011	928049		
92789136001	HAM-PT-07	EPA 300.0 Rev 2.1 1993	927500		
92789136002	HAM-PT-08	EPA 300.0 Rev 2.1 1993	927500		
92789136003	HAM-PT-09	EPA 300.0 Rev 2.1 1993	927500		
92789136004	HAM-PT-10	EPA 300.0 Rev 2.1 1993	927500		
92789136005	HAM-PT-11	EPA 300.0 Rev 2.1 1993	927500		
92789136006	HAM-PT-12	EPA 300.0 Rev 2.1 1993	927500		
92789136007	HAM-PT-13	EPA 300.0 Rev 2.1 1993	927500		
92789136008	HAM-PT-14	EPA 300.0 Rev 2.1 1993	927500		
92789136009	HAM-PT-15	EPA 300.0 Rev 2.1 1993	927500		
92789136010	HAM-AP1-EB-01	EPA 300.0 Rev 2.1 1993	927500		
92789136011	HAM-AP1-FB-01	EPA 300.0 Rev 2.1 1993	927500		
92789136012	HAM-AP1-FD-01	EPA 300.0 Rev 2.1 1993	927500		
92789136001	HAM-PT-07	EPA 3005A	928129	EPA 6020B	929339
92789136002	HAM-PT-08	EPA 3005A	928129	EPA 6020B	929339
92789136003	HAM-PT-09	EPA 3005A	928129	EPA 6020B	929339
92789136004	HAM-PT-10	EPA 3005A	928129	EPA 6020B	929339
92789136005	HAM-PT-11	EPA 3005A	928129	EPA 6020B	929339
92789136006	HAM-PT-12	EPA 3005A	928129	EPA 6020B	929339
92789136007	HAM-PT-13	EPA 3005A	928130	EPA 6020B	928804
92789136008	HAM-PT-14	EPA 3005A	928130	EPA 6020B	928804
92789136009	HAM-PT-15	EPA 3005A	928130	EPA 6020B	928804
92789136010	HAM-AP1-EB-01	EPA 3005A	928130	EPA 6020B	928804
92789136011	HAM-AP1-FB-01	EPA 3005A	928130	EPA 6020B	928804
92789136012	HAM-AP1-FD-01	EPA 3005A	928130	EPA 6020B	928804
92789136001	HAM-PT-07	EPA 7470A	928649	EPA 7470A	930709
92789136002	HAM-PT-08	EPA 7470A	928649	EPA 7470A	930709
92789136003	HAM-PT-09	EPA 7470A	928649	EPA 7470A	930709
92789136004	HAM-PT-10	EPA 7470A	928649	EPA 7470A	930709
92789136005	HAM-PT-11	EPA 7470A	928649	EPA 7470A	930709
92789136006	HAM-PT-12	EPA 7470A	928649	EPA 7470A	930709
92789136007	HAM-PT-13	EPA 7470A	928649	EPA 7470A	930709
92789136008	HAM-PT-14	EPA 7470A	928649	EPA 7470A	930709
92789136009	HAM-PT-15	EPA 7470A	928649	EPA 7470A	930709
92789136010	HAM-AP1-EB-01	EPA 7470A	928649	EPA 7470A	930709
92789136011	HAM-AP1-FB-01	EPA 7470A	928649	EPA 7470A	930709
92789136012	HAM-AP1-FD-01	EPA 7470A	928649	EPA 7470A	930709

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐ Kernersville ☐Sample Condition
Upon Receipt

Client Name:

GA Power

Project #:

WO#: 92789136



92789136

Courier: ☐ Fed.Ex ☐ UPS ☐ USPS ☐ Client
☐ Commercial ☐ Pace ☐ Other: _____Custody Seal Present? ☐ Yes ☒ No Seals Intact? ☐ Yes ☐ No ☒ N/ADate/Initials Person Examining Contents: 4/4/25
ldyPacking Material: ☐ Bubble Wrap ☐ Bubble Bags ☒ None ☐ Other

Thermometer:

☒ IR Gun ID: 214Type of Ice: ☒ Wet ☐ Blue ☐ None

Cooler Temp:

2.5

Correction Factor: 0.0
Add/Subtract (°C)

Temp should be above freezing to 6°C

☐ Samples out of temp criteria. Samples on ice, cooling process has begun

Cooler Temp Corrected (°C): 2.5

USDA Regulated Soil (☐ N/A, water sample)Did samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ NoDid samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

			Comments/Discrepancy:
Chain of Custody Present?	☒ Yes ☐ No ☐ N/A	1.	
Samples Arrived within Hold Time?	☐ Yes ☐ No ☐ N/A	2.	
Short Hold Time Analysis (<72 hr.)?	☐ Yes ☒ No ☐ N/A	3.	
Rush Turn Around Time Requested?	☐ Yes ☒ No ☐ N/A	4.	
Sufficient Volume?	☒ Yes ☐ No ☐ N/A	5.	
Correct Containers Used?	☒ Yes ☐ No ☐ N/A	6.	
-Pace Containers Used?	☒ Yes ☐ No ☐ N/A		
Containers Intact?	☒ Yes ☐ No ☐ N/A	7.	
Dissolved analysis: Samples Field Filtered?	☐ Yes ☐ No ☒ N/A	8.	
Sample Labels Match COC?	☒ Yes ☐ No ☐ N/A	9.	
-Includes Date/Time/ID/Analysis Matrix: W			
Headspace in VOA Vials (>5-6mm)?	☐ Yes ☐ No ☒ N/A	10.	
Trip Blank Present?	☐ Yes ☐ No ☒ N/A	11.	
Trip Blank Custody Seals Present?	☐ Yes ☐ No ☒ N/A		

COMMENTS/SAMPLE DISCREPANCY

Field Data Required? ☐ Yes ☐ No

Lot ID of split containers:

CLIENT NOTIFICATION/RESOLUTION

Person contacted: _____ Date/Time: _____

Project Manager SCURF Review: _____

Date: _____

Project Manager SRF Review: _____

Date: _____



DC#_Title: ENV-FRM-HUN1-0083 v05_Sample Condition Upon Receipt

Effective Date: 05/24/2024

Project #

WO#: 92789136

PM: BV

Due Date: 04/21/25

CLIENT: 92- GP-HAM

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TOC, Oil and Grease, DRO/8015 (water) DOC, LLHg

**Bottom half of box is to list number of bottles

***Check all unpreserved Nitrates for chlorine

Laboratory Receiving Location: Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☐ Mechanicsville ☐ Atlanta ☐

Client _____ Profile/EZ (Circle one) _____ Notes _____

Item#	CC	BP4U-125 mL Plastic Unpreserved (N/A) (Cl-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (Cl-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic ZN Acetate & NaOH (>9)	BP4B-125 mL Plastic NaOH (pH > 12) (Cl-)	WGFU-Wide-mouthed Glass jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (Cl-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (Cl-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	DG94-40 mL Amber NH4Cl (N/A)(Cl-)	DG9H-40 mL VOA HCl (N/A)	VG9T-40 mL VOA Na2SO3 (N/A)	VG9U-40 mL VOA Unpreserved (N/A)	DG9V-40 mL VOA H3PO4 (N/A)	KP7U-50 mL Plastic Unpreserved (N/A)	V/GK (3 vials per kit)-VPH/Gas kit (N/A)	SP5T-125 mL Sterile Plastic (N/A - lab)	SP2T-250 mL Sterile Plastic (N/A - lab)	BP3R-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved (N/A) (Cl-)	VSGU-20 mL Scintillation vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)
1		2	1			2	1																					
2		2	1			2	1																					
3		2	1			2	1																					
4		2	1			2	1																					
5		2	1			2	1																					
6		2	1			2	1																					
7		2	1			2	1																					
8		2	1			2	1																					
9		2	1			2	1																					
10		2	1			2	1																					
11		2	1			2	1																					
12		2	1			2	1																					

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DENR Certification Office (i.e. Out of hold, incorrect preservative, out of temp, incorrect containers).

CHAIN-OF-CUSTODY / Analytical Request Document
The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

[illegible]

Important Note: By signing this form you are accepting Pace's NET 30 day payment terms and agreeing to late charges of 1.5% per month for any invoices not paid within 30 days.

F-ALL-Q-020 (rev 07, 15-Feb-2007)

Field Sampling Forms

Low-Flow Test Report:

Test Date / Time: 8/1/2024 12:13:26 PM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 37.4 ft Total Depth: 47.4 ft Initial Depth to Water: 25.7 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 42.4 ft Estimated Total Volume Pumped: 19.3 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.06 ft	Instrument Used: Aqua TROLL 400 Serial Number: 850724
--	--	--

Test Notes:
Appendix III and IV and Major Ions.

Weather Conditions:
Sunny, 90F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 5	
8/1/2024 12:13 PM	00:00	6.72 pH	19.56 °C	752.95 µS/cm	5.08 mg/L	29.30 NTU	-36.2 mV	25.74 ft	200.00 ml/min
8/1/2024 12:18 PM	05:00	6.72 pH	19.23 °C	754.48 µS/cm	4.38 mg/L	21.30 NTU	-35.1 mV	25.80 ft	200.00 ml/min
8/1/2024 12:23 PM	10:00	6.72 pH	19.33 °C	751.69 µS/cm	4.04 mg/L	--	-36.7 mV	25.80 ft	200.00 ml/min
8/1/2024 12:28 PM	15:00	6.72 pH	19.30 °C	749.59 µS/cm	3.78 mg/L	--	-35.6 mV	25.80 ft	200.00 ml/min
8/1/2024 12:31 PM	18:23	6.72 pH	19.19 °C	749.33 µS/cm	3.57 mg/L	8.79 NTU	-27.6 mV	25.80 ft	200.00 ml/min
8/1/2024 12:36 PM	23:23	6.72 pH	19.21 °C	744.37 µS/cm	3.29 mg/L	8.47 NTU	-36.5 mV	25.76 ft	200.00 ml/min
8/1/2024 12:41 PM	28:23	6.72 pH	19.07 °C	742.57 µS/cm	3.03 mg/L	9.30 NTU	-37.4 mV	25.76 ft	200.00 ml/min
8/1/2024 12:46 PM	33:23	6.72 pH	19.14 °C	768.07 µS/cm	1.26 mg/L	8.00 NTU	-38.2 mV	25.76 ft	200.00 ml/min
8/1/2024 12:51 PM	38:23	6.71 pH	19.31 °C	765.58 µS/cm	0.18 mg/L	7.60 NTU	-39.1 mV	25.76 ft	200.00 ml/min
8/1/2024 12:55 PM	41:34	6.71 pH	19.27 °C	760.52 µS/cm	0.17 mg/L	--	-38.8 mV	--	200.00 ml/min
8/1/2024 1:00 PM	46:34	6.71 pH	19.11 °C	762.94 µS/cm	0.16 mg/L	--	-40.6 mV	--	200.00 ml/min
8/1/2024 1:05 PM	51:48	6.72 pH	19.09 °C	765.90 µS/cm	0.15 mg/L	6.95 NTU	-32.2 mV	25.80 ft	200.00 ml/min
8/1/2024 1:10 PM	56:48	6.71 pH	19.29 °C	764.05 µS/cm	0.14 mg/L	5.58 NTU	-54.7 mV	25.76 ft	200.00 ml/min

8/1/2024 1:15 PM	01:01:48	6.71 pH	19.25 °C	763.14 µS/cm	0.13 mg/L	5.60 NTU	-54.8 mV	25.76 ft	200.00 ml/min
8/1/2024 1:20 PM	01:06:48	6.71 pH	19.26 °C	781.19 µS/cm	0.67 mg/L	6.10 NTU	-55.4 mV	25.76 ft	200.00 ml/min
8/1/2024 1:25 PM	01:11:48	6.70 pH	19.01 °C	782.39 µS/cm	0.35 mg/L	5.45 NTU	-55.0 mV	25.76 ft	200.00 ml/min
8/1/2024 1:30 PM	01:16:48	6.71 pH	18.77 °C	781.95 µS/cm	0.25 mg/L	6.10 NTU	-55.3 mV	25.76 ft	200.00 ml/min
8/1/2024 1:35 PM	01:21:48	6.71 pH	18.52 °C	779.42 µS/cm	0.19 mg/L	5.49 NTU	-55.8 mV	25.76 ft	200.00 ml/min
8/1/2024 1:40 PM	01:26:48	6.72 pH	18.29 °C	779.41 µS/cm	0.16 mg/L	5.51 NTU	-56.1 mV	25.76 ft	200.00 ml/min
8/1/2024 1:45 PM	01:31:48	6.72 pH	18.01 °C	777.88 µS/cm	0.14 mg/L	4.94 NTU	-56.7 mV	25.76 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-07	Grab.

Low-Flow Test Report:

Test Date / Time: 8/1/2024 2:01:16 PM
Project: GP-Plant Hammond
Operator Name: Thomas Kessler

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 32.2 ft Total Depth: 42.2 ft Initial Depth to Water: 25.6 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 37.2 ft Estimated Total Volume Pumped: 6 liter Flow Cell Volume: 90 ml Final Flow Rate: 100 ml/min Final Draw Down: 0.01 ft	Instrument Used: Aqua TROLL 400 Serial Number: 968202
--	--	--

Test Notes:
Appendix III and IV and Major Ions.

Weather Conditions:
Cloudy, 90 degrees.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/1/2024 2:01 PM	00:00	6.44 pH	23.87 °C	603.64 µS/cm	0.74 mg/L	60.00 NTU	-35.9 mV	25.60 ft	100.00 ml/min
8/1/2024 2:06 PM	05:00	6.44 pH	23.47 °C	610.86 µS/cm	0.57 mg/L	45.90 NTU	-38.8 mV	25.61 ft	100.00 ml/min
8/1/2024 2:11 PM	10:00	6.45 pH	23.43 °C	610.99 µS/cm	0.46 mg/L	35.30 NTU	-36.7 mV	25.61 ft	100.00 ml/min
8/1/2024 2:16 PM	15:00	6.47 pH	23.33 °C	611.56 µS/cm	0.39 mg/L	18.00 NTU	-39.0 mV	25.61 ft	100.00 ml/min
8/1/2024 2:21 PM	20:00	6.47 pH	23.21 °C	615.51 µS/cm	0.36 mg/L	12.40 NTU	-37.6 mV	25.61 ft	100.00 ml/min
8/1/2024 2:26 PM	25:00	6.48 pH	23.73 °C	610.46 µS/cm	0.37 mg/L	11.50 NTU	-40.3 mV	25.61 ft	100.00 ml/min
8/1/2024 2:31 PM	30:00	6.48 pH	23.05 °C	613.75 µS/cm	0.32 mg/L	9.31 NTU	-36.8 mV	25.61 ft	100.00 ml/min
8/1/2024 2:36 PM	35:00	6.49 pH	23.03 °C	614.07 µS/cm	0.28 mg/L	8.29 NTU	-38.4 mV	25.61 ft	100.00 ml/min
8/1/2024 2:41 PM	40:00	6.49 pH	23.06 °C	613.22 µS/cm	0.25 mg/L	6.85 NTU	-36.2 mV	25.61 ft	100.00 ml/min
8/1/2024 2:46 PM	45:00	6.48 pH	23.06 °C	611.29 µS/cm	0.24 mg/L	5.71 NTU	-37.0 mV	25.61 ft	100.00 ml/min
8/1/2024 2:51 PM	50:00	6.48 pH	23.17 °C	609.92 µS/cm	0.22 mg/L	4.96 NTU	-35.4 mV	25.61 ft	100.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.

Low-Flow Test Report:

Test Date / Time: 7/31/2024 11:03:43 AM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.45 ft Total Depth: 27.45 ft Initial Depth to Water: 16.04 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 22.45 ft Estimated Total Volume Pumped: 30 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 850724
---	---	--

Test Notes:
Appendix III and IV and Major Ions.

Weather Conditions:
Sunny, 90F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 5	
7/31/2024 11:03 AM	00:00	6.82 pH	19.06 °C	734.89 µS/cm	0.74 mg/L	--	60.9 mV	16.05 ft	200.00 ml/min
7/31/2024 11:04 AM	00:28	6.82 pH	18.65 °C	740.20 µS/cm	0.73 mg/L	165.00 NTU	66.9 mV	16.05 ft	200.00 ml/min
7/31/2024 11:08 AM	04:25	6.84 pH	19.07 °C	726.49 µS/cm	0.54 mg/L	--	63.4 mV	16.05 ft	200.00 ml/min
7/31/2024 11:11 AM	07:29	6.86 pH	19.08 °C	707.43 µS/cm	2.61 mg/L	160.00 NTU	60.0 mV	16.05 ft	200.00 ml/min
7/31/2024 11:16 AM	12:29	6.88 pH	18.89 °C	722.61 µS/cm	0.86 mg/L	180.00 NTU	63.7 mV	16.01 ft	200.00 ml/min
7/31/2024 11:21 AM	17:29	6.89 pH	18.92 °C	722.32 µS/cm	0.66 mg/L	160.00 NTU	65.6 mV	16.01 ft	200.00 ml/min
7/31/2024 11:26 AM	22:29	6.90 pH	18.92 °C	716.02 µS/cm	2.01 mg/L	134.00 NTU	68.6 mV	16.01 ft	200.00 ml/min
7/31/2024 11:31 AM	27:29	6.89 pH	18.88 °C	710.39 µS/cm	1.92 mg/L	118.00 NTU	86.5 mV	16.01 ft	200.00 ml/min
7/31/2024 11:36 AM	32:29	6.90 pH	18.87 °C	718.11 µS/cm	3.03 mg/L	110.00 NTU	90.9 mV	16.01 ft	200.00 ml/min
7/31/2024 11:41 AM	37:29	6.90 pH	18.83 °C	712.97 µS/cm	2.73 mg/L	89.00 NTU	94.6 mV	16.01 ft	200.00 ml/min
7/31/2024 11:48 AM	44:54	6.91 pH	19.23 °C	701.77 µS/cm	2.23 mg/L	75.20 NTU	46.7 mV	16.01 ft	200.00 ml/min
7/31/2024 11:53 AM	49:54	6.91 pH	19.27 °C	700.61 µS/cm	1.92 mg/L	68.00 NTU	76.7 mV	16.01 ft	200.00 ml/min
7/31/2024 11:58 AM	54:54	6.91 pH	19.10 °C	708.67 µS/cm	1.79 mg/L	49.50 NTU	98.2 mV	16.01 ft	200.00 ml/min

7/31/2024 12:03 PM	59:54	6.91 pH	19.26 °C	711.41 µS/cm	1.61 mg/L	46.50 NTU	100.9 mV	16.01 ft	200.00 ml/min
7/31/2024 12:08 PM	01:04:54	6.91 pH	19.26 °C	706.11 µS/cm	1.44 mg/L	39.40 NTU	102.8 mV	16.01 ft	200.00 ml/min
7/31/2024 12:13 PM	01:09:54	6.90 pH	19.23 °C	704.29 µS/cm	1.31 mg/L	34.30 NTU	104.1 mV	16.01 ft	200.00 ml/min
7/31/2024 12:18 PM	01:14:54	6.90 pH	19.29 °C	694.68 µS/cm	1.12 mg/L	25.30 NTU	105.9 mV	16.01 ft	200.00 ml/min
7/31/2024 12:23 PM	01:19:54	6.89 pH	19.33 °C	701.33 µS/cm	0.31 mg/L	23.60 NTU	87.1 mV	16.01 ft	200.00 ml/min
7/31/2024 12:28 PM	01:24:54	6.89 pH	19.44 °C	701.86 µS/cm	0.25 mg/L	20.60 NTU	87.5 mV	16.01 ft	200.00 ml/min
7/31/2024 12:33 PM	01:29:54	6.89 pH	19.62 °C	699.17 µS/cm	0.23 mg/L	16.60 NTU	88.7 mV	16.01 ft	200.00 ml/min
7/31/2024 12:38 PM	01:34:54	6.89 pH	19.32 °C	699.66 µS/cm	0.22 mg/L	13.40 NTU	112.5 mV	16.01 ft	200.00 ml/min
7/31/2024 12:43 PM	01:39:54	6.89 pH	19.03 °C	712.89 µS/cm	1.97 mg/L	11.00 NTU	114.6 mV	16.01 ft	200.00 ml/min
7/31/2024 12:48 PM	01:44:54	6.90 pH	19.23 °C	704.69 µS/cm	2.33 mg/L	7.76 NTU	92.0 mV	16.01 ft	200.00 ml/min
7/31/2024 12:53 PM	01:49:54	6.89 pH	19.35 °C	692.34 µS/cm	3.03 mg/L	6.06 NTU	92.8 mV	16.01 ft	200.00 ml/min
7/31/2024 12:58 PM	01:54:54	6.89 pH	19.23 °C	697.30 µS/cm	3.04 mg/L	6.26 NTU	92.1 mV	16.01 ft	200.00 ml/min
7/31/2024 1:03 PM	01:59:54	6.89 pH	19.68 °C	691.30 µS/cm	2.72 mg/L	5.14 NTU	93.8 mV	16.01 ft	200.00 ml/min
7/31/2024 1:08 PM	02:04:54	6.89 pH	19.48 °C	691.94 µS/cm	2.35 mg/L	4.23 NTU	92.3 mV	16.01 ft	200.00 ml/min
7/31/2024 1:13 PM	02:09:54	6.88 pH	19.47 °C	702.40 µS/cm	1.20 mg/L	4.18 NTU	115.8 mV	16.01 ft	200.00 ml/min
7/31/2024 1:18 PM	02:14:54	6.90 pH	19.68 °C	699.31 µS/cm	0.94 mg/L	4.03 NTU	92.5 mV	16.01 ft	200.00 ml/min
7/31/2024 1:23 PM	02:19:54	6.89 pH	19.37 °C	700.56 µS/cm	0.69 mg/L	3.34 NTU	114.2 mV	16.01 ft	200.00 ml/min
7/31/2024 1:28 PM	02:24:54	6.90 pH	19.29 °C	699.88 µS/cm	0.61 mg/L	3.17 NTU	114.0 mV	16.01 ft	200.00 ml/min
7/31/2024 1:33 PM	02:29:54	6.90 pH	19.50 °C	699.07 µS/cm	0.54 mg/L	3.03 NTU	113.7 mV	16.01 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.

Low-Flow Test Report:

Test Date / Time: 8/1/2024 9:22:19 AM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-10 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.4 ft Total Depth: 27.4 ft Initial Depth to Water: 16.45 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 22.4 ft Estimated Total Volume Pumped: 9.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 850724
---	---	--

Test Notes:
Appendix III and IV and Major Ions.

Weather Conditions:
Clear, 90F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 5	
8/1/2024 9:22 AM	00:00	6.40 pH	17.74 °C	601.81 µS/cm	1.39 mg/L	2.15 NTU	98.7 mV	16.45 ft	200.00 ml/min
8/1/2024 9:27 AM	05:00	6.53 pH	17.02 °C	614.22 µS/cm	1.74 mg/L	4.25 NTU	117.1 mV	16.45 ft	200.00 ml/min
8/1/2024 9:32 AM	10:00	6.65 pH	17.15 °C	632.15 µS/cm	0.73 mg/L	2.75 NTU	91.7 mV	16.45 ft	200.00 ml/min
8/1/2024 9:37 AM	15:00	6.69 pH	17.00 °C	649.87 µS/cm	3.39 mg/L	2.30 NTU	114.3 mV	16.45 ft	200.00 ml/min
8/1/2024 9:42 AM	20:00	6.73 pH	16.90 °C	648.63 µS/cm	3.96 mg/L	1.25 NTU	96.6 mV	16.46 ft	200.00 ml/min
8/1/2024 9:47 AM	25:00	6.77 pH	16.96 °C	667.15 µS/cm	1.22 mg/L	1.60 NTU	122.6 mV	16.47 ft	200.00 ml/min
8/1/2024 9:52 AM	30:00	6.81 pH	17.30 °C	665.88 µS/cm	1.30 mg/L	1.41 NTU	98.5 mV	16.50 ft	200.00 ml/min
8/1/2024 9:57 AM	35:00	6.83 pH	17.27 °C	667.01 µS/cm	1.05 mg/L	1.63 NTU	123.0 mV	16.50 ft	200.00 ml/min
8/1/2024 10:02 AM	40:00	6.84 pH	17.32 °C	669.10 µS/cm	1.12 mg/L	1.57 NTU	124.1 mV	16.50 ft	200.00 ml/min
8/1/2024 10:07 AM	45:00	6.85 pH	17.27 °C	667.61 µS/cm	1.15 mg/L	1.34 NTU	124.6 mV	16.50 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

HAM-PT-10	Grab.
-----------	-------

Low-Flow Test Report:

Test Date / Time: 7/31/2024 3:20:32 PM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 16.9 ft Total Depth: 26.9 ft Initial Depth to Water: 12.6 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 21.9 ft Estimated Total Volume Pumped: 18 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 850724
--	---	--

Test Notes:
Appendix III and IV and Major Ions.

Weather Conditions:
Cloudy, 90F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 5	
7/31/2024 3:20 PM	00:00	6.80 pH	19.78 °C	640.92 µS/cm	3.13 mg/L	85.70 NTU	78.2 mV	12.60 ft	200.00 ml/min
7/31/2024 3:25 PM	05:00	6.79 pH	19.43 °C	655.62 µS/cm	0.40 mg/L	76.70 NTU	74.0 mV	12.60 ft	200.00 ml/min
7/31/2024 3:30 PM	10:00	6.78 pH	19.14 °C	648.52 µS/cm	0.26 mg/L	109.50 NTU	76.6 mV	12.60 ft	200.00 ml/min
7/31/2024 3:35 PM	15:00	6.76 pH	19.19 °C	644.24 µS/cm	0.25 mg/L	103.00 NTU	56.4 mV	12.60 ft	200.00 ml/min
7/31/2024 3:40 PM	20:00	6.76 pH	19.18 °C	646.28 µS/cm	3.66 mg/L	101.00 NTU	61.5 mV	12.60 ft	200.00 ml/min
7/31/2024 3:45 PM	25:00	6.75 pH	19.18 °C	648.38 µS/cm	0.17 mg/L	89.20 NTU	50.9 mV	12.60 ft	200.00 ml/min
7/31/2024 3:51 PM	31:16	6.75 pH	19.06 °C	648.61 µS/cm	0.20 mg/L	72.10 NTU	56.4 mV	12.60 ft	200.00 ml/min
7/31/2024 3:56 PM	36:16	6.74 pH	19.26 °C	649.63 µS/cm	0.20 mg/L	64.60 NTU	47.0 mV	12.60 ft	200.00 ml/min
7/31/2024 4:01 PM	41:16	6.75 pH	19.15 °C	649.18 µS/cm	0.96 mg/L	52.10 NTU	46.4 mV	12.60 ft	200.00 ml/min
7/31/2024 4:06 PM	46:16	6.74 pH	19.04 °C	646.70 µS/cm	0.19 mg/L	40.30 NTU	45.6 mV	12.60 ft	200.00 ml/min
7/31/2024 4:11 PM	51:16	6.74 pH	18.91 °C	654.38 µS/cm	0.18 mg/L	34.60 NTU	49.9 mV	12.60 ft	200.00 ml/min
7/31/2024 4:16 PM	56:16	6.74 pH	18.96 °C	653.02 µS/cm	0.19 mg/L	24.10 NTU	49.1 mV	12.60 ft	200.00 ml/min

7/31/2024 4:21 PM	01:01:16	6.74 pH	18.98 °C	650.38 µS/cm	0.17 mg/L	10.20 NTU	48.2 mV	12.60 ft	200.00 ml/min
7/31/2024 4:26 PM	01:06:16	6.74 pH	18.92 °C	653.66 µS/cm	0.43 mg/L	9.70 NTU	49.0 mV	12.60 ft	200.00 ml/min
7/31/2024 4:31 PM	01:11:16	6.74 pH	18.99 °C	650.77 µS/cm	0.22 mg/L	11.00 NTU	42.6 mV	12.60 ft	200.00 ml/min
7/31/2024 4:36 PM	01:16:16	6.74 pH	18.66 °C	652.62 µS/cm	0.15 mg/L	7.20 NTU	47.6 mV	12.60 ft	200.00 ml/min
7/31/2024 4:41 PM	01:21:16	6.73 pH	18.72 °C	653.47 µS/cm	0.14 mg/L	6.69 NTU	40.7 mV	12.60 ft	200.00 ml/min
7/31/2024 4:46 PM	01:26:16	6.75 pH	18.03 °C	654.97 µS/cm	0.16 mg/L	4.77 NTU	47.3 mV	12.60 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-11	Grab.

Low-Flow Test Report:

Test Date / Time: 7/31/2024 5:30:06 PM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-12 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.3 ft Total Depth: 27.3 ft Initial Depth to Water: 16.2 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 22.3 ft Estimated Total Volume Pumped: 8 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.04 ft	Instrument Used: Aqua TROLL 400 Serial Number: 850724
--	---	--

Test Notes:
Appendix III and IV and Major Ions.

Weather Conditions:
Sunny, 90F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 5	
7/31/2024 5:30 PM	00:00	6.39 pH	19.31 °C	545.95 µS/cm	4.52 mg/L	16.20 NTU	87.1 mV	12.45 ft	200.00 ml/min
7/31/2024 5:35 PM	05:00	6.54 pH	19.06 °C	689.72 µS/cm	0.83 mg/L	11.10 NTU	91.7 mV	12.45 ft	200.00 ml/min
7/31/2024 5:40 PM	10:00	6.64 pH	18.66 °C	691.44 µS/cm	0.83 mg/L	8.60 NTU	112.6 mV	12.49 ft	200.00 ml/min
7/31/2024 5:45 PM	15:00	6.69 pH	18.58 °C	685.60 µS/cm	0.85 mg/L	7.02 NTU	112.5 mV	12.49 ft	200.00 ml/min
7/31/2024 5:50 PM	20:00	6.71 pH	18.65 °C	679.86 µS/cm	0.86 mg/L	6.60 NTU	88.1 mV	12.49 ft	200.00 ml/min
7/31/2024 5:55 PM	25:00	6.70 pH	18.68 °C	679.76 µS/cm	0.87 mg/L	6.56 NTU	86.0 mV	12.49 ft	200.00 ml/min
7/31/2024 6:00 PM	30:00	6.71 pH	18.65 °C	676.96 µS/cm	0.89 mg/L	5.80 NTU	107.1 mV	12.49 ft	200.00 ml/min
7/31/2024 6:05 PM	35:00	6.74 pH	18.58 °C	678.41 µS/cm	1.00 mg/L	4.74 NTU	85.6 mV	12.49 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-12	Grab.
HAM-AP1-FD-01	Grab.

Low-Flow Test Report:

Test Date / Time: 8/1/2024 11:51:49 AM
Project: GP-Plant Hammond
Operator Name: Thomas Kessler

Location Name: PT-13 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.45 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 6 liter Flow Cell Volume: 90 ml Final Flow Rate: 100 ml/min Final Draw Down: -0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 968202
---	---	--

Test Notes:
Appendix III and IV and Major Ions.

Weather Conditions:
Clear, 90F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/1/2024 11:51 AM	00:00	6.68 pH	23.54 °C	754.87 µS/cm	3.03 mg/L	12.20 NTU	-78.1 mV	25.40 ft	100.00 ml/min
8/1/2024 11:56 AM	05:00	6.69 pH	23.54 °C	750.77 µS/cm	2.83 mg/L	5.00 NTU	-77.7 mV	25.40 ft	100.00 ml/min
8/1/2024 12:01 PM	10:00	6.69 pH	23.47 °C	744.14 µS/cm	2.65 mg/L	6.26 NTU	-83.0 mV	25.40 ft	100.00 ml/min
8/1/2024 12:06 PM	15:00	6.69 pH	23.69 °C	741.73 µS/cm	2.41 mg/L	4.19 NTU	-80.0 mV	25.40 ft	100.00 ml/min
8/1/2024 12:11 PM	20:00	6.70 pH	23.69 °C	739.10 µS/cm	2.21 mg/L	3.39 NTU	-84.8 mV	25.40 ft	100.00 ml/min
8/1/2024 12:16 PM	25:00	6.69 pH	23.72 °C	733.93 µS/cm	2.04 mg/L	2.30 NTU	-85.5 mV	25.40 ft	100.00 ml/min
8/1/2024 12:21 PM	30:00	6.69 pH	23.85 °C	733.77 µS/cm	1.87 mg/L	1.88 NTU	-85.8 mV	25.40 ft	100.00 ml/min
8/1/2024 12:26 PM	35:00	6.68 pH	23.95 °C	730.22 µS/cm	1.72 mg/L	1.72 NTU	-86.3 mV	25.40 ft	100.00 ml/min
8/1/2024 12:31 PM	40:00	6.68 pH	24.08 °C	725.69 µS/cm	1.57 mg/L	2.12 NTU	-82.5 mV	25.40 ft	100.00 ml/min
8/1/2024 12:36 PM	45:00	6.68 pH	24.03 °C	720.46 µS/cm	1.46 mg/L	1.99 NTU	-82.2 mV	25.40 ft	100.00 ml/min
8/1/2024 12:41 PM	50:00	6.69 pH	23.83 °C	719.27 µS/cm	1.38 mg/L	2.53 NTU	-86.2 mV	25.40 ft	100.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-13	Grab.

Low-Flow Test Report:

Test Date / Time: 8/1/2024 3:24:13 PM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-14 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.35 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 17.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 850724
---	---	--

Test Notes:
Appendix III and IV and Major Ions.

Weather Conditions:
Sunny, 90F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 5	
8/1/2024 3:24 PM	00:00	6.87 pH	19.42 °C	807.42 µS/cm	5.10 mg/L	6.66 NTU	-104.9 mV	25.35 ft	200.00 ml/min
8/1/2024 3:29 PM	05:00	6.86 pH	18.98 °C	807.86 µS/cm	4.81 mg/L	5.53 NTU	-103.1 mV	25.35 ft	200.00 ml/min
8/1/2024 3:34 PM	10:00	6.86 pH	18.87 °C	813.03 µS/cm	4.53 mg/L	4.43 NTU	-103.4 mV	25.35 ft	200.00 ml/min
8/1/2024 3:39 PM	15:00	6.85 pH	19.01 °C	813.88 µS/cm	4.20 mg/L	3.16 NTU	-104.2 mV	25.35 ft	200.00 ml/min
8/1/2024 3:44 PM	20:00	6.86 pH	19.02 °C	813.37 µS/cm	3.89 mg/L	2.86 NTU	-104.4 mV	25.35 ft	200.00 ml/min
8/1/2024 3:49 PM	25:00	6.86 pH	19.01 °C	812.66 µS/cm	3.60 mg/L	2.70 NTU	-104.6 mV	25.35 ft	200.00 ml/min
8/1/2024 3:54 PM	30:00	6.86 pH	19.01 °C	812.68 µS/cm	3.36 mg/L	2.24 NTU	-111.4 mV	25.35 ft	200.00 ml/min
8/1/2024 3:59 PM	35:00	6.85 pH	19.26 °C	812.80 µS/cm	3.10 mg/L	2.08 NTU	-105.1 mV	25.35 ft	200.00 ml/min
8/1/2024 4:07 PM	42:56	6.85 pH	19.24 °C	810.89 µS/cm	2.77 mg/L	1.96 NTU	-105.4 mV	25.35 ft	200.00 ml/min
8/1/2024 4:12 PM	47:56	6.85 pH	19.22 °C	809.21 µS/cm	2.63 mg/L	1.74 NTU	-105.4 mV	25.35 ft	200.00 ml/min
8/1/2024 4:17 PM	52:56	6.85 pH	19.29 °C	810.34 µS/cm	2.44 mg/L	1.70 NTU	-105.6 mV	25.35 ft	200.00 ml/min
8/1/2024 4:22 PM	57:56	6.85 pH	19.35 °C	809.68 µS/cm	2.26 mg/L	1.56 NTU	-105.9 mV	25.35 ft	200.00 ml/min
8/1/2024 4:27 PM	01:02:56	6.84 pH	19.39 °C	809.77 µS/cm	2.08 mg/L	1.44 NTU	-106.3 mV	25.35 ft	200.00 ml/min
8/1/2024 4:32 PM	01:07:56	6.85 pH	19.34 °C	809.78 µS/cm	1.93 mg/L	1.40 NTU	-106.0 mV	25.35 ft	200.00 ml/min

8/1/2024 4:37 PM	01:12:56	6.85 pH	19.35 °C	821.31 µS/cm	0.20 mg/L	1.22 NTU	-105.7 mV	25.35 ft	200.00 ml/min
8/1/2024 4:42 PM	01:17:56	6.85 pH	19.32 °C	824.22 µS/cm	0.16 mg/L	1.10 NTU	-113.6 mV	25.35 ft	200.00 ml/min
8/1/2024 4:47 PM	01:22:56	6.84 pH	19.24 °C	824.67 µS/cm	0.16 mg/L	0.96 NTU	-114.0 mV	25.35 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-14	Grab.

Low-Flow Test Report:

Test Date / Time: 8/1/2024 9:16:53 AM
Project: GP-Plant Hammond
Operator Name: Thomas Kessler

Location Name: PT-15 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.25 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 9.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 100 ml/min Final Draw Down: 0.15 ft	Instrument Used: Aqua TROLL 400 Serial Number: 968202
---	--	--

Test Notes:
Appendix III and IV and Major Ions.

Weather Conditions:
Clear, 80F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/1/2024 9:16 AM	00:00	6.63 pH	22.54 °C	696.34 µS/cm	6.57 mg/L	11.35 NTU	-42.2 mV	26.00 ft	100.00 ml/min
8/1/2024 9:21 AM	05:00	6.66 pH	22.79 °C	737.62 µS/cm	5.93 mg/L	6.99 NTU	-48.3 mV	25.30 ft	100.00 ml/min
8/1/2024 9:26 AM	10:00	6.70 pH	22.58 °C	731.68 µS/cm	5.45 mg/L	7.21 NTU	-57.9 mV	25.40 ft	100.00 ml/min
8/1/2024 9:31 AM	15:00	6.72 pH	22.82 °C	728.27 µS/cm	5.03 mg/L	1.84 NTU	-60.1 mV	25.40 ft	100.00 ml/min
8/1/2024 9:36 AM	20:00	6.73 pH	22.93 °C	726.92 µS/cm	4.67 mg/L	2.51 NTU	-62.3 mV	25.40 ft	100.00 ml/min
8/1/2024 9:41 AM	25:00	6.74 pH	23.04 °C	723.93 µS/cm	4.33 mg/L	2.49 NTU	-56.3 mV	25.40 ft	100.00 ml/min
8/1/2024 9:46 AM	30:00	6.75 pH	23.12 °C	720.83 µS/cm	4.06 mg/L	2.21 NTU	-65.5 mV	25.40 ft	100.00 ml/min
8/1/2024 9:51 AM	35:00	6.75 pH	23.15 °C	719.23 µS/cm	3.75 mg/L	1.54 NTU	-67.0 mV	25.40 ft	100.00 ml/min
8/1/2024 9:56 AM	40:00	6.75 pH	23.15 °C	723.09 µS/cm	3.50 mg/L	2.00 NTU	-67.4 mV	25.40 ft	100.00 ml/min
8/1/2024 10:01 AM	45:00	6.76 pH	23.33 °C	720.76 µS/cm	3.26 mg/L	2.94 NTU	-68.1 mV	25.40 ft	100.00 ml/min
8/1/2024 10:06 AM	50:00	6.76 pH	23.40 °C	717.67 µS/cm	3.03 mg/L	1.67 NTU	-69.5 mV	25.40 ft	100.00 ml/min
8/1/2024 10:11 AM	55:00	6.77 pH	23.38 °C	714.14 µS/cm	2.82 mg/L	2.00 NTU	-69.7 mV	25.40 ft	100.00 ml/min
8/1/2024 10:16 AM	01:00:00	6.77 pH	23.53 °C	711.13 µS/cm	2.60 mg/L	0.41 NTU	-69.7 mV	25.40 ft	100.00 ml/min

8/1/2024 10:21 AM	01:05:00	6.77 pH	23.55 °C	708.44 µS/cm	2.42 mg/L	0.38 NTU	-70.3 mV	25.40 ft	100.00 ml/min
8/1/2024 10:26 AM	01:10:00	6.78 pH	23.52 °C	708.27 µS/cm	2.24 mg/L	0.51 NTU	-71.1 mV	25.40 ft	100.00 ml/min
8/1/2024 10:31 AM	01:15:00	6.77 pH	23.62 °C	705.42 µS/cm	2.08 mg/L	1.78 NTU	-64.6 mV	25.40 ft	100.00 ml/min
8/1/2024 10:36 AM	01:20:00	6.78 pH	23.65 °C	708.56 µS/cm	2.02 mg/L	0.95 NTU	-72.7 mV	25.40 ft	100.00 ml/min
8/1/2024 10:41 AM	01:25:00	6.79 pH	23.76 °C	705.43 µS/cm	1.89 mg/L	0.82 NTU	-67.7 mV	25.40 ft	100.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-15	Grab.

Low-Flow Test Report:

Test Date / Time: 8/12/2024 1:43:12 PM
Project: Plant Hammond
Operator Name: Elisabeth Russell

Location Name: MW-53 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 26 ft Total Depth: 36 ft Initial Depth to Water: 16.76 ft	Pump Type: Peristaltic Tubing Type: Poly Pump Intake From TOC: 31 ft Estimated Total Volume Pumped: 11 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.06 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080293
--	--	---

Test Notes: Metals and Major Ions.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 10	+/- 0.5	
8/12/2024 1:43 PM	00:00	6.75 pH	21.18 °C	657.99 µS/cm	0.34 mg/L	1.59 NTU	107.6 mV	16.82 ft	200.00 ml/min
8/12/2024 1:48 PM	05:00	6.76 pH	21.37 °C	665.25 µS/cm	0.86 mg/L	1.43 NTU	83.3 mV	16.82 ft	200.00 ml/min
8/12/2024 1:53 PM	10:39	6.74 pH	21.49 °C	663.54 µS/cm	0.74 mg/L	1.30 NTU	90.9 mV	16.82 ft	200.00 ml/min
8/12/2024 1:58 PM	15:39	6.73 pH	21.69 °C	664.37 µS/cm	0.60 mg/L	1.19 NTU	77.9 mV	16.82 ft	200.00 ml/min
8/12/2024 2:03 PM	20:39	6.78 pH	21.49 °C	665.29 µS/cm	0.66 mg/L	0.97 NTU	96.2 mV	16.82 ft	200.00 ml/min
8/12/2024 2:08 PM	25:39	6.76 pH	21.44 °C	666.14 µS/cm	0.44 mg/L	0.83 NTU	94.6 mV	16.82 ft	200.00 ml/min
8/12/2024 2:13 PM	30:39	6.74 pH	21.55 °C	665.44 µS/cm	0.62 mg/L	0.76 NTU	74.3 mV	16.82 ft	200.00 ml/min
8/12/2024 2:18 PM	35:39	6.70 pH	21.65 °C	663.94 µS/cm	0.76 mg/L	0.71 NTU	73.8 mV	16.82 ft	200.00 ml/min
8/12/2024 2:23 PM	40:39	6.72 pH	21.56 °C	668.84 µS/cm	0.47 mg/L	0.54 NTU	89.5 mV	16.82 ft	200.00 ml/min
8/12/2024 2:28 PM	45:39	6.96 pH	23.26 °C	1.18 µS/cm	8.41 mg/L	0.53 NTU	70.3 mV	16.82 ft	200.00 ml/min
8/12/2024 2:33 PM	50:39	6.79 pH	22.94 °C	649.18 µS/cm	0.38 mg/L	0.51 NTU	70.7 mV	16.82 ft	200.00 ml/min
8/12/2024 2:38 PM	55:39	6.75 pH	22.04 °C	669.18 µS/cm	0.28 mg/L	0.47 NTU	86.8 mV	16.82 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-MW-53	Grab.

Low-Flow Test Report:

Test Date / Time: 8/12/2024 11:09:27 AM
Project: Plant Hammond
Operator Name: Elisabeth Russell

Location Name: MW-54 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 28 ft Total Depth: 38 ft Initial Depth to Water: 25.75 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 33 ft Estimated Total Volume Pumped: 16 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.18 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080293
--	--	---

Test Notes: Metals and Major Ions.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 10	+/- 0.5	
8/12/2024 11:09 AM	00:00	5.36 pH	22.98 °C	508.75 µS/cm	1.00 mg/L	90.90 NTU	203.0 mV	25.93 ft	200.00 ml/min
8/12/2024 11:14 AM	05:00	5.71 pH	22.36 °C	534.05 µS/cm	0.74 mg/L	88.70 NTU	143.2 mV	25.93 ft	200.00 ml/min
8/12/2024 11:19 AM	10:00	5.91 pH	22.39 °C	556.08 µS/cm	0.56 mg/L	85.30 NTU	155.4 mV	25.93 ft	200.00 ml/min
8/12/2024 11:24 AM	15:00	6.06 pH	22.32 °C	568.83 µS/cm	0.43 mg/L	84.00 NTU	105.8 mV	25.93 ft	200.00 ml/min
8/12/2024 11:29 AM	20:00	6.18 pH	22.45 °C	585.26 µS/cm	0.31 mg/L	67.30 NTU	115.5 mV	25.93 ft	200.00 ml/min
8/12/2024 11:34 AM	25:00	6.33 pH	22.52 °C	602.23 µS/cm	0.20 mg/L	40.40 NTU	76.7 mV	25.93 ft	200.00 ml/min
8/12/2024 11:39 AM	30:00	6.41 pH	22.42 °C	615.34 µS/cm	0.15 mg/L	30.30 NTU	66.2 mV	25.93 ft	200.00 ml/min
8/12/2024 11:44 AM	35:00	6.47 pH	22.45 °C	623.44 µS/cm	0.11 mg/L	27.60 NTU	58.1 mV	25.93 ft	200.00 ml/min
8/12/2024 11:49 AM	40:00	6.52 pH	22.45 °C	631.01 µS/cm	0.09 mg/L	22.80 NTU	48.8 mV	25.93 ft	200.00 ml/min
8/12/2024 11:54 AM	45:00	6.54 pH	22.34 °C	630.80 µS/cm	0.11 mg/L	19.70 NTU	46.7 mV	25.93 ft	200.00 ml/min
8/12/2024 11:59 AM	50:00	6.55 pH	22.40 °C	630.35 µS/cm	0.12 mg/L	16.70 NTU	43.6 mV	25.93 ft	200.00 ml/min
8/12/2024 12:04 PM	55:00	6.58 pH	22.48 °C	633.63 µS/cm	0.11 mg/L	14.80 NTU	35.2 mV	25.93 ft	200.00 ml/min
8/12/2024 12:09 PM	01:00:00	6.57 pH	22.45 °C	635.29 µS/cm	0.11 mg/L	13.20 NTU	35.2 mV	25.93 ft	200.00 ml/min
8/12/2024 12:14 PM	01:05:00	6.58 pH	22.44 °C	636.93 µS/cm	0.11 mg/L	9.70 NTU	34.9 mV	25.93 ft	200.00 ml/min
8/12/2024 12:19 PM	01:10:00	6.58 pH	22.52 °C	636.79 µS/cm	0.11 mg/L	7.60 NTU	34.6 mV	25.93 ft	200.00 ml/min

8/12/2024 12:24 PM	01:15:00	6.59 pH	22.50 °C	641.34 µS/cm	0.11 mg/L	6.70 NTU	31.6 mV	25.93 ft	200.00 ml/min
8/12/2024 12:29 PM	01:20:00	6.61 pH	22.47 °C	640.87 µS/cm	0.10 mg/L	5.00 NTU	29.5 mV	25.93 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-MW-54	Grab,

Low-Flow Test Report:

Test Date / Time: 8/9/2024 11:27:52 AM
Project: Plant Hammond
Operator Name: Elisabeth Russell

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 36.73 ft Total Depth: 46.73 ft Initial Depth to Water: 25.65 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 42 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080293
---	---	---

Test Notes: Metals.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 10	+/- 0.5	
8/9/2024 11:27 AM	00:00	6.96 pH	21.46 °C	770.26 µS/cm	0.20 mg/L	75.10 NTU	-82.1 mV	25.65 ft	200.00 ml/min
8/9/2024 11:32 AM	05:00	6.96 pH	21.11 °C	768.48 µS/cm	0.13 mg/L	40.30 NTU	-85.0 mV	25.65 ft	200.00 ml/min
8/9/2024 11:37 AM	10:00	6.95 pH	20.98 °C	773.06 µS/cm	0.11 mg/L	14.50 NTU	-92.6 mV	25.65 ft	200.00 ml/min
8/9/2024 11:42 AM	15:00	6.95 pH	20.94 °C	773.55 µS/cm	0.09 mg/L	10.30 NTU	-86.3 mV	25.65 ft	200.00 ml/min
8/9/2024 11:47 AM	20:00	6.94 pH	20.93 °C	771.79 µS/cm	0.07 mg/L	7.73 NTU	-85.9 mV	25.65 ft	200.00 ml/min
8/9/2024 11:52 AM	25:00	6.93 pH	20.89 °C	773.14 µS/cm	0.07 mg/L	4.19 NTU	-85.5 mV	25.65 ft	200.00 ml/min
8/9/2024 11:57 AM	30:00	6.93 pH	20.75 °C	772.04 µS/cm	0.06 mg/L	2.62 NTU	-85.3 mV	25.65 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-07	Grab.

Low-Flow Test Report:

Test Date / Time: 8/8/2024 2:44:36 PM
Project: Plant Hammond
Operator Name: Elisabeth Russell

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 31.95 ft Total Depth: 41.95 ft Initial Depth to Water: 25.73 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 36 ft Estimated Total Volume Pumped: 41.75 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.07 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080293
--	---	---

Test Notes: Metals.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 10	+/- 0.5	
8/8/2024 2:44 PM	00:00	6.47 pH	22.98 °C	615.23 µS/cm	0.10 mg/L	10,000.0 NTU	-49.4 mV	25.79 ft	200.00 ml/min
8/8/2024 2:49 PM	05:00	6.36 pH	21.99 °C	636.89 µS/cm	0.10 mg/L	10,000.0 NTU	-54.1 mV	25.79 ft	200.00 ml/min
8/8/2024 2:54 PM	10:00	6.36 pH	21.60 °C	645.82 µS/cm	0.10 mg/L	10,000.0 NTU	-51.1 mV	25.80 ft	200.00 ml/min
8/8/2024 2:59 PM	15:00	6.35 pH	21.65 °C	647.74 µS/cm	0.09 mg/L	10,000.0 NTU	-40.7 mV	25.80 ft	200.00 ml/min
8/8/2024 3:04 PM	20:00	6.36 pH	21.77 °C	647.74 µS/cm	0.09 mg/L	10,000.0 NTU	-47.7 mV	25.80 ft	200.00 ml/min
8/8/2024 3:09 PM	25:00	6.36 pH	21.57 °C	647.59 µS/cm	0.08 mg/L	100,000 NTU	-47.2 mV	25.80 ft	200.00 ml/min
8/8/2024 3:14 PM	30:00	6.37 pH	21.19 °C	649.46 µS/cm	0.10 mg/L	105.10 NTU	-46.3 mV	25.80 ft	200.00 ml/min
8/8/2024 3:19 PM	35:00	6.37 pH	21.47 °C	650.34 µS/cm	0.07 mg/L	91.20 NTU	-38.0 mV	25.80 ft	200.00 ml/min
8/8/2024 3:24 PM	40:00	6.37 pH	21.42 °C	650.38 µS/cm	0.07 mg/L	87.30 NTU	-45.9 mV	25.80 ft	200.00 ml/min
8/8/2024 3:29 PM	45:00	6.36 pH	21.24 °C	655.64 µS/cm	0.07 mg/L	73.70 NTU	-37.2 mV	25.80 ft	200.00 ml/min
8/8/2024 3:34 PM	50:00	6.38 pH	21.06 °C	654.60 µS/cm	0.07 mg/L	72.10 NTU	-45.4 mV	25.80 ft	200.00 ml/min
8/8/2024 3:39 PM	55:00	6.38 pH	20.82 °C	656.42 µS/cm	0.06 mg/L	67.40 NTU	-36.8 mV	25.80 ft	200.00 ml/min
8/8/2024 3:44 PM	01:00:00	6.39 pH	20.67 °C	657.66 µS/cm	0.06 mg/L	50.10 NTU	-36.5 mV	25.80 ft	200.00 ml/min
8/8/2024 3:49 PM	01:05:00	6.39 pH	20.73 °C	657.09 µS/cm	0.06 mg/L	67.20 NTU	-45.1 mV	25.80 ft	200.00 ml/min
8/8/2024 3:54 PM	01:10:00	6.40 pH	20.70 °C	659.56 µS/cm	0.06 mg/L	55.30 NTU	-37.1 mV	25.80 ft	200.00 ml/min

8/8/2024 3:59 PM	01:15:00	6.41 pH	20.76 °C	659.08 µS/cm	0.05 mg/L	50.20 NTU	-45.6 mV	25.80 ft	200.00 ml/min
8/8/2024 4:04 PM	01:20:00	6.41 pH	20.72 °C	659.82 µS/cm	0.05 mg/L	47.00 NTU	-36.8 mV	25.80 ft	200.00 ml/min
8/8/2024 4:09 PM	01:25:00	6.40 pH	21.73 °C	661.32 µS/cm	0.04 mg/L	55.00 NTU	-47.6 mV	25.80 ft	200.00 ml/min
8/8/2024 4:14 PM	01:30:00	6.41 pH	21.69 °C	655.98 µS/cm	0.05 mg/L	62.00 NTU	-38.3 mV	25.80 ft	200.00 ml/min
8/8/2024 4:19 PM	01:35:00	6.41 pH	21.02 °C	650.30 µS/cm	0.07 mg/L	40.10 NTU	-35.6 mV	25.80 ft	200.00 ml/min
8/8/2024 4:24 PM	01:40:00	6.40 pH	20.64 °C	657.15 µS/cm	0.06 mg/L	33.20 NTU	-43.4 mV	25.80 ft	200.00 ml/min
8/8/2024 4:29 PM	01:45:00	6.42 pH	20.67 °C	661.90 µS/cm	0.09 mg/L	28.50 NTU	-35.8 mV	25.80 ft	200.00 ml/min
8/8/2024 4:34 PM	01:50:00	6.43 pH	21.21 °C	660.54 µS/cm	0.09 mg/L	22.40 NTU	-29.5 mV	25.80 ft	200.00 ml/min
8/8/2024 4:39 PM	01:55:00	6.43 pH	20.65 °C	659.43 µS/cm	0.07 mg/L	18.90 NTU	-39.2 mV	25.80 ft	200.00 ml/min
8/8/2024 4:44 PM	02:00:00	6.43 pH	20.49 °C	661.76 µS/cm	0.07 mg/L	16.70 NTU	-31.9 mV	25.80 ft	200.00 ml/min
8/8/2024 4:49 PM	02:05:00	6.44 pH	20.61 °C	662.62 µS/cm	0.06 mg/L	14.40 NTU	-41.1 mV	25.80 ft	200.00 ml/min
8/8/2024 4:54 PM	02:10:00	6.44 pH	20.54 °C	662.47 µS/cm	0.07 mg/L	13.70 NTU	-33.1 mV	25.80 ft	200.00 ml/min
8/8/2024 4:59 PM	02:15:00	6.44 pH	20.42 °C	664.23 µS/cm	0.10 mg/L	12.10 NTU	-40.9 mV	25.80 ft	200.00 ml/min
8/8/2024 5:04 PM	02:20:00	6.44 pH	20.48 °C	662.67 µS/cm	0.12 mg/L	12.50 NTU	-32.2 mV	25.80 ft	200.00 ml/min
8/8/2024 5:09 PM	02:25:00	6.44 pH	20.40 °C	661.85 µS/cm	0.12 mg/L	11.30 NTU	-39.5 mV	25.80 ft	200.00 ml/min
8/8/2024 5:14 PM	02:30:00	6.43 pH	20.48 °C	661.99 µS/cm	0.12 mg/L	10.20 NTU	-39.3 mV	25.80 ft	200.00 ml/min
8/8/2024 5:19 PM	02:35:00	6.45 pH	20.55 °C	663.86 µS/cm	0.12 mg/L	--	-40.4 mV	25.80 ft	200.00 ml/min
8/8/2024 5:24 PM	02:40:00	6.49 pH	20.39 °C	671.92 µS/cm	0.11 mg/L	--	-37.6 mV	25.80 ft	200.00 ml/min
8/8/2024 5:29 PM	02:45:00	6.46 pH	20.28 °C	663.31 µS/cm	0.11 mg/L	--	-32.0 mV	25.80 ft	200.00 ml/min
8/8/2024 5:34 PM	02:50:00	6.46 pH	20.27 °C	665.00 µS/cm	0.10 mg/L	--	-40.0 mV	25.80 ft	200.00 ml/min
8/8/2024 5:39 PM	02:55:00	6.47 pH	20.33 °C	668.23 µS/cm	0.10 mg/L	--	-32.0 mV	25.80 ft	200.00 ml/min
8/8/2024 5:44 PM	03:00:00	6.46 pH	20.25 °C	665.15 µS/cm	0.10 mg/L	--	-39.9 mV	25.80 ft	200.00 ml/min
8/8/2024 5:49 PM	03:05:00	6.47 pH	20.16 °C	666.16 µS/cm	0.10 mg/L	--	-31.9 mV	25.80 ft	200.00 ml/min
8/8/2024 5:54 PM	03:10:00	6.47 pH	20.11 °C	666.21 µS/cm	0.10 mg/L	--	-31.3 mV	25.80 ft	200.00 ml/min
8/8/2024 5:59 PM	03:15:00	6.47 pH	20.12 °C	667.84 µS/cm	0.09 mg/L	--	-31.5 mV	25.80 ft	200.00 ml/min
8/8/2024 6:04 PM	03:20:00	6.48 pH	20.10 °C	666.62 µS/cm	0.10 mg/L	4.89 NTU	-39.6 mV	25.80 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.

Low-Flow Test Report:

Test Date / Time: 8/6/2024 9:04:56 AM
Project: Plant Hammond
Operator Name: Elisabeth Russell

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20 ft Total Depth: 30 ft Initial Depth to Water: 16.19 ft	Pump Type: Peri Pump Tubing Type: Poly Pump Intake From TOC: 25 ft Estimated Total Volume Pumped: 20 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.06 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080293
---	---	---

Test Notes: Metals.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 10	+/- 0.5	
8/6/2024 9:04 AM	00:00	6.90 pH	21.33 °C	694.59 µS/cm	0.25 mg/L	28.80 NTU	90.9 mV	16.21 ft	200.00 ml/min
8/6/2024 9:09 AM	05:00	6.94 pH	20.66 °C	687.99 µS/cm	0.16 mg/L	24.90 NTU	78.4 mV	16.23 ft	200.00 ml/min
8/6/2024 9:14 AM	10:00	6.90 pH	20.48 °C	683.26 µS/cm	0.17 mg/L	24.50 NTU	55.6 mV	16.25 ft	200.00 ml/min
8/6/2024 9:19 AM	15:00	6.91 pH	20.39 °C	681.26 µS/cm	0.18 mg/L	33.40 NTU	49.0 mV	16.25 ft	200.00 ml/min
8/6/2024 9:24 AM	20:00	6.96 pH	20.48 °C	678.29 µS/cm	0.19 mg/L	48.60 NTU	43.8 mV	16.25 ft	200.00 ml/min
8/6/2024 9:29 AM	25:00	6.95 pH	20.47 °C	669.78 µS/cm	0.19 mg/L	44.50 NTU	39.6 mV	16.25 ft	200.00 ml/min
8/6/2024 9:34 AM	30:00	6.98 pH	20.41 °C	664.70 µS/cm	0.19 mg/L	45.30 NTU	37.6 mV	16.25 ft	200.00 ml/min
8/6/2024 9:39 AM	35:00	6.96 pH	20.29 °C	681.10 µS/cm	0.18 mg/L	44.20 NTU	39.1 mV	16.25 ft	200.00 ml/min
8/6/2024 9:44 AM	40:00	6.97 pH	20.83 °C	685.50 µS/cm	0.17 mg/L	39.40 NTU	37.7 mV	16.25 ft	150.00 ml/min
8/6/2024 9:49 AM	45:00	6.98 pH	21.16 °C	680.55 µS/cm	0.15 mg/L	37.30 NTU	37.2 mV	16.25 ft	150.00 ml/min
8/6/2024 9:54 AM	50:00	6.97 pH	21.19 °C	666.37 µS/cm	0.14 mg/L	34.90 NTU	34.6 mV	16.25 ft	150.00 ml/min
8/6/2024 9:59 AM	55:00	6.96 pH	21.25 °C	675.24 µS/cm	0.13 mg/L	31.70 NTU	35.5 mV	16.25 ft	150.00 ml/min
8/6/2024 10:04 AM	01:00:00	6.97 pH	21.15 °C	662.27 µS/cm	0.11 mg/L	28.30 NTU	32.8 mV	16.25 ft	150.00 ml/min
8/6/2024 10:09 AM	01:05:00	6.98 pH	21.09 °C	663.76 µS/cm	0.20 mg/L	23.70 NTU	32.6 mV	16.25 ft	150.00 ml/min
8/6/2024 10:14 AM	01:10:00	6.97 pH	21.22 °C	667.07 µS/cm	0.26 mg/L	21.40 NTU	32.7 mV	16.25 ft	150.00 ml/min

8/6/2024 10:21 AM	01:16:51	6.96 pH	21.37 °C	664.36 µS/cm	0.22 mg/L	18.20 NTU	35.8 mV	16.25 ft	150.00 ml/min
8/6/2024 10:26 AM	01:21:51	6.97 pH	21.43 °C	679.71 µS/cm	0.12 mg/L	14.40 NTU	32.9 mV	16.25 ft	150.00 ml/min
8/6/2024 10:31 AM	01:26:51	6.96 pH	21.59 °C	680.60 µS/cm	0.11 mg/L	11.50 NTU	34.5 mV	16.25 ft	150.00 ml/min
8/6/2024 10:36 AM	01:31:51	6.97 pH	21.55 °C	673.65 µS/cm	0.23 mg/L	11.20 NTU	32.5 mV	16.25 ft	150.00 ml/min
8/6/2024 10:41 AM	01:36:51	6.95 pH	21.78 °C	675.72 µS/cm	0.16 mg/L	10.75 NTU	34.6 mV	16.25 ft	150.00 ml/min
8/6/2024 10:46 AM	01:41:51	6.94 pH	21.91 °C	677.83 µS/cm	0.16 mg/L	9.70 NTU	35.2 mV	16.25 ft	150.00 ml/min
8/6/2024 10:51 AM	01:46:51	6.95 pH	22.56 °C	660.67 µS/cm	0.17 mg/L	8.04 NTU	33.1 mV	16.25 ft	150.00 ml/min
8/6/2024 10:56 AM	01:51:51	6.95 pH	22.76 °C	661.05 µS/cm	0.23 mg/L	6.35 NTU	34.8 mV	16.25 ft	150.00 ml/min
8/6/2024 11:01 AM	01:56:51	6.93 pH	22.69 °C	660.00 µS/cm	0.22 mg/L	4.97 NTU	36.6 mV	16.25 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.

Low-Flow Test Report:

Test Date / Time: 8/5/2024 4:29:00 PM

Project: Plant Hammond

Operator Name: Elisabeth Russell

Location Name: PT-10 Well Diameter: 2 in Screen Length: 10 ft Top of Screen: 21.07 ft Total Depth: 31.07 ft Initial Depth to Water: 16.21 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 25 ft Estimated Total Volume Pumped: 6.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080293
---	---	---

Test Notes: Metals.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 10	+/- 0.5	
8/5/2024 4:29 PM	00:00	6.85 pH	22.28 °C	657.87 µS/cm	0.12 mg/L	6.47 NTU	45.3 mV	16.21 ft	200.00 ml/min
8/5/2024 4:34 PM	05:00	6.87 pH	22.77 °C	645.50 µS/cm	0.11 mg/L	5.76 NTU	40.6 mV	16.25 ft	200.00 ml/min
8/5/2024 4:39 PM	10:00	6.86 pH	25.50 °C	648.42 µS/cm	0.11 mg/L	5.07 NTU	41.6 mV	16.27 ft	200.00 ml/min
8/5/2024 4:44 PM	15:00	6.84 pH	22.52 °C	643.67 µS/cm	0.14 mg/L	4.53 NTU	36.3 mV	16.29 ft	200.00 ml/min
8/5/2024 4:49 PM	20:00	6.85 pH	22.44 °C	644.34 µS/cm	0.20 mg/L	4.25 NTU	37.9 mV	16.29 ft	200.00 ml/min
8/5/2024 4:54 PM	25:00	6.88 pH	22.24 °C	639.26 µS/cm	0.13 mg/L	3.92 NTU	34.2 mV	16.30 ft	200.00 ml/min
8/5/2024 4:59 PM	30:00	6.87 pH	22.38 °C	644.85 µS/cm	0.11 mg/L	3.87 NTU	33.6 mV	16.30 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.

Low-Flow Test Report:

Test Date / Time: 8/7/2024 9:16:00 AM
Project: Plant Hammond
Operator Name: Elisabeth Russell

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 16.57 ft Total Depth: 26.57 ft Initial Depth to Water: 12.82 ft	Pump Type: Peri Pump Tubing Type: Poly Pump Intake From TOC: 21 ft Estimated Total Volume Pumped: 16 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.01 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080293
---	---	---

Test Notes: Metals.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 10	+/- 0.5	
8/7/2024 9:16 AM	00:00	6.79 pH	20.70 °C	635.11 µS/cm	0.15 mg/L	80.40 NTU	75.3 mV	12.82 ft	200.00 ml/min
8/7/2024 9:21 AM	05:00	6.76 pH	20.97 °C	624.08 µS/cm	0.10 mg/L	64.90 NTU	53.5 mV	12.82 ft	200.00 ml/min
8/7/2024 9:26 AM	10:00	6.77 pH	21.11 °C	628.51 µS/cm	0.09 mg/L	55.30 NTU	45.8 mV	12.82 ft	200.00 ml/min
8/7/2024 9:31 AM	15:00	6.78 pH	21.21 °C	631.86 µS/cm	0.08 mg/L	48.90 NTU	47.2 mV	12.83 ft	200.00 ml/min
8/7/2024 9:36 AM	20:00	6.77 pH	21.24 °C	632.52 µS/cm	0.07 mg/L	40.20 NTU	43.1 mV	12.83 ft	200.00 ml/min
8/7/2024 9:41 AM	25:00	6.77 pH	21.42 °C	636.36 µS/cm	0.06 mg/L	34.60 NTU	40.2 mV	12.83 ft	200.00 ml/min
8/7/2024 9:46 AM	30:00	6.78 pH	21.46 °C	630.54 µS/cm	0.06 mg/L	29.50 NTU	35.0 mV	12.83 ft	200.00 ml/min
8/7/2024 9:51 AM	35:00	6.79 pH	21.37 °C	632.23 µS/cm	0.06 mg/L	23.70 NTU	32.3 mV	12.83 ft	200.00 ml/min
8/7/2024 9:56 AM	40:00	6.79 pH	21.39 °C	628.01 µS/cm	0.05 mg/L	20.50 NTU	31.7 mV	12.83 ft	200.00 ml/min
8/7/2024 10:01 AM	45:00	6.78 pH	21.44 °C	635.60 µS/cm	0.05 mg/L	15.40 NTU	31.0 mV	12.83 ft	200.00 ml/min
8/7/2024 10:06 AM	50:00	6.78 pH	21.54 °C	634.09 µS/cm	0.05 mg/L	13.70 NTU	30.9 mV	12.83 ft	200.00 ml/min
8/7/2024 10:11 AM	55:00	6.79 pH	21.59 °C	635.39 µS/cm	0.06 mg/L	10.60 NTU	30.3 mV	12.83 ft	200.00 ml/min
8/7/2024 10:16 AM	01:00:00	6.78 pH	21.73 °C	636.52 µS/cm	0.08 mg/L	8.76 NTU	29.8 mV	12.83 ft	200.00 ml/min
8/7/2024 10:21 AM	01:05:00	6.78 pH	21.68 °C	640.31 µS/cm	0.07 mg/L	7.01 NTU	29.9 mV	12.83 ft	200.00 ml/min
8/7/2024 10:26 AM	01:10:00	6.79 pH	21.80 °C	642.12 µS/cm	0.06 mg/L	4.90 NTU	30.2 mV	12.83 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-11	Grab.

Low-Flow Test Report:

Test Date / Time: 8/6/2024 12:29:39 PM
Project: Plant Hammond
Operator Name: Elisabeth Russell

Location Name: PT-12 Well Diameter: 2 ft Casing Type: PVC Screen Length: 10 ft Top of Screen: 16.78 ft Total Depth: 26.78 ft Initial Depth to Water: 12.67 ft	Pump Type: Peri Pump Tubing Type: Poly Pump Intake From TOC: 21 ft Estimated Total Volume Pumped: 39 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080293
--	--	---

Test Notes: Metals.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 10	+/- 0.5	
8/6/2024 12:29 PM	00:00	6.72 pH	23.33 °C	673.24 µS/cm	0.10 mg/L	10,000.0 NTU	44.1 mV	12.69 ft	200.00 ml/min
8/6/2024 12:34 PM	05:00	6.75 pH	23.32 °C	670.76 µS/cm	0.08 mg/L	10,000.0 NTU	43.8 mV	12.70 ft	200.00 ml/min
8/6/2024 12:39 PM	10:00	6.81 pH	23.30 °C	669.25 µS/cm	0.07 mg/L	10,000.0 NTU	39.5 mV	12.70 ft	200.00 ml/min
8/6/2024 12:44 PM	15:00	6.82 pH	23.39 °C	669.93 µS/cm	0.07 mg/L	10,000.0 NTU	37.2 mV	12.70 ft	200.00 ml/min
8/6/2024 12:49 PM	20:00	6.84 pH	23.12 °C	667.49 µS/cm	0.06 mg/L	10,000.0 NTU	35.9 mV	12.70 ft	200.00 ml/min
8/6/2024 12:54 PM	25:00	6.85 pH	23.34 °C	671.01 µS/cm	0.06 mg/L	10,000.0 NTU	37.6 mV	12.70 ft	200.00 ml/min
8/6/2024 1:05 PM	35:50	6.86 pH	23.23 °C	658.00 µS/cm	0.05 mg/L	90.50 NTU	41.8 mV	12.70 ft	200.00 ml/min
8/6/2024 1:10 PM	40:50	6.86 pH	23.03 °C	670.22 µS/cm	0.05 mg/L	86.70 NTU	37.4 mV	12.70 ft	200.00 ml/min
8/6/2024 1:15 PM	45:50	6.86 pH	23.16 °C	666.68 µS/cm	0.05 mg/L	81.00 NTU	34.2 mV	12.70 ft	200.00 ml/min
8/6/2024 1:20 PM	50:50	6.86 pH	23.49 °C	667.17 µS/cm	0.05 mg/L	74.50 NTU	33.7 mV	12.70 ft	200.00 ml/min
8/6/2024 1:25 PM	55:50	6.85 pH	22.75 °C	668.61 µS/cm	0.04 mg/L	68.50 NTU	35.8 mV	12.70 ft	200.00 ml/min
8/6/2024 1:30 PM	01:00:50	6.85 pH	23.12 °C	669.98 µS/cm	0.04 mg/L	70.20 NTU	35.6 mV	12.70 ft	200.00 ml/min
8/6/2024 1:35 PM	01:05:50	6.85 pH	23.07 °C	664.35 µS/cm	0.04 mg/L	69.30 NTU	33.4 mV	12.70 ft	200.00 ml/min
8/6/2024 1:40 PM	01:10:50	6.84 pH	23.16 °C	671.04 µS/cm	0.04 mg/L	75.20 NTU	35.0 mV	12.70 ft	200.00 ml/min
8/6/2024 1:45 PM	01:15:50	6.85 pH	22.77 °C	683.02 µS/cm	0.05 mg/L	70.10 NTU	32.8 mV	12.70 ft	150.00 ml/min

8/6/2024 1:50 PM	01:20:50	6.83 pH	24.87 °C	669.33 µS/cm	0.05 mg/L	68.50 NTU	33.0 mV	12.70 ft	150.00 ml/min
8/6/2024 1:55 PM	01:25:50	6.83 pH	25.19 °C	667.48 µS/cm	0.06 mg/L	63.40 NTU	32.8 mV	12.70 ft	150.00 ml/min
8/6/2024 2:00 PM	01:30:50	6.84 pH	24.95 °C	664.22 µS/cm	0.06 mg/L	54.30 NTU	33.1 mV	12.70 ft	150.00 ml/min
8/6/2024 2:05 PM	01:35:50	6.85 pH	25.13 °C	667.43 µS/cm	0.06 mg/L	56.10 NTU	34.7 mV	12.70 ft	150.00 ml/min
8/6/2024 2:10 PM	01:40:50	6.85 pH	25.69 °C	671.84 µS/cm	0.07 mg/L	53.10 NTU	34.7 mV	12.70 ft	150.00 ml/min
8/6/2024 2:15 PM	01:45:50	6.84 pH	25.42 °C	662.99 µS/cm	0.07 mg/L	47.70 NTU	33.4 mV	12.70 ft	150.00 ml/min
8/6/2024 2:20 PM	01:50:50	6.85 pH	24.78 °C	671.02 µS/cm	0.07 mg/L	41.50 NTU	34.6 mV	12.70 ft	150.00 ml/min
8/6/2024 2:25 PM	01:55:50	6.85 pH	25.00 °C	670.14 µS/cm	0.07 mg/L	39.20 NTU	33.1 mV	12.70 ft	150.00 ml/min
8/6/2024 2:32 PM	02:02:39	7.09 pH	25.88 °C	391.77 µS/cm	5.01 mg/L	37.60 NTU	39.1 mV	12.70 ft	150.00 ml/min
8/6/2024 2:37 PM	02:07:39	6.86 pH	25.01 °C	665.89 µS/cm	0.22 mg/L	35.70 NTU	34.2 mV	12.70 ft	150.00 ml/min
8/6/2024 2:42 PM	02:12:39	6.85 pH	24.74 °C	669.83 µS/cm	0.11 mg/L	33.20 NTU	33.1 mV	12.70 ft	150.00 ml/min
8/6/2024 2:45 PM	02:15:35	6.84 pH	24.88 °C	672.73 µS/cm	0.10 mg/L	30.70 NTU	34.8 mV	12.70 ft	150.00 ml/min
8/6/2024 2:50 PM	02:20:35	6.86 pH	25.14 °C	666.02 µS/cm	0.09 mg/L	29.30 NTU	33.3 mV	12.70 ft	150.00 ml/min
8/6/2024 2:53 PM	02:23:53	6.86 pH	24.74 °C	655.86 µS/cm	0.09 mg/L	27.50 NTU	34.2 mV	12.70 ft	150.00 ml/min
8/6/2024 2:54 PM	02:25:17	6.84 pH	24.59 °C	667.24 µS/cm	0.08 mg/L	25.40 NTU	33.6 mV	12.70 ft	150.00 ml/min
8/6/2024 2:59 PM	02:30:17	6.83 pH	24.91 °C	668.13 µS/cm	0.23 mg/L	23.20 NTU	33.2 mV	12.70 ft	150.00 ml/min
8/6/2024 3:04 PM	02:35:17	6.84 pH	24.70 °C	675.56 µS/cm	0.10 mg/L	21.80 NTU	34.6 mV	12.70 ft	150.00 ml/min
8/6/2024 3:09 PM	02:40:17	6.85 pH	23.84 °C	675.40 µS/cm	0.08 mg/L	17.00 NTU	33.2 mV	12.70 ft	150.00 ml/min
8/6/2024 3:14 PM	02:45:17	6.85 pH	24.53 °C	677.50 µS/cm	0.08 mg/L	15.20 NTU	34.4 mV	12.70 ft	150.00 ml/min
8/6/2024 3:19 PM	02:50:17	6.85 pH	24.53 °C	675.77 µS/cm	0.08 mg/L	14.00 NTU	33.2 mV	12.70 ft	150.00 ml/min
8/6/2024 3:24 PM	02:55:17	6.86 pH	24.24 °C	665.45 µS/cm	0.07 mg/L	13.10 NTU	33.3 mV	12.70 ft	150.00 ml/min
8/6/2024 3:29 PM	03:00:17	6.86 pH	23.42 °C	668.21 µS/cm	0.07 mg/L	12.00 NTU	33.0 mV	12.70 ft	150.00 ml/min
8/6/2024 3:34 PM	03:05:17	6.87 pH	23.85 °C	678.96 µS/cm	0.07 mg/L	11.80 NTU	34.0 mV	12.70 ft	150.00 ml/min
8/6/2024 3:39 PM	03:10:17	6.87 pH	24.65 °C	674.89 µS/cm	0.07 mg/L	11.20 NTU	33.0 mV	12.70 ft	150.00 ml/min
8/6/2024 3:44 PM	03:15:17	6.88 pH	24.46 °C	673.01 µS/cm	0.07 mg/L	8.70 NTU	32.9 mV	12.70 ft	150.00 ml/min
8/6/2024 3:49 PM	03:20:17	6.86 pH	24.57 °C	675.51 µS/cm	0.07 mg/L	8.30 NTU	34.6 mV	12.70 ft	150.00 ml/min
8/6/2024 3:54 PM	03:25:17	6.87 pH	24.93 °C	674.65 µS/cm	0.07 mg/L	8.00 NTU	35.2 mV	12.70 ft	150.00 ml/min
8/6/2024 3:59 PM	03:30:17	6.88 pH	24.92 °C	673.50 µS/cm	0.07 mg/L	7.78 NTU	33.3 mV	12.70 ft	150.00 ml/min
8/6/2024 4:04 PM	03:35:17	6.89 pH	24.71 °C	672.94 µS/cm	0.07 mg/L	6.20 NTU	35.1 mV	12.70 ft	150.00 ml/min

8/6/2024 4:09 PM	03:40:17	6.87 pH	23.83 °C	673.71 µS/cm	0.07 mg/L	5.61 NTU	35.4 mV	12.70 ft	150.00 ml/min
8/6/2024 4:14 PM	03:45:17	6.87 pH	23.49 °C	676.48 µS/cm	0.07 mg/L	4.98 NTU	34.9 mV	12.70 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-12	Grab.
HAM-AP1-FD-01	Grab.

Low-Flow Test Report:

Test Date / Time: 8/9/2024 1:25:50 PM
Project: Plant Hammond
Operator Name: Elisabeth Russell

Location Name: PT-13 Well Diameter: 2 in Screen Length: 10 ft Top of Screen: 35 ft Total Depth: 45 ft Initial Depth to Water: 25.44 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 6.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080293
---	---	---

Test Notes: Metals.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 10	+/- 0.5	
8/9/2024 1:25 PM	00:00	6.88 pH	22.08 °C	742.43 µS/cm	0.37 mg/L	25.70 NTU	-100.4 mV	25.44 ft	200.00 ml/min
8/9/2024 1:30 PM	05:00	6.87 pH	21.40 °C	747.46 µS/cm	0.31 mg/L	11.40 NTU	-104.4 mV	25.44 ft	200.00 ml/min
8/9/2024 1:35 PM	10:00	6.87 pH	21.25 °C	746.14 µS/cm	0.24 mg/L	7.68 NTU	-104.8 mV	25.44 ft	200.00 ml/min
8/9/2024 1:40 PM	15:00	6.87 pH	21.08 °C	747.52 µS/cm	0.20 mg/L	4.58 NTU	-105.6 mV	25.44 ft	200.00 ml/min
8/9/2024 1:45 PM	20:00	6.85 pH	21.11 °C	748.25 µS/cm	0.16 mg/L	3.07 NTU	-105.5 mV	25.44 ft	200.00 ml/min
8/9/2024 1:50 PM	25:00	6.85 pH	21.07 °C	746.76 µS/cm	0.14 mg/L	2.29 NTU	-105.0 mV	25.44 ft	200.00 ml/min
8/9/2024 1:55 PM	30:00	6.86 pH	20.66 °C	745.85 µS/cm	0.12 mg/L	1.58 NTU	-104.7 mV	25.44 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-13	Grab.

Low-Flow Test Report:

Test Date / Time: 8/8/2024 12:46:44 PM
Project: Plant Hammond
Operator Name: Elisabeth Russell

Location Name: PT-14 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35 ft Total Depth: 45 ft Initial Depth to Water: 25.4 ft	Pump Type: bladder Tubing Type: Poly Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 6.75 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080293
---	---	---

Test Notes: Metals.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 10	+/- 0.5	
8/8/2024 12:46 PM	00:00	6.95 pH	21.42 °C	799.78 µS/cm	1.51 mg/L	9.70 NTU	-59.3 mV	25.40 ft	200.00 ml/min
8/8/2024 12:51 PM	05:00	6.96 pH	21.02 °C	797.82 µS/cm	1.60 mg/L	7.15 NTU	-61.5 mV	25.40 ft	200.00 ml/min
8/8/2024 12:56 PM	10:00	6.95 pH	21.10 °C	796.39 µS/cm	1.62 mg/L	6.30 NTU	-64.2 mV	25.40 ft	200.00 ml/min
8/8/2024 1:01 PM	15:00	6.96 pH	21.07 °C	793.51 µS/cm	1.76 mg/L	4.49 NTU	-66.0 mV	25.40 ft	200.00 ml/min
8/8/2024 1:06 PM	20:00	6.96 pH	20.97 °C	788.98 µS/cm	1.83 mg/L	3.77 NTU	-67.1 mV	25.40 ft	200.00 ml/min
8/8/2024 1:11 PM	25:00	6.95 pH	20.92 °C	788.30 µS/cm	1.87 mg/L	3.31 NTU	-67.8 mV	25.40 ft	200.00 ml/min
8/8/2024 1:16 PM	30:00	6.95 pH	20.85 °C	790.64 µS/cm	1.70 mg/L	2.96 NTU	-70.4 mV	25.40 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-14	Grab.

Low-Flow Test Report:

Test Date / Time: 8/9/2024 9:32:36 AM
Project: Plant Hammond
Operator Name: Elisabeth Russell

Location Name: PT-15 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35 ft Total Depth: 45 ft Initial Depth to Water: 25.19 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 8.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.01 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080293
---	--	---

Test Notes: Metals.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 10	+/- 0.5	
8/9/2024 9:32 AM	00:00	6.94 pH	20.86 °C	716.09 µS/cm	0.25 mg/L	13.30 NTU	-72.6 mV	25.19 ft	200.00 ml/min
8/9/2024 9:34 AM	01:52	6.94 pH	20.79 °C	719.20 µS/cm	0.21 mg/L	10.30 NTU	-72.4 mV	25.19 ft	200.00 ml/min
8/9/2024 9:39 AM	06:52	6.94 pH	20.76 °C	715.73 µS/cm	0.16 mg/L	7.90 NTU	-70.7 mV	25.19 ft	200.00 ml/min
8/9/2024 9:44 AM	11:52	6.93 pH	20.75 °C	713.26 µS/cm	0.12 mg/L	5.40 NTU	-77.3 mV	25.20 ft	200.00 ml/min
8/9/2024 9:49 AM	16:52	6.93 pH	20.70 °C	709.96 µS/cm	0.11 mg/L	2.21 NTU	-69.5 mV	25.20 ft	200.00 ml/min
8/9/2024 9:54 AM	21:52	6.92 pH	20.62 °C	709.36 µS/cm	0.09 mg/L	2.00 NTU	-76.6 mV	25.20 ft	200.00 ml/min
8/9/2024 9:59 AM	26:52	6.92 pH	20.75 °C	708.64 µS/cm	0.07 mg/L	1.68 NTU	-77.2 mV	25.20 ft	200.00 ml/min
8/9/2024 10:04 AM	31:52	6.91 pH	20.77 °C	706.70 µS/cm	0.06 mg/L	1.07 NTU	-77.5 mV	25.20 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-15	Grab.

Low-Flow Test Report:

Test Date / Time: 8/14/2024 2:37:37 PM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 37.75 ft Total Depth: 47.75 ft Initial Depth to Water: 25.83 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 42.75 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: -0.01 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080297
--	---	---

Test Notes:
Full Appendix III and IV and major ions.

Weather Conditions:
Sunny, 90F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/14/2024 2:37 PM	00:00	7.03 pH	20.70 °C	707.12 µS/cm	0.42 mg/L	52.50 NTU	-87.7 mV	25.83 ft	200.00 ml/min
8/14/2024 2:42 PM	05:00	7.04 pH	20.38 °C	709.56 µS/cm	0.41 mg/L	12.30 NTU	-93.8 mV	25.85 ft	200.00 ml/min
8/14/2024 2:47 PM	10:00	7.04 pH	20.32 °C	707.84 µS/cm	0.34 mg/L	7.50 NTU	-88.2 mV	25.85 ft	200.00 ml/min
8/14/2024 2:52 PM	15:00	7.04 pH	20.42 °C	708.52 µS/cm	0.33 mg/L	4.32 NTU	-94.4 mV	25.82 ft	200.00 ml/min
8/14/2024 2:57 PM	20:00	7.04 pH	20.28 °C	708.14 µS/cm	0.31 mg/L	4.12 NTU	-94.2 mV	25.82 ft	200.00 ml/min
8/14/2024 3:02 PM	25:00	7.04 pH	20.30 °C	708.56 µS/cm	0.32 mg/L	3.85 NTU	-94.2 mV	25.82 ft	200.00 ml/min
8/14/2024 3:07 PM	30:00	7.04 pH	20.27 °C	708.53 µS/cm	0.30 mg/L	3.35 NTU	-94.4 mV	25.82 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-07	Grab.

Low-Flow Test Report:

Test Date / Time: 8/14/2024 10:11:30 AM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 31.93 ft Total Depth: 41.93 ft Initial Depth to Water: 25.8 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 36.93 ft Estimated Total Volume Pumped: 19 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.01 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080297
--	--	---

Test Notes:
Full Appendix III and IV and major ions.

Weather Conditions:
Sunny, 90F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/14/2024 10:11 AM	00:00	6.46 pH	21.43 °C	548.59 µS/cm	0.66 mg/L	31.90 NTU	-13.8 mV	25.75 ft	200.00 ml/min
8/14/2024 10:16 AM	05:00	6.48 pH	21.75 °C	549.98 µS/cm	0.58 mg/L	25.80 NTU	-15.4 mV	25.80 ft	200.00 ml/min
8/14/2024 10:21 AM	10:00	6.51 pH	21.37 °C	545.42 µS/cm	0.48 mg/L	15.80 NTU	-25.9 mV	25.82 ft	200.00 ml/min
8/14/2024 10:26 AM	15:00	6.51 pH	21.14 °C	572.54 µS/cm	0.42 mg/L	10.10 NTU	-26.0 mV	25.82 ft	200.00 ml/min
8/14/2024 10:31 AM	20:00	6.52 pH	21.67 °C	575.39 µS/cm	0.45 mg/L	12.81 NTU	-16.7 mV	25.91 ft	200.00 ml/min
8/14/2024 10:36 AM	25:00	6.52 pH	21.54 °C	576.74 µS/cm	0.43 mg/L	10.04 NTU	-16.8 mV	25.85 ft	200.00 ml/min
8/14/2024 10:41 AM	30:00	6.52 pH	21.70 °C	578.30 µS/cm	0.38 mg/L	8.84 NTU	-27.1 mV	25.81 ft	200.00 ml/min
8/14/2024 10:46 AM	35:00	6.53 pH	20.98 °C	582.26 µS/cm	0.39 mg/L	8.87 NTU	-26.5 mV	25.81 ft	200.00 ml/min
8/14/2024 10:51 AM	40:00	6.54 pH	21.27 °C	575.12 µS/cm	0.50 mg/L	8.89 NTU	-17.0 mV	25.81 ft	200.00 ml/min
8/14/2024 10:56 AM	45:00	6.55 pH	20.93 °C	584.74 µS/cm	0.43 mg/L	7.62 NTU	-17.0 mV	25.81 ft	200.00 ml/min
8/14/2024 11:01 AM	50:00	6.55 pH	20.96 °C	584.97 µS/cm	0.48 mg/L	7.11 NTU	-16.6 mV	25.81 ft	200.00 ml/min
8/14/2024 11:06 AM	55:00	6.55 pH	21.00 °C	586.54 µS/cm	0.41 mg/L	8.61 NTU	-17.4 mV	25.81 ft	200.00 ml/min
8/14/2024 11:11 AM	01:00:00	6.56 pH	20.96 °C	585.77 µS/cm	0.40 mg/L	7.71 NTU	-17.2 mV	25.81 ft	200.00 ml/min
8/14/2024 11:13 AM	01:01:51	6.56 pH	20.96 °C	586.43 µS/cm	0.46 mg/L		-17.0 mV	25.81 ft	200.00 ml/min
8/14/2024 11:18 AM	01:06:51	6.56 pH	20.87 °C	584.71 µS/cm	0.36 mg/L	6.42 NTU	-17.2 mV	25.81 ft	200.00 ml/min

8/14/2024 11:23 AM	01:11:51	6.56 pH	20.82 °C	586.77 µS/cm	0.32 mg/L	5.72 NTU	-17.4 mV	25.81 ft	200.00 ml/min
8/14/2024 11:28 AM	01:16:51	6.56 pH	21.36 °C	543.01 µS/cm	0.23 mg/L	4.84 NTU	-18.4 mV	25.81 ft	200.00 ml/min
8/14/2024 11:31 AM	01:19:42	6.57 pH	21.27 °C	585.10 µS/cm	0.33 mg/L		-17.6 mV	25.81 ft	200.00 ml/min
8/14/2024 11:36 AM	01:24:42	6.57 pH	21.17 °C	585.25 µS/cm	0.24 mg/L	4.09 NTU	-18.5 mV	25.81 ft	200.00 ml/min
8/14/2024 11:41 AM	01:29:42	6.58 pH	21.67 °C	585.20 µS/cm	0.26 mg/L	3.76 NTU	-19.7 mV	25.81 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.
HAM-AP2-FD-01	Grab.

Low-Flow Test Report:

Test Date / Time: 8/12/2024 1:59:42 PM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Top of Screen: 20.4 ft Total Depth: 30.4 ft Initial Depth to Water: 16.19 ft	Pump Type: Peristaltic Tubing Type: Poly Pump Intake From TOC: 25.4 ft Estimated Total Volume Pumped: 19 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080297
---	---	---

Test Notes:
Full Appendix III and IV and major ions.

Weather Conditions:
Sunny, 95F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/12/2024 1:59 PM	00:00	7.04 pH	23.69 °C	632.63 µS/cm	0.25 mg/L	119.00 NTU	54.7 mV	16.19 ft	200.00 ml/min
8/12/2024 2:04 PM	05:00	7.04 pH	22.79 °C	627.53 µS/cm	0.14 mg/L	144.00 NTU	56.7 mV	16.19 ft	200.00 ml/min
8/12/2024 2:09 PM	10:00	7.04 pH	22.56 °C	622.54 µS/cm	0.10 mg/L	110.00 NTU	51.2 mV	16.19 ft	200.00 ml/min
8/12/2024 2:14 PM	15:00	7.05 pH	22.55 °C	612.07 µS/cm	0.08 mg/L	79.90 NTU	56.4 mV	16.21 ft	200.00 ml/min
8/12/2024 2:19 PM	20:00	7.05 pH	22.54 °C	609.97 µS/cm	0.07 mg/L	61.20 NTU	57.5 mV	16.21 ft	200.00 ml/min
8/12/2024 2:24 PM	25:00	7.05 pH	22.52 °C	608.69 µS/cm	0.06 mg/L	51.90 NTU	58.2 mV	16.21 ft	200.00 ml/min
8/12/2024 2:29 PM	30:00	7.04 pH	22.63 °C	605.17 µS/cm	0.06 mg/L	41.20 NTU	52.6 mV	16.21 ft	200.00 ml/min
8/12/2024 2:34 PM	35:00	7.05 pH	22.41 °C	603.33 µS/cm	0.05 mg/L	30.40 NTU	52.3 mV	16.21 ft	200.00 ml/min
8/12/2024 2:39 PM	40:00	7.04 pH	22.53 °C	603.01 µS/cm	0.05 mg/L	21.60 NTU	53.1 mV	16.21 ft	200.00 ml/min
8/12/2024 2:44 PM	45:00	7.04 pH	22.52 °C	606.39 µS/cm	0.05 mg/L	22.20 NTU	52.5 mV	16.21 ft	200.00 ml/min
8/12/2024 2:49 PM	50:00	7.04 pH	22.51 °C	605.93 µS/cm	0.04 mg/L	16.10 NTU	52.8 mV	16.21 ft	200.00 ml/min
8/12/2024 2:54 PM	55:00	7.03 pH	22.58 °C	611.42 µS/cm	0.05 mg/L	10.80 NTU	53.3 mV	16.21 ft	200.00 ml/min
8/12/2024 2:59 PM	01:00:00	7.04 pH	22.51 °C	607.78 µS/cm	0.05 mg/L	12.70 NTU	53.2 mV	16.21 ft	200.00 ml/min

8/12/2024 3:04 PM	01:05:00	7.03 pH	22.39 °C	606.45 µS/cm	0.05 mg/L	10.25 NTU	53.4 mV	16.21 ft	200.00 ml/min
8/12/2024 3:09 PM	01:10:00	7.03 pH	22.25 °C	605.06 µS/cm	0.04 mg/L	8.15 NTU	60.7 mV	16.21 ft	200.00 ml/min
8/12/2024 3:14 PM	01:15:00	7.03 pH	22.22 °C	607.43 µS/cm	0.05 mg/L	7.33 NTU	54.4 mV	16.21 ft	200.00 ml/min
8/12/2024 3:19 PM	01:20:00	7.04 pH	22.31 °C	600.28 µS/cm	0.04 mg/L	7.44 NTU	53.5 mV	16.21 ft	200.00 ml/min
8/12/2024 3:24 PM	01:25:00	7.03 pH	22.48 °C	607.30 µS/cm	0.05 mg/L	5.50 NTU	53.2 mV	16.21 ft	200.00 ml/min
8/12/2024 3:29 PM	01:30:00	7.02 pH	22.39 °C	601.60 µS/cm	0.04 mg/L	4.48 NTU	53.7 mV	16.21 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.

Low-Flow Test Report:

Test Date / Time: 8/13/2024 1:30:32 PM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-10 Well Diameter: 2 ft Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.4 ft Total Depth: 30.4 ft Initial Depth to Water: 16.31 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 25.4 ft Estimated Total Volume Pumped: 9 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080297
---	--	---

Test Notes:
Full Appendix III and IV and major ions.

Weather Conditions:
Sunny, 90F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/13/2024 1:30 PM	00:00	6.94 pH	22.40 °C	584.40 µS/cm	0.10 mg/L	19.20 NTU	80.2 mV	16.36 ft	200.00 ml/min
8/13/2024 1:35 PM	05:00	6.98 pH	22.21 °C	570.15 µS/cm	0.07 mg/L	14.00 NTU	78.3 mV	16.36 ft	200.00 ml/min
8/13/2024 1:40 PM	10:00	6.99 pH	22.26 °C	571.81 µS/cm	0.06 mg/L	13.20 NTU	61.1 mV	16.36 ft	200.00 ml/min
8/13/2024 1:45 PM	15:00	7.00 pH	22.11 °C	574.99 µS/cm	0.05 mg/L	10.38 NTU	57.8 mV	16.36 ft	200.00 ml/min
8/13/2024 1:50 PM	20:00	7.02 pH	22.10 °C	574.65 µS/cm	0.05 mg/L	8.25 NTU	55.6 mV	16.36 ft	200.00 ml/min
8/13/2024 1:55 PM	25:00	7.04 pH	22.11 °C	572.86 µS/cm	0.04 mg/L	7.22 NTU	52.9 mV	16.36 ft	200.00 ml/min
8/13/2024 2:00 PM	30:00	7.03 pH	22.18 °C	576.68 µS/cm	0.04 mg/L	6.36 NTU	50.6 mV	16.36 ft	200.00 ml/min
8/13/2024 2:05 PM	35:00	7.04 pH	22.36 °C	577.14 µS/cm	0.04 mg/L	7.74 NTU	48.2 mV	16.36 ft	200.00 ml/min
8/13/2024 2:10 PM	40:00	7.05 pH	22.14 °C	579.22 µS/cm	0.04 mg/L	4.87 NTU	44.0 mV	16.36 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.

Low-Flow Test Report:

Test Date / Time: 8/12/2024 4:29:08 PM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 16.9 ft Total Depth: 26.9 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 21.9 ft Estimated Total Volume Pumped: 13 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.1 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080297
---	--	---

Test Notes:
Full Appendix III and IV and major ions.

Weather Conditions:
Sunny, 90F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/12/2024 4:29 PM	00:00	7.09 pH	25.84 °C	567.77 µS/cm	1.06 mg/L	10.40 NTU	74.8 mV	12.80 ft	200.00 ml/min
8/12/2024 4:34 PM	05:00	6.98 pH	23.19 °C	587.37 µS/cm	0.33 mg/L	8.70 NTU	77.9 mV	12.80 ft	200.00 ml/min
8/12/2024 4:39 PM	10:00	6.97 pH	22.40 °C	590.46 µS/cm	0.18 mg/L	12.10 NTU	65.5 mV	12.80 ft	200.00 ml/min
8/12/2024 4:44 PM	15:00	6.96 pH	22.16 °C	588.95 µS/cm	0.12 mg/L	10.10 NTU	62.4 mV	12.80 ft	200.00 ml/min
8/12/2024 4:49 PM	20:00	6.96 pH	22.03 °C	585.50 µS/cm	0.09 mg/L	12.20 NTU	61.0 mV	12.80 ft	200.00 ml/min
8/12/2024 4:54 PM	25:00	6.95 pH	22.39 °C	587.66 µS/cm	0.09 mg/L	12.25 NTU	59.2 mV	12.80 ft	200.00 ml/min
8/12/2024 4:59 PM	30:00	6.96 pH	22.16 °C	585.61 µS/cm	0.08 mg/L	10.60 NTU	68.4 mV	12.80 ft	200.00 ml/min
8/12/2024 5:04 PM	35:00	6.95 pH	21.80 °C	585.79 µS/cm	0.07 mg/L	9.28 NTU	58.7 mV	12.80 ft	200.00 ml/min
8/12/2024 5:09 PM	40:00	6.96 pH	21.64 °C	586.43 µS/cm	0.07 mg/L	8.89 NTU	67.0 mV	12.80 ft	200.00 ml/min
8/12/2024 5:14 PM	45:00	6.95 pH	21.81 °C	586.17 µS/cm	0.07 mg/L	6.80 NTU	57.8 mV	12.80 ft	200.00 ml/min
8/12/2024 5:19 PM	50:00	6.96 pH	21.93 °C	583.91 µS/cm	0.07 mg/L	5.52 NTU	56.5 mV	12.80 ft	200.00 ml/min
8/12/2024 5:24 PM	55:00	6.97 pH	21.66 °C	586.44 µS/cm	0.07 mg/L	4.40 NTU	55.5 mV	12.80 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-11	Grab.

Low-Flow Test Report:

Test Date / Time: 8/13/2024 10:10:04 AM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-12 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.3 ft Total Depth: 27.3 ft Initial Depth to Water: 12.74 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22.3 ft Estimated Total Volume Pumped: 24 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.06 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080297
---	---	---

Test Notes:
Full Appendix III and IV and major ions.

Weather Conditions:
Sunny, 90F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/13/2024 10:10 AM	00:00	6.42 pH	21.69 °C	576.35 µS/cm	0.38 mg/L	136.00 NTU	88.2 mV	12.74 ft	200.00 ml/min
8/13/2024 10:15 AM	05:00	6.62 pH	20.92 °C	596.75 µS/cm	0.15 mg/L	1,122.0 NTU	88.5 mV	12.74 ft	200.00 ml/min
8/13/2024 10:20 AM	10:00	6.72 pH	20.97 °C	602.68 µS/cm	0.10 mg/L	843.00 NTU	68.4 mV	12.74 ft	200.00 ml/min
8/13/2024 10:25 AM	15:00	6.80 pH	20.94 °C	605.58 µS/cm	0.08 mg/L	800.00 NTU	64.3 mV	12.74 ft	200.00 ml/min
8/13/2024 10:30 AM	20:00	6.87 pH	20.92 °C	607.73 µS/cm	0.06 mg/L	149.00 NTU	61.6 mV	12.75 ft	200.00 ml/min
8/13/2024 10:35 AM	25:00	6.92 pH	20.77 °C	606.67 µS/cm	0.05 mg/L	121.00 NTU	59.8 mV	12.80 ft	200.00 ml/min
8/13/2024 10:40 AM	30:00	6.94 pH	20.71 °C	608.00 µS/cm	0.04 mg/L	94.80 NTU	57.2 mV	12.80 ft	200.00 ml/min
8/13/2024 10:45 AM	35:00	6.96 pH	20.54 °C	608.46 µS/cm	0.04 mg/L	76.00 NTU	56.6 mV	12.80 ft	200.00 ml/min
8/13/2024 10:50 AM	40:00	6.97 pH	20.65 °C	608.99 µS/cm	0.04 mg/L	65.40 NTU	54.9 mV	12.80 ft	200.00 ml/min
8/13/2024 10:55 AM	45:00	6.97 pH	20.74 °C	610.01 µS/cm	0.03 mg/L	58.80 NTU	55.3 mV	12.80 ft	200.00 ml/min
8/13/2024 11:00 AM	50:00	6.98 pH	20.80 °C	606.00 µS/cm	0.03 mg/L	51.20 NTU	54.8 mV	12.80 ft	200.00 ml/min
8/13/2024 11:05 AM	55:00	6.99 pH	20.67 °C	608.15 µS/cm	0.03 mg/L	45.00 NTU	54.3 mV	12.80 ft	200.00 ml/min
8/13/2024 11:10 AM	01:00:00	6.99 pH	20.72 °C	611.72 µS/cm	0.03 mg/L	39.10 NTU	53.7 mV	12.80 ft	200.00 ml/min
8/13/2024 11:15 AM	01:05:00	6.99 pH	21.15 °C	604.63 µS/cm	0.02 mg/L	32.20 NTU	62.4 mV	12.80 ft	200.00 ml/min
8/13/2024 11:20 AM	01:10:00	6.99 pH	21.27 °C	605.50 µS/cm	0.03 mg/L	28.50 NTU	54.3 mV	12.80 ft	200.00 ml/min

8/13/2024 11:25 AM	01:15:00	7.00 pH	21.04 °C	607.32 µS/cm	0.02 mg/L	20.60 NTU	52.9 mV	12.80 ft	200.00 ml/min
8/13/2024 11:30 AM	01:20:00	7.02 pH	21.07 °C	606.99 µS/cm	0.02 mg/L	15.90 NTU	52.0 mV	12.80 ft	200.00 ml/min
8/13/2024 11:35 AM	01:25:00	7.03 pH	20.98 °C	606.60 µS/cm	0.02 mg/L	12.80 NTU	51.9 mV	12.80 ft	200.00 ml/min
8/13/2024 11:40 AM	01:30:00	7.02 pH	21.00 °C	608.04 µS/cm	0.02 mg/L	11.50 NTU	51.8 mV	12.80 ft	200.00 ml/min
8/13/2024 11:45 AM	01:35:00	7.03 pH	20.91 °C	604.37 µS/cm	0.02 mg/L	10.40 NTU	51.3 mV	12.80 ft	200.00 ml/min
8/13/2024 11:50 AM	01:40:00	7.03 pH	21.06 °C	604.70 µS/cm	0.02 mg/L	8.90 NTU	51.6 mV	12.80 ft	200.00 ml/min
8/13/2024 11:55 AM	01:45:00	7.04 pH	21.24 °C	606.52 µS/cm	0.02 mg/L	7.30 NTU	59.7 mV	12.80 ft	200.00 ml/min
8/13/2024 12:00 PM	01:50:00	7.03 pH	21.15 °C	606.68 µS/cm	0.02 mg/L	6.02 NTU	52.1 mV	12.80 ft	200.00 ml/min
8/13/2024 12:05 PM	01:55:00	7.04 pH	21.23 °C	606.97 µS/cm	0.02 mg/L	4.38 NTU	51.3 mV	12.80 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-12	Grab.

Low-Flow Test Report:

Test Date / Time: 8/14/2024 4:15:57 PM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-13 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.62 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 9 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080297
---	---	---

Test Notes:
Full Appendix III and IV and major ions.

Weather Conditions:
Sunny, 90F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/14/2024 4:15 PM	00:00	6.94 pH	20.69 °C	699.73 µS/cm	0.61 mg/L	12.00 NTU	-87.2 mV	25.62 ft	200.00 ml/min
8/14/2024 4:20 PM	05:00	6.94 pH	20.51 °C	699.51 µS/cm	0.60 mg/L	6.16 NTU	-86.1 mV	25.62 ft	200.00 ml/min
8/14/2024 4:25 PM	10:00	6.94 pH	20.47 °C	695.73 µS/cm	0.59 mg/L	3.25 NTU	-89.6 mV	25.62 ft	200.00 ml/min
8/14/2024 4:30 PM	15:00	6.94 pH	20.36 °C	687.03 µS/cm	0.59 mg/L	3.88 NTU	-85.0 mV	25.62 ft	200.00 ml/min
8/14/2024 4:35 PM	20:00	6.94 pH	20.29 °C	698.54 µS/cm	0.53 mg/L	3.25 NTU	-88.7 mV	25.62 ft	200.00 ml/min
8/14/2024 4:40 PM	25:00	6.94 pH	20.33 °C	634.71 µS/cm	0.55 mg/L	3.05 NTU	-88.6 mV	25.62 ft	200.00 ml/min
8/14/2024 4:45 PM	30:00	6.94 pH	20.33 °C	699.01 µS/cm	0.57 mg/L	2.78 NTU	-87.9 mV	25.62 ft	200.00 ml/min
8/14/2024 4:50 PM	35:00	6.94 pH	20.20 °C	698.65 µS/cm	0.58 mg/L	2.67 NTU	-87.3 mV	25.62 ft	200.00 ml/min
8/14/2024 4:55 PM	40:00	6.93 pH	20.18 °C	699.08 µS/cm	0.59 mg/L	2.64 NTU	-86.8 mV	25.62 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-13	Grab.

Low-Flow Test Report:

Test Date / Time: 8/13/2024 4:29:45 PM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-14 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.4 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080297
--	--	---

Test Notes:
Full Appendix III and IV and major ions.

Weather Conditions:
Sunny, 90F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/13/2024 4:29 PM	00:00	6.93 pH	22.39 °C	731.64 µS/cm	0.30 mg/L	8.39 NTU	-83.1 mV	25.45 ft	200.00 ml/min
8/13/2024 4:34 PM	05:00	7.00 pH	22.16 °C	735.14 µS/cm	0.23 mg/L	7.62 NTU	-84.7 mV	25.45 ft	200.00 ml/min
8/13/2024 4:39 PM	10:00	7.03 pH	21.33 °C	736.29 µS/cm	0.19 mg/L	4.49 NTU	-103.0 mV	25.45 ft	200.00 ml/min
8/13/2024 4:44 PM	15:00	7.03 pH	21.07 °C	736.48 µS/cm	0.17 mg/L	4.12 NTU	-85.2 mV	25.45 ft	200.00 ml/min
8/13/2024 4:49 PM	20:00	7.03 pH	21.17 °C	735.60 µS/cm	0.16 mg/L	2.52 NTU	-85.2 mV	25.45 ft	200.00 ml/min
8/13/2024 4:54 PM	25:00	7.03 pH	21.21 °C	734.44 µS/cm	0.15 mg/L	1.10 NTU	-85.7 mV	25.45 ft	200.00 ml/min
8/13/2024 4:59 PM	30:00	7.03 pH	21.10 °C	734.47 µS/cm	0.15 mg/L	0.85 NTU	-102.9 mV	25.45 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-14	Grab.

Low-Flow Test Report:

Test Date / Time: 8/14/2024 12:59:27 PM
Project: GP-Plant Hammond (2)
Operator Name: Jacob Tracy

Location Name: PT-15 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.42 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080297
---	---	---

Test Notes:
Full Appendix III and IV and major ions.

Weather Conditions:
Sunny, 90F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/14/2024 12:59 PM	00:00	6.93 pH	21.89 °C	659.93 µS/cm	0.53 mg/L	6.58 NTU	-68.8 mV	25.42 ft	200.00 ml/min
8/14/2024 1:04 PM	05:00	6.98 pH	21.40 °C	584.38 µS/cm	0.47 mg/L	6.12 NTU	-68.7 mV	25.42 ft	200.00 ml/min
8/14/2024 1:09 PM	10:00	6.98 pH	21.49 °C	660.98 µS/cm	0.43 mg/L	2.21 NTU	-76.6 mV	25.42 ft	200.00 ml/min
8/14/2024 1:14 PM	15:00	6.98 pH	21.54 °C	661.02 µS/cm	0.41 mg/L	1.37 NTU	-68.3 mV	25.42 ft	200.00 ml/min
8/14/2024 1:19 PM	20:00	6.98 pH	21.87 °C	659.35 µS/cm	0.41 mg/L	1.42 NTU	-76.6 mV	25.42 ft	200.00 ml/min
8/14/2024 1:24 PM	25:00	6.97 pH	21.85 °C	660.41 µS/cm	0.40 mg/L	1.13 NTU	-76.6 mV	25.42 ft	200.00 ml/min
8/14/2024 1:29 PM	30:00	6.97 pH	21.85 °C	660.80 µS/cm	0.39 mg/L	0.97 NTU	-76.1 mV	25.42 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-15	Grab.

Low-Flow Test Report:

Test Date / Time: 8/21/2024 1:42:20 PM
Project: GP-Plant Hammond
Operator Name: Elisabeth Russell

Location Name: INW-03 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.3 ft Total Depth: 27.3 ft Initial Depth to Water: 13.03 ft	Pump Type: peri Tubing Type: Polyethylene Pump Intake From TOC: 22 ft Estimated Total Volume Pumped: 4 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 965586
--	---	--

Test Notes:
Field parameters only, no sample.
Fe = 0 mg/L Fe2+ = 0 mg/L.

Weather Conditions:
Sunny, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/21/2024 1:42 PM	00:00	6.68 pH	22.71 °C	664.47 µS/cm	0.21 mg/L	36.10 NTU	50.7 mV	13.03 ft	200.00 ml/min
8/21/2024 1:47 PM	05:00	6.56 pH	21.50 °C	689.97 µS/cm	0.13 mg/L	31.80 NTU	46.3 mV	13.05 ft	200.00 ml/min
8/21/2024 1:52 PM	10:00	6.54 pH	21.39 °C	696.61 µS/cm	0.09 mg/L	24.40 NTU	43.4 mV	13.05 ft	200.00 ml/min
8/21/2024 1:57 PM	15:00	6.54 pH	20.88 °C	702.70 µS/cm	0.10 mg/L	18.20 NTU	41.9 mV	13.05 ft	200.00 ml/min
8/21/2024 1:58 PM	15:52	6.54 pH	20.83 °C	704.26 µS/cm	0.10 mg/L	18.20 NTU	41.7 mV	13.05 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 8/20/2024 2:46:39 PM
Project: GP-Plant Hammond
Operator Name: Tristan Halterman

Location Name: INW-04 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.52 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 4000 ml Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.11 ft	Instrument Used: Aqua TROLL 400 Serial Number: 968202
--	--	--

Test Notes:
Field parameters only, no sample.
Fe = 5 mg/L Fe2+ = 10 mg/L.

Weather Conditions:
Sunny, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/20/2024 2:46 PM	00:00	6.25 pH	24.23 °C	612.54 µS/cm	1.76 mg/L	9,999.0 NTU	-14.0 mV	25.63 ft	200.00 ml/min
8/20/2024 2:51 PM	05:00	6.31 pH	22.36 °C	636.28 µS/cm	0.91 mg/L	9,999.0 NTU	-21.2 mV	25.63 ft	200.00 ml/min
8/20/2024 2:56 PM	10:00	6.32 pH	22.12 °C	645.19 µS/cm	0.72 mg/L	9,999.0 NTU	-20.8 mV	25.63 ft	200.00 ml/min
8/20/2024 3:01 PM	15:00	6.32 pH	21.91 °C	648.61 µS/cm	0.59 mg/L	9,999.0 NTU	-25.2 mV	25.63 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 8/20/2024 5:12:45 PM
Project: GP-Plant Hammond
Operator Name: Elisabeth Russell

Location Name: INW-05 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 34.15 ft Total Depth: 44.15 ft Initial Depth to Water: 25.06 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 3 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 965586
--	---	--

Test Notes:
Field parameters only, no sample

Weather Conditions:
Sunny, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/20/2024 5:12 PM	00:00	6.66 pH	26.77 °C	737.22 µS/cm	1.45 mg/L	1,000,000 NTU	-23.0 mV	25.06 ft	200.00 ml/min
8/20/2024 5:17 PM	05:00	6.74 pH	22.13 °C	778.22 µS/cm	0.77 mg/L	1,000,000 NTU	-50.1 mV	25.06 ft	200.00 ml/min
8/20/2024 5:22 PM	10:00	6.76 pH	21.55 °C	785.76 µS/cm	0.72 mg/L	1,000,000 NTU	-60.4 mV	25.06 ft	200.00 ml/min
8/20/2024 5:27 PM	15:00	6.78 pH	21.32 °C	794.71 µS/cm	0.65 mg/L	1,000,000 NTU	-69.5 mV	25.06 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 8/20/2024 2:43:15 PM
Project: GP-Plant Hammond
Operator Name: Elisabeth Russell

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 37.75 ft Total Depth: 47.75 ft Initial Depth to Water: 25.67 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 42 ft Estimated Total Volume Pumped: 14 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.08 ft	Instrument Used: Aqua TROLL 400 Serial Number: 965586
---	---	--

Test Notes:
Metals.
Fe = >7 mg/L Fe2+ = 1.7 mg/L.

Weather Conditions:
Sunny, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/20/2024 2:43 PM	00:00	6.71 pH	25.26 °C	766.38 µS/cm	2.02 mg/L	1,000,000 NTU	-49.4 mV	25.75 ft	200.00 ml/min
8/20/2024 2:48 PM	05:00	6.73 pH	22.88 °C	793.25 µS/cm	1.27 mg/L	1,000,000 NTU	-79.4 mV	25.75 ft	200.00 ml/min
8/20/2024 2:53 PM	10:00	6.76 pH	22.39 °C	795.18 µS/cm	0.88 mg/L	104.50 NTU	-86.6 mV	25.75 ft	200.00 ml/min
8/20/2024 2:58 PM	15:00	6.79 pH	22.24 °C	798.43 µS/cm	0.62 mg/L	36.20 NTU	-91.0 mV	25.75 ft	200.00 ml/min
8/20/2024 3:03 PM	20:00	6.80 pH	22.04 °C	794.75 µS/cm	0.50 mg/L	24.10 NTU	-92.1 mV	25.75 ft	200.00 ml/min
8/20/2024 3:08 PM	25:00	6.81 pH	22.08 °C	796.54 µS/cm	0.44 mg/L	15.80 NTU	-92.9 mV	25.75 ft	200.00 ml/min
8/20/2024 3:13 PM	30:00	6.82 pH	21.93 °C	796.72 µS/cm	0.34 mg/L	14.10 NTU	-92.9 mV	25.75 ft	200.00 ml/min
8/20/2024 3:18 PM	35:00	6.83 pH	22.02 °C	796.94 µS/cm	0.27 mg/L	12.20 NTU	-93.2 mV	25.75 ft	200.00 ml/min
8/20/2024 3:23 PM	40:00	6.83 pH	21.86 °C	794.82 µS/cm	0.23 mg/L	10.80 NTU	-92.5 mV	25.75 ft	200.00 ml/min
8/20/2024 3:28 PM	45:00	6.83 pH	21.90 °C	796.14 µS/cm	0.20 mg/L	7.76 NTU	-93.0 mV	25.75 ft	200.00 ml/min
8/20/2024 3:33 PM	50:00	6.83 pH	21.94 °C	794.57 µS/cm	0.18 mg/L	6.88 NTU	-91.7 mV	25.75 ft	200.00 ml/min
8/20/2024 3:38 PM	55:00	6.83 pH	22.08 °C	793.87 µS/cm	0.16 mg/L	6.31 NTU	-92.6 mV	25.75 ft	200.00 ml/min
8/20/2024 3:43 PM	01:00:00	6.84 pH	21.86 °C	789.42 µS/cm	0.15 mg/L	5.69 NTU	-92.0 mV	25.75 ft	200.00 ml/min
8/20/2024 3:48 PM	01:05:00	6.84 pH	21.73 °C	790.53 µS/cm	0.13 mg/L	5.00 NTU	-91.6 mV	25.75 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-07	Grab.

Low-Flow Test Report:

Test Date / Time: 8/20/2024 12:49:34 PM
Project: GP-Plant Hammond
Operator Name: Tristan Halterman

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 32.2 ft Total Depth: 42.2 ft Initial Depth to Water: 25.8 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 37.2 ft Estimated Total Volume Pumped: 8000 ml Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 968202
--	--	--

Test Notes:
Metals.
Fe2+ = 6.0 mg/L Fe = 4.5 mg/L.

Weather Conditions:
Sunny, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/20/2024 12:49 PM	00:00	6.39 pH	25.05 °C	650.04 µS/cm	1.86 mg/L	32.70 NTU	-26.3 mV	25.81 ft	200.00 ml/min
8/20/2024 12:54 PM	05:00	6.40 pH	22.35 °C	658.66 µS/cm	0.99 mg/L	18.80 NTU	-26.4 mV	25.81 ft	200.00 ml/min
8/20/2024 12:59 PM	10:00	6.40 pH	21.99 °C	678.95 µS/cm	0.54 mg/L	13.10 NTU	-30.0 mV	25.82 ft	200.00 ml/min
8/20/2024 1:04 PM	15:00	6.40 pH	22.00 °C	686.02 µS/cm	0.28 mg/L	11.90 NTU	-29.4 mV	25.82 ft	200.00 ml/min
8/20/2024 1:09 PM	20:00	6.40 pH	21.85 °C	688.87 µS/cm	0.19 mg/L	8.07 NTU	-29.8 mV	25.82 ft	200.00 ml/min
8/20/2024 1:14 PM	25:00	6.39 pH	21.90 °C	689.44 µS/cm	0.14 mg/L	7.41 NTU	-29.9 mV	25.82 ft	200.00 ml/min
8/20/2024 1:19 PM	30:00	6.40 pH	21.81 °C	689.81 µS/cm	0.11 mg/L	4.77 NTU	-30.2 mV	25.82 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.

Low-Flow Test Report:

Test Date / Time: 8/21/2024 1:19:31 PM
Project: GP-Plant Hammond
Operator Name: Tristan Halterman

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.47 ft Total Depth: 30.47 ft Initial Depth to Water: 16.45 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 25.47 ft Estimated Total Volume Pumped: 34000 ml Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 968202
---	---	--

Test Notes:
Metals.
Fe2+ = 0 mg/L Fe = 0 mg/L.

Weather Conditions:
Sunny, 75 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/21/2024 1:19 PM	00:00	6.59 pH	24.79 °C	684.89 µS/cm	0.53 mg/L	90.80 NTU	49.4 mV	16.49 ft	200.00 ml/min
8/21/2024 1:24 PM	05:00	6.83 pH	22.62 °C	699.73 µS/cm	0.21 mg/L	104.00 NTU	44.8 mV	16.45 ft	200.00 ml/min
8/21/2024 1:29 PM	10:00	6.87 pH	21.83 °C	700.49 µS/cm	0.17 mg/L	93.50 NTU	43.6 mV	16.45 ft	200.00 ml/min
8/21/2024 1:34 PM	15:00	6.88 pH	22.23 °C	697.25 µS/cm	0.17 mg/L	82.60 NTU	45.7 mV	16.45 ft	200.00 ml/min
8/21/2024 1:39 PM	20:00	6.89 pH	21.81 °C	693.35 µS/cm	0.18 mg/L	74.90 NTU	49.5 mV	16.45 ft	200.00 ml/min
8/21/2024 1:44 PM	25:00	6.89 pH	21.99 °C	692.53 µS/cm	0.19 mg/L	70.40 NTU	51.3 mV	16.45 ft	200.00 ml/min
8/21/2024 1:49 PM	30:00	6.88 pH	22.26 °C	689.60 µS/cm	0.18 mg/L	64.10 NTU	52.8 mV	16.45 ft	200.00 ml/min
8/21/2024 1:54 PM	35:00	6.89 pH	22.11 °C	687.64 µS/cm	0.25 mg/L	65.90 NTU	54.6 mV	16.45 ft	200.00 ml/min
8/21/2024 1:59 PM	40:00	6.89 pH	21.60 °C	685.87 µS/cm	0.22 mg/L	58.50 NTU	56.3 mV	16.45 ft	200.00 ml/min
8/21/2024 2:04 PM	45:00	6.89 pH	21.87 °C	681.36 µS/cm	0.19 mg/L	57.00 NTU	57.8 mV	16.45 ft	200.00 ml/min
8/21/2024 2:09 PM	50:00	6.88 pH	22.10 °C	678.48 µS/cm	0.21 mg/L	52.40 NTU	59.0 mV	16.45 ft	200.00 ml/min
8/21/2024 2:14 PM	55:00	6.87 pH	22.42 °C	677.27 µS/cm	0.24 mg/L	43.80 NTU	60.3 mV	16.45 ft	200.00 ml/min
8/21/2024 2:19 PM	01:00:00	6.87 pH	22.64 °C	675.57 µS/cm	0.27 mg/L	38.60 NTU	62.1 mV	16.45 ft	200.00 ml/min

8/21/2024 2:24 PM	01:05:00	6.87 pH	22.08 °C	679.77 µS/cm	0.25 mg/L	34.90 NTU	64.9 mV	16.45 ft	200.00 ml/min
8/21/2024 2:29 PM	01:10:00	6.86 pH	22.28 °C	681.45 µS/cm	0.23 mg/L	30.70 NTU	66.5 mV	16.45 ft	200.00 ml/min
8/21/2024 2:34 PM	01:15:00	6.85 pH	23.02 °C	680.28 µS/cm	0.24 mg/L	27.60 NTU	67.9 mV	16.45 ft	200.00 ml/min
8/21/2024 2:39 PM	01:20:00	6.85 pH	22.43 °C	678.17 µS/cm	0.26 mg/L	23.40 NTU	86.1 mV	16.45 ft	200.00 ml/min
8/21/2024 2:44 PM	01:25:00	6.85 pH	22.82 °C	678.87 µS/cm	0.23 mg/L	19.80 NTU	72.7 mV	16.45 ft	200.00 ml/min
8/21/2024 2:49 PM	01:30:00	6.85 pH	22.03 °C	679.50 µS/cm	0.29 mg/L	19.00 NTU	74.7 mV	16.45 ft	200.00 ml/min
8/21/2024 2:54 PM	01:35:00	6.85 pH	22.73 °C	680.87 µS/cm	0.28 mg/L	17.40 NTU	74.4 mV	16.45 ft	200.00 ml/min
8/21/2024 2:59 PM	01:40:00	6.84 pH	23.01 °C	672.68 µS/cm	0.64 mg/L	15.40 NTU	94.4 mV	16.45 ft	200.00 ml/min
8/21/2024 3:04 PM	01:45:00	6.84 pH	23.02 °C	673.17 µS/cm	0.26 mg/L	11.30 NTU	100.8 mV	16.45 ft	200.00 ml/min
8/21/2024 3:09 PM	01:50:00	6.84 pH	23.15 °C	668.87 µS/cm	0.26 mg/L	11.30 NTU	85.1 mV	16.45 ft	200.00 ml/min
8/21/2024 3:14 PM	01:55:00	6.83 pH	23.33 °C	668.32 µS/cm	0.24 mg/L	10.21 NTU	86.9 mV	16.45 ft	200.00 ml/min
8/21/2024 3:19 PM	02:00:00	6.85 pH	23.31 °C	660.35 µS/cm	0.30 mg/L	10.09 NTU	90.4 mV	16.45 ft	200.00 ml/min
8/21/2024 3:24 PM	02:05:00	6.83 pH	23.06 °C	662.19 µS/cm	0.34 mg/L	9.75 NTU	93.0 mV	16.45 ft	200.00 ml/min
8/21/2024 3:29 PM	02:10:00	6.84 pH	23.15 °C	668.24 µS/cm	0.33 mg/L	7.04 NTU	95.0 mV	16.45 ft	200.00 ml/min
8/21/2024 3:34 PM	02:15:00	6.84 pH	23.24 °C	664.79 µS/cm	0.31 mg/L	7.25 NTU	96.7 mV	16.45 ft	200.00 ml/min
8/21/2024 3:39 PM	02:20:00	6.84 pH	23.07 °C	663.17 µS/cm	0.36 mg/L	6.79 NTU	99.5 mV	16.45 ft	200.00 ml/min
8/21/2024 3:44 PM	02:25:00	6.83 pH	23.20 °C	660.58 µS/cm	0.47 mg/L	5.84 NTU	128.4 mV	16.45 ft	200.00 ml/min
8/21/2024 3:49 PM	02:30:00	6.83 pH	23.16 °C	657.18 µS/cm	0.31 mg/L	5.47 NTU	107.0 mV	16.45 ft	200.00 ml/min
8/21/2024 3:54 PM	02:35:00	6.83 pH	23.47 °C	658.52 µS/cm	0.30 mg/L	5.12 NTU	106.9 mV	16.45 ft	200.00 ml/min
8/21/2024 3:59 PM	02:40:00	6.83 pH	23.47 °C	665.92 µS/cm	0.30 mg/L	4.84 NTU	108.0 mV	16.45 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.

Low-Flow Test Report:

Test Date / Time: 8/20/2024 4:04:07 PM
Project: GP-Plant Hammond
Operator Name: Tristan Halterman

Location Name: PT-10 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.45 ft Total Depth: 30.45 ft Initial Depth to Water: 16.51 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 25.45 ft Estimated Total Volume Pumped: 9000 ml Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 968202
---	---	--

Test Notes:
Metals.
Fe2+ = 0 mg/L Fe = 0 mg/L

Weather Conditions:
Sunny, 85 degrees F

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/20/2024 4:04 PM	00:00	6.65 pH	25.88 °C	624.90 µS/cm	0.54 mg/L	27.80 NTU	100.3 mV	16.53 ft	200.00 ml/min
8/20/2024 4:09 PM	05:00	6.81 pH	23.35 °C	667.66 µS/cm	0.35 mg/L	22.00 NTU	96.9 mV	16.53 ft	200.00 ml/min
8/20/2024 4:14 PM	10:00	6.84 pH	23.20 °C	672.19 µS/cm	0.68 mg/L	18.20 NTU	121.9 mV	16.53 ft	200.00 ml/min
8/20/2024 4:19 PM	15:00	6.86 pH	22.79 °C	670.00 µS/cm	0.50 mg/L	13.90 NTU	104.9 mV	16.53 ft	200.00 ml/min
8/20/2024 4:24 PM	20:00	6.85 pH	23.02 °C	673.75 µS/cm	0.53 mg/L	8.19 NTU	134.2 mV	16.53 ft	200.00 ml/min
8/20/2024 4:29 PM	25:00	6.87 pH	22.80 °C	669.19 µS/cm	0.48 mg/L	7.15 NTU	113.2 mV	16.53 ft	200.00 ml/min
8/20/2024 4:34 PM	30:00	6.87 pH	22.95 °C	668.09 µS/cm	0.43 mg/L	5.27 NTU	142.0 mV	16.53 ft	200.00 ml/min
8/20/2024 4:39 PM	35:00	6.86 pH	22.76 °C	664.93 µS/cm	0.48 mg/L	4.27 NTU	149.9 mV	16.53 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.

Low-Flow Test Report:

Test Date / Time: 8/21/2024 9:28:33 AM
Project: GP-Plant Hammond
Operator Name: Tristan Halterman

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 16.9 ft Total Depth: 26.9 ft Initial Depth to Water: 13.05 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 21.9 ft Estimated Total Volume Pumped: 40000 ml Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.01 ft	Instrument Used: Aqua TROLL 400 Serial Number: 968202
--	--	--

Test Notes:
Metals.
Fe2+ = 0 mg/L Fe = 0 mg/L

Weather Conditions:
Sunny, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/21/2024 9:28 AM	00:00	6.52 pH	22.37 °C	623.82 µS/cm	0.68 mg/L	32.60 NTU	116.2 mV	13.05 ft	200.00 ml/min
8/21/2024 9:33 AM	05:00	6.77 pH	21.01 °C	664.09 µS/cm	0.60 mg/L	48.60 NTU	118.9 mV	13.05 ft	200.00 ml/min
8/21/2024 9:38 AM	10:00	6.83 pH	20.88 °C	665.81 µS/cm	0.43 mg/L	51.00 NTU	93.8 mV	13.05 ft	200.00 ml/min
8/21/2024 9:43 AM	15:00	6.84 pH	20.87 °C	662.73 µS/cm	0.41 mg/L	43.60 NTU	92.0 mV	13.05 ft	200.00 ml/min
8/21/2024 9:48 AM	20:00	6.84 pH	20.87 °C	662.25 µS/cm	0.23 mg/L	42.00 NTU	114.8 mV	13.05 ft	200.00 ml/min
8/21/2024 9:53 AM	25:00	6.84 pH	21.01 °C	652.56 µS/cm	0.38 mg/L	37.30 NTU	97.6 mV	13.05 ft	200.00 ml/min
8/21/2024 9:58 AM	30:00	6.84 pH	21.03 °C	656.12 µS/cm	0.71 mg/L	33.70 NTU	97.4 mV	13.05 ft	200.00 ml/min
8/21/2024 10:03 AM	35:00	6.84 pH	21.05 °C	653.76 µS/cm	0.67 mg/L	31.80 NTU	98.6 mV	13.05 ft	200.00 ml/min
8/21/2024 10:08 AM	40:00	6.84 pH	21.10 °C	650.65 µS/cm	0.62 mg/L	25.30 NTU	100.0 mV	13.05 ft	200.00 ml/min
8/21/2024 10:13 AM	45:00	6.83 pH	21.14 °C	651.54 µS/cm	0.36 mg/L	20.40 NTU	101.4 mV	13.05 ft	200.00 ml/min
8/21/2024 10:18 AM	50:00	6.84 pH	21.18 °C	651.14 µS/cm	0.34 mg/L	19.20 NTU	102.7 mV	13.06 ft	200.00 ml/min
8/21/2024 10:23 AM	55:00	6.84 pH	21.25 °C	652.48 µS/cm	0.33 mg/L	14.10 NTU	103.8 mV	13.06 ft	200.00 ml/min
8/21/2024 10:28 AM	01:00:00	6.84 pH	21.37 °C	644.58 µS/cm	0.30 mg/L	12.30 NTU	105.4 mV	13.06 ft	200.00 ml/min

8/21/2024 10:33 AM	01:05:00	6.83 pH	21.14 °C	652.90 µS/cm	0.26 mg/L	12.40 NTU	106.9 mV	13.06 ft	200.00 ml/min
8/21/2024 10:38 AM	01:10:00	6.83 pH	21.20 °C	645.92 µS/cm	0.23 mg/L	12.10 NTU	107.9 mV	13.07 ft	200.00 ml/min
8/21/2024 10:43 AM	01:15:00	6.83 pH	21.41 °C	647.42 µS/cm	0.21 mg/L	10.10 NTU	107.7 mV	13.07 ft	200.00 ml/min
8/21/2024 10:48 AM	01:20:00	6.83 pH	21.38 °C	646.55 µS/cm	0.19 mg/L	9.14 NTU	107.8 mV	13.07 ft	200.00 ml/min
8/21/2024 10:53 AM	01:25:00	6.83 pH	21.63 °C	640.34 µS/cm	0.17 mg/L	10.10 NTU	108.5 mV	13.07 ft	200.00 ml/min
8/21/2024 10:58 AM	01:30:00	6.83 pH	21.59 °C	641.03 µS/cm	0.15 mg/L	17.90 NTU	109.2 mV	13.07 ft	200.00 ml/min
8/21/2024 11:03 AM	01:35:00	6.84 pH	21.45 °C	639.79 µS/cm	0.14 mg/L	20.10 NTU	107.8 mV	13.07 ft	200.00 ml/min
8/21/2024 11:08 AM	01:40:00	6.83 pH	21.57 °C	638.02 µS/cm	0.30 mg/L	14.00 NTU	107.8 mV	13.07 ft	200.00 ml/min
8/21/2024 11:13 AM	01:45:00	6.84 pH	21.32 °C	641.18 µS/cm	0.14 mg/L	13.40 NTU	108.3 mV	13.07 ft	200.00 ml/min
8/21/2024 11:18 AM	01:50:00	6.83 pH	21.34 °C	643.12 µS/cm	0.12 mg/L	11.80 NTU	108.4 mV	13.07 ft	200.00 ml/min
8/21/2024 11:23 AM	01:55:00	6.83 pH	21.29 °C	638.13 µS/cm	0.15 mg/L	11.60 NTU	108.0 mV	13.07 ft	200.00 ml/min
8/21/2024 11:28 AM	02:00:00	6.83 pH	21.68 °C	635.85 µS/cm	0.17 mg/L	10.30 NTU	108.0 mV	13.07 ft	200.00 ml/min
8/21/2024 11:33 AM	02:05:00	6.83 pH	21.51 °C	618.42 µS/cm	0.15 mg/L	10.20 NTU	109.7 mV	13.07 ft	200.00 ml/min
8/21/2024 11:38 AM	02:10:00	6.82 pH	21.54 °C	632.64 µS/cm	0.14 mg/L	8.20 NTU	110.6 mV	13.07 ft	200.00 ml/min
8/21/2024 11:43 AM	02:15:00	6.83 pH	21.63 °C	644.80 µS/cm	0.09 mg/L	7.03 NTU	111.9 mV	13.07 ft	200.00 ml/min
8/21/2024 11:48 AM	02:20:00	6.83 pH	21.58 °C	639.36 µS/cm	0.10 mg/L	6.52 NTU	111.8 mV	13.07 ft	200.00 ml/min
8/21/2024 11:53 AM	02:25:00	6.82 pH	21.56 °C	642.97 µS/cm	0.11 mg/L	7.70 NTU	112.4 mV	13.07 ft	200.00 ml/min
8/21/2024 11:58 AM	02:30:00	6.84 pH	21.54 °C	641.87 µS/cm	0.11 mg/L	6.07 NTU	111.9 mV	13.07 ft	200.00 ml/min
8/21/2024 12:03 PM	02:35:00	6.82 pH	21.87 °C	646.04 µS/cm	0.08 mg/L	5.65 NTU	112.6 mV	13.07 ft	200.00 ml/min
8/21/2024 12:08 PM	02:40:00	6.82 pH	21.94 °C	656.34 µS/cm	0.08 mg/L	5.87 NTU	113.3 mV	13.07 ft	200.00 ml/min
8/21/2024 12:13 PM	02:45:00	6.82 pH	21.85 °C	653.48 µS/cm	0.13 mg/L	5.03 NTU	114.1 mV	13.07 ft	200.00 ml/min
8/21/2024 12:18 PM	02:50:00	6.82 pH	21.90 °C	658.01 µS/cm	1.20 mg/L	4.24 NTU	146.1 mV	13.07 ft	200.00 ml/min
8/21/2024 12:23 PM	02:55:00	6.83 pH	21.37 °C	659.04 µS/cm	1.39 mg/L	4.16 NTU	120.4 mV	13.06 ft	200.00 ml/min
8/21/2024 12:28 PM	03:00:00	6.82 pH	21.45 °C	676.95 µS/cm	0.17 mg/L	3.86 NTU	115.2 mV	13.06 ft	200.00 ml/min
8/21/2024 12:33 PM	03:05:00	6.83 pH	21.69 °C	665.53 µS/cm	0.16 mg/L	3.66 NTU	113.5 mV	13.06 ft	200.00 ml/min
8/21/2024 12:38 PM	03:10:00	6.82 pH	21.37 °C	660.19 µS/cm	0.12 mg/L	4.40 NTU	112.5 mV	13.06 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

HAM-PT-11	Grab.
-----------	-------

Low-Flow Test Report:

Test Date / Time: 8/21/2024 9:34:46 AM
Project: GP-Plant Hammond
Operator Name: Elisabeth Russell

Location Name: PT-12 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.3 ft Total Depth: 27.3 ft Initial Depth to Water: 12.81 ft	Pump Type: peri Tubing Type: Polyethylene Pump Intake From TOC: 22 ft Estimated Total Volume Pumped: 39.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 965586
---	--	--

Test Notes:
Metals.
Fe = 0 mg/l Fe2+ = 0 mg/L.

Weather Conditions:
Sunny, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/21/2024 9:34 AM	00:00	6.77 pH	19.61 °C	663.10 µS/cm	0.54 mg/L	1,000,000 NTU	59.0 mV	12.81 ft	200.00 ml/min
8/21/2024 9:39 AM	05:00	6.76 pH	19.54 °C	705.81 µS/cm	0.42 mg/L	1,000,000 NTU	60.1 mV	12.81 ft	200.00 ml/min
8/21/2024 9:44 AM	10:00	6.79 pH	19.52 °C	706.47 µS/cm	0.43 mg/L	1,000,000 NTU	60.2 mV	12.83 ft	200.00 ml/min
8/21/2024 9:49 AM	15:00	6.81 pH	19.54 °C	710.86 µS/cm	0.35 mg/L	1,000,000 NTU	60.7 mV	12.83 ft	200.00 ml/min
8/21/2024 9:54 AM	20:00	6.83 pH	19.59 °C	711.61 µS/cm	0.44 mg/L	1,000,000 NTU	61.0 mV	12.83 ft	200.00 ml/min
8/21/2024 9:59 AM	25:00	6.83 pH	19.59 °C	705.66 µS/cm	0.42 mg/L	1,000,000 NTU	62.0 mV	12.83 ft	200.00 ml/min
8/21/2024 10:04 AM	30:00	6.85 pH	19.65 °C	709.78 µS/cm	0.29 mg/L	1,000,000 NTU	61.6 mV	12.83 ft	200.00 ml/min
8/21/2024 10:09 AM	35:00	6.84 pH	19.71 °C	713.72 µS/cm	0.33 mg/L	1,000,000 NTU	62.3 mV	12.83 ft	200.00 ml/min
8/21/2024 10:14 AM	40:00	6.84 pH	19.75 °C	711.28 µS/cm	0.29 mg/L	99.80 NTU	62.5 mV	12.83 ft	200.00 ml/min
8/21/2024 10:19 AM	45:00	6.84 pH	19.85 °C	711.20 µS/cm	0.36 mg/L	100.30 NTU	62.7 mV	12.83 ft	200.00 ml/min
8/21/2024 10:24 AM	50:00	6.84 pH	19.90 °C	709.98 µS/cm	0.33 mg/L	97.80 NTU	62.7 mV	12.83 ft	200.00 ml/min
8/21/2024 10:29 AM	55:00	6.83 pH	20.00 °C	707.97 µS/cm	0.33 mg/L	91.90 NTU	62.9 mV	12.83 ft	200.00 ml/min
8/21/2024 10:34 AM	01:00:00	6.83 pH	20.21 °C	708.28 µS/cm	0.34 mg/L	87.70 NTU	63.0 mV	12.83 ft	200.00 ml/min
8/21/2024 10:39 AM	01:05:00	6.46 pH	21.03 °C	666.98 µS/cm	0.66 mg/L	82.40 NTU	70.2 mV	12.83 ft	200.00 ml/min
8/21/2024 10:44 AM	01:10:00	6.44 pH	21.65 °C	683.12 µS/cm	0.11 mg/L	65.60 NTU	65.6 mV	12.83 ft	200.00 ml/min

8/21/2024 10:49 AM	01:15:00	6.69 pH	21.41 °C	696.79 µS/cm	0.08 mg/L	77.50 NTU	63.7 mV	12.83 ft	200.00 ml/min
8/21/2024 10:54 AM	01:20:00	6.75 pH	21.46 °C	698.40 µS/cm	0.20 mg/L	83.60 NTU	63.7 mV	12.83 ft	200.00 ml/min
8/21/2024 10:59 AM	01:25:00	6.75 pH	21.54 °C	700.10 µS/cm	0.23 mg/L	75.40 NTU	63.9 mV	12.83 ft	200.00 ml/min
8/21/2024 11:04 AM	01:30:00	6.78 pH	21.50 °C	696.46 µS/cm	0.27 mg/L	87.20 NTU	63.3 mV	12.83 ft	200.00 ml/min
8/21/2024 11:09 AM	01:35:00	6.80 pH	21.75 °C	695.34 µS/cm	0.09 mg/L	75.00 NTU	62.9 mV	12.83 ft	200.00 ml/min
8/21/2024 11:14 AM	01:40:00	6.81 pH	21.45 °C	698.08 µS/cm	0.07 mg/L	68.00 NTU	63.0 mV	12.83 ft	200.00 ml/min
8/21/2024 11:19 AM	01:45:00	6.81 pH	21.59 °C	697.62 µS/cm	0.07 mg/L	55.10 NTU	62.9 mV	12.83 ft	200.00 ml/min
8/21/2024 11:24 AM	01:50:00	6.81 pH	21.62 °C	696.40 µS/cm	0.06 mg/L	49.10 NTU	63.0 mV	12.83 ft	200.00 ml/min
8/21/2024 11:29 AM	01:55:00	6.81 pH	22.06 °C	697.54 µS/cm	0.06 mg/L	45.60 NTU	62.0 mV	12.83 ft	200.00 ml/min
8/21/2024 11:34 AM	02:00:00	6.81 pH	21.83 °C	693.25 µS/cm	0.06 mg/L	40.00 NTU	62.5 mV	12.83 ft	200.00 ml/min
8/21/2024 11:39 AM	02:05:00	6.81 pH	21.79 °C	695.41 µS/cm	0.06 mg/L	37.80 NTU	62.7 mV	12.83 ft	200.00 ml/min
8/21/2024 11:44 AM	02:10:00	6.81 pH	21.72 °C	696.34 µS/cm	0.06 mg/L	33.40 NTU	62.8 mV	12.83 ft	200.00 ml/min
8/21/2024 11:49 AM	02:15:00	6.81 pH	21.88 °C	697.88 µS/cm	0.06 mg/L	30.40 NTU	63.0 mV	12.83 ft	200.00 ml/min
8/21/2024 11:54 AM	02:20:00	6.81 pH	21.90 °C	699.22 µS/cm	0.06 mg/L	24.30 NTU	62.0 mV	12.83 ft	200.00 ml/min
8/21/2024 11:59 AM	02:25:00	6.81 pH	22.04 °C	699.08 µS/cm	0.06 mg/L	21.30 NTU	61.9 mV	12.83 ft	200.00 ml/min
8/21/2024 12:04 PM	02:30:00	6.81 pH	22.26 °C	695.27 µS/cm	0.06 mg/L	18.30 NTU	61.8 mV	12.83 ft	200.00 ml/min
8/21/2024 12:09 PM	02:35:00	6.81 pH	22.40 °C	695.46 µS/cm	0.06 mg/L	14.50 NTU	61.2 mV	12.83 ft	200.00 ml/min
8/21/2024 12:14 PM	02:40:00	6.82 pH	22.28 °C	690.47 µS/cm	0.05 mg/L	10.71 NTU	61.9 mV	12.83 ft	200.00 ml/min
8/21/2024 12:19 PM	02:45:00	6.82 pH	22.59 °C	694.41 µS/cm	0.06 mg/L	9.97 NTU	61.8 mV	12.83 ft	200.00 ml/min
8/21/2024 12:24 PM	02:50:00	6.83 pH	21.74 °C	695.58 µS/cm	0.06 mg/L	8.88 NTU	62.2 mV	12.83 ft	200.00 ml/min
8/21/2024 12:29 PM	02:55:00	6.83 pH	22.02 °C	706.69 µS/cm	0.25 mg/L	6.70 NTU	63.0 mV	12.83 ft	200.00 ml/min
8/21/2024 12:34 PM	03:00:00	6.83 pH	22.11 °C	669.88 µS/cm	0.16 mg/L	5.42 NTU	62.8 mV	12.83 ft	200.00 ml/min
8/21/2024 12:39 PM	03:05:00	6.84 pH	22.01 °C	704.74 µS/cm	0.08 mg/L	3.11 NTU	61.5 mV	12.83 ft	200.00 ml/min
8/21/2024 12:44 PM	03:10:00	6.84 pH	22.22 °C	700.15 µS/cm	0.06 mg/L	2.92 NTU	63.3 mV	12.83 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-12	

Low-Flow Test Report:

Test Date / Time: 8/20/2024 11:20:38 AM
Project: GP-Plant Hammond
Operator Name: Elisabeth Russell

Location Name: PT-13 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.3 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 49 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.15 ft	Instrument Used: Aqua TROLL 400 Serial Number: 965586
--	--	--

Test Notes:
Metals.
Fe > 7 mg/L Fe2+ > 10mg/L.

Weather Conditions:
Sunny, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/20/2024 11:20 AM	00:00	6.52 pH	21.99 °C	800.23 µS/cm	1.78 mg/L	80.10 NTU	-1.8 mV	25.45 ft	200.00 ml/min
8/20/2024 11:25 AM	05:00	6.55 pH	22.10 °C	795.34 µS/cm	1.39 mg/L	21.00 NTU	-19.8 mV	25.45 ft	200.00 ml/min
8/20/2024 11:30 AM	10:00	6.57 pH	22.04 °C	797.08 µS/cm	1.22 mg/L	17.50 NTU	-35.6 mV	25.45 ft	200.00 ml/min
8/20/2024 11:35 AM	15:00	6.59 pH	21.94 °C	794.09 µS/cm	1.13 mg/L	8.50 NTU	-45.8 mV	25.45 ft	200.00 ml/min
8/20/2024 11:40 AM	20:00	6.60 pH	21.86 °C	795.04 µS/cm	1.06 mg/L	7.76 NTU	-54.0 mV	25.45 ft	200.00 ml/min
8/20/2024 11:45 AM	25:00	6.61 pH	21.84 °C	794.28 µS/cm	1.00 mg/L	5.56 NTU	-58.2 mV	25.45 ft	200.00 ml/min
8/20/2024 11:50 AM	30:00	6.62 pH	21.82 °C	794.29 µS/cm	0.97 mg/L	3.99 NTU	-61.6 mV	25.45 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-13	Grab.

Low-Flow Test Report:

Test Date / Time: 8/20/2024 11:28:14 AM
Project: GP-Plant Hammond
Operator Name: Tristan Halterman

Location Name: PT-14 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.34 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 8000 ml Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.14 ft	Instrument Used: Aqua TROLL 400 Serial Number: 968202
---	--	--

Test Notes:
Metals.
Fe2+ = 3.0 mg/L Fe = 4.0 mg/L

Weather Conditions:
Sunny, windy, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/20/2024 11:28 AM	00:00	6.55 pH	21.63 °C	844.11 µS/cm	2.21 mg/L	5.40 NTU	-67.4 mV	25.50 ft	200.00 ml/min
8/20/2024 11:33 AM	05:00	6.66 pH	21.21 °C	837.67 µS/cm	1.90 mg/L	5.27 NTU	-73.0 mV	25.50 ft	200.00 ml/min
8/20/2024 11:38 AM	10:00	6.69 pH	21.10 °C	840.13 µS/cm	1.75 mg/L	1.83 NTU	-80.8 mV	25.48 ft	200.00 ml/min
8/20/2024 11:43 AM	15:00	6.72 pH	21.13 °C	838.26 µS/cm	1.57 mg/L	1.82 NTU	-78.0 mV	25.48 ft	200.00 ml/min
8/20/2024 11:48 AM	20:00	6.72 pH	21.09 °C	837.50 µS/cm	1.56 mg/L	1.24 NTU	-83.6 mV	25.48 ft	200.00 ml/min
8/20/2024 11:53 AM	25:00	6.74 pH	21.01 °C	835.42 µS/cm	1.48 mg/L	1.98 NTU	-85.0 mV	25.48 ft	200.00 ml/min
8/20/2024 11:58 AM	30:00	6.75 pH	21.02 °C	834.47 µS/cm	1.51 mg/L	1.12 NTU	-81.1 mV	25.48 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-14	Grab.

Low-Flow Test Report:

Test Date / Time: 8/20/2024 12:50:18 PM
Project: GP-Plant Hammond
Operator Name: Elisabeth Russell

Location Name: PT-15 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.3 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 6.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 965586
--	---	--

Test Notes:
Metals.
Fe = 5 mg/L Fe2+ = 2.5 mg/L.

Weather Conditions:
Sunny, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
8/20/2024 12:50 PM	00:00	6.63 pH	24.33 °C	728.98 µS/cm	1.59 mg/L	14.60 NTU	-54.3 mV	25.30 ft	200.00 ml/min
8/20/2024 12:55 PM	05:00	6.66 pH	22.53 °C	744.15 µS/cm	1.23 mg/L	7.74 NTU	-62.0 mV	25.30 ft	200.00 ml/min
8/20/2024 1:00 PM	10:00	6.69 pH	22.26 °C	745.08 µS/cm	1.15 mg/L	4.83 NTU	-64.2 mV	25.30 ft	200.00 ml/min
8/20/2024 1:05 PM	15:00	6.70 pH	22.17 °C	741.49 µS/cm	0.94 mg/L	3.66 NTU	-64.5 mV	25.30 ft	200.00 ml/min
8/20/2024 1:10 PM	20:00	6.71 pH	22.03 °C	739.57 µS/cm	0.88 mg/L	3.90 NTU	-64.4 mV	25.30 ft	200.00 ml/min
8/20/2024 1:15 PM	25:00	6.72 pH	21.99 °C	741.05 µS/cm	0.91 mg/L	4.97 NTU	-63.2 mV	25.30 ft	200.00 ml/min
8/20/2024 1:20 PM	30:00	6.72 pH	21.77 °C	740.25 µS/cm	0.77 mg/L	4.41 NTU	-64.1 mV	25.30 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-15	Grab
HAM-AP1-FD-01	Grab.

Low-Flow Test Report:

Test Date / Time: 9/5/2024 2:17:52 PM
Project: GP Plant Hammond
Operator Name: Jacob Tracy

Location Name: INW-03 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.4 ft Total Depth: 27.4 ft Initial Depth to Water: 13.56 ft	Pump Type: Peristaltic Tubing Type: Poly Pump Intake From TOC: 22.4 ft Estimated Total Volume Pumped: 3 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883553
--	---	--

Test Notes:
Field parameters only, no sample.

Weather Conditions:
Sunny, 85F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 1	+/- 0.3	
9/5/2024 2:17 PM	00:00	8.14 pH	22.04 °C	431.54 µS/cm	0.20 mg/L	23.30 NTU	19.5 mV	13.56 ft	200.00 ml/min
9/5/2024 2:22 PM	05:00	7.56 pH	21.17 °C	651.03 µS/cm	0.11 mg/L	12.10 NTU	-150.7 mV	13.56 ft	200.00 ml/min
9/5/2024 2:27 PM	10:00	7.50 pH	21.03 °C	763.29 µS/cm	0.07 mg/L	9.03 NTU	-119.9 mV	13.56 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 9/5/2024 12:29:51 PM
Project: GP Plant Hammond
Operator Name: Jacob Tracy

Location Name: INW-04 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.98 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 4 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.06 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883553
--	--	--

Test Notes:
Field parameters only, no sample.

Weather Conditions:
Sunny, 85F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 1	+/- 0.3	
9/5/2024 12:29 PM	00:00	6.73 pH	21.91 °C	708.81 µS/cm	0.11 mg/L	++++	-43.5 mV	26.04 ft	200.00 ml/min
9/5/2024 12:34 PM	05:00	6.65 pH	20.85 °C	710.76 µS/cm	0.03 mg/L	++++	-43.2 mV	26.04 ft	200.00 ml/min
9/5/2024 12:39 PM	10:00	6.62 pH	21.14 °C	716.76 µS/cm	0.02 mg/L	++++	-53.9 mV	26.04 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 9/5/2024 1:01:52 PM
Project: GP Plant Hammond
Operator Name: Jacob Tracy

Location Name: INW-05 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.56 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 3 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.06 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883553
--	--	--

Test Notes:
Field parameters only, no sample.

Weather Conditions:
Sunny, 85F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 1	+/- 0.3	
9/5/2024 1:01 PM	00:00	6.94 pH	22.31 °C	802.19 µS/cm	0.05 mg/L	++++	-113.1 mV	25.59 ft	200.00 ml/min
9/5/2024 1:03 PM	01:10	6.95 pH	22.12 °C	802.33 µS/cm	0.06 mg/L	++++	-113.4 mV	25.56 ft	200.00 ml/min
9/5/2024 1:08 PM	06:10	7.05 pH	21.28 °C	808.51 µS/cm	0.07 mg/L	++++	-112.7 mV	25.62 ft	200.00 ml/min
9/5/2024 1:13 PM	11:10	7.07 pH	21.57 °C	811.13 µS/cm	0.07 mg/L	++++	-114.3 mV	25.62 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 9/4/2024 3:02:09 PM
Project: GP Plant Hammond
Operator Name: Selena Wang

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 37.75 ft Total Depth: 47.75 ft Initial Depth to Water: 26.21 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 42.75 ft Estimated Total Volume Pumped: 6 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883561
---	--	--

Test Notes:
Full App. III and IV and Major Ions. Fe = 5.5 mg/L Fe2+ = 2.0 mg/L.

Weather Conditions:
Sunny, 85F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 10	+/- 0.3	
9/4/2024 3:02 PM	00:00	6.90 pH	20.88 °C	708.93 µS/cm	0.22 mg/L	6.43 NTU	-59.6 mV	26.21 ft	200.00 ml/min
9/4/2024 3:07 PM	05:00	6.89 pH	20.47 °C	726.74 µS/cm	0.16 mg/L	5.25 NTU	-59.9 mV	26.21 ft	200.00 ml/min
9/4/2024 3:12 PM	10:00	6.89 pH	20.31 °C	748.72 µS/cm	0.14 mg/L	7.26 NTU	-81.1 mV	26.21 ft	200.00 ml/min
9/4/2024 3:17 PM	15:00	6.89 pH	20.12 °C	747.35 µS/cm	0.14 mg/L	4.72 NTU	-81.0 mV	26.21 ft	200.00 ml/min
9/4/2024 3:22 PM	20:00	6.89 pH	19.95 °C	751.51 µS/cm	0.13 mg/L	3.01 NTU	-82.4 mV	26.21 ft	200.00 ml/min
9/4/2024 3:27 PM	25:00	6.88 pH	19.99 °C	752.34 µS/cm	0.13 mg/L	2.17 NTU	-83.1 mV	26.21 ft	200.00 ml/min
9/4/2024 3:32 PM	30:00	6.89 pH	20.23 °C	752.53 µS/cm	0.14 mg/L	1.66 NTU	-83.5 mV	26.21 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-07	Grab.

Low-Flow Test Report:

Test Date / Time: 9/5/2024 11:05:14 AM
Project: GP Plant Hammond
Operator Name: Jamie Newsome

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 31.93 ft Total Depth: 41.93 ft Initial Depth to Water: 26.12 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 36.93 ft Estimated Total Volume Pumped: 20 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 843593
---	--	--

Test Notes:
Full App. III and IV and Major Ions. Fe = 3.5 mg/L, Fe2+= 3.0 mg/L.

Weather Conditions:
Cloudy, 80F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 10	+/- 5	
9/5/2024 11:05 AM	00:00	6.37 pH	20.68 °C	457.60 µS/cm	6.60 mg/L	6.84 NTU	-11.6 mV	26.12 ft	200.00 ml/min
9/5/2024 11:10 AM	05:00	6.40 pH	21.06 °C	480.05 µS/cm	6.85 mg/L	6.90 NTU	-19.0 mV	26.12 ft	200.00 ml/min
9/5/2024 11:15 AM	10:00	6.45 pH	21.57 °C	478.17 µS/cm	7.64 mg/L	7.10 NTU	-26.0 mV	26.12 ft	200.00 ml/min
9/5/2024 11:20 AM	15:00	6.50 pH	21.91 °C	483.13 µS/cm	8.24 mg/L	10.90 NTU	-30.8 mV	26.12 ft	200.00 ml/min
9/5/2024 11:25 AM	20:00	6.55 pH	22.27 °C	495.41 µS/cm	8.52 mg/L	8.45 NTU	-35.7 mV	26.12 ft	200.00 ml/min
9/5/2024 11:30 AM	25:00	6.55 pH	21.66 °C	497.74 µS/cm	8.18 mg/L	17.70 NTU	-31.0 mV	26.12 ft	200.00 ml/min
9/5/2024 11:35 AM	30:00	6.54 pH	21.59 °C	503.96 µS/cm	7.92 mg/L	17.30 NTU	-27.8 mV	26.12 ft	200.00 ml/min
9/5/2024 11:40 AM	35:00	6.50 pH	21.12 °C	516.78 µS/cm	7.54 mg/L	16.40 NTU	-24.4 mV	26.12 ft	200.00 ml/min
9/5/2024 11:45 AM	40:00	6.46 pH	20.57 °C	528.78 µS/cm	6.93 mg/L	15.50 NTU	-21.2 mV	26.12 ft	200.00 ml/min
9/5/2024 11:50 AM	45:00	6.45 pH	20.39 °C	548.96 µS/cm	6.78 mg/L	14.80 NTU	-22.0 mV	26.12 ft	200.00 ml/min
9/5/2024 11:55 AM	50:00	6.44 pH	20.39 °C	558.63 µS/cm	6.50 mg/L	14.20 NTU	-22.6 mV	26.12 ft	200.00 ml/min
9/5/2024 12:00 PM	55:00	6.45 pH	20.26 °C	569.41 µS/cm	6.51 mg/L	13.00 NTU	-24.9 mV	26.12 ft	200.00 ml/min
9/5/2024 12:05 PM	01:00:00	6.46 pH	20.14 °C	577.03 µS/cm	6.43 mg/L	14.00 NTU	-25.3 mV	26.12 ft	200.00 ml/min

9/5/2024 12:10 PM	01:05:00	6.48 pH	20.05 °C	580.26 µS/cm	6.60 mg/L	11.30 NTU	-30.2 mV	26.12 ft	200.00 ml/min
9/5/2024 12:15 PM	01:10:00	6.48 pH	20.29 °C	587.20 µS/cm	6.51 mg/L	10.10 NTU	-28.9 mV	26.12 ft	200.00 ml/min
9/5/2024 12:20 PM	01:15:00	6.47 pH	20.22 °C	591.38 µS/cm	6.33 mg/L	9.76 NTU	-27.7 mV	26.12 ft	200.00 ml/min
9/5/2024 12:25 PM	01:20:00	6.49 pH	19.96 °C	593.78 µS/cm	6.47 mg/L	7.15 NTU	-31.0 mV	26.12 ft	200.00 ml/min
9/5/2024 12:30 PM	01:25:00	6.48 pH	19.86 °C	597.49 µS/cm	6.25 mg/L	6.50 NTU	-31.7 mV	26.12 ft	200.00 ml/min
9/5/2024 12:35 PM	01:30:00	6.47 pH	19.79 °C	602.00 µS/cm	6.15 mg/L	4.79 NTU	-31.9 mV	26.12 ft	200.00 ml/min
9/5/2024 12:40 PM	01:35:00	6.48 pH	20.13 °C	605.65 µS/cm	6.22 mg/L	4.81 NTU	-32.9 mV	26.12 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.
HAM-AP1-FD-01	Grab.

Low-Flow Test Report:

Test Date / Time: 9/4/2024 12:36:07 PM
Project: GP Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 in Top of Screen: 20.47 ft Total Depth: 30.47 ft Initial Depth to Water: 16.77 ft	Pump Type: Peristaltic Tubing Type: Poly Pump Intake From TOC: 25.47 ft Estimated Total Volume Pumped: 10 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883553
---	---	--

Test Notes:
Full App. III and IV and Major Ions. Fe = 3.5 mg/L Fe2+= 3.0 mg/L.

Weather Conditions:
Cloudy, 80F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 1	+/- 5	
9/4/2024 12:36 PM	00:00	6.91 pH	23.05 °C	670.50 µS/cm	0.16 mg/L	21.60 NTU	56.3 mV	16.81 in	200.00 ml/min
9/4/2024 12:41 PM	05:00	6.90 pH	21.91 °C	670.56 µS/cm	0.09 mg/L	21.00 NTU	44.4 mV	16.80 in	200.00 ml/min
9/4/2024 12:46 PM	10:00	6.88 pH	21.93 °C	662.83 µS/cm	0.06 mg/L	19.20 NTU	47.2 mV	16.77 in	200.00 ml/min
9/4/2024 12:51 PM	15:00	6.87 pH	21.94 °C	660.53 µS/cm	0.05 mg/L	12.70 NTU	48.3 mV	16.77 in	200.00 ml/min
9/4/2024 12:56 PM	20:00	6.88 pH	21.78 °C	655.44 µS/cm	0.04 mg/L	8.30 NTU	44.4 mV	16.77 in	200.00 ml/min
9/4/2024 1:01 PM	25:00	6.86 pH	21.84 °C	652.65 µS/cm	0.03 mg/L	9.80 NTU	43.0 mV	16.77 in	200.00 ml/min
9/4/2024 1:06 PM	30:00	6.86 pH	21.68 °C	649.13 µS/cm	0.02 mg/L	7.90 NTU	41.5 mV	16.77 in	200.00 ml/min
9/4/2024 1:11 PM	35:00	6.86 pH	21.64 °C	645.67 µS/cm	0.01 mg/L	6.34 NTU	41.1 mV	16.77 in	200.00 ml/min
9/4/2024 1:16 PM	40:00	6.86 pH	21.69 °C	638.06 µS/cm	0.01 mg/L	5.47 NTU	39.7 mV	16.77 in	200.00 ml/min
9/4/2024 1:21 PM	45:00	6.86 pH	21.70 °C	634.71 µS/cm	0.01 mg/L	4.74 NTU	39.1 mV	16.77 in	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.

Low-Flow Test Report:

Test Date / Time: 9/4/2024 10:27:52 AM
Project: GP Plant Hammond
Operator Name: Jamie Newsome

Location Name: PT-10 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.47 ft Total Depth: 30.47 ft Initial Depth to Water: 16.9 ft	Pump Type: Peri Tubing Type: Poly Pump Intake From TOC: 25.47 ft Estimated Total Volume Pumped: 14 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 843593
--	--	--

Test Notes:
Full App. III and IV and Major ions. Fe = 0 mg/L, Fe2+ = 0 mg/L.

Weather Conditions:
Sunny, 75F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 10	+/- 5	
9/4/2024 10:27 AM	00:00	6.96 pH	20.46 °C	693.86 µS/cm	1.22 mg/L	10.50 NTU	99.5 mV	16.90 ft	200.00 ml/min
9/4/2024 10:32 AM	05:00	6.96 pH	20.70 °C	680.23 µS/cm	0.20 mg/L	10.07 NTU	109.2 mV	16.90 ft	200.00 ml/min
9/4/2024 10:37 AM	10:00	6.95 pH	20.84 °C	680.18 µS/cm	0.38 mg/L	5.23 NTU	120.4 mV	16.90 ft	200.00 ml/min
9/4/2024 10:42 AM	15:00	6.95 pH	20.81 °C	681.36 µS/cm	2.58 mg/L	4.67 NTU	136.8 mV	16.90 ft	200.00 ml/min
9/4/2024 10:47 AM	20:00	6.95 pH	20.91 °C	678.90 µS/cm	1.15 mg/L	4.32 NTU	157.3 mV	16.90 ft	200.00 ml/min
9/4/2024 10:52 AM	25:00	6.95 pH	21.41 °C	682.45 µS/cm	0.35 mg/L	3.03 NTU	188.3 mV	16.90 ft	200.00 ml/min
9/4/2024 10:57 AM	30:00	6.96 pH	21.48 °C	678.97 µS/cm	0.60 mg/L	2.74 NTU	286.0 mV	16.90 ft	200.00 ml/min
9/4/2024 11:02 AM	35:00	6.96 pH	21.65 °C	674.58 µS/cm	0.62 mg/L	2.42 NTU	319.5 mV	16.90 ft	200.00 ml/min
9/4/2024 11:07 AM	40:00	6.95 pH	21.69 °C	672.04 µS/cm	0.33 mg/L	2.16 NTU	357.7 mV	16.90 ft	200.00 ml/min
9/4/2024 11:12 AM	45:00	6.97 pH	21.41 °C	675.96 µS/cm	1.21 mg/L	2.19 NTU	371.1 mV	16.90 ft	200.00 ml/min
9/4/2024 11:17 AM	50:00	6.97 pH	21.95 °C	675.84 µS/cm	0.79 mg/L	2.07 NTU	288.3 mV	16.90 ft	200.00 ml/min
9/4/2024 11:22 AM	55:00	6.97 pH	21.95 °C	671.15 µS/cm	0.48 mg/L	1.83 NTU	319.5 mV	16.90 ft	200.00 ml/min
9/4/2024 11:27 AM	01:00:00	6.96 pH	22.00 °C	666.48 µS/cm	0.48 mg/L	1.45 NTU	424.3 mV	16.90 ft	200.00 ml/min

9/4/2024 11:32 AM	01:05:00	6.96 pH	22.00 °C	662.09 µS/cm	0.42 mg/L	1.36 NTU	410.2 mV	16.90 ft	200.00 ml/min
----------------------	----------	---------	----------	--------------	-----------	----------	----------	----------	---------------

Samples

Sample ID:	Description:
HAM-PT-10	Grab.

Low-Flow Test Report:

Test Date / Time: 9/4/2024 10:25:07 AM
Project: GP Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 16.9 ft Total Depth: 26.9 ft Initial Depth to Water: 13.34 ft	Pump Type: Peristaltic Tubing Type: Poly Pump Intake From TOC: 21.9 ft Estimated Total Volume Pumped: 13 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883553
---	---	--

Test Notes:
Full App. III and IV and Major Ions. Fe = 0.3 mg/L Fe2+ = 0 mg/L.

Weather Conditions:
Sunny, 75F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 1	+/- 5	
9/4/2024 10:25 AM	00:00	7.00 pH	21.55 °C	671.07 µS/cm	0.28 mg/L		99.9 mV	13.35 in	200.00 ml/min
9/4/2024 10:26 AM	01:44	6.99 pH	21.46 °C	670.96 µS/cm	0.23 mg/L		101.1 mV	13.35 in	200.00 ml/min
9/4/2024 10:27 AM	02:08	6.99 pH	21.51 °C	669.05 µS/cm	0.22 mg/L	31.30 NTU	100.0 mV	13.35 in	200.00 ml/min
9/4/2024 10:32 AM	07:08	6.97 pH	21.47 °C	665.26 µS/cm	0.14 mg/L	38.20 NTU	69.8 mV	13.39 in	200.00 ml/min
9/4/2024 10:37 AM	12:08	6.97 pH	21.42 °C	661.53 µS/cm	0.10 mg/L	32.70 NTU	78.1 mV	13.39 in	200.00 ml/min
9/4/2024 10:42 AM	17:08	6.96 pH	21.24 °C	660.19 µS/cm	0.06 mg/L	26.50 NTU	73.0 mV	13.39 in	200.00 ml/min
9/4/2024 10:47 AM	22:08	6.97 pH	21.37 °C	658.53 µS/cm	0.04 mg/L	23.40 NTU	68.3 mV	13.39 in	200.00 ml/min
9/4/2024 10:52 AM	27:08	6.96 pH	21.33 °C	655.73 µS/cm	0.03 mg/L	18.10 NTU	65.3 mV	13.39 in	200.00 ml/min
9/4/2024 10:57 AM	32:08	6.95 pH	21.42 °C	647.23 µS/cm	0.02 mg/L	16.90 NTU	63.4 mV	13.39 in	200.00 ml/min
9/4/2024 11:02 AM	37:08	6.96 pH	21.43 °C	643.57 µS/cm	0.01 mg/L	12.40 NTU	61.3 mV	13.39 in	200.00 ml/min
9/4/2024 11:07 AM	42:08	6.96 pH	21.47 °C	637.70 µS/cm	0.01 mg/L	9.80 NTU	59.4 mV	13.39 in	200.00 ml/min
9/4/2024 11:12 AM	47:08	6.95 pH	21.55 °C	636.79 µS/cm	0.01 mg/L	8.78 NTU	58.4 mV	13.39 in	200.00 ml/min
9/4/2024 11:17 AM	52:08	6.95 pH	21.64 °C	628.29 µS/cm	0.00 mg/L	8.02 NTU	57.1 mV	13.39 in	200.00 ml/min
9/4/2024 11:22 AM	57:08	6.94 pH	21.64 °C	625.87 µS/cm	0.00 mg/L	6.23 NTU	56.6 mV	13.39 in	200.00 ml/min
9/4/2024 11:27 AM	01:02:08	6.95 pH	21.51 °C	619.84 µS/cm	0.00 mg/L	4.82 NTU	55.4 mV	13.39 in	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-11	Grab.

Low-Flow Test Report:

Test Date / Time: 9/4/2024 2:56:13 PM
Project: GP Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-12 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.3 ft Total Depth: 27.3 ft Initial Depth to Water: 13.23 ft	Pump Type: Peristaltic Tubing Type: Poly Pump Intake From TOC: 22.3 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.04 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883553
---	--	--

Test Notes:
Full App. III and IV and Major Ions. Fe = 0 mg/L Fe2+ = 0 mg/L.

Weather Conditions:
Sunny, 75F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 1	+/- 0.3	
9/4/2024 2:56 PM	00:00	6.61 pH	23.08 °C	655.25 µS/cm	0.38 mg/L		81.3 mV	13.23 ft	200.00 ml/min
9/4/2024 2:57 PM	01:45	6.65 pH	22.35 °C	665.88 µS/cm	0.28 mg/L	11.10 NTU	70.6 mV	13.27 ft	200.00 ml/min
9/4/2024 3:02 PM	06:45	6.77 pH	22.31 °C	675.15 µS/cm	0.12 mg/L	7.89 NTU	46.8 mV	13.27 ft	200.00 ml/min
9/4/2024 3:07 PM	11:45	6.87 pH	22.13 °C	677.59 µS/cm	0.05 mg/L	6.25 NTU	45.2 mV	13.27 ft	200.00 ml/min
9/4/2024 3:12 PM	16:45	6.88 pH	22.32 °C	672.96 µS/cm	0.03 mg/L	7.07 NTU	42.5 mV	13.27 ft	200.00 ml/min
9/4/2024 3:17 PM	21:45	6.89 pH	22.11 °C	673.11 µS/cm	0.02 mg/L	6.30 NTU	40.1 mV	13.27 ft	200.00 ml/min
9/4/2024 3:22 PM	26:45	6.89 pH	21.69 °C	672.21 µS/cm	0.01 mg/L	5.34 NTU	37.8 mV	13.27 ft	200.00 ml/min
9/4/2024 3:27 PM	31:45	6.88 pH	21.94 °C	669.56 µS/cm	0.01 mg/L	4.42 NTU	37.1 mV	13.27 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-12	Grab.

Low-Flow Test Report:

Created using VuSitu from In-Situ, Inc.

Test Date / Time: 9/4/2024 3:28:31 PM
Project: GP Plant Hammond
Operator Name: Jamie Newsome

Location Name: PT-13 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.17 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40.30 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 843593
---	--	--

Test Notes:
Full App. III and IV and Major Ions. Fe = 6.0 mg/L, Fe2+ = 5.5 mg/L.

Weather Conditions:
Sunny, 95F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 10	+/- 5	
9/4/2024 3:28 PM	00:00	6.93 pH	21.85 °C	754.28 µS/cm	0.43 mg/L	27.10 NTU	-97.1 mV	26.17 ft	200.00 ml/min
9/4/2024 3:33 PM	05:00	6.88 pH	21.33 °C	766.33 µS/cm	0.22 mg/L	28.90 NTU	-93.2 mV	26.17 ft	200.00 ml/min
9/4/2024 3:38 PM	10:00	6.88 pH	20.66 °C	767.74 µS/cm	0.15 mg/L	16.00 NTU	-96.9 mV	26.17 ft	200.00 ml/min
9/4/2024 3:43 PM	15:00	6.87 pH	20.60 °C	771.05 µS/cm	0.12 mg/L	12.10 NTU	-97.5 mV	26.17 ft	200.00 ml/min
9/4/2024 3:48 PM	20:00	6.86 pH	20.75 °C	766.86 µS/cm	0.10 mg/L	11.70 NTU	-95.0 mV	26.17 ft	200.00 ml/min
9/4/2024 3:53 PM	25:00	6.85 pH	20.75 °C	769.54 µS/cm	0.08 mg/L	11.05 NTU	-97.3 mV	26.17 ft	200.00 ml/min
9/4/2024 3:58 PM	30:00	6.83 pH	20.80 °C	768.27 µS/cm	0.08 mg/L	7.51 NTU	-96.3 mV	26.17 ft	200.00 ml/min
9/4/2024 4:03 PM	35:00	6.82 pH	20.77 °C	765.04 µS/cm	0.06 mg/L	4.65 NTU	-95.5 mV	26.17 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-13	Grab.

Low-Flow Test Report:

Test Date / Time: 9/5/2024 11:05:17 AM
Project: GP Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-14 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.98 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883553
---	---	--

Test Notes:
Full App. III and IV and Major Ions. Fe = 6.0 mg/L Fe2+ = 6.4 mg/L.

Weather Conditions:
Sunny, 95F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 1	+/- 0.3	
9/5/2024 11:05 AM	00:00	7.01 pH	20.67 °C	824.57 µS/cm	0.16 mg/L	7.71 NTU	-67.8 mV	25.98 ft	200.00 ml/min
9/5/2024 11:10 AM	05:00	6.97 pH	20.56 °C	826.38 µS/cm	0.12 mg/L	7.32 NTU	-69.4 mV	25.98 ft	200.00 ml/min
9/5/2024 11:15 AM	10:00	6.99 pH	20.46 °C	826.22 µS/cm	0.09 mg/L	4.68 NTU	-66.8 mV	25.98 ft	200.00 ml/min
9/5/2024 11:20 AM	15:00	6.98 pH	20.53 °C	827.41 µS/cm	0.07 mg/L	2.23 NTU	-71.6 mV	25.98 ft	200.00 ml/min
9/5/2024 11:25 AM	20:00	6.99 pH	20.57 °C	826.11 µS/cm	0.07 mg/L	2.10 NTU	-72.3 mV	25.98 ft	200.00 ml/min
9/5/2024 11:30 AM	25:00	6.98 pH	20.59 °C	825.88 µS/cm	0.06 mg/L	1.76 NTU	-73.9 mV	25.98 ft	200.00 ml/min
9/5/2024 11:35 AM	30:00	6.99 pH	20.59 °C	826.47 µS/cm	0.05 mg/L	1.70 NTU	-73.9 mV	25.98 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-14	Grab.

Low-Flow Test Report:

Test Date / Time: 9/4/2024 3:28:31 PM
Project: GP Plant Hammond
Operator Name: Jamie Newsome

Location Name: PT-15 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.82 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40.30 ft Estimated Total Volume Pumped: 8 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 843593
---	--	--

Test Notes:
Full App. III and IV and Major Ions. Fe = 4.5 mg/L, Fe2+ = 2.0 mg/L.

Weather Conditions:
Sunny, 95F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 10	+/- 10	+/- 5	
9/4/2024 3:28 PM	00:00	6.93 pH	21.85 °C	754.28 µS/cm	0.43 mg/L	27.10 NTU	-97.1 mV	25.82 ft	200.00 ml/min
9/4/2024 3:33 PM	05:00	6.88 pH	21.33 °C	766.33 µS/cm	0.22 mg/L	28.90 NTU	-93.2 mV	25.82 ft	200.00 ml/min
9/4/2024 3:38 PM	10:00	6.88 pH	20.66 °C	767.74 µS/cm	0.15 mg/L	16.00 NTU	-96.9 mV	25.82 ft	200.00 ml/min
9/4/2024 3:43 PM	15:00	6.87 pH	20.60 °C	771.05 µS/cm	0.12 mg/L	12.10 NTU	-97.5 mV	25.82 ft	200.00 ml/min
9/4/2024 3:48 PM	20:00	6.86 pH	20.75 °C	766.86 µS/cm	0.10 mg/L	11.70 NTU	-95.0 mV	25.82 ft	200.00 ml/min
9/4/2024 3:53 PM	25:00	6.85 pH	20.75 °C	769.54 µS/cm	0.08 mg/L	11.05 NTU	-97.3 mV	25.82 ft	200.00 ml/min
9/4/2024 3:58 PM	30:00	6.83 pH	20.80 °C	768.27 µS/cm	0.08 mg/L	7.51 NTU	-96.3 mV	25.82 ft	200.00 ml/min
9/4/2024 4:03 PM	35:00	6.82 pH	20.77 °C	765.04 µS/cm	0.06 mg/L	4.65 NTU	-95.5 mV	25.82 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-15	Grab.

Low-Flow Test Report:

Test Date / Time: 9/24/2024 3:50:23 PM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 38 ft Total Depth: 48.0 ft Initial Depth to Water: 27.29 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 43.0 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.06 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1082822
---	--	---

Test Notes:
Appendix III & IV + Total Arsenic. Ferrous Iron: 0 mg/L, Total Iron: 1.0 mg/L.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 1	+/- 0.3	
9/24/2024 3:50 PM	00:00	6.63 pH	25.86 °C	746.48 µS/cm	0.55 mg/L	8.85 NTU	11.0 mV	27.32 ft	200.00 ml/min
9/24/2024 3:55 PM	05:00	6.61 pH	22.98 °C	740.14 µS/cm	0.54 mg/L	7.15 NTU	14.3 mV	27.35 ft	200.00 ml/min
9/24/2024 4:00 PM	10:00	6.61 pH	22.29 °C	738.24 µS/cm	0.39 mg/L	2.96 NTU	17.7 mV	27.35 ft	200.00 ml/min
9/24/2024 4:05 PM	15:00	6.61 pH	22.17 °C	731.94 µS/cm	0.33 mg/L	2.42 NTU	16.2 mV	27.35 ft	200.00 ml/min
9/24/2024 4:10 PM	20:00	6.61 pH	22.18 °C	724.28 µS/cm	0.31 mg/L	1.58 NTU	17.9 mV	27.35 ft	200.00 ml/min
9/24/2024 4:15 PM	25:00	6.61 pH	22.14 °C	719.88 µS/cm	0.29 mg/L	1.06 NTU	21.7 mV	27.35 ft	200.00 ml/min
9/24/2024 4:20 PM	30:00	6.61 pH	22.16 °C	716.65 µS/cm	0.28 mg/L	0.54 NTU	18.7 mV	27.35 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-07	Grab.

Low-Flow Test Report:

Test Date / Time: 9/24/2024 12:31:28 PM
Project: GP-Plant Hammond
Operator Name: Zain W.

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 32.2 ft Total Depth: 42.2 ft Initial Depth to Water: 26.39 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 37.2 ft Estimated Total Volume Pumped: 18 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1120055
---	--	---

Test Notes:
Appendix III & IV + Total Arsenic. Ferrous Iron: 2.5 mg/L, Total Iron: 5.0 mg/L.

Weather Conditions:
Sunny, 90 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
9/24/2024 12:31 PM	00:00	6.56 pH	22.52 °C	561.58 µS/cm	6.35 mg/L	103.00 NTU	134.0 mV	26.39 ft	150.00 ml/min
9/24/2024 12:36 PM	05:00	6.59 pH	21.91 °C	593.88 µS/cm	5.62 mg/L	106.00 NTU	54.5 mV	26.39 ft	150.00 ml/min
9/24/2024 12:41 PM	10:00	6.62 pH	21.73 °C	621.77 µS/cm	4.82 mg/L	98.90 NTU	59.9 mV	26.39 ft	150.00 ml/min
9/24/2024 12:46 PM	15:00	6.62 pH	21.73 °C	631.63 µS/cm	4.28 mg/L	97.40 NTU	41.5 mV	26.39 ft	150.00 ml/min
9/24/2024 12:51 PM	20:00	6.61 pH	21.76 °C	638.19 µS/cm	4.08 mg/L	96.00 NTU	36.5 mV	26.39 ft	150.00 ml/min
9/24/2024 12:56 PM	25:00	6.61 pH	21.73 °C	629.27 µS/cm	3.74 mg/L	79.40 NTU	34.9 mV	26.39 ft	150.00 ml/min
9/24/2024 1:01 PM	30:00	6.59 pH	21.73 °C	612.98 µS/cm	3.52 mg/L	47.60 NTU	37.1 mV	26.39 ft	150.00 ml/min
9/24/2024 1:06 PM	35:00	6.60 pH	21.65 °C	620.24 µS/cm	3.30 mg/L	41.60 NTU	30.5 mV	26.39 ft	150.00 ml/min
9/24/2024 1:11 PM	40:00	6.61 pH	21.78 °C	620.52 µS/cm	3.23 mg/L	30.90 NTU	30.3 mV	26.39 ft	150.00 ml/min
9/24/2024 1:16 PM	45:00	6.59 pH	21.70 °C	603.25 µS/cm	3.13 mg/L	28.10 NTU	34.6 mV	26.39 ft	150.00 ml/min
9/24/2024 1:21 PM	50:00	6.59 pH	21.74 °C	596.56 µS/cm	3.07 mg/L	22.30 NTU	36.4 mV	26.39 ft	150.00 ml/min
9/24/2024 1:26 PM	55:00	6.58 pH	21.87 °C	599.55 µS/cm	2.98 mg/L	19.70 NTU	38.2 mV	26.39 ft	150.00 ml/min
9/24/2024 1:31 PM	01:00:00	6.58 pH	21.91 °C	601.28 µS/cm	2.68 mg/L	16.60 NTU	37.2 mV	26.39 ft	150.00 ml/min

9/24/2024 1:36 PM	01:05:00	6.56 pH	21.87 °C	580.77 µS/cm	2.36 mg/L	14.80 NTU	37.5 mV	26.39 ft	150.00 ml/min
9/24/2024 1:41 PM	01:10:00	6.55 pH	21.85 °C	586.71 µS/cm	2.33 mg/L	11.50 NTU	39.1 mV	26.39 ft	150.00 ml/min
9/24/2024 1:46 PM	01:15:00	6.55 pH	21.93 °C	586.59 µS/cm	2.25 mg/L	9.64 NTU	37.1 mV	26.39 ft	150.00 ml/min
9/24/2024 1:51 PM	01:20:00	6.54 pH	22.07 °C	587.16 µS/cm	2.23 mg/L	8.52 NTU	37.8 mV	26.39 ft	150.00 ml/min
9/24/2024 1:56 PM	01:25:00	6.54 pH	22.09 °C	571.63 µS/cm	2.23 mg/L	8.00 NTU	37.0 mV	26.39 ft	150.00 ml/min
9/24/2024 2:01 PM	01:30:00	6.53 pH	22.09 °C	570.35 µS/cm	2.21 mg/L	7.38 NTU	40.7 mV	26.39 ft	150.00 ml/min
9/24/2024 2:06 PM	01:35:00	6.52 pH	22.13 °C	559.35 µS/cm	2.22 mg/L	6.26 NTU	37.5 mV	26.39 ft	150.00 ml/min
9/24/2024 2:11 PM	01:40:00	6.52 pH	22.21 °C	567.63 µS/cm	2.19 mg/L	6.31 NTU	41.8 mV	26.39 ft	150.00 ml/min
9/24/2024 2:16 PM	01:45:00	6.51 pH	22.10 °C	569.23 µS/cm	2.21 mg/L	5.51 NTU	37.9 mV	26.39 ft	150.00 ml/min
9/24/2024 2:21 PM	01:50:00	6.51 pH	22.14 °C	575.80 µS/cm	2.20 mg/L	5.33 NTU	37.7 mV	26.39 ft	150.00 ml/min
9/24/2024 2:26 PM	01:55:00	6.50 pH	22.19 °C	587.82 µS/cm	2.16 mg/L	4.25 NTU	37.1 mV	26.39 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.

Low-Flow Test Report:

Test Date / Time: 9/25/2024 9:10:58 AM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.45 ft Total Depth: 27.45 ft Initial Depth to Water: 16.89 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22.45 ft Estimated Total Volume Pumped: 40 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1082822
---	--	---

Test Notes:
Appendix III & IV + Total Arsenic. Ferrous Iron: 0 mg/L, Total Iron: 0.5 mg/L.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 1	+/- 0.3	
9/25/2024 9:10 AM	00:00	6.44 pH	21.01 °C	729.49 µS/cm	1.42 mg/L	++++	38.0 mV	16.91 ft	200.00 ml/min
9/25/2024 9:15 AM	05:00	6.53 pH	20.92 °C	726.11 µS/cm	1.03 mg/L	++++	29.0 mV	16.91 ft	200.00 ml/min
9/25/2024 9:20 AM	10:00	6.66 pH	20.83 °C	744.45 µS/cm	1.00 mg/L	++++	30.8 mV	16.91 ft	200.00 ml/min
9/25/2024 9:25 AM	15:00	6.68 pH	20.79 °C	744.74 µS/cm	0.99 mg/L	++++	40.6 mV	16.91 ft	200.00 ml/min
9/25/2024 9:30 AM	20:00	6.68 pH	20.83 °C	743.09 µS/cm	0.98 mg/L	++++	40.6 mV	16.91 ft	200.00 ml/min
9/25/2024 9:35 AM	25:00	6.67 pH	20.82 °C	742.14 µS/cm	0.91 mg/L	++++	40.7 mV	16.91 ft	200.00 ml/min
9/25/2024 9:40 AM	30:00	6.67 pH	20.83 °C	738.57 µS/cm	0.92 mg/L	++++	42.4 mV	16.91 ft	200.00 ml/min
9/25/2024 9:45 AM	35:00	6.67 pH	20.87 °C	738.04 µS/cm	0.92 mg/L	++++	42.2 mV	16.91 ft	200.00 ml/min
9/25/2024 9:50 AM	40:00	6.65 pH	20.83 °C	732.04 µS/cm	0.94 mg/L	++++	43.4 mV	16.91 ft	200.00 ml/min
9/25/2024 9:55 AM	45:00	6.66 pH	20.78 °C	736.60 µS/cm	0.93 mg/L	++++	43.2 mV	16.91 ft	200.00 ml/min
9/25/2024 10:00 AM	50:00	6.66 pH	20.70 °C	737.57 µS/cm	0.96 mg/L	++++	43.4 mV	16.91 ft	200.00 ml/min
9/25/2024 10:05 AM	55:00	6.67 pH	20.67 °C	745.78 µS/cm	0.90 mg/L	++++	42.9 mV	16.91 ft	200.00 ml/min
9/25/2024 10:10 AM	01:00:00	6.66 pH	20.65 °C	742.05 µS/cm	0.97 mg/L	++++	43.2 mV	16.91 ft	200.00 ml/min
9/25/2024 10:15 AM	01:05:00	6.65 pH	20.59 °C	737.57 µS/cm	0.98 mg/L	++++	42.7 mV	16.91 ft	200.00 ml/min
9/25/2024 10:20 AM	01:10:00	6.65 pH	20.51 °C	732.59 µS/cm	0.96 mg/L	++++	46.1 mV	16.91 ft	200.00 ml/min

9/25/2024 10:25 AM	01:15:00	6.65 pH	20.51 °C	733.25 µS/cm	1.03 mg/L	90.60 NTU	43.6 mV	16.91 ft	200.00 ml/min
9/25/2024 10:30 AM	01:20:00	6.65 pH	20.49 °C	733.97 µS/cm	1.09 mg/L	84.60 NTU	45.6 mV	16.91 ft	200.00 ml/min
9/25/2024 10:35 AM	01:25:00	6.65 pH	20.48 °C	736.69 µS/cm	0.95 mg/L	79.70 NTU	43.9 mV	16.91 ft	200.00 ml/min
9/25/2024 10:40 AM	01:30:00	6.63 pH	20.70 °C	733.57 µS/cm	0.32 mg/L	72.10 NTU	41.9 mV	16.91 ft	200.00 ml/min
9/25/2024 10:45 AM	01:35:00	6.63 pH	20.74 °C	731.03 µS/cm	0.32 mg/L	--	39.0 mV	16.91 ft	200.00 ml/min
9/25/2024 10:50 AM	01:40:00	6.65 pH	20.78 °C	731.78 µS/cm	0.31 mg/L	--	36.1 mV	16.91 ft	200.00 ml/min
9/25/2024 10:55 AM	01:45:00	6.64 pH	20.71 °C	731.12 µS/cm	0.29 mg/L	--	35.7 mV	16.91 ft	200.00 ml/min
9/25/2024 11:00 AM	01:50:00	6.65 pH	20.67 °C	736.52 µS/cm	0.79 mg/L	--	42.9 mV	16.91 ft	200.00 ml/min
9/25/2024 11:05 AM	01:55:00	6.65 pH	20.47 °C	735.22 µS/cm	0.92 mg/L	--	47.4 mV	16.91 ft	200.00 ml/min
9/25/2024 11:10 AM	02:00:00	6.65 pH	20.46 °C	731.89 µS/cm	0.95 mg/L	--	47.1 mV	16.91 ft	200.00 ml/min
9/25/2024 11:15 AM	02:05:00	6.65 pH	20.42 °C	729.54 µS/cm	0.98 mg/L	--	47.5 mV	16.91 ft	200.00 ml/min
9/25/2024 11:20 AM	02:10:00	6.66 pH	20.30 °C	727.55 µS/cm	1.00 mg/L	--	48.4 mV	16.91 ft	200.00 ml/min
9/25/2024 11:25 AM	02:15:00	6.66 pH	20.18 °C	728.21 µS/cm	1.00 mg/L	--	49.1 mV	16.91 ft	200.00 ml/min
9/25/2024 11:30 AM	02:20:00	6.66 pH	20.10 °C	736.01 µS/cm	0.99 mg/L	--	46.9 mV	16.91 ft	200.00 ml/min
9/25/2024 11:35 AM	02:25:00	6.66 pH	20.04 °C	735.66 µS/cm	1.01 mg/L	--	46.7 mV	16.91 ft	200.00 ml/min
9/25/2024 11:40 AM	02:30:00	6.67 pH	20.07 °C	734.50 µS/cm	1.01 mg/L	--	51.0 mV	16.91 ft	200.00 ml/min
9/25/2024 11:45 AM	02:35:00	6.66 pH	20.12 °C	733.96 µS/cm	0.98 mg/L	--	45.6 mV	16.91 ft	200.00 ml/min
9/25/2024 11:50 AM	02:40:00	6.66 pH	20.16 °C	732.14 µS/cm	1.00 mg/L	--	48.9 mV	16.91 ft	200.00 ml/min
9/25/2024 11:55 AM	02:45:00	6.69 pH	20.15 °C	734.20 µS/cm	1.03 mg/L	--	44.1 mV	16.91 ft	200.00 ml/min
9/25/2024 12:00 PM	02:50:00	6.67 pH	20.11 °C	731.54 µS/cm	1.05 mg/L	--	48.1 mV	16.91 ft	200.00 ml/min
9/25/2024 12:05 PM	02:55:00	6.67 pH	20.03 °C	732.48 µS/cm	1.06 mg/L	--	46.2 mV	16.91 ft	200.00 ml/min
9/25/2024 12:10 PM	03:00:00	6.66 pH	20.08 °C	731.53 µS/cm	0.95 mg/L	--	48.5 mV	16.91 ft	200.00 ml/min
9/25/2024 12:15 PM	03:05:00	6.66 pH	20.07 °C	731.94 µS/cm	0.93 mg/L	7.04 NTU	49.3 mV	16.91 ft	200.00 ml/min
9/25/2024 12:20 PM	03:10:00	6.66 pH	20.20 °C	735.33 µS/cm	0.96 mg/L	5.25 NTU	47.2 mV	16.91 ft	200.00 ml/min
9/25/2024 12:25 PM	03:15:00	6.67 pH	20.24 °C	737.13 µS/cm	0.83 mg/L	4.90 NTU	45.2 mV	16.91 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

HAM-PT-09	Grab.
-----------	-------

Low-Flow Test Report:

Test Date / Time: 9/25/2024 8:40:38 AM
Project: GP-Plant Hammond
Operator Name: Zain W.

Location Name: PT-10 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.45 ft Total Depth: 30.45 ft Initial Depth to Water: 16.97 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22.4 ft Estimated Total Volume Pumped: 16 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1120055
---	---	---

Test Notes:
Appendix III & IV + Total Arsenic. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Weather Conditions:
Cloudy, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
9/25/2024 8:40 AM	00:00	6.70 pH	19.64 °C	655.29 µS/cm	0.84 mg/L	58.40 NTU	120.6 mV	16.97 ft	200.00 ml/min
9/25/2024 8:45 AM	05:00	6.71 pH	19.56 °C	657.47 µS/cm	0.38 mg/L	45.40 NTU	80.4 mV	16.98 ft	200.00 ml/min
9/25/2024 8:50 AM	10:00	6.72 pH	19.56 °C	657.45 µS/cm	0.81 mg/L	32.30 NTU	84.9 mV	16.99 ft	200.00 ml/min
9/25/2024 8:55 AM	15:00	6.72 pH	19.59 °C	657.37 µS/cm	0.43 mg/L	21.50 NTU	76.7 mV	17.00 ft	200.00 ml/min
9/25/2024 9:00 AM	20:00	6.72 pH	19.51 °C	656.26 µS/cm	0.65 mg/L	20.90 NTU	72.9 mV	17.00 ft	200.00 ml/min
9/25/2024 9:05 AM	25:00	6.74 pH	19.50 °C	655.03 µS/cm	0.31 mg/L	16.40 NTU	70.4 mV	17.00 ft	200.00 ml/min
9/25/2024 9:10 AM	30:00	6.72 pH	19.59 °C	660.92 µS/cm	0.44 mg/L	12.50 NTU	68.8 mV	17.00 ft	200.00 ml/min
9/25/2024 9:15 AM	35:00	6.72 pH	19.64 °C	655.52 µS/cm	0.67 mg/L	11.30 NTU	57.7 mV	17.00 ft	200.00 ml/min
9/25/2024 9:20 AM	40:00	6.71 pH	19.63 °C	631.39 µS/cm	0.51 mg/L	8.76 NTU	68.7 mV	17.00 ft	200.00 ml/min
9/25/2024 9:25 AM	45:00	6.71 pH	19.64 °C	658.29 µS/cm	0.45 mg/L	7.69 NTU	67.8 mV	17.00 ft	200.00 ml/min
9/25/2024 9:30 AM	50:00	6.70 pH	19.65 °C	657.03 µS/cm	0.34 mg/L	5.84 NTU	64.3 mV	17.00 ft	200.00 ml/min
9/25/2024 9:35 AM	55:00	6.70 pH	19.64 °C	660.71 µS/cm	0.46 mg/L	6.15 NTU	61.6 mV	17.00 ft	200.00 ml/min
9/25/2024 9:40 AM	01:00:00	6.69 pH	19.69 °C	644.61 µS/cm	0.24 mg/L	5.63 NTU	60.8 mV	17.00 ft	200.00 ml/min

9/25/2024 9:45 AM	01:05:00	6.69 pH	19.71 °C	666.30 µS/cm	0.28 mg/L	5.29 NTU	59.0 mV	17.00 ft	200.00 ml/min
9/25/2024 9:50 AM	01:10:00	6.68 pH	19.72 °C	660.77 µS/cm	0.25 mg/L	4.43 NTU	58.8 mV	17.00 ft	200.00 ml/min
9/25/2024 9:55 AM	01:15:00	6.69 pH	19.71 °C	661.53 µS/cm	0.38 mg/L	3.46 NTU	51.4 mV	17.00 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.

Low-Flow Test Report:

Test Date / Time: 9/25/2024 10:44:42 AM
Project: GP-Plant Hammond
Operator Name: Zain W.

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 16.9 ft Total Depth: 26.9 ft Initial Depth to Water: 13.47 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 21.9 ft Estimated Total Volume Pumped: 50 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1120055
---	--	---

Test Notes:
Appendix III & IV + Total Arsenic. Ferrous Iron: 2.0 mg/L, Total Iron: 3.0 mg/L.

Weather Conditions:
Rain, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
9/25/2024 10:44 AM	00:00	6.28 pH	21.11 °C	650.44 µS/cm	1.00 mg/L	--	21.7 mV	13.47 ft	200.00 ml/min
9/25/2024 10:49 AM	05:00	6.22 pH	20.53 °C	646.49 µS/cm	1.23 mg/L	--	19.2 mV	13.47 ft	200.00 ml/min
9/25/2024 10:54 AM	10:00	6.24 pH	20.44 °C	651.08 µS/cm	0.60 mg/L	--	15.1 mV	13.47 ft	200.00 ml/min
9/25/2024 10:59 AM	15:00	6.27 pH	20.40 °C	661.44 µS/cm	0.22 mg/L	--	5.6 mV	13.47 ft	200.00 ml/min
9/25/2024 11:04 AM	20:00	6.30 pH	20.31 °C	664.60 µS/cm	0.24 mg/L	--	2.8 mV	13.47 ft	200.00 ml/min
9/25/2024 11:09 AM	25:00	6.31 pH	20.29 °C	668.72 µS/cm	0.33 mg/L	--	10.8 mV	13.47 ft	200.00 ml/min
9/25/2024 11:14 AM	30:00	6.32 pH	20.26 °C	667.70 µS/cm	0.13 mg/L	--	0.3 mV	13.47 ft	200.00 ml/min
9/25/2024 11:19 AM	35:00	6.33 pH	20.17 °C	665.09 µS/cm	0.11 mg/L	--	8.1 mV	13.47 ft	200.00 ml/min
9/25/2024 11:24 AM	40:00	6.35 pH	20.09 °C	662.85 µS/cm	0.10 mg/L	--	5.6 mV	13.47 ft	200.00 ml/min
9/25/2024 11:29 AM	45:00	6.35 pH	19.95 °C	667.55 µS/cm	0.10 mg/L	--	4.9 mV	13.47 ft	200.00 ml/min
9/25/2024 11:34 AM	50:00	6.37 pH	19.87 °C	670.50 µS/cm	0.20 mg/L	--	-2.0 mV	13.47 ft	200.00 ml/min
9/25/2024 11:39 AM	55:00	6.37 pH	19.94 °C	668.72 µS/cm	0.18 mg/L	--	9.2 mV	13.47 ft	200.00 ml/min
9/25/2024 11:44 AM	01:00:00	6.39 pH	19.91 °C	667.56 µS/cm	0.12 mg/L	--	11.4 mV	13.47 ft	200.00 ml/min

9/25/2024 11:49 AM	01:05:00	6.41 pH	19.93 °C	675.16 µS/cm	0.23 mg/L	--	-4.4 mV	13.47 ft	200.00 ml/min
9/25/2024 11:54 AM	01:10:00	6.42 pH	19.95 °C	673.78 µS/cm	0.13 mg/L	6.44 NTU	7.7 mV	13.47 ft	200.00 ml/min
9/25/2024 11:59 AM	01:15:00	6.42 pH	19.95 °C	674.53 µS/cm	1.10 mg/L	--	0.2 mV	13.47 ft	200.00 ml/min
9/25/2024 12:04 PM	01:20:00	6.43 pH	19.87 °C	681.85 µS/cm	0.23 mg/L	--	-4.4 mV	13.47 ft	200.00 ml/min
9/25/2024 12:09 PM	01:25:00	6.44 pH	19.86 °C	673.53 µS/cm	0.25 mg/L	8.65 NTU	-5.8 mV	13.47 ft	200.00 ml/min
9/25/2024 12:14 PM	01:30:00	6.45 pH	19.86 °C	676.31 µS/cm	0.34 mg/L	--	-9.8 mV	13.47 ft	200.00 ml/min
9/25/2024 12:19 PM	01:35:00	6.46 pH	19.95 °C	675.42 µS/cm	0.12 mg/L	--	1.9 mV	13.47 ft	200.00 ml/min
9/25/2024 12:24 PM	01:40:00	6.47 pH	19.98 °C	673.43 µS/cm	0.11 mg/L	--	-0.5 mV	13.47 ft	200.00 ml/min
9/25/2024 12:29 PM	01:45:00	6.49 pH	19.95 °C	676.43 µS/cm	0.32 mg/L	10.05 NTU	5.3 mV	13.47 ft	200.00 ml/min
9/25/2024 12:34 PM	01:50:00	6.48 pH	19.90 °C	674.84 µS/cm	0.18 mg/L	--	2.3 mV	13.47 ft	200.00 ml/min
9/25/2024 12:39 PM	01:55:00	6.50 pH	19.86 °C	675.11 µS/cm	0.19 mg/L	--	1.7 mV	13.47 ft	200.00 ml/min
9/25/2024 12:44 PM	02:00:00	6.50 pH	19.86 °C	674.70 µS/cm	0.19 mg/L	--	1.2 mV	13.47 ft	200.00 ml/min
9/25/2024 12:49 PM	02:05:00	6.51 pH	19.91 °C	673.97 µS/cm	0.20 mg/L	8.61 NTU	7.0 mV	13.47 ft	200.00 ml/min
9/25/2024 12:54 PM	02:10:00	6.51 pH	19.95 °C	671.88 µS/cm	0.12 mg/L	--	-1.5 mV	13.47 ft	200.00 ml/min
9/25/2024 12:59 PM	02:15:00	6.52 pH	19.95 °C	675.72 µS/cm	0.39 mg/L	--	-11.1 mV	13.47 ft	200.00 ml/min
9/25/2024 1:04 PM	02:20:00	6.53 pH	19.95 °C	672.15 µS/cm	0.13 mg/L	--	-0.3 mV	13.47 ft	200.00 ml/min
9/25/2024 1:09 PM	02:25:00	6.54 pH	20.05 °C	673.90 µS/cm	0.11 mg/L	7.25 NTU	-1.1 mV	13.47 ft	200.00 ml/min
9/25/2024 1:14 PM	02:30:00	6.54 pH	20.08 °C	673.61 µS/cm	0.09 mg/L	--	-4.0 mV	13.47 ft	200.00 ml/min
9/25/2024 1:19 PM	02:35:00	6.56 pH	20.13 °C	675.71 µS/cm	0.09 mg/L	--	-7.6 mV	13.47 ft	200.00 ml/min
9/25/2024 1:24 PM	02:40:00	6.58 pH	20.24 °C	675.52 µS/cm	0.09 mg/L	16.00 NTU	-7.2 mV	13.47 ft	200.00 ml/min
9/25/2024 1:29 PM	02:45:00	6.57 pH	20.40 °C	672.90 µS/cm	0.08 mg/L	14.70 NTU	-9.3 mV	13.47 ft	200.00 ml/min
9/25/2024 1:34 PM	02:50:00	6.58 pH	20.35 °C	675.11 µS/cm	0.09 mg/L	14.10 NTU	-8.5 mV	13.47 ft	200.00 ml/min
9/25/2024 1:39 PM	02:55:00	6.58 pH	20.40 °C	670.22 µS/cm	0.08 mg/L	14.80 NTU	-9.5 mV	13.47 ft	200.00 ml/min
9/25/2024 1:44 PM	03:00:00	6.59 pH	20.57 °C	670.85 µS/cm	0.08 mg/L	--	-11.0 mV	13.47 ft	200.00 ml/min
9/25/2024 1:49 PM	03:05:00	6.60 pH	20.61 °C	667.36 µS/cm	0.07 mg/L	--	-12.0 mV	13.47 ft	200.00 ml/min
9/25/2024 1:54 PM	03:10:00	6.60 pH	20.55 °C	666.06 µS/cm	0.07 mg/L	21.20 NTU	-12.7 mV	13.47 ft	200.00 ml/min
9/25/2024 1:59 PM	03:15:00	6.60 pH	20.42 °C	671.08 µS/cm	0.08 mg/L	--	-12.3 mV	13.47 ft	200.00 ml/min
9/25/2024 2:04 PM	03:20:00	6.63 pH	20.30 °C	674.16 µS/cm	0.08 mg/L	19.70 NTU	-12.6 mV	13.47 ft	200.00 ml/min
9/25/2024 2:09 PM	03:25:00	6.63 pH	20.22 °C	671.84 µS/cm	0.08 mg/L	--	-12.7 mV	13.47 ft	200.00 ml/min

9/25/2024 2:14 PM	03:30:00	6.63 pH	20.24 °C	670.00 µS/cm	0.08 mg/L	--	-13.4 mV	13.47 ft	200.00 ml/min
9/25/2024 2:19 PM	03:35:00	6.63 pH	20.29 °C	676.26 µS/cm	0.08 mg/L	12.40 NTU	-13.7 mV	13.47 ft	200.00 ml/min
9/25/2024 2:24 PM	03:40:00	6.63 pH	20.26 °C	675.48 µS/cm	0.07 mg/L	--	-13.7 mV	13.47 ft	200.00 ml/min
9/25/2024 2:29 PM	03:45:00	6.63 pH	20.30 °C	672.34 µS/cm	0.08 mg/L	9.44 NTU	-13.6 mV	13.47 ft	200.00 ml/min
9/25/2024 2:34 PM	03:50:00	6.62 pH	20.21 °C	669.17 µS/cm	0.08 mg/L	--	-14.0 mV	13.47 ft	200.00 ml/min
9/25/2024 2:39 PM	03:55:00	6.63 pH	20.08 °C	670.83 µS/cm	0.08 mg/L	5.87 NTU	-14.4 mV	13.47 ft	200.00 ml/min
9/25/2024 2:44 PM	04:00:00	6.63 pH	20.08 °C	673.42 µS/cm	0.08 mg/L	5.13 NTU	-14.3 mV	13.47 ft	200.00 ml/min
9/25/2024 2:49 PM	04:05:00	6.63 pH	20.04 °C	676.04 µS/cm	0.07 mg/L	4.97 NTU	-13.5 mV	13.47 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-11	Grab.

Low-Flow Test Report:

Test Date / Time: 9/25/2024 2:10:11 PM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-12 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.3 ft Total Depth: 27.3 ft Initial Depth to Water: 13.33 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22.3 ft Estimated Total Volume Pumped: 33 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.01 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1082822
---	---	---

Test Notes:
Appendix III & IV + Total Arsenic. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Weather Conditions:
Cloudy, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 1	+/- 0.3	
9/25/2024 2:10 PM	00:00	6.53 pH	20.36 °C	703.51 µS/cm	0.95 mg/L	++++	92.6 mV	13.36 ft	200.00 ml/min
9/25/2024 2:15 PM	05:00	6.55 pH	20.50 °C	709.20 µS/cm	0.97 mg/L	++++	100.0 mV	13.34 ft	200.00 ml/min
9/25/2024 2:20 PM	10:00	6.57 pH	20.53 °C	708.32 µS/cm	0.95 mg/L	++++	83.2 mV	13.34 ft	200.00 ml/min
9/25/2024 2:25 PM	15:00	6.56 pH	20.44 °C	704.57 µS/cm	0.98 mg/L	++++	82.9 mV	13.34 ft	200.00 ml/min
9/25/2024 2:30 PM	20:00	6.57 pH	20.47 °C	703.04 µS/cm	0.97 mg/L	++++	81.9 mV	13.34 ft	200.00 ml/min
9/25/2024 2:35 PM	25:00	6.57 pH	20.36 °C	705.01 µS/cm	0.95 mg/L	++++	81.3 mV	13.34 ft	200.00 ml/min
9/25/2024 2:40 PM	30:00	6.57 pH	20.31 °C	706.76 µS/cm	0.86 mg/L	++++	81.3 mV	13.34 ft	200.00 ml/min
9/25/2024 2:45 PM	35:00	6.55 pH	20.29 °C	706.85 µS/cm	0.89 mg/L	++++	81.8 mV	13.34 ft	200.00 ml/min
9/25/2024 2:50 PM	40:00	6.56 pH	20.22 °C	707.53 µS/cm	0.87 mg/L	108.00 NTU	80.7 mV	13.34 ft	200.00 ml/min
9/25/2024 2:55 PM	45:00	6.56 pH	20.20 °C	705.69 µS/cm	0.87 mg/L	102.00 NTU	80.6 mV	13.34 ft	200.00 ml/min
9/25/2024 3:00 PM	50:00	6.56 pH	20.23 °C	706.99 µS/cm	0.88 mg/L	96.00 NTU	79.5 mV	13.34 ft	200.00 ml/min
9/25/2024 3:05 PM	55:00	6.57 pH	20.31 °C	707.51 µS/cm	0.85 mg/L	88.00 NTU	79.7 mV	13.34 ft	200.00 ml/min
9/25/2024 3:10 PM	01:00:00	6.56 pH	20.42 °C	717.94 µS/cm	0.88 mg/L	82.50 NTU	92.6 mV	13.34 ft	200.00 ml/min

9/25/2024 3:15 PM	01:05:00	6.54 pH	20.20 °C	716.26 µS/cm	0.87 mg/L	64.30 NTU	79.5 mV	13.34 ft	200.00 ml/min
9/25/2024 3:20 PM	01:10:00	6.53 pH	20.15 °C	715.21 µS/cm	0.85 mg/L	59.60 NTU	80.0 mV	13.34 ft	200.00 ml/min
9/25/2024 3:25 PM	01:15:00	6.52 pH	20.11 °C	715.14 µS/cm	0.85 mg/L	58.20 NTU	80.2 mV	13.34 ft	200.00 ml/min
9/25/2024 3:30 PM	01:20:00	6.54 pH	20.20 °C	715.34 µS/cm	0.86 mg/L	48.30 NTU	78.8 mV	13.34 ft	200.00 ml/min
9/25/2024 3:35 PM	01:25:00	6.56 pH	20.24 °C	713.10 µS/cm	0.87 mg/L	42.40 NTU	78.2 mV	13.34 ft	200.00 ml/min
9/25/2024 3:40 PM	01:30:00	6.54 pH	20.31 °C	712.09 µS/cm	0.86 mg/L	38.40 NTU	77.9 mV	13.34 ft	200.00 ml/min
9/25/2024 3:45 PM	01:35:00	6.50 pH	20.21 °C	712.07 µS/cm	0.85 mg/L	36.60 NTU	78.2 mV	13.34 ft	200.00 ml/min
9/25/2024 3:50 PM	01:40:00	6.50 pH	20.09 °C	711.55 µS/cm	0.85 mg/L	34.40 NTU	79.2 mV	13.34 ft	200.00 ml/min
9/25/2024 3:55 PM	01:45:00	6.50 pH	20.01 °C	711.47 µS/cm	0.83 mg/L	29.50 NTU	79.3 mV	13.34 ft	200.00 ml/min
9/25/2024 4:00 PM	01:50:00	6.50 pH	19.96 °C	708.67 µS/cm	0.83 mg/L	24.30 NTU	91.1 mV	13.34 ft	200.00 ml/min
9/25/2024 4:05 PM	01:55:00	6.50 pH	19.95 °C	708.62 µS/cm	0.85 mg/L	22.00 NTU	79.1 mV	13.34 ft	200.00 ml/min
9/25/2024 4:10 PM	02:00:00	6.48 pH	19.88 °C	710.06 µS/cm	0.78 mg/L	21.90 NTU	79.5 mV	13.34 ft	200.00 ml/min
9/25/2024 4:15 PM	02:05:00	6.51 pH	19.92 °C	711.27 µS/cm	0.88 mg/L	16.50 NTU	77.6 mV	13.34 ft	200.00 ml/min
9/25/2024 4:20 PM	02:10:00	6.50 pH	19.90 °C	705.19 µS/cm	0.90 mg/L	14.70 NTU	78.0 mV	13.34 ft	200.00 ml/min
9/25/2024 4:25 PM	02:15:00	6.50 pH	19.89 °C	703.85 µS/cm	0.90 mg/L	12.00 NTU	77.8 mV	13.34 ft	200.00 ml/min
9/25/2024 4:30 PM	02:20:00	6.49 pH	19.94 °C	705.11 µS/cm	0.91 mg/L	9.90 NTU	78.0 mV	13.34 ft	200.00 ml/min
9/25/2024 4:35 PM	02:25:00	6.52 pH	19.94 °C	707.28 µS/cm	0.90 mg/L	7.47 NTU	77.4 mV	13.34 ft	200.00 ml/min
9/25/2024 4:40 PM	02:30:00	6.50 pH	19.93 °C	702.63 µS/cm	0.90 mg/L	6.98 NTU	78.0 mV	13.34 ft	200.00 ml/min
9/25/2024 4:45 PM	02:35:00	6.47 pH	19.97 °C	702.94 µS/cm	0.88 mg/L	5.88 NTU	79.5 mV	13.34 ft	200.00 ml/min
9/25/2024 4:50 PM	02:40:00	6.51 pH	19.99 °C	709.24 µS/cm	0.86 mg/L	4.72 NTU	76.6 mV	13.34 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-12	Grab.

Low-Flow Test Report:

Test Date / Time: 9/24/2024 9:25:04 AM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-13 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.14 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 37 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.08 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1082822
---	---	---

Test Notes:
Appendix III & IV + Total Arsenic. Ferrous Iron: 5.6 mg/L, Total Iron: 5.7 mg/L.

Weather Conditions:
Cloudy, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 1	+/- 0.3	
9/24/2024 9:25 AM	00:00	6.56 pH	20.78 °C	675.79 µS/cm	1.23 mg/L	++++	26.9 mV	26.19 ft	200.00 ml/min
9/24/2024 9:30 AM	05:00	6.57 pH	20.83 °C	677.43 µS/cm	1.29 mg/L	++++	21.8 mV	26.22 ft	200.00 ml/min
9/24/2024 9:35 AM	10:00	6.57 pH	20.96 °C	667.85 µS/cm	1.27 mg/L	++++	20.9 mV	26.22 ft	200.00 ml/min
9/24/2024 9:40 AM	15:00	6.57 pH	20.96 °C	659.15 µS/cm	1.18 mg/L	++++	14.2 mV	26.22 ft	200.00 ml/min
9/24/2024 9:45 AM	20:00	6.56 pH	21.12 °C	667.82 µS/cm	1.14 mg/L	90.80 NTU	15.1 mV	26.22 ft	200.00 ml/min
9/24/2024 9:50 AM	25:00	6.56 pH	21.63 °C	654.47 µS/cm	1.09 mg/L	72.10 NTU	8.5 mV	26.22 ft	200.00 ml/min
9/24/2024 9:55 AM	30:00	6.55 pH	21.18 °C	652.67 µS/cm	1.06 mg/L	49.60 NTU	12.0 mV	26.22 ft	200.00 ml/min
9/24/2024 10:00 AM	35:00	6.55 pH	21.22 °C	650.18 µS/cm	1.04 mg/L	40.10 NTU	5.6 mV	26.22 ft	200.00 ml/min
9/24/2024 10:05 AM	40:00	6.55 pH	21.56 °C	655.22 µS/cm	0.96 mg/L	36.20 NTU	2.9 mV	26.22 ft	200.00 ml/min
9/24/2024 10:10 AM	45:00	6.55 pH	21.45 °C	652.56 µS/cm	0.97 mg/L	35.90 NTU	1.5 mV	26.22 ft	200.00 ml/min
9/24/2024 10:15 AM	50:00	6.54 pH	21.43 °C	639.36 µS/cm	0.92 mg/L	27.40 NTU	6.5 mV	26.22 ft	200.00 ml/min
9/24/2024 10:20 AM	55:00	6.54 pH	21.68 °C	664.86 µS/cm	0.87 mg/L	20.80 NTU	-0.1 mV	26.22 ft	200.00 ml/min
9/24/2024 10:25 AM	01:00:00	6.54 pH	21.65 °C	663.16 µS/cm	0.83 mg/L	19.50 NTU	-2.1 mV	26.22 ft	200.00 ml/min

9/24/2024 10:30 AM	01:05:00	6.53 pH	21.52 °C	661.72 µS/cm	0.79 mg/L	18.70 NTU	-3.2 mV	26.22 ft	200.00 ml/min
9/24/2024 10:35 AM	01:10:00	6.54 pH	21.88 °C	648.41 µS/cm	0.72 mg/L	18.80 NTU	-0.4 mV	26.22 ft	200.00 ml/min
9/24/2024 10:40 AM	01:15:00	6.53 pH	22.03 °C	651.71 µS/cm	0.69 mg/L	18.20 NTU	-1.0 mV	26.22 ft	200.00 ml/min
9/24/2024 10:45 AM	01:20:00	6.53 pH	22.12 °C	646.25 µS/cm	0.61 mg/L	14.60 NTU	-5.6 mV	26.22 ft	200.00 ml/min
9/24/2024 10:50 AM	01:25:00	6.54 pH	22.20 °C	654.86 µS/cm	0.51 mg/L	11.10 NTU	-16.3 mV	26.22 ft	200.00 ml/min
9/24/2024 10:55 AM	01:30:00	6.53 pH	22.16 °C	647.68 µS/cm	0.45 mg/L	11.30 NTU	-8.7 mV	26.22 ft	200.00 ml/min
9/24/2024 11:00 AM	01:35:00	6.52 pH	22.18 °C	648.57 µS/cm	0.45 mg/L	11.00 NTU	-8.1 mV	26.22 ft	200.00 ml/min
9/24/2024 11:05 AM	01:40:00	6.53 pH	22.28 °C	660.12 µS/cm	0.44 mg/L	10.80 NTU	-14.6 mV	26.22 ft	200.00 ml/min
9/24/2024 11:10 AM	01:45:00	6.53 pH	22.34 °C	653.16 µS/cm	0.42 mg/L	10.40 NTU	-9.0 mV	26.22 ft	200.00 ml/min
9/24/2024 11:15 AM	01:50:00	6.53 pH	22.34 °C	656.38 µS/cm	0.41 mg/L	9.90 NTU	-15.8 mV	26.22 ft	200.00 ml/min
9/24/2024 11:20 AM	01:55:00	6.51 pH	22.39 °C	660.89 µS/cm	0.38 mg/L	9.60 NTU	-10.0 mV	26.22 ft	200.00 ml/min
9/24/2024 11:25 AM	02:00:00	6.52 pH	22.56 °C	662.89 µS/cm	0.37 mg/L	7.84 NTU	-10.6 mV	26.22 ft	200.00 ml/min
9/24/2024 11:30 AM	02:05:00	6.52 pH	22.48 °C	652.05 µS/cm	0.36 mg/L	7.52 NTU	-10.4 mV	26.22 ft	200.00 ml/min
9/24/2024 11:35 AM	02:10:00	6.52 pH	22.52 °C	663.89 µS/cm	0.37 mg/L	7.34 NTU	-10.7 mV	26.22 ft	200.00 ml/min
9/24/2024 11:40 AM	02:15:00	6.52 pH	22.61 °C	665.86 µS/cm	0.38 mg/L	7.18 NTU	-11.2 mV	26.22 ft	200.00 ml/min
9/24/2024 11:45 AM	02:20:00	6.53 pH	22.70 °C	675.26 µS/cm	0.37 mg/L	6.97 NTU	-11.9 mV	26.22 ft	200.00 ml/min
9/24/2024 11:50 AM	02:25:00	6.52 pH	22.67 °C	671.85 µS/cm	0.35 mg/L	6.38 NTU	-11.9 mV	26.22 ft	200.00 ml/min
9/24/2024 11:55 AM	02:30:00	6.52 pH	22.64 °C	670.79 µS/cm	0.34 mg/L	5.71 NTU	-12.9 mV	26.22 ft	200.00 ml/min
9/24/2024 12:00 PM	02:35:00	6.53 pH	22.87 °C	666.81 µS/cm	0.35 mg/L	5.21 NTU	-18.7 mV	26.22 ft	200.00 ml/min
9/24/2024 12:05 PM	02:40:00	6.51 pH	22.81 °C	673.67 µS/cm	0.35 mg/L	5.25 NTU	-11.6 mV	26.22 ft	200.00 ml/min
9/24/2024 12:10 PM	02:45:00	6.53 pH	22.89 °C	670.20 µS/cm	0.36 mg/L	5.34 NTU	-12.8 mV	26.22 ft	200.00 ml/min
9/24/2024 12:15 PM	02:50:00	6.52 pH	23.05 °C	677.61 µS/cm	0.33 mg/L	5.27 NTU	-13.9 mV	26.22 ft	200.00 ml/min
9/24/2024 12:20 PM	02:55:00	6.52 pH	22.90 °C	676.20 µS/cm	0.35 mg/L	5.45 NTU	-12.7 mV	26.22 ft	200.00 ml/min
9/24/2024 12:25 PM	03:00:00	6.52 pH	23.01 °C	682.25 µS/cm	0.37 mg/L	4.97 NTU	-13.8 mV	26.22 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-13	Grab.

Low-Flow Test Report:

Test Date / Time: 9/24/2024 1:45:09 PM
Project: GP-Plant Hammond
Operator Name: Jacob Tracy

Location Name: PT-14 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.05 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 12 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1082822
---	--	---

Test Notes:
Appendix III & IV + Total Arsenic. Ferrous Iron: 5.8 mg/L, Total Iron: 6.2 mg/L.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 1	+/- 0.3	
9/24/2024 1:45 PM	00:00	6.69 pH	22.86 °C	789.63 µS/cm	0.48 mg/L	87.80 NTU	-63.7 mV	26.05 ft	200.00 ml/min
9/24/2024 1:50 PM	05:00	6.69 pH	22.51 °C	791.91 µS/cm	0.37 mg/L	75.40 NTU	-63.6 mV	26.05 ft	200.00 ml/min
9/24/2024 1:55 PM	10:00	6.69 pH	22.34 °C	787.07 µS/cm	0.34 mg/L	53.60 NTU	-64.1 mV	26.05 ft	200.00 ml/min
9/24/2024 2:00 PM	15:00	6.69 pH	22.28 °C	785.24 µS/cm	0.31 mg/L	31.50 NTU	-65.9 mV	26.05 ft	200.00 ml/min
9/24/2024 2:05 PM	20:00	6.71 pH	22.20 °C	777.25 µS/cm	0.29 mg/L	20.70 NTU	-67.5 mV	26.05 ft	200.00 ml/min
9/24/2024 2:10 PM	25:00	6.70 pH	22.07 °C	775.33 µS/cm	0.27 mg/L	17.50 NTU	-66.4 mV	26.05 ft	200.00 ml/min
9/24/2024 2:15 PM	30:00	6.71 pH	22.01 °C	772.16 µS/cm	0.26 mg/L	12.90 NTU	-67.5 mV	26.05 ft	200.00 ml/min
9/24/2024 2:20 PM	35:00	6.70 pH	22.06 °C	772.74 µS/cm	0.25 mg/L	10.60 NTU	-68.6 mV	26.05 ft	200.00 ml/min
9/24/2024 2:25 PM	40:00	6.71 pH	21.98 °C	772.36 µS/cm	0.25 mg/L	9.21 NTU	-77.3 mV	26.05 ft	200.00 ml/min
9/24/2024 2:30 PM	45:00	6.70 pH	21.90 °C	768.99 µS/cm	0.25 mg/L	5.83 NTU	-69.3 mV	26.05 ft	200.00 ml/min
9/24/2024 2:35 PM	50:00	6.69 pH	21.80 °C	768.59 µS/cm	0.24 mg/L	5.64 NTU	-69.4 mV	26.05 ft	200.00 ml/min
9/24/2024 2:40 PM	55:00	6.69 pH	21.91 °C	783.86 µS/cm	0.24 mg/L	4.97 NTU	-69.9 mV	26.05 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-14	Grab.

Low-Flow Test Report:

Test Date / Time: 9/24/2024 10:08:44 AM
Project: GP-Plant Hammond
Operator Name: Zain W.

Location Name: PT-15 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35 ft Total Depth: 45 ft Initial Depth to Water: 26.13 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 8.25 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1120055
---	--	---

Test Notes:
Appendix III & IV + Total Arsenic. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Weather Conditions:
Cloudy, 75 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
9/24/2024 10:08 AM	00:00	6.73 pH	21.04 °C	645.47 µS/cm	1.77 mg/L	10.21 NTU	44.8 mV	26.13 ft	150.00 ml/min
9/24/2024 10:13 AM	05:00	6.73 pH	20.97 °C	630.77 µS/cm	1.46 mg/L	8.49 NTU	42.0 mV	26.13 ft	150.00 ml/min
9/24/2024 10:18 AM	10:00	6.73 pH	20.92 °C	627.07 µS/cm	1.19 mg/L	3.88 NTU	48.8 mV	26.13 ft	150.00 ml/min
9/24/2024 10:23 AM	15:00	6.73 pH	20.93 °C	618.11 µS/cm	0.97 mg/L	2.26 NTU	41.6 mV	26.13 ft	150.00 ml/min
9/24/2024 10:28 AM	20:00	6.72 pH	20.88 °C	614.36 µS/cm	0.85 mg/L	1.99 NTU	47.4 mV	26.13 ft	150.00 ml/min
9/24/2024 10:33 AM	25:00	6.73 pH	20.93 °C	607.24 µS/cm	0.81 mg/L	1.11 NTU	40.9 mV	26.13 ft	150.00 ml/min
9/24/2024 10:38 AM	30:00	6.73 pH	20.93 °C	607.19 µS/cm	0.64 mg/L	1.00 NTU	41.7 mV	26.13 ft	150.00 ml/min
9/24/2024 10:43 AM	35:00	6.73 pH	20.93 °C	600.98 µS/cm	0.56 mg/L	0.93 NTU	50.3 mV	26.13 ft	150.00 ml/min
9/24/2024 10:48 AM	40:00	6.73 pH	20.86 °C	598.09 µS/cm	0.53 mg/L	0.75 NTU	42.3 mV	26.13 ft	150.00 ml/min
9/24/2024 10:53 AM	45:00	6.73 pH	20.88 °C	587.09 µS/cm	0.46 mg/L	0.58 NTU	42.3 mV	26.13 ft	150.00 ml/min
9/24/2024 10:58 AM	50:00	6.73 pH	20.93 °C	582.11 µS/cm	0.43 mg/L	0.55 NTU	41.7 mV	26.13 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-15	Grab.

Low-Flow Test Report:

Test Date / Time: 10/2/2024 4:29:21 PM
Project: GP-Plant Hammond
Operator Name: Elisabeth R.

Location Name: INW-03 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.4 ft Total Depth: 27.4 ft Initial Depth to Water: 12.45 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22 ft Estimated Total Volume Pumped: 5 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883561
--	---	--

Test Notes:
Parameters; No Sample.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/2/2024 4:29 PM	00:00	6.69 pH	22.88 °C	863.53 µS/cm	1.61 mg/L	40.50 NTU	-73.6 mV	12.45 ft	200.00 ml/min
10/2/2024 4:34 PM	05:00	5.92 pH	22.28 °C	728.61 µS/cm	0.71 mg/L	31.30 NTU	-17.6 mV	12.45 ft	200.00 ml/min
10/2/2024 4:35 PM	06:27	6.05 pH	22.17 °C	756.08 µS/cm	0.60 mg/L	28.20 NTU	-32.5 mV	12.45 ft	200.00 ml/min
10/2/2024 4:40 PM	11:27	6.30 pH	22.00 °C	796.46 µS/cm	0.58 mg/L	27.20 NTU	-62.7 mV	12.45 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 10/1/2024 1:40:58 PM
Project: GP-Plant Hammond
Operator Name: Zain W.

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 37.75 ft Total Depth: 47.75 ft Initial Depth to Water: 25.09 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 42.75 ft Estimated Total Volume Pumped: 7.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.04 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883530
---	---	--

Test Notes:
Metals. Ferrous Iron: 0 mg/L. Total Iron: 0 mg/L.

Weather Conditions:
Clear, 90 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/1/2024 1:40 PM	00:00	6.73 pH	22.11 °C	772.84 µS/cm	0.85 mg/L	16.60 NTU	413.2 mV	25.09 ft	150.00 ml/min
10/1/2024 1:45 PM	05:00	6.91 pH	21.70 °C	772.84 µS/cm	0.64 mg/L	15.20 NTU	711.6 mV	25.13 ft	150.00 ml/min
10/1/2024 1:50 PM	10:00	6.91 pH	21.65 °C	764.40 µS/cm	0.52 mg/L	13.40 NTU	818.8 mV	25.13 ft	150.00 ml/min
10/1/2024 1:55 PM	15:00	6.92 pH	21.47 °C	769.95 µS/cm	0.48 mg/L	11.80 NTU	819.5 mV	25.13 ft	150.00 ml/min
10/1/2024 2:00 PM	20:00	6.93 pH	21.27 °C	767.64 µS/cm	0.40 mg/L	10.21 NTU	725.4 mV	25.13 ft	150.00 ml/min
10/1/2024 2:05 PM	25:00	6.93 pH	21.33 °C	765.65 µS/cm	0.37 mg/L	9.48 NTU	752.4 mV	25.13 ft	150.00 ml/min
10/1/2024 2:10 PM	30:00	6.94 pH	21.16 °C	759.75 µS/cm	0.34 mg/L	8.25 NTU	680.7 mV	25.13 ft	150.00 ml/min
10/1/2024 2:15 PM	35:00	6.93 pH	21.04 °C	763.45 µS/cm	0.28 mg/L	6.33 NTU	685.1 mV	25.13 ft	150.00 ml/min
10/1/2024 2:20 PM	40:00	6.93 pH	20.92 °C	761.07 µS/cm	0.22 mg/L	5.18 NTU	646.6 mV	25.13 ft	150.00 ml/min
10/1/2024 2:25 PM	45:00	6.94 pH	21.10 °C	754.99 µS/cm	0.19 mg/L	4.92 NTU	591.7 mV	25.13 ft	150.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

HAM-PT-07	Grab.
-----------	-------

Low-Flow Test Report:

Test Date / Time: 10/1/2024 12:55:40 PM
Project: GP-Plant Hammond
Operator Name: Elisabeth R.

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 31.93 ft Total Depth: 41.93 ft Initial Depth to Water: 25.3 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 37 ft Estimated Total Volume Pumped: 21 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883561
---	--	--

Test Notes:
Metals. Ferrous Iron: 2.0 mg/L, Total Iron: 5.0 mg/L.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/1/2024 12:55 PM	00:00	6.66 pH	21.56 °C	763.85 µS/cm	5.98 mg/L	55.40 NTU	-26.6 mV	25.30 ft	200.00 ml/min
10/1/2024 1:00 PM	05:00	6.65 pH	21.41 °C	770.67 µS/cm	5.48 mg/L	40.10 NTU	-25.6 mV	25.30 ft	200.00 ml/min
10/1/2024 1:05 PM	10:00	6.65 pH	21.42 °C	758.41 µS/cm	5.06 mg/L	34.50 NTU	-21.4 mV	25.31 ft	200.00 ml/min
10/1/2024 1:10 PM	15:00	6.66 pH	21.48 °C	769.08 µS/cm	4.60 mg/L	31.60 NTU	-29.3 mV	25.32 ft	200.00 ml/min
10/1/2024 1:15 PM	20:00	6.66 pH	20.97 °C	765.71 µS/cm	4.22 mg/L	28.10 NTU	-43.8 mV	25.32 ft	200.00 ml/min
10/1/2024 1:20 PM	25:00	6.66 pH	21.38 °C	755.58 µS/cm	3.73 mg/L	28.40 NTU	-45.3 mV	25.32 ft	200.00 ml/min
10/1/2024 1:25 PM	30:00	6.65 pH	21.07 °C	751.02 µS/cm	3.42 mg/L	29.40 NTU	-43.6 mV	25.32 ft	200.00 ml/min
10/1/2024 1:30 PM	35:00	6.65 pH	20.80 °C	776.94 µS/cm	3.15 mg/L	28.50 NTU	-41.9 mV	25.32 ft	200.00 ml/min
10/1/2024 1:35 PM	40:00	6.64 pH	20.73 °C	772.73 µS/cm	2.87 mg/L	27.00 NTU	-30.3 mV	25.32 ft	200.00 ml/min
10/1/2024 1:40 PM	45:00	6.64 pH	21.03 °C	768.51 µS/cm	2.58 mg/L	26.40 NTU	-38.1 mV	25.32 ft	200.00 ml/min
10/1/2024 1:45 PM	50:00	6.64 pH	21.34 °C	762.81 µS/cm	2.29 mg/L	21.30 NTU	-27.8 mV	25.32 ft	200.00 ml/min
10/1/2024 1:50 PM	55:00	6.63 pH	21.37 °C	757.78 µS/cm	2.06 mg/L	14.70 NTU	-26.7 mV	25.32 ft	200.00 ml/min
10/1/2024 1:55 PM	01:00:00	6.64 pH	21.19 °C	756.87 µS/cm	1.86 mg/L	13.20 NTU	-33.7 mV	25.32 ft	200.00 ml/min
10/1/2024 2:00 PM	01:05:00	6.63 pH	21.10 °C	753.53 µS/cm	1.70 mg/L	12.50 NTU	-23.9 mV	25.32 ft	200.00 ml/min
10/1/2024 2:05 PM	01:10:00	6.63 pH	21.15 °C	749.72 µS/cm	1.45 mg/L	11.00 NTU	-23.0 mV	25.32 ft	200.00 ml/min

10/1/2024 2:10 PM	01:15:00	6.64 pH	20.97 °C	743.97 µS/cm	1.32 mg/L	9.67 NTU	-22.4 mV	25.32 ft	200.00 ml/min
10/1/2024 2:15 PM	01:20:00	6.63 pH	20.93 °C	739.23 µS/cm	0.92 mg/L	6.41 NTU	-29.6 mV	25.32 ft	200.00 ml/min
10/1/2024 2:20 PM	01:25:00	6.63 pH	20.84 °C	737.03 µS/cm	0.81 mg/L	5.50 NTU	-28.9 mV	25.32 ft	200.00 ml/min
10/1/2024 2:25 PM	01:30:00	6.62 pH	21.11 °C	732.46 µS/cm	0.70 mg/L	3.57 NTU	-19.7 mV	25.32 ft	200.00 ml/min
10/1/2024 2:30 PM	01:35:00	6.62 pH	21.37 °C	730.56 µS/cm	0.59 mg/L	4.11 NTU	-26.9 mV	25.32 ft	200.00 ml/min
10/1/2024 2:35 PM	01:40:00	6.63 pH	21.51 °C	732.73 µS/cm	0.52 mg/L	3.60 NTU	-27.1 mV	25.32 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.

Low-Flow Test Report:

Test Date / Time: 10/2/2024 11:16:09 AM
Project: GP-Plant Hammond
Operator Name: Zain W.

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.47 ft Total Depth: 30.47 ft Initial Depth to Water: 15.5 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 25.47 ft Estimated Total Volume Pumped: 10.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.01 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883530
--	--	--

Test Notes:
Metals. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Weather Conditions: Clear, 85 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/2/2024 11:16 AM	00:00	6.77 pH	21.20 °C	647.49 µS/cm	0.05 mg/L	32.00 NTU	111.9 mV	15.50 ft	150.00 ml/min
10/2/2024 11:21 AM	05:00	6.80 pH	21.15 °C	693.39 µS/cm	0.04 mg/L	30.60 NTU	401.2 mV	15.51 ft	150.00 ml/min
10/2/2024 11:26 AM	10:00	6.81 pH	21.13 °C	691.98 µS/cm	0.04 mg/L	28.50 NTU	447.7 mV	15.51 ft	150.00 ml/min
10/2/2024 11:31 AM	15:00	6.81 pH	20.98 °C	697.20 µS/cm	0.04 mg/L	27.70 NTU	463.8 mV	15.51 ft	150.00 ml/min
10/2/2024 11:36 AM	20:00	6.81 pH	20.98 °C	698.06 µS/cm	0.04 mg/L	26.90 NTU	469.6 mV	15.51 ft	150.00 ml/min
10/2/2024 11:41 AM	25:00	6.80 pH	21.06 °C	697.25 µS/cm	0.03 mg/L	27.40 NTU	470.3 mV	15.51 ft	150.00 ml/min
10/2/2024 11:46 AM	30:00	6.80 pH	21.11 °C	694.10 µS/cm	0.03 mg/L	23.20 NTU	467.8 mV	15.51 ft	150.00 ml/min
10/2/2024 11:51 AM	35:00	6.80 pH	21.11 °C	698.38 µS/cm	0.03 mg/L	17.90 NTU	465.4 mV	15.51 ft	150.00 ml/min
10/2/2024 11:56 AM	40:00	6.80 pH	21.19 °C	691.78 µS/cm	0.03 mg/L	14.80 NTU	461.8 mV	15.51 ft	150.00 ml/min
10/2/2024 12:01 PM	45:00	6.79 pH	21.05 °C	692.02 µS/cm	0.03 mg/L	11.40 NTU	458.3 mV	15.51 ft	150.00 ml/min
10/2/2024 12:06 PM	50:00	6.79 pH	21.02 °C	693.76 µS/cm	0.03 mg/L	6.93 NTU	455.5 mV	15.51 ft	150.00 ml/min
10/2/2024 12:11 PM	55:00	6.81 pH	21.16 °C	697.36 µS/cm	0.04 mg/L	5.14 NTU	451.8 mV	15.51 ft	150.00 ml/min
10/2/2024 12:16 PM	01:00:00	6.81 pH	21.11 °C	696.66 µS/cm	0.05 mg/L	3.87 NTU	447.2 mV	15.51 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.
HAM-AP1-FD-01	Grab.

Low-Flow Test Report:

Test Date / Time: 10/2/2024 11:33:40 AM
Project: GP-Plant Hammond
Operator Name: Elisabeth R.

Location Name: PT-10 Well Diameter: 2 in Casing Type: PVC Screen Length: 25.45 ft Top of Screen: 20.45 ft Total Depth: 30.45 ft Initial Depth to Water: 15.7 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 25 ft Estimated Total Volume Pumped: 8 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883561
---	---	--

Test Notes:
Metals. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/2/2024 11:33 AM	00:00	7.08 pH	21.57 °C	706.62 µS/cm	0.53 mg/L	21.80 NTU	-40.5 mV	15.70 ft	200.00 ml/min
10/2/2024 11:38 AM	05:00	7.06 pH	21.58 °C	698.33 µS/cm	0.53 mg/L	18.30 NTU	-44.7 mV	15.71 ft	200.00 ml/min
10/2/2024 11:43 AM	10:00	7.04 pH	21.58 °C	689.07 µS/cm	0.53 mg/L	13.40 NTU	-39.2 mV	15.71 ft	200.00 ml/min
10/2/2024 11:48 AM	15:00	7.03 pH	21.49 °C	685.61 µS/cm	0.56 mg/L	7.83 NTU	-31.0 mV	15.71 ft	200.00 ml/min
10/2/2024 11:53 AM	20:00	7.01 pH	21.67 °C	680.20 µS/cm	0.39 mg/L	4.67 NTU	-13.1 mV	15.72 ft	200.00 ml/min
10/2/2024 11:58 AM	25:00	7.01 pH	21.64 °C	676.89 µS/cm	0.28 mg/L	2.98 NTU	-8.8 mV	15.72 ft	200.00 ml/min
10/2/2024 12:03 PM	30:00	6.99 pH	21.62 °C	674.40 µS/cm	0.28 mg/L	2.31 NTU	-6.2 mV	15.72 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.

Low-Flow Test Report:

Test Date / Time: 10/2/2024 9:16:22 AM
Project: GP-Plant Hammond
Operator Name: Zain W.

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 16.9 ft Total Depth: 26.9 ft Initial Depth to Water: 12.1 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 21.9 ft Estimated Total Volume Pumped: 7.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.01 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883530
--	---	--

Test Notes:
Metals. Ferrous Iron: 2.0 mg/L, Total Iron: 2.0 mg/L.

Weather Conditions:
Clear, 75 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/2/2024 9:16 AM	00:00	7.00 pH	21.21 °C	628.69 µS/cm	0.53 mg/L	3.26 NTU	171.2 mV	12.10 ft	150.00 ml/min
10/2/2024 9:21 AM	05:00	6.80 pH	20.75 °C	652.77 µS/cm	0.37 mg/L	4.68 NTU	478.2 mV	12.11 ft	150.00 ml/min
10/2/2024 9:26 AM	10:00	6.79 pH	20.84 °C	656.05 µS/cm	0.28 mg/L	4.85 NTU	505.0 mV	12.11 ft	150.00 ml/min
10/2/2024 9:31 AM	15:00	6.67 pH	20.98 °C	661.83 µS/cm	0.10 mg/L	5.16 NTU	414.7 mV	12.11 ft	150.00 ml/min
10/2/2024 9:36 AM	20:00	6.68 pH	21.01 °C	669.17 µS/cm	0.09 mg/L	4.55 NTU	407.9 mV	12.11 ft	150.00 ml/min
10/2/2024 9:41 AM	25:00	6.68 pH	21.02 °C	667.35 µS/cm	0.08 mg/L	5.93 NTU	460.1 mV	12.11 ft	150.00 ml/min
10/2/2024 9:46 AM	30:00	6.67 pH	20.98 °C	668.51 µS/cm	0.07 mg/L	6.60 NTU	457.6 mV	12.11 ft	150.00 ml/min
10/2/2024 9:51 AM	35:00	6.66 pH	21.07 °C	661.15 µS/cm	0.06 mg/L	6.97 NTU	458.3 mV	12.11 ft	150.00 ml/min
10/2/2024 9:56 AM	40:00	6.66 pH	21.13 °C	664.35 µS/cm	0.06 mg/L	5.49 NTU	417.2 mV	12.11 ft	150.00 ml/min
10/2/2024 10:01 AM	45:00	6.64 pH	21.20 °C	658.94 µS/cm	0.06 mg/L	4.70 NTU	406.7 mV	12.11 ft	150.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

HAM-PT-11	Grab.
-----------	-------

Low-Flow Test Report:

Test Date / Time: 10/2/2024 8:47:38 AM
Project: GP-Plant Hammond
Operator Name: Elisabeth R.

Location Name: PT-12 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.3 ft Total Depth: 27.3 ft Initial Depth to Water: 12.1 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22 ft Estimated Total Volume Pumped: 20 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.01 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883561
--	--	--

Test Notes:
Metals. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/2/2024 8:47 AM	00:00	6.49 pH	19.69 °C	675.14 µS/cm	1.43 mg/L	21.20 NTU	109.8 mV	12.10 ft	200.00 ml/min
10/2/2024 8:52 AM	05:00	6.69 pH	19.64 °C	692.57 µS/cm	1.75 mg/L	18.60 NTU	108.1 mV	12.11 ft	200.00 ml/min
10/2/2024 8:57 AM	10:00	6.70 pH	19.65 °C	690.21 µS/cm	2.04 mg/L	17.30 NTU	78.9 mV	12.11 ft	200.00 ml/min
10/2/2024 9:02 AM	15:00	6.71 pH	19.68 °C	691.52 µS/cm	1.19 mg/L	14.60 NTU	74.2 mV	12.11 ft	200.00 ml/min
10/2/2024 9:07 AM	20:00	6.76 pH	19.67 °C	705.37 µS/cm	3.21 mg/L	15.10 NTU	79.3 mV	12.11 ft	200.00 ml/min
10/2/2024 9:12 AM	25:00	6.78 pH	19.72 °C	627.46 µS/cm	3.36 mg/L	18.30 NTU	81.8 mV	12.11 ft	200.00 ml/min
10/2/2024 9:17 AM	30:00	6.74 pH	19.82 °C	630.40 µS/cm	2.90 mg/L	23.30 NTU	80.4 mV	12.11 ft	200.00 ml/min
10/2/2024 9:22 AM	35:00	6.71 pH	19.90 °C	688.92 µS/cm	2.44 mg/L	22.80 NTU	78.9 mV	12.11 ft	200.00 ml/min
10/2/2024 9:27 AM	40:00	6.68 pH	20.11 °C	690.35 µS/cm	0.42 mg/L	19.50 NTU	72.3 mV	12.11 ft	200.00 ml/min
10/2/2024 9:32 AM	45:00	6.67 pH	20.32 °C	685.26 µS/cm	0.23 mg/L	17.80 NTU	87.4 mV	12.11 ft	200.00 ml/min
10/2/2024 9:37 AM	50:00	6.66 pH	20.44 °C	681.26 µS/cm	0.23 mg/L	15.80 NTU	87.1 mV	12.11 ft	200.00 ml/min
10/2/2024 9:42 AM	55:00	6.66 pH	20.52 °C	677.61 µS/cm	0.22 mg/L	13.40 NTU	86.6 mV	12.11 ft	200.00 ml/min
10/2/2024 9:47 AM	01:00:00	6.67 pH	20.62 °C	677.33 µS/cm	0.21 mg/L	11.10 NTU	66.4 mV	12.11 ft	200.00 ml/min
10/2/2024 9:52 AM	01:05:00	6.67 pH	20.72 °C	673.79 µS/cm	0.21 mg/L	10.70 NTU	83.7 mV	12.11 ft	200.00 ml/min
10/2/2024 9:57 AM	01:10:00	6.66 pH	20.84 °C	672.89 µS/cm	0.21 mg/L	5.85 NTU	65.7 mV	12.11 ft	200.00 ml/min

10/2/2024 10:02 AM	01:15:00	6.65 pH	20.84 °C	681.56 µS/cm	1.12 mg/L	4.19 NTU	67.7 mV	12.11 ft	200.00 ml/min
10/2/2024 10:07 AM	01:19:30	6.65 pH	20.84 °C	682.42 µS/cm	1.57 mg/L	3.70 NTU	71.5 mV	12.11 ft	200.00 ml/min
10/2/2024 10:12 AM	01:24:30	6.65 pH	20.86 °C	673.47 µS/cm	2.18 mg/L	3.20 NTU	86.8 mV	12.11 ft	200.00 ml/min
10/2/2024 10:17 AM	01:29:30	6.70 pH	20.88 °C	678.79 µS/cm	2.35 mg/L	3.22 NTU	94.0 mV	12.11 ft	200.00 ml/min
10/2/2024 10:20 AM	01:32:50	6.71 pH	20.84 °C	674.50 µS/cm	2.21 mg/L	2.93 NTU	75.6 mV	12.11 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-12	Grab.

Low-Flow Test Report:

Test Date / Time: 10/1/2024 9:35:45 AM
Project: GP-Plant Hammond
Operator Name: Zain W.

Location Name: PT-13 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 24.83 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 24 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883530
--	--	--

Test Notes:
Metals. Ferrous Iron: 1.5 mg/L, Total Iron: 1.5 mg/L.

Weather Conditions:
Cloudy, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/1/2024 9:35 AM	00:00	6.73 pH	20.45 °C	817.23 µS/cm	2.32 mg/L	++++	263.2 mV	24.83 ft	150.00 ml/min
10/1/2024 9:40 AM	05:00	6.73 pH	20.31 °C	793.43 µS/cm	2.66 mg/L	++++	472.0 mV	24.87 ft	150.00 ml/min
10/1/2024 9:45 AM	10:00	6.72 pH	20.70 °C	774.18 µS/cm	2.05 mg/L	++++	473.7 mV	24.87 ft	150.00 ml/min
10/1/2024 9:50 AM	15:00	6.70 pH	20.40 °C	754.08 µS/cm	1.83 mg/L	++++	480.7 mV	24.88 ft	150.00 ml/min
10/1/2024 9:55 AM	20:00	6.69 pH	20.27 °C	729.96 µS/cm	1.64 mg/L	70.20 NTU	477.0 mV	24.88 ft	150.00 ml/min
10/1/2024 10:00 AM	25:00	6.68 pH	20.26 °C	726.14 µS/cm	1.46 mg/L	49.30 NTU	374.9 mV	24.88 ft	150.00 ml/min
10/1/2024 10:05 AM	30:00	6.66 pH	20.35 °C	720.21 µS/cm	1.27 mg/L	34.70 NTU	334.4 mV	24.88 ft	150.00 ml/min
10/1/2024 10:10 AM	35:00	6.65 pH	20.81 °C	746.59 µS/cm	0.42 mg/L	26.50 NTU	250.6 mV	24.88 ft	150.00 ml/min
10/1/2024 10:15 AM	40:00	6.65 pH	21.02 °C	737.08 µS/cm	0.34 mg/L	20.50 NTU	248.0 mV	24.88 ft	150.00 ml/min
10/1/2024 10:20 AM	45:00	6.65 pH	21.40 °C	730.98 µS/cm	0.29 mg/L	18.60 NTU	374.1 mV	24.88 ft	150.00 ml/min
10/1/2024 10:25 AM	50:00	6.63 pH	21.22 °C	733.37 µS/cm	0.25 mg/L	15.70 NTU	550.9 mV	24.88 ft	150.00 ml/min
10/1/2024 10:30 AM	55:00	6.64 pH	20.85 °C	728.19 µS/cm	0.23 mg/L	12.80 NTU	574.5 mV	24.88 ft	150.00 ml/min
10/1/2024 10:35 AM	01:00:00	6.64 pH	20.93 °C	727.00 µS/cm	0.22 mg/L	11.30 NTU	614.2 mV	24.88 ft	150.00 ml/min

10/1/2024 10:40 AM	01:05:00	6.64 pH	20.80 °C	726.01 µS/cm	0.20 mg/L	10.60 NTU	634.0 mV	24.88 ft	150.00 ml/min
10/1/2024 10:45 AM	01:10:00	6.64 pH	20.62 °C	726.57 µS/cm	0.18 mg/L	12.10 NTU	641.4 mV	24.88 ft	150.00 ml/min
10/1/2024 10:50 AM	01:15:00	6.65 pH	20.53 °C	748.23 µS/cm	0.14 mg/L	11.20 NTU	644.9 mV	24.88 ft	150.00 ml/min
10/1/2024 10:55 AM	01:20:00	6.64 pH	20.49 °C	745.19 µS/cm	0.12 mg/L	10.50 NTU	680.9 mV	24.88 ft	150.00 ml/min
10/1/2024 11:00 AM	01:25:00	6.64 pH	20.51 °C	742.38 µS/cm	0.11 mg/L	9.49 NTU	629.7 mV	24.88 ft	150.00 ml/min
10/1/2024 11:05 AM	01:30:00	6.64 pH	20.49 °C	740.99 µS/cm	0.10 mg/L	8.73 NTU	618.4 mV	24.88 ft	150.00 ml/min
10/1/2024 11:10 AM	01:35:00	6.65 pH	20.49 °C	739.68 µS/cm	0.10 mg/L	8.45 NTU	618.9 mV	24.88 ft	150.00 ml/min
10/1/2024 11:15 AM	01:40:00	6.63 pH	20.49 °C	738.34 µS/cm	0.10 mg/L	7.86 NTU	656.9 mV	24.88 ft	150.00 ml/min
10/1/2024 11:20 AM	01:45:00	6.64 pH	20.49 °C	742.72 µS/cm	0.09 mg/L	7.44 NTU	613.6 mV	24.88 ft	150.00 ml/min
10/1/2024 11:25 AM	01:50:00	6.64 pH	20.44 °C	743.93 µS/cm	0.09 mg/L	7.11 NTU	621.6 mV	24.88 ft	150.00 ml/min
10/1/2024 11:30 AM	01:55:00	6.63 pH	20.44 °C	741.76 µS/cm	0.08 mg/L	6.35 NTU	665.2 mV	24.88 ft	150.00 ml/min
10/1/2024 11:35 AM	02:00:00	6.64 pH	20.44 °C	739.18 µS/cm	0.08 mg/L	5.94 NTU	622.3 mV	24.88 ft	150.00 ml/min
10/1/2024 11:40 AM	02:05:00	6.64 pH	20.40 °C	735.67 µS/cm	0.07 mg/L	5.78 NTU	619.4 mV	24.88 ft	150.00 ml/min
10/1/2024 11:45 AM	02:10:00	6.63 pH	20.40 °C	734.07 µS/cm	0.07 mg/L	5.91 NTU	663.5 mV	24.88 ft	150.00 ml/min
10/1/2024 11:50 AM	02:15:00	6.64 pH	20.59 °C	732.08 µS/cm	0.06 mg/L	5.47 NTU	621.8 mV	24.88 ft	150.00 ml/min
10/1/2024 11:55 AM	02:20:00	6.64 pH	20.89 °C	728.17 µS/cm	0.06 mg/L	5.23 NTU	625.2 mV	24.88 ft	150.00 ml/min
10/1/2024 12:00 PM	02:25:00	6.63 pH	21.28 °C	726.98 µS/cm	0.06 mg/L	5.17 NTU	653.7 mV	24.88 ft	150.00 ml/min
10/1/2024 12:05 PM	02:30:00	6.63 pH	21.20 °C	727.42 µS/cm	0.06 mg/L	5.69 NTU	683.7 mV	24.88 ft	150.00 ml/min
10/1/2024 12:10 PM	02:35:00	6.63 pH	21.04 °C	726.14 µS/cm	0.06 mg/L	4.83 NTU	716.9 mV	24.88 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-13	Grab.

Low-Flow Test Report:

Test Date / Time: 10/1/2024 10:12:19 AM
Project: GP-Plant Hammond
Operator Name: Elisabeth R.

Location Name: PT-14 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.03 ft Total Depth: 45.03 ft Initial Depth to Water: 25.07 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 12 liter Flow Cell Volume: 90 ml Final Flow Rate: 160 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883561
---	---	--

Test Notes:
Metals. Ferrous Iron: 2.25 mg/L, Total Iron: 6.5 mg/L.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/1/2024 10:12 AM	00:00	6.72 pH	19.99 °C	830.59 µS/cm	4.57 mg/L	64.60 NTU	-28.8 mV	25.10 ft	160.00 ml/min
10/1/2024 10:17 AM	05:00	6.72 pH	19.99 °C	825.95 µS/cm	4.09 mg/L	55.70 NTU	-47.2 mV	25.10 ft	160.00 ml/min
10/1/2024 10:22 AM	10:00	6.72 pH	20.06 °C	818.99 µS/cm	3.63 mg/L	42.60 NTU	-35.2 mV	25.10 ft	160.00 ml/min
10/1/2024 10:27 AM	15:00	6.72 pH	19.96 °C	813.64 µS/cm	3.29 mg/L	35.70 NTU	-37.0 mV	25.10 ft	160.00 ml/min
10/1/2024 10:32 AM	20:00	6.73 pH	19.95 °C	810.29 µS/cm	2.99 mg/L	23.50 NTU	-38.8 mV	25.10 ft	160.00 ml/min
10/1/2024 10:37 AM	25:00	6.73 pH	19.86 °C	807.83 µS/cm	2.70 mg/L	18.50 NTU	-39.5 mV	25.10 ft	160.00 ml/min
10/1/2024 10:42 AM	30:00	6.73 pH	19.72 °C	810.38 µS/cm	0.16 mg/L	16.60 NTU	-38.6 mV	25.10 ft	160.00 ml/min
10/1/2024 10:47 AM	35:00	6.73 pH	19.63 °C	805.85 µS/cm	0.13 mg/L	13.40 NTU	-40.6 mV	25.10 ft	160.00 ml/min
10/1/2024 10:52 AM	40:00	6.73 pH	19.55 °C	801.35 µS/cm	0.13 mg/L	8.87 NTU	-53.6 mV	25.10 ft	160.00 ml/min
10/1/2024 10:57 AM	45:00	6.74 pH	19.53 °C	796.99 µS/cm	0.23 mg/L	6.95 NTU	-54.6 mV	25.10 ft	160.00 ml/min
10/1/2024 11:02 AM	50:00	6.74 pH	19.50 °C	791.95 µS/cm	0.17 mg/L	7.34 NTU	-55.3 mV	25.10 ft	160.00 ml/min
10/1/2024 11:07 AM	55:00	6.72 pH	19.51 °C	790.85 µS/cm	0.17 mg/L	6.92 NTU	-54.8 mV	25.10 ft	160.00 ml/min
10/1/2024 11:12 AM	01:00:00	6.73 pH	19.50 °C	786.55 µS/cm	0.15 mg/L	5.67 NTU	-41.8 mV	25.10 ft	160.00 ml/min
10/1/2024 11:17 AM	01:05:00	6.73 pH	19.49 °C	778.06 µS/cm	0.13 mg/L	4.89 NTU	-43.0 mV	25.10 ft	160.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-14	Grab.

Low-Flow Test Report:

Test Date / Time: 10/1/2024 3:52:20 PM
Project: GP-Plant Hammond
Operator Name: Elisabeth R.

Location Name: PT-15 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35 ft Total Depth: 45 ft Initial Depth to Water: 24.81 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 19 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 883561
---	--	--

Test Notes:
Metals. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/1/2024 3:52 PM	00:00	6.87 pH	22.53 °C	780.08 µS/cm	5.04 mg/L	++++	63.8 mV	24.81 ft	200.00 ml/min
10/1/2024 3:52 PM	00:18	6.88 pH	22.41 °C	779.80 µS/cm	4.89 mg/L	++++	58.5 mV	24.81 ft	200.00 ml/min
10/1/2024 3:57 PM	05:18	6.87 pH	21.58 °C	790.37 µS/cm	4.36 mg/L	++++	53.7 mV	24.81 ft	200.00 ml/min
10/1/2024 4:02 PM	10:18	6.85 pH	21.27 °C	788.88 µS/cm	3.94 mg/L	++++	53.1 mV	24.81 ft	200.00 ml/min
10/1/2024 4:07 PM	15:18	6.85 pH	21.11 °C	785.10 µS/cm	3.47 mg/L	++++	52.1 mV	24.81 ft	200.00 ml/min
10/1/2024 4:12 PM	20:18	6.84 pH	21.00 °C	780.52 µS/cm	3.06 mg/L	86.80 NTU	62.5 mV	24.81 ft	200.00 ml/min
10/1/2024 4:17 PM	25:18	6.84 pH	20.86 °C	776.20 µS/cm	2.73 mg/L	72.30 NTU	63.1 mV	24.81 ft	200.00 ml/min
10/1/2024 4:22 PM	30:18	6.84 pH	20.83 °C	778.55 µS/cm	2.36 mg/L	54.30 NTU	51.6 mV	24.81 ft	200.00 ml/min
10/1/2024 4:27 PM	35:18	6.83 pH	20.78 °C	775.01 µS/cm	2.15 mg/L	31.20 NTU	63.1 mV	24.81 ft	200.00 ml/min
10/1/2024 4:32 PM	40:18	6.82 pH	20.75 °C	771.05 µS/cm	1.94 mg/L	26.20 NTU	62.0 mV	24.81 ft	200.00 ml/min
10/1/2024 4:37 PM	45:18	6.82 pH	20.71 °C	768.33 µS/cm	1.75 mg/L	23.50 NTU	61.3 mV	24.81 ft	200.00 ml/min
10/1/2024 4:42 PM	50:18	6.82 pH	20.75 °C	764.92 µS/cm	1.58 mg/L	17.90 NTU	49.5 mV	24.81 ft	200.00 ml/min
10/1/2024 4:47 PM	55:18	6.82 pH	20.70 °C	777.11 µS/cm	1.41 mg/L	15.30 NTU	59.9 mV	24.81 ft	200.00 ml/min
10/1/2024 4:52 PM	01:00:18	6.82 pH	20.66 °C	772.45 µS/cm	1.25 mg/L	11.00 NTU	60.9 mV	24.81 ft	200.00 ml/min
10/1/2024 4:57 PM	01:05:18	6.82 pH	20.61 °C	769.84 µS/cm	1.10 mg/L	9.81 NTU	49.5 mV	24.81 ft	200.00 ml/min

10/1/2024 5:02 PM	01:10:18	6.81 pH	20.62 °C	768.09 µS/cm	0.99 mg/L	7.32 NTU	50.2 mV	24.81 ft	200.00 ml/min
10/1/2024 5:07 PM	01:15:18	6.81 pH	20.66 °C	771.08 µS/cm	0.73 mg/L	6.78 NTU	50.1 mV	24.81 ft	200.00 ml/min
10/1/2024 5:12 PM	01:20:18	6.81 pH	20.64 °C	769.04 µS/cm	0.64 mg/L	5.53 NTU	60.9 mV	24.81 ft	200.00 ml/min
10/1/2024 5:17 PM	01:25:18	6.81 pH	20.64 °C	771.11 µS/cm	0.55 mg/L	4.97 NTU	61.9 mV	24.81 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-15	Grab.

Low-Flow Test Report:

Test Date / Time: 10/9/2024 1:54:52 PM
Project: GP-Plant Hammond
Operator Name: Elisabeth R.

Location Name: INW-03 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.4 ft Total Depth: 27.4 ft Initial Depth to Water: 13.08 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22.4 ft Estimated Total Volume Pumped: 4 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 968202
--	---	--

Test Notes:
Parameters.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/9/2024 1:54 PM	00:00	6.05 pH	22.58 °C	693.39 µS/cm	1.06 mg/L	3.30 NTU	-12.3 mV	13.08 ft	200.00 ml/min
10/9/2024 1:59 PM	05:00	6.04 pH	21.85 °C	705.48 µS/cm	0.63 mg/L	2.90 NTU	-12.1 mV	13.08 ft	200.00 ml/min
10/9/2024 2:04 PM	10:04	6.68 pH	21.72 °C	834.34 µS/cm	0.05 mg/L	2.03 NTU	-88.6 mV	13.08 ft	200.00 ml/min
10/9/2024 2:09 PM	15:04	6.73 pH	21.53 °C	840.17 µS/cm	0.08 mg/L	1.27 NTU	-98.7 mV	13.08 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 10/9/2024 3:00:19 PM
Project: GP-Plant Hammond
Operator Name: Zain W.

Location Name: INW-04 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.38 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 2.25 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.13 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080302
--	---	---

Test Notes:
Parameters.

Weather Conditions:
Clear, 90 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/9/2024 3:00 PM	00:00	6.33 pH	23.80 °C	610.47 µS/cm	3.43 mg/L	309.00 NTU	13.0 mV	25.38 ft	150.00 ml/min
10/9/2024 3:05 PM	05:00	6.32 pH	21.33 °C	641.31 µS/cm	2.92 mg/L	327.00 NTU	9.8 mV	25.51 ft	150.00 ml/min
10/9/2024 3:10 PM	10:00	6.30 pH	21.20 °C	631.62 µS/cm	2.79 mg/L	294.00 NTU	8.4 mV	25.51 ft	150.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 10/9/2024 3:23:20 PM
Project: GP-Plant Hammond
Operator Name: Zain W.

Location Name: INW-05 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.0 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 2.25 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.04 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080302
---	--	---

Test Notes:
Parameters.

Weather Conditions:
Clear, 90 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/9/2024 3:23 PM	00:00	6.28 pH	25.64 °C	657.79 µS/cm	0.81 mg/L	266.00 NTU	8.1 mV	25.00 ft	150.00 ml/min
10/9/2024 3:28 PM	05:00	6.64 pH	21.71 °C	728.68 µS/cm	2.54 mg/L	304.00 NTU	-69.1 mV	25.04 ft	150.00 ml/min
10/9/2024 3:33 PM	10:00	6.67 pH	21.26 °C	741.49 µS/cm	1.11 mg/L	292.00 NTU	-81.9 mV	25.04 ft	150.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 10/8/2024 2:23:12 PM
Project: GP-Plant Hammond
Operator Name: Zain W.

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 37.75 ft Total Depth: 47.75 ft Initial Depth to Water: 26.0 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 42.75 ft Estimated Total Volume Pumped: 7.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: -0.22 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080302
--	--	---

Test Notes:
Appendix III & IV + Major Ions. Ferrous Iron: 4.0 mg/L, Total Iron: 4.0 mg/L.

Weather Conditions:
Clear, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/8/2024 2:23 PM	00:00	6.73 pH	20.79 °C	755.67 µS/cm	1.03 mg/L	26.10 NTU	-25.3 mV	26.00 ft	150.00 ml/min
10/8/2024 2:28 PM	05:00	6.72 pH	20.84 °C	752.69 µS/cm	0.97 mg/L	18.60 NTU	-34.5 mV	25.76 ft	150.00 ml/min
10/8/2024 2:33 PM	10:00	6.73 pH	20.84 °C	750.11 µS/cm	0.91 mg/L	12.00 NTU	-22.9 mV	25.78 ft	150.00 ml/min
10/8/2024 2:38 PM	15:00	6.73 pH	20.82 °C	747.93 µS/cm	0.84 mg/L	15.90 NTU	-32.8 mV	25.78 ft	150.00 ml/min
10/8/2024 2:43 PM	20:00	6.73 pH	20.84 °C	746.17 µS/cm	0.81 mg/L	14.10 NTU	-21.9 mV	25.78 ft	150.00 ml/min
10/8/2024 2:48 PM	25:00	6.72 pH	20.79 °C	740.51 µS/cm	0.75 mg/L	8.11 NTU	-21.2 mV	25.78 ft	150.00 ml/min
10/8/2024 2:53 PM	30:00	6.72 pH	20.76 °C	741.43 µS/cm	0.69 mg/L	7.56 NTU	-20.8 mV	25.78 ft	150.00 ml/min
10/8/2024 2:58 PM	35:00	6.73 pH	20.81 °C	737.37 µS/cm	0.63 mg/L	6.71 NTU	-20.6 mV	25.78 ft	150.00 ml/min
10/8/2024 3:03 PM	40:00	6.72 pH	20.74 °C	733.68 µS/cm	0.57 mg/L	5.54 NTU	-20.7 mV	25.78 ft	150.00 ml/min
10/8/2024 3:08 PM	45:00	6.72 pH	20.76 °C	729.91 µS/cm	0.54 mg/L	4.40 NTU	-20.5 mV	25.78 ft	150.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

HAM-PT-07	Grab.
-----------	-------

Low-Flow Test Report:

Test Date / Time: 10/8/2024 10:37:10 AM
Project: GP-Plant Hammond
Operator Name: Elisabeth R.

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 31.93 ft Total Depth: 41.93 ft Initial Depth to Water: 25.75 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 37 ft Estimated Total Volume Pumped: 25 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 968202
--	--	--

Test Notes:
Appendix III & IV + Major Ions. Ferrous Iron: 2.25 mg/L, Total Iron: 10 mg/L.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/8/2024 10:37 AM	00:00	6.62 pH	21.61 °C	624.57 µS/cm	3.85 mg/L	++++	-4.2 mV	25.75 ft	200.00 ml/min
10/8/2024 10:42 AM	05:00	6.59 pH	20.82 °C	640.63 µS/cm	3.04 mg/L	++++	0.4 mV	25.80 ft	200.00 ml/min
10/8/2024 10:47 AM	10:00	6.59 pH	20.99 °C	660.71 µS/cm	2.67 mg/L	++++	5.8 mV	25.80 ft	200.00 ml/min
10/8/2024 10:52 AM	15:00	6.60 pH	20.38 °C	676.87 µS/cm	2.58 mg/L	++++	-25.4 mV	25.80 ft	200.00 ml/min
10/8/2024 10:57 AM	20:00	6.62 pH	20.35 °C	685.16 µS/cm	2.30 mg/L	91.70 NTU	-25.2 mV	25.80 ft	200.00 ml/min
10/8/2024 11:02 AM	25:00	6.62 pH	20.29 °C	623.49 µS/cm	1.96 mg/L	75.30 NTU	-20.1 mV	25.80 ft	200.00 ml/min
10/8/2024 11:07 AM	30:00	6.63 pH	20.25 °C	683.03 µS/cm	1.86 mg/L	50.20 NTU	-19.6 mV	25.80 ft	200.00 ml/min
10/8/2024 11:12 AM	35:00	6.63 pH	20.29 °C	702.48 µS/cm	2.20 mg/L	31.40 NTU	-20.6 mV	25.80 ft	200.00 ml/min
10/8/2024 11:17 AM	40:00	6.63 pH	20.30 °C	698.20 µS/cm	2.03 mg/L	27.20 NTU	-19.6 mV	25.80 ft	200.00 ml/min
10/8/2024 11:22 AM	45:00	6.65 pH	20.39 °C	696.30 µS/cm	1.21 mg/L	22.50 NTU	-22.7 mV	25.80 ft	200.00 ml/min
10/8/2024 11:27 AM	50:00	6.65 pH	20.39 °C	692.90 µS/cm	0.93 mg/L	18.70 NTU	-21.6 mV	25.80 ft	200.00 ml/min
10/8/2024 11:32 AM	55:00	6.66 pH	20.34 °C	694.47 µS/cm	0.74 mg/L	16.70 NTU	-30.6 mV	25.80 ft	200.00 ml/min
10/8/2024 11:37 AM	01:00:00	6.67 pH	20.36 °C	691.64 µS/cm	0.63 mg/L	14.10 NTU	-30.6 mV	25.80 ft	200.00 ml/min
10/8/2024 11:42 AM	01:05:00	6.67 pH	20.34 °C	690.94 µS/cm	0.57 mg/L	13.00 NTU	-30.3 mV	25.80 ft	200.00 ml/min
10/8/2024 11:47 AM	01:10:00	6.67 pH	20.37 °C	688.70 µS/cm	0.50 mg/L	12.00 NTU	-29.7 mV	25.80 ft	200.00 ml/min

10/8/2024 11:52 AM	01:15:00	6.67 pH	20.39 °C	686.45 µS/cm	0.48 mg/L	11.20 NTU	-20.9 mV	25.80 ft	200.00 ml/min
10/8/2024 11:57 AM	01:20:00	6.67 pH	20.39 °C	685.91 µS/cm	0.46 mg/L	10.30 NTU	-28.7 mV	25.80 ft	200.00 ml/min
10/8/2024 12:02 PM	01:25:00	6.67 pH	20.39 °C	684.73 µS/cm	0.47 mg/L	9.30 NTU	-21.3 mV	25.80 ft	200.00 ml/min
10/8/2024 12:07 PM	01:30:00	6.67 pH	20.40 °C	681.65 µS/cm	0.45 mg/L	7.42 NTU	-20.6 mV	25.80 ft	200.00 ml/min
10/8/2024 12:12 PM	01:35:00	6.67 pH	20.40 °C	680.22 µS/cm	0.45 mg/L	6.33 NTU	-27.5 mV	25.80 ft	200.00 ml/min
10/8/2024 12:17 PM	01:40:00	6.67 pH	20.47 °C	678.81 µS/cm	0.44 mg/L	6.46 NTU	-20.3 mV	25.80 ft	200.00 ml/min
10/8/2024 12:22 PM	01:45:00	6.67 pH	20.44 °C	676.99 µS/cm	0.42 mg/L	6.07 NTU	-21.5 mV	25.80 ft	200.00 ml/min
10/8/2024 12:27 PM	01:50:00	6.68 pH	20.43 °C	675.17 µS/cm	0.39 mg/L	5.80 NTU	-19.5 mV	25.80 ft	200.00 ml/min
10/8/2024 12:32 PM	01:55:00	6.68 pH	20.46 °C	671.72 µS/cm	0.37 mg/L	5.34 NTU	-19.9 mV	25.80 ft	200.00 ml/min
10/8/2024 12:37 PM	02:00:00	6.69 pH	20.42 °C	669.84 µS/cm	0.36 mg/L	4.99 NTU	-20.0 mV	25.80 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.

Low-Flow Test Report:

Test Date / Time: 10/9/2024 11:27:06 AM
Project: GP-Plant Hammond
Operator Name: Elisabeth R.

Location Name: PT-09 Well Diameter: 2 in Screen Length: 10 ft Top of Screen: 20.47 ft Total Depth: 30.47 ft Initial Depth to Water: 16.32 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 25 ft Estimated Total Volume Pumped: 14 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 968202
---	--	--

Test Notes:
Appendix III & IV + Major Ions.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/9/2024 11:27 AM	00:00	6.90 pH	21.72 °C	716.42 µS/cm	0.10 mg/L	6.37 NTU	96.4 mV	16.33 ft	200.00 ml/min
10/9/2024 11:32 AM	05:00	6.91 pH	21.32 °C	733.39 µS/cm	0.06 mg/L	5.81 NTU	111.0 mV	16.33 ft	200.00 ml/min
10/9/2024 11:37 AM	10:00	6.94 pH	21.27 °C	723.13 µS/cm	0.06 mg/L	5.55 NTU	83.4 mV	16.34 ft	200.00 ml/min
10/9/2024 11:42 AM	15:00	6.96 pH	21.10 °C	727.87 µS/cm	0.06 mg/L	12.20 NTU	74.9 mV	16.34 ft	200.00 ml/min
10/9/2024 11:47 AM	20:00	6.94 pH	21.09 °C	724.34 µS/cm	0.06 mg/L	12.31 NTU	72.9 mV	16.34 ft	200.00 ml/min
10/9/2024 11:52 AM	25:00	6.90 pH	21.19 °C	723.55 µS/cm	0.05 mg/L	16.10 NTU	73.2 mV	16.34 ft	200.00 ml/min
10/9/2024 11:57 AM	30:00	6.91 pH	21.10 °C	722.98 µS/cm	0.04 mg/L	14.10 NTU	73.4 mV	16.34 ft	200.00 ml/min
10/9/2024 12:02 PM	35:00	6.90 pH	21.23 °C	720.59 µS/cm	0.04 mg/L	13.70 NTU	93.2 mV	16.34 ft	200.00 ml/min
10/9/2024 12:07 PM	40:00	6.90 pH	21.32 °C	713.56 µS/cm	0.04 mg/L	10.20 NTU	78.3 mV	16.34 ft	200.00 ml/min
10/9/2024 12:12 PM	45:00	6.92 pH	21.35 °C	718.85 µS/cm	0.04 mg/L	8.19 NTU	77.7 mV	16.34 ft	200.00 ml/min
10/9/2024 12:17 PM	50:00	6.89 pH	21.37 °C	713.52 µS/cm	0.05 mg/L	7.80 NTU	78.5 mV	16.34 ft	200.00 ml/min
10/9/2024 12:22 PM	55:00	6.88 pH	21.39 °C	718.45 µS/cm	0.05 mg/L	6.78 NTU	99.1 mV	16.34 ft	200.00 ml/min
10/9/2024 12:27 PM	01:00:00	6.92 pH	21.45 °C	719.31 µS/cm	0.04 mg/L	5.33 NTU	82.7 mV	16.34 ft	200.00 ml/min
10/9/2024 12:32 PM	01:05:00	6.90 pH	21.43 °C	722.62 µS/cm	0.04 mg/L	3.46 NTU	100.9 mV	16.34 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.

Low-Flow Test Report:

Test Date / Time: 10/9/2024 11:19:02 AM
Project: GP-Plant Hammond
Operator Name: Zain W.

Location Name: PT-10 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.45 ft Total Depth: 30.45 ft Initial Depth to Water: 16.29 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 25.45 ft Estimated Total Volume Pumped: 22.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080302
--	---	---

Test Notes:
Appendix III & IV + Major Ions. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Weather Conditions:
Clear, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/9/2024 11:19 AM	00:00	7.13 pH	20.65 °C	759.56 µS/cm	2.05 mg/L	4.70 NTU	-36.2 mV	16.29 ft	150.00 ml/min
10/9/2024 11:24 AM	05:00	7.13 pH	20.46 °C	762.50 µS/cm	1.52 mg/L	3.65 NTU	-37.5 mV	16.31 ft	150.00 ml/min
10/9/2024 11:29 AM	10:00	7.12 pH	20.39 °C	741.76 µS/cm	1.49 mg/L	1.79 NTU	-60.1 mV	16.31 ft	150.00 ml/min
10/9/2024 11:34 AM	15:00	7.12 pH	20.35 °C	732.05 µS/cm	2.62 mg/L	1.77 NTU	-61.0 mV	16.31 ft	150.00 ml/min
10/9/2024 11:39 AM	20:00	7.11 pH	20.42 °C	730.21 µS/cm	1.01 mg/L	2.06 NTU	-44.7 mV	16.31 ft	150.00 ml/min
10/9/2024 11:44 AM	25:00	7.10 pH	20.48 °C	733.14 µS/cm	2.43 mg/L	1.86 NTU	-62.7 mV	16.31 ft	150.00 ml/min
10/9/2024 11:49 AM	30:00	7.10 pH	20.47 °C	729.61 µS/cm	1.10 mg/L	1.44 NTU	-60.4 mV	16.31 ft	150.00 ml/min
10/9/2024 11:54 AM	35:00	7.08 pH	20.52 °C	708.54 µS/cm	1.37 mg/L	1.63 NTU	-55.2 mV	16.31 ft	150.00 ml/min
10/9/2024 11:59 AM	40:00	7.08 pH	20.52 °C	716.06 µS/cm	1.50 mg/L	1.01 NTU	-51.0 mV	16.31 ft	150.00 ml/min
10/9/2024 12:04 PM	45:00	7.07 pH	20.70 °C	721.43 µS/cm	2.43 mg/L	0.85 NTU	-49.9 mV	16.31 ft	150.00 ml/min
10/9/2024 12:09 PM	50:00	7.06 pH	20.69 °C	715.96 µS/cm	3.13 mg/L	0.72 NTU	-45.4 mV	16.31 ft	150.00 ml/min
10/9/2024 12:14 PM	55:00	7.06 pH	20.62 °C	709.34 µS/cm	2.23 mg/L	0.83 NTU	-44.8 mV	16.31 ft	150.00 ml/min
10/9/2024 12:19 PM	01:00:00	7.06 pH	20.47 °C	715.11 µS/cm	2.31 mg/L	0.60 NTU	-45.2 mV	16.31 ft	150.00 ml/min

10/9/2024 12:24 PM	01:05:00	7.06 pH	20.34 °C	709.49 µS/cm	4.13 mg/L	0.44 NTU	-42.9 mV	16.31 ft	150.00 ml/min
10/9/2024 12:29 PM	01:10:00	7.05 pH	20.33 °C	709.06 µS/cm	2.95 mg/L	0.49 NTU	-25.3 mV	16.31 ft	150.00 ml/min
10/9/2024 12:34 PM	01:15:00	7.05 pH	20.39 °C	712.58 µS/cm	2.66 mg/L	0.54 NTU	-40.1 mV	16.31 ft	150.00 ml/min
10/9/2024 12:39 PM	01:20:00	7.05 pH	20.56 °C	710.99 µS/cm	1.82 mg/L	0.50 NTU	-39.5 mV	16.31 ft	150.00 ml/min
10/9/2024 12:44 PM	01:25:00	7.05 pH	20.74 °C	698.13 µS/cm	2.93 mg/L	0.51 NTU	-39.4 mV	16.31 ft	150.00 ml/min
10/9/2024 12:49 PM	01:30:00	7.05 pH	20.71 °C	699.64 µS/cm	1.82 mg/L	0.48 NTU	-38.9 mV	16.31 ft	150.00 ml/min
10/9/2024 12:54 PM	01:35:00	7.04 pH	20.76 °C	702.33 µS/cm	1.11 mg/L	0.40 NTU	-38.0 mV	16.31 ft	150.00 ml/min
10/9/2024 12:59 PM	01:40:00	7.04 pH	20.75 °C	700.31 µS/cm	1.38 mg/L	0.72 NTU	-37.1 mV	16.31 ft	150.00 ml/min
10/9/2024 1:04 PM	01:45:00	7.04 pH	20.71 °C	671.37 µS/cm	1.74 mg/L	0.82 NTU	-37.0 mV	16.31 ft	150.00 ml/min
10/9/2024 1:09 PM	01:50:00	7.03 pH	20.74 °C	699.29 µS/cm	2.05 mg/L	0.93 NTU	-36.0 mV	16.31 ft	150.00 ml/min
10/9/2024 1:14 PM	01:55:00	7.03 pH	20.79 °C	685.35 µS/cm	2.04 mg/L	0.43 NTU	-21.4 mV	16.31 ft	150.00 ml/min
10/9/2024 1:19 PM	02:00:00	7.03 pH	20.87 °C	700.82 µS/cm	1.78 mg/L	0.32 NTU	-35.0 mV	16.31 ft	150.00 ml/min
10/9/2024 1:24 PM	02:05:00	7.03 pH	20.70 °C	709.62 µS/cm	0.29 mg/L	0.36 NTU	-35.8 mV	16.31 ft	150.00 ml/min
10/9/2024 1:29 PM	02:10:00	7.02 pH	20.57 °C	698.96 µS/cm	0.25 mg/L	0.31 NTU	-20.9 mV	16.31 ft	150.00 ml/min
10/9/2024 1:34 PM	02:15:00	7.02 pH	20.43 °C	689.09 µS/cm	0.24 mg/L	0.27 NTU	-20.0 mV	16.31 ft	150.00 ml/min
10/9/2024 1:39 PM	02:20:00	7.01 pH	20.49 °C	679.88 µS/cm	0.24 mg/L	0.24 NTU	-19.4 mV	16.31 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.

Low-Flow Test Report:

Test Date / Time: 10/9/2024 8:42:40 AM
Project: GP-Plant Hammond
Operator Name: Zain W.

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 16.9 ft Total Depth: 26.9 ft Initial Depth to Water: 12.82 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 21.9 ft Estimated Total Volume Pumped: 12.75 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080302
---	---	---

Test Notes:
Appendix III & IV + Major Ions. Ferrous Iron: 0.5 mg/L, Total Iron: 0.5 mg/L.

Weather Conditions:
Clear, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/9/2024 8:42 AM	00:00	6.76 pH	20.06 °C	662.03 µS/cm	0.33 mg/L	4.86 NTU	135.9 mV	12.82 ft	150.00 ml/min
10/9/2024 8:47 AM	05:00	6.76 pH	19.90 °C	672.16 µS/cm	0.27 mg/L	4.74 NTU	74.0 mV	12.82 ft	150.00 ml/min
10/9/2024 8:52 AM	10:00	6.74 pH	19.87 °C	680.99 µS/cm	0.31 mg/L	4.45 NTU	35.9 mV	12.82 ft	150.00 ml/min
10/9/2024 8:57 AM	15:00	6.72 pH	19.85 °C	667.58 µS/cm	0.28 mg/L	5.38 NTU	26.0 mV	12.82 ft	150.00 ml/min
10/9/2024 9:02 AM	20:00	6.70 pH	20.00 °C	672.34 µS/cm	0.26 mg/L	7.62 NTU	22.9 mV	12.82 ft	150.00 ml/min
10/9/2024 9:07 AM	25:00	6.69 pH	19.85 °C	682.97 µS/cm	0.19 mg/L	8.27 NTU	23.3 mV	12.82 ft	150.00 ml/min
10/9/2024 9:12 AM	30:00	6.68 pH	19.98 °C	675.89 µS/cm	0.18 mg/L	8.62 NTU	21.7 mV	12.82 ft	150.00 ml/min
10/9/2024 9:17 AM	35:00	6.67 pH	20.03 °C	669.65 µS/cm	0.20 mg/L	8.09 NTU	20.3 mV	12.82 ft	150.00 ml/min
10/9/2024 9:22 AM	40:00	6.66 pH	20.08 °C	676.07 µS/cm	2.05 mg/L	6.77 NTU	21.6 mV	12.82 ft	150.00 ml/min
10/9/2024 9:27 AM	45:00	6.67 pH	20.08 °C	674.38 µS/cm	1.31 mg/L	3.15 NTU	21.4 mV	12.82 ft	150.00 ml/min
10/9/2024 9:32 AM	50:00	6.66 pH	20.12 °C	664.57 µS/cm	1.13 mg/L	4.22 NTU	19.4 mV	12.82 ft	150.00 ml/min
10/9/2024 9:37 AM	55:00	6.66 pH	20.08 °C	661.60 µS/cm	1.15 mg/L	2.37 NTU	20.0 mV	12.82 ft	150.00 ml/min
10/9/2024 9:42 AM	01:00:00	6.65 pH	20.21 °C	664.43 µS/cm	0.24 mg/L	1.46 NTU	18.8 mV	12.82 ft	150.00 ml/min

10/9/2024 9:47 AM	01:05:00	6.66 pH	20.25 °C	671.17 µS/cm	0.19 mg/L	1.10 NTU	19.8 mV	12.82 ft	150.00 ml/min
10/9/2024 9:52 AM	01:10:00	6.65 pH	20.33 °C	665.32 µS/cm	0.17 mg/L	2.18 NTU	20.7 mV	12.82 ft	150.00 ml/min
10/9/2024 9:57 AM	01:15:00	6.64 pH	20.39 °C	652.56 µS/cm	0.17 mg/L	2.04 NTU	20.2 mV	12.82 ft	150.00 ml/min
10/9/2024 10:02 AM	01:20:00	6.64 pH	20.48 °C	664.68 µS/cm	0.16 mg/L	1.23 NTU	21.8 mV	12.82 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-11	Grab.

Low-Flow Test Report:

Test Date / Time: 10/9/2024 9:20:00 AM
Project: GP-Plant Hammond
Operator Name: Elisabeth R.

Location Name: PT-12 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.3 ft Total Depth: 27.3 ft Initial Depth to Water: 13.85 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22.3 ft Estimated Total Volume Pumped: 15.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 968202
---	--	--

Test Notes:
Appendix III & IV + Major Ions. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/9/2024 9:20 AM	00:00	6.86 pH	21.88 °C	617.87 µS/cm	0.17 mg/L	22.20 NTU	145.5 mV	13.85 ft	200.00 ml/min
10/9/2024 9:25 AM	05:00	6.88 pH	20.96 °C	695.52 µS/cm	0.16 mg/L	16.40 NTU	144.5 mV	13.85 ft	200.00 ml/min
10/9/2024 9:30 AM	10:00	6.87 pH	20.68 °C	684.40 µS/cm	0.13 mg/L	10.80 NTU	108.9 mV	13.85 ft	200.00 ml/min
10/9/2024 9:35 AM	15:00	6.85 pH	20.38 °C	686.47 µS/cm	0.13 mg/L	12.10 NTU	98.9 mV	13.85 ft	200.00 ml/min
10/9/2024 9:40 AM	20:00	6.86 pH	20.11 °C	696.91 µS/cm	0.10 mg/L	13.30 NTU	92.6 mV	13.85 ft	200.00 ml/min
10/9/2024 9:45 AM	25:00	6.83 pH	20.12 °C	696.13 µS/cm	0.09 mg/L	12.40 NTU	109.8 mV	13.85 ft	200.00 ml/min
10/9/2024 9:50 AM	30:00	6.82 pH	20.08 °C	672.72 µS/cm	0.08 mg/L	14.40 NTU	89.0 mV	13.85 ft	200.00 ml/min
10/9/2024 9:55 AM	35:00	6.82 pH	20.08 °C	688.98 µS/cm	0.06 mg/L	12.10 NTU	83.9 mV	13.85 ft	200.00 ml/min
10/9/2024 10:00 AM	40:00	6.81 pH	20.22 °C	690.82 µS/cm	0.06 mg/L	10.30 NTU	81.8 mV	13.85 ft	200.00 ml/min
10/9/2024 10:05 AM	45:00	6.80 pH	20.43 °C	689.05 µS/cm	0.07 mg/L	8.70 NTU	80.9 mV	13.85 ft	200.00 ml/min
10/9/2024 10:10 AM	50:00	6.80 pH	20.47 °C	687.27 µS/cm	0.05 mg/L	7.19 NTU	82.0 mV	13.85 ft	200.00 ml/min
10/9/2024 10:15 AM	55:00	6.79 pH	20.59 °C	685.78 µS/cm	0.07 mg/L	6.00 NTU	84.7 mV	13.85 ft	200.00 ml/min
10/9/2024 10:20 AM	01:00:00	6.79 pH	20.65 °C	694.08 µS/cm	0.09 mg/L	5.65 NTU	88.2 mV	13.85 ft	200.00 ml/min
10/9/2024 10:25 AM	01:05:00	6.79 pH	20.81 °C	691.29 µS/cm	0.07 mg/L	4.65 NTU	92.8 mV	13.85 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-12	Grab.

Low-Flow Test Report:

Test Date / Time: 10/8/2024 10:45:45 AM
Project: GP-Plant Hammond
Operator Name: Zain W.

Location Name: PT-13 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.45 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 20.25 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: -0.09 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080302
--	--	---

Test Notes:
Appendix III & IV + Major Ions. Ferrous Iron: 5.0 mg/L, Total Iron: 9.2 mg/L.

Weather Conditions:
Clear, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/8/2024 10:45 AM	00:00	6.65 pH	20.26 °C	739.61 µS/cm	1.14 mg/L	183.00 NTU	-30.1 mV	25.45 ft	150.00 ml/min
10/8/2024 10:50 AM	05:00	6.66 pH	20.19 °C	729.76 µS/cm	0.85 mg/L	203.00 NTU	-42.2 mV	25.34 ft	150.00 ml/min
10/8/2024 10:55 AM	10:00	6.66 pH	20.14 °C	730.44 µS/cm	0.62 mg/L	148.00 NTU	-28.7 mV	25.34 ft	150.00 ml/min
10/8/2024 11:00 AM	15:00	6.66 pH	20.12 °C	728.40 µS/cm	0.51 mg/L	79.50 NTU	-29.6 mV	25.35 ft	150.00 ml/min
10/8/2024 11:05 AM	20:00	6.66 pH	20.12 °C	725.88 µS/cm	0.45 mg/L	60.70 NTU	-30.7 mV	25.36 ft	150.00 ml/min
10/8/2024 11:10 AM	25:00	6.66 pH	20.12 °C	731.22 µS/cm	0.39 mg/L	48.90 NTU	-31.5 mV	25.36 ft	150.00 ml/min
10/8/2024 11:15 AM	30:00	6.66 pH	20.08 °C	737.12 µS/cm	0.34 mg/L	39.00 NTU	-33.4 mV	25.36 ft	150.00 ml/min
10/8/2024 11:20 AM	35:00	6.66 pH	20.08 °C	733.88 µS/cm	0.33 mg/L	29.90 NTU	-32.9 mV	25.36 ft	150.00 ml/min
10/8/2024 11:25 AM	40:00	6.66 pH	20.09 °C	731.37 µS/cm	0.28 mg/L	21.70 NTU	-31.8 mV	25.36 ft	150.00 ml/min
10/8/2024 11:30 AM	45:00	6.65 pH	20.12 °C	729.19 µS/cm	0.26 mg/L	18.00 NTU	-32.3 mV	25.36 ft	150.00 ml/min
10/8/2024 11:35 AM	50:00	6.66 pH	20.09 °C	720.87 µS/cm	0.24 mg/L	16.50 NTU	-31.8 mV	25.36 ft	150.00 ml/min
10/8/2024 11:40 AM	55:00	6.66 pH	20.08 °C	724.33 µS/cm	0.23 mg/L	14.80 NTU	-32.4 mV	25.36 ft	150.00 ml/min
10/8/2024 11:45 AM	01:00:00	6.65 pH	20.08 °C	720.68 µS/cm	0.21 mg/L	13.20 NTU	-31.8 mV	25.36 ft	150.00 ml/min

10/8/2024 11:50 AM	01:05:00	6.65 pH	20.07 °C	718.91 µS/cm	0.20 mg/L	11.90 NTU	-31.5 mV	25.36 ft	150.00 ml/min
10/8/2024 11:55 AM	01:10:00	6.65 pH	20.12 °C	715.70 µS/cm	0.20 mg/L	11.30 NTU	-31.0 mV	25.36 ft	150.00 ml/min
10/8/2024 12:00 PM	01:15:00	6.65 pH	20.07 °C	714.35 µS/cm	0.19 mg/L	9.08 NTU	-30.8 mV	25.36 ft	150.00 ml/min
10/8/2024 12:05 PM	01:20:00	6.65 pH	20.11 °C	710.63 µS/cm	0.19 mg/L	8.43 NTU	-30.9 mV	25.36 ft	150.00 ml/min
10/8/2024 12:10 PM	01:25:00	6.65 pH	20.14 °C	707.51 µS/cm	0.18 mg/L	7.31 NTU	-30.3 mV	25.36 ft	150.00 ml/min
10/8/2024 12:15 PM	01:30:00	6.65 pH	20.15 °C	707.18 µS/cm	0.18 mg/L	7.40 NTU	-30.1 mV	25.36 ft	150.00 ml/min
10/8/2024 12:20 PM	01:35:00	6.66 pH	20.15 °C	701.85 µS/cm	0.17 mg/L	6.61 NTU	-30.4 mV	25.36 ft	150.00 ml/min
10/8/2024 12:25 PM	01:40:00	6.65 pH	20.15 °C	698.33 µS/cm	0.17 mg/L	6.23 NTU	-30.4 mV	25.36 ft	150.00 ml/min
10/8/2024 12:30 PM	01:45:00	6.65 pH	20.20 °C	694.60 µS/cm	0.17 mg/L	5.90 NTU	-29.5 mV	25.36 ft	150.00 ml/min
10/8/2024 12:35 PM	01:50:00	6.65 pH	20.19 °C	692.54 µS/cm	0.16 mg/L	6.18 NTU	-29.7 mV	25.36 ft	150.00 ml/min
10/8/2024 12:40 PM	01:55:00	6.65 pH	20.20 °C	689.98 µS/cm	0.16 mg/L	5.62 NTU	-43.9 mV	25.36 ft	150.00 ml/min
10/8/2024 12:45 PM	02:00:00	6.65 pH	20.20 °C	688.13 µS/cm	0.16 mg/L	5.44 NTU	-29.2 mV	25.36 ft	150.00 ml/min
10/8/2024 12:50 PM	02:05:00	6.65 pH	20.21 °C	693.81 µS/cm	0.16 mg/L	5.18 NTU	-29.6 mV	25.36 ft	150.00 ml/min
10/8/2024 12:55 PM	02:10:00	6.65 pH	20.24 °C	691.25 µS/cm	0.15 mg/L	4.83 NTU	-29.4 mV	25.36 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-13	Grab.

Low-Flow Test Report:

Test Date / Time: 10/8/2024 2:32:10 PM
Project: GP-Plant Hammond
Operator Name: Elisabeth R.

Location Name: PT-14 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.4 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 11 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 968202
--	---	--

Test Notes:
Appendix III & IV + Major Ions. Ferrous Iron: 2.0 mg/L, Total Iron: 9.0 mg/L.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/8/2024 2:32 PM	00:00	6.84 pH	21.79 °C	786.91 µS/cm	1.06 mg/L	70.80 NTU	-115.2 mV	25.40 ft	200.00 ml/min
10/8/2024 2:37 PM	05:00	6.85 pH	21.59 °C	788.61 µS/cm	0.77 mg/L	53.90 NTU	-114.3 mV	25.40 ft	200.00 ml/min
10/8/2024 2:42 PM	10:00	6.86 pH	21.40 °C	789.19 µS/cm	0.65 mg/L	37.60 NTU	-123.5 mV	25.42 ft	200.00 ml/min
10/8/2024 2:47 PM	15:00	6.86 pH	21.22 °C	788.23 µS/cm	0.59 mg/L	24.50 NTU	-115.1 mV	25.43 ft	200.00 ml/min
10/8/2024 2:52 PM	20:00	6.87 pH	21.10 °C	792.46 µS/cm	0.41 mg/L	19.70 NTU	-115.9 mV	25.43 ft	200.00 ml/min
10/8/2024 2:57 PM	25:00	6.87 pH	21.10 °C	794.42 µS/cm	0.36 mg/L	14.60 NTU	-116.4 mV	25.43 ft	200.00 ml/min
10/8/2024 3:02 PM	30:00	6.87 pH	20.99 °C	793.88 µS/cm	0.29 mg/L	13.10 NTU	-116.9 mV	25.43 ft	200.00 ml/min
10/8/2024 3:07 PM	35:00	6.87 pH	20.92 °C	794.06 µS/cm	0.25 mg/L	11.70 NTU	-116.8 mV	25.43 ft	200.00 ml/min
10/8/2024 3:12 PM	40:00	6.87 pH	20.96 °C	792.83 µS/cm	0.22 mg/L	10.00 NTU	-117.4 mV	25.43 ft	200.00 ml/min
10/8/2024 3:17 PM	45:00	6.87 pH	20.85 °C	793.65 µS/cm	0.21 mg/L	8.00 NTU	-117.1 mV	25.43 ft	200.00 ml/min
10/8/2024 3:22 PM	50:00	6.87 pH	20.83 °C	793.03 µS/cm	0.19 mg/L	4.20 NTU	-125.1 mV	25.43 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-14	Grab.

Low-Flow Test Report:

Test Date / Time: 10/8/2024 4:09:48 PM
Project: GP-Plant Hammond
Operator Name: Zain W.

Location Name: PT-15 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.37 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 8.25 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: -0.17 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080302
---	--	---

Test Notes:
Appendix III & IV + Major Ions. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Weather Conditions:
Clear, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/8/2024 4:09 PM	00:00	6.76 pH	27.28 °C	650.15 µS/cm	3.88 mg/L	151.00 NTU	6.0 mV	25.37 ft	150.00 ml/min
10/8/2024 4:14 PM	05:00	6.73 pH	21.09 °C	682.96 µS/cm	2.40 mg/L	77.80 NTU	8.7 mV	25.18 ft	150.00 ml/min
10/8/2024 4:19 PM	10:00	6.73 pH	20.69 °C	683.14 µS/cm	1.98 mg/L	65.30 NTU	5.3 mV	25.20 ft	150.00 ml/min
10/8/2024 4:24 PM	15:00	6.73 pH	20.61 °C	681.47 µS/cm	1.71 mg/L	53.60 NTU	9.9 mV	25.20 ft	150.00 ml/min
10/8/2024 4:29 PM	20:00	6.73 pH	20.52 °C	681.63 µS/cm	1.48 mg/L	20.20 NTU	6.2 mV	25.20 ft	150.00 ml/min
10/8/2024 4:34 PM	25:00	6.72 pH	20.54 °C	679.00 µS/cm	1.33 mg/L	12.90 NTU	11.0 mV	25.20 ft	150.00 ml/min
10/8/2024 4:39 PM	30:00	6.72 pH	20.52 °C	681.95 µS/cm	1.22 mg/L	7.36 NTU	11.9 mV	25.20 ft	150.00 ml/min
10/8/2024 4:44 PM	35:00	6.72 pH	20.51 °C	678.89 µS/cm	1.13 mg/L	6.83 NTU	12.9 mV	25.20 ft	150.00 ml/min
10/8/2024 4:49 PM	40:00	6.72 pH	20.49 °C	678.97 µS/cm	1.03 mg/L	5.22 NTU	13.3 mV	25.20 ft	150.00 ml/min
10/8/2024 4:54 PM	45:00	6.72 pH	20.47 °C	676.55 µS/cm	0.95 mg/L	4.74 NTU	13.5 mV	25.20 ft	150.00 ml/min
10/8/2024 4:59 PM	50:00	6.72 pH	20.43 °C	674.38 µS/cm	0.91 mg/L	3.69 NTU	13.2 mV	25.20 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-15	Grab.
HAM-AP1-FD-01	Grab.

Low-Flow Test Report:

Test Date / Time: 10/16/2024 1:13:10 PM
Project: GP-Plant Hammond
Operator Name: Jamie Newsome

Location Name: INW-03 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.4 ft Total Depth: 27.4 ft Initial Depth to Water: 13.37 ft	Pump Type: Peristaltic Tubing Type: Poly Pump Intake From TOC: 25.47 ft Estimated Total Volume Pumped: 2000 ml Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 843285
--	--	--

Test Notes:
No samples, field parameters only.

Weather Conditions:
Sunny, 65 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/16/2024 1:13 PM	00:00	6.05 pH	20.87 °C	716.81 µS/cm	0.22 mg/L	24.20 NTU	-6.0 mV	13.37 ft	200.00 ml/min
10/16/2024 1:18 PM	05:00	6.09 pH	20.55 °C	715.49 µS/cm	0.11 mg/L	19.90 NTU	-9.5 mV	13.37 ft	200.00 ml/min
10/16/2024 1:23 PM	10:00	6.05 pH	20.15 °C	722.72 µS/cm	0.07 mg/L	21.20 NTU	-9.0 mV	13.37 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 10/15/2024 3:05:38 PM
Project: GP-Plant Hammond
Operator Name: Jamie Newsome

Location Name: INW-04 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.45 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 2000 ml Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 843285
--	---	--

Test Notes:
No sample, field parameters only.

Weather Conditions:
Cloudy, 65 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/15/2024 3:05 PM	00:00	6.70 pH	20.65 °C	729.74 µS/cm	0.61 mg/L	++++	-66.0 mV	25.45 ft	200.00 ml/min
10/15/2024 3:10 PM	05:00	6.68 pH	20.02 °C	731.62 µS/cm	1.17 mg/L	++++	-65.2 mV	25.45 ft	200.00 ml/min
10/15/2024 3:15 PM	10:00	6.68 pH	19.95 °C	728.50 µS/cm	1.34 mg/L	++++	-71.1 mV	25.45 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 10/15/2024 3:30:20 PM
Project: GP-Plant Hammond
Operator Name: Jamie Newsome

Location Name: INW-05 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.94 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 2000 ml Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 843285
--	---	--

Test Notes:
No samples, field parameters only.

Weather Conditions:
Cloudy, 65 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/15/2024 3:30 PM	00:00	6.16 pH	20.20 °C	561.56 µS/cm	1.41 mg/L		42.1 mV	25.94 ft	200.00 ml/min
10/15/2024 3:35 PM	05:00	6.24 pH	20.05 °C	607.26 µS/cm	1.66 mg/L		22.8 mV	25.94 ft	200.00 ml/min
10/15/2024 3:40 PM	10:00	6.29 pH	19.93 °C	628.69 µS/cm	1.38 mg/L		13.1 mV	25.94 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 10/15/2024 1:50:47 PM
Project: GP-Plant Hammond
Operator Name: Jamie Newsome

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 37.6 ft Total Depth: 47.6 ft Initial Depth to Water: 26.16 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 6476.667 ml Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 843285
---	---	--

Test Notes:
Metals. Fe = 1.0 mg/L Fe2+ = 0.5 mg/L

Weather Conditions:
Cloudy, 65 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/15/2024 1:50 PM	00:00	6.74 pH	20.11 °C	748.88 µS/cm	0.52 mg/L	13.30 NTU	-53.1 mV	26.16 ft	200.00 ml/min
10/15/2024 1:55 PM	05:00	6.74 pH	19.79 °C	752.32 µS/cm	0.27 mg/L	3.39 NTU	-57.7 mV	26.16 ft	200.00 ml/min
10/15/2024 2:00 PM	10:00	6.75 pH	19.63 °C	749.58 µS/cm	0.25 mg/L	3.16 NTU	-54.4 mV	26.16 ft	200.00 ml/min
10/15/2024 2:05 PM	15:00	6.75 pH	19.62 °C	749.03 µS/cm	0.15 mg/L	2.03 NTU	-54.3 mV	26.16 ft	200.00 ml/min
10/15/2024 2:10 PM	20:00	6.75 pH	19.58 °C	748.34 µS/cm	0.11 mg/L	0.92 NTU	-53.4 mV	26.16 ft	200.00 ml/min
10/15/2024 2:15 PM	25:00	6.75 pH	19.53 °C	748.01 µS/cm	0.15 mg/L	1.45 NTU	-59.1 mV	26.16 ft	200.00 ml/min
10/15/2024 2:20 PM	30:00	6.75 pH	19.49 °C	747.98 µS/cm	0.09 mg/L	1.12 NTU	-59.5 mV	26.16 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 10/15/2024 12:15:31 PM
Project: GP-Plant Hammond
Operator Name: Amanda Tomlinson

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 32.2 ft Total Depth: 42.2 ft Initial Depth to Water: 25.98 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 42.6 ft Estimated Total Volume Pumped: 24000 ml Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.04 ft	Instrument Used: Aqua TROLL 400 Serial Number: 843593
---	---	--

Test Notes:
Metals. Total Fe: 2.5 mg/L. Fe2+: 2.0 mg/L.

Weather Conditions:
Partly cloudy, 59 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/15/2024 12:15 PM	00:00	6.74 pH	20.21 °C	662.24 µS/cm	0.92 mg/L	1,694.0 NTU	4.9 mV	26.01 ft	200.00 ml/min
10/15/2024 12:20 PM	05:00	6.68 pH	20.36 °C	668.30 µS/cm	0.83 mg/L	1,165.0 NTU	16.7 mV	26.01 ft	200.00 ml/min
10/15/2024 12:25 PM	10:00	6.68 pH	19.95 °C	659.01 µS/cm	0.80 mg/L	733.00 NTU	27.7 mV	26.01 ft	200.00 ml/min
10/15/2024 12:30 PM	15:00	6.69 pH	19.81 °C	665.83 µS/cm	0.66 mg/L	113.00 NTU	27.6 mV	26.01 ft	200.00 ml/min
10/15/2024 12:35 PM	20:00	6.69 pH	19.77 °C	675.02 µS/cm	0.50 mg/L	87.37 NTU	28.0 mV	26.02 ft	200.00 ml/min
10/15/2024 12:40 PM	25:00	6.69 pH	20.04 °C	681.94 µS/cm	0.41 mg/L	65.96 NTU	22.5 mV	26.02 ft	200.00 ml/min
10/15/2024 12:45 PM	30:00	6.72 pH	20.23 °C	682.16 µS/cm	0.38 mg/L	51.32 NTU	20.1 mV	26.02 ft	200.00 ml/min
10/15/2024 12:50 PM	35:00	6.72 pH	20.10 °C	682.00 µS/cm	0.36 mg/L	41.43 NTU	21.2 mV	26.02 ft	200.00 ml/min
10/15/2024 12:55 PM	40:00	6.72 pH	20.22 °C	688.29 µS/cm	0.40 mg/L	32.86 NTU	20.3 mV	26.02 ft	200.00 ml/min
10/15/2024 1:00 PM	45:00	6.72 pH	20.22 °C	690.13 µS/cm	0.36 mg/L	26.81 NTU	20.6 mV	26.02 ft	200.00 ml/min
10/15/2024 1:05 PM	50:00	6.74 pH	19.75 °C	688.15 µS/cm	0.33 mg/L	19.78 NTU	20.4 mV	26.02 ft	200.00 ml/min
10/15/2024 1:10 PM	55:00	6.75 pH	19.90 °C	692.50 µS/cm	0.30 mg/L	17.81 NTU	18.3 mV	26.02 ft	200.00 ml/min
10/15/2024 1:15 PM	01:00:00	6.76 pH	19.82 °C	691.94 µS/cm	0.29 mg/L	14.79 NTU	15.4 mV	26.02 ft	200.00 ml/min
10/15/2024 1:20 PM	01:05:00	6.75 pH	20.11 °C	698.73 µS/cm	0.27 mg/L	12.90 NTU	8.4 mV	26.02 ft	200.00 ml/min

10/15/2024 1:25 PM	01:10:00	6.78 pH	20.13 °C	696.67 µS/cm	0.30 mg/L	11.35 NTU	9.7 mV	26.02 ft	200.00 ml/min
10/15/2024 1:30 PM	01:15:00	6.79 pH	20.13 °C	700.01 µS/cm	0.28 mg/L	9.63 NTU	5.2 mV	26.02 ft	200.00 ml/min
10/15/2024 1:35 PM	01:20:00	6.80 pH	20.13 °C	699.73 µS/cm	0.29 mg/L	8.64 NTU	5.0 mV	26.02 ft	200.00 ml/min
10/15/2024 1:40 PM	01:25:00	6.80 pH	20.04 °C	699.71 µS/cm	0.29 mg/L	8.42 NTU	5.7 mV	26.02 ft	200.00 ml/min
10/15/2024 1:45 PM	01:30:00	6.82 pH	19.77 °C	700.29 µS/cm	0.29 mg/L	7.38 NTU	3.6 mV	26.02 ft	200.00 ml/min
10/15/2024 1:50 PM	01:35:00	6.83 pH	19.73 °C	700.81 µS/cm	0.29 mg/L	7.56 NTU	0.3 mV	26.02 ft	200.00 ml/min
10/15/2024 1:55 PM	01:40:00	6.83 pH	19.59 °C	699.94 µS/cm	0.28 mg/L	6.20 NTU	-2.9 mV	26.02 ft	200.00 ml/min
10/15/2024 2:00 PM	01:45:00	6.83 pH	19.58 °C	700.68 µS/cm	0.28 mg/L	6.42 NTU	-7.8 mV	26.02 ft	200.00 ml/min
10/15/2024 2:05 PM	01:50:00	6.85 pH	19.64 °C	703.47 µS/cm	0.28 mg/L	5.70 NTU	-10.4 mV	26.02 ft	200.00 ml/min
10/15/2024 2:10 PM	01:55:00	6.85 pH	19.47 °C	703.51 µS/cm	0.28 mg/L	5.37 NTU	-13.8 mV	26.02 ft	200.00 ml/min
10/15/2024 2:15 PM	02:00:00	6.84 pH	19.46 °C	702.16 µS/cm	0.29 mg/L	4.95 NTU	-15.5 mV	26.02 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.

Low-Flow Test Report:

Test Date / Time: 10/16/2024 11:20:36 AM
Project: GP-Plant Hammond
Operator Name: Jamie Newsome

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.47 ft Total Depth: 30.47 ft Initial Depth to Water: 16.65 ft	Pump Type: Peristaltic Tubing Type: Poly Pump Intake From TOC: 25.47 ft Estimated Total Volume Pumped: 13000 ml Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 843285
---	--	--

Test Notes:
Metals. Fe = 0 mg/L Fe2+ = 0 mg/L.

Weather Conditions:
Sunny, 65 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/16/2024 11:20 AM	00:00	6.68 pH	19.40 °C	771.21 µS/cm	0.28 mg/L	59.50 NTU	52.4 mV	16.65 ft	200.00 ml/min
10/16/2024 11:25 AM	05:00	6.72 pH	18.79 °C	768.91 µS/cm	0.17 mg/L	51.60 NTU	54.3 mV	16.65 ft	200.00 ml/min
10/16/2024 11:30 AM	10:00	6.74 pH	18.62 °C	761.50 µS/cm	0.09 mg/L	41.70 NTU	46.5 mV	16.65 ft	200.00 ml/min
10/16/2024 11:35 AM	15:00	6.75 pH	18.72 °C	764.96 µS/cm	0.07 mg/L	35.90 NTU	45.2 mV	16.70 ft	200.00 ml/min
10/16/2024 11:40 AM	20:00	6.78 pH	18.64 °C	762.76 µS/cm	0.06 mg/L	36.60 NTU	44.6 mV	16.70 ft	200.00 ml/min
10/16/2024 11:45 AM	25:00	6.78 pH	18.86 °C	758.23 µS/cm	0.05 mg/L	31.10 NTU	44.1 mV	16.70 ft	200.00 ml/min
10/16/2024 11:50 AM	30:00	6.78 pH	18.89 °C	756.87 µS/cm	0.05 mg/L	24.40 NTU	43.2 mV	16.70 ft	200.00 ml/min
10/16/2024 11:55 AM	35:00	6.79 pH	18.77 °C	748.27 µS/cm	0.05 mg/L	21.20 NTU	42.9 mV	16.70 ft	200.00 ml/min
10/16/2024 12:00 PM	40:00	6.78 pH	18.95 °C	762.03 µS/cm	0.05 mg/L	16.10 NTU	42.1 mV	16.70 ft	200.00 ml/min
10/16/2024 12:05 PM	45:00	6.79 pH	19.09 °C	756.65 µS/cm	0.04 mg/L	15.60 NTU	41.5 mV	16.70 ft	200.00 ml/min
10/16/2024 12:10 PM	50:00	6.79 pH	18.89 °C	760.92 µS/cm	0.04 mg/L	11.50 NTU	41.3 mV	16.70 ft	200.00 ml/min
10/16/2024 12:15 PM	55:00	6.79 pH	18.87 °C	760.98 µS/cm	0.04 mg/L	7.81 NTU	40.8 mV	16.70 ft	200.00 ml/min
10/16/2024 12:20 PM	01:00:00	6.78 pH	18.77 °C	760.86 µS/cm	0.04 mg/L	5.79 NTU	40.6 mV	16.70 ft	200.00 ml/min

10/16/2024 12:25 PM	01:05:00	6.79 pH	19.06 °C	759.06 µS/cm	0.04 mg/L	4.92 NTU	39.2 mV	16.70 ft	200.00 ml/min
------------------------	----------	---------	----------	--------------	-----------	----------	---------	----------	---------------

Samples

Sample ID:	Description:
HAM-PT-09	Grab.

Low-Flow Test Report:

Test Date / Time: 10/16/2024 9:40:15 AM
Project: GP-Plant Hammond
Operator Name: Amanda Tomlinson

Location Name: PT-10 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.45 ft Total Depth: 30.45 ft Initial Depth to Water: 16.75 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 25.45 ft Estimated Total Volume Pumped: 11233.333 ml Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 843593
---	--	--

Test Notes:
Metals. Total Fe: 0.5 mg/L. Fe2+: 0.25 mg/L.

Weather Conditions:
Clear, 42 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/16/2024 9:40 AM	00:00	7.38 pH	17.29 °C	723.06 µS/cm	0.44 mg/L	62.53 NTU	1.5 mV	16.77 ft	200.00 ml/min
10/16/2024 9:45 AM	05:00	7.33 pH	17.67 °C	716.50 µS/cm	0.49 mg/L	57.43 NTU	-28.4 mV	16.77 ft	200.00 ml/min
10/16/2024 9:46 AM	06:10	7.35 pH	17.73 °C	716.21 µS/cm	0.37 mg/L		-27.4 mV	16.77 ft	200.00 ml/min
10/16/2024 9:51 AM	11:10	7.41 pH	17.57 °C	718.59 µS/cm	0.28 mg/L	40.69 NTU	-53.4 mV	16.77 ft	200.00 ml/min
10/16/2024 9:56 AM	16:10	7.51 pH	17.63 °C	727.17 µS/cm	0.22 mg/L	31.32 NTU	-66.2 mV	16.77 ft	200.00 ml/min
10/16/2024 10:01 AM	21:10	7.62 pH	17.79 °C	725.67 µS/cm	0.17 mg/L	21.31 NTU	-79.3 mV	16.77 ft	200.00 ml/min
10/16/2024 10:06 AM	26:10	7.74 pH	17.72 °C	722.91 µS/cm	0.16 mg/L	15.82 NTU	-83.0 mV	16.77 ft	200.00 ml/min
10/16/2024 10:11 AM	31:10	7.83 pH	17.54 °C	717.76 µS/cm	0.15 mg/L	14.42 NTU	-80.3 mV	16.77 ft	200.00 ml/min
10/16/2024 10:16 AM	36:10	7.93 pH	17.73 °C	716.30 µS/cm	0.14 mg/L	12.52 NTU	-96.2 mV	16.77 ft	200.00 ml/min
10/16/2024 10:21 AM	41:10	8.00 pH	17.86 °C	716.91 µS/cm	0.17 mg/L	8.92 NTU	-99.2 mV	16.77 ft	200.00 ml/min
10/16/2024 10:26 AM	46:10	8.07 pH	17.89 °C	708.92 µS/cm	0.13 mg/L	6.66 NTU	-104.3 mV	16.77 ft	200.00 ml/min
10/16/2024 10:31 AM	51:10	8.12 pH	17.90 °C	707.43 µS/cm	0.13 mg/L	6.70 NTU	-88.6 mV	16.77 ft	200.00 ml/min
10/16/2024 10:36 AM	56:10	8.15 pH	17.85 °C	708.42 µS/cm	0.12 mg/L	4.53 NTU	-103.7 mV	16.77 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.

Low-Flow Test Report:

Test Date / Time: 10/16/2024 9:40:05 AM
Project: GP-Plant Hammond
Operator Name: Jamie Newsome

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 16.9 ft Total Depth: 26.9 ft Initial Depth to Water: 12.3 ft	Pump Type: Peristaltic Tubing Type: Poly Pump Intake From TOC: 21.9 ft Estimated Total Volume Pumped: 11000 ml Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 843285
--	--	--

Test Notes:
Metals. Fe = 1.0 mg/L Fe2+ = 0.5 mg/L

Weather Conditions:
Sunny, 40 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/16/2024 9:40 AM	00:00	6.47 pH	18.32 °C	723.65 µS/cm	0.19 mg/L	91.50 NTU	67.7 mV	12.30 ft	200.00 ml/min
10/16/2024 9:45 AM	05:00	6.46 pH	18.37 °C	725.27 µS/cm	0.14 mg/L	69.30 NTU	56.4 mV	12.30 ft	200.00 ml/min
10/16/2024 9:50 AM	10:00	6.49 pH	18.34 °C	722.63 µS/cm	0.12 mg/L	53.90 NTU	44.7 mV	12.30 ft	200.00 ml/min
10/16/2024 9:55 AM	15:00	6.49 pH	18.42 °C	722.01 µS/cm	0.11 mg/L	51.10 NTU	41.1 mV	12.30 ft	200.00 ml/min
10/16/2024 10:00 AM	20:00	6.50 pH	18.55 °C	723.17 µS/cm	0.10 mg/L	32.10 NTU	36.2 mV	12.30 ft	200.00 ml/min
10/16/2024 10:05 AM	25:00	6.52 pH	18.54 °C	727.59 µS/cm	0.09 mg/L	27.20 NTU	34.1 mV	12.30 ft	200.00 ml/min
10/16/2024 10:10 AM	30:00	6.52 pH	18.69 °C	729.42 µS/cm	0.11 mg/L	21.00 NTU	30.5 mV	12.30 ft	200.00 ml/min
10/16/2024 10:15 AM	35:00	6.54 pH	18.85 °C	729.41 µS/cm	0.10 mg/L	17.70 NTU	29.1 mV	12.30 ft	200.00 ml/min
10/16/2024 10:20 AM	40:00	6.55 pH	18.95 °C	731.36 µS/cm	0.10 mg/L	13.50 NTU	25.9 mV	12.30 ft	200.00 ml/min
10/16/2024 10:25 AM	45:00	6.57 pH	18.89 °C	726.06 µS/cm	0.11 mg/L	8.60 NTU	24.7 mV	12.30 ft	200.00 ml/min
10/16/2024 10:30 AM	50:00	6.56 pH	18.96 °C	736.54 µS/cm	0.07 mg/L	6.20 NTU	22.5 mV	12.30 ft	200.00 ml/min
10/16/2024 10:35 AM	55:00	6.57 pH	18.96 °C	735.60 µS/cm	0.08 mg/L	4.84 NTU	21.1 mV	12.30 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-11	Grab.
HAM-AP1-FD-01	Grab.

Low-Flow Test Report:

Test Date / Time: 10/16/2024 11:15:48 AM
Project: GP-Plant Hammond
Operator Name: Amanda Tomlinson

Location Name: PT-12 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.3 ft Total Depth: 27.3 ft Initial Depth to Water: 13.14 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22 ft Estimated Total Volume Pumped: 36000 ml Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 843593
---	--	--

Test Notes:
Metals. Total Fe and Fe2+: 0 mg/L.

Weather Conditions:
Clear, 52 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/16/2024 11:15 AM	00:00	8.51 pH	19.61 °C	699.88 µS/cm	0.13 mg/L	1,098.0 NTU	5.6 mV	13.14 ft	200.00 ml/min
10/16/2024 11:20 AM	05:00	8.67 pH	19.31 °C	710.37 µS/cm	0.20 mg/L	998.00 NTU	15.1 mV	13.14 ft	200.00 ml/min
10/16/2024 11:25 AM	10:00	8.73 pH	18.64 °C	715.19 µS/cm	0.16 mg/L	764.00 NTU	26.5 mV	13.14 ft	200.00 ml/min
10/16/2024 11:30 AM	15:00	8.82 pH	18.43 °C	713.78 µS/cm	0.14 mg/L	769.00 NTU	27.1 mV	13.14 ft	200.00 ml/min
10/16/2024 11:35 AM	20:00	8.96 pH	18.65 °C	715.07 µS/cm	0.10 mg/L	618.00 NTU	22.0 mV	13.14 ft	200.00 ml/min
10/16/2024 11:40 AM	25:00	9.07 pH	18.64 °C	715.51 µS/cm	0.10 mg/L	132.00 NTU	21.5 mV	13.14 ft	200.00 ml/min
10/16/2024 11:45 AM	30:00	9.20 pH	18.75 °C	713.47 µS/cm	0.07 mg/L	168.00 NTU	19.0 mV	13.14 ft	200.00 ml/min
10/16/2024 11:50 AM	35:00	9.24 pH	18.75 °C	716.17 µS/cm	0.06 mg/L	113.00 NTU	13.6 mV	13.14 ft	200.00 ml/min
10/16/2024 11:55 AM	40:00	9.29 pH	18.71 °C	714.56 µS/cm	0.06 mg/L	62.00 NTU	7.9 mV	13.14 ft	200.00 ml/min
10/16/2024 12:00 PM	45:00	9.33 pH	18.76 °C	714.41 µS/cm	0.06 mg/L	50.00 NTU	8.9 mV	13.14 ft	200.00 ml/min
10/16/2024 12:05 PM	50:00	9.35 pH	18.76 °C	715.22 µS/cm	0.04 mg/L	92.54 NTU	0.0 mV	13.14 ft	200.00 ml/min
10/16/2024 12:10 PM	55:00	9.38 pH	18.69 °C	715.18 µS/cm	0.06 mg/L	86.83 NTU	-3.0 mV	13.14 ft	200.00 ml/min
10/16/2024 12:15 PM	01:00:00	9.39 pH	18.53 °C	714.75 µS/cm	0.04 mg/L	67.57 NTU	-3.8 mV	13.14 ft	200.00 ml/min

10/16/2024 12:20 PM	01:05:00	9.40 pH	18.48 °C	716.66 µS/cm	0.04 mg/L	53.02 NTU	-4.0 mV	13.14 ft	200.00 ml/min
10/16/2024 12:25 PM	01:10:00	9.41 pH	18.73 °C	713.70 µS/cm	0.05 mg/L	54.05 NTU	-4.0 mV	13.14 ft	200.00 ml/min
10/16/2024 12:30 PM	01:15:00	9.42 pH	18.79 °C	716.39 µS/cm	0.06 mg/L	31.56 NTU	-4.8 mV	13.14 ft	200.00 ml/min
10/16/2024 12:35 PM	01:20:00	9.43 pH	18.84 °C	714.65 µS/cm	0.06 mg/L	25.92 NTU	3.3 mV	13.14 ft	200.00 ml/min
10/16/2024 12:40 PM	01:25:00	9.45 pH	18.79 °C	714.56 µS/cm	0.05 mg/L	22.55 NTU	3.9 mV	13.14 ft	200.00 ml/min
10/16/2024 12:45 PM	01:30:00	9.45 pH	18.80 °C	716.63 µS/cm	0.05 mg/L	17.76 NTU	-2.8 mV	13.14 ft	200.00 ml/min
10/16/2024 12:50 PM	01:35:00	9.46 pH	18.91 °C	711.33 µS/cm	0.05 mg/L	11.95 NTU	3.7 mV	13.14 ft	200.00 ml/min
10/16/2024 12:55 PM	01:40:00	9.48 pH	19.02 °C	718.69 µS/cm	0.05 mg/L	12.46 NTU	-4.0 mV	13.14 ft	200.00 ml/min
10/16/2024 1:00 PM	01:45:00	9.46 pH	18.95 °C	711.56 µS/cm	0.04 mg/L	8.18 NTU	2.9 mV	13.14 ft	200.00 ml/min
10/16/2024 1:05 PM	01:50:00	9.45 pH	18.92 °C	718.34 µS/cm	0.04 mg/L	36.72 NTU	3.6 mV	13.14 ft	200.00 ml/min
10/16/2024 1:10 PM	01:55:00	9.50 pH	18.97 °C	715.45 µS/cm	0.06 mg/L	55.82 NTU	2.9 mV	13.14 ft	200.00 ml/min
10/16/2024 1:15 PM	02:00:00	9.48 pH	19.06 °C	710.07 µS/cm	0.03 mg/L	35.06 NTU	3.0 mV	13.14 ft	200.00 ml/min
10/16/2024 1:20 PM	02:05:00	9.49 pH	18.92 °C	709.18 µS/cm	0.04 mg/L	29.48 NTU	3.3 mV	13.12 ft	200.00 ml/min
10/16/2024 1:25 PM	02:10:00	9.50 pH	18.92 °C	713.11 µS/cm	0.05 mg/L	29.81 NTU	2.9 mV	13.12 ft	200.00 ml/min
10/16/2024 1:30 PM	02:15:00	9.51 pH	19.06 °C	711.96 µS/cm	0.04 mg/L	31.42 NTU	2.0 mV	13.10 ft	200.00 ml/min
10/16/2024 1:35 PM	02:20:00	9.50 pH	19.06 °C	716.72 µS/cm	0.04 mg/L	29.88 NTU	-6.4 mV	13.10 ft	200.00 ml/min
10/16/2024 1:40 PM	02:25:00	9.50 pH	19.05 °C	715.46 µS/cm	0.04 mg/L	26.92 NTU	-6.9 mV	13.10 ft	200.00 ml/min
10/16/2024 1:45 PM	02:30:00	9.50 pH	19.05 °C	713.15 µS/cm	0.03 mg/L	24.87 NTU	1.1 mV	13.10 ft	200.00 ml/min
10/16/2024 1:50 PM	02:35:00	9.50 pH	19.10 °C	715.91 µS/cm	0.07 mg/L	18.51 NTU	-5.6 mV	13.10 ft	200.00 ml/min
10/16/2024 1:55 PM	02:40:00	9.50 pH	19.15 °C	716.14 µS/cm	0.03 mg/L	15.55 NTU	-6.0 mV	13.10 ft	200.00 ml/min
10/16/2024 2:00 PM	02:45:00	9.50 pH	19.08 °C	715.78 µS/cm	0.05 mg/L	10.54 NTU	-5.4 mV	13.10 ft	200.00 ml/min
10/16/2024 2:05 PM	02:50:00	9.51 pH	19.01 °C	710.84 µS/cm	0.03 mg/L	9.49 NTU	3.3 mV	13.10 ft	200.00 ml/min
10/16/2024 2:10 PM	02:55:00	9.50 pH	19.12 °C	719.14 µS/cm	0.06 mg/L	8.46 NTU	-2.7 mV	13.10 ft	200.00 ml/min
10/16/2024 2:15 PM	03:00:00	9.50 pH	19.15 °C	715.28 µS/cm	0.05 mg/L	6.80 NTU	4.4 mV	13.10 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-12	Grab.

Low-Flow Test Report:

Test Date / Time: 10/15/2024 10:15:06 AM
Project: GP-Plant Hammond
Operator Name: Jamie Newsome

Location Name: PT-13 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35 ft Total Depth: 45 ft Initial Depth to Water: 25.75 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 34000 ml Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 843285
---	--	--

Test Notes:
Metals. Fe = 5.0 mg/L Fe2+ = 3.0 mg/L

Weather Conditions:
Cloudy, 50 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/15/2024 10:15 AM	00:00	6.62 pH	19.06 °C	740.29 µS/cm	2.41 mg/L	1.000e+09 NTU	-32.4 mV	25.75 ft	200.00 ml/min
10/15/2024 10:20 AM	05:00	6.63 pH	19.10 °C	730.89 µS/cm	2.50 mg/L	1.000e+09 NTU	-32.7 mV	25.75 ft	200.00 ml/min
10/15/2024 10:25 AM	10:00	6.64 pH	19.14 °C	728.71 µS/cm	2.50 mg/L	1.000e+09 NTU	-35.0 mV	25.75 ft	200.00 ml/min
10/15/2024 10:30 AM	15:00	6.64 pH	19.13 °C	724.36 µS/cm	2.22 mg/L	1.000e+09 NTU	-36.4 mV	25.80 ft	200.00 ml/min
10/15/2024 10:35 AM	20:00	6.65 pH	19.17 °C	719.29 µS/cm	2.31 mg/L	1.000e+09 NTU	-37.3 mV	25.80 ft	200.00 ml/min
10/15/2024 10:40 AM	25:00	6.65 pH	19.15 °C	718.88 µS/cm	2.11 mg/L	92.60 NTU	-38.6 mV	25.80 ft	200.00 ml/min
10/15/2024 10:45 AM	30:00	6.65 pH	19.19 °C	715.21 µS/cm	2.27 mg/L	82.90 NTU	-39.5 mV	25.80 ft	200.00 ml/min
10/15/2024 10:50 AM	35:00	6.65 pH	19.15 °C	717.17 µS/cm	2.05 mg/L	50.00 NTU	-39.9 mV	25.80 ft	200.00 ml/min
10/15/2024 10:55 AM	40:00	6.64 pH	19.24 °C	716.12 µS/cm	2.03 mg/L	32.00 NTU	-47.4 mV	25.80 ft	200.00 ml/min
10/15/2024 11:00 AM	45:00	6.65 pH	19.26 °C	711.66 µS/cm	1.92 mg/L	30.20 NTU	-40.7 mV	25.80 ft	200.00 ml/min
10/15/2024 11:05 AM	50:00	6.65 pH	19.24 °C	712.08 µS/cm	1.81 mg/L	27.30 NTU	-41.1 mV	25.80 ft	200.00 ml/min
10/15/2024 11:10 AM	55:00	6.65 pH	19.31 °C	711.02 µS/cm	1.69 mg/L	21.60 NTU	-41.2 mV	25.80 ft	200.00 ml/min
10/15/2024 11:15 AM	01:00:00	6.65 pH	19.53 °C	709.29 µS/cm	1.64 mg/L	18.60 NTU	-41.2 mV	25.80 ft	200.00 ml/min

10/15/2024 11:20 AM	01:05:00	6.65 pH	19.31 °C	711.16 µS/cm	1.66 mg/L	18.10 NTU	-41.4 mV	25.80 ft	200.00 ml/min
10/15/2024 11:25 AM	01:10:00	6.65 pH	19.43 °C	723.00 µS/cm	1.53 mg/L	17.20 NTU	-47.8 mV	25.80 ft	200.00 ml/min
10/15/2024 11:30 AM	01:15:00	6.65 pH	19.49 °C	726.39 µS/cm	1.48 mg/L	16.20 NTU	-41.6 mV	25.80 ft	200.00 ml/min
10/15/2024 11:35 AM	01:20:00	6.65 pH	19.35 °C	725.48 µS/cm	1.49 mg/L	15.20 NTU	-42.0 mV	25.80 ft	200.00 ml/min
10/15/2024 11:40 AM	01:25:00	6.65 pH	19.34 °C	726.05 µS/cm	1.42 mg/L	12.80 NTU	-41.7 mV	25.80 ft	200.00 ml/min
10/15/2024 11:45 AM	01:30:00	6.65 pH	19.29 °C	730.60 µS/cm	1.41 mg/L	13.90 NTU	-42.1 mV	25.80 ft	200.00 ml/min
10/15/2024 11:50 AM	01:35:00	6.65 pH	19.37 °C	726.44 µS/cm	1.38 mg/L	12.40 NTU	-48.1 mV	25.80 ft	200.00 ml/min
10/15/2024 11:55 AM	01:40:00	6.65 pH	19.39 °C	727.58 µS/cm	1.33 mg/L	10.90 NTU	-42.2 mV	25.80 ft	200.00 ml/min
10/15/2024 12:00 PM	01:45:00	6.66 pH	19.96 °C	721.87 µS/cm	1.24 mg/L	10.20 NTU	-48.1 mV	25.80 ft	200.00 ml/min
10/15/2024 12:05 PM	01:50:00	6.66 pH	20.02 °C	721.87 µS/cm	1.23 mg/L	11.70 NTU	-48.3 mV	25.80 ft	200.00 ml/min
10/15/2024 12:10 PM	01:55:00	6.66 pH	19.93 °C	721.85 µS/cm	1.20 mg/L	10.50 NTU	-42.8 mV	25.80 ft	200.00 ml/min
10/15/2024 12:15 PM	02:00:00	6.66 pH	19.77 °C	723.15 µS/cm	1.20 mg/L	10.10 NTU	-48.4 mV	25.80 ft	200.00 ml/min
10/15/2024 12:20 PM	02:05:00	6.66 pH	20.14 °C	723.34 µS/cm	1.18 mg/L	10.88 NTU	-48.7 mV	25.80 ft	200.00 ml/min
10/15/2024 12:25 PM	02:10:00	6.66 pH	19.67 °C	725.69 µS/cm	1.18 mg/L	10.30 NTU	-43.2 mV	25.80 ft	200.00 ml/min
10/15/2024 12:30 PM	02:15:00	6.66 pH	19.71 °C	727.41 µS/cm	1.19 mg/L	9.81 NTU	-48.9 mV	25.80 ft	200.00 ml/min
10/15/2024 12:35 PM	02:20:00	6.66 pH	19.84 °C	731.78 µS/cm	1.11 mg/L	9.17 NTU	-49.3 mV	25.80 ft	200.00 ml/min
10/15/2024 12:40 PM	02:25:00	6.66 pH	20.06 °C	728.89 µS/cm	1.10 mg/L	7.90 NTU	-49.7 mV	25.80 ft	200.00 ml/min
10/15/2024 12:45 PM	02:30:00	6.66 pH	19.98 °C	730.55 µS/cm	1.12 mg/L	8.57 NTU	-44.5 mV	25.80 ft	200.00 ml/min
10/15/2024 12:50 PM	02:35:00	6.66 pH	20.07 °C	733.04 µS/cm	1.08 mg/L	7.70 NTU	-50.0 mV	25.75 ft	200.00 ml/min
10/15/2024 12:55 PM	02:40:00	6.66 pH	20.15 °C	731.51 µS/cm	1.02 mg/L	6.58 NTU	-50.4 mV	25.75 ft	200.00 ml/min
10/15/2024 1:00 PM	02:45:00	6.66 pH	20.24 °C	730.37 µS/cm	0.95 mg/L	5.40 NTU	-50.6 mV	25.75 ft	200.00 ml/min
10/15/2024 1:05 PM	02:50:00	6.66 pH	19.80 °C	734.97 µS/cm	0.92 mg/L	4.98 NTU	-50.8 mV	25.75 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-13	Grab.

Low-Flow Test Report:

Test Date / Time: 10/15/2024 10:12:29 AM
Project: GP-Plant Hammond
Operator Name: Amanda Tomlinson

Location Name: PT-14 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.67 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 17350 ml Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 843593
---	---	--

Test Notes:
Metals. Total Fe: 10 mg/L. Fe2+: 5.0 mg/L.

Weather Conditions:
Cloudy, 53 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/15/2024 10:12 AM	00:00	6.84 pH	18.94 °C	813.13 µS/cm	0.27 mg/L	94.30 NTU	-91.9 mV	25.68 ft	200.00 ml/min
10/15/2024 10:17 AM	05:00	6.77 pH	18.67 °C	783.56 µS/cm	0.24 mg/L	63.80 NTU	-98.4 mV	25.68 ft	200.00 ml/min
10/15/2024 10:22 AM	10:00	6.79 pH	18.83 °C	800.33 µS/cm	0.14 mg/L	47.30 NTU	-112.0 mV	25.70 ft	200.00 ml/min
10/15/2024 10:27 AM	15:00	6.80 pH	18.80 °C	799.17 µS/cm	0.10 mg/L	31.40 NTU	-110.0 mV	25.70 ft	200.00 ml/min
10/15/2024 10:32 AM	20:00	6.81 pH	18.74 °C	803.23 µS/cm	0.08 mg/L	25.20 NTU	-111.8 mV	25.70 ft	200.00 ml/min
10/15/2024 10:37 AM	25:00	6.81 pH	18.74 °C	797.74 µS/cm	0.07 mg/L	14.90 NTU	-112.3 mV	25.70 ft	200.00 ml/min
10/15/2024 10:42 AM	30:00	6.84 pH	18.74 °C	798.66 µS/cm	0.06 mg/L	10.43 NTU	-119.9 mV	25.69 ft	200.00 ml/min
10/15/2024 10:47 AM	35:00	6.85 pH	18.79 °C	798.36 µS/cm	0.05 mg/L	10.98 NTU	-114.8 mV	25.70 ft	200.00 ml/min
10/15/2024 10:52 AM	40:00	6.84 pH	18.88 °C	797.06 µS/cm	0.04 mg/L	10.85 NTU	-114.6 mV	25.70 ft	200.00 ml/min
10/15/2024 10:57 AM	45:00	6.88 pH	18.96 °C	796.62 µS/cm	0.03 mg/L	9.64 NTU	-116.8 mV	25.70 ft	200.00 ml/min
10/15/2024 11:02 AM	50:00	6.89 pH	18.88 °C	796.70 µS/cm	0.03 mg/L	7.04 NTU	-122.8 mV	25.71 ft	200.00 ml/min
10/15/2024 11:07 AM	55:00	6.89 pH	18.83 °C	795.53 µS/cm	0.02 mg/L	7.88 NTU	-117.0 mV	25.70 ft	200.00 ml/min
10/15/2024 11:12 AM	01:00:00	6.92 pH	18.91 °C	795.11 µS/cm	0.02 mg/L	5.83 NTU	-117.2 mV	25.71 ft	200.00 ml/min

10/15/2024 11:17 AM	01:05:00	6.93 pH	18.92 °C	796.03 µS/cm	0.01 mg/L	5.78 NTU	-118.5 mV	25.70 ft	200.00 ml/min
10/15/2024 11:22 AM	01:10:00	6.94 pH	18.94 °C	795.29 µS/cm	0.01 mg/L	4.23 NTU	-125.0 mV	25.70 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-14	Grab.

Low-Flow Test Report:

Test Date / Time: 10/15/2024 2:45:04 PM
Project: GP-Plant Hammond
Operator Name: Amanda Tomlinson

Location Name: PT-15 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 25.62 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40 ft Estimated Total Volume Pumped: 6000 ml Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 843593
---	--	--

Test Notes:
Metals. Total Fe: 1.5 mg/L. Fe2+: 1.0 mg/L.

Weather Conditions:
Partly cloudy, 63 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
10/15/2024 2:45 PM	00:00	7.03 pH	20.42 °C	708.80 µS/cm	0.32 mg/L	153.00 NTU	-38.3 mV	25.60 ft	200.00 ml/min
10/15/2024 2:50 PM	05:00	7.02 pH	19.90 °C	710.28 µS/cm	0.33 mg/L	54.44 NTU	-27.7 mV	25.59 ft	200.00 ml/min
10/15/2024 2:55 PM	10:00	7.02 pH	19.90 °C	715.99 µS/cm	0.14 mg/L	19.80 NTU	-24.4 mV	25.59 ft	200.00 ml/min
10/15/2024 3:00 PM	15:00	7.01 pH	19.73 °C	714.15 µS/cm	0.09 mg/L	8.83 NTU	-20.8 mV	25.59 ft	200.00 ml/min
10/15/2024 3:05 PM	20:00	7.04 pH	19.72 °C	712.45 µS/cm	0.07 mg/L	4.30 NTU	-21.7 mV	25.59 ft	200.00 ml/min
10/15/2024 3:10 PM	25:00	7.04 pH	19.67 °C	711.67 µS/cm	0.06 mg/L	3.18 NTU	-19.9 mV	25.60 ft	200.00 ml/min
10/15/2024 3:15 PM	30:00	7.04 pH	19.83 °C	710.88 µS/cm	0.05 mg/L	3.45 NTU	-19.6 mV	25.60 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-15	Grab.

Low-Flow Test Report:

Test Date / Time: 11/5/2024 10:07:38 AM
Project: Plant Hammond
Operator Name: Tristan Halterman

Location Name: INW-03 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.4 ft Total Depth: 27.4 ft Initial Depth to Water: 13.72 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22.4 ft Estimated Total Volume Pumped: 4 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 980712
--	--	--

Test Notes:
Parameters.

Weather Conditions:
Cloudy, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
11/5/2024 10:07 AM	00:00	6.37 pH	20.39 °C	712.31 µS/cm	0.23 mg/L	5.08 NTU	-28.6 mV	13.75 ft	200.00 ml/min
11/5/2024 10:12 AM	05:00	6.35 pH	20.19 °C	719.11 µS/cm	0.17 mg/L	4.77 NTU	-35.3 mV	13.75 ft	200.00 ml/min
11/5/2024 10:17 AM	10:00	6.37 pH	20.17 °C	725.54 µS/cm	0.14 mg/L	3.15 NTU	-41.7 mV	13.75 ft	200.00 ml/min
11/5/2024 10:22 AM	15:00	6.39 pH	20.07 °C	730.96 µS/cm	0.12 mg/L	2.90 NTU	-41.8 mV	13.75 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 11/4/2024 3:27:08 PM
Project: Plant Hammond
Operator Name: Zain Webb

Location Name: INW-04 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.65 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 1.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.08 ft	Instrument Used: Aqua TROLL 400 Serial Number: 989630
--	--	--

Test Notes:
Parameters.

Weather Conditions:
Cloudy, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
11/4/2024 3:27 PM	00:00	6.10 pH	19.50 °C	566.44 µS/cm	0.51 mg/L	++++	41.2 mV	26.65 ft	150.00 ml/min
11/4/2024 3:32 PM	05:00	6.29 pH	19.36 °C	623.26 µS/cm	0.43 mg/L	++++	6.9 mV	26.73 ft	150.00 ml/min
11/4/2024 3:37 PM	10:00	6.34 pH	19.37 °C	636.38 µS/cm	0.25 mg/L	++++	-3.9 mV	26.73 ft	150.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 11/4/2024 3:01:45 PM
Project: Plant Hammond
Operator Name: Tristan Halterman

Location Name: INW-05 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.25 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 4 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 980712
--	---	--

Test Notes:
Parameters.

Weather Conditions:
Cloudy, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
11/4/2024 3:01 PM	00:00	6.75 pH	21.27 °C	735.02 µS/cm	1.04 mg/L	++++	-81.2 mV	26.25 ft	200.00 ml/min
11/4/2024 3:06 PM	05:00	6.76 pH	20.20 °C	746.52 µS/cm	0.67 mg/L	++++	-84.2 mV	26.25 ft	200.00 ml/min
11/4/2024 3:11 PM	10:00	6.76 pH	20.07 °C	750.26 µS/cm	0.81 mg/L	++++	-89.9 mV	26.25 ft	200.00 ml/min
11/4/2024 3:16 PM	15:00	6.77 pH	19.97 °C	753.63 µS/cm	0.77 mg/L	103.30 NTU	-92.1 mV	26.25 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 11/4/2024 11:59:32 AM
Project: Plant Hammond
Operator Name: Tristan Halterman

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 37.75 ft Total Depth: 47.75 ft Initial Depth to Water: 27.09 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 42.75 ft Estimated Total Volume Pumped: 8 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 980712
---	--	--

Test Notes:
Five Bottles: Appendix III and IV + Major Ions. Ferrous Iron: 4.5 mg/L, Total Iron: 5.0 mg/L.

Weather Conditions:
Cloudy, 60 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
11/4/2024 11:59 AM	00:00	6.74 pH	20.92 °C	752.94 µS/cm	1.45 mg/L	3.14 NTU	-76.9 mV	27.08 ft	200.00 ml/min
11/4/2024 12:04 PM	05:00	6.75 pH	20.13 °C	763.05 µS/cm	1.39 mg/L	2.25 NTU	-78.8 mV	27.09 ft	200.00 ml/min
11/4/2024 12:09 PM	10:00	6.76 pH	20.06 °C	761.88 µS/cm	1.53 mg/L	1.28 NTU	-83.8 mV	27.09 ft	200.00 ml/min
11/4/2024 12:14 PM	15:00	6.76 pH	20.06 °C	761.10 µS/cm	1.44 mg/L	0.98 NTU	-83.0 mV	27.09 ft	200.00 ml/min
11/4/2024 12:19 PM	20:00	6.76 pH	20.05 °C	759.72 µS/cm	1.45 mg/L	0.74 NTU	-81.7 mV	27.09 ft	200.00 ml/min
11/4/2024 12:24 PM	25:00	6.76 pH	20.02 °C	757.48 µS/cm	1.46 mg/L	0.48 NTU	-74.7 mV	27.09 ft	200.00 ml/min
11/4/2024 12:29 PM	30:00	6.76 pH	19.98 °C	756.66 µS/cm	1.46 mg/L	0.44 NTU	-79.3 mV	27.09 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-07	Grab.

Low-Flow Test Report:

Test Date / Time: 11/4/2024 10:24:38 AM
Project: Plant Hammond
Operator Name: Zain Webb

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 31.93 ft Total Depth: 41.93 ft Initial Depth to Water: 26.82 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 36.93 ft Estimated Total Volume Pumped: 16.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.04 ft	Instrument Used: Aqua TROLL 400 Serial Number: 989630
---	--	--

Test Notes:
Five Bottles: Appendix III and IV + Major Ions. Ferrous Iron: 0.5 mg/L, Total Iron: 0.6 mg/L.

Weather Conditions:
Cloudy, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
11/4/2024 10:24 AM	00:00	6.30 pH	19.55 °C	594.75 µS/cm	0.71 mg/L	++++	123.4 mV	26.82 ft	150.00 ml/min
11/4/2024 10:29 AM	05:00	6.28 pH	19.44 °C	596.68 µS/cm	0.48 mg/L	++++	104.4 mV	26.84 ft	150.00 ml/min
11/4/2024 10:34 AM	10:00	6.30 pH	19.43 °C	609.37 µS/cm	0.35 mg/L	++++	90.8 mV	26.84 ft	150.00 ml/min
11/4/2024 10:39 AM	15:00	6.29 pH	19.45 °C	612.52 µS/cm	0.27 mg/L	++++	97.3 mV	26.85 ft	150.00 ml/min
11/4/2024 10:44 AM	20:00	6.30 pH	19.45 °C	615.04 µS/cm	0.35 mg/L	98.50 NTU	92.3 mV	26.85 ft	150.00 ml/min
11/4/2024 10:49 AM	25:00	6.29 pH	19.47 °C	615.76 µS/cm	0.46 mg/L	67.80 NTU	73.0 mV	26.85 ft	150.00 ml/min
11/4/2024 10:54 AM	30:00	6.30 pH	19.48 °C	616.43 µS/cm	0.30 mg/L	45.20 NTU	68.8 mV	26.86 ft	150.00 ml/min
11/4/2024 10:59 AM	35:00	6.30 pH	19.45 °C	618.45 µS/cm	0.26 mg/L	39.40 NTU	65.9 mV	26.86 ft	150.00 ml/min
11/4/2024 11:04 AM	40:00	6.31 pH	19.41 °C	619.37 µS/cm	0.23 mg/L	33.80 NTU	79.7 mV	26.86 ft	150.00 ml/min
11/4/2024 11:09 AM	45:00	6.31 pH	19.41 °C	621.36 µS/cm	0.25 mg/L	24.70 NTU	78.3 mV	26.86 ft	150.00 ml/min
11/4/2024 11:14 AM	50:00	6.32 pH	19.41 °C	621.63 µS/cm	0.24 mg/L	22.00 NTU	60.7 mV	26.86 ft	150.00 ml/min
11/4/2024 11:19 AM	55:00	6.31 pH	19.41 °C	618.71 µS/cm	0.26 mg/L	19.30 NTU	59.7 mV	26.86 ft	150.00 ml/min
11/4/2024 11:24 AM	01:00:00	6.31 pH	19.41 °C	622.24 µS/cm	0.23 mg/L	17.80 NTU	58.6 mV	26.86 ft	150.00 ml/min

11/4/2024 11:29 AM	01:05:00	6.32 pH	19.35 °C	619.19 µS/cm	0.35 mg/L	16.70 NTU	57.0 mV	26.86 ft	150.00 ml/min
11/4/2024 11:34 AM	01:10:00	6.33 pH	19.33 °C	626.17 µS/cm	0.14 mg/L	15.10 NTU	71.1 mV	26.86 ft	150.00 ml/min
11/4/2024 11:39 AM	01:15:00	6.34 pH	19.33 °C	627.61 µS/cm	0.19 mg/L	13.50 NTU	69.4 mV	26.86 ft	150.00 ml/min
11/4/2024 11:44 AM	01:20:00	6.34 pH	19.35 °C	630.84 µS/cm	0.15 mg/L	10.60 NTU	66.9 mV	26.86 ft	150.00 ml/min
11/4/2024 11:49 AM	01:25:00	6.36 pH	19.37 °C	632.97 µS/cm	0.19 mg/L	8.99 NTU	49.6 mV	26.86 ft	150.00 ml/min
11/4/2024 11:54 AM	01:30:00	6.37 pH	19.34 °C	637.17 µS/cm	0.19 mg/L	7.80 NTU	59.5 mV	26.86 ft	150.00 ml/min
11/4/2024 11:59 AM	01:35:00	6.38 pH	19.34 °C	638.66 µS/cm	0.20 mg/L	6.92 NTU	56.5 mV	26.86 ft	150.00 ml/min
11/4/2024 12:04 PM	01:40:00	6.38 pH	19.36 °C	640.96 µS/cm	0.17 mg/L	6.26 NTU	53.8 mV	26.86 ft	150.00 ml/min
11/4/2024 12:09 PM	01:45:00	6.39 pH	19.37 °C	643.29 µS/cm	0.15 mg/L	4.98 NTU	39.5 mV	26.86 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.
HAM-AP1-FD-01	Grab.

Low-Flow Test Report:

Test Date / Time: 11/5/2024 11:19:35 AM
Project: Plant Hammond
Operator Name: Tristan Halterman

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.47 ft Total Depth: 30.47 ft Initial Depth to Water: 17.20 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 25.47 ft Estimated Total Volume Pumped: 8 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 980712
---	--	--

Test Notes:
Five Bottles: Appendix III and IV + Major Ions. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Weather Conditions:
Cloudy, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
11/5/2024 11:19 AM	00:00	6.90 pH	21.14 °C	754.52 µS/cm	0.73 mg/L	3.06 NTU	74.1 mV	17.30 ft	200.00 ml/min
11/5/2024 11:24 AM	05:00	6.79 pH	20.39 °C	761.25 µS/cm	0.27 mg/L	3.29 NTU	62.5 mV	17.30 ft	200.00 ml/min
11/5/2024 11:29 AM	10:00	6.80 pH	20.30 °C	758.32 µS/cm	0.21 mg/L	3.20 NTU	78.6 mV	17.30 ft	200.00 ml/min
11/5/2024 11:34 AM	15:00	6.80 pH	20.21 °C	759.98 µS/cm	0.18 mg/L	3.19 NTU	57.4 mV	17.30 ft	200.00 ml/min
11/5/2024 11:39 AM	20:00	6.79 pH	20.20 °C	754.43 µS/cm	0.17 mg/L	3.72 NTU	75.8 mV	17.30 ft	200.00 ml/min
11/5/2024 11:44 AM	25:00	6.78 pH	20.14 °C	758.31 µS/cm	0.15 mg/L	4.03 NTU	56.1 mV	17.20 ft	200.00 ml/min
11/5/2024 11:49 AM	30:00	6.79 pH	20.16 °C	756.70 µS/cm	0.15 mg/L	3.78 NTU	74.2 mV	17.20 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.

Low-Flow Test Report:

Test Date / Time: 11/5/2024 8:54:41 AM
Project: Plant Hammond
Operator Name: Zain Webb

Location Name: PT-10 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.45 ft Total Depth: 30.45 ft Initial Depth to Water: 17.13 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 25.45 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 989630
---	---	--

Test Notes:
Five Bottles: Appendix III and IV + Major Ions. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Weather Conditions:
Cloudy, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
11/5/2024 8:54 AM	00:00	6.85 pH	19.68 °C	675.75 µS/cm	0.26 mg/L	4.77 NTU	183.1 mV	17.13 ft	200.00 ml/min
11/5/2024 8:59 AM	05:00	6.87 pH	19.54 °C	677.59 µS/cm	0.17 mg/L	4.38 NTU	189.9 mV	17.15 ft	200.00 ml/min
11/5/2024 9:04 AM	10:00	6.88 pH	19.54 °C	677.84 µS/cm	0.14 mg/L	3.53 NTU	183.0 mV	17.15 ft	200.00 ml/min
11/5/2024 9:09 AM	15:00	6.89 pH	19.54 °C	679.17 µS/cm	0.11 mg/L	3.39 NTU	153.0 mV	17.16 ft	200.00 ml/min
11/5/2024 9:14 AM	20:00	6.89 pH	19.50 °C	679.78 µS/cm	0.10 mg/L	2.64 NTU	142.6 mV	17.16 ft	200.00 ml/min
11/5/2024 9:19 AM	25:00	6.90 pH	19.50 °C	678.73 µS/cm	0.09 mg/L	2.04 NTU	133.8 mV	17.16 ft	200.00 ml/min
11/5/2024 9:24 AM	30:00	6.90 pH	19.54 °C	677.87 µS/cm	0.09 mg/L	1.92 NTU	126.1 mV	17.16 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.

Low-Flow Test Report:

Test Date / Time: 11/5/2024 8:50:42 AM
Project: Plant Hammond
Operator Name: Tristan Halterman

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 16.9 ft Total Depth: 26.9 ft Initial Depth to Water: 13.64 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 21.9 ft Estimated Total Volume Pumped: 8 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 980712
---	---	--

Test Notes:
Five Bottles: Appendix III and IV + Major Ions. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Weather Conditions:
Cloudy, 65 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
11/5/2024 8:50 AM	00:00	6.85 pH	19.76 °C	752.24 µS/cm	0.43 mg/L	6.81 NTU	92.8 mV	13.64 ft	200.00 ml/min
11/5/2024 8:55 AM	05:00	6.83 pH	19.77 °C	741.50 µS/cm	0.22 mg/L	3.22 NTU	95.7 mV	13.64 ft	200.00 ml/min
11/5/2024 9:00 AM	10:00	6.82 pH	19.81 °C	741.37 µS/cm	0.18 mg/L	2.13 NTU	66.1 mV	13.64 ft	200.00 ml/min
11/5/2024 9:05 AM	15:00	6.80 pH	19.80 °C	736.71 µS/cm	0.17 mg/L	2.84 NTU	84.7 mV	13.64 ft	200.00 ml/min
11/5/2024 9:10 AM	20:00	6.80 pH	19.79 °C	736.79 µS/cm	0.16 mg/L	2.12 NTU	61.9 mV	13.64 ft	200.00 ml/min
11/5/2024 9:15 AM	25:00	6.80 pH	19.81 °C	734.49 µS/cm	0.15 mg/L	2.13 NTU	80.9 mV	13.64 ft	200.00 ml/min
11/5/2024 9:20 AM	30:00	6.80 pH	19.82 °C	735.89 µS/cm	0.14 mg/L	1.79 NTU	59.9 mV	13.64 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-11	Grab.

Low-Flow Test Report:

Test Date / Time: 11/5/2024 11:04:40 AM
Project: Plant Hammond
Operator Name: Zain Webb

Location Name: PT-12 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.3 ft Total Depth: 27.3 ft Initial Depth to Water: 13.52 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22.3 ft Estimated Total Volume Pumped: 8 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.04 ft	Instrument Used: Aqua TROLL 400 Serial Number: 989630
---	--	--

Test Notes:
Five Bottles: Appendix III and IV + Major Ions. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Weather Conditions:
Cloudy, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
11/5/2024 11:04 AM	00:00	6.81 pH	20.46 °C	776.88 µS/cm	0.20 mg/L	4.77 NTU	114.2 mV	13.52 ft	200.00 ml/min
11/5/2024 11:09 AM	05:00	6.78 pH	20.45 °C	743.67 µS/cm	0.15 mg/L	6.26 NTU	129.2 mV	13.55 ft	200.00 ml/min
11/5/2024 11:14 AM	10:00	6.76 pH	20.39 °C	740.39 µS/cm	0.13 mg/L	6.73 NTU	100.9 mV	13.55 ft	200.00 ml/min
11/5/2024 11:19 AM	15:00	6.73 pH	20.30 °C	734.20 µS/cm	0.11 mg/L	5.82 NTU	96.7 mV	13.56 ft	200.00 ml/min
11/5/2024 11:24 AM	20:00	6.68 pH	20.25 °C	731.23 µS/cm	0.10 mg/L	6.14 NTU	122.9 mV	13.56 ft	200.00 ml/min
11/5/2024 11:29 AM	25:00	6.64 pH	20.23 °C	728.18 µS/cm	0.10 mg/L	5.77 NTU	97.7 mV	13.56 ft	200.00 ml/min
11/5/2024 11:34 AM	30:00	6.63 pH	20.21 °C	723.90 µS/cm	0.09 mg/L	5.18 NTU	94.9 mV	13.56 ft	200.00 ml/min
11/5/2024 11:39 AM	35:00	6.61 pH	20.15 °C	717.50 µS/cm	0.08 mg/L	3.23 NTU	94.3 mV	13.56 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-12	Grab.

Low-Flow Test Report:

Test Date / Time: 11/4/2024 9:45:32 AM
Project: Plant Hammond
Operator Name: Tristan Halterman

Location Name: PT-13 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.52 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 17 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.06 ft	Instrument Used: Aqua TROLL 400 Serial Number: 980712
---	---	--

Test Notes:
Five Bottles: Appendix III and IV + Major Ions. Ferrous Iron: 2.5 mg/L, Total Iron: 5.0 mg/L.

Weather Conditions:
Cloudy, 60 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
11/4/2024 9:45 AM	00:00	6.64 pH	19.79 °C	727.16 µS/cm	2.02 mg/L	++++	-46.1 mV	26.59 ft	200.00 ml/min
11/4/2024 9:50 AM	05:00	6.65 pH	19.84 °C	725.57 µS/cm	2.59 mg/L	88.80 NTU	-43.4 mV	26.59 ft	200.00 ml/min
11/4/2024 9:55 AM	10:00	6.66 pH	19.76 °C	726.54 µS/cm	2.85 mg/L	56.60 NTU	-55.1 mV	26.59 ft	200.00 ml/min
11/4/2024 10:00 AM	15:00	6.66 pH	19.76 °C	739.19 µS/cm	3.08 mg/L	39.80 NTU	-55.9 mV	26.59 ft	200.00 ml/min
11/4/2024 10:05 AM	20:00	6.67 pH	19.79 °C	738.28 µS/cm	3.25 mg/L	31.20 NTU	-45.5 mV	26.59 ft	200.00 ml/min
11/4/2024 10:10 AM	25:00	6.68 pH	19.78 °C	738.09 µS/cm	3.29 mg/L	25.40 NTU	-56.6 mV	26.59 ft	200.00 ml/min
11/4/2024 10:15 AM	30:00	6.68 pH	19.80 °C	736.41 µS/cm	3.28 mg/L	19.60 NTU	-46.6 mV	26.59 ft	200.00 ml/min
11/4/2024 10:20 AM	35:00	6.68 pH	19.69 °C	762.30 µS/cm	7.92 mg/L	18.80 NTU	-57.4 mV	26.58 ft	200.00 ml/min
11/4/2024 10:25 AM	40:00	6.69 pH	19.76 °C	754.05 µS/cm	6.73 mg/L	15.80 NTU	-49.0 mV	26.58 ft	200.00 ml/min
11/4/2024 10:30 AM	45:00	6.69 pH	19.77 °C	755.05 µS/cm	6.48 mg/L	11.20 NTU	-49.8 mV	26.58 ft	200.00 ml/min
11/4/2024 10:35 AM	50:00	6.69 pH	19.85 °C	760.04 µS/cm	5.99 mg/L	8.16 NTU	-50.9 mV	26.58 ft	200.00 ml/min
11/4/2024 10:40 AM	55:00	6.69 pH	19.85 °C	758.31 µS/cm	6.88 mg/L	6.56 NTU	-60.2 mV	26.58 ft	200.00 ml/min
11/4/2024 10:45 AM	01:00:00	6.70 pH	19.85 °C	761.70 µS/cm	3.62 mg/L	6.29 NTU	-52.3 mV	26.58 ft	200.00 ml/min

11/4/2024 10:50 AM	01:05:00	6.69 pH	19.82 °C	761.12 µS/cm	3.41 mg/L	6.09 NTU	-52.8 mV	26.58 ft	200.00 ml/min
11/4/2024 10:55 AM	01:10:00	6.70 pH	19.77 °C	761.38 µS/cm	3.41 mg/L	5.34 NTU	-53.4 mV	26.58 ft	200.00 ml/min
11/4/2024 11:00 AM	01:15:00	6.70 pH	19.85 °C	759.92 µS/cm	3.41 mg/L	4.66 NTU	-54.1 mV	26.58 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-13	Grab

Low-Flow Test Report:

Test Date / Time: 11/4/2024 1:35:28 PM
Project: Plant Hammond
Operator Name: Zain Webb

Location Name: PT-14 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.51 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 11.25 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 989630
---	--	--

Test Notes:
Five Bottles: Appendix III and IV + Major Ions. Ferrous Iron: 2.5 mg/L, Total Iron: 16 mg/L.

Weather Conditions:
Cloudy, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
11/4/2024 1:35 PM	00:00	6.71 pH	21.32 °C	758.16 µS/cm	3.01 mg/L	18.60 NTU	-93.1 mV	26.51 ft	150.00 ml/min
11/4/2024 1:40 PM	05:00	6.87 pH	19.59 °C	770.56 µS/cm	1.09 mg/L	14.10 NTU	-109.6 mV	26.54 ft	150.00 ml/min
11/4/2024 1:45 PM	10:00	6.88 pH	19.43 °C	771.51 µS/cm	0.72 mg/L	9.09 NTU	-109.9 mV	26.54 ft	150.00 ml/min
11/4/2024 1:50 PM	15:00	6.89 pH	19.38 °C	770.96 µS/cm	0.75 mg/L	7.58 NTU	-109.7 mV	26.54 ft	150.00 ml/min
11/4/2024 1:55 PM	20:00	6.88 pH	19.35 °C	770.74 µS/cm	0.89 mg/L	5.85 NTU	-94.4 mV	26.54 ft	150.00 ml/min
11/4/2024 2:00 PM	25:00	6.89 pH	19.32 °C	782.68 µS/cm	0.58 mg/L	4.99 NTU	-108.8 mV	26.54 ft	150.00 ml/min
11/4/2024 2:05 PM	30:00	6.89 pH	19.30 °C	770.33 µS/cm	0.47 mg/L	3.72 NTU	-109.3 mV	26.54 ft	150.00 ml/min
11/4/2024 2:10 PM	35:00	6.89 pH	19.28 °C	770.65 µS/cm	0.36 mg/L	3.46 NTU	-110.9 mV	26.54 ft	150.00 ml/min
11/4/2024 2:15 PM	40:00	6.89 pH	19.23 °C	770.52 µS/cm	0.39 mg/L	2.85 NTU	-110.3 mV	26.54 ft	150.00 ml/min
11/4/2024 2:20 PM	45:00	6.89 pH	19.23 °C	770.47 µS/cm	0.43 mg/L	2.67 NTU	-96.4 mV	26.54 ft	150.00 ml/min
11/4/2024 2:25 PM	50:00	6.90 pH	19.21 °C	770.55 µS/cm	0.21 mg/L	2.28 NTU	-113.5 mV	26.54 ft	150.00 ml/min
11/4/2024 2:30 PM	55:00	6.90 pH	19.18 °C	770.34 µS/cm	0.22 mg/L	1.57 NTU	-113.8 mV	26.54 ft	150.00 ml/min
11/4/2024 2:35 PM	01:00:00	6.90 pH	19.18 °C	770.71 µS/cm	0.40 mg/L	1.79 NTU	-111.8 mV	26.54 ft	150.00 ml/min

11/4/2024 2:40 PM	01:05:00	6.90 pH	19.19 °C	770.46 µS/cm	0.34 mg/L	1.42 NTU	-112.5 mV	26.54 ft	150.00 ml/min
11/4/2024 2:45 PM	01:10:00	6.90 pH	19.23 °C	769.88 µS/cm	0.33 mg/L	1.12 NTU	-100.0 mV	26.54 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-14	Grab.

Low-Flow Test Report:

Test Date / Time: 11/4/2024 1:26:33 PM
Project: Plant Hammond
Operator Name: Tristan Halterman

Location Name: PT-15 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.43 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 8 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.04 ft	Instrument Used: Aqua TROLL 400 Serial Number: 980712
---	--	--

Test Notes:
Five Bottles: Appendix III and IV + Major Ions. Ferrous Iron: 1.5 mg/L, Total Iron: 1.5 mg/L.

Weather Conditions:
Cloudy, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
11/4/2024 1:26 PM	00:00	6.77 pH	20.38 °C	719.48 µS/cm	0.52 mg/L	5.17 NTU	-29.3 mV	26.47 ft	200.00 ml/min
11/4/2024 1:31 PM	05:00	6.71 pH	19.85 °C	726.89 µS/cm	0.34 mg/L	2.97 NTU	-33.4 mV	26.47 ft	200.00 ml/min
11/4/2024 1:36 PM	10:00	6.70 pH	19.74 °C	727.71 µS/cm	0.27 mg/L	1.34 NTU	-32.5 mV	26.47 ft	200.00 ml/min
11/4/2024 1:41 PM	15:00	6.69 pH	19.72 °C	726.47 µS/cm	0.22 mg/L	0.78 NTU	-27.8 mV	26.47 ft	200.00 ml/min
11/4/2024 1:46 PM	20:00	6.70 pH	19.72 °C	726.01 µS/cm	0.21 mg/L	0.60 NTU	-31.9 mV	26.47 ft	200.00 ml/min
11/4/2024 1:51 PM	25:00	6.70 pH	19.69 °C	725.42 µS/cm	0.16 mg/L	0.50 NTU	-27.1 mV	26.47 ft	200.00 ml/min
11/4/2024 1:56 PM	30:00	6.70 pH	19.69 °C	724.15 µS/cm	0.16 mg/L	0.21 NTU	-26.7 mV	26.47 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-15	Grab.

Low-Flow Test Report:

Test Date / Time: 12/3/2024 2:39:37 PM
Project: GP-Plant Hammond
Operator Name: Zain W.

Location Name: INW-03 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.4 ft Total Depth: 27.4 ft Initial Depth to Water: 13.77 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22.4 ft Estimated Total Volume Pumped: 5 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.1 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1170065
--	---	---

Test Notes:
Parameters.

Weather Conditions:
Clear, 40 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
12/3/2024 2:39 PM	00:00	6.34 pH	17.86 °C	673.58 µS/cm	0.24 mg/L	14.40 NTU	28.7 mV	13.85 ft	200.00 ml/min
12/3/2024 2:44 PM	05:00	6.34 pH	17.72 °C	679.16 µS/cm	0.20 mg/L	11.30 NTU	44.4 mV	13.86 ft	200.00 ml/min
12/3/2024 2:49 PM	10:00	6.34 pH	17.86 °C	675.83 µS/cm	0.19 mg/L	8.75 NTU	44.6 mV	13.87 ft	200.00 ml/min
12/3/2024 2:54 PM	15:00	6.36 pH	18.08 °C	672.92 µS/cm	0.18 mg/L	7.73 NTU	44.3 mV	13.87 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 12/2/2024 3:40:26 PM
Project: GP-Plant Hammond
Operator Name: Jacob T.

Location Name: INW-04 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.81 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 5.5 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1170046
--	--	---

Test Notes:
Parameters.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
12/2/2024 3:40 PM	00:00	6.57 pH	17.71 °C	654.65 µS/cm	0.13 mg/L	87.40 NTU	-10.4 mV	26.81 ft	200.00 ml/min
12/2/2024 3:45 PM	05:00	6.62 pH	17.77 °C	659.42 µS/cm	0.11 mg/L	72.30 NTU	-14.0 mV	26.84 ft	200.00 ml/min
12/2/2024 3:51 PM	11:02	6.64 pH	17.83 °C	668.93 µS/cm	0.11 mg/L	64.30 NTU	-17.6 mV	26.86 ft	200.00 ml/min
12/2/2024 3:52 PM	12:23	6.65 pH	17.81 °C	630.20 µS/cm	0.10 mg/L	--	-15.8 mV	26.86 ft	200.00 ml/min
12/2/2024 3:57 PM	17:23	6.65 pH	17.76 °C	672.56 µS/cm	0.09 mg/L	50.60 NTU	-25.4 mV	26.86 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 12/2/2024 4:20:07 PM
Project: GP-Plant Hammond
Operator Name: Jacob T.

Location Name: INW-05 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.34 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 4 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.04 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1170046
--	--	---

Test Notes:
Parameters.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
12/2/2024 4:20 PM	00:00	7.12 pH	18.08 °C	757.06 µS/cm	0.47 mg/L	++++	-65.4 mV	26.36 ft	200.00 ml/min
12/2/2024 4:25 PM	05:00	7.13 pH	18.21 °C	754.80 µS/cm	0.35 mg/L	++++	-70.7 mV	26.36 ft	200.00 ml/min
12/2/2024 4:30 PM	10:00	7.12 pH	18.19 °C	758.30 µS/cm	0.22 mg/L	102.70 NTU	-75.3 mV	26.38 ft	200.00 ml/min
12/2/2024 4:35 PM	15:00	7.13 pH	18.26 °C	760.52 µS/cm	0.18 mg/L	65.20 NTU	-78.4 mV	26.38 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 12/2/2024 2:26:10 PM
Project: GP-Plant Hammond
Operator Name: Zain Webb

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 37.75 ft Total Depth: 47.75 ft Initial Depth to Water: 27.22 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 42.75 ft Estimated Total Volume Pumped: 5.25 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: -0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1170065
---	---	---

Test Notes:
Full App. III & IV and Major Ions. Ferrous Iron: 6.5 mg/L, Total Iron: 9.2 mg/L.

Weather Conditions:
Clear, 40 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
12/2/2024 2:26 PM	00:00	6.85 pH	18.76 °C	755.91 µS/cm	0.96 mg/L	5.18 NTU	-63.8 mV	27.22 ft	150.00 ml/min
12/2/2024 2:31 PM	05:00	6.86 pH	18.84 °C	756.73 µS/cm	0.74 mg/L	3.27 NTU	-62.7 mV	27.16 ft	150.00 ml/min
12/2/2024 2:36 PM	10:00	6.86 pH	18.79 °C	759.08 µS/cm	0.61 mg/L	3.36 NTU	-53.7 mV	27.17 ft	150.00 ml/min
12/2/2024 2:41 PM	15:00	6.86 pH	18.83 °C	761.28 µS/cm	0.53 mg/L	2.61 NTU	-55.6 mV	27.18 ft	150.00 ml/min
12/2/2024 2:46 PM	20:00	6.86 pH	18.79 °C	761.15 µS/cm	0.39 mg/L	2.48 NTU	-56.1 mV	27.18 ft	150.00 ml/min
12/2/2024 2:51 PM	25:00	6.86 pH	18.84 °C	759.49 µS/cm	0.42 mg/L	2.04 NTU	-57.0 mV	27.19 ft	150.00 ml/min
12/2/2024 2:56 PM	30:00	6.87 pH	18.82 °C	760.18 µS/cm	0.46 mg/L	1.93 NTU	-57.7 mV	27.19 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-07	Grab.

Low-Flow Test Report:

Test Date / Time: 12/2/2024 11:48:16 AM
Project: GP-Plant Hammond
Operator Name: Jacob T.

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 32.2 ft Total Depth: 42.2 ft Initial Depth to Water: 26.86 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 37.2 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.06 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1170046
---	---	---

Test Notes:
Full App. III & IV and Major Ions. Ferrous Iron: 0.2 mg/L, Total Iron: 0.4 mg/L.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
12/2/2024 11:48 AM	00:00	6.39 pH	18.57 °C	547.38 µS/cm	0.32 mg/L	14.40 NTU	59.2 mV	26.58 ft	200.00 ml/min
12/2/2024 11:53 AM	05:00	6.43 pH	18.57 °C	585.92 µS/cm	0.23 mg/L	11.30 NTU	49.1 mV	26.89 ft	200.00 ml/min
12/2/2024 11:58 AM	10:00	6.47 pH	18.52 °C	602.98 µS/cm	0.19 mg/L	7.11 NTU	44.4 mV	26.92 ft	200.00 ml/min
12/2/2024 12:03 PM	15:00	6.48 pH	18.55 °C	603.27 µS/cm	0.17 mg/L	5.70 NTU	46.6 mV	26.92 ft	200.00 ml/min
12/2/2024 12:08 PM	20:00	6.49 pH	18.54 °C	613.32 µS/cm	0.15 mg/L	4.32 NTU	65.7 mV	26.92 ft	200.00 ml/min
12/2/2024 12:13 PM	25:00	6.49 pH	18.51 °C	613.76 µS/cm	0.15 mg/L	4.20 NTU	66.8 mV	26.92 ft	200.00 ml/min
12/2/2024 12:18 PM	30:00	6.49 pH	18.52 °C	607.25 µS/cm	0.13 mg/L	2.30 NTU	48.5 mV	26.92 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.

Low-Flow Test Report:

Test Date / Time: 12/3/2024 12:50:27 PM
Project: GP-Plant Hammond
Operator Name: Jacob T.

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.47 ft Total Depth: 30.47 ft Initial Depth to Water: 17.09 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 25.47 ft Estimated Total Volume Pumped: 24 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080307
---	---	---

Test Notes:
Full App. III & IV and Major Ions. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
12/3/2024 12:50 PM	00:00	7.12 pH	17.92 °C	760.91 µS/cm	0.73 mg/L	5.47 NTU	89.7 mV	17.09 ft	200.00 ml/min
12/3/2024 12:55 PM	05:00	7.09 pH	17.82 °C	738.10 µS/cm	0.80 mg/L	2.46 NTU	79.3 mV	17.09 ft	200.00 ml/min
12/3/2024 1:00 PM	10:00	7.10 pH	17.72 °C	750.06 µS/cm	0.77 mg/L	2.02 NTU	51.5 mV	17.09 ft	200.00 ml/min
12/3/2024 1:05 PM	15:00	7.09 pH	17.81 °C	744.90 µS/cm	0.78 mg/L	1.81 NTU	46.2 mV	17.09 ft	200.00 ml/min
12/3/2024 1:10 PM	20:00	7.10 pH	17.38 °C	740.10 µS/cm	0.76 mg/L	1.12 NTU	42.8 mV	17.09 ft	200.00 ml/min
12/3/2024 1:15 PM	25:00	7.08 pH	17.40 °C	742.19 µS/cm	0.71 mg/L	1.15 NTU	41.1 mV	17.09 ft	200.00 ml/min
12/3/2024 1:20 PM	30:00	7.09 pH	17.31 °C	730.13 µS/cm	0.69 mg/L	1.41 NTU	40.0 mV	17.09 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.

Low-Flow Test Report:

Test Date / Time: 12/3/2024 11:21:47 AM
Project: GP-Plant Hammond
Operator Name: Zain Webb

Location Name: PT-10 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.45 ft Total Depth: 30.45 ft Initial Depth to Water: 17.19 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 25.45 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.06 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1170065
---	---	---

Test Notes:
Full App. III & IV and Major Ions. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Weather Conditions:
Clear, 40 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
12/3/2024 11:21 AM	00:00	6.61 pH	17.58 °C	668.58 µS/cm	0.28 mg/L	3.68 NTU	38.6 mV	17.19 ft	200.00 ml/min
12/3/2024 11:26 AM	05:00	6.71 pH	17.85 °C	680.97 µS/cm	0.20 mg/L	2.84 NTU	50.2 mV	17.25 ft	200.00 ml/min
12/3/2024 11:31 AM	10:00	6.76 pH	18.17 °C	688.26 µS/cm	0.18 mg/L	1.69 NTU	51.1 mV	17.25 ft	200.00 ml/min
12/3/2024 11:36 AM	15:00	6.78 pH	18.04 °C	685.04 µS/cm	0.16 mg/L	1.35 NTU	53.2 mV	17.25 ft	200.00 ml/min
12/3/2024 11:41 AM	20:00	6.80 pH	17.99 °C	682.95 µS/cm	0.16 mg/L	1.12 NTU	54.5 mV	17.25 ft	200.00 ml/min
12/3/2024 11:46 AM	25:00	6.82 pH	18.16 °C	681.20 µS/cm	0.15 mg/L	1.03 NTU	55.1 mV	17.25 ft	200.00 ml/min
12/3/2024 11:51 AM	30:00	6.83 pH	18.32 °C	678.04 µS/cm	0.15 mg/L	0.94 NTU	57.0 mV	17.25 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.
HAM-AP1-FD-01	Grab.

Low-Flow Test Report:

Test Date / Time: 12/3/2024 2:05:37 PM
Project: GP-Plant Hammond
Operator Name: Jacob T.

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 16.9 ft Total Depth: 26.9 ft Initial Depth to Water: 13.71 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 21.9 ft Estimated Total Volume Pumped: 7.2 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1080307
---	---	---

Test Notes:
Full App. III & IV and Major Ions.

Weather Conditions:
Clear, 40 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
12/3/2024 2:05 PM	00:00	6.94 pH	16.67 °C	686.68 µS/cm	0.39 mg/L	1.72 NTU	92.2 mV	13.71 ft	200.00 ml/min
12/3/2024 2:07 PM	01:38	6.95 pH	17.24 °C	691.29 µS/cm	0.22 mg/L	--	72.1 mV	13.71 ft	200.00 ml/min
12/3/2024 2:12 PM	06:38	7.00 pH	17.54 °C	678.26 µS/cm	0.12 mg/L	0.82 NTU	59.7 mV	13.71 ft	200.00 ml/min
12/3/2024 2:17 PM	11:38	7.03 pH	17.57 °C	691.42 µS/cm	0.11 mg/L	0.64 NTU	38.8 mV	13.71 ft	200.00 ml/min
12/3/2024 2:22 PM	16:38	7.05 pH	17.71 °C	691.94 µS/cm	0.10 mg/L	0.92 NTU	45.3 mV	13.71 ft	200.00 ml/min
12/3/2024 2:27 PM	21:38	7.07 pH	17.45 °C	696.87 µS/cm	0.11 mg/L	0.85 NTU	32.7 mV	13.71 ft	200.00 ml/min
12/3/2024 2:32 PM	26:38	7.07 pH	17.17 °C	706.29 µS/cm	0.11 mg/L	0.89 NTU	30.5 mV	13.71 ft	200.00 ml/min
12/3/2024 2:37 PM	31:38	7.08 pH	17.00 °C	710.00 µS/cm	0.11 mg/L	0.70 NTU	28.9 mV	13.71 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-11	Grab.

Low-Flow Test Report:

Test Date / Time: 12/3/2024 1:22:08 PM
Project: GP-Plant Hammond
Operator Name: Zain Webb

Location Name: PT-12 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.3 ft Total Depth: 27.3 ft Initial Depth to Water: 13.6 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22.3 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1170065
--	---	---

Test Notes:
Full App. III & IV and Major Ions. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Weather Conditions:
Clear, 40 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
12/3/2024 1:22 PM	00:00	6.63 pH	17.81 °C	747.86 µS/cm	0.21 mg/L	6.84 NTU	44.5 mV	13.60 ft	200.00 ml/min
12/3/2024 1:27 PM	05:00	6.63 pH	17.82 °C	749.89 µS/cm	0.20 mg/L	5.12 NTU	77.0 mV	13.60 ft	200.00 ml/min
12/3/2024 1:32 PM	10:00	6.66 pH	17.90 °C	752.37 µS/cm	0.19 mg/L	4.00 NTU	74.2 mV	13.60 ft	200.00 ml/min
12/3/2024 1:37 PM	15:00	6.67 pH	17.49 °C	748.62 µS/cm	0.19 mg/L	4.53 NTU	73.1 mV	13.60 ft	200.00 ml/min
12/3/2024 1:42 PM	20:00	6.64 pH	17.50 °C	742.47 µS/cm	0.18 mg/L	4.30 NTU	70.9 mV	13.60 ft	200.00 ml/min
12/3/2024 1:47 PM	25:00	6.65 pH	17.48 °C	742.14 µS/cm	0.18 mg/L	3.64 NTU	69.2 mV	13.60 ft	200.00 ml/min
12/3/2024 1:52 PM	30:00	6.65 pH	17.50 °C	741.65 µS/cm	0.18 mg/L	3.47 NTU	68.7 mV	13.60 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-12	Grab.

Low-Flow Test Report:

Test Date / Time: 12/2/2024 11:42:31 AM
Project: GP-Plant Hammond
Operator Name: Zain Webb

Location Name: PT-13 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.58 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 14.25 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1170065
---	---	---

Test Notes:
Full App. III & IV and Major Ions. Total Iron: 4.0 mg/L.

Weather Conditions:
Clear, 40 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
12/2/2024 11:42 AM	00:00	6.76 pH	17.86 °C	747.43 µS/cm	3.07 mg/L	52.90 NTU	-48.1 mV	26.58 ft	150.00 ml/min
12/2/2024 11:47 AM	05:00	6.81 pH	18.21 °C	778.89 µS/cm	3.12 mg/L	40.20 NTU	-52.2 mV	26.57 ft	150.00 ml/min
12/2/2024 11:52 AM	10:00	6.82 pH	18.27 °C	779.03 µS/cm	2.80 mg/L	36.70 NTU	-54.2 mV	26.58 ft	150.00 ml/min
12/2/2024 11:57 AM	15:00	6.82 pH	18.33 °C	762.71 µS/cm	2.52 mg/L	21.40 NTU	-54.8 mV	26.58 ft	150.00 ml/min
12/2/2024 12:02 PM	20:00	6.83 pH	18.42 °C	772.12 µS/cm	6.56 mg/L	16.60 NTU	-52.9 mV	26.58 ft	150.00 ml/min
12/2/2024 12:07 PM	25:00	6.83 pH	18.35 °C	774.53 µS/cm	4.26 mg/L	14.30 NTU	-49.3 mV	26.58 ft	150.00 ml/min
12/2/2024 12:12 PM	30:00	6.84 pH	18.26 °C	778.89 µS/cm	0.71 mg/L	13.10 NTU	-68.9 mV	26.58 ft	150.00 ml/min
12/2/2024 12:17 PM	35:00	6.83 pH	18.28 °C	779.09 µS/cm	0.61 mg/L	11.80 NTU	-55.9 mV	26.58 ft	150.00 ml/min
12/2/2024 12:22 PM	40:00	6.83 pH	18.36 °C	779.19 µS/cm	0.65 mg/L	11.00 NTU	-56.5 mV	26.58 ft	150.00 ml/min
12/2/2024 12:27 PM	45:00	6.83 pH	18.35 °C	778.82 µS/cm	0.62 mg/L	9.56 NTU	-56.7 mV	26.58 ft	150.00 ml/min
12/2/2024 12:32 PM	50:00	6.83 pH	18.36 °C	778.50 µS/cm	0.55 mg/L	8.47 NTU	-57.5 mV	26.58 ft	150.00 ml/min
12/2/2024 12:37 PM	55:00	6.83 pH	18.39 °C	773.95 µS/cm	0.50 mg/L	8.33 NTU	-57.6 mV	26.58 ft	150.00 ml/min
12/2/2024 12:42 PM	01:00:00	6.82 pH	18.43 °C	776.26 µS/cm	0.48 mg/L	7.56 NTU	-58.1 mV	26.58 ft	150.00 ml/min

12/2/2024 12:47 PM	01:05:00	6.82 pH	18.50 °C	778.94 µS/cm	0.60 mg/L	7.02 NTU	-58.3 mV	26.58 ft	150.00 ml/min
12/2/2024 12:52 PM	01:10:00	6.82 pH	18.47 °C	773.41 µS/cm	0.45 mg/L	6.24 NTU	-58.5 mV	26.58 ft	150.00 ml/min
12/2/2024 12:57 PM	01:15:00	6.82 pH	18.52 °C	774.20 µS/cm	0.41 mg/L	6.76 NTU	-59.0 mV	26.58 ft	150.00 ml/min
12/2/2024 1:02 PM	01:20:00	6.81 pH	18.51 °C	784.18 µS/cm	0.53 mg/L	5.90 NTU	-58.1 mV	26.58 ft	150.00 ml/min
12/2/2024 1:07 PM	01:25:00	6.82 pH	18.52 °C	774.29 µS/cm	0.38 mg/L	5.62 NTU	-59.1 mV	26.58 ft	150.00 ml/min
12/2/2024 1:12 PM	01:30:00	6.82 pH	18.53 °C	773.35 µS/cm	0.52 mg/L	4.74 NTU	-59.1 mV	26.58 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-13	Grab.

Low-Flow Test Report:

Test Date / Time: 12/2/2024 1:50:48 PM
Project: GP-Plant Hammond
Operator Name: Jacob T.

Location Name: PT-14 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.54 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 10 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1170046
---	---	---

Test Notes:
Full App. III & IV and Major Ions. Ferrous Iron: 5.2 mg/L, Total Iron: 5.6 mg/L.

Weather Conditions:
Clear, 40 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
12/2/2024 1:50 PM	00:00	7.16 pH	18.88 °C	782.39 µS/cm	0.34 mg/L	50.40 NTU	-77.5 mV	26.54 ft	200.00 ml/min
12/2/2024 1:55 PM	05:00	7.16 pH	18.90 °C	783.70 µS/cm	0.21 mg/L	42.70 NTU	-78.0 mV	26.54 ft	200.00 ml/min
12/2/2024 2:00 PM	10:00	7.17 pH	18.84 °C	782.11 µS/cm	0.17 mg/L	36.80 NTU	-104.7 mV	26.54 ft	200.00 ml/min
12/2/2024 2:05 PM	15:00	7.18 pH	18.76 °C	782.95 µS/cm	0.15 mg/L	30.10 NTU	-106.2 mV	26.54 ft	200.00 ml/min
12/2/2024 2:10 PM	20:00	7.18 pH	18.49 °C	783.57 µS/cm	0.14 mg/L	20.30 NTU	-81.4 mV	26.54 ft	200.00 ml/min
12/2/2024 2:15 PM	25:00	7.18 pH	18.26 °C	787.19 µS/cm	0.13 mg/L	17.80 NTU	-107.2 mV	26.54 ft	200.00 ml/min
12/2/2024 2:20 PM	30:00	7.18 pH	18.22 °C	787.83 µS/cm	0.12 mg/L	14.10 NTU	-81.1 mV	26.54 ft	200.00 ml/min
12/2/2024 2:25 PM	35:00	7.18 pH	18.21 °C	787.85 µS/cm	0.12 mg/L	7.48 NTU	-108.5 mV	26.54 ft	200.00 ml/min
12/2/2024 2:30 PM	40:00	7.18 pH	18.17 °C	787.77 µS/cm	0.11 mg/L	6.34 NTU	-84.0 mV	26.59 ft	200.00 ml/min
12/2/2024 2:35 PM	45:00	7.18 pH	18.13 °C	787.18 µS/cm	0.11 mg/L	4.76 NTU	-85.0 mV	26.59 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-14	Grab.

Low-Flow Test Report:

Test Date / Time: 12/2/2024 3:50:39 PM
Project: GP-Plant Hammond
Operator Name: Zain Webb

Location Name: PT-15 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.51 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 5.25 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.01 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1170065
---	---	---

Test Notes:
Full App. III & IV and Major Ions. Ferrous Iron: 0 mg/L, Total Iron: 0.2 mg/L.

Weather Conditions:
Clear, 40 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
12/2/2024 3:50 PM	00:00	6.98 pH	18.48 °C	654.57 µS/cm	0.52 mg/L	27.60 NTU	-78.9 mV	26.51 ft	150.00 ml/min
12/2/2024 3:55 PM	05:00	6.82 pH	18.48 °C	704.98 µS/cm	0.45 mg/L	22.30 NTU	-18.6 mV	26.51 ft	150.00 ml/min
12/2/2024 4:00 PM	10:00	6.79 pH	18.47 °C	708.66 µS/cm	0.43 mg/L	15.50 NTU	-0.9 mV	26.52 ft	150.00 ml/min
12/2/2024 4:05 PM	15:00	6.78 pH	18.45 °C	706.73 µS/cm	0.40 mg/L	8.91 NTU	5.9 mV	26.52 ft	150.00 ml/min
12/2/2024 4:10 PM	20:00	6.77 pH	18.46 °C	706.23 µS/cm	0.31 mg/L	5.37 NTU	10.0 mV	26.52 ft	150.00 ml/min
12/2/2024 4:15 PM	25:00	6.76 pH	18.39 °C	707.28 µS/cm	0.30 mg/L	4.28 NTU	12.8 mV	26.52 ft	150.00 ml/min
12/2/2024 4:20 PM	30:00	6.76 pH	18.43 °C	703.58 µS/cm	0.32 mg/L	2.70 NTU	13.9 mV	26.52 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-15	Grab.

Low-Flow Test Report:

Test Date / Time: 1/6/2025 3:09:18 PM
Project: GP-Plant Hammond
Operator Name: Thomas Kessler

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 37.75 ft Total Depth: 47.75 ft Initial Depth to Water: 26.85 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 42.75 ft Estimated Total Volume Pumped: 6 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1082817
--	---	---

Test Notes:
Full App. III and IV and Major Ions. Ferrous Iron: 6.2 mg/L, Total Iron: 6.2 mg/L.

Weather Conditions:
Cloudy, 40 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
1/6/2025 3:09 PM	00:00	6.91 pH	13.45 °C	698.57 µS/cm	2.23 mg/L	8.45 NTU	-88.1 mV	26.85 ft	200.00 ml/min
1/6/2025 3:14 PM	05:00	6.87 pH	15.62 °C	680.43 µS/cm	0.93 mg/L	6.00 NTU	-65.8 mV	26.85 ft	200.00 ml/min
1/6/2025 3:19 PM	10:00	6.85 pH	15.77 °C	681.80 µS/cm	0.53 mg/L	2.87 NTU	-84.5 mV	26.85 ft	200.00 ml/min
1/6/2025 3:24 PM	15:00	6.86 pH	15.75 °C	679.69 µS/cm	0.36 mg/L	1.60 NTU	-66.6 mV	26.85 ft	200.00 ml/min
1/6/2025 3:29 PM	20:00	6.87 pH	15.61 °C	679.27 µS/cm	0.31 mg/L	1.23 NTU	-66.0 mV	26.85 ft	200.00 ml/min
1/6/2025 3:34 PM	25:00	6.85 pH	15.75 °C	682.97 µS/cm	0.24 mg/L	0.81 NTU	-66.0 mV	26.85 ft	200.00 ml/min
1/6/2025 3:39 PM	30:00	6.86 pH	15.75 °C	681.45 µS/cm	0.17 mg/L	0.39 NTU	-65.2 mV	26.85 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-07	Grab.

Low-Flow Test Report:

Test Date / Time: 1/6/2025 1:16:14 PM
Project: GP-Plant Hammond
Operator Name: Amanda Tomlinson

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 32 ft Total Depth: 42 ft Initial Depth to Water: 26.52	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 38.00 ft Estimated Total Volume Pumped: 42 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.04 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1082822
---	---	---

Test Notes:
Full App. III and IV and Major Ions. Ferrous Iron: 1.0 mg/L, Total Iron: 2.0 mg/L.

Weather Conditions:
Cloudy and snow, 36 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
1/6/2025 1:16 PM	00:00	6.66 pH	14.34 °C	687.04 µS/cm	1.27 mg/L	++++	-37.0 mV	26.52 ft	200.00 ml/min
1/6/2025 1:21 PM	05:00	6.50 pH	15.91 °C	653.28 µS/cm	0.40 mg/L	++++	-14.4 mV	26.52 ft	200.00 ml/min
1/6/2025 1:26 PM	10:00	6.44 pH	15.64 °C	639.56 µS/cm	0.42 mg/L	++++	11.4 mV	26.54 ft	200.00 ml/min
1/6/2025 1:31 PM	15:00	6.41 pH	15.68 °C	632.12 µS/cm	0.37 mg/L	547.00 NTU	21.9 mV	26.56 ft	200.00 ml/min
1/6/2025 1:36 PM	20:00	6.39 pH	15.66 °C	630.44 µS/cm	0.40 mg/L	370.00 NTU	22.3 mV	26.56 ft	200.00 ml/min
1/6/2025 1:41 PM	25:00	6.39 pH	15.49 °C	632.69 µS/cm	0.32 mg/L	255.00 NTU	24.4 mV	26.56 ft	200.00 ml/min
1/6/2025 1:46 PM	30:00	6.41 pH	15.78 °C	633.82 µS/cm	0.31 mg/L	182.00 NTU	22.9 mV	26.56 ft	200.00 ml/min
1/6/2025 1:51 PM	35:00	6.41 pH	15.75 °C	640.84 µS/cm	0.29 mg/L	135.00 NTU	21.8 mV	26.56 ft	200.00 ml/min
1/6/2025 1:56 PM	40:00	6.42 pH	15.74 °C	645.46 µS/cm	0.28 mg/L	86.10 NTU	26.1 mV	26.56 ft	200.00 ml/min
1/6/2025 2:01 PM	45:00	6.42 pH	15.82 °C	643.08 µS/cm	0.27 mg/L	64.80 NTU	26.4 mV	26.56 ft	200.00 ml/min
1/6/2025 2:06 PM	50:00	6.42 pH	15.88 °C	648.01 µS/cm	0.26 mg/L	47.50 NTU	23.1 mV	26.56 ft	200.00 ml/min
1/6/2025 2:11 PM	55:00	6.42 pH	15.87 °C	648.39 µS/cm	0.26 mg/L	36.70 NTU	23.0 mV	26.56 ft	200.00 ml/min
1/6/2025 2:16 PM	01:00:00	6.43 pH	15.74 °C	647.63 µS/cm	0.25 mg/L	28.20 NTU	21.8 mV	26.56 ft	200.00 ml/min
1/6/2025 2:21 PM	01:05:00	6.43 pH	15.78 °C	646.26 µS/cm	0.24 mg/L	24.90 NTU	20.5 mV	26.56 ft	200.00 ml/min

1/6/2025 2:26 PM	01:10:00	6.44 pH	15.42 °C	649.73 µS/cm	0.24 mg/L	22.70 NTU	23.7 mV	26.56 ft	200.00 ml/min
1/6/2025 2:31 PM	01:15:00	6.44 pH	15.51 °C	649.01 µS/cm	0.24 mg/L	23.50 NTU	18.8 mV	26.56 ft	200.00 ml/min
1/6/2025 2:36 PM	01:20:00	6.45 pH	15.69 °C	653.52 µS/cm	0.24 mg/L	19.90 NTU	16.0 mV	26.56 ft	200.00 ml/min
1/6/2025 2:41 PM	01:25:00	6.44 pH	15.77 °C	657.89 µS/cm	1.26 mg/L	19.10 NTU	17.8 mV	26.56 ft	200.00 ml/min
1/6/2025 2:46 PM	01:30:00	6.46 pH	16.08 °C	656.91 µS/cm	1.52 mg/L	17.30 NTU	17.5 mV	26.56 ft	200.00 ml/min
1/6/2025 2:51 PM	01:35:00	6.46 pH	16.01 °C	657.35 µS/cm	1.12 mg/L	16.70 NTU	16.9 mV	26.56 ft	200.00 ml/min
1/6/2025 2:56 PM	01:40:00	6.48 pH	15.94 °C	660.12 µS/cm	0.45 mg/L	14.50 NTU	15.6 mV	26.56 ft	200.00 ml/min
1/6/2025 3:01 PM	01:45:00	6.49 pH	15.97 °C	658.74 µS/cm	0.51 mg/L	16.00 NTU	17.8 mV	26.56 ft	200.00 ml/min
1/6/2025 3:06 PM	01:50:00	6.49 pH	15.73 °C	657.39 µS/cm	0.62 mg/L	12.40 NTU	17.1 mV	26.56 ft	200.00 ml/min
1/6/2025 3:11 PM	01:55:00	6.50 pH	15.82 °C	657.73 µS/cm	0.38 mg/L	12.00 NTU	16.6 mV	26.56 ft	200.00 ml/min
1/6/2025 3:16 PM	02:00:00	6.49 pH	15.74 °C	657.81 µS/cm	0.25 mg/L	13.10 NTU	13.8 mV	26.56 ft	200.00 ml/min
1/6/2025 3:21 PM	02:05:00	6.50 pH	15.66 °C	655.73 µS/cm	0.30 mg/L	11.20 NTU	14.9 mV	26.56 ft	200.00 ml/min
1/6/2025 3:26 PM	02:10:00	6.49 pH	15.72 °C	663.49 µS/cm	0.25 mg/L	10.00 NTU	16.6 mV	26.56 ft	200.00 ml/min
1/6/2025 3:31 PM	02:15:00	6.49 pH	15.61 °C	663.73 µS/cm	1.42 mg/L	9.60 NTU	14.3 mV	26.56 ft	200.00 ml/min
1/6/2025 3:36 PM	02:20:00	6.50 pH	15.78 °C	664.62 µS/cm	0.29 mg/L	10.40 NTU	13.4 mV	26.56 ft	200.00 ml/min
1/6/2025 3:41 PM	02:25:00	6.50 pH	15.82 °C	665.74 µS/cm	0.26 mg/L	8.97 NTU	11.2 mV	26.56 ft	200.00 ml/min
1/6/2025 3:46 PM	02:30:00	6.49 pH	15.96 °C	665.90 µS/cm	0.23 mg/L	9.29 NTU	10.3 mV	26.56 ft	200.00 ml/min
1/6/2025 3:51 PM	02:35:00	6.50 pH	15.60 °C	664.25 µS/cm	0.23 mg/L	9.51 NTU	8.7 mV	26.56 ft	200.00 ml/min
1/6/2025 3:56 PM	02:40:00	6.50 pH	15.69 °C	660.56 µS/cm	0.23 mg/L	9.12 NTU	8.0 mV	26.56 ft	200.00 ml/min
1/6/2025 4:01 PM	02:45:00	6.50 pH	15.69 °C	664.00 µS/cm	0.23 mg/L	12.00 NTU	8.0 mV	26.56 ft	200.00 ml/min
1/6/2025 4:06 PM	02:50:00	6.50 pH	15.63 °C	664.58 µS/cm	0.24 mg/L	11.80 NTU	6.7 mV	26.56 ft	200.00 ml/min
1/6/2025 4:11 PM	02:55:00	6.51 pH	15.58 °C	667.80 µS/cm	1.23 mg/L	9.88 NTU	7.8 mV	26.56 ft	200.00 ml/min
1/6/2025 4:16 PM	03:00:00	6.49 pH	15.47 °C	672.52 µS/cm	1.44 mg/L	8.63 NTU	6.2 mV	26.56 ft	200.00 ml/min
1/6/2025 4:21 PM	03:05:00	6.51 pH	15.41 °C	668.62 µS/cm	0.56 mg/L	6.66 NTU	6.0 mV	26.56 ft	200.00 ml/min
1/6/2025 4:26 PM	03:10:00	6.50 pH	15.74 °C	658.24 µS/cm	0.93 mg/L	6.69 NTU	6.8 mV	26.56 ft	200.00 ml/min
1/6/2025 4:31 PM	03:15:00	6.52 pH	15.17 °C	668.70 µS/cm	0.23 mg/L	6.58 NTU	6.1 mV	26.56 ft	200.00 ml/min
1/6/2025 4:36 PM	03:20:00	6.52 pH	15.46 °C	671.35 µS/cm	0.24 mg/L	7.99 NTU	4.5 mV	26.56 ft	200.00 ml/min
1/6/2025 4:41 PM	03:25:00	6.51 pH	15.56 °C	670.03 µS/cm	0.31 mg/L	8.05 NTU	6.1 mV	26.56 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.
HAM-AP1-FD-01	Grab.

Low-Flow Test Report:

Test Date / Time: 1/7/2025 9:52:12 AM
Project: GP-Plant Hammond
Operator Name: Thomas Kessler

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.47 ft Total Depth: 30.47 ft Initial Depth to Water: 16 ft	Pump Type: Peri Tubing Type: Polyethylene Pump Intake From TOC: 25.47 ft Estimated Total Volume Pumped: 8 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1082817
---	--	---

Test Notes:
Full App. III and IV and Major Ions. Ferrous Iron: 0 mg/L, Total Iron: 0.2 mg/L.

Weather Conditions:
Cloudy, 28 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
1/7/2025 9:52 AM	00:00	6.89 pH	14.81 °C	691.18 µS/cm	0.40 mg/L	3.75 NTU	69.1 mV	16.00 ft	200.00 ml/min
1/7/2025 9:57 AM	05:00	6.91 pH	15.71 °C	663.07 µS/cm	0.25 mg/L	3.86 NTU	62.5 mV	16.00 ft	200.00 ml/min
1/7/2025 10:02 AM	10:00	6.90 pH	15.80 °C	659.07 µS/cm	0.26 mg/L	2.81 NTU	46.3 mV	16.00 ft	200.00 ml/min
1/7/2025 10:07 AM	15:00	6.92 pH	15.97 °C	651.52 µS/cm	0.33 mg/L	2.51 NTU	42.7 mV	16.00 ft	200.00 ml/min
1/7/2025 10:12 AM	20:00	6.90 pH	15.97 °C	657.91 µS/cm	0.30 mg/L	6.57 NTU	51.1 mV	16.00 ft	200.00 ml/min
1/7/2025 10:17 AM	25:00	6.92 pH	16.29 °C	651.61 µS/cm	0.20 mg/L	6.80 NTU	39.8 mV	16.00 ft	200.00 ml/min
1/7/2025 10:22 AM	30:00	6.93 pH	16.05 °C	643.66 µS/cm	0.17 mg/L	7.89 NTU	36.9 mV	16.00 ft	200.00 ml/min
1/7/2025 10:27 AM	35:00	6.92 pH	16.15 °C	638.73 µS/cm	0.19 mg/L	6.82 NTU	35.4 mV	16.00 ft	200.00 ml/min
1/7/2025 10:32 AM	40:00	6.94 pH	15.90 °C	641.49 µS/cm	0.13 mg/L	4.93 NTU	33.4 mV	16.00 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.

Low-Flow Test Report:

Test Date / Time: 1/7/2025 11:55:09 AM
Project: GP-Plant Hammond
Operator Name: Thomas Kessler

Location Name: PT-10 Well Diameter: 2 ft Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.45 ft Total Depth: 30.45 ft Initial Depth to Water: 16.05 ft	Pump Type: Peri Tubing Type: Polyethylene Pump Intake From TOC: 25.45 ft Estimated Total Volume Pumped: 6 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1082817
--	---	---

Test Notes:
Full App. III and IV and Major Ions. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Weather Conditions:
Clear, 28 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
1/7/2025 11:55 AM	00:00	6.63 pH	13.98 °C	541.88 µS/cm	0.28 mg/L	4.02 NTU	74.7 mV	12.07 ft	200.00 ml/min
1/7/2025 12:00 PM	05:00	6.58 pH	14.09 °C	553.41 µS/cm	0.21 mg/L	3.98 NTU	66.0 mV	12.07 ft	200.00 ml/min
1/7/2025 12:05 PM	10:00	6.57 pH	15.62 °C	543.37 µS/cm	0.14 mg/L	4.46 NTU	46.7 mV	12.07 ft	200.00 ml/min
1/7/2025 12:10 PM	15:00	6.57 pH	15.88 °C	535.08 µS/cm	0.10 mg/L	3.22 NTU	42.2 mV	12.07 ft	200.00 ml/min
1/7/2025 12:15 PM	20:00	6.56 pH	16.06 °C	536.63 µS/cm	0.09 mg/L	2.99 NTU	37.4 mV	12.07 ft	200.00 ml/min
1/7/2025 12:20 PM	25:00	6.57 pH	16.08 °C	541.98 µS/cm	0.07 mg/L	3.54 NTU	32.3 mV	12.07 ft	200.00 ml/min
1/7/2025 12:25 PM	30:00	6.60 pH	15.87 °C	546.13 µS/cm	0.07 mg/L	2.65 NTU	12.0 mV	12.07 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.

Low-Flow Test Report:

Test Date / Time: 1/7/2025 11:02:20 AM
Project: GP-Plant Hammond
Operator Name: Thomas Kessler

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 16.9 ft Total Depth: 26.9 ft Initial Depth to Water: 12.6 ft	Pump Type: Peri Tubing Type: Polyethylene Pump Intake From TOC: 21.9 ft Estimated Total Volume Pumped: 6 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1082817
---	---	---

Test Notes:
Full App. III and IV and Major Ions. Ferrous Iron: 0 mg/L, Total Iron: 0 mg/L.

Weather Conditions:
Cloudy, 29 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
1/7/2025 11:02 AM	00:00	6.88 pH	14.96 °C	577.26 µS/cm	0.21 mg/L	2.49 NTU	67.6 mV	12.60 ft	200.00 ml/min
1/7/2025 11:07 AM	05:00	6.88 pH	15.29 °C	567.01 µS/cm	0.16 mg/L	1.37 NTU	61.1 mV	12.60 ft	200.00 ml/min
1/7/2025 11:12 AM	10:00	6.88 pH	15.26 °C	567.08 µS/cm	0.14 mg/L	1.38 NTU	42.5 mV	12.60 ft	200.00 ml/min
1/7/2025 11:17 AM	15:00	6.87 pH	15.93 °C	568.54 µS/cm	0.13 mg/L	0.63 NTU	51.1 mV	12.60 ft	200.00 ml/min
1/7/2025 11:22 AM	20:00	6.88 pH	15.26 °C	558.99 µS/cm	0.11 mg/L	0.53 NTU	38.7 mV	12.60 ft	200.00 ml/min
1/7/2025 11:27 AM	25:00	6.88 pH	14.99 °C	559.88 µS/cm	0.09 mg/L	0.61 NTU	45.6 mV	12.60 ft	200.00 ml/min
1/7/2025 11:32 AM	30:00	6.87 pH	15.26 °C	559.68 µS/cm	0.09 mg/L	0.35 NTU	35.7 mV	12.60 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-11	Grab.

Low-Flow Test Report:

Test Date / Time: 1/7/2025 8:56:36 AM
Project: GP-Plant Hammond
Operator Name: Thomas Kessler

Location Name: PT-12 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.3 ft Total Depth: 27.3 ft Initial Depth to Water: 12.45 ft	Pump Type: Peri Tubing Type: Polyethylene Pump Intake From TOC: 22.3 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1082817
--	---	---

Test Notes:
Full App. III and IV and Major Ions. Ferrous Iron: 0 mg/L, Total Iron: 2.0 mg/L.

Weather Conditions:
Cloudy, 28 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
1/7/2025 8:56 AM	00:00	6.53 pH	14.40 °C	579.45 µS/cm	0.41 mg/L	12.70 NTU	124.2 mV	12.45 ft	200.00 ml/min
1/7/2025 9:01 AM	05:00	6.56 pH	14.54 °C	632.12 µS/cm	0.30 mg/L	16.90 NTU	111.3 mV	12.45 ft	200.00 ml/min
1/7/2025 9:06 AM	10:00	6.54 pH	14.67 °C	635.88 µS/cm	0.24 mg/L	10.90 NTU	81.3 mV	12.45 ft	200.00 ml/min
1/7/2025 9:11 AM	15:00	6.57 pH	15.30 °C	647.29 µS/cm	0.19 mg/L	8.67 NTU	72.2 mV	12.45 ft	200.00 ml/min
1/7/2025 9:16 AM	20:00	6.58 pH	15.57 °C	647.20 µS/cm	0.19 mg/L	7.10 NTU	80.9 mV	12.45 ft	200.00 ml/min
1/7/2025 9:21 AM	25:00	6.58 pH	15.84 °C	648.79 µS/cm	0.14 mg/L	7.22 NTU	65.1 mV	12.45 ft	200.00 ml/min
1/7/2025 9:26 AM	30:00	6.58 pH	15.84 °C	640.17 µS/cm	0.12 mg/L	6.08 NTU	61.3 mV	12.45 ft	200.00 ml/min
1/7/2025 9:31 AM	35:00	6.62 pH	15.86 °C	649.55 µS/cm	0.09 mg/L	4.90 NTU	57.2 mV	12.45 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-12	Grab.

Low-Flow Test Report:

Test Date / Time: 1/6/2025 10:36:38 AM
Project: GP-Plant Hammond
Operator Name: Thomas Kessler

Location Name: PT-13 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.29 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 25 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1082817
--	--	---

Test Notes:
Full App. III and IV and Major Ions. Ferrous Iron: 6.6 mg/L, Total Iron: 6.6 mg/L.

Weather Conditions:
Cloudy, 40 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
1/6/2025 10:36 AM	00:00	6.71 pH	16.38 °C	697.34 µS/cm	2.06 mg/L	185.00 NTU	-169.4 mV	26.31 ft	200.00 ml/min
1/6/2025 10:41 AM	05:00	6.75 pH	17.49 °C	675.79 µS/cm	1.14 mg/L	146.00 NTU	-187.2 mV	26.31 ft	200.00 ml/min
1/6/2025 10:46 AM	10:00	6.77 pH	17.58 °C	677.41 µS/cm	0.97 mg/L	143.00 NTU	-211.1 mV	26.31 ft	200.00 ml/min
1/6/2025 10:51 AM	15:00	6.78 pH	17.63 °C	679.20 µS/cm	0.72 mg/L	85.90 NTU	-200.6 mV	26.31 ft	200.00 ml/min
1/6/2025 10:56 AM	20:00	6.79 pH	17.57 °C	681.39 µS/cm	0.55 mg/L	49.10 NTU	-138.6 mV	26.31 ft	200.00 ml/min
1/6/2025 11:01 AM	25:00	6.80 pH	17.47 °C	677.72 µS/cm	0.43 mg/L	32.40 NTU	-181.9 mV	26.31 ft	200.00 ml/min
1/6/2025 11:06 AM	30:00	6.80 pH	17.55 °C	680.49 µS/cm	0.25 mg/L	25.10 NTU	-125.9 mV	26.31 ft	200.00 ml/min
1/6/2025 11:11 AM	35:00	6.78 pH	17.56 °C	678.99 µS/cm	0.21 mg/L	21.80 NTU	-126.6 mV	26.31 ft	200.00 ml/min
1/6/2025 11:16 AM	40:00	6.80 pH	17.59 °C	684.53 µS/cm	0.17 mg/L	16.30 NTU	-165.3 mV	26.31 ft	200.00 ml/min
1/6/2025 11:21 AM	45:00	6.80 pH	17.45 °C	684.53 µS/cm	0.15 mg/L	16.00 NTU	-117.5 mV	26.31 ft	200.00 ml/min
1/6/2025 11:26 AM	50:00	6.80 pH	17.41 °C	685.63 µS/cm	0.13 mg/L	13.70 NTU	-113.1 mV	26.31 ft	200.00 ml/min
1/6/2025 11:31 AM	55:00	6.80 pH	17.44 °C	683.81 µS/cm	0.11 mg/L	12.30 NTU	-108.4 mV	26.31 ft	200.00 ml/min
1/6/2025 11:36 AM	01:00:00	6.81 pH	17.40 °C	683.92 µS/cm	0.10 mg/L	12.00 NTU	-148.2 mV	26.31 ft	200.00 ml/min

1/6/2025 11:41 AM	01:05:00	6.79 pH	17.48 °C	686.02 µS/cm	0.09 mg/L	11.30 NTU	-113.1 mV	26.31 ft	200.00 ml/min
1/6/2025 11:46 AM	01:10:00	6.80 pH	17.50 °C	682.10 µS/cm	0.08 mg/L	10.10 NTU	-117.5 mV	26.31 ft	200.00 ml/min
1/6/2025 11:51 AM	01:15:00	6.80 pH	17.42 °C	681.80 µS/cm	0.07 mg/L	9.78 NTU	-117.3 mV	26.31 ft	200.00 ml/min
1/6/2025 11:56 AM	01:20:00	6.80 pH	17.28 °C	684.30 µS/cm	0.07 mg/L	8.80 NTU	-117.2 mV	26.31 ft	200.00 ml/min
1/6/2025 12:01 PM	01:25:00	6.80 pH	17.22 °C	680.01 µS/cm	0.06 mg/L	8.41 NTU	-116.9 mV	26.31 ft	200.00 ml/min
1/6/2025 12:06 PM	01:30:00	6.80 pH	17.36 °C	682.96 µS/cm	0.06 mg/L	7.20 NTU	-113.0 mV	26.31 ft	200.00 ml/min
1/6/2025 12:11 PM	01:35:00	6.79 pH	17.36 °C	683.68 µS/cm	0.05 mg/L	7.76 NTU	-114.8 mV	26.31 ft	200.00 ml/min
1/6/2025 12:16 PM	01:40:00	6.79 pH	17.44 °C	681.05 µS/cm	0.05 mg/L	7.13 NTU	-117.0 mV	26.31 ft	200.00 ml/min
1/6/2025 12:21 PM	01:45:00	6.80 pH	17.36 °C	680.31 µS/cm	0.05 mg/L	6.80 NTU	-115.2 mV	26.31 ft	200.00 ml/min
1/6/2025 12:26 PM	01:50:00	6.80 pH	17.21 °C	682.42 µS/cm	0.04 mg/L	6.23 NTU	-153.8 mV	26.31 ft	200.00 ml/min
1/6/2025 12:31 PM	01:55:00	6.79 pH	17.27 °C	679.93 µS/cm	0.04 mg/L	6.06 NTU	-111.5 mV	26.31 ft	200.00 ml/min
1/6/2025 12:36 PM	02:00:00	6.80 pH	17.27 °C	680.14 µS/cm	0.04 mg/L	5.47 NTU	-107.4 mV	26.31 ft	200.00 ml/min
1/6/2025 12:41 PM	02:05:00	6.80 pH	17.29 °C	682.49 µS/cm	0.04 mg/L	4.96 NTU	-104.8 mV	26.31 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-13	Grab.

Low-Flow Test Report:

Test Date / Time: 1/6/2025 10:40:09 AM
Project: GP-Plant Hammond
Operator Name: Amanda Tomlinson

Location Name: PT-14 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.26 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.00 ft Estimated Total Volume Pumped: 24 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: -0.15 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1082822
--	--	---

Test Notes:
Full App. III and IV and Major Ions. Ferrous Iron: 7.0 mg/L, Total Iron: 7.0 mg/L.

Weather Conditions:
Cloudy, 39 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
1/6/2025 10:40 AM	00:00	6.85 pH	17.37 °C	773.16 µS/cm	3.00 mg/L	177.00 NTU	-88.1 mV	25.82 ft	200.00 ml/min
1/6/2025 10:45 AM	05:00	6.86 pH	17.46 °C	761.67 µS/cm	3.43 mg/L	123.00 NTU	-90.2 mV	26.02 ft	200.00 ml/min
1/6/2025 10:50 AM	10:00	6.87 pH	17.53 °C	756.62 µS/cm	3.56 mg/L	75.90 NTU	-92.3 mV	26.10 ft	200.00 ml/min
1/6/2025 10:55 AM	15:00	6.88 pH	17.53 °C	751.02 µS/cm	3.63 mg/L	60.00 NTU	-93.3 mV	26.08 ft	200.00 ml/min
1/6/2025 11:00 AM	20:00	6.88 pH	17.48 °C	749.75 µS/cm	3.62 mg/L	36.20 NTU	-94.7 mV	26.08 ft	200.00 ml/min
1/6/2025 11:05 AM	25:00	6.88 pH	17.45 °C	748.41 µS/cm	3.86 mg/L	34.10 NTU	-102.3 mV	26.11 ft	200.00 ml/min
1/6/2025 11:10 AM	30:00	6.88 pH	17.45 °C	746.04 µS/cm	3.62 mg/L	24.20 NTU	-104.7 mV	26.11 ft	200.00 ml/min
1/6/2025 11:15 AM	35:00	6.89 pH	17.42 °C	749.36 µS/cm	3.50 mg/L	20.60 NTU	-106.0 mV	26.11 ft	200.00 ml/min
1/6/2025 11:20 AM	40:00	6.89 pH	17.36 °C	748.26 µS/cm	3.47 mg/L	18.20 NTU	-98.7 mV	26.11 ft	200.00 ml/min
1/6/2025 11:25 AM	45:00	6.90 pH	17.31 °C	746.15 µS/cm	3.71 mg/L	16.50 NTU	-98.4 mV	26.11 ft	200.00 ml/min
1/6/2025 11:30 AM	50:00	6.90 pH	17.32 °C	759.07 µS/cm	3.81 mg/L	14.40 NTU	-105.7 mV	26.11 ft	200.00 ml/min
1/6/2025 11:35 AM	55:00	6.90 pH	17.26 °C	759.39 µS/cm	3.75 mg/L	12.60 NTU	-99.8 mV	26.11 ft	200.00 ml/min
1/6/2025 11:40 AM	01:00:00	6.90 pH	17.27 °C	758.12 µS/cm	3.78 mg/L	11.10 NTU	-99.9 mV	26.11 ft	200.00 ml/min
1/6/2025 11:45 AM	01:05:00	6.91 pH	17.37 °C	755.32 µS/cm	3.80 mg/L	10.50 NTU	-107.1 mV	26.11 ft	200.00 ml/min

1/6/2025 11:50 AM	01:10:00	6.90 pH	17.26 °C	757.15 µS/cm	3.80 mg/L	9.76 NTU	-106.6 mV	26.11 ft	200.00 ml/min
1/6/2025 11:51 AM	01:11:20	6.90 pH	17.35 °C	753.80 µS/cm	3.84 mg/L	--	-100.3 mV	26.11 ft	200.00 ml/min
1/6/2025 11:56 AM	01:16:20	6.91 pH	17.17 °C	758.62 µS/cm	3.86 mg/L	8.75 NTU	-106.4 mV	26.11 ft	200.00 ml/min
1/6/2025 12:01 PM	01:21:20	6.90 pH	17.08 °C	757.95 µS/cm	3.86 mg/L	8.14 NTU	-105.6 mV	26.11 ft	200.00 ml/min
1/6/2025 12:06 PM	01:26:20	6.90 pH	17.23 °C	756.50 µS/cm	3.82 mg/L	7.31 NTU	-106.8 mV	26.11 ft	200.00 ml/min
1/6/2025 12:11 PM	01:31:20	6.90 pH	17.23 °C	759.70 µS/cm	3.90 mg/L	7.02 NTU	-107.0 mV	26.11 ft	200.00 ml/min
1/6/2025 12:16 PM	01:36:20	6.90 pH	17.31 °C	760.53 µS/cm	3.96 mg/L	6.03 NTU	-107.3 mV	26.11 ft	200.00 ml/min
1/6/2025 12:21 PM	01:41:20	6.91 pH	17.23 °C	757.88 µS/cm	3.93 mg/L	6.03 NTU	-101.7 mV	26.11 ft	200.00 ml/min
1/6/2025 12:26 PM	01:46:20	6.91 pH	17.09 °C	757.92 µS/cm	3.98 mg/L	5.91 NTU	-106.8 mV	26.11 ft	200.00 ml/min
1/6/2025 12:31 PM	01:51:20	6.91 pH	17.14 °C	760.75 µS/cm	3.99 mg/L	5.53 NTU	-106.8 mV	26.11 ft	200.00 ml/min
1/6/2025 12:36 PM	01:56:20	6.90 pH	17.13 °C	760.72 µS/cm	4.01 mg/L	4.85 NTU	-106.7 mV	26.11 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-14	Grab.

Low-Flow Test Report:

Test Date / Time: 1/6/2025 1:28:26 PM
Project: GP-Plant Hammond
Operator Name: Thomas Kessler

Location Name: PT-15 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.2 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 10 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: -0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1082817
---	---	---

Test Notes:
Full app. III and IV and Major Ions. Ferrous Iron: 1.2 mg/L, Total Iron: 1.2 mg/L.

Weather Conditions:
Snowy, 40 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
1/6/2025 1:28 PM	00:00	6.79 pH	14.18 °C	651.10 µS/cm	3.75 mg/L	179.00 NTU	-50.3 mV	26.18 ft	200.00 ml/min
1/6/2025 1:33 PM	05:00	6.77 pH	15.91 °C	639.78 µS/cm	2.73 mg/L	194.00 NTU	-42.0 mV	26.18 ft	200.00 ml/min
1/6/2025 1:38 PM	10:00	6.77 pH	15.89 °C	646.81 µS/cm	2.25 mg/L	69.20 NTU	-37.6 mV	26.18 ft	200.00 ml/min
1/6/2025 1:43 PM	15:00	6.76 pH	15.93 °C	646.63 µS/cm	1.91 mg/L	58.10 NTU	-35.5 mV	26.18 ft	200.00 ml/min
1/6/2025 1:48 PM	20:00	6.76 pH	16.11 °C	648.00 µS/cm	1.62 mg/L	51.10 NTU	-47.2 mV	26.18 ft	200.00 ml/min
1/6/2025 1:53 PM	25:00	6.76 pH	15.97 °C	647.67 µS/cm	1.29 mg/L	14.80 NTU	-42.5 mV	26.18 ft	200.00 ml/min
1/6/2025 1:58 PM	30:00	6.75 pH	16.11 °C	648.18 µS/cm	0.93 mg/L	7.20 NTU	-29.6 mV	26.18 ft	200.00 ml/min
1/6/2025 2:03 PM	35:00	6.76 pH	16.15 °C	645.63 µS/cm	0.78 mg/L	5.32 NTU	-36.3 mV	26.18 ft	200.00 ml/min
1/6/2025 2:08 PM	40:00	6.75 pH	16.25 °C	645.31 µS/cm	0.65 mg/L	4.87 NTU	-35.1 mV	26.18 ft	200.00 ml/min
1/6/2025 2:13 PM	45:00	6.75 pH	16.27 °C	646.29 µS/cm	0.56 mg/L	4.01 NTU	-34.0 mV	26.18 ft	200.00 ml/min
1/6/2025 2:18 PM	50:00	6.76 pH	16.09 °C	643.69 µS/cm	0.48 mg/L	4.40 NTU	-24.4 mV	26.18 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-15	Grab.

Low-Flow Test Report:

Test Date / Time: 1/7/2025 1:22:52 PM
Project: GP-Plant Hammond
Operator Name: Thomas Kessler

Location Name: INW-03 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.4 ft Total Depth: 27.4 ft Initial Depth to Water: 12.72 ft	Pump Type: Peri Tubing Type: Polyethylene Pump Intake From TOC: 22.4 ft Estimated Total Volume Pumped: 3 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1082817
---	---	---

Test Notes:
Parameters.

Weather Conditions:
Clear, 30 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
1/7/2025 1:22 PM	00:00	6.28 pH	12.31 °C	529.25 µS/cm	1.63 mg/L	8.86 NTU	78.2 mV	12.72 ft	200.00 ml/min
1/7/2025 1:27 PM	05:00	6.32 pH	15.42 °C	589.67 µS/cm	0.28 mg/L	2.87 NTU	78.6 mV	12.72 ft	200.00 ml/min
1/7/2025 1:32 PM	10:00	6.44 pH	15.73 °C	598.29 µS/cm	0.17 mg/L	2.93 NTU	69.2 mV	12.74 ft	200.00 ml/min
1/7/2025 1:37 PM	15:00	6.46 pH	15.75 °C	600.20 µS/cm	0.11 mg/L	3.36 NTU	65.6 mV	12.74 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 1/6/2025 5:15:54 PM
Project: GP-Plant Hammond
Operator Name: Thomas Kessler

Location Name: INW-04 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 33.11 ft Total Depth: 43.11 ft Initial Depth to Water: 26.35 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 38.11 ft Estimated Total Volume Pumped: 3 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.2 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1082817
---	---	---

Test Notes:
Parameters.

Weather Conditions:
Cloudy, 30 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
1/6/2025 5:15 PM	00:00	6.26 pH	14.40 °C	557.95 µS/cm	0.51 mg/L	529.00 NTU	4.3 mV	26.55 ft	200.00 ml/min
1/6/2025 5:20 PM	05:00	6.32 pH	15.17 °C	575.00 µS/cm	0.24 mg/L	430.00 NTU	-13.0 mV	26.55 ft	200.00 ml/min
1/6/2025 5:25 PM	10:00	6.39 pH	15.26 °C	600.53 µS/cm	0.18 mg/L	204.00 NTU	-24.5 mV	26.55 ft	200.00 ml/min
1/6/2025 5:30 PM	15:00	6.43 pH	15.30 °C	607.43 µS/cm	0.13 mg/L	124.00 NTU	-30.4 mV	26.55 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 1/6/2025 4:40:30 PM
Project: GP-Plant Hammond
Operator Name: Thomas Kessler

Location Name: INW-05 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 31.6 ft Total Depth: 41.6 ft Initial Depth to Water: 26 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 36.6 ft Estimated Total Volume Pumped: 3 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.1 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1082817
--	--	---

Test Notes:
Parameters.

Weather Conditions:
Cloudy, 30 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
1/6/2025 4:40 PM	00:00	6.90 pH	12.57 °C	649.48 µS/cm	0.99 mg/L	340.00 NTU	-63.0 mV	26.00 ft	200.00 ml/min
1/6/2025 4:45 PM	05:00	6.85 pH	16.22 °C	653.97 µS/cm	0.34 mg/L	163.00 NTU	-84.3 mV	26.10 ft	200.00 ml/min
1/6/2025 4:50 PM	10:00	6.86 pH	16.67 °C	647.92 µS/cm	0.18 mg/L	129.00 NTU	-86.2 mV	26.10 ft	200.00 ml/min
1/6/2025 4:55 PM	15:00	6.85 pH	16.90 °C	640.46 µS/cm	0.17 mg/L	126.00 NTU	-87.1 mV	26.10 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 2/5/2025 11:54:31 AM
Project: GP-Plant Hammond
Operator Name: Tristan Halterman

Location Name: INW-03 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.40 ft Total Depth: 27.40 ft Initial Depth to Water: 13.62 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22.40 ft Estimated Total Volume Pumped: 3 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 965586
---	--	--

Test Notes:
Parameters.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
2/5/2025 11:54 AM	00:00	6.77 pH	22.53 °C	606.42 µS/cm	1.56 mg/L	4.23 NTU	87.5 mV	13.65 ft	200.00 ml/min
2/5/2025 11:59 AM	05:00	6.44 pH	19.51 °C	658.60 µS/cm	0.27 mg/L	3.65 NTU	95.7 mV	13.65 ft	200.00 ml/min
2/5/2025 12:04 PM	10:00	6.38 pH	19.40 °C	654.61 µS/cm	0.19 mg/L	6.26 NTU	84.1 mV	13.65 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 2/4/2025 2:47:02 PM
Project: GP-Plant Hammond
Operator Name: Tristan Halterman

Location Name: INW-04 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.30 ft Total Depth: 45.30 ft Initial Depth to Water: 26.60 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.30 ft Estimated Total Volume Pumped: 3 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.13 ft	Instrument Used: Aqua TROLL 400 Serial Number: 965586
---	--	--

Test Notes:
Parameters.

Weather Conditions:
Cloudy, 75 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
2/4/2025 2:47 PM	00:00	5.88 pH	20.93 °C	617.25 µS/cm	0.84 mg/L	++++	23.8 mV	26.65 ft	200.00 ml/min
2/4/2025 2:52 PM	05:00	6.12 pH	19.49 °C	666.65 µS/cm	0.41 mg/L	++++	23.2 mV	26.70 ft	200.00 ml/min
2/4/2025 2:57 PM	10:00	6.23 pH	19.27 °C	677.90 µS/cm	0.31 mg/L	92.20 NTU	26.2 mV	26.73 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 2/4/2025 1:07:33 PM
Project: GP-Plant Hammond
Operator Name: Zain Webb

Location Name: INW-05 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.30 ft Total Depth: 45.30 ft Initial Depth to Water: 26.17 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.30 ft Estimated Total Volume Pumped: 2.25 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 952637
--	--	--

Test Notes:
Parameters; Fe²⁺ = 4.5 mg/L.

Weather Conditions:
Sunny, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
2/4/2025 1:07 PM	00:00	6.96 pH	19.76 °C	776.82 µS/cm	0.15 mg/L	77.50 NTU	-115.2 mV	26.17 ft	150.00 ml/min
2/4/2025 1:12 PM	05:00	6.95 pH	19.68 °C	782.02 µS/cm	0.10 mg/L	63.90 NTU	-124.4 mV	26.21 ft	150.00 ml/min
2/4/2025 1:17 PM	10:00	6.96 pH	19.60 °C	783.71 µS/cm	0.07 mg/L	48.80 NTU	-118.9 mV	26.22 ft	150.00 ml/min
2/4/2025 1:22 PM	15:00	6.97 pH	19.55 °C	783.95 µS/cm	0.06 mg/L	35.90 NTU	-119.1 mV	26.22 ft	150.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 2/4/2025 11:10:51 AM
Project: GP-Plant Hammond
Operator Name: Zain Webb

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 37.75 ft Total Depth: 47.75 ft Initial Depth to Water: 26.93 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 42.75 ft Estimated Total Volume Pumped: 6.75 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 952637
---	--	--

Test Notes:
Six Bottles: Appendix III & IV + Major Ions; Fe²⁺ = 4.5 mg/L, Fe_T = 6.0 mg/L.

Weather Conditions:
Cloudy, 65 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
2/4/2025 11:10 AM	00:00	6.87 pH	18.73 °C	758.54 µS/cm	0.46 mg/L	11.60 NTU	-89.5 mV	26.93 ft	150.00 ml/min
2/4/2025 11:15 AM	05:00	6.87 pH	18.61 °C	761.84 µS/cm	0.26 mg/L	8.23 NTU	-90.9 mV	26.95 ft	150.00 ml/min
2/4/2025 11:20 AM	10:00	6.88 pH	18.60 °C	761.89 µS/cm	0.21 mg/L	5.14 NTU	-91.7 mV	26.97 ft	150.00 ml/min
2/4/2025 11:25 AM	15:00	6.88 pH	18.64 °C	763.00 µS/cm	0.17 mg/L	3.89 NTU	-92.9 mV	26.98 ft	150.00 ml/min
2/4/2025 11:30 AM	20:00	6.89 pH	18.61 °C	762.65 µS/cm	0.15 mg/L	2.75 NTU	-93.5 mV	26.98 ft	150.00 ml/min
2/4/2025 11:35 AM	25:00	6.89 pH	18.61 °C	760.88 µS/cm	0.14 mg/L	--	-102.1 mV	26.98 ft	150.00 ml/min
2/4/2025 11:40 AM	30:00	6.88 pH	18.66 °C	760.32 µS/cm	0.12 mg/L	--	-92.1 mV	26.98 ft	150.00 ml/min
2/4/2025 11:45 AM	35:00	6.89 pH	18.64 °C	760.16 µS/cm	0.11 mg/L	--	-92.2 mV	26.98 ft	150.00 ml/min
2/4/2025 11:50 AM	40:00	6.88 pH	18.64 °C	759.86 µS/cm	0.10 mg/L	1.21 NTU	-92.8 mV	26.98 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-07	Grab.

Low-Flow Test Report:

Test Date / Time: 2/4/2025 11:19:36 AM
Project: GP-Plant Hammond
Operator Name: Tristan Halterman

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 31.93 ft Total Depth: 41.93 ft Initial Depth to Water: 26.75 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 36.93 ft Estimated Total Volume Pumped: 29 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 965586
---	--	--

Test Notes:
Six Bottles: Appendix III & IV + Major Ions; Fe²⁺ = 1.0 mg/L, Fe_T = 1.0 mg/L.

Weather Conditions:
Cloudy, 60 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
2/4/2025 11:19 AM	00:00	6.50 pH	20.25 °C	642.14 µS/cm	0.30 mg/L	++++	65.4 mV	26.82 ft	200.00 ml/min
2/4/2025 11:24 AM	05:00	6.36 pH	19.05 °C	656.79 µS/cm	0.17 mg/L	++++	69.6 mV	26.82 ft	200.00 ml/min
2/4/2025 11:29 AM	10:00	6.33 pH	18.84 °C	664.19 µS/cm	0.13 mg/L	++++	66.1 mV	26.85 ft	200.00 ml/min
2/4/2025 11:34 AM	15:00	6.33 pH	18.76 °C	668.38 µS/cm	0.11 mg/L	97.80 NTU	67.0 mV	26.85 ft	200.00 ml/min
2/4/2025 11:39 AM	20:00	6.34 pH	18.81 °C	672.66 µS/cm	0.09 mg/L	65.30 NTU	67.4 mV	26.85 ft	200.00 ml/min
2/4/2025 11:44 AM	25:00	6.34 pH	18.74 °C	672.78 µS/cm	0.07 mg/L	51.10 NTU	73.5 mV	26.83 ft	200.00 ml/min
2/4/2025 11:49 AM	30:00	6.34 pH	18.74 °C	674.58 µS/cm	0.06 mg/L	39.00 NTU	68.5 mV	26.85 ft	200.00 ml/min
2/4/2025 11:54 AM	35:00	6.34 pH	18.77 °C	672.67 µS/cm	0.05 mg/L	32.30 NTU	68.7 mV	26.85 ft	200.00 ml/min
2/4/2025 11:59 AM	40:00	6.34 pH	18.76 °C	672.27 µS/cm	0.05 mg/L	28.40 NTU	68.8 mV	26.85 ft	200.00 ml/min
2/4/2025 12:04 PM	45:00	6.33 pH	19.05 °C	671.13 µS/cm	0.05 mg/L	23.70 NTU	69.1 mV	26.85 ft	200.00 ml/min
2/4/2025 12:09 PM	50:00	6.34 pH	19.23 °C	668.43 µS/cm	0.04 mg/L	23.00 NTU	68.4 mV	26.85 ft	200.00 ml/min
2/4/2025 12:14 PM	55:00	6.33 pH	19.28 °C	665.49 µS/cm	0.04 mg/L	21.20 NTU	69.2 mV	26.80 ft	200.00 ml/min
2/4/2025 12:19 PM	01:00:00	6.33 pH	19.27 °C	664.43 µS/cm	0.04 mg/L	16.80 NTU	74.0 mV	26.80 ft	200.00 ml/min

2/4/2025 12:24 PM	01:05:00	6.33 pH	19.29 °C	665.57 µS/cm	0.03 mg/L	15.10 NTU	68.3 mV	26.80 ft	200.00 ml/min
2/4/2025 12:29 AM	01:10:00	6.33 pH	19.32 °C	664.25 µS/cm	0.03 mg/L	14.10 NTU	68.1 mV	26.80 ft	200.00 ml/min
2/4/2025 12:34 PM	01:15:00	6.33 pH	19.32 °C	664.14 µS/cm	0.03 mg/L	14.30 NTU	73.4 mV	26.80 ft	200.00 ml/min
2/4/2025 12:39 PM	01:20:00	6.33 pH	19.32 °C	667.44 µS/cm	0.03 mg/L	12.50 NTU	67.4 mV	26.80 ft	200.00 ml/min
2/4/2025 12:44 PM	01:25:00	6.34 pH	19.32 °C	669.53 µS/cm	0.03 mg/L	9.52 NTU	67.1 mV	26.80 ft	200.00 ml/min
2/4/2025 12:49 PM	01:30:00	6.33 pH	19.29 °C	671.03 µS/cm	0.03 mg/L	9.08 NTU	72.3 mV	26.80 ft	200.00 ml/min
2/4/2025 12:54 PM	01:35:00	6.34 pH	19.32 °C	669.72 µS/cm	0.02 mg/L	7.73 NTU	65.9 mV	26.80 ft	200.00 ml/min
2/4/2025 12:59 PM	01:40:00	6.34 pH	19.28 °C	671.13 µS/cm	0.03 mg/L	8.02 NTU	71.1 mV	26.80 ft	200.00 ml/min
2/4/2025 1:04 PM	01:45:00	6.35 pH	19.30 °C	671.50 µS/cm	0.02 mg/L	7.49 NTU	65.0 mV	26.80 ft	200.00 ml/min
2/4/2025 1:09 PM	01:50:00	6.34 pH	19.32 °C	672.31 µS/cm	0.03 mg/L	6.82 NTU	64.5 mV	26.80 ft	200.00 ml/min
2/4/2025 1:14 PM	01:55:00	6.35 pH	19.33 °C	671.76 µS/cm	0.02 mg/L	6.07 NTU	63.4 mV	26.80 ft	200.00 ml/min
2/4/2025 1:19 PM	02:00:00	6.35 pH	19.31 °C	672.26 µS/cm	0.02 mg/L	6.37 NTU	68.5 mV	26.80 ft	200.00 ml/min
2/4/2025 1:24 PM	02:05:00	6.36 pH	19.31 °C	675.61 µS/cm	0.02 mg/L	5.43 NTU	62.8 mV	26.80 ft	200.00 ml/min
2/4/2025 1:29 PM	02:10:00	6.36 pH	19.25 °C	677.38 µS/cm	0.02 mg/L	5.17 NTU	62.1 mV	26.80 ft	200.00 ml/min
2/4/2025 1:34 PM	02:15:00	6.36 pH	19.17 °C	674.81 µS/cm	0.02 mg/L	4.76 NTU	61.5 mV	26.80 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.

Low-Flow Test Report:

Test Date / Time: 2/5/2024 10:41:48 AM
Project: GP-Plant Hammond
Operator Name: Tristan Halterman

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.47 ft Total Depth: 30.47 ft Initial Depth to Water: 16.89 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 25.47 ft Estimated Total Volume Pumped: 9 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.01 ft	Instrument Used: Aqua TROLL 400 Serial Number: 965586
---	---	--

Test Notes:
Six Bottles: Appendix III & IV + Major Ions; Fe²⁺ = 0 mg/L, Fe_T = 0 mg/L.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
2/5/2025 10:41 AM	00:00	6.87 pH	19.23 °C	698.30 µS/cm	1.00 mg/L	4.35 NTU	81.3 mV	16.90 ft	200.00 ml/min
2/5/2025 10:46 AM	05:00	6.70 pH	18.22 °C	715.08 µS/cm	0.24 mg/L	4.40 NTU	91.2 mV	16.90 ft	200.00 ml/min
2/5/2025 10:51 AM	10:00	6.67 pH	18.19 °C	705.74 µS/cm	0.17 mg/L	5.10 NTU	80.1 mV	16.90 ft	200.00 ml/min
2/5/2025 10:56 AM	15:00	6.67 pH	18.34 °C	706.23 µS/cm	0.15 mg/L	7.63 NTU	79.8 mV	16.90 ft	200.00 ml/min
2/5/2025 11:01 AM	20:00	6.67 pH	18.34 °C	694.51 µS/cm	0.13 mg/L	7.02 NTU	80.1 mV	16.90 ft	200.00 ml/min
2/5/2025 11:06 AM	25:00	6.69 pH	18.34 °C	695.80 µS/cm	0.12 mg/L	6.14 NTU	79.7 mV	16.90 ft	200.00 ml/min
2/5/2025 11:11 AM	30:00	6.68 pH	18.45 °C	689.31 µS/cm	0.11 mg/L	5.48 NTU	79.9 mV	16.90 ft	200.00 ml/min
2/5/2025 11:16 AM	35:00	6.68 pH	18.52 °C	693.51 µS/cm	0.10 mg/L	4.62 NTU	79.8 mV	16.90 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.

Low-Flow Test Report:

Test Date / Time: 2/5/2025 9:25:19 AM
Project: GP-Plant Hammond
Operator Name: Zain Webb

Location Name: PT-10 Well Diameter: 2 ft Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.45 ft Total Depth: 30.45 ft Initial Depth to Water: 16.97 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 25.45 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 952637
---	---	--

Test Notes:
Six Bottles: Appendix III & IV + Major Ions; Fe²⁺ = 0 mg/L, Fe_T = 1 mg/L.

Weather Conditions:
Overcast, 55 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
2/5/2025 9:25 AM	00:00	6.75 pH	17.58 °C	662.83 µS/cm	0.53 mg/L	6.78 NTU	135.1 mV	16.97 ft	200.00 ml/min
2/5/2025 9:30 AM	05:00	6.60 pH	17.74 °C	595.54 µS/cm	0.41 mg/L	4.21 NTU	115.1 mV	16.99 ft	200.00 ml/min
2/5/2025 9:35 AM	10:00	6.59 pH	17.85 °C	594.95 µS/cm	0.34 mg/L	2.57 NTU	71.1 mV	17.00 ft	200.00 ml/min
2/5/2025 9:40 AM	15:00	6.59 pH	17.81 °C	596.59 µS/cm	0.28 mg/L	2.16 NTU	59.7 mV	17.00 ft	200.00 ml/min
2/5/2025 9:45 AM	20:00	6.60 pH	17.85 °C	606.31 µS/cm	0.24 mg/L	1.73 NTU	69.0 mV	17.00 ft	200.00 ml/min
2/5/2025 9:50 AM	25:00	6.63 pH	17.91 °C	615.34 µS/cm	0.27 mg/L	1.92 NTU	27.3 mV	17.00 ft	200.00 ml/min
2/5/2025 9:55 AM	30:00	6.66 pH	17.90 °C	623.67 µS/cm	0.24 mg/L	1.49 NTU	13.2 mV	17.00 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.

Low-Flow Test Report:

Test Date / Time: 2/5/2024 9:11:08 AM
Project: GP-Plant Hammond
Operator Name: Tristan Halterman

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 16.90 ft Total Depth: 26.90 ft Initial Depth to Water: 13.46 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 21.90 ft Estimated Total Volume Pumped: 11 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 965586
---	--	--

Test Notes:
Six Bottles: Appendix III & IV + Major Ions; Fe²⁺ = 0.5 mg/L, Fe_T = 0.5 mg/L.

Weather Conditions:
Cloudy, 60 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
2/5/2025 9:11 AM	00:00	6.11 pH	17.38 °C	584.55 µS/cm	0.52 mg/L	6.15 NTU	75.7 mV	13.49 ft	200.00 ml/min
2/5/2025 9:16 AM	05:00	6.35 pH	17.59 °C	637.86 µS/cm	0.24 mg/L	3.51 NTU	87.3 mV	13.49 ft	200.00 ml/min
2/5/2025 9:21 AM	10:00	6.46 pH	17.67 °C	630.28 µS/cm	0.17 mg/L	2.14 NTU	80.3 mV	13.49 ft	200.00 ml/min
2/5/2025 9:26 AM	15:00	6.52 pH	17.72 °C	631.26 µS/cm	0.17 mg/L	2.03 NTU	80.4 mV	13.49 ft	200.00 ml/min
2/5/2025 9:31 AM	20:00	6.56 pH	17.67 °C	635.76 µS/cm	0.14 mg/L	1.69 NTU	80.6 mV	13.49 ft	200.00 ml/min
2/5/2025 9:36 AM	25:00	6.59 pH	17.79 °C	639.16 µS/cm	0.13 mg/L	1.41 NTU	90.6 mV	13.49 ft	200.00 ml/min
2/5/2025 9:41 AM	30:00	6.61 pH	17.85 °C	629.34 µS/cm	1.97 mg/L	1.39 NTU	80.9 mV	13.49 ft	200.00 ml/min
2/5/2025 9:46 AM	35:00	6.63 pH	17.87 °C	638.53 µS/cm	0.11 mg/L	1.50 NTU	80.6 mV	13.49 ft	200.00 ml/min
2/5/2025 9:51 AM	40:00	6.64 pH	17.84 °C	629.22 µS/cm	0.10 mg/L	1.51 NTU	80.8 mV	13.49 ft	200.00 ml/min
2/5/2025 9:56 AM	45:00	6.65 pH	17.91 °C	630.82 µS/cm	0.10 mg/L	2.26 NTU	80.6 mV	13.49 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

HAM-PT-11	Grab.
-----------	-------

Low-Flow Test Report:

Test Date / Time: 2/5/2025 10:56:01 AM
Project: GP-Plant Hammond
Operator Name: Zain Webb

Location Name: PT-12 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.30 ft Total Depth: 27.30 ft Initial Depth to Water: 13.41 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22.30 ft Estimated Total Volume Pumped: 9 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 952637
---	---	--

Test Notes:
Six Bottles: Appendix III & IV + Major Ions; Fe²⁺ = 0 mg/L, Fe_T = 4.0 mg/L.

Weather Conditions:
Overcast, 60 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
2/5/2025 10:56 AM	00:00	6.51 pH	18.79 °C	662.24 µS/cm	0.94 mg/L	12.90 NTU	73.6 mV	13.41 ft	200.00 ml/min
2/5/2025 11:01 AM	05:00	6.46 pH	18.57 °C	671.60 µS/cm	0.35 mg/L	7.47 NTU	64.4 mV	13.43 ft	200.00 ml/min
2/5/2025 11:06 AM	10:00	6.49 pH	18.52 °C	673.58 µS/cm	1.38 mg/L	5.21 NTU	84.2 mV	13.43 ft	200.00 ml/min
2/5/2025 11:11 AM	15:00	6.50 pH	18.66 °C	667.42 µS/cm	2.59 mg/L	5.28 NTU	61.4 mV	13.43 ft	200.00 ml/min
2/5/2025 11:16 AM	20:00	6.50 pH	18.71 °C	666.26 µS/cm	0.14 mg/L	5.03 NTU	60.7 mV	13.43 ft	200.00 ml/min
2/5/2025 11:21 AM	25:00	6.51 pH	18.90 °C	665.36 µS/cm	0.10 mg/L	4.68 NTU	58.3 mV	13.43 ft	200.00 ml/min
2/5/2025 11:26 AM	30:00	6.52 pH	18.96 °C	659.36 µS/cm	0.09 mg/L	4.47 NTU	57.7 mV	13.43 ft	200.00 ml/min
2/5/2025 11:31 AM	35:00	6.49 pH	18.92 °C	655.28 µS/cm	0.09 mg/L	4.32 NTU	58.0 mV	13.43 ft	200.00 ml/min
2/5/2025 11:36 AM	40:00	6.53 pH	18.97 °C	651.97 µS/cm	0.09 mg/L	3.89 NTU	55.9 mV	13.43 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-12	Grab.

Low-Flow Test Report:

Test Date / Time: 2/4/2025 9:10:15 AM
Project: GP-Plant Hammond
Operator Name: Zain Webb

Location Name: PT-13 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.30 ft Total Depth: 45.30 ft Initial Depth to Water: 26.45 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.30 ft Estimated Total Volume Pumped: 8.25 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.06 ft	Instrument Used: Aqua TROLL 400 Serial Number: 952637
---	--	--

Test Notes:
Six Bottles: Appendix III & IV + Major Ions; Fe²⁺ = 4.0 mg/L, Fe_T = 5.5 mg/L.

Weather Conditions:
Cloudy, 55 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
2/4/2025 9:10 AM	00:00	6.94 pH	17.81 °C	753.64 µS/cm	0.51 mg/L	49.90 NTU	-83.2 mV	26.45 ft	150.00 ml/min
2/4/2025 9:15 AM	05:00	6.82 pH	18.08 °C	748.97 µS/cm	0.32 mg/L	49.20 NTU	-99.6 mV	26.49 ft	150.00 ml/min
2/4/2025 9:20 AM	10:00	6.81 pH	18.17 °C	751.38 µS/cm	0.25 mg/L	35.80 NTU	-85.3 mV	26.50 ft	150.00 ml/min
2/4/2025 9:25 AM	15:00	6.83 pH	18.17 °C	753.63 µS/cm	0.21 mg/L	33.60 NTU	-87.7 mV	26.51 ft	150.00 ml/min
2/4/2025 9:30 AM	20:00	6.82 pH	18.23 °C	753.64 µS/cm	0.18 mg/L	19.50 NTU	-87.2 mV	26.51 ft	150.00 ml/min
2/4/2025 9:35 AM	25:00	6.82 pH	18.26 °C	753.72 µS/cm	0.16 mg/L	14.90 NTU	-86.9 mV	26.51 ft	150.00 ml/min
2/4/2025 9:40 AM	30:00	6.82 pH	18.26 °C	754.13 µS/cm	0.15 mg/L	13.10 NTU	-86.2 mV	26.51 ft	150.00 ml/min
2/4/2025 9:45 AM	35:00	6.82 pH	18.27 °C	754.67 µS/cm	0.13 mg/L	8.77 NTU	-86.6 mV	26.51 ft	150.00 ml/min
2/4/2025 9:50 AM	40:00	6.83 pH	18.30 °C	754.54 µS/cm	0.13 mg/L	5.98 NTU	-86.2 mV	26.51 ft	150.00 ml/min
2/4/2025 9:55 AM	45:00	6.83 pH	18.26 °C	753.52 µS/cm	0.15 mg/L	5.01 NTU	-85.3 mV	26.51 ft	150.00 ml/min
2/4/2025 10:00 AM	50:00	6.82 pH	18.27 °C	753.40 µS/cm	0.13 mg/L	4.90 NTU	-84.8 mV	26.51 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-13	Grab.

Low-Flow Test Report:

Test Date / Time: 2/4/2025 9:03:48 AM
Project: GP-Plant Hammond
Operator Name: Tristan Halterman

Location Name: PT-14 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.30 ft Total Depth: 45.30 ft Initial Depth to Water: 26.45 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.30 ft Estimated Total Volume Pumped: 14 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.10 ft	Instrument Used: Aqua TROLL 400 Serial Number: 965586
---	--	--

Test Notes:
Six Bottles: Appendix III & IV + Major Ions; Fe²⁺ = 5.5 mg/L, Fe_T = 6.5 mg/L.

Weather Conditions:
Sunny, 55 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
2/4/2025 9:03 AM	00:00	6.34 pH	18.34 °C	789.39 µS/cm	0.35 mg/L	86.50 NTU	-42.0 mV	26.60 ft	200.00 ml/min
2/4/2025 9:08 AM	05:00	6.54 pH	18.28 °C	787.99 µS/cm	0.25 mg/L	60.70 NTU	-55.9 mV	26.60 ft	200.00 ml/min
2/4/2025 9:13 AM	10:00	6.63 pH	18.34 °C	789.13 µS/cm	0.21 mg/L	48.20 NTU	-57.6 mV	26.58 ft	200.00 ml/min
2/4/2025 9:18 AM	15:00	6.69 pH	18.34 °C	790.00 µS/cm	0.15 mg/L	34.00 NTU	-61.3 mV	26.58 ft	200.00 ml/min
2/4/2025 9:23 AM	20:00	6.72 pH	18.30 °C	789.74 µS/cm	0.14 mg/L	26.00 NTU	-64.0 mV	26.58 ft	200.00 ml/min
2/4/2025 9:28 AM	25:00	6.74 pH	18.30 °C	789.24 µS/cm	0.12 mg/L	21.20 NTU	-66.1 mV	26.55 ft	200.00 ml/min
2/4/2025 9:33 AM	30:00	6.75 pH	18.33 °C	789.84 µS/cm	0.10 mg/L	15.90 NTU	-67.5 mV	26.55 ft	200.00 ml/min
2/4/2025 9:38 AM	35:00	6.77 pH	18.26 °C	790.02 µS/cm	0.09 mg/L	12.00 NTU	-68.6 mV	26.55 ft	200.00 ml/min
2/4/2025 9:43 AM	40:00	6.78 pH	18.23 °C	790.13 µS/cm	0.08 mg/L	11.10 NTU	-69.5 mV	26.55 ft	200.00 ml/min
2/4/2025 9:48 AM	45:00	6.79 pH	18.25 °C	790.01 µS/cm	0.08 mg/L	7.13 NTU	-70.8 mV	26.55 ft	200.00 ml/min
2/4/2025 9:53 AM	50:00	6.80 pH	18.24 °C	790.11 µS/cm	0.06 mg/L	6.41 NTU	-70.9 mV	26.55 ft	200.00 ml/min
2/4/2025 9:58 AM	55:00	6.81 pH	18.22 °C	790.36 µS/cm	0.07 mg/L	5.53 NTU	-71.6 mV	26.55 ft	200.00 ml/min
2/4/2025 10:03 AM	01:00:00	6.81 pH	18.25 °C	790.08 µS/cm	0.06 mg/L	3.72 NTU	-71.6 mV	26.55 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-14	Grab.
HAM-AP1-FD-01	Grab.

Low-Flow Test Report:

Test Date / Time: 2/4/2025 2:15:19 PM
Project: GP-Plant Hammond
Operator Name: Zain Webb

Location Name: PT-15 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.30 ft Total Depth: 45.30 ft Initial Depth to Water: 26.33 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.30 ft Estimated Total Volume Pumped: 6 liter Flow Cell Volume: 90 ml Final Flow Rate: 150 ml/min Final Draw Down: 0.04 ft	Instrument Used: Aqua TROLL 400 Serial Number: 952637
---	---	--

Test Notes:
Six Bottles: Appendix III & IV + Major Ions; Fe²⁺ = 2.5 mg/L, Fe_T = 5.5 mg/L.

Weather Conditions:
Sunny, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
2/4/2025 2:15 PM	00:00	6.94 pH	21.49 °C	710.72 µS/cm	0.65 mg/L	31.40 NTU	-47.6 mV	26.33 ft	150.00 ml/min
2/4/2025 2:20 PM	05:00	6.85 pH	19.98 °C	746.54 µS/cm	0.30 mg/L	25.90 NTU	-46.8 mV	26.34 ft	150.00 ml/min
2/4/2025 2:25 PM	10:00	6.83 pH	19.78 °C	748.76 µS/cm	0.21 mg/L	23.70 NTU	-46.8 mV	26.35 ft	150.00 ml/min
2/4/2025 2:30 PM	15:00	6.82 pH	19.73 °C	749.28 µS/cm	0.17 mg/L	17.00 NTU	-48.0 mV	26.37 ft	150.00 ml/min
2/4/2025 2:35 PM	20:00	6.81 pH	19.68 °C	748.47 µS/cm	0.15 mg/L	9.13 NTU	-48.1 mV	26.37 ft	150.00 ml/min
2/4/2025 2:40 PM	25:00	6.81 pH	19.67 °C	747.76 µS/cm	0.13 mg/L	7.42 NTU	-47.3 mV	26.37 ft	150.00 ml/min
2/4/2025 2:45 PM	30:00	6.80 pH	19.68 °C	746.58 µS/cm	0.11 mg/L	6.26 NTU	-47.3 mV	26.37 ft	150.00 ml/min
2/4/2025 2:50 PM	35:00	6.79 pH	19.68 °C	748.89 µS/cm	0.11 mg/L	2.75 NTU	-47.4 mV	26.37 ft	150.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-15	Grab.

Low-Flow Test Report:

Test Date / Time: 3/6/2025 10:19:23 AM
Project: GP-Plant Hammond
Operator Name: Z. Webb

Location Name: INW-03 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.40 ft Total Depth: 27.40 ft Initial Depth to Water: 13.59 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22.40 ft Estimated Total Volume Pumped: 3 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1167968
--	--	---

Test Notes:
Parameters; Fe²⁺ = 0 mg/L, Fe_T = 1.0 mg/L.

Weather Conditions:
Clear, 55 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
3/6/2025 10:19 AM	00:00	6.98 pH	17.08 °C	823.63 µS/cm	0.64 mg/L	5.59 NTU	-9.6 mV	13.59 ft	200.00 ml/min
3/6/2025 10:24 AM	05:00	6.96 pH	17.02 °C	814.57 µS/cm	0.42 mg/L	5.21 NTU	-3.6 mV	13.59 ft	200.00 ml/min
3/6/2025 10:29 AM	10:00	7.02 pH	17.09 °C	824.82 µS/cm	0.39 mg/L	5.44 NTU	-5.5 mV	13.59 ft	200.00 ml/min
3/6/2025 10:34 AM	15:00	7.01 pH	17.27 °C	816.91 µS/cm	0.56 mg/L	5.50 NTU	-3.6 mV	13.59 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 3/5/2025 1:42:26 PM
Project: GP-Plant Hammond
Operator Name: Z. Webb

Location Name: INW-04 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.30 ft Total Depth: 45.30 ft Initial Depth to Water: 26.10 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.30 ft Estimated Total Volume Pumped: 3 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.12 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1167968
---	--	---

Test Notes:
Parameters; Fe²⁺ = 3.0 mg/L, Fe_T = 5.5 mg/L.

Weather Conditions:
Cloudy, 50 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
3/5/2025 1:42 PM	00:00	6.43 pH	17.14 °C	589.26 µS/cm	1.57 mg/L	++++	21.6 mV	26.10 ft	200.00 ml/min
3/5/2025 1:47 PM	05:00	6.56 pH	17.79 °C	562.05 µS/cm	2.98 mg/L	++++	21.1 mV	26.19 ft	200.00 ml/min
3/5/2025 1:52 PM	10:00	6.61 pH	17.77 °C	580.40 µS/cm	3.29 mg/L	++++	13.2 mV	26.22 ft	200.00 ml/min
3/5/2025 1:57 PM	15:00	6.63 pH	17.63 °C	569.95 µS/cm	3.29 mg/L	++++	6.2 mV	26.22 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 3/5/2025 4:03:02 PM
Project: GP-Plant Hammond
Operator Name: T. Kessler

Location Name: INW-05 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.30 ft Total Depth: 45.30 ft Initial Depth to Water: 25.75 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.30 ft Estimated Total Volume Pumped: 4 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.05 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1146036
--	---	---

Test Notes:
Parameters; Fe²⁺ = 3.0 mg/L, Fe_T = 3.0 mg/L.

Weather Conditions:
Cloudy, 55 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
3/5/2025 4:03 PM	00:00	6.97 pH	16.56 °C	744.67 µS/cm	0.36 mg/L	365.00 NTU	-18.8 mV	25.80 ft	200.00 ml/min
3/5/2025 4:08 PM	05:00	6.96 pH	16.82 °C	741.68 µS/cm	0.27 mg/L	347.00 NTU	4.7 mV	25.80 ft	200.00 ml/min
3/5/2025 4:13 PM	10:00	6.98 pH	16.79 °C	748.15 µS/cm	0.24 mg/L	315.00 NTU	-28.5 mV	25.80 ft	200.00 ml/min
3/5/2025 4:18 PM	15:00	7.00 pH	16.65 °C	755.09 µS/cm	0.21 mg/L	74.50 NTU	-45.7 mV	25.80 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 3/5/2025 2:57:21 PM
Project: GP-Plant Hammond
Operator Name: T. Kessler

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 37.75 ft Total Depth: 47.75 ft Initial Depth to Water: 26.60 ft	Pump Type: Bladder Tubing Type: Poly Pump Intake From TOC: 42.75 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1146036
---	--	---

Test Notes:
Six Bottles: Appendix III & IV + Major Ions; Fe²⁺ = 3.4 mg/L, Fe_T = 5.0 mg/L.

Weather Conditions:
Rainy, 55 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
3/5/2025 2:57 PM	00:00	6.94 pH	16.31 °C	739.62 µS/cm	3.85 mg/L	1.97 NTU	118.3 mV	26.60 ft	200.00 ml/min
3/5/2025 3:02 PM	05:00	6.93 pH	17.08 °C	747.93 µS/cm	1.22 mg/L	1.07 NTU	278.9 mV	26.60 ft	200.00 ml/min
3/5/2025 3:07 PM	10:00	6.93 pH	17.33 °C	748.67 µS/cm	0.99 mg/L	1.21 NTU	201.1 mV	26.60 ft	200.00 ml/min
3/5/2025 3:12 PM	15:00	6.93 pH	17.41 °C	747.60 µS/cm	0.88 mg/L	0.81 NTU	134.5 mV	26.60 ft	200.00 ml/min
3/5/2025 3:17 PM	20:00	6.94 pH	17.44 °C	746.94 µS/cm	0.81 mg/L	0.72 NTU	104.0 mV	26.60 ft	200.00 ml/min
3/5/2025 3:22 PM	25:00	6.94 pH	17.40 °C	747.01 µS/cm	0.74 mg/L	0.53 NTU	85.4 mV	26.60 ft	200.00 ml/min
3/5/2025 3:27 PM	30:00	6.94 pH	17.38 °C	747.64 µS/cm	0.70 mg/L	0.40 NTU	70.4 mV	26.60 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-07	Grab.

Low-Flow Test Report:

Test Date / Time: 3/5/2025 2:49:54 PM
Project: GP-Plant Hammond
Operator Name: Z. Webb

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 31.93 ft Total Depth: 41.93 ft Initial Depth to Water: 26.27 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 36.93 ft Estimated Total Volume Pumped: 11 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.04 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1167968
---	--	---

Test Notes:
Six Bottles: Appendix III & IV + Major Ions; Fe²⁺ = 0.5 mg/L, Fe_T = 0.5 mg/L.

Weather Conditions:
Cloudy, 50 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
3/5/2025 2:49 PM	00:00	6.42 pH	17.41 °C	685.82 µS/cm	0.56 mg/L	++++	71.0 mV	26.27 ft	200.00 ml/min
3/5/2025 2:54 PM	05:00	6.45 pH	17.56 °C	696.23 µS/cm	0.41 mg/L	49.20 NTU	74.0 mV	26.31 ft	200.00 ml/min
3/5/2025 2:59 PM	10:00	6.47 pH	17.48 °C	699.53 µS/cm	0.40 mg/L	33.80 NTU	60.6 mV	26.31 ft	200.00 ml/min
3/5/2025 3:04 PM	15:00	6.49 pH	17.60 °C	701.34 µS/cm	0.37 mg/L	24.50 NTU	57.2 mV	26.31 ft	200.00 ml/min
3/5/2025 3:09 PM	20:00	6.50 pH	17.63 °C	701.83 µS/cm	0.41 mg/L	19.30 NTU	56.9 mV	26.31 ft	200.00 ml/min
3/5/2025 3:14 PM	25:00	6.50 pH	17.64 °C	701.90 µS/cm	0.34 mg/L	14.60 NTU	56.7 mV	26.31 ft	200.00 ml/min
3/5/2025 3:19 PM	30:00	6.52 pH	17.63 °C	703.49 µS/cm	0.31 mg/L	10.10 NTU	53.8 mV	26.31 ft	200.00 ml/min
3/5/2025 3:24 PM	35:00	6.51 pH	17.71 °C	697.08 µS/cm	0.23 mg/L	8.27 NTU	55.4 mV	26.31 ft	200.00 ml/min
3/5/2025 3:29 PM	40:00	6.51 pH	17.64 °C	687.82 µS/cm	0.18 mg/L	6.94 NTU	54.8 mV	26.31 ft	200.00 ml/min
3/5/2025 3:34 PM	45:00	6.52 pH	17.65 °C	701.16 µS/cm	0.15 mg/L	5.18 NTU	53.8 mV	26.31 ft	200.00 ml/min
3/5/2025 3:39 PM	50:00	6.53 pH	17.66 °C	698.87 µS/cm	0.20 mg/L	4.05 NTU	52.9 mV	26.31 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.

Low-Flow Test Report:

Test Date / Time: 3/6/2025 8:44:14 AM
Project: GP-Plant Hammond
Operator Name: T. Kessler

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.47 ft Total Depth: 30.47 ft Initial Depth to Water: 16.85 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 25.47 ft Estimated Total Volume Pumped: 13 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1146036
--	---	---

Test Notes:
Six Bottles: Appendix III & IV + Major Ions; Fe²⁺ = 0.75 mg/L, Fe_T = 0.75 mg/L.

Weather Conditions:
Sunny, 38 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
3/6/2025 8:44 AM	00:00	6.77 pH	15.39 °C	754.52 µS/cm	0.41 mg/L	133.00 NTU	113.7 mV	16.88 ft	200.00 ml/min
3/6/2025 8:49 AM	05:00	6.76 pH	15.65 °C	746.74 µS/cm	0.21 mg/L	19.00 NTU	415.0 mV	16.88 ft	200.00 ml/min
3/6/2025 8:54 AM	10:00	6.76 pH	15.63 °C	738.83 µS/cm	0.17 mg/L	11.30 NTU	396.7 mV	16.88 ft	200.00 ml/min
3/6/2025 8:59 AM	15:00	6.78 pH	15.92 °C	739.77 µS/cm	0.15 mg/L	11.60 NTU	407.7 mV	16.88 ft	200.00 ml/min
3/6/2025 9:04 AM	20:00	6.75 pH	16.21 °C	735.54 µS/cm	0.13 mg/L	10.10 NTU	416.4 mV	16.88 ft	200.00 ml/min
3/6/2025 9:09 AM	25:00	6.79 pH	16.44 °C	736.14 µS/cm	0.12 mg/L	12.10 NTU	426.8 mV	16.88 ft	200.00 ml/min
3/6/2025 9:14 AM	30:00	6.78 pH	16.08 °C	741.98 µS/cm	0.12 mg/L	10.80 NTU	495.8 mV	16.88 ft	200.00 ml/min
3/6/2025 9:19 AM	35:00	6.79 pH	15.81 °C	734.50 µS/cm	0.12 mg/L	9.38 NTU	442.4 mV	16.88 ft	200.00 ml/min
3/6/2025 9:24 AM	40:00	6.80 pH	15.29 °C	734.83 µS/cm	0.11 mg/L	9.52 NTU	446.0 mV	16.88 ft	200.00 ml/min
3/6/2025 9:29 AM	45:00	6.80 pH	15.59 °C	735.99 µS/cm	0.12 mg/L	12.40 NTU	436.6 mV	16.88 ft	200.00 ml/min
3/6/2025 9:34 AM	50:00	6.79 pH	16.07 °C	736.97 µS/cm	0.11 mg/L	7.93 NTU	427.1 mV	16.88 ft	200.00 ml/min
3/6/2025 9:39 AM	55:00	6.80 pH	16.44 °C	736.67 µS/cm	0.11 mg/L	6.73 NTU	414.2 mV	16.88 ft	200.00 ml/min
3/6/2025 9:44 AM	01:00:00	6.81 pH	16.48 °C	733.89 µS/cm	0.10 mg/L	4.73 NTU	407.0 mV	16.88 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.

Low-Flow Test Report:

Test Date / Time: 3/6/2025 8:41:25 AM
Project: GP-Plant Hammond
Operator Name: Z. Webb

Location Name: PT-10 Well Diameter: 2 ft Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.45 ft Total Depth: 30.45 ft Initial Depth to Water: 6.94 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 25.45 ft Estimated Total Volume Pumped: 9 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1167968
--	---	---

Test Notes:
Six Bottles: Appendix III & IV + Major Ions; Fe²⁺ = 0 mg/L, Fe_T = 0 mg/L.

Weather Conditions:
Cloudy, 50 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
3/6/2025 8:41 AM	00:00	6.50 pH	15.37 °C	592.01 µS/cm	0.45 mg/L	6.92 NTU	84.2 mV	6.94 ft	200.00 ml/min
3/6/2025 8:46 AM	05:00	6.51 pH	15.16 °C	591.56 µS/cm	0.33 mg/L	3.24 NTU	107.1 mV	6.96 ft	200.00 ml/min
3/6/2025 8:51 AM	10:00	6.52 pH	15.25 °C	590.95 µS/cm	0.44 mg/L	2.94 NTU	73.7 mV	6.96 ft	200.00 ml/min
3/6/2025 8:56 AM	15:00	6.64 pH	15.37 °C	661.94 µS/cm	0.45 mg/L	2.85 NTU	14.5 mV	6.96 ft	200.00 ml/min
3/6/2025 9:01 AM	20:00	6.69 pH	15.69 °C	684.23 µS/cm	0.35 mg/L	2.41 NTU	2.9 mV	6.96 ft	200.00 ml/min
3/6/2025 9:06 AM	25:00	6.69 pH	15.83 °C	681.77 µS/cm	0.44 mg/L	2.08 NTU	2.0 mV	6.96 ft	200.00 ml/min
3/6/2025 9:11 AM	30:00	6.72 pH	15.80 °C	684.66 µS/cm	0.46 mg/L	1.92 NTU	-0.9 mV	6.96 ft	200.00 ml/min
3/6/2025 9:16 AM	35:00	6.74 pH	15.90 °C	691.04 µS/cm	0.42 mg/L	1.69 NTU	-4.9 mV	6.96 ft	200.00 ml/min
3/6/2025 9:21 AM	40:00	6.71 pH	15.74 °C	672.95 µS/cm	0.43 mg/L	0.78 NTU	1.5 mV	6.96 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.

Low-Flow Test Report:

Test Date / Time: 3/6/2025 10:33:28 AM
Project: GP-Plant Hammond
Operator Name: T. Kessler

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 16.90 ft Total Depth: 26.90 ft Initial Depth to Water: 13.50 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 21.90 ft Estimated Total Volume Pumped: 10 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1146036
---	---	---

Test Notes:
Six Bottles: Appendix III & IV + Major Ions; Fe²⁺ = 0 mg/L, Fe_T = 0 mg/L.

Weather Conditions:
Clear, 40 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
3/6/2025 10:33 AM	00:00	6.81 pH	16.61 °C	640.71 µS/cm	0.24 mg/L	12.70 NTU	154.5 mV	13.50 ft	200.00 ml/min
3/6/2025 10:38 AM	05:00	6.81 pH	16.88 °C	638.53 µS/cm	0.18 mg/L	10.90 NTU	558.4 mV	13.50 ft	200.00 ml/min
3/6/2025 10:43 AM	10:00	6.84 pH	16.86 °C	640.78 µS/cm	0.15 mg/L	8.77 NTU	515.5 mV	13.50 ft	200.00 ml/min
3/6/2025 10:48 AM	15:00	6.85 pH	17.15 °C	640.20 µS/cm	0.14 mg/L	10.80 NTU	503.0 mV	13.50 ft	200.00 ml/min
3/6/2025 10:53 AM	20:00	6.85 pH	17.26 °C	633.06 µS/cm	0.13 mg/L	8.20 NTU	498.1 mV	13.50 ft	200.00 ml/min
3/6/2025 10:58 AM	25:00	6.86 pH	17.22 °C	631.38 µS/cm	0.12 mg/L	8.46 NTU	500.5 mV	13.50 ft	200.00 ml/min
3/6/2025 11:03 AM	30:00	6.86 pH	17.20 °C	637.55 µS/cm	0.11 mg/L	6.85 NTU	498.4 mV	13.50 ft	200.00 ml/min
3/6/2025 11:08 AM	35:00	6.88 pH	17.25 °C	635.61 µS/cm	0.11 mg/L	5.63 NTU	489.4 mV	13.50 ft	200.00 ml/min
3/6/2025 11:13 AM	40:00	6.86 pH	17.06 °C	640.85 µS/cm	0.12 mg/L	5.34 NTU	478.0 mV	13.50 ft	200.00 ml/min
3/6/2025 11:18 AM	45:00	6.86 pH	17.06 °C	633.63 µS/cm	0.12 mg/L	4.20 NTU	449.5 mV	13.50 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

HAM-PT-11	Grab.
-----------	-------

Low-Flow Test Report:

Test Date / Time: 3/6/2025 11:53:34 AM
Project: GP-Plant Hammond
Operator Name: T. Kessler

Location Name: PT-12 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.30 ft Total Depth: 27.30 ft Initial Depth to Water: 13.35 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22.30 ft Estimated Total Volume Pumped: 9 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1146036
---	--	---

Test Notes:
Six Bottles: Appendix III & IV + Major Ions; Fe²⁺ = 0 mg/L, Fe_T = 0 mg/L.

Weather Conditions:
Sunny, 45 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
3/6/2025 11:53 AM	00:00	6.36 pH	17.33 °C	636.22 µS/cm	0.58 mg/L	48.20 NTU	212.9 mV	13.35 ft	200.00 ml/min
3/6/2025 11:58 AM	05:00	6.33 pH	17.06 °C	646.73 µS/cm	0.21 mg/L	47.50 NTU	658.8 mV	13.35 ft	200.00 ml/min
3/6/2025 12:03 PM	10:00	6.38 pH	17.33 °C	644.71 µS/cm	0.17 mg/L	44.30 NTU	573.5 mV	13.35 ft	200.00 ml/min
3/6/2025 12:08 PM	15:00	6.41 pH	17.24 °C	651.78 µS/cm	0.15 mg/L	38.90 NTU	536.7 mV	13.35 ft	200.00 ml/min
3/6/2025 12:13 PM	20:00	6.42 pH	17.28 °C	655.22 µS/cm	0.13 mg/L	16.30 NTU	500.0 mV	13.35 ft	200.00 ml/min
3/6/2025 12:18 PM	25:00	6.45 pH	17.23 °C	660.55 µS/cm	0.12 mg/L	8.14 NTU	476.8 mV	13.35 ft	200.00 ml/min
3/6/2025 12:23 PM	30:00	6.45 pH	17.25 °C	656.14 µS/cm	0.11 mg/L	6.65 NTU	459.0 mV	13.35 ft	200.00 ml/min
3/6/2025 12:28 PM	35:00	6.47 pH	17.11 °C	661.02 µS/cm	0.10 mg/L	5.05 NTU	443.1 mV	13.35 ft	200.00 ml/min
3/6/2025 12:33 PM	40:00	6.47 pH	17.28 °C	660.11 µS/cm	0.11 mg/L	4.71 NTU	431.4 mV	13.35 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-12	Grab.

Low-Flow Test Report:

Test Date / Time: 3/5/2025 10:39:35 AM
Project: GP-Plant Hammond
Operator Name: T. Kessler

Location Name: PT-13 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.30 ft Total Depth: 45.30 ft Initial Depth to Water: 25.98 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.30 ft Estimated Total Volume Pumped: 20 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.07 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1146036
--	---	---

Test Notes:
Six Bottles: Appendix III & IV + Major Ions; Fe²⁺ = 5.2 mg/L, Fe_T = 5.2 mg/L.

Weather Conditions:
Cloudy, 55 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
3/5/2025 10:39 AM	00:00	6.89 pH	17.86 °C	737.30 µS/cm	3.32 mg/L	73.40 NTU	178.3 mV	26.05 ft	200.00 ml/min
3/5/2025 10:44 AM	05:00	6.91 pH	18.00 °C	750.22 µS/cm	1.39 mg/L	70.00 NTU	418.2 mV	26.05 ft	200.00 ml/min
3/5/2025 10:49 AM	10:00	6.91 pH	18.08 °C	747.35 µS/cm	1.73 mg/L	22.20 NTU	518.5 mV	26.05 ft	200.00 ml/min
3/5/2025 10:54 AM	15:00	6.91 pH	18.14 °C	750.77 µS/cm	2.81 mg/L	15.40 NTU	560.0 mV	26.05 ft	200.00 ml/min
3/5/2025 10:59 AM	20:00	6.90 pH	18.09 °C	727.77 µS/cm	1.20 mg/L	10.33 NTU	590.2 mV	26.05 ft	200.00 ml/min
3/5/2025 11:04 AM	25:00	6.90 pH	18.13 °C	744.30 µS/cm	1.34 mg/L	9.13 NTU	611.2 mV	26.05 ft	200.00 ml/min
3/5/2025 11:09 AM	30:00	6.90 pH	18.10 °C	746.44 µS/cm	1.62 mg/L	7.02 NTU	622.3 mV	26.05 ft	200.00 ml/min
3/5/2025 11:14 AM	35:00	6.91 pH	18.09 °C	744.57 µS/cm	1.25 mg/L	6.31 NTU	625.9 mV	26.05 ft	200.00 ml/min
3/5/2025 11:19 AM	40:00	6.91 pH	17.96 °C	747.33 µS/cm	1.03 mg/L	5.73 NTU	623.7 mV	26.05 ft	200.00 ml/min
3/5/2025 11:24 AM	45:00	6.90 pH	17.88 °C	752.08 µS/cm	1.31 mg/L	5.19 NTU	611.4 mV	26.05 ft	200.00 ml/min
3/5/2025 11:29 AM	50:00	6.91 pH	17.83 °C	756.94 µS/cm	2.11 mg/L	4.99 NTU	583.9 mV	26.05 ft	200.00 ml/min
3/5/2025 11:34 AM	55:00	6.91 pH	17.84 °C	756.47 µS/cm	2.02 mg/L	4.52 NTU	543.8 mV	26.05 ft	200.00 ml/min
3/5/2025 11:39 AM	01:00:00	6.92 pH	17.79 °C	750.56 µS/cm	2.95 mg/L	4.31 NTU	503.7 mV	26.05 ft	200.00 ml/min

3/5/2025 11:44 AM	01:05:00	6.92 pH	17.87 °C	749.82 µS/cm	1.49 mg/L	3.69 NTU	464.7 mV	26.05 ft	200.00 ml/min
3/5/2025 11:49 AM	01:10:00	6.92 pH	18.05 °C	748.78 µS/cm	0.99 mg/L	3.71 NTU	439.0 mV	26.05 ft	200.00 ml/min
3/5/2025 11:54 AM	01:15:00	6.93 pH	18.05 °C	750.36 µS/cm	0.68 mg/L	3.41 NTU	429.2 mV	26.05 ft	200.00 ml/min
3/5/2025 11:59 AM	01:20:00	6.93 pH	18.02 °C	752.11 µS/cm	0.42 mg/L	3.57 NTU	382.1 mV	26.05 ft	200.00 ml/min
3/5/2025 12:04 PM	01:25:00	6.93 pH	17.88 °C	750.76 µS/cm	0.28 mg/L	3.73 NTU	370.7 mV	26.05 ft	200.00 ml/min
3/5/2025 12:09 PM	01:30:00	6.93 pH	17.91 °C	752.17 µS/cm	0.20 mg/L	3.71 NTU	356.9 mV	26.05 ft	200.00 ml/min
3/5/2025 12:14 PM	01:35:00	6.93 pH	17.89 °C	750.54 µS/cm	0.16 mg/L	3.82 NTU	335.0 mV	26.05 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-13	Grab.

Low-Flow Test Report:

Test Date / Time: 3/5/2025 11:04:09 AM
Project: GP-Plant Hammond
Operator Name: Z. Webb

Location Name: PT-14 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.30 ft Total Depth: 45.30 ft Initial Depth to Water: 26.00 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.30 ft Estimated Total Volume Pumped: 18 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.03 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1167968
---	--	---

Test Notes:
Six Bottles: Appendix III & IV + Major Ions; Fe²⁺ = 3.5 mg/L, Fe_T = 7.0 mg/L.

Weather Conditions:
Clear, 50 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
3/5/2025 11:04 AM	00:00	6.91 pH	18.00 °C	744.45 µS/cm	3.00 mg/L	36.50 NTU	-30.5 mV	26.00 ft	200.00 ml/min
3/5/2025 11:09 AM	05:00	6.92 pH	18.16 °C	741.30 µS/cm	3.01 mg/L	24.00 NTU	-50.3 mV	26.03 ft	200.00 ml/min
3/5/2025 11:14 AM	10:00	6.93 pH	18.12 °C	737.50 µS/cm	2.25 mg/L	20.60 NTU	-52.6 mV	26.03 ft	200.00 ml/min
3/5/2025 11:19 AM	15:00	6.95 pH	18.02 °C	734.64 µS/cm	3.08 mg/L	15.40 NTU	-62.7 mV	26.03 ft	200.00 ml/min
3/5/2025 11:24 AM	20:00	6.95 pH	17.92 °C	726.19 µS/cm	2.60 mg/L	12.60 NTU	-62.5 mV	26.03 ft	200.00 ml/min
3/5/2025 11:29 AM	25:00	6.96 pH	17.86 °C	730.03 µS/cm	2.82 mg/L	11.30 NTU	-69.6 mV	26.03 ft	200.00 ml/min
3/5/2025 11:34 AM	30:00	6.96 pH	17.87 °C	724.88 µS/cm	2.70 mg/L	9.95 NTU	-70.6 mV	26.03 ft	200.00 ml/min
3/5/2025 11:39 AM	35:00	6.97 pH	17.80 °C	728.06 µS/cm	2.79 mg/L	7.53 NTU	-75.5 mV	26.03 ft	200.00 ml/min
3/5/2025 11:44 AM	40:00	6.98 pH	17.86 °C	730.65 µS/cm	2.80 mg/L	6.49 NTU	-75.3 mV	26.03 ft	200.00 ml/min
3/5/2025 11:49 AM	45:00	6.98 pH	18.03 °C	732.78 µS/cm	2.47 mg/L	5.77 NTU	-74.5 mV	26.03 ft	200.00 ml/min
3/5/2025 11:54 AM	50:00	6.98 pH	18.07 °C	726.31 µS/cm	2.15 mg/L	5.86 NTU	-80.6 mV	26.03 ft	200.00 ml/min
3/5/2025 11:59 AM	55:00	6.99 pH	18.06 °C	709.29 µS/cm	2.63 mg/L	5.15 NTU	-79.3 mV	26.03 ft	200.00 ml/min
3/5/2025 12:04 PM	01:00:00	6.98 pH	17.93 °C	732.78 µS/cm	2.47 mg/L	4.92 NTU	-78.9 mV	26.03 ft	200.00 ml/min

3/5/2025 12:09 PM	01:05:00	6.98 pH	17.92 °C	725.06 µS/cm	1.68 mg/L	4.43 NTU	-83.2 mV	26.03 ft	200.00 ml/min
3/5/2025 12:14 PM	01:10:00	6.98 pH	17.91 °C	725.91 µS/cm	1.59 mg/L	4.25 NTU	-78.5 mV	26.03 ft	200.00 ml/min
3/5/2025 12:19 PM	01:15:00	6.98 pH	17.91 °C	728.89 µS/cm	1.53 mg/L	4.11 NTU	-79.0 mV	26.03 ft	200.00 ml/min
3/5/2025 12:24 PM	01:20:38	7.00 pH	17.89 °C	718.03 µS/cm	1.66 mg/L	3.82 NTU	-83.1 mV	26.03 ft	200.00 ml/min
3/5/2025 12:29 PM	01:25:38	7.00 pH	17.84 °C	719.20 µS/cm	1.63 mg/L	3.59 NTU	-78.3 mV	26.03 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-14	Grab.
HAM-AP1-FD-01	Grab.

Low-Flow Test Report:

Test Date / Time: 3/5/2025 1:20:11 PM
Project: GP-Plant Hammond
Operator Name: T. Kessler

Location Name: PT-15 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.30 ft Total Depth: 45.30 ft Initial Depth to Water: 25.90 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.30 ft Estimated Total Volume Pumped: 10 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1146036
---	---	---

Test Notes:
Six Bottles: Appendix III & IV + Major Ions; Fe²⁺ = 1.0 mg/L, Fe_T = 1.2 mg/L.

Weather Conditions:
Cloudy, 55 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
3/5/2025 1:20 PM	00:00	6.83 pH	17.81 °C	706.34 µS/cm	3.06 mg/L	66.70 NTU	157.2 mV	25.90 ft	200.00 ml/min
3/5/2025 1:25 PM	05:00	6.83 pH	17.81 °C	726.84 µS/cm	2.21 mg/L	36.40 NTU	441.9 mV	25.90 ft	200.00 ml/min
3/5/2025 1:30 PM	10:00	6.86 pH	17.78 °C	721.82 µS/cm	1.75 mg/L	14.70 NTU	526.2 mV	25.90 ft	200.00 ml/min
3/5/2025 1:35 PM	15:00	6.87 pH	17.78 °C	722.05 µS/cm	1.16 mg/L	10.11 NTU	513.7 mV	25.90 ft	200.00 ml/min
3/5/2025 1:40 PM	20:00	6.87 pH	17.81 °C	720.82 µS/cm	0.87 mg/L	5.16 NTU	532.5 mV	25.90 ft	200.00 ml/min
3/5/2025 1:45 PM	25:00	6.87 pH	17.82 °C	719.34 µS/cm	0.70 mg/L	4.99 NTU	549.4 mV	25.90 ft	200.00 ml/min
3/5/2025 1:50 PM	30:00	6.87 pH	17.64 °C	715.41 µS/cm	0.55 mg/L	2.81 NTU	560.1 mV	25.90 ft	200.00 ml/min
3/5/2025 1:55 PM	35:00	6.88 pH	17.45 °C	715.93 µS/cm	0.42 mg/L	2.50 NTU	568.5 mV	25.90 ft	200.00 ml/min
3/5/2025 2:00 PM	40:00	6.88 pH	17.33 °C	715.47 µS/cm	0.33 mg/L	1.71 NTU	573.0 mV	25.90 ft	200.00 ml/min
3/5/2025 2:05 PM	45:00	6.88 pH	17.41 °C	732.70 µS/cm	0.22 mg/L	1.38 NTU	571.8 mV	25.90 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

HAM-PT-15	Grab.
-----------	-------

Low-Flow Test Report:

Test Date / Time: 4/3/2025 2:29:58 PM
Project: GP-Plant Hammond
Operator Name: Z. Webb

Location Name: INW-03 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.4 ft Total Depth: 27.4 ft Initial Depth to Water: 14.06 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 22.4 ft Estimated Total Volume Pumped: 4 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.09 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1179236
--	--	---

Test Notes:
Parameters. Ferrous Iron: 1.0 mg/L, Total Iron: 1.5 mg/L.

Weather Conditions:
Sunny, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
4/3/2025 2:29 PM	00:00	7.01 pH	19.86 °C	797.80 µS/cm	0.16 mg/L	6.01 NTU	14.3 mV	14.06 ft	200.00 ml/min
4/3/2025 2:34 PM	05:00	7.00 pH	20.06 °C	795.20 µS/cm	0.10 mg/L	7.35 NTU	9.1 mV	14.12 ft	200.00 ml/min
4/3/2025 2:39 PM	10:00	6.99 pH	20.12 °C	799.01 µS/cm	0.08 mg/L	5.91 NTU	14.2 mV	14.14 ft	200.00 ml/min
4/3/2025 2:44 PM	15:00	6.97 pH	20.00 °C	790.55 µS/cm	0.07 mg/L	5.73 NTU	16.3 mV	14.15 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 4/3/2025 8:53:57 AM
Project: GP-Plant Hammond
Operator Name: Z. Webb

Location Name: INW-04 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.62 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 4 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1179236
--	--	---

Test Notes:
Parameters. Ferrous Iron: 3.5 mg/L, Total Iron: 5.5 mg/L.

Weather Conditions:
Clear, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
4/3/2025 8:53 AM	00:00	6.23 pH	19.15 °C	621.68 µS/cm	0.77 mg/L	++++	-30.5 mV	26.62 ft	200.00 ml/min
4/3/2025 8:58 AM	05:00	6.35 pH	19.04 °C	646.71 µS/cm	0.56 mg/L	++++	-44.0 mV	26.63 ft	200.00 ml/min
4/3/2025 9:03 AM	10:00	6.39 pH	19.17 °C	649.73 µS/cm	0.40 mg/L	78.10 NTU	-43.9 mV	26.64 ft	200.00 ml/min
4/3/2025 9:08 AM	15:00	6.44 pH	19.13 °C	653.51 µS/cm	0.42 mg/L	47.00 NTU	-47.1 mV	26.64 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 4/3/2025 10:20:34 AM
Project: GP-Plant Hammond
Operator Name: Y. Wang

Location Name: INW-05 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.12 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 4 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.01 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1149710
---	---	---

Test Notes:
Parameters. Ferrous Iron: 4.9 mg/L, Total Iron: 7.0 mg/L.

Weather Conditions:
Sunny,70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
4/3/2025 10:20 AM	00:00	6.92 pH	19.33 °C	758.82 µS/cm	2.25 mg/L	++++	-78.1 mV	26.14 ft	200.00 ml/min
4/3/2025 10:25 AM	05:00	6.92 pH	18.82 °C	766.39 µS/cm	1.40 mg/L	++++	-71.2 mV	26.13 ft	200.00 ml/min
4/3/2025 10:30 AM	10:00	6.94 pH	18.73 °C	767.75 µS/cm	0.88 mg/L	++++	-74.3 mV	26.13 ft	200.00 ml/min
4/3/2025 10:35 AM	15:00	6.94 pH	18.73 °C	771.69 µS/cm	0.85 mg/L	125.1	-77.1 mV	26.13 ft	200.00 ml/min

Samples

Sample ID:	Description:
------------	--------------

Low-Flow Test Report:

Test Date / Time: 4/3/2025 8:55:31 AM
Project: GP-Plant Hammond
Operator Name: Y. Wang

Location Name: PT-07 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 37.75 ft Total Depth: 47.75 ft Initial Depth to Water: 26.82 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 42.75 ft Estimated Total Volume Pumped: 5 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.1 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1149710
---	--	---

Test Notes:
Full App. III and IV + Major Ions. Ferrous Iron: 4.3 mg/L. Total Iron: 5.5 mg/L.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
4/3/2025 8:55 AM	00:00	6.91 pH	18.71 °C	755.53 µS/cm	1.31 mg/L	0.40 NTU	-92.3 mV	26.91 ft	200.00 ml/min
4/3/2025 9:00 AM	05:00	6.92 pH	18.70 °C	759.47 µS/cm	1.01 mg/L	0.43 NTU	-93.0 mV	26.92 ft	200.00 ml/min
4/3/2025 9:05 AM	10:00	6.92 pH	18.72 °C	759.46 µS/cm	0.91 mg/L	0.23 NTU	-88.0 mV	26.93 ft	200.00 ml/min
4/3/2025 9:10 AM	15:00	6.92 pH	18.71 °C	760.02 µS/cm	0.87 mg/L	0.27 NTU	-85.4 mV	26.92 ft	200.00 ml/min
4/3/2025 9:15 AM	20:00	6.92 pH	18.74 °C	759.60 µS/cm	0.78 mg/L	0.41 NTU	-83.5 mV	26.92 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-7	Grab

Low-Flow Test Report:

Test Date / Time: 4/2/2025 3:12:10 PM
Project: GP-Plant Hammond
Operator Name: Z. Webb

Location Name: PT-08 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 31.93 ft Total Depth: 41.93 ft Initial Depth to Water: 26.61 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 36.93 ft Estimated Total Volume Pumped: 20 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1179236
--	---	---

Test Notes:
Full App. III and IV + Major Ions. Ferrous Iron: 0.4 mg/L. Total Iron: 1.0 mg/L.

Weather Conditions:
Sunny, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
4/2/2025 3:12 PM	00:00	6.53 pH	24.84 °C	618.29 µS/cm	1.47 mg/L	++++	39.6 mV	26.61 ft	200.00 ml/min
4/2/2025 3:17 PM	05:00	6.46 pH	20.95 °C	678.88 µS/cm	0.46 mg/L	++++	47.2 mV	26.61 ft	200.00 ml/min
4/2/2025 3:22 PM	10:00	6.45 pH	20.87 °C	673.00 µS/cm	0.36 mg/L	++++	47.8 mV	26.62 ft	200.00 ml/min
4/2/2025 3:27 PM	15:00	6.47 pH	21.06 °C	671.95 µS/cm	0.29 mg/L	65.40 NTU	43.3 mV	26.62 ft	200.00 ml/min
4/2/2025 3:32 PM	20:00	6.49 pH	21.00 °C	683.70 µS/cm	0.20 mg/L	49.10 NTU	40.3 mV	26.63 ft	200.00 ml/min
4/2/2025 3:37 PM	25:00	6.49 pH	20.77 °C	685.33 µS/cm	0.19 mg/L	33.80 NTU	41.2 mV	26.63 ft	200.00 ml/min
4/2/2025 3:42 PM	30:00	6.50 pH	20.81 °C	678.70 µS/cm	0.16 mg/L	26.90 NTU	40.3 mV	26.63 ft	200.00 ml/min
4/2/2025 3:47 PM	35:00	6.50 pH	20.25 °C	681.51 µS/cm	0.15 mg/L	22.30 NTU	40.3 mV	26.63 ft	200.00 ml/min
4/2/2025 3:52 PM	40:00	6.50 pH	20.42 °C	677.65 µS/cm	0.14 mg/L	15.60 NTU	37.8 mV	26.63 ft	200.00 ml/min
4/2/2025 3:57 PM	45:00	6.51 pH	20.20 °C	680.67 µS/cm	0.13 mg/L	11.40 NTU	37.4 mV	26.63 ft	200.00 ml/min
4/2/2025 4:02 PM	50:00	6.51 pH	20.24 °C	687.60 µS/cm	0.14 mg/L	10.70 NTU	36.3 mV	26.63 ft	200.00 ml/min
4/2/2025 4:07 PM	55:00	6.51 pH	20.60 °C	685.39 µS/cm	0.12 mg/L	9.04 NTU	34.9 mV	26.63 ft	200.00 ml/min
4/2/2025 4:12 PM	01:00:00	6.51 pH	20.77 °C	685.48 µS/cm	0.11 mg/L	7.65 NTU	33.1 mV	26.63 ft	200.00 ml/min

4/2/2025 4:17 PM	01:05:00	6.51 pH	20.46 °C	677.12 µS/cm	0.10 mg/L	6.90 NTU	31.7 mV	26.63 ft	200.00 ml/min
4/2/2025 4:22 PM	01:10:00	6.50 pH	20.24 °C	678.83 µS/cm		6.23 NTU	33.4 mV	26.63 ft	200.00 ml/min
4/2/2025 4:27 PM	01:15:00	6.50 pH	19.94 °C	686.46 µS/cm	0.08 mg/L	5.99 NTU	32.3 mV	26.63 ft	200.00 ml/min
4/2/2025 4:32 PM	01:20:00	6.50 pH	19.96 °C	684.90 µS/cm	0.08 mg/L	5.75 NTU	31.6 mV	26.63 ft	200.00 ml/min
4/2/2025 4:37 PM	01:25:00	6.51 pH	19.94 °C	699.80 µS/cm	0.09 mg/L	5.40 NTU	30.7 mV	26.63 ft	200.00 ml/min
4/2/2025 4:42 PM	01:30:00	6.50 pH	19.95 °C	694.37 µS/cm	0.11 mg/L	4.63 NTU	30.0 mV	26.63 ft	200.00 ml/min
4/2/2025 4:47 PM	01:35:00	6.50 pH	20.01 °C	695.92 µS/cm	0.10 mg/L	4.55 NTU	29.3 mV	26.63 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-08	Grab.

Low-Flow Test Report:

Test Date / Time: 4/3/2025 1:17:23 PM
Project: GP-Plant Hammond
Operator Name: Z. Webb

Location Name: PT-09 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.47 ft Total Depth: 30.47 ft Initial Depth to Water: 17.37 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 21.9 ft Estimated Total Volume Pumped: 8 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.06 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1179236
---	--	---

Test Notes:
Full App. III and IV + Major Ions. Ferrous Iron: 0 mg/L. Total Iron: 0.5 mg/L.

Weather Conditions:
Sunny, 80 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
4/3/2025 1:17 PM	00:00	6.73 pH	19.78 °C	718.45 µS/cm	0.11 mg/L	17.20 NTU	84.2 mV	17.37 ft	200.00 ml/min
4/3/2025 1:22 PM	05:00	6.75 pH	19.83 °C	697.18 µS/cm	0.09 mg/L	16.30 NTU	81.5 mV	17.39 ft	200.00 ml/min
4/3/2025 1:27 PM	10:00	6.76 pH	19.87 °C	708.10 µS/cm	0.07 mg/L	13.10 NTU	59.9 mV	17.41 ft	200.00 ml/min
4/3/2025 1:32 PM	15:00	6.77 pH	20.02 °C	706.40 µS/cm	0.07 mg/L	10.40 NTU	57.8 mV	17.42 ft	200.00 ml/min
4/3/2025 1:37 PM	20:00	6.78 pH	19.91 °C	712.37 µS/cm	0.06 mg/L	9.62 NTU	56.8 mV	17.43 ft	200.00 ml/min
4/3/2025 1:42 PM	25:00	6.77 pH	19.88 °C	716.13 µS/cm	0.06 mg/L	8.17 NTU	56.6 mV	17.43 ft	200.00 ml/min
4/3/2025 1:47 PM	30:00	6.78 pH	20.09 °C	714.20 µS/cm	0.06 mg/L	5.92 NTU	56.1 mV	17.43 ft	200.00 ml/min
4/3/2025 1:52 PM	35:00	6.78 pH	20.38 °C	716.18 µS/cm	0.05 mg/L	4.85 NTU	55.3 mV	17.43 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-09	Grab.

Low-Flow Test Report:

Test Date / Time: 4/3/2025 12:05:08 PM
Project: GP-Plant Hammond
Operator Name: Y. Wang

Location Name: PT-10 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 20.45 ft Total Depth: 30.45 ft Initial Depth to Water: 17.45 ft	Pump Type: Peri Tubing Type: Polyethylene Pump Intake From TOC: 25.45 ft Estimated Total Volume Pumped: 7 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.08 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1149710
--	---	---

Test Notes:
Full App. III and IV + Major Ions. Ferrous Iron: 0 mg/L. Total Iron: 0 mg/L.

Weather Conditions:
Sunny, 65 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
4/3/2025 12:05 PM	00:00	6.76 pH	20.17 °C	754.15 µS/cm	0.17 mg/L	1.23 NTU	26.1 mV	17.46 ft	200.00 ml/min
4/3/2025 12:10 PM	05:00	6.77 pH	20.07 °C	753.51 µS/cm	0.15 mg/L	0.46 NTU	78.9 mV	17.51 ft	200.00 ml/min
4/3/2025 12:15 PM	10:00	6.77 pH	20.26 °C	758.01 µS/cm	0.13 mg/L	0.33 NTU	94.6 mV	17.53 ft	200.00 ml/min
4/3/2025 12:20 PM	15:00	6.79 pH	20.79 °C	761.76 µS/cm	0.13 mg/L	0.21 NTU	98.3 mV	17.51 ft	200.00 ml/min
4/3/2025 12:25 PM	20:00	6.80 pH	20.62 °C	764.99 µS/cm	0.12 mg/L	0.85 NTU	102.0 mV	17.52 ft	200.00 ml/min
4/3/2025 12:30 PM	25:00	6.81 pH	21.07 °C	769.62 µS/cm	0.11 mg/L	0.21 NTU	105.8 mV	17.52 ft	200.00 ml/min
4/3/2025 12:35 PM	30:00	6.82 pH	20.49 °C	767.32 µS/cm	0.11 mg/L	0.49 NTU	139.0 mV	17.52 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-10	Grab.

Low-Flow Test Report:

Test Date / Time: 4/3/2025 11:55:04 AM
Project: GP-Plant Hammond
Operator Name: Z. Webb

Location Name: PT-11 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 16.9 ft Total Depth: 26.9 ft Initial Depth to Water: 13.94 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 21.9 ft Estimated Total Volume Pumped: 10 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1179236
---	--	---

Test Notes:
Full App. III and IV + Major Ions. Ferrous Iron: 0.5 mg/L. Total Iron: 0.5 mg/L.

Weather Conditions:
Sunny, 75 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
4/3/2025 11:55 AM	00:00	6.72 pH	19.58 °C	684.25 µS/cm	0.15 mg/L	12.10 NTU	119.6 mV	13.94 ft	200.00 ml/min
4/3/2025 12:00 PM	05:00	6.70 pH	19.53 °C	650.68 µS/cm	0.12 mg/L	11.40 NTU	97.5 mV	13.94 ft	200.00 ml/min
4/3/2025 12:05 PM	10:00	6.72 pH	19.61 °C	663.55 µS/cm	0.11 mg/L	8.53 NTU	65.0 mV	13.94 ft	200.00 ml/min
4/3/2025 12:10 PM	15:00	6.75 pH	19.63 °C	659.37 µS/cm	0.10 mg/L	6.41 NTU	59.5 mV	13.94 ft	200.00 ml/min
4/3/2025 12:15 PM	20:00	6.74 pH	19.75 °C	660.35 µS/cm	0.09 mg/L	6.18 NTU	56.6 mV	13.94 ft	200.00 ml/min
4/3/2025 12:20 PM	25:00	6.74 pH	20.04 °C	656.46 µS/cm	0.09 mg/L	5.45 NTU	55.2 mV	13.94 ft	200.00 ml/min
4/3/2025 12:25 PM	30:00	6.75 pH	19.89 °C	655.81 µS/cm	0.09 mg/L	4.32 NTU	54.2 mV	13.94 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-11	Grab.

Low-Flow Test Report:

Test Date / Time: 4/3/2025 1:30:16 PM
Project: GP-Plant Hammond
Operator Name: Y. Wang

Location Name: PT-12 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 17.3 ft Total Depth: 27.3 ft Initial Depth to Water: 13.86 ft	Pump Type: Peri Tubing Type: Polyethylene Pump Intake From TOC: 22.3 ft Estimated Total Volume Pumped: 10.8 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.06 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1149710
---	--	---

Test Notes:
Full App. III and IV + Major Ions. Ferrous Iron: 0 mg/L. Total Iron: 0 mg/L.

Weather Conditions:
Sunny, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
4/3/2025 1:30 PM	00:00	7.77 pH	31.87 °C	0.14 µS/cm	6.93 mg/L	9.19 NTU	160.0 mV	13.91 ft	200.00 ml/min
4/3/2025 1:35 PM	05:41	6.32 pH	21.47 °C	643.05 µS/cm	0.23 mg/L	6.41 NTU	224.2 mV	13.92 ft	200.00 ml/min
4/3/2025 1:36 PM	06:20	6.32 pH	20.76 °C	651.77 µS/cm	0.22 mg/L	6.23 NTU	283.5 mV	13.91 ft	200.00 ml/min
4/3/2025 1:37 PM	07:40	6.32 pH	20.41 °C	660.05 µS/cm	0.20 mg/L	6.18 NTU	302.2 mV	13.94 ft	200.00 ml/min
4/3/2025 1:42 PM	12:40	6.33 pH	19.77 °C	670.07 µS/cm	0.14 mg/L	9.81 NTU	439.9 mV	13.92 ft	200.00 ml/min
4/3/2025 1:47 PM	17:40	6.33 pH	19.96 °C	667.55 µS/cm	0.13 mg/L	9.41 NTU	455.2 mV	13.91 ft	200.00 ml/min
4/3/2025 1:52 PM	22:40	6.35 pH	20.13 °C	673.36 µS/cm	0.12 mg/L	9.21 NTU	589.3 mV	13.90 ft	200.00 ml/min
4/3/2025 1:55 PM	25:41	6.39 pH	20.22 °C	678.63 µS/cm	0.12 mg/L	10.24 NTU	412.4 mV	13.91 ft	200.00 ml/min
4/3/2025 2:00 PM	30:41	6.41 pH	20.14 °C	678.68 µS/cm	0.11 mg/L	8.44 NTU	485.1 mV	13.93 ft	200.00 ml/min
4/3/2025 2:05 PM	35:41	6.35 pH	20.00 °C	668.27 µS/cm	0.11 mg/L	4.59 NTU	484.4 mV	13.91 ft	200.00 ml/min
4/3/2025 2:10 PM	40:41	6.41 pH	20.21 °C	678.48 µS/cm	0.11 mg/L	4.32 NTU	480.7 mV	13.92 ft	200.00 ml/min
4/3/2025 2:15 PM	45:41	6.40 pH	20.05 °C	675.61 µS/cm	0.11 mg/L	4.78 NTU	485.5 mV	13.91 ft	200.00 ml/min
4/3/2025 2:20 PM	50:41	6.43 pH	20.21 °C	681.72 µS/cm	0.11 mg/L	2.97 NTU	485.4 mV	13.92 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-12	Grab.

Low-Flow Test Report:

Test Date / Time: 4/2/2025 2:40:14 PM
Project: GP-Plant Hammond
Operator Name: Y. Wang

Location Name: PT-13 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.38 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 31.6 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: -0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1149710
---	--	---

Test Notes:
Full App. III and IV + Major Ions. Ferrous Iron: 3.6 mg/L. Total Iron: 4.8 mg/L.

Weather Conditions:
Sunny, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
4/2/2025 2:40 PM	00:00	6.85 pH	20.57 °C	737.04 µS/cm	0.38 mg/L	++++	-34.9 mV	26.42 ft	200.00 ml/min
4/2/2025 2:43 PM	03:31	6.85 pH	20.22 °C	745.58 µS/cm	0.30 mg/L	++++	-32.0 mV	26.40 ft	200.00 ml/min
4/2/2025 2:48 PM	08:22	6.86 pH	19.96 °C	737.21 µS/cm	0.21 mg/L	++++	-42.0 mV	26.41 ft	200.00 ml/min
4/2/2025 2:53 PM	13:22	6.86 pH	20.18 °C	746.43 µS/cm	0.19 mg/L	56.40 NTU	-31.4 mV	26.37 ft	200.00 ml/min
4/2/2025 2:58 PM	18:22	6.86 pH	20.06 °C	745.58 µS/cm	0.15 mg/L	46.70 NTU	-38.5 mV	26.35 ft	200.00 ml/min
4/2/2025 3:03 PM	23:22	6.86 pH	20.03 °C	745.77 µS/cm	0.13 mg/L	35.50 NTU	-40.8 mV	26.34 ft	200.00 ml/min
4/2/2025 3:08 PM	28:22	6.85 pH	19.99 °C	741.94 µS/cm	0.12 mg/L	28.20 NTU	-37.5 mV	26.34 ft	200.00 ml/min
4/2/2025 3:13 PM	33:22	6.86 pH	19.90 °C	746.76 µS/cm	0.11 mg/L	25.00 NTU	-40.1 mV	26.35 ft	200.00 ml/min
4/2/2025 3:18 PM	38:22	6.85 pH	20.37 °C	749.19 µS/cm	0.10 mg/L	23.30 NTU	-42.4 mV	26.35 ft	200.00 ml/min
4/2/2025 3:23 PM	43:22	6.85 pH	20.48 °C	748.04 µS/cm	0.09 mg/L	22.80 NTU	-41.5 mV	26.34 ft	200.00 ml/min
4/2/2025 3:28 PM	48:22	6.85 pH	20.22 °C	740.36 µS/cm	0.08 mg/L	20.90 NTU	-42.2 mV	26.35 ft	200.00 ml/min
4/2/2025 3:33 PM	53:22	6.84 pH	20.30 °C	739.48 µS/cm	0.08 mg/L	15.40 NTU	-40.6 mV	26.36 ft	200.00 ml/min
4/2/2025 3:38 PM	58:22	6.85 pH	20.49 °C	740.20 µS/cm	0.07 mg/L	17.70 NTU	-42.4 mV	26.35 ft	200.00 ml/min

4/2/2025 3:43 PM	01:03:22	6.85 pH	20.43 °C	739.47 µS/cm	0.07 mg/L	20.20 NTU	-43.3 mV	26.34 ft	200.00 ml/min
4/2/2025 3:48 PM	01:08:22	6.85 pH	19.99 °C	741.54 µS/cm	0.06 mg/L	19.40 NTU	-43.7 mV	26.35 ft	200.00 ml/min
4/2/2025 3:53 PM	01:13:22	6.85 pH	20.08 °C	740.56 µS/cm	0.06 mg/L	18.70 NTU	-43.7 mV	26.36 ft	200.00 ml/min
4/2/2025 3:58 PM	01:18:22	6.86 pH	19.97 °C	738.38 µS/cm	0.06 mg/L	13.90 NTU	-46.1 mV	26.35 ft	200.00 ml/min
4/2/2025 4:03 PM	01:23:22	6.85 pH	19.95 °C	737.63 µS/cm	0.06 mg/L	17.80 NTU	-46.4 mV	26.34 ft	200.00 ml/min
4/2/2025 4:08 PM	01:28:22	6.85 pH	20.24 °C	738.03 µS/cm	0.05 mg/L	20.30 NTU	-45.4 mV	26.35 ft	200.00 ml/min
4/2/2025 4:13 PM	01:33:22	6.86 pH	20.26 °C	737.09 µS/cm	0.06 mg/L	21.20 NTU	-46.6 mV	26.35 ft	200.00 ml/min
4/2/2025 4:18 PM	01:38:22	6.85 pH	20.09 °C	734.90 µS/cm	0.05 mg/L	20.80 NTU	-44.1 mV	26.32 ft	200.00 ml/min
4/2/2025 4:23 PM	01:43:22	6.86 pH	19.86 °C	735.25 µS/cm	0.04 mg/L	19.80 NTU	-46.3 mV	26.35 ft	200.00 ml/min
4/2/2025 4:28 PM	01:48:22	6.86 pH	19.99 °C	738.07 µS/cm	0.05 mg/L	35.50 NTU	-50.9 mV	26.34 ft	200.00 ml/min
4/2/2025 4:33 PM	01:53:22	6.85 pH	19.96 °C	733.77 µS/cm	0.08 mg/L	25.60 NTU	-47.0 mV	26.35 ft	200.00 ml/min
4/2/2025 4:38 PM	01:58:22	6.85 pH	20.20 °C	733.46 µS/cm	0.07 mg/L	12.30 NTU	-51.7 mV	26.32 ft	200.00 ml/min
4/2/2025 4:43 PM	02:03:22	6.86 pH	19.95 °C	731.35 µS/cm	0.05 mg/L	10.33 NTU	-50.3 mV	26.36 ft	200.00 ml/min
4/2/2025 4:48 PM	02:08:22	6.85 pH	20.09 °C	734.77 µS/cm	0.04 mg/L	7.91 NTU	-50.2 mV	26.37 ft	200.00 ml/min
4/2/2025 4:53 PM	02:13:22	6.86 pH	19.88 °C	734.66 µS/cm	0.04 mg/L	6.61 NTU	-51.2 mV	26.33 ft	200.00 ml/min
4/2/2025 4:58 PM	02:18:22	6.85 pH	20.03 °C	734.55 µS/cm	0.04 mg/L	4.96 NTU	-51.3 mV	26.36 ft	200.00 ml/min
4/2/2025 5:03 PM	02:23:22	6.85 pH	19.89 °C	734.66 µS/cm	0.04 mg/L	4.55 NTU	-51.7 mV	26.35 ft	200.00 ml/min
4/2/2025 5:08 PM	02:28:22	6.85 pH	19.80 °C	733.67 µS/cm	0.04 mg/L	4.91 NTU	-50.5 mV	26.32 ft	200.00 ml/min
4/2/2025 5:12 PM	02:32:29	6.85 pH	19.86 °C	731.33 µS/cm	0.04 mg/L	4.97 NTU	-50.1 mV	26.36 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-13	Grab

Low-Flow Test Report:

Test Date / Time: 4/2/2025 12:43:25 PM
Project: GP-Plant Hammond
Operator Name: Z. Webb

Location Name: PT-14 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.34 ft	Pump Type: Peristaltic Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 13 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: 0.07 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1179236
---	---	---

Test Notes:
Full App. III and IV + Major Ions. Ferrous Iron: 4.4 mg/L. Total Iron: 7.0 mg/L.

Weather Conditions:
Sunny, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
4/2/2025 12:43 PM	00:00	6.89 pH	20.77 °C	738.95 µS/cm	0.61 mg/L	31.50 NTU	-89.5 mV	26.34 ft	200.00 ml/min
4/2/2025 12:48 PM	05:00	6.94 pH	20.15 °C	723.95 µS/cm	0.63 mg/L	28.70 NTU	-105.9 mV	26.33 ft	200.00 ml/min
4/2/2025 12:53 PM	10:00	6.95 pH	20.28 °C	698.22 µS/cm	0.45 mg/L	25.00 NTU	-107.8 mV	26.38 ft	200.00 ml/min
4/2/2025 12:58 PM	15:00	6.95 pH	20.18 °C	734.81 µS/cm	0.33 mg/L	22.30 NTU	-95.9 mV	26.40 ft	200.00 ml/min
4/2/2025 1:03 PM	20:00	6.95 pH	20.37 °C	721.70 µS/cm	0.27 mg/L	18.10 NTU	-97.5 mV	26.41 ft	200.00 ml/min
4/2/2025 1:08 PM	25:00	6.96 pH	20.36 °C	655.23 µS/cm	0.20 mg/L	14.30 NTU	-98.3 mV	26.41 ft	200.00 ml/min
4/2/2025 1:14 PM	30:56	6.96 pH	20.46 °C	723.31 µS/cm	0.19 mg/L	11.90 NTU	-86.8 mV	26.41 ft	200.00 ml/min
4/2/2025 1:19 PM	35:56	6.97 pH	20.37 °C	749.94 µS/cm	0.16 mg/L	9.63 NTU	-111.9 mV	26.41 ft	200.00 ml/min
4/2/2025 1:24 PM	40:56	6.96 pH	20.82 °C	724.58 µS/cm	0.18 mg/L	8.28 NTU	-112.9 mV	26.41 ft	200.00 ml/min
4/2/2025 1:29 PM	45:56	6.96 pH	20.67 °C	703.48 µS/cm	0.15 mg/L	7.72 NTU	-101.6 mV	26.41 ft	200.00 ml/min
4/2/2025 1:34 PM	50:56	6.96 pH	20.87 °C	714.10 µS/cm	0.15 mg/L	6.21 NTU	-101.8 mV	26.41 ft	200.00 ml/min
4/2/2025 1:39 PM	55:56	6.96 pH	20.83 °C	722.10 µS/cm	0.12 mg/L	5.52 NTU	-102.4 mV	26.41 ft	200.00 ml/min
4/2/2025 1:44 PM	01:00:56	6.96 pH	20.72 °C	726.72 µS/cm	0.11 mg/L	4.58 NTU	-102.3 mV	26.41 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-14	Grab.
HAM-AP1-FD-01	Grab.

Low-Flow Test Report:

Test Date / Time: 4/2/2025 12:24:21 PM
Project: GP-Plant Hammond
Operator Name: Y. Wang

Location Name: PT-15 Well Diameter: 2 in Casing Type: PVC Screen Length: 10 ft Top of Screen: 35.3 ft Total Depth: 45.3 ft Initial Depth to Water: 26.25 ft	Pump Type: Bladder Tubing Type: Polyethylene Pump Intake From TOC: 40.3 ft Estimated Total Volume Pumped: 8 liter Flow Cell Volume: 90 ml Final Flow Rate: 200 ml/min Final Draw Down: -0.02 ft	Instrument Used: Aqua TROLL 400 Serial Number: 1149710
---	---	---

Test Notes:
Full App. III and IV + Major Ions. Ferrous Iron: 1.2 mg/L. Total Iron: 2.0 mg/L.

Weather Conditions:
Sunny, 70 degrees F.

Low-Flow Readings:

Date Time	Elapsed Time	pH	Temperature	Specific Conductivity	RDO Concentration	Turbidity	ORP	Depth to Water	Flow
		+/- 0.1	+/- 0.5	+/- 5 %	+/- 0.2	+/- 5	+/- 10	+/- 0.3	
4/2/2025 12:24 PM	00:00	6.77 pH	19.42 °C	753.62 µS/cm	0.57 mg/L	5.86 NTU	25.0 mV	26.25 ft	200.00 ml/min
4/2/2025 12:29 PM	05:00	6.78 pH	19.59 °C	749.15 µS/cm	0.45 mg/L	4.32 NTU	59.4 mV	26.21 ft	200.00 ml/min
4/2/2025 12:34 PM	10:00	6.78 pH	19.55 °C	750.26 µS/cm	0.31 mg/L	2.66 NTU	48.8 mV	26.22 ft	200.00 ml/min
4/2/2025 12:39 PM	15:00	6.78 pH	19.54 °C	751.76 µS/cm	0.26 mg/L	3.63 NTU	49.4 mV	26.23 ft	200.00 ml/min
4/2/2025 12:44 PM	20:00	6.78 pH	19.62 °C	733.28 µS/cm	0.20 mg/L	2.76 NTU	49.3 mV	26.22 ft	200.00 ml/min
4/2/2025 12:49 PM	25:00	6.78 pH	19.53 °C	728.82 µS/cm	0.19 mg/L	1.05 NTU	52.3 mV	26.24 ft	200.00 ml/min
4/2/2025 12:54 PM	30:00	6.78 pH	19.71 °C	724.63 µS/cm	0.15 mg/L	1.57 NTU	49.8 mV	26.25 ft	200.00 ml/min
4/2/2025 12:59 PM	35:00	6.78 pH	19.65 °C	728.24 µS/cm	0.13 mg/L	1.05 NTU	48.8 mV	26.23 ft	200.00 ml/min

Samples

Sample ID:	Description:
HAM-PT-15	Grab.

Calibration Forms

Site Name Plant Kemmer

Field Instrumentation Calibration Form

Date 8/11/2024Calibrated By J. KesslerField Conditions Clear, 75°

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Aquatrill</u>	<u>968202</u>
Turbidity Meter	<u>Lemuel</u>	

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>24005598</u>	<u>12/24</u>	<u>1mg.14</u>
pH (SU)	4.00	<u>2400497</u>	<u>12/24</u>	
pH (SU)	7.00	<u>2400085</u>	<u>12/24</u>	
pH (SU)	10.00	<u>2400085</u>	<u>12/24</u>	
D.O. (%)	N/A			
ORP (mV)	228.0	<u>24006903</u>	<u>11/24</u>	

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>4.490</u>	<u>27.15</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.0</u>	<u>27.09</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.0</u>	<u>26.99</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>27.14</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100.0</u>	<u>26.20</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228</u>	<u>26.59</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>1</u>	<u>0.95</u>		
	<u>10</u>	<u>10.0</u>		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>4.400</u>	<u>33.04</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>32.04</u>	± 0.1	GWMP
pH (SU)	7.00	<u>6.95</u>	<u>30.17</u>	± 0.1	GWMP
pH (SU)	10.00	<u>9.95</u>	<u>28.60</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0.00</u>	$\pm 10\%$ of standard	EPA 2023
	<u>1</u>	<u>1.02</u>		
	<u>10</u>	<u>9.90</u>		

Notes

~~HGA-13~~
PT-07
PT-08
PT-13
PT-14
~~PT-15~~

Site Name Hammond
 Calibrated By Jacob Tracy

Field Instrumentation Calibration Form

Date 7/31/2024
 Field Conditions Sunny

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	In Situ	850724
Turbidity Meter	Lamotte	4104-2023

Calibration Standard Information			
Parameter	Standard	Lot #	Date of Expiration
Specific Conductance (μS/cm)	4.490	24003593	11/24
pH (SU)	4.00	24003597	11/24
pH (SU)	7.00	24003597	11/24
pH (SU)	10.00	24003597	12/24
D.O. (%)	N/A	24003597	12/24
ORP (mV)	228.0	24003597	12/24

Calibration					
Time Start	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (μS/cm)	4.490	4.473	22.3	± 10% of standard	EPA 2023
pH (SU)	4.00	3.94	22.35	± 0.1	GWMP
pH (SU)	7.00	6.97	22.24	± 0.1	GWMP
pH (SU)	10.00	9.93	22.22	± 0.1	GWMP
D.O. (%)	N/A	102.34	21.50	± 10%	NA
ORP (mV)	228.0	228.7	22.22	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	0.92		
	10	10.05		

Calibration Check					
Time Start	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (μS/cm)	4.490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0.0	± 10% of standard	EPA 2023
	1	1.0		
	10	10.6		

Notes:

Site Name Hammond
 Calibrated By Jacob Tracy

Field Instrumentation Calibration Form

Date 08/01/24
 Field Conditions 5.1e4

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>10-5120</u>	<u>850-724</u>
Turbidity Meter	<u>hamond</u>	<u>4104-2623</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490			
pH (SU)	4.00			
pH (SU)	7.00			
pH (SU)	10.00			
D.O. (%)	N/A			
ORP (mV)	228.0			

07 01/24

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>4.70</u>	<u>22.76</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.02</u>	<u>↓</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.03</u>		± 0.1	GWMP
pH (SU)	10.00	<u>10.02</u>	<u>22.96</u>	± 0.1	GWMP
D.O. (%)	N/A		<u>96.51</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>232</u>		± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>1</u>	<u>0.97</u>		
	<u>10</u>	<u>10.4</u>		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>1</u>	<u>1.22</u>		
	<u>10</u>	<u>10.5</u>		

Notes

Site Name: Hammond

Field Instrumentation Calibration Form

Date: 08/5/24Calibrated By: Elisabeth RussenField Conditions: Hot

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aquatro	1080293
Turbidity Meter	Lamella 20206	SN1596-3019

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	24005593	12/24	AR
pH (SU)	4.00	24005593	12/24	AR
pH (SU)	7.00	24004517	12/24	AR
pH (SU)	10.00	24000085	12/24	AR
D.O. (%)	N/A			AR
ORP (mV)	228.0	24006903	12/24	

Calibration					
Time Start	1500	Time Finish	1535		
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	4490.3	37.29	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.0	37.06	± 0.1	GWMP
pH (SU)	7.00	7.0	36.11	± 0.1	GWMP
pH (SU)	10.00	10.0	36.09	± 0.1	GWMP
D.O. (%)	N/A	100.1	35.02	$\pm 10\%$	NA
ORP (mV)	228.0	228	35.38	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0.0	0.0	$\pm 10\%$ of standard	EPA 2023
	1.0	1.02		
	10.0	9.89		

Calibration Check					
Time Start	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	24		$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

N/A

Site Name: Hammond

Field Instrumentation Calibration Form

Date: 8/6/24Calibrated By: Elisabeth RussellField Conditions: 70-90, sunny

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aqua-Mill 900	1080293
Turbidity Meter	La Motte 2020T	4080293

EP 1596-3019

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	24005593	12/24	ATC
pH (SU)	4.00	24003593	12/24	ATC
pH (SU)	7.00	24009517	12/24	ATC
pH (SU)	10.00	2400085	12/24	ATC
D.O. (%)	N/A			ATC
ORP (mV)	228.0	24006903	12/24	ATC

Calibration					
Time Start	730		Time Finish	800	
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	4990	27.34	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.0	27.42	± 0.1	GWMP
pH (SU)	7.00	7.0	27.93	± 0.1	GWMP
pH (SU)	10.00	10.0	28.41	± 0.1	GWMP
D.O. (%)	N/A	100%	28.38	$\pm 10\%$	NA
ORP (mV)	228.0	228	28.07	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	6.02	$\pm 10\%$ of standard	EPA 2023
	1	1.07		
	10	9.2		

Calibration Check					
Time Start			Time Finish		
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes: second well unexpectedly took 3.5 hours, no mid day calibration

Site Name: Hammond

Field Instrumentation Calibration Form

Date: 8/7/24Calibrated By: E RussellField Conditions: 70-90, sunny

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aquatrill 960	1080293
Turbidity Meter	LaMotte 2020	SN596-3019

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	24003593	12/24	AIR
pH (SU)	4.00	24003593	12/24	AIR
pH (SU)	7.00	24004517	12/24	AIR
pH (SU)	10.00	24000085	12/24	AIR
D.O. (%)	N/A	—	—	—
ORP (mV)	228.0	24006903	12/24	AIR

Calibration					
Time Start	800		Time Finish	835	
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	4.490	29.11	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.0	29.67	± 0.1	GWMP
pH (SU)	7.00	7.0	29.77	± 0.1	GWMP
pH (SU)	10.00	10.0	29.83	± 0.1	GWMP
D.O. (%)	N/A	—	29.31	$\pm 10\%$	NA
ORP (mV)	228.0	228	29.37	± 10	EPA 2023

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)	0	0.1	$\pm 10\%$ of standard	EPA 2023
	1	1.0		
	10	9.92		

Calibration Check					
Time Start	1300		Time Finish	1315	
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	4.49	35.20	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.0	35.21	± 0.1	GWMP
pH (SU)	7.00	7.0	35.03	± 0.1	GWMP
pH (SU)	10.00	10.0	35.13	± 0.1	GWMP

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)	0	0.13	$\pm 10\%$ of standard	EPA 2023
	1	1.1		
	10	9.97		

Notes:

Site Name: Hammond

Field Instrumentation Calibration Form

Date: 8/8/24Calibrated By: E. RussellField Conditions: 70-95, Sunny

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Yamatrol</u>	<u>1080293</u>
Turbidity Meter	<u>Lamotte 2020t</u>	<u>SN-19963019</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>24005593</u>	<u>12/24</u>	<u>ATR</u>
pH (SU)	4.00	<u>24005593</u>	<u>12/24</u>	<u>ATR</u>
pH (SU)	7.00	<u>24004517</u>	<u>12/24</u>	<u>ATR</u>
pH (SU)	10.00	<u>24000685</u>	<u>12/24</u>	<u>ATR</u>
D.O. (%)	N/A			
ORP (mV)	228.0	<u>24006105</u>	<u>12/24</u>	<u>ATR</u>

Calibration					
Time Start	<u>900</u>				
	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>4490</u>	<u>28.17</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.0</u>	<u>28.54</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.0</u>	<u>28.78</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.0</u>	<u>28.62</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>28.18</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228</u>	<u>28.87</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>-0.07</u>	$\pm 10\%$ of standard	EPA 2023
	<u>1</u>	<u>1.0</u>		
	<u>10</u>	<u>9.90</u>		

Calibration Check					
Time Start	<u>1410</u>				
	Time Finish <u>1430</u>				
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>4490</u>	<u>35.64</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.0</u>	<u>35.33</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.0</u>	<u>34.25</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.0</u>	<u>33.45</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>-0.10</u>	$\pm 10\%$ of standard	EPA 2023
	<u>1</u>	<u>1.07</u>		
	<u>10</u>	<u>9.98</u>		

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 8/9/24Calibrated By: E. RussellField Conditions: 70-80, Sun

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	AquaTron 700	1050293
Turbidity Meter	LA Mot 2-22	1596-3019

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	24005593	12/24	MR
pH (SU)	4.00	24005593	12/24	MR
pH (SU)	7.00	24004317	12/24	MR
pH (SU)	10.00	24000085	12/24	MR
D O (%)	N/A			Am
ORP (mV)	228.0	24006903	12/24	MR

Calibration					
Time Start	805		Time Finish	825	
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	4490	26.50	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.0	26.89	± 0.1	GWMP
pH (SU)	7.00	7.0	27.98	± 0.1	GWMP
pH (SU)	10.00	10.0	27.89	± 0.1	GWMP
D O (%)	N/A		27.98	$\pm 10\%$	NA
ORP (mV)	228.0	228	27.98	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0.0	$\pm 10\%$ of standard	EPA 2023
	1	1.09		
	10	9.97		

Calibration Check					
Time Start	1240		Time Finish	1257	
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	4490	36.2	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.0	35.7	± 0.1	GWMP
pH (SU)	7.00	7.0	35.08	± 0.1	GWMP
pH (SU)	10.00	10.0	35.18	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0.02	$\pm 10\%$ of standard	EPA 2023
	1	1.1		
	10	9.97		

Notes:

Site Name: ~~Essex~~ Hammond

Field Instrumentation Calibration Form

Date: 8/12/24Calibrated By: ER. S. LeeField Conditions: 10-90, Sunny

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aquatrail 900	1080293
Turbidity Meter	Lamotte 200	SN 696-3019

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	24005593	12/24	MP
pH (SU)	4.00	24005593	12/24	MP
pH (SU)	7.00	24004517	12/24	MP
pH (SU)	10.00	24000085	12/24	MP
D O (%)	N/A			MP
ORP (mV)	228.0	24006903	12/24	MP

Calibration					
Time Start		Time Finish			
135		155			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	99.90	22.06	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.0	22.13	± 0.1	GWMP
pH (SU)	7.00	7.0	22.67	± 0.1	GWMP
pH (SU)	10.00	10.0	23.02	± 0.1	GWMP
D O (%)	N/A	10.0	22.80	$\pm 10\%$	NA
ORP (mV)	228.0	228	23.08	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	.23	$\pm 10\%$ of standard	EPA 2023
	1	1.07		
	10	9.98		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

done before 2pm no mid day calibration N/A

Site Name: Hammon

Field Instrumentation Calibration Form

Date: 08/13/24

Calibrated By: Jacob Tracy

Field Conditions: _____

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>108207</u>	<u>AJR</u>
Turbidity Meter		

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (μS/cm)	4,490	<u>24005593</u>	<u>12/24</u>	<u>AJR</u>
pH (SU)	4.00	<u>24004517</u>	<u>12/24</u>	<u>AJR</u>
pH (SU)	7.00	<u>24000085</u>	<u>12/24</u>	<u>AJR</u>
pH (SU)	10.00			
D.O. (%)	N/A			
ORP (mV)	228.0	<u>24006908</u>	<u>12/24</u>	<u>AJR</u>

Calibration					
Time Start	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (μS/cm)	4,490	<u>4140</u>	<u>24.48</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4</u>	<u>24.50</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7</u>	<u>24.50</u>	± 0.1	GWMP
pH (SU)	10.00	<u>9.76</u>	<u>25.12</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>10.8</u>	<u>24.87</u>	± 10%	NA
ORP (mV)	228.0	<u>227.2</u>	<u>24.27</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>8.96</u>		
	<u>10</u>	<u>10.01</u>		

Calibration Check					
Time Start	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (μS/cm)	4,490	<u>4381</u>	<u>25.61</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.02</u>	<u>25.62</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.21</u>	<u>25.72</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.02</u>	<u>25.75</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>8.94</u>		
	<u>10</u>	<u>10.4</u>		

Notes:

Site Name: Hammond

Field Instrumentation Calibration Form

Date: 08/13/24Calibrated By: J. TracyField Conditions: Sunny

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>In situ</u>	<u>1080297</u>
Turbidity Meter	<u>Hach</u>	

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (μS/cm)	4,490	<u>24005593</u>	<u>12/24</u>	<u>Ayle</u>
pH (SU)	4.00			
pH (SU)	7.00	<u>2400457</u>	<u>12/24</u>	
pH (SU)	10.00	<u>2400085</u>	<u>12/24</u>	
D.O. (%)	N/A			
ORP (mV)	228.0	<u>24006903</u>	<u>12/24</u>	

Calibration					
Time Start	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (μS/cm)	4,490	<u>4491</u>	<u>24.59</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4</u>	<u>24.56</u>	± 0.1	GWMP
pH (SU)	7.00	<u>6.97</u>	<u>25.08</u>	± 0.1	GWMP
pH (SU)	10.00	<u>9.97</u>	<u>25.13</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>99.14</u>	<u>24.59</u>	± 10%	NA
ORP (mV)	228.0	<u>226.5</u>	<u>23.77</u>	± 10	EPA 2023

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>0.91</u>		
	<u>10</u>	<u>10.31</u>		

Calibration Check					
Time Start	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (μS/cm)	4,490	<u>4470</u>	<u>23.6</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.1</u>	<u>23.61</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.0</u>	<u>23.73</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.02</u>	<u>23.79</u>	± 0.1	GWMP

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>1.62</u>		
	<u>10</u>	<u>10.31</u>		

Notes:

Site Name: Hammond

Field Instrumentation Calibration Form

Date: 08/15/24

Calibrated By: J. Tracy

Field Conditions: _____

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	In-Situ	1080207
Turbidity Meter		

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	24005593	12/24	
pH (SU)	4.00	24004517	12/24	
pH (SU)	7.00	24000085	12/24	
pH (SU)	10.00			
D.O. (%)	N/A			
ORP (mV)	228.0	24006903	12/24	

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	45372	24.13	± 10% of standard	EPA 2023
pH (SU)	4.00	4.04	24.36	± 0.1	GWMP
pH (SU)	7.00	7.01	24.33	± 0.1	GWMP
pH (SU)	10.00	9.98	24.41	± 0.1	GWMP
D.O. (%)	N/A	99.06	24.3	± 10%	NA
ORP (mV)	228.0	207.5	24.63	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	0.98		
	10	10.2		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	4380	25.13	± 10% of standard	EPA 2023
pH (SU)	4.00	3.98	25.26	± 0.1	GWMP
pH (SU)	7.00	7.00	25.31	± 0.1	GWMP
pH (SU)	10.00	10.01	25.47	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	0.46		
	10	10.1		

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 8/15/24Calibrated By: J. NewsomeField Conditions: Clear, 90F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter		1080293
Turbidity Meter	2006	1594-3019

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	24005593	12/2024	AIR
pH (SU)	4.00	24005593	12/2024	AIR
pH (SU)	7.00	24004512	12/2024	AIR
pH (SU)	10.00	24000085	12/2024	AIR
D.O. (%)	N/A			
ORP (mV)	228.0	24006903	12/2024	AIR

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	4445.1	23.75	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.20	23.75	± 0.1	GWMP
pH (SU)	7.00	6.99	24.37	± 0.1	GWMP
pH (SU)	10.00	9.97	24.81	± 0.1	GWMP
D.O. (%)	N/A	101.78	24.1	$\pm 10\%$	NA
ORP (mV)	228.0	228.0	24.81	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	$\pm 10\%$ of standard	EPA 2023
	1	1.08		
	10	10.0		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

JW
8/15/24

Site Name: Hammond

Field Instrumentation Calibration Form

Date: 8/20/24Calibrated By: THField Conditions: 58-85°F
Sunny

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aqua troll	968202
Turbidity Meter	Lamotte 2020	4365-323

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	24010943	05/2025	AIR
pH (SU)	4.00	24010943	05/2025	AIR
pH (SU)	7.00	24004517	12/2024	AIR
pH (SU)	10.00	24000065	12/2024	AIR
D O (%)	N/A			
ORP (mV)	228.0	24006903	12/2024	AIR

Calibration					
Time Start		Time Finish			
0845		0915			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	4490	26.99	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.00	26.01	± 0.1	GWMP
pH (SU)	7.00	7.00	25.40	± 0.1	GWMP
pH (SU)	10.00	10.00	25.23	± 0.1	GWMP
D O (%)	N/A	100	27.24	$\pm 10\%$	NA
ORP (mV)	228.0	228	25.41	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	$\pm 10\%$ of standard	EPA 2023
	1	0.99		
	10	10		

Calibration Check					
Time Start		Time Finish			
1357		1410			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	4490	39.89	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.00	39.76	± 0.1	GWMP
pH (SU)	7.00	7.00	39.00	± 0.1	GWMP
pH (SU)	10.00	10.00	38.57	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	$\pm 10\%$ of standard	EPA 2023
	1	1.00		
	10	10.00		

Notes:

Site Name: Hammond

Field Instrumentation Calibration Form

Date: 8/20/24

Calibrated By: CR

Field Conditions: clear

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	AquaTron 900	965586
Turbidity Meter	Lamotte 7000	4123-2633

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (μS/cm)	4,490	29003593	12/24	AIR
pH (SU)	4.00	29003593	12/24	AIR
pH (SU)	7.00	29003593	12/24	AIR
pH (SU)	10.00	29003593	12/24	AIR
D O (%)	N/A			AIR
ORP (mV)	228.0	24006903	12/24	AIR

Calibration					
Time Start	8:45		Time Finish	9:15	
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (μS/cm)	4,490	4490	24.94	± 10% of standard	EPA 2023
pH (SU)	4.00	4.0	26.44	± 0.1	GWMP
pH (SU)	7.00	7.0	26.73	± 0.1	GWMP
pH (SU)	10.00	10.0	26.73	± 0.1	GWMP
D O (%)	N/A	100.1	26.57	± 10%	NA
ORP (mV)	228.0	228	26.57	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0.03	± 10% of standard	EPA 2023
	1	0.89		
	10	9.98		

Calibration Check					
Time Start			Time Finish		
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (μS/cm)	4,490	4490	27.6	± 10% of standard	EPA 2023
pH (SU)	4.00	4.0	25.9	± 0.1	GWMP
pH (SU)	7.00	7.0	26.6	± 0.1	GWMP
pH (SU)	10.00	10.0	26.9	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0.01	± 10% of standard	EPA 2023
	1	0.89		
	10	10.1		

Notes:

Site Name: Hammond

Field Instrumentation Calibration Form

Date: 8/21/24

Calibrated By: Tristan

Field Conditions: 65 Sunny

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aqua-tron	968202
Turbidity Meter	Lamotte 2020t	4303-5123

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	24010943	05/2025	AIR
pH (SU)	4.00	24010943	05/2025	
pH (SU)	7.00	24024517	12/2024	
pH (SU)	10.00	24000085	12/2024	
D O (%)	N/A			
ORP (mV)	228.0	24010943	12/2024	

Calibration					
Time Start	0815		Time Finish	0835	
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	4490	23.59	± 10% of standard	EPA 2023
pH (SU)	4.00	4.0	23.46	± 0.1	GWMP
pH (SU)	7.00	7.00	23.16	± 0.1	GWMP
pH (SU)	10.00	10.00	22.69	± 0.1	GWMP
D O (%)	N/A	100	23.23	± 10%	NA
ORP (mV)	228.0	228	22.16	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	1.00		
	10	10.00		

Calibration Check					
Time Start	1258		Time Finish	1305	
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	4490	30.09	± 10% of standard	EPA 2023
pH (SU)	4.00	4.00	30.09	± 0.1	GWMP
pH (SU)	7.00	7.00	29.69	± 0.1	GWMP
pH (SU)	10.00	10.00	30.04	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	1.0		
	10	10		

Notes:

Site Name Hamm and

Field Instrumentation Calibration Form

Date 8/21/24

Calibrated By: er

Field Conditions: clear, 70-90

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Hydrol 900</u>	<u>065586</u>
Turbidity Meter	<u>LaMotte 2020</u>	<u>2123-2623</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4.490	<u>24005593</u>	<u>12/24</u>	<u>APR</u>
pH (SU)	4.00	<u>24005593</u>	<u>12/24</u>	<u>APR</u>
pH (SU)	7.00	<u>24005593</u>	<u>12/24</u>	<u>APR</u>
pH (SU)	10.00	<u>24005593</u>	<u>12/24</u>	<u>APR</u>
D.O. (%)	N/A			<u>APR</u>
ORP (mV)	228.0	<u>24006903</u>	<u>12/29</u>	<u>APR</u>

Calibration					
Time Start	<u>8:15</u>		Time Finish	<u>8:45</u>	
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490	<u>4.490</u>	<u>21.3</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.0</u>	<u>22.34</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.0</u>	<u>23.80</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.0</u>	<u>23.04</u>	± 0.1	GWMP
D.O. (%)	N/A		<u>22.23</u>	± 10%	NA
ORP (mV)	228.0	<u>228</u>	<u>22.95</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0.10</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>0.1</u>		
	<u>10</u>	<u>10.27</u>		

Calibration Check					
Time Start			Time Finish		
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			± 10% of standard	EPA 2023

Notes:

NA - one well sampled

Site Name: Hammond

Field Instrumentation Calibration Form

Date: 09-04-24Calibrated By: JNTField Conditions: Clear

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	SN-Situ	883553
Turbidity Meter	LaMotte	4363-3123

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	24005593	12/24	A+R
pH (SU)	4.00			
pH (SU)	7.00	24024317	12/24	
pH (SU)	10.00	24060085	12/24	
D.O. (%)	N/A			
ORP (mV)	228.0	24006903	12/24	

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	4490	24.73	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.02	24.62	± 0.1	GWMP
pH (SU)	7.00	7	25.32	± 0.1	GWMP
pH (SU)	10.00	10	25.14	± 0.1	GWMP
D.O. (%)	N/A	102.98	25.74	$\pm 10\%$	NA
ORP (mV)	228.0	223	25.33	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	$\pm 10\%$ of standard	EPA 2023
	10	10.14		

Calibration Check					
Time Start 14:00		Time Finish 14:05			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	4460.1	26.02	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.0	26.13	± 0.1	GWMP
pH (SU)	7.00	7.0	25.50	± 0.1	GWMP
pH (SU)	10.00	10.03	25.42	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	$\pm 10\%$ of standard	EPA 2023
	10	9.75		

Notes:

Site Name: GP Plant Hammond Field Instrumentation Calibration FormDate: 9/4/24Calibrated By: J New smField Conditions: Clear, 75°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aquatro II	727023
Turbidity Meter	LA Mot 1010e	1511-411

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	24010943	05/2025	4P2
pH (SU)	4.00	1	05/2025	↓
pH (SU)	7.00	24084517	12/2024	
pH (SU)	10.00	24000085	12/2024	
D.O. (%)	N/A			
ORP (mV)	228.0	240616903	12/2024	↓

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	4452.0	23.91	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.06	25.01	± 0.1	GWMP
pH (SU)	7.00	7.00	25.51	± 0.1	GWMP
pH (SU)	10.00	10.00	25.05	± 0.1	GWMP
D.O. (%)	N/A	10.0	24.94	$\pm 10\%$	NA
ORP (mV)	228.0	228.0	24.79	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	$\pm 10\%$ of standard	EPA 2023
	1	1		
	10	10		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	4490.0	24.63	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.00	23.92	± 0.1	GWMP
pH (SU)	7.00	7.00	24.12	± 0.1	GWMP
pH (SU)	10.00	10.00	23.45	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	$\pm 10\%$ of standard	EPA 2023
	1	1		
	10	10		

Notes:

Site Name: Selena Nam Plant Hamma Field Instrumentation Calibration Form

Date: 9/4/2024

Calibrated By: Selena Wang

Field Conditions Sunny, cool

Instrument	Manufacturer/Model	Serial Number
Water Quality Meter	AQUA TROLL	883561
Turbidity Meter	lanette 100	4111-6122

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	24005593	12/2024	AIR
pH (SU)	4.00	24005593	12/2024	AIR
pH (SU)	7.00	24004517	12/2024	AIR
pH (SU)	10.00	24004517	12/2024	AIR
D.O. (%)	N/A	24004517	12/2024	AIR
ORP (mV)	228.0	24006903	12/2024	AIR

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	4490	35.79	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.00	33.26	± 0.1	GWMP
pH (SU)	7.00	7.00	31.50	± 0.1	GWMP
pH (SU)	10.00	10.00	30.83	± 0.1	GWMP
D.O. (%)	N/A	103.0	32.20	$\pm 10\%$	NA
ORP (mV)	228.0	228.0	31.58	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	$\pm 10\%$ of standard	EPA 2023
	1	1		
	10	10		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

Site Name Hammond

Field Instrumentation Calibration Form

Date: 04-05-24Calibrated By: JNTField Conditions: Clear

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	11-SiXU	883553
Turbidity Meter	La Motte	42
		4363-3123

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4.490	24005343	12/24	AER
pH (SU)	4.00	24005317	12/24	
pH (SU)	7.00	24004517	12/24	
pH (SU)	10.00	24000085	12/24	
D.O. (%)	N/A			
ORP (mV)	228.0	24006903	12/24	

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490	4495	25.38	± 10% of standard	EPA 2023
pH (SU)	4.00	4.00	25.51	± 0.1	GWMP
pH (SU)	7.00	7.0	25.55	± 0.1	GWMP
pH (SU)	10.00	10.0	25.69	± 0.1	GWMP
D.O. (%)	N/A	10.0	24.45	± 10%	NA
ORP (mV)	228.0	228	25.6	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	0.94		
	10	10.1		

Calibration Check					
Time Start 12:00 12:10		Time Finish 12:05 12:05			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490	4482	16.5	± 10% of standard	EPA 2023
pH (SU)	4.00	4.0		± 0.1	GWMP
pH (SU)	7.00	7.01		± 0.1	GWMP
pH (SU)	10.00	10.00		± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0.01	± 10% of standard	EPA 2023
	1	0.48		
	10	10.2		

Notes:

Site Name Plant Hammond

Field Instrumentation Calibration Form

Date 9/5/24Calibrated By J. NewsonField Conditions clear

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aquatrill	845593
Turbidity Meter	La Motte 2000	1511411

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	24005593	12/2024	AIR
pH (SU)	4.00	"	"	AIR
pH (SU)	7.00	2400457	12/2024	AIR
pH (SU)	10.00	24000685	12/2024	AIR
D.O. (%)	N/A			
ORP (mV)	228.0	24006903	12/2024	AIR

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	4496	24.19	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.86	24.97	± 0.1	GWMP
pH (SU)	7.00	7.80	25.49	± 0.1	GWMP
pH (SU)	10.00	10.00	26.05	± 0.1	GWMP
D.O. (%)	N/A	100	22.64	$\pm 10\%$	NA
ORP (mV)	228.0	228.0	25.59	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	$\pm 10\%$ of standard	EPA 2023
	10	1		
	10	10		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	4496	24.31	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.06	24.31	± 0.1	GWMP
pH (SU)	7.00	7.00	24.91	± 0.1	GWMP
pH (SU)	10.00	10.00	24.82	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	$\pm 10\%$ of standard	EPA 2023
	10	10		
	10	10		

Notes.

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 9-24-24Calibrated By: ZWField Conditions: Cloudy, 75°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>La Motte Analytical</u>	<u>1120055</u>
Turbidity Meter	<u>La Motte, 26704</u>	<u>4123-2623</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>24005543</u>	<u>12/2024</u>	<u>AIR</u>
pH (SU)	4.00	<u>24005593</u>	<u>12/2024</u>	<u>AIR</u>
pH (SU)	7.00			<u>AIR</u>
pH (SU)	10.00			<u>AIR</u>
D.O. (%)	N/A			<u>AIR</u>
ORP (mV)	228.0			<u>AIR</u>

Calibration					
Time Start <u>0854</u>		Time Finish <u>0934</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>4490</u>	<u>24.20</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>24.31</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>24.33</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>24.43</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>27.13</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228.0</u>	<u>24.24</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		

Calibration Check					
Time Start <u>—</u>		Time Finish <u>—</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>—</u>	<u>—</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	7.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	10.00	<u>—</u>	<u>—</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>—</u>	<u>—</u>	$\pm 10\%$ of standard	EPA 2023
	<u>—</u>	<u>—</u>		
	<u>—</u>	<u>—</u>		

Notes:

Site Name: Hammond

Field Instrumentation Calibration Form

Date: 09/24/24Calibrated By: JNTField Conditions: Cloudy

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	In Situ	108 3822
Turbidity Meter	Lamotte	4121-2623

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	2400593	12/24	ATR
pH (SU)	4.00	24004517	12/24	ATR
pH (SU)	7.00	24002083	12/24	ATR
pH (SU)	10.00			ATR
D.O. (%)	N/A			ATR
ORP (mV)	228.0	24006903	12/24	ATR

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	4490	26.47	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.0	26.44	± 0.1	GWMP
pH (SU)	7.00	7.0	26.54	± 0.1	GWMP
pH (SU)	10.00	10	26.82	± 0.1	GWMP
D.O. (%)	N/A	100	—	$\pm 10\%$	NA
ORP (mV)	228.0	228	26.97	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	$\pm 10\%$ of standard	EPA 2023
	10	10.7		
	—	—		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	4490	—	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.00	—	± 0.1	GWMP
pH (SU)	7.00	7.00	—	± 0.1	GWMP
pH (SU)	10.00	10.00	—	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	—	—	$\pm 10\%$ of standard	EPA 2023
	—	—		
	—	—		

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 9-25-24Calibrated By: Zain W.Field Conditions: Cloudy, 75°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aqua Troll 400	1120055
Turbidity Meter	LaMotte 2020L	4123-2623

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	2400SS93	12/2024	AIR
pH (SU)	4.00	2400SS93	12/2024	AIR
pH (SU)	7.00			AIR
pH (SU)	10.00			AIR
D.O. (%)	N/A			AIR
ORP (mV)	228.0			AIR

Calibration					
Time Start <u>0735</u>		Time Finish <u>0803</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4490</u>	<u>24.16</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>24.41</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>24.83</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>25.14</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>22.27</u>	± 10%	NA
ORP (mV)	228.0	<u>228.0</u>	<u>25.06</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		
	<u>—</u>	<u>—</u>		

Calibration Check					
Time Start <u>—</u>		Time Finish <u>—</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>—</u>	<u>—</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	7.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	10.00	<u>—</u>	<u>—</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>—</u>	<u>—</u>	± 10% of standard	EPA 2023
	<u>—</u>	<u>—</u>		
	<u>—</u>	<u>—</u>		
	<u>—</u>	<u>—</u>		

Notes:

Field Instrumentation Calibration Form

Site Name: Hammona
 Calibrated By: JNT

Date: 09/25/25
 Field Conditions: Cloudy, 80 F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Hi-Spec</u>	<u>—</u>
Turbidity Meter	<u>LaMotte</u>	<u>—</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	<u>24003593</u>	<u>12/24</u>	<u>AIR</u>
pH (SU)	4.00	<u>24004517</u>	<u>12/24</u>	<u>AIR</u>
pH (SU)	7.00	<u>24004517</u>	<u>12/24</u>	<u>AIR</u>
pH (SU)	10.00	<u>240085</u>	<u>12/24</u>	<u>AIR</u>
D.O. (%)	N/A	<u>24006909</u>	<u>27.94</u>	<u>AIR</u>
ORP (mV)	228.0			

Calibration					
Time Start	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4490</u>	<u>—</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4</u>	<u>27.43</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7</u>	<u>27.79</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10</u>	<u>28.02</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100</u>	<u>27.02</u>	± 10%	NA
ORP (mV)	228.0	<u>228</u>	<u>28.04</u>	± 10	EPA 2023

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>10</u>	<u>10.8</u>		
	<u>—</u>	<u>—</u>		

Calibration Check					
Time Start	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4490</u>	<u>—</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10</u>	<u>—</u>	± 0.1	GWMP

	Standard	Calibration Value	Acceptance Criteria	Reference
Turbidity (NTU)	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>10</u>	<u>10.2</u>		
	<u>—</u>	<u>—</u>		

Notes:

Site Name: Hammond

Field Instrumentation Calibration Form

Date: 10/1/24Calibrated By: ERField Conditions: 75-85, sun

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>TR-11900</u>	<u>883561</u>
Turbidity Meter	<u>2020 E</u>	<u>4126-2623</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490			
pH (SU)	4.00	<u>24010943</u>	<u>09/25</u>	<u>AR</u>
pH (SU)	7.00	<u>24007517</u>	<u>12/24</u>	<u>AR</u>
pH (SU)	10.00	<u>24000082</u>	<u>12/24</u>	<u>AR</u>
D.O. (%)	N/A			<u>AR</u>
ORP (mV)	228.0	<u>24006903</u>	<u>12/24</u>	<u>AR</u>

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>4490</u>	<u>21.21</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.0</u>	<u>21.51</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.0</u>	<u>21.67</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.0</u>	<u>22.43</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100</u>	<u>22.73</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228</u>	<u>22.47</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>4490</u>	<u>21.21</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.0</u>	<u>21.75</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.0</u>	<u>21.30</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.0</u>	<u>22.90</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 10-1-24Calibrated By: Zain W.Field Conditions: Cloudy, 75°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aqua Troll 400	883530
Turbidity Meter	La Motte, 20204	4065-3123

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	24010943	05/2025	ATR
pH (SU)	4.00	24010943	05/2025	ATR
pH (SU)	7.00	2400617	12/2024	ATR
pH (SU)	10.00	24000085	12/2024	ATR
D.O. (%)	N/A	—	—	ATR
ORP (mV)	228.0	2401792	06/2025	ATR

Calibration					
Time Start <u>0730</u>		Time Finish <u>0800</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>4490</u>	<u>21.90</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>22.27</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>22.54</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>22.83</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>21.17</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228.0</u>	<u>22.8, 02, 22.57</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		
	<u>—</u>	<u>—</u>		

Calibration Check					
Time Start <u>—</u>		Time Finish <u>—</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>—</u>	<u>—</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	7.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	10.00	<u>—</u>	<u>—</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>—</u>	<u>—</u>	$\pm 10\%$ of standard	EPA 2023
	<u>—</u>	<u>—</u>		
	<u>—</u>	<u>—</u>		
	<u>—</u>	<u>—</u>		

Notes:

Site Name: Hammond

Field Instrumentation Calibration Form

Date: 10/2/24Calibrated By: CEPField Conditions: 75-80

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>HANNA</u>	<u>883561</u>
Turbidity Meter	<u>2020+</u>	<u>4126-2623</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>24010943</u>	<u>5/24</u>	<u>MDL</u>
pH (SU)	4.00	<u>24010943</u>	<u>5/24</u>	
pH (SU)	7.00	<u>24004511</u>	<u>12/24</u>	
pH (SU)	10.00	<u>24000085</u>	<u>12/24</u>	
D.O. (%)	N/A			
ORP (mV)	228.0	<u>24000903</u>	<u>12/24</u>	

Calibration					
Time Start	Time Finish				
	<u>800</u>	<u>830</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>4490</u>	<u>21.0</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.0</u>	<u>21.10</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.0</u>	<u>21.95</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.0</u>	<u>22.05</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100</u>	<u>22.40</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228</u>	<u>22.54</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		

Calibration Check					
Time Start	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 10-2-24Calibrated By: Zain W.Field Conditions: Clean 70°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	AquaTroll 400	883530
Turbidity Meter	LI-Mottle 2020	4663-3123

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	24010943	05/2025	AIR
pH (SU)	4.00	24010943	05/2025	AIR
pH (SU)	7.00	24004517	12/2024	AIR
pH (SU)	10.00	24000085	12/2024	AIR
D.O. (%)	N/A	—	—	AIR
ORP (mV)	228.0	24011772	06/2025	AIR

Calibration					
Time Start <u>0845</u>		Time Finish <u>0900</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4490</u>	<u>22.60</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>22.68</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>22.85</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>23.08</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>22.22</u>	± 10%	NA
ORP (mV)	228.0	<u>228.0</u>	<u>22.85</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		

Calibration Check					
Time Start <u>—</u>		Time Finish <u>—</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>—</u>	<u>—</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	7.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	10.00	<u>—</u>	<u>—</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>—</u>	<u>—</u>	± 10% of standard	EPA 2023
	<u>—</u>	<u>—</u>		
	<u>—</u>	<u>—</u>		

Notes:

Site Name: Hammond

Field Instrumentation Calibration Form

Date: 10/8/24Calibrated By: ekField Conditions: 70-80 sun

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aquatro 1100	968202
Turbidity Meter	Lamotte 2020	4123-2623

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	24010943	5/25	MR
pH (SU)	4.00	24010943	5/24	MR
pH (SU)	7.00	24004517	12/24	MR
pH (SU)	10.00	24000085	12/24	MR
D.O. (%)	N/A	—	—	MR
ORP (mV)	228.0	24011792	6/25	MR

Calibration					
Time Start	9:30		Time Finish	10	
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	4496	22.6	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.0	23.06	± 0.1	GWMP
pH (SU)	7.00	7.0	23.52	± 0.1	GWMP
pH (SU)	10.00	10	24.11	± 0.1	GWMP
D.O. (%)	N/A	100	25.53	$\pm 10\%$	NA
ORP (mV)	228.0	228	24.22	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0.0	$\pm 10\%$ of standard	EPA 2023
	1	0.91		
	10	10.9		

Calibration Check					
Time Start			Time Finish		
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

N/A 22 wells

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 10/8/24Calibrated By: Zain W.Field Conditions: Clear 70°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	AquaTroll 4a	1080302
Turbidity Meter	La Motte 20201	

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	24010943	05/2025	AIR
pH (SU)	4.00	24010943	05/2025	AIR
pH (SU)	7.00	24004517	12/2024	AIR
pH (SU)	10.00	24000085	12/2024	AIR
D.O. (%)	N/A	—	—	AIR
ORP (mV)	228.0	24006903	12/2024	AIR

Calibration					
Time Start <u>0940</u>		Time Finish <u>1013</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4490</u>	<u>23.20</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>23.34</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>23.90</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>24.06</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>22.49</u>	± 10%	NA
ORP (mV)	228.0	<u>228.0</u>	<u>23.86</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		

Calibration Check					
Time Start <u>—</u>		Time Finish <u>—</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>—</u>	<u>—</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	7.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	10.00	<u>—</u>	<u>—</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>—</u>	<u>—</u>	± 10% of standard	EPA 2023
	<u>—</u>	<u>—</u>		
	<u>—</u>	<u>—</u>		

Notes:

Site Name: Hammond

Field Instrumentation Calibration Form

Date: 10/9/24Calibrated By: E. ProcellField Conditions: 70-80 Sun

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	AquaTron 11900	968202
Turbidity Meter	Lamotte 2020	9123-2623

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	24010943	05/25	AIR
pH (SU)	4.00	24010943	05/25	AIR
pH (SU)	7.00	24004517	12/24	AIR
pH (SU)	10.00	24000083	12/24	AIR
D.O. (%)	N/A	24	—	AIR
ORP (mV)	228.0	24011792	—	—

Calibration					
Time Start		Time Finish			
8:17		8:40			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	4490	23.01	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.0	24.19	± 0.1	GWMP
pH (SU)	7.00	7.0	24.62	± 0.1	GWMP
pH (SU)	10.00	10.0	24.68	± 0.1	GWMP
D.O. (%)	N/A	1.00	24.72	$\pm 10\%$	NA
ORP (mV)	228.0	229	20.52	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0.0	$\pm 10\%$ of standard	EPA 2023
	1	0.7		
	10	10.9		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

N/A
72 wells

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 10-9-24Calibrated By: Zain W.Field Conditions: Clear, 70°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Aqua Trak 400</u>	<u>1080302</u>
Turbidity Meter	<u>La Mott, 20206</u>	<u>1591-3019</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	<u>24010943</u>	<u>05/2025</u>	<u>AIR</u>
pH (SU)	4.00	<u>24010943</u>	<u>05/2025</u>	<u>AIR</u>
pH (SU)	7.00	<u>24004517</u>	<u>12/2024</u>	<u>AIR</u>
pH (SU)	10.00	<u>24000085</u>	<u>12/2024</u>	<u>AIR</u>
D.O. (%)	N/A	<u>—</u>	<u>—</u>	<u>AIR</u>
ORP (mV)	228.0	<u>24006903</u>	<u>12/2024</u>	<u>AIR</u>

Calibration					
Time Start <u>0745</u>		Time Finish <u>0817</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4490</u>	<u>20.92</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>21.00</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>20.99</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>21.46</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>21.42</u>	± 10%	NA
ORP (mV)	228.0	<u>228.0</u>	<u>21.57</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		
	<u>—</u>	<u>—</u>		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>—</u>	<u>—</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	7.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	10.00	<u>—</u>	<u>—</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>—</u>	<u>—</u>	± 10% of standard	EPA 2023
	<u>—</u>	<u>—</u>		
	<u>—</u>	<u>—</u>		
	<u>—</u>	<u>—</u>		

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 10/16/24Calibrated By: J. NewmyerField Conditions: Cloudy 40F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aqua Troll	843285
Turbidity Meter	Lamotte 2020	4126-7627

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	24005503	12/2024	FL
pH (SU)	4.00	"	"	"
pH (SU)	7.00	24004517	12/2024	AL
pH (SU)	10.00	24006085	12/2024	AL
D.O. (%)	N/A			
ORP (mV)	228.0	236-3 24006903	12/2024	AL

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	4193.4	12.42	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.20	12.70	± 0.1	GWMP
pH (SU)	7.00	7.00	13.54	± 0.1	GWMP
pH (SU)	10.00	10.11	13.71	± 0.1	GWMP
D.O. (%)	N/A	96.44	14.51	$\pm 10\%$	NA
ORP (mV)	228.0	236.3	13.61	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0.0	$\pm 10\%$ of standard	EPA 2023
	1	1.01		
	10	10.0		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

JN 10/16/24

Site Name Plant Hammond

Field Instrumentation Calibration Form

Date: 10/15/24Calibrated By: J. NewsomeField Conditions: 43°F, Cloudy

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aqua Troll	843285
Turbidity Meter	LaMotte 2024	4124-2625

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	24005593	12/20/24	A12
pH (SU)	4.00	"	"	"
pH (SU)	7.00	24004517	12/12/24	"
pH (SU)	10.00	24005593	12/26/24	"
D.O. (%)	N/A			
ORP (mV)	228.0	24004903	12/20/24	

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	4490	18.9	± 10% of standard	EPA 2023
pH (SU)	4.00	3.94	19.04	± 0.1	GWMP
pH (SU)	7.00	7.04	18.42	± 0.1	GWMP
pH (SU)	10.00	10.07	18.55	± 0.1	GWMP
D.O. (%)	N/A	16.4	14.69	± 10%	NA
ORP (mV)	228.0	223.3	18.19	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	1		
	10	10		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			± 10% of standard	EPA 2023

Notes:

JN 10/15/24

Site Name: GP Plant Hammond Field Instrumentation Calibration Form

Date: 10/15/2024

Calibrated By: A Tomlinson

Field Conditions: 73°F, cloudy

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Aqua TRAIL</u>	<u>843593</u>
Turbidity Meter	<u>LaMotte 2020nd</u>	<u>1511-411</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	<u>24003593</u>	<u>12/2024</u>	<u>Autocal</u>
pH (SU)	4.00	<u>24003593</u>	<u>11/2024</u>	<u>AIR</u>
pH (SU)	7.00	<u>24000085</u>	<u>12/2024</u>	<u>AIR</u>
pH (SU)	10.00	<u>N/A</u>	<u>11/2024</u>	<u>AIR</u>
D.O. (%)	N/A	<u>24006903</u>	<u>11/2024</u>	<u>AIR</u>
ORP (mV)	228.0			

Calibration					
Time Start	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4490</u>	<u>18.81</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.10</u>	<u>16.67</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.65</u>	<u>16.74</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.03</u>	<u>16.10</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>95.12</u>	<u>16.09</u>	± 10%	NA
ORP (mV)	228.0	<u>237.1</u>	<u>16.56</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0.0</u>	<u>0.0</u>	± 10% of standard	EPA 2023
	<u>10.00</u>	<u>10.01</u>		
	<u>1.00</u>	<u>1.05</u>		

Calibration Check					
Time Start	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			± 10% of standard	EPA 2023

Notes:

Site Name: G.P. Plant Hammond Field Instrumentation Calibration Form

Date: 10/16/2024

Calibrated By: A. Tammins

Field Conditions: 38°F, Clear

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Aqua Troll</u>	<u>943593</u>
Turbidity Meter	<u>LaMotte 2020w</u>	<u>1511-4111</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4.490	<u>24005593</u>	<u>12/2024</u>	<u>AquaCAL A12</u>
pH (SU)	4.00	↓	↓	↓
pH (SU)	7.00	<u>24003597</u>	<u>11/2024</u>	<u>A12</u>
pH (SU)	10.00	<u>24000085</u>	<u>12/2024</u>	↓
D.O. (%)	N/A	<u>N/A</u>	↓	↓
ORP (mV)	228.0	<u>24006903</u>	<u>11/2024</u>	↓

Calibration					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490	<u>4.490</u>	<u>12.03</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>12.96</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.04</u>	<u>14.04</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.11</u>	<u>14.43</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>101.19</u>	<u>14.98</u>	± 10%	NA
ORP (mV)	228.0	<u>212.7</u>	<u>14.37</u>	± 10	EPA 2023

TEMP
12.

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0.0</u>	<u>0.00</u>	± 10% of standard	EPA 2023
	<u>10</u>	<u>9.96</u>		
		<u>9.15</u>		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			± 10% of standard	EPA 2023

Notes:

AKT
10/16/2024

Site Name: Hammond AP-1 Field Instrumentation Calibration Form

Date: 11/4/24

Calibrated By: TH

Field Conditions: cloudy
60°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	AquaTron 400	950112
Turbidity Meter	Labette 2020T	SN 1516-3019

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	24010943	05/25	AIR
pH (SU)	4.00	24008387	06/25	
pH (SU)	7.00	24004996	06/25	
pH (SU)	10.00	24004996	06/25	
D.O. (%)	N/A			
ORP (mV)	228.0	24011792	06/25	

Calibration					
Time Start <u>0850</u>		Time Finish <u>0913</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	—	—	± 10% of standard	EPA 2023
pH (SU)	4.00	—	—	± 0.1	GWMP
pH (SU)	7.00	—	—	± 0.1	GWMP
pH (SU)	10.00	—	—	± 0.1	GWMP
D.O. (%)	N/A	<u>100</u>	<u>17.71</u>	± 10%	NA
ORP (mV)	228.0	<u>+228</u>	<u>17.80</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>10</u>	<u>1.0</u>		
	<u>10</u>	<u>9.96</u>		

Calibration Check					
Time Start <u>—</u>		Time Finish <u>—</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4490</u>	<u>18.34</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>18.45</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>17.91</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>17.82</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	—	—	± 10% of standard	EPA 2023
	—	—		
	—	—		

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 11-4-24Calibrated By: Zain WebbField Conditions: Cloudy, 70°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>AquaTroll 400</u>	<u>989630</u>
Turbidity Meter	<u>LaMotte 2020+</u>	<u>4121-2623</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	<u>24010945</u>	<u>05/2025</u>	<u>AIR</u>
pH (SU)	4.00	<u>24010943</u>	<u>05/2025</u>	<u>AIR</u>
pH (SU)	7.00	<u>24008537</u>	<u>06/2025</u>	<u>AIR</u>
pH (SU)	10.00	<u>24004996</u>	<u>06/2025</u>	<u>AIR</u>
D.O. (%)	N/A	—	—	—
ORP (mV)	228.0	<u>24011792</u>	<u>06/2025</u>	<u>AIR</u>

Calibration					
Time Start <u>0927</u>		Time Finish <u>0951</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4490</u>	<u>18.92</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>18.98</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>19.01</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>18.76</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>19.50</u>	± 10%	NA
ORP (mV)	228.0	<u>228.0</u>	<u>18.94</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>1.00</u>		
	<u>10</u>	<u>10.00</u>		
	—	—		

Calibration Check					
Time Start <u>—</u>		Time Finish <u>—</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	—	—	± 10% of standard	EPA 2023
pH (SU)	4.00	—	—	± 0.1	GWMP
pH (SU)	7.00	—	—	± 0.1	GWMP
pH (SU)	10.00	—	—	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	—	—	± 10% of standard	EPA 2023
	—	—		
	—	—		
	—	—		

Notes:

Site Name: Hammond
 Calibrated By: TH

Field Instrumentation Calibration Form

Date: 11/5/24
 Field Conditions: 63°F, cloudy

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aqua Troll 400	980712
Turbidity Meter	LaMotte 200t	1596-3019

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	24010943	05/2025	AIP ↓
pH (SU)	4.00	24010943	05/2025	
pH (SU)	7.00	24008587	06/2025	
pH (SU)	10.00	24004996	06/2025	
D.O. (%)	N/A			
ORP (mV)	228.0	24011792	06/2025	

Calibration					
Time Start <u>0135</u>		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4490</u>	<u>18.69</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>18.65</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>18.60</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>18.52</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100</u>	<u>18.10</u>	± 10%	NA
ORP (mV)	228.0	<u>228</u>	<u>18.52</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>10</u>	<u>10</u>		
	<u>—</u>	<u>—</u>		

Calibration Check					
Time Start <u>—</u>		Time Finish <u>—</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>—</u>	<u>—</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	7.00	<u>—</u>	<u>—</u>	± 0.1	GWMP
pH (SU)	10.00	<u>—</u>	<u>—</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>—</u>	<u>—</u>	± 10% of standard	EPA 2023
	<u>—</u>	<u>—</u>		
	<u>—</u>	<u>—</u>		

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 11-5-24Calibrated By: Zair W.Field Conditions: Cloudy, 80°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	Aqua Troll 400	989630
Turbidity Meter	LaMotte 20106	4121-2623

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	24010943	05/2025	AIR
pH (SU)	4.00	24010943	05/2025	AIR
pH (SU)	7.00	24008587	06/2025	AIR
pH (SU)	10.00	24004996	06/2025	AIR
D.O. (%)	N/A	—	—	—
ORP (mV)	228.0	24011792	06/2025	AIR

Calibration					
Time Start <u>0735</u>		Time Finish <u>0759</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	4490	19.63	± 10% of standard	EPA 2023
pH (SU)	4.00	4.00	19.75	± 0.1	GWMP
pH (SU)	7.00	7.00	20.12	± 0.1	GWMP
pH (SU)	10.00	10.00	20.43	± 0.1	GWMP
D.O. (%)	N/A	100%	20.65	± 10%	NA
ORP (mV)	228.0	228.0	20.62	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	1		
	10	10		
	—	—		

Calibration Check					
Time Start <u>—</u>		Time Finish <u>—</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	—	—	± 10% of standard	EPA 2023
pH (SU)	4.00	—	—	± 0.1	GWMP
pH (SU)	7.00	—	—	± 0.1	GWMP
pH (SU)	10.00	—	—	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	—	—	± 10% of standard	EPA 2023
	—	—		
	—	—		
	—	—		

Notes:

ZW

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 12-2-24Calibrated By: Zain Lv.Field Conditions: Clear, 30°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Aqua Troll 400</u>	<u>1170065</u>
Turbidity Meter	<u>La Motte 2000</u>	

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>2401074</u>	<u>05/2025</u>	<u>AIR</u>
pH (SU)	4.00	<u>24010943</u>	<u>05/2025</u>	<u>AIR</u>
pH (SU)	7.00	<u>24008587</u>	<u>06/2025</u>	<u>AIR</u>
pH (SU)	10.00	<u>24004996</u>	<u>06/2025</u>	<u>AIR</u>
D.O. (%)	N/A			
ORP (mV)	228.0	<u>24011772</u>	<u>06/2025</u>	<u>AIR</u>

Calibration					
Time Start <u>0725</u>		Time Finish <u>0751</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>4.490</u>	<u>12.32</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>12.51</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>12.88</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>13.34</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>13.00</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228.0</u>	<u>13.43</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		
	<u>-</u>	<u>-</u>		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 12/02/2024Calibrated By: Jacob TracyField Conditions: Sunny, Clear

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	In-situ	1170046
Turbidity Meter	Lamotte	

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	24010943	05/2025	ATA
pH (SU)	4.00	24010943	05/2025	
pH (SU)	7.00	24002527	06/2025	
pH (SU)	10.00	24004946	06/2025	
D.O. (%)	N/A			
ORP (mV)	228.0	24011742	06/2025	

Calibration					
Time Start	11:00	Time Finish	11:30		
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	4490	6.69	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.00	6.73	± 0.1	GWMP
pH (SU)	7.00	7.00	7.84	± 0.1	GWMP
pH (SU)	10.00	10.00	8.38	± 0.1	GWMP
D.O. (%)	N/A	100	8.76	$\pm 10\%$	NA
ORP (mV)	228.0	228.0	8.37	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	$\pm 10\%$ of standard	EPA 2023
	1	1.03		
	10	10.2		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 12/03/24

Calibrated By: Jacob Tracy

Field Conditions: Sunny, Clear

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	In-Situ	1170098
Turbidity Meter	lanotti	

1080307 AIR brought replacement sensor

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	24010943	12/5/2025	AIR ↓
pH (SU)	4.00	24010943	12/5/2025	
pH (SU)	7.00	24008587	12/6/2025	
pH (SU)	10.00	24004496	06/2025	
D.O. (%)	N/A			
ORP (mV)	228.0	24011792	06/2025	

Calibration					
Time Start	Time Finish				
<u>11:45</u>	<u>12:20</u>				
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4495</u>	<u>8.75</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.07</u>	<u>8.75</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.0</u>	<u>9.48</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10</u>	<u>10.08</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100</u>	<u>12.23</u>	± 10%	NA
ORP (mV)	228.0	<u>228</u>	<u>10.42</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0.02</u>	± 10% of standard	EPA 2023
	<u>10</u>	<u>10.2</u>		
	<u>10</u>	<u>10.8</u>		

Calibration Check					
Time Start	Time Finish				
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			± 10% of standard	EPA 2023

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 12/13/24

Calibrated By: Zain W.

Field Conditions: Clear, 30°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>AquaTroll 400</u>	<u>1170065</u>
Turbidity Meter	<u>La Motte 2020e</u>	

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4.490	<u>24010943</u>	<u>05/2025</u>	<u>ATR</u>
pH (SU)	4.00	<u>24010943</u>	<u>05/2025</u>	<u>ATR</u>
pH (SU)	7.00	<u>24008587</u>	<u>06/2025</u>	<u>ATR</u>
pH (SU)	10.00	<u>24004990</u>	<u>06/2025</u>	<u>ATR</u>
D.O. (%)	N/A			
ORP (mV)	228.0	<u>24011792</u>	<u>06/2025</u>	<u>ATR</u>

Calibration					
Time Start <u>8702</u>		Time Finish <u>8723</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490	<u>6.440</u>	<u>6.09</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>5.00</u>	<u>6.73</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>7.84</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>8.38</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>8.70</u>	± 10%	NA
ORP (mV)	228.0	<u>228.0</u>	<u>8.57</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4.490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			± 10% of standard	EPA 2023

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Calibrated By: A. TomlinsonDate: 1/6/2025Field Conditions: 47°F, cloudy

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	AquaTRAIL	1082822
Turbidity Meter	Hach 2100	240900000222

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	24010943	5/2025	AUTO CAL
pH (SU)	4.00	24010943	5/2025	AUTO CAL
pH (SU)	7.00	24008587	6/2025	AIR
pH (SU)	10.00	24004916	6/2025	AIR
D.O. (%)	N/A			
ORP (mV)	228.0	24011792	6/2025	AIR

Calibration					
Time Start <u>0900</u>		Time Finish <u>0920</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	4.490	9.98	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.04	9.08	± 0.1	GWMP
pH (SU)	7.00	7.03	8.88	± 0.1	GWMP
pH (SU)	10.00	10.06	8.76	± 0.1	GWMP
D.O. (%)	N/A	1007.	8.57	$\pm 10\%$	NA
ORP (mV)	228.0	228	8.76	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	20	21.5	$\pm 10\%$ of standard	EPA 2023
	100	102		
	800	803		
	10	9.05		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

Site Name: Hemmond

Field Instrumentation Calibration Form

Date: 1/6/24Calibrated By: T. HesslerField Conditions: Cloudy, 40°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>msi</u>	<u>1082517</u>
Turbidity Meter	<u>bach</u>	<u>241001200073</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>2406943</u>	<u>03/25</u>	<u>msi</u>
pH (SU)	4.00	<u>+</u>	<u>+</u>	<u>+</u>
pH (SU)	7.00	<u>24100387</u>	<u>6/25</u>	<u>+</u>
pH (SU)	10.00	<u>241003996</u>	<u>6/25</u>	<u>+</u>
D.O. (%)	N/A			
ORP (mV)	228.0	<u>2414192</u>	<u>6/25</u>	<u>+</u>

Calibration					
Time Start <u>0845</u>		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>4496</u>	<u>11.14</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>24.33</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.0</u>	<u>24.38</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.0</u>	<u>24.38</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100</u>	<u>8.66</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228</u>	<u>6.80</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>20</u>	<u>19.6</u>	$\pm 10\%$ of standard	EPA 2023
	<u>100</u>	<u>98.6</u>		
	<u>800</u>	<u>790</u>		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

Site Name Plant Hammond

Field Instrumentation Calibration Form

Date 1/17/2024Calibrated By L. HesslerField Conditions Cloudy, 28°

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>112514</u>	<u>1082817</u>
Turbidity Meter	<u>112514</u>	<u>745101200</u> 0173

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>24010713</u>	<u>5/23</u>	<u>112514</u>
pH (SU)	4.00	<u>24010713</u>	<u>5/23</u>	<u>112514</u>
pH (SU)	7.00	<u>24010713</u>	<u>5/23</u>	<u>112514</u>
pH (SU)	10.00	<u>24010713</u>	<u>5/23</u>	<u>112514</u>
D.O. (%)	N/A	<u>24010713</u>	<u>5/23</u>	<u>112514</u>
ORP (mV)	228.0	<u>24010713</u>	<u>5/23</u>	<u>112514</u>

Calibration					
Time Start <u>0605</u>		Time Finish <u>0655</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>4.490</u>	<u>15.93</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.0</u>	<u>15.90</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>15.48</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>15.20</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100</u>	<u>15.05</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228</u>	<u>15.03</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>20</u>	<u>20.6</u>	$\pm 10\%$ of standard	EPA 2023
	<u>100</u>	<u>102</u>		
	<u>800</u>	<u>810</u>		
	<u>10</u>	<u>9.78</u>		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>70.8</u>		$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>1.02</u>		± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 2/4/25Calibrated By: THField Conditions: 46-74 Fpartly cloudy

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>aquatray 400</u>	<u>965584</u>
Turbidity Meter	<u>laMotte 2020T</u>	<u>4126-2623</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>24010943</u>	<u>05/25</u>	<u>AIR</u>
pH (SU)	4.00	<u>"</u>	<u>"</u>	<u>"</u>
pH (SU)	7.00	<u>24008587</u>	<u>06/25</u>	<u>"</u>
pH (SU)	10.00	<u>24004916</u>	<u>06/25</u>	<u>"</u>
D.O. (%)	N/A	<u>"</u>	<u>"</u>	<u>"</u>
ORP (mV)	228.0	<u>24011792</u>	<u>06/25</u>	<u>AIR</u>

Calibration					
Time Start	Time Finish				
<u>0720</u>	<u>0745</u>				
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>4490</u>	<u>17.79</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>17.79</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>17.67</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>17.58</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100</u>	<u>18.10</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228</u>	<u>17.39</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>10</u>	<u>10.5</u>		

Calibration Check					
Time Start	Time Finish				
<u>1412</u>	<u>1425</u>				
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>4490</u>	<u>21.55</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>21.43</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>21.55</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>22.21</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>10</u>	<u>10.5</u>		

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 2-4-25Calibrated By: Zain WebbField Conditions: Cloudy 55°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>AquaTroll 400</u>	<u>752 637</u>
Turbidity Meter	<u>LaMotte 2020</u>	<u>1511-4111</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>24010943</u>	<u>05/2025</u>	<u>AIR</u>
pH (SU)	4.00	<u>24010943</u>	<u>05/2025</u>	<u>AIR</u>
pH (SU)	7.00	<u>24008589</u>	<u>06/2025</u>	<u>AIR</u>
pH (SU)	10.00	<u>24004996</u>	<u>06/2025</u>	<u>AIR</u>
D.O. (%)	N/A	<u>—</u>	<u>—</u>	<u>AIR</u>
ORP (mV)	228.0	<u>24001171</u>	<u>06/2025</u>	<u>AIR</u>

Calibration					
Time Start <u>0742</u>		Time Finish <u>0806</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>4.490</u>	<u>13.80</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>13.32</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>13.72</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>13.81</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>13.60</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228.0</u>	<u>13.68</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		
	<u>—</u>	<u>—</u>		

Calibration Check					
Time Start <u>1245</u>		Time Finish <u>1259</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4.490	<u>4.490</u>	<u>23.53</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>23.20</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>21.14</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>20.12</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		
	<u>—</u>	<u>—</u>		

Notes:

Site Name: Hammond
 Calibrated By: TH

Field Instrumentation Calibration Form

Date: 2/5/25
 Field Conditions: 66, cloudy

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>AquaTroll 400</u>	<u>9C558C</u>
Turbidity Meter	<u>La Motte 2020t</u>	<u>4126-2623</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>24 010943</u>	<u>05/25</u>	<u>AIR</u>
pH (SU)	4.00	<u>24010943</u>	<u>05/25</u>	<u>↓</u>
pH (SU)	7.00	<u>24008587</u>	<u>06/25</u>	<u>↓</u>
pH (SU)	10.00	<u>24004996</u>	<u>06/25</u>	<u>↓</u>
D.O. (%)	N/A			
ORP (mV)	228.0	<u>24011792</u>	<u>06/25</u>	<u>↓</u>

Calibration					
Time Start	Time Finish				
	<u>0745</u>	<u>0805</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>4490</u>	<u>16.65</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>16.65</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>16.78</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>16.29</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>16.42</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228</u>	<u>15.48</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>10</u>	<u>10.5</u>		

Calibration Check					
Time Start	Time Finish				
	<u>—</u>	<u>—</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>—</u>		$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>—</u>		± 0.1	GWMP
pH (SU)	7.00	<u>—</u>		± 0.1	GWMP
pH (SU)	10.00	<u>—</u>		± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>—</u>	<u>—</u>	$\pm 10\%$ of standard	EPA 2023
	<u>—</u>	<u>—</u>		

Notes:

No Midday Cal

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 2-5-25Calibrated By: Zain W.Field Conditions: Cloudy 55°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Aqua Troll 400</u>	<u>952637</u>
Turbidity Meter	<u>La Motte 2020ve</u>	<u>1511-4111</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>24010943</u>	<u>05/2025</u>	<u>AIR</u>
pH (SU)	4.00	<u>24010943</u>	<u>05/2025</u>	<u>AIR</u>
pH (SU)	7.00	<u>24008587</u>	<u>06/2025</u>	<u>AIR</u>
pH (SU)	10.00	<u>24004996</u>	<u>06/2025</u>	<u>AIR</u>
D.O. (%)	N/A			<u>AIR</u>
ORP (mV)	228.0	<u>24011792</u>	<u>06/2025</u>	<u>AIR</u>

Calibration					
Time Start <u>0730</u>		Time Finish <u>0800</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>4490</u>	<u>12.12</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>12.46</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>13.18</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>13.42</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100.2</u>	<u>12.98</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228.0</u>	<u>13.31</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes:

No mid-day calibration

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 3-5-25Calibrated By: Zain W.Field Conditions: Clear, 50°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	AquaTroll 400	1146036
Turbidity Meter		

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	24014218	01/2026	AIR
pH (SU)	4.00	24014218	01/2026	AIR
pH (SU)	7.00	24014266	01/2026	AIR
pH (SU)	10.00	24011537	01/2026	AIR
D.O. (%)	N/A			
ORP (mV)	228.0	22490162	01/2026	AIR

Calibration					
Time Start <u>0800</u>		Time Finish <u>0815</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4490</u>	<u>16.34</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>16.67</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>17.33</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>17.62</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>15.95</u>	± 10%	NA
ORP (mV)	228.0	<u>228.0</u>	<u>17.53</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		
	<u>-</u>	<u>-</u>		

Calibration Check					
Time Start <u>1246</u>		Time Finish <u>1250</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4345.7</u>	<u>16.81</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.09</u>	<u>16.81</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>16.87</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.01</u>	<u>16.84</u>	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>0.99</u>		
	<u>10</u>	<u>9.87</u>		
	<u>-</u>	<u>-</u>		

Notes:

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 3-5-25Calibrated By: Zain W.Field Conditions: Clear, 50°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	AquaTrak 400	1167968
Turbidity Meter	LaMotte 2020	4121-2623

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	24014218	01/2026	AIR
pH (SU)	4.00	24014218	01/2026	AIR
pH (SU)	7.00	24014266	01/2026	AIR
pH (SU)	10.00	24011537	01/2026	AIR
D.O. (%)	N/A			
ORP (mV)	228.0	22490162	01/2026	AIR

Calibration					
Time Start <u>0720</u>		Time Finish <u>0800</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4490</u>	<u>16.78</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>16.84</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>17.03</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>17.13</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>13.54</u>	± 10%	NA
ORP (mV)	228.0	<u>228.0</u>	<u>17.00</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	1		
	10	10		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			± 10% of standard	EPA 2023

Notes:

Zw

3-5-25

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 3/6/2023Calibrated By: J. KesslerField Conditions: Clear, 88°

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Hydrolab 1100</u>	<u>1146036</u>
Turbidity Meter		

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>24014218</u>	<u>1/2026</u>	<u>in situ</u>
pH (SU)	4.00	<u>4</u>	<u>6</u>	
pH (SU)	7.00	<u>24014266</u>	<u>1/26</u>	
pH (SU)	10.00	<u>24011537</u>	<u>1/26</u>	
D.O. (%)	N/A			
ORP (mV)	228.0	<u>22190162</u>	<u>1/26</u>	

Calibration					
Time Start <u>0700</u>		Time Finish <u>0750</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>4490</u>	<u>9.38</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4</u>	<u>9.45</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7</u>	<u>10.28</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10</u>	<u>11.21</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100</u>	<u>11.38</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228</u>	<u>11.18</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>1</u>	<u>97</u>		
	<u>10</u>	<u>10.03</u>		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes: issues w/ orp probe, cal Broken into 3 electronic reports.
no midday, and sampling prior to noon

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 3-6-25Calibrated By: Zain W.Field Conditions: Cloudy, 50°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	AquaTroll 400	1167968
Turbidity Meter	LaMotte 2020t	4121-2023

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	24014218	01/2026	AIR
pH (SU)	4.00	24014218	01/2026	AIR
pH (SU)	7.00	24014266	01/2026	AIR
pH (SU)	10.00	24011537	01/2026	AIR
D.O. (%)	N/A			
ORP (mV)	228.0	22490162	01/2026	AIR

Calibration					
Time Start <u>0716</u>		Time Finish <u>0751</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	4490	6.54	± 10% of standard	EPA 2023
pH (SU)	4.00	4.00	6.72	± 0.1	GWMP
pH (SU)	7.00	7.00	7.27	± 0.1	GWMP
pH (SU)	10.00	10.00	7.63	± 0.1	GWMP
D.O. (%)	N/A	100%	8.60	± 10%	NA
ORP (mV)	228.0	228.0	7.80	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	1		
	10	10		
	-	-		

Calibration Check					
Time Start <u>1151</u>		Time Finish <u>1207</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	4490	12.93	± 10% of standard	EPA 2023
pH (SU)	4.00	4.00	13.17	± 0.1	GWMP
pH (SU)	7.00	7.00	12.62	± 0.1	GWMP
pH (SU)	10.00	10.00	12.39	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	1		
	10	10		
	-	-		

Notes:

ZW

3-6-25

Site Name: plane Hammond
 Calibrated By: Yongk Wang

Field Instrumentation Calibration Form

Date: 4/2/15
 Field Conditions: Sunny / pm cloudy

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	<u>Aquaflow 114010</u>	<u>1149110</u>
Turbidity Meter	<u>16 model 1000</u>	<u>4126-2603</u>

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>24014218</u>	<u>01/2026</u>	<u>AIR</u>
pH (SU)	4.00	<u>24014218</u>	<u>01/2026</u>	<u>AIR</u>
pH (SU)	7.00	<u>24014266</u>	<u>01/2026</u>	<u>AIR</u>
pH (SU)	10.00	<u>2401537</u>	<u>01/2026</u>	<u>AIR</u>
D.O. (%)	N/A	<u>---</u>	<u>---</u>	<u>---</u>
ORP (mV)	228.0	<u>23490162</u>	<u>01/2026</u>	<u>AIR</u>

Calibration					
Time Start	Time Finish				
<u>1025</u>	<u>1045</u>				
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	<u>4490</u>	<u>21.90</u>	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	<u>4.00</u>	<u>21.91</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.00</u>	<u>21.99</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.00</u>	<u>22.00</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>22.26</u>	$\pm 10\%$	NA
ORP (mV)	228.0	<u>228.0</u>	<u>21.93</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	$\pm 10\%$ of standard	EPA 2023
	<u>10</u>	<u>10</u>		
	<u>---</u>	<u>---</u>		

Calibration Check					
Time Start	Time Finish				
<u>---</u>	<u>---</u>				
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490			$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00			± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			$\pm 10\%$ of standard	EPA 2023

Notes: no midday cal, start around noon

Yw

Yw

Site Name: plume Hammond

Field Instrumentation Calibration Form

Date: 4/14/25

Calibrated By: Zuhm

Field Conditions: Sunny

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	AquaTroll 1140	1179236
Turbidity Meter	Lamotte 2400	—

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	24014218	01/2026	AIR
pH (SU)	4.00	24014218	01/2026	AIR
pH (SU)	7.00	24014266	01/2026	AIR
pH (SU)	10.00	24011537	01/2026	AIR
D.O. (%)	N/A	—	—	AIR
ORP (mV)	228.0	22490162	01/2026	AIR

Calibration					
Time Start <u>1115</u>		Time Finish <u>1142</u>			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	<u>4490</u>	<u>22.42</u>	± 10% of standard	EPA 2023
pH (SU)	4.00	<u>4.0</u>	<u>22.47</u>	± 0.1	GWMP
pH (SU)	7.00	<u>7.0</u>	<u>23.08</u>	± 0.1	GWMP
pH (SU)	10.00	<u>10.0</u>	<u>23.19</u>	± 0.1	GWMP
D.O. (%)	N/A	<u>100%</u>	<u>23.41</u>	± 10%	NA
ORP (mV)	228.0	<u>228</u>	<u>23.32</u>	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	<u>0</u>	<u>0</u>	± 10% of standard	EPA 2023
	<u>1</u>	<u>1</u>		
	<u>10</u>	<u>10</u>		
	<u>—</u>	<u>—</u>		

Calibration Check					
Time Start		Time Finish			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490			± 10% of standard	EPA 2023
pH (SU)	4.00			± 0.1	GWMP
pH (SU)	7.00			± 0.1	GWMP
pH (SU)	10.00	<u>24</u>		± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
			± 10% of standard	EPA 2023

Notes:

No midday cal; started around noon

Zuhm

Site Name: Plant Hammond

Field Instrumentation Calibration Form

Date: 4-3-25Calibrated By: Zain W.Field Conditions: Clear, 65°F

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	AquaTron 400	1179236
Turbidity Meter	LaMotte 2020t	—

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance (µS/cm)	4,490	24014218	01/2026	AIR
pH (SU)	4.00	24014218	01/2026	AIR
pH (SU)	7.00	24014266	01/2026	AIR
pH (SU)	10.00	24011557	01/2026	AIR
D.O. (%)	N/A	—	—	—
ORP (mV)	228.0	22490162	01/2026	AIR

Calibration					
Time Start 0727		Time Finish 0751			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	4490	21.62	± 10% of standard	EPA 2023
pH (SU)	4.00	4.00	22.61	± 0.1	GWMP
pH (SU)	7.00	7.00	23.16	± 0.1	GWMP
pH (SU)	10.00	10.00	23.30	± 0.1	GWMP
D.O. (%)	N/A	— 100%	22.60	± 10%	NA
ORP (mV)	228.0	228.0	23.49	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	1		
	10	10		
	—	—		

Calibration Check					
Time Start 1134		Time Finish 1149			
Parameter	Standard	Calibration Value	Calibration Solution Temperature (°C)	Acceptance Criteria	Reference
Specific Conductance (µS/cm)	4,490	4490	25.31	± 10% of standard	EPA 2023
pH (SU)	4.00	4.00	25.21	± 0.1	GWMP
pH (SU)	7.00	7.00	24.50	± 0.1	GWMP
pH (SU)	10.00	10.00	24.31	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	± 10% of standard	EPA 2023
	1	1		
	10	10		
	—	—		

Notes:

2W

Site Name:

plane Hammond

Field Instrumentation Calibration Form

Date:

4/13/25

Calibrated By:

Yongli W

Field Conditions:

Sunny

Instrument	Manufacturer/ Model	Serial Number
Water Quality Meter	AquaTron II	1149715
Turbidity Meter	LaMotte/2002	4126-2/23

Calibration Standard Information				
Parameter	Standard	Lot #	Date of Expiration	Brand
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	24014217	01/2026	ATP
pH (SU)	4.00	24014218	01/2026	ATP
pH (SU)	7.00	24014266	01/2026	ATP
pH (SU)	10.00	24015337	01/2026	ATP
D.O. (%)	N/A			
ORP (mV)	228.0	22641162	01/2026	ATP

Calibration					
Time Start 0724		Time Finish 0744			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	4460	22.16	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.00	22.13	± 0.1	GWMP
pH (SU)	7.00	7.00	22.14	± 0.1	GWMP
pH (SU)	10.00	10.00	22.27	± 0.1	GWMP
D.O. (%)	N/A	100%	21.30	$\pm 10\%$	NA
ORP (mV)	228.0	228	22.11	± 10	EPA 2023

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	$\pm 10\%$ of standard	EPA 2023
	1	1		
	10	10		

Calibration Check					
Time Start 1134		Time Finish 1154			
Parameter	Standard	Calibration Value	Calibration Solution Temperature ($^{\circ}\text{C}$)	Acceptance Criteria	Reference
Specific Conductance ($\mu\text{S}/\text{cm}$)	4,490	4460	25.00	$\pm 10\%$ of standard	EPA 2023
pH (SU)	4.00	4.0	24.01	± 0.1	GWMP
pH (SU)	7.00	7.0	24.16	± 0.1	GWMP
pH (SU)	10.00	10.0	24.17	± 0.1	GWMP

Turbidity (NTU)	Standard	Calibration Value	Acceptance Criteria	Reference
	0	0	$\pm 10\%$ of standard	EPA 2023
	1	1		
	10	10		

Notes:

Yw